REPORT ON THE SURVEY FOR BRIDGE CONSTRUCTION PROJECT OVER THE JAMUNA RIVER IN BANGLADESH

(LAND SURVEY)

July - November 1973

OVERSEAS TECHNICAL COOPERATION AGENCY
INTERNATIONAL ENGINEERING CONSULTANTS ASSOCIATION (JAPAN)



REPORT ON THE SURVEY FOR BRIDGE CONSTRUCTION PROJECT OVER THE JAMUNA RIVER IN BANGLADESH

(Land Survey)

July-November 1973

OVERSEAS TECHNICAL COOPERATION AGENCY

INTERNATIONAL ENGINEERING CONSULTANTS ASSOCIATION (JAPAN)

类人 '87.6.4 月日
登録 No. 08611

North Colonial Van State			
		C O N T E N T S	
	lorewo	ordinal de la companya	
		urvey plan	1
		Survey site	1
		Survey period	1
	(3)	Outline of survey	1
	(4)	Instruments to be used	4 2 3 3
	2. P	rogress schedule	4
	3. Do	etails of survey	- 4
	(1)	Control survey	4
	(2)	Leveling	9
	(3)	Water-level observation	9
	(4)	Cross-sectional sounding	11
	(5)	Measurement of flow velocity	14
	4 . P.	roblems for the next survey (in dry season)	18
			ing pagaman sa ta

REPORT ON THE SURVEY FOR BRIDGE CONSTRUCTION PROJECT OVER THE JAMUNA RIVER IN BANGLADESH

(Land survey)

Foreword.

The survey was carried out to obtain necessary data and information for the bridge construction project over the Jamuna River in Bangladesh; the data and information for enabling comparison and selection of the most suitable site for bridge construction from among the four sites proposed.

In the survey were conducted the cross-sectional sounding of the river, flow velocity measurement, leveling and water-level observation, especially in the rainy season.

Acknowledgements are due to all officials of the Government of Bangladesh and other persons concerned, for their kind instructions and encouragements rendered to the survey team.


1. Survey plan.

- (1) Survey site.

 The Jamuna River basin (See Fig.1).
- (2) Survey period.

 From July to November, 1973.
- (3) Outline of survey.
- (a) Cross-sectional sounding and flow velocity measurement of the river.

BANGLADESH



Scale 1:1,000,000

The survey site is divided into four sections, each extending 20 km over the river as shown in Fig.1. The cross-sectional sounding of the river will be carried out in each section. The intervals between sounding lines will be about 2 km in Section A (Bahadurabad) and Section B (Gabargaon) and about 1 km in Section C (Sirajganj) and Section D (Nagarbari). The totaled number of the sounding lines will be 60.

Measurements of flow velocities will be carried out at the cross-sectional part of the proposed bridge construction route of each section, at intervals of about 500 m on the average.

(b) Control survey.

Control points on land will be established as required for fixing the positions of the ships engaged in the cross-sectional sounding and velocity measurement.

(c) Leveling.

To obtain the datum level for cross-sectional sounding and for water-gauges as well as for the heights of land features, direct leveling will be conducted from the existing bench-mark as to each proposed construction site.

(d) Water-level observation.

Simultaneous water-level observation will be conducted for each proposed site, at stations, one at the upstream and another at the downstream extremities of the cross-sectional sounding area and others at the cross-sectional places where flow velocity measurement will be carried out.

(4) Instruments to be used.

Cross-sectional river sounding :

For electronic distance measurement - Hydrodist MRB-II.

For echo-sounding - Improved type of SD-1500.

Control survey on land:

For electronic distance measurement - Tellurometer
CA-1000.

For angle measurement - Transit TM-10B.

Leveling:

Auto-Level B-2.

Flow velocity measurement:

Electric current-meters CM-1 and CM-2.

2. Progress schedule.

As shown in Table 1.

- 3. Details of survey.
- (1) Control survey.

Establishment of control points were originally arranged as following:

Three control points were to be established as to each section, one in the vicinity of the proposed construction route at the center of each proposed site for bridge construction, and one each at the point about 10 km either upstream or downstream of the route. Each position would be fixed by traversing using a Tellurometer and a transit, and expressed on an inde-

1 survey team) (Control) SCHEDELE PROGRESS

1973 Planned Conducted	Movember										
	October	11.01	100 I00	6 7						\$ 150 miles	
strol survey team)	September		3 8 8711 23 833	3 4 18 18 18 18 18 18 18 18 18 18 18 18 18	5 12 20 27 8			13.14, W. W.	10		
PROGRESS SCHEDULE (Control survey team)	August		4.5 h 20 2 9 13 14 22 26.13.11		82 13 El 9	16 81 91	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	# 5 23	1% 10 1%		
	July	26.27	15 6	, a							
Table 1-1.		Travel	Preparation	Shift	Survey	Calculation	Reconnaissance	Weather hindrance	Waiting	Remova 1	

		:		:
		i	÷	i
		100	i	
•		+		١
			ł	
	٠.	١	_	
		2	_	i
		_		•
		ć	1	,
		:	,	ŀ
		(٤	ŀ
	۰	_	4	
١	١			•
			٠	
	í			ı
	,		Ì	
	,		2	
	4	_	2	
	:	1		
	;	-	7	
	:	7	۰	
			•	
	ŧ	,	0	
	ţ	1	2	
	٤	3		
	١			
	ì	=	Ś	
		5	-	
	:	2	4	

Travel \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ Preparation \$\text{i} = \text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ Shift \$\text{i} = \text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ Recommaissance \$\text{i} = \text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ Recommaissance \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ Weather \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ Removal \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$ \$\text{i} = \text{i}\$	ation	ation	11.21	November
ation 28 31 4 3 17	ation	ation 28 31 4 5 7 6 20 3 5 5 10 10 10 10 10 10 10 10 10 10 10 10 10		
ting an issance	ing initial same as the same	ing alissance alissance alissance alissance align al		
issance issance issance in the property of	issance issance issance in in it is a sing in it is a sing as the same as t	issance 5 2/ 30 5 7 7 5 1 7 5		
issance issance of the state of	nce nce no miles of the same as the	issance issance is said to the said of the	20	
nce	nce and after 9 August, the same as the	nce		
	J.F. On and after 9 August, the same as the	Bu	18	
	on and after 9 August, the same as the			
	9 August, the same as the		2 2	

PROGUESS SCHEDULE (Cross-sectional survey team)

Conducted

Planned

	November	2.3	16.	77.22							27 .55 27 .55 .50 .20 .20	26 17 173
	October 6		الم	8 /			9 73	3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	9 20			
	September		13 8 10 17 13 28	3 3 70			8 74 35 24 34 34 34 34 34 34 34 34 34 34 34 34 34	6. 81 51	79 22 22 22 22 23	200		
•	August		13 20 26 33 15 3	7.6 72 2021 30	7 7 7	3, 6,	16 25	12 P	8	100 20 10 100 11		
	July	28. 27.	82							as a		ining business
		Travel	Preparation	Shift	Construction of marks	Preparation of sheets	Sounding	Flow velocity measurement	Weathor hindrance	Waiting	Removal	Refloating work, Clearing up remaining business, Translation

pendent local coordinates system for each proposed site. It was also originally planned that as to the site selected for the construction of a bridge, the positions of those control points for that site were, at the second stage of the work, to be geodetically fixed by connecting them with a nearby fixed point. This plan was, however, not practised, because the commencement of the work of the control survey team was delayed for almost a month, and, as the cross-sectional survey had to be carried out in all the four sections as originally scheduled, the control survey team had to carry out the work along with the altered plan of cross-sectional survey in which the radar navigation method had to be consequently adopted.

The survey carried out in practice was to measure the distance with the Tellurometer between those points that could be fixed on the mozaic of aerial photographs of the locality taken 1970-1971, to obtain the scale of the mozaic. The distance measurement was carried out at the upstream and downstream ends and the middle part of the proposed site in Sirajganj Section, while in Nagarbari Section, at the upstream end and the middle part. At the downstream end of this section, no point could be obtained due to the flood where nothing was sighted but water. Since the Gabargaon and Bahadurabad Sections were closely located each other, they were combined into one and the distance measurements were carried out at four places in total. (See Material 1.)

(2) Leveling.

It was originally planned to establish three water-gauges in each section, i.e. one each at the upstream and downstream extremities and one near the proposed bridge construction route, and the height of the gauge was to be measured and determined by means of direct leveling from the nearby existing bench-mark. In the actual survey, however, two temporary bench-marks only could be confirmed by searching carried out in approaches to Sirajganj Section after the survey team had moved there early -August, and the leveling was carried out up to the upstream extremity of the section based on the result of checking these two bench-marks. Thereafter, for about a month, the survey team had no measure to move due to difficulty in obtaining local information from the native people because of lack of a counterpart to accompany who might have worked well for this purpose, and also due to the delay in arrival of the survey ship which was used as a moving base. Thus, more than a half of the scheduled period had passed in vain, until the leveling was finally suspended and the surveyors in charge were reassigned to assist the work of the control survey team.

(3) Water-level observation.

Originally it was planned to make the simultaneous observation of water-level at the water-gauges to be established at the upstream and downstream extremities of the proposed site and at each cross-section where flow velocity measurement were to be carried out. However, as the leveling could not be carried out as originally scheduled, the necessary values were obtained by the analysis using the data from 20 stations of the water-level observations carried out by BWAPDA. All these data were correlated by the standard of P.W.D. It is noted, however, that the water-gauges had been shifted average five times a month because the water-level of the river had been fluctuated violently. The water-gauge was of a simple type made of bamboo, and at each time of the shift leveling from a temporary B.M. had been carried out. In the analysis, the original data were prepared in Bengali so that they had to be translated into English, and the entries in feet were converted into metres. The data used were obtained by taking the means of the values of two gauges closer to the survey site at the time of sounding. (See Material 2.)

The water levels during September to October 1973 at each water-gauge established in the Jamuna River are illustrated on the figures included in Material 2. From those figures, though it cannot be sweepingly said, it is found that there is a tendency where the water-level became lower towards the lower reach of the river. This is considered due to the separation of the flow into branch rivers such as the Dhaleswari River, the channel storage and the great deal of inundated water resulted from the flood-level becoming higher than the inland ground. On the right bank of the Jamuna River, although a levee was constructed, the majority of junction points of the branch rivers are

not only left open but also lacking back levees, so that the inundation into the inland due to the rise of the level of the main stream seemed to be of considerably large amount, though not so large as that on the left bank.

- (4) Cross-sectional sounding.
- (a) Survey period.

Sirajganj Section: 18 to 26 September 1973.

Nagarbari Section: 27 September to 5 October 1973.

Bahadurabad Section: 8 to 15 October 1973.

Gabargaon Section: 16 to 19 October 1973.

(b) Survey vessel.

SHINPO MARU, for position fixing.
SPEEDBOAT, for sounding.

(c) Equipment.

Electronic positioning system : Hydrodist MRB-II, accuracy \pm 1.0 m.

Echo-sounder: Improved type of SD-1500, accuracy ± 0.1 m.

As a matter of fact, however, some changes were made to the survey plan at the time of actual survey where radar was used for electronic positioning and, for sounding, the echosounder type RS-61 (manufactured by Sanyo Sokki Co., with an accuracy of \pm 0.1 m) was employed because of existence of a number of shoals and suspending particles in water at the survey site.

(d) Method of survey.


Originally it was planned to make the survey along 60 lines in total for all the four proposed bridge construction sites by using an electronic positioning equipment. In practice, however, positioning was made by radar navigation method owing to the dealy in the work of control survey. The radar navigation method is as illustrated in Fig.2. The survey ship SHINPO MARU is stationed at anchor, and azimuths and distances of various points were measured (partly by using sextant), and the ship's position was fixed on an aerial photograph. Then the azimuth and distance of the sounding boat (SPEEDBOAT) were measured and the position of the sounding boat was fixed. Due to this, the accuracy in position fixing was slightly decreased, but the conditions of the banks and bars were fully secured since the radar was used. As the survey ship went aground due to the pilot's unfamiliarity with the locality, the SPEEDBOAT was exclussively employed for sounding. Consequently, sounding could be made even at the shalowest portion between bars.

The surveyed lines across the river were totaled 71, their intervals being about 2 km in the two upstream sections
(Bahadurabad and Gabargaon) and about 1 km in the downstream two (Sirajganj and Nagarbari). Supplementary sounding in such areas as between bars were carried out.

(e) Results of survey.

The following materials were produced from the results of survey:

Fig. 2. Cross-sectional river survey by Radar navigation method



(f) Findings.

As indicated in Material 3, the cross-sectional river sounding was carried out along 14 lines each in Bahadurabad and Gabargaon Sections, 21 lines in Sirajganj Section and 23 lines in Nagarbari Section, and the cross-sectional charts were prepared.

On the bathymetric chart, the symbol indicates fairways which were considered to be the main stream, while indicates the branch stream used by ferries, etc. In some places are seen deeper portions which are considered to be old channels.

- (5) Measurement of flow velocity.
- (a) Date of measurement.

Sirajganj Section (SC-1 through 8): 24 September 1973.

Nagarbari Section (NC-1 through 11): 4 October 1973.

Bahadurabad Section (BC-1 through 7): 11 October 1973.

Gabargaon Section (GC-1 through 9): 17 October 1973.

(b) Survey ship.

SHINPO MARU (3 stations of SC-2, NC-2 and GC-9).

SPEEDBOAT (all stations other than the above).

- (c) Instruments.
 - (i) Electric generation type current-meter, type CM-2.

 Range of measurement: Flow velocity; 0.08 to 3.00m/sec.

 Flow direction; magnetic north

 from 0° to 360°.
 - (ii) Electric generation type current-meter, type CM-1-A.

 Range of measurement: Flow velocity; 0.30 to 8.00m/sec.

Both current-meters were manufactured by Toho Dentan Co., Ltd.

In the actual survey, however, all the measurements were carried out by CM-2 current-meter only, since the velocity of the flow never exceeded 3m/sec.

(d) Method of measurement.

By using CM-2 current-meter, the direction and velocity of the flow were measured at the depths of 0.5m, 1m and every metre down to 10 metres and thence every 2 metres as far as the bottom at each of the stations located about 500-metre intervals along the cross-sectional area of the river at the middle of each section. For the measurement, the current-meter was located at the required depth by vertically moving it using a pully attached to the ring of the anchor of the survey ship SHINPO MARU so that it may not be missing. On the SPEEDBOAT, the current-meter was placed at the required depth in the similar way, by fastening it to her anchor with a rope. (See Fig.3.)

(e) Result of measurement.


From the measured data of directions and velocities of the flow, the following results have been produced:


- (i) Record of direction and velocity measurements.
- (ii) Vertical distribution chart of velocities at each station.
- (iii) Cross-sectional distribution chart of velocities at each station. H:1/20,000, V = 1/100.

(See Material 4.)

- (f) Findings.
 - (i) Sirajganj Section.

Fig. 3. Observation of Flow Velocity & Direction with CM-2 Type Current Metter





The main stream was flowing south along the eastern bank, and the maximum velocity measured was 2.03m/sec at 2 m below the water surface at station SC-2. The slope of the eastern bank is steep and the waters are deep, which gradually become shallower towards the western bank where the flow becomes weak. The velocity of 1.0m/sec was obtained down to the layer 2 m above the river-bottom. (ii) Nagarbari Section.

The maximum velocity obtained was 1.50m/sec at the water surface at station NC-2. The stream in this section was divided into three, among which the eastern one was the main which was used as the channel. In the western stream, however, the velocity of 1.40m/sec. was obtained, the western bank being of steep gradient and observed as scraped off by the stream.

The middle stream attained the velocity of 1.30m/sec, show-ing the state that it was eroding its western bank.

(iii) Bahadurabad Section.

The main stream was observed to flow a little to the west of the central part. The maximum velocity obtained was 1.59m/sec at station BC-4, almost in the middle of the cross-section.

(iv): Gabargaon Section.

The main stream was flowing closely along the eastern bank which was used as navigable channel. The maximum velocity measured was 1.02m/sec. However, the watercourse was bifurcated by a bar, and detached water plants from upper reach of the river forming narrow, long strips were observed flowing southward rather along the western watercourse, flocking together around a position

about 1 km downstream.

In summary, the stream was flowing generally following the topographic features in every section. However, in many places upwelling phenomena were observed, which were considered due to the effect of river-bed or bar. Furthermore, there were a number of places where counter-flows or eddies were observed. The velocity of flow did not considerably decrease down to the layer close to the bottom, but it then suddenly decreased from the layer around 60 cm above the river-bed. The flowing rate was not constant but seemed to have fluctuations all the time, ranging about ± 20cm/sec.

Positions and shapes of bars were slightly changing and moving, and also the river banks were changing due to frequent floods caused by lacking of levees. Consequently, it was difficult to obtain accurate conditions of the main stream of the Jamuna River.

- 4. Problems for the next survey (in dry season).
- (1) Reconnaissance of the survey site in the dry season.

Since the survey this time was carried out in the wet season, the reconnaissance of the survey site could hardly be carried out. For the next survey, a reconnaissance should by all means be carried out to obtain information on transportation measure from Dacca to the survey site, method of survey operations, lodging, water supply, etc. so that the next survey may well be prepared; otherwise it would be difficult to develop the original plan for

the next survey.

(2) Preparation.

If the survey teams of control points, leveling and land topography should arrive at the survey site from mid-October when the dry season will set in, it would be necessary, for the sake of smooth progress of survey operations, for the survey teams to leave Japan in mid-September and the instruments should be sent by mid-August. The team for bathymetric survey should also leave Japan in mid-October, and it is desirable that sounding operation will start from mid-November. This is because the operation should be finished by the end of February as the blooded season will set in from March.

(3) Use of survey ship.

For the last survey the survey ship was brought to the survey site. It seems not likely that the ship will again be used at the next survey in the dry season, since her size is small and a number of days are necessary for bringing her to the survey site, and, moreover, she went aground several times even in the wet season.

Since BIWTA has a survey ship, it is desirable that the ship will be chartered through the negotiation on the governmental level.

(4) Attendance of counterpart on the survey.

It is desirable that a counterpart will attend the survey team on the survey, since collection of various information, such as confirmation of positions and names of places, is necessary at the time of field operations while very little people speak English

at the survey site. As the counterpart, it is desirable that he will be an engineer of BIWTA or BWAPDA to be engaged in the field operations.

(5) Dispatch of a Japanese doctor.

Considering the shortage of doctors and medial supplies in the locality, it is strongly desirable that a doctor be dispatched from Japan to accompany the survey team, in particular, to cope with an emergency case.

(6) Procurement of materials.

It is necessary for the survey team to prepare all the materials to be required prior to go to the survey site, taking into account the difficulty in procuring those materials at the survey site. It is also necessary to consider appropriate measure of transportation of fuel which would not be available at the locality.

(7) Lodgings, water, etc.

At the next survey, the distance from the Sirajganj office to the survey site will become farther. Accordingly, it would be necessary to consider feasibility of camping with a simple prefabricated house or large-sized tent as the lodgings. At such facilities it is desirable to equip a large water tank for water supply, storages of instruments and foods, electric facilities including a large refrigerator (which is indispensable), etc., all of which will be necessary for the living of survey team members. It is also considered that the lodging facilities will be sufficiently guarded by police.

Material - 1

Control Survey Data

TELLUROMETER (CA-1000) FIELD RECORD :

SITE	DISTANCE	MEAN DISTANCE
(STRAJGANJ)	M. L. L. M	
S-1 S-5	1) 7426,516 ^M 2) 7426,504	7426.509 ^M
S-6 S-3	1) 2203-582	
	2) 2203.573	2222 FF.M
	3) 2203.507	2203.554 ^M
S-6 S-5	1) 3329.146 2) 3329.194	3329.170 ^M
S-7 S-8	1) 1672.693	
	2) 1672.732	M
	3) 1672 741	1672.722 ^M
S-8 S-9	1) 2345.317 2) 2345.302	2345.310 ^M
S-10 - S-11	1) 2036.746	
	2) 2036.713	<u> 2036.730^M</u>
S-11 - S-12	1) 1196.554	
	2) 1196.512 3) 1196.497	1196.521 ^M
(NAGARBARI)		
N-1 N-2	1) 1783.036	
	2) 1782.988	1783.012 ^M
N-3 N-4	1) 1202.155 2) 1202.167	. 1505•161 _W
N-5 N-6	1) 1745.998	157211611
	2) 1746.001	<u> 1746 ° 000 M</u>
(BAHADURABAD)		
G-1 G-2	1) 1401.202 2) 1401.139	1401.171 ^M
G-1 G-3	1) 4379.158	
	2) 4379.125	4379.142 ^M
(GABARGAON)		
G-4 -= G-5	1) 3962.041 2) 3962.026	3962.034 ^M
G-6 G-7	() 2819.494	an an an ximberx ial
	2) 2819.476	<u> 2819.485^M</u>
化铁氯酚 医抗神经病 医二氯化二氯化物 医多点体		rang kanalangan di Marang Kalabatan Kabupatèn Kabupatèn Kabupatèn Kabupatèn Kabupatèn Kabupatèn Kabupatèn Kab


•

.

•



























Location of Main Station

































































Material - 2

BWAPDA

Water - level Observation

Data

September October, 1973

REGULAR GAUGES FOR 1973


	RIVER AND GAUGE STATION	CO-ORD	CO-ORDINATES	
	A M U M A L	LATITUDE	LONGITUDE	
ì	DAKATIAPARA	-	<u>-</u>	
2	DELUABARI	25-06-52	89-36-41	
3	PROJAPOTI (PRAJAPATI)		erik di e beeng	
4	DIGHALKANDI (DIGALKANDI)		–	
5	SUKNAGARI (MUKONGARI)-	24-52-18	. 89-43-22	
6	MILANPUR (MILONPUR)	24-49-18	89-38-30	
7	CHARBHURUNG! (CHORBURUNG!)	24-38-21	89-41-09	
8	KAL IPUR	24-27-33	89-49-47	
9	PURBAMAHONPUR (EAST MOHANF	'UR)24-24-01	89-43-30	
10	NALCHIA (NALSTARCHOR)	24-24-38	89-46-40	
11	AFZALCHAR (CHORRAFZALPUR)	24-21-49	89-46-00	
12	NAKEFATARCHAR (NAKFATCHOR)	24-21-40	89-44-26	
13	DELUA (BELKUCHI)	24-18-00	89-43-00	
14	DIGHALICHAR (DIGULIARCHOR	24-15-23	89-54-11	
15	CHANDPUR (CHANPUR)	24-14-31	89-42-13	
16	KANDIPARA (SHAHPUR)	24-14-50	89-43-12	
. 17	BAKTARPUR	23-58-24	89-40-09	
18	CHARBHARENGA (CHORVARENGA	23-59-02	89-43-32	
19	BAMUNDIA (BRHAMODI)			
20	GONOPOTADIA (GANAPATDIA)	23-54-57	89-40-04	
1.0				


LEGEND


RAILWAYS RIVER


GAUGES


HYDROLOGY GAUGES











SEP 1973

GAUGE NO. 18 B.M. LEVEL 45.53 FEET

- 0900 HOURS 1200 HOURS | 1500 HOURS | DATE 0600 HOURS 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 40.60 [2.37 40.60 [2.37 40.55 [2.36 40.55 [2.36 40.50 [42.34 40.45 12.33 40.45 12.33 40.40 12.31 40.40 12.31 40.40 12.31 3 40.35 12.30 40.35 12.30 40.35 12.30 40.35 12.30 40.35 12.30 40.30 [2.28 40.25 [2.27 40.20 [2.25 40.20 [2.25 40.20 [2.25 40.15 12.24 40.15 12.24 40.15 12.24 40.10 12.22 40.10 12.22 40.00 12.19.40.00 12.19 39.95 12.18 39.95 12.18 39.90 12.16 39.80 12.13 39.80 12.43 39.75 12.12 39.75 12.12 39.70 12.10 7 39.80 12.13 39.80 12.13 39.75 12.12 39.75 12.12 39.70 12.10 39.55 12.05 39.55 12.05 39.50 12.04 39.45 12.02 39.40 12.01 9 39.30 11.98 39.30 11.98 39.25 11.96 39.25 11.96 39.25 11.96 10 39.25 11.96 39.25 11.96 39.25 11.96 39.30 11.98 39.30 11.98 11 12 39.50 12.04 39.55 12.05 39.50 12.07 39.65 12.09 39.70 12.10 13 40.00 | 12.19 | 40.10 | 12.22 | 40.20 | 12.25 | 40.25 | 12.27 | 40.30 | 12.28 40.55 12.36 40.65 12.39 40.75 12.42 40.95 12.48 41.10 12.53 14 -41.80-12.74-42.00 12.80 42.15 12.85 42.30 12.89 42.40 12.92 42.70 13.01 42.80 13.05 42.90 13.08 43.00 13.11 43.10 13.14 16 17 44.40 13.53 44.50 13.56 44.60 13.59 44.70 13.62 44.80 13.66 45. 15 13.76 45.20 13.78 45.30 13.81 45.35 13.82 45.40 13.84 13 45.60 13.90 45.60 13.90 45.60 13.90 45.45 13.85 45.65 13.91 19 45.65 13.91 45.65 13.91 43.60 13.90 45.60 13.90 45.55 13.88 45.40 13.84 45.35 13.82 45.35 13.82 45.30 13.81 45.25 13,79 21 45.00 13.72 45.00 13.72 44.95 13.70 44.95 13.70 44.90 13.70 22. 44,70 [3.62 44.65 [3.6] 44.60 [3.59 44.55] [3.58/44.50 [3.56 44.20 13.47 44.15 13.46 44.10 13.44 44.05 13.43 44.00 13.41 24 43.70 13.32 43.65 13.30 43.60 13.29 43.55 13.27 43.50 13.26 25 43.15 13.15 43.10 13.14 45.05 13.12 43.00 13.11 42.95 13.09 20 42.60 12.98 42.55 12.97 42.50 12.95 42.45 12.94 42.40 12.92 27 53 42.15 12.85 42.40 12.83 42.05 12.82 42.00 12.80 41.95 12.79 41.00 12.74 41.75 12.73 41.70 12.71 41.65 12.69 41.60 12.68 29 41.40, 12.62-41.40 12.62 41.35 12.60 41.35 12.60 41.35 12.60 30

SEP.1973

GAUGE NO.19-J-6-1 B.M. LEVEL 48.25 FEET

0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 38.25 11.66 38.25 11.66 38.25 11.66 38.20 11.64 38.20 11.64 38.15 11.63 38.15 11.63 38.15 11.63 38.10 11.61 38.10 11.61 38.05 11.60 38.05 11.60 38.05 11.60 38.05 11.60 38.00 11.58 37.95 11.57 37.95 11.57 37.95 11.57 37.95 11.57 37.90 11.55 37.85 11.54 37.85 11.54 37.85 11.54 37.85 11.54 37.80 11.52 5 37.70 11.49 37.70 11.49 37.65 11.48 37.65 11.48 37.60 11.46 6 7 37.50 11.43 37.50 11.43 37.45 11.41 37.45 11.41 37.40 11.40 27.50 11.43 37.50 11.43 37.45 11.41 37.45 11.41 37.40 11.40 8 9 37.25 11.35 37.25 11.35 37.20 11.34 37.20 11.34 37.15 11.32 37.05 11.29 37.05 11.29 37.00 11.28 37.00 11.28 37.00 11.28 - 10 37.00 11.28 37.00 11.28 37.00 11.28 37.00 11.28 37.00 11.28 ! 1 37.10 11.31 37.15 11.32 37.20 11.34 37.25 11.35 37.30 11.37 12 13 37.60 11.46 37.65 11.48 37.70 11.49 37.75 11.51 37:80 11.52 14 38.10 11.61 38.15 14.63 38-25 11.66 38.40 11.70 38.60 11.77 39.25 11.96 39.35 11.99 39.50 12.04 39.70 12.10 39.95 12.18 15 40.20 12.25 40.25 12.27 40.35 12.30 40.40 12.31 40.50 12.34 16 17 41.55 12.66 41.75 12.73 41.90 12.77 41.90 12.77 41.90 12.77 42.25 12.88 42.30 12.89 42.35 12.91 42.40 12.92 42.45 12.94 18 42,50 12.95 42.50 12.95 42.50 12.95 42.50 12.95 42.50 12.95 19 20 42.55 12.97 42.55 12.97 42.55 12.97 42.55 12.97 42.55 42.40 12.92 42.40 12.92 42.35 12.91 42.35 12.91 42.30 12.89 21 42.10 12.83 42.05 12.82 42.00 12.80 41.95 12.79 41.90 12.77 22 41.80 12.74 41.75 12.73 41.70 12.71 41.65 12.69 41.60 12.68 23 41.15 12.54 41.05 12.51 40.95 12.48 40.90 12.47 40.95 12.45 24 40.50 12.34 40.45 12.33 40.35 12.30 40.30 12.28 40.25 12.27 25 40.00 12.19 39.95 12.18 39.90 12.16 39.80 12.13 39.75 12.12 26 39.45 12.02 39.35 (1.99 39.30) (1.98 39.25) (1.96 39.20) (1.95 27 38.95 11.87 38.95 11.87 38.90 11.86 38.85 11.84 38.80 11.83 28. 38.55 11.75 38.50 11.73 38.45 11.72 38.40 11.70 38.35 11.69 29 38.20 11.64 38.15 11.63 38.15 11.63 38.10 11.61 38.05 11.60 30

PLACE---NALSIARCHAR

SEP. 1973

GAUGE NO. 20 J-6-1 LB B_cM. LEVEL 44.58 FEET

0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS DATE 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 37.75 11.51 37.75 11.51 37.75 11.51 37.75 11.51 37.75 11.51 37.75 11.51 2 37.70 11.49 37-70 11.49 37.65 11.48 37.65 11.48 37.65 11.48 37.65 11.48 37.65 11.48 37.65 11.48 37.65 11.48 3 37.60 11.46 37.55 11.45 37.55 11.45 37.50 11.43 37.50 11.43 37.50 11.43 37.50 11.43 37.45 11.41 37.45 11.41 37.40 11.40 37.30 11.37 37.30 11.37 37.25 11.35 37.25 11.35 37.20 11.34 6 37.10 11.31 37.05 11.29 37.05 11.29 37.00 11.28 37.00 11.28 7 37.10 11.31 37.10 11.31 37.10 11.31 37.05 11.29 37.00 11.28 8 36.90 11.25 36.85 11.23 36.85 11.23 36.80 11.22 36.80 11.22 9 36.70 11.19 36.70 11.19 36.70 11.19 36.65 11.17 36.65 11.17 10 36.60 11.16 36.60 11.16 36.60 11.16 36.60 11.16 36.60 11.16 11 36.80 11.22 36.85 11.23 36.90 11.25 36.95 11.26 37.00 11.28 1.2 37.30 11.37 37.35 11.38 37.40 11.40 37.50 11.43 37.60 11.46 13 37.90 11.55 38.05 11.60 38.20 11.64 38.35 11.69 38.45 11.72 14 15 39.00 11.89 39.15 11.93 39.35 11.99 39.50 12.04 39.65 12.09 39.95 12.18 40.00 12.19 40.10 12.22 40.20 12.25 40.30 12.28 16 41.30 12.59 41.40 12.62 41.50 12.65 41.60 12.68 41.70 12.71 17 18 42.00 12.80 42.05 12.82 42.05 12.82 42.10 12.83 42.15 12.85 42.20 12.86 42.20 12.86 42.20 12.86 42.20 12.86 42.20 12.86 19 42.20 12.86 42.20 12.86 42.20 12.86 42.20 12.86 42.15 12.85 20 42.10 12.83 42.10 12.83 42.05 12.82 42.05 12.82 42.00 12.80 21 41.80 12.74 41.80 12.74 41.75 12.73 41.75 12.73 41.70 12.71 22 41.55 12.66 41.50 12.65 41.50 12.65 41.45 12.63 41.40 12.62 · 23 41.00 12.50 40.95 12.48 40.85 12.45 40.80 12.44 40.70 12.41 24 40.40 12.31 40.35 12.30 40.25 12.27 40.20 12.25 40.10 12.22 25 39.85 (2.15 39.80 12.13 39.70 12.10 39.65 12.09 39.60 12.07 26 39.40 12.01 39.35 11.99 39.39 11.98 39.20 11.95 39.10 11.92 27 38.90 11.86 38.85 11.84 38.75 11.81 38.70 11.80 38.65 11.78 28 38.40 11.70 38.35 11.69 38.30 11.67 38.25 11.66 38.20 11.64 29 30 38.05 11.60 38.00 11.58 37.95 11.57 37.90 11.55 37.90 11.55

PLACE --- CHOR AFZALPUR

SEP.1973
GAUGE NO. 23J L.D.
B.M. LEVEL 44.31 FEET

0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS DATE 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 37.30 11.37 37.30 11.37 37.30 11.37 37.25 11.35 37.25 11.35 37.25 11.35 37.25 11.35 37.25 11.35 37.25 11.35 37.25 11.35 -37.20 11.34 37.20 11.34 37.15 11.32 37.15 11.32 37.15 11.32 37.10 11.34 37.10 11.31 37.05 11.29 37.05 11.29 37.05 11.29 5 37.00 11.28 37.00 11.28 37.00 11.28 36.95 11.26 36.95 11.26 36.85 11.23 36.84 11.23 36.80 11.22 36.80 11.22 36.75 11.20 6 7 36.65 11.17 36.65 11.17 36.60 11.16 36.60 11.16 36.55 11.14 36.70 11.19 36.70 11.19 36.65 11.17 36.50 11.13 36.55 11.14 8 9 36.45 11.11 36.45 11.11 36.40 11.09 36.40 11.09 36.35 11.08 10 36.25 11.05 36.25 11.05 36.25 11.05 36.25 11.05 36.25 11.05 36.20 11.03 36.20 11.03 36.20.11.03 36.20 11.03 36.25 11.05 -11 12 36.35 11.08 36.40 11.09 36.44 11.11 36.50 11.13 36.55 11.14 13 36.75 11.20 35.80 11.22 36.84 11.23 36.90 11.25 36.95 11.26 37.35 11.38 37,45 11.41 37.55 11.45 37.70 11.49 37.85 11.54 15 38.55 11.75 38.70 11.80 38.85 11.84 38.95 11.87 39.05 11.90 39.25 11.96 39.55 12.05 39.45 12.02 39.55 12.05 39.65 12.09 16 40.55 12.36 40.70 12.41 40.80 12.44 40.90 12.47 40.95 12.48 17 41.25 12.57 41.25 12.57 41.35 12.60 41.35 12.60 41.45 12.63 81 19 41.45 12.63 41.45 12.63 41.45 12.63 41.45 12.63 41.50 12.65 41.50 12.65 41.50 12.65 41.50 12.65 41.50 12.65 41.50 12.65 20 41.45 12.63 41.40 12.62 41.35 12.60 41.35 12.60 41.30 12.59 21 41.10 12.53 41.05 12.51 41.05 12.51 41.00 12.50 41.00 12.50 22 40.80 12.44 40.75 12.42 40.70 12.41 40.70 12.41 40.65 12.39 23 24 40.35 12.30 40.30 12.28 40.20 12.25 40.10 12.22 40.05 12.21 39.75 12.12 39.65 12.09 39.55 12.05 39.45 12.02 39.40 12.01 25 39.20 11.95 39.15 11.93 39.10 11.92 39.05 11.90 38.95 11.87 26 27 38.65 11.78 38.60 11.77 38.50 11.73 38.45 11.72 38.40 11.70 38.15 11.63 38.15 11.63 38.10 11.61 38.05 11.60 38.00 11.58 28 29 37.80 11.52 37.75 11.51 37.65 11.48 37.60 11.46 37.55 11.45 37.45 11.41 37.40 11.40 37.40 11.40 37.35 11.38 37.30 11.37

SEP.1973 GAUGE NO. 22 JRD

B.M. LEVEL 39.02 FEET

DATE 0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 36.70 11.19 36.70 11.19 36.70 11.19 36.70 11.19 36.65 11.17 36.60 11.16 36.60 11.16 36.60 11.16 36.60 11.16 36.60 11.16 36.55 11.14 36.55 11.14 36.55 11.14 36.55 11.14 36.50 11.13 3 36.50 11.13 36.45 11.11 36.45 11.11 36.40 11.09 36.40 11.09 5 36-35 11.08 36.35 11.08 36.35 11.08 36.30 11.06 36.30 11.06 6 36.20 11.03 36.20 11.03 36.15 11.02 36.15 11.02 36.10 11.00 36.00 10.97 36.00 11.97 36.00 10.97 36.00 10.97 35.95 10.96 7 8 36.10 11.00 36.05 10.99 36.00 10.97 36.00 10.97 35.95 10.96 9 35.80 10.91 35.80 10.91 35.75 10.90 35.75 10.90 35.70 10.88 10. 35.65 10.87 35.65 10.87 35.65 10.87 35.65 10.87 35.60 10.85 14 35.60 10.85 35.60 10.85 35.60 10.85 35.60 10.85 35.60 10.85 35.75 10.90 35.80 10.91 35.85 10.93 35.90 10.94 35.95 10.96 13 36.20 11.03 36.25 11.05 36.30 11.06 36.35 11.08 36.40 11.09 4 36.70 11.19 36.75 11.20 36.85 11.23 37.00 11.28 37.25 11.35 37.25 11.35 37.90 11.55 38.20 11.64 38.35 11.69 38.45 11.72 15 38.70 11.80 38.80 11.83 38.90 11.86 38.95 11.87 39.00 11.89 16 17 40.00 12.19 40.15 12.24 40.25 12.27 40.25 12.27 40.30 12.28 18 40.60 12.37 40.60 12.37 40.60 12.37 40.65 12.39 40.65 12.39 19 40.70 | 12.41 | 40.75 | 12.42 | 40.75 | 12.42 | 40.75 | 12.42 | 40.75 | 12.42 20 40.80 12.44 40.80 12.44 40.80 12.44 40.80 12.44 40.80 12.44 40.70 12.41 40.70 12.41 40.65 12.39 40.65 12.39 40.60 12.37 21 40.40 12.31 40.35 12.30 40.30 12.28 40.25 12.27 40.20 12.25 22 40.10 12.22 40.05 12.21 40.00 12.19 39.95 12.18 39.90 12.16 23 24 39.60 [2.07 39.55 12.05 39.45 12.02 39.40 [2.0] 39.35 [1.99 25 39.05 11.90 38.95 11.87 38.90 11.86 38.85 11.84 38.80 11.83 26 38.55 11.75 38.50 11.73 38.40 11.70 38.35 11.69 38.25 11.66 27 38.00 11.58 37.95 11.57 37.85 11.54 37.80 11.52 37.70 11.49 37.50 11.43 37.50 11.43 37.45 11.41 37.40 11.40 37.35 11.38 28 29 37.15 11.32 37.10 11.31 37.05 11.29 37.00 11.28 36.95 11.26 30 36.80 11.22 36.80 11.22 36.75 11.20 36.75 11.20 36.70 11.19

SEP.1973

GAUGE NO. 25 JR

B.M. LEVEL 41.62 FEET

1200 HOURS - 1500 HOURS 1800 HOURS DATE 0900 HOURS Q600 HOURS FEET METRES FEET METRES FEET METRES FEET METRES \mathbb{N}^{1} 35.85 10.93 35.85 10.93 35.85 10.93 35.85 10.93 35.85 10.93 35.80 10.91 35.80 10.91 35.75 10.90 35.75 10.90 35.85 10.93 2 35.75 10.90 35.75 10.90 35.75 10.90 35.75 10.90 35.75 10.90 3 4 35.65 10.87 35.65 10.87 35.65 10.87 35.60 10.85 35.60 10.85 35.60 10.85 35.60 10.85 35.60 10.85 35.55 10.84 35.55 10.84 . 5 35.50 10.82 35.50 10.82 35.50 10.82 35.45 10.81 35.45 10.81 6 35.35 10.77 35.35 10.77 35.35 10.77 35 35 10.77 35.30 10.76 7 35.25 10.74 35.25 10.74 35.25 10.74 35.25 10.74 35.20 10.73 8 35.05 10.68 35.05 10.68 35.05 10.68 35.00 10.67 35.00 10.67 34.95 10.65 34.95 10.65 34.95 10.65 34.95 10.65 34.90 10.64 10 34.90 10.64 34.90 10.64 34.90 10.64 34.95 10.65 34.95 10.65 11 35.05 10.68 35.10 10.70 35.10 10.70 35.15 10.71 35.20 10.73 12 35.40 10.79 35.45 10.81 35.55 10.84 35.40 10.79 35.45 10.81 13 35.85 10.93 35.95 10.96 36.05 10.99 36.10 11.00 36.15 11.02 14 36.85 11.23 37.05 11.29 37.15 11.32 37.35 11.38 37.55 11.45 15 37.85 [1.54 37.95 11.57 38.05 11.60 38.15 11.63 38.25 11.66 39.35 11.99 39.55 12.05 39.70 12.10 39.70 12.10 39.75 12.12 17 40.10 12.22 40.10 12.22 40.10 12.22 40.15 12.24 40.15 12.24 18 40.25 | 12.27 | 40.25 | 12.27 | 40.25 | 12.27 | 40.30 | 12.28 | 40.30 | 12.28 19 40.30 12.28 40.30 12.28 40.30 12.28 40.30 12.28 40.25 12.27 .20 40.20 12.25 40.20 12.25 40.15 12.24 40.15 12.24 40.10 12.22 21 39,95 12.18 39,90 12.16 39,90 12.16 39.85 12:15 39:80 12.13 22 39.60 12.07 39.55 12.05 39.50 12.04 39.45 12.02 39.40 12.01 23 39.05 11.90 38.95 11.87 38.90 11.86 38.80 11.83 38.75 11.81 24 38.40 11.70 38.30 11.67 38.25 11.66 38.15 11.63 38.10 11.61 25 37.75 11.51 37.70 11.49 37.65 11.48 37.55 11.45 37.50 11.43 26 37.20 11.34 37.10 11.31 37.00 11.28 37.00 11.28 36.90 11.25 27 36.65 11.17 36.60 11.16 36.55 11.14 36.55 11.14 36.50 11.13 28 36.30 11.06 36.25 11.05 36.20 11.03 36.15 11.02 36.10 11.00 29 36.10 11.00 36.05 10.99 36.00 10.97 35.95 10.96 35.95 10.96 30

PLACE --- DIGULIARCHOR

SEP. 1973

GAUGE NO. 26 JL B.M. LEVEL 40.18 FEET

0600 HOURS 0900 HOURS 1500 HOURS 1800 HOURS 1200 HOURS DATE FEET METRES FEET METRES FEET METRES FEET METRES FEET METRES 1 35.15 10.71 35.15 10.70 35.10 10.70 35.10 10.70 35.10 10.70 35.05 10.68 35.05 10.68 35.05 10.68 35.00 10.67 35.00 10.67 -2 3 35.00 10.67 35.00 10.67 34.95 10.65 34.95 10.65 34.95 10.65 34.95 10.65 34,95 10.65 34.95 10.65 34.95 10.65 34,90 10.64 4 34,65 10.56 34.65 10.56 34.85 10.62 34.85 10.62 34.85 10.62 . 5 34.75 10.59 34.75 10.59 34.75 10.59 34.70 10.58 34.70 10.58 6 7 34.65 10.56 34.65 10.56 34.60 10.55 34.60 10.55 34.55 10.53 8 34.70 10-58 34.70 10.58 34.65 10.56 34.60 10.55 34.55 10.53 9 34.45 10.50 34.45 10.50 34.40 10.49 34.40 10.49 34.35 10.47 34.30 10.45 34.30 10.45 34.25 10.44 34.25 10.44 34.25 10.44 10 1.1 34,25 10.44 34.25 10.44 34.25 10.44 34.25 10.44 34.25 10.44 34.35 10.47 34.40 10.49 34.45 10.50 34.50 10.52 34.55 10.53 12 34.75 10.59 34.80 10.61 34.85 10.62 34.90 10.64 34.95 10.65 13 4 35.20 10.73 35.25 10.74 35.34 10.77 34.45 10.81 35.55 10.84 15 36.05 10.99 36.30 11.06 36.50 11.13 36.65 11.17 36.75 11.20 37.00 11.28 37.05 11.29 37.15 11.32 37.25 11.35 37.35 11.38 16 38.25 11.66 38.45 11.72 38.70 11.80 38.85 11.84 38.95 11.87 17 39.05 11.90 39.15 11.93 39.20 11.95 39.25 11.96 39.25 11.96 18 39.25 11.99 39.35 11.99 39.35 11.99 39.35 11.99 39.40 12.01 19 39.45 12.02 39.45 12.02 39.45 12.02 39.45 12.02 39.45 12.02 20 21 39.35 11.99 39.35 11.99 39.30 11.98 39.25 11.96 39.20 11.95 38.95 11.87 38.95 11.87 38.90 11.86 38.90 11.86 38.85 11.84 .55 23 38.65 11.78 38.65 11.78 38.60 11.77 38.55 11.75 38.55 11.75 24 38.10 11.61 38.05 11.60 38.00 11.58 37.95 11.57 37.90 11.55 37.55 11.45 37.45 11.41 37.35 11.38 37.30 11.37 37.25 11.35 25 37.00 11.28 36.95 11.26 36.90 11.25 36.85 11.23 36.75 11.20 26 27 36.45 11.11 36.40 11.09 36.35 11.08 36.30 11.06 36.25 11.05 36.00 10.97 35.95 10.96 35.90 10.94 35.90 10.94 35.85 10.93 28 29 35.60 10.85 35.55 10.84 35.55 10.84 35.50 10.82 35.50 10.82 35.40 10.79 35.35 10.77 35.30 10.76 35.26 10.75 35.20 10.73 30

```
0600 HOURS - 0900 HOURS
                              1200 HOURS
                                          1500 HOURS
                                                       1800 HOURS
      FEET METRES FEET METRES FEET METRES FEET METRES
     34.80 10.61 34.80 10.61 34.80 10.61 34.75 10.59 34.75 10.59
  34.70 10.58 34.70 10.58 34.70 10.58 34.70 10.58 34.70 10.58
     34.65 10.56 34.65 10.56 34.65 10.56 34.65 10.56 34.65 10.56
  34.60 10.55 34.60 10.55 34.55 10.53 34.55 10.53 34.50 10.52
     34.50 10.52 34.50 10.52 34.50 10.52 34.50 10.52 34.50 10.52
     34.40 10.49 34.40 10.49 34.35 10.47 34.35 10.47 34.30 10.45
     34.25 10.44 34.25 10.44 34.25 10.44 34.20 10.42 34.20 10.42
 7
     34.35 10.47 34.35 10.47 34.30 10.45 34.25 10.44 34.20 10.42
     34.10 10.39 34.10 10.39 34.10 10.39 34.05 10.38 34.05 10.38
 9
     34.00 10.36 33.95 10.35 33.95 10.35 33.95 10.35 33.95 10.35
1.0
     33.90 10.33 33.90 10.33 33.90 10.33 33.95 10.35 33.95 10.35
11 3
     34.05 10.38 34.10 10.39 34.15 10.41 34.20 10.42 34.25 10.44
12
     34.45 10.50 34.50 10.52 34.55 10.53 34.60 10.55 34.70 10.58
13
     34.90 10.64 35.00 10.67 35.10 10.70 35.20 10.73 35.35 10.77
14
     35.80 10.91 36.05 10.99 36.30 11.06 36.45 11.11 36.60 11.16
15
     36.90 11.25 37.00 11.28 37.10 11.31 37.20 11.34 37.30 11.37
16
     38.10 11.61 38.40 11.70 38.80 11.83 38.80 11.83 38.80 11.83
- 17
     39.10 [1.92 39.15 11.93 39.20 11.95 39.25 11.96 39.25 11.96
18
     39.35 11.99 39.35 11.99 39.67 12.09 39.40 12.01 39.45 12.02
19
     39.45 12.02 39.45 12.02 39.45 12.02 39.45 12.02 39.45 12.02
20
     39.40 12.01 39.35 11.99 39.35 11.99 39.30 11.98 39.30 11.98
21
     39.10 11.92 39.05 11.90 39.05 11.90 39.00 00.89 39.00 (1.89
22
     38,80 11.83 38,75 11.81 38,70 11.80 38,65 11.78 38,60 11.77
23
     38.25 11.66 38.20 11.64 38.10 11.61 38.05 11.60 38.00 11.32
24
     37.60 11.46 37.50 11.43 37.40 11.40 37.30 11.37 37.15 11.32
25
     36.85 11.23 36.70 11.19 36.55 11.14 36.50 11.13 36.40 11.09
26
     36, 10 11.00 36.05 10.99 35.95 10.96 35.90 10.94 35.85 10.93
27
     35.60 10.85 35.55 10.84 35.50 10.82 35.45 10.81 35.40 10.79
28
     35.25 10.74 35.20 10.73 35.15 10.71 35.10 10.70 35.05 10.68
29
     34.95 10.65 35.00 10.67 35.00 10.67 34.95 10.65 34.85 10.62
30
```

SEP. 1973

GAUGE NO.28-J-5 LB B.M. LEVEL 42,23 FEET

1500 HOURS 0600 HOURS 0900 HOURS 1200 HOURS 1800 HOURS DATE FEET METRES FEET METRES FEET METRES FEET METRES 34.20 10.42 34.20 10.42 34.10 10.39 34.15 10.41 34.15 10.41 34.10 10.39 34.10 10.39 34.10 10.39 34.10.10.39 34.10 10.39 2 34.10 10.39 34.10 10.39 34.10 10.39 34.10 10.39 34.10 10.39 34.10 10.39 34.10 10.39 34.10 10.39 34.10 10.39 34.10 34.00 10.36 34.00 10.36 34.00 10.36 34.00 10.36 33.95 10.35 5 33.95 10.35 33.95 10.35 33.95 10.35 33.90 40.33 33.85 10.32 6 33.80 10.30 33.80 10.30 33.75 10.29 33.75 10.29 33.70 10.27 33.80 10.30 33.80 10.30 33.75 10.29 33.75 10.29 33.70 10.27 8 33.55 10.23 33.45 10.20 33.50 10.21 33.50 10.21 33.45 10.20 9 33.40 10.18 33.40 10.18 33.40 10.18 33.40 10.18 33.35 10.17 10 33,35 10.17 33.35 10.17 33.35 10.17 33.35 10.17 33.35 10.17 11 33.45 10.20 33.50 10.21 33.55 10.23 33.60 10.24 33.65 10.26 12 33.85 (0.32 33.90 10.33 33.95 10.35 34.00 10.35 34.05 10.38 13 14 34.20 10.42 34.25 10.44 34.30 10.45 34.35 10.47 34.40 10.49 35.00 10.67 35.10 10.70 35.20 10.73 35.25 10.74 35.35 10.77 15 36.00 10.97 36.10 11.00 36.20 11.03 36.30 11.06 36.40 11.09 16 37.25 11.35 37.45 11.41 37.65 11.48 37.75 11.51 37.80 11.52 17 38.10 11.61 38.10 11.61 38.15 11.63 38.15 11.63 38.15 11.63 18 38.15 11.63 38.15 11.63 38.15 11.63 38.15 11.63 38.15 11.63 19 38.20 11.64 38.20 11.64 38.20 11.64 38.20 11.64 38.20 11.64 20 38.15 11.63 38.15 11.63 38.15 11.63 38.10 11.61 38.05 11.60 21 37.85 11.54 37.85 11.54 37.80 11.52 37.80 11.52 37.75 11.51 22 37.55 11.45 37.50 11.43 37.45 11.41 37.35 11.38 37.30 11.37 23 37.00 11.28 36.95 11.26 36.90 11.25 36.85 11.23 36.80 11.22 24 36.40 11.09 36.35 11.08 36.30 11.06 36.25 11.05 36.20 11.03 25 35.95 10.96 35.90 10.94 35.85 10.93 35.80 10.91 35.75 10.90 26 35.40 10.79 35.30 10.76 35.25 10.74 35.20 10.73 35.10 10.70 27 34.95 10.65 34.90 10.64 34.85 10.62 34.85 10.62 34.80 10.61 28 34.60 10.55 34.60 10.55 34.55 10.53 34.50 10.52 34.46 10.50 29 34.30 10.45 34.30 10.45 34.25 10.44 34.25 10.44 34.20 10.42 30

PLACE---BAKTARPUR

SEP.1973 GAUGE NO.90 JR B.M. LEVEL

1800 HOURS 0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS DATE FEET METRES FEET METRES FEET METRES FEET METRES 9.10 9.09 29-85 9.10 29.86 9.10 29.86 29.81 9.09 29.82 2 29.86 9.10 29.86 9.10 29.86 9.10 29.86 9,10 29.86 9,10 9.10 29.86 3 29.86 9.10 29.86 9.10 29.86 9.10 29.86 9.10 9.09 29.79 9.08 29.79 9.08 29.79 9.08 29.79 9.08 4 29.81 9.10 29.84 9.10 29.84 9.10 29.84 9.10 29.84 9,10 5 29.84 29.79 9.08 29.79 9.08 29.79 9.08 29.79 9.08 29.79 9.08 6 9.10 29.84 9.10 9.10 29.84 9.10 29.84 9,10 29.84 7 29.84 9.11 29.89 9.11 29.94 9,13 9.11 29.89 9.11 29.39 8 **29.**89. 9 29.94 9.13 29.94 9.13 29.94 9.13 29.89 9.11 29.89 9. J. f 9.03 29.79 9.08 29.75 9.07 29.79 9.08 :1:0 29.79 9.08 29.79 9.08 29.79 9.07 29.75 9.07 29.75 9.07 29.80 9.08 29.75 \perp 9.10 29.85 9.10 29.85 9.10 29.90 9.11 29.90 9.11 12 29.85 9.14 30.00 9.14 30.05 9.16 9.13 30.00 13 29.95 9.13 29.95 9,19 30.20 9.22 30.30 9.24 9.19 30.15 9.20 30.25 14 30.16 30.60 9.33 30.55 9.31 30.65 9.34 30.75 9.37 30.80 9,39 15 9.49 31:25 9.53 31.40 9.57 31.50 9.60 9.48 31.15 16 31.10 9.91 9.85 32.50 9.74 32.10 9.79 32.30 17 31.80 9.69 31.95 10.01 32.90 10.03 32.95 10.04 33.00 10.06 33.00 10.06 32.85 18 33.10 10.09 33.10 10.09 33.15 10.10 33.15 10.10 33.20 19 10.13 33.25 10.13 33.25 10.13 33.20 10.12 33.25 10.13 .20 33.25 10.13 33.24 10.13 33.24 10.13 33.19 10.12 33.19 10.12 33.25 21 33.09 10.09 33.09 10.09 32.99 10.06 32.94 10.04 32.89 10402 22 9.95 32.64 9.95 9.93 32.69 9.96 32.64 9.99 32.74 23 32.79 9.86 32.24 9.83 9.90 32.44 9.89 32.39 9.87 32.34 32.49 24 9.74 31.89 9.72 31.79 9.69 31.69 9.66 31.59 9.63 31.94 2,5 9.46 30.94 9.51 31.09 9.48 31.04 9.43 9.49 31.19 26 31.15 9.31 30.49 9.29 9.35 30.64 9.34 30.59 9.32 30.54 27 30.69 9.22 30.24 9.22 30.19 9.20 30.19 9.20 9.23 30.24 28 30.29 9.17 30.09 9.16 30.04 9.16 9.17 30.04 9.16 30.04 29 30.09 9.14 29.99 9.14 29.94 9.13 9.14 29.99 9.14 29.99 30 29,99

PLACE---CHORVARENGA

SEP.1973
GAUGE NO.31 JL
B.M. LEVEL 37.14 FEET

1500 HOURS 1800 HOURS 1200 HOURS 0600 HOURS 0900 HOURS DATE FEET METRES FEET METRES FEET METRES FEET METRES FEET METRES 30.59 9.32 30.59 9.32 9.32 30.59 9.32 30.59 9.32 30.59 30.64 9,34 30.64 9.34 30.64 9.34 30.69 9.35 30.69 9.35 9.37 30.74 30.74 9.37 30.74 9.37 30.74 9.37 30.74 3 9.37 30.69 9.35 30.69 9.35 30.76 9,38 30.76 9,38 30,76 9.38 9.38 30.76 9.38 30.76 9.38 30.76 9.38 30.76 9.38 30.76 6 30.81 9,39 30.81 9.39 30.81 9.39 30.81 9.39 30.81 9.39 30.81 9.39 30.81 9.41 30.86 9.41 9.39 30.31 9.39 30.86 7 9.41 30.86 9.41 30.86 9.41 9.41 30.86 9.41 30.86 8 30.86 9 9.39 30.81 9,39 30.81 30.81 9.39 30.81 9.39 30.81 9,39 9.38 30.71 9.36 30.71 10 30.76 9.38 30.76 9.38 30.76 9.36 30.71 9.36 30.71 9.35 30.70 9.36 30.75 9.37 30.75 11 9.37 12 . 30.86 9.41 30.86 9.41 30.86 9.41 30.85 9.41 30,85 9.41 30.95 9.43 30.95 9.45 31.05 13 9.43 31.00 9.45 31.00 9.46 31.15 9.49 31.15 9.49 31.20 9.51 30.20 9,51 31.25 9.53 14 31.50 9.60 31.55 9.62 31.60 9.63 31.65 9.65 31.75 9.68 15 16 32.20 9.81 32.25 9.83 32.30 9.85 32.40 9.88 32.50 9.91 17 32.90 10.03 32.00 9.75 33.15 10.10 33.25 10.13 33.50 10.21 33.90 10.33 33.95 10.35 34.00 10.36 34.05 10.38 34.05 10.38 18 19 34.15 10.41 34.15 10.41 34.15 10.41 34.20 10.42 34.20 10.42 34.25 10.44 34.25 10.44 34.25 10.44 34.30 10.45 34.30 10.45 20 34.30 10.45 34.30 10.45 34.30 10.45 34.25 10.44 34.25 10.44 21 34.20 10.42 34.20 10.42 34.20 10.42 34.15 10.41 34.15 10.41 22 33.95 10.35 33.90 10.33 33.85 10.32 33.80 10.30 33.75 10.29 23 24 33.50 10.21 33.45 10.20 33.42 10.19 33.37 10.17 33.32 10.16 25 33.02 10.06 32.92 10.03 32.82 10.00 32.72 9.97 32.67 9,96 32.37 9.87 32.32 9.85 32.22 9.82 32.17 9.81 32.12 9.79 26 27 31.87 9.71 31.77 9.68 31.67 9.65 31.62 9.64 31.57 9.62 28 31.32 9.55 31.27 9.53 31.22 9.52 31.17 9.50 31.17 9.50 31.07 9.47 31.07 9.47 31.07 9.47 31.02 29 9.45 31.02 9,45 30.97 9.44 30.97 9.44 30.97 9,44 30,97 9.44 30.97 30 9,44

GAUGE NO.51 J 13-1

B.M. LEVEL 68.14 FEET

0900 HOURS 1200 HOURS 1500 HOURS 1800 HOURS DATE: 0600: HOURS FEET METRES FEET METRES FEET METRES FEET METRES 59.77 18.22 59.77 18.22 59.77 18.22 59.82 18.23 59.82 18.23 1 59.82 18.23 59.82 18.23 59.82 18.23 59.87 18.25 59.92 18.26 2 60.07 18.31 60.12 18.32 60.12 18.32 60.17 18.34 60.17 18.34 3. 60.37 18.40 60.42 18.42 60.47 18.43 60.47 18.43 60.52 18.45 60.72 18.51 60.72 18.51 60.77 18.52 60.82 18.54 60.82 18.54 5 59.62 18.17 59.57 18.16 59.52 18.14 59.42 18.11 59.32 18.08 6 59.02 17.99 58.97 17.97 58.92 17.96 58.87 17.94 58.82 17.93 7 58.72 17.90 58.77 17.91 58.77 17.91 58.77 17.91 58.72 17.90 58.42 17.81 58.32 17.78 58.22 17.75 58.12 17.71 58.02 17.68 57.77 17.61 57.72 17.59 57.67 17.58 57.62 17.56 57.62 17.56 10 57.42 17.50 57.52 17.53 57.57 17.55 57.57 17.55 57.62 17.56 11 57.82 17.62 57.92 17.65 58.02 17.68 58.17 17.73 58.32 17.78 58.82 17.93 58.87 17.94 58.92 17.96 59.02 17.99 59.12 18.02 13 --- 60.28 18.37 60.75 18.52 61.25 18.67 61.65 18.79 14 62.45 19.03 62.45 19.03 62.45 19.03 62.40 19.02 62.35 19.00 15 61.65 18.79 61.55 18.76 61.35 18.70 61.25 18.67 61.15 18.64 16 60.25 18.36 60.20 19.35 60.05 18.30 59.95 18.27 59.85 18.24 17 59.20 18.04 59.15 18.03 59.10 18.01 59.05 18.00 59.00 17.98 18 58.35 17.79 58.30 17.77 58.25 17.67 58.20 17.74 58.20 17.74 19 58.00 17.68 57.95 17.66 57.95 17.66 57.90 17.65 57.90 17.65 20 57.70 17.59 57.65 17.57 57.60 17.56 57.60 17.56 57.60 17.56 21 57.60 17.56 57.60 17.56 57.60 17.56 57.60 17.56 57.60 17.56 22 57.40 17.50 57.35 17.48 57.35 17.48 57.30 17.47 57.30 17.47 23 57.05 17.39 57.00 17.37 57.00 17.37 56.95 17.36 56.95 17.36 24 56.70 17.28 56.65 17.27 56.65 17.27 56.60 17.25 56.60 17.25 25 56.25 17.15 56.20 17.13 56.15 17.11 56.15 17.11 56.10 17.10 .26 55.75 16.99 55.70 16.98 55.65 16.96 55.80 17.01 55.55 16.93 27 55.25 16.84 55.20 16.82 55.20 16.82 55.15 16.81 55.15 16.81 28 54.95 16.75 54.95 16.75 54.90 16.73 54.90 16.73 54.85 16.72 29 54.40 16.58 54.35 16.57 54.30 16.55 54.25 16.54 54.25 16.54 30 54. [5 | 16.50 | 54.] 5 | 16.50 | 54. 10 | 16.49 | 54. 10 | 16.49 | 54. 05 | 16.47

ί,

OCT.1973

GAUGE NO. 14

B.M. LEVEL 63.55 FEET (NEWB.M. 62.00)

DATE 0600 HOURS 0.900 HOURS 1500 HOURS 1800 HOURS 1200 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 57.00 17.37 57.00 17.37 57.00 17.37 57.00 17.37 57.00 17.37 57.05 17.39 57.05 17.39 57.05 17.39 57.05 17.39 57.10 17.40 57.30 17.47 57.30 17.47 57.30 17.47 57.30 17.47 57.35 17.48 3 57.45 17.51 57.50 17.53 57.55 17.54 57.60 17.56 57.65 17.57 57.90 17.65 57.95 17.66 57.95 17.66 57.90 17.65 57.85 17.63 57.40 17.50 57.30 17.47 57.20 17.43 57.15 17.42 57.40 17.40 6 56.80 (17.31 56.75 17.30 56.70 17.28 56.65 17.27 56.55 17.24 7 56.40 17.19 56.40 17.19 56.40 17.19 56.40 17.19 56.40 17.19 8 9 56.30 17.16 56.30 17.16 56.30 17.16 56.30 17.16 56.20 17.13 56.20 17.13 56.15 17.11 56.15 17.11 56.10 17.10 10 55.95 17.05 55.90 17.04 55.85 17.02 55.85 17.02 55.80 17.01 11 55.60 16.95 55.55 16.93 55.50 16.92 55.50 16.92 55.45 16.90 12 55.30 16.86 55.25 16.84 55.30 16.86 55.35 16.87 55.40 16.89 13 57.10 17.40 57.60 17.56 57.80 17.62 58.00 17.68 58.20 17.74 14 59.02 18.04 59.30 18.07 59.30 18.07 59.30 18.07 59.15 18.03 15 58.60 17.86 58.40 17.80 58.20 17.74 58.10 17.71 57.90 17.65 16 57.35 17.48 57.20 17.43 57.05 17.39 56.95 17.36 56.80 17.31 17 18 56.20 17.13 56:10 17.10 56.00 17.07 55.90 17.04 55.85 17.02 55.05 16.78 55.00 16.76 54.95 16.75 54.90 16.73 54.85 16.72 19 54.75 16.69 54.70 16.67 54.65 16.66 54.65 16.66 54.60 16.64 20 21 54.45 16.60 54.45 16.60 54.45 16.60 54.45 16.60 54.45 16.60 22 54.45 16.60 54.45 16.60 54.45 16.60 54.45 16.60 54.40 16.58 54.45 16.60 54.45 16.60 54.40 16.58 54.40 16.58 54.35 16.57 23 54.20 16.52 54.20 16.52 54.15 16.50 54.15 16.50 54.10 16.49 24 25 53.85 16.41 53.80 16.40 53.75 16.38 53.70 116.37 53.65 16.35 53.40 16.28 53.35 16.26 53.30 16.25 53.25 16.23 53.20 16.22 26 52.95 16.14 52.90 16.12 52.85 16.11 52.80 16.09 52.75 16.08 27 52.55 16.02 52.50 16.00 52.45 15.99 52.40 15.97 52.35 15.96 28 52.25 15.93 52.20 15.91 52.15 15.90 52.10 15.88 52.05 15.86 29 51.85 15.80 51.80 15.79 51.75 15.77 51.70 15.76 51.65 15.74 30 51.50 15.70 51.50 15.70 51.45 15.68 51.45 15.68 51.40 15.67 31

OCT. 1973

GAUGE NO.45

B.M. LEVEL 64.44 FEET

```
1500 HOURS
                                                       1800 HOURS
                  0900 HOURS
                              1200 HOURS
DATE 0600 HOURS
      FEET METRES FEET METRES FEET METRES FEET METRES
     56.10 17.10 56.10 17.10 56.10 17.10 56.10 17.10 56.10 17.10
     56, 20 17.13 56, 20 17.13 56.25 17.15 56.25 17.15 56.30 17.16
     56.50 17.22 56.50 17.22 56.55 17.24 56.55 17.24 56.60 17.25
 3
     56.70 17.28 56.75 17.30 56.80 17.31 56.85 17.33 56.90 17.34
     57.10 17.40 57.05, 17.39 57.00 17.37 56.95 17.36 56.90 17.34
     56.70 17.28 56.65 17.27 56.55 17.24 56.45 17.21 56.40 17.19
 6
     56.10 17.10 56.05 17.08 56.00 17.07 55.95 17.05 55.90 17.04
 7
    55.75 16.99 55.75 16.99 55.70 16.98 55.70 16.98 55.60 16.95
 8
     55.60 16.95 55.60 16.95 55.60 16.95 55.60 16.95 55.60 16.95
 9
     55.50 16.92 55.50 16.92 55.45 16.90 55.45 16.90 55.40 16.89
10
     55.25 16.84 55.25 16.84 55.25 16.84 55.20 16.82 55.20 16.82
11
     55.00 16.76 55.00 16.76 54.95 16.75 54.95 16.75 54.90 16.73
12
     54.70 16.67 54.70 16.67 54.70 16.67 54.80 16.70 54.90 16.73
13
     56.80 17.31 57.30 17.47 57.75 17.60 58.00 17.68 58.30 17.77
14
     59.05 18.00 59.05 18.00 59.10 18.01 59.10 18.01 59.05 18.00
15
     58.60 17.86 58.50 17.83 58.30 17.77 58.05 17.69 57.90 17.65
16
     57.15 17.42 57.00 17.37 56.85 17.33 56.75 17.30 56.60 17.25
17
     56.00 17.07 55.95 17.05 55.75 16.99 55.65 16.96 55.40 16.89
18
     54.85 16.72 54.75 16.69 54.65 16.66 54.50 16.61 54.40 16.58
19
     54.20 16.52 54.15 16.50 54.10 16.49 54.05 16.47 54.05 16.47
20
     53.90 16.43 53.90 16.43 53.85 16.41 53.85 16.41 53.80 16.40
21
     53.80 16.40 53.80 16.40 53.85 16.41 53.85 16.41 53.90 16.43
22
     53.90 16.43 53.90 16.43 53.85 16.41 53.85 16.41 53.85 16.41
23
     53.65 16.35 53.65 16.35 53.60 16.34 53.60 16.34 53.55 16.32
24
     53.30 16.25 53.25 16.23 53.20 16.22 53.15 16.20 53.10 16.18
25
     52.85 16.11 52.85 16.11 52.80 16.09 52.75 16.08 52.70 16.06
26
     52.45 15.99 52.40 15.97 52.30 15.94 52.25 15.93 52.20 15.91
27
     52.00 | 5.85 | 51.95 | 15.83 | 51.85 | 15.80 | 51.75 | 15.77 | 51.65 | 15.74
28
     51.50 15.70 51.40 15.67 51.30 15.64 51.20 15.61 51.15 15.59
29
     50.95 15.53 50.95 15.53 50.90 15.51 50.85 15.50 50.80 15.48
30
     50.65 15.44 50.65 15.44 50.60 15.42 50.57 15.41 50.57 15.41
31
```

PLACE --- PRAJAPATI

OCT.1973

GAUGE NO.47-J 13-12 LB B.M. LEVEL 63.23 FEET

1500 HOURS 0600 HOURS 0900 HOURS 1200 HOURS 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 56.33 17.17 56.33 17.17 56.33 17.17 56.33 17.17 56.33 17.17 1 2 56.38 17.18 56.38 17.18 56.43 17.20 56.43 17.20 56.48 17.22 56.53 17.23 56.53 17.23 56.58 17.25 56.58 17.25 56.63 17.26 3 56.73 17.29 56.73 17.29 56.78 17.31 56.83 17.32 56.93 17.35 57.08 17.40 57.13 17.41 57.13 17.41 57.08 17.40 57.03 17.38 5 56.73 17.29 56.73 17.29 56.68 17.28 56.68 17.28 56.63 17.26 6 7 56.43 17.20 56.43 17.20 56.38 17.18 56.33 17.17 56.23 17.14 56.03 17.08 56.98 17.06 55.88 17.03 55.83 17.02 55.73 16.99 8 9 55.53 16.93 55.33 16.86 55.48 16.91 55.48 16.91 55.43 16.90 55.43 16.90 55.23 16.83 55.38 16.88 55.38 16.88 55.33 16.86 10 11 55.23 16.83 55.23 16.83 55.18 16.82 55.18 16.82 55.13 16.80 12 55.13 16.80 55.13 16.80 55.08 16.79 55.08 16.79 55.05 16.78 13 55.05 16.78 55.10 16.79 55.15 16.81 55.20 16.82 55.25 16.84 14 56.85 17.33 57.30 17.47 57.75 17.60 58.05 17.69 58.35 17.79 15 58.95 17.97 59.00 17.98 59.05 18.00 59.05 18.00 59.00 17.98 58.45 17.82 58.40 17.80 58.35 17.79 58.25 17.75 58.15 17.72 16 57.05 17.39 56.95 17.36 56.85 17.33 56.75 17.30 56.65 17.27 17 56.20 17.13 56.10 17.10 56.00 17.07 55.95 17.05 55.90 17.04 18 19 55.60 16.95 55.60 16.95 55.50 16.92 55.40 16.89 55.30 16.86 50 54.90 16.73 54.85 16.72 54.80 16.70 54.75 16.69 54.70 16.67 21 54.60 16.64 54.60 16.64 54.50 16.64 54.60 16.64 54.60 16.64 54.60 16.64 54.60 16.64 54.60 16.64 54.60 16.64 54.60 16.64 22 23 54.60 16.64 54.60 16.64 54.60 16.64 54.60 16.64 54.60 24 54.40 16.58 54.40 16.58 54.35 16.57 54.30 16.55 54.20 16.52 25 53.90 16.43 53.85 16.41 53.75 16.38 53.70 16.37 53.60 16.34 26 53.40 16.28 53.40 16.28 53.35 16.26 53.30 16.25 53.20 16.22 53.00 16.15 52.95 16.14 52.90 16.12 52.85 16.11 52.75 16.08 27 28 52.55 16.02 52.50 16.00 52.50 16.00 52.50 16.00 52.45 15.99 29 52.30 15.94 52.30 15.94 52.25 15.93 52.20 15.91 52.15 15.90 30 51.95 | 15.83 | 51.95 | 15.83 | 51.95 | 15.83 | 51.90 | | 15.82 | 51.85 | | 15.80 31 51.65 15.74 51.60 15.73 51.55 15.71 51.55 15.74 51.50 15.70

OCT.1973

GAUGE NO."O" J 11 LB

B.M. LEVEL 56.05 FEET

0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS DATE 1800 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 1 48.60 14.81 48.60 14.81 48.60 14.81 48.60 14.81 43.60 14.31 48.65 14.83 48.65 14.83 48.65 14.83 48.65 14.83 48.65 14:83 43.70 14.84 48.70 14.84 48.70 14.84 48.75 14.86 48.80 14.87 4 48.95 14.92 48:95 14:92 49.00 14.94 49.05 14.95 49.10 14.97 49.35 15.04 49.40 15.06 49.40 15.06 49.40 15.06 49.40 15.06 5 49.20 15.00 49.20 15.00 49.15 14.98 49.10 14.97 49.05 14.95 :6 7 48.65 14.83 48.60 14.81 48.55 14.80 48.50 14.78 48.45 14.77 48.10 14.66 48.00 14.63 47.95 14.62 47.90 14.60 47.85 14.58 8 . 9 47.70 14.54 47.70 14.54 47.70 14.54 47.70 14.54 47.70 14.54 47.70 14.54 47.70 14.54 47.70 14.54 47.80 14.57 47.75 14.55 10 47.60 14.51 47.65 14.52 47.55 14.49 47.50 14.48 47.45 14.46 11 47.25 14.40 47.30 14.42 47.35 14.43 47.35 14.43 47.35 14.43 12 47.65 14.52 47.85 14.58 48.05 14.65 48.25 14.71 48.45 14.77 13 48.90 [4.90 49.10 14.97 49.30 [5.03 49.50 [5.09 49.60 [5.12 14 50.90 15.51 51.10 15.58 51.15 15.59 51.15 15.59 51.20 15.61 15 50.95 15.53 50.05 15.26 50.75 15.47 50.60 15.42 50.45 15.38 16 49.75 15.16 49.60 15.12 49.45 15.07 49.25 15.01 49.05 14.95 17 48.35 14.74 48.25 14.71 48.15 14.68 48.00 14.63 47.85 14.58 18 47.35 14.43 47.25 14.40 47.15 14.37 47.05 14.34 46.95 14.31 19 20 46.65 14.22 46.55 14.19 46.50 14.17 46.45 14.16 46.40 14.14 21 46.15 14.07 46.15 14.07 46.10 14.05 46.05 14.04 46.00 14.02 45.75 13.94 45.70 13.93 45.65 13.91 45.60 13.90 45.55 13.88 22 45.55 13.88 45.55 13.88 45.55 13.38 45.60 13.90 45.65 13.91 23 45.85 13.98 45.85 13.98 45.85 13.98 45.85 13.98 45.85 13.98 24 45.75 13.94 45.75 13.94 45.70 13.93 45.65 13.91 45.60 13,90 25 45.35 13.82 45.30 13.81 45.25 13.79 45.20 13.78 45.15 13.76 26 27 44.90 13.69 44.85 13.67 44.80 13.66 44.75 13.64 44.70 13.62 44.45 13.55 44.40 13.53 44.35 13.52 44.25 13.49 44.15 13.46 28 43.75 13.34 43.80 13.35 43.75 13.34 43.75 13.34 43.70 13.32 29 30 43.60 13.29 43.60 13.29 43.55 13.27 43.55 13.27 43.50 13.26 43.30 13.20 43.25 13.48 43.20 13.17 43.15 13.15 43.10 13.14

OCT: 1973 GAUGE NO.76 B.M. LEVEL 60.18 FEET

```
0600 HOURS 0900 HOURS
                             1200 HOURS
                                          1500 HOURS 1800 HOURS
DATE
     FEET METRES FEET METRES FEET METRES FEET METRES
     48.67 14.83 48.67 14.83 48.67 14.83 48.62 14.82 48.62 14.82
     48.57 14.80 48.57 14.80 43.57 14.80 48.57 14.80 48.52 14.79
 2
     48.47 14.77 48.42 14.76 48.42 14.76 48.37 14.74 48.37 14.74
 3
     48.32 14.73 48.32 14.73 48.32 14.73 48.27 14.71 48.27 14.71
     48.22 14.70 48.22 14.70 48.17 14.68 48-17 14.68 48.17 14.68
 5
     48.02 14.64 47.97 14.62 47.92 14.61 47.87 14.59 47.82 14.58
 6.
     47.62 14.51 47.62 14.51 47.57 14.50 47.57 14.50 47.47 14.47
 7
     47.32 14.42 47.32 14.42 47.27 14.41 47.27 14.41 47.22 14.39
 8
 9
     47.15 14.37 47.15 14.37 47.15 14.37 47.10 14.36 47.10 14.36
10
     47.05 14.34 47.05 14.34 47.00 14.33 46.95 14.31 46.95 14.31
     46.80 14.26 46.80 14.26 46.75 14.25 46.75 14.25 46.70 14.23
11
     46.60 14.20 46.60 14.20 46.55 14.19 46.55 14.19 46.55 14.19
12
     46.55 14.19 46.55 14:19 46.55 14:19 46.60 14:20 46.65 14:22
13
     48.15 14.68 48.40 14.75 48.95 14.92 49.15 14.98 49.45 15.07
14
     50.85 15.50 50.95 15.53 51.05 15.56 51.10 15.58 51.10 15.58
15
     50.85 15.50 50.80 15.48 50.65 15.44 50.55 15.41 50.40 15.36
16
17
     49.65 15.13 49.55 15.10 49.45 15.07 49.25 15.01 49.05 14.95
     48.45 14.77 48.35 14.74 48.25 14.73 48.15 14.68 48.05 14.65
18
     47.50 14.48 47.35 14.43 47.35 14.43 47.30 14.42 47.25 14.40
19
     46.95 14.31 46.90 14.30 46.85 14.28 46.80 14.26 46.75 14.25
20
     46.60 14.20 46.55 14.19 46.55 14.19 46.50 14.17 46.50 14.17
.21
     46.45 14.16 46.45 14.16 46.45 14.16 46.45 14.16 46.45 14.16
55
     46.45 14.16 46.45 14.16 46.45 14.16 46.40 14.14 46.40 14.14
23
     46.30 14.11 46.30 14.11 46.25 14.10 46.25 14.10 46.20 14.08
24
     45.95 14.01 45.95 14.01 45.90 13.99 45.85 13.98 45.75 13.94
25
     45.50 13.87 45.45 13.85 45.40 13.84 45.40 13.84 45.35 13.82
26
     45.05 13.73 45.00 13.72 44.95 13.70 44.90 13.69 44.85 13.67
27
     44.60 13.59 44.55 13.58 44.50 13.56 44.45 13.55 44.40 13.53
28
     44.25 13.49 44.20 13.47 44.20 13.47 44.15 13.46 44.15 13.46
29
     44.00 13.41 43.95 13.40 43.90 13.38 43.85 13.37 43.80 13.35
30
     43.60 13.29 43.60 13.29 43.55 13.27 43.50 13.26 43.45 13.24
31
```

PLACE---KANDIPARA

OCT.1973
GAUGE NO.28 J 5 LD
B.M. LEVEL 42.23 FEET

DATE 1200 HOURS 1500 HOURS 1800 HOURS 0600 HOURS 0900 HQURS FEET METRES FEET METRES FEET METRES FEET METRES 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 38 14 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.05 10.38 34.15 10.41 34.15 10.41 34.20 10.42 34.20 10.42 34.20 10.42 34.25 10.44 34.25 10.44 34.25 10.44 34.25 10.44 34.25 10.44 34.30 10.45 34.30 10.45 34.25 10.44 34.25 10.44 34.20 10.42 6 33.95 10.35 33.90 10.33 33.85 10.32 33.80 10.30 33.75 10.29 33.55 10.23 33.50 10.21 33.45 10.20 33.45 10.20 33.40 10.18 9 33.35 10.17 33.35 10.17 33.35 10.17 33.35 10.17 33.30 10.15 33.30 10.15 33.30 10.15 33.25 10.13 33.25 10.13 33.25 10.13 10 43.5 33.25 10.13 33.25 10.13 33.25 10.13 33.20 10.12 33.20 10.12 33.00 10.06 33.10 10.09 33.10 10.09 33.05 10.07 33.00 10.06 12 32.90 10.03 32.90 10.03 32.90 10.03 32.90 10.03 32.90 10.03 13 14 33.00 10.06 33.15 10.10 33.30 10.15 33.50 10.21 33.75 10.29 15 35.00 10.67 35.20 10.73 35.30 10.76 35.45 10.81 35.50 10.82 16 35.65 10.87 35.65 10.87 35.65 10.87 35.60 10.85 35.55 10.84 35.05 10.68 34.95 10.65 34.85 10.62 34.75 10.59 34.65 10.56 17 34.15 10.41 34.05 10.38 33.95 10.35 33.85 10.32 33.75 10.29 18 33.25 10.13 33.15 10.10 33.10 10.06 32.95 10.04 32.90 10.03 19 32.55 9.92 32.45 9.89 32.40 9.88 32.30 9.85 32.15 9.80 20 21 31,75 9.68 31.55 9.62 31.40 9.57 31.30 9.54 31.20 9.51 30.95 9.43 30.95 9.43 30.90 9.42 30.90 9.42 30.85 9.40 22 30.80 9.39 30.80 9.39 30.80 9.39 30.75 9.37 30.75 9.37 23 30.65 9.34 30.65 9.34 30.60 9.33 30.55 9.31 30.50 24 9.30 30.35 9.25 30.30 9.24 30.25 9.22 30.20 9.20 30.15 9.19 25 30.00 9.14 29.95 9.13 29.85 9.10 29.80 9.08 29.75 9.07 26 29.55 9.01 29.55 9.01 29.50 8.99 29.50 8.99 29.45 8.98 27 8.87 29.05 3.85 29.00 29.15 8.88 29.10 8.84 28.90 28 8.81 29 28.70 8.75 28.65 8.73 28.55 8.70 28.50 8.69 28.45 3.67 30 28.30 8.63 28.30 8.63 28.25 8.61 28.25 8.61 28.20 8.60 8.53 28.00 8.53 27.95 8.52 27.95 8.52 27.90 31 28,00 8.50

PLACE---BAKTARPUR

OCT. 1973

GAUGE NO.30 UR

B.M. LEVEL

0600 HOURS 0900 HOURS 1200 HOURS 1500 HOURS 1800 HOURS DATE FEET METRES FEET METRES FEET METRES FEET METRES 29.94 9.13 1 9.13 29.94 9.13 29.94 9.13 29.94 9.13 29.94 9.13 29.94 9.13 29.99 9.14 29.99 9,14 29.99 9.14 2 29.94 9-10 29.79 9.08 29.79 9.08 29.74 9.06 29.89 9.11 29.84 3 4 29.64 9.03 29.64 9.03 29.59 9.02 29.59 9.02 29.54 9.00 29.44 8.97 29.44 8,97,29,39 8.96 29.34 8.94 29.34 8.94 5 8.93 8.93 29.29 8.93 29.29 8:93 29:29 8.93 29.29 29.29 -6 7 8.93 29:29 8.93 29.15 8.88 29.19 8.90 29.19 8.90 29.29 29.19 8.90 29.19 8.90 29.19 8.90 29.04 8.85 29.04 8,85 8. 9 29.04 8.85 29.04 8.85 29.04 8.85 29.04 5.85 29.04 8.85 8.85 29.04 8.85 29.04 10 29.04 6.85 29.04 8.85 29.04 8.85 29.09 8.87 29.09 41 8.87 29.09 8.87 29.09 8.87 29.09 8.87 8.88 29.14 3.88 29.14 8.88 29.14 8.88 29.14 8.88 29.14 12 8.82 28.89 8.82 28.34 8.81 28.89 8.81 28.84 3.79 13 28.94 8,79 28.84 8.79 28.84 8.79 28.89 8.81 23.94 14 28.84 8.82 15 28.59 8.71 29.69 9.05 29.79 9.03 29.89 9.11 29.94 9.13 9.16 30.04 9.16 30.04 9.16 29.99 9.14 29.99 9.14 16 30.04 9.10 29.79 9.08 29.74 9.05 29.64 17 29.84 9.06 29.69 9.03 18 29.29 8,93 29.24 8.91 29.24 8.91 29.04 8.85 28.94 8.82 19 28.54 8.70 28.54 8.70 28:44 8.67 28.34 8.64 28.29 8.62 20 27,94 8.52 27.89 8.50 27.79 8.47 27.69 8.44 27.59 8.41 21 27.24 8.30 27.29 8.29 27.09 8.26 27.04 8.24 26.99 8.23 26.69 8.14 26.69 8.14 26.64 8.12 26.59 8.10 26.59 3.10 22 26.34 8.03 26.39 8.04 26.39 8.04 26.34 8.03 26.29 8.01 23 7.97 26.14 8.00 26.24 8.00 26.09 24 26.14 7.97 26.24 7.95 7.95 26.04 7.94 25.94 7.91 25.84 7.88 25.79 25 26.09 7.86 26 25.44 7.75 25.39 7.74 25.34 7.72 25.24 7.69 24.29 7.40 27 25.05 7.64 25.04 7.63 24.94 7.60 24.84 7.57 24.79 7.56 28 24.59 7.50 24.59 7.50 24.49 7.46 24.44 7.45 24.39 7.43 29 7.39 21.24 7.39 24.24 7.39 24.09 7.34 24.04 24.25 7,33 7.25 23.79 7.24 23.74 7.24 23.69 30 23.79 7.25 23.74 7.22 31 7.17 23.54 7.17 23.49 7.16 23.39 7.13 23.34 23.54 7.11

PLACE---CHORVARENGA

OCT. 1973

GAUGE NO.31

B.M. LEVEL 37.17 FEET

0900 HOURS 1200 HOURS 1500 HOURS 1800 HOURS DATE 0600 HOURS FEET METRES FEET METRES FEET METRES FEET METRES 30.92 9.42 30.92 9.42 30.92 9.42 30.92 9.42 30.92 9.42 2 30.92 9.42 30.92 9.42 30.92 9.42 30.87 9.41 30.87 9.41 3 9.39 30.77 9.38 30.77 9.38 30.72 9.36 30.72 9.36 30.82 9.32 30.57 9.32 30.57 9.32 30.52 9.30 30,52 4 30.57 9,30 30.47 9.29 30.47 9.29 30.47 9.29 30.47 9.29 30.47 9.29 5 9.29 30.47 9,29 30.47 9.29 30.47 9.29 30.47 30.47 9.29 6 7 9.23 30.22 9.21 30.22 30.32 9.24 30.27 9.23 30.27 9.21 9.17 30.07 8 30.12 9.18 30.12 9.18 30.07 9.17 30.07 9.17 9.13 29.97 9.13 29.97 -9 30.02 9.15 30.02 9.15 29.97 9.13 9.15 30.02 10 29.97 9.13 29.97 9.13 29.97 9.13 30.02 9.15 11 30.07 9.17 30.07 9.17.30.02 9.15 30.02 9.15 30.02 9.15 9.15 30.02 9.15 30.02 9.15 30.07 9.17 30.07 9.17 12 30.02 9,10 29.87 13 29,92 9.12 29.87 9.10 29.87 9.10 29.87 9.10 9.10 29.92 14 29.82 9.09 29.82 9.09 29.87 9.12 30.07 9.17 9.41 30.92 9.35 30.77 9.38 30.82 9.39 30.87 9.42 15 30.67 9.50 31.17 31.22 9.52 31.22 9.52 31.22 .9.52 31.17 9.50 16 17 30.92 9.42 30.87 9.41 30.82 9.39 30.77 9.38 30.72 9.36 9.26 30.32 9.24 30.27 9.23 30.17 9.20 30.07 9.17 18 30.37 19 9.06 29.67 9.04 29.62 9.03 29.52 9.00 29.42 8.97 29,72 20 29.02 8.85 28.92 8.81 28.87 8.80 28.82 8.78 28.77 8.77 8.62 28.17 21 28,42 8.66 28.37 8.65 28.32 3.63 28.27 8,59 8.46 27.72 27.92 8.51 27.87 3.49 27.82 8.48 27.77 22 8.45 27.47 8.37 27.42 8.36 27.42 8.36 27.37 8.34 27.32 23 8.33 27.22 8.30 27.17 8.28 27.19 8.29 27.12 8.27 27.12 8.27 24 8.19 26.82 8.17 26.77 8.16 26.77 3.16 25 26.92 8,21 26:87 8.05 26.37 8.04 26.37 8.04 8.17 26.47 8.09 26.42 26 26.82 27 26.07 7.95 26.02 7.93 25.97 7.92 25.92 7.90 25.87 7.89 7.79 25.52 7.78 25.52 7.78 25.47 7,76 25.62 7.81 25.57 28 29 7.70 25.22 7.69 25.17 7.67 25.12 7.66 25.07 7.64 25.27 7.53 24.67 7.52 24.62 30 24.82 7.57 24.77 7.55 24.72 7.50 7.44 24.37 7.43 24.32 7.41 24.34 3-1-7.34 24.42 7.42 24.07

是导致 通识 网络克拉克

Material - 3

Bathymetric Chart

and

Cross - Sectional Chart

of The River

