

PHILIPPINE REPUBLIC OF SANGAYAN

JAVENA RIVER BRIDGE CONSTRUCTION PROJECT

FEASIBILITY STUDY REPORT

VOLUME I
ROAD LINES

AUGUST 1976

JAPAN INTERNATIONAL COOPERATION AGENCY

PEOPLE'S REPUBLIC OF BANGLADESH
JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT

FEASIBILITY STUDY REPORT
VOLUME V
ROAD LINKS

JICA LIBRARY



1011786[9]

AUGUST 1976

JAPAN INTERNATIONAL COOPERATION AGENCY

国際協力事業団


| | |
|---------------------|------|
| 受入 月日 '84. 5. 19 | 101 |
| 登録No. 05940 | 61.5 |
| | JP |

FEASIBILITY STUDY REPORT ON JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT

| | | |
|---------------|-------------|--|
| VOLUME | I | SUMMARY AND CONCLUSIONS |
| VOLUME | II | RIVER CONTROL |
| VOLUME | III | BRIDGE |
| VOLUME | IV | RAILWAY LINKS |
| VOLUME | V | ROAD LINKS |
| VOLUME | VI | GEOLOGY AND STONE MATERIAL |
| VOLUME | VII | TRAFFIC AND ECONOMIC BENEFITS |
| VOLUME | VIII | OVERALL CONSTRUCTION PLAN AND ECONOMIC EVALUATION |

ROAD MAP OF BANGLADESH

ROAD NETWORK



ABBREVIATIONS, DEFINITIONS AND UNITS

| | |
|------------------------------|--|
| Bangladesh | The People's Republic of Bangladesh. |
| MOC | Ministry of Communications. |
| IWTA | Inland Water Transport Authority. |
| BWDB | Bangladesh Water Development Board. |
| R & H | Roads and Highways Directorate of the Ministry of Communications. |
| WAPDA | Water and Power Development Authority. |
| JICA | Japan International Cooperation Agency, Government of Japan. |
| OTCA | Former name of JICA. |
| Jamuna River | The Brahmaputra-Jamuna River. |
| Jamuna Bridge Project | Jamuna River Bridge Construction Project. |
| Jamuna Bridge | Tentative name of the bridge in the present project. |
| Preliminary Study Report | Preliminary Report on the Jamuna River Bridge Construction Project prepared by the Preliminary Study Team of OTCA, Mar., 1973 (Written in Japanese). |
| Inception Report | Inception Report on Feasibility Study of Jamuna River Bridge Construction Project submitted by OTCA. |
| Interim Report | Interim Report on Feasibility Study of Jamuna River Bridge Construction Project submitted by JICA. |
| Feasibility Report Volume I | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume I Summary and Conclusions. |
| Feasibility Report Volume II | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume II River Control. |

| | |
|-----------------------------------|---|
| Feasibility Report Volume III | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume III Bridge. |
| Feasibility Report Volume IV | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume IV Railway Links. |
| Feasibility Report Volume V | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume V Road Links. |
| Feasibility Report Volume VI | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume VI Geology and Stone. |
| Feasibility Report Volume VII | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume VII Traffic and Economic Benefits. |
| Feasibility Report Volume VIII | Feasibility Study Report on Jamuna River Bridge Construction Project, Volume VIII Overall Construction Plan and Economic Analysis. |
| Project | Main Works and Construction works, including railways and road links. |
| Main works | Jamuna Bridge construction works comprising Jamuna Bridge, approaches and treatment of the Dhaleswari River. |
| Approach | Railway and/or road between an abutment of the bridge and a point at which it descends to the normal formation. |
| railway links | Railway between an end of the approach and a connection point on the existing railway. |
| road links | Road between the end of an approach and a connecting point on the existing road. |
| Guide bank | Dike built to guide the river flow. |

| | |
|------------|---|
| Gross dike | Dike built crosswise in the river to check the river flow |
| Causeway | Raised path built over wet ground and/or river |
| DIWL | Design high water level |
| DIPL | Design high flood level |
| HWL | High water level |
| PWD | Public Works Department Datum |
| GTS | Great Trigonometrical Survey |
| PH | Proposed height |
| H | Water depth |
| v | Velocity |
| JIS | Japanese Industrial Standard |
| ASTM | American Society for Testing Materials |
| BS | British Standard |
| c | Cohesion of soil |
| ϕ | Internal friction angle of soil |
| C | Clay |
| M | Silt in case of soil classification |
| S | Sand |
| γ_t | Wet density |
| γ_d | Dry density |
| m | meter |
| s, sec | second |
| cm | centimeter |
| mm | millimeter |
| km | kilometer |
| g. gr. | gram |

| | |
|-------------------|----------------------------|
| kg | kilogram |
| lb | pound |
| t, ton | ton (metric) |
| f, ft, (') | foot |
| m ³ /s | cubic meter per second |
| cfs | cubic foot per second |
| gal | gallon |
| F | Fine in case of grain size |
| M | Medium |
| in, (") | inch |
| yd | yard |
| mi | mile |
| ac | acre |
| hr | hour |
| mon | month |
| yr | year |
| sq | square |
| cu | cubic |
| max. | maximum |
| min. | minimum |

| TO CONVERT | TO | Multiply by | |
|------------------------------|---|----------------|---------|
| inches (in.) | millimeters (mm) | | 25.40 |
| inches (in.) | centimeters (cm) | | 2.540 |
| inches (in.) | meters (m) | | 0.0254 |
| feet (ft) | meters (m) | | 0.3048 |
| miles (ml) | kilometers (km) | | 1.609 |
| yards (yd) | meters (m) | | 0.91 |
| square inches (squ.in) | square centimeters (cm ²) | | 6.45 |
| square feet (sq ft) | square meters (m ²) | | 0.093 |
| square yards (sq yd) | square meters (m ²) | | 0.836 |
| acres (ac) | square meters (m ²) | | 4047. |
| square miles (sq ml) | square kilometers (km ²) | | 2.59 |
| cubic inches (cu in) | cubic centimeters (cm ³) | | 16.4 |
| cubic feet (cu ft.) | cubic meters (m ³) | | 0.0283 |
| cubic yards (cu yd) | cubic meters (m ³) | | 0.765 |
| pounds (lb) | kilograms (kg) | | 0.453 |
| tons (ton) | kilograms (kg) | | 907.2 |
| one pound force (lbf) | newtons (N) | | 4.45 |
| one kilogram force (kgf) | newtons (N) | | 9.81 |
| pounds per square foot (pst) | newtons per square meter (N/m ²) | | 47.9 |
| pounds per square inch (psi) | kilonewtons per square meter (KG/m ²) | | 6.9 |
| gallons (gal) | cubic meters (m ³) | | 0.0038 |
| gallons (gal) | liter (c/m ³) | | 3.8 |
| acre-feet (ac-fe) | cubic - meters (m ³) | | 1233. |
| gallons per minuts (spg) | cubic meter/minute (m ³ /min) | | 0.0038 |
| gallons per second (gps) | cubic meter/second | | 0.00063 |
| TAKA (TK) | YEN (Used in the preliminary design) | | 36 |
| US\$ | TAKA | | 13 |
| TAKA (TK) | YEN | | 13 |

C O N T E N T S

LOCATION MAP

ABBREVIATIONS, DEFINITIONS AND UNITS

CONTENTS

| | | |
|-------------|--------------------------------------|----|
| CHAPTER I | INTRODUCTION | 1 |
| 1. | Objective of the Study | 1 |
| 2. | Progress of the Study | 1 |
| 3. | Member of the Road Links Study Team | 2 |
| 4. | Acknowledgement | 2 |
| CHAPTER II | THE AREA FOR ROAD LINKS PLANNING | 3 |
| 1. | General | 3 |
| 1.1 | Topography | 3 |
| 1.2. | Geology | 3 |
| 1.3. | Climate | 3 |
| 1.4. | Population | 3 |
| 1.5. | Land use | 6 |
| 2. | Inventory of Existing Roads | 6 |
| 2.1. | All-weather roads | 6 |
| 2.2. | Roads approaching to the Jamuna | 10 |
| CHAPTER III | PRELIMINARY DESIGN | 15 |
| 1. | Geometric Design Standard | 15 |
| 2. | Design Elements | 15 |
| 2.1. | Major bridges and necessary openings | 15 |
| 2.2. | Embankment | 17 |
| 2.3. | Pavement | 17 |
| 2.4. | Navigation clearance | 18 |
| 3. | Route Location | 18 |
| 3.1. | Horizontal location | 18 |
| 3.2. | Vertical location | 21 |

| | | |
|--------------|---|----|
| CHAPTER IV | COMPARISON FOR PROPOSED FOUR ROAD LINKS | 29 |
| 1. | Comparison of Construction Costs | 29 |
| 2. | Selection of the Most Suitable Site for Bridge Crossing | 32 |
| CHAPTER V | ROAD CRITERIA AND DESIGN ELEMENTS AT THE SIRAJGANJ SITE | 33 |
| 1. | Lane Width | 33 |
| 2. | Analysis of Road Capacity | 35 |
| 2.1. | Traffic forecast | 35 |
| 2.2. | Road capacity | 35 |
| 2.3. | Design volume/capacity ratio | 35 |
| 2.4. | Level of service | 36 |
| 3. | Stability of Embankment | 36 |
| 4. | Volume Change of Soil | 37 |
| 5. | Free Board | 39 |
| 6. | Pavement | 39 |
| CHAPTER VI | DESIGN OF ROAD LINKS FOR BRIDGE CROSSING AT SIRAJGANJ SITE | 44 |
| 1. | Beginning Point and Terminal Point | 44 |
| 2. | Route Location | 44 |
| 2.1. | Right bank | 44 |
| 2.2. | Left bank | 45 |
| 3. | Vertical Alignment | 47 |
| 3.1. | Design high flood level | 47 |
| 3.2. | Proposed height of the roads | 47 |
| 4. | Quantity of the Works | 48 |
| CHAPTER VII | EXECUTION OF THE ROAD LINKS WORKS | 50 |
| 1. | Schedule of Construction Works | 51 |
| 2. | Number of Labour by Year | 52 |
| 3. | Number of Construction Equipment by Year | 55 |
| 4. | Quantity of the Works by Year | 56 |
| 5. | Quantity of the Construction Materials by Year | 57 |
| CHAPTER VIII | CONSTRUCTION COSTS & MAINTENANCE COSTS | 59 |
| 1. | Construction Costs | 59 |
| 2. | Maintenance Works and Their Costs | 65 |

| | | |
|------------|--|-----|
| APPENDIX A | BIBLIOGRAPHY | (1) |
| APPENDIX B | GEOMETRIC DESIGN STANDARDS OF RURAL ROADS IN BANGLADESH | (3) |
| APPENDIX C | PLAN AND PROFILE OF ROAD LINKS OF SIRAJGANJ SITE | (6) |
| APPENDIX D | PLAN OF NO. 1 AND NO. 2 MAJOR BRIDGES | (8) |

FIGURES

| | |
|---------|---|
| Fig.2-1 | LAND LEVEL MAP |
| Fig.2-2 | GEOLOGICAL MAP |
| Fig.2-3 | POPULATION MAP |
| Fig.2-4 | LAND USE MAP |
| Fig.2-5 | ROAD MAP |
| Fig.3-1 | BAHADURABAD SITE |
| Fig.3-2 | GABARGAON SITE |
| Fig.3-3 | SIRAJGANJ SITE |
| Fig.3-4 | NAGARBARI SITE |
| Fig.3-5 | RIVER SECTION SURVEY MAP |
| Fig.3-6 | LEFT SIDE D.H.F.L. |
| Fig.3-7 | RIGHT SIDE D.H.F.L. |
| Fig.5-1 | TYPICAL CROSS SECTION |
| Fig.5-2 | SLIP CIRCLE ANALYSIS |
| Fig.5-3 | DESIGN CHART-2 |
| Fig.5-4 | C.B.R. DESIGN CURVES |
| Fig.5-5 | TYPICAL PAVEMENT SECTION FOR ROAD LINKS |
| Fig.6-1 | ROUTE LOCATION MAP |
| Fig.7-1 | SCHEDULE OF CONSTRUCTION WORKS |

TABLES

| | |
|-------------|---|
| Table 2-1 | INVENTORY OF ROAD FACILITIES |
| Table 3-1 | GEOMETRIC DESIGN STANDARDS |
| Table 3-2 | SPIILWAY & BRIDGE OPENINGS |
| Table 3-3 | CLEARANCE CLASSIFICATION |
| Table 4-1 | TOTAL LENGTH |
| Table 4-2 | CONSTRUCTION COST IN PHASE I |
| Table 5-1 | TRAFFIC FORECAST |
| Table 5-2 | ROAD CAPACITY |
| Table 5-3 | DESIGN VOLUEM - CAPACITY RATIO |
| Table 7-1 | NUMBER OF LABOUR BY YEAR (TOTAL) |
| Table 7-2 | - DO - (1ST YEAR) |
| Table 7-3 | - DO - (2ND YEAR) |
| Table 7-4 | - DO - (3RD YEAR) |
| Table 7-5 | NUMBER OF CONSTRUCTION EQUIPMENT BY YEAR |
| Table 7-6 | QUANTITY OF WORKS BY YEAR |
| Table 7-7-1 | QUANTITY OF CONSTRUCTION MATERIALS |
| Table 7-7-2 | - DO - |
| Table 8-1 | UNIT COSTS |
| Table 8-2 | TOTAL CONSTRUCTION COSTS OF THE ROAD LINKS |
| Table 8-3 | CONSTRUCTION COSTS OF THE ROAD LINKS BY YEAR (1ST YEAR) |
| Table 8-4 | - DO - (2ND YEAR) |
| Table 8-5 | - DO - (3RD YEAR) |
| Table 8-6 | NUMBER OF LABOURS |
| Table 8-7 | QUANTITY OF MATERIALS FOR MAINTENANCE WORKS |
| Table 8-8 | UNIT COST |
| Table 8-9 | MAINTENANCE COSTS |

CHAPTER I

INTRODUCTION

1. Objective of the Study.

At the request of the Government of the People's Republic of Bangladesh, the Government of Japan decided to conduct a feasibility study for the construction of a bridge over the Brahmaputra-Jamuna River as its international economic assistance contribution.

The objective of the present study is the planning of road links between all-weather roads on both sides of the Jamuna River and the proposed sites for bridge construction, from upstream to downstream on the Jamuna River, the Bahadurabad site, the Gabargaon site, the Sirajganj site and the Nagarbari site, from the viewpoint of road engineering.

First, in Phase I study, designs and initial costs estimation were carried out for the road links at every four proposed sites to connect the Jamuna Bridge with the existing all-weather roads including the Tangail - Bhuapur - Gopalganj Road and the Sirajganj - Hatikumrul Road, on both sides of the Jamuna.

Second, next to the selection of the most suitable site for bridge construction, in Phase II designs and estimates of construction and maintenance costs for a two-lane undivided highway at the Sirajganj site have been made.

This report gives the results of the study made by the Road Link Study Team during the period from January 1974 to March 1976 in accordance with the Inception Report which was submitted by the Japan International Cooperation Agency to the government of the People's Republic of Bangladesh in August 1973.

2. Progress of the Study.

When the Preliminary Study Team for the Jamuna River Bridge Construction Project was dispatched in December 1972 by the Overseas Technical Cooperation Agency, one of the Japanese governmental executing agencies, the Government of Japan proposed four candidate sites for Jamuna Bridge construction from upstream to downstream; namely, downstream from Bahadurabad, near Gabargaon, about 10 km downstream of Sirajganj and about 20 km upstream from Aricha. For the purposes of reconnoitering the existing road on both sides of the Jamuna River and collecting data necessary to the study of the above-mentioned four sites, H. Nishikawa and K. Ohashi, road engineers, were sent to Bangladesh from January 18, 1974 to February 22, 1974.

During the stage of compiling the Interim draft report, a meeting was held in Tokyo from August 31, 1974 to September 13, 1974 in order to discuss the selection of the most suitable site for bridge crossing and some problems in each field of the study team. The further discussion meeting was held in Dacca from October 28, 1974 to November 6, 1974. In that meeting, the Sirajganj site was chosen as the most

suitable for the Jamuna bridge construction.

During the stay of the Japanese delegation in Dacca from November 29, 1974 to December 14, 1974 the Interim Report was submitted to the Ministry of Communications and the location of bridge axis in the Sirajganj site was determined on the basis of aerial photographs newly taken by the Japanese Survey Team in November 1974.

Soil investigation and the main river cross section survey on the road link at the Sirajganj site were also carried out by the Japanese Survey Team in the 1974/1975 dry season.

Based upon the survey results and additional flood data in 1974, the road link study plan has been completed.

3. Members of the Road Links Study Team.

The study was undertaken by Mitsui Consultants Company, Ltd. Tokyo key members who were engaged in the study were:

| | |
|--------------------|---------------|
| Kunimura Nagashima | Team Leader |
| Harumi Nishikawa | Road Engineer |
| Kunio Ohashi | Road Engineer |

4. Acknowledgement.

The Study Team wishes to extend its great appreciation for the cooperation offered by the authorities of the Government of the People's Republic of Bangladesh, especially its wholehearted gratitude to the members of the counterpart team; and the Study Team wishes to express its gratitude to the Embassy of Japan in Dacca for their kind cooperation and encouragement.

CHAPTER II

THE AREA FOR ROAD LINK PLANNING

1. General.

1.1. Topography.

Generally speaking the ground slopes towards the south, and most of the land of the project area lies between the 20 ft. and 60 ft. contourlines above the Survey of Bangladesh level. All of the land elevations described in this report are in terms of the Great Trigonometrical Survey (G.T.S.) data of the Survey of Bangladesh. To put G.T.S. data in terms of PWD data, 1.509 feet (0.46 m) is to be added. The land in the Western part of the Jamuna is generally higher than the eastern part of the project area.

The land level map is shown in Fig. 2-1.

1.2. Geology.

The project area is entirely a part of the Bengal Basin which is filled with alluvium gradually deposited by the Jamuna and its numerous tributaries in the quaternary geological age. The alluvial deposits typically range from silt and clay to sand. All alluvial deposits in the Basin comprise Pleistocene and recent sediments. The Jamuna sediments are characterised by a higher percentage of fine materials and a typically red-brown colour. The project area consists of the flood plains of the Jamuna, its numerous tributaries and distributaries.

The geological map is shown in Fig. 2-2.

1.3. Climate.

Climatically, the country has two distinct seasons, a dry season from October to May and a wet season from June to September. Over 80% of the annual rainfall occurs during the wet monsoon or rainy season when flood invariably occurs as well. The normal annual rainfall varies from approximately 70 in. to 80 in. in the project area. In addition the project area is the flooded area of the Jamuna. The recent maximum flood occurred in the year 1974, which reportedly corresponds to 50 year flood.

1.4. Population.

The population of Bangladesh, now estimated at 76 million, is growing at an annual rate of over 3%. This adds more than 2 million people each year to a land whose population density is already one of the highest in the world. The population map which was made by the U.N. is shown in Fig. 2-3.

Fig. 2 - 1 LAND LEVELS MAP





Fig. 2 - 2 GEOLOGICAL MAP



1.5. Land Use.

Land use in Bangladesh is generally intensive, involving rotation of two or more crops per year on the same piece of land. It is also well adjusted to the environmental conditions, especially to land levels in relation to the flooding.

Various kinds of paddy may be grown on different parts of the land depending on flood depth and duration.

The economy is dominated by the agricultural sector which contributes, directly and indirectly, more than two-thirds of the gross domestic product, absorbs the bulk of the employed labour force and provides the only source of foreign exchange earnings.

Land use map is shown in Fig. 2-4.

2. Inventory of Existing Roads and Facilities.

Road map is shown in Fig. 2-5.

2.1. All weather road.

2.1.1. DACCA-ARICH SECTION (ASIAN HIGHWAY ROUTE A-1, ROUTE A-2).

Asian Highway Routes A-1 and A-2 constitute this Section. Works are under way for improving and widening it to a 2-lane pavement over 90 kilometers long. It runs mostly over paddy fields except for a hilly portion on the Dacca side of Nayarhat.

Three R & H ferries have operated within this Section at the Buriganga, Bangsh and Kaliganga rivers but at each of these sites bridge construction is in progress under U.S. AID.

At Mirpur the road crosses the Buriganga by a 1-lane truss bridge but this bridge is used only by light vehicles, while heavy vehicles use the R & H ferry.

2.1.2. NAGARBARI - SHAZADPUR - ULLAPARA SECTION.

This is a section of about 50 kilometers, the portion of Asian Highway Route A-2 (395 kilometer from Tetsuria on the Indian border to Nagarbari). This is a 1-lane paved road. This area is in the vicinity of the confluence of the Ganges and the Jamuna and the road runs on an embankment of several meters high.

One R & H ferry operates at the Bangari within this Section.

2.1.3. ULLAPARA - BOGRA - GOBINDGANJ SECTION.

This Section of about 100 kilometers is also a portion of Asian Highway Route A-2 and has a 1-lane pavement for most of its length. Around Bogra, however, it has a paved width of about 2-lanes. From Ullapara to Sherpur the high embankment continues but from there the road runs over rolling terrain.

Fig. 2 - 3 POPULATION MAP






Fig. 2-4 LAND USE MAP



| MAINLY AUS RICE ROTATIONS | | SECONDARY LAND USE | | OTHER LAND USE | |
|---------------------------|--|--------------------|-------------|----------------|--|
| 3 | Low (low water) - Annual Rice | 1 | Forest | 1 | Low (low water) - Annual Rice |
| 4 | High (high water) - Annual Rice | 2 | Open Land | 2 | High (high water) - Annual Rice |
| 5 | Low (low water) - Transplanted Aman Rice | 3 | Barren Land | 3 | Low (low water) - Transplanted Aman Rice |
| 6 | High (high water) - Transplanted Aman Rice | 4 | Barren Land | 4 | High (high water) - Transplanted Aman Rice |
| 7 | Low (low water) - Broadcast Aman Rice | 5 | Barren Land | 5 | Low (low water) - Broadcast Aman Rice |
| 8 | High (high water) - Broadcast Aman Rice | 6 | Barren Land | 6 | High (high water) - Broadcast Aman Rice |
| 9 | Low (low water) - Broadcast Aman Rice | 7 | Barren Land | 7 | Low (low water) - Broadcast Aman Rice |
| 10 | High (high water) - Broadcast Aman Rice | 8 | Barren Land | 8 | High (high water) - Broadcast Aman Rice |
| 11 | Low (low water) - Broadcast Aman Rice | 9 | Barren Land | 9 | Low (low water) - Broadcast Aman Rice |
| 12 | High (high water) - Broadcast Aman Rice | 10 | Barren Land | 10 | High (high water) - Broadcast Aman Rice |
| 13 | Low (low water) - Broadcast Aman Rice | 11 | Barren Land | 11 | Low (low water) - Broadcast Aman Rice |
| 14 | High (high water) - Broadcast Aman Rice | 12 | Barren Land | 12 | High (high water) - Broadcast Aman Rice |
| 15 | Low (low water) - Broadcast Aman Rice | 13 | Barren Land | 13 | Low (low water) - Broadcast Aman Rice |
| 16 | High (high water) - Broadcast Aman Rice | 14 | Barren Land | 14 | High (high water) - Broadcast Aman Rice |
| 17 | Low (low water) - Broadcast Aman Rice | 15 | Barren Land | 15 | Low (low water) - Broadcast Aman Rice |
| 18 | High (high water) - Broadcast Aman Rice | 16 | Barren Land | 16 | High (high water) - Broadcast Aman Rice |
| 19 | Low (low water) - Broadcast Aman Rice | 17 | Barren Land | 17 | Low (low water) - Broadcast Aman Rice |
| 20 | High (high water) - Broadcast Aman Rice | 18 | Barren Land | 18 | High (high water) - Broadcast Aman Rice |
| 21 | Low (low water) - Broadcast Aman Rice | 19 | Barren Land | 19 | Low (low water) - Broadcast Aman Rice |
| 22 | High (high water) - Broadcast Aman Rice | 20 | Barren Land | 20 | High (high water) - Broadcast Aman Rice |
| 23 | Low (low water) - Broadcast Aman Rice | 21 | Barren Land | 21 | Low (low water) - Broadcast Aman Rice |
| 24 | High (high water) - Broadcast Aman Rice | 22 | Barren Land | 22 | High (high water) - Broadcast Aman Rice |
| 25 | Low (low water) - Broadcast Aman Rice | 23 | Barren Land | 23 | Low (low water) - Broadcast Aman Rice |
| 26 | High (high water) - Broadcast Aman Rice | 24 | Barren Land | 24 | High (high water) - Broadcast Aman Rice |
| 27 | Low (low water) - Broadcast Aman Rice | 25 | Barren Land | 25 | Low (low water) - Broadcast Aman Rice |
| 28 | High (high water) - Broadcast Aman Rice | 26 | Barren Land | 26 | High (high water) - Broadcast Aman Rice |
| 29 | Low (low water) - Broadcast Aman Rice | 27 | Barren Land | 27 | Low (low water) - Broadcast Aman Rice |
| 30 | High (high water) - Broadcast Aman Rice | 28 | Barren Land | 28 | High (high water) - Broadcast Aman Rice |
| 31 | Low (low water) - Broadcast Aman Rice | 29 | Barren Land | 29 | Low (low water) - Broadcast Aman Rice |

1. Principal roads
 2. District boundaries
 3. Subdivisions of these boundaries
 4. Contour lines
 5. Contour interval
 6. Contour interval
 7. Contour interval
 8. Contour interval
 9. Contour interval
 10. Contour interval
 11. Contour interval
 12. Contour interval
 13. Contour interval
 14. Contour interval
 15. Contour interval
 16. Contour interval
 17. Contour interval
 18. Contour interval
 19. Contour interval
 20. Contour interval
 21. Contour interval
 22. Contour interval
 23. Contour interval
 24. Contour interval
 25. Contour interval
 26. Contour interval
 27. Contour interval
 28. Contour interval
 29. Contour interval
 30. Contour interval
 31. Contour interval

Fig. 2-5 ROAD MAP



Within this Section the bridges damaged during the War of liberation were particularly noticeable. Those bridges have been replaced by Bailey Bridges but they are still deemed to be the bottleneck to traffic.

2.1.4. HAYARHAT - KALIAKUR BYPASS.

This road, which was constructed in 1972, runs over rolling terrain for the most part with fair horizontal alignment. It has one paved lane but at the portion around the structures it actually has a 2-lane paved width.

2.1.5. DACCA - JOYDEBPUR SECTION.

This road runs about 30 kilometers from Dacca to Joydebpur. It has a 4-lane divided highway section for about 6 kilometers from the point of intersection with the railway near Dacca Airport to where it again intersects with the railway near the New Kurmitola Dacca Airport. This Section is topographically hilly.

From Tongi the roadway becomes a undivided 2-lane road up to Joydebpur.

Most of this Section is on a low embankment.

2.1.6. JOYDEBPUR - TANGAIL SECTION.

The Joydebpur - Tangail section is a 1-lane paved road of about 60 kilometers in length.

From Joydebpur to Mirzapur the road runs over rolling terrain for about 25 kilometers and from Mirzapur to Tangail the embankment section continues for about 35 kilometers. Conspicuous within this embankment section are the bridges damaged during the War of liberation and a sharply curved portion with poor horizontal and vertical alignment between Kaliakur and Karatia.

2.1.7. TANGAIL - JAMALPUR SECTION.

This section, from Tangail to Jamalpur via Madhupur, of about 85 kilometers in length, with poor horizontal alignment that does not permit comfortable driving or safe overtaking. There is hilly terrain around Tangail but the rest of the road passes paddy fields for the most part. The broad shoulder on the left toward Jamalpur, made wider than the other side for use by ox-carts, is a characteristic of this 1-lane paved road.

2.2. Road approaching to the Jamuna.

Inventory table is shown in Table 2-1.

2.2.1. Left side.

L-1) JAMALPUR - BAHADURABAD SECTION

The existing road from Jamalpur to Bahadurabad the railway ghat, is about 40 kilometers in length.

This road runs keeping almost parallel to the Jamalpur - Bahadurabad Railway and the Brahmaputra, also called Old Jamuna. There are four railway stations between Jamalpur and Bahadurabad and the road is paved with brick near the stations, but most of the rest is kacha road.

The driving time by jeep for this section is three and a half hours.

L-2) JAMALPUR - GABARGAON SECTION

This existing approach road is about 30 kilometers in length and it runs almost straight westward from Jamalpur to Gabargaon.

During the rainy season two private ferries have been operating on this section. They are merely contrivances consisting of two barges bound together with bamboo platforms laid between and which can hardly carry a jeep. During the survey of this section the jeep was trapped in an ox-cart but from which it was freed with much difficulty with the help of its winch.

The driving time by jeep for this section is three hours.

L-3) ELENGA - GOPALGONJ SECTION (T.B.G. Road)

The approximately 25 kilometers of this road, from Elenga to the left bank of the Jamuna via Bhuapur, is now under reconstruction. The initial section of 19 kilometers from Elenga to Bhuapur consists of improvement and widening of the existing road and the section of 6 kilometers from Bhuapur to the left bank of the Jamuna is new road construction. It will be opened in 1977.

- a) The Aricha - Nagarbari Road Ferry Ghat is the only existing highway link between Dacca and northern districts of the country. Nevertheless the present overcrowded ferry can no longer function as an effective link between Dacca and northern districts. A new road ferry ghat which would be able to navigate to the north of Aricha during the dry season is therefore required.
- b) On the right side there is a road under reconstruction between Hatikumrul on the Asian Highway and Sirajganj where there is a passenger ferry ghat at present. On the left side also there is a road under reconstruction between Elenga, about 8 kilometers to the north of Tangail on Tangail - Mymensingh Road, and Bhuapur. Not much new road construction is therefore needed for either route. Between Gopalganj and Sirajganj the ferry can operate even during the dry season.

Under the above circumstances and in compliance with requirements, the T.B.G. Road, Sirajganj - Hatikumrul Route was planned as a road link between Dacca and northern districts. The Gopalganj Road Ferry Ghat was planned at first for use during the rainy and dry seasons but the plan was later changed on 27th January in 1974 to make it available for the dry season only.

Table 2-1 INVENTORY OF ROAD FACILITIES

EXISTING APPROACH ROADS

| ROUTE & SECTION | DISTANCE | ALL-WEATHER ROAD | | FAIR WEATHER JEEPABLE | NO ACCESS | STRUCTURE | | FERRY CROSSING | FORD | LINIOR-METER - OF - SPILLWAY OPENING - PER - KILOMETER |
|---|----------|------------------|-----------------|-----------------------|--------------------|-----------|-----------------|----------------|------|--|
| | | 1 LANE PAVEMENT | GRAVEL SURFACED | | | BOX - CUL | SPILLWAY BRIDGE | | | |
| BAHADURABAD SITE JAMALPUR - BAHADURABAD | 42.0 km | | | 42.0 km | | 6 | 9 | | 1 | $\frac{89^m}{42.0^km} = 0.002$ |
| | 20.0 km | 16.5 km | | 3.5 km | | 3 | 7 | PRIVATE | | $\frac{92^m}{16.5^km} = 0.006$ |
| GABARGAON SITE JAMALPUR - GABARGAON | 32.5 km | | | 32.5 km | | 4 | 2 | PRIVATE | | $\frac{22.5^m}{32.5^km} = 0.001$ |
| | 20.5 km | BRICK 9.2 km | | 11.3 km | | | 17 | PRIVATE | 1 | $\frac{313^m}{20.5^km} = 0.015$ |
| SEBALGANJ SITE ELINGA - GOPALGANJ | 26.0 km | | | UNDER CONST 19.0 km | 7.0 km | 5 | 12 | | 2 | $\frac{358^m}{19.0^km} = 0.019$ |
| | 6.0 km | 1.6 km | | UNDER CONST 4.4 km | | | 5 | | | $\frac{73^m}{6.0^km} = 0.013$ |
| NATIKAMPUL - SIRAJGANJ SIRAJGANJ - SIRAJGANJ | 17.0 km | | | UNDER CONST 17.0 km | | 6 | 4 | RAH 1 | 4 | $\frac{92^m}{17.0^km} = 0.005$ |
| | 13.8 km | 9.0 km | 2.8 km | | RIGHT EMSTY 2.0 km | | | | 1 | $\frac{24^m}{11.8^km} = 0.002$ |
| NAGARBARI SITE TANGAIL - NAGARPUR (NAGARBARI SITE) | 19.5 km | BRICK 5.8 km | | 13.7 km | | | | PRIVATE | | $\frac{264^m}{19.5^km} = 0.013$ |
| | 21.0 km | | | 16.0 km | RIGHT EMSTY 5.0 km | 2 | 7 | PRIVATE | 8 | $\frac{111^m}{16.0^km} = 0.007$ |

L-4) TANGAIL - CHARABARI SECTION

This section is about 4.5 kilometers from Tangail to Charabari where there is a rainy season ferry ghat at present. On January 27, 1974 R & H changed the road ferry ghat for the rainy season, which was first planned for Gopalgonj, to Charabari.

Works on this section are under way by R & H for improvement and widening.

L-5) TANGAIL - NAGARPUR SECTION

The existing road from Tangail to Nagarpur is about 20 kilometers long. Two private ferries operate in this Section.

The road is 1-lane and paved with brick for about 6 kilometers from Tangail to the first ferry site but most of the rest of the section is kacha road. This initial section now has heavier ox-cart traffic and horse-cart traffic than other approach roads on the left side. The first ferry site from Tangail is in shallow water that a jeep could drive through.

The second ferry site is located on the Dhaleswari river, about 1 kilometer wide, with a steep right bank and a sand beach on the left bank. Its width in the dry season is reduced to about 100 meters. The section from Nagarpur to the left bank of the Jamuna was not passable by jeep due to the erosion of the road.

The driving time between Tangail and Nagarpur is three hours.

2.2.2. Right side.

R-1) GOBINDGANJ - BAHADURABAD SITE

This existing road is about 30 kilometers long, from Gobindganj, about 30 kilometers to the north of Bogra, to Shaghatta, of which the last section of 10 kilometers was not passable by jeep due to erosion of the existing road. For about 17 kilometers from Gobindganj to Gapalpur, where there is a sugar mill, the road is 1-lane and paved with concrete but many cracks are observed.

In the last section from Capalpur to the Right Flood Embankment are destroyed by flood.

R-2) BOGRA - SHARIAKANDI SECTION

From Bogra to the private ferry site of Shariakandi, about 20 kilometers, the road passes over comparatively rolling terrain. For 9 kilometers from Bogra to Gabtali, the road is 1-lane, paved with bricks and runs parallel to the railway. At present a light public bus is servicing between Bogra and Gabtali. From Gabtali to Shariakandi, 10 kilometers, the route is a kacha road.

The driving time by jeep from Bogra to Shariakandi is one and a half hours.

R-3)

a) HATIKUMRUL - SIRAJGANJ TOWN SECTION

About 17 kilometers of road from Hatikumrul on the Asian Highway to Sirajganj is now under construction. At present the R & H ferry and a private ferry operate at a point of 5 kilometers from Hatikumrul.

The driving time by jeep from Hatikumrul to Sirajganj Town is one and a half hours.

b) SIRAJGANJ TOWN - SIRAJGANJ SITE SECTION

This section extends from Sirajganj town straight southward for about 12 kilometers to the Right Embankment. For about 9 kilometers from Sirajganj the road is 1-lane, paved with concrete. Thenceforth kacha road extends for 3 kilometers to the Right Embankment of the Jamuna. On the latter route there was the Hurasagar river with 100 m dried river bed.

The driving time by jeep from Shirajganj town to the Right Embankment is 45 minutes.

R-4) SHAHADPUR - NAGARBARI SITE

From Shahadpur to the Right Embankment of the Jamuna the length of the road is 14 kilometers long and from the Right Flood Embankment to the right bank of the Jamuna the length is 16 kilometers. Both are kacha roads totalling 16 kilometers in length.

The shortest route mentioned on the topographic map of 1:50,000 scale, from Shahadpur to the Right Embankment, has a private ferry only on the Karatoya river but none on the other tributaries. It is considered possible to drive from Sirajganj to the Nagarbari site by way of the Right Flood Embankment crest, which has a width of about 5 m.

The driving time by jeep from Shahadpur to Nagarbari site is two and a half hours.

CHAPTER III
PRELIMINARY DESIGN

1. Geometric Design Standard.

For geometric design standards in Phase I, the "Geometric Design Standards of Rural Road in Bangladesh" shown in Appendix B were adopted as they were.

With regard to road width a total road width of 40 feet for primary road stipulated in the above standards were adopted with due considerations given to the result of the future traffic forecast in Phase I.

Table 3-1 shows the geometric design standards.

Table 3-1. GEOMETRIC DESIGN STANDARDS

| | | 2-LINE TWO-WAY HIGHWAY |
|-------------------------|--------|------------------------|
| ROADBED | | 12.200 m (40'-0") |
| LANE | | 3.355 m (11'-0") |
| SHOULDER | | 2.440 m (8'-0") |
| EARTHBERM | | 0.305 m (1'-0") |
| DESIGN SPEEDS | RURAL | 96.5 km (60 mph) |
| | URBAN | 80.5 km (50 mph) |
| RUNNING SPEEDS | RURAL | 72.5 km (45 mph) |
| | URBAN | 64.5 km (40 mph) |
| RADIUS OF CURVATURE | 60 mph | 350 m (1,146') |
| | 50 mph | 230 m (754') |
| GRADES | | 3.0% MAX |
| PASSING SIGHT DISTANCE | 60 mph | 610 m (2,000') |
| | 50 mph | 520 m (1,700') |
| STOPPING SIGHT DISTANCE | 60 mph | 145 m (475') |
| | 50 mph | 107 m (350') |
| SUPERELEVATION | | 8.0% MAX |

2. Design Elements.

2.1. Major bridge and necessary openings.

Topographic surveys and inland waterway investigations were not carried out in the Phase I study. Therefore, the study team divided the

structure design into two types, one for the bridge longer than 100 m and the other for the spillway and the bridge shorter than 100 m because of the accuracy of the 1:50,000 Photo-mosaic and Topographic map.

The study team made preparations for the site selection for the major bridges, which are longer than 100 m, according to the study data collected at sites and 1:50,000 photo-mosaic. In relation to spillways and a bridge openings shorter than 100m, the study team adopted the value of 4% of openings shorter than 100 m, the study team adopted the value of 4% of opening ratio "linear-meter-of-spillway-and-bridge-shorter-than-100 m-opening-per-kilometer" of the structure to total road length, is taken from the data of Aricha-Kaliganga Road inventory, which is the only all-weather road in Bangladesh at right angles to the Jamuna. The calculated figure is shown in Table 3-2.

Table 3-2 SPILLWAY & BRIDGE OPENINGS
KALIGANGA RIVER - ARICHA ROAD

| DISTANCE | EXISTING & PROPOSED STRUCTURE LENGTH | |
|----------------|--------------------------------------|--|
| | SPILLWAY & BRIDGE L 100 m | |
| 0 - 1.6 km | FERRY CROSSING | 666.0 m UNDER CONSTRUCTION KALIGANGA BRIDGE |
| " | 18.3 m TEE - BM | |
| 1.6 - 3.2 km | 24.4 m 2 SPAN TEE - BM | |
| 3.2 - 4.8 km | 36.6 m 3 SPAN TEE - BM | |
| " | 24.4 m MULTI-SPAN BOX CUL | |
| " | 90.0 m | PROPOSED SINGLE UNIT "OVERLAND FLOW" |
| 4.8 - 6.4 km | 24.4 m 2 SPAN TEE - BM | |
| " | 30.5 m MULTI-SPAN BOX CUL | |
| 6.4 - 8.0 km | 18.3 m TEE - BM | |
| 8.0 - 9.6 km | 50.0 m 3" SPAN TEE-BM | PROPOSED SINGLE UNIT "OVERLAND FLOW" |
| " | 90.0 m | |
| 9.6 - 11.2 km | 18.3 m TEE - BM | |
| " | 36.6 m MULTI-SPAN BOX CUL | |
| 11.2 - 12.8 km | 50.0 m 3 SPAN TEE - BM | |
| 12.8 - 14.4 km | 18.3 m TEE - BM | |
| 14.4 - 16.0 km | 50.0 m 3 SPAN TEE - BM | |
| 16.0 - 17.6 km | 42.7 m MULTI-SPAN BOX CUL | |
| " | 18.3 m TEE-BM | |
| 17.6 - 19.2 km | 30.0 m MULTI-SPAN BOX CUL | |
| " | 50.0 m 3 SPAN TEE - B | |
| " | 24.3 m MULTI-SPAN BOX OIL | |
| TOTAL | 745.4 m | |

$$\frac{745.4 \text{ m}}{19.2 \text{ km}} = 0.039 = 4\%$$

2.2. Embankment.

It is recommended that the whole alignment will be built with a minimum free-board of three feet above the design high flood level. This is considered necessary because the maximum benefits to be derived from the road can be realized if it is passable throughout the year. In other words, three feet free-board has been provided to keep the moisture content of the subgrade within an allowable level by preventing saturation during the flood season, and spillway openings have been provided to preventing the rapid deterioration of the pavement and embankment.

Soil investigation were not carried out for Phase I study. On the other hand, a 1:2 embankment side slope is standard for roads in Bangladesh. For the purpose of the cost estimate, therefore, a 1:2 embankment side slope was adopted for all proposed roads.

Turfing will be required to maintain the normal height embankment side slope without sloughing. Enchased brick rivetment in the high approaches of bridge and spillway will be required to keep the embankment side slope from sloughing and to prevent erosion at the bridge abutments.

A soil in Bangladesh vary from sandy clay to silty clay. They are usually not suitable materials for embankment and have low stabilization quality. Road embankment and bridge approaches will be constructed by spreading and compacting the borrowed earth from the road sides. The ground surface of all embankment borrowpits and embankment foundations should, therefore, be stripped to remove organic materials. However, where a bad soil is encounters with the top layer of subgrade of 2 feet thick, this is to be adequately mixed with sand and duly compacted. Earth moving and compacting equipment will be used in conjunction with handbasket labor to distribute the embankment materials and ensure a uniform embankment section. The moisture content control will be achieved by use of compaction equipment.

For the purpose of cost estimates, embankment earth work quantities are to be increased by 10% to allow for settling.

2.3. Pavement.

From practical experience in this country, a flexible pavement is considered the best to ensure against any possible settling of the embankment.

From practical experience in this country, it has been observed that a 3 inch layer of brick flat soling under a 9 inch crushed brick water bound macadam, with a 2 inch bituminous macadam or concrete surface, for a total thickness of 14 inches, is suitable for this kind of Project Area. The sub-base is provided for the distribution of the load on the subgrade and it also aids in drainage. The road links study team adopted the value of 6 inches for the sub-base, being the minimum value for drainage.

2.4. Navigation clearance.

The classified waterway clearance is determined by local requirement and need. BIWTA set the clearance classification, but the waterways which the proposed alignment would cross have not been officially classified.

For the purpose of cost estimates, the study team determined the navigation clearance classification, for waterways that were not classified, from the NEDECO report and BIWTA's clearance classification method.

The determined clearance classification is shown in Table 3-3.

Table 3-3 CLEARANCE CLASSIFICATION

| WATERWAY TRAFFIC DESCRIPTION | CLASS | VERTICAL CLEARANCE ON H.F.L. | RECOMMENDED CLASSIFICATION |
|--|-------|------------------------------|---|
| LARGEST VESSELS - RIVER STEAMERS 6 feet DRAUGHT - GROUP | A | 40 feet | |
| LARGEST VESSELS - CARGO BARGES & CARGO SAIL BOATS 4.5 feet DRAUGHT - GROUP | B | 25 feet | HURASAGAR RIVER |
| LARGEST VESSELS - COUNTRY BOATS 3 feet DRAUGHT - GROUP | C | 12 feet | BANGALI RIVER KARATOYA RIVER CJATA: RIVER |
| | OTHER | 6 feet | OTHER MINOR CHANNELS |

3. Route Location.

3.1. Horizontal location.

3.1.1. Primary elements of horizontal alignment.

- (1) The definition of Road Links proposed by the study team are the linking all-weather roads to the proposed Jamuna Bridge sites from existing all-weather roads, including the Tangail-Bhuapur-Gopalganj and Sirajganj-Htaikumrul roads, on the both sides of the Jamuna.

| All-weather Road on Left Side | Proposed Bridge site | All-weather Road on Right Side |
|--|----------------------|--|
| Jamapul Madhupur Road | Bahadurabad Site | Nagarbari-Saidpur Road (Asian Highway A-2) |
| Jamapul-Madhupur Road | Gabangaon Site | Nagarbari-Saidpur Road |
| Tangail-Bhuapur-Gopalgonj Road & Tangail-Madhupur Road | Sirajganj Site | Sirajganj-Hatikumrul Road |
| Dacca-Aricha Road (Asian Highway A-1, A-2) | Nagarbari Site | Nagarbari-Saidpur Road |

(2) Taking into account the results of the field survey and regional speciality of Bangladesh, the study team planned the horizontal alignment, giving priority to the (1) reconstruction of existing roads (2) stable river crossings (3) shortest distance. The proposed alignment passes through principal villages because of the above.

Besides, there are many marshes in the project area. Therefore the road links study team designed the route with detours and curves so as to keep away from the marshes on the left side of Bahadurabad and Gabargaon.

3.1.2. Proposed route.

Road Link Type B: Dist. bew. guide banks 4.2 km
 Type C: Dist. bew. guide banks 5.2 - 5.6 km

(1) Bahadurabad Site B = 67,500 m, C = 67,000 m

Right side B, C = 25,000 m

The proposed route follows the existing kacha road, with improving and widening the section from Kamar on the Asian Highway to Shahapur where there is a sugar mill at present, and the existing brick road for the section from Shahapur to Mahimaganj. Thereafter it turns south following the existing road from Gobaripara to Muhammadpur, which will be widened and improved.

Left Side B = 42,500 m, C = 42,000 m

From Jamalpur to northwest up to Dharmakara the proposed road link was planned on the left side of Jamalpur - Bahadurabad Railway and in parallel thereto and to Old Jamuna. Westward from Dharmakura to Ghilabari the present route will be followed, with improving and widening the existing kacha road. The new alignment was planned southward from Ghilabari the proposed bridge site at Rajapur.

Due to the low and marshy ground in this area, it was necessary to lead the route in a large round-about curve to the north.

Proposed Road Links Route Location is shown in Fig. 3-1.

- (2) Gabargaon Site B, C = 65,100 m
 Right side B, C = 31,100 m

The proposed route followed the existing brick paved road from Bogra on the Asian Highway eastward to Gabtali, and the present kacha road from Gabtali to Phurbari improving and widening them. The new alignment was planned from Phurbari southeast to the proposed bridge site at Chandanbaisa.

Left side B, C = 34,000 m

The proposed route goes westward from Kochagar, about 5 kilometers to the south of Jamalpur, crossing the Chatal River up to the proposed bridge site. As there are many marshes and river crossing in this area, like the left bank area of Bahadurabad, almost the whole route is new construction except for the portion between Kochgar and the Chatal River where the existing kacha road is improved and widened.

Proposed Road Links Route Location is shown in Fig. 3-2.

- (3) Sirajganj Site B, C = 29,750 m
 Right side B, C = 15,500 m

From Hatikumrul on the Asian Highway to Slalkal, the Hatikumrul-Sirajganj Highway, now under re-construction for completion in 1978 is wholly used. From Slalkol the new road was planned toward southeast, passing the railway and bypassing Sirajganj Town, up to Banbaria. From Banbaria the route turns southward following the existing partly paved 1-lane road, with widening it, up to Tengrail. From Tengrail the new alignment follows the shortest route to the proposed bridge site.

Left side B, C = 14,250 m

The proposed road goes westwards straight by the use of the existing road from Parima on the Tangail-Bhuapur-Gopalgonj Road, to the end of the existing road.

Thence, it goes southwestwards, crossing the Dhaleswari River, to the proposed site.

Proposed Road Links Route Location is shown in Fig. 3-3.

- (4) Nagarbari Site B, C = 35,250 m
 Right side B, C = 6,500 m

To northeast from Bangram on the Asian Highway to the Hurasagar River, the existing road was followed and widened, and henceforth the new alignment follows the shortest route to the

proposed bridge site.

Left side B, C = 28,750 m

The proposed route starts from Mahadebpur, about 10 kilometers from Aricha on the Dacca-Aricha Road, and extends northwards to Tebaria, with widening and improving the existing kacha road now badly eroded. From there on the new alignment was planned to go westward from Tebaria to the proposed bridge site via Haparikatra.

Proposed Road Links Route Location is shown in Fig. 3-4.

3.2. Vertical location.

3.2.1. Design high flood level.

Flood height is of vital importance for planning of highways in Bangladesh.

Left side

The study team adopted the maximum flood height from the Jamuna river section survey which was recorded at the end of July, 1970. And it is also reported that the year 1970 recorded the largest floods in the recent years.

River section survey map is shown in Fig. 3-5.

Left side D.H.F.L. is shown in Fig. 3-6.

Right side


The study team decided the D.H.F.L. by consultation at the sites for the Bahadurabad (Gobindganj) and Gabargaon (Bogra) sites; because the Nagarbari-Saidpur Road has not been built with a minimum free board above high flood level, and the study team decided the D.H.F.L., from the Stream Gaging Data and 100 year probability for the Right Embankment Project at Sirajganj (Ullapara gage) and Nagarbari (Bagabari gage) sites.

Sirajganj: The 100 year flood elevation at Ullapara was used as the design water profile for the Right Embankment. Therefore, the study team adopted the above figure for Sirajganj site.

Nagarbari: The 100 year flood elevation at Bagabari was not used directly in establishment of design water profile for the Right Embankment. On the other hand, the highest record was observed on August 15, 1955 and was equal to the 1970 Jamuna Record. Therefore, the study team adopted the 1955 figure for the Nagarbari site.

Right side D.H.F.L. is shown in Fig. 3-7.

Fig.3-1 BAHADURABAD SITE









Fig. 3-3 SIRAJGANJ SITE



SIRAJGANJ SITE



| | |
|---------------------|----------|
| DATE OF PREPARATION | 1957 |
| PROJECT NAME | SIKHOVA |
| PROJECT NO. | SIKHOVA |
| SCALE | 1:10,000 |
| BY | SIKHOVA |
| CHECKED BY | SIKHOVA |
| APPROVED BY | SIKHOVA |
| DATE | SIKHOVA |
| PROJECT NO. | SIKHOVA |
| SCALE | SIKHOVA |
| BY | SIKHOVA |
| CHECKED BY | SIKHOVA |
| APPROVED BY | SIKHOVA |
| DATE | SIKHOVA |





Fig.3-4 NAGARBARI SITE



NAGARBARI SITE





Fig. 3 - 5 RIVER SECTION SURVEY MAP





Fig. 3-6 Determination of Left Side High Flood Levels.
Left Side Inland High Water Level (July Aug 1970)

Left Side Inland High Water Level (July, Aug 1970)


Note: All elevation in this table refer to S.O.B datum.



LEGEND

- Determined high flood level
- Proposed high flood level

Fig. 3 - 7 Determination of Right Side High Flood Levels



CHAPTER IV

COMPARISON OF THE FOUR PROPOSED ROAD LINKS

1. Comparison of Construction Costs.

The purpose of Phase I work was to select the most suitable site for a bridge crossing among the four alternative sites. The study team, therefore undertook a comparison of the total construction costs in line with the total road links for the four sites.

From the study, it was made clear that the Sirajganj site is the shortest in length, with the lowest construction cost.

Table 4-1 shows the total length of each site, and Table 4-2, comparison of cost estimate for each site.

Table 4-1 TOTAL LENGTH

Unit : m

| | B Type of Road Links | | | C Type of Road Links | | | Bridge Length longer than 100 m | |
|----------------------|----------------------|------------|-----------|----------------------|------------|-----------|---------------------------------------|-------|
| | Road Link | Embankment | Structure | Road Link | Embankment | Structure | | |
| Bahadurabad, site | Right side | 25,000 | 23,520 | 1,480 | 25,000 | 23,520 | 1,480 | 500 |
| | Left side | 42,500 | 40,680 | 1,820 | 42,000 | 40,200 | 1,800 | 100 |
| | Total | 67,500 | 64,200 | 3,300 | 67,000 | 63,720 | 3,280 | 600 |
| Gabargaon site | Right side | 31,100 | 29,460 | 1,640 | 31,100 | 29,460 | 1,640 | 400 |
| | Left side | 34,000 | 32,000 | 1,960 | 34,000 | 32,040 | 1,960 | 600 |
| | Total | 65,100 | 61,500 | 3,600 | 65,100 | 65,100 | 3,600 | 1,000 |
| Sirajganj site | Right side | 15,500 | 14,800 | 620 | 15,500 | 14,880 | 620 | - |
| | Left side | 14,250 | 13,680 | 570 | 14,250 | 13,680 | 570 | - |
| | Total | 29,570 | 28,560 | 1,190 | 29,750 | 28,560 | 1,100 | - |
| Nagarbari site | Right side | 6,500 | 5,340 | 1,160 | 6,500 | 5,340 | 1,160 | 900 |
| | Left side | 28,750 | 27,300 | 1,450 | 28,750 | 27,300 | 1,450 | 300 |
| | Total | 35,250 | 32,640 | 2,610 | 35,250 | 12,600 | 2,610 | 1,200 |

Table 4-2 CONSTRUCTION COST IN PHASE I

Unit: million Taka

| Article | Total Length of Road Links km (mile) | Earthwork & Land Acquisition | Bridge L 100m | Spillway L 100m | Bridge & Dhaleswari River Cross-dam | Pavement Work | Miscellaneous | Total Amount |
|------------------|--|------------------------------|---------------|-----------------|-------------------------------------|---------------|---------------|--------------|
| Bahadurabad site | B 67.500 (43.3) | 77.5 | 16.1 | 75.0 | | 53.6 | 5.6 | 227.8 |
| | C 67.000 (41.6) | 76.6 | 16.1 | 74.4 | | 53.1 | 5.6 | 225.8 |
| Gabargaon site | B 65.100 (40.4) | 84.4 | 42.5 | 72.2 | | 51.4 | 5.6 | 256.1 |
| | C 65.100 (40.4) | 84.4 | 42.5 | 72.2 | | 51.4 | 5.6 | 256.1 |
| Sirajganj site | B 29.750 (18.5) | 46.7 | | 33.1 | 175.0 | 23.9 | 2.5 | 281.1 |
| | C 29.750 (18.5) | 46.7 | | 33.1 | 175.0 | 23.9 | 2.5 | 281.1 |
| Nagarbari site | B 35.250 (21.9) | 40.3 | 53.9 | 39.2 | | 27.2 | 3.0 | 163.6 |
| | C 35.250 (21.9) | 40.3 | 53.9 | 39.2 | | 27.2 | 3.0 | 163.6 |

2. Selection of the most Suitable Site for Bridge Crossing.

From the viewpoint of road transportation and in consideration of the geology, economy, traffic, and feasibility of a railway link, the Sirajganj Site is considered to be the most suitable site for Road-cum-Railway Bridge over the Jamuna River.

The Inception Report mentions that the selection of the most suitable site for bridge crossing must be made based on these criteria; (a) stability of river channel, (b) construction costs including river control works and (c) traffic volume.

As mentioned above, all four candidate sites, which have been proposed as bridge crossing points are certainly located at nodes of braiding, which suggests that any of them is favorable for spanning a bridge across the Jamuna River.

From the geomorphological point of view, the Sirajganj narrow is the most suitable among the four sites, the Gabargaon site comes closely next, the Bahadurabad site is comparatively unfavorable in comparison with the former two, and the Nagarbari site falls behind all the others.

From point of view of river morphology, the Nagarbari site is the worst one while the other three are almost equal judging from the fact that the banklines have shown little change since around 1860; but the Gabargaon site is the best and the Bahadurabad and Sirajganj sites are almost equal in view of the width between the banks.

Therefore, from both geomorphological and river-morphological points of view, there is nothing to choose between the Sirajganj and Gabargaon sites.

At the Sirajganj site, the bridge axis was chosen a little downstream from the Sirajganj narrow. This site lies under the protection of the narrow as well as the Sirajganj bank-protection works and has only one main stream with chars on both sides of the Jamuna River. This means that the site is very favorable for spanning a bridge. However, this site has two branch channels to the Dhaleswari River, one of which must be crossed by a cross-dam. Fortunately, the entrances to the two branch channels lie with the proposed bridge axis between them. Therefore, it is the best to close the upper inlet channel and improve the lower inlet channel to make it the main one to the Dhaleswari River.

The overall costs, including those of the river control work, the bridge building works, and access link construction works were compared on the A, B, C basis.

It was decided to take the Sirajganj site as the most suitable site for the bridge crossing based on the above-mentioned viewpoints.

CHAPTER V

ROAD CRITERIA AND DESIGN ELEMENTS AT THE SIRAJGANJ SITE

1. Lane Width.

The capacity and service volumes of a 2-lane highway are expressed in total vehicles per hour, regardless of the distribution of traffic by direction.

Furthermore, overtaking and passing maneuvers must be done on the traffic lane normally occupied by opposing traffic.

As far as the maintenance of a desired speed on a 2-lane highway requires passing maneuvers, the volume of traffic plus highway geometrics, which establish available passing sight distance, have much more significant effects on operation speeds than in the case of multi-lane roads.

Therefore, whenever service volumes are considered for 2-lane roads, the corresponding range of the available passing sight distance (1,500 ft or greater) must also be considered.

The width of the roadway on 2-lane highways, taking traffic volume, design speed, character of terrain, and economy into consideration may vary from 26 ft (18 feet pavement carriageway plus 4 feet shoulders) to about 44 ft (24 feet pavement carriageway plus 10-foot shoulders).

From the standpoint of driver's convenience, operation and safety, it is desirable to construct 2-lane highways with 12 feet lanes and with usable shoulders of 10 feet width. The "usable" width of the shoulder can be used when a driver makes an emergency stop.

In accordance with the above condition and analysis of the road capacity described hereunder, the access highway study team adopted the geometric standards of primary roads established by R & H Directorate in Bangladesh.


All the proposed road links have 22 feet flexible pavement, 11-foot wide carriageways with 8 feet paved shoulders, on a 40 feet embankment. A typical cross section is shown in Fig. 5-1.

The Government of the People's Republic of Bangladesh will take appropriate action to reserve sufficient land for two additional lanes for future extension on the other side of the borrowpit and the road.


Fig. 5 - 1 TYPICAL CROSS - SECTION

SCALE 1/200

STA. 0.000 ~ 13.754
 STA. 30.540 ~ 37.350



STA. 26.768 ~ 30.540



2. Analysis of the Road Capacity.

2.1. Traffic forecast.

The methods are described in Vol VII, TRAFFIC ECONOMIC BENEFITS, for the calculation of vehicle operating costs required as daily input capacity of a road in terms of equivalent passenger car units (p.c.u.'s). In the Vol VII report, the traffic forecast on the Sirajganj Site Road Links for key years are as follows.

Table 5-1 TRAFFIC FORECAST

| Year | Passenger cars | Buses | Trucks | Total | Equivalent in passenger car units |
|------|----------------|-------|--------|-------|-----------------------------------|
| 1993 | 3,460 | 303 | 169 | 3,932 | 4,876 |
| 2020 | 5,495 | 480 | 552 | 6,527 | 8,591 |

* Passenger car equivalent of trucks and buses = 3

2.2. Road capacity.

The concept and methodology used to develop the highway capacity analysis of the proposed road links are based on the Highway Geometric Design Standard of Japan.

The capacity for proposed road links for uninterrupted flow under ideal conditions are summarized in Table 5-2.

Table 5-2 ROAD CAPACITY

| Road type | Capacity (passenger cars per hour) |
|-------------------|---------------------------------------|
| Two-lane, two-way | 2,500 total, both directions |

2.3. Design volume to capacity ratio.

Table 5-3 shows the methods used to determine volume/capacity ratios on the facility during the peak hours in a given year.

Table 5-3 DESIGN VOLUME - CAPACITY RATIO

| Year | A D T (p.c.u.'s) | Capacity $2,500 \times W_c \times T_s = \text{Capacity}$ | DHV Design Volume (p.c.u.'s) $\text{ADT} \times 12\% \text{ Ratio}$ | Level to Capacity of Service |
|------|---------------------|---|---|------------------------------------|
| 1993 | 4,876 | $2,500 \times 0.96 \times 0.76 = 1,824$ | 585 | 0.32 C |
| 2020 | 8,591 | $2,500 \times 0.96 \times 0.76 = 1,824$ | 1,030 | 0.56 D |

p.c.u.'s = passenger car units

W_c = Adjustment for lane width and lateral clearance

E_T = Passenger car equivalents of trucks

E_B = Passenger car equivalents of buses

T_C = Truck factor at capacity = $\frac{100}{100 - P_T + E_T \cdot P_T}$

T_B = Buses factor at capacity = $\frac{100}{100 - P_B + E_B \cdot P_B}$

P_T = Percentage of trucks

P_B = Percentage of buses

2.4. Level of service.

Two-lane highway geometrics primarily affect operating speeds during the free flow representative level of service A, their effects becoming less significant by the time the maximum volume at this level is reached. Average speeds are most influenced by speed limits at this level also. At the limit of level of service C, still stable flow, operating speeds for uninterrupted flow on all two-lane highways are 40 mph or above, with total volume for both directions reaching 51 percent of capacity with or 930 passenger cars per hour, the condition of passing sight distance, under ideal conditions.

Unstable flow is approached as operating speeds fall to 35 mph and volumes carried, in both directions, may reach 67 percent of capacity with continuous passing sight distance, or 1,222 passenger cars per hour, under ideal conditions. This represents the limiting conditions for the level of service D, or the highest volume that can be maintained for short periods of time without a high probability of breakdown in flow.

3. Stability of Embankment.

Soil investigation was done during the 1975 dry season.

As already stated in the Volume VI, the predominant soil group throughout the route is sand containing silty soil (SM). Therefore the embankment material is proposed to be obtained by excavating soil above the ground water table as far as practicable along the proposed

route. The above soil group classified as offering "fair" to good materials for embankments.

The main values are as follows.

| | Ground soil | 90% Modified AASHO Compaction soil |
|----------------------------|----------------------|---------------------------------------|
| Unit weight | 0.9 T/m ³ | 2.0 T/m ³ |
| Angle of internal friction | 13.0° | 17.5° |
| Cohesion | 1.0 | 1.0 |

Soil stability analyses were made for several typical conditions of side slope and embankment height in consideration of the surcharge on the embankment.

The results of the calculations are as follows.

Results of Slip-Circle Analysis

| Slide Slope | Embankment height | Factor of Safety against Sliding |
|-------------|----------------------|-------------------------------------|
| 1:2 | 3 m | 1.51 |
| *1:2 | 4 | 1.32 |
| 1:2.5 | 4 | 1.39 |
| 1:2.5 | 5 | 1.28 |

The embankment height will not exceed 13 feet (4 m).

Therefore a 1:2 embankment side slope was adopted for the proposed road links.

The 4 meter height embankment Slip-Circle analysis is shown in Fig. 5-2.

4. Volume Change of Soil.

The volume of soil changes according to whether it is excavated and loosened, or compacted in banking.


It will therefore be necessary to calculate the volume change factors in working out the earthwork requirements and distribution plans.

The average volume change factors for the soil of the area were found to be:

$$L = \frac{\text{Disturbed volume}}{\text{Undisturbed volume}} = 1.30$$

$$C = \frac{\text{Compacted volume}}{\text{Undisturbed volume}} = 0.89 - 0.87$$

Fig. 5-2 SLIP CIRCLE ANALYSIS



In calculation of required right-of-way, the volume change factor of fill has been set at $C=0.85$. Earth work quantities, therefore, have been increased by 15% to allow for settling.

5. Free Board.

Freeboard should be provided in consideration of the variation of design high flood level and wind velocity, etc. Three feet freeboard was adopted in the case of the Tangail-Bhuapur-Gopalgonj Road and the Sirajganj-Hatikumrul Road. Therefore, it is judged that about a three feet (1.000 m) freeboard is sufficient also in this case. However, in order to make sure, the run-up height of wind wave was examined as follows.

Wind velocity for examination of the wave was determined at 9 m/s (20 mile/hr) which was taken in the case of the Right Flood Embankment of the Jamuna.

5 km fetch and 3 m (10 feet) depth were adopted in consideration of topographic features and design high flood level.

Wave height and period

Calculated by Bretschneidek theory on shallow waves (119B) under the conditions of: wind speed $u_{10}=9\text{m/s}$, fetch $F=5\text{km}$ and water depth $h=3\text{m}$, the dimensions of the wave are as follows:

| | | | |
|----------------------------|---|-----------------------|--------------------|
| Wave height (H_3) | : | $gH_3/u_{10}^2=0.05$ | $H_3=0.41\text{m}$ |
| Wave period (T_3) | : | $T_3=3.86 \sqrt{H_3}$ | $=2.48\text{sec.}$ |
| Wave length (L) | : | $L=9.60\text{m}$ | |
| Wave celerity (C) | : | $C=3.87\text{m}$ | |
| Wave steepness (H_3/L) | : | $H_3/L=0.042$ | |

Run-up height.


The run-up height of the wave on the slope of the road embankment was estimated by Savil's study (119 GB). In case the slope gradient of the road-embankment is 1:2, the ratio of run-up height R to the wave height H_0 of corresponding water depth is 1.8 for smooth slopes.

$R = 1.8 \times 0.41 = 0.738\text{m} (2.42 \text{ feet})$ for significant waves in the case of smooth slopes.

6. Pavement.

From practical experience in this country, a flexible pavement is considered most suitable to ensure against any possible settling of the embankment.

The pavement thickness has been determined directly, using the lowest CBR value, from the Design Chart 2, page 25, Road Note 31,



APPROXIMATE GUIDE TO SUBGRADE CONDITIONS

Fig. 5 - 3 DESIGN CHART - 2.

(150-1500 COMMERCIAL VEHICLES PER DAY)

Road Research Laboratory, Ministry of Transportation, UK. It is shown in Fig. 5-3.

CBR tests performed in soaked condition the showed a minimum value of 6.

Road Note 31 was produced for tropical and sub-tropical conditions and assumes a pavement life of only about ten years, with provision for adding strengthening layers. A limitation of Road Note 31, at present, is that design curves are for a maximum of 1,500 commercial vehicles per day and some roads in this country will carry more than that.

To use Road Note 29 for these cases would be certainly safe, and it is reasonable to assume that it would result in a pavement with a longer life.

CBR Design Curve is shown in Fig. 5-4.

The Pavement Section is shown in Fig. 5-5.

But from practical experience in this country, it has been observed that a 3 in. layer of brick flat soling under a 9 in. jama khoa consolidation is best. With a $2\frac{1}{2}$ in. bituminous concrete, the total thickness comes to $14\frac{1}{2}$ in. It is recommended to be placed over a plastic subgrade of sand in 6 inches thickness. This is considered adequate in light of the experience of the road engineers of Bangladesh and also conforms with the recommendation of the Road Research Laboratory.

Fig. 5-4 C.B.R. DESIGN CURVES







Fig. 5 - 5 TYPICAL PAVEMENT SECTION FOR ROAD LINKS




BRICK FLAT SOLING



BRICK ON EDGE (HERRING BONE)



BRICK APPROX Wt. 8 LBS



CHAPTER VI

DESIGN OF ROAD LINKS FOR BRIDGE CROSSING AT SIRAJGANJ SITE

1. Beginning Point and Terminal Point.

1.1. Beginning point.

The Road is planned to begin at Siakol, located 4 km west of Sirajganj, on the Sirajganj-Hatikumrul Road which is scheduled to open in 1978.

1.2. Terminal point.

It is planned to end at a point 500 m north to the intersection of the Tangail-Madupur Road and the Tangail-Bhuapur-Gopalganj Road.

1.3. Length of the road links.

| | Definition of Section | Length (m) |
|------------|--|------------|
| Right Bank | Beginning Point to Bridge Approach on the Right Bank | 13,754 |
| Left Bank | Bridge Approach on the Left Bank to Terminal Point | 10,582 |
| | Total | 24,336 |

2. Route Location.

2.1. Right bank.

The road links on the right side of the Jamuna is planned in accordance with the discussion between Bangladesh and the JICA as follows:

- (1) giving priority to the shortest approach to the Sirajganj-Hatikumrul Road which connect with Asian Highway A-2 (Nagarbari-Saidpur Road) at Hatikumrul,
- (2) reconstruction of existing road and
- (3) accesible to the Sirajganj town.

In order to make the traffic by-pass the town of Sirajganj, the study team has designed a straight route at the section between Siakol, which is the beginning point on the Sirajganj-Hatikumrul Road, and a point south of the Raipur Railway Station (STA 0 to STA 2+650).

Railway traffic between Sirajganj town and the Jamuna bridge will be decreased after completion of the Jamuna bridge and the railway links. Intersection with railway at Raipur is planned as an atgrade intersection for the time being because of small railway traffic volume.

Between the point STA 4+850 and STA 5+600, the intersection of the Sirajganj-Halua Kandi Road and the Right Embankment rehabilitated in 1974, the road is designed as a straight route which parallel the Sirajganj Halua Kandi Road and close to the existing railway. And between the point STA 2+650 and STA 4+850, the Study Team designed a curving route with $R=2,000$ m.

Between the point STA 5+600 and STA 9+400, the existing Sirajganj-Halua Kandi Road is to be used, being widened and improved.

Between the point STA 9+400 and the end of the Right Embankment section, the road was designed as a curving route with $R=2,250$ m in order to connect with the bridge axis.

2.2. Left bank.

2.2.1. For the route location of the road link on the left bank, some revisions were made of the Phase I study because of the following reasons:

- (1) In order to block the Dhaleswari River by the causeway, the road and the newly-planned railway are to use the same bridge approach designed as a straight line;
- (2) Although the study team planned to use the existing road in Phase I, it is very unsuitable for use because of its heavy erosion; and
- (3) The road is to reach the destination point over the shortest distance.

2.2.2. Between the point STA 26+768 where the bridge approach on the left bank ends and STA 30+540, the Road was designed as a straight route along the bridge axis on the same embankment.


With an angle of 15° from the Jamuna bridge axis, going north-east to the river-crossing point of Bridge No. 2 the Study Team designed a curving route with $R=4,000$ m between the point STA 30+540 and STA 31+600. In addition, between the point STA 31+600 and STA 32+450 which is a beginning point of the sequent curving route, the road was designed as a straight route.

The study team designed the road with an angle of about 20° going south-east from the river-crossing point of Bridge No. 2 to avoid traffic interference by sunlight and with a straight route up to the Tangail-Bhuapur-Gopalganj Road. Between the point STA 32+450 and STA 34+850, the road was designed, sequently as a curving route with $R=2,000$ m.

Between the point STA 36+500, which identifies the intersection of the Tangail-Bhuapur-Gopalgonj Roads, and STA 37+350, the terminal point of the Tangail-Madupur Road, the Study Team designed a curving route with $R=750$ m.

Route Location is shown in Fig. 6-1.

FIG. 6-1 ROUTE LOCATION MAP



3. Vertical Alignment.

3.1. Design high flood level.

3.1.1. Design high flood level on the right bank.

At present, observations on the inland water level have been made at Ullapara on the right bank. The maximum water level was recorded at 11.46m (G.T.S.) at Ullapara in 1974, while the profile of the Jamuna River is 1/20,000. Therefore, the study team adopted the value which was adjusted to the design point by the 1/20,000 profile for the design high flood level on the right bank. In short, the values have been identified as 11.84m (G.T.S.) in the vicinity of the bridge axis and 12.34 m (G.T.S.) in the vicinity of Sirajganj.

3.1.2. Design high flood level on the left bank.

For the design high flood level on the left bank in close vicinity of the Dhaleswari River, the study team adopted 13.19m (G.T.S.) as the value, which was derived from the maximum water level of the Jamuna River that was observed at Sirajganj in 1974 and was adjusted to the point of the Jamuna bridge axis. In close proximity to the terminal point of the road, the observation on the inland water level was not done in 1974. Therefore, the value of 12.84m (G.T.S.), which was gotten by consultation when the Japanese Survey Team executed the river section survey was adopted.

3.2. Proposed height of the roads.

3.2.1. Right bank.

The Right Embankment in the vicinity of the proposed road link was collapsed over a distance of about 4 km south of Sirajganj by the flood in 1974. Recently, the new Right Embankment, connecting the Right Embankment and the Siriganj-Halua Kandi Road, was constructed for the time being.

However, because of the connection with the Sirajganj-Halua Kandi Road, the new Right Embankment of the section has not ensured enough safety against flooding in comparison with the design height of the Right Embankment before collapse.

On the other hand, the section where almost all of the road link are located will be encircled by the existing railway and the high embankment of the proposed Railway Link.

Since the road link of the Jamuna Bridge is so fundamental, the road is to be used even in time of flood. Therefore, although the railway link has enough openings, from the viewpoint of road engineering the proposed road height of the section will not be based on the high flood level at Ullapara plus 1m, but the existing railway height designed before the completion of the Right Embankment will be adopted as the proposed height of the road link on the right bank.

The heights of the road are proposed to be at the level of high

flood level plus 1.25m in the vicinity of Sirajganj and high flood level plus 1.75m in the vicinity of the bridge axis.

3.2.2. Left bank.

The value of the design high flood level plus 1m is adopted as the proposed height of the Road Link on the left bank.

4. Quantity of the Works.

4.1. Running length.

o Total length of the road links

| | |
|------------|----------|
| Right side | 13,754 m |
| Left side | 10,582 m |
| Total | 24,336 m |

o Major bridges length

| | |
|------------------------|-------|
| Right side No.1 Bridge | 100 m |
| Left side No.2 Bridge | 135 m |
| Total | 235 m |

o Total pavement length of the road links

| | |
|------------|---|
| Right side | $13,754 \text{ m} - 100 \text{ m} = 13,654 \text{ m}$ |
| Left side | $10,582 \text{ m} - 135 \text{ m} = 10,447 \text{ m}$ |
| Total | 24,101 m |

o Total culvert length

| | |
|------------|--|
| Right side | $13,654 \text{ m} \times 0.04 = 546.2 \text{ m}$ |
| Left side | $10,447 \text{ m} \times 0.04 = 417.9 \text{ m}$ |
| Total | 964.1 m. |

4.2. Area & volume.

o Land acquisition

| | |
|------------|--------------------------|
| Right side | 483,847 m ² |
| Left side | 611,118 m ² |
| Total | 1,094,965 m ² |

o Pavement area

6" Sand sub-base

| | |
|--------------|--|
| o Right side | $13,654 \text{ m} \times 13.716 \text{ m} = 187,278 \text{ m}^2$ |
| Left side | $10,447 \text{ m} \times 13.716 \text{ m} = 143,291 \text{ m}^2$ |
| Total | 330,569 m ² |

4-1/2" Brick on edge

Right side $13,654 \text{ m} \times 4.877 \text{ m} = 66,590 \text{ m}^2$

Left side $10,447 \text{ m} \times 4.877 \text{ m} = 50,950 \text{ m}^2$

Total 117,540 m

9" Water bound mac'adam

Right side $13,654 \text{ m} \times 6.706 \text{ m} = 91,564 \text{ m}^2$

Left side $10,447 \text{ m} \times 6.706 \text{ m} = 70,058 \text{ m}^2$

Total 161,622 m²

3" Brick flat, 2-1/2" Bituminous concrete
1/2" Surface

Right side $13,654 \text{ m} \times 11.582 \text{ m} = 158,141 \text{ m}^2$

Left side $10,447 \text{ m} \times 11.582 \text{ m} = 158,141 \text{ m}^2$

279,138 m²

o Shoulder protect area

Right side 124,001 m²

Left side 117,587 m²

Total 241,588 m²

o Volume of culvert

Right side $3,048 \text{ m} \times 11.58 \text{ m} \times 546.2 \text{ m} = 19,279 \text{ m}^3$

Left side $3,048 \text{ m} \times 11.58 \text{ m} \times 417.9 \text{ m} = 14,750 \text{ m}^3$

Total 34,029 m³

o Earth work volume

Right side including 15% extra volume = 255,398 m³

$255,398 - 19,279$ (structure elimination) = 236,119 m³

Left side including 15% extra volume = 380,387 m³

$380,387 - 14,750$ (structure elimination) = 365,637 m³

Total 601,756 m³

CHAPTER VII

EXECUTION OF THE ROAD LINKS

Rainy season begins in June and continues through September in Bangladesh. The earthmoving from borrowpit will be performed by hand-basket labors. But in order to attain the desired percentage of moisture content by compaction, mechanical compacting equipments will be used for earth compaction. The construction of major bridges and culverts will be undertaken at the same time of the embankment. The bituminous concreting and surface course should be laid by modern mechanical methods in dry season only. Schedule of construction works is shown in Fig. 7-1. Quantity of labours, equipments, works and materials required for the road links are shown in Tables 7-1, 7-2, 7-3, 7-4, 7-5, 7-6 and 7-7.

Table 7-1 NUMBER OF LABOUR BY YEAR (TOTAL)

| ITEM | | RIGHT SIDE (man/day) | LEFT SIDE (man/day) | TOTAL (man/day) |
|------------------|-------------------|-------------------------|------------------------|--------------------|
| EMBANKMENT | SKILLED LABOUR | 685 | 1,061 | 1,746 |
| | UN-SKILLED LABOUR | 104,176 | 161,319 | 256,495 |
| PAVEMENT | SKILLED LABOUR | 46,942 | 35,917 | 82,859 |
| | UN-SKILLED LABOUR | 66,843 | 51,144 | 117,987 |
| BOX CULVERT | SKILLED LABOUR | 16,059 | 12,287 | 28,346 |
| | UN-SKILLED LABOUR | 39,928 | 30,549 | 70,477 |
| SHOULDER PROTECT | SKILLED LABOUR | 2,481 | 2,352 | 4,833 |
| | UN-SKILLED LABOUR | 9,921 | 9,407 | 19,328 |
| MAJOR BRIDGES | SKILLED LABOUR | 4,328 | 5,061 | 9,389 |
| | UN-SKILLED LABOUR | 5,328 | 7,782 | 13,110 |
| TOTAL | SKILLED LABOUR | 70,495 | 56,678 | 127,173 |
| | UN-SKILLED LABOUR | 226,196 | 260,201 | 486,397 |

Fig. 7-1 SCHEDULE OF CONSTRUCTION WORKS

| | 1st Year | | | | | | | | | | | | 2nd Year | | | | | | | | | | | | 3rd Year | | | | | | | | | | | |
|---------------------|----------|---|---|---|---|---|---|---|---|---|---|---|----------|---|---|---|---|---|---|---|---|---|---|---|----------|---|---|---|---|---|---|---|---|---|---|---|
| | J | A | S | O | N | D | J | F | M | A | M | J | J | A | S | O | N | D | J | F | M | A | M | J | J | A | S | O | N | D | J | F | M | A | M | J |
| LAND ACQUISITION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PREPARATIONS WORKS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| EMBANKMENT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| STRUCTURE WORKS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Box culverts | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Bridge works | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sub-structure | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| super-structure | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PAVEMENT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| SHOULDER PROTECTION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MISCELLANEOUS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Note: (1) Construction Season
 (2) Flood Season

Table 7-2 NUMBER OF LABOUR BY YEAR (1st Year0

| ITEM | | RIGHT SIDE (man/day) | LEFT SIDE (man/day) | TOTAL (man/day) |
|------------------|----------------------|-------------------------|------------------------|--------------------|
| EMBANKMENT | SKILLED LABOUR | 211 | 326 | 537 |
| | UN-SKILLED LABOUR | 32,054 | 49,637 | 81,691 |
| PAVEMENT | SKILLED LABOUR | 7,824 | 5,986 | 13,810 |
| | UN-SKILLED LABOUR | 11,141 | 8,524 | 19,665 |
| BOX CULVERT | SKILLED LABOUR | 3,381 | 2,587 | 5,968 |
| | UN-SKILLED LABOUR | 8,406 | 6,431 | 14,837 |
| SHOULDER PROTECT | SKILLED LABOUR | 551 | 523 | 1,074 |
| | UN-SKILLED LABOUR | 2,205 | 2,090 | 4,295 |
| MAJOR BRIDGES | SKILLED LABOUR | - | - | - |
| | UN-SKILLED LABOUR | - | - | - |
| TOTAL | SKILLED LBOUR | 11,967 | 9,422 | 21,389 |
| | UN-SKILLED LABOUR | 53,806 | 66,682 | 120,488 |

Table 7-3 NUMBER OF LABOUR BY YEAR (2nd year)

| ITEM | | RIGHT SIDE (man/day) | LEFT SIDE (man/day) | TOTAL (man/day) |
|------------------|----------------------|-------------------------|------------------------|--------------------|
| EMBANKMENT | SKILLED LABOUR | 290 | 449 | 739 |
| | UN-SKILLED LABOUR | 44,074 | 68,250 | 112,324 |
| PAVEMENT | SKILLED LABOUR | 15,647 | 11,972 | 27,619 |
| | UN-SKILLED LABOUR | 22,281 | 17,048 | 39,329 |
| BOX CULVERT | SKILLED LABOUR | 8,452 | 6,467 | 14,919 |
| | UN-SKILLED LABOUR | 21,015 | 16,078 | 37,093 |
| SHOULDER PROTECT | SKILLED LABOUR | 1,103 | 1,045 | 2,148 |
| | UN-SKILLED LABOUR | 4,409 | 4,181 | 8,590 |
| MAJOR BRIDGES | SKILLED LABOUR | 1,229 | 1,438 | 2,667 |
| | UN-SKILLED LABOUR | 2,462 | 2,964 | 5,426 |
| TOTAL | SKILLED LABOUR | 26,721 | 21,371 | 48,092 |
| | UN-SKILLED LABOUR | 94,241 | 108,521 | 202,762 |

Table 7-4 NUMBER OF LABOUR BY YEAR (3rd year)

| ITEM | | RIGHT SIDE (man/day) | LEFT SIDE (man/day) | TOTAL (man/day) |
|------------------|----------------------|-------------------------|------------------------|--------------------|
| EMBANKMENT | SKILLED LABOUR | 184 | 286 | 470 |
| | UN-SKILLED LABOUR | 28,048 | 43,432 | 71,480 |
| PAVEMENT | SKILLED LABOUR | 23,471 | 17,959 | 41,430 |
| | UN-SKILLED LABOUR | 33,421 | 25,572 | 58,993 |
| BOX CULVERT | SKILLED LABOUR | 4,226 | 3,233 | 7,459 |
| | UN-SKILLED LABOUR | 10,507 | 8,040 | 18,547 |
| SHOULDER PROTECT | SKILLED LABOUR | 827 | 784 | 1,611 |
| | UN-SKILLED LABOUR | 3,307 | 3,136 | 6,443 |
| MAJOR BRIDGES | SKILLED LABOUR | 3,099 | 3,623 | 6,722 |
| | UN-SKILLED LABOUR | 2,866 | 4,818 | 7,684 |
| TOTAL | SKILLED LABOUR | 31,807 | 25,885 | 57,692 |
| | UN-SKILLED LABOUR | 78,149 | 84,998 | 163,147 |

Table 7-5 NUMBER OF CONSTRUCTION EQUIPMENT BY YEAR

(Unit: Number)

| ITEM | 1st year | | | 2nd year | | | 3rd year | | | TOTAL |
|-----------------------|------------|-----------|-------|------------|-----------|-------|------------|-----------|-------|-------|
| | Right side | Left side | Total | Right side | Left side | Total | Right side | Left side | Total | |
| Tire roller | 4 | 5 | 9 | 4 | 5 | 9 | 2 | 3 | 5 | 9 |
| 5 ton bull dozer | 2 | 2 | 4 | 2 | 2 | 4 | - | - | - | 4 |
| Motor grade 3.7m type | 2 | 2 | 4 | 4 | 4 | 8 | 4 | 4 | 8 | 8 |
| Water spray | 2 | 2 | 4 | 2 | 2 | 4 | 2 | 2 | 4 | 4 |
| 5 ton dump track | - | - | - | 5 | 5 | 10 | 5 | 5 | 10 | 10 |
| Soil mixing plant | - | - | - | 2 | 2 | 4 | 2 | 2 | 4 | 4 |
| Hot mixing plant | - | - | - | 1 | 1 | 2 | 1 | 1 | 2 | 2 |
| Mac'adam roller | 2 | 2 | 4 | 5 | 5 | 10 | 5 | 5 | 10 | 10 |
| Concrete mixing | 2 | 1 | 3 | 2 | 1 | 3 | 2 | 1 | 3 | 3 |

Table 7-6 QUANTITY OF WORKS BY YEAR

| ITEM | UNIT | 1st year | 2nd year | 3rd year | TOTAL |
|--|---------------------------|----------|----------|----------|---------|
| LAND ACQUISITION | m ² Right Side | 483,847 | | | 483,847 |
| | Left Side | 611,118 | | | 611,118 |
| EMBANKMENT | m ³ Right Side | 72,652 | 99,897 | 63,570 | 236,119 |
| | Left Side | 112,504 | 154,692 | 98,441 | 365,637 |
| PAVEMENT | | | | | |
| 6" Sand Sub-base | m ² Right Side | 31,213 | 62,426 | 93,639 | 187,278 |
| | Left Side | 23,882 | 47,764 | 71,645 | 143,291 |
| 9" Water bound Mac'adam | m ³ Right Side | 15,261 | 30,521 | 45,782 | 91,564 |
| | Left Side | 11,676 | 23,353 | 35,029 | 70,058 |
| 4-1/2" Brick on Edge | m ² Right Side | 11,098 | 22,197 | 33,295 | 66,590 |
| | Left Side | 8,492 | 16,983 | 25,475 | 50,950 |
| 3" Brick Flat 2-1/2" Bituminous Concrete | m ² Right Side | 26,357 | 52,714 | 79,070 | 158,141 |
| | Left Side | 20,166 | 40,332 | 60,499 | 120,997 |
| 1/2" Surface 3" Brick on End | R.m Right Side | 2,276 | 4,551 | 6,827 | 13,654 |
| | Left Side | 1,741 | 3,482 | 5,224 | 10,447 |
| BOX CULVERT | R.m Right Side | 155 | 287.5 | 143.7 | 546.2 |
| | Left Side | 88 | 219.9 | 110 | 417.9 |
| SHOULDER PROTECT | m ² Right Side | 27,556 | 55,112 | 41,333 | 124,001 |
| | Left Side | 26,130 | 52,261 | 39,196 | 117,587 |
| MISCELLANEOUS | m Right Side | | | 13,654 | 13,654 |
| | Left Side | | | 10,447 | 10,447 |

Table 7-7-1 QUANTITY OF CONSTRUCTION MATERIALS

| ITEM | UNIT | 1st year | 2nd year | 3rd year | TOTAL |
|--------------------------|----------------|-----------|------------|------------|------------|
| PAVEMENT | | | | | |
| Sand | m ³ | 14,970 | 29,950 | 44,930 | 89,850 |
| Brick | nos | 5,313,900 | 10,627,700 | 15,941,500 | 31,883,100 |
| Stone chip | m ³ | 2,400 | 4,800 | 7,200 | 14,400 |
| Bitumen | ton | 483 | 967 | 1,450 | 2,900 |
| Coal | ton | 98 | 195 | 293 | 586 |
| BOX CULVERT | | | | | |
| Sand | m ³ | 4,750 | 11,870 | 5,930 | 22,550 |
| Brick | nos | 55,900 | 135,700 | 69,800 | 265,400 |
| Stone chip | m ³ | 205 | 512 | 256 | 973 |
| Cement | ton | 1,320 | 3,299 | 1,649 | 6,268 |
| Reinforce rods | ton | 733 | 1,832 | 916 | 3,481 |
| SHOULDER PROTECT | | | | | |
| Sand | m ³ | 1,450 | 2,900 | 2,180 | 6,530 |
| Brick | nos | 87,200 | 174,300 | 130,700 | 392,200 |
| NO. 1 BRIDGE | | | | | |
| Portlandcement | ton | - | 360 | 90 | 450 |
| Admixture | kg | - | 760 | 420 | 1,180 |
| Fine aggregate | cu.m | - | 430 | 230 | 660 |
| Coarse aggregate | cu.m | - | 720 | 400 | 1,120 |
| Form area | sq.m | - | 780 | 2,860 | 3,640 |
| Excavation for structure | cm.m | - | 1,600 | - | 1,600 |
| Deformed steel ber | ton | - | 75 | 45 | 120 |
| Brick | nos | - | 32,000 | - | 32,000 |
| H.E.S. cement | ton | - | - | 150 | 150 |
| Prestreeing tendon | ton | - | - | 18 | 18 |
| Erection work | ton | - | - | 835 | 835 |

Table 7-7-2 QUANTITY OF CONSTRUCTION MATERIALS

| ITEM | UNIT | 1st year | 2nd year | 3rd year | TOTAL |
|--------------------------|------|----------|----------|----------|--------|
| NO. 2 BRIDGE | | | | | |
| Portland cement | ton | - | 420 | 110 | 530 |
| Admixture | kg | - | 900 | 550 | 1,450 |
| Fine aggregate | cu.m | - | 510 | 310 | 820 |
| Coarse aggregate | cu.m | - | 840 | 530 | 1,370 |
| Form area | sq.m | - | 960 | 4,000 | 4,960 |
| Excavation for structure | cm,m | - | 2,000 | - | 2,000 |
| Deformed steel ber | ton | - | 91 | 63 | 154 |
| Brick | nos | - | 35,900 | - | 35,900 |
| H.E.S. cement | ton | - | - | 210 | 210 |
| Prestressing tendon | ton | - | - | 24 | 24 |
| Erection work | ton | - | - | 1,170 | 1,170 |

CHAPTER VIII

CONSTRUCTION COSTS & MAINTENANCE COSTS

1. Construction Costs.

Construction unit costs for each work are shown in Table 8-1 and estimated total construction cost and construction costs by year are shown in Tables 8-2, 8-3, 8-4 and 8-5.

Table 8-1 UNIT COSTS

| ITEM | UNIT | UNIT COST |
|------------------------------|-----------------------|-----------|
| LAND ACQUISITION | TK/1 acre | 33,000 |
| EMBANKMENT | | |
| Earth Work by Borrowed Earth | TK/100 m ³ | 785.1 |
| Earth Work by Carted Earth | TK/100 m ³ | 1,391.65 |
| PAVEMENT | | |
| 6" Sand Sub-Base | TK/100 m ² | 925.5 |
| 3" Brick Flat | TK/100 m ² | 2,170.1 |
| 9" Water Bound Mac'Adam | TK/100 m ² | 7,128 |
| 2-1/2" Bituminous Concrete | TK/100 m ² | 4,065.9 |
| 1/2" Surface | TK/100 m ² | 964.1 |
| 4-1/2" Brick on Edge | TK/100 m ² | 4,430.1 |
| 3" Brick on End | TK/100 m | 1,362 |
| SHOULDER PROTECT | TK/100 m ² | 122 |
| SURFACE PAINTING | TK/100 m ² | 2,437.4 |
| BOX CULVERT | R, M | 23,459.9 |
| MISCELLANEOUS | R, M | 91,450.5 |

Table 8-2. TOTAL CONSTRUCTION COSTS OF THE ROAD LINKS (NOTE) T,C,C, : Total construction cost
 F,C, : Foreign currency
 L,C, : Local currency
 (103 KT)

| WORKS | RIGHT SIDE | | | LEFT SIDE | | | TOTAL | | |
|-------------------------------|------------|--------|--------|-----------|--------|--------|--------|--------|--------|
| | T,C,C | F,C | L,C | T,C,C | F,C | L,C | T,C,C | F,C | L,C |
| LAND ACQUISITION | 3,945 | - | 3,945 | 4,983 | - | 4,983 | 8,928 | - | 8,928 |
| EMBANKMENT | 1,854 | 11 | 1,843 | 2,871 | 17 | 2,854 | 4,725 | 28 | 4,697 |
| BOX CULVERT | 12,814 | 9,785 | 3,029 | 9,804 | 7,486 | 2,318 | 22,618 | 17,271 | 5,347 |
| BRIDGE WORKS Sub-structure | 2,466 | 948 | 1,518 | 2,917 | 1,052 | 1,865 | 5,383 | 2,000 | 3,383 |
| Super-structure | 2,677 | 1,266 | 1,411 | 3,490 | 1,622 | 1,868 | 6,167 | 2,888 | 3,279 |
| PAVEMENT | 22,783 | 2,791 | 19,992 | 17,432 | 2,136 | 15,296 | 40,215 | 4,927 | 35,288 |
| SHOULDER PROTECT | 295 | - | 295 | 279 | - | 279 | 574 | - | 574 |
| MISCELLANEOUS | 1,249 | - | 1,249 | 955 | - | 955 | 2,204 | - | 2,204 |
| TOTAL | 48,083 | 14,801 | 33,282 | 42,731 | 12,313 | 30,418 | 90,814 | 27,114 | 63,700 |

Table 8-3 CONSTRUCTION COSTS OF THE ROAD LINKS BY YEAR (NOTE) T,C,C, : Total construction cost
 F,C, : Foreign currency
 L,C, : Local currency
 (1st year) (10³ TK)

| W O R K S | RIGHT SIDE | | | LEFT SIDE | | | TOTAL | | |
|-------------------------------|------------|-------|-------|-----------|-------|-------|--------|-------|--------|
| | T,C,C | F,C | L,C | T,C,C | F,C | L,C | T,C,C | F,C | L,C |
| LAND ACQUISITION | 3,945 | - | 3,945 | 4,983 | - | 4,983 | 8,928 | - | 8,928 |
| EMBANKMENT | 571 | 3 | 568 | 883 | 5 | 878 | 1,454 | 8 | 1,446 |
| BOX CULVERT | 2,698 | 2,060 | 638 | 2,064 | 1,576 | 488 | 4,761 | 3,636 | 1,126 |
| BRIDGE WORKS Sub-structure | - | - | - | - | - | - | - | - | - |
| Super-structure | - | - | - | - | - | - | - | - | - |
| PAVEMENT | 3,797 | 465 | 3,332 | 2,905 | 356 | 2,549 | 6,702 | 821 | 5,881 |
| SHOULDER PROTECT | 66 | - | 66 | 62 | - | 62 | 128 | - | 128 |
| MISCELLANEOUS | - | - | - | - | - | - | - | - | - |
| TOTAL | 11,077 | 2,528 | 8,549 | 10,897 | 1,937 | 8,960 | 21,974 | 4,465 | 17,509 |

(NOTE) T,C,C, : Total construction cost
 F,C, : Foreign currency
 L,C, : Local currency

Table 8-4 CONSTRUCTION COSTS OF THE ROAD LINKS BY YEAR
 (2nd Year) (10³ TK)

| W O R K S | RIGHT SIDE | | | LEFT SIDE | | | TOTAL | | |
|-------------------------------|------------|-------|--------|-----------|-------|-------|--------|--------|--------|
| | T,C,C | F,C | L,C | T,C,C | F,C | L,C | T,C,C | F,C | L,C |
| LAND ACQUISITION | - | - | - | - | - | - | - | - | - |
| EMBANKMENT | 784 | 5 | 779 | 1,215 | 7 | 1,208 | 1,999 | 12 | 1,987 |
| BOX CULVERT | 6,744 | 5,150 | 1,594 | 5,160 | 3,940 | 1,220 | 11,904 | 9,090 | 2,814 |
| BRIDGE WORKS Sub-structure | 2,466 | 948 | 1,518 | 2,917 | 1,052 | 1,865 | 5,383 | 2,000 | 3,383 |
| Super-structure | - | - | - | - | - | - | - | - | - |
| PAVEMENT | 7,594 | 930 | 6,664 | 5,811 | 712 | 5,099 | 13,405 | 1,642 | 11,763 |
| SHOULDER PROTECT | 131 | - | 131 | 124 | - | 124 | 255 | - | 255 |
| MISCELLANEOUS | - | - | - | - | - | - | - | - | - |
| TOTAL | 17,719 | 7,033 | 10,686 | 15,227 | 5,711 | 9,516 | 32,946 | 12,744 | 20,202 |

(NOTE) T,C,C, : Total construction cost
 F,C, : Foreign currency
 L,C, : Local currency

Table 8-5 CONSTRUCTION COSTS OF THE ROAD LINKS BY YEAR

(3rd year)

(10³ TK)

| W O R K S | RIGHT SIDE | | | LEFT SIDE | | | TOTAL | | |
|-------------------------------|------------|-------|--------|-----------|-------|--------|--------|-------|--------|
| | T,C,C | F,C | L,C | T,C,C | F,C | L,C | T,C,C | F,C | L,C |
| LAND ACQUISITION | - | - | - | - | - | - | - | - | - |
| EMBANKMENT | 499 | 3 | 496 | 773 | 5 | 768 | 1,272 | 8 | 1,264 |
| BOX CULVERT | 3,372 | 2,575 | 797 | 2,580 | 1,970 | 610 | 5,952 | 4,545 | 1,407 |
| BEIDGE WORKS Sub-structure | - | - | - | - | - | - | - | - | - |
| Super-structure | 2,677 | 1,266 | 1,411 | 3,490 | 1,622 | 1,868 | 6,167 | 2,888 | 3,279 |
| PAVEMENT | 11,392 | 1,396 | 9,996 | 8,716 | 1,068 | 7,648 | 20,108 | 2,464 | 17,644 |
| SHOULDER PROTECT | 98 | - | 98 | 93 | - | 93 | 191 | - | 191 |
| MISCELLANEOUS | 1,249 | - | 1,249 | 955 | - | 955 | 2,204 | - | 2,204 |
| TOTAL | 19,287 | 5,240 | 14,047 | 16,607 | 4,665 | 11,942 | 35,894 | 9,905 | 25,989 |

2. Maintenance Works and Their Costs.

2.1. Maintenance works.

The maintenance works classified as follows:

- a) Surface painting works at intervals of 2 years,
- b) Surface dressing works at intervals of 5 years, and
- c) Repaving works at intervals of 10 years.

The maintenance works for the projected road links were assumed referring to those in the Khulna-Mongla Road Project.

Road Sections for maintenance works are 13,754 m for the right side road 10,582 m for the left side road, totaling 24,336 m.

Number of labours and quantity of materials required for the maintenance works are shown in Tables 8-6 and 8-7.

Table 8-6 NUMBER OF LABOURS

| Unit: Man | | | | |
|------------------|--------|------------|-----------|--------|
| Work items | man/km | Right side | Left side | Total |
| Surface Painting | 497 | 6,836 | 5,259 | 12,095 |
| Surface Dressing | 746 | 10,260 | 7,894 | 18,154 |
| Repaving | 2,119 | 29,144 | 22,423 | 51,567 |

Table 8-7 QUANTITY OF MATERIALS FOR MAINTENANCE WORKS

| Work items | Quantity/km | Unit | Right side | Left side | Total |
|------------------|-------------|----------------|------------|-----------|--------|
| Surface Painting | | | | | |
| Sand | 70.4 | m ³ | 968 | 745 | 1,713 |
| Bitumen | 7.15 | ton | 98 | 76 | 174 |
| Coal | 1.62 | ton | 22 | 17 | 39 |
| Surface dressing | | | | | |
| Sand | 176.0 | m ³ | 2,400 | 1,862 | 4,282 |
| Bitumen | 17.71 | ton | 244 | 187 | 431 |
| Coal | 3.73 | ton | 51 | 39 | 90 |
| Repaving | | | | | |
| Stone chips | 424 | m ³ | 5,831 | 4,487 | 10,318 |
| Sand | 274 | m ³ | 3,397 | 2,613 | 6,010 |
| Bitumen | 59 | ton | 811 | 624 | 1,435 |
| Coal | 11.8 | ton | 162 | 125 | 287 |

2.2. Maintenance costs.

Unit costs of the maintenance works were calculated as shown in Table 8-8 based on the above mentioned maintenance works, number of labours, quantity of materials and the unit prices as of July 1975.

Table 8-8 Unit Cost

| Work items | (TK) | | |
|------------------|-------------|----------------|-----------|
| | Direct cost | General charge | Unit cost |
| Surface Painting | 41,706.8 | 1,043.2 | 42,750 |
| Surface Dressing | 143,737.4 | 3,562.6 | 147,300 |
| Repaving | 439,076.4 | 10,973.6 | 450,050 |

Maintenance costs were thus estimated as shown in Table 8-9.

Table 8-9 Maintenance Costs

| Work items | (10 ³ TK) | | |
|------------------|----------------------|-----------|--------|
| | Right side | Left side | Total |
| Surface Painting | 588 | 452 | 1,040 |
| Surface Dressing | 2,026 | 1,559 | 3,585 |
| Repaving | 6,189 | 4,762 | 10,951 |

Miscellaneous costs for 30 years will be added to above maintenance cost.

APPENDICES

APPENDIX A

BIBLIOGRAPHY

- | | | | |
|----|---|--|-----------|
| 1 | Faridpur--Jhenida Jissor-Khulna Roads Economic and Engineering Feasibility Report, Volume I | Lowis Berger Inc., USA | Aug.1963 |
| 2 | id., Volume II | Lowis Berger Inc., USA | Aug.1963 |
| 3 | Dacca--Aricha Road Economic and Engineering Feasibility Report, Volume I | Amman & Whitney International Ltd., USA | Sept.1963 |
| 4 | id., Volume II | Amman & Whitney International Ltd., USA | Sept.1963 |
| 5 | Khulna--Mongla Road Economic and Engineering Feasibility Study, Volume I | Bangladesh Consultants Ltd. | Dec.1972 |
| 6 | id., Volume II | Bangladesh Consultants Ltd. | Dec.1972 |
| 7 | Brahmaputra (Jamuna) River Crossing Feasibility Study Stage One | Freeman, Fox and Partners | |
| 8 | Surveys of Inland Waterways and Ports 1963-1967, General Report | NEDECO, Holland | July 1967 |
| 9 | id., Investigation of Waterways | NEDECO, Holland | July 1867 |
| 10 | Bangladesh Transport Survey Inventory of Transport Facilities 3 Road | The Economist Intelligence Unit Ltd. in association with Scott Wilson Kirpatrk | Aug.1973 |
| 11 | Report on Investigations for Jessore-Madhukhali Road Construction Project | Government of Japan | Sept.1969 |
| 12 | Brahmaputra Flood Embankment Project Phulchari to Sirajganj | WAPDA. Leedsell-Delew Engineers | Nov.1965 |
| 13 | Annual Report on Flood in Bangladesh for 1970 | WAPDA | |
| 14 | id., for 1971 | WAPDA | |
| 15 | Ground Water Investigation 1970 | WAPDA | |
| 16 | Traffic Survey for 1968-69 and 1972-73 | R & H Directorate | |

- | | | |
|----|---|--------------------------|
| 17 | Tangail--Bhuapur -- Gopalgon) Road, Skim Report | R & H Directorate |
| 18 | Serajganj--Hatikamrul Road. Skim Report | R & H Directorate |
| 19 | Serajganj--Kazipur Road, Skim Report | R & H Directorate |
| 20 | Tangail--Charabari Road Skim Report | R & H Directorate |
| 21 | The First Five Year Plan 1974-78 | Government of Bangladesh |
| 22 | Specification for Road Structure and Earth Work (Road Specification) | R & H Planning Division |
| 23 | Geometric Design Standards of Rural Roads in Bangladesh | |
| 24 | Schedule of rate for road and bridge works. July-1975 | R & H Directorate |
| 25 | UNDP Country and Inter-country Programing 1974 | UNDP |
| 26 | Guide to highway feasibility study 1973 | United Nations |
| 27 | Roadmaking materials and pavement design in tropical and sub- tropical countries | RRL Report LR279 |
| 28 | Guide to highway design standards | ECAFE 1969 |
| 29 | Report on the relationship bet- ween varying traffic densities and the optimum thickness of pavement | ECAFE 1969 |

APPENDIX B

GEOMETRIC DESIGN STANDARDS OF RURAL ROADS IN BANGLADESH

1. Basic Principles.

The terrain of Bangladesh is mostly flat excepting some hilly areas in the east and south eastern part of the country. The plains get inundated by monsoon floods necessitating construction of high roadway embankments. These conditions greatly influence the design standards of roads in this country. Uniform application of design standards is most desirable here. In road planning the aim is to apply the minimum standards on short range basis since high level of standards the country cannot afford at this stage.

2. Classification of Roads.

The road system has been classified into three different categories in consideration of traffic service and importance. These classifications are as under:-

(a) Primary roads:-

Roads connecting the district HQs with the Metropolis come under this category. These roads have 40'ft wide roadway embankment and 22'ft wide hard crest with or without brick paved shoulders.

(b) Secondary roads:-

Roads connecting Sub-divisional HQs with district HQs or primary roads come under this category. The secondary roads have 32'ft wide roadway embankment and 18' ft wide pavement.

(c) Feeder roads:-

Roads connecting business centers, industrial centers, places of importance inaccessible areas etc. with primary and secondary roads come under this category. Feeder roads have 24'ft. wide roadway embankment and 12'ft wide pavement.

3. Design Speeds.

The design speed is 60 MPH for rural areas, 50 MPH for Urban and 40 MPH in special cases where existing structures control.

4. Running Speeds.

The running speeds are 45 MPH, 40 MPH and 34 MPH corresponding to design speeds, of 60 MPH, 50 MPH and 40 MPH respectively.

5. Radius of Curvature.

The radii of curvature are 1,146 ft, 754 ft and 430 ft corresponding to design speeds, of 60 MPH, 50 MPH and 40 MPH respectively.

6. Max^m Degree of Curvature.

The max^m degrees of curvature corresponding to the above noted radii of curvature are 5.0°, 7.6° and 12.4°.

7. Grades.

The grades provided to roads vary from 0% to 3.0% max^m.

8. Passing Sight Distance.

Passing sight distances provided to roads are 2,000 ft., 1700 ft and 1,300 ft corresponding to design speeds of 60 MPH, 50 MPH and 40 MPH respectively.

9. Stopping Sight Distance.

The following stopping sight distances are provided assuming height of eye as 44 inches and height of object as 4 inches.

| | | |
|--------|---------------------|--------|
| 475 ft | for design speed of | 60 MPH |
| 350 " | " " | 50 MPH |
| 40 " | " " | 40 MPH |

10. Cross Slope. -- 3/4" inch both ways with parabolic crown.

11. Extra with on Curves.

Over 11° only.

For 60 MPH - not reqd.
50 MPH - not required
40 MPH - 2'ft for R(520' ft)

12. Superelevation.

1. inch in one foot (e = 0.8) max^m
No, crown for the stated design speeds.

13. Embankment side slopes

2 in 1

14. Embankment Slope Protection.

Turfing in normal cases and encased brick rivetment in high approaches of bridges and culverts.

Soil stabilisation Methods.

The soils in Bangladesh vary from sandy clay to silty clay. These soils usually from a good embankment material and do not usually require stabilisation. However, where a bad soil is

encountered th top layer of sub-grade of 2'ft in thickness is adequately mixed up with sand and duly compacted.

Superintending Engineer (R&H),
Road Planning Circle, Dacca.

HATIKUMRUL

SIR

SIRAJGANJ - HATIKUMRUL ROAD

STA NO.0

ICHAMATI RIVER

BATAN KANDI

ARIA MOHAN

27 RAIPUR

BANBARIA

KALIA HARIPUR

R 2000M
SUNAHATI

STA NO.5

KARAIKOT RIVER

SADANANBPUR

ACCESS ROAR LINK
L=13.754M

BC R=2250M

STA NO.10

HALUA KANDI

HURASAGAL N
BRIDGE


NANDINAMADHU

TENGRAD


PROPOSED RAILWAY

STA NO.15

ASIAN HIGHWAY



APPROACH L=



SIRAJGANJ

JAMUNA RIVER

STA NO. 20

ABZAPUR

CHAR SINGURI 10.5

STA NO. 25

BERIPATAI 11.8

10.1

DURGAPUR 11.4

STA NO. 30

DHALA 10.5

9.2

STA NO. 35

HARIMPUR 10.7

11.0

ELEN

APPROACH L = 1114 m

JAMUNA BRIDGE L = 4800 m

APPROACH L = 5100 m

ACCESS ROAD

PROPOSED RAILWAY

R = 750 STA.

ROL ROAD SIALKOL STA NO. 0

ARIA MOHAN 11.2

12.7 RAIPUR

BANBARIA 11.4

SUNAHATI R 2000M

STA NO. 5 12.8

SADANANDPUJ 11.4

HALUA KANDI BC R 2250M

STA NO. 10

NANDINAMADHU 10.9

TENGRAD 11.3

CHANDRAPARA 11.3

NAKPHATA 11.9

JAMUNABALI 12.1

12.5

GHUNIADARA 12.1

BRIDGE

T.B.G. ROAD

PALI


DHALESWARI RIVER

26.768

30.540 BC R 4000M

L = 10582

R = 750 STA. EC





| | |
|--|------|
| JAPAN INTERNATIONAL COOPERATION AGENCY | |
| PEOPLE'S REPUBLIC OF BANGLADESH | |
| JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT SIRAJGANJ SITE | |
| ACCESS ROAD LINK HORIZONTAL ALIGNMENT | |
| DRAWN | DATE |
| APPROVED | DATE |
| MITSUI CONSULTANTS CO., LTD. | FIG |

SIRAJGANJ HATIKUMRUL ROAD ACCESS ROAD LINK L=13754^m APPROACH L=3114^m JAMUNA

0.00 5700 EXISTING ROAD L=3800^m 9500 13.754 16.868

RAIL CROSSING

RIGHT EMBANKMENT




KILOMETRE


CURVES

R=2000^m

R=2250^m




| |
|------------|
| JAPAN IN |
| PEOPLE |
| JAMUNA R |
| S |
| ACCES |
| DRAWN |
| APROVED |
| MITSUI CON |




| | |
|--|------|
| JAPAN INTERNATIONAL COOPERATION AGENCY | |
| PEOPLE'S REPUBLIC OF BANGLADESH | |
| JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT SIRAJGANJ SITE | |
| ACCES ROAD LINK VERTICAL ALIGNMENT | |
| DRAWN | DATE |
| APPROVED | DATE |
| MITSUI CONSULTANTS CO., LTD | FIG |

APPENDIX D ROAD BRIDGE NO.1



PROFILE SCALE 1:400



CROSS SECTION SCALE 1:200




PLAN SCALE 1:400




PEOPLE'S REPUBLIC OF
 JAMUNA RIVER BRIDGE COMPANY
 VOLUME V ROAD BRIDGE
 JAPAN INTERNATIONAL CO.
 JAPAN BRIDGE & STRUCTURE
 Scale 1:400,200
 Drawn Y. Wakabayashi
 Approved K. Sogabe

APPENDIX D ROAD BRIDGE NO.1



PROFILE SCALE 1:400



PLAN SCALE 1:400




CROSS SECTION SCALE 1:200




| | |
|--|----------|
| PEOPLE'S REPUBLIC OF BANGLADESH | |
| JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT | |
| VOLUME IV ROAD LINKS | |
| ROAD BRIDGE NO.1 | |
| JAPAN INTERNATIONAL COOPERATION AGENCY | |
| JAPAN BRIDGE & STRUCTURE INSTITUTE, INC. | |
| Scale 1:400,200 | Date |
| Drawn <i>[Signature]</i> | DRW. NO. |
| Approved <i>[Signature]</i> | |

APPENDIX D ROAD BRIDGE NO.2

PROFILE SCALE 1:400




P L A N SCALE 1:400




APPENDIX D ROAD BRIDGE NO.2



PROFILE SCALE 1:400



PLAN SCALE 1:400



CROSS SECTION SCALE 1:200



| | |
|--|----------|
| PEOPLE'S REPUBLIC OF BANGLADESH | |
| JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT | |
| VOLUME V ROAD LINKS | |
| ROAD BRIDGE NO.2 | |
| JAPAN INTERNATIONAL COOPERATION AGENCY | |
| JAPAN BRIDGE & STRUCTURE INSTITUTE, INC. | |
| Scale 1:400,200 | Date |
| Drawn <i>J. Nakagawa</i> | DRW. NO. |
| Approved <i>K. Fujikura</i> | |

