#### CHAPTER VI

#### SCOUR AT BRIDGE PIERS

#### 1. Studies on Depth of Scour at Bridge Piers.

P. Andru (124 GB) has obtained the following formula expressing the relation among scoured depth, bed factor  $Q^2/B^2H^3$  and unit discharge on the basis of field measurements and model tests.

$$H_{g}(Q^{2}/B^{2}H^{3})^{1} = 1.8(Q/B)^{2}$$
 (6.1)  
 $H_{g} = 1.8 H$ 

or where

where

Н = scoured depth measured downwards from the water surface Q = discharge B = width of wide rectangular channel H = water depth.

On the other hand, E.M. Laursen has obtained the following formula on the basis of extensive experiments (123 GB).

H <sub>s</sub>	= H + d × k ×	$k_{\alpha} \times k_{\tau}$ (6.2)	÷
d s	scoured depth before scour; given in Fig.	measured downwards from the river the relation between $H/b$ and $d_s/b$ 6-2-1.	bed 1s

Ъ	₽	width of a pier,
k	=	shape coefficient for nose forms to be used only for
a		piers aligned with flow; Fig. 6-2-2 is prepared,
$\mathbf{k}_{\alpha}$	=	multiplying factor to be applied to the depth of
- <sup>-</sup>	÷	scour obtained from the basic curve; a family of
	. ·	curves for $\alpha$ , L/b and k is prepared in Fig. 6-2-3,
	=	angle of attack between <sup>a</sup> the pier and the flow,
$\mathbf{L}^{-}$	=	length of a pier in the direction of the flow,
kr	=	ratio of depth of scour under suspended-load
		conditions to depth of scour under bed-load
	k <sub>s</sub> k <sub>α</sub> L	$k_s = k_\alpha = l_a $

conditions; curves for d \_/H, u \_/w \_ and k \_ are prepared in Fig. 6-2-4;

k = 1 in the case of  $u_{\star}/w_{o} < 1/2$ ,

- = friction velocity, u.,
- settling velocity of sediment particle. ۳o


According to the study made by Breusers (133 GB), the equilibrium depth of scour with continuous sediment motion is given by

> $d_{g} = 1.4 b$ (6.3)

for circular cylindrical piers. On the other hand, Larras (134 GB) found that

> - 134 -

#### Fig. 6-1 Relation Between Scour Depth and Discharge (Andru)




and the state of the second of the

 $\{i_1, \dots, i_n\}$ 



an salah seberahan seberah pertak

مرابعتها وأنتأت بعليه بلاجات



			· · · · · ·	- 1.4 r			Fig.6-2-2
			Fig.6-2-4		Ka	Length-width ratio	Nose form
		2 <vahmi th="" wo<=""><th></th><th></th><th>1.00</th><th></th><th>Rectangular</th></vahmi>			1.00		Rectangular
	vghmi/wo=1 -			1.2	0.90		Semicircular
T	and and the grad				0.80	2:1 🗲	Elliptic
					0.75		
<u> </u>	2				and the second second	ear that is an indicate the	Lenticular
	2 2 2 2 2	ds/H		<b>i.o</b>	0.80 0.70		Lenticular

- 135 -

also for circular cylindrical piers.

Shen, Schneider and Karaki gave a formula

$$d_{a} = 0.000223 R_{a}^{0.619} (d_{a}: m)$$
 (6.5)

 $d_{z} = 1.05 b^{0.75}$  ( $d_{z}, b: m$ )

for the equilibrium scour depth in the clear-water scour region. R means the pier Reynolds number

 $\frac{1}{2} = \frac{1}{2} \frac{$ 

where U is the mean velocity of the undisturbed flow and  $\boldsymbol{\nu}$  the kinematic viscosity.

The above-mentioned formulas from (6.1) to (6.5) are shown in Fig.6-3 in comparison. The values by Andru's, Laursen's and Shen and others' formulas are given with regard to the case of Sirajganj site in the preliminary study (Chapter V).

As seen in this figure, these formulas give a very wide range of values. It can be said, however, that (1) Andru's formula cannot hold with regard to piers of small diameter since scoured depth depends only on water depth according to the formula, (2) Laursen's formula may hold with regard to piers of large diameter because the formula was obtained for the range of H/b = 1 to 7, (3) Breuser's and Larras' formulas seem to be unreasonable in case of large diameter because these formulas are independent of water velocity and bed material and relate to pier width alone, but they seem to hold with regard to piers of small diameter such as pipes, and (4) Shen and others' formula seems to hold over a considerably wide range of pier width.

After all, in our judgement, Andru's formula is applicable for a pier width larger than about 10 m and Shen and others' formula for a pier width smaller than about 3 m in case of the Jamuna River.

2. Scour Depth around Wide Piers.


If we adopt a well type as substructure, the width or the diameter will be of the order of 12 m. If we assume that b = 12 m, k = 0.90 and  $k_{\alpha} = 1.0$ , Laursen's formula becomes

 $H_{s} = H + 0.9 k_{\tau} d_{s}$ 


(6.6)

since  $u_*/w_o > 2$  in case of the Jamuna River.

Values of H /H calculated for H/b = 1 to 7 are shown in Fig.6-4, which indicates that H /H < 1.8 for a range of H/b > 3 and H /H > 1.8 for a range of H/b < 3 according to Laursen's formula, while H /H > 1.8 for a range of H/b 3 according to Laursen's formula, while H /H > is always equal to 1.8 according to Andru's.







In the preliminary design in Chapter V, depths of scour at the piers in each type of the constructions at the four proposed sites were calculated by the two formulas mentioned above. The results are shown in Table 6-1. It is seen from this table that, in the types of A and B, the values calculated by Andru's formula are larger than those by Laursen's but both formulas give almost equal values in the type C. In view of these facts, the values by Andru's were adopted and are shown in Fig.5-6 by double-circle points.

3. Protection Works around Wide Piers.

Bridge piers should be sunk deep enough to stand by themselves without any protection around them. If there are some reasons that this is very difficult or too uneconomical, we will be forced to consider some protection works although undesirable. Thinking of this condition. a study was made of range of protection and size of stones to be placed around piers. This may be called pier apron.

3.1. Range of area for protection.

3.1.1. Gales' proposal.

R.R. Gales proposed a protection range of area to be taken around piers in consideration of oblique attack of flow and scattering of stones in falling, which is shown in Fig. 6-5.

3.1.2. K. Ishizaki and K. Honma's study.

Katsuyoshi Ishizaki and Katsuichi Honma (129 GB) obtained the result shown in Fig.6-6 and 6-7 on the basis of extensive experiments. In these figures, H denotes normal water depth without scour, q and v unit discharge and mean velocity in the normal water depth, X distance from the pier wall, r radius of the pier, d depth of scour at the pier wall or at X = 0, H' the scoured depth measured from the water surface, q' and v' unit discharge and mean velocity at the pier wall, and y a value of q'/q at the pier wall or at X = 0. Fig.6-6 shows the correlation between q'/q and X/r, and Fig.6-7 shows the correlation between d /H and y.

As seen in Fig.6-6, the ratio q'/q is larger than unity in the range X/r 2 or in the distance smaller than D from the pier wall. Therefore, it may be sufficient, if we take the range for protection as 2D from the pier wall in consideration of scattering of stones, where D is diameter of pier.

3.1.3. Present state at Hardinge Bridge.


According to the results of pricking around the piers of Hardinge Bridge, it is reported that stones have been scattered around the piers approximately within the range of about 2D from the pier wall.

3.2. Size of stones.

S.V. Isbash studies the stability of rock-fill dam in running

- 138 -

Site	Type	Depth H (m)	Laur H/b	Laursen's method /b Hs/H H	thod Hs(m)	Andru's Hs/H	s formula Hs(m)	Design water depth at piers
	A	56.139	4.678	1.56	87.577	1.80		102 <sup>m</sup> (334.4)
Nagarbari	æ	42.384	3.532	1.69	71.629	=	76.291	77 (252.5)
	ບ	36.825	3.069	1.77	65.180	<b>.</b>	66.285	67 (219.7)
				 		:		97 (318 D)
	А	53.862	4.489	1.57	84.563	=	70.92	INTENTE IL
Sirajganj	В	40.749	3.396	1.71	69.681	-	73.348	74 (242.6)
	U	33.473	2.789	1.82	60.921	• <b>=</b> • •	60.251	61 (200.0)
					•			
	A	54.891	4.574	1.56	85.630	2	98.804	99 (324.6)
Gabargaon	<b>E</b>	41.041	3.420	1.70	69.770	<b>.</b>	73.874	74 (242.6)
	<b>U</b>	35.554	2.963	1.80	63.997	=	63.997	64 (209.8)
	· :					· · ·		
	A	50.542	4.212	1.60	80.867	<b>=</b>	90.976	91 (298.4)
Bahadurabad	<b>£</b>	37.682	3.140	1.75	65.944	=	67.828	
	ပ	31.229	2.602	1.86	58.086		56.212	57 (186.9)



water and obtained the following formula giving the relation between flow velocity and weight of stones required for stability.

$$v = EK / d$$

$$K = \sqrt{2g(w_s - w_o)/w_o}$$
(6.7)

where v = critical mean velocity (mean velocity on a vertical) (m/s)

d = diameter of a stone (m) w = unit weight of stone (t/cub. m) w<sup>S</sup> = unit weight of water (t/cub. m) g<sup>O</sup> = acceleration of gravity (m/sq. s) E = coefficient depending on shape of the crest of dam (nondimension).

The values of coefficient E are

E = 0.86 for triangular crest E = 1.20 for trapezoidal crest.

In a local scour as shown in Fig.6-6,

= 
$$q/H$$
,  $v' = q'/H'$   
'.  $v' = (H/H')yv$  (6.8)

Substituting the equation (6.8) into the equation (6.7), we get

$$d = (H/H')^{2} (y/EK)^{2} v^{2}.$$
(6.9)

요즘 사람은 물건을 다 가지 않는 것 같아. 가지 않는 것

Therefore, we can estimate the size of a stone which will not be moved by the flow in the scour hole, if we can get the values of scoured depth, unit discharge at the pier wall and the mean velocity at the normal depth. Weight of the stone can be approximately estimated by the following equation.

$$W = 2.65(4/3)\pi(d/2)^{3}$$
 (6.10)

Regarding the mean velocity v, we must take the velocity at the thalweg. Now, let v be the mean velocity at the thalweg and v the mean velocity of the whole water area, we get

$$v = (1/n)H^{2/3}I^{1/2}, v_{M} = (1/n_{M})R^{2/3}I_{M}^{1/2}$$

where n is coefficient of roughness, H water depth and I water-surface slope at the thalweg and  $n_M$  is coefficient of roughness, R mean depth and  $I_M$  water surface slope of the whole cross-sectional area. If we can approximately put

$$n = n_M$$
,  $I =$ 

the mean velocity at the thalweg between both the guide banks can be estimated by the following equation

- 141 -

ing signs

Now, if we take the values,  $g = 9.8 \text{ m/s}^2$ ,  $w = 2.65 \text{ t/m}^3$ .  $w_0 = 1 \text{ t/m}^3$ , and E = 1.20, the equation (6.9) becomes

 $v = (H/R)^{2/3} v_{M}$ 

$$d = 0.0215(H/H')^2 y^2 v^2.$$
 (6.12)

(6.11)

According to the study made by Ishizaki and Honma, the relation between d /H and y is given by Fig.6-7. If we take H'/H = 1.8 or d/H = 0.8, we get y = 2.05 from Fig.6-7. On the other hand, the theoretical solution gives

$$v'/v = 1 + (X/r + 1)^{-2}$$

for the stage of non-scour, or y = 2 at the pier wall. Therefore, we can understand that the value of y varies from 2 to 2.05 depending on the state of scour, from the beginning to the equilibrium, on the assumption that H'/H = 1.8 or  $d_c/H = 0.8$ .

Since the value of y at the equilibrium state of scour scarcely differ from that at the beginning of scour, we can use the value y = 2.05 for the intermediate state of scour. In this case, the equation (6.12) becomes

#### $d = 0.09035(H/H')^2 v^2.$ (6.13)

Tables 6-2-1 to 6-2-2 give the values of diameter d and weight W of the stones which will resist to the flow expected to occur at the bottom of scour hole. For this calculation, the equations (6.13) and (6.10) were used and, as mentioned above, H means water depth at a thalweg, H the water depth from the water surface to the bottom of the scour in the equilibrium state and H' a water depth of the scour in a state on the way to the equilibrium.

It will be considered on the basis of the results of the calculation shown in Table 6-2-1 to 6-2-2 as follows.

(a) Theoretically, it is necessary to place stones larger than those shown below so as not to allow any scour around piers. In practice, stones smaller than these may serve if additional supply for maintenance is considered.

1	and the second		
Type A;	Nagarbari site	d = 135  cm	w = 3,430  kg
	Sirajganj site	d = 171 cm	w = 6,960  kg
	Gabargaon site	d = 166 cm	$w = 6,370 \ kg$
	Bahadurabad site		w =10,480 kg
Type B;	Nagarbari site	d = 115 cm	w = 2,120 kg
	Sirajganj site	d = 146  cm	w = 4,340  kg
	Gabargaon site	d = 144  cm	w = 4,160  kg
an a	Bahadurabad site	d = 171  cm	w = 6,960  kg
Type C:	Nagarbari site	d = 100  cm	w = 1.380  kg
	Sirajganj site		w = 2,520  kg
	Gabargaon site		w = 2,740  kg
	Bahadurabad site	d = 140  cm	

- 142

	B	vm	H	v	н'	i an rua r i g	d and d	<b>W</b>
Гуре	(m)	(m/s)	(m)	(m/s)	(m)	н/н'	(m)	(t)
	الد مير يورد ال. الم		e de la composición d La composición de la c	national de la composition de la compo La composition de la c	Hs H	= 101.050	Hs/H = 1.8	an ang Santang
		ik, Bhattya	ar stadoù "			1	1.352	3.429
·			şir.		56.139 67	0.838	0.950	1.190
	0.000	1.993	56 120	3.871	78	0.720	0.701	0.480
A	2,000	1.993	56.139	2.011	89	0.631	0.538	0.216
ere e		a da serie de la companya de la comp			101.050	0.556	0.418	0.101
			100 A. C. S. S.	i kylt	101.000		· · ·	0.101
		an An an			Hs	= 76.291	Hs/H = 1.8	· · ·
					42.384	1	1.152	2.121
17 e -	n in the second s		· · ·		50	0.848	0.828	0.788
В	4,200	1.580	42.384	3.573	59	0.718	0.594	0.291
					68	0.623	0.447	0.125
		· · · ·			76.291	0.556	0.356	0.063
					Hs	= 66.285	Hs/H = 1.8	
	· · ·				36.825	1	0.997	1.379
	· · · · ·			1997 - 11 T	44	0.837	0.696	0.468
Ċ	5,200	1.468	36.825	3.319	51	0.722	0.518	0.193
۰. <b>۲</b> .	, 200	11100	501045	3.545	58	0.635	0.401	0.090
	т. Т				66.285	0.556	0.307	0.041
<u> </u>					· · · · · · · · · · · · · · · · · · ·		and the second second	and the set
Site	: Siraj	eani	· .					
	<u> </u>	<b>0</b> 0			Hs	= 96.952	Hs/H = 1.8	
							1.712	6.959
					53.862 60	1 0.898	1.381	3.653
ile si ∎	0.000	1 7/6	E7 067	1 256		0.769	1.013	1.442
A	2,000	2.246	53.862	4.330	80	0.673	0.776	0.648
n a an nu. Ta an su					96.952	0.556	0.529	0.205
						and the second	Hs/H = 1.8	
					. · · · ·		1.463	4.343
					40.749	1 0.815	0.971	1.270
at et l'	1 000	1 700	40 740	1. 076	50	0.679	0.674	0.425
В	4,200	1.780	40.749	4.026	60	0.582	0.495	0.168
			n na standar (d. 1947) Na standar (d. 1947)		70 73.348	0.556	0.452	0.128
					1			0.120
• •				ta tal	a ser a s	51 (J. 1997)	Hs/H = 1.8	0 510
	an a	$\mathcal{Q} \in \{1, 2\}$			33.473	1		2.518
	4 <u>6. (</u> 18		and the exp		40	0.837		0.864
<b>C</b> [	5,600	1.625	33.473	3.676	<b>50</b> (1999), 11	0.669		0.226
1990 ( ) 1990 ( )	(		18 A A		60	0.558		0.076
			and the second	1 A.	60,251	0.556	0.377	0.074

Table 6-2-1 Weight of Pitching Stone for Pier Apron

Site:	Gabarg	gaon			n an		مربع معادم ا	an gene Kaba Han Seneration sectore	n in the former of the second s
Туре	B (m)	vm (m/s)	H (m)	v (m/s)	H' (m)		H/H '	d (m)	w (t)
an an taon an t Taon an taon an t			1973 - 1973 - 19 19	·		Hs =	98.804	Hs/H = 1.8	↓ · · · · ·
en da Loria. No finales		a Africa de			54.8	91	1	1.662	6.370
					65	e en la construcción La construcción	0.844	1.184	2.303
A	2,000	2.209	54.891	4.291	76 87		0.722 0.631	0.866 0.662	0.901
					98.8	04	0.556	0.514	0.403
	•	er Exce		i tari i			73.874	Hs/H = 1.8	
					1.2.0		1. St. 19		
		·	1 + 3 + 1 + 1 + 1	- 	41.0 49	4 <b>1</b>	1 0.838	1.442 1.012	4.160
В	4,200	1.767	41.041	3.997			0.720	0.748	0.581
u en letter Nacionalitzaria	en la transformación Referencias	an a	an an Airtean taois		65	1 	0.631	0.574	0.262
					73.8	74	0.556	0.446	0.123
				1		Hs =	63,997	Hs/H = 1.8	
		in the second	2	ne start. S	35.5	54	1	1.254	2.736
	_				42	- SP . C	0.847	0.900	1.011
С	5,200	1.648	35.554	3.728	49 56		0.726	0.661 0.506	0.403 0.180
ar 1975) A Maria I				·	63.9	97	0.556	0.388	
Site:	Bahadu	rabad	·						
· · · ·				e jela se		Hs =	90.976	Hs/H = 1.8	
				n an Ariana An Ariana	50.5	42	1	1.961	10.479
	2,000	2 400	50 540	4.662	60	lan Ari	0.842 0.722	1.391 1.022	3.807
<b>n</b>	2,000	2.400	JU.J42	4.002	80		0.632		1.481
			gian de la		90.9		0.556	0.606	0.309
n in the All and the second s						Hs =	67.828	Hs/H = 1.8	
			an a	1997 - 1997 1997 - 1997 - 1997	36.6	82	1	1.711	6.962
-					45		0.837	1.199	
В	4,200	1.925	37.682	4.354	52 60		0.725 0.628	0.899	1.011
at generalis					67.8		0.556	0.529	0.429
							100 A.	Hs/H = 1.8	
	,	ni in 1 Maria Argana		•	31.2	29	1	1.401	3.824
~	E 600	1 740	A1 000	0.010	37	ی کار کار ایک ا	0.844	0.998	
С	5,600a		31.229	3.940	43 50	9 - <b>41</b>	0.726 0.625		
		ni National anna			56.2	12	0.556	0.433	
1. L.									
	1.1.1.1.1.1.1	1.2				and a second	and the state		

(b) If a pier be sunk deep enough to have a required grip length from the bottom of the equilibrium scour hole, it is of course unnecessary to place stones in the hole, because, in the state of equilibrium, the scoured hole will be supplied with sediment by water flow and hold a definite equilibrium depth. The values given in the tables mean the sizes of stones which will not be moved without the supply of sediment.

(c) If we want to reduce secured depth or hold a depth H' smaller than H,, it will be necessary to place stones of the order of sizes calculated in the tables with regard to scoured depth H'. Also in this case, stones smaller than these will serve if we consider the continuous supply of sediment to the hole and maintenance supplement of stones.

(d) Since the sizes of stones given in the tables are those capable of resisting to the maximum velocity at the pier wall, it may be allowed to use smaller stones on the downstream side of the pier.

i shera di

网络哈哈德 医胸膜的 计正式分词 机运行 医网络网络 3.3. Thickness of stones to be placed.

Alexandra Alexandra (Maria) Alexandra (Maria) Alexandra (Maria) Alexandra (Maria)

In our judgement, it will be necessary to provide the same thickness as in the case of the apron in the meaning of preventing the leakage of sand through voids of the placed stones.

and the second second

an an ann an Arland ann an Arland ann an Arland ann an Arland A Arland Arland

aatas gaa

- 145 -

 $(a,b) = \{ \psi_i : i \in M \}$ 

#### CHAPTER VII

COMPARISON OF THE FOUR PROPOSED SITES

a lan gan dia Castago Sena cana ang sana ang s

and the

1. Geomorphological Comparison.

無道 法认为法律规定法律 医反子

M. Ohya prepared geomorphological land classification maps of the four areas including the proposed bridge sites by photointerpretation and field investigations. These are shown in Figs.7-1 and 7-2.

1.1. Bahadurabad site and its vicinity.

There are alluvial fans along both banks of the river. The alluvial fans in Japan consist of sand and gravel and have steep slopes, but it is merely sand and very flat in the Bahadurabad region. This phenomena are caused by severer chemical-weathering of rock than in Japan because this area belongs to a subtropical region. Also the width of the fan is narrow but the length is short. Two alluvial fans are developed as long narrow stripes along the left bank. Old alluvial plains which consist of natural levees and back-swamps are located in the above-mentioned fans. The old alluvial fans were formed before 1830. The shape of the fan indicates that the formation process is not completed yet.

1.2. Gabargaon site and its vicinity.


Width of the alluvial fan in this area is wider than that in the Bahadurabad region. Old alluvial plains formed before 1830 are seen here and there in the fan. The old alluvial plains consist of natural levees, back-swamps, former river courses, etc. On the right bank, there are a number of large river courses.


1.3. Sirajganj site and its vicinity.

The above-mentioned two places are alluvial fans but the Sirajganj area is a natural levee region. Several distributaries are diverted at Bahadurabad but astricted at the upper part of the Sirajganj area. Namely the distributaries form anabranches. Thereafter the distributaries are diverted again at the lower reaches of the Sirajganj area. There are cliffs about 4 m high between the present alluvial plain and the old alluvial plain on the left bank of the Jamuna River. Distinct regional differences in topography are seen between the present alluvial plain and the old alluvial plain as shown in Fig.7-2. There are many natural levees in the old alluvial plain but few in the present alluvial plain. The town of Sirajganj is located in the old alluvial plain, that is, the town is located in a narrow of the plain (about 10 km or 6.2 mi in width) which was formed by the old alluvial plain. The villages located on the natural levees on the right bank were founded 150 or 200 years ago.

1.4. Aricha, Nagarbari and their Vicinity.

There are distinct differences in regional geomorphology between the left and the right banks in this region. There is a big swamp-area





on the right bank. The area was formed by the back-water of the Ganges during flood time. On the left bank, natural levees are developed. The levees were formed not by the present Jamuna River but the former rivers. There is a distinct former river course whose width is about 3.5 km or 2.2 mi on the left bank.

1.5. Comparison of the four sites.

1.13

The geomorphological features of the four sites are summarized in Table 7-1. Namely the Bahadurabad and Gabargaon sites are located on the alluvial fan, whereas Sirajganj is located in a natural levee region and Nagarbari and Aricha are located in natural-levee or delta regions.

Generally speaking, shifting of river courses in the alluvial fan was frequent. The width of the river in the alluvial fan is wider than that in the natural levee region because it is difficult to confine flood water within banks in the former cases. Furthermore, age of formation of the alluvial fan is new, namely since 1830. Therefore, it is still unstable in the Bahadurabad and Gabargaon regions. But we can find that the stage of the Jamuna River in these regions is advancing little by little. There are small and narrow natural levees being formed along the river courses. This shows that the river courses are being stabilized little by little.

River course in natural-levee region is more stable than that in alluvial fan. The reason is as follows; natural levee has not been formed by flood flow from upper reaches but by overflow from the main channel to its adjacent regions. Natural levees formed in stripes indicate stability of the river course. In Japan, there are more bridges in natural levee region than in alluvial fan. From this viewpoint, we can regard that the Sirajganj site is the most stable place among the four.

Aricha and Nagarbari are located in the natural levee or the delta region. But the region is remarkably influenced by the flow of the Ganges. It was found that changes in river banks in this region are the largest among the four.


At Sirajganj, there is a narrow which has been formed by the old alluvial plain, whose width is about 10 km or 6.2 mi. According to studies of plains in Japan, a narrow is located in an anticline region but a wider area is located in a syncline region. If further research can be conducted in this region, we will be able to confirm the process of formation of this narrow.

2. River-morphological Comparison.

Changes in bank lines of the Jamuna River were studied in 3, Chapter II and they were shown in Fig.2-7 and Fig.2-8. It is seen from these figures that the proposed bridge sites are rightly situated at nodes of width variation along the river course and the variation of the banklines is comparatively stable at these nodes.

Fig. 7-3 shows time variation of river width and time variation of banklines at the proposed bridge sites taking the year of 1830 as

le four proposed	region Right bank omorphological ele ition by Deposit	Alluvial fan Natural levee Natural levee Back-swamp	Alluvial fan Natural levee Natural levee Back-swamp Back-swamp	Natural levee Natural levee Back-swamp (big) Former river course (clear)	Natural levee Natural levee Back-swamp Back-swamp Delta Delta	
Comparison of geomorphology among the four proposed bridge sites	Geomorphology of inland Left bank Geomorphological element Deposition by Deposition by Depos	Alluvial fan Natural levee Natural levee Back-swamp Back-swamp Point bar Former river course (big)	Alluvial fan Natural levee Natural levee Back-swamp Former river course (big)	Natural levee Natural levee Back-swamp Back swamp	Natural levee Natural levee Back-swamp Delta Delta	
Table 7-1	compari- son River morphology	ABAD Braided stream Alluvial fan	JN Braided stream Alluvial fan	U D D D D D D D D D D D D D D D D D D D	I Natural levee Change of the river bank is remarkable	
	Place	BAHADURABAD	CABARCAON	SIRAJGANJ	NAGARBARI	



the reference. It may be found from these figures that the river widths at Sirajganj, Gabargaon and Bahadurabad sites are almost constant except for Nagarbari and variations of displacement of banklines are also almost constant except for the early 30 years, while the variation at Nagarbari is quite large.

3. Comparison in Costs.

At the stage of the preliminary design, costs of the river control works were estimated in 8, Chapter V. In every case of the four sites, the cost of Type-A is the highest and the cost decreases rapidly with increase of guide-bank span. Therefore, so far as cost of the river control works is concerned, Type-C is the most economical one.

4. Selection of the Most Suitable Site for Bridge Crossing.

The Inception Report mentions that selection of the most suitable site for bridge crossing must be made based on the factors; (a) stability of river channel, (b) construction costs including those of river control works and (c) traffic voluem.

As mentioned above, all the four sites which have been proposed as bridge crossing points are certainly located at nodes of braiding, which suggests that any of them is favorable for spanning a bridge across the river.

From the geomorphological point of view, the Sirajganj narrow is most stable among the four, the Gabargaon site comes closely next, the Bahadurabad site compares unfavorably with the former two and the Nagarbari site falls behind any of the others.

From the river-morphological point of view, the Nagarbari site is the worst one while the other three are almost equal judging from the fact that the variation of the displacement of banklines is almost constant since nearly 1860, but the Gabargaon site is best and the Bahadurabad and the Sirajganj sites are almost equal from the aspect of the size of width between the banks.

Therefore, from both the geomorphological and river-morphological points of view, there is nothing to choose between the two sites of Sirajganj and Gabargaon. Taking into consideration the other two factors together, that is, further considering the total construction costs including those of the river control works and the traffic volume estimated at the stage of the preliminary design, it was decided to take the Sirajganj site as the most suitable one for the bridge crossing.

- 152 -

Phase II Second stage of the study

n gene gebennen sollte er sollte sonstatte sollteter andere sollte besten der bestenden bestellte sollte sollt Miller – tennangen verk offen verkenden gebenne her konstantisken er bestellte sollte sollte sollte sollte soll Miller – tennangen gebenne offen verkende gebenne her sollte sollte sollte sollte sollte sollte sollte sollte s

A place des last de désignées en années en la construction de la construction des replacement de la construction de

-1997 – Analas Bayeli ang ali shira da dikaraka mata kata shira kata shira. Ta bata sanda di karata da shira kata kata kata saniyin sa sasara saniyin sa sasara saniya kata ang Ta saniya saniya saniya saniya saniya saniya saniya saniya sa saniya sa saniya saniya saniya saniya saniya sani

- 153 -

#### CHAPTER VIII

#### RIVER CONTROL WORKS AT SIRAJGANJ SITE

#### 1. Determination of Spanning Site.

At a meeting which was held at Dacca from Oct. 28, 1974 to Nov. 6, 1974, Sirajganj site was chosen as the most suitable site and the spanning site or the bridge axis was located during the Study Teams' stay in Dacca from Nov. 29, 1974 to Dec. 14, 1974 based on the aerophotographs newly taken by the Japanese Surveying Team in Nov. 1974.

Topography of the area surrounding the bridge axis is shown in Fig.8-1.

M. Ohya prepared a geomorphological land classification map of the Sirajganj area utilizing the above-mentioned photographs. This is shown in Fig.8-2.

Two alluvial terraces are found on the left bank in the Sirajganj site. As shown in Fig.8-3, relative height of the lower terrace is 1.5 m and that of the higher terrace is 3 m. The lower terrace is utilized as upland-crops field. This area is not inundated by ordi-





Fig.8-3 Schematic Cross Section of the Left Bank of the Sirajganj Area

nary floods but occasionally inundated when high floods occur. The depth of inundation is relatively shallow. Small villages have been settled for 25 or 30 years on this lower terrace.

The higher terrace is surrounded by cliffs as shown in Fig.8-3. The cliff continues from north to south but the relative height is highest on the opposite side of Sirajganj Town. Balkutia Village which is located on this terrace is surrounded by dikes which were con-



the Area Surrounding the


# Fig. 8-2 GEUMORPHOLOGIC MAP OF THE BRAHMAPU (SIRAJGANJ AND ITS SURROU




## C MAP OF THE BRAHMAPUTRA-JAMUNA RIVER BASIN AJGANJ AND ITS SURROUNDING AREA)













### BOUNDARY OF TOPOGRAPHY AND CLIFF



UPPER NATURAL LEVEE



NATURAL LEVEE FORMED BY R. BRAHMAPUTRA JAMUNA DURING THE LAST 140-160 YEARS



В


FR

EXPLANATORY NOTES



FORMER RIVER COURSE

UPPER SANDY DELTA




SANDY DELTA FORMED BY R. BRAHMAPUTRA-JAMUNA DURING THE LAST 140-160 YEARS



D

WATER SURFACE

CONTOUR LINE OF THE GROUND HEIGHT IN METERS OF THE RIVER BED



BASE PHOTO MAP WAS MADE FROM AERIAL PHOTOGRAPHS TAKEN IN DECEMBER 1974. ELEVATIONS AND CONTOUR LINES WERE TRACED AND COMPILED FROM THE BASE MAP WHICH WAS MADE BY THE JICA AND THE GOVERNMENT OF BANGLADESH (ELEVATIONS IN METERS AND CONTOURS MADE ON THE BASIS OF PWD LEVEL DATUM)

SURVEYED, COMPILED AND CARTOGRAPHED BY MASAHIKO OHYA

WATER SURFACE

PUTRA-JAMUNA



CONTOUR LINE OF THE GROUND HEIGHT IN METERS OF THE RIVER BED

SCALE 1:50,000

PRINTED BY KOKUDO CHIZU CO., LTD. TOKYO 1976

structed in 1965. Before construction of the dikes, this area was sometimes inundated during high floods but after the construction of dikes, no inundation has occured. There are not only upland-crop fields, but also many big trees. From the research by hearing and the size of these big trees, it was found that the village was founded 150 or 200 years ago, that is, around the same year or just before the present Brahmaputra-Jamuna River was formed. Sirajganj is also an old town.

As seen in Fig.8-3, there are geomorphological regional differences between the inside of the cliff i.e. protected area and the outside of it i.e. unprotected area. The former has many but small natural levees but the latter was few. M. Ohya presumed that the natural levees were formed not by the present Brahmaputra-Jamuna River but by the rivers such as the Tista which flowed in the area before formation of the present Brahmaputra-Jamuna River.

Based on the photo-interpretation of the ERTS, M. Ohya found a light black-colored belt crossing the Brahmaputra-Jamuna River from NNW to SSE at Sirajganj. The belt is presumed to be an old alluvial plain. This indicates that the old alluvial plain which had been formed not by the present Brahmaputra-Jamuna River but by the former rivers such as the Tista was developed around Sirajganj. At Sirajganj, there is a narrow (about 10 km in width) which consists of old alluvial plain which was formed 150 or 200 hears ago. This means that Sirajganj and its opposite side have been stable for the last 150 or 200 years. Except for Sirajganj and its opposite side we can not find any place of old alluvial plain. This is the main reason why this place is suitable for bridge construction from the viewpoint of geomorphology.

As mentioned previously in Chapter VII, the upper region from Sirajganj is an alluvial fan, whereas the lower region is a natural levee region. The river course in the natural levee region is more stable than that in the alluvial fan. Also from this viewpoint, the Sirajganj site is suitable for bridge crossing.

In view of topographical consideration of the aerophotograph and geomorphological consideration mentioned above, the bridge axis was chosen about 12 km downstream of the town of Sirajganj as shown in Fig.8-1. In accordance with the idea mentioned in Chapter III, guidebank system was adopted together with cross dikes for the purpose of guiding flow and protecting bridge abutments and approaches. The arrangement of the guide banks and the cross dikes are shown in Fig. 8-1. In this case, the left-side approach must cross the Dhaleswari River. But, if the approach will cross the river by a bridge, this opening on the approach may have a posibility of inducing flood flow and causing serious damages to the approach and the bridge as well. In order to protect the approach from this menance, we will have to place another pair of guide banks around this opening. This pair of guide banks will be built nearly on the same scale as the main guide banks and especially, the right bank on the Dhaleswari will have to be connected with the left guide bank of the Jamuna.

This system ought to need another huge cost and, in spite of this treatment, will not be able to escape from the menace of strong flood flow to run through the opening. Therefore, we decided to cross the Dhaleswari by a cross dam and to connect the Dhaleswari with the Jamuna by excavating a new channel making use of a branch located about 6 km downstream of the bridge axis. This is also shown in Fig. 8-1.

Further in future, in making detail designs, hydraulic model tests are recommendable for determing the allignment and the length of the guide banks including the Dhaleswari new channel.

2. Design discharge.

The flood said to the biggest discharge in the record of Jamuna River arose in July 1974. According to B.W.D.B., water level and discharge recorded at Bahadurabad station are as follows.

Date	Aug. 7th, 1974
W.L.	65.55 ft PWD
Discharge	3,210,000 cfs (90,920 m <sup>3</sup> /s)

This discharge, as easily recognized when compared with the discharges in Table 2-3, is extremely big.

This flood is not included in the samples for statistical analysis in 1, Chapter IV, becausd this happed after the study on Phase I. As this discharge is very important, the statistical analysis has been excuted again with the same procedure as in 1, Chapter IV, including this discharge and data in 1971 that were proved to be available afterwards, into the samples in Table 2-3.

Table 8-1 shows the data and Fig.8-4 shows the calculation result by Thomas plot method.

Table 8-2 shows the return period of discharge based on Fig.8-4. The series 1, 2, 3, 4 of these calculation are the same as mentioned in 1, Chapter IV.


Based upon this results, under the same reason as in 1, Chapter IV, the average value of the series 1, 2, 3, 4 has been taken as the return period of discharge at Bahadurabad site.


Design discharge is as shown in Fig.8-5 as the results of discharge allocation with the same idea as explained in 2, 3, Chapter IV.

Based on Fig.8-5, the design discharge for bridge construction at Sirajganj site has been determined as 96,850  $m^3/s$  (3,420,000 cfs).

3. Guide-bank Span and Design High-water Level.

The design discharge was determined as 3,420,000 cfs or 96,850 cub. m/s as already mentioned above. Net minimum width between the pair of guide banks was calculated at 4,200 m for th is discharge by using the third method mentioned in Chapter III. On the other hand, the study in the bridge planning gives a span of 177.5 m as the most economical one and a pier width of 13 m as required therefore. Hence we need 26





<u>_</u>		<u></u>	94 A 3	0	•	la La seguina de la seguina de La seguina de la seguina de	الالتوجة بتنتقيه المتنقري	والمدينية المراجع	ا المرجع بحديد هي مراكبياً ال ا	na na sanai ni ana ma		
ĸ.	د از د مربعه مربعه			a se si a Se se si a Se se se se si	0	00	<del>5 0 0 0 0 0 0</del>	9 <del>000 0</del>		and and	1 - 4	
•• ••	-*:*: -*:			ب فقاطید ۱۹۰۶ ۱۹۰۰ ز					<b>~~~</b>	0	Serie	
										1 6 6 <b>1 4 5</b> 5 6 1 - 6 5 5 6 5 5		

8-4 Return Period of Discharge at Bahadurabad

Fig.

- 161 -

	water level		Discharge	(10 <sup>3</sup> cfs)	
Date	(ft, PWD)	series-1	series-2	series-3	series-4
50. 7.20	62.02		1730	1680	1870
51. 7.19	62.80		2020	1800	2050
52. 7.15	63.55	an an an an an Anna. An an an an Anna Anna	2310	1950	2230
53. 7.31	62,00	. *	1730	1680	1890
54. 7.31	64,50	· · · · · ·	2660	2140	2450
55.8.1	64.95	an <sup>an an</sup> an	2800	2240	2600
56. 6.24	64,18	2130	2130	2130	2130
57. 8.12	64.78	2210	2210	2210	2210
58.8.18	65.65	2520	2520	2520	2520
59. 6.26	64.15	2420	2420	2420	2420
60.9.18	63.90	2190	2190	2190	2190
61. 7.19	62.03	1900	1900	1900	1900
62. 8.23	65.60	. 2460	2460	2460	2460
63. 7.16	63.43	1990	1990	1990	1990
64.8.4	64,40	2230	2230	2230	2230
65. 8.15	64.00	2270	2270	2270	2270
66. 8.31	64.05	2430	2430	2430	2430
67. 7.12	63.43	2460	2460	2460	2460
68. 7.25	64.22	2200	2200	2200	2200
69. 7.23	64.65	1980	1980	1980	1980
70. 7.28	65.20	2700	2700	2700	2700
71. 8.21	63.05	1960	1960	1960	1960
74. 7.28	65.55	3210	3210	3210	3210

Table 8-1 Annual Maximum Discharges at Bahadurabad Station

Table 8-2 Return Period of Discharge at Bahadurabad

1

Return Period		Disc	harge $(10^3)$	cfs)	
(years)	Series-1	Series-2	Series-3	Series-4	Average
10	2797	2809	2719	2739	2766
20	2960	2989	2893	2893	2934
30	3048	3087	2990	2977	3026
40	3109	3154	3055	3-34	3088
50	3154	3205	3105	3077	3135
60	3191	3246	3145	3112	3174
80	3248	3309	3207	3166	3233
100	3291	3358	3254	3207	3278
150	3369	3444	26- <b>3338</b> 7	3279	3358
200	3422	3504	3396	3330	3413

- 162 -





Fig. 8-5 Discharge Allocation of Jamuna River 14月1日日 - A seit south

piers in total. If we assume 25 % of the total widths of the piers to be a loss of width to be added to the total piers width and assume an arrangement of guide bank and abutment as shown below, we obtain 4,680 m or 15,354.3 ft as the guide-bank span.

Using the topographic map and the cross sections of the river which were prepared by the Japanese Surveying Team based on the surveyings which were made during the dry season from November 1974 to February 1975, water level was calculated on the stretch of 23 km from Section No. 26 to Section No.

3 on condition that (a) discharge; Q = 96,850 cub.m/s(3,420,000 cfs), (b) the reference water level at the lower end of the stretch is determined by the same method as used in Chapter V, (c) coefficient of roughness is 0.020, (d) interval between two successive sections is 1 km and (e) distance between cliffs on both banks is an effective width of the river. Since there are shallows within a width, river section wasstreated

r. 191 -



as a double section and nonuniform-flow equation was used for the calculation assuming that the discharge will be confined within two embankments to be built on both banks in the future.

Water surface profile was calculated with regard to the following three cases.

Case 1: There are no guide banks and the Dhaleswari River branches at the present bifurcation; that is, the present natural state.

- Case 2: The river channel in Case 1 is constricted by a pair of guide banks but there are no piers. In this case, the Dhaleswari shall branch at a point 6 km downstream from the bridge axis with a discharge of 7,360 cub.m/s or 260,000 cfs. Lowering of river bed due to the constriction shall be taken into consideration.
- Case 3: Piers are placed in the river channel in Case 2. Loss of head due to piers shall be calculated by the Nagler formula using constants obtained by Yarnel.

The results of the above calculations are shown in Table 8-3.

	Case	1	Case	<b>2</b>	Case	. 3
NO	P.W.D.(m)	P.W.D.(ft)	P.W.D.(m)	P.W.D.(ft)	P.W.D.(m)	P.W.D.(ft)
26	14.550	47.74	14.550	47.74	14.550	47.74
25	14.611	47.94	14.611	47.94	14.611	47.94
24	14.654	48.08	14.654	48.08	14.654	48.08
23	14.685	48.18	14.685	48.18	14.685	48.18
22	14.710	48.26	14.710	48.26	14.710	48.26
21	14.747	48.38	14.753	48.40	14.753	48.40
20	14.847	48.71	14.882	48.83	14.882	48.83
19	14.876	48.81	14.913	48.93	14.913	48.93
18	14.936	49.00	14.983	49.16	14.983	49.16
17	15.032	49.32	15,079	49.47	15.079	49.47
16	15.109	49.57	15.162	49.74	15.162	49.74
15	15.106	49.56	15.196	49.86	15.221	49.94
14	15.090	49.51	15.151	49.71	15.176	49.79
13	15.230	49.97	15.303	50.21	15.327	50.29
12	15.348	50.35	15.445	50.67	15.468	50.75
11	15.420	50.59	15.546	51.00	15.568	51.08
10	15.419	50.59	15.494	50.83	15.517	50.91
9	15.562	51.06	15.659	51.37	15,680	51.44
8	15.705	51.53	15.821	51.91	15.840	51.97
7	15.783	51.78	15.909	52.19	15.928	52,26
6	15.947	51.99	16.094	52.80	16.112	52.86
5	16.049	52.65	16.208	53.18	16.226	53.23
4	16.136	52.94	16.306	53.50	16.323	53,55
3	16.215	53.20	16.382	53.75	16.398	53.80

Table 8-3. Water Level on the Stretch of 23 km of the Sirajganj Bridge Site

This table indicates that (a) in cases 1 and 2, water-level difference at a point closely upstream of the bridge (Section No.15) is 9 cm, that is, the constriction due to the guide banks and the replacement of the inlet channel of the Dhaleswari will cause a rise of water level of 9 cm at a point closely upstream of the bridge and (b) water-level difference between case 2 and case 3 is 2.5 cm or loss of head due to piers is 2.5 cm. It must be noticed that these rises of water level are all those in case flood water is confined within embankments to be built on both river banks.

In consideration of the water level 15.221 m at Section No.15 in Case 3, we decided to take 15.25 m or 50.033 ft PWD as the design high water level at the bridge axis.

4. Guide Banks and Cross Dikes.

4.1. Guide banks.

According to the study mentioned in 2, Chapter V, guide banks were arranged as shown in Fig.8-1. Length of circular arc at the upper end of one guide bank is 1,523 m, length of straight portion is 2,735 m, length of the lower arc is 680 m and total length of one guide bank is

te have de<u>hte</u>ra

4,938 m or 16,200 ft. If we place another guide bank of the same shape and the same length on the opposite side, the length of the pair of guide banks amounts to 9,876 m or 32,400 ft in total. Other dimensions were also determined by the same methods as studied in 4, Chapter V.

(a) Crown height of guide bank.

Crown height of guide bank was set at 18.25 m PWD adding 3 m of freeboard to the design high-water level.

(b) Crown width.

Crown width of guide bank was set at 10 m.

(c) Gradient of slope face.

Gradient of river-side face was set at 1 : 3 and that of land-side face was set at 1 : 2. But the latter shall be 1 : 3 as a whole including berms on the face.

(d) Apron.

Lowering of river bed between the pair of guide banks and water depth at thalweg between the guide banks were calculated by the methods mentioned in 4, Chapter V. The calculation is shown in Table 8-4. From this table, it was found that depth at thalweg below ground level would be 37.1 m at the foot of the left guide bank and 36.1 m at the foot of the right guide bank. Based on these depths, lengths of aprons were determined as follows.


> Left apron: L = 1.5 D = 55.7 m. Right apron: L = 1.5 D = 54.2 m.

Table 8-4 Mean Depth and Thalweg Depth between Both Guide-Banks

Without guide-banks: B B<sub>m</sub> H<sub>m</sub> A (m) (m) (m) (m<sup>2</sup>) 5,560 4,697 9.776 45,915

With guide banks:

- 166 -



It was decided that stone should be used for apron after study of alternative materials or methods. Thickness of the apron was set at 3 m after the idead mentioned in Chapter V.

(e) Weight of pitching stone.


Weight of pitching stone was determined at 60 to 100 kg for revetment on river-side face and 30 to 70 kg for aprons according to the study in Chapter V.

(f) Standard cross section of guide bank.

Standard cross section designed based on the above-mentioned factors is shown in Fig.8-6.

4.2. Cross dikes.

The approaches to the bridge shall be used as cross dikes. They can serve as cross dikes since they should have sufficient strength. But they shall be protected by riprap revetment up to a height of 14.0



- 168 -

m PWD or 45.93 ft PWD so as to resist to flow and wave. The standard section is shown in DRW No. II-1.

astrongen Segned beruter den enwichten Andrableg seen er soch
 **4.3. Study on the material alternative** (to stone. A AMA el objection and a statistical sectors)

1.5100

1.12.14

Concrete block with sufficient strength and specific weight can be used as the material alternative to stone. But it is hard to say that it is economical compared with stone to use concrete block because it needs a great amount of cement and aggregates.

It is very economical to use the soil cement block if it is possible to make the soil cement blocks by using the site sands and use them, because materials for soil cement blocks except cement can be cheaply obtained at site. But the soil cement block has defects that it is rather easy to break down and lacks in durability and the specific weight is small.

If the specific weight is small, a block shall be made bigger to be able to stand with water flow. If a block is made bigger, water flow resistance become bigger, and accordingly a block shall be made bigger that much.

On this point, assuming that the specific weight of stone is 2.65 and that of soil cement block is 1.83, eq. (6.7) in 3.2, Chapter VI shows that soil cement block about 6 times of stone in weight is necessary in place of stone. In other words, a block about 420 kg in weight is necessary for stone 70 kg in weight. Soil cement block can not be considered to be suitable as the material for this kind of river works because pitching block work so big as mentioned above is not economical compared with stone and besides soil cement block is easy to break down and lacks in durability.

Covering works with Stell Jack over the blocks was adopted to make up for these defects of soil cement block for the revetment works at Sirajganj. According to the survey result by the survey team of unit price and others dispatched in July 1975, unit construction cost of block per 100 cfs for this revetment work is about 1200 TK/  $10^2$  cfc. It is not economical compared with the unit price of stone. Furthermore, the works are now under construction and it is still impossible to decide whether it is successful or not as a working method method at the present stage.

As studied above, good material alternative to stone can not be found technically and economically as the material for apron at the present stage.

But if stone is to be used for this work, a great deal of stone will be needed and stone will be needed to be imported because stone has not been produced in the country. But it is necessary to study enough before the time of execution of works, about exploitting stone in the country or a new working method which does not need stone so much, because it will be greatly economical.

-- 🗐 69 🗠

### anti ----5. Quantity of Works.

n an an Arthur ann an Arrainn an Arrainn an Arrainn. An Arrainn an Arrainn Arrainn an Arrainn an Arrainn. Quantity of the guide-bank works was calculated based upon the design shown in DRW No. II-1 and is shown in Table 8-5. Quantity of the cross dike works will be incorporated in that of the bridge approach works in Volume III BRIDGE.

. . .

Works		Left	Right	Total
GUIDE-BANK		an tha tha she an tao an ta Tao an tao an		
Embankment	(1,000 m <sup>3</sup> )	727.6	692.5	1,420.0
Stone pitching	(1,000 m <sup>3</sup> )	1,278	1,273	2.551
Placing of mat	(1,000 m <sup>2</sup> )	112	108	220
Sodding	(1,000 m <sup>2</sup> )	80	80	160
Crown protection	(1,000 m <sup>2</sup> )	35	35	70
CROSS-DIKES (BRIDGE A	PPROACH)			
Embankment	(1,000 m <sup>3</sup> )	2,894	3,367	6,262
Gabion (brick)	(1,000 m <sup>3</sup> )	58.5	50.3	108.8
Placing of mat	(1,000 m <sup>2</sup> )	42	35	77
Sodding	(1,000 m <sup>2</sup> )	124	150.7	274.7
Slope protection (brick)	(1,000 m <sup>2</sup> )	134.7	130.9	265.6

- 170 -

### CHAPTER IX

#### TREATMENT OF THE DHALESWARI RIVER

#### 1. Cross dam across the Dhaleswari River.

As already mentioned in 1, Chapter VIII, it was decided to cross the Dhaleswari River by a cross dam and, as a substitute therefore, to excavata a new channel connecting the Dhaleswari with the Jamuna by making use of a branch located about 6 km downstream of the bridge axis. The alignment of this new channel has already been shown in Fig.8-1.

The Dhaleswari River may easily closed, since the river almost runs out of flow in the dry season. The river shall be closed by a cross dike and road-cum-railway approach shall be banked thereon. Fig.9-1 shows a typical cross section of the cross dam. As seen in this figure, the river shall first be closed by stone dikes at both feet of the cross dike up to a height of 9.00 m PWD (29.52 ft PWD) and then the space between both stone dikes shall be reclaimed by earth up to a height of mean ground level 12.0 m PWD, on which the bridge approach shall be built.

2. New Inlet Channel of the Dhaleswari River.

The 100-year discharge of the Dhaleswari River, that is, 260,000 cfs or 7,360 cub.m/s is not the present discharge but a future discharge to be expected in case the discharge of the Old Brahmaputra is limited to 30,000 cfs and the discharge of the Jamuna is confined within both the levees. At present, without regard to this discharge, it is sufficient for the new inlet channel to secure the same water area as the present one. The water area below the average ground level is  $1,400 \text{ m}^2$  and the mean bank-full width of the river is about 600 m. Considering these factors, standard cross section of the new channel was determined as shown in Fig.9-2. In actual construction, it will be sufficient only to dredge the central portion 300 m in width up to the depth shown in Fig.9-2.


3. Quantity of Works.


Quantity of the dredging works of the Dhaleswari New Channel is as follows.

Dredging works

Length 6 km Quantity of earth 6,400,000 m<sup>3</sup> Area of land for spoil 2,970,000 m<sup>2</sup>

Spoil shall be dumped into stream channels which will become unnecessary by dredging the new channel. Before starting the dredging works, small streams to be crossed by the new channel shall be closed by sheet piles with a view to prevent returning of spoil. The sheet piles which were employed in embankment of the guide banks





shall again be used in these closing works.

The cross dam works will consist of stone dike 350 m in length  $(6,500 \text{ m}^3 \text{ in volume})$  and earth work 141,300 m<sup>3</sup> in volume. These works are incorporated in the bridge approach works in Volume III BRIDGE.

174 -

(1. <del>1</del>. 1. 1. 1.

# CHAPTER X

### EXECUTION OF THE RIVER WORKS AND COSTS SALES OF THE RIVER WORKS AND CUSTS THE RIVER WORKS AND CUSTS

### 1. Natural Conditions at the Work Site.

Such natural conditions at the work site as temperature, wind rainfall and water level were already mentioned in detail in 7.1, Chapter V. These were used for establishing work schedules. 2. Quantity of Works.

Quantity of guide-bank works and Dhaleswari new channel works are shown in Table 10-1, in which quantity of stone pitching work is increased by 10 % and that of earth work is increased by 20 % considering losses of those in the course of the works and shrinkage

Table 10-1 Quantity of River Works

Guide Banks

Works	Unit	Right G.B.	Left G.B.	Total	Remarks
Apron works		the state of the			
Loading, trans- portation and unloading	10 <sup>3</sup> m <sup>3</sup>	1,400	1,406	2,806	Rate of increase 1.1 (including chip)
Stone pitching	10 <sup>3</sup> _3	1,400	1,406	2,806	
Embankment works	10 11	1,400	1,400	2,000	na shekara ta ka shekara ta aya. Mana shekara ta shekara ta shekara
	3 3			n an eilte Airtís	
Embankment	10 <sup>3</sup> m <sup>3</sup>	831	874	1,705	Rate of increase
Dredging	10 <sup>3</sup> m <sup>3</sup>	1,188	1,248	2,436	Rate of increase
Placing of mats	$10^3 m^2$	108	112	220	10/7
Dike protection work			Vérigi tana Papitang		
Sodding	$10^3 \text{ m}^2$	80	80	160	
Crown pavement	$10^3 m^2$	35	35	70	
Miscellaneous works	an an an a' san an a' san an a	r Aller Aller Aller			
Dhaleswari New Chann	e]				
Works	Unit	Quar	ntity		an an the second se Second second
Dredging work			······································		
Sheet pile drivin	g m	3.	,000	an servis	
Dredging	10 <sup>3</sup> n <sup>3</sup>		,600		
Sheet pile drawin	g m	3	,000		
Miscellaneous works					

- 175 n presidente de la construir d La construir de la construir de

allowance of embankments. Construction roads for apron works form a part of the works hence the quantity of the construction roads is included in the apron works. Quantity of cross-dike works is included in the bridge approach works to be mentioned in the bridge planning.

California al ser des

19.20

#### 3. Execution Schedule of the River Works.

(a) Guide banks.

Guide-bank works shall be started with the right bank. The work shall be commenced after stone of about 700,000 m<sup>3</sup> which is about a half of the total quantity required for one guide bank have been stocked in the right-bank stock yard by railway in a year. One guide bank shall be completed in two years; earth work and about a half of stone-pitching work shall be carried out in the first year and the remaining work shall be completed in the second year. The guide-bank works shall be shifted to the left bank after completion of the right bank. The left guide-bank works, in the same way as in the case of the right bank, shall be commenced after about a half of the total quantity of stone required for this bank have been stocked in stock yard and completed in two years. The stone for the left bank shall be transported by boats.

After all, the guide-bank works shall be completed in four years. The execution schedule of the guide-bank works is shown in Fig.10-1.

(b) Dhaleswari new channel.

Opening works of the Dhaleswari new channel shall be commenced in the year following completion of the left guide-bank and completed in three years. In order to avoid being filled up by sediment during the flood season, the new channel shall be opened in the first year over the whole length in a small width and completed by widening in the following two years. Further, in the year of commencement of the cross dam works, the left road link as well as the left bridge approach shall be completed contemplating that these structures will prevent disturbances of streams located over the area in the north of the new channel and assist the new channel to function as a floodway without being filled up by sediment. The execution schedule of the new channel works is shown in Fig.10-1.

(c) Execution schedule of the river works.

Fig.10-2 shows the whole schedule of the river works.

4. Execution of the River Works.

4.1. Temporary railways and temporary roads.

For the purpose of transportation of stone and other materials required for the construction works on the right bank, temporary railways shall be laid between the end of the railway link and the stone stock yard to be built near the central part of the right guidebank. The length of the railway is about 8,400 m, alignment of which is shown in Fig.10-3.

rig. 10-	<b>ا</b> .	Exec	ution	୍ରମ	neaul	e or	Rive	r Col		worl	(S		· · ·
	•	· · · · · · · · · · · · · · · · · · ·		n en		· · · ·			•	· · · · ·			
Works	Jul.	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	Remrk
(Working Days)	001.	0	0	13	28	29	29	26	28	27	25	10	215
lst.yedr (Right G.B.)			<u> </u>					20		61	2.5	- 10	215
Preparatory work			<u> </u>	 									
Apron work			- · ·										· .
Embankment work					<u> </u>	<b></b>				╞╼┥			
Dike protection work													
			· · ·						· ·				
2nd. year (Right G.B.)	<u> </u>	· · ·	· · ·					<u> </u>					
Preparatory work			-	<u> </u>		:							
Apron work		1				1				<u> </u>			
		· ·					1						
3rd.year (Left G.B.)	· · · · · · ·	<u> </u>		1	<u> </u>	· ·	<u>.</u>			· ·			
Preparatory work	· ·		1		<u> </u>	1	1	1			<u> </u>	· ·	;
Apron work			·										a digi di
Embankment work		·		<u> </u>		· · ·							. :
Dike protection work	1					1	ŀ						
		1		· ·	1.000		1		1				
4th. year (Left G.B.)	· ·	:					· .						
Preparatory work	· .			<u> </u>					. 1	- 43			
Apron work			· · · .										
(D. New channel)						1		<u> </u>					
Preparatory work							· .						
Sheet plie driving work		· .	·			·		-			· ·		
Dredging work					<b> -</b>								
5th.year (D.New channel)		. :		· · · ·								· · · ·	· · .
Preparatory work									·. · · ·			4	
Dredging work													
													1.1
6th.year (D.New channel)												·	
Preparatory : work											·		
Dredging work							·						
Sheet pile driving work		1. A. A.		· ·	:		<del> </del>			[			

# Fig. 10-1 Execution Schedule of River Control Works

a i

- 177 -

ω Т ŝ I 4 Fig. 10-2 Execution Schedule of River Works T T ю for left 2 T 1 for right : Rainy season Year Embonkment work Dike protection work Dike protection work Embankment work Dhaleswari new channel Dredging work Transportation Right Guide bank Apron work Apron work of stone Legend Preparatory works Left Guide bank Works

- 178 -

•

For the purpose of communication and transportation, temporary roads shall be built from a nearest road on the right bank to the stone stock yard, from the branch construction base on the left bank to the stone stock yard on the left bank and from the branch base to the work site of the Dhaleswari new channel. Their lengths are as follows.

> Temporary roads on the right bank: 3,100 m Temporary roads on the left bank : 3,150 m Temporary road to the new channel: 7,400 m Total: 14,000 m (roughly)

> > and the second second second second

The alignment of the temporary roads is shown in Fig.10-3.

4.2. Guide banks.

4.2.1. Embankment.

Since the construction area is submerged every flood season, banking work of one guide bank together with stone pitching work on the slope faces and a part of apron on one side shall be completed in one dry season in order to avoid losses of construction materials and works due to flood flow in the course of the construction. For this purpose, we adopted a method of banking by dredging which is capable of moving a large quantity of earth in a shortest time and at a cheapest cost.

Outline of the banking work is shown in Fig.10-4. Dredged sand will be banked in blocks which will be formed by sheet-pile partition walls. Length of a block shall be 500 m. Height of banking shall be 1.5 m at a time. For supporting the sheet-pile walls, earth shall be moved and heaped up at the back of the walls by swamp-type bulldozers. For this dredging, a 4,000-PS-class dredger was adopted taking into consideration height of banking, distance of transportation of sand and quantity of banking works. Flow of the construction works is shown in Fig.10-5 and main construction equipment for the works are as follows.

> 4,000-PS Diesel pump dredger. 200-PS anchor barges 1S-KW vibro-pile drivers (drawer). 20-ton crawler cranes. 125-KVA engine dynamos. 16-ton swamp-type bulldozers.

4.2.2. Stone pitching works.

River banks seldom retreat more than 500 m in a year. In consideration of this fact, the alignment of the guide banks was planned to keep distance of about 500 m from bank edge and stone pitching works of one guide bank were planned to be completed in two years. Accordingly, stone pitching works in the first year shall be done simultaneously with banking works. For these works, about a half of total quantity of stone required for one guide bank shall be spent. The stone pitching works shall be completed in the second year using the remainder of stone. A set of the set of the state of the set o

Fig.10-6 shows horizontal arrangement and cross section of construction roads for guide bank work. They are planned as one-way roads located along apron part of guide bank. The first layer shall be built with 0.5 m-thick stone chip. The road shall be raised by 0.5 m with the progress of apron construction and shall be switched to new ones which shall be built beside the preceding ones. The second and subsequent layers shall be built with stone and filling-up chip. Thus, every new road shall be built 0.5 m higher than the preceding one.

Stone pitching shall be carried out by loading in the stock of a set yards by tractor shovels, carrying by heavy-duty dump trucks and pitching by man power. The number of workers for pitching was counted assuming that the maximum carriage distance by manpower is 40 m, one unit of workers consists of 20 persons and the units are distributed on the pitching area as uniformly as possible. Further, tiredozers of 19-ton-class were added for assisting manpower pitching. Principal machinery required for stone pitching is as follows. un generatione

	والمحاجب والمحاج والمحاج والمعاجب والمعاجب والمحاج والمحاج والمحاج والمحاج والمحاج والمحاج والمحاج والمحاج وال
Loading:	5 m <sup>3</sup> wheel-type tractor shovels.
Carrying:	32-ton heavy-duty dump trucks.
Pitching:	Manpower.
s faul Thurs	19-ton tiredozers.

4.3. Cross dikes.

Execution of cross-dike works is mentioned in Volume III BRIDGE. والمستحك فالمتعارف والمعالي والمتعاول والمتعاد والمتعار والمعاري والمعاري والمعاري والمعاري والمعاري 4.4. Cross dam and Dhaleswari new channel. an da na Sagara

1.1

4.4.1. Cross dam.

Stone dikes of the cross dam shall be built with stone transported. by 32-ton heavy-duty dump trucks in the first year of the bridge approach works. In this case, the dump trucks used in guide-bank works shall again be used and pitching of stone shall be carried out by manpower. After completion of stone dikes, banking shall be carried out by the same method as approach construction works. Plan of the works is included in the bridge approach works in Volume III. Principal machinery required for the stone pitching work is as follows.

· ·	and a second provide a standard standard standard standard the
Loading:	5 m <sup>3</sup> wheel-type tractor shovels.
Carrying:	32-ton heavy-duty dump trucks.
Pitching:	Manpower

4.4.2. Dhaleswari new channel. 

Construction of Dhaleswari new channel shall be carried out by the dredger which was used in the guide-bank works. As seen in Fig.9-2, a center channel 65 m in bottom width shall be opened over the whole work length in the first year and shall be completed in the third year after widening the width in two years. Spoil shall be dumped in adjacent Fig. 10-3

Location of Guide banks, Temporary Railways, Temporary Roads, Construction Base and Stone Stock Yard SCALE 2000<sup>m</sup>

1000

3 000<sup>m</sup>

4000

5 000




Fig. 10-3 Location of Guide banks, Temporary Railways, Temporary Roads, Construction Base and Stone Stock Yard


2000

1000

3 000<sup>m</sup>

4000


5 000<sup>m</sup>



## Fig. 10-4 Schematic View of Banking Work (1) Sheet pile driving Dredged sand Polyethylene mat Sheet pile (2) Banking againist the back of sheet pile walls ¿Earth moving TIAN/AN **सम्बद्ध**ीत् तः तुः ह्वतः सित्रः (3) Dredging, banking and drying-up 11/25/1/25/1 G1 (4) Sheet pile drawing G.L. (5) Polyethylene mat and filling-up chips A Sec. A Park 7775775577557 G.L


- 183 -





- 184 -

Fig. 10-6 Construction Roads



- 185 -

depressions of 2,970,000 m<sup>2</sup>. Swamp-type bulldozers shall be provided as assistant machinery for the dredging works. In dumping spoil, sheet-pile walls shall be used for separating the depressions from Dhaleswari new channel and swamp-thpe bulldozers shall also be used as assistant machinery. Principal machinery required for the works is as follows.

> 4,000-PS Diesel pump dredger with pipes 6,000 m in length. 200-PS anchor barge. 15-KW vibro-pile drivers (drawer). 20-ton crawler cranes. 125-KVA engine dynamos. 16-ton swamp-type bulldozers. 32-ton heavy-duty dump trucks.

4.5. Principal machinery for construction works.

Necessary number of principal machinery was counted by construction work, month and year based upon the execution schedule of the river construction works shown in Fig.10-2 and summarized in Table 10-2.

Table 10-2 Major Equipment for River Construction Works

Equipment	الم	Specificatio	on	Number
	Capacity	Rated H.P.	Weight (t)	•
	<b>9</b>	n an		
Tractor shovel	5 m <sup>3</sup>	325 PS	29.9	5
Damp truck	32 t	427 PS	26.1	17
Tire dozer	19 t	200 PS	18.9	5
Bull dozer (swamp)	16 t	140 PS	16.2	8
Vibro pile driver	15 kw	15 kw	1.1	68
Crawler crane	20 t	98 PS	26.5	68
Sheet pile	1 = 5 m b =	0.333 m(1,235	t) 0.074	5,550 m
Engine dynamo	125 kvA	160 kw	3.1	18
Diesel pump dredger	4,000 PS	4,000 PS	and the second second	1
Anchor barge		200 PS		1
Pipe	1 = 5  m D =	710 mm (1,000	sets)	6,000 m
Floater	1 = 4.5 m D	= 1,300 mm (20	58 sets)	1,210 m
Joint	1 = 1.5  m (26)	6 sets)		400 m
Macadam roller	10 - 12 t	65 kw	10	
Asphalt sprayer	200 1	4 PS	0.2	6
Tamper	60 kg	4 PS	0.08	5
Spare parts			an an ann an thairte. Tha an tha an	<b>1.s.</b>

### 5. Materials.

Necessary quantity of major materials was estimated by construction work, month and year based upon the execution schedule of the river works shown in Fig.10-2 and summarized in Tables 10-3 and 4. These tables contain sheet piles which are to be used for separation walls of the Dhaleswari new channel after employment in the guidebank works.

Materials	Unit	Right G.B.	Lefr G.B.	Total
Apron works				
Stone	10 <sup>3</sup> m <sup>3</sup>	1,400	1,406	2,806
Light oil	kl	1,345	1,368	2,713
Miscellaneous		1.s.	<b>1.s.</b>	<b>1.s.</b>
Embankment works	· · · · · · · · · · · · · · · · · · ·	nangigi seri kula te Guna seri seri kula te		الملك في الأ
Log	3	1,073	1,100	2,173
Polyethylene mat	$10^{3} m^{2}$	119	123	242
Light oil	k1	734	734	1,468
Heavy oil	kl.	1,680	1,764	3,444
Miscellaneous		<b>1.s.</b>	1.s.	1.s.
Dike protection works				
Sodding	$10^3 m^2$	88	88	176
Ballast (chip)	10 <sup>3</sup> m <sup>3</sup>	30	30	60
Asphalt emulsion	kl	305	305	610
Light oil	kl	81	81	162
Miscellaneous		1.s.		1.s.
	an an an Anna an Anna An Anna Anna Anna			
Dhaleswari new Channel	en de la composition de la composition La composition de la c	an an tha an an tha an t an an tha an tha an tha an t	en et la la companya. A serie de la companya de la	
Materials	Unit	Quantit	y	
Sheet pile driving work				
Light oil	k1	44		
Miscellaneous		1.s.	ing an the second s	, Alta an A
Dredging				
Light oil		. 298	an a	n in Strag (1941)
Heavy oil	kl	9,341		n an Alaga L
Log	3	396		
Miscellaneous	a hardan sa	1.5.		4 1 4 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Sheet pile drawing work	n Anna Anna Anna			· · · · · · · · · · · · · · · · · · ·
Light oil	kl	34		
Miscellaneous		1.s.		

Table 10-3 Materials Required for River Construction Works (1) Guide banks Materials Unit Right G.B. Left G.B. Total

Materials	Unit	Right G.B.	Left G.B.	Dhaleswari	Total .
Stone	<u>103 m</u> 3	1,400	1,406	يدهد بالمع بديني ه	2,806
Sand	10 <sup>3</sup> m <sup>3</sup>	831	874 ····	الألية في الأركانية. مناطقة محمدهم بيارية والقط	1,705
Polyethylene mat	$10^3 m^2$	119	123		242
Log	m <sup>3</sup>	1,073	1,100	396	2,569
Light oil	k1	2,160	2,183	376	4,719
Heavy oil	k1	1,680	1,764	9,341	12,785
Sođ	$10^{3} m^{2}$	88	88	e kriste og k	176
Ballast (chip)	$10^3 m^{3}$	<sup>335</sup> , 1 30, <sup>14</sup>	30		60
Asphalt emulsion	<b>k1</b>	305	305	ు సంగార్ సినియార్ సినియార్ సినిమాలు	610
Miscellaneous		1.s.	1.s.	1.s.	<b>1.s.</b>

Table 10-4 Materials Required for River Construction Works (2)

### 6. Labor

Number of skilled labour and unskilled labour was counted by construction work, month and year based upon the execution schedule of the river work shown in Fig.10-2, and daily maximum number of labor is listed in Table 10-5 by skilled, unskilled and year, in which miscellaneous labor is not included.

a server a fill for the server as the

1.1.8 341.533

due requirements and a report?

1.1.2

Table 10-5 Daily maximum Number of Labor at Work Sites

алар Аларанан Аларанан Ал <u>ар</u> ан	lst year	2nd year	3rd year	4th year	5th year	6th year
						.120
Unskilled	2,215	2,205	2,210	2,210	0	2012 <b>0</b> - 10 - 10 - 10 - 10

7. Major Facilities Required for Managing the River Works and the set of the

A construction office shall be built in the main construction base on the right bank, sub-offices shall be put at work sites and control offices shall be put in the stone stock yards. Sub-offices are for controling the guide-bank works and the Dhaleswari new channel works.

Construction office in the main construction base.

Plottage  $2,000 \text{ m}^2$ Floorage  $300 \text{ m}^2$ 

Three sub-offices for right guide-bank, left guide-bank and Dhaleswari new channel.

Plottage	6,000	m <sup>2</sup>
Floorage	900	m <sup>2</sup>

- 188 -

Two control offices in the stone stock yards.

### Plottage Floorage

Communication system, cars and other facilities are required for the above offices.

 $1,600 \text{ m}^2$ 

 $400 \text{ m}^2$ 

As shown in Fig.10-3, stone stock yards shall be put near the central part of the guide-banks. Each stock yard shall be provided with a plottage required for storing 700,000 m<sup>3</sup> in a year. On the right bank, stone shall be carried in by railway; and on the left bank, by boat. Polyethylene mat shall also be stored in the stone stock yards. Other miscellaneous materials and machinery shall be stored in warehouses to be built in the stone stock yards. Area required for the stock yards and floorage of the warehouses are as follows.

Area of the stock yards  $510,000 \text{ m}^2$  each. Floorage of the warehouses  $800 \text{ m}^2$ 

Motor-pools required for construction of guide-banks shall be put on the both banks of the river. The motor-pool for the left guide-bank works shall also be used for the opening works of the Dhaleswari new channel.

Detailed plan for the above-mentioned facilities will be incorporated in Volume VIII OVERALL CONSTRUCTION PLAN AND ECONOMIC ANALYSIS.

8. Costs.

8.1. Unit Prices.

In estimating the costs of the river works, unit prices of materials, equipment and labor to be procured locally and to be imported from abroad were set based on the results of surveying of the Price Survey Team (143CS) which was organized by the JICA in July 1975. Accordingly the costs estimated in this report are those as of July 1975.

Besides the materials mentioned above, purchase plan of pitching stone was made as shown in Table 10-6 based on the results of surveying of the Stone Material Survey Team (Feasibility Report Volume VI GEOLOGY AND STONE MATERIAL). For estimating the cost of stone pitching works was used the weighted-mean unit price of stone to be collected from Manikarchar, Dhubri, Jagioghopa, Dhulian and Pakur of India.

We assumed that import and excise taxes will not be imposed upon the materials and equipment to be imported for this project. The unit prices which were used in this report are summarized in Table 10-7, in which the unit prices of oils, lubricants and asphalt emulsion are given in CIF prices and inland transportation costs which were estimated on the basis of breakdown of the local prices but polyethylen mat price is given in CIF price added FOB price to transportation cost and inland transportation cost.

			406	n Le anti	064		103	1			
	Total	r C	д, /0/, чэо 341,406		89,399,790		160,593,				
		by train	180,000	234	000	391			an a	teriano 1995 - Angelander 1995 - Angelander	
		by t	180,000	alian Silan Silan	42,120,000		70,380,000	n na seu a 1995 - Alfan 1997 - Anfred 1997 - Anfred	n on a sea Seat a teorita Site de set in Site da Isa		
	.a Bihar Dhulian	by boat	75,600	312	, 200	645	000	elandi kabu Sila kabutat Mata kabupa		andar Alamatika Alamatika	
Stone	India Dhu	by	2/c 2/		23,587,200		48,762,000				
Purchase Plan of Pitching Stone	f stone in Jagioghopa	by boat	24,948	165	4,116,420	404	8,992	e an tair sao a stair agus s	an a	an ta Status to succession a	
an of P	O	by t			4,11		10,078,992			ran Mijaz Minaka Santa Minaka Minaka Santa	
hase P1	Sources Assam Dhubri	by boat	28,350	243	6,889,050	453	12,842,560				· · · · · · · · · · · · · · · · · · ·
				· · ·	6,8		12,8/	cft	<sup>2</sup> cft	- - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910 - 1910	
Table 10-6	Manikarchar	by boat	32,508	390	2,687,120	570	8,529,560	262 Tk/10 <sup>2</sup> cft	470 Tk/10 <sup>2</sup> cft	la gana Angana Angana	
Tai	Mar				12,6		18,5	11	IJ		
	Unit		10 <sup>2</sup> cft/yr	Tk/10 <sup>2</sup> cft	Tk/yr	10<sup 2cft		89,399,790 34,140,600	160,593,102 34,140,600		
	1997 - 1997 -			H				ty dan ya Astri A		na na sina si Pilang sa sina si Pilang Sa sina sina	
		ctation	1 per	ອງ	cost	ð	L S O O O O	Mean unit price; F O B :	tsite	lad og Storf og som Storf skrigt	
		Transportation Outration	required	Unit price F O B	Annual c F 0 B	Unit Price at site	Annual cost at site	ean mi	××ste <b>n</b> an Constant Anti-control a Constant a		
			, m <u>1</u> 0	μ		μ	4			na ježe s	
					- 190						
, sector (Constraints)	<u>ente te difi</u> e	1997 - 1997 -			i de la contra de la La contra de la contra		an a	an di Keliki		는 이 관련 당신 	

### Table 10-7 Unit Price of the second state of t

1. Wages. <u>en j</u>ederati 14. urten de 1444

Labor	\$/day	Tk/day
Skilled labor		าสุรกุณที่มีวิทธุรษายสารสุทธิ์ มีสุทธิ์ มีสุทธิ์ 1969 - พระกุณที่มีการสารสุทธิ์ (ค.ศ. 1976)
Operator 1 (Crawler crane)		<b>45</b>
Operator 2 Assistant operator (Crawler crane)		<b>28</b>
Driver High class crew	60.8 110	<b>28</b>
Crew Special skilled labor Skilled labor		23. 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 100 - 23.
Foreman Unskilled labor		45 17

### 2. Materials

		For the first of <b>FOB</b> and the first of the	Transpor- tation Tk	Tk
Stone and chip 100	) cft	*20.15 (Tk 262)	208	470,
Light oil	IG	*0.2815(Tk 3.66)	0.80	4.46
Lublicants	IG	*3.255 (Tk 42.31)	1.93	44.24
Heavy oil	IG	*0.2892(Tk 3.76)	0.88	4.64
Polyethylene mat	2 	2.967		
Asphalt emulsion	k1	*115.4 (Tk 1500)	194	1694
Log	cft			90
Sod 100	ft			8
Note: IG = Imperial ga	llon			

 $\star = C I F$ 

3. Land acquisition 1 acre

Tk 12,000

renerative experience a

8.2. Costs of river control works including Dhaleswari new channel works.

Costs of the river control works including the opening works of Dhaleswari new channel were calculated on the basis of the unit prices mentioned above. These are shown in Table 10-8. The costs required for cross-dike works and cross dam crossing the Dhaleswari River are incorporated in the costs of bridge construction as a part of the bridge approaches.

It was decided to import all the equipment required for the river control works. For estimation of the construction costs were used the CIF price which was added the transportation cost to FOB price to be planned in a lump of the equipment. Also cost of inland transportation were estimated as to be carried out by water channel from the Chalna port to the site.

Table 10-9 shows breakdown of the labor costs given in Table 10-8. Table 10-10 shows breakdown of the purchase costs of the equipment and Table 10-11 breakdown of the costs of materials.

The annual costs of construction are shown in Table 10-12-1 and Table 10-12-2, which were estimated on basis of the work schedule of the Table 10-2.

8.3. Maintenance costs.

1.1.1

الم المركز ا المركز المركز

Maintenance costs for the river facilities will contain those required for inspection, surveying, repair of the guide banks, maintenance of the Dhaleswari new channel and management including maintenance of offices. Therefore, the maintenance costs, together with those required for the bridge, will be dealt with in Volume VIII OVERALL CONSTRUCTION PLAN AND ECONOMIC ANALYSIS.

法武法 建合物性 计正常分子

8 4 5 C

14 W 14

salida and september in

territe 1., andered real pass territe it

生化于自己的 自己成本 网络外孢体的 医外外管核

网络雷拉威斯 的复数形式

and the second second

Sec. 8

t.a.e

一日 人名瓦莱马拉氏病 经销售的现金分子

The Ball A Service Charles are the

Table 10-8 Construction Costs of Guide-banks and New Channel المراجع من عن المراجع المراجع المراجع مع معنون من مع معامل المراجع مع من المراجع المراجع المراجع المراجع المراجع

symmetric scellaneou soron bankment ke protect scellaneou btotal guide-bank oron bankment ke protect scellaneou btotal scellaneou btotal	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> (10 <sup>3</sup> cft) is (10 <sup>3</sup> cft) is (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup>	Quantity 1,400 (49,435) 831 (29,343) Sodding 80(861) Pavement 35(377) 874 (30,862) Sodding 80(861) Pavement 35(377)	Local 10 <sup>3</sup> Tk 118,450 4,756 3,985 6,357 133,548 119,140 4,867 3,985 6,397 134,389	Foreign 10 <sup>3</sup> \$ 11,933 14,345 254 1,315 27,847 11,947 14,366 255 1,319 27,887	Total 10 <sup>3</sup> Tk 273,579 191,241 7,287 23,452 495,559 274,451 191,625 7,300 23,544 496,920
guide-bar oron abankment ke protect scellaneou abtotal guide-bank oron abankment ke protect scellaneou abtotal, eswari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft)	1,400 (49,435) 831 (29,343) Sodding 80(861) Pavement 35(377) 1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	118,450 4,756 3,985 6,357 133,548 119,140 4,867 3,985 6,397 134,389	11,933 14,345 254 1,315 27,847 11,947 14,366 255 1,319	273,579 191,241 7,287 23,452 495,559 274,451 191,625 7,300 23,544
oron abankment ke protect scellaneou abtotal guide-bank oron abankment ke protect scellaneou abtotal, eswari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> (10 <sup>3</sup> cft) is (10 <sup>3</sup> cft) is (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup>	1,400 (49,435) 831 (29,343) Sodding 80(861) Pavement 35(377) 1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	4,756 3,985 6,357 133,548 119,140 4,867 3,985 6,397 134,389	11,933 14,345 254 1,315 27,847 11,947 14,366 255 1,319	191,241 7,287 23,452 495,559 274,451 191,625 7,300 23,544
abankment ke protect scellaneou abtotal guide-bank oron abankment ke protect scellaneou abtotal swari new	(10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion (10 <sup>3</sup> cft) is 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> is	1,400 (49,435) 831 (29,343) Sodding 80(861) Pavement 35(377) 1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	4,756 3,985 6,357 133,548 119,140 4,867 3,985 6,397 134,389	14,345 254 1,315 27,847 11,947 14,366 255 1,319	191,241 7,287 23,452 495,559 274,451 191,625 7,300 23,544
abankment ke protect scellaneou abtotal guide-bank oron abankment ke protect scellaneou abtotal swari new	(10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion (10 <sup>3</sup> cft) is 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> is	(49,435) 831 (29,343) Sodding 80(861) Pavement 35(377) 4 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	4,756 3,985 6,357 133,548 119,140 4,867 3,985 6,397 134,389	14,345 254 1,315 27,847 11,947 14,366 255 1,319	191,241 7,287 23,452 495,559 274,451 191,625 7,300 23,544
ke protect scellaneou btotal guide-bank oron bankment ke protect scellaneou btotal	(10 <sup>3</sup> cft) :10n (10 <sup>3</sup> m <sup>2</sup> ) (10 <sup>3</sup> cft) is (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) :10n 10 <sup>3</sup> m <sup>2</sup>	(29,343) Sodding 80(861) Pavement 35(377) 1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	3,985 6,357 133,548 119,140 4,867 3,985 6,397 134,389	254 1,315 27,847 11,947 14,366 255 1,319	7,287 23,452 495,559 274,451 191,625 7,300 23,544
scellaneou btotal guide-bank oron bbankment ke protect scellaneou btotal, eswari new	:10n 10 <sup>3</sup> m <sup>2</sup> (10 <sup>3</sup> cft) 18 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup>	Sodding 80(861) Pavement 35(377) 1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	6,357 133,548 119,140 4,867 3,985 6,397 134,389	1,315 27,847 11,947 14,366 255 1,319	23,452 495,559 274,451 191,625 7,300 23,544
scellaneou btotal guide-bank oron bbankment ke protect scellaneou btotal, eswari new	(10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup> 10 <sup>3</sup> m <sup>2</sup>	Pavement 35(377) 1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	6,357 133,548 119,140 4,867 3,985 6,397 134,389	1,315 27,847 11,947 14,366 255 1,319	23,452 495,559 274,451 191,625 7,300 23,544
abtotal guide-bank oron abankment ke protect scellaneou abtotal, eswari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>2</sup>	1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	133,548 119,140 4,867 3,985 6,397 134,389	27,847 11,947 14,366 255 1,319	495,559 274,451 191,625 7,300 23,544
btotal guide-bank oron abankment ke protect scellaneou btotal, eswari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion 10 <sup>3</sup> m <sup>2</sup>	1,406 (49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	119,140 4,867 3,985 6,397 134,389	11,947 14,366 255 1,319	274,451 191,625 7,300 23,544
guide-bank pron bankment ke protect scellaneou btotal, eswari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion 10 <sup>3</sup> m <sup>2</sup>	(49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	119,140 4,867 3,985 6,397 134,389	11,947 14,366 255 1,319	274,451 191,625 7,300 23,544
oron bbankment .ke protect .scellaneou .btotal, eswari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion 10 <sup>3</sup> m <sup>2</sup>	(49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	4,867 3,985 6,397 134,389	14,366 255 1,319	191,625 7,300 23,544
abankment ke protect scellaneou ibtotal swari new	(10 <sup>3</sup> cft) 10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion 10 <sup>3</sup> m <sup>2</sup>	(49,647) 874 (30,862) Sodding 80(861) Pavement 35(377)	4,867 3,985 6,397 134,389	14,366 255 1,319	191,625 7,300 23,544
ke protect scellaneou btotal, swari new	10 <sup>3</sup> m <sup>3</sup> (10 <sup>3</sup> cft) ion 10 <sup>3</sup> m <sup>2</sup>	874 (30,862) Sodding 80(861) Pavement 35(377)	3,985 6,397 134,389	14,366 255 1,319	7,300 23,544
ke protect scellaneou btotal, swari new	(10 <sup>3</sup> cft) ion 10 <sup>3</sup> m <sup>2</sup>	(30,862) Sodding 80(861) Pavement 35(377)	3,985 6,397 134,389	255 1,319	7,300 23,544
scellaneou btotal, swari new	10 <sup>3</sup> m <sup>2</sup>	Sodding 80(861) Pavement 35(377)	6,397 134,389	1,319	23,544
ibtotal, eswari new	n a shi ƙasar 1939 - Asar 1939 - Asar	i an an Angel Standard an Angel State State State State State State State State	134,389	1,319	
ibtotal, eswari new	n a shi ƙasar 1939 - Asar 1939 - Asar	lands faithe Sector Contact	134,389	· · · · · ·	
ibtotal, eswari new	channel			27,887	496 97
	channel				
eet pile				N C L L	
ICCC PITC	Ξ.	3,000	17	572	7 /57
	(ft)	(9,843)	17	212	7,453
edging	$10^{3} \text{m}^{3}$	6,600	3,697	4,325	59,922
scellaneou	(10 <sup>3</sup> cft)	(233,051)	186	245	3,371
s fertil.					
DECEAL			3,900	5,142	70,746
tal (1)+(2	:)+(3)		271,837	60,876	1,063,225
ment			1 907	16 216	010 616
	N+(3) 1 (4)	에 있는 것은 가지 않는 것이다. 같은 것을 같은 것을 하는 것이다.			212,615
/Lai (1)+(2	.)+(3)+(4)		2/3,044	//,092	1,275,840
acquisitic	n	and the second			
ght guide-	bank acre	157	1,883		1,883
ft guide-b	ank acre	151	1,812		1,812
		900			10,799
👌 channel	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1				
ibcotal			14,494		14,494
Generalista Ganta data		「「「」」「「「」」」。 「「」」「「」」」「「」」」。 「」」「」」」「」」」			630
81 			288,138	77,092	1,290,334
	ement otal (1)+(2 acquisitic ght guide- ft guide-b maleswari n channel	otal (1)+(2)+(3) ment otal (1)+(2)+(3)+(4) acquisition ght guide-bank acre acre acre acre channel btotal al	<pre>ptal (1)+(2)+(3) pment ptal (1)+(2)+(3)+(4) acquisition ght guide-bank acre 157 eft guide-bank acre 151 saleswari new acre 900 channel btotal al</pre>	otal (1)+(2)+(3)       271,837         oment       1,807         otal (1)+(2)+(3)+(4)       273,644         acquisition       157       1,883         aft guide-bank       acre       157       1,883         aft guide-bank       acre       151       1,812         aleswari new       acre       900       10,799         channel       14,494       14,494	tal (1)+(2)+(3)       271,837       60,876         nment       1,807       16,216         tal (1)+(2)+(3)+(4)       273,644       77,092         acquisition       157       1,883         eft guide-bank       acre       157       1,883         eft guide-bank       acre       151       1,812         maleswari new       acre       900       10,799         channel       14,494       14,494         al       288,138       77,092

Works	Description	Person No. (m.d)		Amount (10 <sup>3</sup> )
Right guide-bank		a a construction and a second s		
Apron	Skilled	29,620	Tk	1,210
an an an Anna a Anna an Anna an	Unskilled	877,500		14,930
	Foreign	29,620	. \$	1,946
	Subtotal	936,740	Tk	41,430
Embankment	Skilled	28,700	Tk	670
	Unskilled	680	Tk	10
	Foreign	210,690		14,430
	Subtotal	240,070	Tk 1	.88,270
Dike protection	Skilled	35,990	Tk	940
	Unskilled	45,980	Tk	780
	Foreign		\$	-
	Subtotal	81,970	Tk	1,720
Total	Skilled	94,310	Tk	2,820
	Unskilled	924,160	Tk	15,720
	Foreign	240,310	\$	16,376
	Total	1,258,780	Tk 2	231,420
Left guide-bank				an a
Apron	Skilled	30,090	Tk	1,230
	Unskilled	891,540	Tk	15,170
	Foreign	30,090	\$	1,977
	Subtotal	951,720	Tk	42,090
Embankment	Skilled	28,700	Tk	670
	Unskilled	710	Tk	10
	Foreign	210,690	\$	14,420
	Subtotal	240,100		.88,270
Dike protection	Silled	35,990	Tk	930
	Unskilled	45,980	Tk	780
	Foreign		\$	
	Subtotal	81,970	Tk	1,720
<b>Fotal</b>	Skilled	94,780	Tk	2,830
	Unskilled	938,230		15,960
그리는 말에 있는 사람이 있는 것은	Foreign	240,780		16,406
	Total	1,273,790	Tk 2	32,070
Dhaleswari new channel	and the state of the		12 ( 3 	
Sheet pile	Skilled	$-\frac{1}{2} \sum_{i=1}^{n} \frac{1}{2} \sum_{i=1}^{n} 1$	Tk	<b></b>
	Unskilled		Tk	<del>-</del> 1 <sup>1</sup>
	Foreign	8,700	\$ i a	595
	Subtotal	8,700	Tk	7,730
Dredging	Skilled	25,020	Tk	600
	Unskilled	-	Tk	· — · · · ·
	Foreign	51,180	\$	3,895
	Subtotal	76,200	Tk	51,230
Total	Skilled	25,020	Tk	600
	Unskilled	an 🗋 🛨 🖓 an	Tkoster	i si <del>n</del> i di
	Foreign	59,880	<b>*\$</b> ≥ galio	4,490
	Total	84,900	Tk	58,970
Grand total	Skilled	214,110	Tk	6,250
	Unskilled	1,862,390		31,680
د می از م موجه از این می موجه از می از می از می می می می می می از م	Foreign	504,970		37,272
	Grand total	2,617,470		22,470
	The ludine mi	scellaneous v	iorle (5	91

		n kan sa	Costs			
Equipment	Quantity	Unit price (\$)	F.C. (10 <sup>3</sup> \$)	D.C. (10 <sup>3</sup> Tk)		
Tractor shovel (5 m <sup>3</sup> )	6	167,800	1,007			
Dump truck (32t)	19	135,800	2,756			
Tire dozer (19t)	6	66,000	396	n an an t-		
Bull dozer (16t, swamp)	9	63,390	571			
Vibro pile driver (15 kw)	73	8,645	631			
Crawler crane (20t)	73	59,660	4,355	na dha an ta sao Taon Na Staine 📅 👘		
Sheet pile (1=5m, b=0.333m)	1,355t	267	356			
Engine dynamo (125kvA)	20	20,000	400			
Diesel Pump dredger (4,000PS)	1	accounted	in constru	uction base		
Anchor barge (15t)	1	-do-				
Dredging pipe ( <sub>\$\$710mm</sub> , 5m)	500sets	808	404	-		
Floater (ø1,300mm, 4.5m)	134sets	3,630	486			
Joint (1-1.5m, rubber)	500sets	1,400	186	-		
Macadam roller (10-12t)	16	20,700	331			
Asphalt sprayer (200 1)	7	1,220	9			
Tamper (60kg)	6	495	3	-		
Spare parts and others (30% above)	)		3,568	-		
Total amount in FOB price			15,459			
Total amount in CIF price	an a		16,216	1,807		

Table 10-10 Cost of Equipment a an ann an Airtean Airtean an Airtean Airtean Airtean Airtean Airtea

Notes: These equipments are used for the guide-bank works and some of them are applied for the Dhaleswari new channel works. 5 - S  $e^{-it}$ 

- 195 -

t se eg

(1, 2, 2)

1.25

н,

Ander der B

2 X2 🖓

÷.,

 $\{1,2,2,3,1\}$ 

on the section

1.1810


82. ant - 4 er part de la de Me


- 1433 ( ) - 54 ( )

	Qu	antity	Cos	<u>st</u>
	Unit	Quantity	D.C. (10 <sup>3</sup> Tk)	F.C. Remarks (10 <sup>3</sup> \$)
GUIDE BANK WORKS	and an and an a	<mark>ala an an</mark>	agana terre angra fato ago iterra. T	n an a chair an
Domestic materials				The Contract against
Log	<u>т</u> 3	2,173	6,902	an a <u>F</u> ste Fotoera de
Sod	$10^{3}m^{2}$	176	150	1、19段111、天政社会 ————————————————————————————————————
Miscellaneous	<b>1.s.</b>	• 1	353	n an
Total	4.2.9.3	ана у <sup>тан</sup> ана. Казана се с	7,405	e de la compañía de la grana de la grana de la grana de la decembra de la compañía de la decembra de la decembr
Foreign materials	$\mathbf{C} = \mathbf{C}$		• • •	the fail that a toky
Stone	10 <sup>3</sup> m <sup>3</sup>	2,806	206,090	19,969
Ballast (chip)	alles in	60	4,410	427 427
Light oil	K1	4,341	764	269 269 JUNE 1 100
Heavy oil	11	3,444	665	219 219
Lubricants	1.s. <sup>2</sup>	2.2998/28 1	153	54 1993 A 28 28 28 28 28 28 28 28 28 28 28 28 28
Asphalt emulsion	F	610	118	70 <sup>338</sup> (1997)
Polyethylene mat	10 <sup>3</sup> m <sup>2</sup>	242	110	70 718 FOB
Miscellaneous	10-m- 1.s.		10 500	1,080
Subtotal of CIF	and the second	1	10,522	
	•		222,722	22,052
Subtotal of FOB	i se station de la company		ava (* 1200)	752
CIF cost for ab	ove		480	900
Total				22,952 A. A. A. A.
Grand Total			230,607	<b>122.952</b> 7 (0.00)
DHALESWARI NEW CHAN			tanata anti-ta al-	Gaitheil (1995 an 1945 à 1977) à chasa air
Domestic materials				torges when at the conserver
Log	ш <sup>3</sup>	396	1,258	
Miscellaneous	1.s.	1	63	
Total	n an Araba. An Araba an Araba		1,321	te de la constante de la const
Foreign materials				
Light oil	Kl	378	66	23
Heavy oil	. U	9,341	1,805	594
Lubricants	<b>1.s.</b>	<b>1</b>	13	5
Miscellaneous	1.s.	1	95	30
Total			1,979	652
Grand Total			3,300	652
		- 196 -		


Table: 10-11: Cost of Materials of

	Table 10-12-2Construction Cost by YearWorks: Dhaleswarf New ChannelOutline of works: Dredging and miscellaneous.	Labor Labor - Alexandre - A	Equipment Materials Skilled Unskilled Total	D.C. F.C. D.C. F.C. D.C. F.C. D.C. $10^{3}$ Tk) ( $10^{3}$ Tk)	(2) (3) (4) (5) (6) (7) (8)							1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年 1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,1997年,199		1.250	225 200 1,334 200	226 200 21		
--	---	---	---	--	-----------------------------	--	--	--	--	--	--	--	--	-------	-------------------	------------	--	--







Dhaleswari New Channel



Stone dike

Existing river bed





PEOPLES' REPUBLIC OF BANGLADESH JAMUNA RIVER BRIDGE CONSTRUCTION PROJECT VOLUME II RIVER CONTROL OF GUIDE BANKS AND DHALESWARI NEW CHANNEL JAPAN INTERNATIONAL COOPERATION AGENCY NIKKEN CONSULTANTS, INC. Date Scale Drawn DRW. NO. 2-1 Approved

- (1)~(2) -

						Works:	Guide	bank		- 1
Item						Year		an a la ca		^
	Unit	6th	7th	8th	9th	10th	11th	12th	13th	Tota
EQUIPMENT (FOREIGN)		•		<u>1</u>						
Tractorshovel (5m <sup>3</sup> )	nos		6	6	6	6	ſ		÷	
Dump truck (32t)	11		19	19	19	19				
Tire-dozer (19t)	ан — <b>т</b> асал	· (	6	6	6	6			1 	
Bull-dozer(swamp,,16t)	11		. 9	÷ .	. <sup>.</sup> 9		25			
Vibro-pile driver(15KW)	$^{1}$ $n^{2}$	a at	73	1 -	÷ 73		л Набла с			
Crawler crane (20t)	П.		73		73					
Sheet pile (5mx0.333m)	t	1	,355	25 <b>1</b>	,355	e a la como e Como e a como e a				
Engine dynamo (125KW)	nos	٢	20	• .	20		ans an an anns			en e
Diezel pump dredger (4,000PS)	n II A San A		1		1		č, t			н - н - н - н
Anchor barge (15t)	11		1		1					
Dredging pipe (¢710mmx5m)	11	• 1	,000	1	,000					
Flooter(\$1,300mmx4.5m)	i ni i		268	÷.,	268					· · · ·
Joint (rubber, 1.5m)	n		266		266					• .
Macadam roller (10t)			16		16		internet Santon			
Asphalt sprayer(200 1)	11	3	<b>7</b>	· "	7	1997 - 1997 1997 - 1997 1997 - 1997 - 1997				
Tamper (60Kg)	11		6		6				· .	

	1	•••			Works:	Dhale	eswari	new ch	annel
Item	Unit				Year				
		6th	7th 8th	9th	10th	llth	12th	13th	Total
QUIPMENT (FOREIGN)				·					
Dump truck (32t)	nos				2	2	2		
Bull-dozer(swamp.,16t)	<b>11</b>			•	5	5	- - 5-		
Vibro-pile driver(15KW)	U.	All and			3		3	 	
Crawler crane (20t)	11				3	2	3		2
Engine dynamo (125KW)	11				3		2		
Diezel pump dredger (4,000PS)	Ħ				1	1	l		
Anchor barge	, tt				1	1	1		en Recent
Dredging pipe (¢710mmx5m)	11				1,000	1,000	1,000		
Flooter( $\phi$ 310mmx4.5m)	11				268	268	268		
Joint (rubber, 1.5m)	11				266	266	266		
Sheet pile(5mx0.333m)	t	2			1,355	1,355	1.355	1.11	

WorksDescription1st2nd3rd4th5th6thde-banksde-banksfor indicationististististististderbanksSkilledForeign labor76767676ApronSkilledLocal labor7777777777EmbankmentSkilledLocal labor2,2082,2032,2032,209EmbankmentSkilledForeign labor1,218-1,218	Description1st2nd3rd4th5th6tSkilledForeign labor7777777777NskilledLocal labor7777777777UnskilledLocal labor7777777777SkilledLocal labor1,218-1,218Local labor1,218-1,218SkilledLocal labor167-167Local labor157-167-167NskilledLocal labor5-5Local labor796NskilledForeign labor-7796NskilledForeign laborNskilledForeign laborNskilledForeign laborNskilledForeign labor	s     Description     lst     2nd     3rd     4th     5th     6t       Skilled     Foreign labor     76     76     7     7     71     71     77     71<	1 f 1	1.1			11	•	•			s i	- 1						÷.,		
s     Description     lst     2nd     3th     4th     5t       Skilled     Foreign labor     77     71     77     71	s     Description     lst     2nd     3rd     4th     5t       skilled     Foreign labor     7     71     71     77     71     77     71     71     71     71     71     71     71     71     71     71     71     71     71     71     71<	s     Description     lst     2nd     3rd     4th     5t       skilled     Foreign labor     76     76     76     76     77     71	6 th		1	 1	1.	I	<b>I</b>	-	ļ		. <b>.</b>	-	33	I.	l	54	40	ł	
s     Description     lst     2nd     3rd     4th       Skilled     Foreign labor     76     76     76     76       Skilled     Foreign labor     77     77     77     77     77       Unskilled     Local labor     77     77     77     77     77       Inskilled     Foreign labor     1,218     -     1,218     -       Inskilled     Foreign labor     1,218     -     167     -       Inskilled     Local labor     1,218     -     167     -       Inskilled     Foreign labor     1,218     -     167     -       Inskilled     Foreign labor     5     -     -     -       Inskilled     Foreign labor     796     -     -     -       Inskilled     Foreign labor     -     -     -     -     -       Inskilled     Foreign labor     -     -     -     -     -     -       Inskilled     Foreign labor     -     -     -     -     -     -     -       Inskilled     Foreign labor     -     -     -     -     -     -     -       Inskilled     Foreign labor     -     -     -<	s Description lst 2nd 3rd 4th Skilled Foreign labor 76 76 76 76 Skilled Foreign labor 77 77 77 77 77 77 Unskilled Local labor 77 77 77 77 77 77 Unskilled Local labor 1,218 - 1,218 - 1,218 - 1,218 - 1,67 - 160 - 1	s Description lst 2nd 3rd 4th bescription lst 2nd 3rd 4th Skilled Foreign labor 77 77 77 77 Unskilled Local labor 77 77 77 77 Unskilled Local labor 2,208 2,203 2,209 nt Skilled Local labor 1,218 - 1,218 - Local labor 1,218 - 1,218 - Unskilled Local labor 167 - 167 - Local labor 796 - 796 - tection Skilled Local labor 796 - 796 - new channel skilled Local labor 796 - 796 - Unskilled Local labor 796 - 796 - Skilled Local labor 796 - 796 - Skilled Local labor 796 - 796 - Unskilled Local labor 796 - 796 - Unskilled Local labor 796 - Unskilled Local labor	5 th		1 1	1 da 1 1	1	i u Lu		1	· . I	2 i. 1	1 	1 . . 1 .	 I.	.1	. 1	. 81	40	н 14 - <b>П</b> 14 - Ал - А	•:
s Description lst 2nd 3rd 3rd 5killed Foreign labor 76 76 76 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 3rd 3rd skilled Foreign labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description Ist 2nd 3rd 3rd 3rd Skilled Foreign labor 76 76 76 76 77 77 77 77 77 77 77 77 77	4th		76	77	2,209		<b>I</b>	ł	1		 I		33	1	د بالا د الارد	79	40	s A Eu∎	
s Description lst 2nd Skilled Foreign labor 76 76 Local labor 77 77 Unskilled Local labor 1,218 - Local labor 2,208 2,203 Local labor 1,218 - Local labor 2,208 2,203 Local labor 2,208 2,203 - Local labor 2,208 2,203 - Local labor 2,208 2,203 - Local labor 1,218 - Local labor 2,208 2,203 - Local labor 2,208 2,203 - Local labor 1,218 - Local labor 2,208 2,203 - Local labor 2,208 2,203 - Local labor 1,218 - Local labor 2,208 2,203 - Local labor 1,218 - Local labor 2,208 2,203 - Local labor 1,218 - Local labor 2,208 2,203 - Local labor 2,208 2,203	s Description lst 2nd Skilled Foreign labor 76 76 Inskilled Foreign labor 77 77 Unskilled Local labor 2,208 2,203 skilled Local labor 1,218 - Local labor 1,218 - Local labor 167 - Local labor 796 - Unskilled Local labor 796 - Unskilled Local labor 796 - Unskilled Local labor 796 - Unskilled Local labor 796 - Skilled Foreign labor Skilled Local labor Unskilled Local labor Skilled Local labor Unskilled Local labor Skilled Local labor	s Description lst 2nd Skilled Foreign labor 76 76 Iocal labor 77 77 Unskilled Local labor 1,218 - Skilled Local labor 1,218 - Local labor 1,218 - Local labor 1,218 - Local labor 167 - Local labor 625 - Unskilled Local labor 796 - New channel Skilled Local labor 796 - Unskilled Local labor 796 - New channel Local labor 796 - Unskilled Local labor Skilled Foreign labor Skilled Local labor Skilled Local labor Unskilled Local labor Skilled Local labor	3rd	· .	76	77		1,218	167	<mark>َ</mark> ا	I	625	796		ļ	1	1	I	I	ین ۲۰۰۹ ۲۰۱۹	
s Description lst skilled Foreign labor 76 Unskilled Foreign labor 77 Unskilled Local labor 2,208 nt Skilled Foreign labor 1,218 Local labor 1,218 Local labor 167 Unskilled Foreign labor 625 Unskilled Local labor 796 new channel Skilled Local labor 625 new channel Skilled Local labor 625 new channel Skilled Local labor 625 new channel Skilled Local labor 625 Unskilled Local labor 796 new channel Skilled Local labor 796 new channel Unskilled Local labor 796 new channel Unskilled Local labor 796 new channel Unskilled Local labor 796 new channel Local labor 796 new channel Unskilled Local labor 796 new channel Local labor 796 new channel Local labor 796 new channel Local labor 796	s Description lst Skilled Foreign labor 76 Skilled Foreign labor 77 Unskilled Local labor 2,208 nt Skilled Foreign labor 1,218 Local labor 167 Unskilled Local labor 625 Unskilled Local labor 625 Unskilled Local labor 625 new channel Skilled Local labor 625 new channel Skilled Local labor 796 new channel Skilled Local labor 796 new channel Skilled Local labor 796 unskilled Local labor 796 new channel Unskilled Local labor 796 Unskilled Local labor 796 new channel Unskilled Local labor 796 Unskilled Local labor 796 new channel Local labor 796 new channel Local labor 796 new channel Local labor 796 Unskilled Local labor 796 Unskilled Local labor 706	s Description lst Skilled Foreign labor 76 Skilled Foreign labor 77 Unskilled Local labor 2,208 nt Skilled Foreign labor 1,218 Local labor 167 Unskilled Local labor 625 Unskilled Local labor 625 Unskilled Local labor 625 new channel Skilled Local labor 625 new channel Skilled Local labor 796 new channel Skilled Local labor 796 new channel Skilled Local labor 796 unskilled Local labor 796 new channel Unskilled Local labor 796 Unskilled Local labor 796 new channel Unskilled Local labor 796 Unskilled Local labor 796 new channel Local labor 796 new channel Local labor 796 new channel Local labor 796 Unskilled Local labor 796 Unskilled Local labor 706	2nd		26	11		1	1	1	ſ		1	н 11		ļ	ļ	I		•	
s Description Skilled Foreign labor Unskilled Foreign labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Foreign labor Unskilled Local labor	s Description Skilled Foreign labor Unskilled Foreign labor Unskilled Foreign labor Unskilled Foreign labor Unskilled Local labor Unskilled Local labor Unskilled Foreign labor Unskilled Foreign labor Unskilled Foreign labor Unskilled Local labor	s Description Skilled Foreign labor Unskilled Foreign labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Local labor Unskilled Foreign labor Unskilled Foreign labor Unskilled Local labor	lst		76	77		1,218	167	'n		625	296	· · . ·	1	t	1	j.	1	ļ	
s Descr Skilled unskilled unskilled tection Skilled new channel unskilled Skilled Skilled Unskilled Unskilled	s Descr Skilled unskilled unskilled tection Skilled new channel unskilled Skilled Skilled Unskilled Unskilled	s Descr Skilled unskilled unskilled tection Skilled new channel unskilled Skilled Skilled Unskilled Unskilled			labor	bor	· ' .	1.11	bor	bor	labor	bor	рог	•	labor	bor	bor	labor	bor	рог	  
s Descr Skilled Unskilled Unskilled Unskilled tection Skilled new channel Unskilled Skilled Skilled Unskilled	s Descr Skilled Skilled Unskilled Unskilled tection Skilled new channel Unskilled Skilled Skilled Unskilled	s Descr Skilled Skilled Unskilled Unskilled tection Skilled new channel Unskilled Skilled Skilled Unskilled	iption		Foreign	Local la	Local la	Foreign	Local la	Local la	Foreign	ccal la	local la		oreign	local la	local la	Poreign	ocal la	ocal la	
s nt tection le v channel	s nt tection le v channel	s nt tection le v channel	Descr						. <b>-</b> :							. <b>I</b>		- 1 - -	Η	. ·	
Works de-banks Apron Embankment Dike protection leswari new channel Sheet pile Dredging	Works Guide-banks Apron Embankment Embankment Dike protection Dhaleswari new channel Sheet pile Dredging	Works Guide-banks Apron Embankment Embankment Dike protection Dike protection Sheet pile Bredging		• • • • • • • •	Skflld		Unsk1	Skille		Unski.	Skille		Unski.		Skille	::: :	Unski]	Skille		Unskil	•
Works de-banks Apron Embankment Dike protecti leswari new c Sheet pile Dredging	Works Guide-banks Apron Embankment Embankment Dike protecti Sheet pile Dredging	Works Guide-banks Apron Embankment Dike protecti. Sheet pile Sheet pile					- - - - - - -				по		, , , ,	nannel			-				- 14 - 
Wor de-bank Apron Embank Dike pr leswari Sheet p Dredgin	Wor Guide-bank Apron Embank Dike pr Dhaleswari Sheet p Sheet p Dredgin	Wor Guide-bank Apron Embank Dike pr Sheet p Sheet p Dredgin	ks	S.				lent			otectio	· · · ·	· · ·	new cl	ile	1 - 4 - -		60			- - 
			ГОМ	de-bank	Apron			Embankn			Dike pr			leswari	Sheet p	ъ.,		Dredgin			
				Description lst 2nd 3rd 4th 5th	s Description lst 2nd 3rd 4th 5th	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 -	s Description lst 2nd 3rd 4th 5th 5th Skilled Foreign labor 76 76 76 - 77 77 77 77 77 77 77 77 77 77 77 77 7	s Description lst 2nd 3rd 4th 5th 5th Skilled Foreign labor 76 76 76 76 - Local labor 77 77 77 77 77 - Unskilled Local labor 2,208 2,203 2,209 -	<pre>s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 76 -</pre>	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 76 - Skilled Local labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 76 - Skilled Local labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 76 - Skilled Foreign labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 76 - Local labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 7 Nnskilled Focal labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th Skilled Foreign labor 76 76 76 - Skilled Foreign labor 77 77 77 77 77 77 77 77 77 77 77 77 77	<pre>s Description lst 2nd 3rd 4th 5th 6t killed Foreign labor 76 76 76 76 -</pre>	<pre>s Description lst 2nd 3rd 4th 5th 6t killed Foreign labor 76 76 76 76 -     Skilled Foreign labor 77 77 77 77 77 77     Unskilled Local labor 2,208 2,203 2,209 -     Local labor 1,218 - 1,218     Local labor 167 - 167     Local labor 167 - 167     tection Skilled Foreign labor 796 - 796     Local labor 796 - 796     loskilled Foreign labor 33 -     le Skilled Foreign labor</pre>	s Description lst 2nd 3rd 4th 5th 6t Skilled Foreign labor 76 76 76 76 - Local labor 77 77 77 77 77 - Unskilled Local labor 2,208 2,203 2,209 - nt Skilled Local labor 1,218 - 1,218 - 7 Local labor 1,218 - 1,218 - 7 nt Skilled Local labor 1,218 - 1,67 - 1 Cocal labor 167 - 167 - 1 Local labor 5 - 5	s Description lst 2nd 3rd 4th 5th 6t Skilled Foreign labor 76 76 76 76 - Local labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th 6t Skilled Foreign labor 76 76 76 76 - Skilled Foreign labor 77 77 77 77 77 77 77 77 77 77 77 77 77	s Description lst 2nd 3rd 4th 5th 6t Skilled Foreign labor 76 76 76 76 - Skilled Foreign labor 77 77 77 77 77 77 77 77 77 77 77 77 77

APPENDIX D BIBLIOGRAPHY AND DATA All bibliography and data collected in Bangladesh and in Japan and used in the present study are listed in this appendix. For the con-venience of reference, they have been calssified into the categories shown below.

WL	: Data on water level.and control of the second state of the data and
DIS	: Data on discharge.
RF	: Data on rainfall.
FLD	: Data on flood.
SED	: Data on sediment.
BR	: Data on boring test.
RC	: Data on river course.
SVY	: Data on surveying.
TOP	: Topographic map.
PHT	: Photograph.
CS	: Data on construction cost.
PJT	: Report on project concerning the Jamuna River.
GN	: Data on general description of the Jamuna River.
ADM	: Data on administration.
CF	: Data on consulting firm.
MET	: Data on meteorology.
CON	: Data on construction works.
GB	: General bibliography.
JB	: Report on the Jamuna Bridge.
GE	: Report on geography.
GM	: Report on Geomorphology.

- (5) -

	eri. No.	Kind of Data	Bibliography or Data	Data Sources
	1	WL	BWDB WATER SUPPLY PAPER - 168 Gauge Readings of Brahmaputra-Jamuna River at Sirajganj, 1945 - 56	Surface Water Hydrology Directorate, BWDE
	2	WL,DIS	BWDB WATER SUPPLY PAPER - 2	
			Gauge & Discharge Observations for Ganges River at Hardinge Bridge, Paksey, 1933 - 58	
:	3	WL,DIS	BWDB WATER SUPPLY PAPER - 18 Gauge & Discharge Records for B-J River at Bahadurabad, 1948 - 58	1
	4	WL	BWDB WATER SUPPLY PAPER - 53 Gauge Readings of B-J River at Chilmari, 1957 - 58	n an
	5	WL	BWDB WATER SUPPLY PAPER - 55 Gauge Readings of B-J River at Chilmari, 1957 - 58	n an an Arrange an Arr Arrange an Arrange an Ar
	6	WL	BWDB WATER SUPPLY PAPER - 142 Gauge Readings of B-J River at Sirajganj 1957 - 58	• • • • • • • • • • • • • • • • • • •
	7	WL,DIS	BWDB WATER SUPPLY PAPER - 102 Gauge & Discharge Observations of B-J River, 1959 - 61	<b>n</b>
	8	WL,DIS	BWDB WATER SUPPLY PAPER - 194 Gauge Readings & Discharge Observations of Ganges River, 1959 - 61	ali ang kanalang kanalan Ang kanalang kanalan Ang kanalang
	9	WL,DIS	BWDB WATER SUPPLY PAPER - 192 Gauge Readings & Discharge Observations of B-J River, 1962	
1	0	WL	HYDROLOGICAL YEAR BOOK, 1964 - 65 Vol II : Water Levels	1997 - 1993 - 1997 - 19
1	1	DIS	HYDROLOGICAL YEAR BOOK, 1964 - 65 Vol III : Discharge	<b>U</b>
1	2	WL	HYDROLOGICAL YEAR BOOK, 1965 - 66 Vol II : Water levels	All and a second sec All and a second s
1	3	DIS	HYDROLOGICAL YEAR BOOK, 1965 - 66 Vol III : Discharge	Surface Water, BWDB
14	4	WL	HYDROLOGICAL YEAR BOOK, 1966 - 67 Vol II : Water Levels	H.
1	5	DIS	HYDROLOGICAL YEAR BOOK, 1966 - 67 Vol III : Discharge	۵. این
1	6 <sup>`</sup>	WL	HYDROLOGICAL YEAR BOOK, 1968 - 69 Vol II, Part-A : Water Levels	n de la construcción de la constru La construcción de la construcción d La construcción de la construcción d
			- (6) -	

No.	of Data	Bibliography or Data	Data Source
17	DIS	HYDROLOGICAL YEAR BOOK, 1968 - 69 Vol III : Discharge	Surface Water, BWDB
18	ADM	Organization Chart of BWDB and River Morphology, Research and Training	River Morphology Research and Training, BWDB
19	- GN	REPORT ON STUDY OF BANK MOVEMENT OF RIVER BRAHMAPUTRA by IECO, 1964	11
20	FLD	BWDB WATER SUPPLY PAPER - 7 Technical Report on Flood in East Pakistan, 1960	Surface Water, Hydrology, BWDB
21	FLD	BWDB WATER SUPPLY PAPER - 223 Annual Report on Flood in Bangladesh for 1964	11
22	FLD	BWDB WATER SUPPLY PAPER - 251 Annual Report on Flood in East Pakistan for 1965	la su de la superior de la superior La superior de la superior de la superior de la superior de
23	FLD	BWDB WATER SUPPLY PAPER - 272 Annual Report on Flood in East Pakistan for 1966	u u
24	FLD	BWDB WATER SUPPLY PAPER - 308 Annual Report on Flood in East Pakistant for 1967	an a
25	FLD	BWDB WATER SUPPLY PAPER - 355 Annual Report on Flood in Bangladesh for 1970	$\label{eq:states} \left\{ \begin{array}{ll} \mathbf{H}_{\mathbf{n}} = \left\{ \mathbf{H}_{\mathbf{n}}$
26	FLD	BWDB WATER SUPPLY PAPER - 357 Annual Report on Flood in Bangladesh for 1971	1000 - 10000 - 10000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 -
27	WL, DIS	BWDB WATER SUPPLY PAPER - 318 Water Level & Discharge Observation Records of Ganges River, Jan. 1963 - Mar. 1965	Surface Water, BWDB
28	SED	FAO-SF SECOND HYDROLOGICAL SURVEY IN BANGLADESH : Sediment Investigation, 1966 & 1967	1
29	SED	BWDB WATER SUPPLY PAPER - 359 Sediment Investigations in Main Rivers of Bangladesh, 1968 & 1969	1977 - 1978 - 1979 - 19
30		Omitted	
31	GN	REPORT ON HYDROLOGY OF BANGLADESH By J. TH. THIJSSE, 1964	River Morphology BWDB
32	PJT	DESIGN REPORT ON BANK PROTECTION STRUCTURE FOR THE PROTECTION OF SERAJGANJ TOWN FROM EROSION BY THE RIVER JAMUNA by Engineering Consultants, Inc. 1970	Western Zone, BWDB
		- (7) -	

No.	of Data	Bibliography or Data	Data Source
33	PJT,CS	Serajganj Town Protection Project •Plan : scale 16" = 1 mile •Weekly progress report for the week ending, 17 Aug. 1973	Western Zone, BWDB
34	GN	WATER RESOURCES DEVELOPMENT AND FLOOD CONTROL IN BANGLADESH	Planning, BWDB
<b>35</b> (1) (1)	PJT	BRAHMAPUTRA LEFT EMBANKMENT by International Engineering Co. Inc., 1965	1
36	PJT	BRAHMAPUTRA FLOOD EMBANKMENT PROJECT: Feasibility Report, Phulchari to Sirajganj; by International Engineering Co. Ltd., 1962	1000 - 1000
37	PJT	BRAHMAPUTRA FLOOD EMBANKMENT PROJECT: Definite Report by International Engineering Co., Ltd.	
38	PJT	BRAHMAPUTRA BARRACE; Studies	U
39	PFT	FEASIBILITY REPORT FOR THE PROTECTION OF CHANDPUR TOWN: Vol. I Summary, Conclusion and Recommendations by Prokaushali Sangsad Limited	
40	SED	MATERIAL TESTING REPORT: Report No. SED - 60, 1969	River Morphology, BWDB
41	SED	SEDIMENT TESTING REPORT: Report No. SED - 68, 1970	ана сайта. 1997 — Правил Алариан, 1997 — Правил Алариан, 1997 — Правил Алариан, 1997 — Правил Алариан, 1997 — Правил Алариа 1997 — Правил Алариан, 1997 — Правил Алариан, 1997 — Правил Алариан, 1997 — Правил Алариан, 1997 — Правил Алариа
42	SED	SEDIMENT PROBLEM STUDY: Note on Computation of Sediment Discharge and Bed-load, 1972	in the second seco
43	DIS	Discharge Observation by River Morphology: Discharge Explanatory Notes Chilmari : 1965/66 - 1972/73 (1971/72; no data)	
		Sirajganj: 1965/66 - 1972/73 Nagarbari: 1965/66 - 1971/72 Kalikapur: 1968/69 - 1972/73 Haripur : 1968/69 - 1972/73 (1971/72; no data)	
		Jamalpur : 1968/69 - 1972/73 (1971/72; no data)	
44	SED	Data on Sediment Discharge for 1970/71 at Nagarbari and Kalikapur	ана (разволо Собрани) Н
45	<b>WL</b> (1997) (199	Monthly Maximum Water Level of Regular Gages and Valley Gauges Since 1965	4 2000 - 2000 2000 - <b>Ω</b> 2000 - <b>Ω</b> 2000 - 2000 - 2000 - 2000 2000 - 2000 - 2000 - 2000 - 2000
			je 1990 – John Steiner, so 1990 – Statistica Statistica 1990 – Statistica Statistica

46		Bibliography or Data	Data Source
	RC	Cross Section of the Brahmaputra River Within the Extent from Aricha to Bahadurabad for the Period from 1965 to 1973	River Morphology BWDB
47	RF	HYDROLOGICAL YEAR BOOK, 1964 - 65 Vol I: Rainfall & Evaporation	Surface Water, BWDB
48	RF	HYDROLOGICAL YEAR BOOK, 1965 - 66 Vol I: Rainfall & Evaporation	11 - 11 - 11 - 11 - 11 - 11 - 11 - 11
49	RF	HYDROLOGICAL YEAR BOOK, 1966 - 67 Vol I: Rainfall & Evaporation	11
50	RF	HYDROLOGICAL YEAR BOOK, 1967 - 68 Vol I: Rainfall & Evaporation	Ħ
51	RF	HYDROLOGICAL YEAR BOOK, 1968 - 69 Vol I: Rainfall & Evaporation	n
52	RF	HYDROLOGICAL YEAR BOOK, 1969 - 70 Vol I: Rainfall & Evaporation	11
53	TOP	<pre>Irrigation Maps; scale = 1 : 40,000 No.79(E/9), 79(E/3), 78(H/9) - 78(H/16); 78(G/9) - 78(G/16)</pre>	River Morphology BWDB
54	WL,DIS	Stage Discharge Relation of River Brahmaputra; Sirajganj : 1967/68, 1966/67 Chilmari : 1967/68	1000 - 10000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1000 - 1
55	WL	Water Level Record of Regular and Valley Gauges for the Period from Apr. 1970 to Mar. 1971	ана стала стала 1993 — Прина Стала 1993 — Прина Стала стала стала 1994 — Прина Стала
56	BR		Ground Water, BWDB
57	BR	Exploratory Drilling Logs; 1000 Tube Well Project	11
58	CS	No.7 : 1970 - 71	Bureau of Statistics Bangladesh
<b>59</b>	CS	Revised Estimates of Gross Domestic Product of Bangladesh for 1960/70 and 1972/73, Apr. 1973	
60	CS	Price Index for 1972/73; •Wholesale Prices of Agricultural Product in Bangladesh Including Detail prices of Some Selected Items •Cost of living : Dacca Middle Class •Consumer Price Index for Industrial	S II
		Workers at Narayanganj °Wholesale Prices of Industrial Products of Some Selected Items - (9) -	

Seri. No.	Kind of Data	Bibliography or Data Data Source
61	ADM	MANIFESTO OF BANGLADESH AWAMI LEAGUE IWATA
62	RC	Sounding Maps; scale 1 : 25,000 Nagarbari to Mirkutia via Char Pechokhole Sohagpur to Sirajganj Ghat, Sirajganj
63	HDG	Data on Hardinge Bridge Typical Cross Section of Left Guide Bank Protection Works at Right Bank Left Guide Bank Showing Progress in Different Years Plan Showing Successive Alignment in Damukdia & Right Guide Bank in Connection with Closure of Gap
64	HDG	Hardinge Bridge Section Taken at Center Line; from Jan. to Jun., 1968 from Jul. to Dec., 1968 from Jan. to Jun., 1969 from Jan. to Jun., 1970 from Jul. to Dec., 1970
65	DIS,HDG	Discharge Measurements at the River Gauges at Hardinge Bridge from the Year 1968 to 1970
66	HDG	HISTORY OF THE HARDINCE BRIDGE up to 1941
67	HDG	RIVER TRAINING AND CONTROL by Francis J. E. Spring
68	FLD	BWDB WATER SUPPLY PAPER - 67Surface Water,Flood Report of East Pakistan, 1961BWDB
69	FLD	BWDB WATER SUPPLY PAPER - 119 Annual Report on Flood in Bangladesh " for 1962
70	FLD	BWDB WATER SUPPLY PAPER - 182 Annual Report on Flood in Bangladesh " for 1963
71	FLD	BWDB WATER SUPPLY PAPER - 330 Annual Report on Flood in East Pakistan " for 1968
72	FLD	BWDB WATER SUPPLY PAPER - 357 Annual Report on Flood in Bangladesh " for 1971
73	WL	HYDROLOGICAL YEAR BOOK, 1967-68 Vol II : Water Level "
74	RF	Daily RAINFALL OF EAST PAKISTAN Jan. to Dec., 1960
75	RF	BWDB WATER SUPPLY PAPER - 170 Daily Rainfall of East Pakistan " Jan. to Dec., 1961
		- (10) -

Seri. No.	Kind of Data	Bibliography or Data	Data Source
76	RF	BWDB WATER SUPPLY PAPER - 227 Daily Rainfall of East Pakistan Jan. to Dec., 1962	Surface Water, BWDB
77	RF	BWDB WATER SUPPLY PAPER - 226 Daily Rainfall of East Pakistan Jan. to Dec., 1962	
78	GN	Line Diagram Showing Important River System in Bangladesh	ан 1997 - Алар Алар Алар Алар 1997 - Алар Алар Алар Алар Алар Алар Алар Алар
79	WL	Monthly Max & Min Water Level; Supplemental Data on Water Level of the Brahmaputra-Jamuna River and Ganges River	аналар 1996 — <b>Л</b> аналар 1997 — Паралар 1997 — Паралар
80	RPL	FEASIBILITY REPORT FOR THE PROTECTION OF CHANDPUR TOWN; Vol II Economic Investigation & Urban Planning	Planning, BWDB
81	RPL	FEASIBILITY REPORT FOR THE PROTECTION OF CHANDPUR TOWN; Vol III Engineering Aspects & Legislation	n T
82	RPL	RESUME AND DESIGN Drawings for Chandpur Town Protection, 1st Phase	$ \begin{array}{l} \sum_{i=1}^{n} \left\{ \left\{ \left\{ {{\mathbf{u}}_{i}} \right\} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{\mathbf{u}}_{i}} \right\} \in \left\{ {{\mathbf{u}}_{i}} \right\} \\ = \left\{ {{u$
83	GN	RIVER AND FLOOD PROBLEMS OF BANGLADESH AND THEIR SOLUTIONS	Ministry of Flood Control and Water Resources
84	WL	HYDROLOGICAL YEAR BOOK, 1969 - 70 Vol II Part - A : Water Level	Surface Water, BWDB
85	CS	Unit Cost of Construction Works, Materials and Wages	Western Zone, BWDB
86	PJT,CS	FEASIBILITY REPORT FOR THE PROTECTION ON CHANDPUR TOWN;	Planning, BWDB
		Vol IV Financial Consideration & Project Evaluation	
87	GN	MASTER PLAN: Vol II by IECO	River Morphology, BWDB
88	PJT	REPORT FOR PRELIMINARY ENGINEERING SURVEY AND CONSTRUCTION ESTIMATE FOR ISHURDI-PABNA-NAGARBARI RAILWAY PROJECT, 1963	Railway, MOC
89	PJT	REPORT FOR PRELIMINARY ENGINEERING SURVEY AND CONSTRUCTION ESTIMATE FOR DACCA-TUNGI-ARICHA RAILWAY PROJECT, 1963	
		- (11) -	

90	177		na in the second s
90	WL	Water Level Records of All Regular Gauges within the Extent from Aricha to Bahadurabad for the Period from 1st Sept. 1973 to 31st Oct. 1973	River Morphology, BWDB
91	РНТ	Aerophotographs Covering the Jamuna River for 1952, 1960 and 1970 - 71, scale 1 : 50,000	Survey of Bangladesh
92	РНТ	Aerophotographs Covering the Four Proposed Sites for 1970 - 71: scale nearly 1 : 10,000	9. H
93	тор	Topographic Maps Covering the Jamuna River; scale 1:250,000, 1 : 50,000	Survey of Bangladesh
94	TOP	Topographic Maps Covering the Whole Country; scale 1:250,000, 1 : 50,000	
95	PHT	Photographs of Right & Left Bank along the Jamuna River Taken, from Helicopter at 1,000 m in altitude	River Study Team
96	BR	SOIL TESTING REPORT OF BRIDGE OVER RIVER BRAHMAPUTRA & JAMUNA, Miranpur (Bogra) Hole No.G4	Hydraulic Researc Laboratory
97	SVY	Geodesic Triangulation Station	Survey of Bangladesh
98	GN	SEMINAR ON FLOOD CONTROL AND WATER RESOURCES DEVELOPMENT IN BANGLADESH, Aug. 1972	Ministry of Flood Control and Water Resources
99	PJT	DACCA SOUTH-WEST PROJECT : Feasibility Report Vol. IV Hydrology and River Hydraulics by ECI-ACE, Aug. 1970	an an an an Antara an Angan tao amin'ny taona 1000 Mangana amin'ny taona 2008–2014.
100	MET	Data on Meteorology for the Period from 1960 to 1972 at Rangpur, Bogra, Sirajganj and Faridpur	Meteorological an and Geophysical Center in Chittago
101	GN	Extract from SOME ASPECTS OF SEDIMEN- TOLOGY AND GEOLOGY OF BENGAL BASIN WITH SPECIAL REFERENCE TO THE BRAHMAPUTRA BASIN	Ground Water, Hydrology, BWDB
102	GN	Extract from RIVER OF THE BENGAL DELATA, by S. C. Majumder, 1941	<b>H</b>
103	GN,PJT	Extract from RIVER MECHANICS AND MORPHOLO DACCA SOUTH-WEST PROJECT BANGLADESH, Reported by D. B. Simon & Others	GY, "
104	PJT	PRELIMINARY DESIGN REPORT: EAST-WEST INTERCONNECTOR PROJECT, Vol. II plates, Acres International Ltd. Consulting Engineers (PAK) Ltd.	Π.
		- (12) -	

(

No.	of Data	Bibliography or Data	Data Source
.05	Br	Well Record Card; Kuchma X-l, Bogra X-l, Hazipur HX-l	Ground Water Hydrology, BWDB
.06	ADM	PORT OF CHITTAGONG (Booklet), year book of information, 1972-73	Chittagong Port Trust
.07	CS	Rental Rates of Schedule of Equipment MEO, BWDB	MEO, BWDB
.08	CON	A SHORT NOTE ON DREDGING IN BANGLADESH, submitted by Adal Chief Engineer Services, BWDB	Dredger Organization BWDB
09	CS	BASIC DATA AND IDEAS ABOUT FUTURE DEVELOPMENT, Chittagon Steel Mill Ltd.	Chittagong Steel Mill Ltd.
10	SC	PRICE LIST, Chittagong Steel Mill Ltd.	<b>I</b> T
11	<b>CS</b>	GENERAL ABSTRACT OF BUDGET OF SIRAJGANJ TOWN PROTECTION SCHEME UNDER BORGA W.D. CIRCLE FOR THE YEAR 1973-74	Brahmaputra Survey Division BWDB
12	CON	NOTE ON EXPERIMENTS WITH MODELS OF FALLING APRONS, Oct. 1935, Irrigation Research Division	BRB
13	GN	FLOOD CONTROL PLAN FOR EAST PAKISTAN, Fir Pakistan Water and Power Development Auth 1964.	st Stage, East ority, Oct.,
14	GB	Gerald Lacey: STABLE CHANNELS IN ALLUVIU Vol. 229, 1929-30.	M, Proc. I.C.E.
15	GB	C.C. Inglis: THE RELATIONSHIP BETWEEN MEADISTANCE BETWEEN MEANDERS ON AXIS OF STREADISCHARGE OF RIVERS IN FLOOD PLAINS AND IN Government of India, Central Board of Irr: Power, Annual Report, 1938-1939, New Delh	AM, WIDTH OF NCISED RIVERS; igation and
16	JB	BRAHMAPUTRA (JAMUNA) RIVER CROSSING FEASING Stage One; Freeman, Fox and Partners; Road ways Directorate, Government of East Pakis	ls and High-
17	JB	PREFEASIBILITY STUDY REPORT ON JAMUNA RIVI PROJECT IN BANGLADESH, March 1973, Oversea Cooperation Agency, Japan (in Japanese).	
18	GB Trans States	Sir Robert Richard Gales: THE PRINCIPLES TRAINING FOR RAILWAY BRIDGES, AND THEIR AN THE CASE OF HARDINGE BRIDGE OVER THE LOWEN SARA; Jour. Inst. C.E., 1938.	PLICATION TO
19	GB	Formulas on Hydraulics, published by the . of Civil Engineers, 1971.	Japan Society
20	GB	Bertram Lionel Harvey: THE RESTORATION OF BREACHES IN THE RIGHT GUIDE BANK OF THE HA Jour. Inst. C.E., Vol.4, 1936-37.	THE ARDINGE BRIDGE;
		- (13) -	

121 GN	Abdul Latif: INVESTIGATION OF BRAHMAPUTRA RIVER; Proc. A.S.C.E., Sept., 1969.
122 GN	FLOOD CONTROL PLAN OF EAST PAKISTAN; Water and Power Deve- lopment Authority, Sept., 1968.
123 GB	Emmett M. Laursen: SCOUR AT BRIDGE CROSSINGS, Trans. A.S.C.E., Vol. 127, 1962, Part I.
124 GB	Akihiko Tsuchiya: SCOUR AROUND PIER; Bridge and Foundation, Vol. 4, Jan., 1970 (in Japanese).
125 GB	G. Suga and K. Ishizaki: Local Scour in River; Civil Engineering Data, Sept., 1967, Vol. 9, No. 9, Public Works Research Institute, Ministry of Construction, Japan (in Japanese).
126 GB	Tetsuo Kunihiro: PRELIMINARY STUDY ON THE JAMUNA RIVER CROSSING BRIDGE PROJECT, CIVIL Engineering Data, Jun., 1973, Vol. 15, No. 6, Public Works Research Institute, Ministry of Construction, Japan (in Japanese).
127 GB	Kiyoshi Sato: DAMAGES DUE TO CYCLONE IN BANGLADESH, Proc. J.S.C.E., Vol. 56, No. 4, April 1971 (in Japanese).
128 GB	Sir Robert Richard Gales: THE HARDINGE BRIDGE OVER THE LOWER GANGES AT SARA, Proc. Inst. C.E., Vol. 205, 1917-18.
129 GB	Katsuyoshi Ishizaki and Katsuichi Honma: STUDY ON SCOUR AT PIERS, Annual Report of the Public Works Research Institute, Ministry of Construction, Japan, 1968 (in Japanese).
130 GB	S.V. Isbashi: CONSTRUCTION OF DAMS BY DEPOSITING ROCK IN RUNNING WATER, Second Congress on Large Dams (1936).
131 GB	Hideo Kikkawa: SOME CONSIDERATIONS ON SUSPENDED LOAD, Report of the Public Works Research Institute, Ministry of Construction, Japan, 1952 (in Japanese).
132 GB	Seiichi Sato: ON THE DESIGN OF RIVER CHANNELS, Journal of Japanese Society of Civil Engineers, Vol. 42, No. 4, 1957 (in Japanese).
133 GB	H.N.C. Breusers: SCOUR AROUND DRILLING PLATFORMS, Bulletin, Hydraulic Research 1964 and 1965, International Association for Hydraulic Research, Vol. 19, P. 276.
134 GB	J. Larras: MAXIMUM DEPTH OF EROSION IN SHIFTING BEDS AROUND RIVER PIERS, Annales des pots et chausses, Vol. 133, No. 4, pp411-424.
135 GB	H.W. Shen, V.R. Schneider and S. Karaki: LOCAL SCOUR AROUND BRIDGE PIERS, Journal of the Hydraulic Division, Proceedings of the American Society of Civil Engineers, Nov., 1969, HY 6, pp1919-1940.
136 GM	J.P. Morgan and W.C. McIntire: QUARTERNARY GEOLOGY OF THE BENGAL BASIN, EAST PAKISTAN AND INDIA, Bulletin of the Geological Society of America, 70, 1959.
137 GE	Centre for Urban Studies: Bangladesh Geographical Account.
	- (14) -

	.,		
•	138	GM	Masahiko Oya: CLASSIFICATION OF ALLUVIAL PLAINS BASED ON THE MORPHOLOGICAL CHARACTERISTICS, The Scientific Researches 20 School of Education, Waseda University, 1971.
· <sup>•</sup> .	139	GE	MOUNTAINS AND RIVERS OF INDIA, 21st International Geographical Congress, 1968.
•	140	GM	M.I. Showdhury: ON THE GRADUAL SHIFTING OF THE GANGES FROM WEST TO EAST IN DELTA BUILDING OPERATIONS, Proceed- ing of the Dacca Symposium, 1964.
	L\$L	GM	Masahiko Oya: COMPARATIVE STUDY OF THE GEOMORPHOLOGY AND FLOODING IN THE PLAINS OF THE CHO-SHUI-CHI, SHAO-PHYA, IRRAWADDY AND GENGES, Proceeding of the Dacca Symposium, 1964.
	142	GM	A.I.H. Rizve: COMPARATIVE PHYSIOGRAPHY OF THE LOWER GANGES AND LOWER MISSISSIPPI RIVER, Louisiana State University, 1955.
	143	CS	SURVEY REPORT ON UNIT PRICES FOR JAMUNA BRIDGE PROJECT, August 1975, Japan International Cooperation Agency (written in Japanese).

- (15) -

