

Table N-1 ESTIMATION OF WORKABLE DAYS

Item	(Unit: day)												Total	
	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.		
1. Monthly day	31	28	31	30	31	30	31	31	30	31	30	31	31	365
2. Frequency of rainfall ^{1/}														
0 - 10 mm	1	2	1	2	2	2	2	2	2	2	0	1	1	19
10 - 30 mm	1	1	2	3	4	2	4	4	5	7	2	1	1	36
30 - 50 mm	1	2	1	1	2	0	0	1	1	2	0	1	1	12
more than 50 mm	1	0	0	2	1	0	0	0	1	1	0	1	1	7
3. Time length to be suspended	6	5	3	10	9	1	2	4	8	11	1	6	6	66
4. Workable days	25	23	28	20	22	29	29	27	22	20	29	25	299	299

Remarks: ^{1/} Averaged data from 1979 to 1983 at Lacovia rainfall station.

Table N-2 SUMMARY OF INITIAL INVESTMENT COST

Item	(Unit: US\$10 ³)		
	Foreign Currency	Local Currency	Total
I. Construction Cost			
1.1 Direct Construction Cost			
Holland Area	2,460	1,570	4,030
Black River Left Bank Area	5,060	2,390	7,450
Broad River Right Bank Area	3,840	1,770	5,610
Broad River Left Bank Area	3,870	1,910	5,780
Office & Quarters	720	780	1,500
Observation Wells	50	20	70
Conservation of Environment	100	100	200
<u>Sub-total</u>	<u>16,100</u>	<u>8,540</u>	<u>24,640</u>
1.2 O & M Equipment	830	0	830
1.3 General Expense	0	650	650 ^{1/}
1.4 Land Acquisition	0	730	730
1.5 Engineering Service	2,930	1,110	4,040 ^{2/}
<u>Sub-total</u>	<u>19,860</u>	<u>11,030</u>	<u>30,840</u>
1.6 Physical Contingency	1,990	1,100	3,080
<u>Sub-total</u>	<u>21,850</u>	<u>12,130</u>	<u>33,980</u>
1.7 Price Contingency	4,370	5,090	9,460
<u>Sub-total</u>	<u>26,220</u>	<u>17,220</u>	<u>43,440</u>
II. Farm Guidance Service	<u>2,790</u>	<u>180</u>	<u>2,970</u>
III. Farm Machinery (see Annex G)	7,470	440	7,910
IV. Total (I + II)	36,480	17,840	54,320
V. Post Harvest Facility (see Annex G)	10,830	860	11,690
VI. Social Infrastructures (see Annex F)	-	5,610	5,610
VII. Grand Total (IV + V + VI)	47,310	24,310	71,620

Remarks: ^{1/}: Including environmental monitoring cost.

^{2/}: Including cost for investigation and computer model simulation analysis of post project ground water inflow.

Table N-3 ANNUAL DISBURSEMENT SCHEDULE

(Unit: US\$103)

Item	1st Year		2nd Year		3rd Year		4th Year		5th Year		6th Year		7th Year	
	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.
I. Construction														
1.1 Direct Construction Cost														
Holland Area	0	0	586	384	1,297	692	587	502	0	0	0	0	0	0
Black River Left Bank Area	0	0	999	340	2,259	901	1,414	854	390	290	0	0	0	0
Broad River Right Bank Area	0	0	0	0	1,007	346	1,249	546	973	450	610	429	0	0
Broad River Left Bank Area	0	0	0	0	829	232	1,293	605	1,039	500	708	569	0	0
Office & Quarters	0	0	720	780	0	0	0	0	0	0	0	0	0	0
Observation Wells	0	0	54	23	0	0	0	0	0	0	0	0	0	0
Conservation of Environment	0	0	20	20	20	20	20	20	20	20	20	20	0	0
Sub-total	0	0	2,379	1,547	5,402	2,181	4,563	2,527	2,422	1,260	1,338	1,018	0	0
1.2 O & M Equipment	0	0	0	0	0	0	430	0	0	0	400	0	0	0
1.3 General Expense	0	58	0	106	0	114	0	123	0	123	0	123	0	0
1.4 Land Acquisition	0	360	0	370	0	0	0	0	0	0	0	0	0	0
1.5 Engineering Services	580	220	470	180	470	180	470	180	470	180	470	172	0	0
Sub-total	580	638	2,849	2,203	5,872	2,475	5,463	2,830	2,892	1,563	2,208	1,313	0	0
1.6 Physical Contingency	58	64	285	220	587	248	546	283	289	156	221	131	0	0
Sub-total	638	702	3,134	2,423	6,459	2,723	6,009	3,113	3,181	1,719	2,429	1,444	0	0
1.7 Price Contingency	32	70	321	509	1,018	901	1,295	1,445	879	1,050	826	1,114	0	0
Sub-total	670	772	3,455	2,932	7,477	3,624	7,304	4,558	4,060	2,769	3,255	2,558	0	0
II. Farm Guidance Service	0	0	0	0	509	29	535	32	562	35	590	39	596	49
III. Farm Machinery	0	0	1,565	230	2,007	110	0	0	3,895	113	0	0	0	0
IV. Grand Total	670	772	5,020	3,152	9,993	3,763	7,839	4,590	8,517	2,917	3,845	2,598	596	49

Remarks: F.C.: Foreign Currency
L.C.: Local Currency

Table N-4 DIRECT CONSTRUCTION COST OF EACH AREA

(Unit: 10³US\$)

Work Item	Development Area												Total				
	Y.S. Intake System Holland Area				Black River Left Bank Area				Lacovia Pump Up System Broad River Right Bank Area				Broad River Left Bank Area		F.C.	L.C.	Total
	F.C.	L.C.	Total	F.C.	L.C.	Total	F.C.	L.C.	Total	F.C.	L.C.	Total	F.C.	L.C.			
															F.C.	L.C.	Total
1. Preparatory works	120	78	198	249	115	364	184	97	281	185	96	281	738	386	1,124		
2. Dike	369	50	419	323	50	373	178	23	201	213	26	239	1,083	149	1,232		
3. Drainage Pump Station	765	205	970	1,186	315	1,501	976	260	1,236	773	208	981	3,700	988	4,688		
4. Drainage Canal	54	38	92	1,090	164	1,254	667	68	735	738	82	820	2,549	352	2,901		
5. Catch Drain	-	-	-	-	-	-	67	37	104	174	73	247	241	110	351		
6. Intake Weir	30	60	90	-	-	-	-	-	-	-	-	-	30	60	90		
7. Irrigation Pump Station	-	-	-	256	74	330	260	75	335	260	75	335	776	224	1,000		
8. Irrigation Canal	271	529	800	376	596	972	231	318	549	208	449	657	1,086	1,892	2,978		
9. Farm Road	204	81	285	292	105	397	236	91	327	240	90	330	972	367	1,339		
10. On-Farm-Development	647	527	1,174	1,290	966	2,256	1,040	802	1,842	1,078	807	1,885	4,055	3,102	7,157		
11. Office & Quarters	-	-	-	-	-	-	-	-	-	-	-	-	720	780	1,500		
12. Observation Wells	-	-	-	-	-	-	-	-	-	-	-	-	54	33	87		
13. Conservation of Environment	-	-	-	-	-	-	-	-	-	-	-	-	100	100	200		
Total	2,460	1,568	4,028	5,062	2,385	7,447	3,839	1,771	5,610	3,809	1,906	5,775	16,104	8,543	24,647		

Remarks: F.C.: Foreign Currency
L.C.: Local Currency

Table N-5 BREAKDOWN OF DIRECT CONSTRUCTION
COST FOR THE HOLLAND AREA

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
1. Preparatory Works	L.S.		<u>120,000</u>	<u>78,000</u>		
2. Dike						
2.1 Black river right dike (1.9 km)			<u>77,000</u>	<u>12,000</u>		
Embankment (Clay)	m ³	47,000	26,000	2,500		
Excavation and embankment (Clay)	m ³	25,000	51,000	4,500		
Slope tamping	m ²	18,800	0	5,000		
2.2 Holland east dike (2.9 km)			<u>60,000</u>	<u>8,000</u>		
Excavation and embankment	m ³	29,000	60,000	5,000		
Slope tamping	m ²	10,500	0	3,000		
2.3 Holland west dike (2.4 km)			<u>17,000</u>	<u>3,000</u>		
Embankment (Clay)	m ³	3,900	2,000	200		
Excavation and embankment (Clay)	m ³	7,300	15,000	1,500		
Slope tamping	m ²	5,600	0	1,300		
2.4 Y.S. river bank (Improvement) (1.6 km)			<u>11,000</u>	<u>2,000</u>		
Excavation and embankment	m ³	5,400	11,000	1,000		
Slope tamping	m ²	2,900	0	1,000		
2.5 Black river short cut (0.5 km)						
Excavation and hauling	m ³	33,000	<u>201,000</u>	<u>19,000</u>		
2.6 Miscellaneous works	L.S.		<u>3,000</u>	<u>6,000</u>		
<u>Sub-total (2.1 - 2.6)</u>			<u>369,000</u>	<u>50,000</u>		
3. Drainage Pump Station						
Approach road	m	300	1,500	500		
Excavation	m ³	1,200	1,500	1,000		
Backfill	m ³	300	500	500		
Reinforced concrete	m ³	360	16,000	29,000		
Plain concrete	m ³	50	500	3,000		
Form and scaffoldings	L.S.		500	12,500		
Pump control house	m ²	60	0	30,000		
Related facilities	L.S.		1,000	200		
Pump equipment (Ø800)	set	3	742,000	128,000		
Miscellaneous works	L.S.		1,500	300		
<u>Sub-total</u>			<u>765,000</u>	<u>205,000</u>		
4. Drainage Canal (8.9 km)						
Excavation, peat soil	m ³	30,000	53,000	5,000		
Slope tamping	m ³	28,000	0	7,000		
Drainage culvert Type I	nos.	1	100	4,000		
Drainage culvert Type III	nos.	6	400	21,000		
Miscellaneous	L.S.		500	1,000		
<u>Sub-total</u>			<u>54,000</u>	<u>38,000</u>		

- to be continued -

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
5. Intake Weir						
Excavation	m ³	1,900	2,500	400		
Embankment	m ³	100	100	100		
Gabion	m ³	740	3,700	6,000		
Demolition of existing weir	m ³	80	0	4,500		
Reinforcement concrete	m ³	450	21,000	41,500		
Metal works	kg	3,000	1,800	2,300		
Miscellaneous works	L.S.		900	5,200		
<u>Sub-total</u>			<u>30,000</u>	<u>60,000</u>		
6. Irrigation Canal						
6.1 Holland main canal (3.2 km)			<u>45,000</u>	<u>147,000</u>		
Excavation	m ³	1,000	1,000	100		
Embankment	m ³	18,700	16,000	1,000		
Slope tamping	m ²	16,000	0	4,000		
Concrete lining	m ³	1,600	20,000	99,000		
Sod facing	m ²	6,300	0	12,000		
Related structures						
- Turnout	nos.	3	1,000	2,000		
- Culvert	nos.	7	3,000	14,000		
- Checkgate	nos.	2	1,000	8,000		
- Spillway	nos.	2	500	4,000		
- Cross drain	nos.	5	100	500		
Miscellaneous works	L.S.		2,400	2,400		
6.2 Secondary and sub-secondary canal (11.1 km)			<u>226,000</u>	<u>382,000</u>		
Excavation	m ³	3,500	4,000	500		
Embankment	m ³	30,900	27,000	2,000		
Embankment (Dump truck 500 m)	m ³	30,800	125,000	13,000		
Slope tamping	m ²	30,000	0	8,000		
Concrete lining	m ³	3,000	37,000	183,000		
Sod facing	m ²	43,000	0	81,000		
Related structures						
- Turnout	nos.	11	10,000	17,000		
- Culvert	nos.	37	12,000	58,000		
- Spillway	nos.	4	1,000	7,000		
- Checkgate	nos.	7	1,000	1,500		
- Drop	nos.	5	1,000	4,000		
Miscellaneous works	L.S.		8,000	7,000		
<u>Sub-total (6.1 and 6.2)</u>			<u>271,000</u>	<u>529,000</u>		
7. Farm Road						
7.1 Main farm road (9.0 km)			<u>85,000</u>	<u>34,000</u>		
Pavement	m ³	16,000	78,000	32,000		
Excavation (Clay)	m ³	3,900	3,000	300		
Embankment (Clay)	m ³	3,900	3,000	100		
Slope tamping	m ²	1,600	0	400		
Miscellaneous works	L.S.		1,000	1,200		

- to be continued -

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
7.2 Secondary farm road (19.4 km)			<u>119,000</u>	<u>47,000</u>		
Pavement	m ³	19,000	92,000	38,000		
Embankment (Peat)	m ³	2,800	2,500	300		
Embankment (Clay)	m ³	15,000	13,000	1,000		
Excavation (Clay)	m ³	9,100	6,500	200		
Slope tamping	m ²	13,000	0	3,000		
Road passing	nos.	1	500	3,000		
Miscellaneous works	L.S.		4,500	1,500		
Sub-total (7.1 and 7.2)			<u>204,000</u>	<u>81,000</u>		
8. Land Reclamation (560 ha)						
8.1 Irrigation facilities			<u>76,000</u>	<u>237,000</u>		
Soil cement	m ³	3,600	50,000	122,000		
Excavation	m ³	7,400	0	45,000		
Embankment	m ³	18,700	13,000	1,000		
Slope tamping	m ²	183,000	0	5,000		
Related structure						
- Culvert	nos.	28	4,000	25,000		
- Division box	nos.	140	12,000	39,000		
8.2 Drainage facilities			<u>131,000</u>	<u>60,000</u>		
Excavation	m ³	7,300	9,000	1,000		
Slope tamping	m ²	16,000	0	4,000		
Farm drain	km	120	115,000	7,000		
Culvert	nos.	28	7,000	48,000		
8.3 Farm road			<u>128,000</u>	<u>84,000</u>		
Embankment	m ³	51,000	36,000	1,700		
Slope tamping	m ²	61,000	0	16,000		
Marl pavement	m ³	17,000	82,200	34,000		
Tractor passage (with Flume)	nos.	140	9,500	32,000		
Tractor passage	nos.	420	300	300		
8.4 Land grading			<u>802,000</u>	<u>140,000</u>		
Land clearing (Pasture)	ha	280	0	102,000		
Land grading (Clay)	m ³	134,000	124,000	5,000		
Ripping	ha	560	178,000	8,000		
Levee	ha	560	0	25,000		
8.5 Miscellaneous works	L.S.		<u>10,000</u>	<u>6,000</u>		
Sub-total (8.1 - 8.5)			<u>647,000</u>	<u>527,000</u>		
Total			<u>2,460,000</u>	<u>1,568,000</u>		

Table N-6 BREAKDOWN OF DIRECT CONSTRUCTION COST
FOR THE BLACK RIVER LEFT BANK AREA

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
1. Preparatory Works	L.S.		249,000	115,000		
2. Dike (8.7 km)						
Excavation and embankment (Clay)	m ³	117,000	230,000	21,000		
Embankment (Clay)	m ³	70,000	40,000	3,000		
Embankment (Peat)	m ³	46,000	40,000	3,000		
Sodding	m ²	61,800	0	16,000		
Miscellaneous works	L.S.		13,000	8,000		
<u>Sub-total</u>			<u>323,000</u>	<u>50,000</u>		
3. Drainage Pump Station						
Approach road	m	1,000	5,000	2,000		
Excavation	m ³	2,000	1,500	500		
Backfill	m ³	350	500	500		
Reinforced concrete	m ³	500	24,000	42,500		
Plain concrete	m ³	100	1,000	4,000		
Form and scaffoldings	L.S.		1,000	20,000		
Pump control house	m ²	60	0	30,000		
Related facilities	L.S.		1,500	500		
Pump equipment (ø800)	set	5	1,150,000	214,000		
Miscellaneous works	L.S.		1,500	1,000		
<u>Sub-total</u>			<u>1,186,000</u>	<u>315,000</u>		
4. Drainage Canal (13.6 km)						
Excavation (Clay)	m ³	104,000	181,000	16,000		
Excavation (Peat)	m ³	193,000	890,000	50,000		
Excavation (Limestone)	m ³	1,350	2,000	100		
Sodding (Clay)	m ²	75,000	0	19,000		
Sodding (Peat)	m ²	118,000	0	30,000		
Drainage culvert Type I	nos.	2	200	15,000		
Drainage culvert Type II	nos.	1	100	5,000		
Drainage culvert Type III	nos.	6	400	26,000		
Miscellaneous works	L.S.		16,300	2,900		
<u>Sub-total</u>			<u>1,090,000</u>	<u>164,000</u>		

- to be continued -

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
5. Lacovia Irrigation Pump Station						
Approach road	m	500	2,500	1,000		
Excavation	m ³	2,100	2,300	1,400		
Backfill	m ³	400	400	200		
Reinforced concrete	m ³	500	23,000	40,000		
Plain concrete	m ³	100	600	3,000		
Form and scaffoldings	L.S.		800	18,000		
Pump control house	m ²	60	1,400	31,000		
Related facilities	L.S.		800	300		
Pump equipment (ø700)	set	4	743,000	128,000		
Miscellaneous works	L.S.		1,200	1,100		
Sub-total			776,000	224,000		
<u>Allocation for Black River Left Bank Area</u>			<u>256,000</u>	<u>74,000</u>		
Allocation for Broad River Right Bank Area			260,000	75,000		
Allocation for Broad River Left Bank Area			260,000	75,000		
6. Irrigation Canal						
6.1 Slipe main canal (5.2 km)						
Excavation	m ³	18,000	21,000	1,000		
Embankment (with Backhoe)	m ³	10,000	21,000	1,000		
Embankment (Dump Truck 2,000 m)	m ³	49,000	228,000	26,000		
Slope tamping	m ²	29,000	0	7,000		
Concrete lining	m ³	3,000	36,000	180,000		
Sod facing	m ²	23,000	0	44,000		
Related structures						
- Turnout	nos.	16	13,000	21,000		
- Culvert	nos.	6	4,000	21,000		
- Checkgate	nos.	6	23,000	21,000		
- Spillway	nos.	5	1,000	9,000		
- Drop	nos.	1	500	1,000		
Miscellaneous works	L.S.		7,500	5,000		
Total			355,000	337,000		
<u>Allocation for Black River Left Bank Area</u>			<u>214,000</u>	<u>203,000</u>		
Allocation for Broad River Right Bank Area			141,000	134,000		
6.2 Secondary and sub-secondary canal (12.3 km)			162,000	393,000		
Excavation	m ³	8,000	10,000	1,000		
Embankment (with Backhoe)	m ³	36,000	76,000	5,000		
Slope tamping	m ²	36,000	0	9,000		
Concrete lining	m ³	4,000	44,000	223,000		
Sod facing	m ²	30,000	0	56,000		
Related structures						
- Turnout	nos.	25	16,000	43,000		
- Culvert	nos.	12	7,000	35,000		
- Spillway	nos.	5	1,000	9,000		
- Checkgate	nos.	13	1,000	2,000		
- Drop	nos.	3	1,000	3,000		
Miscellaneous works	L.S.		6,000	7,000		
<u>Sub-total (6.1 and 6.2)</u>			<u>376,000</u>	<u>596,000</u>		

- to be continued -

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
7.	Farm Road					
7.1	Main farm road (7.1 km)					
	Pavement	m ³	13,000	97,000	34,000	
	Embankment (Clay)	m ³	31,000	63,000	26,000	
	Slope tamping	m ²	13,000	27,000	2,000	
	Miscellaneous works	L.S.		0	3,500	
				6,000	2,500	
7.2	Secondary farm road (26.5 km)					
	Pavement	m ³	27,000	195,000	71,000	
	Embankment (Peat)	m ³	16,000	131,000	54,000	
	Embankment (Clay)	m ³	47,000	13,500	1,500	
	Slope tamping	m ²	35,000	41,500	3,000	
	Miscellaneous works	L.S.		0	9,000	
				9,000	3,500	
	Sub-total (7.1 and 7.2)			292,000	105,000	
8.	Land Reclamation (920 ha)					
8.1	Irrigation facilities					
	Soil cement	m ³	6,500	116,000	509,000	
	Excavation	m ³	8,800	70,000	217,000	
	Embankment	m ³	27,500	0	54,000	
	Slope tamping	m ²	43,500	19,500	1,500	
	Related structure			0	11,400	
	- Culvert	nos.	46	8,000	57,500	
	- Division box	nos.	230	18,500	167,600	
8.2	Drainage facilities					
	Excavation	m ³	12,000	316,000	105,000	
	Slope tamping	m ²	26,000	22,000	2,000	
	Farm drain	km	200	0	7,000	
	Culvert	nos.	46	283,000	24,000	
				11,000	72,000	
8.3	Farm road					
	Embankment	m ³	192,000	249,000	123,000	
	Slope tamping	m ²	100,000	130,000	10,000	
	Marl pavement	m ³	24,000	0	26,000	
	Tractor passage (with Flume)	nos.	165	117,300	48,500	
	Tractor passage	nos.	570	1,200	38,300	
				500	200	
8.4	Land grading					
	Land clearing - Grass -	ha	460	584,000	213,000	
	Land grading	m ³	190,000	0	143,000	
	Ripping	ha	920	217,000	13,000	
	Levee	ha	920	367,000	16,000	
				0	41,000	
8.5	Miscellaneous works					
		L.S.		16,000	16,000	
	Sub-total (8.1 - 8.5)			1,290,000	966,000	
Total				5,062,000	2,385,000	

Table N-7 BREAKDOWN OF DIRECT CONSTRUCTION COST
FOR THE BROAD RIVER RIGHT BANK AREA

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
1. Preparatory Works	L.S.		184,000	97,000		
2. Dike (5.5 km)						
Excavation and embankment (Peat)	m ³	27,000	128,000	8,000		
Embankment (Peat)	m ³	55,000	48,000	4,000		
Sodding	m ²	20,000	0	5,000		
Miscellaneous works	L.S.		2,000	6,000		
Sub-total			178,000	23,000		
3. Drainage Pump Station						
Approach road	m	200	1,000	400		
Excavation	m ³	1,400	4,000	2,800		
Backfill	m ³	300	300	200		
Reinforced concrete	m ³	450	20,000	35,000		
Plain concrete	m ³	50	600	3,000		
Form and scaffoldings	L.S.		500	16,000		
Pump control house	m ²	60	0	30,000		
Related facilities	L.S.		700	700		
Pump equipment (ø800)	set	4	948,000	171,000		
Miscellaneous works	L.S.		900	900		
Sub-total			976,000	260,000		
4. Drainage Canal (7.0 km)						
Excavation (Peat)	m ³	142,000	655,000	57,000		
Drainage culvert Type III	nos.	2	200	10,500		
Miscellaneous	L.S.		11,800	500		
Sub-total			667,000	68,000		
5. Catch Drain (4.0 km)						
Excavation	m ³	42,000	51,700	3,000		
Embankment	m ³	8,000	4,500	500		
Ripping	m ²	4,200	7,300	300		
Related structures						
- Culvert Type I	nos.	2	400	12,000		
- Culvert Type II	nos.	1	200	3,500		
- Drain culvert Type I	nos.	1	2,000	16,500		
Miscellaneous works	L.S.		900	1,200		
Sub-total			67,000	37,000		
6. Lacovia Irrigation Pump Station			260,000	75,000		

- to be continued -

(Unit: US\$)				
Item	Unit	Q'ty	Foreign Currency	Local Currency
7. Irrigation Canal				
7.1 Mountainside main canal (8.8 km)				
Excavation	m ³	10,000	13,000	900
Embankment	m ³	34,000	30,000	2,000
Embankment (Dump truck 1,000 m)	m ³	18,000	77,000	8,000
Slope tamping	m ²	42,000	0	11,000
Concrete lining	m ³	4,000	52,000	260,000
Sod facing	m ²	24,000	0	44,000
Related structures				
- Turnout	nos.	13	8,000	13,000
- Culvert	nos.	6	4,000	27,000
- Checkgate	nos.	6	22,000	20,000
- Spillway	nos.	2	500	4,000
- Cross drain	nos.	3	700	4,000
Miscellaneous works	L.S.		7,800	7,100
Total			215,000	401,000
Allocation for Broad River Right Bank Area			43,000	80,000
Allocation for Broad River Left Bank Area			172,000	321,000
7.2 Slupe main canal (5.2 km)			141,000	134,000
7.3 Secondary and sub-secondary canal (3.1 km)			47,000	104,000
Excavation	m ³	300	500	100
Embankment (Backhoe)	m ³	12,000	25,000	1,000
Slope tamping	m ²	10,000	0	2,000
Concrete lining	m ³	1,000	12,000	62,000
Sod facing	m ²	9,000	0	18,000
Related structures				
- Turnout	nos.	8	5,000	8,000
- Culvert	nos.	4	1,000	6,000
- Spillway	nos.	2	1,000	4,000
- Checkgate	nos.	2	500	500
Miscellaneous works	L.S.		2,000	2,400
Sub-total (7.1 - 7.3)			231,000	318,000
8. Farm Road				
8.1 Main farm road (8.7 km)			118,000	46,000
Pavement	m ³	19,000	92,000	38,000
Embankment, peat	m ³	8,700	7,500	1,000
Embankment, clay	m ³	17,000	15,000	1,000
Slope tamping	m ²	18,000	0	4,500
Miscellaneous works	L.S.		3,500	1,500

- to be continued -

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
8.2	Secondary farm road (16.5 km)		<u>118,000</u>	<u>45,000</u>		
	Pavement	m ³ 17,000	83,000	34,000		
	Embankment (Peat)	m ³ 7,500	6,000	1,000		
	Embankment (Clay)	m ³ 27,000	24,000	2,000		
	Slope tamping	m ² 25,000	0	6,500		
	Miscellaneous works	L.S.	5,000	1,500		
	<u>Sub-total (8.1 and 8.2)</u>		<u>236,000</u>	<u>91,000</u>		
9.	Land Reclamation (800 ha)					
9.1	Irrigation facilities		<u>89,000</u>	<u>482,000</u>		
	Soil cement	m ³ 5,900	50,000	198,000		
	Excavation	m ³ 7,100	0	44,000		
	Embankment	m ³ 24,000	16,000	1,000		
	Slope tamping	m ² 42,000	0	11,000		
	Related structure					
	- Culvert	nos. 40	8,000	54,000		
	- Division box	nos. 200	15,000	174,000		
9.2	Drainage facilities		<u>302,000</u>	<u>100,000</u>		
	Excavation	m ³ 10,000	20,000	2,000		
	Slope tamping	m ² 23,000	0	6,000		
	Farm drain	km 168	272,000	24,000		
	Culvert	nos. 40	10,000	68,000		
9.3	Farm road		<u>215,000</u>	<u>73,000</u>		
	Embankment	m ³ 174,000	117,600	10,000		
	Slope tamping	m ² 87,000	0	22,900		
	Marl pavement	m ³ 20,000	97,000	40,000		
	Tractor passage	nos. 400	400	100		
9.4	Land grading		<u>415,000</u>	<u>134,000</u>		
	Land clearing - Grass -	ha 800	0	79,000		
	Land grading (Peat)	m ³ 65,000	78,000	6,000		
	Ripping	ha 800	337,000	14,000		
	Levee	ha 800	0	35,000		
9.5	Miscellaneous works		<u>19,000</u>	<u>13,000</u>		
	<u>Sub-total (9.1 - 9.5)</u>		<u>1,040,000</u>	<u>802,000</u>		
<u>Total</u>			<u>3,839,000</u>	<u>1,771,000</u>		

Table N-8 BREAKDOWN OF DIRECT CONSTRUCTION COST
FOR THE BROAD RIVER LEFT BANK AREA

					(Unit: US\$)	
Item	Unit	Q'ty	Foreign Currency	Local Currency		
1. Preparatory Works	L.S.		185,000	96,000		
2. Dike (5.7 km)						
Excavation and embankment (Peat)	m ³	35,000	168,000	10,000		
Embankment (Peat)	m ³	49,000	43,000	4,000		
Sodding	m ²	20,000	0	5,000		
Miscellaneous works	L.S.		2,000	7,000		
<u>Sub-total</u>			<u>213,000</u>	<u>26,000</u>		
3. Drainage Pump Station						
Approach road	m	1,400	7,000	3,000		
Excavation	m ³	1,200	4,000	2,000		
Backfill	m ³	300	300	200		
Reinforced concrete	m ³	360	17,000	29,000		
Plain concrete	m ³	40	500	2,000		
Form and scaffoldings	L.S.		500	12,000		
Pump control house	m ²	60	0	30,000		
Related facilities	L.S.		1,500	1,000		
Pump equipment (ø800)	set	3	741,000	128,000		
Miscellaneous works	L.S.		1,200	800		
<u>Sub-total</u>			<u>773,000</u>	<u>208,000</u>		
4. Drainage Canal (8.2 km)						
Excavation (Peat)	m ³	158,000	730,000	65,000		
Drainage culvert Type I	nos.	1	100	7,000		
Drainage culvert Type III	nos.	2	100	9,000		
Miscellaneous	L.S.		7,800	1,000		
<u>Sub-total</u>			<u>738,000</u>	<u>82,000</u>		
5. Catch Drain (13.0 km)						
Excavation	m ³	105,400	130,000	7,000		
Embankment	m ³	38,000	21,000	2,000		
Ripping	m ²	10,500	18,000	1,000		
Related structures						
- Culvert Type I	nos.	5	1,000	30,000		
- Culvert Type II	nos.	4	500	13,500		
- Drainage culvert Type I	nos.	1	2,000	17,000		
Miscellaneous works	L.S.		1,500	2,500		
<u>Sub-total</u>			<u>174,000</u>	<u>73,000</u>		
6. Lacovia Irrigation Pump Station			260,000	75,000		

- to be continued -

					(Unit: US\$)		
Item	Unit	Q'ty	Foreign Currency	Local Currency			
7.	Irrigation Canal						
7.1	Mountainside main canal (8.8 km)				<u>172,000</u>	<u>321,000</u>	
7.2	Secondary and sub-secondary canal (5.05 km)				<u>36,000</u>	<u>128,000</u>	
	Excavation	m ³	3,500	4,000	200		
	Embankment	m ³	8,000	7,000	500		
	Slope tamping	m ²	15,000	0	4,000		
	Concrete lining	m ³	1,500	18,000	93,000		
	Sod facing	m ²	8,000	0	15,000		
	Related structures						
	- Turnout	nos.	3	2,000	3,000		
	- Culvert	nos.	4	1,000	6,000		
	- Spillway	nos.	1	200	2,000		
	- Checkgate	nos.	2	100	300		
	- Cross drain	nos.	1	200	2,000		
	Miscellaneous works	L.S.		3,500	2,000		
	<u>Sub-total (7.1 and 7.2)</u>				<u>208,000</u>	<u>449,000</u>	
8.	Farm Road						
8.1	Main farm road (9.7 km)				<u>129,000</u>	<u>45,000</u>	
	Pavement	m ³	17,500	85,000	35,000		
	Embankment (Peat)	m ³	4,500	4,000	500		
	Embankment (Clay)	m ³	38,000	33,000	2,000		
	Slope tamping	m ²	18,000	0	5,000		
	Miscellaneous works	L.S.		7,000	2,500		
8.2	Secondary farm road (17.3 km)				<u>111,000</u>	<u>45,000</u>	
	Pavement	m ³	17,300	84,000	34,000		
	Embankment (Peat)	m ³	7,600	6,000	1,000		
	Embankment (Clay)	m ³	17,400	15,000	1,000		
	Slope tamping	m ²	25,000	0	7,000		
	Miscellaneous works	L.S.		6,000	2,000		
	<u>Sub-total (8.1 and 8.2)</u>				<u>240,000</u>	<u>90,000</u>	
9.	Land Reclamation (800 ha)						
9.1	Irrigation facilities				<u>98,000</u>	<u>482,000</u>	
	Soil cement	m ³	5,900	59,000	198,000		
	Excavation	m ³	7,100	0	44,000		
	Embankment	m ³	24,000	16,000	1,000		
	Slope tamping	m ²	42,000	0	11,000		
	Related structure						
	- Culvert	nos.	40	8,000	54,000		
	- Division box	nos.	200	15,000	174,000		
9.2	Drainage facilities				<u>302,000</u>	<u>100,000</u>	
	Excavation	m ³	10,000	20,000	2,000		
	Slope tamping	m ²	23,000	0	6,000		
	Farm drain	km	168	272,000	24,000		
	Culvert	nos.	40	10,000	68,000		

- to be continued -

(Unit: US\$)				
Item	Unit	Q'ty	Foreign Currency	Local Currency
9.3 Farm road				
Embankment	m ³	174,000	215,000	73,000
Slope tamping	m ²	87,000	117,000	9,900
Marl pavement	m ³	20,000	0	23,000
Tractor passage	nos.	400	97,600	40,000
			400	100
9.4 Land grading			452,000	139,000
Land clearing - Grass -	ha	800	0	79,000
Land grading (Peat)	m ³	96,000	115,000	10,000
Ripping	ha	800	337,000	14,000
Levee	ha	800	0	36,000
9.5 Miscellaneous works	L.S.		11,000	13,000
<u>Sub-total (9.1 - 9.5)</u>			<u>1,078,000</u>	<u>807,000</u>
<u>Total</u>			<u>3,869,000</u>	<u>1,906,000</u>

Table N-9 BREAKDOWN OF DIRECT CONSTRUCTION
COST OF OFFICE AND QUARTERS

(Unit: US\$)					
Item	Unit	Q'ty	Foreign Currency	Local Currency	Total
1. Main office	m ²	400	100,000	76,000	176,000
2. Branch office (90m ² x4)	m ²	360	96,000	62,000	158,000
3. Workshop	m ²	100	24,000	20,000	44,000
4. Quarters	m ²	2,000	480,000	400,000	880,000
5. Motor pool	m ²	5,000	0	75,000	75,000
6. Land reparation for office yard including fencing, etc.	L.S.		20,000	147,000	167,000
Total			720,000	780,000	1,500,000

Table N-10 PROCUREMENT COST OF MAJOR OPERATION
AND MAINTENANCE EQUIPMENT

(Unit: US\$)

Equipment	Q'ty	Unit Price	Total
1. Tractor shovel 1.0 m ³	1	60,000	60,000
2. Swamp type bulldozer 13 t	2	95,000	190,000
3. Swamp type backhoe 0.4 m ³	2	100,000	200,000
4. Dump truck 8 t	1	30,000	30,000
5. Truck 4 t	2	15,000	30,000
6. Light truck 4 wheel drive 1 t	4	12,000	48,000
7. Passenger car 4-wheel drive	8	12,000	96,000
8. Motor cycle 90 cc	8	850	6,800
9. Slope compactor 3 PS	1	5,500	5,500
10. Concrete mixer 7 PS	2	3,500	7,000
11. Pump with engine 7 PS	4	2,000	8,000
Sub-total			681,300
Workshop equipment and miscellaneous			10,700
Spare parts (20%)			138,000
Total			830,000

Table N-11 GENERAL EXPENSES
(Construction Stage)

(Unit: US\$)

Year	Staff ^{1/} Salary	Labour Wage	Office Expenses	Fuel Cost for Passenger Car	Other Related Cost	Total
1	54,000	-	2,000	1,000	1,000	58,000
2	85,200	9,600	5,400	2,000	4,000	106,200
3	86,400	9,600	10,800	3,000	4,400	114,200
4	92,400	9,600	10,800	3,000	7,000	122,800
5	92,400	9,600	10,800	3,000	7,000	122,800
6	92,400	9,600	10,800	3,000	7,200	123,000
Total	502,800	48,000	50,600	15,000	30,600	647,000

Remarks: ^{1/}: Refer to Table N-12.

Table N-12 STAFF SALARY FOR THE PROJECT OFFICE
(Construction Stage)

(Unit: US\$)

Year	Director		Engineer		Assistant Engineer		Administrator		Equipment Procurement Office		Clerical Staff		Total	
	No.	Salary	No.	Salary	No.	Salary	No.	Salary	No.	Salary	No.	Salary	No.	Salary
1	1	18,000	2	24,000	1	12,000	-	-	-	-	-	-	3	54,000
2	1	18,000	2	24,000	2	7,200	1	12,000	1	12,000	2	12,000	8	85,200
3	-	-	3	86,000	4	14,400	1	12,000	1	12,000	2	12,000	10	86,000
4	-	-	3	36,000	4	14,400	1	12,000	1	12,000	3	18,000	11	92,400
5	-	-	3	36,000	4	14,400	1	12,000	1	12,000	3	18,000	11	92,400
6	-	-	3	36,000	4	14,400	1	12,000	1	12,000	3	18,000	11	92,400
Total		36,000		192,000		76,800		60,000		60,000		78,000		502,800

Remarks: Since the farm operation will commence from the fall cultivation in third year, the organization for O&M is to be established in the second year. The director is also responsible to manage the O&M. His salary would be covered by O&M cost since second year (Table N-16).

Table N-13 PRICE LIST OF BASIC MATERIALS
AND LABOUR WAGES

			(Unit: J\$)
Item	Unit	Unit Price	
A. Materials			
1. Ordinary portland cement	ton	550.0	
2. Reinforcement bar	ton	2,250.0	
3. Course aggregate	m ³	48.8	
4. Fine aggregate	m ³	42.0	
5. Marl	m ³	15.7	
6. Light diesel oil	ℓ	1.58	
B. Labour			
1. Common labour	man-day	23.0	
2. Carpenter	man-day	31.3	
3. Mason	man-day	29.2	
4. Operator	man-day	42.1	
5. Driver	man-day	41.5	
6. Steel fixer/bender	man-day	31.3	
7. Foreman	man-day	60.0	

Table N-14 LIST OF UNIT PRICE FOR MAJOR WORK ITEMS

(Unit: US\$)

Work Items	Unit	Foreign Currency	Local Currency	Total
1. Stripping including site clearing	m ²	0.06	0.02	0.08
2. Excavation				
- Hard limestone by pick hammer	m ³	7.65	5.73	13.38
- Decomposed limestone	m ³	1.72	0.10	1.82
- Inundated peat	m ³	4.61	0.26	4.87
- Soft clayey soil	m ³	1.74	0.15	1.89
- Clayey soil	m ³	1.23	0.07	1.30
3. Embankment				
- Peat	m ³	0.87	0.07	0.94
- Clayey soil	m ³	0.56	0.05	0.61
- Clayey soil including hawling L= 1.0km	m ³	4.26	0.46	4.72
4. Backfill	m ³	0.98	0.06	1.04
5. Sod facing	m ²	-	1.91	1.91
6. Land clearing				
- Grass	ha	-	363	363
- Forest	ha	810	470	1,280
7. Land leveling L= 10m	m ³	0.67	0.06	0.73
8. Concrete works				
- Reinforced concrete 1:2:4	m ³	46.88	82.02	128.90
- Plain concrete 1:3:6	m ³	12.29	60.00	72.29
- Leveling concrete 1:4:8	m ³	12.49	51.30	63.79
- Lining concrete 1:3:6	m ³	12.29	62.01	74.73
- Soil cement, cement 100 kg/m ³	m ³	10.00	33.50	43.50
9. Form works for concrete	m ²	-	11.10	11.10
10. Metal works	kg	0.59	0.78	1.37
11. Concrete pipe				
- Ø300	m	-	27.31	27.31
- Ø600	m	-	48.96	48.96
12. Marl pavement	m ³	4.86	2.00	6.86
13. Ripping for deep tillage				
- Clayey soil	ha	319	13.50	332.50
- Peat	ha	421.50	17.84	438.89
14. Gravel foundation	m ³	4.15	13.77	17.92
15. Slope tamping	m ²	-	0.26	0.26

Table N-15 ANNUAL OPERATION AND MAINTENANCE COST

		(Unit: 10 ³ US\$)
Item		Amount
1. Salary and wages		
(1) Staff salaries (see Table N-16)		298
(2) Labour wages		188
2. Office expenses	L.S.	59
3. O & M for pump stations		
(1) Lacovia pump station	L.S.	70
(2) Four drainage pump stations	L.S.	225
4. Repair and maintenance cost		
(1) Cutting grass and repair of embankment	L.S.	69
(2) Repair of lining concrete	L.S.	26
(3) Repair of soil cement lining	L.S.	44
(4) Repair of road pavement	L.S.	38
(5) Others	L.S.	18
5. Miscellaneous		65
Total		1,100


Table N-16 ANNUAL STAFF SALARY AT O & M STAGE

Item	Required Number	Monthly Rate (US\$)	Annual Amount (US\$)
A. Management Department Director			
Director	1	1,500	18,000
Secretary	2	500	12,000
B. Technical Department			
Manager	1	1,000	12,000
i) Irrigation & drainage unit			
Irrigation engineer	1	1,000	12,000
Civil engineer	1	1,000	12,000
Mechanical engineer	1	1,000	12,000
Assistant engineer	6	500	36,000
Clerical staff	3	500	18,000
ii) Pilot farm unit			
Research officer	1	1,000	12,000
Clerical staff	1	500	6,000
iii) Settlement unit			
Officer	1	1,000	12,000
Extension officer	7	800	67,200
Clerical staff	2	500	12,000
C. Administration Department			
Finance officer	2	800	19,200
Personnel	3	800	28,800
Land management	1	800	9,600
Total			298,800 (298,000)

Remarks: The salary of drivers and operators is included in the labour wages in Table N-15.

Table N-17 REPLACEMENT COST AND USEFUL LIFE


Item	Useful Life (year)	Replacement Cost (US\$)
1. O & M Equipment (see Table N-10)		
(1) Heavy equipment	10	510,000
(2) Vehicles and small equipment	5	320,000
2. Project Facilities		
(1) Irrigation and drainage pump	20	5,031,000
(2) Gates for irrigation and drainage facilities	20	26,000




BLACK RIVER LOWER MORASS
AGRICULTURAL DEVELOPMENT PROJECT

Fig. N-1
PROJECT IMPLEMENTATION SCHEDULE

JAPAN INTERNATIONAL COOPERATION AGENCY





ANNEX O

PROJECT EVALUATION



ANNEX O

PROJECT EVALUATION

TABLE OF CONTENTS

	<u>Page</u>
1. GENERAL	O- 1
2. ECONOMIC EVALUATION	O- 1
2.1 Irrigation and Drainage Benefits	O- 1
2.2 Economic Cost	O- 2
2.3 Economic Evaluation	O- 2
2.3.1 Economic internal rate of return (EIRR)	O- 2
2.3.2 Sensitivity analysis	O- 3
3. FINANCIAL EVALUATION	O- 4
3.1 General	O- 4
3.2 Financial Cost	O- 4
3.3 Capacity to Pay	O- 4
3.4 Water Charge	O- 5
3.5 Repayment Capability of the Farm Development Company	O- 5
3.6 Repayment of the Project Cost	O- 6
4. SOCIO-ECONOMIC IMPACTS	O- 7

LIST OF TABLES

	<u>Page</u>
Table O-1 ECONOMIC BENEFITS FLOW	O- 9
Table O-2 ANNUAL ECONOMIC COSTS AND BENEFIT FLOW	O-10
Table O-3 FARM BUDGET ANALYSIS	O-11
Table O-4 CASH FLOW STATEMENT OF THE FARM DEVELOPMENT COMPANY	O-12
Table O-5 CASH FLOW STATEMENT OF THE PROJECT	O-13

ANNEX O

PROJECT EVALUATION

1. GENERAL

The economic feasibility of the Black River Lower Morass Agricultural Development Project was assessed through the economic internal rate of return (EIRR). The sensitivity analysis was made assuming changes in accrued benefits, built-up and project cost. Then the financial evaluation was carried out by following two ways; farm budget analysis to assess the net reserve of the settlement farm both on mineral and peat soils and the analysis of financial projections of the Farm Development Company and of the Project as a whole to evaluate their repayment capacity on the basis of the estimated fund requirement with assumed terms of the anticipated loan and the expected revenue from the Project. The socio-economic and environmental impacts from the implementation of the Project and their effects on the regional development were also studied.

2. ECONOMIC EVALUATION

2.1 Irrigation and Drainage Benefits

The irrigation and drainage benefits of the Black River Lower Morass Agricultural Project will primarily accrue from the increased crop production due to stable irrigation water supply and drainage. These benefits were estimated as the difference between the annual net production values under the present conditions projected into the future, as against those of the proposed development. Gradually, not only will the acreage be increased but productivity as well. Construction work for the whole project area will be completed in 1990. The full development stage will be attained in 1997 making allowance for a phased agricultural development during construction. The economic gross direct benefits will amount to about J\$33.7 million (US\$8.2 million) per annum at full development.

The economic net direct benefit amounted to about J\$33.3 million (US\$8.1 million) per annum at the full development stage of 3,080 ha.

According to the proposed construction plan, the benefits will begin to accrue in 1987 with completion of the Y.S. intake weir and canals, and will gradually increase as more lands become available. The Project will reach maximum paddy production 7 years after completion of the construction works. The incremental benefits were also considered, as they will accrue annually during the development period, as shown in Table O-1.

2.2 Economic Cost

The financial costs for construction works, replacement of certain equipment, and operation and maintenance of the Project were estimated at 1984 price levels as given in Annex N. The economic cost of the Project was obtained by deducting transfer payments from the financial costs. Price contingencies are not included in the economic cost nor the costs of land acquisition and farm guidance service. And also the shadow exchange rate (SER) of 1.02 is applied to the economic costs.

The total economic cost of the Project was estimated to be J\$136.0 million (US\$33.3 million), consisting of J\$89.6 million (US\$21.9 million) of foreign currency component and J\$46.4 million (US\$11.4 million) of local currency component.

It was assumed that the engineering work for the Project would commence at the beginning of 1985 and be completed by the end of 1990; whole project works would be implemented within 6 years. According to the construction schedule proposed in Annex N and the work quantities, the flow of the project costs, operation and maintenance cost, and replacement costs were estimated as shown in Table O-2.

2.3 Economic Evaluation

2.3.1 Economic internal rate of return (EIRR)

The project life is assumed to be 50 years from 1985 to 2034. The construction period will be 5 years from the beginning of 1986 excluding about one year for detailed design and selection of contractor. The project benefits will begin to accrue in 1987 and will increase annually to attain the maximum level in 1997.

Operation and maintenance cost of the Project will commence being disbursed in 1987 when the partial operation will commence. The operation and maintenance costs will increase linearly year by year and will reach the full amount in 1990 when the full operation will start for the whole Project area of 3,080 ha. Pumps and their attachments will be replaced twice during the entire period of the project life and operation and maintenance equipments both heavy and small for the irrigation and drainage system will be replaced every ten and five years respectively.

The economic internal rate of return (EIRR) was calculated from the economic direct benefit and cost flows given in Table O-2. The EIRR thus calculated was 13.3%. The result shows that the Project was economically feasible.

2.3.2 Sensitivity analysis

The sensitivity analysis was made with respect to change in annual irrigation and drainage benefits, project costs, and over-runs in the agricultural development schedules. The following five conditions to be anticipated are tested:

- 1) Base case
- 2) 20% cost increase and benefit as scheduled
- 3) 20% benefit decrease and cost as scheduled
- 4) 20% cost increase and 20% benefit decrease
- 5) 2 years over-run in the agricultural development schedule
- 6) 2 years over-run in the agricultural development schedule and 20% cost increase.

The results are summarized below:

Conditions	EIRR (%)	SI*
1)	13.3	-
2)	11.6	0.6
3)	10.6	1.0
4)	9.1	-
5)	10.8	-
6)	9.5	-

*: SI = Sensitivity Indicator = (% change in EIRR) / (EIRR of base case x % change in condition)

According to the above results, the change in benefits is most sensitive to economical feasibility of the Project. Therefore, to maintain economical feasibility, careful management for attainment of the anticipated benefits as scheduled will be required.

3. FINANCIAL EVALUATION

3.1 General

The financial feasibility of the Project is evaluated from the viewpoint of farmer's economy. In this connection, the assessment of the amount of water charge to be collected the farmer is made on provisional basis. Assessment of capital cost repayment capability is also made at Project and Farm Development Company level by preparing the cash flow tables.

3.2 Financial Cost

Based on the current market prices and costs as of 1984, the financial cost of the Project was estimated to be J\$217.3 million (US\$54.3 million), comprising J\$145.9 million (US\$36.5 million) in foreign currency and J\$71.4 million (US\$17.8 million) in local currency as shown in Annex N. In this estimate, the physical contingencies of 10%, and the price contingencies of 5% per annum for foreign currency and 10% per annum for local currency were added to the direct cost. Table N-3 in Annex N shows the annual disbursement schedule of the said financial cost.

3.3 Capacity to Pay

In evaluation of project feasibility from the financial viewpoint of farmers, average farm budget analyses both on mineral soil and peat soil were made with future projections under the Project conditions as shown in Table O-3.

The potential net reserve of a small farmer working in the Project was estimated to be J\$21,310 on 3.0 ha of mineral soil and J\$25,390 on 5.0 ha of peat soil.

3.4 Water Charge

It is desirable that a water charge per hectare be imposed on small farm land to cover operation and maintenance cost and the replacement cost of equipment utilized in the drainage and irrigation system.

The annual operation and maintenance cost of the Irrigation and Drainage System was estimated to be J\$4.4 million which is equivalent to about J\$2,000/ha of the land of small farmer. This corresponds to about 28% on mineral soil and 39% on peat soil of the net annual reserve of each farmer

The water charge of J\$2,000/ha/annum was considered to be within the capacity of the farmers to pay, and would not serve as a disincentive to production. This charge was taken to be the project revenue in the financial evaluation of the Project.

3.5 Repayment Capability of the Farm Development Company

The financial evaluation of the Farm Development Company was made for recovery of the capital cost of the farm machinery and workshop. In examining the repayment capability, it was assumed that the capital required for implementation would be arranged under the following conditions.

- 1) Capital cost of farm machinery and workshop: The capital will be financed by the Holding Company at an assumed interest rate of 4.75% per annum for a repayment period of 25 years including a grace period of 7 years.
- 2) Water charge: The amount of this charge will be J\$2,000/ha/annum same as for small farm.

A repayment schedule for the capital cost of farm machinery and workshop was prepared as shown in Table O-4. This table indicates that the direct revenue from the benefit of the mother farm and from hire of farm machinery can cover the necessary annual repayments, except during the initial operation stage. Hence, it is considered that some financial arrangement like a subsidy from the Government will be indispensable for implementation during the initial operation stage.

3.6 Repayment of the Project Cost

The financial evaluation of the Project was made by examining the repayment capacity for the capital cost of the Project. In examining the repayment capability, it was assumed that the capital required for the project implementation would be arranged under the following conditions:

- 1) Foreign currency portion: The capital will be financed through the arrangements by the Government at an assumed interest rate of 4.75% per annum for a repayment period of 25 years including a grace period of 7 years.
- 2) Local currency portion: The capital will be invested by the budget allocation of the Government with no repayment.

A repayment schedule for the foreign currency portion was prepared as shown in Table O-5. This indicates that the direct revenue from Farm Development Company and small farmers cannot cover the annual repayment of the fund, except the farm machinery cost, O&M cost and replacement cost, and the repayment of the fund has to be made by the Government

4. SOCIO-ECONOMIC IMPACTS

Various socio-economic impacts are expected to result from the implementation of the Project. There are:

1) Foreign exchange saving

Rice production in Jamaica is insufficient to meet domestic demand. In 1983, 57,000 tons of rice were imported at a cost of J\$44.8 million (US\$11.2 million). With the Project, local paddy production will be increased by 28,950 tons of dried paddy (15,400 tons of marketable milled rice) per annum. The estimated foreign exchange saving will be approximately J\$12.1 million (US\$3.0 million) per annum by substituting for imported rice.

2) Demonstration effects

With the completion of the Project, farmers in other agricultural areas as well as those in the Project area will become familiar with modern irrigation and drainage practices and their incentive for adopting improved irrigation and drainage practices will be greatly enhanced. Enthusiasm generated from this success may even shorten the development period of the Project.

3) Increase of employment opportunities

It is expected that the present unemployment in and around the Project area will be reduced by the implementation of the Project. After completion of the Project, more intensive land use resulting from year-round irrigation system, drainage, and farm mechanization, will certainly increase employment opportunities. In addition, there are the experience, technical know-how and skills in farmers. These up-graded human resources will provide motivation for future development in the Parish of St. Elizabeth and in Jamaica.

4) Environmental impacts

As shown in Annex L the Project would have minor or negligible impacts on the natural environment providing the use and choice of agricultural chemicals is properly monitored. It is nevertheless essential that such monitoring be carried out on a systematic basis

together with monitoring of effects on local biota especially as there are many existing or potential economic activities in the Black River Lower Morass.

5) Secondary benefits

The implementation of the Project works would certainly lead to beneficial changes in the rural economy. The social infrastructure and local transportation system would be improved. This would contribute to the improvement of rural economic activities. The increased crop production in the Project area would stimulate improvement of the marketing system and the agricultural support services.

6) In summary

Together these benefits will serve to improve the standard of living and the quality of life of the local people and contribute substantially to one of the main objectives of the Project.

Table O-1 ECONOMIC BENEFITS FLOWS

Year	Planted Area (ha)		Direct Benefit		(Unit: J\$10 ³) Annual Direct
	Mineral Soil	Peat Soil	Mineral Soil	Peat Soil	Benefits
1	-	-	-	-	-
2	-	-	-	-	-
3	260	-	718	-	718
4	780	130	5,354	862	6,216
5	780	700	6,773	1,653	8,426
6	780	1,500	8,433	2,913	11,346
7	780	2,300	9,346	6,212	15,558
8	780	2,300	10,219	8,542	18,761
9	780	2,300	10,863	11,210	22,073
10	780	2,300	11,241	14,543	25,784
11	780	2,300	11,241	18,453	29,694
12	780	2,300	11,241	21,009	32,250
13	780	2,300	11,241	22,107	33,348

Remark: From 13th year, the annual direct benefit continues constantly.

Table O-2 ANNUAL ECONOMIC COSTS AND BENEFIT FLOW

(Unit: J\$10³)

Year	Construction Cost	O & M Cost	Replacement Cost	Total Cost	Benefit
1	3,870	0	0	3,870	0
2	21,115	0	0	21,115	0
3	37,646	1,640	0	39,286	718
4	37,400	2,669	0	40,069	6,216
5	20,090	3,559	0	23,649	8,426
6	15,879	4,449	0	20,328	11,346
7	0	4,449	0	4,449	15,558
8	0	4,449	1,312	5,761	18,761
9	0	4,449	0	4,449	22,073
10	0	4,449	0	4,449	25,784
11	0	4,449	0	4,449	29,694
12	0	4,449	0	4,449	32,250
13	0	4,449	403	7,852	33,348
14	0	4,449	0	4,449	33,348
15	0	4,449	0	4,449	33,348
16	0	4,449	0	4,449	33,348
17	0	4,449	0	4,449	33,348
18	0	4,449	1,312	5,761	33,348
19	0	4,449	0	4,449	33,348
20	0	4,449	0	4,449	33,348
21	0	4,449	0	4,449	33,348
22	0	4,449	0	4,449	33,348
23	0	4,449	24,137	28,585	33,348
24	0	4,449	0	4,449	33,348
25	0	4,449	0	4,449	33,348
26	0	4,449	0	4,449	33,348
27	0	4,449	0	4,449	33,348
28	0	4,449	1,312	5,761	33,348
29	0	4,449	0	4,449	33,348
30	0	4,449	0	4,449	33,348
31	0	4,449	0	4,449	33,348
32	0	4,449	0	4,449	33,348
33	0	4,449	3,403	7,852	33,348
34	0	4,449	0	4,449	33,348
35	0	4,449	0	4,449	33,348
36	0	4,449	0	4,449	33,348
37	0	4,449	0	4,449	33,348
38	0	4,449	1,312	5,761	33,348
39	0	4,449	0	4,449	33,348
40	0	4,449	0	4,449	33,348
41	0	4,449	0	4,449	33,348
42	0	4,449	0	4,449	33,348
43	0	4,449	24,137	28,585	33,348
44	0	4,449	0	4,449	33,348
45	0	4,449	0	4,449	33,348
46	0	4,449	0	4,449	33,348
47	0	4,449	0	4,449	33,348
48	0	4,449	1,312	5,761	33,348
49	0	4,449	0	4,449	33,348
50	0	4,449	0	4,449	33,348

EIRR = 13.3%

Table O-3 FARM BUDGET ANALYSIS

Planting/ Harvesting Area (ha)	Gross Income			Gross Outgo			Net Reserve (J\$)
	Unit Yield (ton/ha)	Produc- tion (ton)	Unit Price (J\$/ton)	Total Value (J\$)	Farming Expense Unit Produc- tion Cost (J\$/ha)	Total Cost (J\$)	
I. Mineral Soil							
3	5.5	16.5	1,100	18,150	1,465	4,395	-
3	5.5	16.5	1,100	18,150	1,367	4,101	-
3	2.5	7.5	1,300	9,750	2,082	6,246	-
-	-	-	-	46,050	-	14,742	10,000
II. Peat Soil							
5	4.5	22.5	1,100	24,750	1,477	7,385	-
5	4.5	22.5	1,100	24,750	1,346	6,730	-
-	-	-	-	49,500	-	14,115	10,000
							21,308
							25,385

Table O-4 CASH FLOW STATEMENT OF THE FARM DEVELOPMENT COMPANY

(Unit: J\$103)

Year	Cash Outflow			Cash Inflow					Total	Balance	Accumulation
	Capital Cost	Loan Repayment	O & M Cost	Replace-ment Cost	Water Charge	Total	Fund	Benefit from Mother Farm			
1	0	0	0	0	0	0	0	0	0	0	0
2	7,140	339	0	0	0	7,479	7,140	0	0	0	-339
3	8,468	741	0	811	400	10,420	8,468	356	507	0	-1,428
4	0	741	0	1,990	800	3,531	0	955	2,967	3,922	391
5	16,032	1,503	0	2,503	800	20,838	16,032	1,307	2,967	20,306	-1,037
6	0	1,503	0	2,503	1,600	5,606	0	1,796	4,355	6,151	-1,569
7	0	1,503	0	2,503	1,600	6,406	0	2,362	5,744	8,106	-1,024
8	0	1,420	0	1,290	1,600	8,567	0	2,969	5,744	8,713	676
9	0	1,336	0	2,503	1,600	7,197	0	3,612	5,744	9,356	822
10	0	1,253	0	2,503	1,600	12,514	0	4,339	5,744	10,083	2,981
11	0	1,169	0	2,503	1,600	11,790	0	4,991	5,744	10,735	-2,431
12	0	1,086	0	2,503	1,600	7,747	0	5,387	5,744	11,131	-1,055
13	0	1,002	0	2,503	1,600	17,123	0	5,519	5,744	11,263	3,384
14	0	919	0	2,503	1,600	6,780	0	5,519	5,744	11,263	-5,860
15	0	835	0	2,503	1,600	9,136	0	5,519	5,744	11,263	4,483
16	0	752	0	2,503	1,600	6,613	0	5,519	5,744	11,263	2,127
17	0	668	0	2,503	1,600	7,329	0	5,519	5,744	11,263	3,629
18	0	585	0	2,503	1,600	10,696	0	5,519	5,744	11,263	4,650
19	0	501	0	2,503	1,600	11,122	0	5,519	5,744	11,263	3,934
20	0	418	0	2,503	1,600	8,719	0	5,519	5,744	11,263	12,213
21	0	334	0	2,503	1,600	15,165	0	5,519	5,744	11,263	567
22	0	251	0	2,503	1,600	6,912	0	5,519	5,744	11,263	141
23	0	167	0	2,503	1,600	7,318	0	5,519	5,744	11,263	2,544
24	0	84	0	2,503	1,600	5,945	0	5,519	5,744	11,263	-3,902
25	0	0	0	2,503	1,600	8,301	0	5,519	5,744	11,263	4,351


Remarks: 1/ Interest: 4.75%
 Grace period: 7 years
 Repayment period including grace period: 25 years

Table O-5 CASH FLOW STATEMENT OF THE PROJECT

(Unit: US\$10³)

Year	Cash Outflow				Cash Inflow				Total	Balance		
	Capital Cost		Loan Repayment ^{3/}		Fund		Revenue					
	F.C. ^{1/}	L.C. ^{2/}	Interest	Principal	F.C.	L.C.	Development Company	Small Farmer				
1	2,680	3,088	127	0	0	5,895	2,680	3,088	0	0	5,768	-127
2	20,080	12,608	1,081	0	0	33,769	20,080	12,608	339	0	33,027	-742
3	39,972	15,052	2,980	0	1,600	59,604	39,972	15,052	1,141	120	56,285	-3,319
4	31,356	18,360	4,469	0	2,604	56,789	31,356	18,360	1,541	2,040	53,297	-3,492
5	34,068	11,668	6,087	0	3,472	55,295	34,068	11,668	2,303	2,040	50,079	-5,216
6	15,380	10,392	6,818	0	4,340	36,930	15,380	10,392	3,103	2,840	31,715	-5,215
7	2,384	196	6,931	0	4,340	13,851	2,384	196	3,103	4,440	10,123	-3,728
8	0	0	6,439	7,974	4,340	20,037	0	0	4,774	4,440	9,214	-10,823
9	0	0	6,060	7,974	4,340	18,374	0	0	4,694	4,440	9,134	-9,240
10	0	0	5,681	7,974	4,340	17,995	0	0	4,611	4,440	9,051	-8,944
11	0	0	5,303	7,974	4,340	17,617	0	0	4,527	4,440	8,967	-8,650
12	0	0	4,924	7,974	4,340	17,238	0	0	4,444	4,440	8,884	-8,354
13	0	0	4,545	7,974	4,340	20,179	0	0	4,360	4,440	8,800	-11,379
14	0	0	4,166	7,974	4,340	16,480	0	0	4,277	4,440	8,717	-7,763
15	0	0	3,788	7,974	4,340	16,102	0	0	4,193	4,440	8,633	-7,469
16	0	0	3,409	7,974	4,340	15,723	0	0	4,110	4,440	8,550	-7,173
17	0	0	3,030	7,974	4,340	15,344	0	0	4,026	4,440	8,466	-6,878
18	0	0	2,651	7,974	4,340	16,245	0	0	3,943	4,440	8,383	-7,862
19	0	0	2,273	7,974	4,340	14,587	0	0	3,859	4,440	8,299	-6,288
20	0	0	1,894	7,974	4,340	14,208	0	0	3,776	4,440	8,216	-5,992
21	0	0	1,515	7,974	4,340	13,829	0	0	3,692	4,440	8,132	-5,697
22	0	0	1,136	7,974	4,340	13,450	0	0	3,609	4,440	8,049	-5,401
23	0	0	758	7,974	4,340	36,620	23,548	0	3,525	4,440	7,965	-28,655
24	0	0	379	7,974	4,340	12,693	0	0	3,442	4,440	7,882	-4,811
25	0	0	0	7,974	4,340	12,314	0	0	3,358	4,440	7,798	-4,516

Remarks: 1/: Foreign Currency
 2/: Local Currency
 3/: Interest; 4.75%
 Grace period; 7 years
 Repayment period including grace period; 25 years



THE AGRICULTURAL DEVELOPMENT PROJECT

JICA
614
80.7
AFT
LIBRARY