5-11-3 Project Benefits

Annual benefits attainable under the implementation of this project would amount to \$2,691,000 which is made up of \$2,590,000 by agricultural production increase and \$101,000 by subsistence water supply.

The ratio of the total benefits (B) to the total project costs (C) is estimated at 0.031.

Table 5-2-1 Meteorological Data for the Period 1951-1980

Temperature (°C)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Vой	Dec	Year
Mean	21.6	24.1	27.1	28,7	28.0	27.9	27.6	27.0	26.4	25.7	23.6	21.7	25.8
Ext. Max.	35.9	38.5	40.6	43.1	41.2	38.7	36.8	36.3	36.2	34.9	35.6	34.9	43.1
Ext. Min.	0.1	6.2	7.7	14.4	18.2	19.7	20.4	20.5	16.9	12.8	5.6	2.2	0.1

Relative Humidity (%)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Year
Меап	65.0	61.0	59.0	64.0	75.0	78.0	78.0	80.0	83.0	79.0	74.0	70.0	72.0
Mean Max.	92.4	89.8	88.5	89.6	92.1	92.8	92.5	93.5	95.5	95.3	94.6	93.7	92.5
Mean Min.	40.4	36.7	35.9	42.0	56.1	61.4	61.6	65.0	67.4	60.6	51.9	45.1	52.0

Evaporation (mm.)

	Jan	Feb	Mar	Apr	Мау	Jun	Jul	Aug	Sep	Oct	Nov.	Dec	Year
Mean-Piché					No-ob:	servat:	Lon						
Mean-Pan	124.4	134.4	160.9	175.7	155.9	139.9	138.0	123.7	106.2	122.4	113.8	117.3	1612.6

Rainfall (mm.)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Year
Mean	5.8	16.4	47.2	87.6	195.3	174.7	159.0	193.0	247.0	94.8	11.7	3.7	1236.2
Mean Rainy Days	1.5	3.0	5.7	9.6	18.7	17.9	18.1	20.5	21.3	11.2	2.7	0.8	131.0
Daily Maximum	17.0	41.7	61.8	101.2	139.1	110.6	125.0	148.2	148.6	102.5	34.1	25.4	148.6
Day/Year	19/69 11/75	9/79	26/55	25/74	22/79	13/79	13/78	12/78	23/67	9/64	5/74	12/72	23/67

Sunshine Duration (hr.)

	Jan	Feb	Mar	Apr	Мау	Jun	Jul	Aug	Sep	Oct	Nov.	Dec	Year
Mean	251.8	228.7	224.2	230.2	203.1	160.5	155.7	139.5	146.9	210.9	221.8	240.9	2413.4

Wind (Knots)

	Jan	Feb	Mar	Apr	May	Jun	Ju1	Aug	Sep	0et	Nov	Dec	Year
Prevailing Wind	E	E	Е	E	N	W	W	N	N	N	N	. N	-
Mean Wind Speed	3.3	3.7	3.6	3.8	3.6	3.3	3.7	3.5	3.1	2.8	2.8	3.0	-
Max. Wind Speed	30	32	45	47	45	40	33	30	35	33	21	27	47
	NW	W	N	W	N	sw	NW	W	NW	N,E	n,e, se	E	W

Monthly Rainfall (Loei)

Table 5-2-2

	Apr	Мау	Jun	Jul	Aug	Šep	Oct	Nov	Dec	Jan	Feb	Mar	Rainy Season	Dry Season	Total
02/69	87.1	157.4	193.9	187.8	102.7	212.9	85.9	53.8	0.0	4.2	4.4	55.0	854.7	290.4	1145.1
70/71	166.7	277.9	338.9	52.0	264.1	296.3	41.5	5.8	2.0	0.8	8.3	30.8	1229.2	255.9	1485.1
71/72	20.1	158.1	151.0	98.1	248.9	225.3	102.8	3.4	5.3	0.0	24.7	27.9	881.4	184.2	1065.6
72/73	73.1	77.5	211.7	88.8	119.6	245.9	189.2	21.8	33.8	0.0	0.0	62.0	743.5	379.9	1123.4
73/74	48.8	184.5	242.4	158.8	158.1	465.2	20.2	9.0	0.0	3.1	4.6	67.1	1209.0	144.4	1353.4
74/75	178.3	178.3 152.8	49.3	120.2	350.7	197.8	163.5	45.1	1.9	43.1	32.0	52.8	870.8	516.7	1387.5
75/76	31.9	304.2	135.1	176.6	103.0	263.5	117.6	1.3	0.0	0.0	53.1	4.5	982.4	208.4	1190.8
76/77	67.0	165.5	144.5	162.4	150.3	178.5	123.5	8.4	0.0	12.0	0.0	42.2	801.2	253.1	1054.3
77/78	153.0	106.5	66.1	173.5	179.1	165.8	85.8	4.1	2.0	3.0	7.9	71.4	691.0	327.2	1088.2
78/79	52.2	228.1	199.6	508.5	281.4	293.2	41.9	0.0	0.0	0.0	9.67	8.3	1510.8	182.0	1692.8
79/80	4.89	272.7	442.2	121.3	142.2	165.3	5.4	2.7	0.0	0.0	23.3	67.4	1143.7 167.2 1310.9	167.2	1310.9


Rainy Season; May - Sep

Dry Season ; Oct - Apr

Table 5-7-1

Computation Sheet of Net Water Requirement (Loei)

	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
Cropping Pattern		•		Wet Season	on Paddy				B /	Upland Cı	Crop	
Evapotrans- (mm/day)	6.8	5.8	4.9	5.3	4.9	4.3	4.2	3.4	3.5	3.5	6.4	0.9
piration (mm/mon)	204	180	147	164	152	129	130	102	109	109	137	186
Crop Coefficient	0.30	1.10	1.10	1.10	1.08	1.05	1.00	0.95	0.35	0.70	1.05	0.30
Crop Consumptive Use (mm/mon)	61	198		180	164	135	130	97	38	9/	. 144	56
Percolation (mm/mon)	30	16	15	16	16	15	16	30	31	31	28	31
Net Water Requirement (mm/mon)	91	214	177	196	180	150	146	127	69	107	172	87
Water Requirement for Land Preparation (mm)	· — · · · · · · · · · · · · · · · · · ·		200						70			<u> </u>
Net Irrigation Area (ha/100ha)	50	ы	100	100	100	100	100	100	100 50	100	100	100
Weighted NWR (mm/mon)	9+	9 .	293	196	180	150	146	127	75	107	172	87





Alluvium Deluvium. vaileyfill and river gravel (Quaternary to Recent)



Mudstone, conglomerate, tuff and limestone-interbeded shale (Carboniferous and Permian)



Greywacke mudston and slate (Carboniferous.Devonian and Silurian)





Granite and granodiorite. (Triassic)



Mafic and ultramafic. (Carboniferous)

Fig 5-3-1 Location and Geological Profile of Huai Chom Diversion Weir Site









Fig 5-5-1 Minimum Pressure Head Line

Distributing Tank q=0.3497m3/s 4Km 9 = 0.3497 m³/s $1R = 0.0398 \text{ m}^3/\text{s} (A = 20 \text{ hg})$ 11 -LOKm $9 = 0.3099 \,\text{m}^3/\text{s}$ $1R = 0.0239 \,\mathrm{m}^3/\mathrm{s}(A = 12 \,\mathrm{hg})$ L=0.9Km IR = 09=0.2860 m3/s Ban Na Kho Living Water = $0.0098 \,\mathrm{m}^3/\mathrm{s}$ 7.8 Km Ban Na Hong L=0.6 Km III KI IR Living Water 9 = 0.2153 m³/s =0.0120 m 3/s(A=6ha) 0.0011m3/s L=I.IKm 1R =13.2 Km =0.0339 m³/s (A=17ha) (A=30ha) 0.0598 m³/s Total 0.0609 m³/s $q = 0.2033 \,\text{m}^3/\text{s}$ 4.5 Km EX. 9=0.1694 m³/s $=0.0339 \,\mathrm{m} \, \mathrm{s}(A = 17 \,\mathrm{hg})$ 2Km] $=0.0239 \,\mathrm{m}^3/\mathrm{s}(A=12 \,\mathrm{hg})$ $9 = 0.1355 \text{ m}^3/\text{s}$ → A=6ha, 0.0119 m³/s $q = 0.0997 \text{ m}^{3/s}$ 2 [Living Water 0.0005m³/s 0.0797m³/s(A=40ha) 0.0802m³/s A.T. F Total 29 Km $q = 0.0195 \text{ m}^3/\text{s}$ Ban Si Putoh Living Water 0.0031m3/s =0.3Km $9 = 0.0164 \text{ m}^3/\text{s}$ Ban Pak Chom Living Water 0.0164 m³/s

Fig 5-6-1 Water Distribution Chart

Fig 5-6-2 Location Map of Benefited Area







Fig 5-6-3 Profile of Pipeline (1/5)



g. 5-6-4 Profile of Pipeline (2/5)

Fig 5-6-5 Profile of Pipeline (3/5)




Fig 5-6-6 Profile of Pipeline (4/5)

Fig 5-6-7 Profile of Pipeline (5/5)

Fig. 5-8-1 Construction Schedule of Huai Chom Diversion Weir Project

2.	Work Item	Quantities	Apr	Мау	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
Engineering Service Detailed Design & S	Engineering Service Detailed Design & Supervision							· • • • • • • • • • • • • • • • • • • •						
Preparatory Work	Work								П					
Temporary Road	load	3.0km												
	Jungle Clearing	10,310m ²			:						П			
	Excavation	26,500m ³						<u>-</u>				П		
	Concrete Works	578m ³									!			
Weir	Revetment & Riprap	2,350m ²			·*									П
	Diverting River									-				
	Intake	48m3	-					-						
	Pump House	38m3	***									 1		
Pump Station	Delivery Pipeline	1,100m		, , , , , , , , , , , , , , , , , , ,	···								7.7	
	Distributing Tank	225m ³							i			П		
Convevance	Pipeline	14.6km	— '***											
Pipeline	Water Supply & Accessary	416		· · · · · · · · · · · · · · · · · · ·										П

CHAPTER 6 CONCLUSION AND RECOMMENDATION

6-1 Conclusion

The field survey, studies and analysis were conducted by the current survey team to work out water supply plans for the following two projects:

- (1) Huai Laeng Yai Reservoir Construction Project
- (2) Huai Chom Diversion Weir Construction Project

As a result of the survey and studies, continuous domestic water supply in those projects will be secured and contributes not only to upgrading of the living conditions and improvement of the health conditions of inhabitants in villages around the Nakhon Phanom and Pak Chom camps of displaced persons, but also to encouraging villagers to accelerate rural development by supplying irrigation water and making self-helping efforts of the villagers.

Especially, the Government of the Kingdom of Thailand set the "Rural Poverty Eradication Plan" as one of the targets formulated in the 5-year plan started in 1982. The major objective of the plan is to upgrade living conditions, education, health, income, etc. of the inhabitants through the development of underdeveloped areas.

As those projects are inconformity with the objective of the "Rural Poverty Eradication Plan", the Government of the Kingdom of Thailand and the local authorities are vigorously desiring the prompt implementation of the projects.

Based on the above consideration, Huai Laeng Yai Reservoir Construction Project and Huai Chom Diversion Weir Construction Project will be deemed justifiable enough to be implemented under the grant aid of the Government of Japan.

6-2 Recommendation

Prior to commencement of the construction works, the Government of the Kingdom of Thailand is requested kindly to take necessary measures under full consideration for prompt settlement of the following matters even if diplomatic formality has been completed between the Government of the Kingdom of Thailand and the Government of Japan.

Huai Laeng Yai Reservoir Construction Project

- (1) Compensation or land acquisition for the proposed dam site, the proposed borrow area, the inundated area, and the proposed sites for a pumping station and a water distribution tank:
- (2) Approval of a road inspector for laying pipelines under the ground or alternatively in case of changing the original pipeline route, agreement with landowners by making compensation or others in determining a new pipeline route and cutting and removal of trees within the route to conduct the topographical survey;
- (3) Land acquisition for a field office, labours' houses, stock-yeards of construction machinery and materials, and other facilities necessary for the construction work;
- (4) Agreement with the concerned villages for improvement of an access road; and
- (5) Completion of all formalities as stipulated under the laws of Thailand for the implementation of the construction work and the work for transmission lines, if any.

Huai Chom Diversion Weir Construction Project

- (1) Compensation and land acquisition for the proposed diversion weir site and the proposed sites for a pumping station, a water distribution tank and water supply tanks;
- (2) Compensation for the site for the proposed pipeline route within private lands (farmhouse area, paddy and upland fields, orchards, etc);
- (3) Approval of a road inspector for laying pipelines under the ground along the roads or crossing the road-bed, or alternatively in case of changing the original pipeline route, agreement with landowners by making compensation or others in determining a new pipeline route and cutting and removal of trees within the route

to conduct the topographical survey;

- (4) Land acquisition for widening of an access road between Ban Na
 Kho and the proposed diversion weir site for construction
 purpose;
- (5) Land acquisition for a field office, labours' houses, stock-yeards of construction machinery and materials, and other facilities necessary for the construction work; and
- (6) Completion of all formalities as stipulated under the laws of Thailand for the implementation of the construction work and the work for transmission lines, if any.

APPENDIX I

- I-1. Members' List of the Survey Team
- I-2. Work Record
- I-3. Interviewees
- I-4. Collected Data

I-1. Member's List of Survey Team

Team Leader	Fumio TAMURA	Japan Engineering Consultants Co., Ltd.
Dam Engineer	Kazuo MIBAYASIII	- Do -
Weir Engineer	Chu NAKAJIMA	- Do -
Hydrologist	Seishiro SUZUKi -	- bo -
Design Engineer	KOJI SHINOHARA	- bo -
Geologist & Soil Mechanical Engineer	Terukazu HAGIWARA	- Do -
Surveyer	Kenichi SUENAGA	- Do -
Project Evaluation Engineer	Junji OHAMA	- po -

I-2 Work Record

Day in () indicates a holiday

No.	Date/Day	Bangkok	Nakhon Phanom (NP)	Pak Chom (PC)
ı	Nov 24 Wed	Lv. Tokyo Ar. Bangkok		
2	25 Thu	Coutesy call to Embassy of Japan, JICA, MOI & DTEC		
3	26 Fri	Discussion with MOI & RID Data collection	•	
4	27 Sat	Data collection and preparation of field survey		
5	28 (Sun)	- do -		
6	29 Mon	Discussion with MOI & JICA Contract with Geological & Topografic Survey Contracto	r	
7	30 Tue	Lv. Bangkok	Ar. Nakhon Phanom	•
8	Dec 1 Wed		Coutesy call to NP Provincial Office, RID Office and NP Camp	
9	2 Thu		Discussion with Provincial Office, District Office, RID and ARD	
10	3 Fri		Field reconnaisance at dam site	4
11	4 Sat		Geological & Topographic survey	
12	5(Sun)		- do - Field reconnaisance of pipeline route	
13	6 Mon		Geological & Topographic survey Hydrological analysis 4 members Lv. NP	4 members Ar. Loci
[4	7 Tue		Geological & Topographic survey Hydrological analysis	Courtesy call to Loei Provin- cial Office & PC District Office
15	8 Wed		- do -	Field reconnaisance of Weir sice
16	9 Thu		- do -	- do -
17	lO Frí		- do - Hagiwara Ar. NP	- do - Leveling of existing village road Hagiwara Lv. Loei
18	11 Sat		Geological & Topographic survey Hydrological analysis	Survey for pipeline route Leveling of existing provin- cial road
19	12(Sun)		- do -	- do -
20	13 Mon		- do ~ Survey for Camp	- do - Survey for alternative weir site
21	l4 Tue		- do -	Survey for pipeline route and Topographic survey
22	15 Wed		Geological & Topographic survey Hydrological analysis	- do - Survey for river cross section

					- 116 -	
	No.	Dat	ce/Day	Bangkok	Nakhon Phanom (NP)	Pak Chom (PC)
	23	Dec	16 Thu		Geological & Topographic survey Hydrological analysis	Survey for pipeline route and Topographic survey
	24		17 Fri		Interview on agriculture products and market price Hydrological analysis Kagiwara Lv. NP	- do - Discussion at PC District Office Hagiwara Ar, Loei
	25		18 Sat		Interview on market price at NP market Embankment design	Topographic survey for pipe- line route
	· 26		19(Sun)		Interview in villages along Mekong River Suzuki Lv. NP	- do - Suzuki Ar. Loei
	27		20 Mon		Embankment & Spillway design	Topographic survey for pipe- line route Test pit digging
	28		21 Tue	•	- do - 2 members Ar. NP	- do - Courtesy call to Governer of Loei 2 members Lv. Loei
	29		22 Wed		Report writing on the out- line of Huai Laeng Yai Reservoir	Drawing of Topographic Survey Design
	30		23 Thu		Meeting with Provincial Officer, RID, ARD & HD	~ do ~
	31		24 Fri		3 members Lv. NP	~ do ~ 3 members Ar. Loei
	32		25 Sat			Design
	33		26 (Sun)	2 members Ar. Bangkok		~ do ~ 2 members Lv. Loei
	34		27 Mon	Interim Report to Embassy of Japan and JICA		Design
	35		28 Tue	2 members Lv. Bangkok	,	- do - 2 members Ar. Loeí
	36		29 Wed			Desing
	37		30 Thu	•		- do -
	38		31(Fri)			do
	39	Jan	l(Sat)			off
	40		2(Sun)			Basic design of structures
	41		3 (Mon)			- do -
	42		4 Tue			- do - `
4	43		5 Wed	3 members Ar. Bangkok		- do - 3 members Lv. Loei Discussion at PC District Office
·	44		6 Thu	Report the result to JICA		Report writing on the outline of Huai Chom Diversion project
	45		7 Fri	Hagiwara Lv. Bangkok 2 members Lv. Bangkok Ar. Tokyo		Discussion with Provincial Officer, ARD, etc. Hagiwara Ar. Loei
	46		8 Sat			Basic design of structures

No.	Date/Day	Bangkok	Nakhon Phanom (NP)	Pak Chom (PC)		
47	Jan 9(Sun)			Basic Design of structures		
48	10			- do - Additional field reconnaisance		
49	11 Tue			- do -		
50	12 Wed	All members Ar. Bangkok		All members Lv. Loei		
51	13 Thu	Report the result of reconnaissance to Embassy of Japan, JICA and MOI	•			
52	14 Fri	Report writing				
53	15 Sat	- do -				
54	16(Sun)	- do -				
55	17 Mon	- do -		•		
56	18 Tue	Submission of Draft Report to MOI and DTEC		•		
57	19 Wed	Discussion with MOI & DTEC		•		
58	20 Thu	Report the result to Embassy of Japan and JICA Discussion with MOI				
59	21 Fri	Discussion with Embassy of Japan and JICA				
60	22 Saț	All members Lv. Bangkok Ar. Tokyo				

I-3. Interviewees

1) Ministry of Interior

Operation Center for Displaced Persons

Mr. Charoenjit Na Sangkhla Director

Mr. Virachai Naewboonnien Deputy Director

Mr. Pranai Suwanrath Chief, Foreign Affairs

Section

Mr. Praphakorn Smiti Chief of Operation Section

Mr. Santi Kardintra Chief Assistant, Welfare

Division

Mr. Soon Than Surintha Chief, Welfare Section

2) Department of Technical and Economic Cooperation (DTEC) Colombo Plan Sub-Division

Mr. Apilas Ostananda Director General

Mr. Kasem Unahasuvan Deputy Director

Mr. Thawal Polpuech Director of Colombo Plan

Sub-Division

Mr. Surayuth Kungsadan

Mr. Sutin Susila

Member

Member

3) Royal Irrigation Department

Mr. Boonthai Otaganonta Director, Design Division

Mr. Suha Thanomsingha Bang-Pra Project, A. Sriraja

P. Chunburi

Mr. Prasert Milintangul Hydrogy Division

Mr. Somneuk Sungsuwan Nakhon Phanom Office

Mr. Nirundi Narttatim Nakhon Phanom Office

Mr. Nirun Naktubtin Nakhon Phanom Office

4) Nakhon Phanom Provincial Office

Mr. Wirote Amarat Governor

Maj. Prasit Poonsawat Deputy Governor

Mr. Theranont Voraprakun Director of Civil Division

Mr. Kimo Look Civil Division (U.S. Peace

Corps)

Mr. Prayursuk Sakronwansuk Deputy Highway District

Engineer

Mr. Jumroon Panichying

Mr. Pongton Palivanik

Forest Office, Forest Office

Officer of Land

5) Amphur Muang Distric Office

Maj. Payungsak Supehusang

Mr. Battamasak Aswanuwat

Mr. Anirut Chartavaraha

Mr. Chaovalit Chamkrom

District Officer

Assistant District Officer

Community Development

Assistant District Officer

6) ARD (Accelerated Rural Development) Nakhon Phnom

Mr. Veerapol Theppratra

Sub-LT, Vijitr Thommachart

Chief Engineer

Chief Construction Technician

7) PEA (Provincial Electric Authority) Nakhon Phanom

Mr. Rai Suwannasub

Supervisor

Mr. Prakit Boongun

Power Distribution Reinforcement Project

8) Highway Department

Mr. Bunjong Chareanphanich

Engineer, Nakhon Phanom

9) Na Pho Camp

Mr. Thamrongsak Buranaphalin

Mr. Sahob Sittikorakan

Mr. Pipat Greigarn

Miss Wanee Wattanahsetpono

Na pho Camp Commander

Deputy Camp Commander

Field Officer (Napho), UNHCR

IRC Sanitarian NAPHO

10) Loei Provincial Office

Mr. Thengdum Bancheun

Mr. Napadol Hengchareon

Mr. Preecha Butrasri

Governor

Chief of Governor's Office

Officer of the Governor

11) Pak Chom District Office

Mr. Narait Jitsujaritwong

Mr. Wisa Yayaluksana

District Officer

Deputy District Officer

Mr. Sittisuk Pimrasri

Community Development Officer

Mr. Yuttasin Bunpan

Deputy District Agricultural

Officer

12) ARD (Accelerated Rural Development) Loei

Mr. Manit Silapaarcha

Director

Mr. Prayat Shampipat

13) PWWA (Provincial Water Works Authority)

Mr. Sarayut Ruengrung

Foreman Construction

I-4. Collected Data

(1) Suparerk Sinsupan

: Rural Water Supply

(2) Nukeel Thengtawee

: Some Aspects of Water Uses

(3) Adul Apinantara

: Social Aspects of Small-Scale

Water Resources for Irrigation

Water Management

(4) A.R.D.

: General Design Considerations

for Hydraulic Structure

(5) Canadian Embassy


: Ban Suk Churoen Spillway Project


(6) UNHCR


: Water


- (7) Daily Rainfall Data
 - (i) Chiang Khan, Loei
 - (ii) Nakhon Phanom
 - (iii) Si Chiang Mai, Nong Chai


APPENDIX II DRAWINGS




































SECTION 1-1





S = 1 : 100


THE KINGDOM OF THAILAND
THE ENVIRONMENTAL IMPROVEMENT PROJECT
IN THAI-LAO BORDER REGION
HUAI LAENG YAI RESERVOIR


DISTRIBUTING TANK PLAN AND SECTIONS


Date Mar 1983 Orawing No N - 12
JAPAN INTERNATIONAL COOPERATION AGENCY





















THE KINGDOM OF THAILAND
THE ENVIRONMENTAL IMPROVEMENT PROJECT
IN THAI-LAO BORDER REGION


HUAL CHOM DIVERSION WEIR


WEIR CROSS SECTION (2/2)


Date Mai 1983 Drowing No P-5
JAPAN INTERNATIONAL COOPERATION AGENCY

















DISTRIBUTING TANK




SECTION 2 - 2




SECTION 3-3



SECTION I - I




0 1 2 3 4 5^m S = 1 100



THE KINSDOM OF THAILAND
THE ENVIRONMENTAL IMPROVEMENT PROJECT
IN THAI-LAO BORDER REGION
HUAI CHOM DIVERSION WEIR

DISTRIBUTING TANK
PLAN AND SECTIONS

Date Mar. 1983 Drowing No. P-12
JAPAN INTERNATIONAL COOPERATION AGENCY



マ イ ク ロ フィルム作成

