(6) Car Parking

Car parking is planned to be located in front of the International Passenger Terminal Building on the landside.

A ceremony garden is designed in the middle of the car parking in order to express Bali traditional characteristic presenting Bali dances to all visitors as a welcome.

## 3.4 Other Facilities


(1) Control Tower and Administration Building
Taking into consideration a deteriorated
condition of the existing Control Tower
and the existing air navigation and facilities installed in the existing Control Tower
which have depreciated, a new Control Tower
is planned to be constructed in the new
International Departure Building in the
Short Term Plan.


A new Administration Building is planned to be accommodated in the new Domestic Passenger Terminal Building in the Middle Term Plan. The reason is the same explained as the Domestic Passenger Terminal Building item 3.2 (4) above.


### (2) Localizer


The existing off-set localizer can be relocated on the right position on the basis of meterological analyses and economical considerations.


Hence, the existing off-set localizer will not be necessary to relocate on the prolonged center line of the runway until the Middle Term Plan. In the Long Term Plan the existing localizer is planned to be











CEREMONY GARDEN


- 27 -


VIP TERMINAL BUILDING

RADAR (ASR) OFFICE

CUSTOM OFFICE







installed on the right position at the 09 side (east side) and a new localizer is also planned to be installed at the 27 side (west side) in order to provide the appropriate conditions for an international airport and to meet functional requirements for the localizers.

\* ....

The facilities other than above are explained in the main report.

### 3.5 Aircraft Noise and Airport Organization

(1) Aircraft Noise and Land Use Surrounding the BIA

The WECPNL noise contours for the BIA in the Long Term Plan is shown Fig. 3.7 on the basis of future aircraft movement forecast. As it can be seen in Fig. 3.7, a wide area of the sea, the town of Benoa, the Benoa seaport, small villages surrounding the BIA and Living Quarter for airport staff are expected to be covered by more than WECPNL 70. However, the town of Kuta, hotels and cottages located in the north of the BIA will not be affected by aircraft noise. As a matter of fact, aircraft noise standards for land use control should be studied on the basis of aircraft noise survey carried outside. Thereafter, taking into account Bali local characteristics, the land use control on aircraft noise should be integrated with areawide comprehensive planning designed by BUPATI in order to solve the impact of aircraft noise.




Fig. 3.7 WECPNL NOISE CONTOUR (THE YEAR 2010) S=1:50,000

(2) Airport Organization

Although there has been no problem in organization or staffing of the existing airport, it is necessary to reconsider the capacity and organization due to the development plan and the growth of airport.

The demand level of airport staff number for the Short Term, the Middle and the Long Term Plan are expected to be 800, 1100 and 1200 staff respectively in contrast to 400 staff employed at present.

3.6 Construction Schedule and Summary of Project Cost
The construction schedule for major work items is
summarized in Table 3.2.

Each development plan requires for its implementation approximately 6 to 8 months to select the planning consultant and complete drawings, and also about 20 to 24 months for selecting the contractor and for the construction. Therefore, the preparation should begin about 4 to 5 years in advance of each construction completion target year.

It is noted that construction method and its schedule must be coordinated with the airport authority not to influence the airport operation and maintenance in the course of the construction. Especially, pavement works for the extension of the runway and taxiways should be studied carefully and should be coordinated with the airport authority to explain the work method and its schedule. Temporary works, work schedule and its method for architectural work also should be provided in safety and convenience for the passengers and the airport staff during the construction period.

Project cost for the development plan of BIA is summarized in Table 3.3. About 30.7 billion Rp for the Short Term Plan is estimated roughly. The amount includes the engineering fees and physical contingency.

Although oil prices were increased in January, 1982 by 60% in the area concerned and affecting the price index locally, the estimate of construction cost has been based on the price index as of the end of December, 1981, without taking those factors into consideration.

Table 3.2 CONSTRUCTION SCHEDULE

Calender Year		Sh	Short Term	r.n			Ptw.	Middle Term	rin											
Work There	-	,	7	•		-	Γ.	6		:						] <sup>¥</sup>	Term Term	F		T
Win Itelia	•	•	<u>,                                    </u>	,	n	٥	-	<u>.</u>	6	70	11	12	13	14	15	16	17	1.8	19	20
Feasibility Study and Engineering Service	E		N. 11	10 m		5										=			111111111111111111111111111111111111111	
Land Acquisition and Relocation of Temples				200					=											
CONSTRUCTION,		-						日日	日日	-							-			_
1.Mobilization	1	,		less :		<b> </b>		H										<u> </u>		
2.Earth Works	<del></del>	~ <del> </del>					<del>,                                    </del>				1	: !	1   1	1	1	     	   	<del>/ =</del> .   	<u> </u>	     <b>-</b>
3.Pavement Works	1	<del>-  </del>   	1	-     	- <del></del> - ! !™!								<u>.                                    </u>	   	]	!   	1	_=_   		! !
ng Area	 1 1	<del>-</del> i !	     		—————————————————————————————————————					   	<u>                                     </u>	   	<del>                                     </del>	   	   	<del> </del>   	1	<u>: =</u>   	<u> </u>	
1	L   	<del>{</del> !	,	]	    g		 					1	   	<u> </u> 	<del> </del>     		1 1			
6. Cargo Terminal BLDG. — — — — —	<del>   </del>   	     		<u> </u>	- <u> </u>	<u>-</u>   	<del></del> !			└──┴ │		<sup> </sup> 			   	<u> </u>	 			I I
7.0ther Bing.	     	<del>-</del> i	1		   		<del></del>			   					<del></del>   	<u> </u>	   	! ≣		i   
8.Nav Aids Works	   	   	<del>ا</del> ا ا			 !				_					 	   	i i	 		   
9.AFL Horks	<u>!</u>   	—-í	- <b>-</b>				r <del>`</del>		耳	<u>'                                     </u>	 	   	i I	<u> </u>	  - 	i . 1	] ]	<del>1</del> 1 1		1   
10.0tilltes	<del>     </del>   	1	_ <b></b>	1		r					]	 			1	] 1	;   	=     	<del>   </del>	i 1 1 _
	_	$\dashv$			$\dashv$	_		<del> </del>				. 1				   	!   	<u>'</u> 1	<u> </u>   	l I

Table 3.3 ESTIMATED CONSTRUCTION COST Unit Million Rupiali Phase of Construction Short Term Middle Term Long Term TOTAL Foreign Local Foreign Portion Local Local Portion Foreign Portion Local Portion Item Total Total Foreign Portion Total Portion Portion Total Runway 1.367 844 2.211 1,367 844 2,211 Pavement 1,337 852 2.189 Taxiway 1,212 774 1,986 2,549 1.626 4,175 Work 1,016 648 1,664 1,425 Apron 911 2,336 152 96 2,593 248 4,248 1,655 Car patking Area Work 126 79 205 91 55 146 102 67 169 319 201 520 Drainage Work 245 456 701 82 152 234 3 3 327 611 938 1,121 Earth Work 748 1,869 2,733 1,822 4,555 3,212 2,140 5,352 7,066 4,710 11,776 Miscellaneous 272 166 9 438 6 15 6 6 12 287 178 465 5,484 3,793 9,277 5,552 3,720 9,272 3,472 SUR TOTAL 2,312 5.784 14,508 9,825 24,333 6,097 4,065 International PAX BLDG 10,162 1,840 1,226 3,066 3.451 2,301 5,752 11,388 7,592 18,980 Architectural Work Domestic PAX R L D G 420 631 1,051 9,005 6,004 15,009 4,836 3,224 8,060 14,472 9,648 24,120 596 Cargo Terminal B L D G 397 993 254 169 423 596 397 993 1,446 963 2,409 491 327 818 1,752 1,168 2,920 526 350 876 1,845 Others 2,769 4,614 SUB TOTAL 7,815 5,209 13,024 12,851 8,567 21,418 9,409 6,272 15,681 30,075 20.048 50,123 972 Navigational Aids 108 1,080 1,314 146 1,460 447 50 497 2,733 304 3,037 Navigational Aids System Work Field Lighting 552 61 613 26 3 29 263 29 292 841 93 934 SUB TOTAL 1,524 169 1,693 1,340 149 1,489 710 79 789 3,574 397 3,971 Works Power Supply & Generating System 251 44 295 920 161 1,081 622 108 730 1,793 313 2,106 Facility 496 584 1,367 239 1,606 1,241 88 219 1,460 3,104 3,650 Others 546 Services SUB TOTAL 747 132 879 2,287 400 2,687 1,863 327 2,190 4,897 859 5,754 Services y Works Special Se Facility V 359 20 379 1,104 123 1,227 Boarding Bridge 625 32 657 2,088 175 2,263 25,530 | 22,389 | 12,856 35,245 16,558 9,113 25,671 TOTAL 16,195 9,335 55,142 31,304 86,446 3,500 1,600 1,600 900 2,500 2,200 1,300 900 2,500 5,400 3,100 8,500 Contingency 7,066 2,686 2,628 1,752 2,686 2,628 1.752 7,066 Consulting Fee

NOTE: Exchange rate: US 1\$=644Rp=220.1 yen

19,910

10,013

29,923

67,608

34,404 102,012

41,373

14,156

27,217

30,716

20,481

10,235

**GRAND TOTAL** 

# CHAPTER 4 EGONOMIC AND FINANCIAL ANALYSIS



#### CHPATER 4 ECONOMIC AND FINANCIAL ANALYSIS

Detailed economic and financial analysis for the development plan of BIA are explained in the Chapter 12 of the main report. In this chapter, only the result of economic and financial analysis are discussed.

- Economic evaluation : Forecast minimal economic benefit is adopted.

EIRR 20.8%

B/C 1.49 (On the basis of 15% discount rate)

NPV 20,750 million Rp

- Sensitivity analysis:

Taking into consideration Indonesian economic condition and calculation method on the construction cost and cost benefit for the development plan, sensitivity analysis is studed based on the construction cost increased by 10% and 20% respectively.

For 10° cost increase

EIRR 19.5

B/C 1.) 7 (/) n +) 111/

1

For 20' cost inci a e

EIRR 18.3

B/C 1.27 (Ot. 1), 1+ .

15 discount no


In fact, sensitivity analysis on a variation of the cost benefit and the construction cost, shows that the project will influenced by the actual number of passengers for the project benefit.

- Financial evaluation: The results of financial analysis, show that a 40% increment of the air-port charge such as landing charge, facility charges, etc. is necessary in order to provide suitable finance after the completion of the project in the Short Term Plan.

Accordingly, the project is considered financially feasible if a 40% increment in the airport charge is implemented.

Therefore, it is concluded that this project is a suitable plan for promotion by the Indonesian Government based on the both economic and financial evaluation.

## RECOMMENDATIONS FOR PROJECT IMPLEMENTATION



### RECOMMENDATIONS FOR PROJECT IMPLEMENTATION

The following recommendations are made concerning project implementation.

- The preparations including request for financial assistance, topographic survey, soil investigation, etc. should be initiated at the earliest possible date so that the engineering services including basic design, detailed design, preparation of tender documents assistance in evaluation of the contractors, etc. can be completed by the end of 1983 at latest.
- The works included in the Short Term Plan correspond to the facility requirements for 1990. However, it is recommended to initiate the construction of the works included in the Short Term Plan at the beginning of financial year 1984 and complete them by the end of fiscal year 1985 since the earlier completion will make a great improvement in the safety of airport operation.
- The construction of the works included in the Middle Term Plan for the air traffic demand in the year 2 should be completed by the end of 1994.
- The construction of the works included the 'Plan for the air traffic demands in ': 'Plan for the beginning of 2001.





