
## 4.4 Aircraft Noise

The influence of aircraft noise was evaluated in WECPNL (Weighted Equivalent Continuous Perceived Noise Level) for the year 2010. Fig. 4.3 shows the existing land use around the new airport site and WECPNL contours in year 2010.

Many houses are scattered around the new airport site at present, though the site is designated as an agricultural area under the land utilization plan by BAPPEDA.

Therefore, control measures on land use will be necessary for the areas affected by aircraft noise in order to achieve environmental compatibility with the surrounding community.



ig. 4.3 Aircraft Noise Counters for New Yogyakarta Airport (Year 2010)

## 4.5 Land Use Planning for the Area Surrounding the New Airport

Land use planning should take the following 3 items into consideration.

#### (1) Aircraft Noise

Criteria for land use control were established and is proposed taking into account the local condition and current land use control practices for aircraft noise in Japan, France, etc.

#### - Proposed Criteria -

WECPNL  $\geq 70$ : No school, hospital, mosque, church, etc., is permitted.

 $\geq$  75 : No new residence is permitted in principle. Agricultural land use is recommended.

 $\geq$  85 : No residence is permitted in principle.

Residences are recommended to be relocated. Exchange of noise affected residential area with agricultual area outside WECPNL 70 is recommended.

# (2) Future Expansion of Airport Facilities

Land use planning for the surrounding areas should consider the future development of airport facilities.

Construction of buildings or houses in the areas shown in Fig. 4.4 are necessary to be restricted for future expansion of the terminal area and runway extension up to 3,000~m.

#### (3) Obstacle Control

Control of obstacles which hinder safe aircraft operation is necessary.


#### - Height Limitation

All the structures and trees are restricted in height so as not to infringe the obstacle limitation surfaces. As for the area for future runway extension, the height restrictions should be enforced in advance for the surfaces to be established when the planned 2,500 m

long runway is extended to 3,000 m.

# - Obstacle Clearance

From the standpoint of safe and efficient operations of aircraft and the air navigation system, all structures and trees should be avoided in the area indicated in Fig. 4.4.



# 4.6 <u>Airport Organization</u>

Fig. 4.5 shows airport organization chart of the New Yogyakarta airport anticipated for Phase I and II developments. Compared with the existing Yogyakarta airport, air safety division which belongs to technical division at present will be an independent division due to the strengthening of the ATC function. The existing 3 division organizations will be revised to 4 division organizations, accordingly. The existing 124 DGAC staff is considered adequate to be increased to 285 and 355 staff numbers in Phases I and II, respectively.




Fig. 4.5 Organization Chart of New Yogyakarta Airport

# 4.7 Construction Schedule and Cost Estimates

The construction schedule of the new Yogyakarta airport development was planned as indicated in Fig. 4.6. Construction works for the Phase I development will start in mid 1991 and end in mid 1994.

After that, about 6 months will be spent for such preparations as flight checks, training for navaids, test operation of airport facilities, maturity flights, issue of NOTAM, mobilization of control agency and airlines, etc. Inauguration date will be the beginning of 1995.

Within 4.5 years before the start of the construction works, the topographic survey, soil investigation, detailed engineering services, etc., should be completed. Compensation work related to land acquisition and relocation of houses is recommended to be started at an early date of this period, because it may take a long time for coordination and discussions.

The following works will be given first priority as regards the construction works.

- Access road which will be used as a temporary road for the construction works
- Diversion works of the Tepus River
- Diversion works of irrigation channels for the surrounding agricultural fields

Construction costs necessary for the Phase I and II developments are estimated to be 104 billion Rp. and 30 billion Rp. in 1986 price, respectively, as shown in Table 4.2. These costs include detailed engineering cost and a 10 % physical contingency.

Herein, the exchange rate is set at:

US\$ 1.0 = Rp. 1,125 US\$  $1.0 = \text{\tilde{Y}} 200$ 

Fig. 4.6 Construction Schedule of New Yogyakarta Airport Development

| Year   | 20 80 70 30 300 | 91   92          | 0.2   | 9    | 90              | 6        | 80 | 2000 | 5        | 3    | 2      | - 8         | ج<br>ا | 2       | 0.7 | <u>g</u> | 2010 |
|--|-----------------|------------------|-------|------|-----------------|----------|----|------|----------|------|--------|-------------|--------|---------|-----|----------|------|
| 1  | 6               | — <del> </del> — |       |      | <del> [</del> - |          | -  |      |          | ;    | 3      |             |        |         |     |          | 1    |
| Airport Development Concept                                      |                 |                  |       | _    |                 |          |    |      |          | Ì    | 1      | 7           |        |         |     | $\dashv$ |      |
| Feasibility Study  |                 |                  |       |      |                 |          |    | 1    |          |      |        |             |        |         | ·   |          |      |
| Financial Arrangements   |                 |                  |       |      | 777             |          |    |      |          |      |        |             |        |         |     |          |      |
| Detailed Engineering Services                                    | Topo, Soil      |                  |       |      | Topo, Soil      | Soil     |    |      |          |      |        |             |        |         |     |          |      |
| Tender, Evaluation and Award of Contract for Construction        |                 |                  |       |      |                 |          |    |      |          |      |        |             |        |         |     | ·        |      |
| Land Acquisition   |                 |                  |       |      |                 |          |    |      | _        |      |        | <del></del> |        | <u></u> |     |          |      |
| Compensation   |                 |                  |       |      |                 | :        |    |      |          |      |        |             |        |         |     |          |      |
| Construction   |                 |                  |       |      |                 |          |    |      |          |      |        |             |        |         |     |          |      |
| 1. Site Preparation  |                 |                  | - KCG |      |                 |          |    |      | :        |      |        |             |        |         |     |          |      |
| 2. Pavement Works  |                 | 1771             |       |      |                 |          |    | 677  |          | 7721 |        |             |        |         | {   |          |      |
| 3. Access Road   |                 |                  |       |      |                 |          |    |      |          |      |        |             |        |         |     | _        |      |
| 4. Passerger Terminal Building                                   |                 |                  |       | h    |                 |          |    |      | 123      |      |        |             |        |         |     |          |      |
| 5. Cargo Building  |                 |                  |       | FCTI |                 |          |    | -    | 1221     |      |        |             |        |         |     | _        |      |
| 6. Administration and Other<br>Buildings                         |                 |                  |       | 100  |                 |          |    |      |          |      |        |             |        |         |     |          |      |
| 7. Air Navigation Systems  |                 |                  |       |      |                 |          |    |      |          | 144  |        |             |        |         | _   |          |      |
| 8. Utilities Works   |                 |                  |       | 570  |                 | $\dashv$ |    |      |          |      | $\neg$ |             |        |         | _   |          |      |
| 9. Others  |                 |                  |       |      |                 |          |    | -    | 223      | _    |        | <u>_</u>    |        |         | _   |          |      |
| Flight Check, Commissioning Training, Maturity Flight, and Notam |                 |                  |       |      |                 | _        |    |      |          | 123  |        |             |        |         | _   |          |      |
| Adjustment with Airforce   |                 |                  |       |      |                 |          |    |      |          |      |        |             |        |         |     | _        |      |
|  | :               |                  |       | [.   |                 |          |    |      |          |      |        |             |        |         |     |          |      |
| Service Period   |                 | -                |       | ]    | ρ. Ι            | Phase    | н  |      | $/\!\!/$ |      |        |             | Phase  | Se II   |     |          |      |
|  |                 |                  |       |      |                 |          |    |      |          |      |        |             |        |         | .   |          |      |
|  |                 |                  |       |      |                 |          |    |      |          |      |        |             |        |         |     |          |      |

Table 4.2 Estimated Construction Cost for New Yogyakarta Airport Development

(Unit: million Rp.) Total Phase II Phase I Phase of Construction Foreign Local Sub Local Foreign Total Foreign Sub Local Portion Portion Total Work Item Portion Portion Total Portion Portion 0 15,979 15,979 0 O 0 15,979 0 15,979 Land Acquisition Acquisition 280 280 0 0 0 0 280 0 280 Compensation (3,835)(3,835)0) በ) Land Acquisition 0) ( 0) (3,835)(3,835)0) (Ultimate Expansion Area) 0 16,259 Ð 16,259 O O 16,259 0 16,259 Sub Total 4,308 1,807 85 2,501 45 40 4,223 1,767 2,456 Earth Work 1,030 577 32 453 12 20 557 998 441 Drainage Works Works 6,710 23,275 7,769 15,506 11,061 16,565 2,265 4,445 5,504 Pavement Works 745 500 Ð 0 0 Civil 745 500 245 Access Road 644 422 0 222 0 644 0 222 422 River Diversion 30,002 11,445 18,557 4,505 6,827 2,322 14,052 23,175 Sub Total 9,123 14,850 8,019 6,831 2,686 4,974 5,333 9,876 2,288 4,543 Passenger Terminal Building Works 681 320 361 247 434 131 116 204 230 Cargo Terminal Building 749 1,361 612 170 309 Architectural 473 579 1,052 139 Administration Building 0 322 285 607 0 607 0 285 322 Other Buildings 5,960 1,498 n 5,960 0 1,498 4,462 4,462 0 Special Equipment 15,333 23,459 7,028 8,126 4,470 10,863 16,431 2,558 5,568 Sub Total 6,750 7,332 1,943 582 4,888 5,389 81 1.862 Systems 501 Radio Navigation Aids Air Traffic Control and Aero-4,993 161 5,154 118 3,570 3,688 43 1,423 1,466 nautical Telecommunications 12,851 353 12,498 Navigation 3,669 ATC Radar System 254 8,928 9,182 99 3,570 5,723 4,213 1,510 248 699 947 Aeronautical Ground Lights 1,262 3,514 4,776 2,537 2,618 19 582 601 2,017 Meteorological System 62 1,955 Air 30,991 33,678 2,197 25,052 490 8.136 8,626 2,687 22,855 Sub Total 986 397 3,363 3,760 2,404 2,774 27 959 370 Power Supply System 167 0 4 4 56 111 Works 56 107 163 Water Supply System 679 12 38 255 424 243 398 641 26 Sewarage System Utilities 161 0 0 0 30 131 Solid Waste Disposal System 30 131 161 804 0 0 O 185 619 185 619 804 Telecommunication System 5,571 923 4,648 884 3,659 4,543 39 989 1,028 Sub Total Other Equipment Vehicles for Fire Fighting 0 1,268 0 1,642 1,642 374 374 1,268 0 Services, etc. 0 374 374 0 1,268 1,268 0 1,642 1,642 Sub Total 34,031 51,803 85,834 5,409 19,368 24,777 39,440 71,171 110,611 Total of Construction Works Engineering Services Cost 3,403 5,180 8,583 541 1,937 2,478 3,944 7,117 11,061 5,950 121,672 37,434 56,983 94,417 21,305 27,255 43,384 78,288 Sub Total 3,743 5,698 9,441 595 2,131 2,726 4,338 7,829 12,167 Contingency 62,681 103,858 6,545 23,436 133,839 41,177 29,981 47,722 86,117 Grand Total

<sup>\*</sup> Land Acquisition Cost for Ultimate Expansion Area is not included in Total Cost. Exchange Rate: US\$ 1.00 = Rp 1,125, ¥ 1 = Rp. 5.625

## 4.8 Economic and Financial Analyses

Economic and financial feasibilty was examined for the new Yogyakarta airport development.

## (1) Economic Analysis

Assessment for the economic feasibility was made in terms of EIRR (Economic Internal Rate of Return), B/C Ratio (Benefit Cost Ratio) and NPV (Net Present Value) as shown in Table 4.3.

Table 4.3 Economic Assessment

| EIRR (%) | B/C Ratio* | NPV <sup>*</sup> (million Rp., 1985) |
|----------|------------|--------------------------------------|
| 13.9     | 1.21       | 15,026                               |

Note \*: at discount rate 12%

The EIRR of 13.9 % indicates that this project is economically feasible because it exceeds 12 %, the opportunity cost of capital for airports project in Indonesia.

Sensitivity analysis was also made to provide a probablistic judgement on the feasibility. The results in Table 4.4 show that the EIRR almost satisfies the opportunity cost of capital even in case of the worst projection, 10 % increase in construction cost and 10 % decrease in traffic demand simultaneously.

Table 4.4 Sensitivity Analysis

| P        | rojections  | EIRR (%) |
|----------|---|----------|
|          | Base Case   | 13.9     |
| Case I   | Construction Cost<br>up by 10 %   | 12.9     |
| Case II  | Traffic Demand<br>down by 10 %  | 12.9     |
| Case III | Construction Cost<br>up by 10 %<br>Traffic Demand<br>down by 10 %<br>(simultaneously) | 12.0     |

Along with the direct and tangible benefits, this project will bring about various indirect and/or intangible benefits, for instance, promotion of regional industries including the tourist industry, development of the regional economy, increase of employment opportunities, improvement of air safety, etc.

Consequently, economic and sensitivity analyses prove the rationality of investment for this project from the viewpoints of national economy and regional society as well.

# (2) Financial Analysis

The results of the financial analysis show that airport revenues under the present charging system cannot cover the construction, maintenance and administration costs. It was also found that the level of charges needs to be increased by 30 % to cover only maintenance and administration costs of the airport.

As is well known, except for big airports it is very difficult for an airport to achieve a financial balance. Therefore, procurement of low interest funds and introduction of government subsidies are considered essential in order to implement this project as a social infrastructure.

At the same time, raising of the airport charges may be necessary to be considered through the evaluation of the existing charging system.

# 4.9 Conclusions and Recommendations

Part I of this report concluded that the long-term development of the major airports in the Central Java province and D.I. Yogyakarta should be implemented by the following development policies:

- Development of new Yogyakarta airport
- Redevelopment of the existing Surakarta airport
- Redevelopment of the existing Semarang airport after a review of the master plan already prepared

The feasibility study on the new Yogyakarta airport development project was executed based on the above conclusion.

After discussing the comprehensive study presented in Part II, Vol.1, the construction project for the new airport which is located 2 Km east of the existing Yogyakarta airport was judged feasible in terms of both engineering and national economy of Indonesia.

Implementation of the project will require the cost of approximately billion Rp. 104 and billion Rp. 30 in Phases I and II, respectively. The economic internal rate of return (EIRR) was estimated to be 13.9 %, and net present value (NPV) to be approx. billion Rp. 15.

By the implementation of this project, following can be expected for the air transportation and the socio-economic situation

- Unrestricted and flexible air transport services can be ensured to the increasing air traffic in future.
- Safe and efficient operations for aircraft can be promoted, especially for training aircraft and civil flights in the military training area.
- Aircraft noise influence within Yogyakarta city area can be largely reduced.
- Implementation of this project will contribute to the airlines' profitability by means of the introduction of medium and/or wide-body aircraft.

- Tourism development can be promoted by enabling the accommodation of the direct flights from neighboring countries.
- Implementation of this project will also contribute to the economic activities in the Yogyakarta region.
- Employment opportunity can be enlarged.

It is recommended that the following actions should be taken for the project implementation.

- Preparation of necessary negotiations for land acquisition and compensation should be initiated at the earliest possible stage so that Phase I project can be proceeded without any delay.
- Airspace above the new Yogyakarta airport should not be rearranged for itself solely but in relation with the redevelopment project of existing Surakarta airport. To do so, DGAC should establish a committee through which close coordination with the Indonesian Air Force can be made.
- Land acquisition, compensation, topographic survey, soil investigation and detailed engineering services should be completed by mid 1991 so that the construction work for the Phase I project can be started in 1991 and the airport can inaugurate its operations in early 1995.
- By the time of inauguration of the new airport operation, DGAC and BAPPEDA in D.I. Yogyakarta should prepare the land use plan in the vicinity of the airport which is to be executed after local communial agreement has been obtained.
- The Phase I facilities are to be designed to cope with the demand in the year 2000. The construction work for the Phase II project should be completed by 2000 to cope with the demand in the year 2010.

| ير خ |         |       |      | Sec. 7 |      |        |      |       | K. A. S. S. | 2    |                   |      | <br>    |    |     |          |     | - 1    |     |       |     |     |     |     |      |       | 11.    | 100  |        |      | Acres 1    |     | 4.7  | 1021  |        | S - 5 |     |
|------|---------|-------|------|--------|------|--------|------|-------|-------------|------|-------------------|------|---------|----|-----|----------|-----|--------|-----|-------|-----|-----|-----|-----|------|-------|--------|------|--------|------|------------|-----|------|-------|--------|-------|-----|
|      |         | 24    |      | •      |      |        |      |       |             |      |                   | - X  |         |    |     |          | 11  |        |     |       | (r) |     | -   |     | 1.0  | -     |        |      |        | -    | - 4        |     |      | - 2   | -6     | -     | 1   |
|      | (B      | 14.   | 01   | / 1    | 40 L | 4. 0.0 | 100  | 9.0   |             |      | 1.1               |      |         | ъ. | 1.0 | <br>     | - 1 |        | w   | ΛĿ    |     | v   | 200 |     |      |       | -      |      | 111    |      |            |     |      | M     | At The | и.    |     |
| 7.7  |         |       | - 14 | * L    |      |        |      | 126.1 | 14 a        | ~ .  |                   |      | <br>    | •  | 200 |          |     | - М    | 555 | ~~    | ٠,  |     |     |     | •    |       |        |      |        |      |            |     | 4 5  |       |        | 100   | ~   |
| -    | 3.7     | 10.00 | 77   | 1.0    |      |        |      | 1.    |             |      |                   |      | _       |    | 27. |          |     | ~ ~    | •   | •     | -   |     |     |     | •    |       |        |      |        | ~~~  |            |     |      |       | ***    |       | 100 |
|      | 20      | 25%   |      |        |      |        |      |       |             | 4    |                   |      |         |    |     |          |     |        |     | A     | 200 |     |     |     |      |       | 1. 540 |      | : K.E. | . 44 |            |     |      |       |        |       | 1   |
| 2    | South C |       | 1225 | 446    |      |        | Lace |       | N.V.        | 2.00 | $M_{\rm eff} > 3$ | 0.00 | <br>100 |    | 120 | <br>1.20 |     | S. 46. | 4.0 | A01 1 |     | -3. |     | 475 | 2531 | 40 V. |        | 4.06 | 15.15  |      | and the St | 4.6 | 3454 | de la | Art.   | . 10. | -9  |
|      |         |       |      |        |      |        |      |       |             |      |                   |      |         |    |     |          |     |        |     |       |     |     |     |     |      |       |        |      |        |      |            |     |      |       |        |       |     |

# CHAPTER 5 MASTER PLAN FOR SURAKARTA AIRPORT REDEVELOPMENT

#### 5.1 General

This chapter summarizes the feasibility study for the Surakarta airport redevelopment which constitutes airports development concept-A selected in Chapter 3.


As discussed in Chapter 3, the existing Surakarta airport will be saturated due to the increase in passengers in 1993; and therefore, Phase I construction works should be completed by that time.

Phase I development is planned to accommodate the traffic demand anticipated in the year 2000 so that no major investiment may be required for at least 5 years after the completion of works. Phase II development will accommodate the traffic demand up to the year 2010.

#### 5.2 Airport Master Planning

Redevelopment plan for Surakarta airport includes the eastward runway extension up to 2,150 m and relocation of the terminal area to the northern side of the runway where the transmigration terminal is located at present.

Layout plan and outline of the Phase I development are shown in Fig. 5.1 and Table 5.1, respectively.






Table 5.1 Outline of Surakarta Airport in the Phase I Development

| "X" indicates services available | Note:<br>Control Agency;    | Danc                       | Note:             | Approach Category;<br>Instrument, | Precision Approach |              |         |          |     |           |                        | -         | -    |                 |    |          | Completion of Phase I | development:   | End of 1993 |                                  |                       |                  |           |                      |                    |                      |                   |                                       | Drawn by JLCA<br>As of 1986 |                      |                   |             |
|----------------------------------|-----------------------------|----------------------------|-------------------|-----------------------------------|--------------------|--------------|---------|----------|-----|-----------|------------------------|-----------|------|-----------------|----|----------|-----------------------|----------------|-------------|----------------------------------|-----------------------|------------------|-----------|----------------------|--------------------|----------------------|-------------------|---------------------------------------|-----------------------------|----------------------|-------------------|-------------|
| K" indicates se                  | Seasonal<br>Availability    | All Seasons                |                   |                                   |                    |              |         |          |     | AIIS      | ı                      | AFL O.L.  | ×    |                 |    |          |                       |                |             | -                                |                       |                  |           |                      |                    | 0.                   |                   |                                       | 6,400                       | 4,850                | 776,000           | 2010        |
| ŧ,                               | Operation<br>Hours          |                            | 20                | vis                               |                    | # 008        | 1,200 m |          |     | MICROWAVE | x                      | ABN IWDI  | ×    | WX-IIX          | ×  |          |                       |                |             | 1                                | \                     |                  |           |                      |                    | 2010                 | 4                 |                                       | 5,500                       | 3,530                | 592,000           | 2005        |
|                                  | Aerodrome<br>Ref. Temp.     | 34.7°C                     | Operating Minimum | DH/MDA                            | 1 1                | 587          | 760     |          |     | TTY       | ×                      | TGS       | ×    | WX Radar        |    |          | (00                   |                |             |                                  | /                     |                  |           |                      |                    | 2005                 |                   |                                       | 4,500                       | 2,570                | . 408,000         | 2000        |
|                                  | - :                         | N 77015'6"E<br>(True)      |                   | Procedure                         | ILS                | LS           | OR      | VHF D.F. |     | A.F.S     | ×                      | IML IMC   | - X  | Radiosonde W    | ,  |          | sers (x1,000)         |                |             |                                  |                       |                  | \         |                      | - 1                | 2000                 |                   |                                       | 3,900                       | 1,740                | 299,000           | 1995        |
|                                  | <del></del> -               |                            |                   |                                   |                    |              |         |          |     |           |                        | DMC PAPI  | ×    |                 |    |          | al Passengers         |                | 00          |                                  |                       | 200              | _         | 1                    |                    | 7661                 |                   |                                       | 3,388                       | 618                  | 92,745            | 1983        |
|                                  | Airport<br>Elevation        | S 118.6 m                  | -                 | Runway                            | Apch to 08         | 45.07 40.04  | 3 11344 | LOCATOR  | ×   | VHF A/G   | ×                      | 2L REIL   | -    | APT-RX          |    |          | Annual                | . ;            | 1,000       |                                  |                       | ทั               |           |                      | Ē                  | 7                    |                   |                                       | D TOF                       | Annual Freight (ton) | Annual Passengers |             |
|                                  | Acrodrome<br>Ref. Point     | 7031,3"S                   | 7 - 711           | Coverage                          | 08 /7 (191         | 99.7% (20kt) |         | ILS      | ×   | ARTS      |                        | ORL IDZL  | ×    | WX-FAX          | ×  |          |                       |                |             | <del></del>                      | <b>89</b>             | :<br>2           |           |                      |                    |                      |                   |                                       | LDG AND TOF                 | Annuel               | Annual            | Year        |
|                                  | Airport<br>Total Area       | 25 1 ha                    | tation            | Taxi Bus                          |                    | ×            |         | TACAN    | 1   | ASDE      | 1                      | RWCL RWIL | ×    | Ceilometer      | ×  | Note     |                       |                |             | Parking<br>Configuration         | Self-maneuvering      | Self-maneuvering | Note      |                      |                    |                      | Height 23 m       | lers CAT-7                            | PERTAMINA                   |                      |                   |             |
| -                                | Commencement<br>of Services | 1.978                      | Transportation    | Railway, Ta:                      |                    | N.A.         |         | DMC      | x   | PAR       |                        | CGL RWL   | x -  | RVR             | ×  | Pavement | -                     | Asphalt        | Asphalt     | Area                             | 20,460 m <sup>2</sup> | 5,760 m²         | Structure | RC                   | кс                 | ) BC                 | RC                | 2 Air Crash Tenders<br>2 Fire Engines |                             |                      | Asphalt           | Asphalt     |
|                                  | INTL/DOM.                   | Dom.                       |                   | Distance to<br>Airport            | 3                  | by Road      |         | VOR      | ×   | SSR       | -                      | SALS ALB  | - x  | Surface Sensors | 2  | Size     | 2,270 m x 300 m       | 2,150 m x 45 m | 35 m x 23 m | Pavement                         | Concrete/<br>Asphalt  | Asphalt          | Size      | 7,700 m <sup>2</sup> | 800 m <sup>2</sup> | 1,200 m <sup>2</sup> | 60 m <sup>2</sup> | 400 m <sup>2</sup>                    | (Jet Al 520 kg)             |                      | 190 cars          | 2 lanes     |
|                                  | Name of<br>Airport          | Surskarta<br>(Adi Sumarmo) | City/Town         | Population                        | ייייין דיא אַ ט    | (1983)       |         | ECM      | x   | ASR.      |                        | ALS SFL   | - ×  | RWY Surfac      | ×  |          | -                     | 2,15           | 285         | Design Nr. of<br>Aircraft Stands | 8 8                   | B-767            |           | ·                    | ding               | tion                 | ver               | no                                    |                             |                      |                   | · p         |
|                                  | Country                     | Republic of<br>Indonesia   |                   | Name                              |                    | Surakarta    |         | Sm:      | لبن | <u></u>   | 100 /2/44<br>E00 /2/44 | Sat.      | i ve | <u>-</u> -      | įv |          | Runway Strip          | e Runway       | Textway     | 1000                             | Ll_,                  | 1801             | waron i   | Passenger Bldg.      | Carge Building     | Administration Bldg. | Ь                 | Rire Station                          | E Fuel Supply<br>System     | L                    | Vehicle Parking   | Access Road |
|                                  |                             |                            | 1                 | <del></del>                       |                    |              | L       |          |     |           |                        |           |      |                 |    |          | _                     | 6              | 1           | -                                |                       |                  |           |                      | ·. ·               |                      |                   |                                       |                             | 1                    |                   |             |

# (1) Airport Layout Planning

## a) Runway, Taxiway and Apron

The required runway length for Phases I and II is to be 2,150 m. The existing Runway 08 threshold was planned to be displaced eastward by 250 m in order to provide the area necessary for IIS localizer antenna and MLS azimuth antenna, and also in order to avoid reclamation and diversion of the Wungu River which are very costly. Accordingly, the 1,760 m long east portion of the existing runway will be utilized as a part of the new runway and the remaining 390 m will be constructed as an eastern extension of the runway.

Although a parallel taxiway is not considered to be necessary even in the Phase II development, the area for a complete parallel taxiway should be reserved for future development.

The passenger terminal apron for the Phase I development will be constructed by an overlay and partial expansion of the existing transmigration apron taking into account the maximum utilization of existing facilities. It will be expanded to the east in Phase II.

#### b) Terminal Facilities and Access Road

The terminal facilities are laid out in the terminal area facing the passenger terminal apron by taking their functions and expansibility into consideration.

The passenger terminal building was planned to be located at a distance of 67.5 m from the passenger terminal apron so that the apron can be expanded toward terminal building in case of introduction of B-747 aircraft in the future.

The airport access road will run along the north side of the airport to connect with the existing road.

## (2) Airport Facility Planning

## a) Site Preparation

Site preparation will be required for runway extension area, new terminal area and runway strip in Phase I. Longitudinal slope for the runway extension portion was planned to be the same gradient of 0.26 % with the existing Runway 26 side.

The existing runway strip will be graded to ensure a 300 m wide strip required for the precision approach runway.

Earthwork volume (cut volume) for Phase I will be about 140,000 cu.m.

Wungu River running through the runway extension area will have to be diverted by about 900 m.

## b) Building Facilities

The passenger terminal building will cater for the annual passengers of 408,000 and 776,000 and require floor areas of 7,700 sq.m. and 12,200 sq.m in Phases I and II, respectively.

The passenger terminal building is located 67.5 m away from the passenger terminal apron, and passengers will be transported by bus or on foot between them.

Simple flow of passengers and cargo which is one of the major elements for the functional design of the passenger terminal building were considered.

The cargo terminal building, administration building, control tower, fire station, VIP building, etc., will be planned taking into consideration their functions, expansibility and security requirements.

#### c) Air Navigation Systems

Air navigation systems were planned to meet the aircraft operational category of precision approach Category-I, ICAO.

The ILS will be replaced by a MLS in late 1990s in accordance with the ILS/MLS transition plan by ICAO.

#### d) Others

Airport utilities including power supply system, water supply system, sewerage system, solid waste disposal system and telecommunications system were planned based on the facility requirements. General services facilities including rescue and fire fighting facilities, airport maintenance equipment, fuel supply system and a heliport are also necessary as airport supporting elements.

## 5.3 Airspace Use

## (1) Rearrangement of Corridor and Terminal Area

Aircraft departing from and arriving at Surakarta airport at present utilize the air routes protected by the Yogyakarta-Solo corridor which has been established in the military training area. The following rearrangement was proposed in this Study.

# a. Establishment and Rearrangement of Corridors

Corridors in the training area were proposed to be established and/or rearranged along new Yogyakarta and Surakarta VOR/DMEs. Widening of the corridors will be also necessary.

#### b. Shift of the Training Area

The existing training area centered at "SO" NDB should be shifted as to be centered at the new Surakarta VOR/DME which is under construction at present for better self-recognition of aircraft position by air force trainees.

## c. Establishment of Additional Control Airspaces

Additional control airspaces were proposed to be established in order to ensure the safety of IFR operations in the training area.

## (2) Aircraft Operation Procedures

As basic instrument approach procedures, ILS approach for Runway 26, VOR/DME approach for Runway 08 and 26 were evaluated. Standard instrument departure routes for both Runway 08 and 26 were also studied. No problem has been seen for the establishment of procedures.

## (3) Provision of Radar Monitoring

For the prevention against near collisions between civil and military training aircraft, radar monitoring and radar assistance were proposed to be provided using a terminal radar approach control facility which will be installed near Yogyakarta airport.

## (4) Equipment of SSR Transponder

In order to promote the air traffic control services, SSR transponder on aircraft operating within the Yogya Military Controlled Airspace were proposed to be equipped.

#### 5.4 Aircraft Noise

Aircraft noise influence was evaluated in WECPNL for the year 2010. WECPNL contours for the year 2010 were drawn on the existing land use map around the airport as shown in Fig. 5.2.

Many houses are scattered arround the airport, therefore, control measures on land use will be necessary for the areas affected by aircraft noise in order to achieve environmental compatibility with the surrounding community.




Fig. 5.2 Aircraft Noise Contours for Surakarta Airport (Year 2010)

## 5.5 Land Use Planning of the Area Surrounding the Airport

Land use planning surrounding the airport should take the following 3 items into consideration.

#### (1) Aircraft Noise

Criteria for land use control were established and is proposed taking into account the local condition and current land use control practices for aircraft noise in Japan, France, etc.

#### - Proposed Criteria -

WECPNL  $\geq 70$ : No school, hospital, mosque, church, etc., is permitted.

 $\geq$  75 : No new residence is permitted in principle.

Agricultural land use is recommended.

 $\geq$  85 : No residence is permitted in principle.

Residences are recommended to be relocated. Exchange of noise affected residential area with agricultual area outside WECPNL 70 is recommended.

# (2) Future Expansion of Airport Facilities


Land use planning for the surrounding areas should consider the future development of airport facilities.

Construction of buildings and houses in the area shown in Fig. 5.3 are necessary to be restricted for future runway extension up to 2,500 m.

## (3) Obstacle Control

All the structures and trees are restricted in height so as not to infringe the obstacle limitation surfaces.

The height restrictions for the surfaces should be established in advance considering those surfaces established for 2,500 m long runway.



## 5.6 Airport Organization

Fig. 5.4 shows the airport organization chart of Surakarta airport anticipated for the Phase I and II developments. The existing organization comprising of 3 divisions and 12 sections are to be kept the same in the future. The staff numbers is 76 at present, and this number will be increased to 210 and 265 numbers in Phases I and II, respectively, as airport facilities develop.




Fig. 5.4 Organization Chart for Surakarta Airport

#### 5.7 Construction Schedule and Cost Estimates

The construction schedule of the Surakarta airport redevelopment was planned as indicated in Fig. 5.5. Construction works for the Phase I development will start at the beginning of 1990. Passenger facilities including a passenger terminal apron, passenger terminal building and vehicle parking will be completed by the end of 1991, and services will commence from the beginning of 1992. Runway extension and other works will be completed in mid 1993 and operations of the Phase I development will start at the beginning of 1994 after a 6 month period for flight checks, training for navaids, maturity flights, issue of NOTAM, etc.

Prior to the construction works, a 3 year period for a topographic survey, soil investigation, detailed engineering services, etc. will be required. The compensation work related to land acquisition and relocation of houses is recommended to be started at an early date of this period because it may consume a long time for coordination and discussion.

Construction costs necessary for the Phase I and II developments are estimated to be 52 billion Rp. and 15 billion Rp. in 1986 price, respectively, as shown in Table 5.2. These costs include detailed engineeringcostand10 % a physical contingency.

Herein, the exchange rate is set at:

US\$ 1.0 = Rp. 1,125 US\$  $1.0 = \text{\fiveal{Y}} 200$ 

Fig. 5.5 Construction Schedule of Surakarta Airport Redevelopment

| Year<br>Work Items   | 1985 86 87 88 89 90 91 92 93 | 94 95 96 97 | 86 86       | 2000 01    | 05 | 03 0 | 04 05    | 90       | 07   | 8 | 0102 60 |
|--|------------------------------|-------------|-------------|------------|----|------|----------|----------|------|---|---------|
| Airport Develogment Concept                                      |                              |             |             |            |    |      |          |          |      |   |         |
| Feasibility Study  |                              |             |             |            |    |      |          | · .      |      |   |         |
| Financial Arrangements   |                              | 2000000     |             |            |    |      |          |          |      |   |         |
| Detailed Engineering Services                                    | Topo . So:                   | Topo. Sol   | 127         |            |    |      |          |          |      |   |         |
| Tender, Evaluation and Award<br>of Contract for Construction     |                              |             |             |            |    |      |          |          |      |   |         |
| Land Acquisition   |                              |             |             |            |    |      |          |          |      |   |         |
| Compensation   |                              |             |             |            |    |      | <u> </u> |          |      |   |         |
| Construction   |                              |             |             | <br>       |    |      |          |          |      |   |         |
| 1. Site Preparation  |                              |             |             |            |    |      |          |          |      |   |         |
| 2. Pavement Works  |                              |             |             |            |    |      |          |          |      |   |         |
| 3. Access Road   |                              |             | <i>2000</i> |            |    |      |          |          |      |   |         |
| 4. Passenger Terminal Building                                   |                              |             |             |            |    |      |          |          |      |   |         |
| 5. Cargo Building  |                              |             |             | <u>[2]</u> |    |      |          |          |      |   |         |
| 6. Administration and Other<br>Buildings                         |                              |             |             |            |    |      |          |          |      |   |         |
| 7. Air Navigation Systems  |                              |             |             |            |    |      |          |          |      | - |         |
| 8. Utilities Works   |                              |             |             |            |    |      |          |          |      |   |         |
| 9. Others  |                              |             |             |            |    |      |          |          |      |   |         |
| Flight Check, Commissioning Training, Maturity Flight, and Notam |                              |             |             | 62         |    |      |          |          |      |   |         |
| Service Period   |                              | I əseda     | · :         |            |    |      | , ar     | Phase II | li-d |   |         |
|  | -                            |             |             | _          |    |      |          |          |      |   |         |

Table 5.2 Estimated Construction Cost for Surakarta Airport Redevelopment

(Unit: million Rp.) Phase of Construction Total Phase I Phase II Foreign Local Sub Local Foreign Sub Local Foreign Work Item Total Total Portion Portion Total Portion Portion Portion Portion Land Acquisition 1,560 0 1,560 0 1,560 0 1,560 35 0 ٥. Compensation 35 0 35 0 0 35 Land Acquisition (1,654) (1,654)(1,654)O) O) O) (1,654)0) 1 0) 1 (Ultimate Expansion Area) 0 1,595 Sub Total 1,595 0 1,595 0 Ω 0 1,595 1,468 1,517 Earth Work 966 502 10 39 49 976 541 Û 529 730 1,259 Drainage Works 529 730 1,259 0 Û 5,581 8,358 7,352 11,084 2,777 955 1,771 2,726 3,732 Pavement Works Civil 1,077 705 372 Access Road 235 122 357 470 250 720 47 81 47 0 0 34 River Diversion 34 81 0 15,018 5,976 9,042 4,541 6,982 11,523 1,435 2,060 3,495 Sub Total 4,077 7,549 4,579 1,366 1,604 2,970 3,472 2,473 Passenger Terminal Building 2,106 437 929 262 233 495 230 204 434 492 Cargo Terminal Building 742 111 136 247 445 544 989 334 408 Architectural Administration Building 270 576 306 270 576 0 0 O 306 Other Buildings 2,756 95 0 2,756 2,661 0 95 0 2,661 Special Equipment 3,746 4,715 8,084 12,799 3,008 6.045 9.053 1,707 2,039 Sub Total 7,376 7,679 1,702 1,770 303 68 Radio Navigation Aids 235 5,674 5,909 Air Traffic Control and Aero 3,700 3,576 37 1,021 1,058 124 87 2,555 2,642 Syst nautical Telecommunications 0 0 0 0 0 0 በ ATC Radar System 0 4,641 247 681 928 1,485 4,084 5,569 3,403 1,238 Aeronautical Ground Lights 2,556 569 588 81 2,475 1,906 1,968 19 Meteorological System Air 17,511 19,504 13,538 15,160 371 3,973 4,344 1,993 1,622 Sub Total 3,465 3,967 23 947 970 2,997 Power Supply System 479 2,518 44 94 138 0 90 134 4 44 Water Supply System NO. 400 669 12 3 15 269 397 654 257 Sewarage System 159 Ø Û 29 130 159 0 29 130 Solid Waste Disposal System 879 619 0 260 879 0 0 260 619 Telecommunication System 1,104 4,708 5,812 3,754 4,823 35 954 989 Sub Total 1,069 Vehicles for Fire Fighting 1,086 1,086 0 1,086 1,086 0 0 0 Services 1,086 n n 1,086 1,086 된젊 1,086 Sub Total 40,431 55,814 31,405 43,240 3,548 9,026 12,574 15,383 11,835 Total of Construction Works 4,325 355 903 1,258 1,539 4,044 5,583 3,141 1,184 Engineering Services Cost 61,397 16,922 44,475 3,903 9,929 13,832 13,019 34,546 47,565 Sub Total 993 1,383 1,692 4,448 6,140 4,757 390 3,455 1,302 Contingency 18,614 48,923 67,537 4,293 10,922 15,215 38,001 52,322 14,321 Grand Total

<sup>\*</sup> Land Acquisition Cost for Ultimate Expansion Area is not included in Total Cost. Exchange Rate: US\$ 1.00 = Rp. 1,125, ¥ 1 = Rp 5.625

## 5.8 Economic and Financial Analyses

Economic and financial feasibility was examined for the Surakarta airport redevelopment.

## (1) Economic Analysis

Assessment for the economic feasibility was made in terms of EIRR (Economic Internal Rate of Return), B/C Ratio (Benefit Cost Ratio) and NPV (Net Present Value) as shown in Table 5.3.

Table 5.3 Economic Assessment

| EIRR (%) | B/C Ratio* | NPV <sup>*</sup> (million Rp., 1985) |
|----------|------------|--------------------------------------|
| 14.0     | 1.23       | 9,800                                |

Note \*: at discount rate 12%

The EIRR of 14.0 % indicates that this project is feasible in terms of national economy because it exceeds 12 %, the opportunity cost of capital for airports project in Indonesia.

Sensitivity analysis was also made to provide a probablistic judgement on the feasibility. The results in Table 5.4 show that the EIRR almost satisfies the opportunity cost of capital even in case of the worst projection, 10 % increase in construction cost and 10 % decrease in traffic demand simultaneously.

Table 5.4 Sensitivity Analysis

| P        | rojections  | EIRR (%) |
|----------|---|----------|
|          | Base Case   | 14.0     |
| Case I   | Construction Cost<br>up by 10 %   | 13.1     |
| Case II  | Traffic Demand<br>down by 10 %  | 13.1     |
| Case III | Construction Cost up by 10 % Traffic Demand down by 10 % (simultaneously) | 12.2     |

Along with the direct and tangible benefits, this project will bring about various indirect and/or intangible benefits, for instance, promotion of regional industries including the tourist industry, development of regional economy, increase in employment opportunities, improvement in air safety, etc.

Consequently, economic and sensitivity analyses prove the rationality of investment on this project when viewed nationally as well as regionally.

## (2) Financial Analysis

The results of the financial analysis show that airport revenues under the present charging system cannot cover the construction, maintenance and administration costs. It is also found that when the new terminal will commence the operation, the level of charges needs to be increased by at least 30% to cover only maintenance and administration costs anticipated in a first few years.

As is well known, except for the big airports it is very difficult for an airport to achieve a financial balance. Therefore, procurement of low interest funds and the introduction of government subsidies are considered essential in order to implement this project as a social infrastructure.

At the same time, raising in airport charges may be necessary after an evaluation of the existing charging system is carried out. Furthermore, it is suggested that in the future, some countermeasures such subsidies of the government, etc., will be required.

#### 5.9 Conclusions and Recommendations

It is concluded in Part I "Formation of the airports development concept" that the long-term development of the major airports in the Central Java province and D.I. Yogyakarta should be implemented by the following development policies:

- Development of the new Yogyakarta airport
- Redevelopment of the existing Surakarta airport
- Redevelopment of the existing Semarang airport after review of the master plan already prepared

The feasibility study on the redevelopment project of the existing Surakarta airport was executed in Part II based on the above conclusion.

Based on the comprehensive study presented in Part II, Vol. 2, the redevelopment project of the existing Surakarta airport is judged feasible in terms of both engineering and the national economy of Indonesia.

The cost of the project is estimated to be approximately billion Rp. 52 and billion Rp. 15 in Phases I and II, respectively and the economic internal rate of return (EIRR) is estimated to be 14.0 %, and net present value (NPV) to be approx. billion Rp. 10.

By the implementation of this project, the following can be expected for the air transportation and the socio-economic situation:

- Unrestricted and flexible air transport services can be ensured to the increasing air traffic demand in the future.
- Safe and efficient operations for aircraft can be promoted, especially for training aircraft and civil flights in the military training area.
- Implementation of this project will contribute to the airlines' profitability by means of introduction of larger aircraft.
- Development of the tourist industry can be promoted by the provision of unrestricted air transport services.

- Implementation of this project will also contribute to the economic activities in the Surakarta region.
- Employment opportunities can be enlarged.

It is recommended that the following actions should be taken for the project implementation.

- Preparation of negotiations necessary for land acquisition and compensation should be initiated at the earliest possible stage so that the Phase I project can be proceeded without any delay.
- Airspace above the Surakarta airport should not be rearranged for itself solely but in relation with the development project of the new Yogyakarta airport. To do so, DGAC should constitute a committee through which close coordination with the Indonesian Air Force can be maintained.
- Land acquisition, compensation, topographic survey, soil investigation and detailed engineering services should be completed by the end of 1989 so that the construction work for the Phase I project can be started in 1990 and completed in 1993. Since the existing passenger terminal building has already been saturated even for the present passengers, the new terminal building should be constructed prior to the other works by 1992.
- By the time of completion of the Phase I project, DGAC and BAPPEDA in Surakarta should prepare a land use plan, which requires the consensus of the regional society, in the vicinity of the airport.
- The Phase I facilities are to be designed to cope with the air traffic demand in the year 2000. The construction work for the Phase II project should be completed by 2000 to cope with the air traffic demand in the year 2010.

