

Project. Physical contingencies of 10% have been added to all estimated costs. Price increases were estimated by applying the annual rates of price escalation of 10% for local costs and 6% for foreign costs. Expected price increases amount to Rs. 1,232 million, or 74% of base cost plus physical contingencies.

2.2. Procurement

Construction works would be carried out by international competitive bidding, and equipment would be procured through international competitive bidding. CDA would retain consulting firms, composed of foreign specialist in association with local consultants to assist in the detail design of project features, preparation of design and contract documents, supervision of construction, and the establishment of operation and maintenance programs.

2.3. Operation and Maintenance Costs

Operation and maintenance costs (O & M cost) of the project include electric power costs, chemical costs, repairing costs and replacement costs. O & M cost at full development stage is summarized below. (Breakdown of electric power costs, chemical costs and replacement costs are given in Table C.II-20):

Annual running expenses	(Rs. 1,000)
1. Electric power cost	10,971
2. Chemical cost	12,813
3. Personnel expense	2,288
4. Repair	3,318
<u>Total</u>	<u>29,390</u>

Total replacement cost for 50 years 1985 to 2034:

	(Rs. 1,000)
1. Water treatment plant	92,140
2. Pumping plant	68,519
3. Electric plant	152,058
<u>Total</u>	<u>312,717</u>

TABLE C.II-1

COST SUMMARY (1)

<u>Item</u>	<u>Local</u> ----- Rs. Million	<u>Foreign</u> ----- -----	<u>Total</u> -----	<u>Foreign</u> (%)
1. Conduction main	249.7	177.8	427.5	42
2. Water treatment plant	190.3	184.9	375.2	49
3. Pumping station	51.6	54.1	105.7	51
4. Distribution main	70.5	70.5	141.0	50
5. Service reservoir	112.8	77.8	190.6	41
6. Electric works	13.8	23.3	37.1	63
<u>Sub-total (1~6)</u>	<u>688.7</u>	<u>588.4</u>	<u>1,277.1</u>	<u>46</u>
7. Project office	12.0	-	12.0	-
8. Land acquisition	35.6	-	35.6	-
9. Office equipment	2.2	6.3	8.5	74
10. Engineering	31.2	116.4	147.6	79
11. Administration	35.6	-	35.6	-
<u>Sub-total (7~11)</u>	<u>116.6</u>	<u>122.7</u>	<u>239.3</u>	<u>51</u>
<u>Base Cost (1~11)</u>	<u>805.3</u>	<u>711.1</u>	<u>1,516.4</u>	<u>47</u>
12. Physical contingency	80.5	71.1	151.6	
13. Price escalation	842.7	389.3	1,232.0	
<u>Total Cost</u>	<u>1,728.5</u>	<u>1,171.5</u>	<u>2,900.0</u>	<u>40</u>

TABLE C.II-2

COST SUMMARY (2)

(Unit: Rs. Million)

<u>Item</u>	<u>Phase I</u>	<u>Phase II</u>	<u>Phase III</u>	<u>Total</u>
1. Conduction main	427.5	-	-	427.5
2. Water treatment plant	196.1	101.2	77.9	375.2
3. Pumping station	89.4	10.4	5.9	105.7
4. Distribution main	76.0	65.0	-	141.0
5. Service reservoir	124.6	43.0	23.0	190.6
6. Electric works	32.2	3.4	1.5	37.1
<u>Sub-total (1~6)</u>	<u>945.8</u>	<u>223.0</u>	<u>108.3</u>	<u>1,277.1</u>
7. Project office	12.0	-	-	12.0
8. Land acquisition	35.6	-	-	35.6
9. Office equipment	8.5	-	-	8.5
10. Engineering	121.1	17.8	8.7	147.6
11. Administration	27.8	4.5	3.3	35.6
<u>Sub-total (7~11)</u>	<u>205.0</u>	<u>22.3</u>	<u>12.0</u>	<u>239.3</u>
<u>Base Cost (1~11)</u>	<u>1,150.8</u>	<u>245.3</u>	<u>120.3</u>	<u>1,516.4</u>
12. Physical contingency	115.1	24.5	12.0	151.6
13. Price escalation	659.1	288.2	284.7	1,232.0
<u>Total Cost</u>	<u>1,925.0</u>	<u>558.0</u>	<u>417.0</u>	<u>2,900.0</u>

TABLE C.II-3 COST SUMMARY - LOCAL COST

(Unit: Rs. Million)

<u>Item</u>	<u>Phase I</u>	<u>Phase II</u>	<u>Phase III</u>	<u>Total</u>
1. Conduction main	249.7	-	-	249.7
2. Water treatment plant	99.6	51.4	39.3	190.3
3. Pumping station	44.2	4.6	2.8	51.6
4. Distribution main	38.2	32.3	-	70.5
5. Service reservoir	72.1	26.4	14.3	112.8
6. Electric works	11.9	1.3	0.6	13.8
<u>Sub-total (1 ~ 6)</u>	<u>515.7</u>	<u>116.0</u>	<u>57.0</u>	<u>688.7</u>
7. Project office	12.0	-	-	12.0
8. Land acquisition	35.6	-	-	35.6
9. Office equipment	2.2	-	-	2.2
10. Engineering	25.8	3.6	1.8	31.2
11. Administration	27.8	4.5	3.3	35.6
<u>Sub-total (7 ~ 11)</u>	<u>103.4</u>	<u>8.1</u>	<u>5.1</u>	<u>116.6</u>
<u>Base Cost (1 ~ 11)</u>	<u>619.1</u>	<u>124.1</u>	<u>62.1</u>	<u>805.3</u>
12. Physical contingency	61.9	12.4	6.2	80.5
13. Price escalation	448.4	193.4	200.9	842.7
<u>Total Cost</u>	<u>1,129.4</u>	<u>329.9</u>	<u>269.2</u>	<u>1,728.5</u>

TABLE C.II-4 COST SUMMARY - FOREIGN COST

(Unit: Rs. Million)

<u>Item</u>	<u>Phase I</u>	<u>Phase II</u>	<u>Phase III</u>	<u>Total</u>
1. Conduction main	177.8	-	-	177.8
2. Water treatment plant	96.5	49.8	38.6	184.9
3. Pumping station	45.2	5.8	3.1	54.1
4. Distribution main	37.8	32.7	-	70.5
5. Service reservoir	52.5	16.6	8.7	77.8
6. Electric works	20.3	2.1	0.9	23.3
<u>Sub-total (1 ~ 6)</u>	<u>430.1</u>	<u>107.0</u>	<u>51.3</u>	<u>588.4</u>
7. Project office	-	-	-	-
8. Land acquisition	-	-	-	-
9. Office equipment	6.3	-	-	6.3
10. Engineering	95.3	14.2	6.9	116.4
11. Administration	-	-	-	-
<u>Sub-total (7 ~ 11)</u>	<u>101.6</u>	<u>14.2</u>	<u>6.9</u>	<u>122.7</u>
<u>Base Cost (1 ~ 11)</u>	<u>531.7</u>	<u>121.2</u>	<u>58.2</u>	<u>711.1</u>
12. Physical contingency	53.2	12.1	5.8	71.1
13. Price escalation	210.7	94.8	83.8	389.3
<u>Total Cost</u>	<u>795.6</u>	<u>228.1</u>	<u>147.8</u>	<u>1,171.5</u>

TABLE C.II-5 COST SUMMARY - PHASE I

(Unit: Rs. Million)

<u>Item</u>	<u>Local</u>	<u>Foreign</u>	<u>Total</u>
1. Conduction main	249.7	177.8	427.5
2. Water treatment plant	99.6	96.5	196.1
3. Pumping station	44.2	45.2	89.4
4. Distribution main	38.2	37.8	76.0
5. Service reservoir	72.1	52.5	124.6
6. Electric works	11.9	20.3	32.2
<u>Sub-total (1~6)</u>	<u>515.7</u>	<u>430.1</u>	<u>945.8</u>
7. Project office	12.0	-	12.0
8. Land acquisition	35.6	-	35.6
9. Office equipment	2.2	6.3	8.5
10. Engineering	25.8	95.3	121.1
11. Administration	27.8	-	27.8
<u>Sub-total (7~11)</u>	<u>103.4</u>	<u>101.6</u>	<u>205.0</u>
<u>Base Cost (1~11)</u>	<u>619.1</u>	<u>531.7</u>	<u>1,150.8</u>
12. Physical contingency	61.9	53.2	115.1
13. Price escalation	448.4	210.7	659.1
<u>Total Cost</u>	<u>1,129.4</u>	<u>795.6</u>	<u>1,925.0</u>

TABLE C.II-6 COST SUMMARY - PHASE II

(Unit: Rs. Million)

<u>Item</u>	<u>Local</u>	<u>Foreign</u>	<u>Total</u>
1. Conduction main	-	-	-
2. Water treatment plant	51.4	49.8	101.2
3. Pumping station	4.6	5.8	10.4
4. Distribution main	32.3	32.7	65.0
5. Service reservoir	26.4	16.6	43.0
6. Electric works	1.3	2.1	3.4
<u>Sub-total (1 ~ 6)</u>	<u>116.0</u>	<u>107.0</u>	<u>223.0</u>
7. Project office	-	-	-
8. Land acquisition	-	-	-
9. Office equipment	-	-	-
10. Engineering	3.6	14.2	17.8
11. Administration	4.5	-	4.5
<u>Sub-total (7 ~ 11)</u>	<u>8.1</u>	<u>14.2</u>	<u>22.3</u>
<u>Base Cost (1 ~ 11)</u>	<u>124.1</u>	<u>121.2</u>	<u>245.3</u>
12. Physical contingency	12.4	12.1	24.5
13. Price escalation	193.4	94.8	288.2
<u>Total Cost</u>	<u>329.9</u>	<u>228.1</u>	<u>558.0</u>

TABLE C.II-7 COST SUMMARY - PHASE III

(Unit: Rs. Million)

<u>Item</u>	<u>Local</u>	<u>Foreign</u>	<u>Total</u>
1. Conduction main	-	-	-
2. Water treatment plant	39.3	38.6	77.9
3. Pumping station	2.8	3.1	5.9
4. Distribution main	-	-	-
5. Service reservoir	14.3	8.7	23.0
6. Electric works	0.6	0.9	1.5
<u>Sub-total (1 ~ 6)</u>	<u>57.0</u>	<u>51.3</u>	<u>108.3</u>
7. Project office	-	-	-
8. Land acquisition	-	-	-
9. Office equipment	-	-	-
10. Engineering	1.8	6.9	8.7
11. Administration	3.3	-	3.3
<u>Sub-total (7 ~ 11)</u>	<u>5.1</u>	<u>6.9</u>	<u>12.0</u>
<u>Base Cost (1 ~ 11)</u>	<u>62.1</u>	<u>58.2</u>	<u>120.3</u>
12. Physical contingency	6.2	5.8	12.0
13. Price escalation	200.9	83.8	284.7
<u>Total Cost</u>	<u>269.2</u>	<u>147.8</u>	<u>417.0</u>

TABLE C.II-8 SCHEDULE OF EXPENDITURE - PHASE I

(Unit: Rs. Million)

	<u>1985</u>	<u>1986</u>	<u>1987</u>	<u>1988</u>	<u>1989</u>	<u>1990</u>	<u>1991</u>	<u>1992</u>	<u>Total</u>
1. Conduction main	-	-	26.2	78.8	90.0	91.9	96.6	44.0	427.5
2. Water treatment plant	-	-	-	-	43.2	104.6	47.5	0.8	196.1
3. Pumping station	-	-	-	-	1.9	35.5	36.5	15.5	89.4
4. Distribution main	-	-	-	17.0	21.5	27.1	8.2	2.2	76.0
5. Service reservoir	-	-	-	-	-	49.7	49.7	25.2	124.6
6. Electric works	-	-	-	-	-	1.5	18.7	12.0	32.2
Sub-total (1~6)	-	-	26.2	95.8	156.6	310.3	257.2	99.7	945.8
7. Project office	-	-	12.0	-	-	-	-	-	12.0
8. Land acquisition	-	-	6.0	29.6	-	-	-	-	35.6
9. Office equipment	-	-	8.5	-	-	-	-	-	8.5
10. Engineering	24.9	16.6	8.1	7.8	11.9	23.9	19.9	8.0	121.1
11. Administration	5.5	3.4	0.6	1.9	3.1	6.2	5.1	2.0	27.8
Sub-total (7~11)	30.4	20.0	35.2	39.3	15.0	30.1	25.0	10.0	205.0
Base Cost (1~11)	30.4	20.0	61.4	135.1	171.6	340.4	282.2	109.7	1,150.8
11. Physical contingency	3.0	2.0	6.1	13.5	17.2	34.1	28.2	11.0	115.1
12. Price escalation	1.2	2.5	15.5	50.1	80.6	203.6	206.0	99.6	659.1
Total Cost	34.6	24.5	83.0	198.7	269.4	578.1	516.4	220.3	1,925.0

TABLE C.II-9 SCHEDULE OF EXPENDITURE - PHASE I/LOCAL COST

	(Unit: Rs. Million)										
	1985	1986	1987	1988	1989	1990	1991	1992	Total		
1. Conduction main	-	-	16.3	45.4	52.1	53.5	53.3	29.1	249.7		
2. Water treatment plant	-	-	-	-	22.1	55.0	22.0	0.5	99.6		
3. Pumping station	-	-	-	-	1.3	17.7	17.9	7.3	44.2		
4. Distribution main	-	-	-	8.4	10.7	13.6	4.3	1.2	38.2		
5. Service reservoir	-	-	-	-	-	28.7	28.7	14.7	72.1		
6. Electric works	-	-	-	-	-	0.6	7.0	4.3	11.9		
Sub-total (1-6)	-	-	16.3	53.8	86.2	169.1	133.2	57.1	515.7		
7. Project office	-	-	12.0	-	-	-	-	-	12.0		
8. Land acquisition	-	-	6.0	29.6	-	-	-	-	35.6		
9. Office equipment	-	-	2.2	-	-	-	-	-	2.2		
10. Engineering	4.5	3.0	1.9	1.7	2.7	5.5	4.6	1.9	25.8		
11. Administration	5.5	3.4	0.6	1.9	3.1	6.2	5.1	2.0	27.8		
Sub-total (7-11)	10.0	6.4	22.7	33.2	5.8	11.7	9.7	3.9	103.4		
Base Cost (1-11)	10.0	6.4	39.0	87.0	92.0	180.8	142.9	61.0	619.1		
12. Physical contingency	1.0	0.6	3.9	8.7	9.2	18.1	14.3	6.1	61.9		
13. Price escalation	0.5	1.1	11.6	38.1	54.3	137.3	135.3	70.1	448.3		
Total Cost	11.5	8.1	54.5	133.8	155.5	336.2	292.5	137.2	1,129.3		

TABLE C.II-10 SCHEDULE OF EXPENDITURE - PHASE I/FOREIGN COST

	(Unit: Rs. Million)									
	1985	1986	1987	1988	1989	1990	1991	1992	Total	
1. Conduction main	-	-	9.9	33.4	37.9	38.4	43.3	14.9	177.8	
2. Water treatment plant	-	-	-	-	21.1	49.6	25.5	0.3	96.5	
3. Pumping station	-	-	-	-	0.6	17.8	18.6	8.2	45.2	
4. Distribution main	-	-	-	8.6	10.8	13.5	3.9	1.0	37.8	
5. Service reservoir	-	-	-	-	-	21.0	21.0	10.5	52.5	
6. Electric works	-	-	-	-	-	0.9	11.7	7.7	20.3	
Sub-total (1 to 6)	-	-	9.9	42.0	70.4	141.2	124.0	42.6	430.1	
7. Project office	-	-	-	-	-	-	-	-	-	
8. Land acquisition	-	-	-	-	-	-	-	-	-	
9. Office equipment	-	-	6.3	-	-	-	-	-	6.3	
10. Engineering	20.4	13.6	6.2	6.1	9.2	18.4	15.3	6.1	95.3	
11. Administration	-	-	-	-	-	-	-	-	-	
Sub-total (7 to 11)	20.4	13.6	12.5	6.1	9.2	18.4	15.3	6.1	101.6	
Base Cost (1 to 11)	20.4	13.6	22.4	48.1	79.6	159.6	139.3	48.7	531.7	
12. Physical contingency	2.0	1.4	2.2	4.8	8.0	16.0	13.9	4.9	53.2	
13. Price escalation	0.7	1.4	3.9	12.0	26.3	66.3	70.7	29.4	210.7	
Total Cost	23.1	16.4	28.5	64.9	113.9	241.9	223.9	83.0	795.6	

TABLE C.II-11 SCHEDULE OF EXPENDITURE - PHASE II

	(Unit: Rs. Million)				
	1992	1993	1994	1995	Total
1. Conduction main	-	-	-	-	-
2. Water treatment plant	-	37.7	43.9	19.6	101.2
3. Pumping station	-	4.0	4.3	2.1	10.4
4. Distribution main	19.5	19.5	19.5	6.5	65.0
5. Service reservoir	-	8.6	21.5	12.9	43.0
6. Electric works	-	-	2.4	1.0	3.4
Sub-total (1~6)	19.5	69.8	91.6	42.1	223.0
7. Project office	-	-	-	-	-
8. Land acquisition	-	-	-	-	-
9. Office equipment	-	-	-	-	-
10. Engineering	1.6	5.6	7.3	3.3	17.8
11. Administration	0.4	1.4	1.8	0.9	4.5
Sub-total (7~11)	2.0	7.0	9.1	4.2	22.3
Base Cost (1~11)	21.5	76.8	100.7	46.3	245.3
12. Physical contingency	2.1	7.7	10.1	4.6	24.5
13. Price escalation	18.7	79.9	123.7	65.9	288.2
Total Cost	42.3	164.4	234.5	116.8	558.0

TABLE C.II-12 SCHEDULE OF EXPENDITURE - PHASE II/LOCAL COST

	(Unit: Rs. Million)				
	1992	1993	1994	1995	Total
1. Conduction main	-	-	-	-	-
2. Water treatment plant	-	18.9	22.6	9.9	51.4
3. Pumping station	-	1.8	1.9	0.9	4.6
4. Distribution main	9.7	9.7	9.7	3.2	32.3
5. Service reservoir	-	5.3	13.2	7.9	26.4
6. Electric works	-	-	0.9	0.4	1.3
<u>Sub-total (1~6)</u>	<u>9.7</u>	<u>35.7</u>	<u>48.3</u>	<u>22.3</u>	<u>116.0</u>
7. Project office	-	-	-	-	-
8. Land acquisition	-	-	-	-	-
9. Office equipment	-	-	-	-	-
10. Engineering	0.3	1.1	1.5	0.7	3.6
11. Administration	0.4	1.4	1.8	0.9	4.5
<u>Sub-total (7~11)</u>	<u>0.7</u>	<u>2.5</u>	<u>3.3</u>	<u>1.6</u>	<u>8.1</u>
<u>Base Cost (1~11)</u>	<u>10.4</u>	<u>38.2</u>	<u>51.6</u>	<u>23.9</u>	<u>124.1</u>
12. Physical contingency	1.0	3.8	5.2	2.4	12.4
13. Price escalation	12.0	52.6	83.7	45.3	193.6
<u>Total Cost</u>	<u>23.4</u>	<u>94.6</u>	<u>140.5</u>	<u>71.6</u>	<u>330.1</u>

TABLE C.II-13 SCHEDULE OF EXPENDITURE - PHASE II/FOREIGN COST

	(Unit: Rs. Million)				
	1992	1993	1994	1995	Total
1. Conduction main	-	-	-	-	-
2. Water treatment plant	-	18.8	21.3	9.7	49.8
3. Pumping station	-	2.2	2.4	1.2	5.8
4. Distribution main	9.8	9.8	9.8	3.3	32.7
5. Service reservoir	-	3.3	8.3	5.0	16.6
6. Electric works	-	-	1.5	0.6	2.1
Sub-total (1 to 6)	9.8	34.1	43.3	19.8	107.0
7. Project office	-	-	-	-	-
8. Land acquisition	-	-	-	-	-
9. Office equipment	-	-	-	-	-
10. Engineering	1.3	4.5	5.8	2.6	14.2
11. Administration	-	-	-	-	-
Sub-total (7 to 11)	1.3	4.5	5.8	2.6	14.2
Base Cost (1 to 11)	11.1	38.6	49.1	22.4	121.2
12. Physical contingency	1.1	3.9	4.9	2.2	12.1
13. Price escalation	6.7	27.3	40.0	20.8	94.8
Total Cost	18.9	69.8	94.0	45.4	228.1

TABLE C.II-14 SCHEDULE OF EXPENDITURE - PHASE III

	(Unit: Rs. Million)		
	1998	1999	2000
			Total
1. Conduction main	-	-	-
2. Water treatment plant	29.0	43.4	5.5
3. Pumping station	2.3	2.4	1.2
4. Distribution main	-	-	-
5. Service reservoir	-	16.1	6.9
6. Electric works	-	1.0	0.5
Sub-total (1 to 6)	31.3	62.9	14.1
7. Project office	-	-	-
8. Land acquisition	-	-	-
9. Office equipment	-	-	-
10. Engineering	2.5	5.1	1.1
11. Administration	0.9	1.9	0.5
Sub-total (7 to 11)	3.4	7.0	1.6
Base Cost (1 to 11)	34.7	69.9	15.7
12. Physical contingency	3.4	7.0	1.6
13. Price escalation	72.2	170.4	42.1
Total Cost	110.3	247.3	59.4
			417.0

TABLE C.II-15 SCHEDULE OF EXPENDITURE - PHASE III/LOCAL COST

	(Unit: Rs. Million)			
	1998	1999	2000	Total
1. Conduction main	-	-	-	-
2. Water treatment plant	14.4	22.8	2.1	39.3
3. Pumping station	1.1	1.1	0.6	2.8
4. Distribution main	-	-	-	-
5. Service reservoir	-	10.0	4.3	14.3
6. Electric works	-	0.4	0.2	0.6
Sub-total (1~6)	<u>15.5</u>	<u>34.3</u>	<u>7.2</u>	<u>57.0</u>
7. Project office	-	-	-	-
8. Land acquisition	-	-	-	-
9. Office equipment	-	-	-	-
10. Engineering	0.5	1.1	0.2	1.8
11. Administration	0.9	1.9	0.5	3.3
Sub-total (7~11)	<u>1.4</u>	<u>3.0</u>	<u>0.7</u>	<u>5.1</u>
Base Cost (1~11)	<u>16.9</u>	<u>37.3</u>	<u>7.9</u>	<u>62.1</u>
12. Physical contingency	1.7	3.7	0.8	6.2
13. Price escalation	48.8	122.6	29.8	201.2
Total Cost	<u>67.4</u>	<u>163.6</u>	<u>38.5</u>	<u>269.5</u>

TABLE C.II-16 SCHEDULE OF EXPENDITURE - PHASE III/FOREIGN COST

(Unit: Rs. Million)

	<u>1998</u>	<u>1999</u>	<u>2000</u>	<u>Total</u>
1. Conduction main	-	-	-	-
2. Water treatment plant	14.6	20.6	3.4	38.6
3. Pumping station	1.2	1.3	0.6	3.1
4. Distribution main	-	-	-	-
5. Service reservoir	-	6.1	2.6	8.7
6. Electric works	-	0.6	0.3	0.9
Sub-total (1 to 6)	<u>15.8</u>	<u>28.6</u>	<u>6.9</u>	<u>51.3</u>
7. Project office	-	-	-	-
8. Land acquisition	-	-	-	-
9. Office equipment	-	-	-	-
10. Engineering	2.0	4.0	0.9	6.9
11. Administration	-	-	-	-
Sub-total (7 to 11)	<u>2.0</u>	<u>4.0</u>	<u>0.9</u>	<u>6.9</u>
Base Cost (1 to 11)	<u>17.8</u>	<u>32.6</u>	<u>7.8</u>	<u>58.2</u>
12. Physical contingency	1.7	3.3	0.8	5.8
13. Price escalation	23.4	47.8	12.6	83.8
Total Cost	<u>42.9</u>	<u>83.7</u>	<u>21.2</u>	<u>147.8</u>

TABLE C.II-17 COST ESTIMATE SUMMARY

(Unit: Rs. Million)			
<u>Item</u>	<u>Local</u>	<u>Foreign</u>	<u>Total</u>
<u>1. Conduction main</u>			
- Intake tower	10.6	7.9	18.5
- No.1 tunnel, D= 2.4m, L= 770m	16.8	11.4	28.2
- Pressure break basin	10.3	12.4	22.7
- Conduit, L= 106m	1.0	0.7	1.7
- No.2 tunnel, D= 2.4m, L= 11,480m	209.0	144.1	353.1
- Pipe line, PRCC, ϕ 1,650mm, L= 2 x 650m	2.0	1.3	3.3
<u>Total</u>	<u>249.7</u>	<u>177.8</u>	<u>427.5</u>
<u>2. Water treatment plant</u>			
- Civil works	107.5	80.0	187.5
- Buildings	17.9	12.0	29.9
- Pipe	11.5	12.0	23.5
- Mechanical plant	36.5	57.1	93.6
- Chemical system	14.2	13.7	27.9
- Instruments	2.7	10.1	12.8
<u>Total</u>	<u>190.3</u>	<u>184.9</u>	<u>375.2</u>
<u>3. Pumping station</u>			
- Civil works	3.2	1.5	4.7
- Building	4.3	2.9	7.2
- Pump and motor	44.1	49.7	93.8
<u>Total</u>	<u>51.6</u>	<u>54.1</u>	<u>105.7</u>

(Cont'd)

COST ESTIMATE SUMMARY (CONT.)

	(Unit: Rs. Million)		
<u>Item</u>	<u>Local</u>	<u>Foreign</u>	<u>Total</u>
4. <u>Distribution main</u>			
4.1 Low zone, L= 1,550m			
- Earth works	0.8	0.6	1.4
- Pipe, DIP, ϕ 800mm	5.0	4.7	9.7
<u>Sub-total (1)</u>	<u>5.8</u>	<u>5.3</u>	<u>11.1</u>
4.2 High zone, L= 2 x 1,530m			
- Earth works	1.1	0.9	2.0
- Pipe, DIP, ϕ 700mm	7.6	7.1	14.7
<u>Sub-total (2)</u>	<u>8.7</u>	<u>8.0</u>	<u>16.7</u>
4.3 Rawalpindi, L= 2 x 6,420m			
- Earth works	13.2	7.2	20.4
- Pipe, PRCC, ϕ 1,500mm	42.8	50.0	92.8
<u>Sub-total (3)</u>	<u>56.0</u>	<u>57.2</u>	<u>113.2</u>
<u>Total</u>	<u>70.5</u>	<u>70.5</u>	<u>141.0</u>
5. <u>Service reservoir</u>			
5.1 H-11 reservoir, V= 104,000m ³			
- Earth works	1.6	1.6	3.2
- Concrete works	38.4	15.0	53.4
- Pipe	23.1	24.7	47.8
<u>Sub-total (1)</u>	<u>63.1</u>	<u>41.3</u>	<u>104.4</u>
5.2 Gorla-2 reservoir 16,610m ³			
- Earth works	2.6	2.6	5.2
- Concrete works	5.8	4.6	10.4
- Prestressing works	6.3	2.3	8.6
- Pipe works	0.7	0.5	1.2
- Appurtenant works	1.2	1.6	2.8
<u>Sub-total (2)</u>	<u>16.6</u>	<u>11.6</u>	<u>28.2</u>

(Cont'd)

COST ESTIMATE SUMMARY (CONT.)

(Unit: Rs. Million)

<u>Item</u>	<u>Local</u>	<u>Foreign</u>	<u>Total</u>
5.3 Gorla-1 reservoir, V = 26,000m ³			
- Earth works	6.3	6.5	12.8
- Concrete works	9.5	7.6	17.1
- Prestressing works	10.0	3.6	13.6
- Pipe works	5.0	4.5	9.5
- Appurtenant works	2.3	2.7	5.0
<u>Sub-total (3)</u>	<u>33.1</u>	<u>24.9</u>	<u>58.0</u>
<u>Total</u>	<u>112.8</u>	<u>77.8</u>	<u>190.6</u>
6. <u>Electric works</u>			
- Transmission line, 11kV, 25km	2.9	4.7	7.6
- Sub-station and distribution	10.9	18.6	29.5
<u>Total</u>	<u>13.8</u>	<u>23.3</u>	<u>37.1</u>
<u>Base Cost (1 to 6)</u>	<u>688.7</u>	<u>588.4</u>	<u>1,277.1</u>

TABLE C.II-18 OPERATION AND MAINTENANCE

1. Electric power cost (Tariff B-3)

a. Pumping station

- Installed capacity	2,750 Kw
- Annual operation	7,008 hr
- Annual power consumption	19.27 Mwh
- Annual power charge	
Fixed charge	2,541 Rs.x10 ³
Energy charge	6,746 -do-
<u>Sub-total</u>	<u>9,287 -do-</u>

b. Water treatment plant

- Installed capacity	800 Kw
- Daily water treatment	442.5 m ³ x10 ³
- Daily power consumption	7,369 Kwh
- Annual water treatment	161.5 m ³ x10 ⁶
- Annual power charge	
Fixed charge	739 Rs.x10 ³
Energy charge	945 -do-
<u>Sub-total</u>	<u>1,684 -do-</u>

c. Total electric power cost 10,971 Rs.x10³

2. Chemical cost

a. Alum

- Daily consumption	8.85 ton
- Annual cost: Rs. 3,400x8.85x365	<u>10,982 Rs.x10³</u>

b. Chlorine

- Daily consumption	1,328 kg
- Annual cost (Rs. 3,400/900 kg)x1,328x365	<u>1,831 Rs.x10³</u>

c. Total chemical cost 12,813 Rs.x10³

TABLE C.II-19 REPLACEMENT COST

1.	<u>Water treatment plant</u>				(Rs. 1,000)
	a. Phase I				
	- Mechanical equipment: life span of 20 years				15,234
	- Chemical equipment: life span of 15 years				14,546
	b. Phase II				
	- Mechanical equipment: life span of 20 years				8,203
	- Chemical equipment: life span of 15 years				9,015
	c. Phase III				
	- Mechanical equipment: life span of 20 years				6,347
2.	<u>Pumping equipment (life span of 20 years)</u>				
	a. Phase I				27,086
	b. Phase II				8,993
	c. Phase III				5,354
3.	<u>Electric equipment (life span of 15 years)</u>				
	a. Phase I				48,953
	b. Phase II				19,713
	c. Phase III				7,363
4.	<u>Yearly replacement cost (Rs.10³)</u>				
	<u>Year</u>	<u>Phase I</u>	<u>Phase II</u>	<u>Phase III</u>	<u>Total</u>
	2006	63,499	-	-	63,499
	10	-	28,728	-	28,728
	11	42,320	-	-	42,320
	15	-	17,196	7,363	24,559
	20	-	-	11,701	11,701
	21	63,499	-	-	63,499
	25	-	28,728	-	28,728
	30	-	-	7,363	7,363
	31	42,320	-	-	42,320

TABLE C.II-20 SUMMARY OF COST ALLOCATION

(Unit: Rs. Million)

Item	Phase I		Phase II		Phase III	
	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.
1. <u>Islamabad</u>	325.8	453.9	70.4	102.6	45.4	79.7
		779.7		173.0		125.1
2. <u>Rawalpindi</u>	468.2	677.2	157.7	227.3	102.4	189.5
2.1. RMC	223.4	323.2	75.4	108.7	48.7	90.2
2.2. CB	244.8	354.0	82.3	118.6	53.7	99.3
		598.7		200.9		153.0
<u>Whole Project (1 + 2)</u>	794.0	1,131.1	228.1	329.9	147.8	269.2
Total		1,925.0		558.0		417.0

TABLE C.II-21 COST ALLOCATION OF PHASE I PROJECT

(Unit: Rs. Million)

Item	Islamabad (32.24%)		Rawalpindi (67.76%)				Total				
	FC	LC	RMC(47.70%)		CB(52.30%)		FC	LC			
			FC	LC	FC	LC					
1. Conduction Main	57.3	80.5	57.5	80.7	63.0	88.5	120.5	169.2	177.8	249.7	427.5
2. W. Treatt. Plant	31.1	32.1	31.2	32.2	34.2	35.3	65.4	67.5	96.5	99.6	196.1
3. Pumping Station	37.2	36.3	3.8	3.8	4.2	4.1	8.0	7.9	45.2	44.2	89.4
4. Distribution Main	9.3	10.2	13.6	13.4	15.0	14.6	28.6	28.0	37.9	38.2	76.1
5. Service Reservoir	26.1	36.4	11.8	17.8	12.9	19.6	24.7	37.4	50.8	73.8	124.6
6. Electric Works	16.7	9.8	1.7	1.0	1.9	1.1	3.6	2.1	20.3	11.9	32.2
<u>Sub-total</u>	<u>177.7</u>	<u>205.3</u>	<u>119.6</u>	<u>148.9</u>	<u>131.2</u>	<u>163.2</u>	<u>250.8</u>	<u>312.1</u>	<u>428.5</u>	<u>517.4</u>	<u>945.9</u>
(Ratio)	(40.5%)		(28.4%)		(31.1%)		(59.5%)				
7. Project Office	-	4.9	-	3.4	-	3.7	-	7.1	-	12.0	12.0
8. Land Acquisition	-	14.4	-	10.1	-	11.1	-	21.2	-	35.6	35.6
9. Office Equipment	2.6	0.9	1.8	0.6	1.9	0.7	3.7	1.3	6.3	2.2	8.5
10. Engineering	38.6	10.4	27.1	7.4	29.6	8.0	56.7	15.4	95.3	25.8	121.1
11. Administration	-	11.3	-	7.9	-	8.6	-	16.5	-	27.8	27.8
<u>Sub-total</u>	<u>41.2</u>	<u>41.9</u>	<u>28.9</u>	<u>29.4</u>	<u>31.5</u>	<u>32.1</u>	<u>60.4</u>	<u>61.5</u>	<u>101.6</u>	<u>103.4</u>	<u>205.0</u>
12. Contingencies	106.9	206.7	74.9	144.9	82.1	158.7	157.0	303.6	263.9	510.3	774.2
<u>Total</u>	<u>325.8</u>	<u>453.9</u>	<u>223.4</u>	<u>323.2</u>	<u>244.8</u>	<u>354.0</u>	<u>468.2</u>	<u>677.2</u>	<u>794.0</u>	<u>1,131.1</u>	<u>1,925.1</u>

Note: Allocation ratio: Islamabad = $33.00/102.37 \approx 0.3224$
 Rawalpindi = $69.37/102.37 \approx 0.6774$

FC; Foreign Cost, LC; Local Cost

TABLE C.II-22 COST ALLOCATION OF PHASE II PROJECT

Item	(Unit: Rs. Million)											
	Islamabad (32.24%)		RMS(47.70%)				Rawalpindi (67.76%)				Total	
	FC	LC	FC	LC	FC	LC	FC	LC	FC	LC	FC	LC
1. Conduction Main	-	-	-	-	-	-	-	-	-	-	-	-
2. W. Treatt. Plant	16.1	16.6	16.1	16.6	17.6	18.2	33.7	34.8	49.8	51.4	101.2	
3. Pumping Station	4.2	3.3	0.8	0.6	0.8	0.7	1.6	1.3	5.8	4.6	10.4	
4. Distribution Main	4.1	4.3	13.6	13.4	15.0	14.6	28.6	28.0	32.7	32.3	65.0	
5. Service Reservoir	7.0	11.2	4.6	7.3	5.0	7.9	9.6	15.2	16.6	26.4	43.0	
6. Electric Works	1.5	0.9	0.3	0.2	0.3	0.2	0.6	0.4	2.1	1.3	3.4	
Sub-total	32.9	36.3	35.4	38.1	38.7	41.6	74.1	79.7	107.0	116.0	223.0	
(Ratio)	(31.0%)		(33.0%)		(36.0%)		(69.0%)					
7. Project Office	-	-	-	-	-	-	-	-	-	-	-	-
8. Land Acquisition	-	-	-	-	-	-	-	-	-	-	-	-
9. Office Equipment	-	-	-	-	-	-	-	-	-	-	-	-
10. Engineering	4.4	1.1	4.7	1.2	5.1	1.3	9.8	2.5	14.2	3.6	17.8	
11. Administration	-	1.4	-	1.5	-	1.6	-	3.1	-	4.5	4.5	
Sub-total	4.4	2.5	4.7	2.7	5.1	2.9	9.8	5.6	14.2	8.1	22.3	
12. Contingencies	33.1	63.8	35.3	67.9	38.5	74.1	73.8	142.0	106.9	205.8	312.7	
Total	70.4	102.6	75.4	108.7	82.3	118.6	157.7	227.3	228.1	329.9	558.0	

Note: FC; Foreign Cost
LC; Local Cost

TABLE C.II-23 COST ALLOCATION OF PHASE III PROJECT

Item	Islamabad (32.24%)		Rawalpindi (67.76%)		Total	
	FC	LC	RMC(47.70%)		CB(52.30%)	
			FC	LC	FC	LC
1. Conduction Main	-	-	-	-	-	-
2. W. Treatt. Plant	12.4	12.7	12.5	12.7	13.7	13.9
3. Pumping Station	3.1	2.8	-	-	-	-
4. Distribution Main	-	-	-	-	-	-
5. Service Reservoir	-	-	4.1	6.8	4.6	7.5
6. Electric Works	0.9	0.6	-	-	-	-
<u>Sub-total</u>	<u>16.4</u>	<u>16.1</u>	<u>16.6</u>	<u>19.5</u>	<u>18.3</u>	<u>21.4</u>
(Ratio)	(30.0%)		(33.3%)		(36.7%)	(70.0%)
7. Project Office	-	-	-	-	-	-
8. Land Acquisition	-	-	-	-	-	-
9. Office Equipment	-	-	-	-	-	-
10. Engineering	2.1	0.5	2.3	0.6	2.5	0.7
11. Administration	-	1.0	-	1.1	-	1.2
<u>Sub-total</u>	<u>2.1</u>	<u>1.5</u>	<u>2.3</u>	<u>1.7</u>	<u>2.5</u>	<u>1.9</u>
12. Contingencies	26.9	62.1	29.8	69.0	32.9	76.0
<u>Total</u>	<u>45.4</u>	<u>79.7</u>	<u>48.7</u>	<u>90.2</u>	<u>53.7</u>	<u>99.3</u>
					<u>102.4</u>	<u>189.5</u>
					<u>147.8</u>	<u>269.2</u>
					<u>51.3</u>	<u>57.0</u>
					<u>38.6</u>	<u>39.3</u>
					<u>3.1</u>	<u>2.8</u>
					<u>6.9</u>	<u>8.7</u>
					<u>0.9</u>	<u>0.6</u>
					<u>51.3</u>	<u>57.0</u>
					<u>6.9</u>	<u>1.8</u>
					<u>3.3</u>	<u>3.3</u>
					<u>6.9</u>	<u>5.1</u>
					<u>207.1</u>	<u>296.7</u>
					<u>147.8</u>	<u>269.2</u>
					<u>57.0</u>	<u>108.3</u>
					<u>0.6</u>	<u>1.5</u>
					<u>14.3</u>	<u>23.0</u>
					<u>8.7</u>	<u>14.3</u>
					<u>26.2</u>	<u>26.6</u>
					<u>39.3</u>	<u>77.9</u>

(Unit: Rs. Million)

Note: FC; Foreign Cost
LC; Local Cost

CHAPTER III. OPERATION AND MAINTENANCE

CHAPTER III. OPERATION AND MAINTENANCE

3.1. Proposed Organization

The organizations of respective levels concerning Khanpur water supply are indicated in Figure C.III-1, C.III-2, C.III-3 and C.III-4 respectively.

3.2. Functions and Responsibilities

3.2.1. Boards

The Water Management Board on the Khanpur water will be organized consisting of the representatives of Ministry of Water and Power, Ministry of Agriculture, Ministry of Industry, Ministry of Defence, Capital Development Authority, Water and Power Development Authority, Government of Punjab and Government of NWFP. The major purpose of the board are to decide on water allocation of Khanpur water for respective consumers, to direct revision for seasonal fluctuation of water requirement and priority of water release from Khanpur reservoir during drought period, to decide on water charge revision if required and other political matters concerning Khanpur water.

Under the supervision of the water management board, Regional Water Supply System Operation and Maintenance Board (RWSSB), which will be consisted of Capital Development Authority (CDA), Public Health Engineering Department (PHED) of Punjab Government, Rawalpindi Municipal Corporation (MES), Cantonment Board (CB) and Military Engineering Services (MES), will be organized.

Major functions of RWSSB are to decide on treated water allocation and adjustment for common use water supply system between Islamabad and Rawalpindi, to decide on water charges and tariff system for respective consumers, to deliberate and evaluate annual operation and maintenance budget, to evaluate operation and maintenance activities on the water supply systems.

3.2.2. Committees

The Water Supply System Coordinating Committee on the Khanpur Water (CCKW) is established to undertake the following activities. Members of the CCKW consist of WAPDA, CDA, PHED, MRC, RCB, MES, Irrigation Department of Punjab and NWFP Government, POF and PIDC of Industry.

- To prepare annual operation and maintenance programmes on the Khanpur water
- To prepare annual water supply programmes including seasonal requirements
- To decide on and arrange detailed water release plan for each consumers based on the direction of Water Management Board on Khanpur water on the revision of water allocation and release schedules
- To evaluate annual operation and maintenance cost of raw water and treated water including repairing works for common use facilities
- To prepare annual and periodical assessment reports which will be directed by the Boards
- To function as working group for the Boards

Another committee concerned is Water Supply System Coordinating Committee on other water sources such as Simly and Rawal dams, groundwater developed in the twin cities and surface water in Islamabad area. The functions of this committee will be similar to those of CCKW.

3.2.3. Operation and Maintenance Offices

Under the control of regional water supply system operation and maintenance board and water supply system coordinating committee on Khanpur water, following three offices are proposed such as WAPDA Khanpur Dam O.M. Office, Islamabad Water Supply O.M. Office and Rawalpindi Water Supply O.M Office. Major function and responsibility of divisions in respective offices are described in this Appendix C.

A. WAPDA Khanpur Dam Operation/Maintenance Office

Under the WAPDA Superintendent, three divisions are organized such as Administration and Finance, Khanpur dam and Canal Control Division.

The Office, headed by the Superintendent of WAPDA will take care of overall operation and maintenance work on the Khanpur dam and left and Right Bank Main Canal as well as related appurtenant facilities including operation of intake tower, diversion facilities and head regulators along the main canals.

a. Administration and Finance Division

Under the division director, six sections are established such as Administration and Personal Services, Budget Formulation and Control, Revenue and Cost Control and Accounting, Bill and Collection, Procurement of Material, Education and Training.

1) Administration and Personal Services

- General affairs of the office
- Personal control and labour recruitment
- Other related activities of the office

2) Budget Formulation and Control

- Responsible for the formulation and control of yearly and monthly budgets related to the operation/maintenance of water supply systems
- To formulate revenue and expenditure budgets
- To check revenue and expenditure budgets against actual achievements
- To revise and restructure water tariff systems in collaboration with Revenue and Cost Control and Accounting Section

3) Revenue and Cost Control and Accounting

- To calculate the amount of revenue from water charges and other sources on monthly and yearly basis
- To check and analyse revenue achievements in comparison with budget
- To calculate the amount of costs incurred on operation/maintenance and labor/personnel on monthly and yearly basis
- To check and analyse actual expenditure in comparison with budget
- To regularly compile financial statements including profit and loss statement, cashflow statement and balance sheet
- To make recommendation on the revision and restructuring of water tariff systems

4) Bill and Collection

- Responsible for the issuance of bills and collection of charges related to water supply and relevant services
- To take charge of meter fixing for users

5) Procurement of Materials

- Responsible for the control of procurement and storing of materials and spares
- To perform quality control of material and equipment

6) Education and Training

- In charge of education and training of personnel so that they may acquire up-to-date knowledge and technology on engineering, machines, electricity, finance, accounting and management in connection with water supply

b. Khanpur Dam Division

Under the Division Director, four units sector are organized, such as Operation, Monitoring and Recording, Maintenance and Repairing, and Mechanics and Workshop

- To prepare seasonal water release schedule based on respective consumers' requirement and operation rule curve on the Khanpur reservoir
- To operate intake tower, head regulators at division work and main gate of spillway
- To monitor and record hydro-meteorological data and storage water in the reservoir
- To inspect and patrol dam and its appurtenant structures
- To survey and design required repairing and improving work on the dam and related appurtenants structures

- To maintain not only dam body and facilities but also overall the equipments and instruments related to the O & M works

c. Canal Control Division

Under the Division Director, three units sector are set up such as Operation and Recording, Maintenance and Repairing, and Terminal Control for Industry and Irrigation

- To prepare, evaluate and report water distribution schedule for the Irrigation and Industry water supply
- To operate the head regulator and check gate at distribution points
- To patrol and maintain the Left Bank Main Canal up to end point of the canal
- To plan maintenance, repairing and rehabilitation works within their territory systems
- To patrol both Left and Right Main Canal as well as branch and tertial canal system and to educate terminal consumers of irrigation and industry
- To record water distribution to respective consumers.

B. Islamabad Water Supply Operation/Maintenance Office

Under the CDA Superintendent, five divisions are organized such as Administration and Finance, Khanpur dam, Simly dam, Headwork and Tubewell, and Distribution Division.

The Office, headed by the Superintendent of CDA, will take care of overall operation and maintenance work on the water supply systems within Islamabad Capital area for the time being.

a. Administration and Finance Division

Under the division director six sections are established instead of existing CDA maintenance directorate, such as Administration and Personal Service, Budget Formation and Control, Revenue and Cost & Accounting, Bill and Collection, Procurement of Materials, and Education & Training.

Major functions and responsibilities are similar to those of WAPDA Khanpur Dam O & M Office Organization (Please refer to Item 3.1.).

b. Khanpur Dam Division

Under the division director, five sections are proposed such as Golra Water Treatment Plant, Pumping Station, Discharge and Conduction Main, Mechanics & Repairing, and Workshop.

- To coordinate water release plan from Khanpur dam and supply/production plan with concerned divisions and offices such as WAPDA Khanpur Dam O & M Office and Rawalpindi Water Supply System O & M Office
- To test and analyze raw water and to control water quality
- To operate and maintain the water treatment and pumping plants
- To monitor and record production and consumed materials and chemicals
- To patrol, maintain and operate pipeline main and valves
- To maintain and control the equipment, instrument and workshop

c. Simly Dam Division

Under the division director three sections such as Dam Operation and Monitoring, Simly Water Treatment Plant, and Conduction Main Maintenance are organized.

- To prepare seasonal water release schedule and reservoir operation rules
- To monitor and record hydro-meteorological data and storage water in the reservoir
- To inspect and patrol dam and its appurtenant structures
- To survey and design required repairing and improving work on the dam and related structures
- To test and analyze raw water and to control water quality
- To operate and maintain water treatment plant
- To monitor and record production and consumed materials and chemicals
- To patrol, maintain conduction main and service reservoirs

d. Head Work, Tubewell Division

Under the division director four sections such as Head Work and Water Treatment Tubewell and Sump Pump, Conduction Main Maintenance, and Mechanics & Workshop are organized.

- To operate and maintain head works, tubewell and sump pumps and water treatment plants
- To monitor and record production of water
- To analyze raw water and to control water quality
- To patrol, maintain conduction main and to operate valves along pipeline systems

e. Distribution Division

Under the division director, three sections are proposed such as Distribution Control, Service Reservoir Control and Patrolling & Maintenance.

- To control water distribution to each sectors and Rawalpindi area

- To maintain and patrol distribution main and distribution networks
- To instruct and promote saving water leakage and wastage

C. Rawalpindi Water Supply Operation/Maintenance Office

Under the PHED Superintendent four division such as Administration & Finance, Khanpur Dam, Rawal Dam, and Distribution Divisions are organized.

The office, headed by PHED superintendent, will take care of overall operation and maintenance works on the water supply systems upto main distribution points and instruct operation and maintenance manners for respective terminal consumer agencies concerned.

FIGURE C.III-1 PROPOSED ORGANIZATION CHART OF WATER SUPPLY SYSTEM OPERATION AND MAINTENANCE (1)




FIGURE C.III-2 PROPOSED ORGANIZATION CHART OF WATER SUPPLY SYSTEM OPERATION AND MAINTENANCE (2)




FIGURE C.III-3 PROPOSED ORGANIZATION CHART OF WATER SUPPLY SYSTEM OPERATION AND MAINTENANCE (3)





FIGURE C.III-4 PROPOSED ORGANIZATION CHART OF WATER SUPPLY SYSTEM OPERATION AND MAINTENANCE (4)



CHAPTER IV. PROJECT JUSTIFICATION

CHAPTER IV. PROJECT JUSTIFICATION

4.1. Evaluation of Socio-Economic Survey

The Study Team has conducted extensive house visit sampling investigations to determine the economic value per unitary consumption of water. They covered all project areas, namely, Islamabad, Rawalpindi City and Cantonment, and the number of samples reached approximately 3,000. Investigators visited domestic houses, public institutions and commercial/industrial establishments. An outcome of this on-the-spot inquiry survey is that the domestic and commercial/industrial users are willing to pay Rs. 6.21 and Rs. 3.01 per thousand gallons of water respectively. This, further, boils down to the weighted average figure of Rs. 5.37 per thousand gallons of water.

When analysis is confined to those consumers who voiced their satisfaction with the present water charges, the willingness to pay per thousand gallons of water works out to Rs. 6.80 and Rs. 5.62 for domestic and commercial/industrial users respectively, ultimately being rendered to Rs. 6.49 as the total average value.

Since those who are dissatisfied with the existing status of water supply, be it water charges or otherwise, will not express the true and real level of their willingness, the latter figures have been ultimately adopted as representing the unitary economic values of urban water. Those who are satisfied with the present water charges comprise 73.9% of the total consumers.

To calculate the total yearly economic value of the Khanpur water, the volume of the water to be consumed in a certain future year is multiplied by this unitary economic value of water.

However, the benefit of water will increase as years go by, even on the assumption that the volume of water to be supplied remain the same. This is because people attach more economic value per unitary consumption of water as their income grows. In economists' jargons, it is called the income elasticity of economic value of water. As a result of the surveys, it has been found that the elasticity is 50%, which means that when income increases by 10% the economic value of water will increase by 5%. This income elasticity factor has been integrated in the computer programs to determine the economic benefit of the supply of the Khanpur Dam urban water.

As one of other findings of house-visit investigations, monthly income per household is Rs. 2,937, Rs. 1,495 and Rs. 1,977 for Islamabad, Rawalpindi City and Rawalpindi Cantonment respectively. The total weighted average works out at Rs. 1,890. The number of household members is 6.18, 7.65 and 5.75 for the above areas in the same order, respectively. The total average is calculated at 6.61.

Table C.IV-1 summarizes the outcome of sampling surveys.

2. Weighted Average of Willingness to Pay

Items	Weighted Average of Willingness to Pay		
1. Domestic Water	Rs. 1.37/000 ℓ (Rs. 6.21 / 000 gal.)		
2. Com./Ind. Water	Rs. 0.66/000 ℓ (Rs. 3.01 / 000 gal.)		
3. Total Weighted Average	Rs. 1.18/000 ℓ (Rs. 5.37 / 000 gal.)		
Items	Islamabad	Rawalpindi	
		City	Cantonment
Willingness to Pay, Domestic Water	Rs.1.41/000 ℓ (Rs.6.43/000gal.)	Rs.0.63/000 ℓ (Rs.2.87/000gal.)	Rs.1.89/000 ℓ (Rs.8.59/000gal.)
Willingness to Pay, Com./Ind. Water	Rs.0.49/000 ℓ (Rs.2.21/000gal.)	Rs.0.44/000 ℓ (Rs.1.98/000gal.)	Rs.0.98/000 ℓ (Rs.4.47/000gal.)
Share on Khanpur Water	0.324	0.294	0.382
Share of Dom./Pub. Water	0.75	0.73	0.73
Share of Com./Ind. Water	0.25	0.27	0.27
Process for Calculation of Total Weighted Average	$\begin{aligned} &Rs.6.43 \times 0.324 \times 0.75 + Rs. 2.21 \times 0.324 \times 0.25 + \\ &Rs.2.87 \times 0.294 \times 0.73 + Rs. 1.98 \times 0.294 \times 0.27 + \\ &Rs.8.59 \times 0.382 \times 0.73 + Rs. 4.47 \times 0.382 \times 0.27 = \\ &Rs. 5.37/000 gal. = Rs. 1.18/000 \ell \end{aligned}$		

- Cont'd -

3. Weighted Average of Willingness to Pay for the Satisfied ^{1/}

Items	Weighted Average of Willingness to Pay		
1. Domestic Water	Rs. 1.50 / 000 ¢ (Rs. 6.80 / 000 gal.)		
2. Com./Ind. Water	Rs. 1.24 / 000 ¢ (Rs. 5.62 / 000 gal.)		
3 Total Weighted Average	Rs. 1.43 / 000 ¢ (Rs. 6.49 / 000 gal.)		
Items	Islamabad	Rawalpindi	
		City	Cantonment
Willingness to Pay, Domestic Water	Rs. 1.54/000 ¢ (Rs. 7.01/000 gal.)	Rs. 0.68/000 ¢ (Rs. 3.07/000 gal.)	Rs. 2.09/000 ¢ (Rs. 9.49/000 gal.)
Willingness to Pay, Com./Ind. Water	Rs. 1.29/000 ¢ (Rs. 5.87/000 gal.)	Rs. 1.04/000 ¢ (Rs. 4.71/000 gal.)	Rs. 1.34/000 ¢ (Rs. 6.11/000 gal.)
Share on Khanpur Water	0.324	0.294	0.382
Share of Dom./ Pub. Water	0.75	0.73	0.73
Share of Com./Ind. Water	0.25	0.23	0.23
Process for Calculation of Total Weighted Average	$\begin{aligned} &Rs. 7.01 \times 0.324 \times 0.75 + Rs. 5.87 \times 0.324 \times 0.25 + \\ &Rs. 3.07 \times 0.294 \times 0.73 + Rs. 4.71 \times 0.294 \times 0.27 + \\ &Rs. 9.49 \times 0.382 \times 0.73 + Rs. 6.11 \times 0.382 \times 0.27 = \\ &Rs. 6.49/000 gal. = Rs. 1.43/000 ¢ \end{aligned}$		

^{1/} the Satisfied : the Customers Who Are Satisfied with the Present Water Charges

- Cont'd -

4. Income Elasticity of Willingness to Pay per Thousand Gallons

Unit : Rs.

Items	Islamabad		City		Rawalpindi		Cantonment		Weighted Average	
	Wages/M	Willingness to Pay/000 gal.	Wages/M	Willingness to Pay/000 gal.	Wages/M	Willingness to Pay/000 gal.	Wages/M	Willingness to Pay/000 gal.	Wages/M	Willingness to Pay/000 gal.
	No.1	-	-	-	-	300	4.5	300	4.5	
2	-	-	750	2.7	750	7.1	750	7.1		
3	1,500	3.4	1,500	2.8	1,500	8.4	1,500	8.4		
4	2,500	5.4	2,500	2.9	2,500	9.8	2,500	9.8		
5	3,500	4.9	3,500	3.3	3,500	8.6	3,500	8.6		
6	4,500	6.8	4,500	3.6	4,500	7.2	4,500	7.2		
7	6,800	9.7	-	-	5,000	11.2	5,000	11.2		
Regression Equation	$Y=1.7789+0.00113X$ ^{2/}		$Y=2.4373+0.000244X$		$Y=6.0867+0.000786X$		$Y=3.6181+0.000739X$			
Corr. Coeff.	0.969		0.971		0.671					
Elasticity	0.652 (X=Rs. 2,937) 0.832 (X=Rs. 7,769) <u>4/</u>		0.130 (X=Rs. 1,495) 0.384 (X=Rs. 3,955) <u>4/</u>		0.203 (X=Rs. 1,977) 0.403 (X=Rs. 5,230) <u>4/</u>		0.279 (X=Rs. 1,890) 0.505 (X=Rs. 5,000) <u>4/</u>			

^{1/} Weighted : Shares on population in 1981, namely, 15%, 48% and 37% for Islamabad, Rawalpindi City and Rawalpindi Cantonment respectively.

^{2/} X: Wages/M ^{3/} $\frac{X \cdot dY}{Y \cdot dX}$

Y: Willingness to Pay/000 gal.

^{4/} Forecasted Monthly Wages in the Year 2000

4.2. Economic Analysis

The economic internal rate of return (EIRR) is a comprehensive index expressing the economic feasibility of a project. It integrates both capital investments and operation/maintenance costs aspects as well as time aspects of a project. Also, it is an assessment from the standpoint of national economy.

Annual benefits are computed by multiplying the volume of water to be sold in a given year by the unitary economic value of water (= Rs. 6.49/000 gal.). They are added together over the entire period of project life.

Project costs are composed of construction, operations/maintenance and replacement costs of Khanpur water storage, conduction, treatment and distribution facilities.

The construction costs, allocable to urban water, of Khanpur Dam including Left Bank Canals are incorporated in the costs. They amount to Rs. 876.106 million at 1984 prices. (Refer to Table C.IV-2)

Costs are estimated on a yearly basis and ultimately aggregated over the entire period of project life.

In totalizing yearly benefits and costs a discount rate that equalizes the present worths of both of them is sought and found. The value of EIRR for the Project has been computed at 6.2% as shown in Table C.IV-4. If the costs of distribution facilities including mains and networks are excluded from project costs because of uncertain elements involved in their estimation, then it works out at 5.5% as shown in Table C.IV-5. It is to be remembered that the unitary economic value of water is cut to Rs. 3.75 in calculating the second value of EIRR.

The costs over the entire period of project life amount to Rs. 6,410 million. When distribution costs are excluded they come to Rs. 3,705 million. The coefficient of 0.578 deriving from the cost ratio (3,705/6,410) is applied to Rs. 6.49, resulting in Rs. 3.75.

The EIRR value of 6.2% is low compared with standard levels of the rate of the opportunity cost of capital which fall between 8% and 15%. It is to be stressed, however, that 5% to 6% is a standard level as an EIRR value for a project in water supply sector.

The value is based upon the project benefits calculated from consumers' willingness to pay for water supply service. It is, as has been seen, Rs. 6.49 per thousand gallons. It is to be reminded that it expresses the very minimum of the unitary value of water, because such major benefits as health and time saving benefits may not be included in it, and also because indirect benefits in the form of far-reaching socio-economic impacts are excluded from it.

Supposing all the benefits deriving from water supply are quantitatively expressed, the unitary economic value of water will be pushed up to a much higher level, which in turn will bring up the value of EIRR to a proper and reasonable height.

It is not uncommon in a project for the construction of a social infrastructure and whose primary objective is the provision of public service to have an EIRR value in the range of 3 to 5%, and in spite of it to be judged feasible because of the magnitude of expected intangible benefits.

TABLE C.IV-2 ECONOMIC COST OF KHANPUR DAM CONSTRUCTION

Unit: Rs. million

Five Year Plan Period	Total <u>1/</u> Financial Costs	Economic <u>2/</u> Costs	Representative Year	Conversion Factor to 1984 Prices	Economic Costs at 1984 Prices
2	17.060	5.389	1963-64	5.447	29.354
3	71.351	22.538	1967-68	4.557	102.706
4	362.428	114.480	1972-73	3.387	387.744
5	750.913	237.192	1980-81	1.258	298.388
6	183.348	57.914	1984	1	57.914
	1,385.100	437.513			876.106

1/ Financial costs on the construction of the Khanpur Dam reservoir and the irrigation facilities (RBC + LBC), including direct, overhead and interest costs

2/ Economic costs on the construction of the Khanpur Dam reservoir and LBC, allocable to urban water supply

the Dam : 379.472

LBC : 58.041

437.513

(Interest and taxes have been deducted.)

Sources: Khanpur Dam P.C. 1 proforma,
Pakistan Economic Survey 1983-84
and the study by JICA

TABLE C.IV-3

ABBREVIATION TABLE

- ECONOMIC EVALUATION -

1) Input

CC	:	Construction Costs (Rs. million)
Mm	:	Number of Replacement Years
RY	:	Replacement Year
RC	:	Replacement Costs (Rs. million)
OMC	:	Operation & Maintenance Costs (Rs. million)

2) IRR Computation

DC.RT:	Discount Rate (= Discount Factor)
PW.BF:	Present Worth (= Present Value) of Benefit (Rs. million)
RW.CS:	Present Worth (= Present Value) of Cost (Rs. million)
NPW	: Net Present Worth (= Net Present Value) (Rs. million)
BC.RT:	Benefit Cost Ratio (%)

3) Cash Flow Analysis

YR	:	Year
BNFT	:	Benefit (Rs. million)
COST	:	Cost (Rs. million)
CSFL	:	Cash Flow (Rs. million)
AC.BF:	Accumulated Benefit (Rs. million)	
AC.CS:	Accumulated Cost (RS. million)	
AC.CF:	Accumulated Cash Flow (Rs. million)	

TABLE C.IV-4

ECONOMIC EVALUATION

< ECONOMIC EVALUATION >

< INPUT >

X= 0.06

CC 1= 33.418
 CC 2= 39.578
 CC 3= 65.631
 CC 4= 151.861
 CC 5= 303.69
 CC 6= 509.935
 CC 7= 396.121
 CC 8= 179.079
 CC 9= 107.904
 CC 10= 189.796
 CC 11= 173.673
 CC 12= 60.2
 CC 13= 0
 CC 14= 34.231
 CC 15= 108.468
 CC 16= 71.349
 CC 17= 25.5

< CASH FLOW ANALYSIS >

	YR	BNFT	COST	CSFL	AC.BF	AC.CS	AC.CF
	1	0	908	-908	0	908	-908
	2	0	35	-35	0	943	-943
	3	0	55	-55	0	998	-998
	4	0	120	-120	0	1118	-1118
	5	0	227	-227	0	1345	-1345
	6	0	359	-359	0	1705	-1705
	7	0	263	-263	0	1968	-1968
	8	58	133	-75	58	2101	-2043
	9	60	86	-26	119	2187	-2068
	10	62	129	-67	181	2316	-2136
	11	64	116	-52	244	2432	-2188
	12	84	58	26	328	2490	-2162
	13	86	27	59	415	2517	-2102
	14	88	40	48	503	2557	-2055
	15	90	70	20	592	2627	-2035
	16	92	52	40	684	2680	-1995
	17	107	35	73	792	2714	-1922
	18	109	24	84	900	2738	-1838
	19	106	23	84	1006	2761	-1754
	20	103	21	82	1110	2782	-1672
	21	101	20	81	1210	2802	-1592
	22	99	37	62	1309	2839	-1530
	23	96	18	78	1404	2856	-1452
	24	93	17	76	1497	2873	-1376
	25	91	16	75	1588	2889	-1301
	26	88	21	67	1676	2911	-1234
	27	86	23	63	1763	2933	-1171
	28	84	13	70	1846	2947	-1100
	29	82	13	69	1928	2959	-1031
	30	80	12	68	2008	2971	-964
	31	77	13	62	2085	2987	-901
	32	75	11	65	2161	2997	-836
	33	74	10	64	2234	3007	-773
	34	72	9	62	2306	3017	-711
	35	70	9	61	2376	3025	-650
	36	68	10	58	2444	3035	-592
	37	66	15	51	2510	3051	-541
	38	64	7	57	2574	3058	-484
	39	63	7	56	2637	3065	-428
	40	61	7	55	2698	3072	-373
	41	60	9	51	2758	3081	-323
	42	58	6	52	2816	3086	-271
	43	57	6	51	2872	3092	-220
	44	55	5	50	2927	3097	-170
	45	54	5	49	2981	3102	-121
	46	52	5	47	3033	3107	-74
	47	51	7	44	3084	3115	-30
	48	50	4	45	3134	3119	15
	49	49	4	44	3182	3123	59
	50	47	4	43	3229	3126	103

MM= 9
 RY 1= 22 RC 1= 63.499
 RY 2= 26 RC 2= 28.728
 RY 3= 27 RC 3= 42.32
 RY 4= 31 RC 4= 24.559
 RY 5= 36 RC 5= 11.701
 RY 6= 37 RC 6= 63.499
 RY 7= 41 RC 7= 28.728
 RY 8= 46 RC 8= 7.363
 RY 9= 47 RC 9= 42.32

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.050	4199	3401	798	123
0.060	3229	3126	103	103
0.070	2518	2900	-382	87

BC.RT= 103.2833508047

- Cont'd -

X= 0

< CASH FLOW ANALYSIS >

YR	BNFT	COST	CSFL	AC.BF	AC.CS	AC.CF
1	0	910	-910	0	910	-910
2	0	40	-40	0	949	-949
3	0	66	-66	0	1015	-1015
4	0	152	-152	0	1167	-1167
5	0	304	-304	0	1470	-1470
6	0	510	-510	0	1980	-1980
7	0	396	-396	0	2376	-2376
8	93	212	-119	93	2588	-2495
9	102	145	-44	195	2734	-2539
10	111	232	-121	306	2965	-2659
11	121	220	-99	427	3185	-2758
12	169	116	53	596	3301	-2705
13	184	57	127	780	3359	-2579
14	199	91	108	979	3450	-2471
15	215	168	48	1194	3618	-2424
16	233	133	100	1427	3751	-2323
17	289	93	196	1717	3844	-2127
18	309	68	241	2025	3912	-1886
19	321	68	253	2347	3980	-1633
20	332	68	264	2679	4048	-1370
21	343	68	274	3021	4117	-1095
22	354	132	222	3375	4248	-873
23	365	68	297	3740	4317	-576
24	377	68	309	4118	4385	-267
25	389	68	321	4507	4453	54
26	402	97	305	4909	4550	359
27	415	111	305	5324	4661	663
28	429	68	360	5753	4729	1024
29	443	68	374	6196	4797	1398
30	457	68	389	6653	4866	1787
31	472	93	379	7124	4959	2166
32	487	68	419	7612	5027	2585
33	503	68	435	8114	5095	3019
34	519	68	451	8634	5164	3470
35	536	68	468	9170	5232	3938
36	554	90	474	9724	5312	4412
37	572	132	440	10295	5444	4852
38	590	68	522	10886	5512	5374
39	609	68	541	11495	5580	5915
40	629	68	561	12124	5649	6476
41	650	97	553	12774	5746	7028
42	671	68	602	13444	5814	7631
43	693	68	624	14137	5882	8255
44	715	68	647	14852	5950	8902
45	738	68	670	15590	6019	9572
46	762	76	687	16353	6094	10258
47	787	111	676	17140	6205	10935
48	813	68	744	17952	6273	11679
49	839	68	771	18791	6342	12450
50	866	68	798	19658	6410	13248

BC.RT= 306.6802480636

TABLE C.IV-5 ECONOMIC EVALUATION
- EXCL. DISTRIBUTION -

< ECONOMIC EVALUATION >

< INPUT >

K= 0.05

CC 1= 33.418
CC 2= 21.978
CC 3= 58.131
CC 4= 126.761
CC 5= 160.09
CC 6= 300.832
CC 7= 242.721
CC 8= 94.9
CC 9= 65.604
CC 10= 87.096
CC 11= 39.573
CC 12= 0
CC 13= 0
CC 14= 34.231
CC 15= 68.368
CC 16= 15.349
CC 17= 0

< CASH FLOW ANALYSIS >

	YR	BNFT	COST	CSFL	AC.BF	AC.CS	AC.CF
	1	0	908	-908	0	908	-908
	2	0	20	-20	0	928	-928
	3	0	50	-50	0	978	-978
	4	0	104	-104	0	1082	-1082
	5	0	125	-125	0	1208	-1208
	6	0	224	-224	0	1432	-1432
	7	0	172	-172	0	1605	-1605
	8	36	71	-35	36	1676	-1640
	9	38	51	-13	74	1727	-1653
	10	39	63	-23	114	1790	-1677
	11	41	32	9	155	1822	-1668
	12	54	12	42	209	1835	-1626
	13	56	12	44	265	1847	-1581
	14	58	29	29	323	1875	-1552
	15	60	44	16	383	1919	-1536
	16	62	17	44	445	1937	-1492
	17	73	13	60	518	1949	-1431
	18	74	12	62	592	1961	-1369
	19	73	12	62	666	1973	-1308
	20	72	11	61	738	1984	-1246
	21	71	11	61	809	1995	-1186
	22	70	32	38	879	2026	-1148
	23	69	10	59	947	2036	-1089
	24	68	9	58	1015	2045	-1030
	25	66	9	58	1081	2054	-972
	26	65	16	49	1147	2070	-923
	27	64	19	45	1211	2089	-878
	28	63	7	56	1274	2097	-828
	29	62	7	55	1336	2104	-788
	30	61	7	54	1397	2111	-713
	31	60	12	48	1458	2123	-665
	32	59	6	53	1517	2129	-612
	33	58	6	52	1575	2135	-560
	34	57	6	52	1632	2140	-509
	35	56	5	51	1688	2146	-458
	36	55	7	48	1743	2153	-410
	37	54	15	39	1798	2168	-371
	38	53	5	49	1851	2173	-322
	39	53	4	48	1903	2177	-274
	40	52	4	47	1955	2181	-226
	41	51	3	43	2006	2189	-183
	42	50	4	46	2056	2193	-137
	43	49	4	45	2105	2196	-92
	44	48	3	45	2153	2200	-47
	45	47	3	44	2201	2203	-2
	46	47	4	43	2247	2207	40
	47	46	7	39	2293	2214	79
	48	45	3	42	2338	2217	121
	49	44	3	42	2383	2220	163
	50	44	3	41	2426	2222	204

GM 8= 10.71
GM 9= 13.771
GM 10= 15.301
GM 11= 15.301
GM 12= 21.996
GM 13= 22.739
GM 14= 22.739
GM 15= 22.739
GM 16= 22.739
GM 17= 28.725
GM 18= 29.39
GM 19= 29.39

NM= 9
RY 1= 22 RC 1= 63.499
RY 2= 26 RC 2= 29.728
RY 3= 27 RC 3= 42.32
RY 4= 31 RC 4= 24.559
RY 5= 36 RC 5= 11.701
RY 6= 37 RC 6= 63.499
RY 7= 41 RC 7= 29.728
RY 8= 46 RC 8= 7.363
RY 9= 47 RC 9= 42.32

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.050	2426	2222	204	109
0.060	1966	2086	-220	89

BC.RT= 109.1833214319

- Cont'd -

X= 0

< CASH FLOW ANALYSIS >

YR	BNFT	CBST	CSFL	AC.BF	AC.CS	AC.CF
1	0	910	-910	0	910	-910
2	0	22	-22	0	932	-932
3	0	58	-58	0	990	-990
4	0	127	-127	0	1116	-1116
5	0	160	-160	0	1276	-1276
6	0	301	-301	0	1577	-1577
7	0	243	-243	0	1820	-1820
8	54	106	-52	54	1926	-1872
9	59	79	-21	113	2005	-1893
10	64	102	-38	177	2107	-1931
11	70	55	15	247	2162	-1916
12	98	22	76	344	2184	-1840
13	106	23	83	450	2207	-1757
14	115	57	58	566	2264	-1698
15	125	91	33	690	2355	-1665
16	135	38	97	825	2393	-1568
17	167	29	138	992	2422	-1430
18	173	29	149	1170	2451	-1281
19	186	29	156	1356	2481	-1125
20	192	29	162	1548	2510	-962
21	198	29	169	1746	2539	-794
22	204	93	112	1950	2632	-682
23	211	29	182	2161	2662	-500
24	218	29	189	2379	2691	-312
25	225	29	196	2604	2721	-116
26	232	58	174	2837	2779	58
27	240	72	168	3076	2850	226
28	248	29	218	3324	2880	444
29	256	29	226	3580	2909	671
30	264	29	235	3844	2939	905
31	273	54	219	4117	2992	1124
32	281	29	252	4398	3022	1376
33	291	29	261	4689	3051	1637
34	300	29	271	4989	3081	1908
35	310	29	280	5299	3110	2189
36	320	41	279	5618	3151	2467
37	330	93	237	5949	3244	2705
38	341	29	312	6290	3273	3016
39	352	29	323	6642	3303	3339
40	364	29	334	7005	3332	3673
41	375	58	317	7381	3390	3991
42	388	29	358	7768	3420	4349
43	400	29	371	8169	3449	4719
44	413	29	384	8582	3478	5103
45	427	29	397	9008	3508	5500
46	440	37	404	9449	3545	5904
47	455	72	383	9904	3616	6287
48	470	29	440	10373	3646	6727
49	485	29	455	10858	3675	7183
50	501	29	471	11359	3705	7654

BC.RT= 306.6140296644

4.3. Water Tariff

Under the average water rate of Rs. 9.0 per thousand gallons a household pays the water bill corresponding to 2% of its monthly income. It is known that a household has the ability to pay for water 4% to 5% of its income. In this regard the rate is not an unduly hard one for the beneficiaries.

The water tariff proposed here is based on this average water rate and is so structured that up to a certain volume of water to be consumed unitary charge is low, and from there on unitary charge progressively goes up in parallel with the rise of water consumption.

As shown in Table C.IV-6, water charge per thousand gallons is Rs. 2 up to two thousand gallons of water to be consumed per month. If monthly water consumption exceeds two thousand gallons, for the third one thousand gallons Rs. 4 are charged. Likewise, for the fourth, fifth and sixth one thousand gallons Rs. 20, Rs. 36 and Rs. 46 are charged. For instance, when a household consumes five thousand gallons of water a month, it shall pay Rs. 64 (= 2 + 2 + 4 + 20 + 36).

This volume-related progressive water tariff is so intended that the notion of water as a basic human need will be met, and at the same time the costs of water supply service will be borne according to the size of income as is clearly evinced in the latter half of Table C.IV-6.

It is to be remembered that the water tariff will be applied only to domestic users.

It is true that the beneficiaries are able to pay the bill under the proposed average water rate of Rs. 9.0/000 gal. in terms of international standard. But, it is also true that the rate is

unusually high compared with the prevailing domestic standards. You can bring a horse to a pond, but you cannot force it to drink. However a water rate is theoretically justified, it is of little use if the beneficiaries are opposed to it. In that case, the average water rate will be Rs. 6.49 per thousand gallons since this is the rate they are willing to pay. And the difference of Rs. 2.51 per thousand gallons will be subsidized by the Government. The subsidy will amount to Rs. 67.7 million ($= 102.37 \text{ mgd} \times 1,000 \times 0.95 \times 0.95 \times 0.80 \times \text{Rs. } 2.51 \times 365/\text{days}/1,000,000$) per annum.

The water tariff under the average rate of Rs. 6.49/000 gal. will be structured as shown in Table C.IV-7.

TABLE C.IV-6 PROPOSED WATER TARIFF STRUCTURE

- AVERAGE RATE: Rs. 9.0/000 gal. -

1. Water Tariff Structure

Consumption (000 gal.)	0	1	2	3	4	5	6
Rate/000 gal. (Rs.)		2	2	4	20	36	46
Charges (Rs.)	0	2	4	8	28	64	110

2. Water Charges by Income

No.	Income (Rs./M)	Share of Household	Water Cons. /M(000 gal.)	Water Charges /M (Rs.)	Water Charge /000 gal.(Rs.)
1	300	4.4	2.9	7.6	2.6
2	750	22.3	3.6	20.0	5.6
3	1,500	38.0	4.1	31.6	7.7
4	2,500	17.9	4.3	38.8	9.0
5	3,500	9.8	4.8	56.8	11.8
6	4,500	3.5	5.1	68.6	13.5
7	5,270	4.1	7.1	160.1	22.5
<hr/>					
Ave.	1,890	-	4.2	37.6	9.0

TABLE C.IV-7 PROPOSED WATER TARIFF STRUCTURE

- AVERAGE RATE: Rs. 6.49/000 gal.-

1. Water Tariff Structure

Consumption (000 gal.)	0	1	2	3	4	5	6
Rate/000 gal (Rs.)		1.5	1.5	3	16	28	34
Charges (Rs.)	0	1.5	3	6	22	50	84

2. Water Charges by Income

No.	Income (Rs./M)	Share of Household	Water Cons. /M(000 gal.)	Water Charges /M (Rs.)	Water Charges /000 gal. (Rs.)
1	300	4.4	2.9	5.7	2.0
2	750	22.3	3.6	15.6	4.3
3	1,500	38.0	4.1	24.8	6.0
4	2,500	17.9	4.3	30.4	7.1
5	3,500	9.8	4.8	44.4	9.3
6	4,500	3.5	5.1	53.4	10.5
7	5,270	4.1	7.1	121.4	17.1
<hr/>					
Ave.	1,890	-	4.2	27.3	6.5

4.4. Financial Analysis

Financial analysis is an assessment of the financial situation of an organization directly involved in a project.

Project costs are composed of the costs of raw water, construction, operation/maintenance and replacement, whereas project benefits are water charges receipts. Incremental benefits result by subtracting the former from the latter.

4.4.1. Cash Flow Analysis

A. Costs

Raw water will be purchased from WAPDA at the rate of Rs. 2.77 per thousand gallons. This rate is necessary to cover the financial costs for the construction and operation maintenance of the Khanpur Dam. (Refer to Table C.IV-8) The volume of water to be supplied will be 51.185 MGD from 1992 to 1995, 76.778 MGD from 1996 to 2000 and 102.370 MGD from 2001 on.

The capital for the construction of Khanpur water conduction facilities will be invested during the construction period of 1985 to 2000. It will be borrowed from external and domestic sources. Lending terms for foreign exchange component will be 5% annual rate of interest and the payback period of thirty 30 years with 10 year grace period. Terms for local currency component will be 11% annual rate of interest and the payback period of 25 years with 5 year grace period.

The proposed lending terms on foreign loans are one of the standard cases for a project in the public sector. The terms on local loans are somewhat soft in that the annual rate of interest is by three points lower than the prevailing rate. They are supposed to be borne by the central government. Financial costs arise in the form of principal and interest to be repaid to the lenders.

The costs for the maintenance and operation of the facilities concerned will arise from 1992 when water will start to be supplied, recurring over the whole period of project life.

Lastly, the capital for the replacement of some equipment in pumping stations and treatment plant will be required during 50 years of project life.

B. Benefits

Benefits are calculated by multiplying the volume of water to be consumed by water rate. The average rate will be Rs. 9.0 per thousand gallons. From 1992 to 1995, 30.4 to 35.9 MGD, from 1996 to 2000, 48.6 to 59.0 MGD and from 2001 on, 70.9 to 73.9 MGD will be consumed. It is assumed that the rates of conveyance, treatment and distribution losses are 5%, 5% and 27 to 20% respectively.

The water rate of Rs. 9.0 per thousand gallons is theoretically appropriate and reasonable since it means that a household will pay water charges corresponding to 2% of its income. But, it cannot be denied that the proposed rate is very high compared with the existing water tariffs and charges. If the rate is difficult to be implemented, and the willingness to pay of Rs. 6.49 is adopted in its stead, the difference of Rs. 2.51 must be covered by subsidies.

C. Cash Flow

The third page of Table C.IV-10 shows the cash flow of the Project over 50 years of project life. It can be observed in the table that for 28 years since the commencement of the Project incremental benefits are negative, but from the 29th year on they are positive and increase as years progress. So far as accumulated incremental benefits are concerned, they continue to be negative until the 37th year. That is to say, the capital recovery period is 36 years.

Further, it is to be observed that at the end of the project life accumulated costs and benefits come to Rs. 17,040 million and Rs. 27,260 million respectively. It means that accumulated incremental benefits are Rs. 10,219 million, and the benefits/costs ratio is 160%.

4.4.2. Financial Analysis

A. Computation of FIRR

The primary objective of this study is to find out the optimum water conduction route from Khanpur to a service reservoir around Tomar. In this sense it is basically different from the ordinary water supply feasibility study, in which the costs of water distribution mains and networks are calculated based on the construction plan and time schedule, along with the costs of water transmission and treatment.

However, if the costs of distribution are not taken into account, discrepancy and imbalance arise between benefits and costs since the former is derived from the water price for end users. Thus, they have ultimately been incorporated in the project costs to calculate FIRR, although they may not be as firmly based as the costs of conduction and treatment. Preliminary estimates of the costs for the construction of distribution facilities are as shown in Table C.IV-12.

At the same time, the water price covering the costs up to service reservoir has been calculated in order to put benefits in a balanced position vis-a-vis "without distribution" costs, and from this approach FIRR has been computed.

FIRR(= financial internal rate of return) is a discount rate (= discount factor) at which the present worth (= present value) of financial costs equals that of financial benefits. That is to say, when the FIRR value is applied as the discount rate the accumulated incremental benefits in the cash flow table are rendered zero.

As shown in the first page of Table C.IV-10, the value of FIRR for the Khanpur water conduction facilities construction project works out to 6.6%.^{1/}

If distribution costs are excluded, and along with it water rate is proportionately cut from Rs. 9.0 to Rs. 6.0 per thousand gallons, the resultant FIRR value is put at 6.9% as shown in the first page of Table C.IV-11.

Generally speaking, a project can be said to be financially viable if the value of FIRR is beyond the annual rate of the opportunity cost of capital. It varies from one country to another, and from one period to another. It can be known from the prevailing annual rate of interest in bank loans. In Pakistan it is now around 14%.

What is to be stressed here is that the ultimate objective of the Project is to supply urban water to the public and industry, and in this sense it is basically different from an undertaking in the private sector.

If "no loss, no profit" principle is to be followed as a public project, theoretically the value of FIRR for the Project should be zero. However, to meet unexpected expenditure in the unforeseen future and to alleviate financial losses in the first half of project life, that is to say, to maintain financial safety and security a certain level of FIRR will be necessitated. It is to be determined side by side with water rate and lending terms on investment capital so as to keep a balance among them. Ultimately it settled down to about half the value of the prevailing bank rate in Pakistan.

Note: ^{1/} If the payment of interest is not incorporated in the project costs, the value of FIRR works out to 8.2%.

B. B/C Ratio and NPW

FIRR is a discount rate at which benefits to costs ratio is one, and the net present worth is zero as described above. At 0% discount rate B/C ratio is 160% and NPW Rs. 10,219 million as already observed. (The net present worth (= net present value) or NPW (= NPV) is another expression of accumulated incremental benefits).

B/C ratios and NPW at different discount rates falling between 5% and the FIRR value are as shown in the first page of Table C.IV-10.

TABLE C.IV-8

UNITARY CHARGE OF KHANPUR DAM WATER (URBAN)

1. Data & Information Concerned

- 1) Financial costs for the construction of
 the Dam (allocable to urban water supply): Rs. 622.332 million
 the LBC (allocable to urban water supply): Rs. 95.188 million

Total Rs. 717.520 million

- 2) Interest rate (annual) : 14%
 3) Economic life of the Dam & LBC : 55 Years
 4) Annual O/M costs as percentage : 0.5%
 of capital costs

2. Capital Recovery Costs (Annual)

$$\text{Rs. } 717.520 \text{ million} \times \frac{0.14 (1+0.14)^{55}}{(1+0.14)^{55} - 1} = \text{Rs. } 100.527 \text{ million}$$

3. Annual O/M Costs

Rs. 622.332 million x 0.005 = 3.112 million

4. Annual Supply of Raw Water

Rs. 102.37 MGD x 1000 x 365 = 37,365,050

thousand gal./year

5. Unitary Rate

$$\frac{\text{Rs. } 100,527 \text{ million} + \text{Rs. } 3.112 \text{ million}}{37,365,050 \text{ thousand gal.}}$$

= Rs. 2.77/000 gal. = Rs. 0.61/000 l

Source :based on the study by JICA

TABLE C.IV-9 ABBREVIATION TABLE

- FINANCIAL EVALUATION -

<u>Abbreviation</u>	<u>Meaning</u>
WP	Water Price per Thousand Gal. (Rs.)
CCF (Rs.mln)	Construction Cost, Foreign Exchange Component
CCL	Construction Cost, Local Currency Component (Rs.mln)
OM	Operations and Maintenance Cost (Rs.mln)
MM	Number of Replacement Years
RY	Replacement Year
RCF	Replacement Cost, Foreign Exchange Component (Rs.mln)
RCL	Replacement Cost, Local Currency Component (Rs.mln)
I1	Annual Interest Rate, Foreign Exchange Component
PB1	Payback Period, Foreign Exchange Component (Years)
G1	Grace Period, Foreign Exchange Component (Years)
I2	Annual Interest Rate, Local Currency Component
PB2	Payback Period, Local Currency Component (Years)
G2	Grace Period, Local Currency Component (Years)
DC.RT	Discount Rate
PW.BF	Present Worth, Benefit (Rs.mln)
PW.CW	Present Worth, Raw Water Cost (Rs.mln)
PW.CC1	Present Worth, Construction Cost-Foreign Exchange Component (Rs.mln)
PW.CC2	Present Worth, Construction Cost-Local Currency Component (Rs.mln)
PW.CC	Present Worth, Construction Cost (Rs.mln)
PW.RC	Present Worth, Replacement Cost (Rs.mln)
PW.OM	Present Worth, Operations and Maintenance Cost (Rs.mln)
PW.CS	Present Worth, Cost (Rs.mln)
PW.NPW	Net Present Worth (Rs.mln)
BC.RT	Benefit Cost Ratio (%)
X	Discount Rate
YR	Year
BNFT	Benefit (Rs.mln)

<u>Abbreviation</u>	<u>Meaning</u>
CW	Raw Water Cost (Rs.mln)
CC	Construction Cost (Rs.mln)
RC	Replacement Cost (Rs.mln)
OM	Operations and Maintenance Cost (Rs.mln)
COST	Cost (Rs.mln)
CSFL	Incremental Benefit (Rs.mln)
AC.BF	Accumulated Benefit (Rs.mln)
AC.CW	Accumulated Raw Water Cost (Rs.mln)
AC.CC	Accumulated Construction Cost (Rs.mln)
AC.RC	Accumulated Replacement Cost (Rs.mln)
AC.OM	Accumulated Operations and Maintenance Cost (Rs.mln)
AC.CS	Accumulated Cost (Rs.mln)
AC.CF	Accumulated Incremental Benefit (Rs.mln)

TABLE C.IV-10 FINANCIAL EVALUATION

[FINANCIAL EVALUATION]

< INPUT >

WP= 9

CCF 1 = 22.44	CCL 1 = 10.978
CCF 2 = 27.26	CCL 2 = 12.318
CCF 3 = 29.961	CCL 3 = 45.109
CCF 4 = 67.373	CCL 4 = 110.853
CCF 5 = 170.672	CCL 5 = 187.499
CCF 6 = 305.324	CCL 6 = 312.866
CCF 7 = 237.137	CCL 7 = 264.068
CCF 8 = 103.059	CCL 8 = 116.825
CCF 9 = 67.234	CCL 9 = 67.206
CCF 10 = 113.595	CCL 10 = 118.334
CCF 11 = 102.449	CCL 11 = 106.671
CCF 12 = 35	CCL 12 = 36
CCF 13 = 0	CCL 13 = 0
CCF 14 = 19.524	CCL 14 = 18.615
CCF 15 = 59.351	CCL 15 = 64.935
CCF 16 = 40.98	CCL 16 = 42.171
CCF 17 = 14.9	CCL 17 = 15.2

OM 8 = 32.81
 OM 9 = 37.371
 OM 10 = 42.001
 OM 11 = 46.301
 OM 12 = 55.796
 OM 13 = 57.239
 OM 14 = 57.239
 OM 15 = 59.339
 OM 16 = 61.439
 OM 17 = 67.425
 OM 18 = 68.19
 OM 19 = 68.296

MM= 9

RY 1 = 22	RCF 1 = 0	RCL 1 = 63.499
RY 2 = 26	RCF 2 = 0	RCL 2 = 28.728
RY 3 = 27	RCF 3 = 0	RCL 3 = 42.32
RY 4 = 31	RCF 4 = 0	RCL 4 = 24.559
RY 5 = 36	RCF 5 = 0	RCL 5 = 11.701
RY 6 = 37	RCF 6 = 0	RCL 6 = 63.499
RY 7 = 41	RCF 7 = 0	RCL 7 = 28.727
RY 8 = 46	RCF 8 = 0	RCL 8 = 7.363
RY 9 = 47	RCF 9 = 0	RCL 9 = 42.32

I1= 0.05 PB1= 30 G1= 10
 I2= 0.11 PB2= 25 G2= 5

< FIRR COMPUTATION >

DC. RT	PW. BF	PW. CW	PW. CC1	PW. CC2	PW. CC	PW. RC	PW. OM	PW. CS	NPW	BC. RT
0.050	5823	1094	1032	2308	3340	116	752	5304	+519	109
0.060	4477	876	863	1911	2774	81	605	4337	+139	103
0.070	3492	711	727	1590	2318	56	492	3579	-87	97

X= 0.07

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	QM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.DM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	2	0	0	2	-2	0	0	3	0	0	3	-3
3	0	0	3	0	0	3	-3	0	0	6	0	0	6	-6
4	0	0	5	0	0	5	-5	0	0	12	0	0	12	-12
5	0	0	11	0	0	11	-11	0	0	23	0	0	23	-23
6	0	0	22	0	0	22	-22	0	0	45	0	0	45	-45
7	0	0	29	0	0	29	-29	0	0	75	0	0	75	-75
8	75	30	36	0	19	65	-10	75	30	112	0	19	161	-86
9	76	28	48	0	20	97	-20	151	56	160	0	39	258	-106
10	78	26	58	0	21	116	-37	230	84	229	0	60	374	-144
11	79	24	99	0	21	145	-65	309	109	327	0	82	519	-209
12	104	34	118	0	24	177	-73	413	143	445	0	107	697	-283
13	105	32	121	0	23	177	-71	519	175	567	0	131	874	-354
14	107	30	120	0	22	172	-65	626	205	687	0	153	1047	-420
15	106	28	125	0	21	175	-67	735	234	813	0	175	1222	-487
16	109	26	130	0	20	177	-68	844	260	944	0	195	1400	-555
17	126	32	128	0	21	182	-55	971	293	1072	0	217	1592	-610
18	126	30	120	0	20	171	-44	1098	323	1192	0	237	1753	-655
19	123	28	114	0	18	161	-38	1221	352	1306	0	256	1915	-693
20	118	26	110	0	17	155	-36	1340	379	1417	0	273	2070	-730
21	114	24	106	0	16	147	-33	1455	404	1524	0	290	2218	-763
22	110	23	99	0	15	138	-27	1565	427	1623	0	305	2357	-791
23	106	21	92	0	14	128	-22	1672	449	1716	0	320	2486	-813
24	103	20	86	0	13	120	-16	1775	469	1802	0	333	2606	-830
25	99	19	80	0	12	112	-12	1875	488	1883	0	346	2718	-842
26	96	17	74	0	11	104	-8	1971	506	1957	0	357	2822	-850
27	92	16	68	0	10	98	-5	2064	523	2026	2	368	2920	-856
28	89	15	62	0	10	90	+0	2153	538	2088	4	379	3011	-857
29	86	14	54	0	9	80	+5	2239	553	2143	6	388	3091	-851
30	83	13	45	0	8	69	+13	2323	566	2188	7	397	3161	-838
31	80	12	33	0	8	57	+23	2403	579	2222	10	406	3218	-814
32	77	11	24	0	7	47	+30	2480	591	2246	13	414	3265	-784
33	74	11	19	0	7	41	+33	2555	602	2266	16	421	3306	-751
34	72	10	16	0	6	36	+35	2627	613	2282	19	428	3343	-715
35	69	9	11	0	6	30	+39	2697	622	2294	22	434	3373	-676
36	67	9	7	0	5	25	+41	2764	631	2301	25	440	3399	-634
37	64	8	5	0	5	21	+42	2829	640	2306	27	446	3421	-591
38	62	7	4	0	5	20	+42	2892	648	2311	30	451	3441	-548
39	60	7	3	0	4	18	+42	2952	655	2314	32	456	3459	-506
40	58	6	1	0	4	15	+42	3010	662	2316	35	460	3474	-464
41	56	6	0	0	4	13	+42	3066	668	2317	37	465	3488	-421
42	54	6	0	0	3	13	+40	3121	674	2317	40	469	3501	-380
43	52	5	0	0	3	12	+39	3173	680	2318	42	472	3514	-340
44	50	5	0	0	3	11	+38	3224	685	2318	45	476	3526	-301
45	48	4	0	0	3	10	+38	3272	690	2318	47	479	3536	-263
46	47	4	0	0	2	10	+36	3319	695	2318	50	482	3546	-226
47	45	4	0	0	2	8	+36	3365	699	2318	51	485	3555	-190
48	43	4	0	0	2	8	+34	3409	703	2318	53	488	3564	-155
49	42	3	0	0	2	7	+34	3451	707	2318	55	490	3571	-120
50	40	3	0	0	2	7	+33	3492	711	2318	56	492	3579	-87

-- Cont'd --

BC.RT= 97.569116904

X= 0

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	DM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	2	0	0	2	-2	0	0	3	0	0	3	-3
3	0	0	3	0	0	3	-3	0	0	7	0	0	7	-7
4	0	0	7	0	0	7	-7	0	0	14	0	0	14	-14
5	0	0	15	0	0	15	-15	0	0	30	0	0	30	-30
6	0	0	33	0	0	33	-33	0	0	64	0	0	64	-64
7	0	0	47	0	0	47	-47	0	0	112	0	0	112	-112
8	128	51	62	0	32	147	-18	128	51	174	0	32	259	-130
9	141	51	89	0	37	178	-37	270	103	264	0	70	438	-167
10	154	51	134	0	42	228	-74	424	155	399	0	112	666	-242
11	167	51	207	0	46	305	-137	591	207	606	0	158	971	-379
12	234	77	266	0	55	399	-165	826	284	872	0	214	1371	-545
13	254	77	292	0	57	427	-172	1081	382	1164	0	271	1798	-717
14	276	77	310	0	57	445	-169	1357	439	1475	0	328	2244	-886
15	298	77	346	0	59	483	-184	1656	517	1822	0	388	2727	-1071
16	323	77	385	0	61	524	-201	1979	595	2206	0	449	3252	-1273
17	401	103	404	0	67	575	-174	2380	698	2612	0	516	3828	-1447
18	429	103	407	0	69	579	-151	2808	602	3020	0	585	4407	-1598
19	445	103	412	0	69	584	-138	3254	905	3432	0	653	4991	-1737
20	460	103	429	0	69	601	-140	3714	1009	3862	0	721	5593	-1878
21	475	103	440	0	68	612	-137	4189	1112	4302	0	790	6205	-2015
22	490	103	442	0	68	614	-123	4680	1216	4745	0	858	6819	-2139
23	506	103	439	0	68	610	-104	5187	1319	5184	0	926	7430	-2243
24	523	103	436	0	68	608	-85	5710	1423	5621	0	994	8039	-2329
25	540	103	436	0	68	608	-68	6250	1526	6057	0	1063	8647	-2397
26	557	103	432	0	68	604	-47	6807	1630	6490	0	1131	9252	-2444
27	575	103	427	13	66	612	-37	7383	1733	6918	13	1199	9865	-2481
28	594	103	414	13	68	599	-5	7977	1837	7332	26	1268	10485	-2487
29	613	103	387	13	68	572	+41	8591	1940	7720	40	1336	11037	-2446
30	633	103	344	13	68	529	+104	9225	2044	8064	53	1404	11567	-2341
31	654	103	273	19	68	464	+159	9879	2147	8338	73	1472	12032	-2152
32	675	103	212	28	68	412	+262	10555	2251	8550	101	1541	12445	-1889
33	697	103	183	28	68	383	+314	11252	2354	8733	130	1609	12828	-1575
34	720	103	162	28	68	362	+357	11972	2458	8896	156	1677	13190	-1217
35	743	103	125	28	68	329	+417	12716	2561	9021	187	1746	13516	-799
36	767	103	84	33	68	290	+477	13484	2685	9106	220	1814	13806	-322
37	792	103	63	33	68	268	+523	14276	2768	9169	254	1882	14075	+201
38	818	103	56	33	68	262	+556	15095	2872	9226	288	1951	14337	+757
39	845	103	48	33	68	253	+591	15940	2975	9274	321	2019	14591	+1348
40	872	103	27	33	68	233	+639	16813	3079	9302	358	2087	14825	+1987
41	900	103	13	36	68	221	+679	17713	3162	9316	391	2155	15046	+2667
42	930	103	7	49	68	229	+700	18644	3286	9323	441	2224	15278	+3368
43	960	103	7	49	68	228	+731	19604	3389	9331	490	2292	15504	+4100
44	991	103	6	49	68	227	+764	20596	3493	9337	540	2360	15732	+4864
45	1023	103	2	49	68	224	+799	21619	3596	9340	589	2429	15956	+5653
46	1057	103	0	55	68	228	+828	22677	3700	9341	645	2497	16184	+6492
47	1091	103	0	42	68	214	+877	23768	3803	9341	687	2565	16398	+7369
48	1126	103	0	42	68	214	+912	24895	3907	9341	730	2634	16612	+8262
49	1163	103	0	42	68	214	+949	26059	4010	9341	772	2702	16826	+9232
50	1201	103	0	42	68	214	+987	27260	4114	9341	814	2770	17040	+10219

BC.RI= 159.972332403

TABLE C.IV-11 FINANCIAL EVALUATION
- EXCL. DISTRIBUTION -

[FINANCIAL EVALUATION]

< INPUT >

WP= 6

CCF 1 = 22.44	CCL 1 = 10.978
CCF 2 = 14.96	CCL 2 = 7.018
CCF 3 = 24.661	CCL 3 = 42.909
CCF 4 = 52.873	CCL 4 = 95.653
CCF 5 = 87.572	CCL 5 = 101.199
CCF 6 = 175.524	CCL 6 = 198.766
CCF 7 = 153.337	CCL 7 = 157.268
CCF 8 = 65.659	CCL 8 = 78.425
CCF 9 = 42.534	CCL 9 = 42.009
CCF 10 = 53.995	CCL 10 = 56.734
CCF 11 = 24.649	CCL 11 = 26.271
CCF 12 = 0	CCL 12 = 0
CCF 13 = 0	CCL 13 = 0
CCF 14 = 19.524	CCL 14 = 18.615
CCF 15 = 35.951	CCL 15 = 41.035
CCF 16 = 8.58	CCL 16 = 8.571
CCF 17 = 0	CCL 17 = 0

OM 8 = 10.71
OM 9 = 13.771
OM 10 = 15.301
OM 11 = 15.301
OM 12 = 21.996
OM 13 = 22.739
OM 14 = 22.739
OM 15 = 22.739
OM 16 = 22.739
OM 17 = 28.725
OM 18 = 29.39
OM 19 = 29.39

MM= 9

RY 1 = 22	RCF 1 = 0	RCL 1 = 63.499
RY 2 = 26	RCF 2 = 0	RCL 2 = 28.728
RY 3 = 27	RCF 3 = 0	RCL 3 = 42.32
RY 4 = 31	RCF 4 = 0	RCL 4 = 24.559
RY 5 = 36	RCF 5 = 0	RCL 5 = 11.701
RY 6 = 37	RCF 6 = 0	RCL 6 = 63.499
RY 7 = 41	RCF 7 = 0	RCL 7 = 28.727
RY 8 = 46	RCF 8 = 0	RCL 8 = 7.363
RY 9 = 47	RCF 9 = 0	RCL 9 = 42.32

I1= 0.05
I2= 0.11

PB1= 30
PB2= 25

G1= 10
G2= 5

< FIRR COMPUTATION >

DC. RT	PW. BF	PW. CW	PW. CC1	PW. CC2	PW. CC	PW. RC	PW. OM	PW. CS	NPW	BC. RT
0.050	3882	1094	584	1378	1965	116	309	3486	+396	111
0.060	2985	876	493	1147	1641	81	247	2846	+138	104
0.070	2328	711	417	960	1378	56	200	2346	-18	99

- Cont'd -

X= 0.07

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	OM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	1	0	0	1	-1	0	0	2	0	0	2	-2
3	0	0	2	0	0	2	-2	0	0	5	0	0	5	-5
4	0	0	4	0	0	4	-4	0	0	9	0	0	9	-9
5	0	0	7	0	0	7	-7	0	0	16	0	0	16	-16
6	0	0	14	0	0	14	-14	0	0	30	0	0	30	-30
7	0	0	18	0	0	18	-18	0	0	49	0	0	49	-49
8	50	30	24	0	6	61	-11	50	30	74	0	6	111	-61
9	51	28	35	0	7	71	-19	101	58	110	0	13	182	-80
10	52	26	45	0	7	79	-27	153	84	155	0	21	261	-108
11	53	24	63	0	7	95	-42	206	109	219	0	28	356	-150
12	69	34	74	0	9	118	-49	275	143	293	0	38	475	-199
13	70	32	76	0	9	118	-48	346	175	370	0	47	594	-247
14	71	30	76	0	8	115	-44	417	205	447	0	56	709	-291
15	72	28	78	0	8	114	-42	490	234	525	0	65	824	-334
16	73	26	77	0	7	111	-38	563	240	602	0	72	936	-373
17	84	32	74	0	9	116	-32	647	293	677	0	81	1052	-405
18	84	30	70	0	8	109	-25	732	323	748	0	90	1162	-430
19	82	28	67	0	8	103	-21	814	352	815	0	98	1266	-452
20	79	26	65	0	7	99	-20	893	379	881	0	106	1366	-472
21	76	24	61	0	7	93	-16	970	404	942	0	113	1459	-489
22	73	23	56	0	6	86	-13	1043	427	999	0	119	1546	-502
23	71	21	52	0	6	80	-9	1115	449	1052	0	124	1627	-512
24	68	20	48	0	5	75	-6	1183	469	1101	0	131	1703	-519
25	66	19	46	0	5	70	-4	1250	486	1147	0	137	1773	-523
26	64	17	42	0	5	65	-1	1314	506	1189	0	142	1838	-524
27	61	16	39	2	4	62	+0	1376	523	1226	2	147	1901	-525
28	59	15	34	2	4	56	+2	1435	538	1263	4	151	1958	-522
29	57	14	29	1	4	49	+7	1493	553	1293	4	155	2008	-515
30	55	13	24	1	3	43	+11	1548	566	1317	7	159	2051	-503
31	53	12	17	2	3	35	+17	1602	579	1334	10	163	2087	-485
32	51	11	12	3	3	30	+21	1653	591	1346	13	166	2118	-464
33	49	11	9	3	2	26	+23	1703	602	1355	16	169	2144	-441
34	48	10	7	2	2	23	+24	1751	613	1363	19	172	2168	-416
35	46	9	5	2	2	20	+26	1798	622	1368	22	175	2188	-390
36	44	9	3	2	2	17	+26	1843	631	1371	25	177	2206	-363
37	43	8	2	2	2	14	+27	1886	640	1373	27	180	2222	-335
38	41	7	1	2	2	14	+27	1928	648	1375	30	182	2236	-308
39	40	7	1	2	2	13	+27	1968	655	1377	32	184	2250	-281
40	38	6	0	2	1	11	+27	2007	662	1377	35	186	2261	-254
41	37	6	0	2	1	10	+26	2044	668	1377	37	188	2272	-227
42	36	6	0	2	1	10	+25	2080	674	1378	40	190	2283	-202
43	34	5	0	2	1	10	+24	2115	680	1378	42	191	2293	-177
44	33	5	0	2	1	9	+24	2149	685	1378	45	193	2303	-153
45	32	4	0	2	1	8	+23	2181	690	1378	47	194	2311	-129
46	31	4	0	2	1	8	+22	2213	695	1378	50	196	2320	-106
47	30	4	0	1	1	7	+22	2243	699	1378	51	197	2327	-83
48	29	4	0	1	1	6	+22	2272	703	1378	51	198	2334	-61
49	28	3	0	1	1	6	+21	2300	707	1378	55	199	2340	-39
50	27	3	0	1	0	5	+21	2328	711	1378	56	200	2346	-18

BC.RT= 99.2153295487

- Cont'd -

X= 0

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	DM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	1	0	0	1	-1	0	0	2	0	0	2	-2
3	0	0	3	0	0	3	-3	0	0	6	0	0	6	-6
4	0	0	5	0	0	5	-5	0	0	11	0	0	11	-11
5	0	0	10	0	0	10	-10	0	0	21	0	0	21	-21
6	0	0	21	0	0	21	-21	0	0	43	0	0	43	-43
7	0	0	30	0	0	30	-30	0	0	73	0	0	73	-73
8	95	51	42	0	10	105	-19	85	51	116	0	10	178	-92
9	94	51	65	0	13	130	-36	180	103	181	0	34	309	-129
10	102	51	89	0	15	155	-53	282	155	270	0	39	465	-182
11	111	51	133	0	15	200	-86	394	207	404	0	55	665	-271
12	156	77	167	0	21	267	-110	550	284	571	0	77	933	-382
13	169	77	185	0	22	285	-115	720	362	757	0	99	1219	-498
14	184	77	197	0	22	298	-114	904	439	954	0	122	1517	-612
15	199	77	215	0	22	315	-116	1104	517	1170	0	145	1833	-729
16	215	77	229	0	22	330	-114	1319	595	1400	0	168	2163	-843
17	267	103	236	0	28	348	-101	1587	698	1636	0	196	2532	-945
18	295	103	239	0	29	371	-85	1872	802	1875	0	226	2903	-1031
19	297	103	243	0	29	375	-78	2169	905	2118	0	255	3279	-1110
20	306	103	252	0	29	385	-78	2476	1009	2371	0	284	3665	-1188
21	316	103	254	0	29	387	-70	2793	1112	2625	0	314	4052	-1259
22	327	103	252	0	29	385	-58	3120	1216	2877	0	343	4437	-1317
23	337	103	252	0	29	383	-45	3458	1319	3128	0	373	4821	-1363
24	348	103	249	0	29	382	-33	3806	1423	3378	0	402	5203	-1397
25	360	103	249	0	29	382	-22	4166	1526	3628	0	431	5586	-1419
26	371	103	245	0	29	378	-7	4538	1630	3873	0	461	5965	-1426
27	383	103	242	13	29	388	-4	4922	1733	4116	13	490	6354	-1431
28	396	103	231	13	29	377	+16	5318	1837	4347	26	520	6731	-1413
29	409	103	209	13	29	355	+53	5727	1940	4557	40	549	7087	-1359
30	422	103	185	13	29	332	+90	6150	2044	4742	53	578	7419	-1269
31	436	103	140	19	29	293	+143	6586	2147	4883	73	608	7712	-1126
32	450	103	104	28	29	266	+184	7036	2251	4988	101	637	7978	-942
33	465	103	85	28	29	246	+218	7501	2354	5073	130	667	8225	-723
34	480	103	71	28	29	233	+246	7981	2458	5145	159	696	8458	-476
35	495	103	53	28	29	215	+280	8477	2561	5199	187	725	8673	-195
36	511	103	37	33	29	204	+307	8989	2665	5237	220	755	8878	+111
37	528	103	29	33	29	195	+332	9517	2768	5266	254	784	9074	+443
38	545	103	25	33	29	191	+353	10063	2872	5291	288	813	9265	+797
39	563	103	18	33	29	185	+377	10627	2975	5310	321	843	9451	+1175
40	581	103	7	33	29	173	+408	11208	3079	5317	355	872	9624	+1583
41	600	103	3	36	29	172	+427	11809	3182	5321	391	902	9797	+2011
42	620	103	3	36	29	166	+433	12429	3286	5325	441	931	9963	+2445
43	640	103	3	39	29	165	+454	13069	3389	5328	490	960	10169	+2899
44	661	103	2	49	29	164	+476	13730	3493	5330	540	990	10354	+3376
45	682	103	0	49	29	162	+499	14413	3596	5331	589	1019	10537	+3875
46	704	103	0	55	29	168	+516	15118	3700	5331	645	1049	10726	+4391
47	727	103	0	42	29	175	+552	15845	3803	5331	687	1078	10901	+4944
48	751	103	0	42	29	175	+576	16597	3907	5331	730	1107	11076	+5520
49	775	103	0	42	29	175	+600	17372	4010	5331	772	1137	11251	+6121
50	800	103	0	42	29	175	+625	18173	4114	5331	814	1166	11426	+6747

BC: RT= 159.04643745

4.5. Sensitivity Analysis

4.5.1. Sensitivity Analysis in Economic Evaluation

Sensitivity analysis has been conducted to see how the value of EIRR is affected if conditions and premises under which it is computed are changed. This is necessary because a project is a future undertaking and there are inevitably a lot of uncertainties in the future.

Firstly, an analysis has been made to observed the effect to EIRR if the completion of the first phase of construction works is delayed. As a result of the analysis it has been found that one year delay lowers EIRR by 0.1% to 6.1%, and 2 year delay brings down the index by 0.2% to 6.0%. This comparatively light negative impact of the delays in tunnel construction will be mainly accounted for by the fact that only 50% of Khanpur urban water will be supplied at the end of Phase I.

The second analysis is to find how it will affect EIRR if an overrun of construction costs occurs. The result reveals that the overrun by 10% reduces EIRR by 0.3% to 5.9%. If it is by 20%, the index goes down by 0.5% to 5.7%. It shows a considerable extent to which EIRR is affected if estimate of construction costs is not proper and exact. But the Study Team is confident that its estimate is correct and firm, and any overrunning will not happen.

The third analysis is based on the supposition that Khanpur water is not sold 100%. Supposing it is demanded by 90%, EIRR is reduced by 0.6% to 5.6%. If only 80% is sold, the feasibility index is further reduced by 1.3% to 4.9%. It testifies to the importance of the study of water demand and supply.

Lastly, an analysis has been performed, supposing the situation where all the negative aspects in the preceding three cases are combined together. One instance is the combination of one year completion delay of Phase I, 10% overrun of construction costs and water sale ratio of 90%. In the next one, two year delay, 20% overrun and water sale of 80% are put together.

Computation resulted in the EIRR value of 5.3% for the first instance, and 4.3% in the second.

If things go bad as in the two instances, the feasibility of the Project will be strongly affected, though not to the extent that it is rendered nil. Besides, it is improbable that things will turn out altogether adverse and negative.

4.5.2. Sensitivity Analysis in Financial Evaluation

Sensitivity analysis from financial standpoint has been made by changing the conditions upon which the value of FIRR is computed.

In the first place, the annual rate of interest on local currency component is presupposed to be a full 14%. As regard other factors in the lending terms and the average water rate, they are unchanged.

As a result of the analysis it has been discovered that under the lending terms of 14% annual rate of interest and the repayment period of 25 years with the grace period of 5 years for local component, and 5% annual rate of interest and the repayment period of 30 years with the grace period of 10 years for FEC, and the average water rate of Rs. 9.0 per thousand gallons, the value of FIRR is calculated at 4.1%.

This value itself is not to be argued about. The problem is the cashflow. As shown in the third page of Table C.IV-13 negative

incremental benefits exceeding Rs. 200 million appear consecutively for 13 years. It cannot but put financial strains on the water supply organization.

The objective of the second analysis is to find out the water rate that will produce the FIRR value of 6% to 7% under the same lending terms as in the first case. The result is that water rate of Rs. 10.5 per thousand gallons produces the FIRR of 6.5%. In other words, if the terms on local component is not attenuated, the beneficiaries will have to pay Rs. 1.5 more to make up for it.

In the third case, under the given water rate of Rs. 8.0, the interest rates on both components that will produce the FIRR of 6% to 7% have been sought. It has been found that under the water rate of Rs. 8.0 per thousand gallons, and the lending terms of 4% annual rate of interest and the payback period of 30 years with the grace period of 10 years for foreign exchange component, and 9% annual rate of interest and the payback period of 25 years with the grace period of 5 years for the local currency component, the value of EIRR is calculated at 6.8%. That is to say, if the water rate is cut by Rs. 1, interest rates on foreign exchange and local currency portions shall be cut by 1% and 2% respectively to retain the value of FIRR.

Lastly, it is clarified that if the water rate is further cut down to Rs. 6.5, interest rates on FC and LC must be lowered to 1% and 7% respectively to have the FIRR value of 6.6%.

TABLE C.IV-13 SENSITIVITY ANALYSIS - ECONOMIC EVALUATION

1. Completion Delay of Phase I

A. One Year Delay

121 KM(1)=0

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	13903	5441	8462	256
0.020	10034	4719	5315	213
0.030	7355	4169	3186	176
0.040	5475	3741	1734	146
0.050	4136	3401	735	122
0.060	3171	3126	44	101
0.070	2464	2900	-436	85

B. Two Year Delay

121 KM(1)=0; KM(2)=0

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	13810	5441	8369	254
0.020	9949	4719	5230	211
0.030	7277	4169	3108	175
0.040	5403	3741	1662	144
0.050	4071	3401	670	120
0.060	3110	3126	-16	99

2. Overrun of Construction Costs

A. Ten Percent

1260 COST=K+1.1*SC+SR+OM

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	13989	5668	8321	247
0.020	10114	4930	5184	205
0.030	7429	4365	3064	170
0.040	5543	3924	1619	141
0.050	4199	3572	628	118
0.060	3229	3286	-57	98

B. Twenty Percent

1260 COST=K+1.2*SC+SR+OM

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	13989	5895	8094	237
0.020	10114	5141	4973	197
0.030	7429	4561	2868	163
0.040	5543	4107	1436	135
0.050	4199	3742	457	112
0.060	3229	3445	-216	94

3. Demand Shortage

A. Ten Percent

1030 BENEFIT=(SBR1+SBR2)*0.9

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	12590	5441	7149	231
0.020	9102	4719	4383	193
0.030	6686	4169	2517	160
0.040	4989	3741	1247	133
0.050	3779	3401	378	111
0.060	2906	3126	-220	93

4. Combination of 1., 2. and 3.

A, 1.A., 2.A. and 3.A.

121 KW(1)=0

1260 COST=K+1.1*SC+SR+DM

1030 BENEFIT=(SBR1+SBR2)*0.9

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	12519	5668	6844	221
0.020	9031	4930	4101	189
0.030	6620	4365	2255	152
0.040	4927	3924	1004	126
0.050	3723	3572	151	104
0.060	2854	3286	-432	87

B. Twenty Percent

1020 BENEFIT=(SBR1+SBR2)*0.8

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	11191	5441	5750	206
0.020	8091	4719	3372	171
0.030	5943	4169	1774	143
0.040	4434	3741	693	119
0.050	3360	3401	-42	99

B. 1.B., 2.B. and 3.B.

121 KW(1)=0;KW(2)=0

1260 COST=K+1.2*SC+SR+DM

1030 BENEFIT=(SBR1+SBR2)*0.8

< IRR COMPUTATION >

DC.RT	PW.BF	PW.CS	NPW	BC.RT
0.010	11048	5895	5153	187
0.020	7959	5141	2819	155
0.030	5822	4561	1261	128
0.040	4323	4107	216	105
0.050	3257	3742	-486	87

TABLE C.IV-14 SENSITIVITY ANALYSIS-FINANCIAL EVALUATION

1. WP = Rs.9.0, I1 = 5%, I2 = 14%

[FINANCIAL EVALUATION]

< INPUT >

WP= 9

CCF 1 = 22.44	CCL 1 = 10.978
CCF 2 = 27.26	CCL 2 = 12.318
CCF 3 = 29.961	CCL 3 = 45.109
CCF 4 = 67.373	CCL 4 = 110.853
CCF 5 = 170.672	CCL 5 = 187.499
CCF 6 = 305.324	CCL 6 = 312.866
CCF 7 = 237.137	CCL 7 = 264.068
CCF 8 = 103.059	CCL 8 = 116.825
CCF 9 = 67.234	CCL 9 = 67.206
CCF 10 = 113.595	CCL 10 = 118.334
CCF 11 = 102.449	CCL 11 = 106.671
CCF 12 = 35	CCL 12 = 36
CCF 13 = 0	CCL 13 = 0
CCF 14 = 19.524	CCL 14 = 18.615
CCF 15 = 59.351	CCL 15 = 64.935
CCF 16 = 40.98	CCL 16 = 42.171
CCF 17 = 14.9	CCL 17 = 15.2

OM 8 = 32.81
OM 9 = 37.371
OM 10 = 42.001
OM 11 = 46.301
OM 12 = 55.796
OM 13 = 57.239
OM 14 = 57.239
OM 15 = 59.339
OM 16 = 61.439
OM 17 = 67.425
OM 18 = 68.19
OM 19 = 68.296

MM= 9

RY 1 = 22	RCF 1 = 0	RCL 1 = 63.499
RY 2 = 26	RCF 2 = 0	RCL 2 = 28.728
RY 3 = 27	RCF 3 = 0	RCL 3 = 42.32
RY 4 = 31	RCF 4 = 0	RCL 4 = 24.559
RY 5 = 36	RCF 5 = 0	RCL 5 = 11.701
RY 6 = 37	RCF 6 = 0	RCL 6 = 63.499
RY 7 = 41	RCF 7 = 0	RCL 7 = 28.727
RY 8 = 46	RCF 8 = 0	RCL 8 = 7.363
RY 9 = 47	RCF 9 = 0	RCL 9 = 42.32

I1= 0.05
I2= 0.14

PB1= 30
PB2= 25

G1= 10
G2= 5

< FIRR COMPUTATION >

DC. RT	PW. BF	PW. CW	PW. CC1	PW. CC2	PW. CC	PW. RC	PW. OM	PW. CS	NPW	BC. RT
0.030	10301	1776	1513	4703	6216	341	1210	9544	+757	107
0.040	7686	1384	1244	3850	5095	233	947	7660	+25	100
0.050	5823	1094	1032	3170	4203	160	752	6211	-387	93

X= 0.04

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	OM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	2	0	0	2	-2	0	0	3	0	0	3	-3
3	0	0	3	0	0	3	-3	0	0	6	0	0	6	-6
4	0	0	6	0	0	6	-6	0	0	13	0	0	13	-13
5	0	0	13	0	0	13	-13	0	0	26	0	0	26	-26
6	0	0	27	0	0	27	-27	0	0	53	0	0	53	-53
7	0	0	37	0	0	37	-37	0	0	91	0	0	91	-91
8	94	37	49	0	23	111	-17	94	37	140	0	23	202	-108
9	99	36	72	0	26	135	-34	193	74	212	0	50	338	-144
10	104	34	110	0	28	174	-69	297	109	324	0	78	512	-214
11	108	33	169	0	30	233	-124	406	142	493	0	108	745	-339
12	146	48	212	0	34	296	-149	552	191	706	0	143	1041	-488
13	153	46	225	0	34	306	-153	705	237	932	0	177	1348	-642
14	159	44	230	0	33	308	-149	865	282	1163	0	210	1657	-792
15	165	43	247	0	32	323	-157	1031	325	1411	0	243	1980	-949
16	172	41	263	0	32	337	-164	1203	367	1874	0	278	2318	-1114
17	205	53	264	0	34	351	-145	1409	420	1938	0	311	2670	-1260
18	211	51	255	0	33	340	-128	1421	471	2193	0	344	3010	-1388
19	211	49	248	0	32	330	-118	1832	520	2442	0	377	3340	-1507
20	210	47	249	0	31	327	-117	2042	567	2691	0	408	3667	-1625
21	208	45	245	0	29	321	-112	2251	613	2937	0	436	3989	-1737
22	207	43	237	0	28	310	-103	2458	656	3175	0	467	4299	-1840
23	205	41	227	0	27	296	-91	2663	698	3402	0	495	4596	-1932
24	204	40	217	0	26	284	-80	2867	739	3619	0	521	4880	-2013
25	202	38	209	0	25	273	-71	3070	778	3829	0	547	5154	-2084
26	201	37	199	0	24	261	-60	3271	815	4028	0	571	5416	-2144
27	199	35	189	6	23	255	-55	3471	851	4218	6	595	5671	-2200
28	198	34	174	6	22	240	-41	3669	885	4395	12	618	5911	-2242
29	196	33	158	5	21	219	-22	3866	919	4553	18	640	6131	-2265
30	195	31	134	5	21	193	+2	4041	950	4688	24	661	6324	-2262
31	193	30	100	7	20	159	+34	4255	981	4789	32	681	6484	-2228
32	192	29	173	11	19	133	+58	4448	1011	4862	43	701	6618	-2170
33	191	28	60	10	18	118	+73	4639	1039	4923	53	719	6736	-2097
34	189	27	51	10	17	106	+83	4829	1066	4974	64	737	6843	-2014
35	188	26	37	9	17	90	+97	5017	1093	5011	74	755	6934	-1916
36	187	25	24	11	16	77	+109	5204	1118	5035	85	771	7011	-1806
37	185	24	17	10	16	66	+117	5390	1142	5053	96	787	7079	-1689
38	184	23	15	10	15	64	+119	5574	1165	5068	106	803	7144	-1569
39	183	22	12	10	14	59	+123	5757	1188	5081	116	817	7204	-1446
40	181	21	6	9	14	52	+129	5939	1209	5088	126	832	7256	-1316
41	180	20	2	9	13	47	+133	6120	1230	5090	136	845	7303	-1183
42	179	19	1	13	13	47	+131	6299	1250	5092	149	859	7351	-1052
43	177	19	1	12	12	45	+132	6477	1269	5093	162	871	7397	-920
44	176	18	1	12	12	43	+132	6653	1288	5094	174	883	7441	-787
45	175	17	0	11	11	41	+133	6828	1305	5095	185	895	7482	-653
46	174	17	0	12	11	40	+133	7002	1322	5095	198	906	7523	-520
47	172	16	0	9	10	34	+136	7175	1339	5095	207	917	7559	-384
48	171	15	0	8	10	34	+136	7347	1354	5095	216	927	7594	-247
49	170	15	0	8	9	33	+134	7517	1370	5095	224	937	7628	-111
50	169	14	0	8	9	32	+136	7686	1384	5095	233	947	7660	+25

- Cont'd -

BC.RT= 100.33442165P

X# 0

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	DM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.BM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	2	0	0	2	-2	0	0	3	0	0	3	-3
3	0	0	3	0	0	3	-3	0	0	7	0	0	7	-7
4	0	0	7	0	0	7	-7	0	0	14	0	0	14	-14
5	0	0	15	0	0	15	-15	0	0	30	0	0	30	-30
6	0	0	34	0	0	34	-34	0	0	65	0	0	65	-65
7	0	0	49	0	0	49	-49	0	0	114	0	0	114	-114
8	128	51	68	0	32	152	-23	128	51	182	0	32	267	-138
9	141	51	103	0	37	192	-51	270	403	296	0	70	460	-190
10	154	51	163	0	42	257	-103	424	155	450	0	112	717	-293
11	167	51	261	0	46	359	-191	591	207	711	0	158	1076	-485
12	234	77	340	0	55	474	-239	826	284	1052	0	271	2042	-724
13	254	77	376	0	57	511	-256	1081	362	1428	0	328	2597	-981
14	276	77	399	0	57	534	-258	1357	439	1828	0	398	3179	-1239
15	298	77	445	0	59	582	-283	1656	517	2273	0	449	3811	-1523
16	323	77	492	0	61	631	-308	1979	595	2766	0	516	4496	-1832
17	401	103	514	0	67	685	-284	2360	698	3281	0	595	5185	-2116
18	428	103	517	0	68	689	-260	2808	802	3798	0	653	5881	-2377
19	445	103	523	0	68	695	-249	3254	905	4322	0	721	6599	-2627
20	460	103	545	0	68	717	-257	3714	1009	4868	0	790	7331	-2884
21	475	103	560	0	68	732	-256	4189	1112	5428	0	858	8066	-3141
22	490	103	563	0	68	735	-244	4680	1216	5991	0	926	8798	-3385
23	506	103	560	0	68	731	-225	5187	1319	6552	0	994	9528	-3611
24	523	103	557	0	68	729	-206	5710	1423	7109	0	1063	10257	-3817
25	540	103	557	0	68	729	-189	6250	1526	7667	0	1131	10982	-4007
26	557	103	553	0	68	724	-167	6807	1630	8220	0	1199	11719	-4174
27	575	103	546	0	68	730	-161	7383	1733	8767	18	1268	12439	-4335
28	594	103	530	18	68	720	-125	7977	1837	9297	36	1336	13124	-4461
29	613	103	494	18	68	684	-70	8591	1940	9791	55	1404	13750	-4532
30	633	103	436	18	68	626	+7	9225	2044	10228	73	1472	14290	-4525
31	654	103	340	26	68	539	+115	9879	2147	10568	100	1541	14760	-4410
32	675	103	259	39	68	469	+205	10555	2251	10827	139	1609	15191	-4204
33	697	103	220	39	68	431	+266	11252	2354	11048	178	1677	15596	-3938
34	720	103	193	39	68	404	+315	11972	2458	11242	217	1746	15954	-3623
35	743	103	147	39	68	358	+384	12716	2561	11389	257	1814	16271	-2787
36	767	103	98	46	68	316	+500	13484	2665	11488	303	1882	16564	-2287
37	792	103	74	46	68	292	+502	14276	2768	11563	349	1951	16850	-1754
38	818	103	67	46	68	286	+566	15095	2875	11631	395	2019	17126	-1185
39	845	103	58	46	68	276	+621	15940	2975	11689	442	2087	17376	-563
40	872	103	32	46	68	250	+644	16813	3079	11721	488	2155	17612	+101
41	900	103	14	49	68	235	+682	17713	3182	11736	538	2224	17860	+783
42	930	103	7	49	68	247	+712	18644	3289	11744	606	2292	18108	+1496
43	960	103	7	49	68	247	+745	19604	3399	11751	674	2360	18354	+2241
44	991	103	2	49	68	246	+780	20596	3493	11757	742	2429	18597	+3022
45	1023	103	0	49	68	242	+808	21619	3596	11760	810	2497	18846	+3830
46	1057	103	0	49	68	249	+861	22677	3700	11761	886	2497	18846	+3830
47	1091	103	0	49	68	229	+897	23768	3803	11761	944	2565	19075	+4692
48	1126	103	0	49	68	229	+933	24895	3907	11761	1002	2634	19305	+5589
49	1163	103	0	49	68	229	+971	26059	4010	11761	1060	2702	19535	+6523
50	1201	103	0	49	68	229	+971	27260	4114	11761	1118	2770	19765	+7495

- Cont'd -

BC.RT= 137.920156617

2. WP= Rs.10.5, I1 = 5%, I2 = 14%

[FINANCIAL EVALUATION]

< INPUT >

WP= 10.5

CCF 1 = 22.44	CCL 1 = 10.978
CCF 2 = 27.26	CCL 2 = 12.318
CCF 3 = 29.961	CCL 3 = 45.109
CCF 4 = 67.373	CCL 4 = 110.853
CCF 5 = 170.672	CCL 5 = 187.499
CCF 6 = 305.324	CCL 6 = 312.866
CCF 7 = 237.137	CCL 7 = 264.068
CCF 8 = 103.059	CCL 8 = 116.825
CCF 9 = 67.234	CCL 9 = 67.206
CCF 10 = 113.595	CCL 10 = 118.334
CCF 11 = 102.449	CCL 11 = 106.671
CCF 12 = 35	CCL 12 = 36
CCF 13 = 0	CCL 13 = 0
CCF 14 = 19.524	CCL 14 = 18.615
CCF 15 = 59.351	CCL 15 = 64.935
CCF 16 = 40.98	CCL 16 = 42.171
CCF 17 = 14.9	CCL 17 = 15.2

OM 8 = 32.81
 OM 9 = 37.371
 OM 10 = 42.001
 OM 11 = 46.301
 OM 12 = 55.796
 OM 13 = 57.239
 OM 14 = 57.239
 OM 15 = 59.339
 OM 16 = 61.439
 OM 17 = 67.425
 OM 18 = 68.19
 OM 19 = 68.296

MM= 9

RY 1 = 22	RCF 1 = 0	RCL 1 = 63.499
RY 2 = 26	RCF 2 = 0	RCL 2 = 28.728
RY 3 = 27	RCF 3 = 0	RCL 3 = 42.32
RY 4 = 31	RCF 4 = 0	RCL 4 = 24.559
RY 5 = 36	RCF 5 = 0	RCL 5 = 11.701
RY 6 = 37	RCF 6 = 0	RCL 6 = 63.499
RY 7 = 41	RCF 7 = 0	RCL 7 = 28.727
RY 8 = 46	RCF 8 = 0	RCL 8 = 7.363
RY 9 = 47	RCF 9 = 0	RCL 9 = 42.32

I1= 0.05
 I2= 0.14

PB1= 30
 PB2= 25

G1= 10
 G2= 5

< FIRR COMPUTATION >

DC. RT	PW. BF	PW. CW	PW. CC1	PW. CC2	PW. CC	PW. RC	PW. OM	PW. CS	NPW	BC. RT
0.050	6794	1094	1032	3170	4203	160	752	6211	+583	109
0.060	5224	876	863	2625	3489	111	605	5082	+141	102
0.070	4074	711	727	2185	2913	77	492	4195	-120	97

XF 0.07

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	DM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	2	0	0	2	-2	0	0	3	0	0	3	-3
3	0	0	3	0	0	3	-3	0	0	6	0	0	6	-6
4	0	0	5	0	0	5	-5	0	0	12	0	0	12	-12
5	0	0	11	0	0	11	-11	0	0	23	0	0	23	-23
6	0	0	22	0	0	22	-22	0	0	46	0	0	46	-46
7	0	0	31	0	0	31	-31	0	0	77	0	0	77	-77
8	87	30	39	0	19	88	-1	87	30	116	0	19	166	-78
9	89	28	56	0	104	177	-15	177	59	173	0	39	270	-93
10	91	26	83	0	130	268	-39	268	84	256	0	60	401	-133
11	92	24	124	0	170	361	-77	361	109	360	0	82	572	-210
12	121	34	151	0	210	482	-89	482	143	531	0	107	783	-300
13	123	32	156	0	212	606	-88	606	175	687	0	131	995	-368
14	124	30	155	0	207	731	-82	731	205	843	0	153	1202	-471
15	126	28	161	0	211	857	-84	857	234	1004	0	175	1413	-556
16	127	26	166	0	214	985	-86	985	260	1171	0	195	1627	-642
17	148	32	162	0	216	1133	-68	1133	293	1334	0	217	1844	-711
18	147	30	153	0	203	1281	-56	1281	323	1487	0	237	2048	-767
19	143	28	144	0	192	1432	-48	1432	352	1632	0	256	2240	-815
20	138	26	141	0	185	1583	-46	1583	379	1773	0	273	2426	-862
21	133	24	135	0	176	1697	-42	1697	404	1908	0	290	2603	-905
22	129	23	127	0	165	1826	-36	1826	427	2035	0	305	2769	-942
23	124	21	118	0	154	1951	-29	1951	449	2153	0	320	2923	-971
24	120	20	109	0	143	2071	-23	2071	469	2263	0	333	3067	-995
25	116	19	102	0	134	2167	-18	2167	488	2366	0	346	3201	-1013
26	112	17	95	0	124	2300	-12	2300	506	2461	0	357	3326	-1026
27	108	16	87	0	118	2408	-10	2408	523	2549	2	368	3445	-1037
28	104	15	79	2	108	2512	-4	2512	538	2629	5	379	3553	-1041
29	100	14	69	2	96	2613	+4	2613	553	2699	6	388	3649	-1036
30	97	13	57	2	82	2710	+14	2710	566	2756	10	397	3732	-1021
31	93	12	41	3	66	2803	+27	2803	579	2798	14	406	3798	-994
32	90	11	29	4	53	2894	+36	2894	591	2828	18	414	3852	-957
33	87	11	23	4	46	2981	+41	2981	602	2851	22	421	3898	-916
34	84	10	19	3	40	3065	+43	3065	613	2871	26	428	3938	-873
35	81	9	13	3	33	3147	+47	3147	622	2884	30	434	3972	-825
36	78	8	8	3	27	3225	+50	3225	631	2893	34	440	4000	-774
37	75	6	6	3	23	3301	+51	3301	640	2899	38	446	4024	-723
38	73	7	5	3	21	3374	+51	3374	648	2904	41	451	4046	-671
39	70	7	4	3	19	3444	+50	3444	655	2908	44	456	4065	-621
40	67	6	2	3	16	3512	+51	3512	662	2911	48	460	4082	-570
41	65	6	0	3	14	3578	+50	3578	668	2912	51	465	4097	-519
42	63	6	0	3	14	3641	+48	3641	674	2912	55	469	4111	-470
43	61	5	0	3	13	3702	+47	3702	680	2912	59	472	4125	-422
44	58	5	0	3	12	3761	+46	3761	685	2913	62	476	4137	-376
45	56	4	0	3	11	3818	+45	3818	690	2913	65	479	4149	-331
46	54	4	0	3	11	3873	+43	3873	695	2913	68	482	4160	-287
47	52	4	0	2	9	3926	+43	3926	699	2913	71	485	4169	-243
48	51	4	0	2	8	3977	+42	3977	703	2913	73	488	4178	-201
49	49	3	0	2	8	4026	+40	4026	707	2913	75	490	4187	-160
50	47	3	0	1	7	4074	+39	4074	711	2913	77	492	4195	-120

- Cont'd -

BC.RT= 97.1182044491

X= 0

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	OM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	1	0	0	1	-1	0	0	1	0	0	1	-1
2	0	0	2	0	0	2	-2	0	0	3	0	0	3	-3
3	0	0	3	0	0	3	-3	0	0	7	0	0	7	-7
4	0	0	7	0	0	7	-7	0	0	14	0	0	14	-14
5	0	0	15	0	0	15	-15	0	0	30	0	0	30	-30
6	0	0	34	0	0	34	-34	0	0	65	0	0	65	-65
7	0	0	49	0	0	49	-49	0	0	114	0	0	114	-114
8	150	51	68	0	32	152	-2	150	51	182	0	32	267	-117
9	134	51	103	0	37	192	-28	315	103	286	0	70	460	-145
10	179	51	163	0	42	257	-77	494	155	450	0	112	717	-222
11	195	51	261	0	43	359	-163	690	207	711	0	158	1076	-386
12	273	77	340	0	55	474	-200	963	284	1052	0	214	1551	-587
13	297	77	376	0	57	511	-213	1261	362	1428	0	271	2062	-800
14	322	77	399	0	57	534	-212	1583	439	1828	0	328	2597	-1013
15	348	77	445	0	59	582	-233	1932	517	2273	0	385	3179	-1247
16	377	77	492	0	61	631	-254	2309	595	2766	0	449	3811	-1502
17	468	103	514	0	67	685	-217	2777	698	3281	0	516	4496	-1719
18	499	103	517	0	68	689	-189	3276	802	3798	0	585	5185	-1909
19	520	103	523	0	68	695	-175	3796	905	4322	0	653	5861	-2084
20	536	103	545	0	68	717	-180	4333	1009	4868	0	721	6599	-2265
21	554	103	560	0	68	732	-177	4888	1112	5428	0	790	7331	-2442
22	572	103	563	0	68	735	-162	5460	1216	5991	0	858	8066	-2605
23	591	103	550	0	68	731	-140	6051	1319	6552	0	926	8798	-2746
24	610	103	557	0	68	729	-119	6661	1423	7109	0	994	9528	-2866
25	630	103	557	0	68	729	-99	7291	1526	7667	0	1063	10257	-2965
26	650	103	553	0	68	724	-74	7842	1630	8220	0	1131	10982	-3039
27	671	103	546	18	68	737	-65	8614	1733	8767	18	1199	11719	-3105
28	693	103	530	18	68	720	-26	9307	1837	9297	36	1268	12439	-3132
29	716	103	494	18	68	684	+31	10023	1940	9791	55	1336	13124	-3100
30	739	103	436	18	68	626	+112	10762	2044	10228	73	1404	13750	-2957
31	763	103	340	26	68	539	+224	11526	2147	10568	100	1472	14290	-2763
32	788	103	259	39	68	469	+318	12314	2251	10827	139	1541	14760	-2445
33	813	103	220	39	68	431	+382	13128	2354	11048	178	1609	15191	-2083
34	840	103	193	39	68	404	+435	13968	2458	11242	217	1677	15596	-1627
35	867	103	147	39	68	358	+508	14835	2561	11389	257	1745	15954	-1118
36	895	103	98	46	68	316	+578	15731	2665	11488	303	1814	16271	-540
37	924	103	74	46	68	292	+632	16656	2768	11563	349	1882	16564	+92
38	954	103	67	46	68	286	+688	17611	2872	11631	395	1951	16850	+761
39	985	103	58	46	68	276	+709	18597	2975	11689	442	2019	17126	+1470
40	1017	103	32	46	68	250	+767	19615	3079	11721	488	2087	17376	+2238
41	1051	103	14	49	68	235	+815	20666	3182	11736	538	2155	17612	+3053
42	1085	103	7	49	68	247	+837	21751	3286	11744	606	2224	17860	+3890
43	1120	103	7	49	68	247	+873	22871	3389	11751	674	2292	18108	+4763
44	1156	103	4	49	68	246	+910	24028	3493	11757	742	2360	18354	+5674
45	1194	103	2	49	68	242	+984	25223	3596	11760	810	2429	18597	+6626
46	1233	103	0	49	68	249	+984	26456	3700	11761	886	2497	18846	+7610
47	1273	103	0	58	68	229	+1043	27730	3803	11761	944	2565	19075	+8654
48	1314	103	0	58	68	229	+1094	29044	3907	11761	1002	2634	19305	+9738
49	1357	103	0	58	68	229	+1127	30402	4010	11761	1060	2702	19535	+10866
50	1401	103	0	58	68	229	+1171	31803	4114	11761	1118	2770	19765	+12038

- Cont'd -

BC.RT= 160.906851951

3. WP = Rs.8, I1 = 4%, I2 = 9%

[FINANCIAL EVALUATION]

< INPUT >

WP= 8

CCF 1 = 22.44	CCL 1 = 10.978
CCF 2 = 27.26	CCL 2 = 12.318
CCF 3 = 29.961	CCL 3 = 45.109
CCF 4 = 67.373	CCL 4 = 110.853
CCF 5 = 170.672	CCL 5 = 187.499
CCF 6 = 305.324	CCL 6 = 312.866
CCF 7 = 237.137	CCL 7 = 264.068
CCF 8 = 103.059	CCL 8 = 116.825
CCF 9 = 67.234	CCL 9 = 67.204
CCF 10 = 113.595	CCL 10 = 118.334
CCF 11 = 102.449	CCL 11 = 106.671
CCF 12 = 35	CCL 12 = 36
CCF 13 = 0	CCL 13 = 0
CCF 14 = 19.524	CCL 14 = 18.615
CCF 15 = 59.351	CCL 15 = 64.935
CCF 16 = 40.98	CCL 16 = 42.171
CCF 17 = 14.9	CCL 17 = 15.2

OM 8 = 32.81
 OM 9 = 37.371
 OM 10 = 42.001
 OM 11 = 46.301
 OM 12 = 55.796
 OM 13 = 57.239
 OM 14 = 57.239
 OM 15 = 59.339
 OM 16 = 61.439
 OM 17 = 67.425
 OM 18 = 68.19
 OM 19 = 68.296

MM= 9

RY 1 = 22	RCF 1 = 0	RCL 1 = 63.499
RY 2 = 26	RCF 2 = 0	RCL 2 = 28.728
RY 3 = 27	RCF 3 = 0	RCL 3 = 42.32
RY 4 = 31	RCF 4 = 0	RCL 4 = 24.559
RY 5 = 36	RCF 5 = 0	RCL 5 = 11.701
RY 6 = 37	RCF 6 = 0	RCL 6 = 63.499
RY 7 = 41	RCF 7 = 0	RCL 7 = 28.727
RY 8 = 46	RCF 8 = 0	RCL 8 = 7.363
RY 9 = 47	RCF 9 = 0	RCL 9 = 42.32

I1= 0.04
 I2= 0.09

PB1= 30
 PB2= 25

G1= 10
 G2= 5

< FIRR COMPUTATION >

DC. RT	PW. BF	PW. CW	PW. CC1	PW. CC2	PW. CC	PW. RC	PW. OM	PW. CS	NPW	BC. RT
0.050	5176	1094	905	1838	2743	93	752	4683	+492	110
0.060	3980	876	753	1522	2275	64	605	3822	+158	104
0.070	3104	711	631	1267	1898	45	492	3147	-43	98

- Cont'd -

X= 0.07

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	DM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.OM	AC.CS	AC.CF
1	0	0	0	0	0	0	+0	0	0	0	0	0	0	+0
2	0	0	1	0	0	1	-1	0	0	2	0	0	2	-2
3	0	0	2	0	0	2	-2	0	0	5	0	0	5	-5
4	0	0	4	0	0	4	-4	0	0	9	0	0	9	-9
5	0	0	9	0	0	9	-9	0	0	18	0	0	18	-18
6	0	0	17	0	0	17	-17	0	0	36	0	0	36	-36
7	0	0	23	0	0	23	-23	0	0	60	0	0	60	-60
8	66	30	29	0	19	78	-11	66	30	89	0	19	138	-72
9	68	28	38	0	20	87	-19	134	58	128	0	39	226	-91
10	69	26	54	0	21	102	-32	204	84	183	0	60	328	-123
11	70	24	78	0	21	125	-54	275	109	261	0	82	453	-178
12	92	34	94	0	24	153	-61	367	143	356	0	107	607	-239
13	94	32	97	0	23	153	-58	461	175	453	0	131	760	-298
14	95	30	96	0	22	148	-53	597	205	549	0	153	909	-352
15	96	28	101	0	21	151	-54	653	234	651	0	175	1060	-406
16	97	26	106	0	20	153	-56	750	260	757	0	195	1213	-463
17	112	32	104	0	21	158	-46	863	293	862	0	217	1372	-509
18	112	30	99	0	20	149	-37	976	323	961	0	237	1522	-546
19	109	28	93	0	18	141	-31	1085	352	1055	0	256	1663	-578
20	105	26	91	0	17	135	-30	1191	379	1146	0	273	1799	-608
21	102	24	87	0	16	129	-27	1293	404	1234	0	290	1929	-635
22	98	23	82	0	15	121	-22	1391	427	1317	0	308	2050	-658
23	94	21	75	0	14	112	-17	1486	449	1393	0	320	2163	-676
24	91	20	71	0	13	105	-13	1578	469	1464	0	333	2268	-689
25	88	19	66	0	12	98	-9	1667	488	1531	0	345	2366	-699
26	85	17	61	0	11	91	-6	1752	506	1593	0	357	2459	-705
27	82	16	57	1	10	86	-4	1834	523	1650	1	368	2544	-709
28	79	15	51	1	10	79	+0	1914	538	1702	3	379	2623	-709
29	76	14	45	1	9	71	+5	1990	553	1747	4	388	2694	-704
30	73	13	37	1	8	61	+12	2064	566	1785	6	397	2756	-692
31	71	12	28	1	8	51	+19	2136	579	1814	8	406	2808	-672
32	68	11	21	2	7	43	+25	2205	591	1835	10	414	2851	-646
33	66	11	17	2	7	37	+28	2271	602	1852	13	421	2889	-618
34	64	10	14	2	6	33	+30	2335	613	1865	15	428	2923	-587
35	61	9	10	2	6	28	+33	2397	622	1877	17	434	2952	-554
36	59	9	6	2	5	24	+35	2457	631	1883	19	440	2976	-516
37	57	8	4	2	5	20	+36	2515	640	1888	22	446	2996	-481
38	55	7	3	2	5	18	+36	2570	648	1892	24	451	3015	-445
39	53	7	3	1	4	17	+36	2624	655	1895	26	456	3033	-408
40	51	6	1	1	4	14	+36	2676	662	1896	27	460	3048	-371
41	49	6	0	1	4	13	+36	2726	668	1897	29	465	3061	-335
42	48	6	0	2	3	12	+35	2774	674	1898	31	469	3074	-299
43	46	5	0	2	3	11	+34	2820	680	1898	34	472	3086	-265
44	44	4	0	2	3	11	+33	2865	685	1898	36	476	3097	-231
45	43	4	0	1	3	10	+33	2909	690	1898	38	479	3107	-198
46	41	4	0	1	2	9	+32	2951	695	1898	39	482	3116	-165
47	40	4	0	1	2	8	+31	2991	699	1898	41	485	3125	-134
48	38	4	0	1	2	7	+30	3030	703	1898	42	488	3133	-103
49	37	3	0	1	2	7	+30	3067	707	1898	43	490	3140	-73
50	36	3	0	1	2	6	+29	3104	711	1898	45	492	3147	-43

- Cont'd -

BC.RT= 98.606030225

X= 0

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	QM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.QM	AC.CS	AC.CF
1	0	0	0	0	0	0	+0	0	0	0	0	0	0	+0
2	0	0	1	0	0	1	-1	0	0	2	0	0	2	-2
3	0	0	3	0	0	3	-3	0	0	6	0	0	6	-6
4	0	0	5	0	0	5	-5	0	0	11	0	0	11	-11
5	0	0	12	0	0	12	-12	0	0	24	0	0	24	-24
6	0	0	26	0	0	26	-26	0	0	51	0	0	51	-51
7	0	0	38	0	0	38	-38	0	0	89	0	0	89	-89
8	114	51	50	0	32	134	-19	114	51	139	0	32	224	-109
9	125	51	71	0	37	160	-35	240	103	211	0	70	384	-144
10	137	51	107	0	42	201	-64	377	155	318	0	112	586	-209
11	149	51	165	0	46	263	-114	526	207	484	0	158	849	-323
12	208	77	212	0	55	346	-137	734	284	697	0	214	1194	-461
13	226	77	233	0	57	368	-142	961	362	930	0	271	1564	-603
14	245	77	249	0	57	384	-138	1206	439	1180	0	328	1948	-742
15	265	77	279	0	59	416	-151	1472	517	1459	0	388	2365	-893
16	287	77	313	0	61	453	-165	1759	595	1773	0	449	2818	-1059
17	356	103	331	0	67	502	-145	2116	698	2105	0	516	3320	-1204
18	380	103	334	0	68	506	-125	2496	802	2439	0	585	3827	-1330
19	392	103	339	0	68	511	-114	2892	905	2779	0	653	4338	-1445
20	409	103	353	0	68	525	-116	3301	1009	3132	0	721	4863	-1561
21	422	103	363	0	68	535	-113	3724	1112	3486	0	790	5399	-1674
22	436	103	365	0	68	537	-101	4160	1216	3862	0	858	5936	-1776
23	450	103	363	0	68	534	-84	4610	1319	4225	0	926	6471	-1860
24	464	103	361	0	68	533	-68	5075	1423	4566	0	994	7004	-1929
25	480	103	361	0	68	533	-53	5555	1526	4948	0	1063	7538	-1982
26	495	103	359	0	68	531	-35	6051	1630	5307	0	1131	8069	-2017
27	511	103	355	10	68	537	-25	6563	1733	5662	10	1199	8607	-2043
28	528	103	344	10	68	527	+1	7091	1837	6007	21	1268	9134	-2042
29	545	103	323	10	68	505	+39	7637	1940	6330	32	1336	9639	-2002
30	563	103	282	10	68	471	+92	8200	2044	6619	42	1404	10111	-1910
31	581	103	232	15	68	419	+162	8781	2147	6851	58	1472	10530	-1748
32	600	103	183	22	68	377	+222	9382	2251	7034	81	1541	10908	-1526
33	620	103	159	22	68	353	+266	10002	2354	7194	103	1609	11262	-1259
34	640	103	142	22	68	336	+303	10642	2458	7336	126	1677	11599	-956
35	660	103	111	22	68	305	+355	11303	2561	7447	149	1746	11904	-600
36	682	103	75	26	68	274	+408	11986	2665	7523	175	1814	12178	-192
37	704	103	56	26	68	254	+449	12690	2768	7579	202	1882	12433	+257
38	727	103	49	26	68	248	+479	13418	2872	7629	229	1951	12682	+736
39	751	103	42	26	68	241	+510	14169	2975	7671	256	2019	12923	+1246
40	775	103	25	26	68	223	+551	14944	3079	7696	283	2087	13146	+1798
41	800	103	12	28	68	212	+587	15745	3162	7709	311	2155	13359	+2385
42	826	103	7	39	68	218	+607	16572	3286	7716	351	2224	13578	+2993
43	853	103	7	39	68	218	+635	17426	3389	7724	390	2292	13797	+3628
44	881	103	6	39	68	217	+664	18307	3493	7730	430	2360	14014	+4292
45	910	103	2	39	68	214	+695	19217	3596	7733	469	2429	14229	+4988
46	939	103	0	44	68	216	+722	20157	3700	7734	514	2497	14445	+5711
47	970	103	0	33	68	205	+764	21127	3803	7734	547	2565	14651	+6476
48	1001	103	0	33	68	205	+796	22129	3907	7734	581	2634	14856	+7272
49	1034	103	0	33	68	205	+828	23163	4010	7734	615	2702	15062	+8101
50	1067	103	0	33	68	205	+862	24231	4114	7734	648	2770	15267	+8963

- Cont'd -

BC.RT= 158.711626911

4. WP= Rs.6.5, I1= 1%, I2= 7%

< INPUT >

WP= 6.5

CCF 1 = 22.44	CCL 1 = 10.978
CCF 2 = 27.26	CCL 2 = 12.318
CCF 3 = 29.961	CCL 3 = 45.109
CCF 4 = 67.373	CCL 4 = 110.853
CCF 5 = 170.672	CCL 5 = 187.499
CCF 6 = 305.324	CCL 6 = 312.866
CCF 7 = 237.137	CCL 7 = 264.068
CCF 8 = 103.059	CCL 8 = 116.825
CCF 9 = 67.234	CCL 9 = 67.206
CCF 10 = 113.595	CCL 10 = 118.334
CCF 11 = 102.449	CCL 11 = 106.671
CCF 12 = 35	CCL 12 = 36
CCF 13 = 0	CCL 13 = 0
CCF 14 = 19.524	CCL 14 = 18.615
CCF 15 = 59.351	CCL 15 = 64.935
CCF 16 = 40.98	CCL 16 = 42.171
CCF 17 = 14.9	CCL 17 = 15.2

OM 8 = 32.81
 OM 9 = 37.371
 OM 10 = 42.001
 OM 11 = 46.301
 OM 12 = 55.796
 OM 13 = 57.239
 OM 14 = 57.239
 OM 15 = 59.339
 OM 16 = 61.439
 OM 17 = 67.425
 OM 18 = 68.196
 OM 19 = 68.29

MM= 9

RY 1 = 22	RCF 1 = 0	RCL 1 = 63.499
RY 2 = 26	RCF 2 = 0	RCL 2 = 28.728
RY 3 = 27	RCF 3 = 0	RCL 3 = 42.32
RY 4 = 31	RCF 4 = 0	RCL 4 = 24.559
RY 5 = 36	RCF 5 = 0	RCL 5 = 11.701
RY 6 = 37	RCF 6 = 0	RCL 6 = 63.499
RY 7 = 41	RCF 7 = 0	RCL 7 = 28.727
RY 8 = 46	RCF 8 = 0	RCL 8 = 7.363
RY 9 = 47	RCF 9 = 0	RCL 9 = 42.32

I1= 0.01	PB1= 30	G1= 10
I2= 0.07	PB2= 25	G2= 5

< FIRR COMPUTATION >

DC. RT	PW. BF	PW. CW	PW. CC1	PW. CC2	PW. CC	PW. RC	PW. OM	PW. CS	NPW	BC. RT
0.050	4205	1094	522	1444	1966	73	752	3886	+319	108
0.060	3234	876	422	1195	1617	50	605	3150	+83	102
0.070	2522	711	343	995	1339	35	492	2578	-56	97

- Cont'd -

X= 0.06

< CASH FLOW ANALYSIS >

YR	BNFT	CW	CC	RC	DM	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.DM	AC.CS	AC.CF
1	0	0	0	0	0	0	0	0	0	0	0	0	0
2	0	0	0	0	0	0	0	0	0	0	0	0	0
3	0	0	0	0	0	0	0	0	1	0	0	1	-1
4	0	0	1	0	1	-1	0	0	2	0	0	2	-2
5	0	0	2	0	2	-2	0	0	4	0	0	4	-4
6	0	0	5	0	5	-5	0	0	10	0	0	10	-10
7	0	0	7	0	7	-7	0	0	18	0	0	18	-18
8	58	32	11	0	64	-6	58	32	29	0	20	82	-24
9	60	30	20	0	72	-12	118	63	49	0	42	155	-36
10	62	28	33	0	85	-23	180	91	83	0	66	241	-60
11	63	27	54	0	106	-42	244	119	137	0	90	347	-103
12	64	38	69	0	135	-51	328	157	207	0	118	483	-154
13	66	36	73	0	136	-50	415	194	281	0	145	620	-205
14	68	34	75	0	138	-48	503	228	356	0	170	755	-252
15	90	32	81	0	142	-48	593	260	437	0	195	893	-300
16	91	30	88	0	150	-50	685	291	525	0	219	1036	-351
17	107	38	89	0	152	-45	792	329	614	0	244	1189	-396
18	108	36	85	0	146	-37	901	366	700	0	268	1335	-434
19	106	34	82	0	139	-33	1007	400	783	0	290	1474	-467
20	103	32	82	0	135	-32	1111	432	865	0	312	1610	-499
21	100	30	80	0	131	-30	1212	463	946	0	332	1742	-529
22	98	28	77	0	124	-26	1310	491	1023	0	351	1866	-556
23	95	27	72	0	117	-21	1406	518	1096	0	369	1984	-577
24	93	25	68	0	110	-17	1499	544	1164	0	385	2095	-595
25	90	24	65	0	105	-14	1590	568	1229	0	401	2200	-609
26	88	22	61	0	99	-10	1679	591	1291	0	416	2299	-620
27	86	21	57	1	94	-8	1765	612	1348	1	431	2394	-629
28	83	20	53	1	88	-4	1849	633	1401	3	444	2482	-633
29	81	19	47	1	80	+1	1931	652	1449	4	457	2563	-632
30	79	18	40	1	71	+6	2010	670	1489	6	468	2634	-623
31	77	17	30	1	60	+16	2088	687	1519	8	480	2695	-607
32	75	16	23	2	52	+22	2163	703	1543	11	490	2748	-584
33	73	15	19	2	47	+26	2237	718	1562	13	500	2795	-557
34	71	14	16	2	42	+29	2309	732	1578	16	510	2837	-528
35	69	13	12	2	36	+32	2379	746	1591	18	518	2874	-495
36	68	12	7	2	31	+36	2447	758	1599	21	527	2906	-459
37	66	11	5	2	27	+38	2513	770	1604	23	535	2934	-420
38	64	11	4	2	25	+38	2578	782	1609	25	542	2959	-381
39	62	10	3	2	23	+39	2641	792	1612	28	549	2983	-342
40	61	10	2	2	20	+40	2702	802	1615	30	556	3004	-302
41	59	9	0	2	18	+40	2761	812	1616	32	562	3023	-261
42	58	8	0	2	16	+39	2820	821	1616	34	568	3041	-221
43	56	8	0	2	17	+39	2876	829	1617	37	574	3058	-181
44	55	7	0	2	16	+39	2931	837	1617	39	579	3074	-142
45	53	7	0	2	14	+38	2985	845	1617	42	584	3089	-103
46	52	7	0	2	14	+38	3037	852	1617	44	589	3103	-65
47	50	6	0	1	12	+38	3088	859	1617	46	593	3116	-27
48	49	6	0	1	12	+37	3138	865	1617	47	597	3128	+9
49	48	5	0	1	11	+36	3186	871	1617	49	601	3140	+46
50	47	5	0	1	10	+36	3234	876	1617	50	605	3150	+83

- Cont'd -

X# 0

< CASH FLOW ANALYSIS(S) >

YR	BNFT	CW	CC	RC	DM	COST	CSFL	AC.BF	AC.CW	AC.CC	AC.RC	AC.DM	AC.CS	AC.CF
1	0	0	0	0	0	0	+0	0	0	0	0	0	0	+0
2	0	0	0	0	0	0	+0	0	0	0	0	0	0	+0
3	0	0	0	0	0	0	+0	0	0	0	0	0	1	-1
4	0	0	1	0	0	1	-1	0	0	2	0	0	2	-2
5	0	0	3	0	0	3	-3	0	0	6	0	0	6	-6
6	0	0	7	0	0	7	-7	0	0	13	0	0	13	-13
7	0	0	11	0	0	11	-11	0	0	23	0	0	23	-23
8	93	51	16	0	32	103	-10	93	51	44	32	32	128	-35
9	101	51	34	0	37	123	-21	195	103	78	0	70	251	-56
10	111	51	59	0	42	153	-42	304	155	139	0	112	405	-99
11	121	51	103	0	46	201	-80	427	207	241	0	156	607	-179
12	169	77	140	0	55	273	-104	596	284	362	0	214	880	-284
13	184	77	157	0	57	292	-107	780	362	539	0	271	1172	-392
14	199	77	169	0	57	304	-105	980	439	708	0	328	1477	-497
15	215	77	194	0	59	331	-115	1196	517	903	0	368	1806	-612
16	233	77	223	0	61	363	-129	1429	595	1127	0	449	2171	-742
17	269	103	240	0	67	411	-121	1719	698	1367	0	516	2583	-863
18	309	103	245	0	68	416	-107	2028	802	1612	0	585	2999	-971
19	321	103	250	0	68	422	-100	2350	905	1863	0	653	3422	-1071
20	332	103	264	0	68	436	-103	2682	1009	2127	0	721	3858	-1175
21	343	103	277	0	68	446	-102	3026	1112	2401	0	790	4304	-1278
22	354	103	277	0	68	449	-94	3380	1216	2679	0	858	4753	-1373
23	365	103	276	0	68	448	-82	3746	1319	2956	0	926	5202	-1456
24	377	103	277	0	68	448	-71	4124	1423	3233	0	994	5651	-1527
25	390	103	279	0	68	451	-61	4514	1526	3512	0	1063	6102	-1588
26	402	103	279	0	68	451	-48	4916	1630	3792	0	1131	6553	-1637
27	415	103	277	8	68	458	-42	5332	1733	4070	8	1199	7011	-1679
28	429	103	271	8	68	451	-22	5761	1837	4341	16	1268	7463	-1701
29	443	103	255	8	68	435	+7	6205	1940	4596	25	1336	7899	-1694
30	457	103	230	8	68	410	+47	6662	2044	4827	33	1404	8309	-1646
31	472	103	167	12	68	371	+101	7135	2147	5014	45	1472	8680	-1545
32	487	103	149	17	68	339	+148	7623	2251	5164	63	1541	9020	-1396
33	503	103	132	17	68	321	+181	8127	2354	5296	91	1609	9342	-1215
34	520	103	119	17	68	309	+211	8647	2458	5415	99	1677	9651	-1004
35	537	103	94	17	68	284	+252	9184	2561	5510	117	1746	9935	-751
36	554	103	64	21	68	257	+297	9738	2665	5575	138	1814	10192	-454
37	572	103	47	21	68	240	+332	10311	2768	5622	159	1882	10433	-122
38	591	103	42	21	68	235	+356	10902	2872	5664	180	1950	10668	+233
39	610	103	36	21	68	228	+381	11512	2975	5701	201	2019	10897	+615
40	630	103	21	21	68	214	+415	12142	3079	5722	222	2087	11111	+1030
41	650	103	10	22	68	205	+445	12793	3182	5733	245	2155	11317	+1476
42	671	103	6	31	68	209	+462	13465	3286	5740	276	2224	11526	+1938
43	693	103	6	31	68	209	+483	14158	3389	5747	307	2292	11736	+2422
44	716	103	5	31	68	208	+507	14874	3493	5753	338	2360	11945	+2929
45	739	103	2	31	68	205	+533	15614	3596	5756	369	2428	12150	+3463
46	763	103	0	34	68	207	+556	16377	3700	5756	403	2497	12358	+4019
47	788	103	0	26	68	198	+590	17166	3803	5756	430	2565	12556	+4602
48	813	103	0	26	68	198	+615	17980	3907	5756	456	2633	12754	+5225
49	840	103	0	26	68	198	+642	18820	4010	5756	483	2702	12952	+5867
50	867	103	0	26	68	198	+669	19688	4114	5756	509	2770	13151	+6537

BC.RT= 149.707911986

CHAPTER V. RECOMMENDATIONS

CHAPTER V. RECOMMENDATIONS

5.1. Survey and Investigation

5.1.1. Topographic Survey and Mapping

The following topographic survey and mapping shall be undertaken prior to and of during detailed design stage of the project implementation by the Government of Pakistan.

A. Topographic Map along Tunnel Route

The mapping of tunnel route shall be made based on the following specifications prior to commencement of detailed design works. The mapping works will be able to produce from aerophotograph which has been made by the Survey of Pakistan.

Mapping area : 3.0 km width along proposed tunnel route
Scale of mapping: 1:5,000
Contour interval: 20 feet or 5 m

B. Topographic Survey and Mapping at Major Facilities

Topo-map for major facilities such as water treatment plant, pumping station, service reservoir, intake tower, vertical shaft of tunnel as well as appurtenant structure along pipeline shall be made with scale 1:500 to 1:1,000 during detailed design stage.

5.1.2. Geological Investigation

Geological survey for No.1 and No.2 tunnel and major facilities shall be undertaken during detailed design stage by the execution agencies of Pakistan and consultants. Summary of the survey items and quantities, concepts and specifications are described as under.

A. Geological survey of tunnels

The following survey such as seismic survey, drilling, permeability test, geological and hydro-geological reconnaissance and rock test shall be executed to clarify conditions of rock mass and groundwater along the proposed tunnel routes.

Seismic survey and geological reconnaissance shall be made to picturize approximate conditions of rock mass along the tunnel routes. Seismic survey shall be made by refractive method. Drilling of proposed holes shall be made to examine the conditions of rock mass around tunnel portals, vertical shafts and faults. Drilling shall be carried out to take all cores as much as possible with appropriate tools such as double core tubes, and all cores shall be preserved. Permeability test at the drilling hole and hydrogeological reconnaissance shall be made to confirm the conditions and quantity of groundwater around mountain area of proposed tunnel routes. Method of permeability test shall be executed principally to the length of 20 - 30 m of drilling holes around the tunnel center to be excavated by means of pressure test. At the vertical shaft sites, however, it shall be made to the full length of its drilling holes. The interval of the tests shall be principally 5 m.

The rock tests shall be carried out to know engineering characteristic of rocks, and shall include uniaxial pressure test, supersonic velocity measurement and specific gravity measurement.

The geological maps shall be prepared to cover the area of 500 m on both side of the tunnel routes with scale 1:5,000.

Hydrogeological reconnaissance shall clarify conditions of groundwater in the mountain around the tunnel routes through observation of discharge on the streams and springs taking account of rainfall data.

Locations of the survey area shown in Figure VII-1 and approximately quantities of the respective survey are shown as below:

(1) Seismic Survey

<u>Line No.</u>	<u>Length of Line</u>	<u>Location</u>
S-1	1,200 m	Along Tunnel-1
S-2	4,560	Along Tunnel-2-1
S-3	7,920	Along Tunnel-2-2 and 2-3
S-4	720	Depression North of Chhoi
S-5	720	Depression South of Chhoi
S-6	960	Across Vertical Shaft No.1
S-7	960	Across the fault near Sabra
S-8	720	Alluvium Area near Chauntra
S-9	720	Ditto
<u>Total</u>	<u>18,480</u>	

(2) Drilling and Permeability Test

<u>Line No.</u>	<u>Depth</u>	<u>No. of Test</u>	<u>Location</u>
B-1	15 m	3 times	Intake Tower
B-2	20	-	Tunnel-1 (Outlet)
B-3	70	6	Depression North of Chhoi
B-4	60	6	Depression South of Chhoi
B-5	120	24	Vertical Shaft No.1
B-6	75	14	Vertical Shaft No.2
B-7	60	6	Alluvium Area near Chauntra
B-8	50	6	Ditto
B-9	40	4	Ditto
<u>Total</u>	<u>510</u>	<u>69</u>	

Note: Standard penetration test shall be carried out to the unconsolidated layers of B-2, B-7, B-8 and B-9.

(3) Rock Tests

Rock tests shall be carried out to 18 samples in total for two samples from each holes.

B. Geological Survey of Major Facilities

The following geological survey of the major facilities shall be executed during detailed design stage.

(1) Drilling

<u>Facilities</u>	<u>No. of Hole and Length</u>	
1. Water Treatment Plant		
- Flocculation and Sedimentation Basin	8 holes	x 20 m = 160 m
- Rapid Sand Filter Basin	4 "	x 20 m = 80 m
- Administration Building	1 "	x 20 m = 20 m
- Clear Water Reservoir	2 "	x 20 m = 40 m
2. Pumping Station	2 "	x 25 m = 50 m
3. Service Reservoir (H-11)	4 "	x 20 m = 80 m
<u>Total</u>	<u>21 holes</u>	<u>430 m</u>

(2) Standard Penetration Test

The standard penetration test shall be made at respective holes with interval of each two meters.

(3) Physical Soil Test

The following items on the soil test shall also be carried out to 12 samples in total from six sites of proposed facilities.

<u>Item</u>	<u>Test Samples</u>
Water Content	6 holes x 2 samples
Liquid & Plastic Limits	Ditto
Grain Size Analysis	Ditto
Specific Gravity	Ditto
Consolidation Test	Ditto
Uniaxial Compression Test	Ditto




FIGURE C.V-1 LOCATION MAP OF GEOLOGICAL SURVEY OF PROPOSED TUNNEL ROUTE

CHAPTER VI. MAJOR RECORDS OF MEETING AND CONFIRMATIONS

CHAPTER VI. MAJOR RECORDS OF MEETING AND CONFIRMATIONS

6.1. General

Major records of discussion meeting and confirmations during course of field study in Pakistan are summarized in this chapter as a reference. The list of records and confirmations is shown as under.

<u>Reference No.</u>	<u>Description</u>
RDC-01	Construction schedule of Islamabad development
-02	Beneficiary area in Rawalpindi district
-03	Agreement of Khanpur water allocation in respective consumers
-04	Minutes of meeting on the water balance of Khanpur water (1)
-05	Ditto (2)
-06	Confirmation on the minute of RDC-05
-07	Confirmation of study result on water balance of Khanpur water
-08	Staged development plan of Khanpur water
-09	CDA comments on comparative study of conduction main and appurtenant structures on Khanpur water supply system
-10	Reply to CDA' comments on RDC-09