




B-B CROSS SECTION




D-D CROSS SECTION



C-C CROSS SECTION




E-E CROSS SECTION



DRY DOCK, SECTION (2)

PLAN
A1


UNIT IN METER




REPAIRING JETTY, PLAN

UNIT IN METER


A-A CROSS SECTION



B-B CROSS SECTION



REPAIRING JETTY, SECTION



TUG BOAT GENERAL ARRANGEMENT

4・10 Scope of the Construction:

4・10・1 Scope of the Plan:

At present, some 70 vessels of the PPFC fleet are inspected or serviced each year at the Gyaung Waing Fishing Boat Repair Center. However, with the planned improvement and expansion of the existing facilities and the introduction of new equipment, based on a grant-in-aid from Japan, the subject program is intended to upgrade the capacity of the Fishing Boat Repair Center to 100 vessels a year. The scope of the project is as shown below:

- 1) Site preparation for the Fishing Boat Repair Center.
- 2) Construction and Modification of facilities at this Center.
- 3) Provision of equipment and materials for the Center.
- 4) Provision services required to the implement and supervise the above project.
- 5) Carrying out the necessary procedures and obtaining the required permissions and approvals to implement the above plan.

4・10・2 Division of Responsibility between the Government of Burma and the Japanese Side:

Assuming the project is implemented on the basis of a grant-in-aid from Japan, the respective areas of responsibility for our two countries would be as follows:

(1) Responsibilities of and Services by the Burmese Government

- 1) Removal of all obstacles, including buildings, if necessary from the proposed site and necessary leveling.

- 2) Improvement and preparation of the existing facilities.
- 3) Procuring the necessary water supply.
- 4) Payment of all duties, commissions, and other charges in connection with the customs clearance of all materials and equipment imported into Burma for the subject project.
- 5) Obtaining tax and other exemptions for construction equipment, materials and Japanese technicians rendering services in Burma for this project.
- 6) Obtaining and providing permissions, clearances, licenses, and other privileges for persons from Japan, as required to implement this program.
- 7) Making budgetary provisions for the effective maintenance and repair of the facilities to be built under this grant-in-aid and for preparation of the required materials, parts, and furnishings.

(2) Responsibilities of the Japanese Government

- 1) Procurement of all construction equipment, materials and labor.
- 2) Ocean and inland shipment of materials and equipment imported for the construction program and the placing of transport insurance.
- 3) Consulting services in connection with the detail design, assistance in bidding tenders, and construction supervision.

SECTION 5 PROJECT IMPLEMENTATION

5 • 1 Implementing Organization:

When the subject Plan is implemented, the implementing organization for all aspects of the fishing vessel repair center will be PPFC, which falls under the jurisdiction of the Ministry of Livestock Breeding and Fishery. Direct responsibility for the project will lie with the Engineering Division of the Marine Fisheries Department, one of the principal PPFC divisions, which will take care of planning, procedural matters, and supervision and operation of the facilities upon completion. Construction, structural work, related facility checks, licenses and permits, and other technical operations will be the responsibility of the Civil Engineering Section of the Administration Department.

5 • 2 Construction Plan:

5 • 2 • 1 Construction Methods:

The construction works under this Plan will be carried out under a contract for design and construction between the PPFC and a corporation(s) of Japanese national. Based on detailed design prepared by the consultants, PPFC will file a construction application, which will be approved following a technical evaluation by the Civil Engineering Section. After establishment tender qualification, making tenders, and the evaluation of tender documents, the contracting organization(s) will be selected. The Construction contract is to be signed after approval by the cabinet of the Burmese government.

5 • 2 • 2 Construction Plan:

(1) Cooperating Organizations:

It should be noted, in connection with the construction program, that the subject project includes not only ordinary construction work but structural work in the river portion of the port area.

Ordinary construction will be under the jurisdiction of the Construction Corporation (C.C.), while structural works in the port area will be under that of the Burma Ports Corporation (BPC). Thus, it will be necessary to request the cooperation of both these organizations in the construction program. To prevent any loss of operating efficiency due to a split of orders, considerable advance discussion and review will be necessary.

The BPC feels that the construction of the buildings under this Plan, being related to the port structural work, should be well within its capability. There will, therefore, be a need in the implementing stage to make a selection of the cooperating organization on the basis of a study and examination of capabilities and operating conditions in both these corporations.

(2) Building Construction:

Steel frames and iron bars for the principal building structures will be procured from Japan, with the remaining finishing and basic materials obtained locally.

The main materials that can be obtained in Burma are such items as cement, aggregate, brick, timber, and corrugated slate sheets. However, since aggregate for concrete is not produced in the Rangoon area, while obtainable, it will be relatively expensive, sand are produced on the Rangoon River and supplies are adequate. Grain sizes are generally fine, so that it will be necessary to make adjustments in mixing the aggregate.

These materials are all adequately available on the Burmese market but, during the dry season, when the volume of construction work picks up, there may be temporary shortages of certain items. Accordingly, a flexible procurement plan is called for.

There is ample supply of construction labor, but proper measures will have to be taken to assure the availability of skilled labor.

With regard to the construction, particular consideration will have to be given to the rainy season, during which it would be wise to assume that no foundation work can be undertaken. It would, therefore, be desirable to schedule the peak of the construction activity for the dry season.

(3) Civil Works:

(1) Construction Methods:

The construction works for the dry dock may be broken down as follows:

- a) Sheet piling
- b) Steel pipe piling
- c) H-section steel pile driving
- d) Form work
- e) Reinforced iron work
- f) Concrete works
- g) Dock construction
- h) Paving works
- i) Dredging
- j) Appurtenance work
- k) Provisional work (provisional cofferdam etc.)

The above construction activities will all be undertaken, based on a provisional cofferdam, as shore-based construction so as to prevent the entry of river water.

The construction works for the repair jetty will be as follows:

- a) Steel pipe driving
- b) Form works
- c) Reinforced iron bar works
- d) Concrete works
- e) Covering works
- f) Appurtenance work

A portion of this work can be undertaken on shore, but construction will be based largely on floating equipment.

(2) Preparation Yard:

A wide yard will be required for the storage of construction materials, the form works and reinforced iron bar works. An open space will be used for this purpose to minimize any disturbance to the works within the existing site area.

(4) Facilities Construction:

The main items of equipment are to be procured from Japan. The terminal equipment, for reasons of maintenance and administration, will, to the maximum extent possible, be procured locally but, since quality and availability will not necessarily be constant, there is a need to develop a flexible equipment procurement plan.

5) Provisional works:

For the provisional equipment for the construction program, we plan to use equipment of the Construction Corporation, supplemented by equipment brought in by the contractor from overseas.

One cannot be entirely complacent about the types, performance, and rental periods of the equipment available from local sources, and so a considerable effort will be required to obtain these items.

One unique feature of the Burmese system is that under its tax laws, the title to all equipment brought in from abroad effectively shifts to the Burmese side. The importation of simple items of provisional equipment, then, can lead to an escalation of costs. This equipment should, therefore, be selected on the basis of a carefully developed provisional plan.

5 • 3 Supervisory Plan:

When the subject plan is implemented, the consultant will, upon the signing of a consultant contract, establish in Japan a Plan Administration Head Quarter, which will set about implementing the program.

A Design Team, to be composed of both a Design and Supervision Team, will, upon the exchange of contract, deploy the required personnel to the group for the various construction, works, facility, boat-building, and machinery operations and will prepare design specifications for the tender documents.

Following the completion of the tender documents, the Head Quarter will obtain the Plan approvals from PPFC, conduct qualification evaluations, put out tenders, evaluate the bid, and select the contractor(s).

After the construction contract(s) are signed, the Design Team will check construction plans and manufacturer lists, supervise factory production, and inspect the final products along with the tugboat. The supervision of the tugboat construction, in particular, will be accomplished by dispatching technicians to the boat-yard to supervise each stage of construction, from hull to main and auxiliary engines and riggings.

The Supervision Team will, upon conclusion of the construction contract(s); dispatch supervisory technicians to Burma to coordinate activities with the contractor(s), sit in at completion inspections, and prepare reports on their supervisory tasks. This local supervision will be maintained over the entire construction period. The required

supervisory technicians for the construction, works, and equipment phases, will be dispatched in accordance with the progress of the construction program.

5 • 4 Implementation Schedule:

The subject Plan divides generally into three schemes, civil works, building construction, and the provision of equipment.

Based on a consideration of the implementation schedules for each scheme, the construction activities have been classified into:

- ... construction that must be carried out ahead of the other works;
- ... construction works that can be done together
- ... and construction that can be done independently.

An optimum time-table for the project has been established from the standpoint of construction cost, construction time, material procurement, and the provisional plan.

(1) Civil Works:

The primary facilities under the civil works scheme are the repairing jetty and dry dock. Following are the approximate time requirements for each segment of the work for each facility:

| | |
|--|------------------|
| a) <u>Repairing jetty</u> | <u>11 months</u> |
| 1. Procurement of equipment and materials in Japan | 3 " |
| 2. Shipment; customs clearance | 2 " |
| 3. Preparatory construction | 1 " |
| 4. Substructure work (piling) | 3 " |
| 5. Superstructure work and finishing . | 4 " |


Items 4 and 5 can overlap. On the basis of a 2-month overlap, we have established the total construction time at 11 months.

b) Dry Dock

16 months

| | | |
|---|---|---|
| 1. Procurement of equipment and materials in Japan | 3 | " |
| 2. Shipment; customs clearance | 2 | " |
| 3. Sheet piling | 2 | " |
| 4. Earth works | 3 | " |
| 5. Piling | 6 | " |
| 6. Concrete works | 3 | " |
| 7. Finishing | 2 | " |

Items 4-6 can overlap. Based on a one-month overlap for stages 4-6, we have estimated the total construction period at 16 months, as per the following progress chart:



2) Building Construction Scheme 10 months

The main facilities included in this scheme are the iron works' shop, the machine shop, the generator house, and the shower and lavatory building. The approximate construction time-table will be as follows:

| | | |
|----|---|-----------|
| a) | Iron Work's Shops; | |
| | Machinery Shop | 10 months |
| | (360 sq.m for each building) | |
| | 1) Preparations in Japan | 3 " |
| | 2) Shipment; customs clearance | 2 " |
| | 3) Foundation and structural work | 5 " |
| | 4) Finishing work | 2 " |
| b) | Generator House, Shower and Lavatory Building | 9 months |
| | 1) Preparations in Japan | 3 " |
| | 2) Shipment; customs clearance | 2 " |
| | 3) Foundation and structural work | 3 " |
| | 4) Finishing | 1 " |
| c) | Other | |
| | Exterior works | 5 months |
| | Equipment for exterior works | 4 " |

The time required for the building construction scheme, as shown in the chart below, will be 10 months in all.

Iron Work's Shop:

&

Machine Shop


Preparations in Japan



Shipment; customs clearance



Foundation and structure work



Finishing




Generator House;


&

Showers and Lavatory Building

Preparations in Japan



Shipment; customs clearance



Foundation and structure work



Finishing





Other

Exterior work



Equipment work



3) Provision of Machinery

9 months

The main items included in this scheme are cranes, fork-lifts, and other material handling equipment; lathes, milling machines, and other machine tools; tug-boat; and other components and spare parts.


The procurement time for ordinary types of machinery in Japan is 2-3 months but, after allowing for the time required to manufacture large items, such as the cranes, we have chosen to allow a period of 6 months.

The longest period within this group of equipment items will be that for the tug-boat. We estimate 3 months for preparation and approval of design plans; 4.5 months for production, and 1.5 months for sailing the vessel to Burma - for a total of 9 months in all.

Based on the above examination, there should, in principle, be no problems, from the standpoint of either scheduling or the implementation plan, to undertaking the construction and equipment schemes simultaneously within a single year. However, with respect to the civil works scheme, if the dry dock and repair jetty operations were to be undertaken at the same time, the number of heavy equipment items needed for the provisional construction stage would about double, thereby creating considerable waste in the provisional plan.

In addition, were the construction period to overlap with the rainy season, serious problems would develop in connection with the earth work on the dry dock, which consumes the longest period, making it difficult to complete within a single fiscal year.


In light of the above factors, we have decided that the optimum implementing schedule for the subject Plan would, as shown below, be one that extends over a period of 25 months, straddling 2 fiscal years and 2 construction seasons.



SECTION 6 MANAGEMENT PLAN

6 • 1 Personnel Plan :

The typical organizational structure in Japan for a shipyard capable of repairing 100-150 vessels a year is shown below:



Thus, with 15 office workers, 6 engineers, 42 permanent workers, and 20-60 temporary workers, such a yard can service some 100-150 vessels per year. However, in the case of Japan, peripheral industries are well developed, and so the shipyard operations are greatly facilitated by outside contracting. If these outside contractors were converted to in-plant operations, we may estimate roughly that a regular worker of about 100 persons would be required.

Against this standard, PPFC employs 51 regular staff, 240 temporary workers, and 260 daily workers, for a total of 551 in all, in the shore section of its Engineering Division (Cf. Section 2.4.2). Even excluding the Communications and Electronics Section, which engages in different work, the total remains over 400 persons. Accordingly, even with an expansion and upgrading of the facilities, so long as the number of vessels to be serviced does not greatly exceed the 153 vessels presently owned by PPFC, the personnel requirements of the subject project should be amply covered.

There is, however, a need to reassess the operations of the Dockyard Branch, Workshop Branch, and Repair and Maintenance Branch with a view to possibly integrating these units. If, based on the expansion and upgrading of the facilities, the existing operations could be rationalized, in improving the repair efficiency of the Engineering Division as a whole.

6 • 2 Operating Costs:

6 • 2 • 1 Labor Costs:

The wage system in the Engineering Division of PPFC's Marine Fisheries Department is based on a combination of a basic wage and production incentives. The basic wage is determined on the basis of qualifications at the time of employment, taking into account years of experience.

The basic wage scale is as follows:

| | | | |
|--------------------------|----------|------|-----------|
| Managerial level | 450-1300 | kyat | per month |
| Engineering level | 450-1300 | " | " |
| Technician foreman level | 320-400 | " | " |
| Ordinary workers | 205 | " | " |

Production incentives at the managerial level run 90-550 kyat per month and at the non-managerial level run 90-400 kyat per month.

Total labor costs at present run 300,000 kyat per year but, as previously explained, since even with the projected expansion and upgrading of the repair facilities, this expansion will entail no additional personnel requirements, the project can be implemented within the parameters of the current payroll.

6.2.2 Power Costs:

Since all power requirements for the repair facilities will be provided by in-house generators, power costs may be categorized as fuel costs.

There will be two regular generators in the Repair Center with a generating capacity of 225 KVA each. The power requirements of the dock drainage pump and of the water pump for cleaning hull bottoms will come to about 170 KVA, but these pumps are expected to operate only once every two weeks for a period of 3 hours.

Assuming that all other equipment operates at 75% of capacity, the average daily load will work out to:

$$\begin{aligned}
 &280 \text{ KVA} \times 0.75 + 170 \text{ KVA} \times \frac{3 \text{ hours}}{2 \text{ weeks} \times 5 \text{ days} \times 8 \text{ hrs.}} \\
 &= 210 + 6.4 \text{ KVA} \\
 &\approx 217 \text{ KVA}
 \end{aligned}$$

Accordingly, the fuel consumption become:

$$\begin{aligned}
 &(270 \text{ PS}) \times 2 \times \frac{217 \text{ KVA}}{450 \text{ KVA}} \times 0.185 \text{ kg/hr. PS} \times \frac{1}{0.85 \text{ kg/lit.}} \\
 &\quad \times 50 \text{ weeks} \times 5 \text{ days} \times 8 \text{ hrs.} \\
 &= 113,350 \text{ liters}
 \end{aligned}$$

PPFC's purchase price for diesel fuel is 3.38 kyat per gallon. On this basis, total fuel costs will come to:

$$113,350 \times \frac{3.38}{4.546} \text{ Kyat} = 84,276 \text{ kyats/annum}$$

The cost of lubricating oil, at 10% of fuel costs, will come to 8,428 kyat per annum.

6.2.3 Cost of Materials and Replacement Parts:

Breakdown of PPFC's cost of materials for repairing vessels in 1981/1982 are as shown below.

| Item | Quantity | Amount (in kyat) |
|----------------|----------------------|------------------|
| Coconut Fibres | 411 band | 13,660 kyat |
| Enamelled wire | 86 kg | 17,015 |
| Electrodes | 27.6 ton | 646,422 |
| Timber | 402.0 ton | |
| Teak | 89.0 ton | |
| Hard wood | 226.0 ton | |
| Others | 87.0 ton | |
| Oxygen | 4,996 M ³ | 34,860 |
| Accetylene | 1,569 M ³ | |
| Paints | 31,640 lit | |
| Resin Dust | 2,727 kg | |
| Zinc Blocks | 4,368 kg | |
| Pipes | 217 M. | 184,180 |
| Electric Bulbs | 4,774 pcs. | 114,976 |
| Bolts/Nuts | 1,934 dozens | 53,196 |
| Ball Brgs | 829 pcs. | 58,804 |
| Total | | 1,200,000 |

At present, only about 90 of the 153 vessels owned by PPFC are being repaired per year. We can thus anticipate that, when repairs can be made on the entire PPFC fleet, material costs will increase by a factor of some 30% to 1,560,000 kyat.

Replacement parts are currently being imported in a volume of 1,500,000 kyat per year. Since the budget for replacement parts naturally increases in response to a more complete program for inspection, checks and repairs, a shortage of parts has been cited as another major cause of operating down-time for the PPFC fishing vessels.

Based on an expansion and upgrading of the repair facilities, there will, it is true, be a slight increase also in the number of items produced internally but, nonetheless, there will probably be a need overall to increase the imports of replacement parts by at least 30%. Accordingly, the annual parts budget can be anticipated to run 1,950,000 kyat under the proposed plan.

6 • 2 • 4 Outside Contracting Expenses; Other Costs:

Outside Contracting

At present, the PPFC contracts out the repairs on some 30 vessels a year to BPC, DMA and other shipyards at an annual cost of about 3,500,000 kyat. However, with the exception of private facilities which repair the wooden ships, once the Fishing Boat Repair Center is upgraded and expanded, this outside contracting will become unnecessary. Accordingly, these outside expenses are expected to fall by more than 70% to a level of only 1,050,000 kyat.

Forklifts

Forklifts are to be provided for the Fishing Boat Repair Center for use in transporting components and materials. Assuming that the fuel consumption of each forklift is 3 gallons a day, the annual cost of their fuel will be:

$$2 \text{ unit} \times 3 \text{ gallons} \times 3.38 \text{ kyat} \times 5 \text{ days} \times 50 \text{ weeks} = 5,070 \text{ kyat/year}$$

Water

Hull of vessels are washed-up with high-pressured water upon docking. These water, as it is required to be fresh water, can not be obtained within the planned site, will be supplied by water supply boat. Number of vessels to be docking are 26 vessels for the slipway and 35 vessels for the dry dock, accordingly the annual cost of water will be:

$$200 \text{ lit./min.} \times 2 \text{ units} \times 60 \text{ min.} \times 61 \text{ times} \times \\ 30 \text{ kyat/cu.m} = 43,930 \text{ kyat.}$$

Tugboat

The docking facilities, including the floating dock, will receive 100 vessels per year. Thus, if we set the number of operating dates for the tugboat at:

$$100 \text{ times} \times 2 \text{ days} = 200 \text{ days,}$$

the fuel expenses for the tugboat become:

$$200 \text{ days} \times 8 \text{ hrs.} \times 625 \text{ ps} \times 0.185 \times \frac{1}{0.85} \times \frac{3.38}{4.546} \\ = 161,822 \text{ kyat} \\ \doteq 162,000 \text{ kyat}$$

Assuming that all other running costs for the tugboat will equal the fuel costs, the annual operating expenses for this boat work out to 324,000 kyat.

Other Expenses

All other expenses are estimated at 10% of the above total.

Total Expenses

Summarizing now the above cost elements, the annual projected budget for operating the facility will be as follows:

(in '000 kyat)

| Cost Category | Current Operating Cost (1981/82) | Incremental Costs Based on the Expansion and Upgrading Program | Total |
|-------------------------|---|--|---------|
| Labor | 300 | - | 300 |
| Power | - | 92.7 | 92.7 |
| Materials | 1,200 | 360 | 1,560 |
| Replacement parts | 1,500 | 450 | 1,950 |
| Outside contracting | 3,500 | (-2,450) | 1,050 |
| Fuel | - | 5 | 5 |
| Water | - | 44 | 44 |
| Operating costs | 400 | 100 | 500 |
| Tugboat operating costs | - | 324 | 324 |
| TOTAL | 6,900 | (-1,074.3) | 5,177.7 |

SECTION 7 PROJECT EVALUATION

7 • 1 Financial Review:

7 • 1 • 1 The Fishing Boat Repair Center :

The Fishing Boat Repair Center, since it is intended to perform repairs on the PPFC fleet, will not in itself be an income generating facility. Thus, the impact of this Center, based on an expansion and upgrading of the repair facilities, will be evident only through a change in the level of expenditures. We anticipate that, as seen in the analysis of operating costs in Section 6.2, there will be a saving in total expenses of 1,074,300 kyat per year, based on a huge drop in outside contracting costs.

7 • 1 • 2 The Marine Fisheries Department:

The impact of the upgrading and expansion of the repair facilities will show up as an improvement in the operating ratios for the fishing vessels operated by the Marine Fisheries Department of the PPFC. This improved operating rate will lead to an increase in fish catches, as a result of which the Corporation's export and domestic sales revenues will both expand. In Section 2.3.3, Table 2.6, we presented the average operating results for the PPFC fleet. The subject plan will eliminate the existing underutilization based on the 10% backlog of vessels currently awaiting dock space.

Docking operations and repair works on water presently consume an average of 100 days a year. However, based on an upgrading of the cranes, repair jetty, and machine tools, a 50% reduction in operating time should be possible at the outset, and, in the future, efforts should be made to reduce this time to only 30 days. When these non-operating days are then shifted to fishing operations i.e., are converted to fishing days, the following increases in the catch volume of the PPFC trawl vessels can be anticipated:

Table 7.1 Anticipated increase in the catch volume of PPFC trawler

| | Type of Fishing (Vessel) | Number of Vessels | Present Catch (tons) | No. of Fishing Days per Vessel Per Year | Catch per Fishing Day Per Vessel (tons) | Increase in the Number of Fishing Days Per Vessel | | | Increase in the Catch Per Vessel (tons) | Increase in the Total Catch (tons) | Total Catch Volume After the Increase (tons) |
|---|--|-------------------------|----------------------------|---|---|---|---|-------|--|--|---|
| | | | | | | Based on Elimi- nating the Backlog Awaiting Dock Space | Based on a Shorten- ing in Operating Time | Total | | | |
| 1 | 100 Series (Korea) | 10 | 3,548.05 | 109.2 | 3.25 | 36 | 51 | 87 | 282.75 | 2,827.5 | 6,375.55 |
| 2 | 500 Series (Korea) | 3 | 1,729.56 | 102.0 | 5.65 | 36 | 51 | 87 | 491.55 | 1,474.65 | 3,204.21 |
| 3 | 500 Series (Japan) | 2 | 779.08 | 65.5 | 5.95 | 36 | 51 | 87 | 517.65 | 1,035.3 | 1,814.38 |
| 4 | 400 Series (Norway) | 9 | 707.18 | 47.8 | 1.64 | 36 | 51 | 87 | 142.68 | 1,284.12 | 1,991.3 |
| 5 | 500 Series (Norway) | 2 | 1,419.45 | 111.5 | 6.37 | 36 | 51 | 87 | 554.19 | 1,108.38 | 2,527.83 |
| 6 | 400 Series (Australia) (100 ton class) | 10 | 762.67 | 86.9 | 0.88 | 36 | 51 | 87 | 76.56 | 765.6 | 1,528.27 |
| 7 | 400 Series (Australia) | 3 | 361.65 | 95.0 | 1.27 | 36 | 51 | 87 | 110.49 | 331.47 | 693.12 |
| 8 | 400 Series (U.K.) | 10 | 999.01 | 99.8 | 1.00 | 36 | 51 | 87 | 87.00 | 870.0 | 1,861.01 |
| 9 | 400 Series (Denmark) | 4 | 573.25 | 103.3 | 1.39 | 36 | 51 | 87 | 120.93 | 483.72 | 1,056.97 |
| | Total | 53 | 10,879.9 | 89.6 | 2.29 | 36 | 51 | 87 | 264.86 | 10,180.74 | 21,060.64 |

Since no data are available on fish catches by vessel type, if we apply the species composition of the PPFC trawl vessels, as shown at the Appendix III-7 of this report, we see that export species, such as Thread Fin, Yellow Croaker, Chub Mackerel, and Milk Fish, comprise about 9% of total catch and shrimp (White and Tiger) and lobster about 1%. On this basis, the breakdown of the presumed incremental catch can be estimated as follows:

| | |
|-------------------------------|-------------|
| Shrimp and lobster for export | 101.81 tons |
| Fish for export | 916.27 |
| Fish for the domestic market | 9,162.66 |
| Total | 10,180.74 |

The breakdown of PPFC sales is as follows:

(In tons and millions of kyat)

| | 1980/1981 | | 1981/1982 | | 1982/1983 | |
|---------------------|-----------|-------|-----------|-------|-----------|-------|
| | Volume | Value | Volume | Value | Volume | Value |
| Exports | - | 81.7 | - | 115.8 | - | 140 |
| Fish (marine) | 4,218 | 23.0 | 5,752 | 35.8 | - | - |
| Shrimp | 2,253 | 58.4 | 2,665 | 77.6 | - | - |
| Other Items | - | 0.3 | - | 2.4 | - | - |
| Domestic Fish Sales | 21,962 | 65.7 | 28,304 | 86.5 | 40,737 | 96.3 |
| Other Sales | - | 77.6 | - | 71.7 | - | 57.7 |
| Total | | 225 | | 274 | | 294 |

From the above table, the unit values work out to:

| | | |
|---------------|-----------------|----------|
| Export fish | 5,453 - 6,224 | kyat/ton |
| Export shrimp | 25,921 - 29,118 | kyat/ton |
| Domestic fish | 2,364 - 3,056 | kyat/ton |

Based on export values per ton of 6,000 kyat for exported fish, 28,000 kyat for shrimp, and 2,800 kyat for domestic fish, the value of the incremental catch, based on an expansion and upgrading of the Fishing Boat Repair Center, would rise as follows:

| | | |
|------------------|-------------------------|------------------|
| Fish Exports | 916.27 ton x 6,000 kyat | = 5,497,620 kyat |
| Shrimp Exports | 101.81 " x 28,000 " | = 2,850,680 " |
| Domestic Fish | 9,162.66 " x 2,800 " | = 25,655,450 " |
| Total increment: | | 34,003,750 kyat |

The expenses required to achieve the above increase may be estimated at 22,552,000 kyatt, broken down between: 11,276,000 kyat for fuel and an identical amount for all other costs. Accordingly, the net profit for the incremental catch may be estimated at 11,451,000 kyat.

As shown above, based on an upgrading and expansion of the PPFC Fishing Boat Repair Center, the PPFC, which now depends heavily on outside contractors for its repairs, will be in a position to decrease these outside contracts. We may anticipate that, based on a reduction in these outside costs, there will be an overall saving of 1,074,000 kyat per year in total operating expenses. At the same time, based on the elimination of the waits for docking facilities and a shortening in the time of repair operations, there will be an improved utilization of fishing vessels, on the basis of which we can expect an increase in net catch earnings of 11,451,000 kyat per year.

7 • 2 Economic Analysis:

Following are the principal benefits that can be expected from the Fishing Boat Repair Center Project.

- 1) An increase in catches based on improved fishing vessel utilization.
- 2) A decrease in outside contracting.

- 3) Improved supplies of animal protein, based on an increase in the domestic supply of fish products and a resulting improvement in nutritional levels.
- 4) A reduction in vessel wear-and-tear as a result of the program of regular inspections and repairs.

The benefits from the increased catches can be measured on the basis of the foreign exchange that will be earned from the exports of fish and shrimp and on the basis of sales revenues from the domestic sale of catches.

The reduction in the outside contracting costs, based on the use of PPFC's own facilities, will be a simple transfer of costs from other public corporations to PPFC and so would not constitute per se a net benefit for the national economy. However, by decreasing the amount of outside contracts, new capacity will develop in the BPC and BDC facilities which can certainly be diverted to other productive activities. Accordingly, the reduction in these outside contracting costs may indeed be calculated as a benefit of the program.

The improvement in the country's nutritional levels and the decrease in vessel wear-and-tear as a result of the repair program would be difficult to measure quantitatively and so have been excluded from the evaluation criteria.

The following new or increased costs can be expected as a consequence of implementing the proposed project:

- 1) an increase in power and fuel costs.
- 2) an increase in material costs.
- 3) an increase in the cost of replacement parts.
- 4) water costs.
- 5) an increase in operating costs.
- 6) an increase in the costs of operating the fishing vessels.
- 7) an increase in tugboat operating costs.

We have not planned for any increases in labor costs, since we have concluded that implementation of the project will not necessitate any increases in personnel.

We have valued the above costs and benefits in terms of domestic market prices.

Turning now to the useful life of the proposed facilities, in Japan, a dry dock has a useful life of 45 years, a jetty 50 years, a tugboat 10 years, buildings 35 years, and Equipment for steel vessels building 12 years. We have set 45 years as the project life and have assumed that all of the various facilities will be renewed upon termination of their useful lives.

The results of this cost/benefit analysis are given in next page.

With a discount rate of 8%, the cost-to-benefit ratio works out to 142.9%, and the Net Present Value to 166,257,000 kyat. The Internal Rate of Return is seen to be 27.36%, making it clear beyond doubt that implementation of this project will contribute to the Burmese economy.

Cost/Benefit Analysis

(in '000 kyat)

| Year | Cost | | | | | | | | | | Benefit | | | | Net Benefit | |
|-------|-----------------|----------------------|----------|----------------|------|-------|---------------|---|---------------------------------------|-----------|----------------|------------------|-------------------|---|-------------|---------|
| | Invest- ment | Fuel for Power | Material | Spare Parts | Fuel | Water | Over- head | Fishing Boat Oper- ating Cost | Tug Boat Oper- ating Cost | Total | Fish Export | Shrimp Export | Domestic Sales | Decrease of Outside Con- tracting | | Total |
| 1 | 40,000 | 47 | 180 | 225 | 3 | 22 | 50 | 22,552 | 324 | 63,403 | 4,581 | 331 | 5,727 | 0 | 10,639 | -52,764 |
| 2 | 30,000 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 53,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | -8,922 |
| 3 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 4 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 5 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 6 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 7 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 8 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 9 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 10 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 11 | 3,333 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 27,261 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 17,745 |
| 12 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 13 | 6,667 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 30,595 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 14,411 |
| 14 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 15 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 16 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 17 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 18 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 19 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 20 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 21 | 3,333 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 27,261 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 17,745 |
| 22 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 23 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 24 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 25 | 6,667 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 30,595 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 14,411 |
| 26 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 27 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 28 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 29 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 30 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 31 | 3,333 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 27,261 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 17,745 |
| 32 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 33 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 34 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 35 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 36 | 13,333 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 37,261 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 7,745 |
| 37 | 6,667 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 30,595 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 14,411 |
| 38 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 39 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 40 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 41 | 3,333 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 27,261 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 17,745 |
| 42 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 43 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 44 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| 45 | 0 | 93 | 360 | 450 | 5 | 44 | 100 | 22,552 | 324 | 23,928 | 18,325 | 1,324 | 22,907 | 2,450 | 45,006 | 21,078 |
| Total | 106,666 | 4,315 | 16,020 | 20,025 | 223 | 1,958 | 4,450 | 1,014,840 | 14,580 | 1,192,900 | 810,881 | 58,587 | 1,013,635 | 107,800 | 1,990,900 | 798,002 |

SECTION 8 CONCLUSIONS AND RECOMMENDATIONS

The major priority in the Burmese Government's program for fisheries development is being placed on the development of the coastal and marine fisheries, based on an investment in the modernization of the PPFC facilities and an expansion of both the domestic and exportable supply of fish products.

The PPFC has been actively engaged in a program to build up its fishing fleet as well as ice-making and refrigeration facilities. Since 1977, in particular, there has been a 3.5 fold expansion in steel and FRP vessels. However, despite this rapid increase in vessel strength, Burma's vessel repair facilities in general remain inadequate, while the repair facilities of the PPFC itself have also lagged behind in development. As a result, the planned expansion of fish production has run into a serious snag, owing to a decline in fishing vessel utilization.

As a consequence of the above situation, the PPFC is under considerable pressure to expand its Fishing Boat Repair Center in the Gyaung Waing area, where it maintains a slipway.

If the subject plan is carried out, the PPFC will then be able to repair 100 fishing vessels a year, on its slipway, floating dock and dry dock. This will eliminate the present bottleneck caused by the wait for dock access and help shorten the time required for repair operations, both of which factors have been cited as prime reasons for the drop in fishing vessel utilization. Also, on the basis of a major increase in the number of fishing days, it will become possible to achieve an increase in fish production as well. With an expanded supply of fish, we can expect not only an improvement in the nutritional levels of the Burmese people but a contribution as well to foreign exchange earnings based on expanded exports of fish and shrimp.

With regard to the maintenance and operating costs of this Fishing Boat Repair Center, as a result of an increase in the number of repairs,

there will naturally be an increase in material and fuel costs over present levels. But, despite these increases, there will be no need to expand personnel beyond existing levels, while there will also be a significant drop in the amounts paid to utilize outside repair facilities-- i.e., for outside contracting costs. On an overall basis, then, it can be anticipated that costs will be less than at present.

On the basis of PPFC's current technical capabilities, we anticipate no particular difficulties with respect to the operation of the Fishing Boat Repair Center. Future problems will, rather, concern how to operate the facilities more efficiently and the possibility of rationalizing operations.

For the above reasons, the Basic Design Survey Team came to the conclusion that the plan to upgrade and expand the PPFC Fishing Vessel Repair Center at Gyaung Waing would be of immense benefit to the Burmese economy and that there would, therefore, be considerable significance in the Government of Japan making a grant-in-aid for this project.

In order to more effectively utilize the plan facilities in the future and further develop the fishing vessel repair capabilities of the PPFC, consideration should, we believe, be given to the following points.

- 1) An effort should be made to procure materials and components for repair operations according to plan.

The size of the PPFC Fishing Boat Repair Center upon completion of the subject project, will be almost comparable to the repair facilities of a medium-class ship-building yard in Japan. In order to efficiently utilize this capacity, it is naturally essential that materials and replacement parts for repair use be procured in a smooth and timely manner. For, if the procurement of such items is subject to delays, the productive efficiency of the entire facility will decline, and this would be tantamount to lowering the capacity of the complex. It is vital, therefore, that a major effort should be made to insure the procurement of parts and materials according to plan.

2) An effort should be made to improve technical levels.

Only by fully utilizing the subject facilities can their capabilities be given full play. At present, the facilities are merely being "used"; to give full play to the capacity of the improved facilities, it will be necessary in the future to take steps to rapidly upgrade the technical and skill levels of the technicians and workers operating and managing the complex. Particularly with respect to machine tools, we feel that mere fabrication of machinery components for the PPFC fishing vessels will only serve to lower the utilization ratios for machine tools in the machine shop. There is, therefore, a clear need to actively increase the amount of equipment, such as through the in-house production of small types of machinery for vessel use, and to nurture greater skills among the work force in the handling of machine tools with a view to maintaining and improving technological levels. It is vital, in this connection, to take advantage of the training programs offered by Japan and other countries as a means of developing trained technicians.

3) An effort should be made to rationalize management and raise productivity.

In our opinion, decisive measures should be taken to review existing customs with respect to such areas as working hours and work rules.

There is a need to unify concepts of plant management, introduce scientific management methods, and generally rationalize production control.

- Based on such rationalization measures, productivity will inevitably rise, but there is a compelling need to maintain continuing and persistent efforts until such time as technology, product quality, and costs reduction are brought up to international levels.

4) A move should be made toward specialization and division of labor.

The ship-building industry becomes viable only with the cooperation of a large number and variety of peripheral industries. For, no matter how concentrated the investment in any one ship-building yard, there are definite limits to the cost saving that can be achieved, so that it is unrealistic to expect total results from such investments.

Accordingly, in fields where high utilization ratios cannot be obtained only through the repair operations within PPFC, or in certain highly specialized technical areas, efforts should be made to foster the growth of peripheral industries as well as sub-contracting operations, with a view to specialization and division of labor.

A P P E N D I X

Appendix I-1 Basic Design Study

Appendix I-1-1 Team Members

| | | |
|------------------------|-------------------------------------|--|
| Mr. Junichi FUJITA | Team Leader | Fishing Boat Inspector, Fishing Boat Div. Fisheries Agency, Ministry of Agriculture, Forestry and Fisheries (MAFF) |
| Mr. Shoji NAKANO | Planning, Fishing Boat Repair | Office for the Overseas Fishery Cooperation, Fisheries Agency, MAFF |
| Mr. Naoyoshi SASAKI | Project Coordinator | Basic Design Div., Grant Aid Dept., Japan International Cooperation Agency (JICA) |
| Mr. Kuniaki TAKAHASHI | Fisheries Development | Fisheries Engineering Co., Ltd. |
| Mr. Toshiya OGASAWARA | Planning, Shipyard | Fisheries Engineering Co., Ltd. |
| Mr. Taizo KANEKO | Architect | Fisheries Engineering Co., Ltd. |
| Mr. Masayoshi SAKURADA | Naval Architect | Fisheries Engineering Co., Ltd. |
| Mr. Yutaka OCHI | Civil Engineer | Fisheries Engineering Co., Ltd. |

Appendix I-1-2 Burmese Discussants

| NAME | ORGANIZATION | TITLE |
|---------------------|--|--|
| Colonel AUNG WIN | Ministry of Livestock Breeding and Fisheries (MLBF) People's Pearl and Fishery Corporation (PPFC) | Deputy Minister & Managing Director |
| U SAN MYINT | PPFC | Additional Managing Director |
| U TIN MAUNG MYINT | MLBF | Director, Planning and Statistics Dept. |
| U KHIN MAUNG HTUN | PPFC | General Manager, Pearl Culture Dept. |
| Lt.Cdr. HAN HTUN | PPFC | General Manager, Marine Fisheries Dept. |
| Lt.Cdr. THEIN MYINT | PPFC | Chief Engineer, Marine Fisheries Dept. |
| U THAN HTAY | PPFC | General Manager, Planning and Budget Dept. |
| U C. YIN CHAN | PPFC | Asst. General Manager Freshwater Fisheries Dept. |
| Dr. SAN AUNG | PPFC | Manager, Marine Research Div. |
| U HTWE | PPFC | Dy. Chief Engineer, Engineering Div. |
| U WUN NA | PPFC | Manager, Cold Stores Dept. |
| DAW TIN TIN HTAY | PPFC | Manager, Planning and Budget Dept. |
| U KHIN LATT | PPFC | Manager, Civil Engineering Dept. |

| NAME | ORGANIZATION | TITLE |
|-------------------|-------------------------------------|--|
| U OHN MYA | PPFC | Naval Architect, Engineering Div. |
| U MYO MYINT | PPFC | Mechanical Engineer, Engineering Div. |
| U HLA MAUNG | PPFC | Manager, Workshop Branch |
| U SAW WAI LIN | PPFC | Manager, Communication Branch |
| U AUNG KHIN SHEIN | PPFC | Marine Superintendent, Marine Fisheries Dept. |
| U KYAW HTUN | PPFC | Mechanical Engineer, Engineering Div. |
| DAW MEY PEW AYE | PPFC | Manager, Freshwater Fisheries Dept. |
| U NYANA | Burma Dockyard Corporation (BDC) | Chief Engineer |
| U THA HLA | BDC | Store Officer |
| U HLA MG | BDC | Naval Architect |
| Lt.Cdr. HLA MYINT | Burma Port Corporation (BPC). | Chief Mechanical Engineer |
| U MAUNG MAUNG HLA | BPC | Chief Civil Engineer |
| U TIN HTUT | BPC | Dredging Master |
| 渡 部 彰 三 | PPFC | Guarantee Engineer |
| 白 蟠 克 巳 | PPFC | Master Fisherman |

Appendix I-1-3 Survey Itinerary

| Day | Date | Itinerary | Description |
|-----|----------------|--|--|
| 1 | June 6 (Sun.) | Tokyo <u>TG741</u> Bangkok | |
| 2 | June 11 (Mon.) | Bangkok <u>TG305</u> Rangoon (RGN) | |
| 3 | June 12 (Tue.) | RGN Japanese Embassy PPFC Ahlone Office PPFC GYAUNG WAING Slipway | Courtesy call on Japanese Embassy Discussion on the Plan Visit to the site |
| 4 | June 13 (Wed.) | RGN PPFC Floating Dock Dock Corporation Sinmalike Dockyard | Discussion on the Plan Visit to Floating Dock and Sinmalike Dockyard |
| 5 | June 14 (Thu.) | RGN PPFC | Discussion on the Plan |
| 6 | June 15 (Fri.) | RGN PPFC | Discussion on the Plan |
| 7 | June 16 (Sat.) | RGN | Discussion within the team |
| 8 | June 17 (Sun.) | RGN | Discussion within the team |
| 9 | June 18 (Mon.) | RGN Port Corporation PPFC Ahlone Office | Visit to the dry dock Interim discussion with PPFC |

| Day | Date | Itinerary | Description |
|-----|----------------|---|--|
| 10 | June 19 (Tue.) | RGN PPFC Ahlone Office | Discussion on the Plan |
| 11 | June 20 (Wed.) | RGN PPFC Ahlone Office | Discussion on PPFC's activities Discussion on the Plan |
| 12 | June 21 (Thu.) | RGN PPFC Ahlone Office | Discussion on the Plan |
| 13 | June 22 (Fri.) | RGN PPFC Ahlone Office Japanese Embassy JICA Team Leader and Mr. Nakano RGN $\xrightarrow{\text{UB221}}$ Bangkok | Signature of Minutes of Discussions Reporting of the outline of the Project |
| 14 | June 23 (Sat.) | RGN Team Leader and Mr. Nakano Bangkok $\xrightarrow{\text{JL766}}$ Tokyo | Data and information collection |
| 15 | June 24 (Sun.) | RGN | Data and information collection |
| 16 | June 25 (Mon.) | RGN PPFC GYAUNG WAING Keighley Office | Field Survey Data Collection |

| Day | Date | Itinerary | Description |
|-----|----------------|---|--|
| 17 | June 26 (Tue.) | RGN PPFC GYAUNG WAING Japanese Embassy PPFC Ahlone Office | Field Survey Interim Report Discussion on the Plan |
| 18 | June 27 (Wed.) | RGN PPFC GYAUNG WAING PPFC Ahlone Office | Discussion on the soil test Discussion on the Plan |
| 19 | June 28 (Thu.) | RGN PPFC Ahlone Office | Discussion on the Plan |
| 20 | June 29 (Fri.) | RGN PPFC Ahlone Office Japanese Embassy JICA RGN <u>UB221</u> → Bangkok | Reporting of the result of the survey |
| 21 | June 30 (Sat.) | Bangkok <u>JL766</u> → Tokyo | |

Appendix I-2 Draft Final Report Explanation

Appendix I-2-1 Team Members

| | | |
|------------------------|--------------------------|--|
| Mr. Junichi FUJITA | Team Leader | Fishing Boat Inspector, Fishing Boat Div. Fisheries Agency, Ministry of Agriculture, Forestry and Fisheries (MAFF) |
| Mr. Naoyoshi SASAKI | Project Coordinator | Basic Design Div., Grant Aid Dept., Japan International Cooperation Agency (JICA) |
| Mr. Kuniaki TAKAHASHI | Fisheries Development | Fisheries Engineering Co., Ltd. |
| Mr. Toshiya OGASAWARA | Planning, Shipyard | Fisheries Engineering Co., Ltd. |
| Mr. Masayoshi SAKURADA | Naval Architect | Fisheries Engineering Co., Ltd. |

Appendix I-2-2 Burmese Discussants

| NAME | ORGANIZATION | TITLE |
|---------------------|--|---|
| U NYUNT MG | Foreign Economic Relation Department (FERD) | Director General |
| U NYUNT LWIN | FERD | Deputy Director |
| Colonel AUNG WIN | Ministry of Livestock Breeding and Fisheries (MLBF) People's Pearl and Fishery Corporation (PPFC) | Deputy Minister & Managing Director |
| U SAN MYINT | PPFC | Additional Managing Director |
| U KAN NYUNT | PPFC | General Manager, Project |
| Lt.Cdr. HAN HTUN | PPFC | General Manager, Marine Fisheries Dept. |
| Lt.Cdr. THEIN MYINT | PPFC | Chief Engineer, Marine Fisheries Dept. |
| Lt.Cdr. KYAW LWIN | MLBF | Additional Director, Planning and Statistics Dept. |
| U AYE ZAW WIN | PPFC | Deputy General Manager Cold Stores, Processing Marketing and Export |
| U HTWE | PPFC | Deputy Chief Engineer, Engineering Div. |
| U OHN MYA | PPFC | Naval Architect, Engineering Div. |
| U MYO MYINT | PPFC | Mechanical Engineer, Engineering Div. |
| U HLA MAUNG | PPFC | Manager, Workshop Branch |
| U SAW WAI LIN | PPFC | Manager, Communication Branch |
| U AUNG KYAW AYE | PPFC | Engineer, G.R.P. Branch |
| U BATHAN CHAIN | PPFC | Engineer, Civil Engineering Dept. |
| U KYAW HTUN | PPFC | Mechanical Engineer, Engineering Div. |

Appendix I-2-3 Survey Itinerary

| Day | Date | Itinerary | Description |
|-----|----------------|---|--|
| 1 | Aug. 31 (Fri.) | Tokyo $\xrightarrow{\text{TG741}}$ Bangkok | |
| 2 | Sep. 1 (Sat.) | Bangkok $\xrightarrow{\text{TG305}}$ Rangoon (RGN) | Discussion on the Survey Schedule |
| 3 | Sep. 2 (Sun.) | RGN | Discussion within the Study Team |
| 4 | Sep. 3 (Mon.) | RGN Japanese Embassy JICA office PPFC FERD | Courtesy call on Embassy, discussion on the Plan Courtesy call on PPFC, discussion on the Plan Courtesy call on FERD, discussion on the Plan |
| 5 | Sep. 4 (Tue.) | RGN PPFC | Discussion on the Plan |
| 6 | Sep. 5 (Wed.) | RGN PPFC | Discussion on the Plan |
| 7 | Sep. 6 (Thu.) | RGN PPFC | Discussion on the Plan |
| 8 | Sep. 7 (Fri.) | RGN | Discussion within the Team |
| 9 | Sep. 8 (Sat.) | RGN PPFC Team Leader RGN $\xrightarrow{\text{TG306}}$ BKK | Signature of Minutes of Discussions |
| 10 | Sep. 9 (Sun.) | RGN Team Leader BKK $\xrightarrow{\text{TG604}}$ NRT | Discussion within the Team |
| 11 | Sep. 10 (Mon.) | RGN Japanese Embassy PPFC RGN $\xrightarrow{\text{TG306}}$ BKK | Reporting Reporting |
| 12 | Sep. 11 (Tue.) | BKK $\xrightarrow{\text{TG604}}$ NRT | |

Appendix 1-2 Minutes of Discussions

MINUTES OF DISCUSSIONS ON THE EXPANSION PROJECT FOR FISHING BOAT REPAIRSHOP

In response to the request made by the Government of the Socialist Republic of the Union of Burma for the expansion project for Fishing boat repairshop in Burma (hereinafter referred to as "the project"), the Government of Japan has sent, through the Japan International Cooperation Agency (hereinafter referred to as "JICA"), a team headed by Mr. Junichi FUJITA to conduct a basic design study for 21 days from June 10, 1984. The team carried out a field survey, had a series of discussions and exchanged views with the authorities concerned.

As the result of the study and discussions, both parties have agreed to recommend to their respective Governments to examine the results of the survey attached herewith towards the realization of the project.

Managon, June 21, 1984

Junichi Fujita

Junichi FUJITA
Team Leader
The Japanese Survey Team

U San Myint
U San Myint
Add: Managing Director
People's Pearl & Fisheries
Corporation

中野 荘次
Shoji NAKANO
Deputy Team Leader

N. SASAKI
Naoyoshi SASAKI
Project Coordinator

Han Tun
Lt. Cdr. Han Tun
General Manager
Marine Fisheries Department

Thein Myint
Lt. Cdr. Thein Myint
Chief Engineer


MINUTES

1. The objectives of the Project are to expand and upgrade the fishing boat repair facilities owned by People's Pearls and Fisheries Corporation (PPFC) for the purpose of improvement of fishing boat's efficiency in pursuit of increase of fish production, and in the consequence, to improve the financial situation of PPFC.
2. The Proposed site of the facilities for the Project is QYANG WAING, which is allocated to the PPFC for the fishing boat repairshop by the Government of Burma, as shown in Annex I.
3. The Ministry of Livestock Breeding and Fisheries is responsible for the administration of the Project, and the PPFC is the executing agency of the Project.
4. The Japanese Survey Team will convey to the Government of Japan the desire of the Government of the Socialist Republic of the Union of Burma that the former takes necessary measures to cooperate in implementing the Project and provide the latter with the items listed in Annex II within the scope of Japanese economic cooperation in grant-aid system.
5. The Government of the Socialist Republic of the Union of Burma will take the necessary measures listed in Annex III on condition that the grant assistance by the Government of Japan is extended to the Project.
6. Both sides confirmed that the Japanese Survey Team explained the Japanese Grant Aid Programme and Burmese side understood it.

J. F


P 83

N. S



ANNEX I

Location of the Site




ANNEX II

Items requested in order of priority by the Government of the Socialist Republic of the Union of Burma, the cost of which will be borne by the Government of Japan in the limitation of the budget of Japanese Government and scheme of Japanese grant aid.

Facilities and equipment for the expansion of the fishing boat repairs facilities to cope with 100 vessels owned by PPFC.

1. Power Station
 - (1) Electricity supply
 - (2) Water Supply
 - (3) Air Supply
2. Dry Dock
3. Concrete jetty with a fixed crane.
4. Tug Boat.
5. Haulage and Transportation Equipment Fork lift(s)
6. Shop and/or shop's equipment
 - (1) Welding, plating and plumber shop
 - (2) Calibration Apparatus
 - (3) Engine and refrigeration repairshop
 - (4) Electrical repair shop
 - (5) Machine shop
 - (6) GRP/Insulation Repair shop
 - (7) Carpentry shop
 - (8) Docker shop
 - (9) Electronic repairshop
 - (10) Drawing shop
7. Spare parts for emergency repairs

J. F
中野
N's

 SAN




ANNEX III

Items to be undertaken by the Government of the Socialist Republic of the Union of Burma are as follows ;

1. To provide data and information necessary for the design and the expansion of the fishing boat repairshop,
2. To secure a lot of land necessary for the expansion of the fishing boat repairshop.
3. To clear and level the Project site prior to construction,
4. To ensure prompt unloading and customs clearance in the Socialist Republic of the Union of Burma.
5. To exempt the Japanese nationals concerned from customs duties, internal taxes and other fiscal levies imposed in the Socialist Republic of the Union of Burma with respect to the supply of the products and services for the Project,
6. To provide the necessary permissions, licences and other authorizations for carrying out the Project.
7. To bear all expenses necessary for the execution of the Project other than those to be borne by the Japanese Grant,
8. To maintain and use the facilities, equipment and materials properly with due diligence.

J. F

中野
N. S



Dr.



A N N E X IV

Memorandum for the Expansion Project for
Fishing Boat Repairshop of P. P. F. C.


As a result of careful study and ~~thorough~~ discussions between P.P.F.C. and the Japanese Basic Design Team, we have arrived at the following conclusions with regard to the P.P.F.C. fisheries development particularly in terms of the P.P.F.C.'s fishing boat repairshop.

1. Major Constraints to the high operational rate of the fishing boats are identified as follows:-
 - (a) Dock and workshop facilities are inefficient and inadequate to effectively maintain all the fishing support crafts of P.P.F.C.
 - (b) Shortage of genuine spare parts and materials P.P.F.C. has to import due to economic and financial situations.
 - (c) Shortage of fund for capital investment in fisheries development including the fishing boat repair facilities.
2. To overcome these constraints, both parties consider the following measures to be taken.
 - (a) Japanese Basic Design Team will recommend the appropriate basic design for the Project to the Government of Japan.
 - (b) P.P.F.C. shall operate the upgraded and expanded repair facilities with full efficiency and effectiveness. Both parties clearly understand that success of the project is duely related to the P.P.F.C.'s concentrated efforts for increase of it's production and the promotion of export based upon the Burma's marine fisheries development programme.

J. F

中野

N.S


SAN

Da.



I-3-2 Draft Final Report Explanation

MINUTES OF DISCUSSIONS
ON
THE DRAFT FINAL REPORT ON THE BASIC DESIGN STUDY
ON
THE EXPANSION PROJECT FOR FISHING BOAT REPAIRSHOP
IN
THE SOCIALIST REPUBLIC OF THE UNION OF BURMA.

The Government of Japan has sent, through the Japan International Cooperation Agency (JICA), a Basic Design Study Team to the Socialist Republic of the Union of Burma from Aug. 31 to Sep. 11, 1984, for the purpose of presenting and explaining the Draft Final Report on the Basic Design Study (the Report) on the Expansion Project for Fishing Boat Repairshop. The team held meetings with the officials concerned to explain and to discuss the Report. As a result of the discussions, both parties have agreed to the following items :

1. The Burmese side principally has agreed to the basic design proposed in the Report, and appropriate alterations (Annex 1) agreed during the discussions will be incorporated in the Final Report
2. The Final Report (12 copies in English) on the Project will be submitted to the Burmese side by the end of Oct. 1984.
3. Land clearing and levelling of the proposed site shall be completed by the Burmese side by the end of Feb. 1985. (Annex 2)

J.F

W

8

Q

2/-

4. Modification of the existing buildings shall be completed by the Burmese side prior to the commencement of the construction work. (Annex 3)

Rangoon, Sep. 7, 1984.

Junichi Fujita

Junichi Fujita.
Team Leader
Basic Design Study Team.

U Kan Nyunt

U Kan Nyunt
General Manager for the Projects
P.P.F.C.

Witnesses:

1. Alba Motozuga

2. [Signature]

1. Han-Su
Lt Col Han Tien

2. Chair Nyunt

Appropriate alterations

1. Manual operation arrangement for Dry Dock Flap Gate shall also be included.
2. Capstans for the dolphin shall be included.
3. Air compressor set complete with fittings for tube well shall be included.
4. Spare crucible for tilting furnace shall be included.
5. Furnaces with blowers shall be included.

J.F.
11/11/77
C. M. S.
J



Modification of the Existing Buildings

| | Undertakings by the Burmese side | Undertakings by the Japanese side |
|---|---|--|
| Engine Repair Shop | (a) Painting (b) Lighting | (a) Foundation of Equipment. (b) Partition for the Diesel Test Shop and the store. (c) Power distribution network necessary for equipment. (d) Installation of Equipment. |
| Electrical Repair Shop | (a) Painting (b) Lighting | (a) Power distribution network necessary for equipment (b) Installation of Equipment, if necessary. |
| Carpenter Shop | (a) Painting (b) Lighting | (a) Foundation of the Equip- ment, if necessary. (b) Power distribution network necessary for equipment. (c) Installation of Equipment. |
| The F.R.P. Repair Shop and the Mould loft | (a) Raising the floor to be at the same level. (b) Painting (c) Lighting | (a) Partition for the F.R.P repair shop & Insulation. (b) Air conditioning for the F.R.P repair shop (c) Power distribution network necessary for equipment. |

JF *[Signature]* 3. J
[Signature]

II. P H O T O G R A P H S


Fishing Fleet of PPFC




Fishing Fleet

Fishing Vessel






Proposed Site for Dry Dock (right : Existing Slipway)



Existing Facilities
(right : Generator House, left : Iron Work Shop)


Existing Facilities
(Carpenter's Shop & Stores)




Floating Jetty

Floating Dock







Slipway




Slipway


Slipway
Docking Work (1)




(2)

(3)





Machine Shop





Iron Work Shop




Foundry


Iron Work Shop,
Sinmalike Dockyard,
BDC



Iron Work Shop,
Sinmalike Dockyard,
BDC


Crane & Slipway,
Sinmalike Dockyard,
BDC






Slipway,
Sinmalike Dockyard,
BDC

Dry Dock,
Sat Sun Dockyard,
BPC




Dry Dock,
Sat Sun Dockyard,
BPC




III. DATA


III-1 Mean Monthly Rainfall




III-2 Mean Monthly Rain Days




III-3 Soil Tests Points



III-4 Soil Bearing Test Results



III-5 Drilling Log



III-6 Results of Soil Analysis

| Bore Hole No. | Depth (m) | Specific Gravity | Density (t/m ³) | | Water Content (%) | Consistency | | Cohesion (kg/m ²) | Friction Angle (tan ϕ) |
|---------------|-----------|------------------|-----------------------------|------|-------------------|------------------|-------------------|-------------------------------|------------------------------|
| | | | Dry | Wet | | Liquid Limit (%) | Plastic Limit (%) | | |
| BH-1 | -3 | 2.76 | 1.73 | 1.21 | 43 | 50 | 26 | 281.2 | 0.0866 |
| | -6 | 2.86 | 1.75 | 1.46 | 20 | - | - | 421.8 | 0.0566 |
| | -9 | 2.62 | 1.52 | 1.24 | 23 | - | - | 632.7 | 0.5272 |
| | -12 | 2.79 | 1.69 | 1.46 | 16 | - | - | 70.3 | 0.7536 |
| BH-2 | -3 | 2.85 | 1.66 | 1.05 | 57 | 64 | 32 | 1406.0 | 0.0087 |
| | -6 | 2.73 | 1.63 | 0.98 | 65 | 58 | 29 | 632.7 | 0.0175 |
| | -9 | 2.76 | 1.90 | 1.59 | 20 | 38 | 21 | 703.0 | 0.4245 |
| | -12 | 2.65 | 1.65 | 1.44 | 14 | - | - | 843.6 | 0.6128 |
| BH-3 | -3 | 2.69 | 1.66 | 1.05 | 58 | 61 | 29 | 597.6 | 0.0332 |
| | -6 | 2.91 | 1.59 | 0.99 | 60 | 63 | 27 | 562.4 | 0.0349 |
| | -9 | 2.82 | - | - | - | 39 | 21 | - | - |
| | -12 | 2.72 | 1.55 | 1.33 | 17 | - | - | 1602.8 | 0.3819 |
| | -15 | 2.60 | 1.54 | 1.29 | 19 | - | - | 246.1 | 0.6200 |
| | -18 | 2.62 | 1.55 | 1.30 | 18 | - | - | - | - |
| BH-4 | -3 | 2.60 | 1.69 | 1.12 | 51 | 53 | 26 | 703.0 | 0.0175 |
| | -6 | 2.70 | 1.64 | 1.07 | 53 | 52 | 26 | 632.7 | 0.0201 |
| | -9 | 2.88 | - | - | - | 33 | 19 | - | - |
| | -12 | 2.78 | 1.46 | 1.17 | 25 | - | - | - | - |

III-7 Catch Composition of PPFC's Marine Trawlers

(1980/81)

(M.T.)

| SR NO | NAME OF FISH | | CATCH | |
|----------|-------------------------|-------------------------------|---------|--------|
| | ENGLISH COMMON NAME | SCIENTIFIC NAME | TON | % |
| 1 | Red Pony Fish | <u>Liovnathus insidiator</u> | 1420.91 | 16.8 |
| 2 | Javalin Fish | <u>Pomadasys- argyreus</u> | 788.08 | 9.3 |
| 3 | Herring | <u>Ilisha elongata</u> | 800.88 | 9.5 |
| 4 | Sea Cat Fish | <u>Arius venosus</u> | 736.34 | 8.7 |
| 5 | Ribbon Fish | <u>Trichiurus savala</u> | 599.76 | 7.1 |
| 6 | Croaker | <u>Sciaena coiter</u> | 422.67 | 5.0 |
| 7 | Sea Eel | <u>Muraenesox telabonides</u> | 426.53 | 5.0 |
| 8 | Red Snapper | <u>Lutianus Sp.</u> | 171.08 | 2.0 |
| 9 | Pony Fish | <u>Liovnathus Sp.</u> | 226.89 | 2.7 |
| 10 | Yellow Croaker | | 353.80 | 4.2 |
| 11 | Croaker | <u>Otolithus maculatus</u> | 182.63 | 2.2 |
| 12 | Thread Fin | <u>Polynemus indicus</u> | 191.01 | 2.3 |
| 13 | Sickle Fish | <u>Drepane punctata</u> | 55.77 | 0.7 |
| 14 | White or Silver Pomfret | <u>Pampus argenteus</u> | 56.86 | 0.7 |
| 15 | Rays | <u>Trygonidae</u> | 96.33 | 1.1 |
| 16 | Shark | <u>Aprionodon acutidens</u> | 74.00 | 0.8 |
| 17 | Horse Mackerel | <u>Chorinemous lysan</u> | 45.39 | 0.5 |
| 18 | Thread Fin Bream | <u>Nemipterus japonicus</u> | 244.63 | 2.9 |
| 19 | Lizard Fish | <u>Saurida Sp.</u> | 100.84 | 1.2 |
| 20 | Wolf Herring | <u>Chinocentrus Sp.</u> | 26.45 | 0.3 |
| 21 | Milk Fish | <u>Chanos chanos</u> | 47.84 | 0.6 |
| 22 | Croaker | <u>Sciaena blekeri</u> | 21.76 | 0.3 |
| 23 | Spiny Eel | <u>Mastacembelus Sp.</u> | 12.27 | 0.1 |
| 24 | Dolphin Fish | <u>Coryphaena hippurus</u> | 18.45 | 0.2 |
| 25 | Horse Mackerel | <u>Carangoides-ferdau</u> | 82.64 | 1.0 |
| 26 | Spotted Field Perch | <u>Nandus marmoratus</u> | 12.87 | 0.2 |
| 27 | Squid/Cuttle Fish | <u>Sepia Sp.</u> | 9.40 | 0.1 |
| 28 | Goat Fish | <u>Upeneus Sp.</u> | 88.35 | 1.0 |
| 29 | Chub Mackerel | <u>Rastrelliger neglectus</u> | 29.89 | 0.4 |
| 30 | Lobster | <u>Penulirus Sp.</u> | 6.59 | 0.1 |
| 31 | White Shrimp | <u>Peneaus merguensis</u> | 21.52 | 0.3 |
| 32 | Tiger Shrimp | <u>Peneaus monodon</u> | 39.26 | 0.5 |
| 33 | Others | | 1019.45 | 12.0 |
| 34 | Sole Fish | <u>Cynoghossus Sp.</u> | 20.10 | 0.2 |
| | | | 8451.24 | 100.0% |

(1982/83)

(M.T.)

| SR NO | NAME OF FISH | | CATCH | |
|----------|-------------------------|-------------------------------|----------|--------|
| | ENGLISH COMMON NAME | SCIENTIFIC NAME | TON | % |
| 1 | Red Pony Fish | <u>Liovnathus insidiator</u> | 1379.81 | 12.4 |
| 2 | Javalin Fish | <u>Pomadasys-argyreus</u> | 1213.70 | 10.9 |
| 3 | Herring | <u>Ilisha elongata</u> | 1911.85 | 17.2 |
| 4 | Sea Cat Fish | <u>Arius venosus</u> | 851.22 | 7.7 |
| 5 | Ribbon Fish | <u>Trichiurus savala</u> | 563.91 | 5.1 |
| 6 | Croaker | <u>Sciaena coiter</u> | 274.86 | 2.5 |
| 7 | Sea Eel | <u>Muraenesox telabonides</u> | 372.94 | 3.4 |
| 8 | Red Snapper | <u>Lutianus Sp.</u> | 163.72 | 1.5 |
| 9 | Pony Fish | <u>Liovnathus Sp.</u> | 99.17 | 0.9 |
| 10 | Yellow Croaker | | 553.79 | 5.0 |
| 11 | Croaker | <u>Otolithus maculatus</u> | 183.41 | 1.6 |
| 12 | Thread Fin | <u>Polynemus indicus</u> | 229.12 | 2.1 |
| 13 | Sickle Fish | <u>Drepane punctata</u> | 103.29 | 0.9 |
| 14 | White or Silver Pomfret | <u>Pampus argenteus</u> | 104.93 | 0.9 |
| 15 | Rays | <u>Trygonidae</u> | 519.60 | 4.7 |
| 16 | Shark | <u>Aprionodon acutidens</u> | 73.23 | 0.7 |
| 17 | Horse Mackerel | <u>Chorinemous lysan</u> | 35.76 | 0.3 |
| 18 | Thread Fin Bream | <u>Nemipterus japonicus</u> | 131.79 | 1.2 |
| 19 | Lizard Fish | <u>Saurida Sp.</u> | 84.68 | 0.8 |
| 20 | Wolf Herring | <u>Chinocentrus Sp.</u> | 48.21 | 0.4 |
| 21 | Milk Fish | <u>Chanos chanos</u> | 46.64 | 0.4 |
| 22 | Croaker | <u>Sciaena blekeri</u> | 33.38 | 0.3 |
| 23 | Spiny Eel | <u>Mastacembelus Sp.</u> | 8.38 | 0.1 |
| 24 | Dolphin Fish | <u>Coryphaena hippurus</u> | 29.95 | 0.3 |
| 25 | Horse Mackerel | <u>Carangoides-ferdau</u> | 61.59 | 0.6 |
| 26 | Spotted Field Perch | <u>Nandus marmoratus</u> | 18.87 | 0.2 |
| 27 | Squid/Cuttle Fish | <u>Sepia Sp.</u> | 24.08 | 0.2 |
| 28 | Goat Fish | <u>Upeneus Sp.</u> | 143.65 | 1.3 |
| 29 | Chub Mackerel | <u>Rastrelliger neglectus</u> | 20.91 | 0.2 |
| 30 | Lobster | <u>Penulirus Sp.</u> | 12.51 | 0.1 |
| 31 | White Shrimp | <u>Peneaus merguensis</u> | 40.09 | 0.4 |
| 32 | Tiger Shrimp | <u>Peneaus monodon</u> | 26.97 | 0.2 |
| 33 | Others | | 1719.30 | 15.5 |
| 34 | Sole Fish | <u>Cynoghossus Sp.</u> | 0.06 | - |
| | | | 11085.37 | 100.0% |

(1981/82)

(M.T.)

| SR NO | NAME OF FISH | | CATCH | |
|----------|-------------------------|-------------------------------|----------|--------|
| | ENGLISH COMMON NAME | SCIENTIFIC NAME | TON | % |
| 1 | Red Pony Fish | <u>Liovnathus insidiator</u> | 1674.40 | 16.0 |
| 2 | Javalin Fish | <u>Pomadasys-argyreus</u> | 1039.12 | 10.0 |
| 3 | Herring | <u>Ilisha elongata</u> | 1142.00 | 11.0 |
| 4 | Sea Cat Fish | <u>Arius venosus</u> | 825.22 | 7.8 |
| 5 | Ribbon Fish | <u>Trichiurus savala</u> | 651.95 | 6.1 |
| 6 | Croaker | <u>Sciaena coiter</u> | 376.36 | 3.6 |
| 7 | Sea Eel | <u>Muraenesox telabonides</u> | 389.46 | 3.7 |
| 8 | Red Snapper | <u>Lutianus Sp.</u> | 327.06 | 3.1 |
| 9 | Pony Fish | <u>Liovnathus Sp.</u> | 299.14 | 2.8 |
| 10 | Yellow Croaker | | 308.36 | 3.0 |
| 11 | Croaker | <u>Otolithus maculatus</u> | 172.57 | 1.6 |
| 12 | Thread Fin | <u>Polynemus indicus</u> | 337.31 | 3.2 |
| 13 | Sickle Fish | <u>Drepane punctata</u> | 139.95 | 1.3 |
| 14 | White or Silver Pomfret | <u>Pampus argenteus</u> | 112.78 | 1.1 |
| 15 | Rays | <u>Trygonidae</u> | 120.53 | 1.1 |
| 16 | Shark | <u>Aprionodon acutidens</u> | 92.98 | 0.8 |
| 17 | Horse Mackerel | <u>Chorinemous lysan</u> | 74.60 | 0.7 |
| 18 | Thread Fin Bream | <u>Nemipterus japonicus</u> | 168.87 | 1.6 |
| 19 | Lizard Fish | <u>Saurida Sp.</u> | 66.39 | 0.6 |
| 20 | Wolf Herring | <u>Chinocentrus Sp.</u> | 37.16 | 0.4 |
| 21 | Milk Fish | <u>Chanos chanos</u> | 19.50 | 0.2 |
| 22 | Croaker | <u>Sciaena blekeri</u> | 45.11 | 0.4 |
| 23 | Spiny Eel | <u>Mastacembelus Sp.</u> | 13.32 | 0.1 |
| 24 | Dolphin Fish | <u>Coryphaena Hippurus</u> | 26.65 | 0.2 |
| 25 | Horse Mackerel | <u>Carangoides-ferdau</u> | 87.55 | 0.8 |
| 26 | Spotted Field Perch | <u>Nandus marmoratus</u> | 28.83 | 0.3 |
| 27 | Squid/Cuttle Fish | <u>Sepia Sp.</u> | 11.91 | 0.1 |
| 28 | Goat Fish | <u>Upeneus Sp.</u> | 22.81 | 0.2 |
| 29 | Chub Mackerel | <u>Rastrelliger neglectus</u> | 21.04 | 0.2 |
| 30 | Lobster | <u>Penulirus Sp.</u> | 8.90 | 0.1 |
| 31 | White Shrimp | <u>Peneaus merguensis</u> | 41.41 | 0.4 |
| 32 | Tiger Shrimp | <u>Peneaus monodon</u> | 34.92 | 0.3 |
| 33 | Others | | 1814.34 | 17.2 |
| 34 | Sole Fish | <u>Cynoghossus Sp.</u> | 1.73 | - |
| | | | 10534.23 | 100.0% |

III-8 Catch Composition of PPFC Freshwater Fisheries

(1982/83)

| SR NO | NAME OF FISH | | CATCH | |
|----------|--------------------------|-----------------------------------|------------|-------|
| | ENGLISH COMMON NAME | SCIENTIFIC NAME | Kg | % |
| | <u>Freshwater Fishes</u> | | | |
| 1 | Mouth Breeder Fish | <u>Tilapia mossambica</u> | 288,895.84 | 13.29 |
| 2 | Barb Fish | <u>Barbus stigma</u> | 495,881.88 | 22.81 |
| 3 | Climbing Perch | <u>Trichogaster labiosus</u> | 284,018.48 | 13.06 |
| 4 | Climbing Perch | <u>Anabas testudineus</u> | 66,764.40 | 3.07 |
| 5 | Glass Fish | <u>Ambassis baculis</u> | 49,895.36 | 2.29 |
| 6 | Carplet | <u>Amblypharyngodon mola</u> | 42,426.80 | 1.95 |
| 7 | Snakehead Fish | <u>Ophiocephalus striatus</u> | 111,829.96 | 5.14 |
| 8 | Fish Fry | - | 143,047.36 | 6.58 |
| 9 | Cat Fish | <u>Clarius batrachus</u> | 54,387.32 | 2.50 |
| 10 | Snakehead Fish | <u>Ophiocephalus punctatus</u> | 46,676.04 | 2.15 |
| 11 | Small Assorted Fishes | - | 41,470.68 | 1.91 |
| 12 | Scorpion Fish | <u>Heteropneustes fossilis</u> | 72,479.80 | 3.33 |
| 13 | Dwarf Cat Fish | <u>Mystus bleekeri</u> | 94,944.52 | 4.37 |
| 14 | Goby Fish | <u>Gobius natus</u> | 38,213.64 | 1.76 |
| 15 | Featherback Fish | <u>Notopterus notopterus</u> | 4,368.96 | 0.20 |
| 16 | Featherback Fish | <u>Notopterus notopterus</u> | 5,052.84 | 0.23 |
| 17 | Sheat Fish | <u>Wallago attu</u> | 34,114.80 | 1.57 |
| 18 | Carplet Fish | <u>Rohtee belangeri</u> | 27,110.84 | 1.25 |
| 19 | Small Assorted Fishes | - | 12,511.56 | 0.57 |
| 20 | Spotted Field Perch | <u>Nandus Marmoratus</u> | 3,442.36 | 0.16 |
| 21 | Featherback Fish | <u>Notopterus notopterus</u> | 29,782.40 | 1.37 |
| 22 | Sheat Fish | <u>Ompok pabo</u> | 16,204.84 | 0.74 |
| 23 | Carp | <u>Labeo calabasu</u> | 7,317.68 | 0.34 |
| 24 | Butter Cat Fish | <u>Pseudotropius acutirostris</u> | 11,330.76 | 0.52 |
| 25 | Carp | <u>Catla catla</u> | 18,340.12 | 0.84 |
| 26 | Spiny Eel | <u>Mastacembelus zebrinus</u> | 10,158.16 | 0.47 |
| 27 | Carp | <u>Labeo rohita</u> | 2,935.60 | 0.14 |
| 28 | Carplet Fish | <u>Rohtee cotio</u> | 23,329.00 | 1.07 |
| 29 | Carp | <u>Cirrhina mrigala</u> | 3,642.44 | 0.17 |
| 30 | Flying Barb | <u>Chela sardinella</u> | 1,215.24 | 0.06 |


(1982/83)

| SR NO | NAME OF FISH | | CATCH | |
|----------|---------------------|-------------------------------|--------------|--------|
| | ENGLISH COMMON NAME | SCIENTIFIC NAME | Kg | % |
| 31 | Butter Cat Fish | <u>Eutropiichthyes vecha</u> | 447.72 | 0.02 |
| 32 | Sea Perch Fish | <u>Lates calcarifer</u> | 2,937.24 | 0.14 |
| 33 | Gar Fish | <u>Belone cancila</u> | 2,983.16 | 0.14 |
| 34 | Carp | <u>Labeo kontius</u> | 1,366.12 | 0.06 |
| 35 | Barb Fish | <u>Barbus sewelli</u> | 32.80 | 0.002 |
| 36 | Snakehead Fish | <u>Ophiocephalus marulius</u> | 121.36 | 0.006 |
| 37 | Dwarf Cat Fish | <u>Mystus seenghala</u> | 149.24 | 0.007 |
| 38 | Assorted Fishes | - | 52.48 | 0.002 |
| 39 | Imperialangel Fish | <u>Holaeanthus imperator</u> | 103.32 | 0.005 |
| 40 | Carp | <u>Catlocarpio siamenses</u> | 4.92 | 0.0002 |
| 41 | Croaker | <u>Sciaena coitor</u> | 121,628.96 | 5.60 |
| 42 | Carp | <u>Labeo gonius</u> | 2,464.92 | 0.11 |
| | | | 2,174,111.92 | 100.0% |

(1982/83)

| SR NO | NAME OF FISH | | CATCH | |
|----------|-------------------------|--|------------|--------|
| | ENGLISH COMMON NAME | SCIENTIFIC NAME | Kg | % |
| | <u>Freshwater Prawn</u> | | | |
| 1 | Freshwater Prawn | <u>Palaemon mirabilis</u> | 441,848.80 | 77.3 |
| 2 | " | <u>Metapenaeus monoceros</u> | 87,375.92 | 15.3 |
| 3 | " | <u>Metapenaeus lysianassa</u> | 13,608.72 | 2.38 |
| 4 | " | <u>Penaeus penicillatus</u> | 1,379.24 | 0.24 |
| 5 | " | - | 16,933.00 | 2.96 |
| 6 | " | <u>Palaemon mirabilis/</u> <u>Metapenaeus monoceros</u> | 4,821.60 | 0.84 |
| 7 | " | <u>Palaemon villosimanus</u> | 5,525.16 | 0.97 |
| 8 | Tiger Prawn | <u>Penaeus monodon</u> | 8.20 | 0.0014 |
| | | | 571,500.64 | 100.0% |

III-9 Chart A-1 Flow Rate Chart.



JICA