

## 9-5 代替案の設定

代替案の設定はチェンカレン地区 (Cengkareng) にふさわしい住戸密度を実現すると共に、F5タイプ住宅率、分譲用地率においても適切な数値を得るような住戸配分パターンを選び出すことにある。事業収支バランスの節で述べたように、住戸配分パターンが住戸密度とF5タイプ住宅率を決定する基本的要素である。以下に住戸配分パターンによって上述の諸要素がどのような影響をうけるかの検討をおこなう。

### 9-5-1 供給住宅群パターン特性

タイプ別住戸数の配分比により住戸密度・F5住宅率、分譲用地率がどのように変化するかを、供給住宅群パターン毎にみたものがFig-9-6から9-9までの4図である。Fig-9-5はこれを模式的にあらわしたものであり、縦軸にF5住宅の戸数比をパーセントであらわし、横軸に住戸密度と分譲用地率をとったグラフを並べて一組の図としている。図中の6本の曲線は2本づつが組になった3組からなり、三つの償還方式に対応している。一組2本の曲線は同じ償還方式でF5住宅が累積所得分布の50パーセントより下位に供給される場合と、上に供給される場合のちがいをあらわしている。また住戸密度をあらわしたグラフと分譲用地率をあらわしたグラフを横軸に平行な直線で結ぶことにより、そのときの住戸密度・分譲用地率・F5住宅率の数値を知ることができる。たとえば傾斜償還方式の場合、分譲用地率が30%の点をとると、そのときのF5住宅率は10% (A点)であり住戸密度は70戸/ha (B点)であることが図から読みとれる。




Fig 9-5 償還方式別相関模式図  
(密度-F5タイプ住宅率-分譲用地率)




Fig 9-6 供給パターン別住戸密度等相関図  
— 高密完成型




Fig 9-7 供給パターン別住戸密度等相関図  
— 高密混合型




Fig 9-8 供給パターン別住戸密度等相関図  
—中密増築型




Fig 9-9 供給パターン別住戸密度等相関図  
—中密従来型

四つの供給住宅群を比較すると、高密完成型住宅群は住戸密度 100戸/ha をこえる住戸配分が可能であるのに対して高密混合型・中密増築型においては 70戸/ha 前後が最大の住戸密度である。また中密従来型では 60戸/ha未満である。これは各住宅群の平均戸当り宅地面積を素直に反映しているとみることができる。F5住宅率をみると、傾斜償還の場合で30%、定額償還の場合で20%がおおよその上限である。この傾向は供給住宅群のちがいでによって大きく異なるということはない。しかもどの場合においても、F5住宅率が上限に近づいたときの分譲用地率は60%から80%というような大きな割合になる。これはF5住宅のコストが高いために、その割合が大きくなればサブシディのための分譲用地率も高くなることを示している。

ひとつの供給住宅群に着目した場合には、当然のことながら傾斜償還による場合が最も住戸密度が高く、定額償還(30~70パーセント)定額償還(20~70パーセント)の順に密度が低くなる。ただし定額償還の二つの場合の差はそれほど大きくはない。

### 9-5-2 代替案の設定

代替案の設定は前項のグラフを参考にして以下の枠組の中から選択する。

- 1) 計画目標密度の範囲である 60戸/ha ~ 80戸/haを実現できること。
- 2) 低所得者層を対象としていない分譲用地の比率は 30%をこえないこと。

ただし住宅地に必要な商業用地のために 76,000 $m^2$ の分譲用地は最低確保する。これは用地全体の約 12%にあたる。

これらの条件に合ったグラフ上の線分を Fig-9-10、11に示す。太線部は分譲用地率が 12%から 30%の範囲である。




Fig 9-10 最終代替案の抽出—高密混合型

以上の検討により三つの供給パターンが代替案に該当することがわかる。各供給パターンの中で住戸密度およびF5タイプ住宅率の最も高い点を選び、その点の住戸配分を示したものが Table-9-8である。これらを最終的な代替案に設定する。

Table 9-8 最終代替案の諸元

Type of Housing Group for Supply	Repayment Method	Lower + Housing Supply + Upper Allocation					Total Housing Units	Housing Density	Walk-up Flat Ratio	Empty lot Ratio
		F5-36	F2-36	M-36	R-36N	E.L.				
1. High Density Combination	Gradual	F5-36	F2-36	M-36	R-36N	E.L.	7550	69	12	30
		880	2510	1890	1500	770				
2. High Density Combination	Gradual	F5-36	F2-36	M-36	R-36N	E.L.	8340	76	2	12
		170	4000	2340	1830	0				
3. High Density Combination	Gradual	F2-36	M-36	F5-36	R-36-N	E.L.	6670	61	4	30
		1590	1360	240	2710	770				

### 9-5-3 代替案の総合評価

3つの代替案について定性的、定量的側面からそれぞれの評価を行ない、現時点で最も適切と考えられる代替案を選択する。

まず、<sup>\*</sup>中層住宅の割合をみると、最低2%、170戸から最高12%、880戸までの拡がりがある。本プロジェクトの中で中層住宅の位置づけは、実験的なものというよりは、住宅団地を構成する一つの「コマ」<sup>\*</sup>として把えておく。従って、住宅団地の全体構成からみて10%前後の中層住宅供給が妥当と考えられる。<sup>\*</sup>F5タイプ。

分譲用地の割合は、12~30%と設定したものの、それが12%の場合は住宅用分譲用地の供給は不可能であり、全て、商業・業務用地となる。そこで本プロジェクトでは家内工業あるいは、店舗付住宅等の立地により、既存集落の住民の定着化、複合コミュニティの形成等を一つの計画目標に掲げているため、住宅用分譲用地の確保は不可欠である。そのため全供給戸数の10%前後の分譲用地が一つの適切な供給量と考えておく。

住宅の戸数密度は CENGKARENG の立地特性からより高い方が望ましい。これら三つの代替案はいずれも60戸/ha以上を確保しており、従来の住宅団地よりは20%以上も高密な住宅地を形成しているが、可能であれば70戸/ha以上を確保することが望ましい。

中層住宅および2階建フラットをより低い所得階層に供給し、増築可能な住宅タイプをより高い所得階層に供給することが住宅地の環境水準をより高く維持するための一つの手法と考えられる。かつ所得の高い階層は増築可能な接地形住宅を求める意識が強く、これまでの住宅団地をみると、それらの階層は比較的良質な増築を行って来ている。従って代替案(3)のような供給パターンは余り望ましくない。

供給すべき住宅タイプの配分は、あるタイプが極端に多く、他は極端に少ないというよりは、需要の多様性、住宅地の変化ある構成等から配分にバランスを

持つ必要がある。そこで代替案(2)の場合は全体の半数が2階建フラット、中層は2%、分譲用地は0ということで全体にバランスを欠いていると云える。一方代替案(1)は全体に各タイプとも10%以上の配分を示しており、バランスのとれた住宅タイプの配分と云える。

クロスサブシディは、所得の高い階層から低い階層へ、さらにより低い階層がより多いサブシディを受けることが最も自然な形である。そこで代替案(3)の場合はより高い階層の住宅がより低い階層の住宅よりはより多いサブシディを受けていることになり不自然な形となっている。

以上のような代替案の評価から総合的な判断として代替案(1)が最も現時点で適切な代替案と考えられる。

そこで以下の作業はこの代替案(1)を基礎に地区の総合計画、建設計画、財務分析、経済分析を展開する。



9-5-4 高地価地区を想定した住戸密度等の補足検討

(1) 従来 PERUM PERUMNAS が開発してきた住宅地にくらべると Cengkareng の土地価格は高い方に属する。しかし Jakarta市の中心部にくらべるとまだまだ低価格である。前項までの検討において、住宅建設費のなかをしめる土地整備費のコストは約1/2であることがわかっている。したがって、住戸密度をあげることによって戸当たりコストを低くする効果はそれほど大きくはない。しかし更に地価の高い地区ならば、住戸密度をあげることによって戸当たりコストを低くする効果は十分大きくなるであろう。将来、地価の上昇率が建築費の上昇率を上まわるような時にも同じ考え方を適用できるであろう。そしてこのような想定は人口集中のすすむ大都市近郊地では十分現実的である。

以上のような観点から、他の条件は同じで土地価格だけを上昇させた場合の検討を以下に試みる。地価は現況の2倍、5倍、10倍の三つの場合を想定する。検討内容は住戸密度とF5タイプ住宅率・分譲用地率の相関である。

(2) 検討のケースは、三つの土地価格設定に対して住宅供給群パターンの四つの場合をかけあわせた12ケースである(Table 9-10。)償還方式は傾斜方式(20~80パーセント対象)のみとする。

Table 9-9 検討ケース

土地価格の設定(1980年)	開発土地原価*	住宅供給群	償還方式
6,000RP/m <sup>2</sup> (2倍)	36,700RP/m <sup>2</sup> (1.3倍)	F2-26 F5 F2-36 M	20 50 80 (傾斜償還)
15,000RP/m <sup>2</sup> (5倍)	55,900RP/m <sup>2</sup> (2.4倍)	F5 F2-36 M R-36N	
		F5 M R-36N R-36	
30,000RP/m <sup>2</sup> (10倍)	92,300RP/m <sup>2</sup> (4.1倍)	F5 D-15 D-21 D-36	

\* 1983年12月価格

\*\* いずれも Cengkareng の価格に対する比。

Cengkareng の設定買収地価は、3,000RP/m<sup>2</sup>。(8-4説明参照)。

これらの検討ケースに Cengkareng の場合を加えてグラフにあらわしたものが Fig 9-11~14 である。




Fig 9-1-1 地価の変動による住戸密度等の検討 一高密完成型




Fig 9-1-2 地価の変動による住戸密度等の検討 一高密混合型




Fig 9-13 地価の変動による住戸密度等の検討 — 中密増築型




Fig 9-14 地価の変動による住戸密度等の検討 — 中密従来型

これらのグラフによれば

- i) 地価が高くなるにつれて住戸密度がさがり、分譲用地率が上る。
- ii) 分譲用地率が65パーセント近くの値のとき、地価の影響をうけないような住戸密度とF5タイプ住宅率がどの住宅供給群にも存在する。このときのF5タイプ住宅率は20～30パーセント、住戸密度は45～60戸/haである。
- iii) 地価が5倍以上になると、F2-26タイプの住宅をふくまない三つの住宅供給群において、住戸密度とF5タイプ住宅率が正比例の関係になる。

の三つが特徴点である。特に第3点目は、F5タイプ住宅を増すことによって住戸密度をあげるためには、Cengkareng の5倍の地価の場所であること、または建築費に比べて地価上昇率が5倍に達するような時期であることのどちらかが必要なことを示している。このような条件を満たしてはじめて、F5タイプ住宅が住戸密度を高める手段として有効となる。

## 第10章 財務分析

Handwritten notes in the top right corner, including the number '10' and some illegible scribbles.

Handwritten notes on the right side of the page, including the number '10' and some illegible scribbles.

Handwritten notes on the right side of the page, including the number '10' and some illegible scribbles.

Handwritten notes in the center of the page, including the number '10' and some illegible scribbles.

A single handwritten mark or character in the lower middle section of the page.

Handwritten notes in the bottom right corner, including the number '10' and some illegible scribbles.

## 第10章 財務分析

10-1	概 要 .....	1
10-2	キャッシュ・フロー .....	2
10-3	事業収支 .....	5

.



## 10-1 概要

PERUMNAS の事業は中央政府等からの出資金、民間ローンの50%近い13.5%/年という低金利の資金を政府関連金融機関から借入れ、それと自己資金とを組み合せ、事業単位ごとに収支をバランスさせることを原則としている。従って本プロジェクトもその原則に基づき、キャッシュフローを作成して財務分析評価を行った結果、最終的には41,143百万円Rpの投資額（事業費総支出額）に対して43,012百万Rpの収入を得て、収支がほぼバランスを保っている。

一方 PERUMNAS の REPELITA III で12万戸の住宅建設を予定した場合の総事業規模は350,000百万Rp以上である。その中で本プロジェクトの総投資額は約40,000百万Rpであるところから、総事業規模に占める本プロジェクトの割合は約11%になる。一方本プロジェクトの総住宅建設戸数は7,500戸であり、12万戸の6%に当たり、本プロジェクトの投資額は戸数比に対しては大きい。しかしこれは本プロジェクトがインドネシア国全体でみた場合、最も高地価の都市近郊地に立地していることと、低地開発のための基盤整備費の高コストに起因するものである。他のプロジェクトはより低地価で開発の容易なところに立地しており、戸数当りの投資額は相対的に低くなる。従って、本プロジェクトが PERUMNAS 全体の事業のバランスをくずすことはないと言える。

本プロジェクトでは総建設戸数の10%以上に当る880戸の中層住宅を供給している。現時点でこの中層住宅は先駆的住宅タイプでそれに対する国民の嗜好性も明確ではなく、確実に有効需要を引き出すには若干の不安がある。

しかし本プロジェクトは最も低い所得層に中層住宅を供給しており、建設コストが他と比較して2倍以上であるものの、最も低く販売価格を設定している。そのため若干の売れ残りが生じたとしても本プロジェクトの財務フレームに影響を与える度合は少なく、財務上安全な供給方式と言える。

## 10-2 キャッシュ・フロー

a) 本プロジェクトは政府関連の金融機関であるBTNからの融資とPERUM PERUMNASの自己資金とを組み合わせで遂行される。

開発にあたってPERUM PERUMNASの自己資本は、まず

Land acquisition Cost

Planning Cost

に充当される。さらにそれは

Interest

Overhead

Investment for Allocation

Insurance

をまかなう、

一方BTNからの融資(建設資金)は

Infrastructure Cost

Housing Construction Cost

(Physical ContingencyとPrice Contingencyを含む

という事業の中心部にむけて充当される。

この建設資金融資の金利は13.5% / 年(3.375% / 3ヶ月)である。

b) 事業期間におけるインフレーションは年々15%と見込まれる。

c) 建設終了後直ちに、住宅および住宅地はBTNに売却される。<sup>※</sup>

この売上代金の一部は金融機関からの建設融資への返済に当てられ、他の部分はPERUM PERUMNASの自己資本に移転されて、次の事業のために繰越される

d) キャッシュ・フローをTable 10-1に、期毎の融資及びその利子と返済のフローをTable 10-2に示す。

※注 入居者はBTNからの融資を受けて住宅あるいは住宅地を購入し、20年間でBTNに返済する。そのため資産の受け渡しはPERUM PERUMNAS → BTN (入居者)となり、資金の回収はBTN → PERUM PERUMNASとなる。

Table 10-1 キャッシュフロー

Item	Year	1981					1982					1983					1984			
		Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec	Jan-Mar	Apr-Jun	Jul-Sep	Oct-Dec	Jan-Mar		
Source of Funds	Balance																			
	Capital of PERUMAS	3,815,163	10,893	193,208	277,984	649,369	1,048,081												7,009,963	
	Loan from Government Bank		81,797	1,248,892	1,605,538	3,698,361	5,704,813													
	Selling of Empty Lots										4,355,166								4,355,166	
	Selling of Houses											17,150,967							17,150,967	
	Total	3,815,863	92,690	1,442,100	1,883,522	4,347,730	6,752,894	21,506,133	12,356,484										28,516,096	
	Land Acquisition	3,430,900																		
	Planning	345,258																		
	Infrastructure		35,222	65,437	345,435	489,195	1,231,375	1,983,072	952,900											
	Housing Construction			906,753	938,996	2,469,494	3,332,474	4,013,675	2,493,836											
Use of Funds	Physical Contingency		3,522	99,911	128,443	295,869	456,386	541,220	344,673											
	Price Contingency		5,283	9,816	192,664	443,803	684,578	811,831	517,010											
	Overhead	34,526	8,160	124,889	160,554	369,836	570,482	734,979	430,842											
	Interest of the Loan		1,486	4,247	46,397	100,584	225,403	417,941	417,941											
	Investment for Allocation	5,179	1,227	18,774	74,083	55,475	85,572	110,747	64,677											
	Insurance			45,338	46,950	123,474	166,624	200,684	124,692											
	Cost for the Right to Build											136,000								
	Loan Repayment																			
	Total	3,815,863	92,690	1,442,100	1,883,522	4,347,730	6,752,874	9,149,649	5,346,521	18,685,659										

(12,356,484) (7,009,963) (9,830,437)

Table 10-2 融資と利子及び返済のフロー

Year		Loan from BTN	Loan Repayment	Balance	Interest
'82	Jan-Mar	44,027		44,027	0
	Apr-Jun	81,797		125,824	1,486
	Jul-Sep	1,248,892		1,374,716	4,247
	Oct-Dec	1,605,538		2,980,254	46,397
'83	Jan-Mar	3,698,361		6,678,615	100,584
	Apr-Jun	5,704,813		12,383,428	225,403
	Jul-Sep			12,383,428	417,941
	Oct-Dec			12,383,428	417,941
'84	Jan-Mar		12,383,428	0	417,941

### 10-3 事業収支

上に示したキャッシュ・フローにもとづく期毎の収入と支出を集計 (Sum up) したところで収支計算表を作成すると次のとおり。

#### 1. Revenue (Sales)

FS'5 - 3 6	3,067,483
FS'2 - 3 6	10,139,478
M - 3 6	10,338,725
R - 3 6 N	10,756,247
Empty Lots	4,238,311
Commercial Lots	2,935,627
Irregular Lots	1,536,393
<hr/>	
Total	43,012,264

#### 2. Expenses

Land Acquisition	3,430,900
Planning	345,258
Infrastructure	6,767,320
Housing Construction	16,737,740
Physical Contingency	2,230,481
Price Contingency	3,345,721
Overhead	2,942,655
Interest	1,631,940
Investment for Allocation	441,398
Insurance	836,887
Cost for the Right to Build	272,000
Land Price Increase	2,161,466
<hr/>	
Total	41,143,766

3. Profit 1,868,498



## 第11章 經濟分析

1. The first part of the document discusses the importance of maintaining accurate records of all transactions and activities. It emphasizes that this is crucial for ensuring transparency and accountability in the organization's operations.

2. The second part of the document outlines the specific procedures and protocols that must be followed to ensure that all records are properly maintained and updated. It details the roles and responsibilities of the staff involved in this process.



## 第11章 経 済 分 析

11-1	Cengkareng 地区住宅開発の社会・経済的意義 .....	1
11-1-1	住宅開発の基本的性格・目標	1
11-1-2	Cengkareng 地区の社会公共的環境	5
11-1-3	便 益 の 内 容	6
11-2	経済性の分析 (Economic Feasibility) .....	11
11-2-1	直接的便益の評価と内部収益率 (IRR)	11
11-2-2	その他の社会・経済的便益	18



## 11-1 Cengkareng 地区住宅開発の社会・経済的意義

### 11-1-1 住宅開発の基本的性格・目標

Cengkareng Project の基本性格は、発展途上国に共通な都市過密化問題に対応できる総合的な社会開発計画の実施というところにある。

都市に流入・増大する人口は、都市内の部落部（カンボン）や市街地の各所で質の低い住宅に住みつき、また不法居住をくりかえしている。多数は借家依存の生活を営んでいる。

一方、流入人口の多くは都市における雇用機会の不足や不安定に悩んでいる。これに対応するためには、流入・増大した人口を都市外周部に分散させること、未利用地を活用し、市街地に残る限られた空間を有効利用することによって住宅建設をすすめること、村落部における農業活動を維持するとともに、市街部での商工業建設活動を振興して雇用機会の増大を図ることである。

Cengkareng Project はこの対応策の一環として

- ・ 都市に近い低湿地・未利用地帯を活用し、
- ・ 緑地の確保に努めながら社会公共施設やインフラストラクチャの整備を行い、
- ・ Jakarta-Tangerang 街路沿いの道路交通体系を再編成しつつ、
- ・ 中層住宅を含む都市型高密度住宅建設を行う。
- ・ また産業用地の提供を行って、現存の商工業活動の一部を地区内にとり入れ、また将来の産業化計画との連関を深めることによって雇用機会増大を図る。

そのための都市・住宅開発計画である。

こうして小規模開発では達成しにくい「住む、レクリエートする、就業する」という三つの生活機能を多少とも自足的に営めるような、したがって社会・経済的便益性の高い住宅団地を建設することをめざしているのである。

Fig 11-1 は以上を Cengkareng Project の社会・経済的便益の系譜図としてまとめたものである。


Fig 11-1 社会・経済的便益の系譜図

Problem of Overpopulation in Cities  
in Developing Countries

[Countermeasures]

[Urban Housing Project +  
Formation of Benefit Generation Sources]

[Basic Characteristics and  
Objectives of Project]



A slightly integrated social development program including a supply of residential houses, the consolidation of living environments, and the creation of employment opportunities. Benefits, which cannot be attained by small-scale development, are designed to be achieved in the peripheral sections of cities.



### 11-1-2 Cengkareng 地区の社会公共的環境

現時点においては、Cengkareng 地区の社会的条件、住環境、水道・電気施設の状況は他地域に比して概してよくない。都心から 10 km 以内の地点にあり、しかも将来周辺の Jakarta-Tangerang 地域にむけて商工業、幹線道路、空港等の活発な展開が計画されているという意味ではきわめてポテンシャルの高い地域でありながら、今一つ地域イメージが低いのは、この社会公共的環境の悪さに負っていると言つてよい。

他方学校、運動場、娯楽機関等の施設は、人口数との割合でみれば比較的良く整っているとみることができる。

“Statistik Wilayah DKI Jakarta”<sup>※</sup>の 1979 年版における資料によれば、次の諸点を指摘できる。

- i) まず低湿地帯であることによる洪水の発生、火災や犯罪の発生といった自然的・社会的安全性の指標からみると、Cengkareng は問題地区である。  
1979 年において洪水の発生件数は他の洪水多発地区なみの 6 件であるが、被害者数は人口の割には多く、また被害額は Cengkareng が全 Kecamatan 中最大となっている。それは 33,500 千Rp で DKI Jakarta 全体の被害額 78,047 千Rp の 43% をも占めている。
- ii) 火災による被害者数は Cengkareng が 30 kecamatan 中の 3 位、被害額は 8 位となっている。
- iii) 泥棒や掠奪の犯罪件数も多い方に属しているし、被害額も 30 地区のうち 5 位である。
- iv) 79 年の Cengkareng において水道の敷設されている村数 (kelurahan) は 1、敷設されていない村は 9、水道の水の利用割合は 22.4%、井戸水の利用割合は 64.13% である。これは 10 村中 1 つも水道の敷かれていない Pasar Minggu (South Jakarta) 地区に次ぐ悪条件である。
- v) 電気のきている村が 79 年の Cengkareng においては半数の 5 つを占める。電気利用のウェイトは 18.37%、石油ランプのウェイトは 58.12% である。これは Kel. Seribu 地区 (North Jakarta)、Pasar Rebo、Cakung 地区 (East Jakarta) 等とともに悪条件の代表例である。

30 kecamatan 中電気のきている村をもっているのは 9 地区であり、そ

※ Statistic Data of DKI Jakarta

のうち5地区は1つか2つの村に電気がきているだけである。残りの21地区においては電気利用のウエートはおおむね50%をこえ、高いところは80%前後に達している。

vi) 学校(幼稚園、小学校、中学校、高校)数は、人口の割には多く、また運動施設ではサッカー、テニス、バドミントンその他の運動場が、娯楽施設では映画館が比較的数多く整っている。

### 11-1-3 便益の内容

以上みてきたように現Cengkarengの社会・公共的環境が相対的に良くないだけに、新住宅団地開発のもたらす経済的便益は一層大きいものとなることが期待できる。

先にかかげた「住む、レクリエートする、就業する」の3つの生活機能に関連する諸々の施設・設備、住宅、行政機関、交通手段そして商・工業活動(これらは便益の発生源とみることができる)は、健康性、快適性、安全性、利便性、高効率性(時間節約性)、所得創出性等の指標を通して家計に様々な便益を与えることになろう。

新たな土地・住宅を購入することを通して、住民は結局のところ

- ・家計消費支出の節減
- ・所得増大
- ・提供される社会・経済的便益を享受しうる機会の増大

という成果を手に入れることができるのである。


Table 11-1は現プロジェクトがもたらす社会・経済的便益を、直接的便益と間接的便益にわけてリストアップし、それらの相互関係を示したものである。また11-2は住民が享受する直接的な便益の内容を、その発生源からたどって示したものである。

Table 11-1 プロジェクトの社会・経済的便益

Contents of the Project		[DIRECT BENEFITS]					[Indirect Benefits]						
		Benefits related to Household expenditure		Benefits in social and public activities (Saving in expenditure)	Employment expansion		Others Negative effects	Benefits brought indirectly from the present project					
		(Saving in expenditure)	(Income increase)		Project (Construction period)	(After construction)		Effects into economic and industrial activities	Welfare improvements for personal residents	The orderly growth of "Cities"	Effects by projects of higher level		
Land Preparation Infrastructure	Drainage				○	▲ Negative Traffic Aspects		Decline of flood					
	Sewage Treatment	(Disease control -) Saving in medical expenses							Decline of flood occurrence, diseases, improved health				
	Roads												
	Water	Water Saving							Increase of the fixed water ratio				
	Electricity	Electricity							Improvement in level of power supply				
	Others												
Housing	Expansion			Supply of low cost housing compared with the private sector	○	○	▲ Disturbance to the kampung residents						
Social Facilities (Community Service)	School			Merit as to lower cost in building rather than existing urban re-developing projects	○			Increase of educational opportunities					
	Medical Facilities							○		Improvements in medical care			
	Recreation & Sports Facilities		Increase of Employment opportunities							Increasing opportunities to promote recreational and sporting events			
	Others												
Retailing Industries	Industries			Increase of Employment opportunities	○			Increase of production + and its inter-industrial effects		Continuation of industrial expansion accompanied by opening of new airport			
	Small Scale Industries												
	Markets	Saving in transportation expense for shopping						○			Street peddling - Booth + Store		
	Small Shops												
Others													
Project (Well-Designed Site Planning)	TOTAL	KIP ↓ S68 ↓ ICN ↓ Land Rental/ Price Purchase increase	Improvement of living environment for a specific proportion of the whole population, whole households			Employment expansion in the construction materials industry and related industries during construction periods	▲ Cost of relating People ▲ Compensating them for their lost of property	Effects of public investments Improvement of managerial foundations for construction related industries and firms	Construction related Contiguous industry General improvements in labor productivity	Opportunity to initiate long term direction for the growth of cities Form a great center for urban activities in Jakarta Barat	Labour supply for new airport related business		



Fig 11-2 便益の内容(直接的便益)





## 11-2 経済性の分析 (Economic Feasibility)

チェンカレン地区の住宅開発計画に投じられた土地、資本、労働力等の基本的な生産要素は、どれだけの社会経済的厚生 (Welfare) を生み出すのか。それを明らかにするために 11-1 に示された当 Project の様々な社会・経済的效果を、可能なものについて定量化し、それを開発に要した投資額との関係で評価することが必要となる。同時に社会・経済的效果のうち定量化できない部分についても適切に留意し、評価を与えておかねばならない。つまりここでは次の2つの作業を行なう。

- 1) 当 Project の提供する土地・住宅が、居住者に与える直接的な便益を推計し、それを総建設コストとの関係で評価して実質的意味での収益 (Return) を明らかにする。
- 2) 11-1 に示した当 Project の様々な直接・間接の社会・経済的便益のうち、とくに次の効果を適切に評価する。
  - a) 建設期間中、および期間後における雇用拡大効果
  - b) 建材産業を中心とする生産性向上効果
  - c) 周辺工業地帯への安定的な労働力供給効果

### 11-2-1 直接的便益の評価と内部収益率 (IRR)

- a) この Project の供給する住宅が居住者にもたらす直接的な便益は、次の手順で考えることができる。
- i) 生産活動や開発行為によって形成される物財や資産の価値は、その供給と需要との関係によって規定されるという原理に則して、まず供給の側から考える。

ここで供給とは、この国の土地・資本・労働力という基本的生産要素 (資源) の一定部分を割りあてることによって、土地の造成、インフラの整備、住宅の建設を行うことである。この投資活動の結果、形成された社会的ストック、資産 (Property) はそのコストにみ合うある価値を体化している。それは土地の地価 (Land Price) であり、設備・建造物費用という固定資産価値である。それらの固定資産が年々の使用に供せられるとき、地代、設備機械損料、家賃・住居費 (Household expenditure) といった一種の賃貸料 (Rental Value) を生み出す。

チェンカレン地区の開発行為によって供給されるインフラのよく整備された土地と住宅は、一定の資産価値をもつとともに、この Rental Value を年々新たに生み出していく源となるのである。

ii) 次に土地・住宅を需要する居住者の側からみよう。

居住者が享受する直接的な便益は 11-1 の Fig 11-2 に示してある。

図にみるように居住者は以前に住んでいた所と比較してより一層の

- ・家計支出（食費、医療費、日用品費、交通費等）における様々な節約効果
- ・時間節約効果
- ・就業機会や副収入を得る機会
- ・提供される社会公共施設（病院、教育施設、モスク、運動場等）を利用できる機会


を享受できる。つまり総合的にみて一層良好な住環境を期待できるから、チェンカレン地区の土地・住宅を需要するのである。そして家計収入の中から一定割合の対価支払いに同意するのである。一般的にその対価とは期毎の家賃であり、またローンで住宅を購入する場合はその期毎の返済額である。また自己資金で一括購入する場合には、その将来価値の年々の価値への割引計算が行われる。

具体的にこのチェンカレン Project においては、住宅についてはローン購入とその期毎の返済が前提とされている。また、土地 (Empty Lot と Commercial Lot) については一括払購入が前提とされている。

iii) 以上の供給要因と需要要因は原理的には市場メカニズムの中で作用し、価格決定をもたらす。すなわち、次図のような異種の土地・住宅市場における需給関係が便益測定の基本となる価格（一種の Rental Value）を決定する。つまり A、A'、A''……、B、B'、B''……という各系列の土地・建物の消費者による選択行動と、一方それらの様々な経済的コストによる供給行動とが相互に作用しあって価格を決定するのである。

Property A A' A'' .....  
(well developed)

Property B B' B'' .....  
(non- or not well developed)



しかしながら現実的にはジャカルタ市内において、土地・住宅に関する有効な市場メカニズムは作用していない。ないし、きわめて部分的にしか作用していない。従って、便益測定の基礎となる価格=Rental Value は間接的な方法で推定するしかない。


ここでは住宅についてはまず居住者が家計費から期毎のローン返済にあててることを同意できる部分、つまり住宅の 購買可能価格=販売価格の期毎の償還額を基準として考える。それは現プロジェクトの対象となる所得階層が、80年時点で得ている平均家計収入(60,000 Rp/月)の25%に相当する額である。この金額の中に供給側からみでの経済的コスト要因と、需要側からみでの社会・経済的便益が体化されているものと仮定するのである。

一方土地については、80年時点での市場における地価を基準として考える。後述のケース1の内部収益率(IRR)計算は、この考え方にもとづいている。

もう一つのケースとして、住宅のもたらす便益を、市場価格を基準として考えることもできる。次の図は極めて限られたサンプル数であるが、DKI Jakartaにおける80年時点でのFloor Spaceあたり住宅価格(月あたり住居費に換算)を示している。PERUM PERUMNASが政策的に供給しているローコスト住宅より高価となっているのは当然である。平均的にみて、それをケース1の50%増し(約22,500 Rp/月)と仮定することが可能

である。

ケース2のIRR計算はこの考え方に基づいており、ケース1よりも高い値を示す。



b) チェンカレン地区住宅開発事業の経済的コストは、次のものから構成されている。いずれも調査時点である1980年価格が基準となっている。

i) Right of Development と Tax を差し引いた Land Acquisition Cost

ii) Planning Cost

iii) Price Contingency と Interest を差し引いた Infrastructure Cost

iv) Price Contingency と Interest 及び Insurance を差し引いた Housing construction cost

v) 労務費のなかから未熟練労働部分について減額を行っている。

vi) 当 Project に使用される建設材料については、後の11-2-2のb)でも述べるようにスケール・メリットが働く。特に中小規模の伝統的な生産工程における材料生産性の向上も期待される。近代的な Sector における技術革新も可能である。従って建設材料費に対して経済コストを適用することができよう。

ケース2のIRR計算においては、建設材料の経済コストを財務コストより10%程度低く見積っている。

c) Project Life は入居開始後20年間である。

d) 内部収益率 ( I R R )

ケース 1            4.85 % ( Table 11-2 )

ケース 2            11.46 % ( Table 11-3 )

Table 11-2 IRR(ケース1)

i = 4.85 %

YEAR	COST		BENEFIT	
	..	PRESENT VALUE	PRESENT VALUE	VALUE
1981	3300000.	3147356.	0.	0.
1982	363253.	330425.	0.	0.
1983	1928016.	1672655.	0.	0.
1984	12271726.	10153910.	3042225.	2517207.
1985	2727598.	2152484.	3960225.	3125211.
1986	0.	0.	1224000.	921241.
1987	0.	0.	1224000.	878628.
1988	0.	0.	1224000.	837986.
1989	0.	0.	1224000.	799224.
1990	0.	0.	1224000.	762256.
1991	0.	0.	1224000.	726997.
1992	0.	0.	1224000.	693369.
1993	0.	0.	1224000.	661297.
1994	0.	0.	1224000.	630708.
1995	0.	0.	1224000.	601534.
1996	0.	0.	1224000.	573710.
1997	0.	0.	1224000.	547173.
1998	0.	0.	1224000.	521863.
1999	0.	0.	1224000.	497724.
2000	0.	0.	1224000.	474701.
2001	0.	0.	1224000.	452743.
2002	0.	0.	1224000.	431802.
2003	0.	0.	1224000.	411828.
2004	0.	0.	1224000.	392779.
TOTAL		17456816.		17459952.

B/C = 1.0002



Table 11-3 IRR (ケース2)

I = 11.46 %

YEAR	COST		BENEFIT	
		PRESENT VALUE		PRESENT VALUE
1981	2970000.	2664634.	0.	0.
1982	326928.	263157.	0.	0.
1983	1735214.	1253131.	0.	0.
1984	11044553.	7156047.	3118725.	2020701.
1985	2454838.	1427017.	4495725.	2613401.
1986	0.	0.	1836000.	957547.
1987	0.	0.	1836000.	859096.
1988	0.	0.	1836000.	770767.
1989	0.	0.	1836000.	691519.
1990	0.	0.	1836000.	620420.
1991	0.	0.	1836000.	556630.
1992	0.	0.	1836000.	499400.
1993	0.	0.	1836000.	448053.
1994	0.	0.	1836000.	401986.
1995	0.	0.	1836000.	360655.
1996	0.	0.	1836000.	323574.
1997	0.	0.	1836000.	290305.
1998	0.	0.	1836000.	260457.
1999	0.	0.	1836000.	233678.
2000	0.	0.	1836000.	209652.
2001	0.	0.	1836000.	188096.
2002	0.	0.	1836000.	168757.
2003	0.	0.	1836000.	151406.
2004	0.	0.	1836000.	135839.
TOTAL		12763985.		12761926.

B/C = 0.9998

## 11-2-2 その他の社会・経済的便益

### a) 建設期間中及び建設期間後の雇用拡大効果

当 Project による社会・経済的便益として、雇用拡大効果をあげることができる。

Fig11-3 は建設期間中の Infrastructure 整備に雇用される延べ労働力数(人・日)を、Fig11-4 は Housing Construction に雇用される延べ労働力数(人・日)を示している。合計 1,540 千人・日の雇用(1日平均約 2,100 人の労働者の雇用)が行われることとなっている。

当 Project は建設期間後において各種の社会公共施設の提供を予定している。これがまた雇用拡大効果をもたらす。

Table11-4 は各社会公共施設の数と、そこでの職員、従業員数を推計したものである。約 650 名の永続的な雇用が確保されることとなろう。




Fig 11-3 インフラストラクチャー工事の労働者数の推計




Fig 11-4 住宅工事の労働者数の推計

Table 11-4 社会・公共施設がもたらす雇用効果

Classification of social facilities		Number of facilities	Number of Employees	
Educational				
	Kindergarten	(15)	15×5=75	80
	Elementary school	(28)	8×28=224	+ 250
	Junior high school	(2)		20
	Senior high school	(1)		15
365				
Religious				
	Mosque (Small)	(10)		10
	Mosque	(2)		10
20				
Medical				
	Hospital	(1)		30
	Health center	(1)		5
35				
Administrative/Municipal Utility				
		(5)		30
30				
Commercial				
	Sub-center	(10)		100
	Centre	(1)		100
	Shops			
	Market			
	Cinema			
	Parking			
200				
Total				650

b) 建材産業における生産性向上効果

チェンカレン地区の住宅開発事業の規模は極めて大きいため、これに建設材料を供給する産業はスケール・メリットを享受することができる。

また大量生産を行う過程で、伝統的な生産工程には多くの革新要因がもたれ、条件を整えば近代的生産工程に移行することも可能である。

この過程の中で、労働者の熟練度も一定の向上をみることになり、労働生産性の上昇を期待することができる。

Table 11-5は現Projectに使用される建設材料の生産・流通状況を調査団(Study Team)がヒアリング調査によってとりまとめ、それを一覧表にしたものである。表において、中小規模でかつ伝統的生産工程によっている建材、分散的な生産方法をとっている建材、技術革新の余地の大きな建材、流通過程が比較的整備されていない建材については今後生産性向上を期待することができる。

先に示したIRR算出のケース2における経済的コストには、この要因が含まれている。

Table 11-5 CENGKARENG 住宅開発計画に使用される建設材料の生産・流通状況

	Domestic Products or Imported?		Produced in			Production Scale			Manufacturing System		Room to Improvement (increase) of productivity in 5 years					Distributing route system is ....		
	Domestic	Imported	Modern Sector	Semi-modern Sector	Traditional Sector	Large	Medium	Small	Systematic and Contrived	Scattered	Lower possibilities	Higher possibilities	Technically	by another measures	In good order (systematic)	Not systematic	High	Low
(Housing)																		
Batu-Kali																		
Sand																		
Portland Cement																		
Brick																		
Bataco																		
Concrete Block																		
Tile																		
Roofing																		
Asbestos (coligated)																		
wood (finished)																		
ply wood																		
Particle Board																		
Steel Bar																		
Steel Pipe (for Handrail)																		
Wire																		
Glass																		
Paint																		
Lens																		
(Infrastructure)																		
Crushed Stone																		
Bamboo (for Swampy)																		
Asphalt																		
Concrete Pipe																		
PVC Pipe																		

c) 計画地区周辺への安定的な労働力供給


現Projectの周辺地域の特徴の1つとして、Jakarta-Tangerang 街道沿いに工業地帯が広がっていることがあげられる (Fig11-5、Fig11-6をみよ)。中小工場はもとより、近代的な大工場の多くがここに立地している。業種としては薬品、ゴム、プラスチック加工などの化学関連工業、ガラス製品、電子・電気関連製品 (含むカセットテープ)、食品加工、織物、包装材料、窯業系の建設資材などである。これらは、典型的な内陸型の加工工業であり、極めて労働集約型 (雇用吸収力の高い) の工業である。

従って、この工業地帯に対し、将来とも安定的な労働力を供給することが求められている。

チェンカレンの住宅開発地区には、自分の家を持ち、住居費支出を計画的に行う習慣を身につけ、ある程度の貯蓄にも励むといったタイプの居住者が住むことになる。世帯主の多くは、安定的な勤労意欲に支えられた、比較的質の高い職員層、労働者層であることが期待される。

従来からこの工業地帯に通勤する労働者の多くは、周辺の借家に住んでいた。彼らもチェンカレンの開発住宅に移り住むことによって、より洗練された生活を享受できるようになる。洗練され、かつ規律のある生活は、安定的な勤労意欲につながる。この人々の存在が工業部門の全体としての生産性向上に寄与することになるのである。






相 11-25 图 11-25 工业分布图 (CT)

Fig. 11-6.

△	PORSELIN - GLAS.
○	PORCELAIN - GLASS
◻	BARANG LOGAM - MESIN - LISTRIK
◻	METAL - MACHINE - ELECTRICITY
◻	INDUSTRI DASAR LOGAM
◻	HEAVY METAL INDUSTRY
◻	KAYU - MEUBEL.
◻	WOOD - FURNITURE
◻	INDUSTRI MAKANAN
◻	FOOD INDUSTRY
◻	TEXTIL - KULIT - PAKAIAN
◻	TEXTILE - LEATHER - DRESS
◻	PAPER - PAINTING
◻	KIMIA - KARET - PLASTIK.
◻	CHEMICAL - RUBBER - PLASTICS
◻	INDUSTRI LAINNYA
◻	OTHER INDUSTRIES

Fig 11-6 JAKARTA-TANGERANG 道路沿いの製造業分布(2)



・ 補足資料

1. The first part of the document discusses the importance of maintaining accurate records of all transactions and activities. It emphasizes that this is crucial for ensuring transparency and accountability in the organization's operations.

2.

3.

4.

5.

6. The second part of the document outlines the specific procedures and protocols that must be followed to ensure compliance with all applicable laws and regulations. It provides a detailed overview of the internal controls and monitoring systems in place to prevent and detect any potential issues.

7.

## TABLE OF CONTENTS

1	COST DATA	
1-1	LABOR COST	A- 1
1-2	MATERIAL COST	A- 1
1-3	UNIT COST	A- 2
1-4	MACHINE COST WITH OPERATOR	A- 7
1-5	UNIT COST FOR LARGE SCALE EARTH WORK	A- 8
1-6	COST DATA FOR PLUMBING	A-10
1-7	COST DATA FOR WATER SUPPLY AND SEWERAGE	A-15
1-8	COST DATA FOR LOW-RISE HOUSES	A-19
1-9	COST DATA FOR WALK-UP FLAT	A-35
2	ROUGH STRUCTURAL CALCULATION (EXAMPLES )	
2-1	FS'5-36 (Walk-up Flats Type)	A-45
2-2	FS'2-26 (2 Storied Flats Type)	A-61
2-3	M-24 (Maisonette Type)	A-70
3	SCHEDULE AND MINUTES	A-75



1-1 LABOR

Item	Unit	Cost (Rp)	Remarks
Mandor	day	1,500	
Foreman		2,400	
Unskilled Labor		1,250	
Carpenter		2,100	
Paitner, Mason, Tinsmith		1,750	
Plumber		1,700	
Operater			see machine cost
Earth wark man		750	

1-2 MATERIALS

Item	Unit	Cost (Rp)	Remarks
River Stone			
Crushed Stone	m <sup>3</sup>	6,500	
Round Stone	m <sup>3</sup>	6,500	
Koval			
Sand			
Bedding Sand	m <sup>3</sup>	4,500	
Mortar Sand	m <sup>3</sup>	4,500	
Concrete Sand	m <sup>3</sup>	5,000	
Lime	m <sup>3</sup>	7,750	
Red Brick Powder	m <sup>3</sup>	6,500	
Portland Cement	bag	1,950	40kg/bag
Brick	pc.	19	Tangerang
Brick		82.3	Cetak
Bataco	pc.	85	t=100
Concrete Block	pc.	125	t=100
Concrete Block	pc.	165	t=150
Roofing Tile	pc.	65	Kodok

Item	Unit	Cost (Rp)	Remarks
Wood			
Kamper	m <sup>3</sup>	200,000	Class II
Borneo	m <sup>3</sup>	102,000	Class II III
Meranti	m <sup>3</sup>	100,000	Class IV
Preservated Meranti	m <sup>3</sup>	168,570	
Terentang	m <sup>3</sup>	45,000	Class IV
Firewood		3,000	
Steel Bar	kg	280	
Steel Pipe	kg	350	for a handrail
Wire	kg	500	
Glass	m <sup>2</sup>	7,500	t=5
Glass	m <sup>2</sup>	4,400	t=3
Naco Window	step	400	
Bamboo	pc.	200	φ6cm/4cm
Asphalt	kg	150	60/70
Rumput	m <sup>2</sup>	75	
Plywood	m <sup>2</sup>	810	t=4
Plywood	m <sup>2</sup>	1,090	t=6
Particle Board	m <sup>2</sup>	1,746	t=12
Particle Board	m <sup>2</sup>	2,150	t=16
Corrugated Asbestos	pc.	4,330	4t×2,100×1,050
Nok Patent	pc.	1,860	L=1,050
Asbestos Sheet	m <sup>2</sup>	1,550	t=4

1-3 UNIT COST

Item	Unit	Cost (Rp)	Remarks
(1) Earth Work (Housing & Small Scale Land Development)			
Excavation	Rp/m <sup>3</sup>		Material
			Labor
			Total
		420	



Item	Unit		Cost (Rp)	Remarks
Compaction	Rp/m <sup>2</sup>	Material		
		Labor		
		Total	100	
Back Filling	Rp/m <sup>3</sup>	Material		
		Labor		
		Total	100	
Sand Filling	Rp/m <sup>3</sup>	Material	5,400	
		Labor	200	
		Total	5,600	
Rumpet	Rp/m <sup>2</sup>	Material	75	
		Labor	90	
		Total	165	
(2) Concrete Work				
Concrete 175kg/cm <sup>2</sup>	Rp/m <sup>3</sup>	Material	24,600	1:2:3
		Labor	3,000	
		Total	27,600	
Concrete 500kg/cm <sup>2</sup>	Rp/m <sup>3</sup>	Material		
		Labor		
		Total	32,500	
Concrete	Rp/m <sup>3</sup>	Material	19,350	1:3:5
		Labor	3,000	
		Total	22,350	
Concrete 225kg/cm <sup>2</sup>		Material		
		Labor		
		Total		
Steel Bar	Rp/kg	Material	400	
		Labor	120	
		Total	520	

Item	Unit		Cost (Rp)	Remarks
(3) Form Work				
Foundation	Rp/m <sup>2</sup>	Material	1,806	
		Labor	294	
		Total	2,100	
Wall	Rp/m <sup>2</sup>	Material	2,580	
		Labor	420	
		Total	3,000	
Column	Rp/m <sup>2</sup>	Material	2,838	
		Labor	462	
		Total	3,300	
Beam	Rp/m <sup>2</sup>	Material	2,580	
		Labor	420	
		Total	3,000	
Floor	Rp/m <sup>2</sup>	Material	3,612	
		Labor	588	
		Total	4,200	
Pile	Rp/m <sup>2</sup>	Material	2,580	
		Labor	420	
		Total	3,000	
(4) Masonry Work				
Batu-kari	Rp/m <sup>2</sup>	Material	18,050	
		Labor	2,200	1:4
		Total	20,250	
Batu-kali Plaster, Finish	Rp/m <sup>2</sup>	Material	410	
		Labor	450	
		Total	860	
Weep Hole	Rp/pc.	Material	36	
		Labor	9	
		Total	45	

Item	Unit		Cost (Rp)	Remarks
Bataco	Rp/m <sup>2</sup>	Material	1,570	t=100
		Labor	200	W/Vertical
		Total	1,770(2,520)	Reinforcement φ8 @400
Concrete Block	Rp/m <sup>2</sup>	Material	2,070	t=100
		Labor	200	W/Vertical
		Total	2,270(3,020)	Reinforcement φ8 @400
Concrete Block	Rp/m <sup>2</sup>	Material	2,730	t=150
		Labor	260	
		Total	2,990	
Brick Exposure (full brick)	Rp/m <sup>2</sup>	Material	4,000	
		Labor	600	Tangerang Class II
		Total	4,600	
Brick Exposure (half brick)	Rp/m <sup>2</sup>	Material	5,050	
		Labor	400	Cetak
		Total	5,450	
Brick Exposure (half blick)	Rp/m <sup>2</sup>	Material	2,000	
		Labor	400	Tangerang Class II
		Total	2,400	
(5) Plaster/Painting Work				
Floor Mortar (1:5)	Rp/m <sup>2</sup>	Material		
		Labor		t=30
		Total	840	
Exterior Mortar (1:5)	Rp/m <sup>2</sup>	Material		
		Labor		t=25
		Total	960	
Water Proof Mortar (1:3)	Rp/m <sup>2</sup>	Material	810	
		Labor	420	t=30
		Total	1,230	

Item	Unit		Cost (Rp)	Remarks
Coking	Rp/m	Material		
		Labor		
		Total	700	
Mortar (1:4)		Material		
		Labor		t=15
		Total		
Painting ↓ Concrete	Rp/m <sup>2</sup>	Material		
		Labor		
		Total	400	
Painting ↓ wood	Rp/m <sup>2</sup>	Material		
		Labor		
		Total	500	
(6) Other Works				
Concrete Pile Driving	Rp/m	Material		
		Labor		
		Total	2,800	
Wooden Work General	Rp/m <sup>3</sup>	Material	182,000	Preservated
		Labor	11,790	Meranti
		Total	193,790	
Wooden Work Roof Truss	Rp/m <sup>3</sup>	Material	184,500	Preservated
		Labor	15,140	Meranti
		Total	199,640	
Wooden Work Door & Window Frame	Rp/m <sup>3</sup>	Material	185,500	Preservated
		Labor	32,800	Meranti
		Total	218,300	
Ground Scaffolding	Rp/m <sup>2</sup>	Material		
		Labor		
		Total	600	

Item	Unit		Cost (Rp)	Remarks
Exterior	Rp/m <sup>2</sup>	Material		
Scaffolding (Bamboo)		Labor		
		Total	800	
Roof Tile	Rp/m <sup>2</sup>	Material	1,500	
Kodok		Labor	200	
		Total	1,700	
Ridge Tile	Rp/m	Material		
		Labor		
		Total	1,800	
Metal Work	Rp/kg	Material		
		Labor		
		Total	750	

#### 1-4 MACHINE COST WITH OPERATOR

Name of Machine	Type	Capacity	Cost (Rp/hr)
Bulldozer		(Operating Weight)	
	D60E.6	15.92 ton	19,530
	D65E.6	16.12 ton	20,400
	D85A.18	18.95 ton	27,780
	D155A.1	32.85 ton	31,250
Swamp Bulldozer	D65P	18.88 ton	21,700
Dozer Shovel		(Bucket Capacity)	
	D57S	1.6m <sup>3</sup>	16,930
	D75S.2	2.1m <sup>3</sup>	21,700
Motor Scraper	WS-16	Struck 11.0m <sup>3</sup> Heapen 15.8m <sup>3</sup>	47,310
Wheel loader		(Bucket Capacity)	
	W-90	2.3m <sup>3</sup>	20,830
	W-170	3.5m <sup>3</sup>	23,870
Hydraulic	LS2500BJ	Heavy duty 0.35m <sup>3</sup> Loading work 0.5m <sup>3</sup>	15,840

Name of Machine	Type	Capacity	Cost (Rp/hr)
	LS2800AJ	Heavy duty	0.7m <sup>3</sup>
		Loading work	1.0m <sup>3</sup>
Vibrating Roller	BW212B	8.6 ton	16,930
	BW212SB	9.6 ton	17,790
Road roller		10~12 ton	4,500
Motor Grader		Blade Width	
	GD37-6H	3.71m	16,930
Clawler Mounted Crane	LS78LS	25 ton	15,840
Dump Truck	TOYOTA	5 ton	4,320

1-5 UNIT COST FOR LARGE SCALE EARTH WORK (Land Development)

Item	Unit	Cost (Rp)	Remarks
Stripping	Rp/m <sup>3</sup>	25	Bulldozer D60E 750m <sup>2</sup> /hr
Clearing & Grubbing (manual)	Rp/m <sup>2</sup>	10	
Clearing & Grubbing & Grading	Rp/m <sup>2</sup>	60	Bulldozer D60E Dump Truck (500m) Shovel Loader
Cut	Rp/m <sup>3</sup>	130	Bulldozer D60E 150m <sup>3</sup> /hr
Fill (dozing)	Rp/m <sup>3</sup>	260	Bulldozer D60E (dozing 150m)
Fill (spreading)	Rp/m <sup>3</sup>	100	Bulldozer D60E 200m <sup>3</sup> /hr
Compaction	Rp/m <sup>3</sup>	120	Compactor BW212SP 150m <sup>3</sup> /hr
Site Transportation	Rp/m <sup>3</sup>	400	Shovel Loader Dump Truck (300~600m)

Item	Unit	Cost (Rp)	Remarks
Excavation (manual)	Rp/m <sup>3</sup>	420	
Excavation & Site Transportation	Rp/m <sup>3</sup>	630	Swamp Dozer Back Hoe Dump Truck (1~1.5km)

1-6 COST DATA FOR PLUMBING

(1) PVC-CLASS VP (10 kg/cm<sup>2</sup>)

Size	(1) Pipe material Rp/M	(2) Accessories Rp/M	(3) Sub-total (1) + (2) Rp/M	(4) Excavation & backfilling Rp/M	(5) Sand bedding Rp/M	(6) Installation Rp/M	(7) Sub-total (4) ~ (6) Rp/M	(8) Total (3) + (7) Rp/M
1/2"	305	90	395	d	270	145	470	865
3/4	365	110	475	"	290	145	490	965
1	530	160	690	"	295	215	570	1,260
1 1/4	635	190	825	"	325	215	600	1,425
1 1/2	930	280	1,210	"	335	215	615	1,825
2	1,315	395	1,710	"	360	275	705	2,415
2 1/2	1,695	510	2,205	0.6	410	275	785	2,990
3	2,585	775	3,360	"	440	320	865	4,225
4	4,000	1,200	5,200	"	915	470	1,550	6,750
5	5,240	1,570	6,810	0.8	1,035	470	1,730	8,540
6	7,880	2,365	10,245	"	1,185	635	2,060	12,305
8	11,920	3,575	15,495	1.0	2,085	800	3,290	18,785
10	18,160	5,450	23,610	"	2,440	965	3,865	27,475

d: Depth (M)



(2) PVC-CLASS VU (5 kg/cm<sup>2</sup>, for Sewage)

Size	① Pipe material Rp/M	② Accessories Rp/M	③ Sub-total ① + ② Rp/M	④ Excavation & backfilling Rp/M	⑤ Sand bedding Rp/M	⑥ Installation Rp/M	⑦ Sub-total ④ + ⑤ Rp/M	⑧ Total ③ + ⑦ Rp/M
2"	615	155	770	d 0.4	365	275	705	1,475
3	1,360	340	1,700	0.6	435	320	865	2,565
4	2,040	510	2,550	0.6	920	470	1,550	4,100
6	4,625	1,155	5,780	0.8	1,185	635	2,060	7,840
8	7,720	1,930	9,650	1.0	2,085	800	3,290	12,940
10	11,640	2,910	14,550	1.0	2,440	965	3,865	18,415
12	16,080	4,020	20,100	1.0	2,820	1,130	4,460	24,560

d: Depth (M)

(3) GALVANIZED IRON PIPE (GIP)

Size	① Pipe material Rp/M	② Accessories Rp/M	③ Sub-total ① + ② Rp/M	④ Excavation & backfilling Rp/M d	⑤ Sand bedding Rp/M	⑥ Installation Rp/M	⑦ Sub-total ④ ~ ⑥ Rp/M	⑧ Total ③ + ⑦ Rp/M
1/2"	690	210	900	0.4	270	580	905	1,805
3/4	890	265	1,155	"	285	580	925	2,080
1	1,380	415	1,795	"	295	860	1,215	3,010
1 1/4	1,775	535	2,310	"	325	860	1,245	3,555
1 1/2	2,050	615	2,665	"	335	860	1,260	3,925
2	2,890	865	3,755	"	365	1,100	1,530	5,285
2 1/2	3,720	1,115	4,835	0.6	410	1,100	1,610	6,445
3	4,835	1,450	6,285	"	435	1,280	1,825	8,110
4	6,945	2,085	9,030	"	920	1,880	2,960	11,990
5	9,350	2,805	12,155	0.8	1,035	1,880	3,140	15,295
6	11,090	3,327	14,417	"	1,185	2,540	3,965	18,382

d: Depth (M)

(4) ASBESTOS CEMENT PIPE (ACP) (20 kg/cm<sup>2</sup>, for Drinking Water)

Size	① Pipe material Rp/M	② Accessories Rp/M	③ Sub-total ①+② Rp/M	④ Excavation & backfilling Rp/M	⑤ Sand bedding Rp/M	⑥ Installation Rp/M	⑦ Sub-total ④+⑤ Rp/M	⑧ Total ③+⑦ Rp/M
	-	-	-	d				
4"	2,535	760	3,295	0.6	920	940	2,020	5,315
6	4,120	1,235	5,355	0.8	1,185	1,270	2,695	8,050
8	7,415	2,225	9,640	1.0	2,085	1,600	4,090	13,730
10	10,465	3,140	13,605	1.0	2,440	1,930	4,830	18,435
12	15,270	4,580	19,850	1.0	2,820	2,260	5,590	25,440
14	20,360	6,110	26,470	1.0	3,235	2,590	6,385	32,855

d: Depth (M)

(5) DUCTILE CAST IRON PIPE (DCIP)


Size	① Pipe material Rp/M	② Accessories Rp/M	③ Sub-total ① + ② Rp/M	④ Excavation & backfilling Rp/M	⑤ Sand bedding Rp/M	⑥ Installation Rp/M	⑦ Sub-total ④ + ⑤ Rp/M	⑧ Total ③ + ⑦ Rp/M
4"	11,200	3,360	14,560	d 0.6	920	1,410	2,490	17,050
6	16,275	4,885	21,160	0.8	1,185	1,905	3,330	24,490
8	19,750	5,925	25,675	1.0	2,085	2,400	4,890	30,565
10	26,250	7,875	34,125	"	2,440	2,895	5,795	39,920
12	42,420	12,725	55,145	"	2,820	3,390	6,720	61,865
14	47,450	14,235	61,685	"	3,235	3,885	7,680	69,365

d: Depth (M)

1-7 COST DATA FOR WATER SUPPLY AND SEWERAGE

(1) COST OF EXCAVATION, BACKFILLING & SAND BEDDING - WATER SUPPLY

Size	d mm	ℓ mm	Excava- tion		Back filling		Sand bedding		Total Rp/M	
			M <sup>3</sup>	Rp/M	M <sup>3</sup>	Rp/M	M <sup>3</sup>	Rp/M		
1/2"	400	100	0.114	48	0.066	7	0.048	269	324 →	325
3/4	"	"	0.118	50	0.067	7	0.051	286	343	345
1	"	"	0.122	51	0.069	7	0.053	297	355	355
1 1/4	"	"	0.130	55	0.072	7	0.058	325	387	385
1 1/2	"	"	0.134	56	0.074	7	0.060	336	399	400
2	"	"	0.142	60	0.077	8	0.065	364	432	430
2 1/2	600	"	0.208	87	0.135	14	0.073	409	510	510
3	"	"	0.218	92	0.140	14	0.078	437	543	545
4	"	150	0.346	145	0.182	18	0.164	918	1,081	1,080
5	800	"	0.464	195	0.279	28	0.185	1,036	1,259	1,260
6	"	"	0.503	211	0.291	29	0.212	1,187	1,427	1,425
8	1,000	200	0.850	357	0.478	48	0.372	2,083	2,488	2,490
10	"	"	0.964	405	0.528	53	0.436	2,442	2,900	2,900
12	"	"	1,072	450	0.568	57	0.504	2,822	3,329	3,330
14	"	"	1,186	498	0.608	61	0.578	3,237	3,796	3,795
			420Rp/M <sup>3</sup>		100Rp/M <sup>3</sup>		5,600Rp/M <sup>3</sup>			



(2) WATER METER AND HOUSE CONNECTION

• Meter 1/2"	17,500
• Meter Box	7,500
• Accessories	3,000
• PVC 3/4"×3M	2,895
• GIP 1/2"×1M	1,805
<hr/>	
	32,700Rp/unit

(3) PROTECTION FOR ROAD CROSSING PIPE

• Pipe material cost (DCIP) + Installation cost (DCIP) × 0.8

(4) ELEVATED RESERVOIR (400M<sup>3</sup>, 25M HEIGHT)

• Structure *	R.S.	62,193.97×10 <sup>3</sup> Rp
• Excavation	500.35M <sup>3</sup> × 420Rp/M <sup>3</sup>	= 210.15
• Slab-on-grade	6.27M <sup>3</sup> × 22,500Rp/M <sup>3</sup>	= 141.08
• Sand filling	15.05M <sup>3</sup> × 5,600Rp/M <sup>3</sup>	= 84.28
• Back filling	292.55M <sup>3</sup> × 100Rp/M <sup>3</sup>	= 29.26
• Pain work	1,752.61M <sup>2</sup> × 400Rp/M <sup>2</sup>	= 701.04
• Water proof mortar	297M <sup>2</sup> × 1,230Rp/M <sup>2</sup>	= 365.31
• Stairs (Concrete)	R.S.	2,652.07
• Pile driving (concrete)	572M × 2,800Rp/M <sup>2</sup>	= 1,601.60
• Pipes and Accessories	R.S.	1,746.50
• Scaffolding and others	R.S.	18,274.74
<hr/>		88,000×10 <sup>3</sup> Rp

\* Structure

	Concrete			Form work			Steel Bar		
	Volume m <sup>3</sup>	Unit price 10 <sup>3</sup> Rp/M <sup>3</sup>	Price 10 <sup>3</sup> Rp	Volume m <sup>2</sup>	Unit price 10 <sup>3</sup> Rp/M <sup>2</sup>	Price 10 <sup>3</sup> Rp	Volume tons	Unit price 10 <sup>3</sup> Rp/M <sup>3</sup>	Price 10 <sup>3</sup> Rp
Column	56.94			383.68	3.3	1,266.14	13.30		
Beam	155.75			1,059.97	3.0	3,179.91	30.89		
Slab	29.55	27.50	13,701.33	187.36	4.2	786.91	4.66	520	31,153.2
Wall	18.24			243.20	3.0	729.60	3.87		
Foundation	237.75			184.16	2.1	386.74	2.96		
Pile	35.75	32.50	1,161.88	572.00	3.0	1,716.00	4.23		
Sub-total	533.98		14,863.21	2,630.37		8,065.30	59.91		31,153.2
Total	$54,081.71 \times 1.15 = 62,193.79 \times 10^3 \text{Rp}$								

(5) SEWAGE HOUSE CONNECTION

- PVC 4" x 2M 8,620 (-1.4M Depth)
- Junction box 52,500 = 4 (1 unit/4 households, 70 x 70CM  
-1.4M Depth)

---

21,745 + 21,700Rp/unit

(6) SEWAGE COMMERCIAL BLDG. CONNECTION

- PVC 6" x 2M 15,680 (-0.8M Depth)
- Manhole 20,300 (50 x 50CM, -0.6M Depth)
- Junction box 36,300 (50 x 50CM, -1.5M Depth)

---

72,280 + 72,300Rp/unit

(7) PIPE FOUNDATION

- Bamboo 2.5M x 100Rp/M = 250
- Labor and others = 100

---

350Rp/M

(8) LAGOON (FOR 60ℓ/d.c, Combined System, 70unit/ha)

• Embankment	$7,300\text{M}^3 \times 330\text{Rp}/\text{M}^3$	$= 2,409 \times 10^3\text{Rp}$
• Excavation	$7,300\text{M}^3 \times 420\text{Rp}/\text{M}^3$	$= 3,066$
• Chlorination pit	$40\text{M}^3$ (RC)	1,032
• Equipment and installation		75,000
• Electric house		560
• Generator set	46KW	4,400

---

86,467 + 86.5Mil.Rp



1-8 COST DATA FOR LOW-RISE HOUSES

D-15 ( 2 Unit/Building)							FLOOR AREA	NET 18.00 M <sup>2</sup>
							GROSS 18.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	2	Unit	0.90	1.80	11.55	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp water	2	Unit	1.20	2.40			
	Grading	-	-	-	-			
	Setting & staking out	42.00	M	0.175	7.35			
Earth Work	Scaffolding	-	Unit	4.50, 9.00	-			
	Insectisidation	-	M	1.26	-			
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96	-	448.93	-incl. horizontal RC-brace	
		F <sub>2</sub>	M	3.33	-			
		F <sub>3</sub>	M	3.07	-			
		F <sub>4</sub>	M	2.69	103.83			
	1F. Floor	Slab on grade	38.00	M <sup>2</sup>	1.79			68.44
		Soil floor	-	M <sup>2</sup>	0.11			-
	Ridge stone	F <sub>1</sub>	-	M	0.72			-
		F <sub>2</sub>	8.70	M	0.47			4.09
	Concrete block	HB-15	-	M <sup>2</sup>	2.99			-
		HB-10	71.69	M <sup>2</sup>	2.27			162.74
		Finish plaster	-	M <sup>2</sup>	0.92			-
		WC/M floor mortar	26.01	M <sup>2</sup>	1.34			34.85
R.-Course	C <sub>1</sub>	-	M	3.81	-			
	C <sub>2</sub>	-	M	2.92	-			
	C <sub>3</sub>	-	M	2.38	-			
	C <sub>4</sub>	-	M	3.37	-			
Wall reinforcement	C <sub>1</sub>	-	M	1.77	-			
	C <sub>2</sub>	-	M	2.03	62.50			
	C <sub>3</sub>	30.79	M	2.03	62.50			
	C <sub>4</sub>	-	M	0.41	4.76			
2F Floor	A-1	11.60	M	0.41	4.76			
	A-2	5.80	M	1.16	6.73			
	A-3	5.80	M	0.86	4.99			
Wood Work	Upper wall etc.	RC floor S <sub>1</sub>	M	13.16	-			
		RC floor S <sub>2</sub>	M	11.76	-			
		Wood floor	M <sup>2</sup>	7.02	-			
		Head plate	M	0.41	9.84			
	Handrail	Upper unit wall	6.00	M <sup>2</sup>	5.76	34.56		
		Other upper wall	12.00	M	2.40	28.80		
	Staircase	Upper staircase	-	Set	-	-		
		Upper WC/M	2	Set	2.70	5.40		
	Ceiling Work	Wooden rail	-	Unit	-	-		
		Pipe rail (wooden)	-	Unit	10.76	-		
Door & window work	Ceiling	Asbestos	M <sup>2</sup>	2.38	-			
		J <sub>18</sub>	2	Pc	12.00	24.00		
		J <sub>19</sub>	2	Pc	18.83	37.66		
		J <sub>E</sub>	2	Pc	11.58	23.16		
Roof Work	Lock + Hook	Lock + Hook	2+0	Pc	2.50+0.20	5.00		
		Rafter + Batten + Tile	33.60	M <sup>2</sup>	5.82	195.55		
		Canopy	-	Set	-	-		
		Ridge tile	4	M	1.04	4.16		
		Ridge c. turn	2	Pc	4.154+1.79	8.04		
		Ridge board	4	M	1.52	6.08		
		Brace	2	Pc	4.00	8.00		
		Eaves fascia	29.20	M	0.35	10.22		
		Valley gutter	4	M	2.40	9.60		
		Down pipe	4	M	1.80	7.20		
		Water-tightening	25.6	M	1.65	42.24		
		Plumbing Work	Collar	Collar	-	Pc	-	-
Water tub	2			Unit	5.50	11.00		
Closet	2			Unit	7.00	14.00		
Cleanout, trap	4			Pr	3.00	12.00		
Waste pipe	12.00			M	3.60	43.20		
Water pipe	14.00			M	0.62	8.68		
Water head	4			Pc	1.50	6.00		
Kitchen sink	2			Unit	7.00	14.00		
Electrical Work	Connection pit	Connection pit	2	Unit	3.00	6.00		
		Fixture etc	2	Unit	42.00	84.00		
Outside Work	Power intake	Power intake	-	Unit	-	-		
		Step plate + gutter plate	12+2	Pc	0.30+0.90	5.40		
Painting	Fence	Fence	-	M	1.61	-		
		Painting	-	M <sup>2</sup>	-	-		
Other Work	Guard	Guard	2	Unit	1.20	2.40		
		Cleaning	2	Unit	0.46	0.92		
Total	ALAF, Peselamato Karja	ALAF, Peselamato Karja	2	Unit	0.60	1.20		
			2	Unit	0.60	1.20		

Total 1,128.79 Rp/Building × 1.1 ( 2 ) Unit = 620.83 ×10<sup>3</sup>Rp/unit ; 18.0 M<sup>2</sup> = 34.49 ×10<sup>3</sup>Rp/M<sup>2</sup>

D-21 ( 2 Unit/Building)						FLOOR AREA	NET 24.00 M <sup>2</sup>	GROSS 24.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost x10 <sup>3</sup> Rp	Cost x10 <sup>3</sup> Rp	Sub-total x10 <sup>3</sup> Rp	Note		
Temporary work	Warehouse	2	Unit	0.90	1.80				
	Temp. water	2	Unit	1.20	2.40				
	Grading	-	-	-	-				
	Setting & staking out	54	M	0.175	9.45				
Earth Work	Scaffolding	-	Unit	4.50, 9.00	-	13.65			
	Insectisidation		H	1.26					
Masonry & Concrete Work	Foundation	F <sub>1</sub>	H	5.96					
		F <sub>2</sub>	H	3.13					
		F <sub>3</sub>	H	3.07					
		F <sub>4</sub>	H	2.69	136.81				
	1F. Floor	Slab on grade	59.60	M <sup>2</sup>	1.79	107.40			
		Soil floor	60.00	M <sup>2</sup>	0.11				
	Ridge stone	F <sub>1</sub>		M	0.72				
		F <sub>2</sub>	14.00	M	0.47	6.58			
	Concrete block	HB-15		M <sup>3</sup>	2.99				
		HB-10	91.94	M <sup>3</sup>	2.27	209.70			
		Finish plaster		M <sup>2</sup>	0.92				
		WC/M floor mortar	26.01	M <sup>3</sup>	1.34	34.85			
	KC-Course	C <sub>1</sub>		M	3.81				
		C <sub>2</sub>		M	2.92				
		C <sub>3</sub>		M	2.38				
		C <sub>4</sub>		M	3.17				
		C <sub>5</sub>		M	3.77				
	Wall reinforcement	A-1	34.80	M	0.41	14.27			
		A-2	-	M	1.16				
		A-3	14.50	M	0.86	12.47			
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16				
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76				
	Wood Work	Wood floor		M <sup>2</sup>	7.02		621.75		
		Upper wall etc.	Head plate	30.00	M	0.41	12.30		
			Upper unit wall	10.38	M <sup>2</sup>	5.76	59.79		
Other upper wall			10.38	M <sup>2</sup>	2.40	24.91			
Upper staircase				Set					
Handrail		Upper WC/M		Set		5.40			
		Wooden rail		Unit					
Staircase		Pipe rail (Wooden)		Unit	10.76				
				Unit			102.40		
Ceiling Work		Ceiling	Asbestos						
Door & Window Work	J <sub>1</sub>	J <sub>1a</sub>	4	Pc	12.00	48.00			
		J <sub>1b</sub>	4	Pc	18.83	75.32			
		J <sub>1c</sub>	2	Pc	11.58	23.16			
	Lock + Hook		2x2	Pc			151.88		
				Pc	2.50x0.20		5.40		
Roof Work	Rafter + Batten + Tile	49.20	M <sup>2</sup>	5.42	266.34				
	Canopy		Set						
	Ridge tile	6.00	M	1.04	6.24				
	Ridge column	2	Pc	4.02	8.04				
	Ridge board	6.00	M	1.52	9.12				
	Brace	2	Pc	4.00	8.00				
	Eaves fascia	33.20	M	0.35	11.62				
	Valley gutter	4.00	M	2.40	9.60				
	Down pipe	4.00	M	1.80	7.20				
	Water-tightening	27.20	M	1.65	44.88				
	Collar		Pc			391.04			
	Plumbing Work	Water tub	2	Unit	5.50	11.00			
		Clouet	2	Unit	7.00	14.00			
Cleanout, Trap		4	Pc	3.00	12.00				
Waste pipe		12.00	M	3.60	43.20				
Water pipe		14.00	M	0.62	8.68				
Water head		4	Pc	1.50	6.00				
Kitchen sink		2	Unit	7.00	14.00				
Electrical Work	Connection pit	2	Unit	3.00	6.00	114.88			
	Fixture etc.	2	Unit	42.00	84.00				
Outside Work	Power intake		Unit			84.00			
	Step plate + gutter plate	12x2	Pc	0.30x0.90	5.40				
Painting	Fence		M	1.61		5.40			
	Painting		M <sup>2</sup>						
Other Work	Guard	2	Unit	1.20	2.40				
	Clipping	2	Unit	0.46	0.92				
	AlAR Keselamatan Kerja	2	Unit	0.60	1.20	4.52			
Total		1,409.52 Rp/Building x 1.1 + ( 2 ) Unit = 819.24 x10 <sup>3</sup> Rp/Unit						24 M <sup>2</sup> = 34.14 x10 <sup>3</sup> Rp/M <sup>2</sup>	

D-16 ( 2 Unit/Building)							FLOOR AREA	NET 36.00 M <sup>2</sup>
							GROSS 36.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	2	Unit	0.90	1.80	16.45	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp water	2	Unit	1.20	2.40			
	Grading	-	-	-	-			
	Setting & staking out	70.00	M	0.175	12.25			
Earth Work	Scaffolding	-	Unit	4.50, 9.00	-			
	Insectisidation	-	M	1.26	-			
Masonry & concrete work	Foundation	F <sub>1</sub>	M	5.96	-			
		F <sub>2</sub>	M	3.33	-			
		F <sub>3</sub>	M	3.07	-			
		F <sub>4</sub>	M	2.69	-			
		F <sub>5</sub>	M	1.79	-			
	1F Floor	Slab on grade	70.00	M <sup>2</sup>	-	188.30		
		Soil floor	77.70	M <sup>2</sup>	0.11	139.08		
	Ridge stone	F <sub>1</sub>	-	M	0.72	-		
		F <sub>2</sub>	15.60	M	0.47	7.33		
	Concrete Block	HB-15	127.20	M <sup>2</sup>	2.27	288.74		
		HB-10	-	M <sup>2</sup>	0.92	-		
		Finish plaster	20.50	M <sup>2</sup>	1.34	27.47		
	RC-Course	WC/M Floor mortar	-	M <sup>2</sup>	-	-		
		C <sub>1</sub>	-	M	3.81	-		
		C <sub>2</sub>	-	M	2.92	-		
		C <sub>3</sub>	-	M	2.38	-		
		C <sub>4</sub>	-	M	3.37	-		
	Wall reinforcement	C <sub>5</sub>	-	M	3.77	-		
		C <sub>6</sub>	97.15	M	2.03	197.21		
		A-1	52.87	M	0.41	21.68		
2F Floor	A-2	24.00	M	1.16	27.84			
	A-3	16.80	M	0.86	14.45			
	RC floor S <sub>1</sub>	-	M <sup>2</sup>	13.16	-			
Wood work	RC floor S <sub>2</sub>	-	M <sup>2</sup>	11.76	-			
	Wood floor	-	M <sup>2</sup>	7.02	-			
	Head plate	56.00	M	0.41	22.96			
	Upper wall etc	Upper unit wall	5.19	M <sup>2</sup>	5.76	29.89		
		Other upper wall	26.48	M <sup>2</sup>	2.40	63.55		
	Handrail	Upper staircase	-	Set	-	-		
		Upper WC/M	-	Set	-	-		
		Wooden rail	-	Unit	-	-		
	Staircase	Pipe rail (wooden)	-	Unit	10.76	-		
	Ceiling work	Ceiling	Asbestos	M <sup>2</sup>	2.38	-	116.40	
Door & window work	J <sub>1a</sub>	6	Pc	18.81	144.08			
	J <sub>2a</sub>	6	Pc	10.29	61.74			
	J <sub>3a</sub>	2	Pc	11.58	23.16			
	Lock + Hook	2+2	Pc	2.50+0.25	5.40	234.38		
Roof Work	Rafter + Batten + Tile	91.6	M	5.82	544.75			
	Canopy	-	Set	-	-			
	Ridge tile	12.00	M	1.04	12.48			
	Ridge column	5	Pc	1.44+1.72	22.47			
	Ridge board	12.00	M	1.52	18.24			
	Brace	5	Pc	4.00	20.00			
	Eaves fascia	42.40	M	0.35	14.84			
	Valley gutter	-	M	1.90	-			
	Down pipe	-	M	1.80	-			
	Water-tightening	30.40	M	1.65	50.16			
Plumbing Work	Collar	-	Pc	-	-	680.94		
	Water tub	2	Unit	5.50	11.00			
	Closet	2	Unit	7.00	14.00			
	Cleanout, Trap	4	Pc	3.00	12.00			
	Waste pipe	39.00	M	3.60	140.40			
	Water pipe	17.00	M	0.62	10.52			
	Water head	4	Pc	1.50	6.00			
	Kitchen sink	2	Unit	7.00	14.00			
	Connection pit	2	Unit	3.00	6.00	213.92		
	Fixture etc	2	Unit	47.00	84.00			
Electrical Work	Power intake	-	Unit	-	-	84.00		
	Step plate + gutter plate	4+2	Pc	0.30+0.90	1.00			
Outside work	Fence	-	M	1.21	-	3.00		
	Painting	-	M	-	-	-		
Other work	Guard	2	Unit	1.20	2.40			
	Cleaning	2	Unit	7.44	0.22			
	ALAR <sup>2</sup> Peselamato Farja	2	Unit	0.60	1.20	4.52		
Total		2,265.71 Rp/Building × 1.1 ( 2 ) Unit = 1,246.14 ×10 <sup>3</sup> Rp/unit		36 M <sup>2</sup> = 34.62 ×10 <sup>3</sup> Rp/M <sup>2</sup>				

D-45 ( 2 Unit/Building)							FLOOR AREA	NET 45.00 m <sup>2</sup>
							GROSS 45.00 m <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note	
Temporary work	Warehouse	2	Unit	0.90	1.80	17.76	-See land development -per wall length (M)	
	Temp. water	2	Unit	1.20	2.40			
	Grading Setting & staking out Scaffolding	77.50	M	0.175	13.56			
Earth Work	Insect/solidation		M	4.50, 9.00		17.76	-only for 2F -Other cost incl. founda- tion and floor work	
Masonry & Concrete work	Foundation	F1	M	5.96		1,009.14	-incl. horizontal RC-brace	
		F2	M	3.13				
		F3	M	3.07				
		F4	M	77.50	2.69			208.48
	1F. Floor	Slab on grade	95.10	M <sup>2</sup>	1.79			170.23
		Soil floor		M <sup>2</sup>	0.11			
	Ridge stone	F1	M	0.72				
		F2	M	0.47	7.33			
	Concrete block	HB-15	M <sup>2</sup>	2.99				
		HB-10	M <sup>2</sup>	2.27	319.25			
		Finish plaster	M <sup>2</sup>	0.92				
		WC/M floor mortar	20.50	M <sup>2</sup>	1.34			27.47
	RC-Course	C1	M	3.81				
		C2	M	2.92				
		C3	M	2.38				
		C4	M	3.17				
		C5	M	3.77				
		C6	M	2.03	212.44			
	Wall reinforcement	A-1	52.80	M	0.41			21.65
		A-2	24.00	M	0.16			27.84
A-3		16.80	M	0.86	14.45			
2F. Floor	RC floor S1	M <sup>2</sup>	13.16					
	RC floor S2	M <sup>2</sup>	11.76					
Wood Work	Wood floor	M <sup>2</sup>	7.02					
	Head plate	M	0.41	24.81				
	Upper wall etc.	Upper unit wall	8.14	M <sup>2</sup>	5.76	46.89		
		Other upper wall	32.38	M <sup>2</sup>	2.40	77.71		
		Upper staircase		Set				
	Handrail	Upper WC/M		Set				
		Wooden rail		Unit				
Staircase	Pipe rail		Unit	10.76				
	(wooden)		Unit					
Coiling Work	Ceiling	Asbestos	M	2.38		149.41	-per horizontal M <sup>2</sup>	
Door & window Work	J1	8	Pc	18.01	144.08	383.79	-per horizontal M <sup>2</sup> (incl. laves) L = 2.0M	
	J2	6	Pc	10.29	61.74			
	J3	2	Pc	11.58	23.16			
			Pc					
Roof Work	Lock + Hook	2x2	Pc	2.50+0.20	5.40			
	Rafter + Batten + Tile	111.60	M <sup>2</sup>	5.83	649.51			
	Canopy		Set					
	Ridge tile	12.00	M	1.04	12.48			
	Ridge column	5.00	M	1.14+0.29	21.35			
	Ridge board	12.00	M	1.52	18.24			
	Brace	5	Pc	4.00	20.00			
	Eaves fascia	45.60	M	0.35	15.96			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening	33.60	M	1.65	55.44			
	Collar		Pc					
Plumbing work	Water tub	2	Unit	5.50	11.00	794.98		
	Closet	1	Unit	7.00	14.00			
	Cleanout, trap	4	Pc	3.00	12.00			
	Waste pipe	42.00	M	3.60	151.20			
	Water pipe	20.00	M	0.62	12.40			
	Water head	4	Pc	1.50	6.00			
	Kitchen sink	2	Unit	7.00	14.00			
	Connection pit	2	Unit	3.00	6.00			
Electrical Work	Fixtura etc.	2	Unit	42.00	84.00	226.60		
	Power intake	2	Unit			84.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	4x2	Pc	0.30+0.90	3.00			
	Fence		M	1.61		3.00	-incl. foundation -incl. each item	
Painting	Painting		M <sup>2</sup>					
	Guard	2	Unit	1.20	2.40			
Other Work	Cleaning	2	Unit	0.46	0.92			
	ALAP Keselamatan Kerja	2	Unit	0.60	1.20	4.52		
Total		2,673.20 Rp/Building = 1.1 f ( 2 ) Unit =		1,470.26 *10 <sup>3</sup> Rp/Unit		45 M <sup>2</sup> = 32.67 *10 <sup>3</sup> Rp/M <sup>2</sup>		

		R-15		( 6 Unit/Building)		FLOOR AREA	NET 18.00 M <sup>2</sup>	
						GROSS 11.00 M <sup>2</sup>	M	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	warehouse	6	Unit	0.90	5.40			
	Temp. water Grading	6	Unit	1.20	7.20			
	Setting & staking out Scaffolding	135.00	M	0.175	23.63			
Earth Work	Insectisidation	-	Unit	4 50, 9.00		36.23		
	Foundation	F <sub>1</sub>		M	5.96			
		F <sub>2</sub>		M	3.33			
		F <sub>3</sub>		M	3.07			
F <sub>4</sub>		135.00	M	2.69	363.15			
1F. Floor	Slab on grade	115.98	M <sup>2</sup>	1.79	207.60			
	Soil floor		M <sup>2</sup>	0.11				
Ridge stone	F <sub>1</sub>		M	0.72				
	F <sub>2</sub>	25.20	M	0.47	11.84			
Concrete block	HB-15		M <sup>2</sup>	2.99				
	HB-10	176.16	M <sup>2</sup>	2.27	399.88			
	Finish plaster		M <sup>2</sup>	0.92				
	WC/M floor mortar	68.52	M <sup>2</sup>	1.34	91.82			
RC-Course	C <sub>1</sub>		M	3.81				
	C <sub>2</sub>		M	2.92				
	C <sub>3</sub>		M	2.38				
	C <sub>4</sub>		M	3.37				
wall reinforcement	C <sub>5</sub>		M	3.77				
	C <sub>6</sub>	89.36	M	2.03	181.40			
	A <sub>1-1</sub>	57.60	M	0.41	23.62			
2F Floor	A <sub>2-2</sub>	9.60	M	1.16	11.14			
	A <sub>3-1</sub>	24.00	M	0.86	20.64			
	RC floor S <sub>1</sub>		M <sup>2</sup>	11.16				
Wood Work	RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		1,311.09		
	Wood floor		M <sup>2</sup>	7.02				
	Head plate	69.00	M	0.41	28.29			
	Upper unit wall		M <sup>2</sup>	5.76				
	Other upper wall	27.72	M	2.40	66.53			
	Upper staircase		Set					
	Upper WC/M	6	Set	9.335	56.01			
	Handrail		Unit	10.76				
	Pipe rail		Unit					
	Staircase (Wooden)		Unit			150.83		
Ceiling Work	Ceiling	Asbestos	M <sup>2</sup>	2.38				
		J <sub>11</sub>	12	Pc	18.01	216.12		
Door & Window work		J <sub>2</sub>	12	Pc	10.29	123.48		
		J <sub>3</sub>	6	Pc	11.58	69.48		
				Pc				
				Pc				
Roof Work	Lock + Hook	6*6	Pc	2.50+0.20	16.20	576.11		
	Rafter + Batten + Tile	141.30	M <sup>2</sup>	5.82	822.37			
	Roof		Set					
	Ridge tile	14.40	M	1.04	14.98			
	Ridge column	6	Pc	4,441.79	28.88			
	Ridge board	14.40	M	1.52	21.89			
	Brace	6	Pc	4.00	24.00			
	Eaves fascia	125.40	M	0.35	43.89			
	Valley gutter	14.40	M	3.90	56.16			
	Down pipe	16.20	M	1.80	29.16			
	Water-tightening	109.20	M	1.65	180.18			
	Collar		Pc			1,221.51		
Plumbing Work	Water tub	6	Unit	5.50	33.00			
	Closet	6	Unit	7.00	42.00			
	Cleanout, Trap	12	Pc	3.00	36.00			
	Waste pipe	20.00	M	3.60	72.00			
	Water pipe	15.00	M	0.62	9.30			
	Water head	12	Pc	1.50	18.00			
	Kitchen sink	6	Unit	7.00	42.00			
Electrical Work	Connection pit	6	Unit	3.00	18.00	270.30		
	Fixture etc.	6	Unit	42.00	252.00			
Outside Work	Power intake		Unit			252.00		
	Step plate + gutter plate	18*12	Pc	0.30+0.90	16.20			
Painting	Fence		M	1.61		16.20		
	Painting		M <sup>2</sup>					
Other work	Guard	6	Unit	1.20	7.20			
	Cleaning	6	Unit	0.46	2.76			
	/LAF Keselamatan Kerja	6	Unit	0.60	3.60	13.56		
Total		3,847.83 Rp/Building × 1.1 ( 6 ) Unit = 705.44		×10 <sup>3</sup> Rp/Unit ; 18 M <sup>2</sup> = 39.19 ×10 <sup>3</sup> Rp/M <sup>2</sup>				

		K-22		( 6 Unit/Building)		FLOOR AREA	NET 2 00 M <sup>2</sup>	GROSS 27 00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Slb-total *10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.90	5.40			
	Temp. water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out	198.0	M	0.175	34.65		-Sec. land development -per wall length (M)	
Earth Work	Scaffolding		Unit	4 50, 9.00		47.25	-only for 2F	
	Inspection/indation		M	1.26			-Other cost incl. foundation and floor work	
Masonry & concrete work	Foundation	F <sub>1</sub>	M	5.96				
		F <sub>2</sub>	M	3.33				
		F <sub>3</sub>	M	3.07				
		F <sub>4</sub>	M	2.69	500.34			
	1F Floor	Slab on grade	148.50	M <sup>2</sup>	1.79	265.82		
		Soil floor		M <sup>2</sup>	0.21			
	Ridge stone	F <sub>5</sub>		M	0.73			
		F <sub>6</sub>	12.00	M	0.47	5.64		
	Concrete block	HB-15		M <sup>2</sup>	2.99			
		HB-10	282.00	M <sup>2</sup>	2.27	640.14		
		Finish plaster		M <sup>2</sup>	0.92			
		WC/H floor mortar	68.52	M <sup>2</sup>	1.34	91.82		
	KC-Course	C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>		M	2.38			
C <sub>4</sub>			M	3.37				
C <sub>5</sub>			M	3.77				
Wall reinforcement	A-1	160.73	M	2.01	326.28			
	A-2	108.00	M	0.41	44.28			
	A-3	19.20	M	1.16	22.27			
2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16				
	RC floor S <sub>2</sub>		M <sup>2</sup>	11.78		1,927.55		
	Wood floor		M <sup>2</sup>	1.92				
Wood Work	Upper wall etc.	Head plate	84.00	M	0.41	34.44		-incl. bolts + nuts
		Upper unit wall	41.58	M <sup>2</sup>	5.76	239.50		
		Other upper wall	62.28	M <sup>2</sup>	2.40	149.47		
		Upper staircase	6	Set	4.065	24.39		
	Handrail	Upper WC/H	6	Set	9.335	56.01		
		Wooden rail		Unit				
	Staircase	Pipe rail		Unit	10.76			
Ceiling Work	Ceiling	Asbestos		Unit		503.81		-per horizontal M <sup>2</sup>
			M <sup>2</sup>	2.38				
Door & Window Work		J <sub>11</sub>	12	Pc	18.01	216.12		
		J <sub>2</sub>	12	Pc	10.29	123.48		
		J <sub>3</sub>	6	Pc	11.58	69.48		
				Pc				
Roof Work	Lock + Hook		6+6	Pc	2.50+0.20	16.20	576.11	
		Rafter + Batton + Tile	203.40	M <sup>2</sup>	5.82	1,183.79		-per horizontal M <sup>2</sup> (incl. lavas)
	Canopy			Set				
		Ridge tile	23.40	M	1.04	24.34		
		Ridge column	9	Pc	4,44+1.79	43.11		L = 2 M
		Ridge board	23.40	M	1.52	35.57		
		Brace	9	Pc	4.00	36.00		
		Eaves fascia	143.40	M	0.35	50.19		
		Valley gutter	23.40	M	1.90	44.46		
		Down pipe	16.20	M	1.80	29.16		
		Water-tightening	118.20	M	1.65	195.03		
		Collar		Pc			1,688.67	
Plumbing Work		Water tub	6	Unit	5.50	33.00		
		Closet	6	Unit	7.00	42.00		
		Cleanout, trap	12	Pc	3.00	36.00		
		Waste pipe	20.00	M	3.60	72.00		
		Water pipe	15.00	M	0.62	9.30		
		Water head	12	Pc	1.50	18.00		
		Kitchen sink	6	Unit	7.00	42.00		
		Connection pit	6	Unit	3.00	18.00	270.30	
Electrical Work		Fixture etc.	6	Unit	42.00	252.00		-See electricity list
		Power intake		Unit				
Outside work		Step plate + gutter plate	10+12	Pc	0.30+0.90	19.80		-incl. foundation
		Fence		M	1.61		19.80	-incl. each item
Painting		Painting		M <sup>2</sup>				
		Guard	6	Unit	1.20	7.20		
Other Work		Cleaning	6	Unit	0.46	2.76		
		ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56	
Total		5,299.05 Rp/Building x 1.1 ( 6 ) Unit = 971.49		*10 <sup>3</sup> Rp/unit	25 M <sup>2</sup> = 38.86	*10 <sup>3</sup> Rp/M <sup>2</sup>		

		R-360	( 6 Unit/Building)				FLOOR AREA	NET 18.00 M	
								GROSS 38.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note		
Temporary work	Warehouse	6	Unit	0.90	5.45				
	Temp. water	6	Unit	1.20	7.20				
	Grading	-	-	-	-			-Sec. land development	
	Setting & staking out	214.0	M	0.175	37.45			-per wall length (M)	
	Scaffolding	-	Unit	4.50, 9.00		50.05		-only for 2F	
Earth work	Insectisidation		M	1.26				-Other cost incl. foundation and floor work	
	Foundation		M	5.96					
	F <sub>1</sub>		M	3.33					
	F <sub>2</sub>		M	3.07					
	F <sub>3</sub>	214.00	M	2.69	575.66				
	1F Floor	228.05	M <sup>2</sup>	1.79	408.75				
	Soil floor		M <sup>2</sup>	0.1					
	Ridge stone		M	0.72					
	F <sub>4</sub>	29.10	M	0.47	13.68				
	HB-15		M <sup>2</sup>	2.99					
	HB-10	359.04	M <sup>2</sup>	2.27	815.02				
Masonry & Concrete work	Concrete block		M <sup>2</sup>	0.92					
	Finish plaster		M <sup>2</sup>	1.34	15.02				
	WC/M floor mortar	11.21	M <sup>2</sup>						
	C <sub>1</sub>		M	3.81					
	C <sub>2</sub>		M	2.92					
	C <sub>3</sub>		M	2.38				-incl. horizontal RC-brace	
	C <sub>4</sub>		M	3.37					
	C <sub>5</sub>		M	3.77					
	C <sub>6</sub>	291.46	M	2.03	591.66				
	Wall reinforcement	A <sub>1</sub> -1	225.60	M	0.41	92.50			
	A <sub>1</sub> -2	33.60	M	1.16	38.96				
	A <sub>1</sub> -3	52.80	M	0.86	45.41				
2F. Floor	RC floor S <sub>1</sub>		M	13.16		2,596.68			
	RC floor S <sub>2</sub>		M	11.76					
Wood Work	Wood floor		M <sup>2</sup>	7.02					
	Head plate	210.0	M	0.41	86.10			-incl. bolts + nuts	
	Upper unit wall	51.9	M <sup>2</sup>	5.76	299.94				
	Other upper wall	54.14	M <sup>2</sup>	2.40	129.94				
	Upper staircase		Set						
	Upper WC/M		Set						
Handrail	wooden rail		Unit						
	Pipe rail (wooden)		Unit	10.76					
Ceiling Work	Staircase		Unit			514.98			
	Ceiling	Asbestos		M	2.38			-per horizontal M	
Door & window work	J <sub>1</sub>	12	Pc	15.39	184.68				
	J <sub>2</sub>	24	Pc	18.01	432.24				
	J <sub>3</sub>	18	Pc	10.29	185.22				
	J <sub>4</sub>	6	Pc	5.11	30.66				
	Lock + Hook	6+12	Pc	2.50+0.20	17.40	1,347.78			
	Rafter + Batter + Tile	275.76	M <sup>2</sup>	5.82	1,604.92			-per horizontal M <sup>2</sup> (incl. laves)	
Roof Work	Canopy		Set						
	Ridge tile	54.60	M	1.01	56.78				
	Ridge column	12pc L <sub>1</sub> =1	Pc	1.43+1.79	75.38			L <sub>1</sub> = 1.5M L <sub>2</sub> = 7M	
	Ridge board	107.76	M	1.52	163.80				
	Brace	22	Pc	4.00	88.00				
	Eaves fascia	106.40	M	0.35	37.24				
	Valley gutter		M	3.90					
	Down pipe		M	1.60					
	Water-tightening	174.56	M	1.65	288.02				
		Collar		Pc			2,314.14		
Plumbing Work	Water tub	6	Unit	5.50	33.00				
	Closest	6	Unit	7.00	42.00				
	Clearout, Trap	12	Pc	3.00	36.00				
	Waste pipe	63.00	M	3.60	226.80				
	Water pipe	72.00	M	0.62	44.64				
	Water head	12	Pc	1.50	18.00				
	Kitchen sink	6	Unit	7.00	42.00				
Electrical Work	Connection pit	6	Unit	3.00	18.00	460.44			
	Fixture etc	6	Unit	42.00	252.00				
Outside work	Power intake		Unit			252.00		-Sec. electricity cost	
	Step plate + gutter plate	30+12	Pc	0.30+0.90	19.80				
Painting	Fence		M	1.61		19.80		-incl. foundation	
	Painting		M <sup>2</sup>					-incl. each item	
Other Work	Guard	6	Unit	1.20	7.20				
	Cleaning	6	Unit	0.66	2.76				
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56			
Total	7,569.43 Rp/Building * 1.1 : ( 6 ) Unit = 1,387.73 *10 <sup>3</sup> Rp/Unit 38 M <sup>2</sup> = 36.52 *10 <sup>3</sup> Rp/M <sup>2</sup>								



		R-36		( 6 Unit/Building)		FLOOR AREA	NET	3.0 M	
							GROSS	4.0 M	
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note		
Temporary Work	Warehouse	6	Unit	0.90	5.40				
	Temp. water Grading	6	Unit	1.20	7.20				
	Sitting & staking out Scaffolding	207.00	M	0.175	36.23				
Earth Work	Insectisidation		M	1.26		48.83			
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96					
		F <sub>2</sub>	M	3.33					
		F <sub>3</sub>	M	3.07					
		F <sub>4</sub>	M	2.69	556.83				
	1F. Floor	Slab on grade	217.73	M <sup>2</sup>	1.79	388.84			
		Soil floor		M <sup>2</sup>	0.11				
	Ridge stone	F <sub>5</sub>		M	0.72				
		F <sub>6</sub>	17.40	M	0.47	8.18			
		HB-15		M <sup>2</sup>	2.99				
	Concrete block	HB-10	360.96	M <sup>2</sup>	2.27	819.38			
		Finish plaster WC/M floor mortar	12.48	M <sup>2</sup>	1.34	16.72			
		C <sub>1</sub>		M	3.81				
	RC-Course	C <sub>2</sub>		M	2.92				
		C <sub>3</sub>		M	2.38				
		C <sub>4</sub>		M	3.37				
		C <sub>5</sub>		M	3.77				
		C <sub>6</sub>	285.46	M	2.03	579.48			
	Wall reinforcement	A <sub>1</sub> -1	194.40	M	0.41	79.70			
		A <sub>2</sub> -2	67.20	M	1.16	77.95			
A <sub>3</sub> -3		50.40	M	0.86	43.34				
2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16					
	RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		2,570.42			
Wood Work	Wood floor		M <sup>2</sup>	7.02					
	Head plate	174.00	M	0.41	71.34				
	Upper unit wall	25.95	M <sup>2</sup>	5.76	149.47				
	Other upper wall	76.26	M <sup>2</sup>	2.40	183.02				
	Upper staircase		Set						
	Upper WC/M		Set						
	Handrail	Wooden rail		Unit					
	Pipe rail (wooden)		Unit	10.76					
	Staircase		Unit			403.83			
Ceiling Work	Ceiling	Asbestos	M <sup>2</sup>	2.38					
Door & window Work	J <sub>12</sub>	12	Pc	15.39	184.68				
	J <sub>13</sub>	18	Pc	18.01	324.18				
	J <sub>20</sub>	18	Pc	10.29	185.22				
	J <sub>21</sub>	6	Pc	5.11	30.66				
	Lock & Hook	6+6	Pc	2.50+0.20	16.20	740.94			
Roof Work	Rafter + Batten + Tile	280.80	M <sup>2</sup>	5.82	1,634.26				
	Canopy		Set						
	Ridge tile	36.0	M	1.04	37.44				
	Ridge column	19	Pc	4.14+1.79	77.79				
	Ridge board	36.00	M	1.52	54.72				
	Drace	19	Pc	4.00	76.00				
	Eaves fascia	152.80	M	0.35	53.48				
	Valley gutter		M	3.90					
	Down pipe		M	1.80					
	Water-tightening	164.80	M	1.65	271.92				
	Collar		Pc			2,205.61			
Plumbing Work	Water tub	6	Unit	5.50	33.00				
	Closet	6	Unit	7.00	42.00				
	Cleanout, trap	12	Pc	3.00	36.00				
	Waste pipe	53.00	M	3.60	190.80				
	Water pipe	54.00	M	0.67	36.18				
	Water head	12	Pc	1.50	18.00				
	Kitchen sink	6	Unit	7.00	42.00				
	Connection pit	6	Unit	1.00	6.00	413.28			
Electrical Work	Fixture etc.	6	Unit	42.00	252.00				
	Power intake		Unit			252.00			
Outside Work	Step plate + gutter plate	30x12	Pc	0.30+0.90	19.80				
Painting	Fence		M	1.61		19.80			
	Painting		M <sup>2</sup>						
Other Work	Guard	6	Unit	1.20	7.20				
	Cleaning	6	Unit	0.46	2.76				
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56			
Total		6,668.27 Rp/Building x 1.1 ( 6 ) Unit =		1,222.52 *10 <sup>3</sup> Rp/Unit x 39 M <sup>2</sup> =		31.35 *10 <sup>3</sup> Rp/M <sup>2</sup>			

R-45 ( 6 Unit/Building)							FLOOR AREA	NET 48.00 M <sup>2</sup>
							GROSS 48.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary work	Warehouse	6	Unit	0.96	5.76			
	Temp water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out	226.50	M	0.175	39.64		-See. land development	
Earth work	Scaffolding	-	Unit	4.50, 9.00		52.24	-per wall length (M) -only for 2F	
	Insectisidation		M	1.26			-Other cost incl. foundation and floor work	
Foundation	F <sub>1</sub>		M	5.96				
	F <sub>2</sub>		M	3.33				
	F <sub>3</sub>		M	3.07				
	F <sub>4</sub>	226.50	M	2.62	602.29			
	Slab on grade	269.43	M <sup>2</sup>	1.79	482.28			
	Soil floor		M <sup>2</sup>	0.11				
	Ridge stone	F <sub>5</sub>		M	0.72			
		F <sub>6</sub>	17.40	M	0.47	8.18		
	Concrete block	HB-15		M <sup>2</sup>	2.99			
		HB-10	400.56	M <sup>2</sup>	2.27	909.27		
Finish plaster			M <sup>2</sup>	0.92				
Masonry & concrete work	RC/M floor mortar	62.28	M <sup>2</sup>	1.34	83.46			
	RC-Course	C <sub>1</sub>		M	1.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>		M	2.38			
		C <sub>4</sub>		M	3.37			
		C <sub>5</sub>		M	3.77			
	C <sub>6</sub>	304.96	M	2.03	619.07		-incl. horizontal RC-brace	
	Wall reinforcement	A-1	194.40	M	0.41	79.70		
		A-2	67.20	M	1.16	77.95		
		A-3	50.40	M	0.86	43.34		
2F Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	11.16				
	RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		2,912.54		
Wood Work	Wood floor		M <sup>2</sup>	7.02				
	Head plate	193.50	M	0.41	79.34			
	Upper unit wall	40.70	M <sup>2</sup>	5.76	234.43		-incl. bolts + nuts	
	Other upper wall	102.50	M <sup>2</sup>	2.40	246.00			
	Upper staircase		Set					
	upper RC/M		Set					
	Handrail	Wooden rail		Unit				
		Pipe rail		Unit	10.76			
	Staircase (wooden)		Unit			559.77		
	Ceiling work	Ceiling	Asbestos	M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>
Door & window work	J <sub>12</sub>	12	Pc	15.39	184.68			
	J <sub>11</sub>	18	Pc	18.01	324.18			
	J <sub>20</sub>	18	Pc	10.29	185.22			
	J <sub>1</sub>	6	Pc	5.11	30.66			
Roof work	Lock + Hook	6+6	Pc	2.50+0.20	16.20	740.94		
	Rafter + Batten + Tile	334.80	M <sup>2</sup>	5.82	1,948.54		-per horizontal M <sup>2</sup> (incl. laves)	
	Candy		Set					
	Ridge tile	36.00	M	1.04	37.44			
	Ridge column	19	Pc	4.41+1.79	88.71		L = 2.0M	
	Ridge board	36.00	M	1.52	54.72			
	Brace	19	Pc	4.00	76.00			
	Eaves fascia	165.60	M	0.35	57.96			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening Collar	187.20	M	1.65	308.88			
	Plumbing Work	Water tub	6	Unit	5.50	33.00	2,572.27	
		Closet	6	Unit	7.00	42.00		
Cleanout, Trap		12	Pc	3.00	36.00			
waste pipe		45.00	M	1.60	72.00			
Water pipe		48.00	M	0.62	29.76			
water head		12	Pc	1.50	18.00			
Kitchen sink		6	Unit	7.00	42.00			
Connection pit		6	Unit	3.00	18.00	182.76		
Fixture etc		6	Unit	42.00	252.00			
Power intake			Unit			252.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	30×12	Pc	0.30+0.90	19.80			
	Fence		M	1.61		19.80	-incl. foundation	
Painting	Painting		M <sup>2</sup>				-incl. each item	
	Guard	6	Unit	1.20	7.20			
Other Work	Cleaning	6	Unit	0.46	2.76			
	ALAP Keselanato Karja	6	Unit	0.60	3.60	13.56		
Total		7,503.88 Rp/Building × 1.1 = ( 6 ) Unit = 1,375.71 ×10 <sup>3</sup> Rp/Unit ; 48 M <sup>2</sup> = 28.66 ×10 <sup>3</sup> Rp/M <sup>2</sup>						

M-24 ( 6 Unit/Building)						FLOOR AREA	NET 26.40 M <sup>2</sup>	GROSS 10.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.90	5.40	67.99	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp. water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out	162.20	M	0.175	28.39			
Earth Work	Scaffolding	6	Unit	4.50, 9.00	27.00	67.99		
	Insectinidation		M	1.26				
Masonry & concrete Work	Foundation	F <sub>1</sub>	94.80	M	5.96		2,770.39	-incl. horizontal RC-brace
		F <sub>2</sub>	3.90	M	3.33	315.68		
		F <sub>3</sub>	68.00	M	1.07	11.97		
		F <sub>4</sub>	98.78	M	2.69	182.92		
		Slab on grade		M <sup>2</sup>	1.79	176.82		
	1F. Floor	Soil floor		M <sup>2</sup>	0.11			
		Ridge stone		M	0.72			
	Concrete block	F <sub>5</sub>	25.20	M	0.47	11.84		
		HB-15	207.98	M <sup>2</sup>	2.99	621.86		
		HB-10	100.89	M <sup>2</sup>	2.27	228.82		
		Finish plaster WC/M floor	68.52	M <sup>2</sup>	0.92	91.82		
		mortar		M <sup>2</sup>	1.34	91.82		
	RC-Course	C <sub>1</sub>		M	1.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>	165.48	M	2.38	393.84		
		C <sub>4</sub>	72.00	M	3.37	242.64		
		C <sub>5</sub>	6.00	M	3.77	22.62		
	Wall reinforcement	B <sub>1</sub> -1	290.40	M	2.03	589.92		
		B <sub>2</sub> -2	46.00	M	0.88	255.55		
		B <sub>3</sub> -3	32.80	M	2.72	125.12		
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	2.71	88.89		
		RC floor S <sub>2</sub>		M <sup>2</sup>	13.16			
	Wood Work	Upper wall etc.	Wood floor	64.80	M <sup>2</sup>	11.76		
Head plate			81.60	M	7.02	454.90		
Upper unit wall			2.62	M	0.41	33.46		
Other upper wall			10.48	M	5.76	15.09		
Upper staircase				M <sup>2</sup>	2.30	25.15		
Handrail		Upper WC/M		Set		13.04		
		Wooden rail	3	Set		56.01		
Staircase		Pipe rail		Pc	4.98	14.94		
		(Wooden)		Unit	10.76			
		Asbestos		Unit	10.76			
Ceiling Work	Staircase	3	Pc	35.32	105.96			
	Ceiling		M <sup>2</sup>	2.38				
Door & Window Work	Lock + Hook	J <sub>1</sub>	6	Pc	16.63	99.78	989.52	-per horizontal M <sup>2</sup> (incl. laves)
		J <sub>11</sub>	18	Pc	11.74	211.32		
		J <sub>12</sub>	12	Pc	18.01	216.12		
		J <sub>13</sub>	18	Pc	16.10	289.80		
		J <sub>14</sub>	6	Pc	11.97	71.82		
		J <sub>15</sub>	6	Pc	11.58	69.48		
	J <sub>16</sub>	6	Pc	11.58	69.48			
Roof Work	Rafter + Batten + Tile	144.72	M <sup>2</sup>	2.50+0.20	31.20			
Plumbing Work	Canopy		Set	5.87	842.27			
	Ridge tile	24.00	M	1.04	24.96			
	Ridge column	8	Pc	2.84+1.79	22.38			
	Ridge board	20.40	M	1.52	31.01			
	Brace	8	Pc	4.00	32.00			
	Eaves fascia	157.60	M	0.35	55.16			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening	130.60	M	1.65	215.49			
	Collar	3	Pc	5.76	17.28			
	Water tub	6	Unit	5.50	33.00			
	Close	6	Unit	7.00	42.00			
Cleanout, trap	12	Pc	3.00	36.00				
Waste pipe	30.00	M	2.40	72.00				
Water pipe	15.00	M	0.62	9.30				
Water head	12	Pc	1.50	18.00				
Kitchen sink	6	Unit	7.00	42.00				
Connection pit	6	Unit	3.00	18.00				
Electrical Work	Fixture etc.	6	Unit	42.00	252.00			
	Power intake		Unit		252.00			
Outside Work	Step plate + gutter plate	18*12	Pc	0.30+0.90	16.20			
	Fence		M	1.61	16.20			
Painting	Painting		M <sup>2</sup>					
	Guard	6	Unit	1.20	7.20			
Other Work	Cleaning	6	Unit	0.46	2.76			
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60			
Total		6,139.06 Rp/Building x 1.1 + ( 6 ) Unit = 1,162.16 *10 <sup>3</sup> Rp/Unit + 30 M <sup>2</sup> = 38.74 *10 <sup>3</sup> Rp/M <sup>2</sup>						

4-36 (In case of roof tile) ( 6 Unit/Building)							FLOOR AREA	NET 38.00 M <sup>2</sup>	GROSS 38.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note		
Temporary work	Warehouse	6	Unit	0.90	5.40	65.15	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work		
	Temp water	6	Unit	1.20	7.20				
	Grading	-	-	-	-				
	Setting & staking out	146.00	M	0.175	25.55				
Earth Work	Scaffolding	6	Unit	4.50, 9.00	27.00				
	Insectisidation	-	M	1.26	-				
Foundation	F <sub>1</sub>	-	M	5.96	-				
	F <sub>2</sub>	146.00	M	3.33	486.18				
	F <sub>3</sub>	-	M	3.07	-				
	F <sub>4</sub>	-	M	2.69	-				
	1F Floor	Slab on grade	131.46	M <sup>2</sup>	1.79	235.31			
		Soil floor	-	M <sup>2</sup>	0.11	-			
	Ridge stone	F <sub>5</sub>	-	M	0.72	-			
		F <sub>6</sub>	29.40	M	0.47	13.82			
		HB-15	408.98	M <sup>2</sup>	2.99	1,222.85			
	Concrete Block	HB-10	-	M <sup>2</sup>	2.27	-			
Finish plaster		-	M <sup>2</sup>	0.92	-				
Masonry & concrete work	WC/M floor mortar	10.97	M <sup>2</sup>	1.34	14.70				
	RC-Course	C <sub>1</sub>	-	M	3.81	-			
		C <sub>2</sub>	-	M	2.92	-			
		C <sub>3</sub>	264.00	M	2.38	628.32			
		C <sub>4</sub>	67.33	M	3.17	225.79			
		C <sub>5</sub>	41.50	M	3.77	156.46			-incl. horizontal RC-brace
	wall reinforcement	B-1	231.90	M	3.88	204.07			
		B-2	73.60	M	2.72	200.19			
		B-3	51.20	M	2.71	138.75			
	2F Floor	RC floor Sl	-	M <sup>2</sup>	13.16	-			
RC floor S		-	M <sup>2</sup>	11.76	-	3,526.44			
Wood Work	Wood floor	88.20	M <sup>2</sup>	7.02	619.16				
	Head plate	102.50	M	0.41	42.03				
	Upper wall etc	Upper unit wall	7.50	M <sup>2</sup>	5.76	43.20			
		Other upper wall	31.13	M <sup>2</sup>	2.40	74.71			-incl. bolts & nuts
	Handra..	Upper staircase	-	Set	-	14.25			
		Upper WC/M	-	Set	-	-			
	3 <sup>rd</sup> aircase	wooden rail	6	Unit	5.73	34.38			
		Pipe rail (Wooden)	6	Unit	10.76	64.56			
	Ceiling work	Ceiling	6	Pc	35.32	211.92	1,019.65		-per horizontal M'
		Asbestos	-	M <sup>2</sup>	2.18	-			
Door & window work	J <sub>a</sub>	6	Pc	16.63	99.78				
	J <sub>b</sub>	6	Pc	7.32	43.92				
	J <sub>c</sub>	6	Pc	28.96	171.36				
	J <sub>d</sub>	6	Pc	27.23	163.38				
	J <sub>e</sub>	6	Pc	16.10	96.60				
	J <sub>f</sub>	6	Pc	11.58	69.48				
Roof work	Lock + Hook	6	Pc	2.50+0.20	16.20	660.72			
	Rafter + Batter + Tile	155.40	M	5.82	904.43			-per horizontal M' (incl. laves, L = 1.3M)	
	Canopy	-	Set	-	115.95				
	Ridge tile	24.00	M	1.04	24.96				
	Ridge column	10	Pc	3,441.79	36.62				
	Ridge board	18.30	M	1.52	27.36				
	Brace	12	Pc	4.00	48.00				
	Eaves fascia	112.00	M	0.35	39.20				
	Valley gutter	-	M	1.90	-				
	Down pipe	-	M	1.80	-				
	Water-tightening	91.30	M	1.65	150.15				
	Collar	3	Pc	11.70	35.10	1,381.77			
	Plumbing Work	Water tub	6	Unit	5.50	33.00			
		Closet	6	Unit	7.00	42.00			
		Cleanout, Trap	12	Pc	3.00	36.00			
waste pipe		45.00	M	3.60	162.00				
Water pipe		2.00	M	0.62	5.58				
Water head		12	Pc	1.50	18.00				
Electrical Work	Kitchen sink	6	Unit	7.00	42.00				
	Connection pit	6	Unit	3.00	18.00	156.56			
Outside Work	Fixture etc	6	Unit	42.00	252.00				
	Power intake	-	Unit	-	-	252.00		-See. electricity cost	
Painting	Step plate + gutter plate	4+2	Pc	0.30+0.90	1.00				
	Fence	-	M	1.61	-	3.00		-incl. foundation	
Other Work	Painting	-	M <sup>2</sup>	-	-			-incl. each item	
	Guard	6	Unit	1.20	7.20				
Total	Cleaning	6	Unit	0.46	2.76				
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56			

M-36 (In case of corrugated asbestos) ( 6 Unit/Building)						FLOOR AREA	NET 38.00 M <sup>2</sup>	GROSS 3d.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.96	5.40			
	Temp. water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out	146.00	M	0.175	25.55		-See. land development -per wall length (%)	
Earth Work	Scaffolding	6	Unit	4.50, 9.00	27.00	65.15	-only for 2F -Other cost incl. foundation and floor work	
	Insectisidation		M	1.26				
Masonry & Concrete Work	Foundation	F <sub>1</sub>		M	5.96			
		F <sub>2</sub>	146.00	M	3.33	486.18		
		F <sub>3</sub>		M	3.07			
		F <sub>4</sub>		M	2.69			
	1F. Floor	Slab on grade	131.46	M <sup>2</sup>	1.79	235.31		
		Soil floor		M <sup>2</sup>	0.11			
	Ridge stone	R <sub>1</sub>		M	0.72			
		R <sub>2</sub>	29.30	M	0.47	13.82		
	Concrete block	HU-15	424.70	M <sup>2</sup>	2.99	1,269.85		
		HB-10		M <sup>2</sup>	2.27			
		Finish plaster		M <sup>2</sup>	0.42			
		WC/H floor mortar	10.97	M <sup>2</sup>	1.34	14.70		
	RC-Course	C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>	264.00	M	2.38	628.32		-incl. horizontal RC-brace
		C <sub>4</sub>	67.00	M	3.37	225.79		
		C <sub>5</sub>	41.50	M	3.77	156.46		
		C <sub>6</sub>		M	2.03			
	Wall reinforcement	B-1	240.9	M	0.90	211.93		
		B-2	76.8	M	2.72	208.90		
B-3		52.8	M	2.71	143.09			
2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	11.16				
	RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		3,594.41		
Wood Work	Upper wall etc.	Wood floor	88.20	M <sup>2</sup>	7.02	619.16		
		Head plate	102.50	M	0.41	42.03		-incl. bolts + nuts
		Upper unit wall	3.50	M <sup>2</sup>	5.76	20.16		
		Other upper wall	14.57	M <sup>2</sup>	2.40	34.97		
		Upper staircase		Set				
	Handrail	Upper WC/H		Set				
		Wooden rail	6	Unit	5.73	34.38		
	Staircase	Pipe rail		Unit	10.76			
		(Wooden)	6	Unit	35.32	211.92	962.62	
	Ceiling Work	Ceiling	Asbestos		M <sup>2</sup>	2.38		-per horizontal m <sup>2</sup>
Door & Window Work	Lock + hook	J <sub>11</sub>	6	Pc	18.005	108.03		
		J <sub>4'</sub>	6	Pc	7.320	43.92		
		J <sub>7</sub>	6	Pc	28.560	171.36		
		J <sub>8</sub>	6	Pc	10.225*	181.35		
		J <sub>9</sub>	6	Pc	17.600*	105.60		
		J <sub>5</sub>	6	Pc	11.575	69.45		
Roof Work	Lock + hook	6*6	Pc	2.50*0.20	16.20	679.71		
	Rafter + Batten + Tile Ferlin	155.40	M	4.535	704.74		-per horizontal M <sup>2</sup> (incl. laves)	
	Canopy		Set	115.95	115.95			
	Nok patent	24.00	M	2.00	48.00			
	Ridge column		M					
	Roof truss	119.50	M	1.44	172.08			
	Brace	48.00	Pc	0.45	21.60			
	Eaves fascia	105.60	M	0.35	36.96			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening	24.00	M	1.65	39.60			
	Collar	3	Pc	11.70	35.10	1,174.03		
Plumbing Work	Water tub	6	Unit	5.50	33.00			
	Closet	6	Unit	7.00	42.00			
	Cleanout, Trap	12	Pc	3.00	36.00			
	Waste pipe	45.00	M	3.60	162.00			
	Water pipe	9.00	M	0.62	5.58			
	Water head	12	Pc	1.50	18.00			
	Kitchen sink	6	Unit	7.00	42.00			
	Connection pit	6	Unit	3.00	18.00	356.58		
Electrical Work	Fixture etc.	6	Unit	42.00	252.00			
	Power intake		Unit			252.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	4*2	Pc	0.30*0.90	3.00			
	Fence		M	1.61		3.00	-incl. foundation	
Painting	Painting		M <sup>2</sup>				-incl. each item	
Other Work	Guard	6	Unit	1.20	7.20			
	Cleaning	6	Unit	0.46	2.76			
	ALAP Kesulamato Karja	6	Unit	0.60	3.60	13.56		
Total		7,101.06 Rp/Building * 1.1 ( 6 ) Unit = 1,301.86 *10 <sup>3</sup> Rp/Unit + 38 M <sup>2</sup> = 34.26 *10 <sup>3</sup> Rp/M <sup>2</sup>						

		4-45A	( 6 Unit/Building)				FLOOR ARFA	NET 50.00 M <sup>2</sup>	GROSS 50.00 M
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note		
Temporary work	Warehouse	6	Unit	0.90	5.40				
	Temp water	6	Unit	1.20	7.20				
	Grading	-	-	-	-				
	Setting & staking out	174.50	M	0.175	30.54				
Earth Work	Scaffolding	6	Unit	4.50, 9.00	27.00	62.94			
	Insecticidation		M	1.26					
Masonry & concrete work	Foundation	F <sub>1</sub>		M	5.96				
		F <sub>2</sub>	153.50	M	3.33	511.16			
		F <sub>3</sub>		M	3.07				
		F <sub>4</sub>		M	2.60				
	1F Floor	Slab on grade	137.96	M <sup>2</sup>	1.79	246.95			
		Soil floor		M <sup>2</sup>	0.11				
	Ridge store	F <sub>1</sub>		M	0.72				
		F <sub>2</sub>	18.00	M	0.47	8.46			
		HB-15	508.00	M <sup>2</sup>	2.99	1,518.92			
		HB-10		M <sup>2</sup>	2.47				
	Concrete block	Finish plaster		M <sup>2</sup>	0.92				
		W/M floor mortar	±2.86	M <sup>2</sup>	1.14	84.26			
	RC-Course	C <sub>1</sub>		M	3.81				
		C <sub>2</sub>		M	2.92				
		C <sub>3</sub>	324.87	M	2.30	747.19			
C <sub>4</sub>		88.00	M	3.37	296.56				
wall reinfor cement	B-1	316.90	M	0.88	296.47				
	B-2	68.80	M	2.71	187.14				
	B-3	41.63	M	2.71	112.74				
2F Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16					
	RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		4,152.72			
Wood work	wood floor	121.28	M <sup>2</sup>	7.02	851.39				
	wood floor	125.00	M	0.41	51.25				
	Upper part wall	16.15	M	5.76	93.02				
	Other upper wall	48.88	M	2.40	117.31				
	Upper staircase		Set		18.81				
	Upper W.M		Set						
	Handrail	wooden rail	6	Unit	5.73	34.38			
	Handrail	Eye rail		Unit	13.76				
	Staircase	(Wooden)	4	Unit	35.31	141.24			
	Staircase	Asbestos		M	2.18		1,178.08		
Door & window work	D <sub>1</sub> -6×8.64	1	Pc						
	D <sub>2</sub> -6×7.32	1	Pc						
	D <sub>3</sub> -6×11.74	1	Pc						
	D <sub>4</sub> -12×15.30	1	Pc						
	D <sub>5</sub> -6×18.91	1	Pc						
Roof work	Lock + Hook	6+6	Pc	2.50+0.20	16.20	1,053.48			
	Rafter + Batten + Tile	191.40	M	5.82	1,111.95				
	Anchor	3	Set	19.59	58.77				
	Ridge + tie	24.00	M	1.04	24.96				
	Ridge column	1,10pc=1.6pc	Pc	1.1,44=1.79	59.17				
	Ridge board	24.00	M	1.52	36.48				
	Brace	16	Pc	4.00	64.00				
	Eaves fascia	130.00	M	0.35	45.50				
	Valley gutter		M	3.90					
	Down pipe		M	1.80					
	Water proofing	136.60	M	1.65	225.39				
	Collar		Pc			1,028.22			
Plumbing work	Water tap	6	Unit	5.50	33.00				
	Closet	6	Unit	7.00	42.00				
	Cleanout, Trap	12	Pc	3.00	36.00				
	Waste pipe	42.00	M	3.60	151.20				
	Water pipe	42.00	M	0.62	26.04				
	Water head	12	Pc	1.50	18.00				
	Kitchen sink	6	Unit	7.00	42.00				
Electrical work	connection pit	6	Unit	3.00	18.00	366.24			
	Fixture etc	6	Unit	42.00	252.00				
Outside work	Power intake		Unit			252.00			
	Step plate gutter plate	30×12	Pc	0.30×0.90	19.80				
Painting	Fence		M	1.61		19.80			
	Painting		M						
Other work	Guard	6	Unit	1.20	7.20				
	Cleaning	6	Unit	0.46	2.76				
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	11.56			
Total		8,927.28 Rp/Building × 1.1 ( 6 ) Unit = 1,636.67 ×10 <sup>3</sup> Rp/Unit × 50 M <sup>2</sup> = 32.73 ×10 <sup>3</sup> Rp/M <sup>2</sup>							

FS'-2-36 (5.4M) ( 12 Unit/Building)						FLOOR AREA	NET 35.70 M <sup>2</sup>	GROSS 37.80 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note	
Temporary work	Warehouse	12	Unit	0.90	10.80			
	Temp. water	12	Unit	1.20	14.40			
	Grading	-	-	-	-			
	Setting & staking out	230.80	M	0.175	40.39			
Earth Work	Scaffolding	12	Unit	4.50, 9.00	108.00	171.59		
	Insectisidation	-	M	1.26	-			
Masonry & concrete work	Foundation	F <sub>1</sub>	198.70	M	5.96	1,184.25		
		F <sub>2</sub>	28.20	M	3.33	93.91		
		F <sub>3</sub>	3.90	M	3.07	11.97		
		F <sub>4</sub>	-	M	2.62	-		
	1F. Floor	Slab on grade	226.44	M <sup>2</sup>	1.79	405.33		
		Soil floor	-	M <sup>2</sup>	0.11	-		
	Ridge stone	F <sub>1</sub>	-	M	0.72	-		
		F <sub>2</sub>	31.50	M	0.47	20.45		
		F <sub>3</sub>	596.32	M <sup>2</sup>	2.99	1,781.00		
	Concrete block	HB-15	-	M <sup>2</sup>	2.27	-		
		HB-10	-	M <sup>2</sup>	0.92	-		
		Finish plaster	121.00	M <sup>2</sup>	1.34	163.21		
		W/M floor mortar	230.90	M	3.81	878.21		
	RC-Coursar	C <sub>1</sub>	308.36	M	2.92	900.41		
		C <sub>2</sub>	-	M	2.38	-		
		C <sub>3</sub>	-	M	3.37	-		
		C <sub>4</sub>	-	M	3.77	-		
		C <sub>5</sub>	-	M	2.03	-		
		C <sub>6</sub>	-	M	1.44	-		
	Wall reinforcement	C -1	237.60	M	1.44	342.14		
		B	198.00	M	0.88	174.24		
		C -2	96.00	M	3.92	376.32		
		B	68.00	M	2.72	184.96		
		C -3	48.60	M	4.37	209.76		
	2F. Floor	B	40.00	M	2.71	108.40		
RC floor S <sub>1</sub>		23.34	M <sup>2</sup>	11.16	259.55			
RC floor S <sub>2</sub>		168.84	M <sup>2</sup>	11.76	1,985.56	9,137.17		
wood floor		-	M <sup>2</sup>	7.02	-			
Wood Work	Head plate	156.10	M	0.41	64.00			
	Upper unit wall	14.00	M <sup>2</sup>	5.76	80.64			
	Other upper wall	72.21	M <sup>2</sup>	2.40	173.30			
	Upper staircase	-	Set	-	18.93			
	Upper WC/M	-	Set	-	-			
	Handrail	-	Unit	-	-			
	Wooden rail	-	Unit	-	-			
	Pipe rail	6	Unit	8.37	50.22			
	Staircase (Wooden)	2	Unit	42.69	85.38			
	Ceiling	Asbestos	-	M <sup>2</sup>	2.38	-		
Joiner & millwork	J <sub>1</sub> 6*18 48	J <sub>1</sub> 6*14 21	Pc	-	-			
	J <sub>1</sub> 6*20 995	J <sub>1</sub> 6*17 71	Pc	-	-			
	J <sub>1</sub> 30*16.63	J <sub>1</sub> 6*27 23	Pc	-	-			
	J <sub>1</sub> 6*24 86	J <sub>1</sub> 24*18 31	Pc	-	-			
	J <sub>1</sub> 6*28 56	J <sub>1</sub> 12*5 11	Pc	-	-			
	J <sub>1</sub> 6*28 56	J <sub>1</sub> 12*4 81	Pc	-	-			
Roof work	Lock + Hook	12*18	Pc	2.50*0.26	3.15			
	Rafter + Batten + Tile	291.06	M <sup>2</sup>	5.82	1,693.97	1,996.29		
	Category	-	Set	-	136.98			
	Ridge tile	12.40	M	1.04	12.90			
	Ridge column	7.00	Pc	4*1.44*1.79	31.68			
	Ridge board	12.40	M	1.57	19.47			
	Brace	7	Pc	4.00	28.00			
	Eaves fascia	136.20	M	0.35	47.67			
	Valley gutter	-	M	1.00	-			
	Down pipe	-	M	1.00	-			
	Water-tightening	12*6	M	1.65	19.80			
	Collar	-	Pc	-	-			
	Water tub	12	Unit	5.50	66.00			
	Closet	12	Unit	7.00	84.00			
	Cleanout, Trap	10	Pc	3.00	30.00			
Plumbing work	Waste pipe	87.00	M	1.30	113.10			
	Water pipe	63.00	M	0.42	26.46			
	Water head	24	Pc	1.50	36.00			
	Kitchen sink	12	Unit	7.00	84.00			
Electrical work	Connection pit	6	Unit	3.00	18.00	730.00		
	Fixture etc	12	Unit	42.00	504.00	504.00		
	Power intake	-	Unit	-	-			
Outside work	Stop plate + gutter plate	60*24	Pc	0.30*0.90	19.80			
	Fence	56.00	M	1.61	90.16			
Painting	Painting	-	M <sup>2</sup>	-	-			
	Guard	12	Unit	1.20	14.40			
Other work	Clamping	12	Unit	0.46	5.52			
	ALAT Keselamatan Kerja	12	Unit	0.60	7.20	27.12		
Total						15,430.59 Rp/Building * 1.1 ( 12 ) Unit = 1,414.47 *10 <sup>3</sup> Rp/Unit = 17.8 M <sup>2</sup> = 37.42 *10 <sup>3</sup> Rp/M <sup>2</sup>		

33.6 47.10

FS'-2-2b		(12 Unit/Building)		FLOOR AREA	NFT	25 90	M'	
					GROSS	28.00	M'	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary work	Warehouse	12	Unit	0.90	10.80			
	Temp. water	12	Unit	1.20	14.40			
	Grading	-	-	-	-			
Earth work	Setting & staking out scaffolding	161.50	M	0.175	28.26	161.46	-See. land development -per wall length (M) -only for 1/2 -Other cost incl. foundation and floor work	
	Insectisidation	-	M	1.26	-			
Foundation	F <sub>1</sub>	152.50	M	5.96	908.90			
	F <sub>2</sub>	9.00	M	3.11	28.97			
	F <sub>3</sub>	3.90	M	3.07	11.97			
	F <sub>4</sub>	-	M	2.69	-			
	IF Floor	204.91	M <sup>2</sup>	1.79	366.77			
	Soil floor	-	M <sup>2</sup>	0.11	-			
	Ridge stone	F <sub>5</sub>	-	M	0.72	-		
	concrete block	FA	38.61	M <sup>2</sup>	0.47	17.20		
		HB-15	407.02	M <sup>2</sup>	2.99	1,216.99		
	Masonry & concrete work	HB-10	14.04	M <sup>2</sup>	2.27	31.87		
Finish plaster		-	M <sup>2</sup>	0.92	-			
W/H floor mortar		123.12	M <sup>2</sup>	1.34	164.98			
RC-Course		C <sub>1</sub>	156.1	M	3.81	594.74		
		C <sub>2</sub>	203.41	M	2.92	593.96		-incl. horizontal RC-brace
		C <sub>3</sub>	-	M	2.38	-		
		C <sub>4</sub>	-	M	3.37	-		
		C <sub>5</sub>	-	M	3.77	-		
Wall		C <sub>6</sub>	-	M	2.03	-		
		-1	115.20	M	1.44	165.89		
	-2	26.00	M	0.68	84.48			
	-3	24.00	M	3.92	94.08			
	-4	20.26	M	2.72	55.42			
2 <sup>nd</sup> Floor	-5	48.00	M	4.37	209.76			
	RC floor S <sub>1</sub>	42.20	M <sup>2</sup>	2.71	108.40			
	2 <sup>nd</sup> Floor S <sub>2</sub>	24.97	M <sup>2</sup>	13.16	329.41			
	Wood floor	114.5	M <sup>2</sup>	11.70	1,347.34	6,196.11		
	Head plate	7.02	M <sup>2</sup>	7.02	-			
Wall work	Upper unit wall	14.1	M	0.41	57.85		-incl. bolts + nuts	
	Upper wall	14.0	M	5.76	80.64			
	Upper stair case	46.50	M	2.47	159.60			
	Upper wall	-	Set	-	18.93			
	Upper wall	-	Set	-	-			
Handrail	Wooden rail	-	Unit	-	-			
	Pipe rail	-	Unit	10.76	-			
Scaffolding work	wooden	-	Unit	31.69	172.07	412.09		
	Teak	-	M	2.78	-		-per horizontal m'	
Landing work	3.46*11.54	39.41	Pc	-	941.22			
	3.46*18.46	63.81	Pc	-	-			
	3.46*21.03	72.73	Pc	-	-			
	3.46*21.17	73.17	Pc	-	-			
	3.46*26.63	91.88	Pc	-	-			
Roof work	3.46*24.86	85.92	Pc	-	-			
	Work + Hook	12*18	M <sup>2</sup>	2.50+0.20	31.60	974.82	-per horizontal m' (incl. level)	
	Rafter + Batten + Tile	225.72	M <sup>2</sup>	5.82	1,311.69			
	Roofing	-	Set	-	90.90			
	Pipe	48	M	1.04	24.96			
	Ridge column	7	Pg	1,441.79	31.68		L = 1.94	
	Ridge board	14	M	1.52	21.28			
	Brace	-	Pc	4.00	28.00			
	Eaves fascia	-	M	0.35	14.65			
	Valley gutter	-	M	1.90	-			
	Down Pipe	-	M	1.80	-			
	Water proofing	115.80	M	1.65	191.07	1,751.41		
	Water proofing	12	Unit	5.50	66.00			
	Water proofing	12	Unit	7.00	84.00			
	Water proofing	24	Pc	3.00	72.00			
Plumbing work	Water pipe	87.00	M	3.60	313.20			
	Water pipe	63.00	M	0.62	39.06			
	Water pipe	24	Pc	1.50	36.00			
	Water pipe	14	Unit	7.00	84.00			
	Water pipe	6	Unit	3.00	18.00	712.26		
Electrical work	Power intake	12	Unit	42.00	504.00			
	Fixture etc	-	Unit	-	-			
Outside work	Step plate + gutter plate	6*24	Pc	0.30+0.90	39.60	504.00	-See. electricity	
	Fence	56.00	M	1.61	90.16	129.76	-incl. foundation	
Painting	Painting	-	M <sup>2</sup>	-	-		-incl. each liter	
	Guard	-	M <sup>2</sup>	-	-			
Other work	Cleaning	12	Unit	1.20	14.40			
	ALAP Keselamatan Parja	12	Unit	0.46	5.52			
Total	ALAP Keselamatan Parja	12	Unit	0.60	7.20	27.12		
	11,399.95 Rp/Building * 11 - (12) Unit = 1,017.41 ×10 <sup>3</sup> Rp/Unit * 28 M <sup>2</sup> = 30.34 ×10 <sup>3</sup> Rp/M <sup>2</sup>							



I-9 COST DATA FOR WALK-UP FLAT

FS'5-24		FLOOR AREA		NET		26.18 M <sup>2</sup>	
				GROSS		30.80 M <sup>2</sup>	
Items		Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.				3.75		
	Setting & staking out	0.26	2.11	M	0.55	27.76	
	Scaffolding	0.80	29.33	M <sup>2</sup>	23.46		
Earth Work & 1FL. Floor Work	Excavation	0.42	5.87	M <sup>3</sup>	2.47		
	Backfilling	0.10	4.68	M <sup>3</sup>	0.47		
	Sand bedding	5.60	0.28	M <sup>3</sup>	1.57	24.79	
	Batukali bedding	9.40	0.54	M <sup>3</sup>	5.08		
	1FL. concrete slab	22.35	$\frac{0.54+0.14}{=0.68}$	M <sup>3</sup>	15.20		
Structural Work						1,348.03	
Outer Wall Work	Doors & windows				119.59		
	Brick exposure	5.45	3.30	M <sup>2</sup>	17.99	137.58	
Inside Door & Partition						71.71	
Concrete Block and other Mortar Work	Concrete block t=100	2.27	21.36	M <sup>2</sup>	48.49		
	Light-weight concrete t=120	2.68	3.78	M <sup>2</sup>	10.13		
	Floor mortar t=30	0.84	28.70	M <sup>2</sup>	24.11	101.40	
	Water proof mortar t=30	1.23	15.18	M <sup>2</sup>	18.67		
Roof Work						106.55	
Miscellaneous Work	Outside painting	1.00	14.18	M <sup>2</sup>	14.18		
	Veranda screen						
	Handrail	10.76	2.00	M	21.52	43.68	
	Gutter	1.90	4.20	M	7.98		
Equipment Work	Plumbing				41.16		
	Electricity				42.00	83.16	
Cleaning & Safety Work					2.26	2.26	
Total	$1,946.92 \times 1.1 = 2,141.61$			NET. 81.80		×10 <sup>3</sup> Rp/Unit	
				GROSS 69.53		×10 <sup>3</sup> Rp/Unit	

FS'5-36		FLOOR AREA	NET		GROSS	
			38.78	M <sup>2</sup>	43.40	M <sup>2</sup>
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.			3.75		
	Setting & staking out	0.26	2.83	M	0.74	35.96
	Scaffolding	0.80	39.34	M <sup>2</sup>	31.47	
Earth Work & 1FL. Floor Work	Excavation	0.42	8.27	M <sup>3</sup>	3.47	30.63
	Backfilling	0.10	6.59	M <sup>3</sup>	0.66	
	Sand bedding	5.60	0.40	M <sup>3</sup>	2.24	
	Batukali bedding	9.40	0.75	M <sup>3</sup>	7.05	
	1FL. concrete slab	22.35	$\frac{0.20+0.75}{=0.77}$	M <sup>3</sup>	17.21	
Structural Work						1,858.48
Outer Wall Work	Doors & windows				200.51	218.50
	Brick exposure	5.45	3.30	M <sup>2</sup>	17.99	
Inside Door & Partition						139.67
Concrete Block and other Mortar Work	Concrete block t=100	2.27	22.80	M <sup>2</sup>	51.76	115.25
	Light-weight concrete t=120	2.68	3.78	M <sup>2</sup>	10.13	
	Floor mortar t=30	0.84	41.30	M <sup>2</sup>	34.69	
	Water proof mortar t=30	1.23	15.18	M <sup>2</sup>	18.67	
Roof Work						140.04
Miscellaneous Work	Outside painting	1.00	20.24	M <sup>2</sup>	20.24	63.40
	Veranda screen	22.79	0.50		11.90	
	Handrail	10.76	2.00	M	21.52	
	Gutter	1.90	5.60	M	10.64	
Equipment Work	Plumbing				41.16	83.16
	Electricity				42.00	
Cleaning & Safety Work					2.26	2.26
Total	$2,687.35 \times 1.1 = 2,956.09 \times 10^3 \text{Rp/unit}$			NET.	76.23	×10 <sup>3</sup> Rp/M <sup>2</sup>
				GROSS	68.11	×10 <sup>3</sup> Rp/M <sup>2</sup>

FS'5-45			FLOOR AREA	NET	46.84	M <sup>2</sup>	
				GROSS	51.46	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	36.69		
	Setting & staking out	0.26	2.90	M		0.75	
	Scaffolding	0.80	40.24	M <sup>2</sup>		32.19	
Earth Work & IFL. Floor Work	Excavation	0.42	9.81	M <sup>3</sup>	4.12	41.47	
	Backfilling	0.10	7.81	M <sup>3</sup>	0.78		
	Sand bedding	5.60	0.47	M <sup>3</sup>	2.63		
	Batukali bedding	9.40	0.90	M <sup>3</sup>	8.46		
	IFL. concrete slab	22.35	0.90+0.24 =1.14	M <sup>3</sup>	25.48		
Structural Work					2,176.90		
Outer Wall Work	Doors & windows			200.51	209.98		
	Brick exposure	5.45	4.02	M <sup>2</sup>		9.47	
Inside Door & Partition					151.83		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	27.35	M <sup>2</sup>	62.08	132.34	
	Light-weight concrete t=120	2.68	3.78	M <sup>2</sup>	10.13		
	Floor mortar t=30	0.84	49.36	M <sup>2</sup>	41.46		
	Water proof mortar t=30	1.23	15.18	M <sup>2</sup>	18.67		
Roof Work					167.50		
Miscellaneous Work	Outside painting	1.00	20.44	M <sup>2</sup>	20.44	63.40	
	Veranda screen	22.79	0.50		11.9		
	Handrail	10.76	2.00	M	21.52		
	Gutter	1.90	5.60	M	10.64		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.00			
Cleaning & Safety Work				2.26	2.26		
Total	3,065.53 × 1.1 = 3,372.08 ×10 <sup>3</sup> Rp/unit			NET.	71.99	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	65.53	×10 <sup>3</sup> Rp/M <sup>2</sup>	

FG5-36			FLOOR AREA	NET	38.88	M <sup>2</sup>	
				GROSS	49.74	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	38.52		
	Setting & staking out	0.26	2.64	M		0.69	
	Scaffolding	0.80	42.60	M <sup>2</sup>		34.08	
Earth Work & 1FL. Floor Work	Excavation	0.42	11.66	M <sup>3</sup>	4.90	41.37	
	Backfilling	0.10	9.32	M <sup>3</sup>	0.93		
	Sand bedding	5.60	0.52	M <sup>3</sup>	2.91		
	Batukali bedding	9.40	0.88	M <sup>3</sup>	8.27		
	1FL. concrete slab	22.35	0.88+0.21 =1.09	M <sup>3</sup>	24.36		
Structural Work					1,957.07		
Outer Wall Work	Doors & windows			152.52	172.52		
	Brick exposure	5.45	3.67	M <sup>2</sup>		20.00	
Inside Door & Partition					118.36		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	33.19	M <sup>2</sup>	75.34	143.92	
	Light-weight concrete t=120	2.68	2.16	M <sup>2</sup>	5.79		
	Floor mortar t=30	0.84	35.52	M <sup>2</sup>	29.84		
	Water proof mortor t=30	1.23	26.79	M <sup>2</sup>	32.95		
Roof Work					133.44		
Miscellaneous Work	Outside painting	1.00	25.16	M <sup>2</sup>	25.16	142.72	
	Veranda screen	18.23	0.50		9.12		
	Handrail	10.76	8.81	M	94.80		
	Gutter	1.90	5.60	M	10.64		
	Corridor roof drain				3.00		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.00			
Cleaning & Safety Work				2.26	2.26		
Total	2,833.34 × 1.1 = 3,116.67 ×10 <sup>3</sup> Rp/unit			NET.	80.16	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	62.66	×10 <sup>3</sup> RP/M <sup>2</sup>	

FG5-45		FLOOR AREA		NET	48.06	M <sup>2</sup>	
				GROSS	58.92	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	39.81		
	Setting & staking out	0.26	2.75	M		0.72	
	Scaffolding	0.80	44.18	M <sup>2</sup>		35.34	
Earth Work & IFL. Floor Work	Excavation	0.42	13.92	M <sup>3</sup>	5.85	49.36	
	Backfilling	0.10	11.14	M <sup>3</sup>	1.11		
	Sand bedding	5.60	0.62	M <sup>3</sup>	3.47		
	Batukali bedding	9.40	1.05	M <sup>3</sup>	9.87		
	IFL. concrete slab	22.35	$\frac{1.05+0.25}{=1.30}$	M <sup>3</sup>	29.06		
Structural Work					2,317.15		
Outer Wall Work	Doors & windows			191.51	218.27		
	Brick exposure	5.45	4.91	M <sup>2</sup>		26.76	
Inside Door & Partition					155.87		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	34.68	M <sup>2</sup>	78.72	155.67	
	Light-weight concrete t=120	2.68	2.16	M <sup>2</sup>	5.79		
	Floor mortar t=30	0.84	43.0	M <sup>2</sup>	36.12		
	Water proof mortar t=30	1.23	28.49	M <sup>2</sup>	35.04		
Roof Work					153.08		
Miscellaneous Work	Outside painting	1.00	26.44	M <sup>2</sup>	26.44	160.14	
	Veranda screen	18.23	0.50		9.12		
	Handrail	10.76	10.31	M	110.94		
	Gutter	1.90	5.60	M	10.64		
	Corridor roof drain				3.00		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.00			
Cleaning & Safety Work				2.26	2.26		
Total	$3,334.77 \times 1.1 = 3,668.25$ ×10 <sup>3</sup> Rp/unit			NET.	76.33	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	62.26	×10 <sup>3</sup> Rp/M <sup>2</sup>	

FM6-36		FLOOR AREA		NET	38.70	M <sup>2</sup>	
				GROSS	46.36	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	40.18		
	Setting & staking out	0.26	2.68	M		0.70	
	Scaffolding	0.80	44.67	M <sup>2</sup>		35.74	
Earth Work & IFL. Floor Work	Excavation	0.42	8.41	M <sup>3</sup>	3.53	31.27	
	Backfilling	0.10	6.72	M <sup>3</sup>	0.67		
	Sand bedding	5.60	0.38	M <sup>3</sup>	2.13		
	Batakali bedding	9.40	0.68	M <sup>3</sup>	6.39		
	IFL. concrete slab	22.35	$\frac{0.68 \times 0.15}{=0.83}$	M <sup>3</sup>	58.55		
Structural Work					1,843.85		
Outer Wall Work	Doors & windows			241.55	323.95		
	Brick exposure	5.45	15.12	M <sup>2</sup>		82.40	
Inside Door & Partition					77.54		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	23.05	M <sup>2</sup>	52.32	101.12	
	Light-weight concrete t=120	2.68	3.60	M <sup>2</sup>	9.65		
	Floor mortar t=30	0.84	13.65	M <sup>2</sup>	11.47		
	Water proof mortar t=30	1.23	22.50	M <sup>2</sup>	27.68		
Roof Work					131.35		
Miscellaneous Work	Outside painting	1.00	11.70	M <sup>2</sup>	11.70	318.60	
	Veranda screen	13.67	1.0		13.67		
	Handrail	10.76	7.24	M	77.90		
	Gutter	1.90	5.60	M	10.64		
	Wood floor + staircase				194.69		
	Roofdrain				10.00		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.0			
Cleaning & Safety Work				2.26	2.26		
Total	$2,953.28 \times 1.1 = 3,248.61 \times 10^3 \text{Rp/unit}$			NET.	83.94	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	70.07	×10 <sup>3</sup> RP/M <sup>2</sup>	

FM6-45		FLOOR AREA		NET	46.80	M <sup>2</sup>	
				GROSS	54.46	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	40.77		
	Setting & staking out	0.26	2.75	M		0.72	
	Scaffolding	0.80	45.38	M <sup>2</sup>		36.30	
Earth Work & 1FL. Floor Work	Excavation	0.42	9.95	M <sup>3</sup>	4.18	37.24	
	Backfilling	0.10	7.95	M <sup>3</sup>	0.80		
	Sand bedding	5.60	0.45	M <sup>3</sup>	2.52		
	Batukali bedding	9.40	0.81	M <sup>3</sup>	7.61		
	1FL. concrete slab	22.35	0.81+0.18 =0.99	M <sup>3</sup>	22.13		
Structural Work					2,132.81		
Outer Wall Work	Doors & windows			266.42	336.94		
	Brick exposure	5.45	12.94	M <sup>2</sup>		70.52	
Inside Door & Partition					97.68		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	28.08	M <sup>2</sup>	63.74	117.04	
	Light-weight concrete t=120	2.68	3.96	M <sup>2</sup>	10.61		
	Floor mortar t=30	0.84	17.34	M <sup>2</sup>	14.57		
	Water proof mortar t=30	1.23	22.86	M <sup>2</sup>	28.12		
Roof Work					157.03		
Miscellaneous Work	Outside painting	1.00	11.97	M <sup>2</sup>	11.97	346.23	
	Veranda screen	18.23	1.00		18.23		
	Handrail	10.76	9.39	M	90.28		
	Gutter	1.90	5.60	M	10.64		
	Wood floor + staircase				205.11		
	Roofdrain				10.0		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.00			
Cleaning & Safety Work				2.26	2.26		
Total	3,351.16 × 1.1 = 3,686.28 ×10 <sup>3</sup> Rp/unit			NET.	78.77	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	67.69	×10 <sup>3</sup> Rp/M <sup>2</sup>	



FT5-36		FLOOR AREA		NET	36.90	M <sup>2</sup>
				GROSS	40.93	M <sup>2</sup>
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.			3.75		
	Setting & staking out	0.26	4.20	M	1.09	51.54
	Scaffolding	0.80	58.38	M <sup>2</sup>	46.70	
Earth Work & 1FL. Floor Work	Excavation	0.42	7.80	M <sup>3</sup>	3.28	36.67
	Backfilling	0.10	6.21	M <sup>3</sup>	0.62	
	Sand bedding	5.60	0.38	M <sup>3</sup>	5.98	
	Batukali bedding	9.40	0.71	M <sup>3</sup>	6.67	
	1FL. concrete slab	22.35	$\frac{0.71+0.19}{=0.90}$	M <sup>3</sup>	20.12	
Structural Work					1,874.10	
Outer Wall Work	Doors & windows			126.79		238.68
	Brick exposure	5.45	20.53	M <sup>2</sup>	111.89	
Inside Door & Partition					76.79	
Concrete Block and other Mortar Work	Concrete block t=100	2.27	26.90	M <sup>2</sup>	61.06	120.10
	Light-weight concrete t=120	2.68	2.63	M <sup>2</sup>	7.05	
	Floor mortar t=30	0.84	37.21	M <sup>2</sup>	31.26	
	Water proof mortar t=30	1.23	16.85	M <sup>2</sup>	20.73	
Roof Work					286.84	
Miscellaneous Work	Outside painting	1.00	27.34	M <sup>2</sup>	27.34	85.33
	Veranda screen	22.79	0.50		11.90	
	Handrail	10.76	2.80	M	30.13	
	Gutter	1.90	8.40	M	15.96	
Equipment Work	Plumbing			41.16		83.16
	Electricity			42.00		
Cleaning & Safety Work				2.26	2.26	
Total	$2,855.47 \times 1.1 = 3,141.02 \times 10^3 \text{Rp/unit}$			NET.	85.12	×10 <sup>3</sup> Rp/M <sup>2</sup>
				GROSS	76.74	×10 <sup>3</sup> Rp/M <sup>2</sup>



## 2 ROUGH STRUCTURAL CALCULATION (EXAMPLES)



# FS'5-36 WALK-UP FLATS

We will apply the Indonesian Standards 'NI-2' in principle, but when the relevant standards do not exist, we will refer to the Japanese Building Standards, etc.

## 1. STRUCTURAL PLANNING

### 1-1 PLANNING POLICY

#### Super structure

This building is a five storied reinforced concrete above the ground, consisting of 6 units per floor; and pure Rahmen structure with spans of 2.5 m width and 3.5 m depth. It is desirable to avoid irregular surfaces in rooms for better use of space. Also the types of columns used -, L and T are suited to room arrangement, and - shaped columns only supply bending resistance in one direction. Thus, caution shall be taken as to the direction of columns. In addition, column thickness on each floor makes minimum size enough to be able to place concrete to a height of 2.8 m. And the changing length of columns on each floor shall correspond to the stresses. Each floor will be of concrete but will likely be made thin to lighten the structure. The roof will consist of roof tiles and wooden truss beams, and horizontal bracing will be provided to maintain horizontal rigidity and to prevent spiral grain twist.

#### Sub-structure

Underground beams are being considered as a measure against bending stress due to unexpected settlement and the ratio of rigidity with the columns of upper structure, and for maintaining the stability of the whole building, supposing it is larger than upper beams. Also, the first floor slab is a slab on grade. The foundation should be of isolated footings and should maintain sufficient rigidity and bending bearing capacity in order to transmit the upper load to the piles. The piles to be used will be of reinforced concrete cast in place by the formwork method. Piles will be driven by Drop-hammer, or Diesel-hammer, etc. because the bearing layer is located from 10 m to 15 m below the ground, and concrete of high strength ( $F_c=400 \text{ kg/cm}^2$ ) is used to protect the pile head from damage. The amount of additional tensile reinforcement is more than 0.8 %, increasing the bending bearing capacity of piles.

## 2. ALLOWABLE UNIT STRESS OF MATERIALS

Concrete (Refer to 'NI-2')

	Unit; $\text{kg/cm}^2$					
	Permanent stress			Temporary stress		
	Compression	Tension	Shearing	Compression	Tension	Shearing
$\delta'bk$	$0.33\delta'bk$	$0.36\sqrt{\delta'bk}$	$0.43\delta'bk$	$0.56\delta'bk$	$0.51\sqrt{\delta'bk}$	$0.68\delta'bk$
175	60	5	5.5	100	6.5	9

Reinforcing Bar (Refer to 'NI-2')

Kind	Unit; $\text{kg/cm}^2$	
	Permanent stress	Temporary stress
u-24	1,400	2,000

Cast-in-situ Pile

Unit: ton/pile

Section (cm)	Permanent stress		Temporary stress	
	Boring No.1	Boring No.2	Boring No.1	Boring No.2
25 x 25	19.2	27.0	Double of permanent stress, respectively	
30 x 30	27.2	40.5		

Note. Basic data for the design of pile driving footings; The bearing capacity of piles should be 1/3 of ultimate bearing capacity (Ru) obtained from the bearing capacity formula.

$$R_u = 30\bar{N} \cdot A_p + 1/5 \cdot \bar{N}_s \cdot \psi \cdot L_s = \bar{q}_u/2 \cdot \psi \cdot L_c \quad \dots (1)$$

- $\bar{N}$  : Tip Resistance      b,  $A_p$ : Total Area of Tip of Pile ( $m^2$ )
- c,  $\bar{N}_s$ : Average measured N value for the loose portion of earth around the piles
- $L_s$  : Length of Pile in the loose portion
- $\bar{q}_u$  : Averaged Axial Compression Strength for clay portion around the piles
- $L_c$  : Length of Pile in the clay portion
- $\psi$  : Length of periphery of pile (m)

Here,  $\bar{N} \leq 60$ ,  $\bar{N}_s/5 \leq 10 \text{ t/m}^2$ ,  $\bar{q}_u/2 \leq 10 \text{ t/m}^2$ .

3. LOAD

1) Dead load

roof (tile) (average 20 mm)	40 $kg/m^2$
Truss for gable roof	20 "
2 ~ 4 <sup>F</sup> slab (100 mm)	240 "
1 <sup>F</sup> slab slab on grade	-


ii) Table for load

Contents			For floor	For frame	For earthquake
roof	tile (20 mm)	40	D.L	60	60
	truss	20	B	-	70
		60	L.L	-	-
			60	130	130
each floor	monolithic finish 5 mm slab	12	D.L	252	252
		240	B	-	70
		252	L.L	200	140
			452	462	382
w.c mand,	cinder concrete (150 mm) slab	225	D.L	465	465
		240	B	-	70
		465	L.L	200	140
			665	675	595
stairway	slab (22 mm)	528	D.L	528	528
			B	-	-
			L.L	200	150
			728	668	588


iii) walls

Bamboo mat (double)	10 $kg/m^2$
Concrete block (190 mm)	200 "


PLAN




SECTION



FLAME





iv) Columns



$A_1 = 60 \text{ c}$   
 $A_2 = 100 \text{ c}$

480 kg/m  
 672 "




288 "

v) Girders

general girder

288 "



ground-girdes

840 "

4. C, Mo, Q

	Diagram	Floor	Contents
Line x <sub>2</sub>	<p>385 (ly)</p>	2 ~ 5	$lx = 2.5$ $ly = 3.85$ $w = 0.462 \text{ t/m}^2$ $c = (1.3) \times 0.462 \times 2 = 1.2 \text{ tm}$ $Mo = (2.1) \times 0.462 \times 2 = 1.94 \text{ tm}$ $Q = (1.65) \times 0.462 \times 2 = 1.53 \text{ t}$
	<p>0.2 t/m 385</p>	R	$c = \frac{1}{12} \times 0.2 \times 3.85^2 = 0.25 \text{ tm}$ $Mo = 1.5 \times c = 0.37 \text{ tm}$ $Q = 0.39 \text{ t}$
	<p>250</p>	2 ~ 5	$lx = 2.5$ $w = 0.462 \text{ t/m}^2$ $c = (0.4) \times 0.462 = 0.19 \text{ tm}$ $Mo = (0.65) \times 0.462 = 0.30 \text{ tm}$ $Q = (0.80) \times 0.462 = 0.37 \text{ t}$



	Diagram	Floor	Contents
Line B		R	$w = 0.2 \text{ t/m}$ $c = \frac{1}{12} \times 0.2 \times 2.5^2 = 0.11 \text{ tm}$ $M_0 = 0.17 \text{ tm}$ $Q = 0.25 \text{ t}$

5. PERMANENT STRESS

Omitted because stress is small

6. COLUMN AXIAL LOAD


Unit: ton

C	Floor	Position	Contents	Sub-total	Total		
3-B	5	roof block	$0.13 \times 2.45 \times 3.5$ $0.20 \times 2.0 \times (1.59 + 1.2 + 0.9)$	1.12 1.48	2.60	2.60	
	4	mandy living room block stairway column	$0.675 \times 1.59 \times 1.2$ $0.462 \times 3.5 \times 1.25$ $0.2 \times (1.59 + 1.2 + 0.9) \times 2.8$ $0.668 \times 1.2 \times 1.92$ $0.675 \times 2.8$	1.29 2.02 2.07 1.54 1.89	8.81	11.41	
	3		the same to above		"	20.22	
	2		"		"	29.03	
	1		"		"	37.84	
	Footings	mandy living room " ground-girder footing	$0.675 \times 1.59 \times 1.2$ $0.462 \times 3.5 \times 1.25$ $0.462 \times 3.5 \times 1.25$ $2.4 \times 1.2 \times 0.2 \times (3.5 + 3.7)$ $0.5 \times 0.8 \times 1.5 \times 2.4$	1.29 2.02 1.06 4.20 1.44	10.00	47.84	
	2-B	5	roof partition	$0.13 \times 3.5 \times 2.5$ $0.01 \times 2.0 \times (3.5 + 1.25)$	1.14 0.10	1.15	1.15
		4	room wall column	$0.462 \times 3.5 \times 2.5$ $0.01 \times 2.8 \times (3.5 + 1.25)$ $0.48 \times 2.8$	4.07 0.13 1.35	5.56	6.71
		3		The same above		5.56	12.27
		2		"		5.56	17.83
1			"		5.56	23.39	
Footings		living room ground-girder footing	$0.462 \times 3.5 \times 2.5$ $0.576 \times (3.5 + 2.5)$	4.07 4.00 1.44	10.11	33.50	
1-B		5	roof block	$0.13 \times 3.5 \times 2.5$ $0.20 \times (3.5 \times 2.0)$	1.14 1.40	2.54	2.54
	4	living room wall block column	$0.462 \times 3.5 \times 2.5$ $0.01 \times 2.5 \times 2.8$ $0.2 \times 2.8 \times 3.5$ $0.48 \times 2.8$	4.07 0.07 1.96 1.35	7.45	10.0	
	3		The same above		7.45	17.45	
	2				7.45	24.90	
	1				7.45	32.35	

Unit; ton

C	Floor	Position	Contents	Sub-total	Total	
	Footing	floor	0.462 x 3.5 x 2.5	4.07	10.11	42.46
		ground-girder footing	0.576 x (3.5 + 2.5)	4.60 1.44		
3-C	5	roof block	0.13 x 2.6 x 2.5 0.2 x 2.0 x 2.5	0.845 1.00	1.85	1.85
	4	mandy living room block column	0.675 x 1.2 x 1.575 0.462 x 1.25 x 1.575 0.2 x (2.4 + 1.0) x 2.8 0.48 x 2.8	1.28 0.91 1.91 1.31	5.44	7.29
	3		The same above		5.44	12.73
	2		"		5.44	18.17
	1				5.44	23.61
	Footing	mandy living room ground-girder footing	0.675 x 1.2 x 1.575 0.462 x 1.25 x 1.575 0.576 x (2.4 + 1.575)	1.28 0.91 2.29 1.44	5.91	29.52
	5	roof block	0.13 x 2.4 x 2.6 0.2 x 2.0 x (1.93 + 1.25)	0.82 1.27	2.10	2.10
4	living room stairway block column	0.462 x 1.25 x 1.93 0.668 x 1.2 x 1.92 0.2 x 2.8 x (1.93 + 1.25) 0.675 x 2.8	1.12 1.54 1.78 1.89	6.33	8.43	
3		The same above		6.33	14.76	
2				6.33	21.10	
1				6.33	27.42	
Footing	living room ground-girder	0.462 x 1.25 x 1.93 0.668 x 1.2 x 1.93 0.576 x (2.4 + 1.93)	1.12 1.55 2.49 1.44	6.60	34.02	
1-A	5	roof block	0.13 x 2.5 x 1.93 0.2 x 2.0 x (1.93 + 2.5)	0.63 1.77	2.41	2.41
	4	living room block column	0.462 x 2.5 x 1.93 0.2 x (2.5 + 1.93) x 2.8 1.48 x 2.8	2.23 2.48 1.35	6.06	8.47
	3		The same above		6.06	14.53
	2				6.06	20.60
	1				6.06	26.65
	Footing	living room ground-girder footing	0.462 x 2.5 x 1.93 0.576 x (2.5 + 1.93)	2.23 2.55 1.44	6.22	32.87

Diagram for foundation axial load



7. SEISMIC LOAD

Calculated on 6 units per building

Floor	Position	Contents		Sub-total	Total
5	roof (tile)	$0.04 \times (7.0 + 2.0) \times (6.2 \times 6 + 2) \times 1.3$	16.00	19.62	35.62
	block (out)	$0.2 \times 2.0 \times (3.7 \times 2 \times 6)$	17.76		
	(in)	$0.2 \times 2.0 \times 2.5 \times 2 \times 4$	8.00		
		$0.2 \times 2.0 \times 2.0 \times 2 \times 6$	9.60		
	partition	$0.2 \times 2.0 \times (1.8 \times 3 + 2.4 + 1.4)$	3.68		
		$0.01 \times 2.0 \times (2.85 + 2.15 + 1.5 + 3.0)$	0.19		
4	Floor			107.96	156.02
	L.room	$0.38 \times (7.0 \times 5.0) \times 6$	80.22		
		$0.382 \times 1.35 \times 1.2 \times 6$	3.72		
	M/W	$0.595 \times 1.8 \times 2.4 \times 3$	7.72		
	stairway	$0.588 \times 2.4 \times 3.85 \times 3$	16.30		
	column				
	-type	$0.288 \times 2.8 \times 2$	1.62		
	L,T type	$0.24 \times 2.8 \times 8$	10.76		
	T type	$0.672 \times 2.8 \times 2$	3.77		
	wall				
1	block (out)	$0.20 \times (2.8-1.0) \times 3.7 \times 2 \times 6$	16.00	28.44	164.84
	(in)	$0.20 \times (2.8-0.5) \times 2.5 \times 2 \times 4$	9.20		
		$0.20 \times (2.8-0.5) \times 2.0 \times 2 \times 6$	11.04		
		$0.20 \times (2.8-0.5) \times (1.8 \times 3 + 2.4 + 1.4)$	4.24		
	partition	$0.01 \times 2.8 \times (2.85 + 2.15 + 1.5 + 3.0)$	0.27		
			28.44		

Floor	HM	K	W	KW	$\Sigma kw$
5	14.6	0.15	35.62	5.35	5.35
4	12.2	$0.14^3$	156.02	22.31	27.66
3	9.4	$0.13^4$	164.84	22.09	49.75
2	6.6	0.10	164.84	16.49	66.24
1	3.8	0.10	164.84	16.49	82.73

Here:


$$10M < H, K_0 = 0.1$$

$$K_{th}/K_{bh} = 1 + 0.5H$$

$$K_{bh} = \frac{1}{10 + 0.1 \times H}$$


$K_{th}$ : Top floor

$K_{bh}$ : Base floor



### 8. RATIO OF DISTRIBUTION FOR COLUMNS


This is based on the Muto's D method and the following values are estimated: That is, the exterior column is 0.5, inside column is 1.0 ~ 0.7, inflection point is 0.3 at highest floor, 0.5 at middle floors and 0.7 at lowest floor.



Shearing stress shared at  $D = 1.0$

Floor	$\sum P \cdot W$	X-Direction		Y-Direction	
		$\sum D_x$	$\sum K_w / \sum D_x$	$\sum D_y$	$\sum K_w / \sum D_y$
5	5.75	39.6	0.14	40.2	0.14
4	27.66	"	0.70	"	0.69
3	49.75	"	1.26	"	1.24
2	66.24	"	1.68	"	1.65
1	82.73	"	2.10	"	2.06

9. SEISMIC STRESS



10. CROSS SECTION

i) Girder (Both X & Y-Direction)

$\frac{RF}{}$   $sM = 0.25 \pm 1.09 = 1.34 \text{ tm}$   
 $sQ = 0.39 \pm 0.1 = 0.49 \text{ t}$

$\frac{18C \times 40C}{}$   $j = 7/8 \times 35 = 30.6$   $\text{ft} \cdot j = 2.0 \times 30.6 = 61.2$   
 $at = \frac{1.34 \cdot 10^7}{61.2} = 2.2 \text{ cm}^2$   $2 - 16\phi$

$\tau = \frac{0.49 \cdot 10^3}{18 \times 30.6} = 0.9 \text{ kg/cm}^2, < 5.5$

$\frac{5F}{}$   $sM = 1.2 \pm .55 = 1.75 \text{ tm}$   
 $sQ = 1.53 \pm .62 = 2.15 \text{ t}$

$\frac{18C \times 40C}{}$   $at = 2.9 \text{ cm}^2$

$\tau = \frac{2.15 \cdot 10^3}{18 \times 30.6} = 3.91 \text{ kg/cm}^2, < 5.5$   $2 - 16\phi$

$\frac{4 \setminus 2F}{}$

$sM = 1.2 \pm 2.4 = 3.6 \text{ tm}$   
 $sQ = 1.53 \pm 2.0 = 3.53 \text{ t}$

$\frac{18C \times 60C}{}$   $j = 7/8 \times 55 = 48$   $\text{ft} \cdot j = 2.0 \times 48 = 96$

$at = \frac{3.6 \cdot 10^7}{96} = 3.75 \text{ cm}^2$   $2 - 16\phi$


$\tau = \frac{3.53 \cdot 10^3}{18 \times 48} = 4.1 \text{ kg/cm}^2, < 5.5$

1F

$S_M = 1.8 \text{ tm}$

$S_Q = 1.45 \text{ t}$

$\frac{25C \times 80C}{at} = 1.4 \text{ cm}^2$        $j = 7/8 \times 74 = 65$        $ft \cdot j = 2.0 \times 65 = 130$   
 $2 - 13\phi \rightarrow 2 - 16\phi$




11) Column

Exterior column (1-A)

1F

$$\begin{cases} N_x = 26.65 \pm 5.62 = 32.27 \text{ t}, 21.03 \text{ t} \\ M_x = - \pm 1.8 = 1.8 \text{ tm} \\ Q_x = 1.05 \text{ t} \end{cases}$$

$$\begin{cases} N_y = 26.65 \pm - = 26.65 \text{ t} \\ M_y = - \pm 3.5 = 3.5 \text{ tm} \\ Q_y = - \pm 2.06 = 2.06 \text{ t} \end{cases}$$



$N_x/BD = 26.9, 17.5$

$N_y/BD = 22.2$

$M_x/BD^2 = 5.62$

$M_y/BD^2 = 11.0$

From the diagram

$x_{Pt} = -$

$y_{Pt} = 0.3 \%$

$x_{at} = -$

$y_{at} = 0.003 \times 1.2 \times 10^3 = 3.6 \text{ cm}^2$

$2 - 16\phi$

$J_y = \frac{2.06 \cdot 10^3}{20 \times 7/8 \times 35} = 0.66 \text{ kg/cm}^2$        $st - 9\phi - c200 (P_w = 0.32 \%)$

$$3F \begin{cases} N_x = 14.53 \pm 1.92 = 16.45 \text{ t}, 12.61 \text{ t} \\ M_x = - \pm .9 = .9 \text{ tm} \\ Q_x = .63 \text{ t} \end{cases}$$

$$\begin{cases} N_y = 14.53 \pm - = 14.53 \text{ t} \\ M_y = - \pm 1.8 = 1.8 \text{ tm} \\ Q_y = 1.24 = 1.24 \text{ t} \end{cases}$$

Section is the same above       $BD = 1.2 \times 10^3$   
 $BD^2 = 0.32 \times 10^5$

$N_x/BD = 13.7$

$10.5$

$N_y/BD = 12.1$

$M_x/BD^2 = 2.8$

$M_y/BD^2 = 5.6$

From the diagram

$xPt = -$

$yPt = 0.05$


$\therefore yat = 0.0005 \times 1.2 \times 10^3$   
 $= 0.6 \text{ cm}^2$

$1 - 16\phi$

1,2 floor


3,4,5 floor

1,2 floor (5-16  $\phi$ , 2-13  $\phi$ )  
 3,4,5 floor (7-13  $\phi$ )



(  $Pt = 14.6 / 1200 = 1.2 \%$ ,  $Pt = 10.15 / 1200 = 0.85 \%$  )

1-5 floor



11. PILES

supposed cast-in-situ Piles

Strength of materials:  $F_c \leq 400 \text{ kg/cm}^2$


Formula for bearing strength of piles, Formula (1)

The bearing capacity is obtained by the bearing strength of pile head from the below.

Unit: ton

Pile section	A $\text{cm}^2$	L <sup>M</sup>	Wt	Strength of materials	Strength of pile head	
				$F_c = 75$	Boring No.1	Boring No.2
25 x 25	607	10 or 15	1.46	45.5	19.2	27.0
30 x 30	882	"	2.11	66.0	27.2	40.5
35 x 35	1207	"	2.90	90.5	37.0	54.8

Arrangement of piles





Ex. 25 x 25 cm

point No.1 (L = 15 m)

We get  $\bar{N} = 30$ ,  $\bar{N}_s = 0$ ,  $\bar{q}_u = 1.0 \text{ kg/cm}^2$ ,  $A_p = 0.0607 \text{ m}^2$ ,  $\psi = 1.0 \text{ m}$ ,  $L_c = 6.0 \text{ m}$  from the boring data and the bearing strength of pile head from formula (1)

$$\begin{aligned} q_u &= \frac{1}{3} \times (30 \times 30 \times 0.0607 + 0) + \frac{1}{2} \times 1.0 \times 6.0 \\ &= \frac{1}{3} \times (54 + 0 + 3) \\ &= 19.2 \text{ t} \end{aligned}$$

Cross section of pile is as follow.



12. SLAB

Calculation is made on the assumption that the edge side of slab is fixed elastically and the axis of center of gravity is less than the balanced steel ratio in analysis.

1) Case;  $S_1$

Common to both X & Y-direction



$$\begin{aligned}
 l_x &= 2.7 & \lambda &= 1.0 & \omega_1 &= 0.54 \text{ t/m}^2 \\
 l_y &= 2.7 & \omega_1 l_x^2 &= 0.54 \times 2.7^2 = 3.94 \\
 Mx_1 &= (0.04) \times 3.94 = 0.16 \text{ tm/m, (= My}_1) \\
 x_2 &= (0.028) \text{ " } = 0.11 \text{ tm/m, (= My}_2) \\
 \underline{D = 100 \text{ cm}} & & j &= 6.5 & ft \cdot j &= 1.6 \times 6.5 = 10.4 \\
 \text{End ; at} &= Mx_1 / ft \cdot j = 1.54 \text{ cm}^2/\text{m} \\
 & & & & & \underline{9\phi - 250\phi} \\
 \text{Center; at} &= Mx_2 / ft \cdot j = 1.06 \text{ cm}^2/\text{m} \\
 & & & & & \underline{9\phi - 250\phi}
 \end{aligned}$$

ii) Case;  $S_2$

$$\begin{aligned}
 l_x &= 2.7 & \lambda &= 1.37 & \omega_2 &= 0.452 \text{ t/m}^2 \\
 l_y &= 3.7 & \omega_1 \cdot l_x^2 &= 3.30 \\
 Mx_1 &= (0.065) \times 3.3 = 0.215 \text{ tm/m} \\
 x_2 &= (0.044) \times \text{ " } = 0.145 \text{ " } \\
 My_1 &= (0.042) \times 3.3 = 0.139 \text{ " } \\
 y_2 &= (0.028) \times \text{ " } = 0.093 \text{ " }
 \end{aligned}$$

$$\begin{aligned}
 \underline{D = 100 \text{ cm}} \\
 \text{Short span} \\
 \text{End ; at} &= 0.215 \cdot 10^2 / 10.4 = 2.07 \text{ cm}^2/\text{m} \\
 & & & & & \underline{9\phi - \phi 200} \\
 \text{Center; at} &= & & & & = 1.40 \\
 & & & & & \underline{9\phi - \phi 200} \\
 \text{Long span} \\
 \text{End ; at} &= 1.34 \text{ cm}^2/\text{m} \\
 & & & & & \underline{9\phi - \phi 300} \\
 \text{Center; at} &= 0.9 \text{ cm}^2/\text{m} \\
 & & & & & \underline{9\phi - \phi 300}
 \end{aligned}$$

Note: Slab thickness is regulated more than 12 cm in general floors under 'NI-2' standards, but it is sufficient for the existing stress, here.

### 13. FOUNDATION

i) In the case of two piles

Spacing of pile;  $2.5 \times D = 2.5 \times 30 = 75 \text{ cm}$

$N = 47.84 \text{ t}$  (Axial load)

$$n = N / 27.2 \quad \cdot \quad 2$$

Reaction of one pile

$$\bar{N} \doteq 24.0 \text{ t}$$

Bending moment

$$M = 0.375 \times 24.0 = 9.0 \text{ tm}$$

$$Q = 24.0 \text{ t}$$

$$D = 60 \text{ cm, } j = 48 \text{ cm} \quad ft \times j = 1.4 \times 48 = 67.2 \text{ t/cm}$$

$$at = M / ft \times j = 13.4 \text{ cm}^2 \quad \cdot \quad 6 = 16\phi$$

Shearing force

$$\bar{D} = 55 \text{ cm, } j = 43 \text{ cm, } b = 800$$



$$j = \bar{N} / bxj \doteq 7.0 \text{ kg/cm}^2 \quad \text{OK}$$

11) In the case of one pile


No stress occurs

FOOTING

F2




1 Floor



Except written specially

- 1 Material of floor is composed of sand and lime addicy to compaction
- 2 Foundations are all F3 Types.
- 3 Girders are all G1 Types
- 4 Inside walls are concrete blocks, Outside walls are bricks
- 5 Columns are —, L and T types


2-5 Floor



Except witten specially


- 1 Girdess are all G1 types
- 2 Slabs are R C with thickness of 10 cm
- 3 Inside end outside walls are the same above

R Floor



Except witten specially



- 1 Girders and lateral braces are G1 types
- 2 Slabs are unnecessary



2-2  
**FS' 2-26**

1. SCOPE OF PLANNING

The building is two storied, having six units of 26 m<sup>2</sup> each floor. The inside are of concrete hollow blocks, the roof covering is tile on the joist, and the slab in the second floor is of 10 cm thick concrete and of direct slab on grade in the first floor. The structural planning was made to satisfy the above mentioned specifications, and the figures were obtained after analysis of the required stresses.



2. LOADS

Dead load

Roof (tile), 15 mm $\gamma = 1.6$	25 kg/m <sup>2</sup>
Wooden joist	10 "
Concrete slab, SF (100 mm thick)	240 "
Exterior & exterior wall (concrete block 150 mm)	200 "
Beams, 35 x 15 cm	126 kg/m
Stairway (wood)	15 kg/m <sup>2</sup>

Contents		kg/m <sup>2</sup>		For floor	For frame	For earthquake
roof	tile	25	D.L	35	35	35
	truss	10	B	-	30	30
				L.L	-	-
		<u>35</u>		35	65	65
2nd floor	concrete slsb	240	D.L	240	240	240
			B	-	30	30
			L.L	200	140	60
				<u>440</u>	<u>410</u>	<u>330</u>
wc mandi	water-proof mortar (30 mm)	60	D.L	300	300	300
	concrete slsb	240	B	-	30	30
			L.L	200	140	60
		<u>300</u>		500	470	390
stairway	wooden stair	15	D.L	15	15	15
			B	-	-	-
			L.L	200	140	60
				<u>215</u>	<u>155</u>	<u>75</u>


3. AXIAL LOAD (EXCLUDING DEAD LOAD OF FOUNDATION)

C	Floor	Position	Contents	Sub-total	Total	
YW1	2	roof block	0.065 x (3.5/2 + 1.0) x (3.4 + 0.6) 0.2 x 2.0 x 2.0 0.2 x 1.6 x 1.0	0.72 0.81 0.32	1.85	1.85
	1	floor block	0.41 x 3.4 x 3.5/4 0.2 x 2.0 x 2.4 0.2 x 1.6 x 1.0	1.22 0.96 0.32	2.50	4.35
$\Sigma L_y = 1.9 \text{ m}$ then 2.29 t/m						
YW3	2	roof block	0.065 x 3.5 x 4.0 0.2 x 1.65 x 3.5 0.2 x (1.5 + 1.3) x 2.0	0.91 1.16 1.12	3.19	3.19
	1	floor wc/m floor block	0.45 x 3.4 x 3.5/4 0.45 x 1.2 x 1.2 0.47 x 1.5 x 0.75 x 1/2 0.41 x 2.5 x 1.25 x 1/2 0.2 x (1.5 + 1.3) x 2.4	1.22 0.95 0.27 0.64 1.35	4.07	7.26
$\Sigma L_y = 1.5 + 1.3 = 2.8 \text{ m}$ then 2.60 t/m						
YW5	2	roof block	0.065 x (3.5/2 + 1.0) x 4.0 0.2 x 2.0 x (2.0 + 0.9) 0.2 x 1.0 x 1.2	0.715 1.16 0.24	2.11	2.11
	1	wc/m floor block	0.47 x 1.5 x 0.75 x 1/2 0.41 x 2.5 x 1.25 x 1/2 0.2 x 2.4 x (2.0 + 0.9) 0.2 x 1.0 x 1.2	0.27 0.64 1.40 0.24	2.55	4.66
$\Sigma L_y = 1.5 + 0.9 = 2.4 \text{ m}$ then 1.95 t/m						
XW1	2	roof block	0.065 x 2.0 x (3.5 + 1.0) 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	wc/m block	0.47 x 1/2 x 0.75 x (3.5 + 2.1) x 2 0.2 x 3.5 x 2.4	1.94 1.68	3.62	6.38
$\Sigma L_x = 3.5 \text{ m}$ then 1.83 t/m						
XW2	2	roof block	0.065 x 2.0 x 4.5 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	stair floor block	0.155 x 0.6 x 3.5 0.41 x 3.5 x 3.4/4 0.2 x 3.5 x 2.4	0.33 1.19 1.68	3.20	5.96
$\Sigma L_x = 2.6 \text{ m}$ then 2.3 t/m						
XW3	2	roof block	0.065 x (0.75 + 1.0) x 4.5 0.2 x 3.5 x 3.1	0.51 2.17	2.68	2.68
	1	wc/m floor block	0.47 x 1/2 x 0.75 x (3.5 + 2.0) 0.41 x 1/2 x (3.5 + 1.0) x 1.25 0.2 x 3.5 x 2.4	0.97 1.16 1.68	3.81	6.49
$\Sigma L_x = 2.5 \text{ m}$ then 2.6 t/m						
XW4	2	roof block	0.065 x 2.0 x 4.5 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	floor block	0.41 x 3.4 x 3.5/4 x 2 0.2 x 3.5 x 2.4	2.44 1.68	4.12	6.88
$\Sigma L_x = 3.5 \text{ m}$ then 1.97 t/m						
XW5	2	roof block	0.065 x 2.0 x 4.5 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	floor block	0.41 x 1/2 x (3.5 + 1.0) x 1.25 x 2 0.2 x 3.5 x 2.4	2.31 1.68	3.99	6.75
$\Sigma L_x = 3.5 \text{ m}$ then 1.93 t/m						

Maximum and minimum compressive unit stresses

$$\max \sigma_c = \frac{1040}{15 \times 40} = 1.74 \text{ kg/cm}^2$$

$$\min \sigma_c = \frac{732}{15 \times 40} = 1.23 \text{ kg/cm}^2$$



#### 4. HORIZONTAL LOAD

2nd floor

Floor	Position	Contents	Sub-total	Total
2	roof	0.065 x 9.0 x 4.0 x 6 x 1.13	15.87	82.1 <sup>+</sup>
	block (x)	0.20 x 3.5 x 3.1 x 8	17.36	
		0.20 x (3.5 x 3.1 - 0.9 x 2.0) x 6	10.86	
		0.20 x (3.5 x 3.1 x 9) - (1.0 x 2.0 x 6)	17.13	
		(y)		
	(out)	0.20 x (3.4 x 2.0 - 1.6 x 1.0) x 6	6.24	
		0.20 x (4.0 x 2.0 - 1.6 x 1.0) x 6	7.68	
	(in)	0.20 x (4.0 x 2.0 - 1.1 x 2.0) x 6	6.96	
	2nd floor			56.1
	wc/m	0.39 x 1.5 x 3.5 x 6	12.30	
		0.33 x 2.5 x 3.5 x 6	17.33	
		0.33 x 3.4 x 3.5 x 6	23.60	
		0.33 x 1.2 x 1.2 x 6	2.86	
	block (x)	0.20 x 3.5 x 2.4 x 8	13.44	29.0
0.20 x (3.5 x 2.4 - 0.9 x 2.0) x 6		8.16		
0.20 x (3.5 x 2.4 - 1.0 x 2.0) x 6		7.68		
(y)			56.9	
	(out)	0.20 x (3.4 x 2.4 - 1.6 x 1.0) x 6		7.88
(in)	0.20 x (4.0 x 2.4 - 1.6 x 1.0) x 6	9.60	29.0	
	0.20 x (4.0 x 2.4 - 1.1 x 2.0) x 6	8.68		
stairway	0.075 x 1.2 x 2.3 x 6	1.25		85.1 <sup>+</sup>

#### 5. SEISMIC LOAD AND LENGTH OF WALL

	K x W	KW	ΣKW	ΣLx <sup>m</sup>	ΣLy <sup>m</sup>
2 F	0.1 x 82.10	8.21	8.21	68.5	7.5 x 6
1 F	0.1 x 85.10	8.51	16.72	"	"

#### 6. AVERAGE SHEARING UNIT STRESS

(τ kg/cm<sup>2</sup>)

	Shearing stress	
	x-direction	y-direction
2 F	0.13	0.18 <sup>1</sup>
1 F	0.25	0.37 <sup>2</sup>


$$\tau = \frac{KW \times 1.5}{\Sigma L \times t}$$

Both figures satisfy the allowable shearing unit stress of blocks (1.36 kg/cm<sup>2</sup>)



7. STUDY AFTER THE FAILURE OF UNREINFORCED BLOCKS


Calculations were made supposing a sufficiently sound reinforced block column at the end of a wall and a rigid-framed structure of beams.



7-1 PERMANENT STRESS

Omitted because the stress is small.

7-2 SEISMIC STRESS



7-3 CROSS SECTION

a. Beams

$1F_1 \quad M = 0.46 \text{ tm}$

$Q = 0.31 \text{ t}$

$B \times D = 19C \times 25C$

$\gamma = 17.5C$

$$at = 0.46 \cdot 10^2 / 2.0 \times 17.5 = 1.31 \text{ cm}^2 \quad + 1-13\phi$$

$$Q = 0.31 \times 10^3 / 15 \times 17.5 = 1.2 < 9.0 \text{ kg/cm}^2$$


2F;  $M = 0.40 \text{ tm}$

$Q = 0.54 \text{ t}$

$B \times b = 15C \times 25C$

$at = 1.16 \text{ cm}^2 + 1-13\phi$

Same to 1F.





RF. (Include lateral brace)

$M = 0.07 \text{ tm}$

$Q = 0.1 \text{ t}$

$B \times D = 15C \times 20C$

$at = 0.28 \text{ cm}^2 + 1-9\phi$



#### 7-4 AXIAL LOAD

Supposing the reinforced block columns will support a floor load near the column after the failure of the unreinforced block wall


##### Column (2-B)

roof	$0.065 \times (0.75 \times 1.25) \times 1.13$	0.15	1.3	
	$0.065 \times (1.65 \times 1.75) \times 1.13$	0.25		
wall	$0.20 \times 2.0 \times (1.25 + 1.0)$	0.90		
2nd floor				
slab	$0.47 \times 0.75 \times 1.75$	0.62	3.92	5.22 <sup>+</sup>
	$0.41 \times 1.25 \times 1.75$	0.90		
	$0.41 \times 1.7 \times 1.75$	1.22		
wall	$0.20 \times 2.4 \times (0.45 + 2.0)$	1.18		

##### Column (3-B)

roof	$0.065 \times 1.75 \times 3.4 \times 1.13$	0.44	3.14	
	$0.065 \times 1.75 \times 2.5 \times 1.13$	0.33		
wall	$0.20 \times 2.0 \times (2.5 + 3.4)$	2.36		
2nd floor				
slab	$0.41 \times 1.75 \times (2.5 + 3.4)$	4.24	6.60	9.74 <sup>+</sup>
wall	$0.20 \times 2.0 \times (2.5 + 3.4)$	2.36		

7-5 EFFICIENCY OF REINFORCED BLOCK COLUMN



a. With no filling

x-x axis

$$I_{x1} = \frac{1}{12} \times 1.5 \times 40^3 \times 2 + (12 \times 1.5) \times (20 - 3.0)^2 \times 2 + (12 \times 1.5) \times 5.7^2 \times 2$$

$$= 27,737.5 \text{ cm}^4$$

$$Z_{x1} = 1386.8 \text{ cm}^3$$

$$A_1 = 192.0 \text{ cm}^2$$

b. With filling (No.1)

$$I_{x2} = 78557.0 \text{ cm}^4$$

$$Z_{x2} = 3928 \text{ cm}^3$$


$$A_2 = 415.2 \text{ cm}^2$$

c. With filling (No.2)

$$I_{x2} = 86137.5 \text{ cm}^4$$

$$Z_{x3} = 4306.9 \text{ cm}^3$$

$$A_3 = 447.6 \text{ cm}^2$$



Fiber stress of column

$$6c = \frac{N}{A} \pm \frac{M}{Z} = \frac{5220}{447.6} \pm \frac{68000}{4306.9} = 11.7 \pm 15.8$$

$$= 27.5 \text{ or } -4.1 \text{ kg/cm}^2$$

$$\tau = \frac{470}{40 \times 20} = 0.59 \text{ kg/cm}^2 < 1.36 \text{ kg/cm}^2$$

From the bending moment, the fiber stress gives the above value. Reinforcement is provided on the tension side and twice the  $13.6 \text{ kg/cm}^2$  specified is provided on the compression side. But, it is enough, if the above value in compression stress is less than two third strength of additional cement mortar or concrete. Therefore, it will be necessary to appraise the strength of these composite columns.

8. FOUNDATION


Upper axial load: Two kinds of less than 2.0 t/m and 2.6 t/m bearing capacity of soil;  
Two kinds of  $3.0 \text{ t/m}^2$  and  $5.0 \text{ t/m}^2$

Footing weight

$$\text{Ground-beam} \quad 0.15 \times 1.0 \times 2.4 = 0.36 \text{ t/m} \quad \div 1.0 \text{ t/m}$$

$$\text{Batakali} \quad 0.6 \times 1.0 \times 0.4 \times 2.6 \text{ t/m}^2 = 0.63$$

Contact pressure is both 3.0 t/m and 3.6 t/m per meter. We get effective widths of footing according to the bearing capacity of soil.



In case of 3.0 t/m<sup>2</sup>

$$B_1 = \frac{3.0 \text{ t/m}}{3.0 \text{ t/m}^2} \rightarrow 1.0 \text{ m}$$

$$B_2 = \frac{3.6 \text{ t/m}}{5.0 \text{ t/m}^2} \rightarrow 1.2 \text{ m}$$


In case of 5.0 t/m<sup>2</sup>

$$B_1 = \frac{3.0 \text{ t/m}}{5.0 \text{ t/m}^2} \rightarrow 0.6 \text{ m}$$

$$B_2 = \frac{3.6 \text{ t/m}}{5.0 \text{ t/m}^2} \rightarrow 0.75 \text{ m}$$

Conclusion


PLAN



1 FLOOR

Besides above

1. Footing F1
2. Ground-beam G1
3. Slab-on-grade








2 FLOOR

Besides above

1. shows DT
2. Beam G1
3. Slab 10S2
4. Stairway wood
5. O shows reinforced concrete block (Type B.C)
6. X shows the open reinforcement (Type A)

CROSS SECTION




Same arrangement of bar  
both in long and short span.

# M-24


## 1. OUTLINE OF PLANNING

The building is a six units per floor, two storey house of 24 square meter maisonettes. This material is used the same ones for FS'2-26, but the building itself is light in weight because of the use of wooden floor joists for the second floor. The structural planning satisfy the above-mentioned specifications and stresses are obtained by the analysis.

## 2. PLANS AND FRAMING



## FRAMING



3. LOADS

Dead load

Same to FS'2-28 type except below

Wooden floor, 2F                      25 kg/m<sup>2</sup>  
 Beam 20 x 15                              72 kg/m

	Contents		Floor	Frame	Seismic
		D.L	25	25	25
		Beam		20	20
2F	Wooden floor 25 kg/m <sup>2</sup>	L.L	200	140	60
			225	185	105

4. AXIAL LOAD

• Averaged axial stress of wall along line (B) (Y-Direction)

2F

roof      0.065 x (1 + 1.5)      = 0.163 t/m  
 wall      0.20 x 2.0                      = 0.40              > 0.563 t/m

1F

slab      0.185 x 1.5                      = 0.278  
 wall      0.20 x 2.4                      = 0.48              > 0.758 t/m

Total 1.32 t/m

• Averaged axial stress of wall along line (1) (X-Direction)

2F

roof      (0.065 + 1/2 x 3.0 x 1.5) x 2 x 1/3 = 0.1 t/m  
 wall      0.2 x 2.0                              = 0.4              > 0.50 t/m

1F

slab      0.185 x 1.0                              = 0.185              > 0.665 t/m  
 wall      0.2 x 2.4                              = 0.48

Total 1.265 t/m

5. HORIZONTAL LOAD AND SHEARING UNIT STRESS

2nd floor

roof      0.065 x 4.0 x (3.0 + 2.0) x 6 x 1.13 = 10.14 t              27.19 t  
 block      0.2 x 2.0 x (3.0 x 10 + 4.6 x 6 x 2) = 34.10

1st floor

floor      0.185 x 3.0 x 4.0 x 6                      = 13.32  
 stairway      0.155 x 1.2 x 3.0 x 1.2 x 3              = 2.0              52.82 t  
 block      0.2 x 2.4 x (3.0 x 10 + 4.6 x 6 x 2) = 40.9

For each building (6 units)

Floor	W	K	K <sub>w</sub>	ZKW	LBW <sup>m</sup>	LBK <sup>m</sup>	τ <sub>x</sub> kg/cm <sup>2</sup>	τ <sub>y</sub> kg/cm <sup>2</sup>
2	27.19	0.1	2.72	2.72	31.2	24	0.09	0.1
1	52.82	0.1	5.32	8.02	31.2	30	0.26	0.27

Average shearing unit stress is sufficient in the allowable shearing unit stress.

6. STUDY AFTER THE FAILURE OF UNREINFORCED BLOCKS

Taking FS'2-28 into account.

6-1 PERMANENT STRESS

Line (A) : The distance between supporting points on the beam is small due to reinforced blocks being placed at the opening near the corner so, stress is small.

Span 2.0m,  $w = 0.075 \text{ t/m}$  (beam itself)


$$c = \frac{1}{12} \times 0.075 \times 2.0^2 = 0.025 \text{ tm}$$

$$M_o = 0.038 \text{ tm}$$

$$Q = 0.075 \text{ t}$$

6-2 SEISMIC STRESS

Line (B) stress



No. of column	Shearing force	Shearing force/Column
30	1.82	0.1
30	5.35	0.27

Shearing force is the same to x and y directions.

6-3 AXIAL LOAD ON REINFORCED BLOCK COLUMN AT CORNER

(2)-(A), (2)-(B) column.

2F

$$\begin{array}{l} \text{Line (A)} \quad 0.563 \text{ t/m} \times 1.0 = 0.563 \text{ t} \\ \text{Line (1)} \quad 0.5 \quad \times 3.0/2 = 0.750 \end{array} \quad \left. \vphantom{\begin{array}{l} \text{Line (A)} \\ \text{Line (1)} \end{array}} \right\} 1.31 \text{ t}$$

1F

$$\begin{array}{l} \text{Line (A)} \quad 0.758 \text{ t/m} \times 1.0 = 0.758 \text{ t} \\ \text{Line (1)} \quad 0.665 \quad \times 3.0/2 = 1.00 \end{array} \quad \left. \vphantom{\begin{array}{l} \text{Line (A)} \\ \text{Line (1)} \end{array}} \right\} 1.76$$

$$\text{Total} \quad 3.07 \text{ t}$$

6-4 CROSS SECTION

a. Beams

$$1F, \quad M = 0.16 \text{ tm}$$

$$Q = 0.11 \text{ t}$$

$$B \times D = 15C \times 20C \quad j = 13.0$$

$$at = 0.16/2.0 \times 13.0 = 0.62 \text{ cm}^2 \quad + 1-9\%$$


$$\tau = 0.11 \times 10^3 / 15 \times 13 = 0.6 \text{ kg/cm}^2 \quad \text{OK}$$



2F; M = 0.215 tm  
 Q = 0.21 t  
 B x D = 20C x 15C j = 8.3  
 at = 1.3 cm<sup>2</sup> + 2-9φ  
 τ = 1.23 kg/cm<sup>2</sup> OK

RF; M = 0.095 tm  
 Q = 0.13 t  
 B x D = 15C x 15C  
 at = 0.58 cm<sup>2</sup> 1-9φ  
 τ = 1.1 kg/cm<sup>2</sup> OK

RG1 (TB1)



b. Column

1F; N<sub>x</sub> = 3.07 ± 0.36 = 3.43 t or 2.71  
 M<sub>x</sub> = 0.32 tm  
 Q<sub>x</sub> = 0.27 t

Efficiency of column

I = 85333.5 cm<sup>4</sup>  
 Z = 4266.6 cm<sup>3</sup>  
 A = 303.6 cm<sup>2</sup>

Fiber stress

$$\sigma_{c1}, \tau_1 = \frac{3.43 \times 10^3}{303.3} \pm \frac{0.32 \times 10^5}{4266.6}$$

$$= 11.3 \pm 7.5$$

$$= 18.8 \text{ or } 3.8 \text{ kg/cm}^2$$

Only compression stress.


$$\sigma_{c2}, \tau_2 = \frac{2.71 \times 10^3}{303.3} \pm \frac{0.32 \times 10^5}{4266.6} = 8.9 \pm 7.5$$

$$= 16.4 \text{ or } 1.4 \text{ kg/cm}^2$$

Only compression stress

$$\tau = \frac{0.27 \times 10^3}{40 \times 15} = 0.45 \text{ kg/cm}^2 < 1.36 \text{ kg/cm}^2$$

OK



reinforced concrete block

7. FOUNDATION


We calculate the same condition as FS'2-38 type.

Upper axial load	1.32 t/m	
Footing; Groundbeam	0.06	Total 1.62 t/m
Batukali	0.24	


We get effective widths of footing according to the bearing capacity of soil,

In case of  $3.0 \text{ t/m}^2$ ;  $B_1 = \frac{1.62 \text{ t/m}}{3.00 \text{ t/m}^2} \rightarrow 55 \text{ cm}$

In case of  $5.0 \text{ t/m}^2$ ;  $B_2 = \frac{1.62 \text{ t/m}}{5.00 \text{ t/m}^2} \rightarrow 35 \text{ cm}$



CONCLUSION



Besides above

1. Footing F1
2. Ground beam G1
3. Slab on grade

1. Beam G1
2. Wooden floor + joist
3. Staircase; wood
4. O shows reinforced concrete block (type E,C)
5. x shows open reinforcement (type A0)

### **3 SCHEDULES AND MINUTES**



SCHEDULE OF PHASE I STUDY (Oct.1979 ~ March.1980)

Studies including field surveys, which were carried out three times consecutively, were carried out according to the following schedule.

General schedule

	79		80		Jan.	Feb.	Mar.
	Oct.	Nov.	Dec.	Jan.			
	10 1st. Field survey	9 22 2nd. Field survey	25 Field survey	5 22 3rd. Field survey	22	30	Explanation of Phase I Report Submission of Phase I Report
JIRO SUZUKI Leader	■	---	---	■	---	---	■
HAJIME SABO Town planner	■	---	■	---	---	---	■
TAKESI BABA Architect		---	---	---	---	---	---
SHUNJI KAWADA Architect	■	---	■	■	---	---	---
SHUNRAN TAKAHASHI Structural engr.	■	---	---	■	---	---	---
YUTAKA SAITO Mechanical engr.	■	---	■	---	---	---	---
YASUSHI MIYAZAKI Irrigation engr.	■	---	---	---	---	---	---
RYOICHI KAWASAKI Engineering geologist	■	---	---	---	---	---	---
HIROYA YOSHIKAWA Environmental scientist		■	■	---	---	---	---

■ Field survey  
--- Home study

Main items

1979 12th Oct.	Inception report discussion
16th Oct.	-do-
17th Oct.	-do-
18th Oct.	Arrangement of studies and schedule
26th Oct.	Inception report discussion and signature of the minutes on the discussion by Ir. Suyono, and Suzuki.
26th Oct.	Discussion on the results of the first field survey
27th Oct.	"
14th Dec.	Presentation report by the Japanese Study Team. (Joint conference with Indonesian Steering Committee and Counterpart.)
15th Jan.	Discussion on the results of the studies based on the first and second field surveys.
18th Jan.	Interim report by the Japanese Study Team. Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated experts, Japanese Embassy and JICA.
21st Jan.	Signature of the minutes on the interim report conference by Ir. Suyono, and Suzuki.
27th March.	Signature of the minutes on the Phase I Report by Ir. Suyono and Mr. Suzuki.

SCHEDULE OF PHASE II STUDY (Jul.1980 ~ March.1981)

General schedule

	80	Jul.	Aug.	Sept.	Oct.	Nov.	Dec.	81	Jan.	Feb.	Mar.
		16	29		7	3					4 13
		1st. Field survey			2nd. Field survey						Explanation of Draft Report Final Report
JIRO SUZUKI Leader	---	---	---			---					---
HAJIME SABO Town planner	---	---	---		---	---					---
MASANORI ONOE Town planner	---	---	---			---					---
MICHIKO INAGAKI Architect	---	---	---		---	---					---
SHUNJI KAWADA Architect	---	---	---		---	---					---
SHUNRAN TAKAHASHI Construction engr.	---	---	---		---	---					---
NAOHARU NAGAO Structural engr.	---	---	---		---	---					---
YUTAKA SAITO Mechanical engr.	---	---	---		---	---					---
GEN FUJIWARA Civil engr.	---	---	---		---	---					---
MIKIO TANEMURA Civil engr.	---	---	---		---	---					---
NAOFUMI HIROTA Cost analyzer	---	---	---		---	---					---
MOTOHIDE NISHIO Economist	---	---	---		---	---					---
TAKASHI INOUE Economist	---	---	---		---	---					---

Field survey  
Home study

Main items

- 1980 17th July : Inception report discussion
- 24th July : Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated housing experts, Japanese Embassy and JICA.
- " " : Signature of the minutes of the discussion on the Inception Report by Ir. Suwarno and Mr. Suzuki.
- 9th Oct. : Discussion with local government (DKI)
- 17th Oct. : Discussion with PERUM PERUMNAS directors (Planning and construction div.)
- 22nd Oct. : Discussion with relating government body on the drainage system at PERUMNAS.
- 4th Nov. : Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated housing experts, Japanese Embassy, JICA and other relating government body officials.
- 7th Nov. : Signature of the minute of the discussion on the Progress Report by Ir. Suwarno and Mr. Suzuki.
- 12th Mar. : Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated housing experts, Japanese Embassy, JICA and other relating government body officials.
- " " : Signature of the minute of the discussion on the Draft Final Report by Ir. Radinal Mochtar and Mr. Suzuki.



SCOPE OF WORK  
FOR  
THE STUDY OF LOW COST HOUSING PROJECT

(KTA 20)

Agreed


Between

JAPAN INTERNATIONAL COOPERATION AGENCY


And

CIPTA KARYA

Dated :



(Mr. Takao Hirota)  
Director of  
Social Development Cooperation  
Department, Japan International  
Cooperation Agency.



Ir. Radinal Mochtar  
Director General of Cipta Karya  
Department of Public Works.

## I. INTRODUCTION

In response to a request of the Government of the Republic of Indonesia, the Government of Japan has decided to conduct a feasibility study for the low cost housing project. The Japan International Cooperation Agency ( hereinafter referred to as " JICA " ) the official agency responsible for implementation of technical cooperation programs of the Government of Japan, will carry out the study in close cooperation with the Government of the Republic of Indonesia and its authorities concerned.

## II. BACKGROUND OF THE STUDY.

Housing Policies in Indonesia has been developed since PELITA II ( 1974/75 - 1978/79 ).

Low cost housing, one of the main housing program of the government in PELITA II, were mainly supplied with low rise housing development. But in PELITA III ( 1979/80 - 1984/85 ) some changes in the policy are going to be implemented which will include the development of four storied housing or so called " walk-up-flats ", with the objective of optimizing the use of land especially in the large and density populated urban areas.

According to the housing program in PELITA III, 50.000 units of four storied housing are planned to be constructed by PERUM PERUMNAS as part of the 120.000 units houses to be built by PERUM PERUMNAS in the coming five years period. In this framework, the development of four storied housing is considered of high priority by the Indonesian Government.

It is widely known, that many parts of the northern coast of Java consist of low level and swampy lands presently left undeveloped. Many of these lands are situated close to the city center. Therefore if it can be proven that such undeveloped land can be successfully changed into a good housing estate, such experience can be applied more widely in other areas in Indonesia.

### III. OBJECTIVES.

The study aims at two targets :

One is to conduct feasibility study and preliminary engineering design for housing development project in the site of Cengkareng. The coverage of the engineering design will be subject to further decision by both parties. Secondly is to develop standardized designs for pilot Walk-up flat for public housing, with possible development in Cengkareng Site.

### IV. THE SCOPE OF THE STUDY.

#### 4.1. The feasibility study of housing development project in the site of Cengkareng.

4.1.1. In order to achieve the said objectives, the study will cover :

1. Survey and analysis of general conditions, with particular attention to social, drainage, sewerage and other civil engineering aspects.
2. Assessment of socio-economic development potentials of the site, including preliminary estimate of development cost.
3. Conducting basic designs of site planning in some parts of the site.

4.1.2. The Implementation programme for the feasibility study in Cengkareng site will be decided taking in to consideration the feasibility of the development of standardized designs of pilot walk-up flat.

4.1.3. The size of the site will be decided based on criteria such as the target group, population density, mixed community, etc. The tentative site area is considered within the range of 30 Ha to 50 Ha.

#### 4.2. The development study for the pilot walk-up flat.

4.2.1. In order to achieve the previously mentioned objectives, the study will consider the following :

1. Feasibility of utilizing local materials with due consideration to its socio-economic and employment effects.

2. Conformity between the affordability of the target group and cost of house which will be provided.
  3. The minimum building standard and regulation, and other provisions as appropriate.
  4. Rationalization of construction works in order to shorten the term of works and to simplify the construction works.
- 4.2.2 The results of studies that will be prepared and submitted are the formulation of standardized designs of the pilot walk-up flat, the identification of structural calculation and the estimation of construction cost.

4.2.3. The implementation program of study is as follows :

( The first stage ).

The following preliminary study will be implemented by the Japanese team dispatched to Indonesia under the cooperation with the Indonesian counterpart team.

1. Inventory and analysis of the data and the following fields covered :
  - The characteristics of housing demands.
  - The present situation of housing industries and housing supply system.
  - Construction cost, land price, building materials available and the others.
2. Setting up the pre-condition for tentative design.
  - The floor size of a dwelling unit.
  - The dimensions of each part of building
  - The size of building and the number of storey.
  - The housing equipment performance level
  - The dwelling performance level.
  - The estimation construction cost.
  - The building materials by each part of building.

( The second stage ).

According to the pre-condition for tentative design, draft designs will be formulated either in Indonesia or in Japan. In the latter case, possibilities will be explored for the provision of funds for counterpart personnel to participate in drafting the design in Japan.

( The third stage ).

The draft designs prepared on the second stage will be reassessed fully and orientation of modification is considered in detail by the joint team of Japan and Indonesia.

( The fourth stage ).

In accordance with the result of reassessment on the third stage, modification of the draft designs will be implemented and the final standardized designs of pilot walk-up flat will be completed in Indonesia or in Japan.

V. STAFFING.

The study will be undertaken by a team of professionals covering the following fields :

1. Project management.
2. Architecture designs
3. Building structure engineering
4. Building equipment engineering
5. Civil engineering

It is understood , that city planning and financial / economic analysis necessary for the project is already covered in the above mentioned fields.

VI. CONTRIBUTION OF THE GOVERNMENT OF INDONESIA.

For the purpose of the study , the Government of Indonesia through PERUM PERUMNAS will cooperate to the extent possible by :

1. Providing the team with the data and information concerned with its use in connection with the study.
2. Carrying out works of soil test.
3. Facilitate for obtaining exemption from taxes and duties for machinery equipment and materials necessary for the study.
4. Assigning counterpart personnel ( officials/engineers ) to the team during the study period.
5. Providing the team with suitable office space and office equipment necessary for the study.
6. Providing vehicles with drivers.

7. Providing any other available facilities that may be required for the execution of the study as it will be agreed upon between both parties.

#### VII. CONTRIBUTION OF JICA.

For the purpose of the study , the Government of Japan will assist to the extent possible :

1. Sending the Japanese expert team to conduct the study.
2. Transferring the knowledge to the Indonesian counterpart experts during the period of the study.
3. Arranging the equipment necessary for the efficient conduct of the study.

別紙一七


MINUTES OF THE DISCUSSIONS ON THE  
INCEPTION REPORT FOR THE LOW COST  
HOUSING PROJECT ( KTA-20 )

( Phase I )


The discussion on the Inception Report were held on the 12th, 16th and 17th of October in 1979 at PERUM PERUMNAS ( see ATTACHMENT I ) and the contents of the Inception Report were fundamentally agreed upon by both parties after recognizing the following items :

- 1 - a) The objective of this study is to make pre-feasibility study for Housing Development Project on the site of PERUM PERUMNAS in Cengkareng considering the combination of types of housing.  
b) It will be studied whether a walk up flat is suitable or not to the site of Cengkareng as one of the housing types mentioned above.
- 2 The organization of the study and the members of each part of the organization is shown in ATTACHMENT II.  
The complete members for the steering committee and the counterpart will be nominated in December 1979.
- 3 Indonesian side requested that the transfer of technology shall be considered more.  
Japanese side replied that they would try their best for the effective transfer of technology such as adjustment of working schedule and the way of working.

October 23, 1979. .



Ir. Suyono, M.Sc.  
Director of Planning  
PERUM PERUMNAS



Jiro SUEKI  
Team Leader of Japanese  
Study Team


ATTENDANTS' LIST OF MEETINGS

ATTACHMENT I.

Date Place	1st	2nd	3rd
ATTENDANTS	<p align="center">Oct. 12, 1979 PERUM PERUNNAS</p> <p><u>INDONESIAN SIDE</u> PERUM PERUNNAS Ir. Soenarjono Danoedjo Ir. Suyono, M.Sc. Mr. Soelistijo Tjitrohamidjojo Ir. Duddy Soegoto Ir. Aziz Dahlan Ir. Yos Sidharta</p> <p><u>JAPANESE SIDE:</u> ADVISORY COMMITTEE Mr. Nobuaki Okubo Mr. Toshio Ishiguro Mr. Tetsuo Numnoi</p> <p>STUDY TEAM Mr. Jiro Suzuki Mr. Hajime Sabo Mr. Shunji Kawada Mr. Shuuran Takahashi Mr. Yutaka Saito Mr. Yashushi Miyazaki Mr. Ryoichi Kawasaki</p> <p>JICA Mr. Takeshi Shinoura</p> <p>EMBASSY Mr. Takeo Yamazaki</p> <p>EXPERT FOR KTA 7/8 Mr. Shinsaku Kanetaki Mr. Toshio Itami Mr. Hajime Obata</p>	<p align="center">Oct. 16, 1979. PERUM PERUNNAS</p> <p><u>INDONESIAN SIDE</u> PERUM PERUNNAS Ir. Duddy Soegoto Ir. Aziz Dahlan</p> <p><u>JAPANESE SIDE</u> ADVISORY COMMITTEE Mr. Nobuaki Okubo Mr. Toshio Ishiguro Mr. Tetsuo Numnoi</p> <p>STUDY TEAM Mr. Jiro Suzuki Mr. Hajime Sabo Mr. Shunji Kawada Mr. Yutaka Saito</p>	<p align="center">Oct. 17, 1979 PERUM PERUNNAS</p> <p><u>INDONESIAN SIDE</u> PERUM PERUNNAS Ir. Suyono, M.Sc. Ir. Duddy Soegoto Ir. Aziz Dahlan</p> <p><u>JAPANESE SIDE</u> ADVISORY COMMITTEE Mr. Nobuaki Okubo Mr. Toshio Ishiguro Mr. Tetsuo Numnoi</p> <p>STUDY TEAM Mr. Jiro Suzuki Mr. Hajime Sabo Mr. Shunji Kawada Mr. Shuuran Takahashi Mr. Yutaka Saito Mr. Yashushi Miyazaki Mr. Ryoichi Kawasaki</p> <p>JICA Mr. Takeshi Shinoura</p> <p>EMBASSY Mr. Takeo Yamazaki</p> <p>EXPERT FOR KTA 7/8 Mr. Shinsaku Kanetaki Mr. Toshio Itami Mr. Hajime Obata</p>



ATTACHMENT II Work Organization



1. INDONESIAN STEERING COMMITTEE

Director General of CIPTA KARYA  
 IR. RADINAL MOOCHTAR

Director of Housing of CIPTA KARYA

Director of Sanitation Technic of  
 CIPTA KARYA

President Director of PERUM PERUMNAS

Director of Planning of PERUM  
 PERUMNAS

*Yujid* Director of *Construction* ~~Relate Management~~ of  
 PERUM PERUMNAS

The head of institutions of DKI  
 Jakarta .

3. JAPANESE HOUSING EXPERT for KTA 7/8

SHINSAKU KANETAKI

TOEHIO UETAMA

HAJIME OBATA

HAJIME TOKOROPI

4. JAPANESE STUDY TEAM

JIRO SUZUKI leader  
 Nihon Architects, Engineers & Con-  
 sultants, Inc. (NAEC)

HAJIME SABO Town Planner  
 NAEC

SHUNJI KAWADA Architect  
 NAEC

SHOHRAN TAKAHASHI Structural Engi-  
 neer  
 NAEC

YUTAKA SAITO Mechanical Engineer  
 NAEC

YASUSHI MIYAZAWA Irrigation Engi-  
 neer  
 NAEC

RYOICHI KAWASAKI Engineering Geo-  
 logist  
 NAEC

HIROYA YOSHIKAWA Environmental  
 Scientist  
 NAEC

5. INDONESIA COUNTERPART

IR. DODDY SOEGOTO Coordinator  
 PERUM PERUMNAS

IR. AZIZ DAHLAN Planner  
 PERUM PERUMNAS

IR. HERRY PURNOMO Architect  
 PERUM PERUMNAS

IR. PARYATRO PARBO Civil Engineer  
 PERUM PERUMNAS

•  
 •  
 •  
 •  
 •


MINUTES OF THE DISCUSSIONS  
ON THE INTERIM REPORT FOR LOW COST HOUSING PROJECT  
IN CENKARENG, JAKARTA (KTA-20) PHASE I.

The Interim Report ( see ATTACHMENT 1 ) was submitted and explained by the Japanese Study Team and discussed by the participants ( see ATTACHMENT 2 ) at the Joint Meeting on the 18th of January in 1980 in Jakarta.


The Interim Report which orientates the frame of the Final Report ( draft ) was fundamentally agreed upon by both parties after recognizing the following items :

- 1) The Final Report of Phase I ( draft ) shall be formulated on the basis of the Interim Report with the accomplishment of the purpose of Phase I explained at the Joint Meeting.
- 2) The findings and alternatives proposed during Phase I will be evaluated in Phase II after considering additional data, especially socio-economical aspects.
- 3) The boundary of planning area shall be decided before Phase II.
- 4) The study on various types of houses shall be developed in Phase II on the basis of the Interim Report.

January 21, 1980.



Ir. Suyono, M.Sc.  
Director of Planning  
PERUM PERLUNAS



Jiro Suzuki  
Team Leader of Japanese  
Study Team

THE STUDY OF LOW COST HOUSING PROJECT (KTA-20)  
PHASE I

















INTERIM REPORT

1. INTRODUCTION
2. STUDY OF URBAN DEVELOPMENT
  - 2-1. DEVELOPMENT POLICY
    - A. Site Planning
    - B. Infrastructure
  - 2-2. SITE PLANNING
    - A. Alternative I
    - B. Alternative II
  - 2-3. INFRASTRUCTURE
3. STUDY OF VARIOUS TYPES OF HOUSES
  - 3-1. STUDY POLICY
    - A. Architectural Planning
    - B. Structural Planning
  - 3-2. FLAT HOUSING STUDY
    - A. Architectural Planning
    - B. Structural Planning
  - 3-3. LOW RISE HOUSING STUDY
    - A. Architectural Planning
    - B. Structural Planning
4. SUMMARY
  - A. Proposal on Alternatives
  - B. Total Cost Estimate

Jan. 18th, 1980

JAPANESE STUDY TEAM ( JICA )

# ATTENDANCE LIST 18TH JANUARY 1980

No	NAME	INSTITUTION	SIGNATURE
1	SUYONO	PERUMNAS	
2	[Faint Name]	[Faint Institution]	[Faint Signature]
3	[Faint Name]	[Faint Institution]	[Faint Signature]
4	IMAN SUNARIO	DKI Jakarta	
5	RAI PRATADJIA	DKI Jakarta	
6	RESITA D SAPUTRO	DKI - JKT	
7	[Faint Name]	[Faint Institution]	[Faint Signature]
8	HERI PURNOMO	PERUMNAS	
9	AZIZ DAHLAN	PERUMNAS	
10	Yuji Ishiyama	I ISEE, BRI. Ministry of Construction	
11	Yasunori YAMAMAKA	Ministry of Construction	
12	Takeo YAMAZAKI	Embassy of Japan	
13	Tadashi SHINOURA	J. I. C. A.	
14	Shinsaku Kanetaki	Cipta Karya Expert	
15	JIRO SUZUKI	JILA TEAM (NIHON ARCHITECTS ENGINEERS) 2 CONSULTANTS INC.	
16	Hajime SADO	..	
17	SHUNROU TAKAHASHI	JILA Team	
18	Hajime Obata	Perumahan Expert	
19	Hajime YOKUBERI	Perumahan Expert	


MINUTES OF THE DISCUSSIONS  
ON THE PHASE I REPORT FOR LOW COST HOUSING PROJECT  
IN CENKARENG JAKARTA ( KTA-20 ).

The Phase I Report was submitted and explained by the Japanese Study Team and discussed by the participants ( see attachment ) at a joint meeting in Jakarta on the 27<sup>th</sup> of March in 1980. The report was principally accepted by both parties , written comments will be sent to Japan by the end of April 1980.

The fundamental items of the further study was recognized ~~as~~ <sup>as</sup> follows : ✕


- 1). The planning area is around 400 Ha which is surrounded by trunk roads and major drainage canal based on the DKI Jakarta Master Plan.  
The supplementary survey will be mainly carried out in this planning area.
- 2). The first stage project area will be fixed in August 1980 on the basis of the results of the land acquisition at that moment.
- 3). The scope of work during the Phase II covers :
  - a. general planning for the planning area.
  - b. detail planning and preliminary engineering for the first stage project area.
  - c. detailed engineering for land development especially drainage system.
  - d. detailed study on the walk up flat and other housing types.
  - e. financial feasibility of the above aspects.
- 4). It was requested by the Indonesian party that the joint Study should be performed more continuously in Indonesia.

Jakarta, March 27, 1980



---

Ir. Suyono, M.Sc.  
Director of Planning  
PERUM PERUMNAS



---

Jiro Suzuki  
Team Leader of Japanese  
Study Team

ATTENDANCE LIST  
27TH MARCH 1980

NO	NAME	INSTITUTION	SIGNATURE
1.	Toshio A I	JICA TOKYO	<i>Toshio Ai</i>
2.	Tadashi SHINOBU	JICA Jakarta	<i>Tadashi</i>
3.	Hajime YKOBORI	Japanese Housing Expert	<i>Hajime</i>
4.	Toshio UETAMA	"	<i>Toshio</i>
5.	Shinsaku KANETAKI	"	<i>Kanetaki</i>
6.	Takeo Yamazaki	Embassy of Japan	<i>Yamazaki</i>
7.	TOSHIO ISHIGURO	Japanese Advisory Committee	<i>Ishiguro</i>
8.	Hajime OBATA	Japan Housing Expert	<i>Hajime Obata</i>
9.	Hajime SABO	Japanese Study Team	<i>Hajime Sabo</i>
10.	<i>Jiro</i>	"	
11.	<i>Suyono</i>	Perumma	<i>Suyono</i>
12.	<i>Donady</i>	"	<i>Donady</i>
13.	<i>Mouvan Affandy</i>	— " —	<i>Mouvan</i>
14.	<i>Emi Kyis</i>	"	<i>Emi</i>
15.	AZIZ DAHLAN	— " —	<i>Aziz Dahlan</i>

4	5	6	7	8	9	10
						11
						12
3	2	1	15	14	13	

MINUTES OF THE DISCUSSIONS  
ON  
THE INCEPTION REPORT  
FOR  
THE LOW COST HOUSING PROJECT IN CENGKARENG (KTA-20)


PHASE II.

The discussions on the Inception Report were held between PERUM PERUMNAS and the Japanese Study Team at PERUM PERUMNAS on 18th and 21st of July in 1980.


The contents of the Inception Report were agreed upon and the following items were recognized by both the Japanese and Indonesia parties :

1. The feasibility study at the First Round will be carried out in the project area which will be acquired in September 1980, covered  $\pm$  110 Ha and is located at Kecamatan Cengkareng, wilayah Jakarta Barat.
2. The study at the Second Round will be carried out at the fixed project area which will be appointed by the Indonesian party by the beginning of October 1980 when the Japanese Study Team is expected to arrive in Indonesia.

Jakarta, July 24, 1980.



Mr. Jiro Suzuki  
Team Leader of  
JICA Low Cost Housing  
Project Study Team



Ir. Suwarno Prawirasumantri  
Director of Planning  
PERUM PERUMNAS



DEPARTEMEN PEKERJAAN UMUM  
PERUM PERUMNAS

Perusahaan Umum Pembangunan Perumahan Nasional  
( National Urban Development Corporation )

Alamat : Jl. Letjen Haryono M.T. Kav. 17 Jakarta

Telpon : 822808 (4 saluran)

Kotak Pos No. 137/K87

Nomor : Dirut/2843/10/VII/80  
Lampiran : 1 (satu) lembar.

Jakarta, 22 Juli 1980

Kepada Yth.

Mr. Hajime Sabo .....

Japanese Study Team .....

di.

J A K A R T A

Perihal : U N D A N G A N

Dengan hormat kami mengundang Bapak/ Sdr untuk menghadiri rapat  
pengarahan Studi Proyek PERUM PERUMNAS Cengkareng Fase II yang  
akan diadakan pada :

Hari : K a m i s  
Tanggal : 24 Juli 1980  
J a m : 12.00 WIB - selesai  
Tempat : Dit. Jen. Cipta Karya.

Atas perhatian dan kesediaannya kami ucapkan terima kasih.

An. Steering Committee  
KTA 20 Cengkareng,



Ir. Soedarjono Danoedjo  
Direktur Utama

Tembusan Yth.

1. Direksi PERUM PERUMNAS
2. A r s i p

-----  
ad/sd.



## DAFTAR UNDANGAN

### STEERING COMMITTEE

1. Ir. Radinal Noohtar - Dir. Jen. Mipta Karya
2. Ir. Suyono, M.Sc. - Direktur Perumahan Rakyat
3. Ir. Susanto - Direktur Direktorat Teknik Penyehatan
4. Ir. Soenarjono Danoedjo - Direktur Utama PERUM PERUMNAS
5. Ir. Suwarno P - Direktur Perencanaan PERUM PERUMNAS
6. Ir. Nursaijidi M.K. - Direktur Pembangunan PERUM PERUMNAS
7. Ir. Herbowo - Ketua BAPPELAD D.K.I.
8. Ir. Imam Sunarjo - Ketua Team Perencanaan Perumahan D.K.I.

### JAPAN EMLASSY & JICA

1. Mr. Takeo Yamazaki - First Secretary, Embassy of Japan
2. Mr. Tadasahi Shinoura - Assistant Resident Representative of JICA

### JAPANESE ADVISORY COMMITTEE

1. Mr. Yuji Ishiyama - Advisor, Japanese Advisory Committee  
KTA 20 Cengkareng Project

### JAPANESE HOUSING EXPERT

1. Mr. Shinsaku Kanetaki - Japanese Housing Expert
2. Mr. Toshio Uetama - Japanese Housing Expert
3. Mr. Hajime Obata - Japanese Housing Expert
4. Mr. Hajime Yokobori - Japanese Housing Expert

### JAPANESE STUDY TEAM

















1. Mr. Jiro Suzuki - Leader, Japanese Study Team  
KTA 20 Cengkareng Project.
2. Mr. Hajime Sabo - Japanese Study Team
3. Mr. Masanori Onoe - Japanese Study Team
4. Mrs. Michiko Inagaki - Japanese Study Team
5. Mr. Shunran Takahashi - Japanese Study Team
6. Mr. Yutaka Saito - Japanese Study Team
7. Mr. Gen Fujiwara - Japanese Study Team
8. Mr. Mikio Tanemura - Japanese Study Team
9. Mr. Motohide Nishio - Japanese Study Team
10. Mr. Takashi Inone - Japanese Study Team

### COUNTERPART


1. Ir. Duddy Soegoto - Kepala Bagian Perencanaan Feasibility  
PERUM PERUMNAS
2. Ir. Aziz Dahlan - Kasubag. Kerjasama Luar Negeri  
PERUM PERUMNAS
3. Ir. Herry Purnomo - Staf Perencanaan Feasibility  
PERUM PERUMNAS
4. Ir. Paryatno Parno - Staf Perencanaan Feasibility  
PERUM PERUMNAS
5. Ir. Rai Pratadaya - Ka. Ur. Pengarahan Perencanaan  
Lingkungan D.K.I.
6. Ir. Ny. Rosita Saputro - Kepala Distrik Perencanaan I  
Wilayah Jawa Barat.

STEERING COMMITTEE  
meeting, 12. , July 24 , 1980

● ATTENDANCE LIST

NO	NAME	POSITION	SIGNATURE
1.	Hajime YOKOBORI.	Directorate Perumahan Japan Housing Expert	
2.	ONOE MASANORI	JICA mission	
3	MICHIKO INAGAKI	JICA study team	
4.	Hajime SABO	"	Hajime Sabo
5.	HITENORI. ONO	JICA HDR	
6	RYONOSUKE GOTO	Assistant Resident Representative, JICA JAKARTA	R. Goto
7	Yuji ISHIYAMA	Japanese Advisory Committee Ministry of Construction	
8	Takeo Yamazaki	First Secretary Embassy of Japan	
9	JIRO SUZUKI	LEADER OF JAPANESE STUDY TEAM	Jiro Suzuki
10	Radinal Mochtar	Dir. Gen. Cepata Karya	
11	Soenanjono	DIRUT PERUMNAS	
12	Suyono	Dir. Perumahan	
13	Susanto	Dir. Teknik Pengolahan	
14	Susarno	Dir. Cau. Perumahan	
15.	NOER SAJJIDI	Dir. BANG. Perumahan	
16.	Duddy Soegoto	Perumahan	
17.	Rai Prataadaja	DKI	
18.	Mawan Affandy.	Perumahan	
19	Iman Surario	DKI	

NO	NAME	POSITION	SIGNATURE
20	Shiusaku Kanetaki	Cipta Karya Expert	S. Kanetaki
21	AZIZ DAHLAN	PERUM PERUMNAS	Aziz Dahlan
22	Paryatno Parno	PERUM PERUMNAS	Paryatno Parno
23	Toshio UETAMA	Perumahan Expert	Toshio Uetama



MINUTES OF THE DISCUSSION  
ON  
THE PROGRESS REPORT  
FOR  
THE LOW COST HOUSING PROJECT IN CENGKARENG (KTA - 20)  
( PHASE 11 )

---

The Progress Report for the project submitted by the Japanese Study Team was discussed by the participants (see attachment) of the steering committee meeting on the 4<sup>th</sup> of November 1980, and the following items were confirmed.


- 1). The General Plan for the planning area ( ± 370 Ha ) and the Master Plan for the project area ( ± 110 Ha ) were approved.
- 2). Alternatives on the major infrastructures which are indispensable for this housing project were evaluated and selected as follow :
  - a). DRAINAGE - Direct discharge system to the Java Sea (ALT 1).
  - b). WATER SUPPLY -60l/dc from PAM-JAYA with setting up the booster pumping station at Grogol (ALT 1A).
  - c). SEWERAGE - Combined system with kitchen and toilet (ALT 3).
- 3). The development cost of the off-site infrastructures is not included into the selling price.
- 4). The target income group is within 20 - 70 of the percentile of the income distribution in 1984.
- 5). The proportion of the empty and commercial lots if necessary can be increased more than 30% of the productive area.
- 6). The low rise housing type (R.15 and D.15) is not recommendable for the lowest income group of the target group.
  
- 7). The high .....

- 7). The high density housing was recommended.  
The distribution of mainsonette, walk up flat and empty lot should be studied further.

Jakarta, 7 November 1980.



MR. JIRO SUZUKI  
Team Leader of JICA  
Low Cost Housing Project  
Study Team



IR. SUWARNO PRAWIRASUMANTRI  
Director of Planning  
PERUM PERUMNAS

HS/sd.

ATTENDANTS OF STEERING COMMITTEE  
ON  
THE DRAFT FINAL REPORT ON THE LOW COST HOUSING PROJECT  
IN CENKARENG, JAKARTA (KTA-20)  
12 MARCH, 1981

1. STEERING COMMITTEE

Ir. Radinal Moochtar	: Dit. Jen. Cipta Karya
Ir. Suyono M Sc	: Direktur Perumahan Rakyat
Ir. Susanto	: Direktur Direktorat Teknik Penyehatan
Ir. Soenarjo Danoejo	: Direktur Utama PERUM PERUMNAS
Ir. Suwarno Prawirasumantri	: Direktur Perencanaan PERUM PERUMNAS
Ir. Nursalidi M.K.	: Direktur Pembangunan PERUM PERUMNAS
Ir. Herbowo	: Ketua BAPPEDA D.K.I.
Ir. Iman Sunaryo	: Ketua Team Perencanaan Perumahan D.K.I.

2. JAPANESE EMBASSY, JICA

Mr. K. Teshima	: First Secretary, Embassy of Japan
Mr. Ryonosuke Goto	: Assistant Resident Representative of JICA

3. JAPANESE ADVISORY COMMITTEE

Mr. Toshio Ishiguro	: Advisor, Japanese Advisory Committee KTA 20 Cengkareng Project
---------------------	---

4. JAPANESE HOUSING EXPERTS

Mr. Shinsaku Kanetaki	: Japanese Housing Expert
Mr. Hajime Obata	: Japanese Housing Expert
Mr. Hajime Yokobori	: Japanese Housing Expert

5. JAPANESE STUDY TEAM

Mr. Jiro Suzuki	: Leader, Japanese Study Team KTA 20 Cengkareng
Mr. Hajime Sabo	: Japanese Study Team
Mrs. Michiko Inagaki	: Japanese Study Team
Mr. Motohide Nishio	: Japanese Study Team

6. COUNTERPARTS

Ir. Duddy Soegoto	: Kepala Bagian Perencanaan Feasibility PERUM PERUMNAS
Ir. Aziz Dahlan	: Kasubag. Kerjasama Luar Negeri PERUM PERUMNAS
Ir. Rai Pratadaya	: Ka Ur. Pengarahan Perencanaan Lingkungan DKI

7. PROYEK BANJIR JAKARTA, DEP. P.U.

Ir. Martsanto Ds	: Pemimpin Proyek Banjir Jaya
------------------	-------------------------------

8. DIT. JEN. BINA MARGA DEP. P.U.

Ir. Wiyoto Wiyono	: Kasubit. Perencanaan Jalan Kota
-------------------	-----------------------------------

9. KTA 7/8 REVIEW MISSION (OBSERVER)

Mr. Makoto Tateishi	: Ministry of Construction, Japan
Mr. Shigetada Utsumi	: Ministry of Construction, Japan
Mr. Shunichi Hokura	: Ministry of Construction, Japan

10. CIPTA KARYA

Ir. Hendro Pranoto	: Dit. Jen. Cipta Karya
--------------------	-------------------------

11. PERUM PERUMNAS

Ir. Didi Suwandhi	: Kepala Kabag Perencanaan Umum PERUM PERUMNAS
Ir. Marwan Affandi	: Kepala Kabag Perencanaan Teknis PERUM PERUMNAS
Ir. Moegijono Bae	: Kepala Kabag Persiapan Pembangunan PERUM PERUMNAS

DAFTAR UNDANGAN

DAFTAR UNDANGAN  
RAPAT BERSAMA STEERING COMMITTEE  
KTA-20 CENGKARENG, 4 NOV 1980.

TANDA TANGAN / SIGNATURE

1. STEERING COMMITTEE

- 1.1 Ir. Radinal Mochtar - Dir. Jen Cipta Karya
- 1.2 Ir. Suyono H Sc - Direktur Perusahaan Rakyat
- 1.3 Ir. Susanto - Direktur Direktorat Teknik Penyehatan
- 1.4 Ir. Soenarjo Danoedjo - Direktur Utama PERUM PERUMNAS
- 1.5 Ir. Suwarno Prawirasumantri - Direktur Perencanaan PERUM PERUMNAS
- 1.6 Ir. Nursajidi M.K. - Direktur Pembangunan PERUM PERUMNAS
- 1.7 Ir. Herbowo - Ketua BAPPEKA D.K.I
- 1.8 Ir. Imam Sunarjo - Ketua Tim Perencanaan Perumahan D.K.I

- 1.1.
- 1.2.
- 1.3.
- 1.4.
- 1.5.
- 1.6.
- 1.7.
- 1.8.

2. JAPAN EMBASSY & JICA

- 2.1 Mr. Tetsu Yamazaki - First Secretary, Embassy of Japan
- 2.2 Mr. Moriya Miyamoto - Resident Representative of JICA
- 2.3 Mr. Ryonosuke Goto, - Assistant Resident Representative of JICA

- 2.1.
- 2.2.
- 2.3.

3. JAPANESE ADVISORY COMMITTEE

- 3.1 Mr. Shunichi Hokura - Advisor, Japanese Advisory Committee  
7/101 KTA 20 Cengkareng Project

- 3.1.

4. JAPANESE HOUSING EXPERTS

- 4.1 Mr. Shinsaku Kanetaki - Japanese Housing Expert
- 4.2 Mr. Toshio Uetana - Japanese Housing Expert
- 4.3 Mr. Hajime Obata - Japanese Housing Expert
- 4.4 Mr. Hajime Yokobori - Japanese Housing Expert

- 4.1.
- 4.2.
- 4.3.
- 4.4.

5. JAPANESE STUDY TEAM

- 5.1 Mr. Jiro Suzuki - Leader, Japanese Study Team  
KTA 20 Cengkareng
- 5.2 Mr. Hajime Sabo - Japanese Study Team
- 5.3 Mr. Michio Inagaki - Japanese Study Team
- 5.4 Mr. Yutaka Saito - Japanese Study Team
- 5.5 Mr. Mikio Tanemura - Japanese Study Team
- 5.6 Mr. Motohide Nishio - Japanese Study Team
- 5.7 Mr. Sunji Yawada - Japanese Study Team

- 5.1.
- 5.2.
- 5.3.
- 5.4.
- 5.5.
- 5.6.
- 5.7.

6. COUNTERPARTS

- 6.1 Ir. Duddy Soegoto - Kepala Bagian Perencanaan Feasibility  
PERUM PERUMNAS
- 6.2 Ir. Aziz Dahlan - Kasubag Kerjasama Luar Negeri PERUM PERUMNAS
- 6.3 Ir. Paryatno Parno - Kasubag Pengukuran & Pemetaan  
PERUM PERUMNAS
- 6.4 Ir. Herby Purmono - Staf Perenc Feasibility PERUM PERUMNAS
- 6.5 Ir. Rai Pradadaya - Ka Ur Pengarahan Perencanaan Lingkungan DAI
- 6.6 Ir. Ny. Rosita Saputro - Kepala Distrik Perencanaan I  
Wilayah Jakarta Barat

- 6.1.
- 6.2.
- 6.3.
- 6.4.
- 6.5.
- 6.6.

7. PROYEK BANJIR JAKARTA, DEP. P. U

- 7.1 Ir. Achmad Lanti Dipl H.E - Kepala Staf Proyek Banjir Jaya

- 7.1.

8. DITJEN BINA MARGA DEP. P. U

- 8.1 Ir. Wiyoto Wiyono - Kasubdit. Perencanaan Jalan Kota

- 8.1.

9. PERUSAHAAN AIR MINUM. PFMDA D. K. I

- 9.1 Ir. Budi Rahardjo - Direktur PAM D.K.I

- 9.1.

33/5d


MINUTES OF DISCUSSION  
ON  
THE DRAFT FINAL REPORT ON THE LOW COST HOUSING PROJECT  
IN CENKARENG, JAKARTA (KTA-20)

1. The draft final report was submitted and explained by the Japanese Study Team, and discussed by the participants (see Attach) of the Steering Committee Meeting in Jakarta on the 12th of March, 1981.
2. The report was discussed by the Steering Committee, and the Steering Committee agrees that the draft final report be processed and printed as final report.

Note : the following expressions were made by the Steering Committee :


- a) PERUM PERUMNAS and the Local Government will continue the land acquisition process and it should be finished at latest in December 1981.
- b) In parallel with the land acquisition, PERUM PERUMNAS is going to proceed the review of the feasibility study then to start the detailed design in the fiscal year of 1981/1982.
- c) In relation with the above mentioned process, a request for Japanese loan including the detailed design will be submitted.

Signed at Jakarta, March 12, 1981.



---

Ir. Radinal Mochtar  
Director General  
of  
CIPTA KARYA



---

Jiro Suzuki  
Team Leader  
of  
JAPANESE STUDY TEAM



## BIBLIOGRAPHY

I: Indonesian E: English J: Japanese

SOCIO-ECONOMIC, STATISTICAL AND GENERAL DATA

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
LAPORAN HASIL LATIHAN PENELITIAN PESERTA STUDI PEMBANGUNAN INDONESIA ANGKATAN KE III MASALHA-MASALHA PERKOTAAN DI KOTA MADYA CIREBON	第3次インドネシア建設スタディー調査・西部ジャワラレゴン市に関する市状分析と提案-1978	STUDI PEMBANGUNAN INDONESIA FAKULTAS ILMU-ILMU SOSIAL-UT INDONESIA	I
EVALUASI PLANOLOGI SOSIAL DARI PERMAHAN BARU DI DEPOK INDONESIA	デポック住宅地建設に係る社会的地位の評価	LEMBAGA PLANOLOGI DAN DEMOGRAFI UNIVERSITAS AMSTERDAM	I
RENCANA PEMBANGUNAN LIMA TAHUN KETIGA 1979/80 ~ 1983/84	第3次5ヶ年建設計画	PEMERINTAH DAERAH KHUSUS IBUKOTA JAKARTA	I
STATISTICAL YEAR BOOK OF JAKARTA 1977	ジャカルタ市統計年報 1977	CENSUS & STATISTICAL OFFICE JAKARTA	I-E
PROPOSAL FOR A 10,000 UNIT LOW-COST HOUSING DEVELOPMENT	万戸低所得者用住宅開発計画プロザール	PLANNED COMMUNITY DEVELOPMENT CO., LTD. USA	E
STATISTICAL YEAR BOOK OF INDONESIA 1977 ~ 1978	インドネシア統計年報 1977~78	CENTRAL BUREAU OF STATISTICS	I-E
MAIN TABLES OF THE NATIONAL INCOME OF INDONESIA 1973 ~ 1978	国民所得表 1973~78	"	E
SUMMARY OF INDONESIAN POPULATION BY PROVINCE AND ISLAND 1976	プロビンス別・島別インドネシア人口統計	"	E
LABOR FORCE SITUATION IN INDONESIA 1977	インドネシア労働力統計 1977	"	I-E
SOCIAL INDICATOR 1978	社会指標	"	E
STATISTICAL YEAR BOOK OF JAKARTA 1979	ジャカルタ市統計年報 1979	CENSUS & STATISTICAL OFFICE JAKARTA	I-E
REGIONAL INCOME OF JAKARTA 1975 ~ 1978	ジャカルタ区収入統計	"	I-E
LAPORAN HASIL PROYEK PERINTISAN PELAYANAN KESEJAHTERAAN HASYARAKAT TERPADLI DI DAERAH PENUKIMAN BARU DEPOK BUKU 1	デポック新住宅団地の社会報告	KEJIASANA ANTARA PERSAHAAN UMUM PEMBANGUNAN PERUMAHAN NASIONAL DENGAN FAKULTASI ILMU <sup>2</sup> SOSIAL UNIVERSITAS INDONESIA 1979	I
PENELITIAN KEAPAAN SOCIAL EKONOMI DAN TANGGAAPAN MASYARAKAT PERKAMPUNGAN TERHADAP PROJEK MUHAMMAD HUSNI THAMRIN DKI JAKARTA TAHUN 1973/74	ムハムド・クス・サムリンプロジェクト社会経済調査	PEMERINTAH DAERAH KHUSUS IBKOTA JAKARTA	I
PENELITIAN KEAPAAN SOCIAL EKONOMI MASYARAKAT PADA KAMPUNG <sup>2</sup> YANG AKAN MENDAPAT PERBAIKAN DALAM RANGKA PROJEK MUHAMMAD HUSNI THAMRIN DKI JAKARTA TAHUN 1975/76	ムハムド・クス・サムリンプロジェクト調査 - 村の復興と社会・経済状況 -	"	I
HOUSING WORLD BANK SECTOR POLICY PAPER	ハウジング 世銀白書-	WORLD BANK	E
LAND REFORM " "	ラントリフォーム-世銀白書-	"	E
WORLD DEVELOPMENT INDICATORS 1979	世界開発指標-世銀-	WORLD BANK	E
NATIONAL SOCIO-ECONOMIC SURVEY 1976	インドネシア国民家計統計	CENTRAL BUREAU OF STATISTICS	I-E

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
INDONESIAN PRICE INDEX	物価動向	JETRO	J
HOUSEHOLD AND COTTAGE INDUSTRIES IV	家計と家内工業 VOL IV	CENTRAL BUREAU OF STATISTICS	I・E
"	" VOL V	"	I・E
V			
AVERAGE WAGES OF ESTATE WORKERS 1976 ~ 1979	農業労働者賃金統計 1976-79	"	I・E
STATISTIK WILAYAH DKI JAKARTA 1979	ジャカルタ地域統計	KANTOR SENSUS DAN STATISTIK DKI JAKARTA	I
BULLETIN OF INDONESIAN ECONOMIC STUDIES	インドネシア経済スタディ-期報	AUSTRALIAN NATIONAL UNIV.	E
PROGRAM PELITA III	PELITA III に対する建設計画	PERUMNAS PROGRAMMING DIVISION	I
IMPOR: MANURUT JENIS BARANG DAN NEGERI ASAL 1978	輸入物産統計 1978	BIRO PUSAT STATITIKS	I
TABEL-TABEL POKOK PENDARATAN NASIONAL INDONESIA	"	"	I
RINGKASAN PENDUK INDONESIA	"	"	I
KEADAAN ANGKATAN KERJA DI INDONESIA	"	"	I
EXPOR: MANURUT JENIS BARANG DAN NEGERI ASAL 1978	輸出物産統計 1978	MINISTRY OF INDUSTRY	I
"	" 1979	"	I
1979			
ATLAS INDONESIA	インドネシア地図	-	E
<u>CITY PLANNING AND COMMUNITY PLANNING</u>			
DASAR-DASAR PERENCANAAN LINGKUNGAN	コミュニティ設計基準	BUILDING INFORMATION CENTRE	I
PEDOMAN PERENCANAAN LINGKUNGAN PEMUKIMAN KOTA	都市地域計画基準	CIPTA KARYA	I
JAKARTA PLANNING ATLAS 1975	ジャカルタ計画アトラス	DINAS DATA KOTA	I
JABOTABEK METROPOLITAN DEVELOPMENT PLANNING	首都圏開発計画		E
PROGRAM PENDANAAN KOMPONEN LOKAL JALAN TOL	インドネシア道路建設投資計画書 -LOKAL	BINA MARGA	I
PROGRAM PENDANAAN KOMPONEN ASING JALAN TOL	" -ASING	"	I
BINA PROGRAM JALAN	ジャカルタ道路計画団	"	I
JAKARTA KAMPUNG IMPROVEMENT PROGRAMME	ジャカルタ I P / ノレット	DKI JAKARTA	E
PETUNJUK MEMBANGUN DIWILAYAH DAERAH KHUSUS IBUKOTA JAKARTA	地区計画指針	"	I

TYTLE(題名)	TYTLE IN JAPANESE(和文)	AUTHOR OR PUBLISHER(著者または発行所)	
<u>HOUSING PROJECT REPORT</u>			
FINAL REPORT VOL. 4, SITES & SERVICES AND LOW COST HOUSING AT TANDES IN SURABAYA APR. '78	スラバヤS&SとLCH開発計画報告書	PERUM PERUMNAS	E
PROPOSAL FOR A SITES & SERVICES PROJECT IN CIREBON, INDONESIA DEC. '74	チレボンのS&SとLCH開発計画報告書	"	E
DRAFT REPORT - SITES & SERVICES/ LOW COST HOUSING PROJECT ANNEXES MAR. '76	"	"	E
IMPLEMENTATION REPORT P.I.U. NOV./DEC. '77	"	"	E
FINAL REPORT LOW COST HOUSING IN BEKASI II (SUMMARY)	カンII LCH開発計画報告書	"	I
" (TECHNICAL)	"	"	I
APPRAISAL OF THE JAKARTA URBAN DEVELOPMENT PROJECT IN INDONESIA AUG. '74	クレンタ-アブソイタルレポート	IBRD	E
REQUEST FOR FUNDING TO THE IBRD, A SITE & SERVICE PROGRAM JAKARTA METROPOLITAN AREA	クレンタ デイックチュノカレンのフイーンビリティア・スタディ・レポート	PPU	E
FINAL REPORT SITES & SERVICES BANYUMANIK, SEMARANG VOL. 1 & 3	スマランのフイーンビリティア・スタディ・レポート	PERUM PERUMNAS	E
INTERIM REPORT SITES & SERVICES SEMARANG, SULAKARTA VOL. 1	"	"	E
INTERIM REPORT SITES & SERVICES SEMARANG, SULAKARTA VOL. 2	"	"	E
DETAILED DESIGN REPORT SITES & SERVICES SEMARANG, SULAKARTA VOL. 3	スマランの詳細設計レポート	"	E
FINAL REPORT SITES & SERVICES SEMARANG, SULAKARTA	スマランのフイーンビリティア・スタディ・レポート	"	E
BANDUNG URBAN DEVELOPMENT AND SANITATION PROJECT-BACK GROUND PAPER VOL. 1, 2, 3	バンドンのフイーンビリティア・スタディ・レポート	CIPTA KARYA	E
REPORT TANAH ABANG	タナアブの中層開発レポート	PERUM PERUMNAS	I
<u>ARCHITECTURAL, STRUCTURAL AND MATERIAL DATA</u>			
PERATURAN SEMEN PORTLAND INDONESIA 1972 N.I-8	ポルトランドセメント基準	BUILDING INFORMATION CENTRE	I
MANUAL BANGUNAN TAHAN GEMPA	建設法規マニアル	"	I
KAYU SEBAGAI BAHAN BANGUNAN	木材ガイダンス	"	I
A BRIEF OUTLINE OF SEISMICITY AND EARTHQUAKE	耐震設計の手引	"	E
DEVELOPMENT OF A STEAM-CURED BUILDING MATERIAL ON THE BASIS OF LATERTIC SOIL & LIME	カクハクキハースに於ける建材の開発	DIRECTORATE OF BUILDING RESEARCH	E
PERATURAN BETON BERTULANG INDONESIA N.I-2	RCコンクリート基準	CIPTA KARYA	

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
ULTIMATE STRENGTH ANALYSIS OF RC-SECTION	RC終局強度計算法手引	BUILDING RESEARCH INSTITUTE	E
PERHITUNGAN LENTUR	RCコンクリート計算基準	CIPTA KARYA	I
KEAMANAN KONSTRUKSI DALAM PERHITUNGAN BETON	コンクリート安全要領	"	I
REPORT BANDUNG	バンドンセミナーレポート	BANDUNG INSTITUTE OF TECHNOLOGY	E
REINFORCED CONCRETE DESIGNER'S HANDBOOK	RCコンクリートデザイナーハンドブック	VIEWPOINT PUBLICATION	E
PERATURAN BANGUNAN NASIONAL	国家建築規則	CIPTA KARYA	I
RERATURAN KONSTRUKSI KAYU INDONESIA	木構造基準	"	I
	インドネシア国家建築施工規則 (1-25の和訳)	JAPAN-INDONESIAN ASSOCIATION	J
BATA MERAH SEBAGAI BAHAN BANGUNAN	レンガ造基準	CIPTA KARYA	I
PERATURAN UMUM UNTUK BAHAN BANGUNAN DI INDONESIA	建材 般基準	"	I
PEMBANGUNAN PERUMAH BERTINGKAT EMPAT VOL. 1, 2, 3	Perumnas の新築ビル設計図	PERUM PERUMNAS	I
TECHNICAL REPORT NO. 22	コンクリート関連技術レポート	"	I
MAISONETTE 80	イネット住宅資料	BANDUNG TECHNICAL INSTITUTE	I
COMPETITION "FLAT INDONESIAN"	中層コンへ入選作=プレキャスト方式案=	PERUM PERUMNAS	I
" "FLAT MEXICAN"	" "メキシコ方式案=	"	I
" "FLAT BRECAST"	" "	"	I
PEDOMAN TEKNIK PERENCANAAN PERUMAHAN FLAT DAN MAISONETE	プレキャスト方式案=中層メネット住宅技術ガイダンス	CIPTA KARYA	I
EVALUASI KERJA SUB-INTI	サブコア住宅のココアレーション	PERUM	I
PEDOMAN PERENCANAAN LINGKUNGAN PEMUKIMAN KOTA	ジャカルタ市建築環境基準例	DKI JAKARTA	I
<u>SEWERAGE, WATER SUPPLY AND POWER SUPPLY</u>			
USAHA MEMANFAATKAN AIR HUJAN UNTUK AIR MINUM	雨水と飲料水手引	BUILDING INFORMATION CENTER	I
MANUAL OF STANDARD & CRITERIA FOR PLANNING WATER RESOURCE PROJECT	水資源プロジェクトマニュアル	"	E
RENCANA SEPTIK TANK	セプティックタンク手引	"	I
KAKUS SEDERHANA	トイレ処理手引	"	I
MASTER PLAN FOR JAKARTA WATER SUPPLY SYSTEM	ジャカルタ給水システムマスタープラン	NIHON SUIDO CONSULTANT	E
PENJELASAN SINGKAT PENAUGGULANGAN MASLAH BANJIR'DI DKI JAKARTA	ジャカルタ洪水防止策の説明	DIREKTORAT JENDERAL PENGAIRAN	I
JAKARTA DRAINAGE AND FLOOD CONTROL PROJECT PHASE II	ジャカルタ排水及び洪水プロジェクト	NEDECO	E

TYTLE(題名)	TYTLE IN JAPANESE(和文)	AUTHOR OR PUBLISHER(著者または発行所)	
FINAL REPORT PHASE II JAKARTA DRAINAGE AND FLOOD CONTROL PROJECT	ジャカルタ排水及び対洪水プロジェクト	NEDECO	E
CISADANE-JAKARTA-CIBEET WATER RESOURCES DEVELOPMENT PLAN	チサダインジャカルタチベト水資源開発計画	CIPTA KARYA	E
NUCLEAR APPLICATIONS IN FLOOD CONTROL RESEARCH OVER JAKARTA	洪水制御への放射線の利用	BADAN TENAGA ATOM NASIONAL	E
PERATURAN INSTALASI LISTRIK SYRAT-SYRAT PENYAMBUNGAN LISTRIK	電気設備基準	PERUM PERUMNAS	I
CISADANE-JAKARTA-CIBEET WATER RESOURCES DEVELOPMENT PLAN ANNEX D	CJC水資源計画	CIPTA KARYA	I
JAKARTA SEWERAGE AND SANITATION PROJECT SEP. '77	Jakarta排水衛生プロジェクト	CIPTA KARYA	E
PEDOMAN PLAMING INDONESIA MAR. '74	給排水基準	DIRECTORAT TEKNIK PENYEHATAN	I
OPEN CHANEL HYDRAULICS	開溝の管理	VET TE CHOW, MCGRAW-HILL, KOGAKUSHA	E
SEWAGE TREATMENT IN HOT CLIMATE	熱帯地での汚水処理	DUNCAN MARA, WILEY CO.	E
JAKARTA DRAINAGE FLOOD CONTROL REPORT (FIRST PROGRESS)	ジャカルタ排水調整プロジェクト	PBJR (NEDECO)	E
" (THIRD PROGRESS)	"	"	E
DAILY RAINFALL DATA SHEET IN CENGKARENG	日降雨量観測簿	JAKARTA OBSERVATORY	I
<u>COST AND CONSTRUCTION DATA</u>			
DAFTAR HARGA SATUAN BAHAN BANGUNAN DI JAKARTA AUG. '79	ジャカルタ建材コスト資料 Aug 1979	BUILDING INFORMATION CENTER	I
DAFTAR HARGA SATUAN BAHAN BANGUNAN DI JAKARTA	ジャカルタ建材コスト資料 OCT '79	"	I
DAFTAR HARGA SATUAN BAHAN BANGUNAN DI JAKARTA JUN. '80	ジャカルタ建材コスト	"	I
DAFTAR HARGA SATUAN PEKERJAAN (UNIT PRICE) DI INDONESIA IV/1979	インドネシア標準建設コスト資料	"	I
A GUIDANCE TO THE INDONESIAN TAXATION	TAX 税法	GUNUNG AGUNG	E
PAKET 20 APRIL 1979	"	"	I
PENETAPAN HASIL PREKUALIFIKASI PEMBORONG PERUM PERUMNAS UNTUK TAHUN ANGGARAN '78/'79, '79/'80	業者免許申請書	PERUM PERUMNAS	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN GEDUNG KANTOR PUSAT PERUM PERUMNAS	プラムナス本社ビル工事契約書	"	I
S&S IN KLENDER BILL OF QUANTITIES AND SPECIFICATIONS	クレンダ-S&Sプロジェクト仕様書	"	I
PELAKSANAAN PEKERJAAN LAND CLEARING DI LOKASI PROJEK PERUM PERUMNAS MEDAN II	メカンII宅地工事契約書	"	I

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
PELAKSANAAN PEKERJAAN PEMBUATAN SALAN ROW 10, 6, SALURAN, DUIKER DAN BAK KONTROL DI LOKASI PROJEK PERUM PERUMNAS MEDAN II	メダンⅡ道路フットパス工事契約書	PERUM PERUMNAS	I
PELAKSANAAN PEKERJAAN PEMBUATAN SEBUAH MENARA AIR DARI BETON DI LOKASI PROYEK BEKASI	ヘカシ給水タワー契約書	"	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN 500 UNIT RUMAH TYPE D-21 DI LOKASI DEPOK II	デポックⅡD-21タイプ住戸工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBUATAN JALAN SETAPAK DAN SALURAN LINGKUNGAN 400 UNIT RUMAH TYPE D-21 PADA SITE TIMUR BAGIAN UTARA DI LOKASI DEPOK II	デポックⅡ道路排水、宅造工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN 640 UNIT/10 TWIN BLOCK RUMAH FLAT SYSTEM BRECAST TYPE-36 DI LOKASI BANDUNG DAN SEKITARNYA	バンドンD-36タイプ中層プレキャスト住宅工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBUATAN JALAN KERJA DI LOKASI BEKASI II	ベカシⅡ改設道路工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN 400 UNIT RUMAH TYPE D-33 DI LOKASI TANGERANG	タンクランプロジェクトD-33タイプ住戸工事契約書	"	I
SURAT PERJANJIAN KERJA SAMA PELAKSANAAN PEKERJAAN PENYAMBUNGAN TENAGA LISTRIK UNTUK 174 UNIT RUMAH DI LOKASI CIREBON	チレボン174ユニット住宅の電気施設工事契約書	"	I
BIAYA PELAKSANAAN PEMBANGUNAN PEKERJAAN JALAN KONSTRUKSI BAJA	BINA MARGAの道路・堤防建設コスト追加費	BINA MARGA	I
PELAKSANAAN PEKERJAAN PEMBUATAN LAND-DEVELOPMENT DI LOKASI, KLENDER	クレンダープロジェクト宅造工事契約書	PERUM PERUMNAS	I
GEDUNG KANTOR PUSAT PERUM PERUMNAS VOL. 1, 2	ブルムナス本社ビル仕様・増築費料	"	I
PELAKSANAAN PEKERJAAN PEMBUATAN JALAN BARU PRIMER DAN TERTIER DI LOKASI PROJEK CIREBON	チレボン幹線道路工事契約書	"	I
PELAKSANAAN PEKERJAAN LAND DEVELOPMENT (PEKERJAAN JALAN, KANALAIR, AIR MINUM) DI LOKASI PROJEK CIREBON	チレボン宅造工事契約書	"	I
INFORMASI POTENSI INDUSTRI	工場生産能力データ	ASSOCIATION OF MATERIAL OF INDONESIA	I
PELAKSANAAN PEKERJAAN UP GRADING KALI DAN PINTU PENGENDALI BANJIR PADA KALI CIKALONG DI LOKASI PROJEK CIREBON	チレボン治水工事契約書	PERUM PERUMNAS	I
PELAKSANAAN PEKERJAAN PEMBUATAN INSPEKTION DAN PENGATUR DAN TUTUP-TUTUP BESI BAR METER AIR PIT SERTA PER-BAIKAN SALURAN AIR KOTOR DI LOKASI PROJEK CIREBON	チレボン排水・飲料水工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMASANGAN PIPA AIR KOTOR DAN AIR MINUM FOOT PATH BERIKUT GUTTERNYA DI LOKASI PROJEK CIREBON	チレボン給・排水、道路工事契約書	"	I

TYTLE (題名)	TYPE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
<u>Others</u>			
GEOLOGICAL MAP (JAKARTA)	ジャカルタ地質図	DIRECTORAT GEOLOGI	I.E
SOIL INVESTIGATION DATA SHEET	土質データ	PBJR	I
BERTANAN POHON BUAH-BUAHAN 2	果樹の植樹について	GNUNG AGUN	I
TANAMAN HIAS	インドネシアの庭木	"	I
TUMBUHAN LIAR	インドネシアの草花	"	I
TANAMAN PERINPUNG	インドネシアの樹木	"	I







JICA