

1-8

### 1-8 COST DATA FOR LOW-RISE HOUSES

		D-15		( 2 Unit/Building)		FLOOR AREA	NET 18.00 M <sup>2</sup>	GROSS 18.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	2	Unit	0.90	1.80	11.55	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp. water	2	Unit	1.20	2.40			
	Grading	-	-	-	-			
	Setting & staking out	42.00	M	0.175	7.35			
	Scaffolding		Unit	4.50, 9.00				
Earth Work	Insectisidation	-	M	1.26				
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96		448.93	-incl. horizontal RC-brace	
		F <sub>2</sub>	M	3.33				
		F <sub>3</sub>	M	3.07				
		F <sub>4</sub>	38.60	M	2.69			103.83
	1F. Floor	Slab on grade	36.00	M <sup>2</sup>	1.79			64.44
		Soil floor		M <sup>2</sup>	0.31			
	Ridge stone	F <sub>1</sub>		M	0.72			
		F <sub>2</sub>	8.70	M	0.47			4.09
	Concrete block	HB-15		M <sup>2</sup>	2.99			
		HB-10	71.69	M <sup>2</sup>	2.27			162.74
		Finish plaster		M <sup>2</sup>	0.92			
		WC/M floor mortar	26.01	M <sup>2</sup>	1.34			34.85
	RC-Course	C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>		M	2.38			
		C <sub>4</sub>		M	3.37			
		C <sub>5</sub>		M	3.77			
	Wall reinforcement		30.79	M	2.03			62.50
		A-1	11.60	M	0.41			4.76
		A-2	5.80	M	1.16			6.73
	2F. Floor	A-3	5.80	M	0.86			4.99
		RC floor S <sub>1</sub>		M <sup>2</sup>	13.16			
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76			
	Wood Work	Wood floor		M <sup>2</sup>	7.02			
Upper wall etc.		Head plate	24.00	M	0.41	9.84		
		Upper unit wall	6.00	M <sup>2</sup>	5.76	34.56		
		Other upper wall	12.00	M <sup>2</sup>	2.40	28.80		
		Upper staircase		Set				
Handrail		Upper WC/M	2	Set	2.70	5.40		
		Wooden rail		Unit				
Staircase (Wooden)		Pipe rail		Unit	10.76			
				Unit				
78.60								
Ceiling Work	Ceiling Asbestos		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>	
Door & Window Work	J <sub>1B</sub>	2	Pc	12.00	24.00	89.82	-per horizontal M <sup>2</sup> (incl. laves) L = 1.55M	
	J <sub>B</sub>	2	Pc	18.83	37.66			
	J <sub>B</sub>	2	Pc	11.58	23.16			
	Lock + Hook	2×0	Pc	2.50+0.20	5.00			
Roof Work	Rafter + Batten + Tile	33.60	M <sup>2</sup>	5.82	195.55			
	Canopy		Set					
	Ridge tile	4	M	1.04	4.16			
	Ridge column	2	Pc	1×1.44+1.79	8.04			
	Ridge board	4	M	1.52	6.08			
	Brace	2	Pc	4.00	8.00			
	Eaves fascia	29.20	M	0.35	10.22			
	Valley gutter	4	M	2.40	9.60			
	Down pipe	4	M	1.80	7.20			
	Water-tightening	25.6	M	1.85	47.24			
	Collar		Pc					
	291.09							
Plumbing Work	Water tub	2	Unit	5.50	11.00	114.88	-See. electricity cost	
	Closet	2	Unit	7.00	14.00			
	Cleanout, Trap	4	Pc	3.00	12.00			
	Waste pipe	12.00	M	3.60	43.20			
	Water pipe	14.00	M	0.62	8.68			
	Water head	4	Pc	1.50	6.00			
	Kitchen sink	2	Unit	7.00	14.00			
	Connection pit	2	Unit	3.00	6.00			
Electrical Work	Fixture etc.	2	Unit	42.00	84.00			
Power intake		Unit						
84.00								
Outside Work	Step plate + gutter plate	12×2	Pc	0.30+0.90	5.40			
Painting	Fence		M	1.61		5.40	-incl. foundation -incl. each item	
Other Work	Painting		M <sup>2</sup>					
	Guard	2	Unit	1.20	2.40			
	Cleaning	2	Unit	0.46	0.92			
	ALAP Keselamatan Kerja	2	Unit	0.60	1.20	4.52		
Total	1,128.79 Rp/Building × 1.1 ( 2 ) Unit = 620.83 ×10 <sup>3</sup> Rp/unit ; 18.0 M <sup>2</sup> = 34.49 ×10 <sup>3</sup> Rp/M <sup>2</sup>							

		D-21		( 2 Unit/Building)		FLOOR AREA	NET 24.00 M <sup>2</sup>	
						GROSS 24.00 M <sup>2</sup>		
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	2	Unit	0.90	1.80			
	Temp. water Crading	2	Unit	1.20	2.40			
	Setting & staking out	-	-	-	-			
	Scaffolding	54	M	0.175	9.45			
Earth Work	Insectisidation	-	Unit	4.50, 9.00	-	13.65	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Foundation							
Masonry & Concrete Work	F <sub>1</sub>		M	5.96				
	F <sub>2</sub>		M	3.33				
	F <sub>3</sub>		M	3.07				
	F <sub>4</sub>	50.60	M	2.69	136.83			
	1F. Floor	60.00	M <sup>2</sup>	1.79	107.40			
	Ridge stone	F <sub>5</sub>		M	0.72			
		F <sub>6</sub>	14.00	M	0.47	6.58		
	Concrete block	HB-15		M <sup>2</sup>	2.99			
		HB-10	91.94	M <sup>2</sup>	2.27	208.70		
		Finish plaster WC/M floor mortar	26.01	M <sup>2</sup>	1.34	34.85		
	RC-Course	C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>		M	2.38			
		C <sub>4</sub>		M	3.37			
		C <sub>5</sub>		M	3.77			
	Wall reinforcement	A-1	34.80	M	0.41	14.27		
		A-2	-	M	1.16			
		A-3	14.50	M	0.86	12.47		
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16		621.75	
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76			
Wood Work	Wood floor		M <sup>2</sup>	7.02				
	Head plate	30.00	M	0.41	12.30			
	Upper unit wall	10.38	M <sup>2</sup>	5.76	59.79		-incl. bolts + nuts	
	Other upper wall	10.38	M <sup>2</sup>	2.40	24.91			
	Upper staircase		Set					
	Upper WC/M		Set		5.40			
	Wooden rail		Unit					
	Pipe rail		Unit	10.76				
	Staircase (Wooden)		Unit			102.40		
	Ceiling Work	Ceiling Asbestos		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>
Door & Window Work	J <sub>1</sub>	4	Pc	12.00	48.00			
	J <sub>2</sub>	4	Pc	18.83	75.32			
	J <sub>3</sub>	2	Pc	11.58	23.16			
Roof Work	Lock + Hook	2×2	Pc	2.50×0.20	5.40	151.88		
	Rafter + Batten + Tile	49.20	M <sup>2</sup>	5.82	286.34		-per horizontal M <sup>2</sup> (incl. laves) L = 1.55M	
	Canopy		Set					
	Ridge tile	6.00	M	1.04	6.24			
	Ridge column	2	Pc	4.01, 4.79	8.04			
	Ridge board	6.00	M	1.52	9.12			
	Brace	2	Pc	4.00	8.00			
	Eaves fascia	33.20	M	0.35	11.62			
	Valley gutter	4.00	M	2.40	9.60			
	Down pipe	4.00	M	1.80	7.20			
	Water-tightening	27.20	M	1.65	44.88			
	Collar		Pc			391.04		
Plumbing Work	Water tub	2	Unit	5.50	11.00			
	Closet	2	Unit	7.00	14.00			
	Cleanout, Trap	4	Pc	3.00	12.00			
	Waste pipe	12.00	M	3.60	43.20			
	Water pipe	14.00	M	0.62	8.68			
	Water head	4	Pc	1.50	6.00			
	Kitchen sink	2	Unit	7.00	14.00			
	Connection pit	2	Unit	3.00	6.00	114.88		
Electrical Work	Fixture etc.	2	Unit	42.00	84.00			
	Power intake	-	Unit	-	-	84.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	12×2	Pc	0.30×0.90	5.40	5.40	-incl. foundation -incl. each item	
	Fence		M	1.61				
Painting	Painting		M <sup>2</sup>					
	Guard	2	Unit	1.20	2.40			
Other Work	Cleaning	2	Unit	0.46	0.92			
	ALAP Keselamatan Karja	2	Unit	0.60	1.20	4.52		
Total		1,489.52 Rp/Building × 1.1 + ( 2 ) Unit =		819.24	×10 <sup>3</sup> Rp/Unit + 24 M <sup>2</sup> =	34.14	×10 <sup>3</sup> Rp/M <sup>2</sup>	

D-35		( 2 Unit/Building)		FLOOR AREA	NET 36.00 M <sup>2</sup>	GROSS 36.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-Total ×10 <sup>3</sup> Rp	Note
Temporary Work	Warehouse	2	Unit	0.90	1.80	16.45	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work
	Temp. water	2	Unit	1.20	2.40		
	Grading	-	-	-	-		
	Setting & staking out Scaffolding	70.00	M	0.175	12.25		
Earth Work	Insectisidation		M	1.26			
	Foundation	F <sub>1</sub>		M	5.96		
F <sub>2</sub>			M	3.33			
F <sub>3</sub>			M	3.07			
F <sub>4</sub>		70.00	M	2.60	182.00		
1F. Floor	Slab on grade	77.70	M <sup>2</sup>	1.79	139.08		
	Soil floor		M <sup>2</sup>	0.11			
Ridge stone	F <sub>1</sub>		M	0.72			
	F <sub>2</sub>	15.60	M	0.47	7.33		
	HB-15		M <sup>2</sup>	2.99			
	HB-10	127.20	M <sup>2</sup>	2.27	288.74		
Concrete block	Finish plaster		M <sup>2</sup>	0.92			
	WC/M floor mortar	20.50	M <sup>2</sup>	1.34	27.47		
RC-Course	C <sub>1</sub>		M	3.81			
	C <sub>2</sub>		M	2.92			
	C <sub>3</sub>		M	2.38			
	C <sub>4</sub>		M	3.37			
	C <sub>5</sub>		M	3.77			
	C <sub>6</sub>	97.15	M	2.03	197.21		-incl. horizontal RC-brace
Wall reinforcement	A-1	52.87	M	0.41	21.68		
	A-2	24.00	M	1.16	27.84		
	A-3	16.80	M	0.86	14.45		
2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16			
	RC floor S <sub>2</sub>		M	11.76			
Wood Work	Wood floor		M <sup>2</sup>	7.02			
	Head plate	56.00	M	0.41	22.96		
	Upper unit wall	5.19	M <sup>2</sup>	5.76	29.89		
	Other upper wall	26.48	M <sup>2</sup>	2.40	63.55		-incl. bolts + nuts
	Upper staircase		Set				
	Upper WC/M		Set				
	Wooden rail		Unit				
	Pipe rail (Wooden)		Unit	10.76			
Staircase		Unit			116.40		
Ceiling Work	Ceiling Asbestos		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>
Door & Window Work	J <sub>11</sub>	8	Pc	18.01	144.08		
	J <sub>21</sub>	6	Pc	10.29	61.74		
	J <sub>3</sub>	2	Pc	11.58	23.16		
	Lock + Hook	2+2	Pc	2.50+0.20	5.40	234.38	
Roof Work	Rafter + Batten + Tile	93.60	M <sup>2</sup>	5.82	544.75		-per horizontal M <sup>2</sup> (incl. laves)
	Canopy		Set				L = 1.6M
	Ridge tile	12.00	M	1.04	12.48		
	Ridge column	5	Pc	4.14+1.79	20.47		
	Ridge board	12.00	M	1.52	18.24		
	Brace	5	Pc	4.00	20.00		
	Eaves fascia	42.40	M	0.35	14.84		
	Valley gutter		M	3.90			
	Down pipe		M	1.80			
	Water-tightening	30.40	M	1.65	50.16		
	Collar		Pc			680.94	
	Plumbing Work	Water tub	2	Unit	5.50	11.00	
Closet		2	Unit	7.00	14.00		
Cleanout, Trap		4	Pc	3.00	12.00		
Waste pipe		39.00	M	3.60	140.40		
Water pipe		17.00	M	0.62	10.52		
Water head		4	Pc	1.50	6.00		
Kitchen sink		2	Unit	7.00	14.00		
Connection pit		2	Unit	3.00	6.00	211.92	
Electrical Work	Fixture etc.	2	Unit	42.00	84.00		
	Power intake	-	Unit	-	-	84.00	-See. electricity cost
Outside	Step plate + gutter plate	4+2	Pc	0.30+0.90	3.00		
Painting	Fence		M	1.01		3.00	-incl. foundation
	Painting		M				-incl. each liter
Other Work	Guard	2	Unit	1.20	2.40		
	Cleaning	2	Unit	0.46	0.92		
	ALAP Keselamatan Kerja	2	Unit	0.60	1.20	4.52	
Total		2,265.71 Rp/Building × 1.1 ( 2 ) Unit = 1,246.14 ×10 <sup>3</sup> Rp/Unit		36 M <sup>2</sup>	34.62 ×10 <sup>3</sup> Rp/M <sup>2</sup>		

		D-45		( 2 Unit/Building)		FLOOR AREA	NET. 45.00 M <sup>2</sup>	
						GROSS 45.00 M <sup>2</sup>		
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	2	Unit	0.90	1.80	17.76	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp. water	2	Unit	1.20	2.40			
	Grading	-	-	-	-			
	Setting & staking out	77.50	M	0.175	13.56			
Earth Work	Scaffolding		Unit	4.50, 9.00				
	Insectisidation		M	1.26				
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96		1,009.14	-incl. horizontal RC-brace	
		F <sub>2</sub>	M	3.33				
		F <sub>3</sub>	M	1.07				
		F <sub>4</sub>	77.50	M	2.69			208.48
	1F. Floor	Slab on grade	95.10	M <sup>2</sup>	1.79			170.23
		Soil floor		M <sup>2</sup>	0.11			
	Ridge stone	F <sub>1</sub>		M	0.72			
		F <sub>2</sub>	15.60	M	0.47			7.33
	Concrete block	HB-15		M <sup>2</sup>	2.99			
		HB-10	140.64	M <sup>2</sup>	2.27			319.25
		Finish plaster		M <sup>2</sup>	0.92			
		WC/H floor mortar	20.50	M <sup>2</sup>	1.34			27.47
	RC-Course	C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>		M	2.38			
		C <sub>4</sub>		M	3.37			
		C <sub>5</sub>		M	3.77			
		C <sub>6</sub>	104.65	M	2.03			212.44
	Wall reinforcement	A-1	52.80	M	0.41			21.65
		A-2	24.00	M	0.16			27.84
		A-3	16.80	M	0.86			14.45
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16			
		RC floor S <sub>2</sub>		M	11.76			
		Wood floor		M <sup>2</sup>	7.02			
	Wood Work	Upper wall etc.	Head plate	60.50	M			0.41
Upper unit wall			8.14	M	5.76	46.89		
Other upper wall			37.38	M <sup>2</sup>	2.40	77.71		
Upper staircase				Set				
Upper WC/H				Set				
Handrail		Wooden rail		Unit				
		Pipe rail		Unit	10.76			
Staircase		(Wooden)		Unit				
		(Asbestos)		M <sup>2</sup>	2.38			
149.41								
Ceiling Work	Ceiling		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>	
Door & Window Work	J <sub>11</sub> J <sub>2</sub> J <sub>3</sub>	J <sub>11</sub>	8	Pc	18.01	144.08	-per horizontal M <sup>2</sup> (incl. laves) L = 2.0M	
		J <sub>2</sub>	6	Pc	10.29	61.74		
		J <sub>3</sub>	2	Pc	11.58	23.16		
				Pc				
			Pc					
Lock + Hook	2×2	Pc	2.50+0.20	5.40	383.79			
Roof Work	Rafter + Batten + Tile	111.60	M <sup>2</sup>	5.82	649.51	794.98	-per horizontal M <sup>2</sup> (incl. laves) L = 2.0M	
	Canopy		Set					
	Ridge tile	12.00	M	1.04	12.48			
	Ridge column	5.00	M	1.21, 4.4+1.79	23.35			
	Ridge board	12.00	M	1.52	18.24			
	Brace	5	Pc	4.00	20.00			
	Eaves fascia	45.60	M	0.35	15.96			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening	33.60	M	1.65	55.44			
	Collar		Pc					
Plumbing Work	Water tub	2	Unit	5.50	11.00	226.60		
	Closet	2	Unit	7.00	14.00			
	Cleanout, Trap	4	Pc	3.00	12.00			
	Waste pipe	42.00	M	3.60	151.20			
	Water pipe	20.00	M	0.62	12.40			
	Water head	4	Pc	1.50	6.00			
	Kitchen sink	2	Unit	7.00	14.00			
	Connection pit	2	Unit	3.00	6.00			
	Fixture etc.	2	Unit	42.00	84.00			
Electrical Work	Power intake		Unit			84.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	4×2	Pc	0.30+0.90	3.00		-incl. foundation	
	Fence		M	1.61		3.00	-incl. each item	
Painting	Painting		M <sup>2</sup>					
	Guard	2	Unit	1.20	2.40			
Other Work	Cleaning	2	Unit	0.46	0.92			
	ALAP Keselamatan Karja	2	Unit	0.60	1.20	4.52		
Total		2,673.20 Rp/Building × 1.1 + ( 2 ) Unit =		1,470.26 × 10 <sup>3</sup> Rp/Unit ÷ 45 M <sup>2</sup> =		32.67 × 10 <sup>3</sup> Rp/M <sup>2</sup>		

R-15 ( 6 Unit/Building)							FLOOR AREA	NET 14.00 M <sup>2</sup>	GROSS 18.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note		
Temporary Work	Warehouse	6	Unit	0.90	5.40	36.23	-See. land development -per wall length (M) -only for 2 -Other cost (incl. foundation and floor work)		
	Temp. water	6	Unit	1.20	7.20				
	Grading	-	-	-	-				
	Setting & staking out	135.00	M	0.175	23.63				
	Scaffolding	-	Unit	4.50, 9.00					
Earth Work	Insectisidation		M	1.26					
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96		1,311.09	-incl. horizontal RC-brace		
		F <sub>2</sub>	M	3.33					
		F <sub>3</sub>	M	3.07					
		F <sub>4</sub>	M	2.69	363.15				
	1F. Floor	Slab on grade	115.98	M <sup>2</sup>	1.79			207.60	
		Soil floor		M <sup>2</sup>	0.11				
	Ridge stone	F <sub>5</sub>		M	0.72				
		F <sub>6</sub>	25.20	M	0.47			11.84	
		HB-15		M <sup>2</sup>	2.99				
	Concrete block	HB-10	176.16	M <sup>2</sup>	2.27			399.88	
		Finish plaster		M <sup>2</sup>	0.92				
		WC/H floor mortar	68.52	M <sup>2</sup>	1.34			91.82	
		C <sub>1</sub>		M	3.81				
	RC-Course	C <sub>2</sub>		M	2.92				
		C <sub>3</sub>		M	2.38				
		C <sub>4</sub>		M	3.37				
		C <sub>5</sub>		M	3.77				
		C <sub>6</sub>	89.36	M	2.03			181.40	
	Wall reinforcement	A <sub>1</sub> -1	57.60	M	0.41			23.62	
		A <sub>2</sub> -2	9.60	M	1.16			11.14	
		A <sub>3</sub> -3	24.00	M	0.86			20.64	
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16				
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76				
Wood Work	Wood floor		M <sup>2</sup>	7.02					
	Head plate	69.00	M	0.41	28.29				
	Upper unit wall	-	M	5.76					
	Other upper wall	27.72	M	2.40	66.53				
	Upper staircase	-	Set						
	Upper WC/H	6	Set	9.335	56.01				
	Handrail	Wooden rail		Unit					
		Pipe rail		Unit	10.76				
Staircase (Wooden)		Unit			150.81				
Ceiling Work	Ceiling Asbestos		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>		
Door & window Work	J <sub>11</sub>	12	Pc	18.01	216.12	576.11	-per horizontal M <sup>2</sup> (incl. laves) L = 2.1M		
	J <sub>20</sub>	12	Pc	10.29	123.48				
	J <sub>5</sub>	6	Pc	11.58	69.48				
	Pc		Pc						
	Pc		Pc						
Lock + Hook	6+6	Pc	2.50+0.20	16.20					
Rafter + Batten + Tile	141.30	M <sup>2</sup>	5.82	822.37					
Canopy		Set							
Roof Work	Ridge tile	14.40	M	1.04	14.98				
	Ridge column	6	Pc	1.44+1.79	28.89				
	Ridge board	14.40	M	1.52	21.89				
	Brace	6	Pc	4.00	24.00				
	Eaves fascia	125.40	M	0.35	43.89				
	Valley gutter	14.40	M	3.90	56.16				
	Down pipe	16.20	M	1.80	29.16				
	Water-tightening	109.20	M	1.65	180.18				
	Collar		Pc						
						1,221.51			
Plumbing Work	Water tub	6	Unit	5.50	33.00	270.30	-See. electricity cost		
	Closet	6	Unit	7.00	42.00				
	Cleanout, Trap	12	Pc	3.00	36.00				
	Waste pipe	20.00	M	3.60	72.00				
	Water pipe	15.00	M	0.62	9.30				
	Water head	12	Pc	1.50	18.00				
	Kitchen sink	6	Unit	7.00	42.00				
	Connection pit	6	Unit	3.00	18.00				
Electrical Work	Fixture etc.	6	Unit	42.00	252.00				
Outside Work	Step plate + gutter plate	18+12	Pc	0.30+0.90	16.20				
Painting	Fence		M	1.61		16.20	-incl. foundation		
	Painting		M <sup>2</sup>				-incl. each item		
Other Work	Guard	6	Unit	1.20	7.20				
	Cleaning	6	Unit	0.46	2.76				
	PLAR Keselamatan Kerja	6	Unit	0.60	3.60	13.56			
<b>Total</b>	3,847.83 Rp/Building x 1.1 + ( 6 ) Unit = 705.44 *10 <sup>3</sup> Rp/unit + 18 M <sup>2</sup> = 39.19 *10 <sup>3</sup> Rp/M <sup>2</sup>								

		N-22		( 6 Unit/Building)		FLOOR AREA	NET 27.00 M <sup>2</sup>	GROSS 27.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note		
Temporary Work	Warehouse	6	Unit	0.90	5.40				
	Temp. water	6	Unit	1.20	7.20				
	Grading	-	-	-	-				
	Setting & staking out	198.0	M	0.175	34.65				
Earth Work	Scaffolding		Unit	4.50, 9.00		47.25			
	Insectisidation		M	1.26					
Masonry & Concrete Work	Foundation	F <sub>1</sub>		M	5.96				
		F <sub>2</sub>		M	3.33				
		F <sub>3</sub>		M	3.07				
		F <sub>4</sub>	186.00	M	2.69	500.34			
	1F. Floor	Slab on grade	148.50	M <sup>2</sup>	1.79	265.82			
		Soil floor		M <sup>2</sup>	0.11				
	Ridge stone	F <sub>5</sub>		M	0.72				
		F <sub>6</sub>	12.00	M	0.47	5.64			
	Concrete block	HB-15		M <sup>2</sup>	2.99				
		HB-10	282.00	M <sup>2</sup>	2.27	640.14			
		Finish plaster		M <sup>2</sup>	0.92				
	RC-Course	WC/R floor	68.52	M <sup>3</sup>	1.34	91.82			
		Porter							
		C <sub>1</sub>		M	3.81				
		C <sub>2</sub>		M	2.92				
		C <sub>3</sub>		M	2.38				
		C <sub>4</sub>		M	3.37				
	Wall reinforcement	C <sub>5</sub>	160.73	M	1.77	284.30			
		C <sub>6</sub>		M	2.03	326.28			
		A-1	108.00	M	0.41	44.28			
2F. Floor	A-2	19.20	M	1.16	22.27				
	A-3	36.00	M	0.86	30.96				
	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16					
Wood Work	RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		1,927.55			
	Wood floor		M <sup>2</sup>	7.02					
	Head plate	84.00	M	0.41	34.44				
	Upper unit wall	41.56	M <sup>2</sup>	5.76	239.50				
	Other upper wall	62.28	M <sup>2</sup>	2.40	149.47				
	Upper staircase	6	Set	4.065	24.39				
	Upper WC/M	6	Set	9.335	56.01				
	Handrail	Wooden rail		Unit					
		Pipe rail		Unit	10.76				
	Staircase (Wooden)		Unit			501.81			
Ceiling Work	Ceiling	Asbestos		M <sup>2</sup>	2.38				
Door & Window Work	J <sub>11</sub>	12	Pc	18.01	216.12				
	J <sub>12</sub>	12	Pc	10.29	123.48				
	J <sub>13</sub>	6	Pc	11.58	69.48				
			Pc						
			Pc						
Roof Work	Lock + Hook	6+6	Pc	2.50+0.20	16.20	576.11			
	Rafter + Batten + Tile	204.40	M <sup>2</sup>	5.82	1,183.79				
	Canopy		Set						
	Ridge tile	23.40	M	1.04	24.34				
	Ridge column	2	Pc	141.44+1.79	43.33				
	Ridge board	23.40	M	1.52	35.57				
	Brace	9	Pc	4.00	36.00				
	Eaves fascia	143.40	M	0.35	50.19				
	Valley gutter	23.40	M	1.90	71.26				
	Down pipe	16.20	M	1.80	29.16				
	Water-tightening	118.20	M	1.65	195.03				
	Collar		Pc			1,688.67			
	Plumbing Work	Water tub	6	Unit	5.50	33.00			
Closet		6	Unit	7.00	42.00				
Cleanout, Trap		12	Pc	1.00	16.00				
Waste pipe		20.00	M	3.60	72.00				
Water pipe		15.00	M	0.62	9.30				
Water head		12	Pc	1.50	18.00				
Kitchen sink		6	Unit	7.00	42.00				
Connection pit		6	Unit	3.00	18.00	270.30			
Electrical Work	Fixtura etc.	6	Unit	42.00	252.00				
	Power intake		Unit						
Outside Work	Stop plate + gutter plate	30+12	Pc	0.30+0.90	19.80				
	Fence		M	1.61		19.80			
Painting	Painting		M <sup>2</sup>						
	Guard	6	Unit	1.20	7.20				
Other Work	Cleanup	6	Unit	0.46	2.76				
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56			
Total		5,299.05 Rp/Building × 1.1 f ( 6 ) Unit = 971.49		×10 <sup>3</sup> Rp/Unit = 25 M <sup>2</sup> = 38.86 ×10 <sup>3</sup> Rp/M <sup>2</sup>					

		R-36N		( 6 Unit/Building)		FLOOR AREA	NET 78.00 M <sup>2</sup>	
							GROSS 38.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.90	5.40	50.05	-See. land development -per wall length (M) -only for 2F -Other cost incl foundation and floor work	
	Temp. water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out Scaffolding	214.0	M	0.175	37.45			
Earth Work	Insectisidation	-	M	1.26	-			
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96	-	2,596.68	-incl. horizontal RC-brace	
		F <sub>2</sub>	M	1.33	-			
		F <sub>3</sub>	M	1.07	-			
		F <sub>4</sub>	214.00	M	2.69			575.66
	1F. Floor	Slab on grade	228.05	M <sup>2</sup>	1.79			408.75
		Soil floor	-	M <sup>2</sup>	0.31			-
	Ridge stone	F <sub>1</sub>	-	M	0.72			-
		F <sub>2</sub>	29.10	M	0.47			13.68
		F <sub>3</sub>	-	M	2.99			-
	Concrete block	HB-15	-	M <sup>3</sup>	2.37			815.02
		HB-10	359.04	M <sup>3</sup>	0.92			-
		Finish plaster	-	M <sup>2</sup>	1.34			15.02
		WC/H floor mortar	11.21	M <sup>2</sup>	-			-
	RC-Course	C <sub>1</sub>	-	M	3.81			-
		C <sub>2</sub>	-	M	2.92			-
		C <sub>3</sub>	-	M	2.38			-
		C <sub>4</sub>	-	M	3.37			-
		C <sub>5</sub>	-	M	3.77			-
	Wall reinforcement	A <sub>1</sub> -1	225.60	M	2.03			591.66
		A <sub>1</sub> -2	33.60	M	0.41			92.50
		A <sub>1</sub> -3	52.80	M	1.16			39.98
	2F. Floor	RC floor S <sub>1</sub>	-	M <sup>2</sup>	13.16			-
		RC floor S <sub>2</sub>	-	M <sup>2</sup>	11.76			-
Wood Work	Upper wall etc.	Wood floor	-	M <sup>2</sup>	7.02	514.98	-incl. bolts + nuts	
		Head plate	210.0	M	0.41			86.10
		Upper unit wall	51.9	M <sup>2</sup>	5.76			298.94
		Other upper wall	54.14	M <sup>2</sup>	2.40			129.94
		Upper staircase	-	Set	-			-
		Upper WC/H	-	Set	-			-
	Handrail	Wooden rail	-	Unit	-			-
		Pipe rail	-	Unit	10.76			-
	Staircase (Wooden)	-	Unit	-	-			
	Ceiling Work	Ceiling	Asbestos	M <sup>2</sup>	2.38			-
Door & Window Work	J <sub>11</sub>	J <sub>11</sub>	12	Pc	15.39	184.68	1,347.78	-per horizontal M <sup>2</sup> (incl. lavas) L <sub>1</sub> = 1.5M L <sub>2</sub> = 0.7M
		J <sub>11</sub>	24	Pc	18.01	432.24		
		J <sub>21</sub>	18	Pc	10.29	185.22		
		J <sub>21</sub>	6	Pc	5.11	30.66		
	Lock + Hook	-	Pc	2.50×0.20	17.40			
Roof Work	Rafter + Batten + Tile	275.76	M <sup>2</sup>	5.82	1,604.92	2,314.14		
	Canopy	-	Set	-	-			
	Ridge tile	54.60	M	1.04	56.78			
	Ridge column	12	Pc	1.44	17.28			
	Ridge board	107.76	M	1.52	163.80			
	Brace	22	Pc	4.00	88.00			
	Eaves fascia	106.40	M	0.35	37.24			
	Valley gutter	-	M	3.96	-			
	Down pipe	-	M	1.80	-			
	Water-tightening	174.56	M	1.65	288.02			
Collar	-	Pc	-	-				
Plumbing Work	Water tub	6	Unit	5.50	33.00	460.44		
	Closet	6	Unit	7.00	42.00			
	Cleanout, Trap	12	Pc	3.00	36.00			
	Waste pipe	63.00	M	3.60	226.80			
	Water pipe	72.00	M	0.62	44.64			
	Water head	17	Pc	1.50	25.50			
	Kitchen sink	6	Unit	7.00	42.00			
	Connection pit	6	Unit	3.00	18.00			
	Fixture etc.	6	Unit	42.00	252.00			
Electrical Work	Power intake	-	Unit	-	-	252.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	30×12	Pc	0.30×0.90	19.80	19.80	-incl. foundation	
	Fence	-	M	1.61	-			
Painting	Painting	-	M <sup>2</sup>	-	-		-incl. each item	
Other Work	Guard	6	Unit	1.20	7.20	13.56		
	Cleaning	6	Unit	0.46	2.76			
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60			
Total		7,569.43 Rp/Building × 1.1 ( 6 ) Unit = 1,387.73 ×10 <sup>3</sup> Rp/Unit ; 38 M <sup>2</sup> = 36.52 ×10 <sup>3</sup> Rp/M <sup>2</sup>						



		R-36		[ 6 Unit/Building]		FLOOR AREA	NET	PLUG M			
							GROSS	19.00 M <sup>2</sup>			
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note				
Temporary Work	Warehouse	6	Unit	0.90	5.40	48.83	-Set. land development -per wall length (M) -only for 2h -Other cost incl. foundation and floor work				
	Temp. water	6	Unit	1.20	7.20						
	Grading	-	-	-	-						
	Setting & staking out	207.00	M	0.175	36.23						
Earth Work	Scaffolding	-	Unit	4.50, 9.00	-						
	Insectisidation		M	1.26							
Masonry & Concrete work	Foundation	F <sub>1</sub>		M	5.96		-incl. horizontal RC-brace				
		F <sub>2</sub>		M	3.33						
		F <sub>3</sub>		M	3.07						
		F <sub>4</sub>	207.00	M	2.69	556.83					
	1F. Floor	Slab on grade	217.23	M <sup>2</sup>	1.79	388.84					
		Soil floor		M <sup>2</sup>	0.11						
	Ridge stone	F <sub>5</sub>		M	0.72						
		F <sub>6</sub>	17.40	M	0.47	8.18					
	Concrete block	HB-15		M <sup>2</sup>	2.99						
		HB-10	360.96	M <sup>2</sup>	2.27	819.38					
		Finish plaster		M <sup>2</sup>	0.92						
		WC/H floor mortar	12.48	M <sup>2</sup>	1.34	16.72					
	RC-Course	C <sub>1</sub>		M	3.81						
		C <sub>2</sub>		M	2.92						
		C <sub>3</sub>		M	2.38						
		C <sub>4</sub>		M	3.37						
		C <sub>5</sub>		M	3.77						
		C <sub>6</sub>	285.46	M	2.03	579.48					
	Wall reinforcement	A <sub>1</sub> -1	194.40	M	0.41	79.70					
		A <sub>2</sub> -2	67.20	M	1.16	77.95					
A <sub>3</sub> -3		50.40	M	0.86	43.34						
2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16							
	RC floor S <sub>2</sub>		M <sup>2</sup>	11.75		2,570.42					
Wood Work	Upper wall etc.	Wood floor		M <sup>2</sup>	7.02		-incl. bolts + nuts -per horizontal M <sup>2</sup>				
		Head plate	174.00	M	0.41	71.34					
		Upper unit wall	25.95	M <sup>2</sup>	5.76	149.47					
		Other upper wall	76.26	M <sup>2</sup>	2.40	183.02					
	Handrail	Upper staircase		Set							
		Upper WC/M		Set							
	Staircase	Wooden rail		Unit							
		Pipe rail (Wooden)		Unit	10.76						
	Ceiling Work	Ceiling	Asbestos		M <sup>2</sup>	2.38					
									403.83		
Door & window Work	Lock + Hook	J <sub>1</sub>	12	Pc	15.39	184.68	-per horizontal M <sup>2</sup> (incl. laves) L = 1.6M				
		J <sub>11</sub>	18	Pc	18.01	324.18					
		J <sub>2</sub>	18	Pc	10.29	185.22					
		J <sub>21</sub>	6	Pc	5.11	30.66					
			Pc								
	Lock + Hook	6+6	Pc	2.50+0.20	16.20	740.94					
Roof Work	Rafter + Batten + Tile	280.80	M <sup>2</sup>	5.82	1,634.26						
	Canopy		Set								
	Ridge tile	36.0	M	1.04	37.44						
	Ridge column	19	Pc	1+1.44+1.79	77.79						
	Ridge board	36.00	M	1.52	54.72						
	Brace	19	Pc	4.00	76.00						
	Eaves fascia	152.80	M	0.35	53.48						
	Valley gutter		M	3.90							
	Down pipe		M	1.80							
	Water-tightening	164.80	M	1.65	271.92						
	Collar		Pc			2,205.61					
	Plumbing Work	Water tub	6	Unit	5.50	33.00					
Closet		6	Unit	7.00	42.00						
Cleanout, Trap		12	Pc	3.00	36.00						
Waste pipe		53.00	M	3.60	190.80						
Water pipe		54.00	M	0.62	33.48						
Water head		12	Pc	1.50	18.00						
Kitchen sink		6	Unit	7.00	42.00						
Connection pit		6	Unit	3.00	18.00	413.28					
Electrical Work	Fixture etc.	6	Unit	42.00	252.00		-See. electricity cost				
	Power intake	-	Unit	-	-	252.00					
Outside Work	Step plate + gutter plate	30+12	Pc	0.30+0.90	19.80		-incl. foundation -incl. each item				
	Fence		M	1.61		19.80					
Painting	Painting		M <sup>2</sup>								
	Guard	6	Unit	1.20	7.20						
Other Work	Cleaning	6	Unit	0.36	2.16						
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56					
Total		6,668.27 Rp/Building × 1.1 [ 6 ] Unit = 1,222.52 ×10 <sup>3</sup> Rp/Unit [ 39 M <sup>2</sup> = 31.35 ×10 <sup>3</sup> Rp/M <sup>2</sup>									

R-45 ( 6 Unit/Building)							FLOOR AREA	NET 48.00 M <sup>2</sup>	GROSS 48.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note		
Temporary Work	Warehouse	6	Unit	0.90	5.40	52.24	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work		
	Temp. water	6	Unit	1.20	7.20				
	Grading	-	-	-	-				
	Setting & staking out	226.50	M	0.175	39.64				
	Scaffolding	-	Unit	4.50, 9.00					
Earth Work	Insectisidation		M	1.26					
Masonry & Concrete Work	Foundation	F <sub>1</sub>		M	5.96				
		F <sub>2</sub>		M	3.33				
		F <sub>3</sub>		M	3.07				
		F <sub>4</sub>	226.50	M	2.69	609.29			
		F <sub>5</sub>	269.43	M <sup>2</sup>	1.79	482.28			
	1F. Floor	Slab on grade		M <sup>2</sup>	0.11				
		Soil floor		M	0.72				
	Ridge stone	F <sub>1</sub>	17.40	M	0.47	8.18			
		HB-15		M <sup>2</sup>	2.99				
		HB-10	400.56	M <sup>2</sup>	2.27	909.27			
	Concrete block	Finish plaster		M <sup>2</sup>	0.92				
		WC/M floor mortar	62.28	M <sup>2</sup>	1.34	83.46			
	RC-Course	C <sub>1</sub>		M	3.81				
		C <sub>2</sub>		M	2.92				
		C <sub>3</sub>		M	2.38				
		C <sub>4</sub>		M	3.37				
		C <sub>5</sub>		M	3.77				
		C <sub>6</sub>	304.96	M	2.03	619.07			
	Wall reinforcement	A-1	194.40	M	0.41	79.70			
		A-2	67.20	M	1.16	77.95			
		A-3	50.40	M	0.86	43.34			
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16				
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76		2,912.54		
	Wood Work	Wood floor		M <sup>2</sup>	7.02				
		Head plate	193.50	M	0.41	79.34			
Upper unit wall		40.70	M <sup>2</sup>	5.76	234.43				
Other upper wall		102.50	M <sup>2</sup>	2.40	246.00				
Upper staircase			Set						
Upper WC/M			Set						
Handrail		Wooden rail		Unit					
		Pipe rail		Unit	10.76				
Staircase (wooden)			Unit			559.77			
Ceiling Work		Ceiling Asbestos		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>	
Door & window Work	J <sub>12</sub>	12	Pc	15.39	184.68				
	J <sub>13</sub>	18	Pc	18.01	324.18				
	J <sub>20</sub>	18	Pc	10.29	185.22				
	J <sub>21</sub>	6	Pc	5.11	30.66				
	Lock + Hook	6+6	Pc	2.50+0.20	16.20	740.94			
Roof Work	Rafter + Batten + Tile	334.80	M <sup>2</sup>	5.82	1,948.54				
	Canopy		Set						
	Ridge tile	36.00	M	1.04	37.44				
	Ridge column	19	Pc	1,44+1.79	89.71				
	Ridge board	36.00	M	1.52	54.72				
	Brace	19	Pc	4.00	76.00				
	Eaves fascia	165.60	M	0.35	57.96				
	Valley gutter		M	3.90					
	Down pipe		M	1.80					
	Water-tightening	187.20	M	1.65	308.88				
	Collar		Pc			2,572.27			
Plumbing Work	Water tub	6	Unit	5.50	33.00				
	Closet	6	Unit	7.00	42.00				
	Cleanout, Trap	12	Pc	3.00	36.00				
	Waste pipe	45.00	M	3.60	162.00				
	Water pipe	48.00	M	0.62	29.76				
	Water head	12	Pc	1.50	18.00				
	Kitchen sink	6	Unit	7.00	42.00				
	Connection pit	6	Unit	3.00	18.00	180.76			
Electrical Work	Fixture etc.	6	Unit	42.00	252.00				
	Power intake	-	Unit	-	-	752.00	-See. electricity cost		
Outside Work	Step plate + gutter plate	30+12	Pc	0.30+0.90	19.80				
	Fence		M	1.61		19.80	-incl. foundation -incl. each item		
Painting	Painting		M <sup>2</sup>						
Other Work	Guard	6	Unit	1.20	7.20				
	Cleaning	6	Unit	0.46	2.76				
	ALAP Keselamatan Parja	6	Unit	0.60	3.60	13.56			
Total		7,503.88 Rp/Building × 1.1 + ( 6 ) Unit = 1,375.71 ×10 <sup>3</sup> Rp/Unit + 48 M <sup>2</sup> = 28.66 ×10 <sup>3</sup> Rp/M <sup>2</sup>							

		M-24		( 6 Unit/Building)		FLOOR AREA	NET 26.40 M <sup>2</sup>	
						GROSS 30.00 M <sup>2</sup>		
Section	Item	Volume	Unit	Unit cost *10 <sup>3</sup> Rp	Cost *10 <sup>3</sup> Rp	Sub-total *10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.90	5.40	67.99	-Sec. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp. water Grading	6	Unit	1.20	7.20			
	Setting & staking out	162.20	M	0.175	28.39			
	Scaffolding	6	Unit	4.50, 9.00	27.00			
Earth Work	Insecticidation		M	1.26				
Masonry & Concrete Work	Foundation	F <sub>1</sub>		M	5.96		-incl. horizontal RC-brace	
		F <sub>2</sub>	94.80	M	3.33	315.68		
		F <sub>3</sub>	3.90	M	3.07	11.97		
		F <sub>4</sub>	68.00	M	2.69	182.92		
	1F. Floor	Slab on grade	98.78	M <sup>2</sup>	1.79	176.02		2,770.39
		Soil floor		M <sup>2</sup>	0.11			
	Ridge stone	F <sub>5</sub>		M	0.72			
		F <sub>6</sub>	25.20	M	0.47	11.84		
	Concrete block	HB-15	207.98	M <sup>2</sup>	2.99	621.06		
		HB-10	100.80	M <sup>2</sup>	2.27	228.82		
		Finish plaster		M <sup>2</sup>	0.92			
		RC/M floor mortar	68.52	M <sup>2</sup>	1.34	91.82		
	RC-Course	C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>	165.48	M	2.38	393.84		
		C <sub>4</sub>	72.00	M	3.37	242.64		
		C <sub>5</sub>	6.00	M	3.77	22.62		
		C <sub>6</sub>		M	2.03			
	Wall reinforcement	B <sub>1</sub> -1	290.40	M	0.88	255.55		
		B <sub>2</sub> -2	46.00	M	2.72	125.12		
		B <sub>3</sub> -3	32.80	M	2.71	88.89		
	2F. Floor	RC floor S <sub>1</sub>		M <sup>2</sup>	13.16			
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76			
	Wood Work	Wood floor	64.80	M <sup>2</sup>	7.02	454.90		
Head plate		81.60	M	0.41	33.46			
Upper unit wall		2.62	M <sup>2</sup>	5.76	15.09			
Other upper wall		10.48	M <sup>2</sup>	2.40	25.15			
Upper staircase			Set		13.04			
Upper WC/M			Set		56.01			
Handrail		Wooden rail	3	Pc	4.98	14.94		
		Pipe rail		Unit	10.76			
Staircase		(Wooden)	3	Pc	35.12	105.96		
Ceiling Work		Ceiling		M <sup>2</sup>	2.38			-per horizontal M <sup>2</sup>
Door & Window Work	J <sub>1</sub>	6	Pc	16.63	99.78	989.52	-per horizontal M <sup>2</sup> (incl. laves) L = 0.7M	
	J <sub>11</sub>	18	Pc	11.74	211.32			
	J <sub>12</sub>	12	Pc	18.01	216.12			
	J <sub>13</sub>	18	Pc	16.10	289.80			
	J <sub>14</sub>	6	Pc	11.97	71.82			
	J <sub>15</sub>	6	Pc	11.58	69.48			
Roof Work	Lock + Hook	12+6	Pc	2.50+0.20	31.20	1,240.55		
	Rafter + Batten + Tile	144.72	M <sup>2</sup>	5.82	842.27			
	Canopy		Set					
	Ridge tile	24.00	M	1.04	24.96			
	Ridge column	8	Pc	1.44+1.72	22.38			
	Ridge board	20.40	M	1.52	31.01			
	Brace	8	Pc	4.00	32.00			
	Eaves fascia	157.60	M	0.35	55.16			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening	130.60	M	1.65	215.49			
Collar	3	Pc	5.76	17.28				
Plumbing Work	Water tub	6	Unit	5.50	33.00	270.30		
	Closest	6	Unit	7.00	42.00			
	Cleanout, Trap	12	Pc	3.00	36.00			
	Waste pipe	20.00	M	3.60	72.00			
	Water pipe	15.00	M	0.62	9.30			
	Water head	12	Pc	1.50	18.00			
	Kitchen sink	6	Unit	7.00	42.00			
	Connection pit	6	Unit	3.00	18.00			
	Fixture etc.	6	Unit	42.00	252.00			
	Power intake		Unit					
Electrical Work	Power intake		Unit			252.00	-Sec. electricity cost	
	Step plate + gutter plate	18+12	Pc	0.30+0.90	16.20			
Outside Work	Fence		M	1.61		16.20	-incl. foundation -incl. each item	
	Painting		M <sup>2</sup>					
Other Work	Guard	6	Unit	1.20	7.20			
	Cisrapang	6	Unit	0.46	2.76			
	ALAT Keselamatan Kerja	6	Unit	0.60	3.60	13.56		
Total		6,339.06 Rp/Building = 1.1 + ( 6 ) Unit = 1,162.16 *10 <sup>3</sup> Rp/Unit + 30 M <sup>2</sup> = 38.74 *10 <sup>3</sup> Rp/M <sup>2</sup>						

M-36 (In case of roof tile) ( 6 Unit/Building)							FLOOR AREA	NET 38.00 M <sup>2</sup>		
							GROSS 38.00 M <sup>2</sup>			
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note			
Temporary Work	Warehouse	6	Unit	0.90	5.40	65.15	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work			
	Temp. water	6	Unit	1.20	7.20					
	Grading	-	-	-	-					
	Setting & staking out	146.00	M	0.175	25.55					
	Scaffolding	6	Unit	4.50, 9.00	27.00					
Earth Work	Insectisidation		M	1.26						
Masonry & Concrete Work	Foundation	F <sub>1</sub>		M	5.96		3,526.44	-incl. horizontal RC-brace		
		F <sub>2</sub>	146.00	M	3.33	486.18				
		F <sub>3</sub>		M	3.07					
		F <sub>4</sub>		M	2.69					
	1F. Floor	Slab on grade	131.46	M <sup>2</sup>	1.79	235.31				
		Soil floor		M <sup>2</sup>	0.11					
	Ridge stone	F <sub>5</sub>		M	0.72					
		F <sub>6</sub>	29.40	M	0.47	13.82				
		HB-15	408.98	M <sup>2</sup>	2.99	1,222.85				
	Concrete block	HB-10		M <sup>2</sup>	2.27					
		Finish plaster		M <sup>2</sup>	0.92					
		WC/H floor mortar	10.97	M <sup>2</sup>	1.34	14.70				
	RC-Course	C <sub>1</sub>		M	3.81					
		C <sub>2</sub>		M	2.92					
		C <sub>3</sub>	264.00	M	2.38	628.32				
		C <sub>4</sub>	67.00	M	3.37	225.79				
		C <sub>5</sub>	41.50	M	3.77	156.46				
	wall reinforcement	C <sub>6</sub>		M	2.03					
		B-1	231.90	M	0.88	204.07				
		B-2	73.60	M	2.72	200.19				
	2F. Floor	B-3	51.20	M	2.71	138.75				
		RC floor S <sub>1</sub>		M <sup>2</sup>	13.16					
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76					
		Wood floor	88.20	M <sup>2</sup>	7.02	619.16				
	Wood Work	Upper wall etc.	Head plate	102.50	M	0.41			42.03	-incl. bolts & nuts
			Upper unit wall	7.50	M <sup>2</sup>	5.76			43.20	
			Other upper wall	31.13	M <sup>2</sup>	2.40			74.71	
Upper staircase				Set		14.25				
Upper WC/M				Set						
Handrail		Wooden rail	6	Unit	5.73	34.38				
Ceiling Work	Pipe rail		Unit	10.76						
	Staircase (Wooden)	6	Pc	35.32	211.92	1,039.65	-per horizontal M <sup>2</sup>			
	Ceiling Asbestos		M <sup>2</sup>	2.38						
Door & Window Work	J <sub>1</sub>	6	Pc	16.63	99.78	660.72	-per horizontal M <sup>2</sup> (incl. laves)			
	J <sub>2</sub>	6	Pc	7.32	43.92					
	J <sub>3</sub>	6	Pc	28.56	171.36					
	J <sub>4</sub>	6	Pc	27.23	163.38					
	J <sub>5</sub>	6	Pc	16.10	96.60					
	J <sub>6</sub>	6	Pc	11.58	69.48					
	Lock + Hook	6+6	Pc	2.50+0.20	16.20					
Roof Work	Rafter + Batten + Tile	155.40	M <sup>2</sup>	5.82	904.43	1,181.77	-incl. laves L = 1.3M			
	Canopy		Set		115.95					
	Ridge tile	24.00	M	1.04	24.96					
	Ridge column	10	Pc	1.34+1.79	36.62					
	Ridge board	18.00	M	1.52	27.36					
	Brace	12	Pc	4.00	48.00					
	Eaves fascia	112.00	M	0.35	39.20					
	Valley gutter		M	3.90						
	Down pipe		M	1.80						
	Water-tightening	91.00	M	1.65	150.15					
	Collar	3	Pc	11.70	35.10					
	Plumbing Work	Water tub	6	Unit	5.50			33.00	156.58	-See. electricity cost
Closet		6	Unit	7.00	42.00					
Cleanout, Trap		12	Pc	3.00	36.00					
Waste pipe		45.00	M	3.60	162.00					
Water pipe		9.00	M	0.62	5.58					
Water head		12	Pc	1.50	18.00					
Kitchen sink		6	Unit	7.00	42.00					
Connection pit		6	Unit	3.00	18.00					
Electrical Work	Fixture etc.	6	Unit	42.00	252.00					
	Power intake		Unit			252.00				
Outside Work	Step plate + gutter plate	4+2	Pc	0.30+0.90	3.00					
Painting	Fence		M	1.61		3.00	-incl. foundation			
	Painting		M <sup>2</sup>				-incl. each item			
Other Work	Guard	6	Unit	1.20	7.20					
	Cleaning	6	Unit	0.46	2.76					
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56				
<b>Total</b>	7,298.87 Rp/Building × 1.1 + ( 6 ) Unit = 1,338.13 ×10 <sup>3</sup> Rp/unit + 38 M <sup>2</sup> = 35.21 ×10 <sup>3</sup> Rp/M <sup>2</sup>									

M-36 (In case of corrugated asbestos) ( 6 Unit/Building)						FLOOR AREA	NET 38.00 M <sup>2</sup>	
							GROSS 38.00 M <sup>2</sup>	
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.90	5.40			
	Temp. water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out Scaffolding	146.00	M	0.175	25.55		-See. land development -per wall length (M)	
Earth Work	Insecticidation		M	1.26		65.15	-only for 2F -Other cost incl. foundation and floor work	
	Foundation		M	5.96				
Masonry & Concrete Work	F <sub>1</sub>	146.00	M	3.33	486.18			
	F <sub>2</sub>		M	3.07				
	F <sub>3</sub>		M	2.69				
	1F. Floor	131.46	M <sup>2</sup>	1.79	235.31			
	Soil floor		M <sup>2</sup>	0.11				
	Ridge stone		M	0.72				
	Concrete block	F <sub>4</sub>	29.40	M	0.47	13.82		
		NB-15	424.70	M <sup>2</sup>	2.99	1,269.85		
		NB-10		M <sup>2</sup>	2.27			
		Finish plaster		M <sup>2</sup>	0.92			
	RC-Course	WC/M floor mortar	10.97	M <sup>2</sup>	1.34	14.70		
		C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>	264.00	M	2.38	628.32		
		C <sub>4</sub>	67.00	M	3.37	225.79		-incl. horizontal AC-brace
		C <sub>5</sub>	41.50	M	3.77	156.46		
	Wall reinforcement	C <sub>6</sub>		M	2.03			
		B-1	240.9	M	0.88	211.99		
		B-2	76.8	M	2.72	208.90		
	2F. Floor	B-3	52.8	M	2.71	143.09		
RC floor S <sub>1</sub>			M <sup>2</sup>	13.16				
RC floor S <sub>2</sub>			M <sup>2</sup>	11.76		3,594.41		
Wood Work	Wood floor	88.20	M <sup>2</sup>	7.02	619.16			
	Head plate	102.50	M	0.41	42.03			
	Upper unit wall	3.50	M <sup>2</sup>	5.76	20.16		-incl. bolts + nuts	
	Other upper wall	14.57	M <sup>2</sup>	2.40	34.97			
	Upper staircase		Set					
	Upper WC/M		Set					
	Handrail	6	Unit	5.73	34.38			
Ceiling Work	Wooden rail	6	Unit	10.76				
	Pipe rail	6	Unit	35.32	211.92	962.62	-per horizontal M <sup>2</sup>	
Door & Window Work	Staircase Ceiling	Asbestos	M <sup>2</sup>	2.38				
	J <sub>11</sub>	6	Pc	18.005	108.03			
	J <sub>4'</sub>	6	Pc	7.320	43.92			
	J <sub>2</sub>	6	Pc	28.560	171.36			
	J <sub>10</sub>	6	Pc	30.225*	181.35			
	J <sub>12</sub>	6	Pc	17.600*	105.60			
Roof Work	J <sub>8</sub>	6	Pc	11.975	69.45			
	Lock + Hook	6+6	Pc	2.50+0.20	16.20	679.71		
	Rafter + Batten + Tile Ferlin	155.40	M <sup>2</sup>	4.535	704.74		-per horizontal M <sup>2</sup> (incl. laves)	
	Canopy		Set	115.95	115.95			
	Nok patent	24.00	M	2.00	48.00			
	Ridge column		M					
	Roof truss	119.50	M	1.44	172.08			
	Brace	48.00	Pc	0.45	21.60			
	Eaves fascia	105.60	M	0.35	36.96			
	Valley gutter		M	1.90				
Plumbing Work	Down pipe		M	1.80				
	Water-tightening	24.00	M	1.65	39.60			
	Collar	3	Pc	11.70	35.10	1,174.03		
	Water tub	6	Unit	5.50	33.00			
	Closet	6	Unit	7.00	42.00			
	Cleanout, Trap	12	Pc	3.00	36.00			
	Waste pipe	45.00	M	3.60	162.00			
	Water pipe	9.00	M	0.62	5.58			
	Water head	12	Pc	1.50	18.00			
	Kitchen sink	6	Unit	7.00	42.00			
	Connection pit	6	Unit	3.00	18.00	356.58		
Electrical Work	Fixture etc.	6	Unit	42.00	252.00	252.00	-See. electricity cost	
	Power intake		Unit					
Outside Work	Step plate + gutter plate	4+2	Pc	0.30+0.90	3.00			
	Fence		M	1.61		3.00	-incl. foundation -incl. each item	
Painting	Painting		M <sup>2</sup>					
	Guard	6	Unit	1.20	7.20			
Other Work	Cleaning	6	Unit	0.45	2.76			
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56		
Total		7,101.06 Rp/Building × 1.1 i ( 6 ) Unit = 1,301.66 ×10 <sup>3</sup> Rp/Unit i 38 M <sup>2</sup> = 34.26 ×10 <sup>3</sup> Rp/M <sup>2</sup>						

M-45A ( 6 Unit/Building)						FLOOR AREA	NET 50.00 M <sup>2</sup>	GROSS 50.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	6	Unit	0.90	5.40	62.94	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp. water	6	Unit	1.20	7.20			
	Grading	-	-	-	-			
	Setting & staking out	174.50	M	0.175	30.54			
	Scaffolding	6	Unit	4.50, 9.00	27.00			
Earth Work	Insectisidation		M	1.26				
Masonry & Concrete Work	Foundation	F <sub>1</sub>	M	5.96		4,152.72	-incl. horizontal RC-brace	
		F <sub>2</sub>	153.50	M	3.33			511.16
		F <sub>3</sub>		M	3.07			
		F <sub>4</sub>		M	2.69			
	1F. Floor	Slab on grade	177.96	M <sup>2</sup>	1.79			318.55
		Soil floor		M <sup>2</sup>	0.11			
	Ridge stone	F <sub>5</sub>		M	0.72			
		F <sub>6</sub>	18.00	M	0.47			8.46
		F <sub>7</sub>	508.00	M <sup>2</sup>	2.99			1,518.92
	Concrete block	HB-15		M <sup>2</sup>	2.27			
		HB-10		M <sup>2</sup>	0.92			
		Finish plaster		M <sup>2</sup>				
	RC-Course	WC/M floor mortar	62.88	M <sup>2</sup>	1.34			84.26
		C <sub>1</sub>		M	3.81			
		C <sub>2</sub>		M	2.92			
		C <sub>3</sub>	324.87	M	2.38			773.19
		C <sub>4</sub>	88.00	M	3.37			296.56
		C <sub>5</sub>	31.00	M	3.77			116.87
	Wall reinforcement	C <sub>6</sub>		M	2.03			
		B <sub>1-1</sub>	336.90	M	0.88			296.47
		B <sub>1-2</sub>	68.80	M	2.72			187.14
	2F. Floor	B <sub>1-3</sub>	41.60	M	2.71			112.74
		RC floor S <sub>1</sub>		M <sup>2</sup>	13.16			
		RC floor S <sub>2</sub>		M <sup>2</sup>	11.76			
Wood floor		121.28	M <sup>2</sup>	7.02	851.39			
Wood Work	Upper wall etc.	Head plate	125.00	M	0.41	51.25	-incl. bolts + nuts	
		Upper unit wall	16.15	M <sup>2</sup>	5.76	93.02		
		Other upper wall	48.88	M <sup>2</sup>	2.40	117.31		
		Upper staircase		Set		18.81		
	Handrail	Upper WC/M		Set				
		Wooden rail	6	Unit	5.73	34.38		
		Pipe rail		Unit	10.76			
		Staircase (Wooden)	6	Unit	35.32	211.92		
Ceiling Work	Ceiling		M <sup>2</sup>	2.38		1,178.08	-per horizontal M <sup>2</sup>	
Door & Window Work	Asbestos		M <sup>2</sup>					
	J <sub>1</sub> -12×16.63	J <sub>1</sub> -6×8.64	Pc					
	J <sub>4</sub> -6×7.32	J <sub>4</sub> -12×16.10	Pc					
	J <sub>2</sub> -6×11.74	J <sub>2</sub> -6×7.77	Pc					
	J <sub>3</sub> -12×15.39	J <sub>3</sub> -12×11.58	Pc					
	J <sub>5</sub> -6×18.01		Pc					
	Lock + Hook	6×6	Pc	2.50+0.20	16.20	1,053.48	-per horizontal M <sup>2</sup> (incl. laves)	
Roof work	Rafter + Batten + Tile	191.40	M <sup>2</sup>	5.82	1,113.95			
	Canopy	3	Set	19.59	58.77			
	Ridge tile	24.00	M	1.04	24.96			
	Ridge column	1,10pc×1.6Pc	Pc	1.71, 44.72	52.17			
	Ridge board	24.00	M	1.52	36.48			
	Brace	16	Pc	4.00	64.00			
	Eaves fascia	130.00	M	0.35	45.50			
	Valley gutter		M	3.90				
	Down pipe		M	1.80				
	Water-tightening	136.60	M	1.65	225.39			
	Collar		Pc			1,628.22		
Plumbing Work	Water tub	6	Unit	5.50	33.00			
	Closet	6	Unit	7.00	42.00			
	Cleanout, Trap	12	Pc	3.00	36.00			
	Waste pipe	42.00	M	3.60	151.20			
	Water pipe	42.00	M	0.62	26.04			
	Water head	12	Pc	1.50	18.00			
	Kitchen sink	6	Unit	7.00	42.00			
	Connection pit	6	Unit	3.00	18.00	366.24		
Electrical Work	Fixture etc.	6	Unit	42.00	252.00			
	Power intake	-	Unit	-	-	252.00	-See. electricity cost	
Outside Work	Step plate + gutter plate	30×12	Pc	0.30+0.90	19.80			
	Fence		M	1.61		19.80	-incl. foundation -incl. each item	
Painting	Painting		M <sup>2</sup>					
	Guard	6	Unit	1.20	7.20			
Other Work	Cleaning	6	Unit	0.45	2.76			
	ALAP Keselamatan Kerja	6	Unit	0.60	3.60	13.56		
Total		8,927.28 Rp/Building × 1.1 + ( 6 ) Unit = 1,636.67 ×10 <sup>3</sup> Rp/Unit + 50 M <sup>2</sup> = 32.73 ×10 <sup>3</sup> Rp/M <sup>2</sup>						

FS'-2-36 (5.4M) (12 Unit/Building)							FLOOR AREA	NET 35.70 M <sup>2</sup>	
							GROSS 37.80 M <sup>2</sup>		
Section	Item	Volume	Unit	Unit cost x10 <sup>3</sup> Rp	Cost x10 <sup>3</sup> Rp	Sub-total x10 <sup>3</sup> Rp	Note		
Temporary work	Warehouse	12	Unit	0.90	10.80		-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work		
	Temp. water	12	Unit	1.20	14.40				
	Grading	-	-	-	-				
	Setting & staking out	230.80	M	0.175	40.39				
Earth Work	Scaffolding	12	Unit	4.50, 9.00	108.00	173.59			
	Insecticidation		M	1.2%					
Masonry & Concrete work	Foundation	F <sub>1</sub>	198.70	M	5.96	1,184.25	-incl. horizontal RC-brace		
		F <sub>2</sub>	28.20	M	3.33	93.91			
		F <sub>3</sub>	3.90	M	3.07	11.97			
		F <sub>4</sub>		M	2.69				
	1F. Floor	Slab on grade	226.44	M <sup>2</sup>	1.79	405.33			
		Soil floor		M <sup>2</sup>	0.11				
	Ridge stone	F <sub>5</sub>		M	0.72				
		F <sub>6</sub>	41.50	M	0.47	20.45			
	Concrete block	HD-15	596.32	M <sup>2</sup>	2.99	1,783.00			
		HD-10		M <sup>2</sup>	2.27				
		Finish plaster		M <sup>2</sup>	0.92				
	RC-Course	WC/H floor mortar	121.80	M <sup>2</sup>	1.34	163.21			
		C <sub>1</sub>	230.50	M	3.81	878.21			
		C <sub>2</sub>	308.36	M	2.92	900.41			
		C <sub>3</sub>		M	2.38				
		C <sub>4</sub>		M	3.37				
		C <sub>5</sub>		M	3.77				
	Wall reinforcement	C <sub>6</sub>		M	2.03				
		C	237.60	M	1.44	342.14			
		B -1	198.00	M	0.88	174.24			
		C -2	96.00	M	3.92	376.32			
		B	68.00	M	2.72	184.96			
		C -3	48.60	M	4.37	209.76			
	2F. Floor	B	40.00	M	2.71	108.40			
		RC floor S <sub>1</sub>	21.94	M <sup>2</sup>	13.16	315.05			
		RC floor S <sub>2</sub>	168.84	M <sup>2</sup>	11.76	1,985.56		9,137.17	
		Wood floor		M <sup>2</sup>	7.02				
	Wood work	Upper wall etc.	Head plate	156.10	M	0.41		64.00	
			Upper unit wall	14.00	M <sup>2</sup>	5.76		80.64	
			Other upper wall	72.21	M <sup>2</sup>	2.40		173.30	
Upper staircase				Set		18.93			
Upper WC/H				Set					
Handrail		Wooden rail		Unit					
		Pipe rail	6	Unit	8.37	50.22			
Staircase		(Wooden)	1	Unit	41.69	125.07	512.16		
		(Wooden)		M <sup>2</sup>	2.38				
Ceiling Work		Ceiling	Asbestos						
	J <sub>1</sub> 6x18.48		J <sub>1</sub> 6x14.23	Pc					
	J <sub>1</sub> 6x20.995		J <sub>1</sub> 6x17.73	Pc					
	J <sub>1</sub> 30x16.63		J <sub>1</sub> 6x27.23	Pc					
	J <sub>1</sub> 6x24.86		J <sub>1</sub> 24x18.01	Pc					
	J <sub>1</sub> 6x28.56		J <sub>1</sub> 12x5.11	Pc			1,962.69		
	Lock + Hook	12x18	Pc	2.50x0.20	33.60	1,996.29			
	Rafter + Batten + Tile	291.06	M <sup>2</sup>	5.82	1,693.97		-per horizontal M <sup>2</sup> (incl. laves)		
	Roof Work	Canopy							
			Ridge tile	12.40	M	1.04	33.70		
Ridge column			7.00	Pc	1.71, 4x1.79	31.68			
Ridge board			32.40	M	1.52	49.25			
Brace			7	Pc	4.00	28.00			
Eaves fascia			116.20	M	0.35	47.67			
Valley gutter				M	3.90				
Down pipe				M	1.80				
Water-tightening			120.60	M	1.65	198.99	2,220.24		
Collar				Pc					
Plumbing Work	Water tub		12	Unit	5.50	66.00			
		Closet	12	Unit	7.00	84.00			
		Cleanout, Trap	30	Pc	3.00	90.00			
		Waste pipe	87.00	M	3.60	313.20			
		Water pipe	63.00	M	0.62	39.06			
		Water head	24	Pc	1.50	36.00			
		Kitchen sink	12	Unit	7.00	84.00			
		Connection pit	6	Unit	3.00	18.00	730.26		
		Fixture etc	12	Unit	42.00	504.00	504.00		
		Power intake		Unit					
Outside Work	Step plate + gutter plate		60x24	Pc	0.30x0.90	39.60			
		Fence	56.00	M	1.61	90.16			
Painting	Guard			M <sup>2</sup>					
			12	Unit	1.20	14.40			
Other Work	Cleaning		12	Unit	0.46	5.52			
			12	Unit	0.60	7.20	27.12		

Total 15,430.59 Rp/Building = 1.1 t (12) Unit = 1,414.47 x10<sup>3</sup>Rp/Unit t 37.8 M<sup>2</sup> = 37.42 x10<sup>3</sup>Rp/M<sup>2</sup>

33.6 47.10

PS-2-26 (12 Unit/Building)						FLOOR AREA	NET 25.90 M <sup>2</sup>	GROSS 28.00 M <sup>2</sup>
Section	Item	Volume	Unit	Unit cost ×10 <sup>3</sup> Rp	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	Note	
Temporary Work	Warehouse	12	Unit	0.90	10.80	161.46	-See. land development -per wall length (M) -only for 2F -Other cost incl. foundation and floor work	
	Temp. water Grading	12	Unit	1.20	14.40			
	Setting & staking out	161.50	M	0.175	28.26			
	Scaffolding	12	Unit	4.50, 9.00	108.00			
Earth Work	Insectisidation	-	M	1.26				
Masonry & Concrete Work	Foundation	F <sub>1</sub>	152.50	M	5.96	908.90	-incl. horizontal RC-brace	
		F <sub>2</sub>	9.00	M	3.33	29.97		
		F <sub>3</sub>	3.90	M	3.07	11.97		
		F <sub>4</sub>	-	M	2.69			
	1F. Floor	Slab on grade	204.90	M <sup>2</sup>	1.79	366.77		
		Soil floor	-	M <sup>2</sup>	0.11			
	Ridge stone	F <sub>1</sub>	-	M	0.72			
		F <sub>2</sub>	36.61	M	0.47	17.30		
	Concrete block	HB-15	407.02	M <sup>3</sup>	2.99	1,216.99		
		HB-10	14.04	M <sup>3</sup>	2.27	31.87		
		Finish plaster WC/M floor mortar	123.12	M <sup>2</sup>	1.34	164.98		
	RC-Course	C <sub>1</sub>	156.10	M	3.81	594.74		
		C <sub>2</sub>	203.41	M	2.92	593.96		
		C <sub>3</sub>	-	M	2.38			
		C <sub>4</sub>	-	M	3.37			
		C <sub>5</sub>	-	M	3.77			
	Wall reinforcement	C <sub>6</sub>	-	M	2.03			
		C -1	115.20	M	1.44	165.89		
		B	96.00	M	0.88	84.48		
		C -2	24.00	M	1.92	46.08		
		B	20.00	M	2.72	54.40		
	2F. Floor	C -3	48.00	M	4.37	209.76		
		B	40.00	M	2.71	108.40		
		RC floor S <sub>1</sub>	29.97	M <sup>2</sup>	13.16	394.41		
RC floor S <sub>2</sub>		114.57	M <sup>2</sup>	11.76	1,347.34			
Wood floor		-	M <sup>2</sup>	7.02				
Wood Work	Upper wall etc.	Head plate	141.10	M	0.41	57.85	-incl. bolts + nuts	
		Upper unit wall	14.00	M <sup>2</sup>	5.76	80.64		
		Other upper wall	66.50	M <sup>2</sup>	2.40	159.60		
		Upper staircase	-	Set	-	18.93		
	Handrail	Upper WC/M	-	Set	-			
		Wooden rail	-	Unit	-			
		Pipe rail	-	Unit	10.76			
	Ceiling Work	Staircase (Wooden)	3	Unit	41.69	125.07		
		Ceiling Asbestos	3	M <sup>2</sup>	2.38	7.14		
	Door & Window Work	Lock + Hook	J <sub>1</sub> *6*31.57	J <sub>2</sub> *11.58	Pc			941.22
J <sub>2</sub> *6*18.48				Pc				
J <sub>1</sub> *6*21.00				Pc				
J <sub>2</sub> *6*21.17				Pc				
J <sub>3</sub> *6*16.63				Pc				
J <sub>4</sub> *6*24.86				Pc				
Roof Work	Rafter + Batten + Tile	225.72	M <sup>2</sup>	5.82	1,313.69	-per horizontal M <sup>2</sup> (incl. laves) L = 1.9M		
	Canopy	-	Set	-	90.90			
	Ridge tile	24.00	M	1.04	24.96			
	Ridge column	7	Pc	1.91, 44+1.79	31.68			
	Ridge board	24.00	M	1.53	36.48			
	Brace	7	Pc	4.00	28.00			
	Eaves fascia	99.00	M	0.35	34.65			
	Valley gutter	-	M	3.90				
	Down pipe	-	M	1.80				
	Water-tightening	115.80	M	1.65	191.07			
	Collar	-	Pc	-				
	Plumbing Work	Water tub	12	Unit	5.50		66.00	712.26
Closet		12	Unit	7.00	84.00			
Cleanout, Trap		24	Pc	3.00	72.00			
Waste pipe		87.00	M	3.60	313.20			
Water pipe		63.00	M	0.62	39.06			
Water head		24	Pc	1.50	36.00			
Kitchen sink		12	Unit	7.00	84.00			
Connection pit		6	Unit	3.00	18.00			
Electrical Work	Fixture etc.	12	Unit	42.00	504.00	-See. electricity cost		
	Power intake	-	Unit	-				
Outside Work	Step plate + gutter plate	60+24	Pc	0.30+0.90	39.60	-incl. foundation -incl. each item		
	Fence	56.00	M	1.61	90.16			
Other Work	Painting	-	M <sup>2</sup>	-				
	Guard	12	Unit	1.20	14.40			
	Cleaning	12	Unit	0.46	5.52			
	ALAF Kesulamato Karja	12	Unit	0.60	7.20	27.12		
Total		11,099.05 Rp/Building × 1.1 + (12) Unit = 1,017.41 × 10 <sup>3</sup> Rp/Unit + 28 M <sup>2</sup> = 36.34 × 10 <sup>3</sup> Rp/M <sup>2</sup>						



I-9 COST DATA FOR WALK-UP FLAT

FS'5-24		FLOOR AREA		NET		26.18 M <sup>2</sup>	
				GROSS		30.80 M <sup>2</sup>	
Items		Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.				3.75	27.76	
	Setting & staking out	0.26	2.11	M	0.55		
	Scaffolding	0.80	29.33	M <sup>2</sup>	23.46		
Earth Work & IFL. Floor Work	Excavation	0.42	5.87	M <sup>3</sup>	2.47	24.79	
	Backfilling	0.10	4.68	M <sup>3</sup>	0.47		
	Sand bedding	5.60	0.28	M <sup>3</sup>	1.57		
	Batukali bedding	9.40	0.54	M <sup>3</sup>	5.08		
	IFL. concrete slab	22.35	0.54+0.14 =0.68	M <sup>3</sup>	15.20		
Structural Work						1,348.03	
Outer Wall Work	Doors & windows				119.59	137.58	
	Brick exposure	5.45	3.30	M <sup>2</sup>	17.99		
Inside Door & Partition						71.71	
Concrete Block and other Mortar Work	Concrete block t=100	2.27	21.36	M <sup>2</sup>	48.49	101.40	
	Light-weight concrete t=120	2.68	3.78	M <sup>2</sup>	10.13		
	Floor mortar t=30	0.84	28.70	M <sup>2</sup>	24.11		
	Water proof mortar t=30	1.23	15.18	M <sup>2</sup>	18.67		
Roof Work						106.55	
Miscellaneous Work	Outside painting	1.00	14.18	M <sup>2</sup>	14.18	43.68	
	Veranda screen						
	Handrail	10.76	2.00	M	21.52		
	Gutter	1.90	4.20	M	7.98		
Equipment Work	Plumbing				41.16	83.16	
	Electricity				42.00		
Cleaning & Safety Work					2.26	2.26	
Total	1,946.92 × 1.1 = 2,141.61 ×10 <sup>3</sup> Rp/unit				NET.	81.80	×10 <sup>3</sup> Rp/M <sup>2</sup>
					GROSS	69.53	×10 <sup>3</sup> Rp/M <sup>2</sup>

FS'5-36			FLOOR AREA	NET	38.78	M <sup>2</sup>	
				GROSS	43.40	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	35.96		
	Setting & staking out	0.26	2.83	M		0.74	
	Scaffolding	0.80	39.34	M <sup>2</sup>		31.47	
Earth Work & IFL. Floor Work	Excavation	0.42	8.27	M <sup>3</sup>	3.47	30.63	
	Backfilling	0.10	6.59	M <sup>3</sup>	0.66		
	Sand bedding	5.60	0.40	M <sup>3</sup>	2.24		
	Batukali bedding	9.40	0.75	M <sup>3</sup>	7.05		
	IFL. concrete slab	22.35	0.20+0.75 =0.77	M <sup>3</sup>	17.21		
Structural Work					1,858.48		
Outer Wall Work	Doors & windows			200.51	218.50		
	Brick exposure	5.45	3.30	M <sup>2</sup>		17.99	
Inside Door & Partition					139.67		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	22.80	M <sup>2</sup>	51.76	115.25	
	Light-weight concrete t=120	2.68	3.78	M <sup>2</sup>	10.13		
	Floor mortar t=30	0.84	41.30	M <sup>2</sup>	34.69		
	Water proof mortar t=30	1.23	15.18	M <sup>2</sup>	18.67		
Roof Work					140.04		
Miscellaneous Work	Outside painting	1.00	20.24	M <sup>2</sup>	20.24	63.40	
	Veranda screen	22.79	0.50		11.90		
	Handrail	10.76	2.00	M	21.52		
	Gutter	1.90	5.60	M	10.64		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.00			
Cleaning & Safety Work				2.26	2.26		
Total	2,687.35 × 1.1 = 2,956.09 ×10 <sup>3</sup> Rp/unit			NET	76.23	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	68.11	×10 <sup>3</sup> Rp/M <sup>2</sup>	

FS'5-45		FLOOR AREA	NET 46.84 M <sup>2</sup>			
			GROSS 51.46 M <sup>2</sup>			
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.			3.75	36.69	
	Setting & staking out	0.26	2.90	M		0.75
	Scaffolding	0.80	40.24	M <sup>2</sup>		32.19
Earth Work & IFL. Floor Work	Excavation	0.42	9.81	M <sup>3</sup>	4.12	41.47
	Backfilling	0.10	7.81	M <sup>3</sup>	0.78	
	Sand bedding	5.60	0.47	M <sup>3</sup>	2.63	
	Batukali bedding	9.40	0.90	M <sup>3</sup>	8.46	
	IFL. concrete slab	22.35	0.90+0.24 =1.14	M <sup>3</sup>	25.48	
Structural Work					2,176.90	
Outer Wall Work	Doors & windows			200.51	209.98	
	Brick exposure	5.45	4.02	M <sup>2</sup>		9.47
Inside Door & Partition					151.83	
Concrete Block and other Mortar Work	Concrete block t=100	2.27	27.35	M <sup>2</sup>	62.08	132.34
	Light-weight concrete t=120	2.68	3.78	M <sup>2</sup>	10.13	
	Floor mortar t=30	0.84	49.36	M <sup>2</sup>	41.46	
	Water proof mortar t=30	1.23	15.18	M <sup>2</sup>	18.67	
Roof Work					167.50	
Miscellaneous Work	Outside painting	1.00	20.44	M <sup>2</sup>	20.44	63.40
	Veranda screen	22.79	0.50		11.9	
	Handrail	10.76	2.00	M	21.52	
	Gutter	1.90	5.60	M	10.64	
Equipment Work	Plumbing			41.16	83.16	
	Electricity			42.00		
Cleaning & Safety Work				2.26	2.26	
Total	3,065.53 × 1.1 = 3,372.08 ×10 <sup>3</sup> Rp/unit			NET. 71.99	<10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS 65.53	<10 <sup>3</sup> Rp/M <sup>2</sup>	

FGS-36		FLOOR AREA		NET	38.88	M <sup>2</sup>
				GROSS	49.74	M <sup>2</sup>
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.			3.75	38.52	
	Setting & staking out	0.26	2.64	M 0.69		
	Scaffolding	0.80	42.60	M <sup>2</sup> 34.08		
Earth Work & IFL. Floor Work	Excavation	0.42	11.66	M <sup>3</sup> 4.90	41.37	
	Backfilling	0.10	9.32	M <sup>3</sup> 0.93		
	Sand bedding	5.60	0.52	M <sup>3</sup> 2.91		
	Batukali bedding	9.40	0.88	M <sup>3</sup> 8.27		
	IFL. concrete slab	22.35	0.88+0.21 =1.09	M <sup>3</sup> 24.36		
Structural Work					1,957.07	
Outer Wall Work	Doors & windows			152.52	172.52	
	Brick exposure	5.45	3.67	M <sup>2</sup> 20.00		
Inside Door & Partition					118.36	
Concrete Block and other Mortar Work	Concrete block t=100	2.27	33.19	M <sup>2</sup> 75.34	143.92	
	Light-weight concrete t=120	2.68	2.16	M <sup>2</sup> 5.79		
	Floor mortar t=30	0.84	35.52	M <sup>2</sup> 29.84		
	Water proof mortar t=30	1.23	26.79	M <sup>2</sup> 32.95		
Roof Work					133.44	
Miscellaneous Work	Outside painting	1.00	25.16	M <sup>2</sup> 25.16	142.72	
	Veranda screen	18.23	0.50	9.12		
	Handrail	10.76	8.81	M 94.80		
	Gutter	1.90	5.60	M 10.64		
	Corridor roof drain			3.00		
Equipment Work	Plumbing			41.16	83.16	
	Electricity			42.00		
Cleaning & Safety Work				2.26	2.26	
Total	2,833.34 × 1.1 = 3,116.67 ×10 <sup>3</sup> Rp/unit			NET.	80.16	×10 <sup>3</sup> Rp/M <sup>2</sup>
				GROSS	62.66	×10 <sup>3</sup> Rp/M <sup>2</sup>

FG5-45		FLOOR AREA		NET	48.06	M <sup>2</sup>	
				GROSS	58.92	M <sup>2</sup>	
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp		
Temporary Work	Warehouse, site office etc.			3.75	39.81		
	Setting & staking out	0.26	2.75	M		0.72	
	Scaffolding	0.80	44.18	M <sup>2</sup>		35.34	
Earth Work & IFL. Floor Work	Excavation	0.42	13.92	M <sup>3</sup>	5.85	49.36	
	Backfilling	0.10	11.14	M <sup>3</sup>	1.11		
	Sand bedding	5.60	0.62	M <sup>3</sup>	3.47		
	Batukali bedding	9.40	1.05	M <sup>3</sup>	9.87		
	IFL. concrete slab	22.35	$\frac{1.05+0.25}{=1.30}$	M <sup>3</sup>	29.06		
Structural Work					2,317.15		
Outer Wall Work	Doors & windows			191.51	218.27		
	Brick exposure	5.45	4.91	M <sup>2</sup>		26.76	
Inside Door & Partition					155.87		
Concrete Block and other Mortar Work	Concrete block t=100	2.27	34.68	M <sup>2</sup>	78.72	155.67	
	Light-weight concrete t=120	2.68	2.16	M <sup>2</sup>	5.79		
	Floor mortar t=30	0.84	43.0	M <sup>2</sup>	36.12		
	Water proof mortar t=30	1.23	28.49	M <sup>2</sup>	35.04		
Roof Work					153.08		
Miscellaneous Work	Outside painting	1.00	26.44	M <sup>2</sup>	26.44	160.14	
	Veranda screen	18.23	0.50		9.12		
	Handrail	10.76	10.31	M	110.94		
	Gutter	1.90	5.60	M	10.64		
	Corridor roof drain				3.00		
Equipment Work	Plumbing			41.16	83.16		
	Electricity			42.00			
Cleaning & Safety Work				2.26	2.26		
Total	$3,334.77 \times 1.1 = 3,668.25 \times 10^3 \text{Rp/unit}$			NET	76.33	×10 <sup>3</sup> Rp/M <sup>2</sup>	
				GROSS	62.26	×10 <sup>3</sup> Rp/M <sup>2</sup>	

FM6-36		FLOOR AREA		NET	38.70	M <sup>2</sup>
				GROSS	46.36	M <sup>2</sup>
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.			3.75		
	Setting & staking out	0.26	2.68	M	0.70	40.18
	Scaffolding	0.80	44.67	M <sup>2</sup>	35.74	
Earth Work & IFL. Floor Work	Excavation	0.42	8.41	M <sup>3</sup>	3.53	
	Backfilling	0.10	6.72	M <sup>3</sup>	0.67	
	Sand bedding	5.60	0.38	M <sup>3</sup>	2.13	31.27
	Batukali bedding	9.40	0.68	M <sup>3</sup>	6.39	
	IFL. concrete slab	22.35	0.68+0.15 =0.83	M <sup>3</sup>	58.55	
Structural Work					1,843.85	
Outer Wall Work	Doors & windows			241.55		
	Brick exposure	5.45	15.12	M <sup>2</sup>	82.40	323.95
Inside Door & Partition						77.54
Concrete Block and other Mortar Work	Concrete block t=100	2.27	23.05	M <sup>2</sup>	52.32	
	Light-weight concrete t=120	2.68	3.60	M <sup>2</sup>	9.65	
	Floor mortar t=30	0.84	13.65	M <sup>2</sup>	11.47	101.12
	Water proof mortar t=30	1.23	22.50	M <sup>2</sup>	27.68	
Roof Work					131.35	
Miscellaneous Work	Outside painting	1.00	11.70	M <sup>2</sup>	11.70	
	Veranda screen	13.67	1.0		13.67	
	Handrail	10.76	7.24	M	77.90	
	Gutter	1.90	5.60	M	10.64	318.60
	Wood floor + staircase				194.69	
	Roofdrain				10.00	
Equipment Work	Plumbing			41.16		83.16
	Electricity			42.0		
Cleaning & Safety Work				2.26	2.26	
Total	2,953.28 × 1.1 = 3,248.61 ×10 <sup>3</sup> Rp/unit			NET.	83.94	×10 <sup>3</sup> Rp/M <sup>2</sup>
				GROSS	70.07	×10 <sup>3</sup> Rp/M <sup>2</sup>

FM6-45		FLOOR AREA		NET		GROSS	
				46.80	M <sup>2</sup>	54.46	M <sup>2</sup>
Items		Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.				3.75	40.77	
	Setting & staking out	0.26	2.75	M	0.72		
	Scaffolding	0.80	45.38	M <sup>2</sup>	36.30		
Earth Work & 1FL. Floor Work	Excavation	0.42	9.95	M <sup>3</sup>	4.18	37.24	
	Backfilling	0.10	7.95	M <sup>3</sup>	0.80		
	Sand bedding	5.60	0.45	M <sup>3</sup>	2.52		
	Batukali bedding	9.40	0.81	M <sup>3</sup>	7.61		
	1FL. concrete slab	22.35	$\frac{0.81+0.18}{=0.99}$	M <sup>3</sup>	22.13		
Structural Work						2,132.81	
Outer Wall Work	Doors & windows				266.42	336.94	
	Brick exposure	5.45	12.94	M <sup>2</sup>	70.52		
Inside Door & Partition						97.68	
Concrete Block and other Mortar Work	Concrete block t=100	2.27	28.08	M <sup>2</sup>	63.74	117.04	
	Light-weight concrete t=120	2.68	3.96	M <sup>2</sup>	10.61		
	Floor mortar t=30	0.84	17.34	M <sup>2</sup>	14.57		
	Water proof mortar t=30	1.23	22.86	M <sup>2</sup>	28.12		
Roof Work						157.03	
Miscellaneous Work	Outside painting	1.00	11.97	M <sup>2</sup>	11.97	346.23	
	Veranda screen	18.23	1.00		18.23		
	Handrail	10.76	9.39	M	90.28		
	Gutter	1.90	5.60	M	10.64		
	Wood floor + staircase				205.11		
	Roofdrain				10.0		
Equipment Work	Plumbing				41.16	83.16	
	Electricity				42.00		
Cleaning & Safety Work					2.26	2.26	
Total	$3,351.16 \times 1.1 = 3,686.28 \times 10^3 \text{Rp/unit}$				NET.	78.77	×10 <sup>3</sup> Rp/M <sup>2</sup>
					GROSS	67.69	×10 <sup>3</sup> Rp/M <sup>2</sup>



FT5-36		FLOOR AREA		NET	36.90	M <sup>2</sup>
				GROSS	40.93	M <sup>2</sup>
Items	Unit cost ×10 <sup>3</sup> Rp	Volume	Unit	Cost ×10 <sup>3</sup> Rp	Sub-total ×10 <sup>3</sup> Rp	
Temporary Work	Warehouse, site office etc.			3.75		
	Setting & staking out	0.26	4.20	M	1.09	51.54
	Scaffolding	0.80	58.38	M <sup>2</sup>	46.70	
Earth Work & 1FL. Floor Work	Excavation	0.42	7.80	M <sup>3</sup>	3.28	36.67
	Backfilling	0.10	6.21	M <sup>3</sup>	0.62	
	Sand bedding	5.60	0.38	M <sup>3</sup>	5.98	
	Batukali bedding	9.40	0.71	M <sup>3</sup>	6.67	
	1FL. concrete slab	22.35	$\frac{0.71+0.19}{=0.90}$	M <sup>3</sup>	20.12	
Structural Work						1,874.10
Outer Wall Work	Doors & windows			126.79		238.68
	Brick exposure	5.45	20.53	M <sup>2</sup>	111.89	
Inside Door & Partition						76.79
Concrete Block and other Mortar Work	Concrete block t=100	2.27	26.90	M <sup>2</sup>	61.06	120.10
	Light-weight concrete t=120	2.68	2.63	M <sup>2</sup>	7.05	
	Floor mortar t=30	0.84	37.21	M <sup>2</sup>	31.26	
	Water proof mortar t=30	1.23	16.85	M <sup>2</sup>	20.73	
Roof Work						286.84
Miscellaneous Work	Outside painting	1.00	27.34	M <sup>2</sup>	27.34	85.33
	Veranda screen	22.79	0.50		11.90	
	Handrail	10.76	2.80	M	30.13	
	Gutter	1.90	8.40	M	15.96	
Equipment Work	Plumbing			41.16		83.16
	Electricity			42.00		
Cleaning & Safety Work				2.26		2.26
Total				NET.	85.12	×10 <sup>3</sup> Rp/M <sup>2</sup>
	2,855.47 × 1.1 = 3,141.02 ×10 <sup>3</sup> Rp/unit			GROSS	76.74	×10 <sup>3</sup> Rp/M <sup>2</sup>

The purpose of this study is to investigate the effects of various factors on the performance of a system. The study is organized as follows: Section 2 describes the methodology used in the study. Section 3 presents the results of the study. Section 4 discusses the implications of the findings. Section 5 concludes the study.

### Methodology

The study was conducted using a series of experiments. The first experiment was designed to measure the effect of factor A on the system's performance. The second experiment was designed to measure the effect of factor B on the system's performance. The third experiment was designed to measure the effect of factor C on the system's performance. The fourth experiment was designed to measure the effect of factor D on the system's performance.

The results of the first experiment showed that factor A had a significant positive effect on the system's performance. The results of the second experiment showed that factor B had a significant negative effect on the system's performance. The results of the third experiment showed that factor C had a significant positive effect on the system's performance. The results of the fourth experiment showed that factor D had a significant negative effect on the system's performance.

The results of the study indicate that factor A is a key factor in determining the system's performance. Factor B is a key factor in determining the system's performance. Factor C is a key factor in determining the system's performance. Factor D is a key factor in determining the system's performance.

The study has several limitations. First, the study only measured the effect of four factors on the system's performance. Second, the study only measured the effect of these factors on the system's performance at one point in time. Third, the study only measured the effect of these factors on the system's performance in a laboratory setting.

Future research should investigate the effects of these factors on the system's performance in a real-world setting. Future research should also investigate the effects of these factors on the system's performance over time. Future research should also investigate the effects of these factors on the system's performance in a variety of settings.

The study has several implications. First, the study shows that factor A is a key factor in determining the system's performance. Second, the study shows that factor B is a key factor in determining the system's performance. Third, the study shows that factor C is a key factor in determining the system's performance. Fourth, the study shows that factor D is a key factor in determining the system's performance.

The study has several conclusions. First, factor A is a key factor in determining the system's performance. Second, factor B is a key factor in determining the system's performance. Third, factor C is a key factor in determining the system's performance. Fourth, factor D is a key factor in determining the system's performance.

## 2 ROUGH STRUCTURAL CALCULATION (EXAMPLES)



# FS'5-36 WALK-UP FLATS

We will apply the Indonesian Standards 'NI-2' in principle, but when the relevant standards do not exist, we will refer to the Japanese Building Standards, etc.

## 1. STRUCTURAL PLANNING

### 1-1 PLANNING POLICY

#### Super structure

This building is a five storied reinforced concrete above the ground, consisting of 6 units per floor; and pure Rahmen structure with spans of 2.5 m width and 3.5 m depth. It is desirable to avoid irregular surfaces in rooms for better use of space. Also the types of columns used -, L and T are suited to room arrangement, and - shaped columns only supply bending resistance in one direction. Thus, caution shall be taken as to the direction of columns. In addition, column thickness on each floor makes minimum size enough to be able to place concrete to a height of 2.8 m. And the changing length of columns on each floor shall correspond to the stresses. Each floor will be of concrete but will likely be made thin to lighten the structure. The roof will consist of roof tiles and wooden truss beams, and horizontal bracing will be provided to maintain horizontal rigidity and to prevent spiral grain twist.

#### Sub-structure

Underground beams are being considered as a measure against bending stress due to unexpected settlement and the ratio of rigidity with the columns of upper structure, and for maintaining the stability of the whole building, supposing it is larger than upper beams. Also, the first floor slab is a slab on grade. The foundation should be of isolated footings and should maintain sufficient rigidity and bending bearing capacity in order to transmit the upper load to the piles. The piles to be used will be of reinforced concrete cast in place by the formwork method. Piles will be driven by Drop-hammer, or Diesel-hammer, etc. because the bearing layer is located from 10 m to 15 m below the ground, and concrete of high strength ( $f_c=400 \text{ kg/cm}^2$ ) is used to protect the pile head from damage. The amount of additional tensile reinforcement is more than 0.8 %, increasing the bending bearing capacity of piles.

## 2. ALLOWABLE UNIT STRESS OF MATERIALS

Concrete (Refer to 'NI-2')

	Unit: $\text{kg/cm}^2$					
	Permanent stress			Temporary stress		
	Compression	Tension	Shearing	Compression	Tension	Shearing
$\delta'bk$	$0.33\delta'bk$	$0.36\sqrt{\delta'bk}$	$0.43\delta'bk$	$0.56\delta'bk$	$0.51\sqrt{\delta'bk}$	$0.68\delta'bk$
175	60	5	5.5	100	6.5	9

Reinforcing Bar (Refer to 'NI-2')

Kind	Unit: $\text{kg/cm}^2$	
	Permanent stress	Temporary stress
u-24	1,400	2,000

Cast-in-situ Pile

Unit: ton/pile

Section (cm)	Permanent stress		Temporary stress	
	Boring No.1	Boring No.2	Boring No.1	Boring No.2
25 x 25	19.2	27.0	Double of permanent stress, respectively	
30 x 30	27.2	40.5		

Note: Basic data for the design of pile driving footings; The bearing capacity of piles should be 1/3 of ultimate bearing capacity (Ru) obtained from the bearing capacity formula.

$$R_u = 30\bar{N} \cdot A_p + 1/5 \cdot \bar{N}_s \cdot \psi \cdot L_s = \bar{q}_u/2 \cdot \psi \cdot L_c \quad \dots\dots (1)$$

- $\bar{N}$  : Tip Resistance                       $b, A_p$ : Total Area of Tip of Pile ( $m^2$ )
- $c, \bar{N}_s$ : Average measured N value for the loose portion of earth around the piles
- $L_s$  : Length of Pile in the loose portion
- $q_u$  : Averaged Axial Compression Strength for clay portion around the piles
- $L_c$  : Length of Pile in the clay portion
- $\psi$  : Length of periphery of pile (m)

Here,  $\bar{N} \leq 60, \bar{N}_s/5 \leq 10 \text{ t/m}^2, \bar{q}_u/2 \leq 10 \text{ t/m}^2$ .

3. LOAD

i) Dead load

roof (tile) (average 20 mm)	40 kg/m <sup>2</sup>
Truss for gable roof	20 "
2 ~ 4 <sup>F</sup> slab (100 mm)	240 "
1 <sup>F</sup> slab: slab on grade	-


ii) Table for load

Contents			For floor	For frame	For earthquake
roof	tile (20 mm)	40	D.L	60	60
	truss	20	B	-	70
		60	L.L	-	-
			60	130	130
each floor	monolithic finish 5 mm	12	D.L	252	252
	slab	240	B	-	70
		252	L.L	200	140
			452	462	382
W.C mandy	cinder concrete (150 mm) slabe	225	D.L	465	465
		240	B	-	70
		465	L.L	200	140
			665	675	595
stairway	slab (220 mm)	528	D.L	528	528
			B	-	-
			L.L	200	150
			728	668	588


iii) Walls

Bamboo mat (double)	10 kg/m <sup>2</sup>
Concrete block (100 mm)	200 "


PLAN




SECTION




FLAME



line A,B,C





line 1,2




line 3

iv) Columns



v) Girders

general girder      288 "



ground-girdes      840 "

4. C, Mo, Q

	Diagram	Floor	Contents
Line x <sub>2</sub>	<p>385 (ly)</p>	2 ~ 5	$l_x = 2.5$ $\lambda = 1.54$ $l_y = 3.85$ $w = 0.462 \text{ t/m}^2$ $c = (1.3) \times 0.462 \times 2 = 1.2 \text{ tm}$ $M_0 = (2.1) \times 0.462 \times 2 = 1.94 \text{ tm}$ $Q = (1.65) \times 0.462 \times 2 = 1.53 \text{ t}$
	<p>0.2 t/m 385</p>	R	$c = \frac{1}{12} \times 0.2 \times 3.85^2 = 0.25 \text{ tm}$ $M_0 = 1.5 \times c = 0.37 \text{ tm}$ $Q = 0.39 \text{ t}$
	<p>250</p>	2 ~ 5	$l_x = 2.5$ $\lambda = 1.0$ $w = 0.462 \text{ t/m}^2$ $c = (0.4) \times 0.462 = 0.19 \text{ tm}$ $M_0 = (0.65) \times 0.462 = 0.30 \text{ tm}$ $Q = (0.80) \times 0.462 = 0.37 \text{ t}$



	Diagram	Floor	Contents
Line B		R	$w = 0.2 \text{ t/m}$ $c = \frac{1}{12} \times 0.2 \times 2.5^2 = 0.11 \text{ tm}$ $M_o = 0.17 \text{ tm}$ $Q = 0.25 \text{ t}$

5. PERMANENT STRESS

Omitted because stress is small

6. COLUMN AXIAL LOAD


							Unit; ton	
C	Floor	Position	Contents		Sub-total	Total		
3-B	5	roof block	0.13 x 2.45 x 3.5 0.20 x 2.0 x (1.59 + 1.2 + 0.9)	1.12 1.48	2.60	2.60		
	4	mandy living room block stairway column	0.675 x 1.59 x 1.2 0.462 x 3.5 x 1.25 0.2 x (1.59 + 1.2 + 0.9) x 2.8 0.668 x 1.2 x 1.92 0.675 x 2.8	1.29 2.02 2.07 1.54 1.89	8.81	11.41		
	3		the same to above		"	20.22		
	2		"		"	29.03		
	1		"		"	37.84		
	Footings		mandy living room " ground-girder footing	0.675 x 1.59 x 1.2 0.462 x 3.5 x 1.25 0.462 x 3.5 x 1.25 2.4 x 1.2 x 0.2 x (3.5 + 3.7) 0.5 x 0.8 x 1.5 x 2.4	1.29 2.02 1.06 4.20 1.44	10.00	47.84	
2-B	5	roof partition	0.13 x 3.5 x 2.5 0.01 x 2.0 x (3.5 + 1.25)	1.14 0.10	1.15	1.15		
	4	room wall column	0.462 x 3.5 x 2.5 0.01 x 2.8 x (3.5 + 1.25) 0.48 x 2.8	4.07 0.13 <sup>3</sup> 1.35	5.56	6.71		
	3		The same above		5.56	12.27		
	2		"		5.56	17.83		
	1		"		5.56	23.39		
	Footings		living room ground-girder footing	0.462 x 3.5 x 2.5 0.576 x (3.5 + 2.5)	4.07 4.00 1.44	10.11	33.50	
1-B	5	roof block	0.13 x 3.5 x 2.5 0.20 x (3.5 x 2.0)	1.14 1.40	2.54	2.54		
	4	living room wall block column	0.462 x 3.5 x 2.5 0.01 x 2.5 x 2.8 0.2 x 2.8 x 3.5 0.48 x 2.8	4.07 0.07 1.96 1.35	7.45	10.0		
	3		The same above		7.45	17.45		
	2				7.45	24.90		
	1				7.45	32.35		

Unit; ton

C	Floor	Position	Contents		Sub-total	Total
	Footings	floor	0.462 x 3.5 x 2.5	4.07	10.11	42.46
		ground-girder	0.576 x (3.5 + 2.5)	4.60		
	footings		1.44			
3-C	5	roof block	0.13 x 2.6 x 2.5 0.2 x 2.0 x 2.5	0.845 1.00	1.85	1.85
	4	mandy living room block column	0.675 x 1.2 x 1.575 0.462 x 1.25 x 1.575 0.2 x (2.4 + 1.0) x 2.8 0.48 x 2.8	1.28 0.91 1.91 1.31	5.44	7.29
	3		The same above		5.44	12.73
	2		"		5.44	18.17
	1				5.44	23.61
	Footings	mandy living room ground-girder footings	0.675 x 1.2 x 1.575 0.462 x 1.25 x 1.575 0.576 x (2.4 + 1.575)	1.28 0.91 2.29 1.44	5.91	29.52
		5	roof block	0.13 x 2.4 x 2.6 0.2 x 2.0 x (1.93 + 1.25)	0.82 1.27	2.10
3-A	4	living room stairway block column	0.462 x 1.25 x 1.93 0.668 x 1.2 x 1.92 0.2 x 2.8 x (1.93 + 1.25) 0.675 x 2.8	1.12 1.54 1.78 1.89	6.33	8.43
	3		The same above		6.33	14.76
	2				6.33	21.10
	1				6.33	27.42
	Footings	living room ground-girder	0.462 x 1.25 x 1.93 0.668 x 1.2 x 1.93 0.576 x (2.4 + 1.93)	1.12 1.55 2.49 1.44	6.60	34.02
		5	roof block	0.13 x 2.5 x 1.93 0.2 x 2.0 x (1.93 + 2.5)	0.63 1.77	2.41
1-A	4	living room block column	0.462 x 2.5 x 1.93 0.2 x (2.5 + 1.93) x 2.8 1.48 x 2.8	2.23 2.48 1.35	6.06	8.47
	3		The same above		6.06	14.53
	2				6.06	20.60
	1				6.06	26.65
	Footings	living room ground-girder footings	0.462 x 2.5 x 1.93 0.576 x (2.5 + 1.93)	2.23 2.55 1.44	6.22	32.87

Diagram for foundation axial load

COLUMN AXIAL LOAD ( ) shows axial load for footing



7. SEISMIC LOAD

Calculated on 6 units per building

Floor	Position	Contents		Sub-total	Total
5	roof (tile)	$0.04 \times (7.0 + 2.0) \times (6.2 \times 6 + 2) \times 1.3$	16.00	19.62	35.62
	block (out)	$0.2 \times 2.0 \times (3.7 \times 2 \times 6)$	17.76		
	(in)	$0.2 \times 2.0 \times 2.5 \times 2 \times 4$	8.00		
		$0.2 \times 2.0 \times 2.0 \times 2 \times 6$	9.60		
		$0.2 \times 2.0 \times (1.8 \times 3 + 2.4 + 1.4)$	3.68		
	partition	$0.01 \times 2.0 \times (2.85 + 2.15 + 1.5 + 3.0)$	0.19		
4	Floor	$0.38 \times (7.0 \times 5.0) \times 6$	80.22	107.96	156.02
	L.room	$0.382 \times 1.35 \times 1.2 \times 6$	3.72		
	M/W	$0.595 \times 1.8 \times 2.4 \times 3$	7.72		
	stairway	$0.588 \times 2.4 \times 3.85 \times 3$	16.30		
	column				
1	-type	$0.288 \times 2.8 \times 2$	1.62	28.44	164.84
	L,T type	$0.24 \times 2.8 \times 8$	10.76		
	T type	$0.672 \times 2.8 \times 2$	3.77		
	wall				
	block (out)	$0.20 \times (2.8-1.0) \times 3.7 \times 2 \times 6$	16.00		
	(in)	$0.20 \times (2.8-0.5) \times 2.5 \times 2 \times 4$	9.28		
	$0.20 \times (2.8-0.5) \times 2.0 \times 2 \times 6$	11.04			
partition	$0.20 \times (2.8-0.5) \times (1.8 \times 3 + 2.4 + 1.4)$	4.24			
	$0.01 \times 2.8 \times (2.85 + 2.15 + 1.5 + 3.0)$	0.27			
			28.44		

Floor	HM	K	W	KW	EkW
5	14.6	0.15	35.62	5.35	5.35
4	12.2	0.14 <sup>3</sup>	156.02	22.31	27.66
3	9.4	0.13 <sup>4</sup>	164.84	22.09	49.75
2	6.6	0.10	164.84	16.49	66.24
1	3.8	0.10	164.84	16.49	82.73

Here:


$$10^4 < H, K_0 = 0.1$$

$$K_{th}/K_{bh} = 1 + 0.5H$$

$$K_{bh} = \frac{1}{10 + 0.1 \times H}$$


$K_{th}$ : Top floor

$K_{bh}$ : Base floor



### 8. RATIO OF DISTRIBUTION FOR COLUMNS


This is based on the Muto's D method and the following values are estimated: That is, the exterior column is 0.5, inside column is 1.0 ~ 0.7, inflection point is 0.3 at highest floor, 0.5 at middle floors and 0.7 at lowest floor.



Shearing stress shared at D = 1.0

Floor	ΣK·W	X-Direction		Y-Direction	
		ΣDx	Ekw/ΣDx	ΣDy	Ekw/ΣDy
5	5.35	39.6	0.14	40.2	0.14
4	27.66	"	0.70	"	0.69
3	49.75	"	1.26	"	1.24
2	66.24	"	1.68	"	1.65
1	82.73	"	2.10	"	2.06

9. SEISMIC STRESS



MOMENT STRESS DIAGRAMME

10. CROSS SECTION

1) Girder (Both X & Y-Direction)

RF SM = 0.25 ± 1.09 = 1.34 tm  
 sQ = 0.39 ± 0.1 = 0.49 t

18C x 40C j = 7/8 x 35 = 30.6 ft·j = 2.0 x 30.6 = 61.2  
 at =  $\frac{1.34 \cdot 10^2}{61.2} = 2.2 \text{ cm}^2$  2 - 16φ

$\tau = \frac{0.49 \cdot 10^3}{18 \times 30.6} = 0.9 \text{ kg/cm}^2, < 5.5$

5F SM = 1.2 ± .55 = 1.75 tm  
 xQ = 1.53 ± .62 = 2.15 t

18C x 40C  
 at = 2.9 cm<sup>2</sup>  
 $\tau = \frac{2.15 \cdot 10^3}{18 \times 30.6} = 3.91 \text{ kg/cm}^2, < 5.5$  2 - 16φ


4 ~ 2F  
 SM = 1.2 ± 2.4 = 3.6 tm  
 sQ = 1.53 ± 2.0 = 3.53 t  
18C x 60C j = 7/8 x 55 = 48 ft·j = 2.0 x 48 = 96  
 at =  $\frac{3.6 \cdot 10^2}{96} = 3.75 \text{ cm}^2$  2 - 16φ  
 $\tau = \frac{3.53 \cdot 10^3}{18 \times 48} = 4.1 \text{ kg/cm}^2, < 5.5$

1F

$sM = 1.8 \text{ tm}$

$sQ = 1.45 \text{ t}$

$25C \times 80C \quad j = 7/8 \times 74 = 65 \quad ft \cdot j = 2.0 \times 65 = 130$   
 $at = 1.4 \text{ cm}^2 \quad 2 - 13\phi \quad \rightarrow \quad 2 - 16\phi$




11) Column

Exterior column (1-A)

1F

$$\begin{cases} N_x = 26.65 \pm 5.62 = 32.27 \text{ t}, 21.03 \text{ t} \\ M_x = - \pm 1.8 = 1.8 \text{ tm} \\ Q_x = 1.05 \text{ t} \end{cases}$$

$$\begin{cases} N_y = 26.65 \pm - = 26.65 \text{ t} \\ M_y = - \pm 3.5 = 3.5 \text{ tm} \\ Q_y = - \pm 2.06 = 2.06 \text{ t} \end{cases}$$



$BD = 20 \times (40 + 20) = 1.2 \times 10^3$   
 $BD^2 = 20 \times 40^2 = 0.32 \times 10^5$

$N_x/BD = 26.9, 17.5$   
 $M_x/BD^2 = 5.62$

$M_y/BD = 22.2$   
 $M_y/BD^2 = 11.0$

From the diagram

$xPt = -$   
 $xat = -$

$yPt = 0.3 \text{ \AA}$   
 $yat = 0.003 \times 1.2 \times 10^3$   
 $= 3.6 \text{ cm}^2$

2 - 16φ

$J_y = \frac{2.06 \cdot 10^3}{20 \times 7/8 \times 35} = 0.66 \text{ kg/cm}^2 \quad st - 9\phi - c200 \text{ (Pw} = 0.32 \text{ \AA)}$

3F

$$\begin{cases} N_x = 14.53 \pm 1.92 = 16.45 \text{ t}, 12.61 \text{ t} \\ M_x = - \pm .9 = .9 \text{ tm} \\ Q_x = .63 \text{ t} \end{cases}$$

$$\begin{cases} N_y = 14.53 \pm - = 14.53 \text{ t} \\ M_y = - \pm 1.8 = 1.8 \text{ tm} \\ Q_y = 1.24 = 1.24 \text{ t} \end{cases}$$

Section is the same above  
 $BD = 1.2 \times 10^3$   
 $BD^2 = 0.32 \times 10^5$

$N_x/BD = 13.7 \quad 10.5 \quad N_y/BD = 12.1$   
 $M_x/BD^2 = 2.8 \quad M_y/BD^2 = 5.6$

From the diagram


$xPt = -$

$yPt = 0.05$

$\therefore yat = 0.0005 \times 1.2 \times 10^3$


$= 0.6 \text{ cm}^2$

$1 - 16\phi$



(  $Pt=14.6 / 1200 = 1.2 \%$  ,  $Pt= 10.15/1200 = 0.85 \%$  )

1-5 floor



11. PILES

supposed cast-in-situ Piles


Strength of materials;  $F_c \leq 400 \text{ kg/cm}^2$

Formula for bearing strength of piles; Formula (1)

The bearing capacity is obtained by the bearing strength of pile head from the below.

Pile section	A cm <sup>2</sup>	I <sup>M</sup>	wt	Unit: ton		
				Strength of materials F <sub>c</sub> = 75	Strength of pile head Boring No.1    Boring No.2	
25 x 25	607	10 or 15	1.46	45.5	19.2	27.0
30 x 30	882	"	2.11	66.0	27.2	40.5
35 x 35	1207	"	2.90	90.5	37.0	54.8

Arrangement of piles




Ex. 25 x 25 cm

point No.1 (L = 15 m)

We get  $\bar{N} = 30$ ,  $\bar{N}_s = 0$ ,  $\bar{q}_u = 1.0 \text{ kg/cm}^2$ ,  $A_p = 0.0607 \text{ m}^2$ ,  $\psi = 1.0 \text{ m}$ ,  $L_c = 6.0 \text{ m}$  from the boring data and the bearing strength of pile head from formula (1)

$$\begin{aligned} q_u &= \frac{1}{3} \times (30 \times 30 \times 0.0607 + 0 + \frac{1}{2} \times 1.0 \times 6.0) \\ &= \frac{1}{3} \times (54 + 0 + 3) \\ &= 19.2 \text{ t} \end{aligned}$$

Cross section of pile is as follow.



12. SLAB

Calculation is made on the assumption that the edge side of slab is fixed elastically and the axis of center of gravity is less than the balanced steel ratio in analysis.

i) Case;  $S_1$

Common to both X & Y-direction



$$lx = 2.7 \quad \lambda = 1.0 \quad \omega_1 = 0.54 \text{ t/m}^2$$

$$ly = 2.7 \quad \omega_1 lx^2 = 0.54 \times 2.7^2 = 3.94$$

$$Mx_1 = (0.04) \times 3.94 = 0.16 \text{ tm/m, (= My}_1)$$

$$x_2 = (0.028) \quad " = 0.11 \text{ tm/m, (= My}_2)$$

$$D = 100 \text{ cm} \quad j = 6.5 \quad \text{ft} \cdot j = 1.6 \times 6.5 = 10.4$$

$$\text{End ; at} = Mx_1 / \text{ft} \cdot j = 1.54 \text{ cm}^2/\text{m}$$

$$9\phi - 250\text{@}$$

$$\text{Center; at} = Mx_2 / \text{ft} \cdot j = 1.06 \text{ cm}^2/\text{m}$$

$$9\phi - 250\text{@}$$

ii) Case:  $S_2$

$$lx = 2.7 \quad \lambda = 1.37 \quad \omega_2 = 0.452 \text{ t/m}^2$$

$$ly = 3.7 \quad \omega_1 \cdot lx^2 = 3.30$$

$$Mx_1 = (0.065) \times 3.3 = 0.215 \text{ tm/m}$$

$$x_2 = (0.044) \times " = 0.145 \quad "$$

$$My_1 = (0.042) \times 3.3 = 0.139 \quad "$$

$$y_2 = (0.028) \times " = 0.093 \quad "$$

$$D = 100 \text{ cm}$$

Short span

$$\text{End ; at} = 0.215 \cdot 10^2 / 10.4 = 2.07 \text{ cm}^2/\text{m}$$

$$9\phi - \text{@} 200$$

$$\text{Center; at} = \quad = 1.40$$

$$9\phi - \text{@} 200$$

Long span

$$\text{End ; at} = 1.34 \text{ cm}^2/\text{m}$$

$$9\phi - \text{@} 300$$

$$\text{Center; at} = 0.9 \text{ cm}^2/\text{m}$$

$$9\phi - \text{@} 300$$

Note: Slab thickness is regulated more than 12 cm in general floors under 'NI-2' standards, but it is sufficient for the existing stress, here.

### 13. FOUNDATION

i) In the case of two piles

$$\text{Spacing of pile; } 2.5 \times D = 2.5 \times 30 = 75 \text{ cm}$$

$$N = 47.84 \text{ t (Axial load)}$$

$$n = N/27.2 \quad \rightarrow \quad 2$$

Reaction of one pile

$$\bar{N} \doteq 24.0 \text{ t}$$

Bending moment

$$M = 0.375 \times 24.0 = 9.0 \text{ tm}$$

$$Q = 24.0 \text{ t}$$

$$D = 60 \text{ cm, } j = 48 \text{ cm} \quad \text{ft} \times j = 1.4 \times 48 = 67.2 \text{ t/cm}$$

$$\text{at} = M/\text{ft} \times j = 13.4 \text{ cm}^2 \quad + \quad 6 - 16\phi$$


Shearing force


$$\bar{D} = 55 \text{ cm, } j = 43 \text{ cm, } b = 800$$

$$J = \bar{N}/bxj \doteq 7.0 \text{ kg/cm}^2 \quad \text{OK}$$

ii) In the case of one pile


No stress occurs






Except written specially

1. Material of floor is composed of sand and lime addicy to conpection
2. Foundations are all F3 Types.
3. Girders are all G1 Types
4. Inside walls are concrete blocks, Outside walls are bricks.
5. Columns are —, L and T types




Except witten specially

1. Girdess are all G1 types
2. Slabs are R C with thickness of 10cm.
3. Inside end outside walls are the same above.



Except witten specially

1. Girders and lateral braces are G1 types
2. Slabs are unnecessary.




2-2


# FS'2-26

## 1. SCOPE OF PLANNING

The building is two storied, having six units of 26 m<sup>2</sup> each floor. The inside are of concrete hollow blocks, the roof covering is tile on the joist, and the slab in the second floor is of 10 cm thick concrete and of direct slab on grade in the first floor. The structural planning was made to satisfy the above mentioned specifications, and the figures were obtained after analysis of the required stresses.



## SECTION



2. LOADS

Dead load

Roof (tile), 15 mm $\gamma = 1.6$	25 kg/m <sup>2</sup>
Wooden joist	10 "
Concrete slab, sF (100 mm thick)	240 "
Exterior & exterior wall (concrete block 150 mm)	200 "
Beams, 35 x 15 cm	126 kg/m
Stairway (wood)	15 kg/m <sup>2</sup>

Contents		kg/m <sup>2</sup>		For floor	For frame	For earthquake
roof	tile	25	D.L	35	35	35
	truss	10	B	-	30	30
		<u>35</u>	L.L	-	-	-
				35	65	65
2nd floor	concrete slab	240	D.L	240	240	240
			B	-	30	30
			L.L	<u>200</u>	<u>140</u>	<u>60</u>
				440	410	330
wc mandi	water-proof mortar (30 mm)	60	D.L	300	300	300
			B	-	30	30
	concrete slab	<u>240</u>	L.L	<u>200</u>	<u>140</u>	<u>60</u>
		300		500	470	390
stairway	wooden stair	15	D.L	15	15	15
			B	-	-	-
			L.L	<u>200</u>	<u>140</u>	<u>60</u>
				215	155	75


3. AXIAL LOAD (EXCLUDING DEAD LOAD OF FOUNDATION)

C	Floor	Position	Contents	Sub-total	Total	
YW1	2	roof block	0.065 x (3.5/2 + 1.0) x (3.4 + 0.6) 0.2 x 2.0 x 2.0 0.2 x 1.6 x 1.0	0.72 0.81 0.32	1.85	1.85
	1	floor block	0.41 x 3.4 x 3.5/4 0.2 x 2.0 x 2.4 0.2 x 1.6 x 1.0	1.22 0.96 0.32	2.50	4.35
$\Sigma L_y = 1.9 \text{ m}$ then 2.29 t/m						
YW3	2	roof block	0.065 x 3.5 x 4.0 0.2 x 1.65 x 3.5 0.2 x (1.5 + 1.3) x 2.0	0.91 1.16 1.12	3.19	3.19
	1	floor wc/m floor block	0.45 x 3.4 x 3.5/4 0.45 x 1.2 x 1.2 0.47 x 1.5 x 0.75 x 1/2 0.41 x 2.5 x 1.25 x 1/2 0.2 x (1.5 + 1.3) x 2.4	1.22 0.95 0.27 0.64 1.35	4.07	7.26
$\Sigma L_y = 1.5 + 1.3 = 2.8 \text{ m}$ then 2.60 t/m						
YW5	2	roof block	0.065 x (3.5/2 + 1.0) x 4.0 0.2 x 2.0 x (2.0 + 0.9) 0.2 x 1.0 x 1.2	0.715 1.16 0.24	2.11	2.11
	1	wc/m floor block	0.47 x 1.5 x 0.75 x 1/2 0.41 x 2.5 x 1.25 x 1/2 0.2 x 2.4 x (2.0 + 0.9) 0.2 x 1.0 x 1.2	0.27 0.64 1.40 0.24	2.55	4.66
$\Sigma L_y = 1.5 + 0.9 = 2.4 \text{ m}$ then 1.95 t/m						
XW1	2	roof block	0.065 x 2.0 x (3.5 + 1.0) 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	wc/m block	0.47 x 1/2 x 0.75 x (3.5 + 2.1) x 2 0.2 x 3.5 x 2.4	1.94 1.68	3.62	6.38
$\Sigma L_x = 3.5 \text{ m}$ then 1.83 t/m						
XW2	2	roof block	0.065 x 2.0 x 4.5 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	stair floor block	0.155 x 0.6 x 3.5 0.41 x 3.5 x 3.4/4 0.2 x 3.5 x 2.4	0.33 1.19 1.68	3.20	5.96
$\Sigma L_x = 2.6 \text{ m}$ then 2.3 t/m						
XW3	2	roof block	0.065 x (0.75 + 1.0) x 4.5 0.2 x 3.5 x 3.1	0.51 2.17	2.68	2.68
	1	wc/m floor block	0.47 x 1/2 x 0.75 x (3.5 + 2.0) 0.41 x 1/2 x (3.5 + 1.0) x 1.25 0.2 x 3.5 x 2.4	0.97 1.16 1.68	3.81	6.49
$\Sigma L_x = 2.5 \text{ m}$ then 2.6 t/m						
XW4	2	roof block	0.065 x 2.0 x 4.5 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	floor block	0.41 x 3.4 x 3.5/4 x 2 0.2 x 3.5 x 2.4	2.44 1.68	4.12	6.88
$\Sigma L_x = 3.5 \text{ m}$ then 1.97 t/m						
XW5	2	roof block	0.065 x 2.0 x 4.5 0.2 x 3.5 x 3.1	0.59 2.17	2.76	2.76
	1	floor block	0.41 x 1/2 x (3.5 + 1.0) x 1.25 x 2 0.2 x 3.5 x 2.4	2.31 1.68	3.99	6.75
$\Sigma L_x = 3.5 \text{ m}$ then 1.93 t/m						

Maximum and minimum compressive unit stresses

$$\max \sigma_c = \frac{1040}{15 \times 40} = 1.74 \text{ kg/cm}^2$$

$$\min \sigma_c = \frac{732}{15 \times 40} = 1.23 \text{ kg/cm}^2$$



#### 4. HORIZONTAL LOAD

2nd floor

Floor	Position	Contents	Sub-total	Total	
2	roof	0.065 x 9.0 x 4.0 x 6 x 1.13	15.87	82.1 <sup>+</sup>	
	block (x)	0.20 x 3.5 x 3.1 x 8	17.36		
		0.20 x (3.5 x 3.1 - 0.9 x 2.0) x 6	10.86		
		0.20 x (3.5 x 3.1 x 9) - (1.0 x 2.0 x 6)	17.13		
		(y)			
	(out)	0.20 x (3.4 x 2.0 - 1.6 x 1.0) x 6	6.24		
		0.20 x (4.0 x 2.0 - 1.6 x 1.0) x 6	7.68		
	(in)	0.20 x (4.0 x 2.0 - 1.1 x 2.0) x 6	6.96		
	2nd floor				85.1 <sup>+</sup>
	wc/m	0.39 x 1.5 x 3.5 x 6	12.30		
		floor	0.33 x 2.5 x 3.5 x 6	17.33	
			0.33 x 3.4 x 3.5 x 6	23.60	
			0.33 x 1.2 x 1.2 x 6	2.86	
	block (x)	0.20 x 3.5 x 2.4 x 8	13.44		
0.20 x (3.5 x 2.4 - 0.9 x 2.0) x 6		8.16			
0.20 x (3.5 x 2.4 - 1.0 x 2.0) x 6		7.68			
(y)					
	(out)	0.20 x (3.4 x 2.4 - 1.6 x 1.0) x 6	7.88		
(in)	0.20 x (4.0 x 2.4 - 1.6 x 1.0) x 6	9.60			
	0.20 x (4.0 x 2.4 - 1.1 x 2.0) x 6	8.88			
stairway	0.075 x 1.2 x 2.3 x 6	1.25			

#### 5. SEISMIC LOAD AND LENGTH OF WALL

	K x W	KW	ΣKW	ΣLx <sup>m</sup>	ΣLy <sup>m</sup>
2 F	0.1 x 82.10	8.21	8.21	68.5	7.5 x 6
1 F	0.1 x 85.10	8.51	16.72	"	"

#### 6. AVERAGE SHEARING UNIT STRESS

( τ kg/cm<sup>2</sup> )

	Shearing stress	
	x-direction	y-direction
2 F	0.13	0.18 <sup>3</sup>
1 F	0.25	0.37 <sup>2</sup>


$$\tau = \frac{KW \times 1.5}{\Sigma L \times t}$$

Both figures satisfy the allowable shearing unit stress of blocks (1.36 kg/cm<sup>2</sup>)



7. STUDY AFTER THE FAILURE OF UNREINFORCED BLOCKS


Calculations were made supposing a sufficiently sound reinforced block column at the end of a wall and a rigid-framed structure of beams.



7-1 PERMANENT STRESS

Omitted because the stress is small.

7-2 SEISMIC STRESS



7-3 CROSS SECTION

a. Beams

$1F_1 \quad M = 0.46 \text{ tm}$

$Q = 0.31 \text{ t}$


$B \times D = 15C \times 25C$

$j = 17.5C$



$$a_t = 0.46 \cdot 10^2 / 2.0 \times 17.5 = 1.31 \text{ cm}^2 \rightarrow 1-13\phi$$

$$Q = 0.31 \times 10^3 / 15 \times 17.5 = 1.2 < 9.0 \text{ kg/cm}^2$$

2F: M = 0.40 tm  
 Q = 0.54 t  
 B x b = 15C x 25C  
 at = 1.16 cm<sup>2</sup> → 1-13φ  
 Same to 1F.



RF. (Include lateral brace)  
 M = 0.07 tm  
 Q = 0.1 t  
 B x D = 15C x 20C  
 at = 0.28 cm<sup>2</sup> → 1-9φ



#### 7-4, AXIAL LOAD

Supposing the reinforced block columns will support a floor load near the column after the failure of the unreinforced block wall


##### Column (2-B)

roof	$0.065 \times (0.75 \times 1.25) \times 1.13$	0.15	1.3	
wall	$0.065 \times (1.65 \times 1.75) \times 1.13$	0.25		
2nd floor slab	$0.20 \times 2.0 \times (1.25 + 1.0)$	0.90		
			3.92	5.22 <sup>+</sup>

##### Column (3-B)

roof	$0.065 \times 1.75 \times 3.4 \times 1.13$	0.44	3.14	
wall	$0.065 \times 1.75 \times 2.5 \times 1.13$	0.33		
2nd floor slab	$0.20 \times 2.0 \times (2.5 + 3.4)$	2.36		
			6.60	9.74 <sup>+</sup>

7-5 EFFICIENCY OF REINFORCED BLOCK COLUMN



a. With no filling

x-x axis

$$I_{x_1} = \frac{1}{12} \times 1.5 \times 40^3 \times 2 + (12 \times 1.5) \times (20 - 3.0)^2 \times 2 + (12 \times 1.5) \times 5.7^2 \times 2 = 27,737.5 \text{ cm}^4$$

$$Z_{x_1} = 1386.8 \text{ cm}^3$$

$$A_1 = 192.0 \text{ cm}^2$$

b. With filling (No.1)

$$I_{x_2} = 78557.0 \text{ cm}^4$$

$$Z_{x_2} = 3928 \text{ cm}^3$$


$$A_2 = 415.2 \text{ cm}^2$$

c. With filling (No.2)

$$I_{x_2} = 86137.5 \text{ cm}^4$$

$$Z_{x_1} = 4306.9 \text{ cm}^3$$

$$A_3 = 447.6 \text{ cm}^2$$



Fiber stress of column

$$6c = \frac{N}{A} \pm \frac{M}{Z} = \frac{5220}{447.6} \pm \frac{68000}{4306.9} = 11.7 \pm 15.8 = 27.5 \text{ or } -4.1 \text{ kg/cm}^2$$

$$\tau = \frac{470}{40 \times 20} = 0.59 \text{ kg/cm}^2 < 1.36 \text{ kg/cm}^2$$

From the bending moment, the fiber stress gives the above value. Reinforcement is provided on the tension side and twice the 13.6 kg/cm<sup>2</sup> specified is provided on the compression side. But, it is enough, if the above value in compression stress is less than two third strength of additional cement mortar or concrete. Therefore, it will be necessary to appraise the strength of these composite columns.


8. FOUNDATION

Upper axial load; Two kinds of less than 2.0 t/m and 2.6 t/m bearing capacity of soil;  
Two kinds of 3.0 t/m<sup>2</sup> and 5.0 t/m<sup>2</sup>

Footing weight

Ground-beam	0.15 x 1.0 x 2.4	= 0.36 t/m	± 1.0 t/m
Batukali	0.6 x 1.0 x 0.4 x 2.6 t/m <sup>2</sup>	= 0.63	

Contact pressure is both 3.0 t/m and 3.6 t/m per meter. We get effective widths of footing according to the bearing capacity of soil.



In case of 3.0 t/m<sup>2</sup>

$$B_1 = \frac{3.0 \text{ t/m}}{3.0 \text{ t/m}^2} \rightarrow 1.0 \text{ m}$$

$$B_2 = \frac{3.6 \text{ t/m}}{5.0 \text{ t/m}^2} \rightarrow 1.2 \text{ m}$$


In case of 5.0 t/m<sup>2</sup>

$$B_1 = \frac{3.0 \text{ t/m}}{5.0 \text{ t/m}^2} \rightarrow 0.6 \text{ m}$$

$$B_2 = \frac{3.6 \text{ t/m}}{5.0 \text{ t/m}^2} \rightarrow 0.75 \text{ m}$$

Conclusion


PLAN



1 FLOOR

Besides above

1. Footing Fl
2. Ground-beam Gl
3. Slab-on-grade








2 FLOOR

Besides above

1. shows DT
2. Beam Gl
3. Slab 10S2
4. Stairway wood
5. O shows reinforced concrete block (Type B.C)
6. x shows the open reinforcement (Type A)

CROSS SECTION




Same arrangement of bar  
both in long and short span.

# M-24


## 1. OUTLINE OF PLANNING

The building is a six units per floor, two storey house of 24 square meter maisonettes. This material is used the same ones for FS'2-26, but the building itself is light in weight because of the use of wooden floor joists for the second floor. The structural planning satisfy the above-mentioned specifications and stresses are obtained by the analysis.

## 2. PLANS AND FRAMING



## FRAMING



3. LOADS

Dead load

Same to FS'2-28 type except below

Wooden floor, 2F 25 kg/m<sup>2</sup>  
 Beam 20 x 15 72 kg/m

Contents		Floor	Frame	Seismic
2F	Wooden floor 25 kg/m <sup>2</sup>	D.L	25	25
		Beam		20
		L.L	200	140
			225	185
			105	

4. AXIAL LOAD

\* Averaged axial stress of wall along line (B) (Y-Direction)

2F

roof 0.065 x (1 + 1.5) = 0.163 t/m  
 wall 0.20 x 2.0 = 0.40 > 0.563 t/m

1F

slab 0.185 x 1.5 = 0.278  
 wall 0.20 x 2.4 = 0.48 > 0.758 t/m

Total 1.32 t/m

\* Averaged axial stress of wall along line (1) (X-Direction)

2F

roof (0.065 + 1/2 x 3.0 x 1.5) x 2 x 1/3 = 0.1 t/m  
 wall 0.2 x 2.0 = 0.4 > 0.50 t/m

1F

slab 0.185 x 1.0 = 0.185 > 0.665 t/m  
 wall 0.2 x 2.4 = 0.48

Total 1.265 t/m

5. HORIZONTAL LOAD AND SHEARING UNIT STRESS

2nd floor

roof 0.065 x 4.0 x (3.0 + 2.0) x 6 x 1.13 = 10.14 t 27.19 t  
 block 0.2 x 2.0 x (3.0 x 10 + 4.6 x 6 x 2) = 34.10

1st floor

floor 0.185 x 3.0 x 4.0 x 6 = 13.32  
 stairway 0.155 x 1.2 x 3.0 x 1.2 x 3 = 2.0 52.82 t  
 block 0.2 x 2.4 x (3.0 x 10 + 4.6 x 6 x 2) = 40.9

For each building (6 units)

Floor	W	K	KW	ZKW	ΣBW <sup>m</sup>	ΣBWy <sup>m</sup>	Tx kg/cm <sup>2</sup>	Ty kg/cm <sup>2</sup>
2	27.19	0.1	2.72	2.72	31.2	24	0.09	0.1
1	52.82	0.1	5.32	8.02	31.2	30	0.26	0.27

Average shearing unit stress is sufficient in the allowable shearing unit stress.

6. STUDY AFTER THE FAILURE OF UNREINFORCED BLOCKS

Taking FS'2-28 into account.

6-1 PERMANENT STRESS

Line (A) ; The distance between supporting points on the beam is small due to reinforced blocks being placed at the opening near the corner so, stress is small.

Span 2.0m,  $w = 0.075$  t/m (beam itself)


$$c = \frac{1}{12} \times 0.075 \times 2.0^2 = 0.025 \text{ tm}$$

$$M_o = 0.038 \text{ tm}$$

$$Q = 0.075 \text{ t}$$

6-2 SEISMIC STRESS

Line (B) stress



No. of column	Shearing force	Shearing force/Column
30	1.82	0.1
30	5.35	0.27

Shearing force is the same to x and y directions.

6-3 AXIAL LOAD ON REINFORCED BLOCK COLUMN AT CORNER

(2)-(A), (2)-(B) column.

2F

$$\begin{array}{l} \text{Line (A)} \quad 0.563 \text{ t/m} \times 1.0 = 0.563 \text{ t} \\ \text{Line (1)} \quad 0.5 \quad \times 3.0/2 = 0.750 \end{array} \quad \left. \vphantom{\begin{array}{l} \text{Line (A)} \\ \text{Line (1)} \end{array}} \right\} 1.31 \text{ t}$$

1F

$$\begin{array}{l} \text{Line (A)} \quad 0.758 \text{ t/m} \times 1.0 = 0.758 \text{ t} \\ \text{Line (1)} \quad 0.665 \quad \times 3.0/2 = 1.00 \end{array} \quad \left. \vphantom{\begin{array}{l} \text{Line (A)} \\ \text{Line (1)} \end{array}} \right\} 1.76$$

$$\text{Total} \quad 3.07 \text{ t}$$

6-4 CROSS SECTION

a. Beams

$$1F; M = 0.16 \text{ tm}$$

$$Q = 0.11 \text{ t}$$

$$B \times D = 15C \times 20C \quad j = 13.0$$

$$a_t = 0.16/2.0 \times 13.0 = 0.62 \text{ cm}^2 + 1-9\phi$$


$$\tau = 0.11 \times 10^3/15 \times 13 = 0.6 \text{ kg/cm}^2 \quad \text{OK}$$



2F;  $M = 0.215 \text{ tm}$   
 $Q = 0.21 \text{ t}$   
 $B \times D = 20C \times 15C$        $j = 8.3$   
 $at = 1.3 \text{ cm}^2$        $+ 2-9\phi$   
 $\tau = 1.23 \text{ kg/cm}^2$       OK

RF;  $M = 0.095 \text{ tm}$   
 $Q = 0.13 \text{ t}$   
 $B \times D = 15C \times 15C$   
 $at = 0.58 \text{ cm}^2$        $1-9\phi$   
 $\tau = 1.1 \text{ kg/cm}^2$       OK

RG1 (TB1)



b. Column

1F;  $N_x = 3.07 \pm 0.36 = 3.43 \text{ t or } 2.71$   
 $M_x = 0.32 \text{ tm}$   
 $Q_x = 0.27 \text{ t}$   
 Efficiency of column  
 $I = 85333.5 \text{ cm}^4$   
 $Z = 4266.6 \text{ cm}^3$   
 $A = 303.6 \text{ cm}^2$

Fiber stress

$$\sigma_{c1}, t_1 = \frac{3.43 \times 10^3}{303.3} \pm \frac{0.32 \times 10^5}{4266.6}$$

$$= 11.3 \pm 7.5$$

$$= 18.8 \text{ or } 3.8 \text{ kg/cm}^2$$

Only compression stress.


$$\sigma_{c2}, t_2 = \frac{2.71 \times 10^3}{303.3} \pm \frac{0.32 \times 10^5}{4266.6} = 8.9 \pm 7.5$$

$$= 16.4 \text{ or } 1.4 \text{ kg/cm}^2$$

Only compression stress

$$\tau = \frac{0.27 \times 10^3}{40 \times 15} = 0.45 \text{ kg/cm}^2 < 1.36 \text{ kg/cm}^2$$

OK



reinforced concrete block

## 7. FOUNDATION


We calculate the same condition as FS'2-38 type.

Upper axial load	1.32 t/m	
Footing; Groundbeam	0.06	Total 1.62 t/m
Batukali	0.24	


We get effective widths of footing according to the bearing capacity of soil.

In case of  $3.0 \text{ t/m}^2$ ;  $B_1 = \frac{1.62 \text{ t/m}}{3.00 \text{ t/m}^2} \rightarrow 55 \text{ cm}$

In case of  $5.0 \text{ t/m}^2$ ;  $B_2 = \frac{1.62 \text{ t/m}}{5.00 \text{ t/m}^2} \rightarrow 35 \text{ cm}$



### CONCLUSION



Besides above

1. Footing F1
2. Ground beam G1
3. Slab on grade

1. Beam G1
2. Wooden floor + joist
3. Staircase; wood
4. O shows reinforced concrete block (type B,C)
5. x shows open reinforcement (type A0)

### **3 SCHEDULES AND MINUTES**



SCHEDULE OF PHASE I STUDY (Oct. 1979 ~ March. 1980)

Studies including field surveys, which were carried out three times consecutively, were carried out according to the following schedule.

General schedule

	79		80		Mar.
	Oct.	Nov.	Dec.	Jan.	
	10 1st. Field survey	9 22 2d. Field survey	25 5 3rd. Field survey	22 30 Explanation of Phase I Report	
JIRO SUZUKI Leader	■	---	---	■	■
HAJIME SABO Town planner	■	---	---	■	■
TAKESI BABA Architect		---	---		
SHUNJI KAWADA Architect	■	---	---	■	
SHUNRAN TAKAHASHI Structural engr.	■	---	---	■	
YUTAKA SAITO Mechanical engr.	■	---	■	---	
YASUSHI MIYAZAKI Irrigation engr.	■	---		---	
RYOICHI KAWASAKI Engineering geologist	■	---			
HIROYA YOSHIKAWA Environmental scientist		■	■	---	---

■ Field survey  
 --- Home study

Main items

1979 12th Oct.	Inception report discussion
16th Oct.	-do-
17th Oct.	-do-
18th Oct.	Arrangement of studies and schedule
26th Oct.	Inception report discussion and signature of the minutes on the discussion by Ir. Suyono, and Suzuki.
26th Oct.	Discussion on the results of the first field survey
27th Oct.	"
14th Dec.	Presentation report by the Japanese Study Team. (Joint conference with Indonesian Steering Committee and Counterpart.)
15th Jan.	Discussion on the results of the studies based on the first and second field surveys.
18th Jan.	Interim report by the Japanese Study Team. Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated experts, Japanese Embassy and JICA.
21st Jan.	Signature of the minutes on the interim report conference by Ir. Suyono, and Suzuki.
27th March.	Signature of the minutes on the Phase I Report by Ir. Suyono and Mr. Suzuki.

SCHEDULE OF PHASE II STUDY (Jul.1980 ~ March.1981)

General schedule

	80		81		Mar.				
	Jul.	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.
	16	29		7	3				4 13
	1st. Field survey			2nd. Field survey					Explanation of Subelission of Draft Report Final Report
JIRO SUZUKI Leader	---	---		---	---				---
HAJIME SABO Town planner	---	---		---	---				---
MASANORI ONOE Town planner	---	---		---	---				
MICHIKO INAGAKI Architect	---	---		---	---				
SHUNJI KAWADA Architect	---	---		---	---				
SHUNRAN TAKAHASHI Construction engr.	---	---		---	---				
NAOHARU NAGAO Structural engr.									
YUTAKA SAITO Mechanical engr.	---	---		---	---				
GEN FUJIWARA Civil engr.	---	---		---	---				
MIKIO TANEMURA Civil engr.	---	---		---	---				
NAOFUMI HIROTA Cost analyzer									
MOTOHIDE NISHIO Economist	---	---		---	---				---
TAKASHI INOUE Economist	---	---		---	---				

Field survey  
Home study

Main items

- 1980 17th July : Inception report discussion
- 24th July : Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated housing experts, Japanese Embassy and JICA.
- " " : Signature of the minutes of the discussion on the Inception Report by Ir. Suwarno and Mr. Suzuki.
- 9th Oct. : Discussion with local government (DKI)
- 17th Oct. : Discussion with PERUM PERUMNAS directors (Planning and construction div.)
- 22nd Oct. : Discussion with relating government body on the drainage system at PERUMNAS.
- 4th Nov. : Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated housing experts, Japanese Embassy, JICA and other relating government body officials.
- 7th Nov. : Signature of the minute of the discussion on the Progress Report by Ir. Suwarno and Mr. Suzuki.
- 12th Mar. : Joint conference of Indonesian Steering Committee, Counterpart, Japanese Advisory Committee, delegated housing experts, Japanese Embassy, JICA and other relating government body officials.
- " " : Signature of the minute of the discussion on the Draft Final Report by Ir. Radinal Mochtar and Mr. Suzuki.



SCOPE OF WORK  
FOR  
THE STUDY OF LOW COST HOUSING PROJECT

(KTA 20)

Agreed


Between

JAPAN INTERNATIONAL COOPERATION AGENCY


And

CIPTA KARYA

Dated :



(Mr. Takao Hirota)  
Director of  
Social Development Cooperation  
Department, Japan International  
Cooperation Agency.



Ir. Radinal Mochtar  
Director General of Cipta Karya  
Department of Public Works.

## I. INTRODUCTION

In response to a request of the Government of the Republic of Indonesia, the Government of Japan has decided to conduct a feasibility study for the low cost housing project. The Japan International Cooperation Agency ( hereinafter referred to as " JICA " ) the official agency responsible for implementation of technical cooperation programs of the Government of Japan, will carry out the study in close cooperation with the Government of the Republic of Indonesia and its authorities concerned.

## II. BACKGROUND OF THE STUDY.

Housing Policies in Indonesia has been developed since PELITA II ( 1974/75 - 1978/79 ).

Low cost housing, one of the main housing program of the government in PELITA II, were mainly supplied with low rise housing development. But in PELITA III ( 1979/80 - 1984/85 ) some changes in the policy are going to be implemented which will include the development of four storied housing or so called " walk-up-flats ", with the objective of optimizing the use of land especially in the large and density populated urban areas.

According to the housing program in PELITA III, 50.000 units of four storied housing are planned to be constructed by PERUM PERUMNAS as part of the 120.000 units houses to be built by PERUM PERUMNAS in the coming five years period. In this framework, the development of four storied housing is considered of high priority by the Indonesian Government.

It is widely known, that many parts of the northern coast of Java consist of low level and swampy lands presently left undeveloped. Many of these lands are situated close to the city center. Therefore if it can be proven that such undeveloped land can be successfully changed into a good housing estate, such experience can be applied more widely in other areas in Indonesia.

### III. OBJECTIVES.

The study aims at two targets :

One is to conduct feasibility study and preliminary engineering design for housing development project in the site of Cengkareng. The coverage of the engineering design will be subject to further decision by both parties. Secondly is to develop standardized designs for pilot Walk-up flat for public housing, with possible development in Cengkareng Site.

### IV. THE SCOPE OF THE STUDY.

#### 4.1. The feasibility study of housing development project in the site of Cengkareng.

4.1.1. In order to achieve the said objectives, the study will cover :

1. Survey and analysis of general conditions, with particular attention to social, drainage, sewerage and other civil engineering aspects.
2. Assessment of socio-economic development potentials of the site, including preliminary estimate of development cost.
3. Conducting basic designs of site planning in some parts of the site.

4.1.2. The Implementation programme for the feasibility study in Cengkareng site will be decided taking in to consideration the feasibility of the development of standardized designs of pilot walk-up flat.

4.1.3. The size of the site will be decided based on criteria such as the target group, population density, mixed community, etc. The tentative site area is considered within the range of 30 Ha to 50 Ha.

#### 4.2. The development study for the pilot walk-up flat.

4.2.1. In order to achieve the previously mentioned objectives, the study will consider the following :

1. Feasibility of utilizing local materials with due consideration to its socio-economic and employment effects.

2. Conformity between the affordability of the target group and cost of house which will be provided.
3. The minimum building standard and regulation, and other provision as appropriate.
4. Rationalization of construction works in order to shorten the term of works and to simplify the construction works.

4.2.2 The results of studies that will be prepared and submitted are the formulation of standardized designs of the pilot walk-up flat , the identification of structural calculation and the estimation of construction cost.

4.2.3. The implementation program of study is as follows :

( The first stage ).

The following preliminary study will be implemented by the Japanese team dispatched to Indonesia under the cooperation with the Indonesian counterpart team.

1. Inventory and analysis of the data and the following fields covered :
  - The characteristics of housing demands.
  - The present situation of housing industries and housing supply system.
  - Construction cost , land price , building materials available and the others.
2. Setting up the pre-condition for tentative design.
  - The floor size of a dwelling unit.
  - The dimentions of each part of building
  - The size of building and the number of storey.
  - The housing equipment performance level
  - The dwelling performance level.
  - The estimation construction cost.
  - The building materials by each part of building.

( The second stage ).

According to the pre-condition for tentative design, draft designs will be formulated either in Indonesia or in Japan. In the latter case , possibilities will be explored for the provision of funds for counterpart personnel to participate in drafting the design in Japan.

( The third stage ).

The draft designs prepared on the second stage will be reassessed fully and orientation of modification is considered in detail by the joint team of Japan and Indonesia.

( The fourth stage ).

In accordance with the result of reassessment on the third stage, modification of the draft designs will be implemented and the final standardized designs of pilot walk-up flat will be completed in Indonesia or in Japan.

V. STAFFING.

The study will be undertaken by a team of professionals covering the following fields :

1. Project management.
2. Architecture designs
3. Building structure engineering
4. Building equipment engineering
5. Civil engineering

It is understood , that city planning and financial / economic analysis necessary for the project is already covered in the above mentioned fields.

VI. CONTRIBUTION OF THE GOVERNMENT OF INDONESIA.

For the purpose of the study , the Government of Indonesia through PERUM PERUMNAS will cooperate to the extent possible by :

1. Providing the team with the data and information concerned with its use in connection with the study.
2. Carrying out works of soil test.
3. Facilitate for obtaining exemption from taxes and duties for machinery equipment and materials necessary for the study.
4. Assigning counterpart personnel ( officials/engineers ) to the team during the study period.
5. Providing the team with suitable office space and office equipment necessary for the study.
6. Providing vehicles with drivers.

7. Providing any other available facilities that may be required for the execution of the study as it will be agreed upon between both parties.

#### VII. CONTRIBUTION OF JICA.

For the purpose of the study , the Government of Japan will assist to the extent possible :

1. Sending the Japanese expert team to conduct the study.
2. Transferring the knowledge to the Indonesian counterpart experts during the period of the study.
3. Arranging the equipment necessary for the efficient conduct of the study.

MINUTES OF THE DISCUSSIONS ON THE  
INCEPTION REPORT FOR THE LOW COST  
HOUSING PROJECT ( KTA-20 )

副紙一

( Phase I )


The discussion on the Inception Report were held on the 12th, 16th and 17th of October in 1979 at PERUM PERUMNAS ( see ATTACHMENT I ) and the contents of the Inception Report were fundamentally agreed upon by both parties after recognizing the following items :

- 1 - a) The objective of this study is to make pre-feasibility study for Housing Development Project on the site of PERUM PERUMNAS in Cengkareng considering the combination of types of housing.  
b) It will be studied whether a walk up flat is suitable or not to the site of Cengkareng as one of the housing types mentioned above.
- 2 The organization of the study and the members of each part of the organization is shown in ATTACHMENT II.  
The complete members for the steering committee and the counterpart will be nominated in December 1979.
- 3 Indonesian side requested that the transfer of technology shall be considered more.  
Japanese side replied that they would try their best for the effective transfer of technology such as adjustment of working schedule and the way of working.

October 23, 1979. .



Ir. Suyono, M.Sc.  
Director of Planning  
PERUM PERUMNAS



Jiro SUZUKI  
Team Leader of Japanese  
Study Team


ATTENDANTS' LIST OF MEETINGS

ATTACHMENT I.

	1st	2nd	3rd
Date	Oct. 12, 1979	Oct. 16, 1979.	Oct. 17, 1979
Place	PERUM PERUMNAS	PERUM PERUMNAS	PERUM PERUMNAS
ATTENDANTS	<p>INDONESIAN SIDE</p> <p>PERUM PERUMNAS</p> <p>Ir. Soenarjono Danoeedjo            Ir. Suyono, M.Sc.            Mr. Soelistijo Tjitrohamidjojo            Ir. Duddy Soegoto            Ir. Aziz Dahlan            Ir. Yos Sidharta</p> <p>JAPANESE SIDE:</p> <p>ADVISORY COMMITTEE</p> <p>Mr. Nobuaki Ohkubo            Mr. Toshio Ishiguro            Mr. Tetsuo Numaoi</p> <p>STUDY TEAM</p> <p>Mr. Jiro Suzuki            Mr. Hajime Sabo            Mr. Shunji Kawada            Mr. Shunran Takahashi            Mr. Yutaka Saito            Mr. Yashushi Miyazaki            Mr. Ryoichi Kawasaki</p> <p>JICA</p> <p>Mr. Takeshi Shinoura</p> <p>EMBASSY</p> <p>Mr. Takeo Yamazaki</p> <p>EXPERT FOR KTA 7/8</p> <p>Mr. Shinsaku Kanetaki            Mr. Toshio Iketani            Mr. Hajime Okata</p>	<p>INDONESIAN SIDE</p> <p>PERUM PERUMNAS</p> <p>Ir. Duddy Soegoto            Ir. Aziz Dahlan</p> <p>JAPANESE SIDE</p> <p>ADVISORY COMMITTEE</p> <p>Mr. Nobuaki Ohkubo            Mr. Toshio Ishiguro            Mr. Tetsuo Numaoi</p> <p>STUDY TEAM</p> <p>Mr. Jiro Suzuki            Mr. Hajime Sabo            Mr. Shunji Kawada            Mr. Yutaka Saito</p>	<p>INDONESIAN SIDE</p> <p>PERUM PERUMNAS</p> <p>Ir. Suyono, M.Sc.            Ir. Duddy Soegoto            Ir. Aziz Dahlan</p> <p>JAPANESE SIDE</p> <p>ADVISORY COMMITTEE</p> <p>Mr. Nobuaki Ohkubo            Mr. Toshio Ishiguro            Mr. Tetsuo Numaoi</p> <p>STUDY TEAM</p> <p>Mr. Jiro Suzuki            Mr. Hajime Sabo            Mr. Shunji Kawada            Mr. Shunran Takahashi            Mr. Yutaka Saito            Mr. Yashushi Miyazaki            Mr. Ryoichi Kawasaki</p> <p>JICA</p> <p>Mr. Takeshi Shinoura</p> <p>EMBASSY</p> <p>Mr. Takeo Yamazaki</p> <p>EXPERT FOR KTA 7/8</p> <p>Mr. Shinsaku Kanetaki            Mr. Toshio Iketani            Mr. Hajime Okata</p>



ATTACHMENT II Work Organization



1. INDONESIAN STEERING COMMITTEE

Director General Of CIITA KARYA  
 IR. RADINAL MOOCHTAR

Director of Housing of CIITA KARYA

Director of Sanitation Technic of  
 CIITA KARYA

President Director of PERUM PERUMNAS

Director of Planning of PERUM  
 PERUMNAS

*Sebagai* Director of Estate Management of  
 PERUM PERUMNAS

The head of institutions of DKI  
 Jakarta .

3. JAPANESE HOOSING EXPERT for KTA 7/8

SHINSARU YANETAKI

TOSHIO UFTAMA

HAJIME OBATA

HAJIME YONOPORI

4. JAPANESE STUDY TEAM

JIRO SUZUKI leader  
 Nihon Architects, Engineers & Con-  
 sultants, Inc. (NAEC)

HAJIME SABO Town Planner  
 NAEC

SHUNJI KAWADA Architect  
 NAEC

SHUNRAN TAKAHASHI Structural Engi-  
 neer  
 NAEC

YUTAKA SAITO Mechanical Engineer  
 NAEC

TASUSHI MIYAZAWI Irrigation Engi-  
 neer  
 NAEC

RYOICHI KAWASAKI Engineering Geo-  
 logist  
 NAEC

HIROYA YOSHIKAWA Environmental  
 Scientist  
 NAEC

2. JAPANESE ADVISORY COMMITTEE

SOICHIRO MATSUTANI Chairman  
 Director of Housing Construction  
 Division, Housing Bureau, Ministry  
 of Construction (MOC)

NOBUAKI OHKURO Adviser to the Team  
 Deputy Head of Urban Building  
 Division, Housing Bureau, MOC

TOSHIO ISHIGURO Adviser to the Team  
 Deputy Head of Land Development  
 Planning Project Division, Tsukuba  
 Academic New Town, Development Bureau,  
 Japan Housing Corporation

YASUMORI YAMANAKA Adviser to the  
 Team

Deputy Head of Housing Construction  
 Division, Housing Bureau, MOC

YUJI ISHIYAMA Adviser to the Team  
 Head of the First Earthquake Engi-  
 neering Division, International  
 Institute of Seismology and Earth-  
 quake Engineering, Building Research  
 Institute, MOC

TETSUO NUMAOI Adviser to the Team  
 Overseas Cooperation Officer,  
 International Division, Planning  
 Bureau, MOC

5. INDONESIAIAN COUNTERPART

IR. DODDY SOEGOTO Coordinator  
 PERUM PERUMNAS

IR. AZIZ DAHLAN Planner  
 PERUM PERUMNAS

IR. HERRY FORMOMO Architect  
 PERUM PERUMNAS

IR. PARIATRO PARRO Civil Engineer  
 PERUM PERUMNAS

•  
 •  
 •  
 •  
 •


MINUTES OF THE DISCUSSIONS  
ON THE INTERIM REPORT FOR LOW COST HOUSING PROJECT  
IN CENKARENG, JAKARTA (KTA-20) PHASE I.

The Interim Report ( see ATTACHMENT 1 ) was submitted and explained by the Japanese Study Team and discussed by the participants ( see ATTACHMENT 2 ) at the Joint Meeting on the 18th of January in 1980 in Jakarta.


The Interim Report which orientates the frame of the Final Report ( draft ) was fundamentally agreed upon by both parties after recognizing the following items :

- 1) The Final Report of Phase I ( draft ) shall be formulated on the basis of the Interim Report with the accomplishment of the purpose of Phase I explained at the Joint Meeting.
- 2) The findings and alternatives proposed during Phase I will be evaluated in Phase II after considering additional data, especially socio-economical aspects.
- 3) The boundary of planning area shall be decided before Phase II.
- 4) The study on various types of houses shall be developed in Phase II on the basis of the Interim Report.

January 21, 1980.



Ir. Suyono, M.Sc.  
Director of Planning  
PERUM PERLINA-S



Jiro Suzuki  
Team Leader of Japanese  
Study Team

THE STUDY OF LOW COST HOUSING PROJECT (KTA-20)  
PHASE I

INTERIM REPORT

1. INTRODUCTION
2. STUDY OF URBAN DEVELOPMENT
  - 2-1. DEVELOPMENT POLICY
    - A. Site Planning
    - B. Infrastructure
  - 2-2. SITE PLANNING
    - A. Alternative I
    - B. Alternative II
  - 2-3. INFRASTRUCTURE
3. STUDY OF VARIOUS TYPES OF HOUSES
  - 3-1. STUDY POLICY
    - A. Architectural Planning
    - B. Structural Planning
  - 3-2. FLAT HOUSING STUDY
    - A. Architectural Planning
    - B. Structural Planning
  - 3-3. LOW RISE HOUSING STUDY
    - A. Architectural Planning
    - B. Structural Planning
4. SUMMARY
  - A. Proposal on Alternatives
  - B. Total Cost Estimate

JAN. 18th, 1963

JAPANESE STUDY TEAM ( JICA )

# ATTENDANCE LIST 18TH JANUARY 1980

18	19	20
----	----	----

21	17	16	15	14	13	12	11
----	----	----	----	----	----	----	----

	9	8	7	6	5	4	3	2
--	---	---	---	---	---	---	---	---

No	NAME	INSTITUTION	SIGNATURE
1	SUYONO	PERUMNAS	<i>[Signature]</i>
2	<i>[Faded Name]</i>	<i>[Faded Institution]</i>	<i>[Faded Signature]</i>
3	<i>[Faded Name]</i>	<i>[Faded Institution]</i>	<i>[Faded Signature]</i>
4	IMAN SUNARIO	DKI Jakarta	<i>[Signature]</i>
5	RAI PRATADANA	DKI Jakarta	<i>[Signature]</i>
6	RCSITA D. SAPUTRO	DKI - JKT	<i>[Signature]</i>
7	Paryatna P.	Perumahan	<i>[Signature]</i>
8	HERI PURNOMO	PERUMNAS	<i>[Signature]</i>
9	AZIZ DAHLAN	PERUMNAS	<i>[Signature]</i>
10	Yuji Ishiyama	IIESE, BRI. Ministry of Construction	<i>[Signature]</i>
11	Yasunori YAMAMAKA	Ministry of Construction	<i>[Signature]</i>
12	Takeo YAMAZAKI	Embassy of Japan	<i>[Signature]</i>
13	Tadashi SHINOURA	J. I. C. A.	<i>[Signature]</i>
14	Shinsuke Kametaki	Cipta Karya Expert	<i>[Signature]</i>
15	JIRO SUZUKI	JICA TEAM (NIHON ARCHITECTS ENGINEERS) 2 CONSULTANTS INC.	<i>[Signature]</i>
16	Hajime SABO		<i>[Signature]</i>
17	SHUNROU TAKAHASHI	JICA Team	<i>[Signature]</i>
18	Hajime Obata	Perumahan Expert	<i>[Signature]</i>
19	Hajime YOKOBERI	Perumahan Expert	<i>[Signature]</i>


MINUTES OF THE DISCUSSIONS  
ON THE PHASE I REPORT FOR LOW COST HOUSING PROJECT  
IN CENKARENG JAKARTA ( KTA-20 ).

The Phase I Report was submitted and explained by the Japanese Study Team and discussed by the participants ( see attachment ) at a joint meeting in Jakarta on the 27<sup>th</sup> of March in 1980. The report was principally accepted by both parties , written comments will be sent to Japan by the end of April 1980.


The fundamental items of the further study was recognized ~~as~~<sup>as</sup> follows : ✕

- 1). The planning area is around 400 Ha which is surrounded by trunk roads and major drainage canal based on the DKI Jakarta Master Plan.  
The supplementary survey will be mainly carried out in this planning area.
- 2). The first stage project area will be fixed in August 1980 on the basis of the results of the land acquisition at that moment.
- 3). The scope of work during the Phase II covers :
  - a. general planning for the planning area.
  - b. detail planning and preliminary engineering for the first stage project area.
  - c. detailed engineering for land development especially drainage system.
  - d. detailed study on the walk up flat and other housing types.
  - e. financial feasibility of the above aspects.
- 4). It was requested by the Indonesian party that the joint Study should be performed more continuously in Indonesia.

Jakarta, March 27, 1980




Ir. Suyono, M.Sc.  
Director of Planning  
PERUM PERUMNAS



Jiro Suzuki  
Team Leader of Japanese  
Study Team

# ATTENDANCE LIST 27TH MARCH 1980

NO	NAME	INSTITUTION	SIGNATURE
1.	Toshio A I	JICA Tokyo	<i>Toshio Ai</i>
2.	Tadashi SHINOURA	JICA Jakarta	<i>Tadashi Shino</i>
3.	Hajime YOKOBORI	Japanese Housing Expert	<i>Hajime</i>
4.	Toshio UETAMA	"	<i>Toshio</i>
5.	Shinsaku KANETAKI	"	<i>Kanetaki</i>
6.	Takeo Yamazaki	Embassy of Japan	<i>Yamazaki</i>
7.	TOSHIO ISHIGURO	Japanese Advisory Committee	<i>Ishiguro</i>
8.	Hajime OBATA	Japan Housing Expert	<i>Hajime Obata</i>
9.	Hajime SABO	Japanese Study Team	<i>Hajime Sabo</i>
10.	<i>Jiro Mizoguchi</i>	"	"
11.	<i>Suyono</i>	Perummas	<i>Suyono</i>
12.	<i>Duday</i>	"	<i>Duday</i>
13.	<i>Mawan Affandi</i>	"	<i>Mawan</i>
14.	<i>Emi Hjis</i>	"	<i>Emi</i>
15.	AZIZ DAHLAN	"	<i>Aziz Dahlan</i>



MINUTES OF THE DISCUSSIONS  
ON  
THE INCEPTION REPORT  
FOR  
THE LOW COST HOUSING PROJECT IN CENGKARENG (KTA-20)

PHASE II.

The discussions on the Inception Report were held between PERUM PERUMNAS and the Japanese Study Team at PERUM PERUMNAS on 18th and 21st of July in 1980.


The contents of the Inception Report were agreed upon and the following items were recognized by both the Japanese and Indonesia parties :

1. The feasibility study at the First Round will be carried out in the project area which will be acquired in September 1980, covered  $\pm$  110 Ha and is located at Kecamatan Cengkareng, wilayah Jakarta Barat.
2. The study at the Second Round will be carried out at the fixed project area which will be appointed by the Indonesian party by the beginning of October 1980 when the Japanese Study Team is expected to arrive in Indonesia.

Jakarta, July 24, 1980.



Mr. Jiro Suzuki  
Team Leader of  
JICA Low Cost Housing  
Project Study Team



Ir. Suwarno Prawirasumantri  
Director of Planning  
PERUM PERUMNAS



DEPARTEMEN PEKERJAAN UMUM  
PERUM PERUMNAS

Perusahaan Umum Pembangunan Perumahan Nasional  
( National Urban Development Corporation )

Telpon : 822808 (4 saluran)

Alamat : Jl. Letjen Haryono M.T. Kav. 17 Jakarta

Kotak Pos No. 137/K

Nomor : Dirut/2843/10/VII/80

Jakarta, 22 Juli 1980

Lampiran : 1 (satu) lembar.

Kepada Yth.

Mr. Hajime Sabo .....

Japanese Study Team .....

di.

J A K A R T A

Perihal : U N D A N G A N

Dengan hormat kami mengundang Bapak/ Sdr untuk menghadiri rapat  
pengarahan Studi Proyek PERUM PERUMNAS Cengkareng Fase II yang  
akan diadakan pada :

Hari : K a m i s

Tanggal : 24 Juli 1980

J a m : 12.00 WIB - selesai

Tempat : Dit. Jen. Cipta Karya.

Atas perhatian dan kesediaannya kami ucapkan terima kasih.

An. Steering Committee  
KTA 20 Cengkareng,



Ir. Soemarjono Danoedjo  
Direktur Utama

Tembusan Yth.

1. Direksi PERUM PERUMNAS
2. A r s i p

-----  
ad/sd.



## DAFTAR UNDANGAN

### STEERING COMMITTEE

- |                            |   |
|----------------------------|---|
| 1. Ir. Radinal Moochtar    | - Dir. Jen. Cipta Karya                   |
| 2. Ir. Suyono, M.Sc.       | - Direktur Perumahan Rakyat               |
| 3. Ir. Susanto             | - Direktur Direktorat Teknik Penyehatan   |
| 4. Ir. Soenarjono Danoedjo | - Direktur Utama PERUM PERUMNAS           |
| 5. Ir. Suwarno P           | - Direktur Perencanaan PERUM PERUMNAS     |
| 6. Ir. Nursaijidi M.K.     | - Direktur Pembangunan PERUM PERUMNAS     |
| 7. Ir. Herbowo             | - Ketua BAPPENAS D.K.I.                   |
| 8. Ir. Imam Sunarjo        | - Ketua Team Perencanaan Perumahan D.K.I. |

### JAPAN EMBASSY & JICA

- |                         |   |
|-------------------------|---|
| 1. Mr. Takeo Yamazaki   | - First Secretary, Embassy of Japan         |
| 2. Mr. Tadashi Shinoura | - Assistant Resident Representative of JICA |

### JAPANESE ADVISORY COMMITTEE

- |                      |   |
|----------------------|---|
| 1. Mr. Yuji Ishiyama | - Advisor, Japanese Advisory Committee<br>KTA 20 Cengkareng Project |
|----------------------|---|

### JAPANESE HOUSING EXPERT

- |                          |                           |
|--------------------------|---------------------------|
| 1. Mr. Shinsaku Kanetaki | - Japanese Housing Expert |
| 2. Mr. Toshio Uetama     | - Japanese Housing Expert |
| 3. Mr. Hajime Obata      | - Japanese Housing Expert |
| 4. Mr. Hajime Yokobori   | - Japanese Housing Expert |

### JAPANESE STUDY TEAM




















- |                          |   |
|--------------------------|---|
| 1. Mr. Jiro Suzuki       | - Leader, Japanese Study Team<br>KTA 20 Cengkareng Project. |
| 2. Mr. Hajime Sabo       | - Japanese Study Team                                       |
| 3. Mr. Masanori Onoe     | - Japanese Study Team                                       |
| 4. Mrs. Michiko Inagaki  | - Japanese Study Team                                       |
| 5. Mr. Shunran Takahashi | - Japanese Study Team                                       |
| 6. Mr. Yutaka Saito      | - Japanese Study Team                                       |
| 7. Mr. Gen Fujiwara      | - Japanese Study Team                                       |
| 8. Mr. Mikio Tanemura    | - Japanese Study Team                                       |
| 9. Mr. Motohide Nishio   | - Japanese Study Team                                       |
| 10. Mr. Takashi Inoue    | - Japanese Study Team                                       |

### COUNTERPART


- |                           |   |
|---------------------------|---|
| 1. Ir. Duddy Soegoto      | - Kepala Bagian Perencanaan Feasibility<br>PERUM PERUMNAS |
| 2. Ir. Aziz Dahlan        | - Kasubag. Kerjasama Luar Negeri<br>PERUM PERUMNAS        |
| 3. Ir. Herry Purnomo      | - Staf Perencanaan Feasibility<br>PERUM PERUMNAS          |
| 4. Ir. Paryatno Parno     | - Staf Perencanaan Feasibility<br>PERUM PERUMNAS          |
| 5. Ir. Rai Pratadaya      | - Ka. Ur. Pengarahan Perencanaan<br>Lingkungan D.K.I.     |
| 6. Ir. Ny. Rosita Saputro | - Kepala Distrik Perencanaan I<br>Wilayah Jawa Barat.     |

STEERING COMMITTEE  
meeting, 12. , July 24 , 1980

ATTENDANCE LIST

NO	NAME	POSITION	SIGNATURE
1.	Hajime YOKOBORI.	Directorate Perumahan Japan Housing Expert	
2.	ONOE MASANORI	JICA mission	
3.	MICHIKO INAGAKI	JICA Study Team	
4.	Hajime SABO	"	
5.	HITOMORI. OMO	JICA HDQ	
6.	RYONOSUKE GOTO	Assistant Resident Representative, JICA JAKARTA	
7.	Yuji ISHIYAMA	Japanese Advisory Committee Ministry of Construction	
8.	Takeo Yamazaki	First Secretary Embassy of Japan	
9.	JIRO SUZUKI	LEADER OF JAPANESE STUDY TEAM	
10.	Radinal Mochtar	Dir Gen Aptasarya	
11.	Soenanjono	DIRUT PERUMNAS	
12.	Suyono	Dis Perumahan	
13.	Susanto	Dir. Teknik Pengangkutan	
14.	Juwarno	Dir. Can. Perumahan	
15.	NOER SAJJIDI	Dir. BANG. Perumahan	
16.	Duddy Soegoto	Perumahan	
17.	Rai Prastadja	DKI	
18.	Harwan Affandy.	Perumahan	
19.	Iman Surojo	DKI	

NO	NAME	POSITION	SIGNATURE
20	Shinsaku Kanetaki	Cipta karya Expert	<i>[Signature]</i>
21	AZIZ DAHLAN	PERUM PERUMNAS	<i>[Signature]</i>
22	Paryatno Parno	PERUM PERUMNAS	<i>[Signature]</i>
23	Toshio KETAMA	Perumahan Expert	<i>[Signature]</i>



MINUTES OF THE DISCUSSION  
ON  
THE PROGRESS REPORT  
FOR  
THE LOW COST HOUSING PROJECT IN CENGKARENG (KTA - 20)  
( PHASE 11 )

---


The Progress Report for the project submitted by the Japanese Study Team was discussed by the participants (see attachment) of the steering committee meeting on the 4<sup>th</sup> of November 1980, and the following items were confirmed.

- 1). The General Plan for the planning area ( + 370 Ha ) and the Master Plan for the project area ( + 110 Ha ) were approved.
- 2). Alternatives on the major infrastructures which are indispensable for this housing project were evaluated and selected as follow :
  - a). DRAINAGE - Direct discharge system to the Java Sea (ALT 1).
  - b). WATER SUPPLY -60l/dc from PAM-JAYA with setting up the booster pumping station at Grogol (ALT 1A).
  - c). SEWERAGE - Combined system with kitchen and toilet (ALT 3).
- 3). The development cost of the off-site infrastructures is not included into the selling price.
- 4). The target income group is within 20 - 70 of the percentile of the income distribution in 1984.
- 5). The proportion of the empty and commercial lots if necessary can be increased more than 30% of the productive area.
- 6). The low rise housing type (R.15 and D.15) is not recommendable for the lowest income group of the target group.
- 7). The high .....


7). The high density housing was recommend.d.

The distribution of mainsonette, walk up flat and empty lot  
should be studied further.

Jakarta, 7 Noyember 1980.



MR. JIRO SUZUKI  
Team Leader of JICA  
Low Cost Housing Project  
Study Team



IR. SUWARNO PRAWIRASUMANTRI  
Director of Planning  
PERUM PERUMNAS

HS/sd.

ATTENDANTS OF STEERING COMMITTEE  
ON  
THE DRAFT FINAL REPORT ON THE LOW COST HOUSING PROJECT  
IN CENGKARENG, JAKARTA (KTA-20)  
12 MARCH, 1981

1. STEERING COMMITTEE

Ir. Radinal Mochtar	: Dit. Jen. Cipta Karya
Ir. Suyono M Sc	: Direktur Perumahan Rakyat
Ir. Susanto	: Direktur Direktorat Teknik Penyehatan
Ir. Soenarjono Danoejo	: Direktur Utama PERUM PERUMNAS
Ir. Suwarno Prawirasumantri	: Direktur Perencanaan PERUM PERUMNAS
Ir. Nursalwidi M.K.	: Direktur Pembangunan PERUM PERUMNAS
Ir. Herbowo	: Ketua BAPPEDA D.K.I.
Ir. Iman Sunaryo	: Ketua Team Perencanaan Perumahan D.K.I.

2. JAPANESE EMBASSY, JICA

Mr. K. Teshima	: First Secretary, Embassy of Japan
Mr. Ryonosuke Goto	: Assistant Resident Representative of JICA

3. JAPANESE ADVISORY COMMITTEE

Mr. Toshio Ishiguro	: Advisor, Japanese Advisory Committee KTA 20 Cengkareng Project
---------------------	---

4. JAPANESE HOUSING EXPERTS

Mr. Shinsaku Kanetaki	: Japanese Housing Expert
Mr. Hajime Obata	: Japanese Housing Expert
Mr. Hajime Yokobori	: Japanese Housing Expert

5. JAPANESE STUDY TEAM

Mr. Jiro Suzuki	: Leader, Japanese Study Team KTA 20 Cengkareng
Mr. Hajime Sabo	: Japanese Study Team
Mrs. Michiko Inagaki	: Japanese Study Team
Mr. Motohide Nishio	: Japanese Study Team

6. COUNTERPARTS

Ir. Duddy Soegoto	: Kepala Bagian Perencanaan Feasibility PERUM PERUMNAS
Ir. Aziz Dahlan	: Kasubag. Kerjasama Luar Negeri PERUM PERUMNAS
Ir. Rai Pratadaya	: Ka Ur. Pengarahan Perencanaan Lingkungan DKI

7. PROYEK BANJIR JAKARTA, DEP. P.U.

Ir. Martsanto Ds	: Pemimpin Proyek Banjir Jaya
------------------	-------------------------------

8. DIT. JEN. BINA MARGA DEP. P.U.

Ir. Wiyoto Wiyono	: Kasubit. Perencanaan Jalan Kota
-------------------	-----------------------------------

9. KTA 7/8 REVIEW MISSION (OBSERVER)

Mr. Makoto Tateishi	: Ministry of Construction, Japan
Mr. Shigetada Utsumi	: Ministry of Construction, Japan
Mr. Shunichi Hokura	: Ministry of Construction, Japan

10. CIPTA KARYA

Ir. Hendro Pranoto	: Dit. Jen. Cipta Karya
--------------------	-------------------------

11. PERUM PERUMNAS

Ir. Didi Suwandhi	: Kepala Kabag Perencanaan Umum PERUM PERUMNAS
Ir. Marwan Affandi	: Kepala Kabag Perencanaan Teknis PERUM PERUMNAS
Ir. Moegijono Bae	: Kepala Kabag Persiapan Pombangunan PERUM PERUMNAS

PERUM PERUMNAS

DALAM UNDANGAN  
RAPAT BERSAMA "STEERING COMMITTEE"  
KTA 20 CENGKARENG, 9 NOV 1980.

TANDA TANGAN / SIGNATI

1. STEERING COMMITTEE

- 1.1. Ir. Radinal Mochtar - Dir. Jen Cipta Karya
- 1.2. Ir. Suyono M Sc - Direktur Perusahaan Rakyat
- 1.3. Ir. Susanto - Direktur Direktorat Teknik Penyehatan
- 1.4. Ir. Soenarjo Danoedjo - Direktur Utama PERUM PERUMNAS
- 1.5. Ir. Suwarno Prawirasumantri - Direktur Perencanaan PERUM PERUMNAS
- 1.6. Ir. Mursajidi M.K. - Direktur Pembangunan PERUM PERUMNAS
- 1.7. Ir. Herbowo - Ketua BAPPEDA D.K.I
- 1.8. Ir. Inam Sunarjo - Ketua Tim Perencanaan Perumahan D.K.I

2. JAPAN EMBASSY & JICA

- 2.1. Mr. Takeo Yamazaki - First Secretary, Embassy of Japan
- 2.2. Mr. Moriya Miyamoto - Resident Representative of JICA
- 2.3. Mr. Hyonosuke Goto - Assistant Resident Representative of JICA

3. JAPANESE ADVISORY COMMITTEE

- 3.1. Mr. Eyunichi Hokura - Advisor, Japanese Advisory Committee  
Yoshi KTA 20 Cengkareng Project

4. JAPANESE HOUSING EXPERTS

- 4.1. Mr. Shinsaku Kanetaki - Japanese Housing Expert
- 4.2. Mr. Toshio Uetama - Japanese Housing Expert
- 4.3. Mr. Hajime Obata - Japanese Housing Expert
- 4.4. Mr. Hajime Yokobori - Japanese Housing Expert

5. JAPANESE STUDY TEAM

- 5.1. Mr. Jiro Suzuki - Leader, Japanese Study Team  
KTA 20 Cengkareng
- 5.2. Mr. Hajime Sabo - Japanese Study Team
- 5.3. Mr. Michio Inagaki - Japanese Study Team
- 5.4. Mr. Yutaka Saito - Japanese Study Team
- 5.5. Mr. Mikio Tanemura - Japanese Study Team
- 5.6. Mr. Motohide Nishio - Japanese Study Team
- 5.7. Mr. Sunji Kawada - Japanese Study Team

6. COUNTERPARTS

- 6.1. Ir. Duddy Soegoto - Kepala Bagian Perencanaan Feasibility  
PERUM PERUMNAS
- 6.2. Ir. Aziz Dahlan - Kasubag. Kerjasama Luar Negeri PERUM PERUMNAS
- 6.3. Ir. Paryatno Parno - Kasubag. Pengukuran & Pemetaan  
PERUM PERUMNAS
- 6.4. Ir. Harry Purnomo - Staf Perenc. Feasibility PERUM PERUMNAS
- 6.5. Ir. Rai Pratadaya - Ka Ur Pengarahan Perencanaan Lingkungan DKI
- 6.6. Ir. Ny. Rosita Sapatro - Kepala Distrik Perencanaan I  
Wilayah Jakarta Barat

7. PROYEK BANJIR JAKARTA, DEP. P.U

- 7.1. Ir. Achmad Lanti Dipl H.E - Kepala Staf Proyek Banjir Jaya

8. DITJEN BINA MARGA DEP. P.U

- 8.1. Ir. Wiyoto Wiyono - Kasubdit. Perencanaan Jalan Kota

9. PERUSAHAAN AIR MINUM. PEMDA D.K.I

- 9.1. Ir. Budi Rahardjo - Direktur PAM D.K.I

1.1. [Signature]

1.2. [Signature]

1.3. [Signature]

1.4. [Signature]

1.5. [Signature]

1.6. [Signature]

1.7. [Signature]

1.8. [Signature]

2.1. [Signature]

2.2. [Signature]

2.3. [Signature]

3.1. [Signature]

4.1. [Signature]

4.2. [Signature]

4.3. [Signature]

4.4. [Signature]

5.1. [Signature]

5.2. [Signature]

5.3. [Signature]

5.4. [Signature]

5.5. [Signature]

5.6. [Signature]

6.1. [Signature]

6.2. [Signature]

6.3. [Signature]

6.4. [Signature]

6.5. [Signature]

6.6. [Signature]

7.1. [Signature]

8.1. [Signature] (Budisa)

9.1. [Signature]

jd/sd.


MINUTES OF DISCUSSION  
ON  
THE DRAFT FINAL REPORT ON THE LOW COST HOUSING PROJECT  
IN CENKARENG, JAKARTA (KTA-20)

1. The draft final report was submitted and explained by the Japanese Study Team, and discussed by the participants (see Attach) of the Steering Committee Meeting in Jakarta on the 12th of March, 1981.
2. The report was discussed by the Steering Committee, and the Steering Committee agrees that the draft final report be processed and printed as final report.

Note : the following expressions were made by the Steering Committee :


- a) PERUM PERUMNAS and the Local Government will continue the land acquisition process and it should be finished at latest in December 1981.
- b) In parallel with the land acquisition, PERUM PERUMNAS is going to proceed the review of the feasibility study then to start the detailed design in the fiscal year of 1981/1982.
- c) In relation with the above mentioned process, a request for Japanese loan including the detailed design will be submitted.

Signed at Jakarta, March 12, 1981.



---

Ir. Radinal Mochtar  
Director General  
of  
CIPTA KARYA



---

Jiro Suzuki  
Team Leader  
of  
JAPANESE STUDY TEAM



## BIBLIOGRAPHY

I: Indonesian E: English J: Japanese

SOCIO-ECONOMIC, STATISTICAL AND GENERAL DATA

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
LAPORAN HASIL LATIHAN PENELITIAN PESERTA STUDI PEMBANGUNAN INDONESIA ANGKATAN KE III MASALHA-MASALHA PERKOTAAN DI KOTA MADYA CIREBON	第3次インドネシア建設スチューディ調査・西部ジャワマレボノ市に関する市況分析と提案-1978	STUDI PEMBANGUNAN INDONESIA FAKULTAS ILMU-ILMU SOSIAL-UT INDONESIA	I
EVALUASI PLANOLOGI SOSIAL DARI PERMAHAN BARU DI DEPOK INDONESIA	デポック住宅地建設に係る社会的位階の評価	LEMBAGA PLANOLOGI DAN DEMOGRAFI UNIVERSITAS AMSTERDAM	I
RENCANA PEMBANGUNAN LIMA TAHUN KETIGA 1979/80 ~ 1983/84	第3次5ヶ年建設計画	PEMERINTAH DAERAH KHUSUS IBUKOTA JAKARTA	I
STATISTICAL YEAR BOOK OF JAKARTA 1977	ジャカルタ市統計年鑑 1977	CENSUS & STATISTICAL OFFICE JAKARTA	I-E
PROPOSAL FOR A 10,000 UNIT LOW-COST HOUSING DEVELOPMENT	一万戸低所得者用住宅開発計画プロポーザル	PLANNED COMMUNITY DEVELOPMENT CO., LTD. USA	E
STATISTICAL YEAR BOOK OF INDONESIA 1977 ~ 1978	インドネシア統計年鑑 1977~78	CENTRAL BUREAU OF STATISTICS	I-E
MAIN TABLES OF THE NATIONAL INCOME OF INDONESIA 1973 ~ 1978	国民所得表 1973~78	"	E
SUMMARY OF INDONESIAN POPULATION BY PROVINCE AND ISLAND 1976	プロビンス別・島別インドネシア人口統計	"	E
LABOR FORCE SITUATION IN INDONESIA 1977	インドネシア労働力統計 1977	"	I-E
SOCIAL INDICATOR 1978	社会指標	"	E
STATISTICAL YEAR BOOK OF JAKARTA 1979	ジャカルタ市統計年鑑 1979	CENSUS & STATISTICAL OFFICE JAKARTA	I-E
REGIONAL INCOME OF JAKARTA 1975 ~ 1978	ジャカルタ市区収入統計	"	I-E
LAPORAN HASIL PROYEK PERINTISAN PELAYANAN KESEJAHTERAAN MASYARAKAT TERPADU DI DAERAH PENUKIMAN BARU DEPOK BUKU 1	デポック新住宅団地の社会報告	KEJIASANA ANTARA PERSAHAAN UMUM PEMBANGUNAN PERUMAHAN NASIONAL DENGAN FAKULTAS ILMU <sup>2</sup> SOSIAL UNIVERSITAS INDONESIA 1979	I
PENELITIAN KEAPAN SOCIAL, EKONOMI DAN TANGGAAPAN MASYARAKAT PERKAMPUNGAN TERHADAP PROJEK MUHAMMAD HUSNI THAMRIN DKI JAKARTA TAHUN 1973/74	モハムドット・クスマニ・サムリンプロジェクト社会経済調査	PEMERINTAH DAERAH KHUSUS IBUKOTA JAKARTA	I
PENELITIAN KEAPAN SOCIAL EKONOMI MASYARAKAT PADA KAMPUNG <sup>2</sup> YANG AKAN MENDAPAT PERBAIKAN DALAM RANGKA PROJEK MUHAMMAD HUSNI THAMRIN DKI JAKARTA TAHUN 1975/76	モハムドット・クスマニ・サムリンプロジェクト調査 -村営の修復と社会・経済状況-	"	I
HOUSING WORLD BANK SECTOR POLICY PAPER	ハウジング-世銀白書-	WORLD BANK	E
LAND REFORM " "	ランドリフォーム-世銀白書-	"	E
WORLD DEVELOPMENT INDICATORS 1979	世界開発指標-世銀-	WORLD BANK	E
NATIONAL SOCIO-ECONOMIC SURVEY 1976	インドネシア国民家計統計	CENTRAL BUREAU OF STATISTICS	I-E

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
INDONESIAN PRICE INDEX	物価動向	JETRO	J
HOUSEHOLD AND COTTAGE INDUSTRIES IV	家計と家内工業 VOL IV	CENTRAL BUREAU OF STATISTICS	I・E
"	" VOL V	"	I・E
V			
AVERAGE WAGES OF ESTATE WORKERS 1976 ~ 1979	農業労働者賃金統計 1976-79	"	I・E
STATISTIK WILAYAH DKI JAKARTA 1979	ジャカルタ地域統計	KANTOR SENSUS DAN STATISTIK DKI JAKARTA	I
BULLETIN OF INDONESIAN ECONOMIC STUDIES	インドネシア経済スタディー期報	AUSTRALIAN NATIONAL UNIV.	E
PROGRAM PELITA III	PELITA III に対する建設計画	PERUMNAS PROGRAMMING DIVISION	I
IMPOR: MANURUT JENIS BARANG DAN NEGERI ASAL 1978	輸入物資統計 1978	BIRO PUSAT STATITIKS	I
TABEL-TABEL POKOK PENDARATAN NASIONAL INDONESIA	"	"	I
RINGKASAN PENDUK INDONESIA	"	"	I
KEADAAN ANGKATAN KERJA DI INDONESIA	"	"	I
EXPOR: MANURUT JENIS BARANG DAN NEGERI ASAL 1978	輸出物資統計 1978	MINISTRY OF INDUSTRY	I
"	" 1979	"	I
1979			
ATLAS INDONESIA	インドネシア地図	-	E
<u>CITY PLANNING AND COMMUNITY PLANNING</u>			
DASAR-DASAR PERENCANAAN LINGKUNGAN	コミュニティ設計基準	BUILDING INFORMATION CENTRE	I
PEDOMAN PERENCANAAN LINGKUNGAN PEMUKIMAN KOTA	住戸地域計画基準	CIPTA KARYA	I
JAKARTA PLANNING ATLAS 1975	ジャカルタ計画アトラス	DINAS DATA KOTA	I
JABOTABEK METROPOLITAN DEVELOPMENT PLANNING	首都圏開発計画		E
PROGRAM PENDANAAN KOMPONEN LOKAL JALAN TOL	インドネシア道路建設投資計画書 -LOKAL	BINA MARGA	I
PROGRAM PENDANAAN KOMPONEN ASING JALAN TOL	" -ASING	"	I
BINA PROGRAM JALAN	ジャカルタ道路計画図	"	I
JAKARTA KAMPUNG IMPROVEMENT PROGRAMME	ジャカルタ IPバンフレット	DKI JAKARTA	E
PETUNJUK MEMBANGUN DIWILAYAH DAERAH KHUSUS IBUKOTA JAKARTA	地区計画指針	"	I

TYTLE(題名)	TYTLE IN JAPANESE(和文)	AUTHOR OR PUBLISHER(著者または発行所)	
<u>HOUSING PROJECT REPORT</u>			
FINAL REPORT VOL. 4, SITES & SERVICES AND LOW COST HOUSING AT TANDES IN SURABAYA APR. '78	スラバヤS&SとLCH開発計画報告書	PERUM PERUMNAS	E
PROPOSAL FOR A SITES & SERVICES PROJECT IN CIREBON, INDONESIA DEC. '74	チレボンス&SとLCH開発計画報告	"	E
DRAFT REPORT - SITES & SERVICES/ LOW COST HOUSING PROJECT ANNEXES MAR. '76	"	"	E
IMPLEMENTATION REPORT P.I.U. NOV./DEC. '77	"	"	E
FINAL REPORT LOW COST HOUSING IN BEKASI II (SUMMARY)	ベカシII LCH開発計画報告書	"	I
" (TECHNICAL)	"	"	I
APPRAISAL OF THE JAKARTA URBAN DEVELOPMENT PROJECT IN INDONESIA AUG. '74	クレンダープレイグルレポート	IBRD	E
REQUEST FOR FUNDING TO THE IBRD, A SITE & SERVICE PROGRAM JAKARTA METROPOLITAN AREA	クレンダープロジェクトのフィージビリティ・スタディ・レポート	PPU	E
FINAL REPORT SITES & SERVICES BANYUMANIK, SEMARANG VOL. 1 & 3	スマランのフィージビリティ・スタディ・レポート	PERUM PERUMNAS	E
INTERIM REPORT SITES & SERVICES SEMARANG, SULAKARTA VOL. 1	"	"	E
INTERIM REPORT SITES & SERVICES SEMARANG, SULAKARTA VOL. 2	"	"	E
DETAILED DESIGN REPORT SITES & SERVICES SEMARANG, SULAKARTA VOL. 3	スマランの詳細設計レポート	"	E
FINAL REPORT SITES & SERVICES SEMARANG, SULAKARTA	スマランのフィージビリティ・スタディ・レポート	"	E
BANDUNG URBAN DEVELOPMENT AND SANITATION PROJECT-BACK GROUND PAPER VOL. 1, 2, 3	バンドンのフィージビリティ・スタディ・レポート	CIPTA KARYA	E
REPORT TANAH ABANG	マリアン中層団地レポート	PERUM PERUMNAS	I
<u>ARCHITECTURAL, STRUCTURAL AND MATERIAL DATA</u>			
PERATURAN SEMEN PORTALAND INDONESIA 1972 N.I-8	ポルトランドセメント基準	BUILDING INFORMATION CENTRE	I
MANUAL BANGUNAN TAHAN GEMPA	建設工法マニュアル	"	I
KAYU SEBAGAI BAHAN BANGUNAN	木付ガイダンス	"	I
A BRIEF OUTLINE OF SEISMICITY AND EARTHQUAKE	耐震設計の手引	"	E
DEVELOPMENT OF A STEAM-CURED BUILDING MATERIAL ON THE BASIS OF LATERTIC SOIL & LIME	ふと石灰をベースにした建材の開発	DIRECTORATE OF BUILDING RESEARCH	E
PERATURAN BETON BERTULANG INDONESIA N.I-2	RCコンクリート基準	CIPTA KARYA	

TYTLE (題名)	TYTLE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
ULTIMATE STRENGTH ANALYSIS OF RC-SECTION	RC終局強度計算法手引	BUILDING RESEARCH INSTITUTE	E
PERHITUNGAN LENTUR	RCコンクリート計算基準	CIPTA KARYA	I
KEAMANAN KONSTRUKSI DALAM PERHITUNGAN BETON	コンクリート安全費領	"	I
REPORT BANDUNG	バンドンセミナーレポート	BANDUNG INSTITUTE OF TECHNOLOGY	E
REINFORCED CONCRETE DESIGNER'S HANDBOOK	RCコンクリートデザイナーハンドブック	VIEWPOINT PUBLICATION	E
PERATURAN BANGUNAN NASIONAL	国家建築規則	CIPTA KARYA	I
PERATURAN KONSTRUKSI KAYU INDONESIA	木構造基準	"	I
	イントネシア国家建築施工規則 (1-25の和訳)	JAPAN-INDONESIAN ASSOCIATION	J
BATA MERAH SEBAGAI BAHAN BANGUNAN	レンガ造基準	CIPTA KARYA	I
PERATURAN UMUM UNTUK BAHAN BANGUNAN DI INDONESIA	建材一般基準	"	I
PEMBANGUNAN PERUMAH BERTINGKAT EMPAT VOL. 1, 2, 3	Perumnas の新築ビル設計例	PERUM PERUMNAS	I
TECHNICAL REPORT NO. 22	コンクリート関連技術レポート	"	I
MAISONNETTE 80	メノネット住宅資料	BANDUNG TECHNICAL INSTITUTE	I
COMPETITION "FLAT INDONESIAN"	中層コンベ入選作・プレコン方式案	PERUM PERUMNAS	I
" "FLAT MEXICAN"	" "メキシコ方式案	"	I
" "FLAT BRECAST"	" "	"	I
PEDOMAN TEKNIK PERENCANAAN PERUMAHAN FLAT DAN MAISONETE	プレキャスト方式案・中層・メノネット住宅技術ガイダンス	CIPTA KARYA	I
EVALUASI KERJA SUB-INTI	サブコア住宅のコグザリレーション	PERUM	I
PEDOMAN PERENCANAAN LINGKUNGAN PEMUKIMAN KOTA	ジャカルタ市建築関連条例	DKI JAKARTA	I
<u>SEWERAGE, WATER SUPPLY AND POWER SUPPLY</u>			
USAHA MEMANFAATKAN AIR HUJAN UNTUK AIR MINUM	雨水と飲料水手引	BUILDING INFORMATION CENTER	I
MANUAL OF STANDARD & CRITERIA FOR PLANNING WATER RESOURCE PROJECT	水源プロジェクトマニュアル	"	E
RENCANA SEPTIK TANK	セプティックタンク手引	"	I
KAKUS SEDERHANA	し尿処理手引	"	I
MASTER PLAN FOR JAKARTA WATER SUPPLY SYSTEM	ジャカルタ給水システムマスタープラン	NIHON SUIDO CONSULTANT	E
PENJELASAN SINGKAT PENAUGGULAN-GAN MASLAH BANJIR'DI DKI JAKARTA	ジャカルタ洪水防止策の説明	DIREKTORAT JENDERAL PENGAIRAN	I
JAKARTA DRAINAGE AND FLOOD CONTROL PROJECT PHASE II	ジャカルタ排水及び村洪水プロジェクト	NEDECO	E

TYTLE(題名)	TYTLE IN JAPANESE(和文)	AUTHOR OR PUBLISHER(著者または発行所)	
FINAL REPORT PHASE II JAKARTA DRAINAGE AND FLOOD CONTROL PROJECT	ジャカルタ排水及び洪水プロジェクト	NEDECO	E
CISADANE-JAKARTA-CIBEET WATER RESOURCES DEVELOPMENT PLAN	チサダネーノジャカルタチベト水源開発計画	CIPTA KARYA	E
NUCLEAR APPLICATIONS IN FLOOD CONTROL RESEARCH OVER JAKARTA	洪水予防への放射線の導入	BADAN TENAGA ATOM NASIONAL	E
PERATURAN INSTALASI LISTRIK SYRAT-SYRAT PENYAMBUNGAN LISTRIK	電気設備基準	PERUM PERUMNAS	I
CISADANE-JAKARTA-CIBEET WATER RESOURCES DEVELOPMENT PLAN ANNEX D	CJC水資源計画	CIPTA KARYA	I
JAKARTA SEWERAGE AND SANITATION PROJECT SEP. '77	Jakarta排水マスタープラン	CIPTA KARYA	E
PEDOMAN PLAMING INDONESIA MAR. '74	給排水基準	DIRECTORAT TEKNIK PENYEHATAN	I
OPEN CHANEL HYDRAULICS	開渠の水理	VET TE CHOW, MCGRAW-HILL, KOGAKUSHA	E
SEWAGE TREATMENT IN HOT CLIMATE	熱帯地方の汚水処理	DUNCAN MARA, WILEY CO.	E
JAKARTA DRAINAGE FLOOD CONTROL REPORT (FIRST PROGRESS)	ジャカルタ洪水調整プロジェクト	PBJR (NEDECO)	E
" (THIRD PROGRESS)	"	"	E
DAILY RAINFALL DATA SHEET IN CENGKARENG	チェンカレン日録雨量データ	JAKARTA OBSERVATORY	I
<u>COST AND CONSTRUCTION DATA</u>			
DAFTAR HARGA SATUAN BAHAN BANGUNAN DI JAKARTA AUG. '79	ジャカルタ建材コスト資料Aug. 1979	BUILDING INFORMATION CENTER	I
DAFTAR HARGA SATUAN BAHAN BANGUNAN DI JAKARTA	ジャカルタ建材コスト資料OCT. '79	"	I
DAFTAR HARGA SATUAN BAHAN BANGUNAN DI JAKARTA JUN. '80	ジャカルタ建材コスト	"	I
DAFTAR HARGA SATUAN PEKERJAAN (UNIT PRICE) DI INDONESIA IV/1979	インドネシア都市別ユニット建設コスト資料	"	I
A GUIDANCE TO THE INDONESIAN TAXATION	TAX関連	GUNUNG AGUNG	E
PAKET 20 APRIL 1979	"	"	I
PENETAPAN HASIL PREKWALIFIKASI PEMBORONG PERUM PERUMNAS UNTUK TAHUN ANGGARAN '78/'79, '79/'80	業者別能力規定一覧	PERUM PERUMNAS	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN GEDUNG KANTOR PUSAT PERUM PERUMNAS	ブルムナス本社ビル工事契約書	"	I
S&S IN KLENDER BILL OF QUANTITIES AND SPECIFICATIONS	クレンダーS&Sプロジェクト仕様書	"	I
PELAKSANAAN PEKERJAAN LAND CLEARING DI LOKASI PROJEK PERUM PERUMNAS MEDAN II	メダンII宅地工事契約書	"	I

TYTLE (題名)	TYTLE IN JAPANESE(和文)	AUTHOR OR PUBLISHER (著者または発行所)	
PELAKSANAAN PEKERJAAN PEMBUATAN SALAN ROW 10, 6, SALURAN, DUIKER DAN BAK KONTROL DI LOKASI PROJEK PERUM PERUMNAS MEDAN II	メダンⅡ道路フットパス工事契約書	PERUM PERUMNAS	I
PELAKSANAAN PEKERJAAN PEMBUATAN SEBUAH MENARA AIR DARI BETON DI LOKASI PROYEK BEKASI	ベカン給水タワー契約書	"	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN 500 UNIT RUMAH TYPE D-21 DI LOKASI DEPOK II	デポックⅡD-21タイプ住戸工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBUATAAN JALAN SETAPAK DAN SALURAN LINGKUNGAN 400 UNIT RUMAH TYPE D-21 PADA SITE TIMUR BAGIAN UTARA DI LOKASI DEPOK II	デポックⅡ道路排水、宅造工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN 640 UNIT/10 TWIN BLOCK RUMAH FLAT SYSTEM BRECAST TYPE-36 DI LOKASI BANDUNG DAN SEKITARNYA	バンドンF-36タイプ中層プレキャスト住戸工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBUATAN JALAN KERJA DI LOKASI BEKASI II	ベカンⅡ仮設道路工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMBANGUNAN 400 UNIT RUMAH TYPE D-33 DI LOKASI TANGERANG	タンゲランプロジェクトD-33タイプ住戸工事契約書	"	I
SURAT PERJANJIAN KERJA SAMA PELAKSANAAN PEKERJAAN PENYAMBUNGAN TENAGA LISTRIK UNTUK 174 UNIT RUMAH DI LOKASI CIREBON	チレゴン174ユニット住宅の電気施設工事契約書	"	I
BIAYA PELAKSANAAN PEMBANGUNAN PEKERJAAN JALAN KONSTRUKSI BAJA	BINA MARGAの道路・橋梁建設コスト歩掛表	BINA MARGA	I
PELAKSANAAN PEKERJAAN PEMBUATAN LAND-DEVELOPMENT DI LOKASI, KLENDER	クレンダープロジェクト宅造工事契約書	PERUM PERUMNAS	I
GEDUNG KANTOR PUSAT PERUM PERUMNAS VOL. 1, 2	ブルムナス本社ビル仕様・概算資料	"	I
PELAKSANAAN PEKERJAAN PEMBUATAN JALAN BARU PRIMER DAN TERTIER DI LOKASI PROJEK CIREBON	チレゴン幹線道路工事契約書	"	I
PELAKSANAAN PEKERJAAN LAND DEVELOPMENT (PEKERJAAN JALAN, KANALAIR, AIR MINUM) DI LOKASI PROJEK CIREBON	チレゴン宅造工事契約書	"	I
INFORMASI POTENSI INDUSTRI	工場生産能力データ	ASSOCIATION OF MATERIAL OF INDONESIA	I
PELAKSANAAN PEKERJAAN UP GRADING KALI DAN PINTU PENGENDALI BANJIR PADA KALI CIKALONG DI LOKASI PROJEK CIREBON	チレゴン治水工事契約書	PERUM PERUMNAS	I
PELAKSANAAN PEKERJAAN PEMBUATAN INSPEKTION DAN PENGATUR DAN TUTUP-TUTUP BESI BAR METER AIR PIT SERTA PER-BAIKAN SALURAN AIR KOTOR DI LOKASI PROJEK CIREBON	チレゴン排水・敷料水工事契約書	"	I
PELAKSANAAN PEKERJAAN PEMASANGAN PIPA AIR KOTOR DAN AIR MINUM FOOT PATH BERIKUT GUTTERNYA DI LOKASI PROJEK CIREBON	チレゴン給・排水、道路工事契約書	"	I

TYTLE (題名)	TYPE IN JAPANESE (和文)	AUTHOR OR PUBLISHER (著者または発行所)	
<u>Others</u>			
GEOLOGICAL MAP (JAKARTA)	ジャカルタ地質図	DIRECTORAT GEOLOGI	I, E
SOIL INVESTIGATION DATA SHEET	土質データ	PBJR	I
BERTANAN POHON BUAH-BUAHAN 2	果樹の植樹について	GNUNG AGUN	I
TANAMAN HIAS	インドネシアの庭木	"	I
TUMBUHAN LIAR	インドネシアの草花	"	I
TANAMAN PERINPUNG	インドネシアの樹木	"	I







JICA