

**REPUBLIC OF INDONESIA
MINISTRY OF PUBLIC WORKS
DIRECTORATE GENERAL OF HIGHWAYS**

**THE FEASIBILITY STUDY
OF
THE LOCAL ROAD DEVELOPMENT
IN THE REPUBLIC OF INDONESIA**

KABUPATEN REPORT 2

KABUPATEN INDRAGIRI HILIR

MARCH 1986

JAPAN INTERNATIONAL COOPERATION AGENCY



JICA LIBRARY



1034231 [9]

**REPUBLIC OF INDONESIA
MINISTRY OF PUBLIC WORKS
DIRECTORATE GENERAL OF HIGHWAYS**

**THE FEASIBILITY STUDY
OF
THE LOCAL ROAD DEVELOPMENT
IN THE REPUBLIC OF INDONESIA**

KABUPATEN REPORT 2

KABUPATEN INDRAGIRI HILIR

MARCH 1986

JAPAN INTERNATIONAL COOPERATION AGENCY

国際協力事業団		
受入 月日	'87.5.21	108
登録 No.	16425	61.4
		SDF

PREFACE

This is the Kabupaten Report of the Feasibility Study of the Local Road Development in the Republic of Indonesia for Kabupaten Indragiri Hilir in Riau Province. The report has been prepared by the Study Team of the Japan International Cooperation Agency (hereinafter called JICA).

Based upon a request from the Government of Indonesia, the Government of Japan arranged for JICA to conduct the Study and JICA accordingly organized a Study Team. The study was carried out using data which were generally prepared by the Kabupaten, routed through the province, under the instructions of Bina Marga of the Ministry of Public Works and Bangda of the Ministry of Home Affairs.


Since the study period was limited, without cooperation of Bina Marga, Bangda and local governments of both province and Kabupaten in collecting the data, the study would not have been completed within the period.

The report consists of the results of the feasibility study and proposed implementation programme of the local road development in the Kabupaten.

The simplified economic feasibility evaluation methodology utilized for the study was established by the Study Team in Phase I Study through a pilot study of seven (7) model Kabupatens, and is described in the Main Report.

The purpose of the study for the Kabupaten is mainly to estimate the total Project Cost for the local road development but only limited data is available for study base. Therefore a detailed survey and design for the improvement of the Kabupaten roads should be carried out before commencing the Project together with a review of this report.

LOCATION MAP OF THE PROJECT AREAS





- I · PROPINSI RIAU
 - 01 · KAB · INDRAGIRI HULU
 - 02 · KAB · INDRAGIRI HILIR
 - 03 · KAB · BENGKALIS
- II · PROPINSI SUMATERA SELATAN
 - 04 · KAB · MUSI RAWAS
 - 05 · KAB · MUSI BANYUASIN
 - 06 · KAB · BANGKA
 - 07 · KAB · BELITUG
- III · PROPINSI LAMPUNG
 - 08 · KAB · LAMPUNG TENGAH


LEGEND :

--- PROVINCIAL BOUNDARY


LOCATION OF THE PROPOSED AREA

SCALE :

0 92 184 276 460 Km





KAB · INDRAGIRI HILIR



LEGEND :

- KABUPATEN CAPITAL
- ⊙ KECAMATAN CAPITAL
- OTHER CITY
- ③ LINK NUMBER
- + - + - PROVINCIAL BOUNDARY
- - - - - KABUPATEN BOUNDARY
- - - - - KECAMATAN BOUNDARY
- == NATIONAL ROAD
- == PROVINCIAL ROAD
- == KABUPATEN ROAD
- == VILLAGE ROAD
- ~ RIVER



THE FEASIBILITY STUDY OF THE LOCAL ROAD DEVELOPMENT IN THE REPUBLIC OF INDONESIA

TITLE :

SOURCE: DIREKTORAT JENDRAL CIPTA KARYA	SCALE: AS SHOWN	PROVINCE: RIAU KABUPATEN: INDRAGIRI HILIR
--	--------------------	--

CONTENTS

PREFACE

Chapter 1	BACKGROUND OF THE KABUPATEN	
1.1	Topographic and Meteorological Conditions	2-1
1.1.1	Location and Topography	2-1
1.1.2	Meteorological Conditions	2-2
1.2	Socio-Economic Conditions	2-4
1.2.1	Population	2-4
1.2.2	Land Use	2-6
1.2.3	Agriculture	2-8
1.2.4	Other Economic Activities	2-11
1.3	Present Status of Kabupaten Roads	2-12
1.3.1	Outline of Road Networks	2-12
1.3.2	Road Inventory	2-13
1.3.3	Bridge Inventory	2-17
1.3.4	Traffic	2-22
Chapter 2	ESTIMATIONS OF FUTURE TRAFFIC VOLUME AND BENEFIT	
2.1	Future Traffic Volume	2-23
2.1.1	Traffic Growth Rate	2-23
2.1.2	Present and Future Traffic Volume	2-24
2.2	Benefit	2-26
2.2.1	Benefit Estimation Method	2-26
2.2.2	Benefit	2-28
Chapter 3	ENGINEERING	
3.1	Design Criteria and Specification	2-29
3.1.1	Geometric Design Criteria	2-29
3.1.2	Loading Specification	2-29
3.2	Pavement Design	2-32
3.2.1	Design Conditions	2-32
3.2.2	Pavement Structure	2-33
3.3	Design of Bridges and Other Structures	2-34
3.3.1	Standard Bridge	2-34

	3.3.2	Other Structures	2-36
	3.4	Selection of Equipment Types	2-39
	3.4.1	Points to be Considered for the Selection	2-40
	3.4.2	Combinations of Equipment for Major Works and Maintenance	2-40
	3.5	Workshop and Laboratory	2-43
	3.5.1	Policy of the Kabupaten Workshop	2-43
	3.5.2	Workshop Equipment and Tools	2-43
	3.5.3	Laboratory	2-44
Chapter 4		CONSTRUCTION AND MAINTENANCE COST ESTIMATIONS	
	4.1	Unit Price	2-46
	4.1.1	Unit Labour Price	2-46
	4.1.2	Unit Price of Materials	2-47
	4.1.3	Hourly Equipment Cost	2-48
	4.2	Unit Construction Cost by Work Type	2-49
	4.2.1	All Works Except Bridges	2-49
	4.2.2	Bridges	2-50
Chapter 5		RESULTS OF ECONOMIC FEASIBILITY EVALUATION	
	5.1	Preliminary Screening	2-51
	5.2	Evaluation	2-52
	5.2.1	Primary Analysis	2-52
	5.2.2	Secondary Analysis	2-52
	5.2.3	Ranking of Feasible Road Links	2-52
Chapter 6		IMPLEMENTATION PROGRAMME	
	6.1	Implementation Schedule	2-54
	6.1.1	Project Cost	2-54
	6.1.2	Proposed Road Links	2-55
	6.1.3	Annual Construction and Maintenance Cost	2-59
	6.1.4	Construction and Maintenance Equipment Cost	2-62
	6.1.5	Other Costs	2-65
	6.1.6	Quantities by Work Type	2-65

	6.2	Organization and Construction System	2-67
	6.2.1	Organization	2-67
	6.2.2	Construction System	2-67
Appendix	A-1	Input Data for Estimation of the Producer's Surplus Benefit	2-A-1
	A-2	Engineering Data	2-A-2
	A-3	Construction and Maintenance Cost for Proposed Road Links	2-A-17
	A-4	Construction and Maintenance Quantities for all Proposed Road Links	2-A-23
	A-5	Construction and Maintenance Costs for all Proposed Road Links	2-A-26
	A-6	Quantities of Bridges on Proposed Road Links	2-A-29
	A-7	Construction and Maintenance Cost of Bridges on Proposed Road Links	2-A-31

Chapter 1 BACKGROUND OF THE KABUPATEN

1.1 Topographic and Meteorological Conditions

1.1.1 Location and Topography

Kabupaten Indragiri Hilir is bordered by Kabupaten Indragiri Hulu on the west and faces the sea on the east.

Tembilahan, the capital of the Kabupaten is located on the estuary of the Indragiri River. The equator crosses the Kabupaten slightly north of the centre.

Excetp for a hilly area lying on the southwest boundary of the Kabupaten, which is also the provincial boundary, the Kabupaten is almost flat. However, the coastal area is widely covered by swamps which make use of the land difficult.

The area of the Kabupaten is about 11,606 sqaure kilometers, approximately 12 percent of the total of Riau Province. It administers 11 Kecamatan.

1.1.2 Meteorological Conditions

The average number of rainy days and the average amount of yearly rainfall in Kabupaten Indragiri Hulu are 153 days and 2,139 mm respectively.

One year in the Kabupaten consists of a rainy season and a dry season. The dry season is in general from June through August. However this is variable as Table 1-1-1 shows.

The number of working days per year, which is necessary for planning the construction schedule in chapter 6, is estimated at 220 days using the following formula based upon the data shown in the table referred to above.

$$\text{Working Days} = 365 - \text{Holidays} - \text{Rainy Days} + \frac{\text{Rainy Days} \times (\text{Holiday})}{365} + (0.10 \times \text{Rainy Days})$$

Where :

- Holidays consist of 52 Sundays and 13 national holidays; and
- 10% of rainy days are assumed to be workable days.

Table 1-1-1

METEOROLOGICAL CONDITIONS

PROVINCE : Riau
 KABUPATEN : Indragiri Hulu

STATION : Air Molek

	1 9 8 0	1 9 8 1	1 9 8 2	1 9 8 3	1 9 8 4
MONTH	RAINY DAYS (mm)	RAINFALL (mm)	RAINY DAYS (mm)	RAINFALL (mm)	RAINY DAYS (mm)
January	7	97	10	125	
February	12	314	18	204	
March	16	318	17	214	
April	21	300	20	245	
May	14	197	18	192	
June	7	111	8	79	
July	13	178	14	181	
August	10	142	5	78	
September	15	77	21	276	
October	10	220	12	189	
November	16	242	7	19	
December	17	223	18	178	
Total	158	2,419	168	1,980	132
				2,017	

1.2 Socio-Economic Conditions

1.2.1 Population

The population of Kabupaten Indragiri Hilir in 1984 was 424,583 which was approximately 17.4% of the 2,442,800 total population of Riau Province as shown in Table 1-2-1.

The population density was 0.34 persons per ha which was higher than the provincial density of 0.25 and lower than the national density of 0.84.

The recent annual average growth rate of population of the Kabupaten is 2.0% which is lower than both the provincial rate of 3.1% and the national rate of 2.2%. This may be due to the fact that the transmigration programme in the Kabupaten has not yet commenced.

The population of each Kecamatan and its proportion to the Kabupaten population is shown in Table 1-2-2.

Table 1-2-1 POPULATION BY KABUPATEN

DESCRIPTION	POPULATION	AAGR (%)	AREA (ha)	POPULATION DENSITY (persons/ha)	SURVEY YEAR
KABUPATEN:					
INDRAGIRI HULU	259,032	5.5	1,585,400	0.16	1982
INDRAGIRI HILIR	424,583	2.0	1,232,582	0.34	1984
BENGGALIS	639,607	5.5	3,089,783	0.21	1983
PROVINCE:					
R I A U	2,306,300		9,456,200		1982
	2,373,600	3.1	9,456,200	0.25	1983
	2,442,800		9,456,200		1984
JAWA IS. (Excluding DKI JAKARTA)	91,126,900	1.7	13,159,700	6.92	-
INDONESIA	161,579,500	2.2	191,944,300	0.84	-

Notes :

1. Sources:

Kabupaten; Kabupaten concerned with the study

Province ; Jawa and Indonesia:

Statistical yearbook of Indonesia 1984, published by
the Central statistics Bureau.

2. AAGR ; Average Annual Growth Rate.

Table 1-2-2

POPULATION BY KECAMATAN

Year : 1984

PROVINCE : RIAU

KABUPATEN : INDRAGIRI HILIR

KECAMATAN	POPULATION	PROPORTION (%)
RETEH	62,751	14.8
ENOK	31,845	7.5
KUALA INDRAGIRI	31,925	7.5
TEMBILAHAN	54,562	12.9
TEMPULING	37,710	8.9
GAUNG ANAK SERKA	49,082	11.6
MANDAH	29,954	7.2
KATEMAN	21,410	5.1
KERITANG	53,917	12.8
TANAH MERAH	28,155	6.7
BATANG TUAKA	20,632	4.9
TOTAL	424,583	100

1.2.2 Land Use

In Kabupaten Indragiri Hilir, 393,560 ha of the current available land use area, which is approximately 30.4% of the 1,232,582 ha total area of the Kabupaten, is used for living purposes and for industrial activity of the inhabitants of the Kabupaten. It is the total value of columns (1) through (6) in Table 1-2-3.

The current available land use area consists of 362,827 ha of agricultural harvest area and 11,733 ha of residential area which are 96.9% and 3.1% of the current available land use area respectively.

The agricultural harvest area consists of 43,961 ha of paddy field, 92,864 ha of plantation and 225,002 ha of other cultivated area which are 12.1%, 25.7% and 62.2% of the agricultural harvest area respectively.

It can be realized from the land use that the main industry in the Kabupaten is plantation.

Table 1-2-3

LAND USE

PROVINCE : RIAU

KABUPATEN	(ha)										TOTAL AREA SURVEY YEAR
	WET PADDY FIELD	UPLAND PADDY FIELD	OTHER CULTIVATED AREA	PLANTATION AREA	RESIDENTIAL AREA	USABLE OPEN SPACE	RIVER & LAKE AREA	FORESTRY AREA	OTHERS	TOTAL AREA	
INDRAGIRI HULU	19,242 (1.2)	24,363 (1.5)	81,054 (5.1)	25,000 (1.6)	-	-	-	1,237,490 (78.1)	196,279 (12.5)	1,585,429 (100)	1982
INDRAGIRI HILIR	41,985 (3.4)	1,976 (0.2)	225,002 (18.3)	92,864 (7.5)	11,733 (1.0)	-	15,897 (1.3)	839,230 (68.0)	3,895 (0.3)	1,232,582 (100)	1983
BENGKALIS	23,707 (0.8)	11,730 (0.4)	193,841 (6.3)	111,578 (3.6)	-	226,095 (8.6)	-	2,056,307 (66.5)	426,517 (13.8)	3,089,783 (100)	1983

Notes :

1. The value in () denotes the proportion
2. Source : Kabupaten concerned with the study

1.2.3 Agriculture

The cultivated area and food crop production in Kabupaten Indragiri Hilir in 1984 was 54,297 ha and 191,599 tons respectively as shown in Table 1-2-4. Of food crops, the area and production of paddy which consists of wet paddy and upland paddy was 47,315 ha and 174,143 tons respectively which are 87.1% and 90.9% of the total food crops. The yield rate of paddy production is 3.68 tons per ha. Thus, paddy is the most predominant agricultural crop of the Kabupaten.

As the table shows, average annual growth rates of area and production of paddy in 1980 through 1984 were 5.1% and 9.5% respectively which show a favorable development of paddy production.

A characteristic of the Kabupaten paddy production is that the wet paddy field forms approximately 93% of the total cultivated area.

The commodity crops, of which palm oil and rubber are major, are produced by the plantations. The area and production of plantation crops in 1984 were 163,429 ha and 78,175 tons respectively with current growth rates being 7.1% and 3.1% respectively. Thus the plantation crop, which is an export product, is important agriculturally. Some changes are expected considering the international balance of supply and demand.

The population of the agricultural sector is 74.0% of the total population as shown in Table 1-2-6. Thus the Kabupaten is an agricultural Kabupaten.

Future agricultural development in the Kabupaten depends upon an improvement programme through irrigation projects in order to promote more intensive productivity together with the enforcement of transmigration programmes.

Table 1-2-4

AREA AND PRODUCTION OF FOOD CROPS

KABUPATEN : INDRAGIRI HILIR

CULTIVATED AREA

ITEM	YEAR						(ha)
	1979	1980	1981	1982	1983	1984	AAGR (%)
PADDY	39,314	38,743	45,459	44,295	42,320	47,315	5.1
OTHERS	5,025	4,541	10,692	15,179	22,131	6,982	11.1
TOTAL	44,339	43,284	56,151	59,474	64,451	54,297	5.8

PRODUCTION

ITEM	YEAR						(ton)
	1979	1980	1981	1982	1983	1984	AAGR (%)
PADDY	105,633	92,317	132,790	150,731	148,764	174,143	9.5
OTHERS	6,420	4,509	8,153	28,966	46,845	17,456	40.3
TOTAL	112,053	96,826	140,943	179,697	195,609	191,599	18.6

YIELD RATE

ITEM	YEAR						(ton/ha)
	1979	1980	1981	1982	1983	1984	AAGR (%)
PADDY	2.69	2.38	2.92	3.40	3.52	3.68	6.0

Notes :

1. AAGR : Average annual growth rate
2. Source : Kabupaten concerned with the study

Table 1-2-5 AREA AND PRODUCTION OF PLANTATION CROPS
Year : 1983

PROVINCE : RIAU

KABUPATEN	AREA (ha)	PRODUCTION (ton)	AAGR (%)	
			AREA	PRODUCTION
INDRAGIRI HULU	81,054	21,696	7.8	2.7
INDRAGIRI HILIR	163,429	78,175	7.1	3.6
BENGKALIS	111,578	32,980	8.4	7.1

Table 1-2-6 POPULATION OF AGRICULTURAL SECTOR

PROVINCE : RIAU

KABUPATEN	AGRICULTURAL SECTOR	TOTAL POPULATION	PROPORTION (%)	AAGR		SURVEY YEAR
				(%)		
INDRAGIRI HULU	223,000	259,032	86.0	5.0		1982
INDRAGIRI HILIR	314,000	424,583	74.0	1.5		1984
BENGKALIS	553,000	639,607	86.4	5.5		1983

Notes :

1. AAGR : Average annual growth rate
2. Source : Kabupaten concerned with the Study

1.2.4 Other Economic Activities

Notable economic activities excluding agriculture in Kabupaten Indragiri Hilir are the livestock and forestry sectors.

The following shows the low growth rate of forestry production in recent years.

	<u>1980</u>	<u>1984</u>	<u>AAGR (%)</u>
Production (m ³)	228,242	235,576	0.8

Notes : 1. AAGR : Average annual growth rate

2. Source : Kabupaten data

There is no exact data from which to judge whether the production is used only for the Kabupaten consumption as green wood or exported as sawn wood from Dumai Harbour.

The following shows the growth of livestock production.

	<u>1980</u>	<u>1984</u>	<u>AAGR (%)</u>
Production (ton)	4,575	6,485	9.1

Notes : 1. AAGR : Average annual growth rate

2. Source : Kabupaten data

Judging from present conditions approximately. 5,000 tons are exported from the Kabupaten, therefore this Kabupaten sector is expected to continue to prosper.

The fishery and manufacturing industries are both in less advanced sectors and have just enough production volume to supply the consumption of the Kabupaten itself.

1.3 Present Status of Kabupaten Roads

1.3.1 Outline of Road Networks

The existing transportation system in Kabupaten Indragiri Hilir still relies mainly upon river transportation which leads in all directions, therefore the Kabupaten roads only take a complementary role.

There is one provincial road which reaches Kuala Getek from Tembila-han, the Kabupaten capital leading from Rengat, a neighbouring Kabupa-ten capital. However, it does not appear to be a regional trunk line due to its unsatisfactory surface conditions at present and its geographically unfavorable route as an access road for the whole region.

To unify the regional transportation systems effectively it seems that in Kabupaten Indragiri Hilir it is necessary to improve and extend the existing provincial roads in collaboration with consolida-tion of the infra-structures needed for development of other sectors.

1.3.2 Road Inventory

From the road inventory data prepared by the Kabupaten, the number and total length of Kabupaten roads to be studied in Kabupaten Indragiri Hilir are confirmed as 31 links and 330 Km respectively. These figures exclude Kabupaten roads with no data.

According to the data the present status of the Kabupaten roads is as follows:

(1) Density of Kabupaten Roads

The density of the Kabupaten roads is 0.26 m per ha. This is lower than the national density of 0.48 m per ha and distinctly lower than 2.11 m per ha which is the density in Jawa Island, excluding DKI Jakarta, as shown in the following table. Thus, the Kabupaten lags behind in density of Kabupaten roads.

	<u>Total Length</u> (km)	<u>Area</u> (ha)	<u>Density</u> (m/ha)
Kabupaten: Indragiri Hilir	330	1,232,582	0.26
Province : Riau	1,882	5,907,756	0.32
Jawa Is. (Excluding DKI Jakarta)	27,715	13,159,700	2.11
Indonesia	92,038	191,944,300	0.48

Notes : 1. The value for the province is the total value for the Kabupatens included in the study.

2. The sources of data are as follows:

Kabupaten and Province : Bina Marga Inventory

Jawa and Indonesia : Statistical Yearbook of Indonesia 1984, published by the Central Statistics Bureau.

(2) Kabupaten Road Surface Type

The type of surface on the Kabupaten roads in the Kabupaten is shown in Table 1-3-1.

The legend used in the table is as follows:

ASP : Asphalt

Table 1-3-1 EXISTING ROAD LENGTH BY SURFACE TYPE

PRDV : BIAU KAB : INDRAGIRI MHLIN

(Km)							(Km)						
LINK	102 (7)	INH	BIB	L.L	KRK	TOTAL	LINK	102 (7)	INH	BIB	L.L	KRK	TOTAL
LINK 1	1	4	1	1	1	5	LINK 17	17	3	1	1	1	3
LINK 2	2		1	23	1	23	LINK 18	18	22	1	1	1	22
LINK 3	3		1	1	12	12	LINK 19	19	6	1	1	1	6
LINK 4	4		1	17	1	17	LINK 20	20	16	1	1	1	16
LINK 5	5		1	9	1	9	LINK 21	21	8	1	1	1	8
LINK 6	6		1	16	1	16	LINK 22	22	2	1	1	1	2
LINK 7	7		1	17	1	17	LINK 23	23	4	1	1	1	4
LINK 8	8		1	9	1	9	LINK 24	24	3	1	1	1	3
LINK 9	9		1	16	1	16	LINK 25	25	7	1	1	1	7
LINK 10	10	1	1	1	7	8	LINK 26	26	5	1	1	1	5
LINK 11	11	12	1	1	1	12	LINK 27	27	8	1	1	1	8
LINK 12	12	9	1	1	1	9	LINK 28	28	5	1	1	1	5
LINK 13	13	6	1	1	1	6	LINK 29	29	10	1	1	1	10
LINK 14	14	13	1	1	1	13	LINK 30	30	20	1	1	1	20
LINK 15	15	16	1	1	1	16	LINK 31	31	13	1	1	1	13
LINK 16	16	10	1	1	1	10							
TOTAL							TOTAL						
203							203						
62							62						
0							0						
32							32						
6							6						
(2)							(2)						

KRK : Gravel/Stone/Telford/Water Bound Macadam

TNH : Earth

LL : Others

Comparison of the proportions of surface types in the Kabupaten with other regions is as follows:

	<u>ASP</u>	<u>KRK</u>	<u>TNH/LL</u>
Kabupaten: Indragiri Hilir	-	6.0	94.0
Province : Riau	3.0	23.3	73.7
Jawa Is. (Excluding DKI Jakarta)	56.2	25.0	18.8
Indonesia	26.0	26.6	47.4

Thus, there are no asphalt paved roads. The proportion of low grade roads such as earth roads and others is extremely high. This means that the classification of the Kabupaten roads is very low.

(3) Surface Condition of Kabupaten Roads

The surface condition of the Kabupaten roads classified as good, fair, poor and bad which are shown as BA, SD, RU and RB respectively, are summarized in Table 1-3-2.

Comparison of the proportions of the various surface conditions of the Kabupaten roads in the Kabupaten with other regions is as follows:

	<u>Good</u>	<u>Fair</u>	<u>Poor</u>	<u>Bad</u>
Kabupaten: Indragiri Hilir	8.5	31.8	43.6	16.1
Province :Riau	40.2	30.2	25.9	3.7
Jawa Is. (Excluding DKI Jakarta)	45.6	29.8	19.6	5.0
Indonesia	43.5	21.8	21.1	13.6

Table 1-3-2

EXISTING ROAD CONDITION BY SURFACE TYPE

PROVINCE : RIAU

KABUPATEN : INDRAGIRI HILIR

(KI)

LINK	PAH				DID				LIL				KAK			
	PA	SD	RU	RD	PA	SD	RU	RD	PA	SD	RU	RD	PA	SD	RU	RD
LINK 1		23	26	51		10	30	40								
LINK 2									45	27	29					
LINK 3														48	42	40
LINK 4										53	40					
LINK 5										56	42	2				
LINK 6										71	26					
LINK 7										59	41					
LINK 8									44	33	2					
LINK 9									3	41	33					
LINK 10		60	40											55	40	5
LINK 11		79	21													
LINK 12		81	19													
LINK 13		26	74													
LINK 14		33	67													
LINK 15		3	61	36												
LINK 16			56	44												
LINK 17			69	32												
LINK 18			58	43												
LINK 19			73	27												
LINK 20			66	34												
LINK 21			61	39												
LINK 22			10	40												
LINK 23			30	43												
LINK 24			70	30												
LINK 25	3	26	47	9												
LINK 26	02	18														
LINK 27			74	26												
LINK 28			56	18												
LINK 29			72	20												
LINK 30	35	31	35													
LINK 31	32	40	20													
AVERAGE	7	18	51	21	0	10	30	40	13	55	30		0	52	41	0
LENGTH		703 Km								107 Km				19 Km		
(Km)	14	37	101	47	0	0	0		14	59	32		0	10	0	2

The surface condition levels of the Kabupaten roads in the Kabupaten is lower than either that of Indonesia or of Jawa Island. The proportion in good condition is relatively low. Therefore improvement of Kabupaten roads in poor or bad condition is necessary.

(4) Terrain Conditions of Kabupaten Roads

The difficulty of road improvement is mainly dependent upon the terrain conditions.

The terrain conditions of the Kabupaten roads, classified as flat, hilly, mountainous and swampy which are shown as DT, BK, GN and RW, are summarized in Table 1-3-3.

The proportions of terrain conditions in the Kabupaten are 2.0% flat, and 98.0% swampy. There are no mountainous areas in the Kabupaten. However, road construction is anticipated to be difficult because of the large proportion of swampy ground.

1.3.3 Bridge Inventory

A bridge inventory showing the existing condition of bridges on the Kabupaten roads in Kabupaten Indragiri Hilir was prepared by the Kabupaten.

The bridges types are classified as timber, concrete, steel and others which are shown in the inventory as KY, BT, BJ and LL respectively.

The inventory shown in Table 1-3-5 indicates a total of 157 bridges with a total length of 3,059 m of which 100% are timber. On the other hand, 61 bridges with a total length of 1086 m are required to be newly constructed.

Table 1-3-3 EXISTING ROAD LENGTH BY TERRAIN CONDITION

PROV : RIAU KAB : INDRAGIRI HILIR

(Km)

NO	LINK	RW	DT	TOTAL
1	LINK 1	5		5
2	LINK 2	23		23
3	LINK 3	12		12
4	LINK 4	17		17
5	LINK 5	9		9
6	LINK 6	16		16
7	LINK 7	17		17
8	LINK 8	9		9
9	LINK 9	16		16
10	LINK 10		8	8
11	LINK 11	12		12
12	LINK 12	9		9
13	LINK 13	6		6
14	LINK 14	13		13
15	LINK 15	16		16
16	LINK 16	10		10
17	LINK 17	3		3
18	LINK 18	22		22
19	LINK 19	6		6
20	LINK 20	16		16
21	LINK 21	8		8
22	LINK 22	2		2
23	LINK 23	4		4
24	LINK 24	3		3
25	LINK 25	7		7
26	LINK 26	5		5
27	LINK 27	8		8
28	LINK 28	5		5
29	LINK 29	10		10
30	LINK 30	20		20
31	LINK 31	13		13
TOTAL		322	8	330
RATIO		98	2	(%)

Table 1-3-4 NUMBER AND LENGTH OF BRIDGES

PROV : RIAU KAB : INDRAGIRI HILIR

<<< BRIDGE >>> (UNIT: m)

LINK NO	EXISTING		NOT EXIST		TOTAL	
	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH
1	1	12.00			1	12.00
2	21	187.00			21	187.00
3	5	45.00			5	45.00
4			8	54.00	8	54.00
5	7	78.00			7	78.00
6	32	834.00			32	834.00
7	22	714.00	1	30.00	23	744.00
8	13	171.00			13	171.00
9			8	86.00	8	86.00
10	7	93.00			7	93.00
11	6	75.00			6	75.00
12	8	150.00			8	150.00
13	4	110.00			4	110.00
14	12	172.00			12	172.00
15			6	130.00	6	130.00
16	1	30.00	4	80.00	5	110.00
17			3	70.00	3	70.00
18			3	75.00	3	75.00
19			3	55.00	3	55.00
20			3	75.00	3	75.00
21			6	90.00	6	90.00
22	3	60.00			3	60.00
23	4	58.00			4	58.00
24	3	50.00			3	50.00
25			4	86.00	4	86.00
26	3	45.00			3	45.00
27			7	120.00	7	120.00
28			5	135.00	5	135.00
29	5	175.00			5	175.00
TOTAL	157	3059.00	61	1086.00	218	4145.00

Table 1-3-5 NUMBER OF EXISTING BRIDGES BY BRIDGE TYPE

PRUV : RIAU KAB : INDRAGIRI KILIR

(No)

	(103 (18))	KY
LINK 1	1	1
LINK 2	21	1
LINK 3	5	1
LINK 4		1
LINK 5	7	1
LINK 6	32	1
LINK 7	22	1
LINK 8	13	1
LINK 9		1
LINK 10	7	1
LINK 11	6	1
LINK 12	8	1
LINK 13	4	1
LINK 14	12	1
LINK 15		1
LINK 16	1	1
LINK 17		1
LINK 18		1
LINK 19		1
LINK 20		1
LINK 21		1
LINK 22	3	1
LINK 23	4	1
LINK 24	3	1
LINK 25		1
LINK 26	3	1
LINK 27		1
LINK 28		1
LINK 29	5	1
TOTAL	157	1
RATIO		1

The number of existing bridges by span length is as follows:

<u>Bridges Type</u>	<u>Span Length (m)</u>										<u>Total</u>
	<u><3</u>	<u><5</u>	<u><8</u>	<u><10</u>	<u><12</u>	<u><14</u>	<u><16</u>	<u><18</u>	<u><20</u>	<u><99</u>	
Timber	96	49	6	1	-	-	1	1	1	2	157
Concrete	-	-	-	-	-	-	-	-	-	-	-
Steel	-	-	-	-	-	-	-	-	-	-	-
Others	-	-	-	-	-	-	-	-	-	-	-
Total	96	49	6	1	-	-	1	1	1	2	157

Thus, all of the existing bridges on the Kabupaten roads are timber and the majority of spanlengths is less than 3 m.

1.3.4 Traffic

Inventories of the average daily traffic (ADT) on the Kabupaten roads in Kabupaten Indragiri Hilir were prepared by the Kabupaten and are shown in Chapter 2.

From the inventories, total value of average daily trips by vehicle type and their proportions in the Kabupaten in 1985 are summarized as follows:

	<u>SEDAN</u>	<u>BUS</u>	<u>TRUCK</u>	<u>MOTOR- CYCLE</u>	<u>TOTAL</u>
Total Trips	3	0	0	1,473	743
Proportion (%)	0.27	0.00	0.00	99,73	100.00

Source : Bina Marga Inventory

The proportions of registered vehicles by vehicle type are as follows:

	<u>SEDAN</u>	<u>BUS</u>	<u>TRUCK</u>	<u>MOTOR- CYCLE</u>	<u>TOTAL</u>
Proportion (%)	0.07	0.29	48.00	51.64	100.00

Source : Kabupaten.

Thus, the proportion of motorcycles in the Kabupaten is by far the highest.

From the above tables the following can be observed:

- Number of total trips might be underestimated
- Proportions are probably reasonable.

Essentially, for estimation of future traffic volumes past and present traffic data together with the trend in the number of registered vehicles are important basic data. However the data obtained for the study was traffic count data for each road link in 1985 and of low reliability.

Therefore the future traffic volumes are estimated by the calculation process recommended in chapter 3 of the Main Report.

Chapter 2 ESTIMATIONS OF FUTURE TRAFFIC VOLUME AND BENEFIT

2.1 Future Traffic Volume

2.1.1 Traffic Growth Rate

The traffic growth rate used for estimation of the future traffic volume on the Kabupaten roads was estimated by the following calculation process.

Growth of Production Basis "A":

$$\sqrt{\text{Annual Population Growth of the Kabupaten} \times \text{Growth of the Total Cultivated Area}}$$

Growth of Productivity "B":

$$\sqrt{\text{Growth of the Total Paddy Field Area} \times \text{Growth of the Paddy Production per ha}}$$

Traffic Growth Rate: Initial estimated figure:

$$\overline{GR'} = \sqrt{A \times B}$$

Traffic Growth Rate GR = Final adjusted figure:

$$\sqrt{\overline{GR'} \times \text{Trend of GDP/Capita of the Province Concerned}}$$

Results of the estimation are shown in Table 2-1-1.

Table 2-1-1 TRAFFIC GROWTH RATE ESTIMATION

PROV : RIAU KAB : INDRAGIRI HILIR

A)	Growth Rate of Population	:	2.00 (%)
B)	Growth Rate of Cultivated Area	:	6.00 (%)
C)	Growth Rate of Rice field	:	5.00 (%)
D)	Growth Rate of Rice yield rate	:	6.00 (%)
E)	Growth Rate of GDP / capita	:	6.80 (%)

a)	Geometrical Mean (A x B)	:	3.98 (%)
b)	Geometrical Mean (C x D)	:	5.50 (%)
c)	Geometrical Mean (a x b)	:	4.74 (%)
d)	Geometrical Mean (c x E)	:	5.76 (%)

	TRAFFIC GROWTH RATE	:	5.76 (%)

2.1.2 Present and Future Traffic Volume

The future traffic volumes on the Kabupaten roads in 1998 for the Project life time of ten years were estimated by the following formula :

$$T_n = T_e (1 + r)^n$$

Where :

T_n : Future traffic volume n years later

T_e : Traffic volume in 1985

r : Traffic growth rate

The results are shown in Table 2-1-2 together with the traffic volume in 1985.

Table 2-1-2 EXISTING AND FUTURE TRAFFIC VOLUME

PROV : RIAU KAB : INDRAGIRI HILIR

< SPD : 1/2 >

LINK NO	INVENTORY (1985)					RATE	AFTER 13 YEARS (1998)					CLASS
	NBL	BUS	TRUK	SPD	TOTAL		NBL	BUS	TRUK	SPD	TOTAL	
1	3	0	0	100	53	5.8%	6	0	0	207	110	111B-2
2	0	0	0	35	18	5.8%	0	0	0	72	37	111C
3	0	0	0	100	50	5.8%	0	0	0	207	104	111B-2
4	0	0	0	40	20	5.8%	0	0	0	83	41	111C
5	0	0	0	50	25	5.8%	0	0	0	104	52	111B-2
6	0	0	0	50	25	5.8%	0	0	0	104	52	111B-2
7	0	0	0	30	15	5.8%	0	0	0	62	31	111C
8	0	0	0	40	20	5.8%	0	0	0	83	41	111C
9	0	0	0	50	25	5.8%	0	0	0	104	52	111B-2
10	0	0	0	70	35	5.8%	0	0	0	145	72	111B-2
11	0	0	0	30	15	5.8%	0	0	0	62	31	111C
12	0	0	0	40	20	5.8%	0	0	0	83	41	111C
13	0	0	0	30	15	5.8%	0	0	0	62	31	111C
14	0	0	0	30	15	5.8%	0	0	0	62	31	111C
15	0	0	0	30	15	5.8%	0	0	0	62	31	111C
16	0	0	0	20	10	5.8%	0	0	0	41	21	111C
17	0	0	0	50	25	5.8%	0	0	0	104	52	111B-2
18	0	0	0	60	30	5.8%	0	0	0	124	62	111B-2
19	0	0	0	20	10	5.8%	0	0	0	41	21	111C
20	0	0	0	250	125	5.8%	0	0	0	518	259	111B-1
21	0	0	0	30	15	5.8%	0	0	0	62	31	111C
22	0	0	0	25	13	5.8%	0	0	0	52	27	111C
23	0	0	0	25	13	5.8%	0	0	0	52	27	111C
24	0	0	0	60	30	5.8%	0	0	0	124	62	111B-2
25	0	0	0	3	2	5.8%	0	0	0	6	4	111C
26	0	0	0	3	2	5.8%	0	0	0	6	4	111C
27	0	0	0	15	8	5.8%	0	0	0	31	17	111C
28	0	0	0	50	25	5.8%	0	0	0	104	52	111B-2
29	0	0	0	125	63	5.8%	0	0	0	259	130	111B-2
30	0	0	0	6	3	5.8%	0	0	0	12	6	111C
31	0	0	0	6	3	5.8%	0	0	0	12	6	111C
PERCENT	0.20	0.00	0.00	99.80			0.20	0.00	0.00	99.80		

2.2 Benefit

2.2.1 Benefit Estimation Method

Generally, estimation of the benefit on each Kabupaten road due to the Project was made by analyzing the direct benefit i.e. the VOC reduction benefit, which was estimated by comparing "with project" and "without project" based upon the future traffic volume on the road. However for the following road links it was decided to estimate the indirect benefit through the producer's surplus benefit.

- a) Road links with present traffic volume (ADT) less than 60 equivalent 4-wheel vehicles.
- b) Road links with no 4-wheel vehicle operation at present.

The indirect benefit was changed into the future traffic volume and the VOC reduction benefit was estimated.

The VOC adopted for the estimation is shown in Table 2-2-1.

Table 2-2-1 VEHICLE OPERATION COST ON KABUPATEN ROADS

SURFACE	CONDITION	(KM)			
		SEDAN	BUS	TRUCK	MOTORCYCLE
ASPHALT	GOOD	104.7	86.2	85.4	15.9
	Fair	125.5	101.0	98.0	18.2
	Poor	164.1	135.2	138.5	22.8
	Bad	222.1	202.0	205.0	29.1
GRAVEL	Good	125.7	101.4	102.5	18.5
	Fair	145.0	124.6	127.1	21.1
	Poor	198.6	172.6	178.4	27.1
	Bad	242.7	228.9	231.2	31.8
EARTH	Fair	201.8	180.0	185.1	28.0
	Poor	240.7	218.2	225.8	31.8
	Bad	264.9	278.0	281.7	35.5

Source : Bina Marga

Table 2-2-2

FUTURE TRAFFIC VOLUME ESTIMATED
BY THE PRODUCER'S SURPLUS

FROM : RIAU KAB : INDRAGIRI HILIR

(1998)

LINK NO	CLASS	SURFACE	MOBIL	BUS	TRUCK	SEPEDA	TOTAL
1	IIIB-1	ASP	20	4	32	410	261
2	IIIA	ASP	39	7	61	791	503
3	IIIB-1	ASP	31	6	49	630	401
4	IIIB-1	ASP	26	5	41	528	336
5	IIIB-1	ASP	20	4	32	408	260
6	IIIB-1	ASP	35	7	56	725	461
7	IIIA	ASP	82	16	131	1688	1073
8	IIIA	ASP	62	12	99	1280	813
9	IIIA	ASP	111	21	176	2276	1446
10	IIIA	ASP	55	11	88	1138	723
11	IIIA	ASP	83	16	132	1707	1085
12	IIIB-1	ASP	24	5	39	500	318
13	IIIB-1	ASP	16	3	26	333	212
14	IIIB-1	ASP	30	6	48	620	394
15	IIIB-1	ASP	32	6	51	656	417
16	IIIB-1	ASP	20	4	32	410	261
17	IIIB-2	KRK	6	1	10	123	79
18	IIIA	ASP	142	27	225	2911	1850
19	IIIB-2	KRK	7	1	10	134	85
20	IIIA	ASP	68	13	108	1398	888
21	IIIB-1	ASP	34	7	54	699	445
22	IIIB-2	KRK	9	2	14	181	116
23	IIIB-1	ASP	18	3	28	362	230
24	IIIC	KRK	3	1	5	67	43
25	IIIB-1	ASP	20	4	32	414	263
26	IIIB-1	ASP	21	4	34	437	278
27	IIIA	ASP	46	9	72	937	596
28	IIIA	ASP	47	9	75	974	618
29	IIIA	ASP	40	8	63	819	521
30	IIIA	ASP	44	8	70	906	575
31	IIIB-1	ASP	29	5	46	589	375

2.2.2 Benefit

The benefit estimation was carried out for each Kabupaten road. Table 2-2-3 shows a sample of the result of benefit estimation. In the table "surplus" and "VOC" show the estimation method utilized and III A, III B-1, III B-2 and III C show the road classification.

Table 2-2-3

RESULTS OF BENEFIT ESTIMATION

KABUPATEN : INDRAGIRI HILIR

(1000Rupiah)

	LINK 1	LINK 2	LINK 3	LINK 4	LINK 5	LINK 6	LINK 7	LINK 8	LINK 9	LINK 10
	5 Km	23 Km	12 Km	17 Km	9 Km	16 Km	17 Km	9 Km	16 Km	8 Km
	IIIB-1	IIIA	IIIB-1	IIIB-1	IIIB-1	IIIB-1	IIIA	IIIA	IIIA	IIIA
YEAR	Surplus	Surplus	Surplus	Surplus	Surplus	Surplus	Surplus	Surplus	Surplus	Surplus
1988	0	0	0	0	0	0	0	0	0	0
1989	14616	67558	28586	45069	12709	34252	89873	18625	102878	32450
1990	15495	67893	30440	45521	13528	36514	96375	20046	110236	34676
1991	16612	69536	32675	46388	14320	38498	103066	21527	118851	37168
1992	17846	70392	35003	47717	15579	40899	110458	23163	127840	40200
1993	19298	71783	37051	48684	16264	43719	118447	24848	137035	42872
1994	20355	73078	39494	50063	17187	46019	126815	26834	147736	46350
1995	21807	74078	42362	51929	18377	49373	136585	28857	158306	50091
1996	23318	75517	44921	53047	19832	52548	146008	30989	170383	53576
1997	25371	77004	47997	54576	21248	56044	157218	33299	183584	57841
1998	27001	78587	51894	56155	22568	59753	168516	35796	197264	62023
SUM	201719	725426	390423	499149	171612	457619	1253361	263984	1454093	457247
COST	90315	314938	162776	208374	51442	181043	636870	104370	757437	222010
/Km	18063	13693	13565	12257	5716	11315	37483	11597	47340	27751

Chapter 3 ENGINEERING

3.1 Design Criteria and Specification

3.1.1 Geometric Design Criteria

Currently a technical standard for improvement of Kabupaten roads i.e. PETUNJUK TEKNIS INPRES PENUNJANGAN JALAN KABUPATEN, TAHUN 1984-1985 is established by Bina Marga.

The geometric design criteria in the above standard are recommended to be adopted in general for the Project. Following discussions with Bina Marga, exceptions to this are allowed for Pavement width and pavement type to minimize the construction cost of the Kabupaten road improvement, if necessary. The geometric design criteria adopted for the Project are shown in Table 3-1-1. The typical cross sections of Kabupaten roads are shown in Fig. 3-1-1.

3.1.2 Loading Specification

The LOADING SPECIFICATIONS FOR HIGHWAY BRIDGES BY DIRECTORATE GENERAL BINA MARGA is used in principle as the basic specification of loading and the TECHNICAL STANDARD FOR KABUPATEN ROADS compiled by Bina Marga shows that the design live load for bridges on Kabupaten roads is 70% of the Bina Marga live road. However, after discussions with Bina Marga the following loads were decided as the design live loads for the standard bridges of Kabupaten roads:

- a. 50% of Bina Marga live load (hereinafter BM 50) is applied for concrete and timber bridges on roads of III A classification.
- b. 10-ton truck load is applied for timber bridges on roads of III B-1, III B-2 and III C classification.


Table 3-1-1

DESIGN CRITERIA FOR KABUPATEN ROADS

ROAD CLASSIFICATION		CLASS III A			CLASS III B-1			CLASS III B-2			CLASS III C		
SURFACE TYPE		ASPHALT SEAL (DOUBLE)			ASPHALT SEAL (SINGLE)			GRAVEL			GRAVEL		
TRAFFIC VOLUME : ADT (Forecast 10 th year average per day)		3000 - 500			500 - 200			200 - 50			50		
T E R R A I N		FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS
TRAFFIC LANES		1+	1+	1+	1+	1+	1+	1+	1+	1+	1	1	1
DESIGN (Km/hr)	DESIRABLE	70	60	40	70	40	30	60	40	30	50	30	AS PRACTI- CABLE
	MINIMUM	30	30	30	30	30	AS PRACTI- CABLE	30	30	AS PRACTI- CABLE	30	AS PRACTI- CABLE	
GRADIENT (%)	DESIRABLE	4	5	8	4	6	8	4	7	8	5	8	12
	MAXIMUM	7	7	10	7	8	10	7	9	12	7	12	16
PAVEMENT WIDTH (M)	DESIRABLE	6.0	6.0	6.0	4.5	4.5	4.5	4.5	4.5	4.5	3.5	3.5	3.5
	MINIMUM	4.5	4.5	4.5	3.5	3.5	3.5	3.5	3.5	3.5	3.0	3.0	3.0
SHOULDER WIDTH (M)	DESIRABLE	2.0	1.5	1.5	1.5	1.5	1.0	1.5	1.0	1.0	1.0	1.0	0.75
	MINIMUM	1.5	1.0	0.75	1.0	1.0	0.75	1.0	0.75	0.5	0.75	0.5	0.5
ROAD BED WIDTH (M)	DESIRABLE	10.0	9.0	9.0	8.0	7.5	6.5	7.5	6.5	6.5	5.5	5.5	5.0
	MINIMUM	6.0	6.0	6.0	5.5	5.5	5.0	5.5	5.0	4.5	4.5	4.0	4.0
RIGHT OF WAY (M)	DESIRABLE	16	16			12			12			12	
	MINIMUM	12	12			10			10			8	
ROAD CAMBER (%)	PAVEMENT	3	3			3			4			4	
	SHOULDER	4	4			4			5			5	

STANDARD ROAD CROSS SECTIONS

Fig. 3-1-1



3.2 Pavement Design

3.2.1 Design Conditions

From the engineering data prepared by the Kabupaten it is noted that the pavement structure of the Kabupaten roads seems to have been determined without adequate designs, therefore the Kabupaten roads generally have insufficient capacity. The standards generally used for highway pavement design such as Road Note 29, Road Note 31 and AASHTO are not suitable for Kabupaten roads with small traffic volumes and loads.

Therefore formulae suitable for the pavement design of Kabupaten roads are recommended as described in Chapter 5 of the Main Report.

The following are important factors for the design of pavement thickness.

1) Design Traffic Volume

As the pavement thickness is designed for each road classification the design traffic volume of which the target year is 1998, is adopted for each classification as follows:

<u>Road Classification</u>	<u>Design Traffic Volume (vpd)</u>
III A	1,000
III B-1	500
III B-2	200
III C	50

2) Strength of Roadbed


The CBR value of the existing roadbed is a very important factor for the pavement design but no results are available from CBR tests on the Kabupaten roads.

CBR of the laterite is generally in the range of CBR 4 to 10. However site CBR tests should be conducted before construction to finally decide the pavement thickness.

3.2.2 Pavement Structure

Fig. 3-2-1 shows the standard pavement structures adopted for the Kabupaten roads. In the Kabupaten aggregate material is difficult to obtain and so the price is extremely high, therefore the cement stabilization method is recommended for both the base and sub-base courses as a substitute for crusher run or river gravel.

Fig. 3-2-1



3.3 Design of Bridges and Other Structures

3.3.1 Standard Bridge

There are so many bridges to be improved or to be constructed on the Kabupaten roads in the Project Area that it is very difficult to prepare an individual design for each bridge. Therefore, standardization is recommended as being necessary for the bridge design with conclusions as described below.

(1) Bridge Type

1) Superstructure

The following two types have been finally selected with the agreement of Bina Marga after studying the actual rural conditions of bridge construction. Fig. 3-3-1 shows the cross sections of standard types.

- a. Timber beam bridge (hereinafter timber bridge) for roads class III B-1, III B-2 and III C.
- b. Reinforced concrete T-girder bridge (hereinafter RC-bridge) for roads class III A.

2) Substructure

Taking account of the actual combinations of super and substructure types noted from the field survey, the following two types are recommended as standard because of ease of construction and economy.

- a) Timber pile bents for timber bridge
- b) Rubble in mortar masonry for RC bridge

3) Foundation


There is no information of subsoil conditions in the inventory data. However, timber piles of 20 cm diameter are generally recommended as piles of this type are in common use.

The pile length is suggested to be a minimum of 3 meters under the bottom of the foundation. The length and number of piles should be decided in order to be adequate for the condition of the foundation materials.


Fig. 3-3-1

CROSS SECTIONS OF STANDARD BRIDGES

TIMBER BRIDGE



REINFORCED CONCRETE BRIDGE



(2) Bridge Width

The effective bridge widths for the standard bridges have been decided as follows through discussions with Bina Marga considering the actual width of Kabupaten roads:

- a) Timber bridge: 4.0 m in general
- b) RC bridge : 4.5 m in general

(3) Span Length

The range of span lengths are determined as:

- a) Timber bridge: 3.0, 5.0 and 8.0 m
- b) RC bridge : 3.0, 5.0, 10.0 and 15.0 m

3.3.2 Other Structure

Culverts and retaining walls shown in Fig. 3-3-2 and Fig. 3-3-3 are recommended as standard structures.

(1) Culvert

The following two culvert types have been adopted for the transverse drainage.

- a) Reinforced concrete pipe culvert ϕ 80 cm
- b) Rubble in mortar box culvert with RC slab 80 cm X 80 cm

(2) Retaining Wall


The following two types of retaining walls have been adopted because of ease of construction, economy and familiarity in Indonesia.

- a) Rubble in mortar retaining wall
- b) Timber retaining wall


Fig. 3-3-3

STANDARD RETAINING WALLS

TIMBER RETAINING WALL



RUBBLE IN MORTAR WALL



3.4.1 Points to be Considered for the Selection

Full consideration was given to the following points in studying the selection of equipment type.

- a. Most of the construction in the Project is pavement works for road improvement.
- b. The pavement width adopted is equal to or less than 4.5 m and therefore large sized equipment is omitted from the selection process.
- c. Equipment should be capable of with standing the heavy rainfall and poor soil quality. Equipment for construction in swampy areas is considered if necessary.
- d. Uniformity of equipment types with existing equipment is considered to facilitate repair of the equipment in the provincial work shop.
- e. Since the scale of the construction is small and transportation of equipment will frequently be necessary, wheel type equipment has been selected as much as possible as this can move by itself or by being towed.
- f. The road like to be improved are scattered all over the Kabupatens and therefore a low bed truck or equivalent is necessary for transportation of crawler type equipment. It is desirable to protect the existing pavement from damage caused by the movement of crawler type equipment on the existing roads.
- g. The capacity of the equipment has been decided taking into consideration the construction volume and the combination of equipment in the main work.

3.4.2 Combinations of Equipment for Major Works and Maintenance

The combinations of equipment for major works and maintenance are listed in Table 3-4-2 and 3-4-3 respectively.

Table 3-4-2 EQUIPMENT OF ONE WORK GANG FOR MAJOR TYPES OF WORK

TYPE OF WORK	EQUIPMENT REQUIRED	
1. Site Clearing in Light Bush	1- Bulldozer 90 HP 2- Dump Truck 3.0 Ton	1- Wheel Loader 1.2 m ³
2. Excavation & Embankment		
i) Normal Fill	1- Bulldozer 90 HP 1- Vibratory Roller 4.0 Ton (D&T)	1- Water Tank Truck 4,000 Ltr
ii) Fill by Borrow Material	1- Bulldozer 90 HP 3- Dump Truck 3.0 Ton	1- Wheel Loader 1.2 m ³
iii) Fill in Swamp	1- Swamp Bulldozer 90 HP 1- Water Tank Truck 4,000 Ltr	1- Vibratory Roller 4.0 Ton (D&T)
iv) Excavation to Spoil	1- Bulldozer 90 HP 1- Wheel Loader 1.2 m ³	4- Dump Truck 3.0 Ton
3. Subgrade Preparation	1- Motor Grader 75 HP 1- Vibratory Roller 4.0 Ton (D&T)	1- Water Tank Truck 4,000 Ltr
4. Subbase Course	1- Motor Grader 75 HP 1- Vibratory Roller 4.0 Ton (D&T)	1- Water Tank Truck 4,000 Ltr
5. Base Course	1- Motor Grader 75 HP 1- Vibratory Roller 4.0 Ton 1- Portable Crusher/Screens 30-40 Ton/H	1- Water Tank Truck 4,000 Ltr
6. Cement Stabilizing	1- Motor Grader 70 HP 1- Bulldozer 90 HP 1- Wheel Loader 1.2 m ³ 1- Flat Bed Truck 3.0 Ton	1- Vibratory Roller 4.0 Ton (D&T) 1- Road Stabilizer 1- Water Tank Truck 4,000 Ltr
7. Surface Course	1- Asphalt Sprayer 850 Ltr 1- Tyre Roller 8-15 Ton 1- Portable Crusher/Screens 30-40 Ton/H	1- Flat Bed Truck 3.0 Ton
8. Concrete	1- Concrete Mixer 0.5 m ³ 1- Water Pump 200 Ltr/Min 1- Concrete Vibrator 3.3 HP	1- Flat Bed Truck 3.0 Ton 1- Hand-Guided Vibratory Roller 1000 Kg

Table 3-4-3

EQUIPMENT OF ONE WORK GANG FOR MAINTENANCE

TYPE OF WORK	EQUIPMENT REQUIRED
Road	1- Motor Grader 1- Tyre Roller 8-15 Ton 1- Hand-Guided Vibratory Roller 1000 Kg 1- Flat Bed Truck 3.0 Ton 1- Dump Truck 3.0 Ton
Bridge and Other Structure	1- Flat Bed Truck With Crane 3.0 Ton

3.5 Workshop and Laboratory

3.5.1 Policy of the Kabupaten Workshop

A workshop will be provided for each Kabupaten. The function of the workshop is to cope with requests from the construction site. The main service will be routine maintenance while the secondary service will be light repairs which can be carried out by changing parts. Dismantling and assembling of units which need setting or adjustment using special equipment or facilities will not be carried out in the Kabupaten workshop. Such repairs are planned to be carried out by the provincial workshop or the regional workshop of Bina Marga.

Accordingly the main tasks of the Kabupaten workshop are as follows:

- 1) Administration for and storage of equipment
- 2) Routine maintenance and light repair of equipment
- 3) Storage and supply of spare parts
- 4) Operation of equipment including crushing plant.

3.5.2 Workshop Equipment and Tools

Equipment and tools for the workshop are recommended as shown in Table 3-5-1.

Table 3-5-1 WORKSHOP EQUIPMENT AND TOOLS

DESCRIPTION	QUANTITY
Upright Drilling Machine	1 Set
Electric Hand Drill	1
Electric Portable Grinder	1
Disc Grinder	1
Bench Electric Grinder	1
Engineer's Vice	1
DC Electric Welder with Engine	1 Set
Portable Hydraulic Jack, Screw Head	1
Hydraulic Jack	1
Grease Gun	2
Suction Pump for Oil Recovery	2
High Pressure Grease Pump	1

continued

DESCRIPTION	QUANTITY
Drum Opening Spanner	1
Silicon Normal Charger	1
Tyre Changer Air Operated	1
Tyre Service Tool Set	1
Tyre Pressure Gauge	1
Automatic Tyre Inflator	1
Plug Cleaner and Tester	1
Mechanics Tool Set, Heavy Equipment	1
Mechanics Tool Set, Large Vehicle	1
Portable Air Compressor	1
Electric Cord Reel, 15 A, 50 m	1
Oil Measure, Polyethylene	1
Funnel 200 mm, Steel	3
Hand Truck (Cart), 4-Wheel	1
Nylon Sling, 10 ton	2
Chain Block, 1 ton	2
Wire Rope (for sling), 1.8 ton	2
Wire Rope (for sling) 3.2 ton	2
Generator	1

3.5.3 Laboratory

For quality control of construction in the Project it is recommended that a laboratory is provided for each Kabupaten. For each laboratory, provision of laboratory test equipment for the following tests is recommended:

- Physical characteristic, compaction and strength tests for the road bed and pavement materials.
- Slump and strength tests for the bridge concrete.

In the laboratory a fixed water tank should be provided for CBR tests and curing of concrete specimens.

The proposed laboratory equipment is listed in Table 3-5-2.

Table 3-5-2 LABORATORY TEST EQUIPMENT

DESCRIPTION	QUANTITY
Soil Moisture Test Set (JIS A1203)	1
Liquid Limit Set (JIS A1205)	1
Plastic Limit Set (JIS A1206)	1
Compaction Set (JIS A1210)	1
CBR Laboratory Set, Mechanical (JIS A1211)	1
Sand Density Apparatus (JIS A1214)	1
Aggregate Test Sieve Set	1
Portable Cone Penetrometer	1
Compression & Bending Test Machine	1
Cylinder Mould (JIS A1132, 1108)	9
Slump Test Apparatus (JIS A1101)	2

To conduct the surveys necessary for road and structure construction such as centering, profile leveling, cross section leveling etc., the surveying equipment listed in Table 3-5-3 recommended.

Table 3-5-3 SURVEYING EQUIPMENT

DESCRIPTION	QUANTITY
Transit	1
Level	1
Staff	3

Chapter 4 CONSTRUCTION AND MAINTENANCE COST ESTIMATIONS

4.1 Unit Price

With regard to the unit prices of materials and labor, the data were collected from each Kabupaten through Bina Marga. The collected data were compared with those of Jakarta using BAHAN BANGUNAN DKI-JAKARTA MAY & JUNE 1985 compiled by PUSAT INFORMASI TEHNIK PEMBANGUNAN, and then finalized.

4.1.1 Unit Labour Price

The unit labour prices of Kabupaten Indragiri Hilir and other Kabupatens in Riau Province are shown in Table 4-1-1.

Table 4-1-1 UNIT LABOUR PRICE

KABUPATEN	MAN	SKL LAB	CAP	MAS	LAB	DRIV	(Rp)
							OPE
Indragiri Hulu	4,400	3,300	4,400	4,400	2,750	3,300	5,500
Indragiri Hilir	4,400	3,250	4,500	4,500	2,750	5,000	5,000
Bengkalis	3,000	3,000	3,500	3,500	2,500	3,500	4,500
Average	3,800	3,185	4,135	4,135	2,667	3,935	5,000

Notes :

- MAN : Mandur
- SKL LAB : Skilled Labour
- CAP : Carpenter
- MAS : Mason
- LAB : Labourer
- DRIV : Driver
- OPE : Operater

4.1.2 Unit Price of Materials

Table 4-1-2 shows the unit price of materials for Kabupaten Indragiri Hilir together with for other Kabupaten in Riau Province.

The unit price of river stone in the Kabupaten which has direct effects upon construction costs is significantly high.

Stone and sand are not produced in the Kabupaten. Therefore unit prices of these materials include the shipping cost from the producing Kabupaten.

Table 4-1-2 UNIT PRICE OF MATERIALS

MATERIAL	UNIT				(Rp)
		INDRAGIRI HULU	INDRAGIRI HILIR	BENGKALIS	AVERAGE
Bitumen	L	400	750	350	500
Asphalt Oil	L	1,500	1,500	1,500	1,500
Gasoline	L	250	250	250	250
Sand	M ³	4,000	4,500	15,000	3,667
Cement	bag	4,500	6,000	4,800	5,100
River Stone	M ³	20,000	30,000	40,000	30,000
Steel moulds	Set	8,000	8,000	8,000	8,000
Timber	M ³	85,000	180,000	110,000	125,000
Paint	L	2,500	2,000	2,500	2,333
Reinforcing Steel	Kg	500	1,200	750	817
Tying	Kg	1,200	1,000	1,200	1,133

4.1.3 Hourly Equipment Cost

The hourly equipment cost for Kabupaten is shown in Table 4-1-3.

Table 4-1-3

HOURLY EQUIPMENT COST

PROVINCE : RIAU
KABUPATEN : INDRAGIRI HILIR

(UNIT : Rp) ('85)

CODE NO	EQUIPMENT NAME	CLASS	LOCAL COST			FOREIGN COST			TOTAL COST
			OWNERSHIP	OPERATION	SUB-TOTAL	OWNERSHIP	OPERATION	SUB-TOTAL	
	Bulldozer	120 HP	195	19,796	19,991	7,769	1,019	8,788	28,779
	Bulldozer/Ripper	120 HP	213	20,802	21,015	8,499	1,568	10,067	31,082
	Swamp Bulldozer	120 HP	222	21,044	21,266	8,880	1,638	10,518	31,784
	Bulldozer	90 HP	123	13,742	13,865	4,914	644	5,558	19,423
	Bulldozer/Ripper	90 HP	133	14,330	14,463	5,299	977	5,276	20,739
	Bulldozer	65 HP	88	10,019	10,107	3,499	458	3,957	14,064
	Bulldozer/Ripper	65 HP	96	10,466	10,562	3,819	704	4,523	15,085
	Swamp Bulldozer	90 HP	133	14,321	14,454	5,284	974	6,258	20,712
	Swamp Bulldozer	65 HP	102	10,025	10,127	4,049	747	4,796	14,923
	Motor Grader	110 HP	173	16,805	16,978	6,920	1,276	8,196	25,174
	Motor Grader	75 HP	120	11,497	11,617	4,779	881	5,660	17,277
	Motor Grader	65 HP	108	10,064	10,172	4,299	793	5,092	15,264
	Road Stabilizer	M=1850 mm	215	3,365	3,580	8,594	422	9,016	12,596
	Vibratory Roller	4 ton	73	5,131	5,204	2,899	380	3,279	8,483
	Hand-guide Vib. Roller	1000 Kg	51	880	931	850	28	878	1,809
	Tire Roller	B-15 ton	78	12,579	12,657	3,106	101	3,207	15,864
	Vibratory Roller (D&T)	4 ton	73	5,131	5,204	2,899	380	3,279	8,483
	Hand-guide Vib. Roller	600 Kg	36	596	632	600	20	620	1,252
	Rough Terrain Crane	10 ton	251	19,686	19,937	10,040	740	10,780	30,717
	Hydraulic Excavator; Wheel	0.3 m ³	103	12,477	12,580	4,109	538	4,647	17,227
	Wheel Loader	1.2 m ³	176	12,207	12,383	7,019	920	7,939	20,322
	Wheel Loader	0.3 m ³	57	4,351	4,408	2,269	297	2,566	6,974
	Water Tank Truck	4000 ltr.	53	4,929	4,982	868	117	985	5,967
	Fuel Tank Truck	4000 ltr.	53	4,935	4,988	882	119	1,001	5,989
	Dump Truck	3.0 ton	89	5,823	5,912	1,469	199	1,668	7,580
	Flat Bed Truck with Crane	3.0 ton	43	5,180	5,223	1,717	126	1,843	7,066
	Dump Loader Truck	12 ton	96	34,221	34,317	3,838	125	3,963	38,280
	Dump Truck	5.0 ton	132	9,741	9,873	2,189	296	2,485	12,358
	Flat Bed Truck	3.0 ton	15	4,756	4,771	562	41	603	5,374
	Portable Crusher/Screening	30-40 t/h	470	32,986	33,456	18,800	2,466	21,266	54,722
	Concrete Mixer	0.5 m ³	324	2,617	2,941	5,400	412	5,812	8,753
	Water Pump	200 l/min	12	432	444	188	6	194	638
	Concrete Vibrator	3.3 HP	5	396	401	73	2	75	476
	Asphalt Sprayer	850 ltr.	62	1,014	1,076	1,019	138	1,157	2,233

4.2 Unit Construction Cost by Work Type

4.2.1 All Works Except Bridges

The unit construction costs by work type, excluding bridge construction costs, have been estimated using the combination of equipment described in Clause 3.4 and the unit prices already listed. The results are summarized in Table 4-2-1.

Table 4-2-1 UNIT COST BY WORK TYPE EXCEPT BRIDGE WORK

PROV : RIAU KAB : INDRAGIRI HILIR

(Rp)				
ITEM	UNIT	LOCAL	FOREIGN	TOTAL
Site Clearance in Light Bush	m ²	245	91	336
Subgrade Preparation	m ²	31	11	42
Normal Fill	m ³	2,574	862	3,436
Fill in Swamp	m ³	5,385	267	5,652
Normal Excavation to Spoil	m ³	1,495	522	2,017
Cement Stabilizing	m ³	11,814	14,289	26,103
Cement Stabilizing	m ³	11,814	14,289	26,103
Shoulder	m ²	447	146	593
Asphalt Patching	m ²	10,443	1,644	12,087
Surface Dressing (Single)	m ²	1,514	1,323	2,837
Surface Dressing (Double)	m ²	2,080	2,087	4,167
Earth Drain	m	1,336	119	1,455
Earth Drain in Swamp (by machine)	m ³	1,836	473	2,309
Pipe Culvert Ø80cm	m	58,867	58,844	117,711
Masonry Culvert (80x80cm)	m	118,628	44,536	163,164
Retaining Wall and Wing Wall (Timber)	m ²	18,526	246	18,772
Retaining Wall and Wing Wall (Masonry)	m ³	86,546	10,826	97,372
Gabion Protection	m ³	36,654	120	36,774
Manual routine maintenance of road	Km	220,752	7,236	227,988
Routine maintenance of earth road	Km	147,180	37,880	185,060
Routine maintenance of gravel road	Km	975,577	42,615	1,018,192
Routine maintenance of asphalt road	Km	1,044,300	164,400	1,208,700

4.2.2 Bridges

The unit construction costs by bridge type including the cost of demolition of existing bridges are shown in Table 4-2-2.

Table 4-2-2

BRIDGE COST

PROV : RIAU KAB : INDRAGIRI HILIR

				(Rp)
ITEM	UNIT	LOCAL	FOREIGN	TOTAL
Superstructure (Timber; Span 3m; IOT)	m2	67,141	2,998	70,139
Superstructure (Timber; Span 5m; IOT)	m2	74,368	3,311	77,679
Superstructure (Timber; Span 8m; IOT)	m2	98,504	4,351	102,855
Superstructure (Timber; Span 3m; BNSO)	m2	83,252	3,707	86,959
Superstructure (Timber; Span 5m; BNSO)	m2	90,888	4,019	94,907
Superstructure (Timber; Span 8m; BNSO)	m2	115,270	5,088	120,358
Superstructure (Concrete; Span 3m; BNSO)	m2	88,097	127,583	215,680
Superstructure (Concrete; Span 5m; BNSO)	m2	91,223	142,694	233,917
Superstructure (Concrete; Span 8m; BNSO)	m2	94,543	155,500	250,043
Superstructure (Concrete; Span 10m; BNSO)	m2	103,629	176,711	280,340
Superstructure (Concrete; Span 15m; BNSO)	m2	112,858	208,298	321,156
Substructure (Pier; for Timber; IOT)	NO	584,835	27,724	612,559
Substructure (Abut; for Timber; IOT)	NO	1,667,310	112,169	1,779,479
Substructure (Pier; for Timber; BNSO)	NO	860,118	41,015	901,133
Substructure (Abut; for Timber; BNSO)	NO	1,874,927	126,412	2,001,339
Substructure (Pier; for Concrete; BNSO)	NO	3,495,498	496,793	3,992,291
Substructure (Abut; for Concrete; BNSO)	NO	7,096,827	953,086	8,049,913
Demolition of Bridge (Timber->Timber)	m2	18,990	1,061	20,051
Demolition of Bridge (Timber->Concrete)	m2	18,990	1,061	20,051
Demolition of Bridge (Concrete)	m2	158,945	92,920	251,865
Maintenance of Timber Bridge (New)	m2	12,393	1,009	13,392
Maintenance of Concrete Bridge (New)	m2	3,698	3,604	7,302
Maintenance of Timber Bridge (Exist)	m2	12,414	2,347	14,761
Maintenance of Concrete Bridge (Exist)	m2	6,962	2,563	9,525

5.1 Preliminary Screening

The road links to be improved should be effective for development of the Project Area. The road links where improvements were assumed to be inefficient for development of the Project Area were generally screened out using the following cut-off criteria.

- (1) Very short roads, less than 2 Km long, which have no connection with the trunk road network.
- (2) Roads not connected to the network at any point
- (3) Unpreferred roads, due to poor suitability for transportation compared to other existing alternative roads serving the same purpose.
- (4) Road in good condition according to the Bina Marga road inventory which lists improvement projects carried out in the last two or three years
- (5) Roads with asphalt surface in good condition
- (6) Urban roads, except those forming part of a longer route
- (7) Roads serving single large organizations rather than the general public
- (8) Roads with no inventory data
- (9) Kabupaten roads also assigned as provincial roads

The road links to be screened out in Kabupaten Indragiri Hilir are shown in Table 5-1-1.

Table 5-1-1 ROAD LINKS TO BE SCREENED OUT

KABUPATEN : INDRAGIRI HILIR

CRITERIA NO	ROAD LINK NO
-	-

5.2 Evaluation

5.2.1 Primary Analysis

The Kabupaten roads were classified by using the future traffic volume on the road links in 1998. The primary analysis of the IRR was carried out using the construction and maintenance costs. Road links where IRRs were more than 10% were defined as feasible links.

Results of primary analysis are shown in Table 5-2-1.

5.2.2 Secondary Analysis

From the infeasible road links evaluated by the primary analysis, road links where the IRRs were between 1% and 10%, i.e. road links which could become feasible if down graded by one rank, in classification were down graded and the costs re-estimated. Using these costs, a secondary analysis of IRR was carried out. Road links where these IRRs were then more than 10% were also defined as feasible links. This reflected that even though the road classification was rather low the road link should be improved.

Results of secondary analysis are shown in Table 5-2-2.

5.2.3 Ranking of Feasible Road Links

From the results of the primary and secondary analysis, road links where the IRRs were more than 10% were selected and their NPVs and B/Cs were estimated. The ranking of feasible road links from the economic evaluation are decided in the order of the NPVs, i.e. the larger the NPV the higher the road link priority as shown in Table 5-2-3.

Table 5-2-1

RESULTS OF PRIMARY ANALYSIS

PROVINCE : RIAU KABUPATEN : INDRAGIRI HILIR

LINK NO	LENGTH	CLASS	IRR (%)	REMARK
10	22 Km	IIIA	31.617	Surplus
11	12 Km	IIIA	12.582	Surplus
20	16 Km	IIIA	11.085	Surplus
9	16 Km	IIIA	4.007	Surplus
30	20 Km	IIIA	3.156	Surplus
29	10 Km	IIIA	0.402	Surplus
7	17 Km	IIIA	0.078	Surplus
8	9 Km	IIIA	0.078	Surplus
1	5 Km	IIIB-1	0.078	Surplus
10	8 Km	IIIA	0.078	Surplus
2	23 Km	IIIA	0.078	Surplus
12	9 Km	IIIB-1	0.078	Surplus
13	6 Km	IIIB-1	0.078	Surplus
14	13 Km	IIIB-1	0.078	Surplus
15	16 Km	IIIB-1	0.078	Surplus
16	10 Km	IIIB-1	0.078	Surplus
17	3 Km	IIIB-2	0.078	Surplus
3	12 Km	IIIB-1	0.078	Surplus
19	6 Km	IIIB-2	0.078	Surplus
4	17 Km	IIIB-1	0.078	Surplus
21	8 Km	IIIB-1	0.078	Surplus
22	2 Km	IIIB-2	0.078	Surplus
23	4 Km	IIIB-1	0.078	Surplus
24	3 Km	IIIC	0.078	Surplus
25	7 Km	IIIB-1	0.078	Surplus
26	5 Km	IIIB-1	0.078	Surplus
27	8 Km	IIIA	0.078	Surplus
28	5 Km	IIIA	0.078	Surplus
5	9 Km	IIIB-1	0.078	Surplus
6	16 Km	IIIB-1	0.078	Surplus
31	13 Km	IIIB-1	0.078	Surplus

Table 5-2-2

RESULTS OF SECONDARY ANALYSIS

PROVINCE : RIAU KABUPATEN : INDRAGIRI HILIR

LINK NO	LENGTH	CLASS	IRR (%)	REMARK
9	16 Km	IIIB-1	17.164	Surplus
30	20 Km	IIIB-1	4.437	Surplus
29	10 Km	IIIB-1	4.130	Surplus

Table 5-2-3

RANKING OF FEASIBILITY ROAD LINKS

PROVINCE : RIAU KABUPATEN : INDRAGIRI HILIR

LINK NO	LENGTH	CLASS	NPV (1000Rp)	B/C	IRR (%)	REMARK
10	22 Km	IIIA	2216729	2.209	31.617	Surplus
9	16 Km	IIIB-1	204978	1.307	17.164	Surplus
11	12 Km	IIIA	101539	1.120	12.582	Surplus
20	16 Km	IIIA	73469	1.052	11.085	Surplus
BUM	66 Km		2596715			

Chapter 6 IMPLEMENTATION PROGRAMME

6.1 Implementation Schedule

6.1.1 Project Cost

The total Project Cost for the Kabupaten is composed of the cost of construction and maintenance, supplementation as described later, and workshop, laboratory and survey equipment. The total Project Cost for the Kabupaten is summarized in Table 6-1-1.

Table 6-1-1 TOTAL PROJECT COST (1)

KABUPATEN: Indragiri Hilir

(Rp $\times 10^6$)

COST	FOREIGN CURRENCY	LOCAL CURRENCY	TOTAL
CONSTRUCTION	1,909	3,020	4,929
MAINTENANCE	56	477	533
SUPPLEMENTATION	350	-	350
WORKSHOP EQUIPMENT & TOOLS	28	-	28
LABORATORY EQUIPMENT	12	-	12
SURVEY EQUIPMENT	5	-	5
TOTAL	2,360	3,497	5,857

The total Project Cost can be divided into costs as shown in Table 6-1-2.

Table 6-1-2 TOTAL PROJECT COST (2)

(Rp $\times 10^6$)

COST	FOREIGN CURRENCY	LOCAL CURRENCY	TOTAL
CIVIL WORK	1,460	3,483	4,943
CONSTRUCTION & MAINTENANCE EQUIPMENT	798	-	798
SPARE PARTS	57	14	71
WORKSHOP/LABORATORY/SURVEY EQUIPMENT	45	-	
TOTAL	2,360	3,497	5,857

The cost for civil work is composed of the cost of labour and materials, operation cost excluding spare parts, indirect cost and transportation cost of equipment.

6.1.2 Proposed Road Links

(1) Road Link to be Improved

The road links to be improved were generally selected taking into consideration the following criteria:

- (1) Feasible road links
 - Feasible road links from the primary evaluation
 - Feasible road links from the secondary evaluation
- (2) Road links selected from the engineering points of view
- (3) Road links selected because of basic human needs.

The final proposal for road links to be in the Kabupaten development plan are the 6 links with a total length of 68 km which is 21% of the 330 km total length of Kabupaten roads to be studied. Road Link No 11 is a feasible road link. However it is located at the end of the local road network, therefore this road link was removed from the list. The proposed road links are shown in Table 6-1-3.

Table 6-1-3 ROAD LINKS TO BE IMPROVED

KABUPATEN : INDRAGIRI HILIR

<u>REASON FOR SELECTION</u>	<u>ROAD LINK NO</u>
Feasible	
- Primary	18,20
- Secondary	9
Engineering Point of View	2,4,5
Basic Human Needs	-

Road Links No 2, No 4 and No 5 are trunk roads which connect the Kabupaten capital with Kecamatan capital, these road links are selected from the engineering points of view.

The order of proceeding with the improvement of the proposed road links are decided as shown in Table 6-1-4.

Table 6-1-4 ROAD LINKS TO BE IMPROVED BY YEAR


PROV : RIAU KAB : INDRAGIRI HILIR

YEAR	LINK NO	() : rate
1988	20	(50%)
1989	2, 18, 20	(20%), (30%), (50%)
1990	2, 18	(25%), (70%)
1991	2, 4, 9	(55%), (25%), (70%)
1992	4, 5, 9	(75%), (30%)

KAB. INDRAGIRI HILIR



CONSTRUCTION PROGRAMME

ROAD LINE NUMBER	FISCAL YEAR				
	1988/89	1989/90	1990/91	1991/92	1992/93
20	422				
02.19.20		1,031			
02.19			1,124		
02.04.09				1,226	
04.03.00					1,063
TOTAL COST (10 ⁹ Rp.)	422	1,031	1,124	1,226	1,063



LEGEND :

- KABUPATEN CAPITAL
- KECAMATAN CAPITAL
- OTHER CITY
- LINK NUMBER
- PROVINCIAL BOUNDARY
- KABUPATEN BOUNDARY
- KECAMATAN BOUNDARY
- NATIONAL ROAD
- PROVINCIAL ROAD
- KABUPATEN ROAD
- VILLAGE ROAD
- RIVER



THE FEASIBILITY STUDY OF THE LOCAL ROAD DEVELOPMENT IN THE REPUBLIC OF INDONESIA

TITLE: CONSTRUCTION PROGRAMME

SOURCE: DIREKTORAT JENDERAL CIPTA KARYA	SCALE: AS SHOWN	PROVINCE: RIAU KABUPATEN INDRAGIRI HILIR
---	--------------------	---

(2) Road Links to Be Maintained

It is desirable that all Kabupaten roads are maintained. However, because of the limited budget it is inevitable that some road links in the Kabupatens will be left without maintenance for the time being. The budget should be used for those which are effective in producing more useful development of the Kabupaten through the road development project. The road links to be maintained are finally proposed as shown in Table 6-1-5.

Table 6-1-5

ROAD LINKS TO BE MAINTAINED

PRDV : RIAU KAB : INDRAGIRI HILIR

(1000Rp)

LINK NO	LENGTH (Km)	BA (X)	SD (X)	RU (X)	RD (X)	ASPHAL (Km)	GRAVEL (Km)	EARTH (Km)	TN NO	AREA (m2)	RC NO	AREA (m2)	BRIDGE COST	LOCAL COST	FOREIGN COST	TOTAL COST
2	23	44.8	27.4	27.8	0.0	0	23	0	21	591.40	0	0.00	8,730	34,857	2,535	37,392
3	12	0.0	47.9	41.7	10.4	0	12	0	3	142.20	0	0.00	2,099	16,121	932	17,053
12	9	0.0	81.1	18.9	0.0	0	0	9	8	480.00	0	0.00	7,085	9,270	1,533	10,803
13	6	0.0	25.8	74.2	0.0	0	0	6	4	352.00	0	0.00	5,196	6,577	1,097	7,674
14	13	0.0	33.5	66.5	0.0	0	0	13	12	555.00	0	0.00	8,192	11,673	1,889	13,562
26	5	82.0	18.0	0.0	0.0	0	0	5	3	144.00	0	0.00	2,126	3,627	584	4,191
SUM	68					0	35	33	53	2264.60	0	0.00	33,428	82,125	8,550	90,673

6.1.3 Annual Construction and Maintenance Cost

The annual allocation of the total construction and maintenance cost in the five years programme for Kabupaten Indragiri Hilir is finally recommended as shown in Tables 6-1-6 (1), (2) and (3) for the construction, maintenance and total respectively.

The proposed construction cost is Rp 4,929 x 10⁶ and maintenance cost is Rp 533 x 10⁶ which is approximately 11% of the total expenditure.

Table 6-1-6 (1) CONSTRUCTION AND MAINTENANCE COST
(CONSTRUCTION)

PROV : RIAU KAB : INDRAGIRI HILIR

(UNIT : 1000Rp)

ITEM	(1988)	(1989)	(1990)	(1991)	(1992)	(TOTAL)	
LOCAL CURRENCY :	258,820	628,591	679,736	779,561	672,957	3,019,665	(61.32)
Ownership Cost	1,122	2,853	3,106	3,579	3,438	14,098	(0.51)
Operation Cost	93,671	237,025	256,009	296,778	282,564	1,166,047	(38.62)
Material Cost	92,754	214,806	231,186	258,448	190,137	987,331	(32.72)
Labour Cost	37,514	91,917	100,774	119,074	109,041	458,320	(15.22)
Contingency	33,759	81,990	88,661	101,682	87,777	393,869	(13.02)
FOREIGN CURRENCY :	162,940	404,139	444,102	506,723	391,017	1,908,921	(38.72)
Ownership Cost	32,886	82,998	89,869	104,045	100,036	409,834	(21.52)
Operation Cost	4,240	10,727	11,627	13,401	13,113	53,108	(2.82)
Material Cost	104,561	257,700	284,680	323,183	226,866	1,196,990	(62.72)
Labour Cost	0	0	0	0	0	0	(0.02)
Contingency	21,253	52,714	57,926	66,094	51,002	248,989	(13.02)
TOTAL COST :	421,760	1,032,730	1,123,839	1,286,284	1,063,974	4,928,587	
Ownership Cost	34,008	85,851	92,975	107,624	103,474	423,932	(0.62)
Operation Cost	97,911	247,752	267,636	310,179	295,677	1,219,155	(24.72)
Material Cost	197,315	472,506	515,866	581,631	417,003	2,184,321	(44.32)
Labour Cost	37,514	91,917	100,774	119,074	109,041	458,320	(9.32)
Contingency	55,012	134,704	146,508	167,776	138,779	642,859	(13.02)

(Contingency : 15%)

Table 6-1-6 (2) CONSTRUCTION AND MAINTENANCE COST
(MAINTENANCE)

PROV : RIAU KAB : INDRAGIRI HILIR

(UNIT : 1000Rp)

ITEM	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >	
LOCAL CURRENCY :	41,039	78,621	98,002	124,306	134,514	476,482	(89.4%)
Ownership Cost	92	180	238	311	381	1,202	(0.3%)
Operation Cost	12,875	24,968	28,690	33,385	36,419	136,337	(28.6%)
Material Cost	17,341	32,677	41,948	54,006	54,771	200,743	(42.1%)
Labour Cost	10,731	20,796	27,126	36,604	42,943	138,200	(29.0%)
FOREIGN CURRENCY :	4,274	8,297	10,980	14,678	17,999	56,228	(10.6%)
Ownership Cost	3,693	7,168	8,129	9,354	10,240	38,584	(68.6%)
Operation Cost	329	638	744	876	963	3,550	(6.3%)
Material Cost	252	491	2,107	4,448	6,796	14,094	(25.1%)
Labour Cost	0	0	0	0	0	0	(0.0%)
TOTAL COST :	45,313	86,918	108,982	138,984	152,513	532,710	
Ownership Cost	3,785	7,348	8,367	9,665	10,621	39,786	(7.5%)
Operation Cost	13,204	25,606	29,434	34,261	37,382	139,887	(26.3%)
Material Cost	17,593	33,168	44,055	58,454	61,567	214,837	(40.3%)
Labour Cost	10,731	20,796	27,126	36,604	42,943	138,200	(25.9%)

Table 6-1-6 (3)

CONSTRUCTION AND MAINTENANCE COST
(TOTAL)

PROV : RIAU KAB : INDRAGIRI HILIR

(UNIT : 1000Rp)

I T E M	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >	
LOCAL CURRENCY :	299,859	707,212	777,738	903,867	807,471	3,496,147	(64.0%)
Ownership Cost	1,214	3,033	3,344	3,890	3,819	15,300	(0.4%)
Operation Cost	106,546	261,993	284,699	330,163	318,983	1,302,384	(37.3%)
Material Cost	110,095	247,483	273,134	312,454	244,908	1,188,074	(34.0%)
Labour Cost	48,245	112,713	127,900	155,678	151,984	596,520	(17.1%)
Contingency	33,759	81,990	88,661	101,682	87,777	393,869	(11.3%)
FOREIGN CURRENCY :	167,214	412,436	455,082	521,401	409,016	1,965,149	(36.0%)
Ownership Cost	36,579	90,166	97,998	113,399	110,276	448,418	(22.8%)
Operation Cost	4,569	11,365	12,371	14,277	14,076	56,658	(2.9%)
Material Cost	104,813	258,191	286,787	327,631	233,662	1,211,084	(61.6%)
Labour Cost	0	0	0	0	0	0	(0.0%)
Contingency	21,253	52,714	57,926	66,094	51,002	248,989	(12.7%)
TOTAL COST :	467,073	1,119,648	1,232,821	1,425,268	1,216,487	5,461,297	
Ownership Cost	37,793	93,199	101,342	117,289	114,095	463,718	(8.5%)
Operation Cost	111,115	273,358	297,070	344,440	333,059	1,359,042	(24.9%)
Material Cost	214,908	505,674	559,921	640,085	478,570	2,399,158	(43.9%)
Labour Cost	48,245	112,713	127,900	155,678	151,984	596,520	(10.9%)
Contingency	55,012	134,704	146,588	167,776	138,779	642,859	(11.8%)

< Contingency : 15% >

6.1.4 Construction and Maintenance Equipment Cost

(1) Required Number of Equipment

The required numbers of construction equipment for Kabupaten Indragiri Hilir are estimated from the annual proposed construction quantities as shown in Table 6-1-7.

The proposed numbers of equipment to be purchased are finally decided considering the following number of existing equipment in the Kabupaten which are available for the Project.

- Nil

The proposed numbers of maintenance equipment have been decided as shown below from the proposed annual maintenance volume taking into account the capacity of the proposed maintenance gangs.

a. Equipment for Road Maintenance

- 1-Flat Bed Truck 3 ton

b. Equipment for Bridge Maintenance

- Nil

(2) Equipment Cost

The proposed construction and maintenance equipment and their purchase costs are shown in Table 6-1-8. In the Project the supplementation cost or equipment cost supplemented is the difference between the purchase cost for newly supplied equipment and the depreciated value.

This comes about because full depreciation of the supplied equipment would not be completed within the Project Period of 5 years.

Table 6-1-7

REQUIRED NUMBER OF EQUIPMENT

PROV : RIAU KAB : INDRAGIRI HILIR

EQUIPMENT NAME	WORKABLE	EXISTING	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >
Bulldozer	220	0	0.23	0.56	0.62	0.70	0.67
Bulldozer/Ripper	220	0	0.09	0.23	0.26	0.30	0.30
Swamp Bulldozer	220	0	0.11	0.25	0.26	0.19	0.31
Motor Grader	240	0	0.42	1.08	1.21	1.40	1.35
Road Stabilizer	220	0	0.23	0.56	0.62	0.70	0.67
Hand-guide Vib. Roller	240	0	0.05	0.11	0.10	0.32	0.33
Tire Roller	220	0	0.18	0.43	0.47	0.53	0.11
Vibratory Roller (D&T)	240	0	0.48	1.18	1.31	1.41	1.44
Hydraulic Excavator; Wheel	220	0	1.71	4.30	4.35	5.36	5.37
Wheel Loader	240	0	0.39	0.97	1.09	1.24	1.19
Water Tank Truck	240	0	0.40	0.97	1.07	1.13	1.15
Dump Truck	240	0	3.59	9.34	10.34	11.70	11.39
Flat Bed Truck with Crane	240	0	0.10	0.18	0.17	0.31	0.28
Flat Bed Truck	240	0	0.52	1.27	1.40	1.65	1.14
Concrete Mixer	220	0	0.00	0.01	0.01	0.01	0.00
Water Pump	220	0	0.00	0.01	0.01	0.01	0.00
Concrete Vibrator	220	0	0.00	0.01	0.01	0.01	0.00
Asphalt Sprayer	220	0	0.18	0.43	0.47	0.53	0.11

NOTE WORKABLE : workable days in a year
EXISTING : number of existing equipment

Table 6-1-8

EQUIPMENT PURCHASE COST

PROV : RIAU KAB : INDRAGIRI HILIR

(1000 Rp)

EQUIPMENT NAME	CLASS	CIF (JAKARTA)	PURCHASE NO.	PURCHASE COST
Bulldozer	90 HP	49,150	1	49,150
Bulldozer/Ripper	90 HP	53,000	-	-
Swamp Bulldozer	90 HP	52,850	1	52,850
Swamp Bulldozer	65 HP	40,500	-	-
Motor Grader	75 HP	47,800	2	95,600
Road Stabilizer	W=1850 mm	85,950	1	85,950
Hand-guide Vib. Roller	1000 Kg	8,500	1	8,500
Tire Roller	8-15 ton	31,070	1	31,070
Vibratory Roller (D&T)	4 ton	29,000	2	58,000
Vibratory Roller	4 ton	29,000	-	-
Rough Terrain Crane	10 ton	100,400	-	-
Hydraulic Excavator; Wheel	0.3 m ³	41,100	2	82,200
Wheel Loader	1.2 m ³	70,200	1	70,200
Water Tank Truck	4000 ltr.	12,750	1	12,750
Dump Truck	3.0 ton	14,700	11	161,700
Dump Loader Truck	12 ton	56,300	-	-
Flat Bed Truck with Crane	3.0 ton	25,190	1	25,190
Flat Bed Truck	3.0 ton	11,275	2	22,550
Portable Crusher/Screening	30-40 t/h	188,000	-	-
Concrete Mixer	0.5 m ³	18,000	-	-
Water Pump	200 l/min	630	-	-
Concrete Vibrator	3.3 HP	740	-	-
Asphalt Sprayer	850 ltr.	10,200	1	10,200
Service Car	3 ton	11,600	1	11,600
4 Wheel Drive Vehicle	70 HP	17,500	1	17,500
Motorcycle	100 cc	1,100	3	3,300
PURCHASE COST TOTAL				798,310
OWNERSHIP COST (FOREIGN)				448,418
EQUIPMENT COST SUPPLEMENTED				349,892

6.1.5 Other Costs

Cost other items includes the costs of workshop equipment and tools, laboratory test equipment and survey equipment which are recommended in Sub-Clause 3.5. These total costs are summarized in Table 6-1-1.

6.1.6 Quantities by Work Type

The annual construction and maintenance quantities for all proposed road links are shown in Table 6-1-9.

Table 6-1-9

CONSTRUCTION QUANTITIES FOR ALL
PROPOSED LINKS

PROV : RIAU KAB : INDRAGIRI HILIR

ITEM	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
Site Clearance in Light Bush	m2	0.00	0.00	0.00	0.00	0.00	0.00
Subgrade Preparation	m2	48000.00	128160.00	146675.00	127251.00	127494.00	577580.00
Normal Fill	m3	0.00	0.00	0.00	0.00	0.00	0.00
Fill in Swamp	m3	4350.00	9600.75	10158.75	7275.23	11923.28	43308.00
Normal Excavation to Spoil	m3	1213.00	2312.70	2479.30	297.50	697.50	7000.00
Cement Stabilizing	m3	3920.00	10024.70	11134.38	11746.31	11844.02	48669.40
Cement Stabilizing	m3	1960.00	4704.00	5181.75	6735.75	5743.50	24325.00
Shoulder	m2	20000.00	55900.00	66325.00	92750.00	90525.00	325500.00
Asphalt Patching	m2	0.00	0.00	0.00	0.00	0.00	0.00
Surface Dressing (Single)	m2	28000.00	67200.00	74025.00	83475.00	16800.00	269500.00
Surface Dressing (Double)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Earth Drain	m	0.00	5320.00	11850.00	1430.00	0.00	18600.00
Earth Drain in Swamp (by machine)	m3	30000.00	75600.00	76500.00	94260.00	94440.00	370800.00
Pipe Culvert 80cm	m	0.00	1.60	2.00	4.40	0.00	8.00
Masonry Culvert (80x80cm)	m	0.00	0.00	0.00	0.00	0.00	0.00
Retaining Wall and Wing Wall (Timber)	m2	0.00	20.00	25.00	207.50	522.50	775.00
Retaining Wall and Wing Wall (Masonry)	m3	0.00	0.00	0.00	0.00	0.00	0.00
Gabion Protection	m3	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 3m; IOT)	m2	0.00	20.80	26.00	57.20	0.00	112.00
Superstructure (Timber; Span 5m; IOT)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 8m; IOT)	m2	150.00	240.00	210.00	294.80	265.20	1160.00
Superstructure (Timber; Span 3m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 5m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 8m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 3m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 5m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 8m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 10m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 15m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Pier; for Timber; IOT)	NO	4.50	8.30	7.35	7.35	1.50	29.00
Substructure (Abut; for Timber; IOT)	NO	3.00	6.00	5.70	18.50	18.80	52.00
Substructure (Pier; for Timber; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Abut; for Timber; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Pier; for Concrete; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Abut; for Concrete; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Demolition of Bridge (Timber->Timber)	m2	0.00	15.24	19.05	41.91	6.40	82.60
Demolition of Bridge (Timber->Concrete)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Demolition of Bridge (Concrete)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Manual routine maintenance of road	Km	34.00	65.70	81.13	99.68	106.00	386.50
Routine maintenance of earth road	Km	16.50	33.00	33.00	33.00	33.00	148.50
Routine maintenance of gravel road	Km	17.50	32.70	32.13	28.68	12.00	123.00
Routine maintenance of asphalt road	Km	0.00	0.00	16.00	38.00	61.00	115.00
Maintenance of Timber Bridge (New)	m2	0.00	0.00	0.00	300.00	300.00	600.00
Maintenance of Concrete Bridge (New)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Maintenance of Timber Bridge (Exist)	m2	1132.30	2205.46	2190.68	2101.97	2188.40	9818.80
Maintenance of Concrete Bridge (Exist)	m2	0.00	0.00	0.00	0.00	0.00	0.00

6.2 Organization and Construction System

6.2.1 Organization

The Bupati as head of the Kabupaten has been authorized by Law No. 13, 1980 as an official responsible for the Local Road Development Project implementation. This means that the DPUK is considered as a responsible agency for the actual execution of the Project.

According to instruction letter dated June 24, 1982 Ref. No. 620/975-/BANGDA, the Project Manager appointed by the Bupati will be responsible for the operation and maintenance of the equipment. Accordingly the Equipment Coordinator appointed from the staff of the Regional Public Works (Kantor Wilayah) by Bina Marga as a coordinator between the Governor and the Bupati will be responsible for delivery, effectual utilization and maintenance of the equipment.

The standard organization of DPUK consists of a minimum of four sections, i.e. Road Section, Housing and City Planning Section, Irrigation Section and Administration Section. For execution of the Project it is strongly recommended that the structural organization of DPUK is established. It will be necessary not only to organize new sections but also to reorganize the current structure through a review of the roles and responsibilities of each inter-related section.

It is recommended that the workshop is newly organized to consist of three sub-sections, i.e. maintenance and repair of equipment, operation and materials, and administration to execute the main tasks described in Clause 3.5.


The sub-section of laboratory would be under the relevant Road Section. The proposed organization is shown in Fig. 6-2-1.

6.2.2 Construction System

For the construction of Kabupaten roads with a ten year effective design life, it has been recommended in Clause 3.4 that the equipment intensive method should be adopted for earth work and pavement work with the exception of surface dressing.

Fig. 6-2-1

PROPOSED ORGANIZATION



: Equipment delivery flow



: New position/subsection

Current road construction in the Kabupatens is obliged to rely upon the traditional labour intensive method. It is therefore assumed that both the DPUK and the local contractors in the Kabupatens do not have sufficient experience and technique for the equipment intensive method of road construction.

For realization of the Local Road Development Project the GOI has ensured availability of the required human resources of DPUK and intends to conduct training programmes for those human resources as described in Clause 8.3 of the Main Report. This means that the GOI intends the Kabupatens to have the ability to execute the Project by force account (Swakelola).

It should be recognized from the experiences in the first local road project, which was assisted by OECF, ADB and IBRD, that because of their poor construction management and traditional labour intensive methods most of the road construction by local contractors could not be completed within the contract periods. Therefore execution of the road improvement by force account is desirable as recommended from their experience by the consultants for the first local road project.

It is strongly recommended that except for labourers the staff of the force account team should not be hired by the day as it would then not be able to consolidate the foundations for development of self reliability.

However, it will be very difficult to execute all the Projects by force account because of the need for many Kabupaten staff. The GOI has emphasized the need to promote the employment of local weak contractors in order to up-grade their capability in the road project schemes within the Fourth Five-Year Plan (REPELITA)

Taking into consideration the conditions mentioned above it is strongly recommended that the DPUK is obliged to lend some equipment with skilled operators to the local contractors in the Kabupatens for the execution of a part of the road improvement works.

The types of work executed only by force account are recommended as follows:

- Routine maintenance work for the Kabupaten roads
- Laboratory tests
- Production of crushed stone
- Technical service for the equipment

