

**REPUBLIC OF INDONESIA
MINISTRY OF PUBLIC WORKS
DIRECTORATE GENERAL OF HIGHWAYS**

**THE FEASIBILITY STUDY
OF
THE LOCAL ROAD DEVELOPMENT
IN THE REPUBLIC OF INDONESIA**

KABUPATEN REPORT 28

KABUPATEN NGADA

MARCH 1986

JAPAN INTERNATIONAL COOPERATION AGENCY

S D F

86-46(28/38)

JICA LIBRARY



1034257[4]

**REPUBLIC OF INDONESIA
MINISTRY OF PUBLIC WORKS
DIRECTORATE GENERAL OF HIGHWAYS**

**THE FEASIBILITY STUDY
OF
THE LOCAL ROAD DEVELOPMENT
IN THE REPUBLIC OF INDONESIA**

KABUPATEN REPORT 28

KABUPATEN NGADA

MARCH 1986

JAPAN INTERNATIONAL COOPERATION AGENCY

國際協力事業団		
受入 月日	'87.5.21	108
登録 No.	16451	61.4
		SDF

PREFACE

This is the Kabupaten Report of the Feasibility Study of the Local Road Development in the Republic of Indonesia for Kabupaten Ngada in Nusa Tenggara Timur Province. The report has been prepared by the Study Team of the Japan International Cooperation Agency (hereinafter called JICA).

Based upon a request from the Government of Indonesia, the Government of Japan arranged for JICA to conduct the Study and JICA accordingly organized a Study Team. The study was carried out using data which were generally prepared by the Kabupaten, routed through the province, under the instructions of Bina Marga of the Ministry of Public Works and Bangda of the Ministry of Home Affairs.


Since the study period was limited, without cooperation of Bina Marga, Bangda and local governments of both province and Kabupaten in collecting the data, the study would not have been completed within the period.

The report consists of the results of the feasibility study and proposed implementation programme of the local road development in the Kabupaten.

The simplified economic feasibility evaluation methodology utilized for the study was established by the Study Team in Phase I Study through a pilot study of seven (7) model Kabupatens, and is described in the Main Report.

The purpose of the study for the Kabupaten is mainly to estimate the total Project Cost for the local road development but only limited data is available for study base. Therefore a detailed survey and design for the improvement of the Kabupaten roads should be carried out before commencing the Project together with a review of this report.


LOCATION MAP OF THE PROJECT AREAS




LEGEND:

- CAPITAL CITY
- PROVINCIAL CITY
- ++++ NATIONAL BOUNDARY
- PROVINCIAL BOUNDARY
- ▨ LOCATION OF THE PROJECT AREA

SCALE:




NUSA TENGGARA TIMUR
PROV · NUSA TENGGARA TIMUR




PROVINCE : NUSA TENGGARA TIMUR

- 26 · KAB · SUMBA BARAT
- 27 · KAB · ENDE
- 28 · KAB · NGADA


LEGEND :

- PROVINCIAL BOUDER
-  LOCATION OF THE PROPOSED AREA


SCALE :




NUSA TENGGARA TIMUR
PROV · NUSA TENGGARA TIMUR
KAB · NGADA





LEGEND :

- PROVINCIAL BOUNDARY
-  LOCATION OF THE PROJECT AREA

SCALE :




KAB. NGADA



LEGEND :

- ⊙ KABUPATEN CAPITAL
- ⊙ KECAMATAN CAPITAL
- OTHER CITY
- ③ LINK NUMBER
- + -+ -+ PROVINCIAL BOUNDARY
- - - - - KABUPATEN BOUNDARY
- - - - - KECAMATAN BOUNDARY
- ==== NATIONAL ROAD
- ==== PROVINCIAL ROAD
- ==== KABUPATEN ROAD
- ==== VILLAGE ROAD
- ~ RIVER



THE FEASIBILITY STUDY OF THE LOCAL ROAD DEVELOPMENT IN THE REPUBLIC OF INDONESIA

TITLE :

SOURCE: DIREKTORAT JENDERAL CIPTA KARYA	SCALE: AS SHOWN	PROVINCE: NUSATenggara TIMUR KABUPATEN: NGADA
---	--------------------	--

C O N T E N T S

PREFACE

Chapter 1	BACKGROUND OF THE KABUPATEN	
1.1	Topographic and Meteorological Conditions	28-1
1.1.1	Location and Topography	28-1
1.1.2	Meteorological Conditions	28-2
1.2	Socio-Economic Conditions	28-4
1.2.1	Population	28-4
1.2.2	Land Use	28-6
1.2.3	Agriculture	28-8
1.2.4	Other Economic Activities	28-11
1.3	Present Status of Kabupaten Roads	28-12
1.3.1	Outline of Road Networks	28-12
1.3.2	Road Inventory	28-13
1.3.3	Bridge Inventory	28-17
1.3.4	Traffic	28-22
Chapter 2	ESTIMATIONS OF FUTURE TRAFFIC VOLUME AND BENEFIT	
2.1	Future Traffic Volume	28-23
2.1.1	Traffic Growth Rate	28-23
2.1.2	Present and Future Traffic Volume	28-24
2.2	Benefit	28-25
2.2.1	Benefit Estimation Method	28-25
2.2.2	Benefit	28-28
Chapter 3	ENGINEERING	
3.1	Design Criteria and Specification	28-29
3.1.1	Geometric Design Criteria	28-29
3.1.2	Loading Specification	28-29
3.2	Pavement Design	28-32
3.2.1	Design Conditions	28-32
3.2.2	Pavement Structure	28-33
3.3	Design of Bridges and Other Structures	28-34
3.3.1	Standard Bridge	28-34
3.3.2	Other Structures	28-36

3.4	Selection of Equipment Types	28-39
3.4.1	Points to be Considered for the Selection	28-40
3.4.2	Combinations of Equipment for Major Works and Maintenance	28-40
3.5	Workshop and Laboratory	28-43
3.5.1	Policy of the Kabupaten Workshop	28-43
3.5.2	Workshop Equipment and Tools	28-43
3.5.3	Laboratory	28-44
Chapter 4	CONSTRUCTION AND MAINTENANCE COST ESTIMATIONS	
4.1	Unit Price	28-46
4.1.1	Unit Labour Price	28-46
4.1.2	Unit Price of Materials	28-47
4.1.3	Hourly Equipment Cost	28-48
4.2	Unit Construction Cost by Work Type	28-49
4.2.1	All Works Except Bridges	28-49
4.2.2	Bridges	28-50
Chapter 5	RESULTS OF ECONOMIC FEASIBILITY EVALUATION	
5.1	Preliminary Screening	28-51
5.2	Evaluation	28-52
5.2.1	Primary Analysis	28-52
5.2.2	Secondary Analysis	28-52
5.2.3	Ranking of Feasible Road Links	28-52
Chapter 6	IMPLEMENTATION PROGRAMME	
6.1	Implementation Schedule	28-55
6.1.1	Project Cost	28-55
6.1.2	Proposed Road Links	28-56
6.1.3	Annual Construction and Maintenance Cost	28-60
6.1.4	Construction and Maintenance Equipment Cost	28-63
6.1.5	Other Costs	28-66
6.1.6	Quantities by Work Type	28-66

	6.2	Organization and Construction System	28-68
	6.2.1	Organization	28-68
	6.2.2	Construction System	28-68
Appendix	A-1	Input Data for Estimation of the Producer's Surplus Benefit	28-A-1
	A-2	Engineering Data	28-A-2
	A-3	Construction and Maintenance Cost for Proposed Road Links	28-A-18
	A-4	Construction and Maintenance Quantities for all Proposed Road Links	28-A-27
	A-5	Construction and Maintenance Costs for all Proposed Road Links	28-A-30
	A-6	Quantities of Bridges on Proposed Road Links	28-A-33
	A-7	Construction and Maintenance Cost of Bridges on Proposed Road Links	28-A-34

Chapter 1 BACKGROUND OF THE KABUPATEN

1.1 Topographic and Meteorological Conditions

1.1.1 location and Topography

Kabupaten Ngada is located slightly to the west of the centre of Flores Island. Its north coast faces the Flores Sea, and south coast the Sawu Sea. It is bordered on the east by Kabupaten Ende and on the west by Kabupaten Manggarai.

The south of the Kabupaten is entirely covered with 1000 to 1500 meter high volcanic mountains from which steep slopes fall into the sea. On the north coast a flat area lies on the Sissa basin, which is a typical feature of a volcanic island. The capital of the Kabupaten, Bajawa, is located in the southwest of the mountainous region.

The area of the Kabupaten is about 3,038 square kilometers approximately 6 percent of the total of the province. It consists administratively of 9 Kecamatan.

1.1.2 Meteorological Conditions

The average number of rainy days and the average amount of yearly rainfall in Kabupaten Ngada are 69 days and 1,184 mm respectively.

One year in the Kabupaten consists of a rainy season and a dry season. The dry season is from June through October in general. However this is variable as Table 1-1-1 shows.

The number of working days which is necessary for planning the construction schedule in chapter 6, is estimated at 250 days using the following formula based upon the data shown in the table referred to above.

$$\text{Working Days} = 365 - \text{Holidays} - \text{Rainy Days} + (\text{Rainy Days} \times \frac{\text{Holiday}}{365}) + (0.10 \times \text{Rainy Days})$$

Where :

- Holidays consist of 52 Sundays and 13 national holidays; and
- 10% of rainy days are assumed to be workable days.

Table 1-1-1

METEOROLOGICAL CONDITIONS

PROVINCE : Nusa Tenggara Timur
KABUPATEN : Ngada

STATION : Ngada

MONTH	1 9 8 0		1 9 8 1		1 9 8 2		1 9 8 3		1 9 8 4	
	RAINY DAYS	RAINFALL (mm)	RAINY DAYS	RAINFALL (mm)	RAINY DAYS	RAINFALL (mm)	RAINY DAYS	RAINFALL (mm)	RAINY DAYS	RAINFALL (mm)
January	13	169	14	265	13	213	9	156	10	182
February	8	107	9	120	11	176	14	276	14	283
March	6	54	7	92	11	176	14	273	12	221
April	6	78	4	52	5	95	11	193	10	174
May	2	21	6	125	3	16	6	81	6	78
June	1	5	4	42	1	12	-	-	2	22
July	-	-	6	66	1	1	-	-	2	23
August	3	17	2	20	1	12	-	-	1	5
September	3	6	4	49	-	-	1	26	2	28
October	7	25	2	42	-	-	4	125	3	144
November	5	65	13	175	1	15	7	159	8	178
December	1	154	16	211	8	169	9	221	9	222
Total	55	701	87	1,259	55	886	75	1,511	75	1,561

NOTE : Data show the mean value of 5 stations.

1.2 Socio-Economic Conditions

1.2.1 Population

The population of the Kabupaten Ngada in 1984 was 183,532 which was approximately 6.2% of the 2,947,900 total population of Nusa Tenggara Timur Province as shown in Table 1-2-1.

The population density was 0.60 persons per ha which was almost the same as the provincial density of 0.61.

The recent annual average growth rate of population of the Kabupaten is 2.0% which is lower than both the provincial rate of 2.3% and the national rate of 2.2%. This may be caused by outflow of population to other areas.

The population of each Kecamatan and its proportion to the Kabupaten population is shown in Table 1-2-2.

Table 1-2-1 POPULATION BY KABUPATEN

DESCRIPTION	POPULATION	AAGR (%)	AREA (ha)	POPULATION DENSITY (persons/ha)	SURVEY YEAR
KABUPATEN:					
SUMBA BARAT	261,721	3.0	458,700	0.57	1984
ENDE	214,627	2.0	204,650	1.05	1984
NGADA	183,532	2.0	303,788	0.60	1984
PROVINCE:					
NUSA TENGGARA TIMUR	2,846,400	} 2.3	4,787,600	} 0.61	1982
	2,917,900		4,787,600		1983
	2,947,900		4,787,600		1984
JAWA IS. (Excluding DKI JAKARTA)	91,126,900	1.7	13,159,700	6.92	-
INDONESIA	161,579,500	2.2	191,944,300	0.84	-

Notes :

1. Sources:

Kabupaten; Kabupaten concerned with the study

Province ; Jawa and Indonesia:

Statistical yearbook of Indonesia 1984, published by the Central statistics Bureau.

2. AAGR ; Average Annual Growth Rate.

Table 1-2-2

POPULATION BY KECAMATAN

Year : 1984

PROVINCE : NUSA TENGGARA TIMUR

KABUPATEN : NGADA

KECAMATAN	POPULATION	PROPORTION (%)
AEIMERE	15,966	8.7
WOGOMANGULEWA	24,954	13.6
MAUPONGGO	27,699	15.1
NANGARORO	20,359	11.1
BOAWAE	22,926	12.5
BAJAWA	25,436	13.8
RIUNG	14,807	8.1
AESESA	22,128	12.1
KOPETA BAJAWA	9,257	5.0
TOTAL	183,532	100

1.2.2 Land Use

In Kabupaten Ngada, 149,055 ha of the current available land use area, which is approximately 49.1% of the 303,788 ha total area of the Kabupaten, is used for living purposes and for industrial activity of the inhabitants of the Kabupaten. It is the total value of columns (1) through (6) in Table 1-2-3.

The current available land use area consists of 102,048 ha of agricultural harvest area, 3,175 ha of residential area and 43,832 ha of usable open space which are 68.5%, 2.1% and 29.4% of the current available land use area respectively.

The agricultural harvest area consists of 45,345 ha of paddy field, 12,864 ha of plantation and 43,839 ha of other cultivated area which are 44.4%, 12.6% and 43.0% of the agricultural harvest area respectively.

It can be realized from the land use that the main industrial production in the Kabupaten is food crops, especially paddy.

Table 1-2-3

LAND USE

PROVINCE : NUSA TENGARA TIMUR

KABUPATEN	(ha)										TOTAL AREA	SURVEY YEAR
	WET PADDY FIELD	UPLAND PADDY FIELD	PADDY FIELD TIVATED AREA	OTHER CUL-TIVATED AREA	PLANTATION AREA	RESIDENTIAL AREA	USABLE OPEN SPACE	RIVER & LAKE AREA	FORESTRY AREA	OTHERS		
SUMBA BARAT	13,298 (3.0)	62,061 (13.8)	8,270 (1.8)	59,819 (13.3)	10,371 (2.3)	13,100 (2.9)	42,805 (9.5)	56,043 (12.4)	192,133 (41.0)	450,700 (100)	1984	
ENDE	1,401 (0.7)	7,954 (3.9)	14,970 (7.3)	16,300 (8.0)	9,987 (4.9)	100,000 (48.8)	19,485 (9.5)	33,878 (16.6)	675 (0.3)	204,650 (100)	1984	
NGADA	7,250 (2.4)	38,095 (12.5)	43,839 (14.4)	12,864 (4.2)	3,175 (1.0)	43,832 (14.4)	32 (0)	110,865 (36.5)	43,837 (14.4)	303,788 (100)	1984	

Notes :

1. The value in () denotes the proportion
2. Source : Kabupaten concerned with the study

1.2.3 Agriculture

The cultivated area and food crop production in Kabupaten Ngada in 1984 were 29,435 ha and 102,175 ton respectively as shown in Table 1-2-4. Of food crops, the area and production of paddy, which consists of wet paddy and upland paddy, was 14,126 ha and 65,522 ton respectively which are 48.0% and 64.1% of the total food crops. The yield rate of paddy production is 4.64 ton per ha. Thus, paddy is the most predominant agricultural crop of the Kabupaten.

As the table shows, average annual growth rates of area and production of paddy in 1981 through 1984 were 6.0% and 9.0% respectively which indicate favorable development of the paddy production in the long term.

Upland paddy accounts for 40% of the all paddy production. Regarding the fluctuation of annual productivity it is pointed out that the agriculture of the Kabupaten is easily affected by weather changes because of undeveloped irrigation facilities.

The commodity crops, of which palm oil, and coffee are major, are produced in the plantations. The area and production of plantation crops in 1983 were 40,183 ha and 10,891 ton respectively with current growth rates of 16.5% and 16.5% as shown in Table 1-2-5. Thus the plantation crop which is exported is an important agricultural product. Some changes are expected considering the international balance of supply and demand.

The population of the agricultural sector which is assumed from the employment in the Kabupaten is 84.5% of the total population as shown in Table 1-2-7. Thus this is an agricultural Kabupaten.

Future measures suggested to be taken by the kabupaten include increase of the cultivated area with the progress of road development and appropriation of agricultural investment for improvement of irrigation facilities in order to attain stable growth of productivity.

Table 1-2-4

AREA AND PRODUCTION OF FOOD CROPS

KABUPATEN : NGADA

CULTIVATED AREA							(ha)
ITEM	YEAR						AAGR
	1979	1980	1981	1982	1983	1984	(%)
PADDY	13,082	17,459	22,792	18,825	17,666	9,778	6.0
OTHERS	15,599	20,755	22,712	19,152	17,894	27,665	-20.0
TOTAL	28,681	38,214	45,504	37,977	35,560	37,443	-9.8

PRODUCTION							(ton)
ITEM	YEAR						AAGR
	1979	1980	1981	1982	1983	1984	(%)
PADDY	11,902	38,939	25,184	30,434	30,813	26,459	9.0
OTHERS	41,407	118,784	53,711	77,862	95,817	100,344	-20.0
TOTAL	53,309	157,723	78,895	108,296	126,630	126,803	-6.0

YIELD RATE							(ton/ha)
ITEM	YEAR						AAGR
	1979	1980	1981	1982	1983	1984	(%)
PADDY	0.91	2.23	1.10	1.62	1.74	2.71	5.0

Notes :

1. AAGR : Average annual growth rate
2. Source : Kabupaten concerned with the study

Table 1-2-5 AREA AND PRODUCTION OF PLANTATION CROPS
Year : 1983

PROVINCE : NUSA TENGGARA TIMUR				
KABUPATEN	AREA (ha)	PRODUCTION (ton)	AAGR (%)	
			AREA	PRODUCTION
SUMBA BARAT	38,564	2,646	0.4	1.3
ENDE	15,309	3,106	5.1	0
NGADA	40,183	10,891	16.5	16.5

Table 1-2-6 POPULATION OF AGRICULTURAL SECTOR

PROVINCE : NUSA TENGGARA TIMUR					
KABUPATEN	AGRICULTURAL SECTOR	TOTAL POPULATION	PROPORTION (%)	AAGR (%)	SURVEY
					YEAR
SUMBA BARAT	187,000	261,721	71.5	2.5	1984
ENDE	178,000	214,627	83.0	5.0	1984
NGADA	160,000	183,532	84.2	5.0	1984

Notes :

1. AAGR : Average annual growth rate
2. Source Kabupaten concerned with the Study

1.2.4 Other Economic Activities

Notable economic activities excluding agriculture in Kabupaten Ngada are only livestock sector.

According to the Kabupaten data, the production volume of livestock in 1983 recorded approx. 2,410 tons and approx 1,500 tons out of 2,410 tons excluding the consumption of the Kabupaten itself are exported out of the Kabupaten. And this sector is expected to become prosperous.

1.3 Present Status of Kabupaten Roads

1.3.1 Outline of Road Networks

The regional trunk roads of Kabupaten Ngada consist of one national road and four provincial roads. The national road runs across the Kabupaten in the southern region from east to west via Bajawa, the Kabupaten capital. Two of the provincial roads lead to the south coast of the Kabupaten, to Manpongo and Maumbawa from Gako and Malanusa, respectively their junctions with the national road. The other two provincial roads run towards the north, to Danga and Poma from Aegela and Bajawa, respectively their junctions with the national road.

However two provincial roads which run towards the central and northern regions do not act as regional trunk roads at present due to their bad road surface conditions.

The Kabupaten roads formed in the central area north of the national road seem to have an important role as the facility for industrial development of the Kabupaten. It seems necessary to develop access roads to the northern coastal area which is expected to be one of the centers for developing the Kabupaten.

1.3.2 Road Inventory

From the road inventory data prepared by the Kabupaten, the number and total length of Kabupaten roads to be studied in Kabupaten Ngada are confirmed as 50 links and 937 Km respectively. These figures exclude Kabupaten roads with no data.

According to the data the present status of the Kabupaten roads is as follows:

(1) Density of Kabupaten Roads

The density of the Kabupaten roads is 3.08 m per ha. This is distinctly higher than the national density of 0.48 m per ha and distinctly more than 2.11 m per ha which is the density in Jawa Island, excluding DKI Jakarta, as shown in the following table. Thus, the Kabupaten is well advanced in density of Kabupaten roads.

	<u>Total Length</u> (km)	<u>Area</u> (ha)	<u>Density</u> (m/ha)
Kabupaten : Ngada	937	303,788	3.08
Province : Nusa Tenggara Timur	1,882	967,138	1.95
Jawa Is. (Excluding DKI Jakarta)	27,715	13,159,700	2.11
Indonesia	92,038	191,944,300	0.48

Notes : 1. The value for the province is the total value for the Kabupatens included in the study.

2. The source of data are as follows:

Kabupaten and Province : Bina Marga Inventory

Jawa and Indonesia : Statistical Yearbook of
Indonesia 1984, published
by the Central Statistics
Bureau

(2) Kabupaten Road Surface Type

The type of surface on the Kabupaten roads in the Kabupaten is shown in Table 1-3-1.

The legend used in the table is as follows:

ASP : Asphalt

Table 1-3-1 EXISTING ROAD LENGTH BY SURFACE TYPE

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(Km)							(Km)						
102	THH	KRK	ASP	BTB	L.L	TOTAL	102	THH	KRK	ASP	BTB	L.L	TOTAL
LINK 1	5					5	LINK 26	15					15
LINK 2	16					16	LINK 27	5					5
LINK 3	4	12				16	LINK 28	15					15
LINK 4				6		6	LINK 29	38					38
LINK 5	3	15				18	LINK 30	25					25
LINK 6	8					8	LINK 31	10					10
LINK 7		20				20	LINK 32	25					25
LINK 8		11		31		42	LINK 33	4					4
LINK 9	19					19	LINK 34	7					7
LINK 10	16			18		34	LINK 35	7					7
LINK 11	26	6		2		34	LINK 36	10					10
LINK 12		28				28	LINK 37	12					12
LINK 13	25					25	LINK 38	9					9
LINK 14	47					47	LINK 39	15					15
LINK 15	41					41	LINK 40	4					4
LINK 16	15					15	LINK 41	56					56
LINK 17	9	4				13	LINK 42	12					12
LINK 18	22					22	LINK 43	7					7
LINK 19	50					50	LINK 44	5					5
LINK 20	20					20	LINK 45	18					18
LINK 21	8					8	LINK 46	7					7
LINK 22	25					25	LINK 47	30					30
LINK 23	10					10	LINK 48	18					18
LINK 24	20					20	LINK 49	9					9
LINK 25		16				16	LINK 50	8					8
TOTAL							761	113	2	59	2	937	
RATIO							81	12	0	6	0	(%)	

KRK : Gravel/Stone/Telford/Water Bound Macadam
 TNH : Earth
 LL : Others

Comparison of the proportion of surface type in the Kabupaten with other regions is as follows:

	<u>ASP</u>	<u>KRK</u>	<u>TNH/LL</u>
Kabupaten : Ngada	0.2	18.3	81.4
Province : Nusa Tenggara Timur	1.6	26.5	71.9
Jawa Is.(Excluding DKI Jakarta)	56.2	25.0	18.8
Indonesia	26.0	26.6	47.4

Thus, in the Kabupaten the proportion of Kabupaten roads with asphalt surface is much lower either than that of Indonesia and of Jawa Island. The proportion of low grade roads such as earth roads and others is distinctly high. This means that the road classification in the Kabupaten is low.

(3) Surface Condition of Kabupaten Roads

The surface condition of the Kabupaten roads classified as good, fair, poor and bad which are shown as BA, SD, RU and RB respectively, are summarized in Table 1-3-2.

Comparison of the proportions of the various surface conditions of the Kabupaten roads in the Kabupaten with other regions is as follows:

	<u>Good</u>	<u>Fair</u>	<u>Poor</u>	<u>Bad</u>
Kabupaten : Ngada	16.3	20.2	29.0	34.5
Province : Nusa Tenggara Timur	13.8	29.5	30.7	26.0
Jawa Is.(Excluding DKI Jakarta)	45.6	29.8	19.6	5.0
Indonesia	43.5	21.8	21.1	13.6

The surface condition level of the Kabupaten roads in the Kabupaten is lower than that of Indonesia and Jawa Island.

Table 1-3-2

EXISTING ROAD CONDITION BY SURFACE TYPE

PROVINCE : NUSA TENGGARA TIMUR

KABUPATEN : NGADA

(2)

No	TMI				KPK				ASP				BTS				L.L				
	BA	SD	RU	RB	BA	SD	RU	RB	BA	SD	RU	RB	BA	SD	RU	RB	BA	SD	RU	RB	
LINK 1		24	76																		
LINK 2	6	18	28	48																	
LINK 3	60		48		41	24	35														
LINK 4									80	10	10			80	14	6					
LINK 5	13	37	27	23	4	56	33	7													
LINK 6		38	31	32																	
LINK 7					56	11	33														
LINK 8	40	40	20		61	26	13							91	7	3					
LINK 9	39	43	13	6										80	20						
LINK 10	17	47	22	14										53	30	17					
LINK 11	20	39	36	4	25	58	17							60	38	3					
LINK 12						64	36														
LINK 13		16	48	36																	
LINK 14	18	30	48	8																	
LINK 15		17	37	46																	
LINK 16	10	13	31	46																	
LINK 17	3	9	22	66	15	23	63														
LINK 18	20	5	18	58																	
LINK 19			19	81																	
LINK 20	3	32	55	10																	
LINK 21			60	40																	
LINK 22	12	18	12	59																	
LINK 23	4	14	24	58																	
LINK 24	9	18	19	55																	
LINK 25					21	28	2														
LINK 26	26	8	27	39																	
LINK 27		67	33			55	45														
LINK 28	23	15	27	35																	
LINK 29			26	74																	
LINK 30	16	17	9	58																	
LINK 31	6	14	20	60																	
LINK 32	7	22	18	55																	
LINK 33		86	14																		
LINK 34		3	55	12																	
LINK 35			5	92																	
LINK 36		3	43	55					60	40					95	5					
LINK 37		10	50	40																	
LINK 38		22	47	31																	
LINK 39			1	99																	
LINK 40	18	20	38	25																	
LINK 41			27	73																	
LINK 42			6	94																	
LINK 43	36	23	41																	99	
LINK 44	31	12	29	28													5	35	60		
LINK 45				99																	
LINK 46	21	19	51	10																	
LINK 47				99																	
LINK 48		6	78	16																	
LINK 49	34	12	31	23																	
LINK 50				99																	
AVERAGE	11	18	30	42	30	38	31		10	35	25	0		61	19	21		0	3	18	80
LENGKAP		761 Km				113 Km				2 Km				59 Km					2 Km		
(%)	84	137	228	320	34	43	35					0		36	11	12		0	0	0	2

The proportion in good condition is relatively low. Therefore, improvement of Kabupaten roads in poor or bad condition is desirable.

(4) Terrain Conditions of Kabupaten Roads

The difficulty of road improvement is mainly dependent upon the terrain conditions.

The terrain conditions of the Kabupaten roads, classified as flat, hilly, mountainous and swampy which are shown as DT, BK, GN and RW, are summarized in Table 1-3-3.

The proportions of terrain conditions in the Kabupaten are 42.0% flat, and 39.0% hilly, 19.0% mountainous. There is no swampy area in the Kabupaten.

1.3.3 Bridge Inventory

A bridge inventory showing the existing condition of bridges on the Kabupaten roads in Kabupaten Ngada was prepared by the Kabupaten.

The bridge types are classified as timber, concrete, steel and others which are shown in the inventory as KY, BT, BJ and LL respectively.

The inventory shown in Table 1-3-4 and Table 1-3-5 indicates a total of 29 bridges with a total length of 231 m of which 1 or 6.9% are timber, 8 or 27.6% are concrete and 17 or 58.6% are others. Steel bridges account for only 2 or 6.7% of the total. On the other hand, 121 bridges with a total length of 1,716 m are required to be newly constructed.

Table 1-3-3 EXISTING ROAD LENGTH BY TERRAIN CONDITION

PROV : NUSA TENGGARA TIMUR

KAB : NGADA

(Km)							(Km)						
LINK	102 (3)	BK	DT	RM	GN	TOTAL	LINK	102 (3)	BK	DT	RM	GN	TOTAL
LINK 1	5					5	LINK 27	4	2				6
LINK 2	1	14				16	LINK 28	8	7				15
LINK 3	2	6			8	16	LINK 29					38	38
LINK 4		7				7	LINK 30	15	10				25
LINK 5	16	2				18	LINK 31	4	6				10
LINK 6	3	5				8	LINK 32	9	16				25
LINK 7	11	7			2	20	LINK 33	4					4
LINK 8		42				43	LINK 34	6	1				7
LINK 9		17			3	20	LINK 35	6	1				7
LINK 10	1	29			4	34	LINK 36	5	7				12
LINK 11	14	12			8	34	LINK 37		12				12
LINK 12	7	21				28	LINK 38					9	9
LINK 13	5	20				25	LINK 39	10				5	15
LINK 14	47					47	LINK 40	2	1			1	4
LINK 15	15	26				41	LINK 41	5				5	56
LINK 16	3	12				15	LINK 42	12					12
LINK 17	2	11				13	LINK 43	1	6				8
LINK 18	13	9				22	LINK 44	2	4				6
LINK 19	45				5	50	LINK 45	18					18
LINK 20	20					20	LINK 46	2	5				7
LINK 21	4	4				8	LINK 47					30	30
LINK 22	8	17				25	LINK 48					18	18
LINK 23		10				10	LINK 49	4	5				9
LINK 24	6	14				20	LINK 50	8					8
LINK 25		16				16							
LINK 26	10	5				15							
TOTAL		364	389	2	182	937							
RATIO		39	42	0	19	(%)							

Table 1-3-4 NUMBER AND LENGTH OF BRIDGES

PROV : NUSA TENGGARA TIMUR KAR : NGADA

<<< BRIDGE >>>							(UNIT: m)
		EXISTING		NOT EXIST		TOTAL	
LINK NO	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	
1				6.00	1	6.00	
2	1	8.00	3	40.00	4	48.00	
3	1	5.00			1	5.00	
4	3	50.00	1	50.00	4	100.00	
5			1	60.00	1	60.00	
6			3	141.00	3	141.00	
7	13	87.00			13	87.00	
8	1	7.00	3	44.00	4	51.00	
9			1	150.00	1	150.00	
11			2	28.00	2	28.00	
12	4	28.00	2	26.00	6	54.00	
13			4	38.00	4	38.00	
14			3	55.00	3	55.00	
15			6	210.00	6	210.00	
16			9	92.00	9	92.00	
17			11	140.00	11	140.00	
18	1	6.00	2	21.00	3	27.00	
19			3	43.00	3	43.00	
20			2	20.00	2	20.00	
21			2	24.00	2	24.00	
22			5	65.00	5	65.00	
23			6	35.00	6	35.00	
24			2	15.00	2	15.00	
25	3	10.00			3	10.00	
26	1	6.00	2	18.00	3	24.00	
27			2	30.00	2	30.00	
28			4	50.00	4	50.00	
29	1	24.00			1	24.00	
30			5	34.00	5	34.00	
31			4	35.00	4	35.00	
32			6	36.00	6	36.00	
33			3	22.00	3	22.00	
34			3	40.00	3	40.00	
35			3	15.00	3	15.00	
36			1	7.00	1	7.00	
37			1	7.00	1	7.00	
38			1	8.00	1	8.00	
39			2	18.00	2	18.00	
40			1	7.00	1	7.00	
41			2	20.00	2	20.00	
42			2	15.00	2	15.00	
43			1	7.00	1	7.00	
44			1	9.00	1	9.00	
45			2	15.00	2	15.00	
47			1	7.00	1	7.00	
48			1	8.00	1	8.00	
49			1	5.00	1	5.00	
TOTAL	29	231.00	121	1716.00	150	1947.00	

Table 1-3-5

NUMBER OF EXISTING BRIDGES BY BRIDGE TYPE

PROV : HUSA TENGGARA TIMUR KAB : NGADA

<<< BRIDGE >>> (No)

LINK	103 (18)	KY	LL	BJ	BT	TOTAL
LINK 1	1					1
LINK 2	1					1
LINK 3			1			1
LINK 4			1	2		3
LINK 5						
LINK 6						
LINK 7	1		10		2	13
LINK 8					1	1
LINK 9						
LINK 11						
LINK 12			3		1	4
LINK 13						
LINK 14						
LINK 15						
LINK 16						
LINK 17						
LINK 18			1			1
LINK 19						
LINK 20						
LINK 21						
LINK 22						
LINK 23						
LINK 24						
LINK 25					3	3
LINK 26			1			1
LINK 27						
LINK 28						
LINK 29					1	1
LINK 30						
LINK 31						
LINK 32						
LINK 33						
LINK 34						
LINK 35						
LINK 36						
LINK 37						
LINK 38						
LINK 39						
LINK 40						
LINK 41						
LINK 42						
LINK 43						
LINK 44						
LINK 46						
LINK 47						
LINK 48						
LINK 49						
TOTAL	2	17	2	8	29	
RATIO	7	59	7	28	(%)	

The number of existing bridges by span length is as follows:

<u>Bridge Type</u>	<u>Span Length (m)</u>										
	<u><3</u>	<u><5</u>	<u><8</u>	<u><10</u>	<u><12</u>	<u><14</u>	<u><16</u>	<u><18</u>	<u><20</u>	<u><99</u>	<u>Total</u>
Timber	-	-	-	-	-	-	-	-	-	-	-
Concrete	2	2	1	-	3	-	-	-	-	-	8
Steel	-	-	-	-	-	-	-	-	-	-	-
Others	-	-	-	-	-	-	-	-	-	-	-
Total	2	2	1	-	3	-	-	-	-	-	8

Existing bridges are of in various types but concrete bridge is prevailing. The majority of spanlengths is within the range of 5 m to 8 m.

1.3.4 Traffic

Inventories of the average daily traffic (ADT) on the Kabupaten roads in Kabupaten Ngada were prepared by the Kabupaten and are shown in Chapter 2.

From the inventories, total value of average daily trips by vehicle type and their proportions in the Kabupaten in 1985 are summarized as follows:

	<u>SEDAN</u>	<u>BUS</u>	<u>TRUCK</u>	<u>MOTOR- CYCLE</u>	<u>TOTAL</u>
Total Trips	498	145	160	513	1,316
Proportion (%)	37.84	11.02	12.16	38.98	100.00

Source : Bina Marga Inventory

The proportions of registered vehicles by vehicle type are as follows:

	<u>SEDAN</u>	<u>BUS</u>	<u>TRUCK</u>	<u>MOTOR- CYCLE</u>	<u>TOTAL</u>
Proportion (%)	0.00	4.97	14.93	80.10	100.00

Source : Kabupaten.

Thus, the proportion of motorcycles in the Kabupaten is by far the highest.

From the above tables the following can be observed:

- Number of total trips might be underestimated
- Proportions are probably reasonable.

Essentially, for estimation of future traffic volumes past and present traffic data together with the trend in the number of registered vehicles are important basic data. However the data obtained for the study was traffic count data for each road link in 1985 and of low reliability.

Therefore the future traffic volumes are estimated by the calculation process recommended in chapter 3 of the Main Report.

Chapter 2 ESTIMATIONS OF FUTURE TRAFFIC VOLUME AND BENEFIT

2.1 Future Traffic Volume

2.1.1 Traffic Growth Rate

The traffic growth rate used for estimation of the future traffic volume on the Kabupaten roads was estimated by the following calculation process.

Growth of Production Basis "A":

$$\sqrt{\frac{\text{Annual Population Growth of the Kabupaten}}{\text{Growth of the Total Cultivated Area}} \times \text{Growth of the Total Cultivated Area}}$$

Growth of Productivity "B" :

$$\sqrt{\frac{\text{Growth of the Total Paddy Field Area}}{\text{Growth of the Paddy Production per ha}} \times \text{Growth of the Paddy Production per ha}}$$

Traffic Growth Rate: Initial estimated figure:

$$GR^I = \sqrt{A \times B}$$

Traffic Growth Rate GR = Final adjusted figure:

$$\sqrt{GR^I \times \text{Trend of GDP/Capita of the Province Concerned}}$$

Results of the estimation are shown in Table 2-1-1.

Table 2-1-1 TRAFFIC GROWTH RATE ESTIMATION

PROV : NUSA TENGGARA TIMUR		KAB : NGADA	
A)	Growth Rate of Population	:	2.00 (%)
B)	Growth Rate of Cultivated Area	:	7.00 (%)
C)	Growth Rate of Rice field	:	8.00 (%)
D)	Growth Rate of Rice yield rate	:	5.00 (%)
E)	Growth Rate of GDP / capita	:	7.70 (%)
<hr/>			
a)	Geometrical Mean (A x B)	:	4.47 (%)
b)	Geometrical Mean (C x D)	:	6.49 (%)
c)	Geometrical Mean (a x b)	:	5.47 (%)
d)	Geometrical Mean (c x E)	:	6.58 (%)
<hr/>			
TRAFFIC GROWTH RATE		:	6.58 (%)

2.1.2 Present and Future Traffic Volume

The future traffic volumes on the Kabupaten roads in 1998 for the Project life time of ten years were estimated by the following formula :

$$T_n = T_e (1 + r)^n$$

Where :

T_n : Future traffic volume n years later

T_e : Traffic volume in 1985

r : Traffic growth rate

The results are shown in Table 2-1-2 together with the traffic volume in 1985.

Table 2-1-2

EXISTING AND FUTURE TRAFFIC VOLUME

PROV : NUSA TENGGARA TIMUR KAB : NGADA

< SPD : 1/2 >

LINK NO	INVENTORY (1985)					RATE	AFTER 13 YEARS (1998)					CLASS
	MBL	BUS	TRUK	SPD	TOTAL		MBL	BUS	TRUK	SPD	TOTAL	
1	50	20	10	40	100	6.6%	114	46	23	92	229	111B-1
2	25	10	10	40	65	6.6%	57	23	23	92	149	111B-2
3	0	0	0	20	10	6.6%	0	0	0	46	23	111C
4	40	20	20	20	90	6.6%	92	46	46	46	206	111B-1
5	1	0	0	2	2	6.6%	2	0	0	5	5	111C
6	10	10	5	20	35	6.6%	23	23	11	46	80	111B-2
7	2	0	0	4	4	6.6%	5	0	0	9	9	111C
8	10	0	10	5	23	6.6%	23	0	23	11	53	111B-2
9	8	0	2	0	10	6.6%	18	0	5	0	23	111C
10	0	0	2	0	2	6.6%	0	0	5	0	5	111C
11	2	0	0	0	2	6.6%	5	0	0	0	5	111C
12	20	10	10	20	50	6.6%	46	23	23	46	114	111B-2
13	1	0	2	0	3	6.6%	2	0	5	0	7	111C
14	0	0	0	0	0	6.6%	0	0	0	0	0	111C
15	1	0	2	0	3	6.6%	2	0	5	0	7	111C
16	50	40	0	0	90	6.6%	114	92	0	0	206	111B-1
17	10	0	0	8	14	6.6%	23	0	0	18	32	111C
18	10	0	0	10	15	6.6%	23	0	0	23	34	111C
19	0	0	2	2	3	6.6%	0	0	5	5	7	111C
20	0	0	2	2	3	6.6%	0	0	5	5	7	111C
21	0	0	1	1	2	6.6%	0	0	2	2	5	111C
22	30	0	0	20	40	6.6%	69	0	0	46	92	111B-2
23	15	0	0	15	23	6.6%	34	0	0	34	53	111B-2
24	15	0	0	15	23	6.6%	34	0	0	34	53	111B-2
25	8	2	15	15	33	6.6%	18	5	34	34	76	111B-2
26	10	0	0	10	15	6.6%	23	0	0	23	34	111C
27	15	1	25	25	54	6.6%	34	2	57	57	124	111B-2
28	20	0	0	25	33	6.6%	46	0	0	57	76	111B-2
29	0	0	0	0	0	6.6%	0	0	0	0	0	111C
30	30	0	0	25	43	6.6%	69	0	0	57	98	111B-2
31	20	0	0	15	28	6.6%	46	0	0	34	64	111B-2
32	25	0	0	25	39	6.6%	57	0	0	57	87	111B-2
33	0	0	10	15	18	6.6%	0	0	23	34	41	111C
34	20	10	5	40	55	6.6%	46	23	11	92	126	111B-2
35	40	20	20	60	110	6.6%	92	46	46	137	252	111B-1
36	0	0	2	2	3	6.6%	0	0	5	5	7	111C
37	0	0	0	0	0	6.6%	0	0	0	0	0	111C
38	2	0	2	2	5	6.6%	5	0	5	5	11	111C
39	0	0	1	2	2	6.6%	0	0	2	5	5	111C
40	0	0	2	4	4	6.6%	0	0	5	9	9	111C
41	0	0	0	0	0	6.6%	0	0	0	0	0	111C
42	0	0	0	0	0	6.6%	0	0	0	0	0	111C
43	0	0	0	0	0	6.6%	0	0	0	0	0	111C
44	0	0	0	0	0	6.6%	0	0	0	0	0	111C
45	0	0	0	0	0	6.6%	0	0	0	0	0	111C
46	0	0	0	0	0	6.6%	0	0	0	0	0	111C
47	0	0	0	0	0	6.6%	0	0	0	0	0	111C
48	2	0	0	0	2	6.6%	5	0	0	0	5	111C
49	0	0	0	0	0	6.6%	0	0	0	0	0	111C
50	6	2	0	4	10	6.6%	14	5	0	9	23	111C
PERCENT	37.84	11.02	12.16	38.98			37.84	11.02	12.16	38.98		

2.2 Benefit

2.2.1 Benefit Estimation Method

Generally, estimation of the benefit on each Kabupaten road due to the Project was made by analyzing the direct benefit i.e. the VOC reduction benefit, which was estimated by comparing "with project" and "without project" based upon the future traffic volume on the road. However for the following road links it was decided to estimate the indirect benefit through the producer's surplus benefit.

- a) Road links with present traffic volume (ADT) less than 60 equivalent 4-wheel vehicles.
- b) Road links with no 4-wheel vehicle operation at present.

The indirect benefit was changed into the future traffic volume and the VOC reduction benefit was estimated.

The VOC adopted for the estimation is shown in Table 2-2-1.

Table 2-2-1 VEHICLE OPERATION COST ON KABUPATEN ROADS

SURFACE	CONDITION	(KM)			
		SEDAN	BUS	TRUCK	MOTORCYCLE
ASPHALT	GOOD	104.7	86.2	85.4	15.9
	Fair	125.5	101.0	98.0	18.2
	Poor	164.1	135.2	138.5	22.8
	Bad	222.1	202.0	205.0	29.1
GRAVEL	Good	125.7	101.4	102.5	18.5
	Fair	145.0	124.6	127.1	21.1
	Poor	198.6	172.6	178.4	27.1
	Bad	242.7	228.9	231.2	31.8
EARTH	Fair	201.8	180.0	185.1	28.0
	Poor	240.7	218.2	225.8	31.8
	Bad	264.9	278.0	281.7	35.5

Source : Bina Marga

Table 2-2-2

FUTURE TRAFFIC VOLUME ESTIMATED
BY THE PRODUCER'S SURPLUS

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(1998)

LINK NO	CLASS	SURFACE	MOBIL	BUS	TRUCK	SEPEDA	TOTAL
3	111C	KRK	3	1	1	3	7
5	111B-2	KRK	82	24	27	85	176
6	111C	KRK	19	6	6	20	41
7	111B-2	KRK	41	12	13	43	88
8	111B-1	ASP	139	40	45	143	296
9	111B-2	KRK	55	16	18	57	118
10	111C	KRK	7	2	2	8	15
11	111C	KRK	7	2	2	7	15
12	111B-2	KRK	64	19	20	66	136
13	111B-1	ASP	117	34	38	121	250
14	111B-1	ASP	116	34	37	120	247
15	111B-1	ASP	117	34	38	121	250
17	111C	KRK	1	0	0	1	2
18	111C	KRK	11	3	4	11	24
19	111C	KRK	8	2	3	8	17
20	111B-2	KRK	77	23	25	80	165
21	111B-2	KRK	23	7	8	24	50
22	111B-2	KRK	85	25	27	88	181
23	111C	KRK	17	5	6	18	37
24	111B-2	KRK	64	19	21	66	137
25	111B-2	KRK	55	16	18	56	117
26	111B-2	KRK	47	14	15	48	100
27	111C	KRK	13	4	4	13	28
28	111B-2	KRK	26	8	8	27	56
29	111C	KRK	1	0	0	1	2
30	111B-2	KRK	76	22	24	79	162
31	111B-2	KRK	32	9	10	33	68
32	111B-2	KRK	78	23	25	81	167
33	111C	KRK	12	4	4	13	27
34	111C	KRK	22	6	7	22	46
36	111B-2	KRK	37	11	12	38	79
37	111B-2	KRK	41	12	13	42	87
38	111C	KRK	13	4	4	13	28
39	111C	KRK	16	5	5	16	34
40	111C	KRK	7	2	2	7	15
41	111B-1	ASP	138	40	44	142	293
42	111C	KRK	19	6	6	20	41
43	111C	KRK	2	1	1	2	5
44	111C	KRK	10	3	3	11	22
45	111B-2	KRK	31	9	10	32	66
46	111C	KRK	12	4	4	12	26
47	111C	KRK	3	1	1	4	7
48	111B-2	KRK	34	10	11	35	73
49	111B-2	KRK	71	21	23	73	152
50	111C	KRK	14	4	4	14	29

2.2.2 Benefit

The benefit estimation was carried out for each Kabupaten road. Table 2-2-3 shows a sample of the result of benefit estimation. In the table "surplus" and "VOC" show the estimation method utilized and III A, III B-1, III B-2 and III C show the road classification.

Table 2-2-3

RESULTS OF BENEFIT ESTIMATION

KARUPATEN : NGADA

(1000Rupiah)

	LINK 1	LINK 2	LINK 3	LINK 4	LINK 5	LINK 6	LINK 7	LINK 8	LINK 9	LINK 10
	5 Km	16 Km	16 Km	7 Km	18 Km	8 Km	20 Km	43 Km	20 Km	34 Km
	III B-1	III B-2	III C	III B-1	III B-2	III C	III B-2	III B-1	III B-2	III C
YEAR	VOC	VOC	Surplus	VOC	Surplus	Surplus	Surplus	Surplus	Surplus	Surplus
1988	0	0	0	0	0	0	0	0	0	0
1989	25376	47235	298	6382	22662	3960	6081	49694	27407	2960
1990	27069	50469	298	6809	24964	3960	6704	54340	29967	3708
1991	28566	54471	298	7182	27267	4997	7338	58986	32630	3708
1992	30490	57706	298	7609	29569	5706	8165	64145	35882	4456
1993	32470	61791	883	8164	32300	6427	9183	69772	39133	4456
1994	34653	65108	883	8655	35358	7174	9637	75445	42385	4538
1995	37087	69193	1154	9327	38821	7528	10679	82414	45709	5953
1996	39298	73279	1154	9882	42652	9273	11720	88554	49549	7417
1997	41732	78049	1452	10555	46484	9665	12762	96550	53534	8165
1998	44664	83833	1452	11291	51131	11096	13827	104957	58096	8246
SUM	341405	641134	8170	85856	351208	69786	96096	744857	414292	53607
COST	172573	317611	-53314	12180	136363	10325	-17023	195571	166587	-92354
/Km	34515	19851	-3332	1740	7576	1291	-851	4548	8329	-2716

Chapter 3 ENGINEERING

3.1 Design Criteria and Specification

3.1.1 Geometric Design Criteria

Currently a technical standard for improvement of Kabupaten roads i.e. PETUNJUK TEKNIS INPRES PENUNJANGAN JALAN KABUPATEN, TAHUN 1984-1985 is established by Bina Marga.

The geometric design criteria in the above standard are recommended to be adopted in general for the Project. Following discussions with Bina Marga, exceptions to this are allowed for Pavement width and pavement type to minimize the construction cost of the Kabupaten road improvement, if necessary. The geometric design criteria adopted for the Project are shown in Table 3-1-1. The typical cross sections of Kabupaten roads are shown in Fig. 3-1-1.

3.1.2 Loading Specification

The LOADING SPECIFICATIONS FOR HIGHWAY BRIDGES BY DIRECTORATE GENERAL BINA MARGA is used in principle as the basic specification of loading and the TECHNICAL STANDARD FOR KABUPATEN ROADS compiled by Bina Marga shows that the design live load for bridges on Kabupaten roads is 70% of the Bina Marga live road. However, after discussions with Bina Marga the following loads were decided as the design live loads for the standard bridges of Kabupaten roads:

- a. 50% of Bina Marga live load (hereinafter BM 50) is applied for concrete and timber bridges on roads of III A classification.
- b. 10-ton truck load is applied for timber bridges on roads of III B-1, III B-2 and III C classification.


Table 3-1-1

DESIGN CRITERIA FOR KABUPATEN ROADS

ROAD CLASSIFICATION	CLASS III A				CLASS III B-1				CLASS III B-2				CLASS III C		
	ASPHALT SEAL (DOUBLE)		ASPHALT SEAL (SINGLE)		GRAVEL		GRAVEL		GRAVEL		GRAVEL		GRAVEL		
TRAFFIC VOLUME (Forecast 10 th year average per day)	3000 - 500				500 - 200				200 - 50				50		
T E R R A I N	FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS	FLAT TO ROLLING	HILLY	MOUNT- AINOUS
TRAFFIC LANES	1+	1+	1+	1+	1+	1+	1+	1+	1+	1+	1+	1+	1	1	1
DESIGN (Km/hr)	70	60	40	70	40	30	60	40	30	50	30	30	50	30	AS PRACTI- CABLE
SPEED	30	30	30	30	30	AS PRACTI- CABLE	30	30	AS PRACTI- CABLE	30	30	AS PRACTI- CABLE	30	AS PRACTI- CABLE	AS PRACTI- CABLE
GRADIENT (LIMITING)	4	5	8	4	6	8	4	7	8	4	7	8	5	8	12
PAVEMENT WIDTH (M)	7	7	10	7	8	10	7	9	12	7	9	12	7	12	16
SHOULDER WIDTH (M)	6.0	6.0	6.0	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	4.5	3.5	3.5	3.5
ROAD BED WIDTH (M)	4.5	4.5	4.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.0	3.0	3.0
RIGHT OF WAY (M)	2.0	1.5	1.5	1.5	1.5	1.0	1.5	1.0	1.0	1.5	1.0	1.0	1.0	1.0	0.75
ROAD CAMBER (%)	1.5	1.0	0.75	1.0	1.0	0.75	1.0	0.75	0.5	1.0	0.75	0.5	0.75	0.5	0.5
	10.0	9.0	9.0	8.0	7.5	6.5	7.5	6.5	6.5	7.5	6.5	6.5	5.5	5.5	5.0
	6.0	6.0	6.0	5.5	5.5	5.0	5.5	5.0	4.5	5.5	5.0	4.5	4.5	4.0	4.0
	16	12	12	12	10	10	12	10	10	12	10	10	12	12	12
	12	12	12	12	10	10	12	10	10	12	10	10	12	12	12
	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4

STANDARD ROAD CROSS SECTIONS

Fig. 3-1-1



3.2 Pavement Design

3.2.1 Design Conditions

From the engineering data prepared by the Kabupaten it is noted that the pavement structure of the Kabupaten roads seems to have been determined without adequate designs, therefore the Kabupaten roads generally have insufficient capacity. The standards generally used for highway pavement design such as Road Note 29, Road Note 31 and AASHTO are not suitable for Kabupaten roads with small traffic volumes and loads.

Therefore formulae suitable for the pavement design of Kabupaten roads are recommended as described in Chapter 5 of the Main Report.

The following are important factors for the design of pavement thickness.

1) Design Traffic Volume

As the pavement thickness is designed for each road classification the design traffic volume of which the target year is 1998, is adopted for each classification as follows:

<u>Road Classification</u>	<u>Design Traffic Volume (vpd)</u>
III A	1,000
III B-1	500
III B-2	200
III C	50

2) Strength of Roadbed

The CBR value of the existing roadbed is a very important factor for the pavement design but no results are available from CBR tests on the Kabupaten roads.


CBR of the laterite is generally in the range of CBR 4 to 10. However site CBR tests should be conducted before construction to finally decide the pavement thickness.

3.2.2 Pavement Structure

Fig. 3-2-1 shows the standard pavement structure adopted for the Kabupaten roads.

Fig. 3-2-1

PAVEMENT STRUCTURE



- = SURFACE DRESSING (ASPHALT)
- = BASE COURSE (CRUSHER - RUN)
- = SUBBASE COURSE (SANDY GRAVEL)

3.3 Design of Bridges and Other Structures

3.3.1 Standard Bridge

There are so many bridges to be improved or to be constructed on the Kabupaten roads in the Project Area that it is very difficult to prepare an individual design for each bridge. Therefore, standardization is recommended as being necessary for the bridge design with conclusions as described below.

(1) Bridge Type

1) Superstructure

The following two types have been finally selected with the agreement of Bina Marga after studying the actual rural conditions of bridge construction. Fig. 3-3-1 shows the cross sections of standard types.

- a. Timber beam bridge (hereinafter timber bridge) for roads class III B-1, III B-2 and III C.
- b. Reinforced concrete T-girder bridge (hereinafter RC-bridge) for roads class III A.

2) Substructure

Taking account of the actual combinations of super and substructure types noted from the field survey, the following two types are recommended as standard because of ease of construction and economy.

- a) Timber pile bents for timber bridge
- b) Rubble in Mortar masonry for RC bridge

3) Foundation


There is no information of subsoil conditions in the inventory data. However, timber piles of 20 cm diameter are generally recommended as piles of this type are in common use.

The pile length is suggested to be a minimum of 3 meters under the bottom of the foundation. The length and number of piles should be decided in order to be adequate for the condition of the foundation materials.


Fig. 3-3-1

CROSS SECTIONS OF STANDARD BRIDGES

TIMBER BRIDGE



REINFORCED CONCRETE BRIDGE



(2) Bridge Width

The effective bridge widths for the standard bridges have been decided as follows through discussions with Bina Marga considering the actual width of Kabupaten roads:

- a) Timber bridge: 4.0 m in general
- b) RC bridge : 4.5 m in general

(3) Span Length

The range of span lengths are determined as:

- a) Timber bridge: 3.0, 5.0 and 8.0 m
- b) RC bridge : 3.0, 5.0, 10.0 and 15.0 m

3.3.2 Other Structure

Culverts and retaining walls shown in Fig. 3-3-2 and Fig. 3-3-3 are recommended as standard structures.

(1) Culvert

The following two culvert types have been adopted for the transverse drainage.

- a) Reinforced concrete pipe culvert ϕ 80 cm
- b) Rubble in mortar box culvert with RC slab 80 cm X 80 cm

(2) Retaining Wall


The following two types of retaining walls have been adopted because of ease of construction, economy and familiarity in Indonesia.

- a) Rubble in mortar retaining wall
- b) Timber retaining wall

Fig. 3-3-2

STANDARD CULVERTS

80 x 80 RUBBLE IN MORTAR BOX CULVERTS



Ø 80 REINFORCED CONCRETE PIPE CULVERT






Fig. 3-3-3

STANDARD RETAINING WALLS

TIMBER RETAINING WALL



RUBBLE IN MORTAR WALL



3.4 Selection of Equipment Types

From the results of comparison of two types of Kabupaten road construction methods, i.e. equipment intensive method and labour intensive method construction methods for major works were basically decided as shown in Table 3-4-1.

Table 3-4-1

CONSTRUCTION METHODS FOR
MAJOR WORKS

METHOD	WORK TYPE
Equipment Intensive	Earthwork, Base Course and Subbase Course
Labour Intensive	Surface Dressing, Drainage, Bridge and Other Structures.

3.4.1 Points to be Considered for the Selection

Full consideration was given to the following points in studying the selection of equipment type.

- a. Most of the construction in the Project is pavement works for road improvement.
- b. The pavement width adopted is equal to or less than 4.5 m and therefore large sized equipment is omitted from the selection process.
- c. Equipment should be capable of with standing the heavy rainfall and poor soil quality. Equipment for construction in swampy areas is considered if necessary.
- d. Uniformity of equipment types with existing equipment is considered to facilitate repair of the equipment in the provincial work shop.
- e. Since the scale of the construction is small and transportation of equipment will frequently be necessary, wheel type equipment has been selected as much as possible as this can move by itself or by being towed.
- f. The road like to be improved are scattered all over the Kabupatens and therefore a low bed truck or equivalent is necessary for transportation of crawler type equipment. It is desirable to protect the existing pavement from damage caused by the movement of crawler type equipment on the existing roads.
- g. The capacity of the equipment has been decided taking into consideration the construction volume and the combination of equipment in the main work.

3.4.2 Combinations of Equipment for Major Works and Maintenance

The combinations of equipment for major works and maintenance are listed in Table 3-4-2 and 3-4-3 respectively.

Table 3-4-2

EQUIPMENT OF ONE WORK GANG FOR MAJOR
TYPES OF WORK

TYPE OF WORK	EQUIPMENT REQUIRED	
1. Site Clearing in Light Bush	1- Bulldozer 90 HP 2- Dump Truck 3.0 Ton	1- Wheel Loader 1.2 m ³
2. Excavation & Embankment		
i) Normal Fill	1- Bulldozer 90 HP 1- Vibratory Roller 4.0 Ton (D&T)	1- Water Tank Truck 4,000 Ltr
ii) Fill by Borrow Material	1- Bulldozer 90 HP 3- Dump Truck 3.0 Ton	1- Wheel Loader 1.2 m ³
iii) Fill in Swamp	1- Swamp Bulldozer 90 HP 1- Water Tank Truck 4,000 Ltr	1- Vibratory Roller 4.0 Ton (D&T)
iv) Excavation to Spoil	1- Bulldozer 90 HP 1- Wheel Loader 1.2 m ³	4- Dump Truck 3.0 Ton
3. Subgrade Preparation	1- Motor Grader 75 HP 1- Vibratory Roller 4.0 Ton (D&T)	1- Water Tank Truck 4,000 Ltr
4. Subbase Course	1- Motor Grader 75 HP 1- Vibratory Roller 4.0 Ton (D&T)	1- Water Tank Truck 4,000 Ltr
5. Base Course	1- Motor Grader 75 HP 1- Vibratory Roller 4.0 Ton 1- Portable Crusher/Screens 30-40 Ton/H	1- Water Tank Truck 4,000 Ltr
6. Cement Stabilizing	1- Motor Grader 70 HP 1- Bulldozer 90 HP 1- Wheel Loader 1.2 m ³ 1- Flat Bed Truck 3.0 Ton	1- Vibratory Roller 4.0 Ton (D&T) 1- Road Stabilizer 1- Water Tank Truck 4,000 Ltr
7. Surface Course	1- Asphalt Sprayer 850 Ltr 1- Tyre Roller 8-15 Ton 1- Portable Crusher/Screens 30-40 Ton/H	1- Flat Bed Truck 3.0 Ton
8. Concrete	1- Concrete Mixer 0.5 m ³ 1- Water Pump 200 Ltr/Min 1- Concrete Vibrator 3.3 HP	1- Flat Bed Truck 3.0 Ton 1- Hand-Guided Vibratory Roller 1000 Kg

Table 3-4-3 EQUIPMENT OF ONE WORK GANG FOR MAINTENANCE

TYPE OF WORK	EQUIPMENT REQUIRED
Road	1- Motor Grader 1- Tyre Roller 8-15 Ton 1- Hand-Guided Vibratory Roller 1000 Kg 1- Flat Bed Truck 3.0 Ton 1- Dump Truck 3.0 Ton
Bridge and Other Structure	1- Flat Bed Truck With Crane 3.0 Ton

3.5 Workshop and Laboratory

3.5.1 Policy of the Kabupaten Workshop

A workshop will be provided for each Kabupaten. The function of the workshop is to cope with requests from the construction site. The main service will be routine maintenance while the secondary service will be light repairs which can be carried out by changing parts. Dismantling and assembling of units which need setting or adjustment using special equipment or facilities will not be carried out in the Kabupaten workshop. Such repairs are planned to be carried out by the provincial workshop or the regional Workshop of Bina Marga.

Accordingly the main tasks of the Kabupaten workshop are as follows:

- 1) Administration for and storage of equipment
- 2) Routine maintenance and light repair of equipment
- 3) Storage and supply of spare parts
- 4) Operation of equipment including crushing plant.

3.5.2 Workshop Equipment and Tools

Equipment and tools for the workshop are recommended as shown in Table 3-5-1.

Table 3-5-1 WORKSHOP EQUIPMENT AND TOOLS

DESCRIPTION	QUANTITY
Upright Drilling Machine	1 Set
Electric Hand Drill	1
Electric Portable Grinder	1
Disc Grinder	1
Bench Electric Grinder	1
Engineer's Vice	1
DC Electric Welder with Engine	1 Set
Portable Hydraulic Jack, Screw Head	1
Hydraulic Jack	1
Grease Gun	2
Suction Pump for Oil Recovery	2
High Pressure Grease Pump	1

continued

DESCRIPTION	QUANTITY
Drum Opening Spanner	1
Silicon Normal Charger	1
Tyre Changer Air Operated	1
Tyre Service Tool Set	1
Tyre Pressure Gauge	1
Automatic Tyre Inflator	1
Plug Cleaner and Tester	1
Mechanics Tool Set, Heavy Equipment	1
Mechanics Tool Set, Large Vehicle	1
Portable Air Compressor	1
Electric Cord Reel, 15 A, 50 m	1
Oil Measure, Polyethylene	1
Funnel 200 mm, Steel	3
Hand Truck (Cart), 4-Wheel	1
Nylon Sling, 10 ton	2
Chain Block, 1 ton	2
Wire Rope (for sling), 1.8 ton	2
Wire Rope (for sling) 3.2 ton	2
Generator	1

3.5.3 Laboratory

For quality control of construction in the Project it is recommended that a laboratory is provided for each Kabupaten. For each laboratory, provision of laboratory test equipment for the following tests is recommended:

- Physical characteristic, compaction and strength tests for the road bed and pavement materials.
- Slump and strength tests for the bridge concrete.

In the laboratory a fixed water tank should be provided for CBR tests and curing of concrete specimens.

The proposed laboratory equipment is listed in Table 3-5-2.

Table 3-5-2 LABORATORY TEST EQUIPMENT

DESCRIPTION	QUANTITY
Soil Moisture Test Set (JIS A1203)	1
Liquid Limit Set (JIS A1205)	1
Plastic Limit Set (JIS A1206)	1
Compaction Set (JIS A1210)	1
GBR Laboratory Set, Mechanical (JIS A1211)	1
Sand Density Apparatus (JIS A1214)	1
Aggregate Test Sieve Set	1
Portable Cone Penetrometer	1
Compression & Bending Test Machine	1
Cylinder Mould (JIS A1132, 1108)	9
Slump Test Apparatus (JIS A1101)	2

To conduct the surveys necessary for road and structure construction such as centering, profile leveling, cross section leveling etc., the surveying equipment listed in Table 3-5-3 recommended.

Table 3-5-3 SURVEYING EQUIPMENT

DESCRIPTION	QUANTITY
Transit	1
Level	1
Staff	3

Chapter 4 CONSTRUCTION AND MAINTENANCE COST ESTIMATIONS

4.1 Unit Price

With regard to the unit prices of materials and labor, the data were collected from each Kabupaten through Bina Marga. The collected data were compared with those of Jakarta using BAHAN BANGUNAN DKI-JAKARTA MAY & JUNE 1985 compiled by PUSAT INFORMASI TEHNIK PEMBANGUNAN, and then finalized.

4.1.1 Unit Labour Price

The unit labour prices of Kabupaten Ngada and other Kabupatens in Nusa Tenggara Timur Province are shown in Table 4-1-1.

Table 4-1-1 UNIT LABOUR PRICE

KABUPATEN	MAN	SKL LAB	CAP	MAS	LAB	DRIV	(Rp)
							OPE
Sumba Barat	2,000	2,000	2,000	2,000	1,500	2,500	2,750
Ende	2,500	1,600	1,750	1,750	1,100	2,500	2,500
Ngada	1,500	1,300	2,000	2,000	1,100	2,000	3,000
Average	2,000	1,300	1,917	1,917	1,233	2,333	2,750

Notes :

- MAN : Mandur
- SKL LAB : Skilled Labour
- CAP : Carpenter
- MAS : Mason
- LAB : Labourer
- DRIV : Driver
- OPE : Operater

4.1.2 Unit Price of Materials

Table 4-1-2 shows the unit price of materials for Kabupaten Ngada together with for other Kabupatens in Nusa Tenggara Timur Province.

Table 4-1-2

UNIT PRICE OF MATERIALS

MATERIAL	UNIT	(Rp)			
		SUMBA BARAT	ENDE	NGADA	AVERAGE
Bitumen	L	500	400	400	433
Asphalt oil	L	1,500	1,500	1,500	1,500
Gasoline	L	300	250	250	267
Sand	M ³	9,000	8,000	5,000	7,333
Cement	bag	6,000	6,000	5,500	5,833
River Stone	M ³	8,000	6,000	4,000	6,000
Steel moulds	Set	8,500	8,500	8,500	8,500
Timber	M ³	200,000	200,000	200,000	200,000
Paint	L	4,000	2,500	1,750	2,750
Reinforcing Steel	Kg	1,500	800	1,750	1,350
Tying Wire	Kg	1,250	1,250	2,500	1,667
Equivalent Royalty	M ³	250	250	250	250

4.1.3 Hourly Equipment Cost

The hourly equipment cost for Kabupaten is shown in Table 4-1-3.

Table 4-1-3

HOURLY EQUIPMENT COST

PROVINCE : NUSA TENGGARA TIMUR
KABUPATEN : NGADA

(UNIT : Rp) (6 '85)

CODE NO	EQUIPMENT NAME	CLASS	LOCAL COST			FOREIGN COST			TOTAL COST
			OWNERSHIP	OPERATION	SUB-TOTAL	OWNERSHIP	OPERATION	SUB-TOTAL	
	Bulldozer	120 HP	311	12,800	13,111	7,769	1,034	8,803	21,914
	Bulldozer/Ripper	120 HP	340	13,821	14,161	8,500	1,591	10,091	24,252
	Swamp Bulldozer	120 HP	356	14,065	14,421	8,879	1,662	10,541	24,962
	Bulldozer	90 HP	197	8,657	8,854	4,914	654	5,568	14,422
	Bulldozer/Ripper	90 HP	212	9,254	9,466	5,300	992	6,292	15,758
	Bulldozer	65 HP	140	6,290	6,430	3,500	465	3,965	10,395
	Bulldozer/Ripper	65 HP	153	6,744	6,897	3,819	714	4,533	11,430
	Swamp Bulldozer	90 HP	212	9,244	9,456	5,284	989	6,273	15,729
	Swamp Bulldozer	65 HP	162	6,647	6,809	4,050	758	4,808	11,617
	Motor Grader	110 HP	277	11,088	11,365	6,919	1,295	8,214	19,579
	Motor Grader	75 HP	192	7,600	7,792	4,779	894	5,673	13,465
	Motor Grader	65 HP	172	6,689	6,861	4,300	804	5,104	11,965
	Road Stabilizer	M-1850 mm	344	3,414	3,758	8,594	428	9,022	12,780
	Vibratory Roller	4 ton	116	3,323	3,439	2,900	385	3,285	6,724
	Hand-guide Vib. Roller	1000 Kg	94	602	696	849	30	879	1,575
	Tire Roller	8-15 ton	125	7,342	7,467	3,106	103	3,209	10,676
	Vibratory Roller (D&T)	4 ton	116	3,323	3,439	2,900	385	3,285	6,724
	Hand-guide Vib. Roller	600 Kg	66	411	477	600	21	621	1,098
	Rough Terrain Crane	10 ton	402	12,926	13,328	10,039	751	10,790	24,118
	Hydraulic Excavator; Wheel	0.3 m ³	165	7,781	7,946	4,109	546	4,655	12,601
	Wheel Loader	1.2 m ³	281	8,426	8,707	7,019	934	7,953	16,660
	Wheel Loader	0.3 m ³	91	2,939	3,030	2,269	302	2,571	5,601
	Water Tank Truck	4000 ltr.	96	2,825	2,921	868	123	991	3,912
	Fuel Tank Truck	4000 ltr.	98	2,833	2,931	882	125	1,007	3,938
	Dump Truck	3.0 ton	162	3,550	3,712	1,469	208	1,677	5,389
	Flat Bed Truck with Crane	3.0 ton	69	3,067	3,136	1,717	128	1,845	4,981
	Dump Loader Truck	12 ton	154	18,820	18,974	3,838	127	3,965	22,939
	Dump Truck	5.0 ton	241	5,859	6,100	2,189	311	2,500	8,600
	Flat Bed Truck	3.0 ton	23	2,637	2,660	563	42	605	3,265
	Portable Crusher/Screening	30-40 t/h	752	21,619	22,371	18,800	2,502	21,302	43,673
	Concrete Mixer	0.5 m ³	594	2,454	3,048	5,400	431	5,831	8,879
	Water Pump	200 l/min	21	262	283	188	6	194	477
	Concrete Vibrator	3.3 HP	9	226	235	73	2	75	310
	Asphalt Sprayer	850 ltr.	113	774	887	1,019	144	1,163	2,050

4.2 Unit Construction Cost by Work Type

4.2.1 All Works Except Bridges

The unit construction costs by work type, excluding bridge construction costs, have been estimated using the combination of equipment described in Clause 3.4 and the unit prices already listed. The results are summarized in Table 4-2-1.

Table 4-2-1 UNIT COST BY WORK TYPE EXCEPT BRIDGE WORK

PROV : NUSA TENGGARA TIMUR		KAB : NGADA		
(Rp)				
ITEM	UNIT	LOCAL	FOREIGN	TOTAL
Site Clearance in Light Bush	m ²	153	91	244
Subgrade Preparation	m ²	19	11	30
Normal Fill	m ³	1,576	865	2,441
Fill in Swamp	m ³	2,325	1,054	3,379
Normal Excavation to Spoil	m ³	926	523	1,449
Sub Base Course	m ³	2,984	1,350	4,334
Base Course	m ³	4,100	2,303	6,403
Shoulder	m ²	273	146	419
Asphalt Patching	m ²	2,938	1,514	4,452
Surface Dressing (Single)	m ²	843	766	1,609
Surface Dressing (Double)	m ²	1,001	1,207	2,208
Earth Drain	m	629	119	748
Earth Drain in Swamp (by machine)	m ³	1,065	474	1,539
Pipe Culvert Ø80cm	m	36,892	76,576	113,468
Masonry Culvert (80x80cm)	m	47,364	53,860	101,224
Retaining Wall and Wing Wall (Tiebar)	m ²	15,772	246	16,018
Retaining Wall and Wing Wall (Masonry)	m ³	32,773	12,077	44,850
Gabion Protection	m ³	11,004	121	11,125
Manual routine maintenance of road	Km	96,920	7,260	104,180
Routine maintenance of earth road	Km	85,342	37,948	123,290
Routine maintenance of gravel road	Km	176,065	88,186	264,251
Routine maintenance of asphalt road	Km	293,800	151,400	445,200

4.2.2 Bridges

The unit construction costs by bridge type including the cost of demolition of existing bridges are shown in Table 4-2-2.

Table 4-2-2

BRIDGE COST

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(Rp)				
ITEM	UNIT	LOCAL	FOREIGN	TOTAL
Superstructure (Timber; Span 3m; IOT)	m2	52,702	2,727	55,429
Superstructure (Timber; Span 5m; IOT)	m2	58,376	3,012	61,388
Superstructure (Timber; Span 8m; IOT)	m2	77,325	3,961	81,286
Superstructure (Timber; Span 3m; BH50)	m2	65,349	3,373	68,722
Superstructure (Timber; Span 5m; BH50)	m2	71,346	3,658	75,004
Superstructure (Timber; Span 8m; BH50)	m2	90,487	4,632	95,119
Superstructure (Concrete; Span 3m; BH50)	m2	52,924	171,810	224,734
Superstructure (Concrete; Span 5m; BH50)	m2	53,980	192,600	246,580
Superstructure (Concrete; Span 8m; BH50)	m2	55,318	210,151	265,469
Superstructure (Concrete; Span 10m; BH50)	m2	60,222	239,232	299,454
Superstructure (Concrete; Span 15m; BH50)	m2	64,324	282,524	346,848
Substructure (Pier; for Timber; IOT)	NO	458,897	25,168	484,065
Substructure (Abut; for Timber; IOT)	NO	1,200,388	128,063	1,328,451
Substructure (Pier; for Timber; BH50)	NO	674,875	37,224	712,099
Substructure (Abut; for Timber; BH50)	NO	1,362,835	140,846	1,503,681
Substructure (Pier; for Concrete; BH50)	NO	1,393,463	487,788	1,881,251
Substructure (Abut; for Concrete; BH50)	NO	2,948,676	1,017,596	3,966,272
Demolition of Bridge (Timber->Timber)	m2	14,316	1,106	15,422
Demolition of Bridge (Timber->Concrete)	m2	14,316	1,106	15,422
Demolition of Bridge (Concrete)	m2	73,686	121,003	194,689
Maintenance of Timber Bridge (New)	m2	9,334	954	10,288
Maintenance of Concrete Bridge (New)	m2	1,822	4,303	6,125
Maintenance of Timber Bridge (Exist)	m2	8,203	2,322	10,525
Maintenance of Concrete Bridge (Exist)	m2	3,900	2,705	6,605

5.1 Preliminary Screening

The road links to be improved should be effective for development of the Project Area. The road links where improvements were assumed to be inefficient for development of the Project Area were generally screened out using the following cut-off criteria.

- (1) Very short roads, less than 2 Km long, which have no connection with the trunk road network.
- (2) Roads not connected to the network at any point
- (3) Unpreferred roads, due to poor suitability for transportation compared to other existing alternative roads serving the same purpose.
- (4) Road in good condition according to the Bina Marga road inventory which lists improvement projects carried out in the last two or three years
- (5) Roads with asphalt surface in good condition
- (6) Urban roads, except those forming part of a longer route
- (7) Roads serving single large organizations rather than the general public
- (8) Roads with no inventory data
- (9) Kabupaten roads also assigned as provincial roads

The road links to be screened out in Kabupaten Ngada are shown in Table 5-1-1.

Table 5-1-1 ROAD LINKS TO BE SCREENED OUT

KABUPATEN : NGADA

CRITERIA NO	ROAD LINK NO
-	-

5.2 Evaluation

5.2.1 Primary Analysis

The Kabupaten roads were classified by using the future traffic volume on the road links in 1998. The primary analysis of the IRR was carried out using the construction and maintenance costs. Road links where IRRs were more than 10% were defined as feasible links.

Results of primary analysis are shown in Table 5-2-1.

5.2.2 Secondary Analysis

From the infeasible road links evaluated by the primary analysis, road links where the IRRs were between 1% and 10%, i.e. road links which could become feasible if down graded by one rank, in classification were down graded and the costs re-estimated. Using these costs, a secondary analysis of IRR was carried out. Road links where these IRRs were then more than 10% were also defined as feasible links. This reflected that even though the road classification was rather low the road link should be improved.

Results of secondary analysis are shown in Table 5-2-2.

5.2.3 Ranking of Feasible Road Links

From the results of the primary and secondary analysis, road links where the IRRs were more than 10% were selected and their NPVs and B/Cs were estimated. The ranking of feasible road links from the economic evaluation are decided in the order of the NPVs, i.e. the larger the NPV the higher the road link priority as shown in Table 5-2-3.

Table 5-2-1

RESULTS OF PRIMARY ANALYSIS

PROVINCE : NUSA TENGGARA TIMUR KABUPATEN : NGADA

LINK NO	LENGTH	CLASS	IRR (%)	REMARK
35	7 Km	IIIB-1	45.671	VOC
32	25 Km	IIIB-2	33.841	Surplus
16	15 Km	IIIB-1	31.795	VOC
22	25 Km	IIIB-2	31.572	Surplus
30	25 Km	IIIB-2	30.899	Surplus
24	20 Km	IIIB-2	29.825	Surplus
14	47 Km	IIIB-1	27.453	Surplus
1	5 Km	IIIB-1	26.673	VOC
13	25 Km	IIIB-1	22.064	Surplus
2	16 Km	IIIB-2	20.761	VOC
49	9 Km	IIIB-2	19.430	Surplus
20	20 Km	IIIB-2	17.676	Surplus
26	15 Km	IIIB-2	15.853	Surplus
5	18 Km	IIIB-2	13.208	Surplus
37	12 Km	IIIB-2	12.661	Surplus
15	41 Km	IIIB-1	10.828	Surplus
36	12 Km	IIIB-2	9.875	Surplus
41	56 Km	IIIB-1	9.850	Surplus
45	18 Km	IIIB-2	9.632	Surplus
12	28 Km	IIIB-2	5.831	Surplus
31	10 Km	IIIB-2	5.621	Surplus
9	20 Km	IIIB-2	4.829	Surplus
23	10 Km	IIIC	0.078	Surplus
3	16 Km	IIIC	0.078	Surplus
25	16 Km	IIIB-2	0.078	Surplus
6	8 Km	IIIC	0.078	Surplus
27	6 Km	IIIC	0.078	Surplus
28	15 Km	IIIB-2	0.078	Surplus
29	38 Km	IIIC	0.078	Surplus
7	20 Km	IIIB-2	0.078	Surplus
8	43 Km	IIIB-1	0.078	Surplus
4	7 Km	IIIB-1	0.078	VOC
33	4 Km	IIIC	0.078	Surplus
34	7 Km	IIIC	0.078	Surplus
17	13 Km	IIIC	0.078	Surplus
18	22 Km	IIIC	0.078	Surplus
19	50 Km	IIIC	0.078	Surplus
38	9 Km	IIIC	0.078	Surplus
39	15 Km	IIIC	0.078	Surplus
40	4 Km	IIIC	0.078	Surplus
10	34 Km	IIIC	0.078	Surplus
42	12 Km	IIIC	0.078	Surplus
43	8 Km	IIIC	0.078	Surplus
44	6 Km	IIIC	0.078	Surplus
21	8 Km	IIIB-2	0.078	Surplus
46	7 Km	IIIC	0.078	Surplus
47	30 Km	IIIC	0.078	Surplus
48	18 Km	IIIB-2	0.078	Surplus
11	34 Km	IIIC	0.078	Surplus
50	8 Km	IIIC	0.078	Surplus

Table 5-2-2

RESULTS OF SECONDARY ANALYSIS

PROVINCE : NUSA TENGGARA TIMUR KABUPATEN : NGADA

LINK NO	LENGTH	CLASS	IRR (%)	REMARK
45	18 Km	IIIC	14.854	Surplus
36	17 Km	IIIC	13.010	Surplus
41	56 Km	IIIB-2	10.589	Surplus
31	10 Km	IIIC	7.851	Surplus
12	28 Km	IIIC	7.293	Surplus
9	20 Km	IIIC	6.707	Surplus

Table 5-2-3

RANKING OF FEASIBILITY ROAD LINKS

PROVINCE : NUSA TENGGARA TIMUR KABUPATEN : NGADA						
LINK NO	LENGTH	CLASS	NPV (1000Rp)	B/C	IRR (%)	REMARK
14	47 Km	IIIB-1	815683	1.887	27.453	Surplus
13	25 Km	IIIB-1	413233	1.614	22.064	Surplus
16	15 Km	IIIB-1	383175	2.079	31.795	VOC
22	25 Km	IIIB-2	352809	2.132	31.572	Surplus
32	25 Km	IIIB-2	351508	2.218	33.841	Surplus
30	25 Km	IIIB-2	317019	2.066	30.899	Surplus
35	7 Km	IIIB-1	258111	2.870	45.671	VOC
24	20 Km	IIIB-2	214032	1.978	29.825	Surplus
2	16 Km	IIIB-2	126991	1.497	20.761	VOC
20	20 Km	IIIB-2	112110	1.369	17.676	Surplus
1	5 Km	IIIB-1	91882	1.818	26.673	VOC
41	56 Km	IIIB-2	76439	1.028	10.580	Surplus
15	41 Km	IIIB-1	68282	1.038	10.828	Surplus
49	9 Km	IIIB-2	56273	1.453	19.430	Surplus
26	15 Km	IIIB-2	44518	1.260	15.853	Surplus
45	18 Km	IIIC	38413	1.212	14.854	Surplus
5	18 Km	IIIB-2	23406	1.129	13.208	Surplus
37	12 Km	IIIB-2	17095	1.117	12.661	Surplus
36	12 Km	IIIC	16039	1.128	13.010	Surplus
SUM	411 Km		3777018			

Chapter 6 IMPLEMENTATION PROGRAMME

6.1 Implementation Schedule

6.1.1 Project Cost

The total Project Cost for the Kabupaten is composed of the cost of construction and maintenance, supplementation as described later, and workshop, laboratory and survey equipment. The total Project Cost for the Kabupaten is summarized in Table 6-1-1.

Table 6-1-1 TOTAL PROJECT COST (1)

KABUPATEN: Ngada

(Rp $\times 10^6$)

COST	FOREIGN CURRENCY	LOCAL CURRENCY	TOTAL
CONSTRUCTION	891	1,564	2,455
MAINTENANCE	127	378	505
SUPPLEMENTATION	524	-	524
WORKSHOP EQUIPMENT & TOOLS	28	-	28
LABORATORY EQUIPMENT	12	-	12
SURVEY EQUIPMENT	5	-	5
TOTAL	1,587	1,942	3,529

The total Project Cost can be divided into costs as shown in Table 6-1-2.

Table 6-1-2 TOTAL PROJECT COST (2)

(Rp $\times 10^6$)

COST	FOREIGN CURRENCY	LOCAL CURRENCY	TOTAL
CIVIL WORK	455	1,925	2,380
CONSTRUCTION & MAINTENANCE EQUIPMENT	1,019	-	1,019
SPARE PARTS	68	17	85
WORKSHOP/LABORATORY/SURVEY EQUIPMENT	45	-	45
TOTAL	1,587	1,942	3,529

The cost for civil work is composed of the cost of labour and materials, operation cost excluding spare parts, indirect cost and transportation cost of equipment, and ownership cost for existing equipment.

6.1.2 Proposed Road Links

(1) Road Link to be Improved

The road links to be improved were generally selected taking into consideration the following criteria:

- (1) Feasible road links
 - Feasible road links from the primary evaluation
 - Feasible road links from the secondary evaluation
- (2) Road links selected from the engineering points of view
- (3) Road links selected because of basic human needs.

The road links finally proposed to be improved in the Kabupaten are the 9 links with the total length of 191 km which is 20% of the 937 km total length of Kabupaten roads studied. The proposed road links are shown in Table 6-1-3.

Table 6-1-3 ROAD LINKS TO BE IMPROVED

KABUPATEN : NGADA

REASON FOR SELECTION	ROAD LINK NO
Feasible	
- Primary	2,13,14,20,24,26,30,
- Secondary	-
Engineering Point of View	4,25
Basic Human Needs	-

There are so many feasible road links in the Kabupaten that some road links are not selected to be improved. Among feasible road links following road links are proposed to be improved:

- Road links which form the local road network; and
- Road links which are effective in providing more effective development from road improvement.

Since Road Link No 4 is a trunk road which connects two provincial roads, this road link is selected from the engineering points of view.

Since Road Link No 25 is a key road link which is located at the strategic point to complete the local road network together with a feasible road link, this road link is also selected.

The order of proceeding with the improvement of the proposed road links are decided as shown in Table 6-1-4.

Table 6-1-4 ROAD LINKS TO BE IMPROVED BY YEAR

PROV : NUSA TENGGARA TIMUR KAB : NGADA

YEAR	LINK NO	() : rate
1988	14	(30%)
1989	13, 14, 25	(40%), (30%),
1990	13, 14	(40%), (40%)
1991	2, 4, 13, 24, 30	(20%), (40%),
1992	20, 26, 30	(60%)


KAB. NGADA

CONSTRUCTION PROGRAMME

ROAD LINK NUMBER	FISCAL YEAR				
	1986/87	1987/88	1988/89	1989/90	1990/91
14	226				
13		505			
24,23					
15,14			337		
02,04					
15,24,20				694	
20					
28,30					331
TOTAL COST (Rp.)	226	505	337	694	331




LOCATION MAP



LEGEND :

- KABUPATEN CAPITAL
- KECAMATAN CAPITAL
- OTHER CITY
- LINK NUMBER
- PROVINCIAL BOUNDARY
- KABUPATEN BOUNDARY
- KECAMATAN BOUNDARY
- NATIONAL ROAD
- PROVINCIAL ROAD
- KABUPATEN ROAD
- VILLAGE ROAD
- RIVER



THE FEASIBILITY STUDY OF THE LOCAL ROAD DEVELOPMENT IN THE REPUBLIC OF INDONESIA

TITLE : CONSTRUCTION PROGRAMME

SOURCE: DIREKTORAT JENDERAL CIPTA KARYA	SCALE: AS SHOWN	PROVINCE NUSATENGGA TIMUR KABUPATEN NGADA
---	--------------------	--

(2) Road Links to Be Maintained

It is desirable that all Kabupaten roads are maintained. However, because of the limited budget it is inevitable that some road links in the Kabupatens will be left without maintenance for the time being. The budget should be used for those which are effective in producing more useful development of the Kabupaten through the road development project. The road links to be maintained are finally proposed as shown in Table 6-1-5.

Table 6-1-5

ROAD LINKS TO BE MAINTAINED

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(1000Rp)

LINK NO	LENGTH (Km)	RA (X)	SD (X)	RU (X)	RB (X)	ASPHAL (Km)	GRAVEL (Km)	EARTH (Km)	TN NO	AREA (m2)	RC NO	AREA (m2)	BRIDGE COST	LOCAL COST	FOREIGN COST	TOTAL COST
1	5	0.0	24.0	76.0	0.0	0	0	5	0	0.00	0	0.00	0	911	226	1,137
3	16	45.6	18.1	36.3	0.0	0	12	4	0	0.00	1	20.00	132	4,083	1,380	5,463
4	7	80.0	13.6	6.4	0.0	1	6	0	0	0.00	3	188.00	1,242	2,762	1,240	4,002
5	18	5.6	53.1	31.9	9.4	0	15	3	0	0.00	0	0.00	0	4,642	1,567	6,209
7	20	55.8	11.0	33.3	0.0	0	20	0	1	28.00	12	301.50	2,286	6,865	2,789	9,654
8	43	81.8	12.2	5.9	0.0	0	42	1	0	0.00	1	28.00	185	11,757	4,130	15,887
9	20	41.0	41.5	12.0	5.5	0	1	19	0	0.00	0	0.00	0	3,736	954	4,690
10	34	35.9	38.1	19.3	6.8	0	18	16	0	0.00	0	0.00	0	7,830	2,441	10,271
12	28	0.0	63.6	36.4	0.0	0	28	0	0	0.00	4	98.00	647	8,026	2,938	10,964
14	47	15.5	29.7	46.5	8.3	0	0	47	0	0.00	0	0.00	0	8,566	2,125	10,691
20	20	3.3	32.0	54.8	10.0	0	0	20	0	0.00	0	0.00	0	3,645	904	4,549
25	16	70.6	27.5	1.9	0.0	0	16	0	0	0.00	3	33.50	221	4,498	1,610	6,116
27	6	0.0	65.0	35.0	0.0	0	1	3	0	0.00	0	0.00	0	1,184	321	1,505
33	4	0.0	86.0	14.0	0.0	0	0	4	0	0.00	0	0.00	0	729	181	910
43	8	31.3	20.0	36.4	12.4	0	1	7	0	0.00	0	0.00	0	1,549	412	1,961
46	7	20.7	18.6	50.7	10.0	0	0	7	0	0.00	0	0.00	0	1,276	316	1,592
48	18	0.0	5.6	78.3	16.1	0	0	18	0	0.00	0	0.00	0	3,281	814	4,095
49	9	34.4	11.7	30.6	23.3	0	0	9	0	0.00	0	0.00	0	1,640	407	2,047
SUM	326					1	160	165	1	28.00	24	669.00	4,713	76,980	24,763	101,743

6.1.3 Annual Construction and Maintenance Cost

The annual allocation of the total construction and maintenance cost in the five years programme for Kabupaten Ngada is finally recommended as shown in Tables 6-1-6 (1), (2) and (3) for the construction, maintenance and total respectively.

The proposed construction cost is Rp 2,455 x 10⁶ and maintenance cost is Rp 505 x 10⁶ which is approximately 17% of the total expenditure.

Table 6-1-6 (1) CONSTRUCTION AND MAINTENANCE COST
(CONSTRUCTION)

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(UNIT : 1000Rp)

ITEM	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >	
LOCAL CURRENCY :	141,062	304,066	322,250	426,932	367,979	1,562,297	163.6%
Ownership Cost	2,097	4,924	4,864	7,835	7,897	27,417	(1.8%)
Operation Cost	55,196	129,204	127,465	198,575	201,440	711,880	(45.6%)
Material Cost	45,778	86,887	101,140	86,573	39,136	359,514	(23.0%)
Labour Cost	19,592	43,390	46,755	78,262	71,709	259,708	(16.6%)
Contingency	18,399	39,661	42,034	55,687	47,997	203,778	(13.0%)
FOREIGN CURRENCY :	85,446	201,052	213,661	228,347	164,169	892,675	(36.4%)
Ownership Cost	30,076	71,832	69,810	110,794	109,662	392,174	(43.9%)
Operation Cost	4,135	9,878	9,501	15,691	15,732	54,937	(6.2%)
Material Cost	40,090	93,118	106,481	72,078	17,362	329,129	(36.9%)
Labour Cost	0	0	0	0	0	0	(0.0%)
Contingency	11,145	26,224	27,869	29,784	21,413	116,435	(13.0%)
TOTAL COST :	226,509	505,118	535,910	655,279	532,149	2,454,973	
Ownership Cost	32,173	76,756	74,674	118,629	117,359	419,591	(17.1%)
Operation Cost	59,331	139,082	136,966	214,266	217,172	766,817	(31.2%)
Material Cost	85,868	180,005	207,621	158,651	56,498	688,643	(28.1%)
Labour Cost	19,592	43,390	46,755	78,262	71,709	259,708	(10.6%)
Contingency	29,545	65,885	69,902	85,471	67,411	320,214	(13.0%)

(Contingency : 15%)

Table 6-1-6 (2)

CONSTRUCTION AND MAINTENANCE COST
(MAINTENANCE)

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(UNIT : 1000Rp)

I T E M	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >	
LOCAL CURRENCY :	37,830	73,429	75,245	85,369	106,459	378,332	(74.9%)
Ownership Cost	512	983	1,017	1,329	1,708	5,549	(1.5%)
Operation Cost	23,263	45,086	46,297	50,703	61,972	227,321	(60.1%)
Material Cost	547	1,051	1,096	2,004	4,112	8,810	(2.3%)
Labour Cost	13,508	26,309	26,835	31,333	38,667	136,652	(36.1%)
FOREIGN CURRENCY :	12,218	23,633	24,336	29,476	37,198	126,861	(25.1%)
Ownership Cost	10,659	20,614	21,220	23,625	29,191	105,317	(83.0%)
Operation Cost	1,271	2,455	2,531	2,835	3,510	12,602	(9.9%)
Material Cost	288	564	577	3,016	4,497	8,942	(7.0%)
Labour Cost	0	0	0	0	0	0	(0.0%)
TOTAL COST :	50,048	97,062	99,581	114,845	143,657	505,193	
Ownership Cost	11,171	21,597	22,245	24,954	30,899	110,866	(21.9%)
Operation Cost	24,534	47,541	48,828	53,538	65,482	239,923	(47.5%)
Material Cost	835	1,615	1,673	5,020	8,609	17,752	(3.5%)
Labour Cost	13,508	26,309	26,835	31,333	38,667	136,652	(27.0%)

Table 6-1-6 (3)

CONSTRUCTION AND MAINTENANCE COST

(TOTAL)

PROV : NUSA TENGGARA TIMUR

KAB : NGADA

(UNIT : 1000Rp)

ITEM	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >	
LOCAL CURRENCY :	178,892	377,495	397,503	512,301	474,438	1,940,629	(65.6%)
Ownership Cost	2,609	5,907	5,881	9,164	9,405	32,966	(1.7%)
Operation Cost	78,459	174,290	173,762	249,278	263,412	939,201	(48.4%)
Material Cost	46,325	87,938	102,236	88,577	43,240	368,324	(19.0%)
Labour Cost	33,100	69,699	73,590	109,595	110,376	396,360	(20.4%)
Contingency	18,399	39,661	42,034	55,687	47,997	203,778	(10.5%)
FOREIGN CURRENCY :	97,664	224,685	237,997	257,823	201,367	1,019,536	(34.4%)
Ownership Cost	40,735	92,446	91,038	134,419	138,853	497,491	(48.8%)
Operation Cost	5,406	12,333	12,032	18,526	19,242	67,539	(6.6%)
Material Cost	40,378	93,682	107,058	75,094	21,859	338,071	(33.2%)
Labour Cost	0	0	0	0	0	0	(0.0%)
Contingency	11,145	26,224	27,869	29,784	21,413	116,435	(11.4%)
TOTAL COST :	276,557	602,180	635,499	770,124	675,806	2,960,166	
Ownership Cost	43,344	98,353	96,919	143,583	148,258	530,457	(17.9%)
Operation Cost	83,865	186,623	185,794	267,804	282,654	1,006,740	(34.0%)
Material Cost	86,703	181,620	209,294	163,671	65,107	706,395	(23.9%)
Labour Cost	33,100	69,699	73,590	109,595	110,376	396,360	(13.4%)
Contingency	29,545	65,885	69,902	85,471	69,411	320,214	(10.8%)

< Contingency : 15% >

6.1.4 Construction and Maintenance Equipment Cost

(1) Required Number of Equipment

The required numbers of construction equipment for Kabupaten Ngada are estimated from the annual proposed construction quantities as shown in Table 6-1-7.

The proposed numbers of equipment to be purchased are finally decided considering the following number of existing equipment in the Kabupaten which are available for the Project.

- 1-Asphalt Sprayer

The proposed numbers of maintenance equipment have been decided as shown below from the proposed annual maintenance volume taking into account the capacity of the proposed maintenance gangs.

a. Equipment for Road Maintenance

- 1-Motor Grader 75 HP
- 1-Tire Roller 8-15 Ton
- 1-Dump Truck 3 Ton
- 1-Hand Guided Vibratory Roller 1000 Kg
- 1-Flat Bed Truck 3 Ton

b. Equipment for Bridge Maintenance

- 1-Flat Bed Truck with Crane 3 Ton

(2) Equipment Cost

The proposed construction and maintenance equipment and their purchase costs are shown in Table 6-1-8. In the Project the supplementation cost or equipment cost supplemented is the difference between the purchase cost for newly supplied equipment and the depreciated value.

This comes about because full depreciation of the supplied equipment would not be completed within the Project Period of 5 years.

Table 6-1-7

REQUIRED NUMBER OF EQUIPMENT

PROV : NUSA TENGGARA TIMUR KAB : NGADA

EQUIPMENT NAME	WORKABLE	EXISTING	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >
Bulldozer/Ripper	250	0	0.11	0.35	0.30	0.75	0.69
Swamp Bulldozer	250	0	0.01	0.02	0.03	0.01	0.08
Motor Grader	250	0	0.46	0.98	0.93	1.73	1.59
Hand-guide Vib. Roller	250	0	0.09	0.46	0.49	1.00	0.54
Tire Roller	250	0	0.32	0.54	0.64	0.12	0.00
Vibratory Roller (D&I)	250	0	0.37	0.76	0.77	1.46	1.38
Hydraulic Excavator; Wheel	250	0	0.04	0.40	0.42	0.18	1.51
Wheel Loader	250	0	0.56	1.35	1.27	2.25	2.04
Water Tank Truck	250	0	0.27	0.53	0.55	0.99	0.92
Dump Truck	250	0	5.29	11.85	11.86	19.95	20.12
Flat Bed Truck with Crane	250	0	0.07	0.36	0.39	0.91	0.37
Flat Bed Truck	250	0	0.41	0.80	0.93	0.48	0.18
Portable Crusher/Screening	250	1	0.13	0.32	0.27	0.35	0.28
Concrete Mixer	250	0	0.02	0.12	0.12	0.21	0.10
Water Pump	250	0	0.02	0.09	0.10	0.17	0.08
Concrete Vibrator	250	0	0.01	0.05	0.05	0.10	0.03
Asphalt Sprayer	250	1	0.32	0.54	0.64	0.12	0.00

NOTE WORKABLE : workable days in a year
EXISTING : number of existing equipment

Table 6-1-8

EQUIPMENT PURCHASE COST

PROV : NUSA TENGGARA TIMUR

KAB : NGADA

(1000 Rp)

EQUIPMENT NAME	CLASS	CIF (JAKARTA)	PURCHASE NO.	PURCHASE COST
Bulldozer	90 HP	49,150	-	-
Bulldozer/Ripper	90 HP	53,000	1	53,000
Swamp Bulldozer	90 HP	52,850	-	-
Swamp Bulldozer	65 HP	40,500	-	-
Motor Grader	75 HP	47,800	2	95,600
Road Stabilizer	W=1850 mm	85,950	-	-
Hand-guide Vib. Roller	1000 Kg	8,500	1	8,500
Tire Roller	8-15 ton	31,070	1	31,070
Vibratory Roller (D&T)	4 ton	29,000	1	29,000
Vibratory Roller	4 ton	29,000	-	-
Rough Terrain Crane	10 ton	100,400	-	-
Hydraulic Excavator; Wheel	0.3 m ³	41,100	1	41,100
Wheel Loader	1.2 m ³	70,200	3	210,600
Water Tank Truck	4000 ltr.	12,750	1	12,750
Dump Truck	3.0 ton	14,700	17	249,900
Dump Loader Truck	12 ton	56,300	-	-
Flat Bed Truck with Crane	3.0 ton	25,190	1	25,190
Flat Bed Truck	3.0 ton	11,275	2	22,550
Portable Crusher/Screening	30-40 t/h	188,000	1	188,000
Concrete Mixer	0.5 m ³	18,000	1	18,000
Water Pump	200 l/min	630	1	630
Concrete Vibrator	3.3 HP	740	1	740
Asphalt Sprayer	850 ltr.	10,200	-	-
Service Car	3 ton	11,600	1	11,600
4 Wheel Drive Vehicle	70 HP	17,500	1	17,500
Motorcycle	100 cc	1,100	3	3,300
PURCHASE COST TOTAL				1,019,030
OWNERSHIP COST (FOREIGN)				495,047
EQUIPMENT COST SUPPLEMENTED				523,983

NOTE : OWNERSHIP COST (FOREIGN) for Existing Equipment

Asphalt Sprayer

2,444

6.1.5 Other Costs

Cost other items includes the costs of workshop equipment and tools, laboratory test equipment and survey equipment which are recommended in Sub-Clause 3.5. These total costs are summarized in Table 6-1-1.

6.1.6 Quantities by Work Type

The annual construction and maintenance quantities for all proposed road links are shown in Table 6-1-9.

Table 6-1-9

CONSTRUCTION QUANTITIES FOR ALL

PROPOSED LINKS

PROV : NUSA TENGGARA TIMUR KAE : NGADA

ITEM	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
Site Clearance in Light Bush	m2	0.00	16000.00	16000.00	48500.00	52500.00	133000.00
Subgrade Preparation	m2	84600.00	144600.00	172800.00	314000.00	310000.00	1026000.00
Normal Fill	m3	0.00	0.00	0.00	2670.00	1590.00	4260.00
Fill in Swamp	m3	104.40	873.92	908.72	384.76	3206.30	5478.10
Normal Excavation to Spoil	m3	1598.10	4356.10	4888.80	8938.60	7358.40	27140.00
Sub Base Course	m3	7896.00	13696.00	16128.00	29428.50	26600.00	93748.50
Base Course	m3	3948.00	10588.00	8064.00	13880.00	11400.00	47880.00
Shoulder	m2	28200.00	80200.00	57600.00	124000.00	120000.00	410000.00
Asphalt Patching	m2	0.00	0.00	0.00	33.00	0.00	33.00
Surface Dressing (Single)	m2	56400.00	96400.00	115200.00	20000.00	0.00	288000.00
Surface Dressing (Double)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Earth Drain	m	22110.00	33910.00	41280.00	61100.00	80700.00	239100.00
Earth Drain in Swamp (by machine)	m3	720.00	7920.00	8160.00	3600.00	30000.00	50400.00
Pipe Culvert 80x80cm	m	3.00	363.00	364.00	790.60	213.40	1734.00
Masonry Culvert (80x80cm)	m	25.20	25.20	33.60	0.00	18.00	102.00
Retaining Wall and Wing Wall (Timber)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Retaining Wall and Wing Wall (Masonry)	m3	12.00	146.40	150.40	274.56	165.54	748.90
Gabion Protection	m3	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 3m; 10T)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 5m; 10T)	m2	0.00	30.40	30.40	100.00	187.20	348.00
Superstructure (Timber; Span 8m; 10T)	m2	66.00	96.40	118.40	436.80	46.40	764.00
Superstructure (Timber; Span 3m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 5m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Timber; Span 8m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 3m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 5m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 8m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 10m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Superstructure (Concrete; Span 15m; BMS0)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Pier; for Timber; 10T)	NO	1.50	2.70	3.20	10.40	4.20	22.00
Substructure (Abut; for Timber; 10T)	NO	1.80	5.00	5.60	19.60	14.00	46.00
Substructure (Pier; for Timber; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Abut; for Timber; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Pier; for Concrete; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Substructure (Abut; for Concrete; BMS0)	NO	0.00	0.00	0.00	0.00	0.00	0.00
Demolition of Bridge (Timber->Timber)	m2	0.00	0.00	0.00	24.00	0.00	24.00
Demolition of Bridge (Timber->Concrete)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Demolition of Bridge (Concrete)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Manual routine maintenance of road	Km	159.48	310.95	316.60	322.50	377.00	1486.53
Routine maintenance of earth road	Km	78.98	157.95	155.60	118.00	108.00	618.53
Routine maintenance of gravel road	Km	80.00	152.00	160.00	157.00	197.00	746.00
Routine maintenance of asphalt road	Km	0.50	1.00	1.00	47.50	72.00	122.00
Maintenance of Timber Bridge (New)	m2	0.00	0.00	0.00	0.00	220.00	220.00
Maintenance of Concrete Bridge (New)	m2	0.00	0.00	0.00	0.00	0.00	0.00
Maintenance of Timber Bridge (Exist)	m2	14.00	28.00	28.00	28.00	28.00	126.00
Maintenance of Concrete Bridge (Exist)	m2	334.50	652.25	669.00	575.00	669.00	2899.75

6.2 Organization and Construction System

6.2.1 Organization

The Bupati as head of the Kabupaten has been authorized by Law No. 13, 1980 as an official responsible for the Local Road Development Project implementation. This means that the DPUK is considered as a responsible agency for the actual execution of the Project.

According to instruction letter dated June 24, 1982 Ref. No. 620/975-/BANGDA, the Project Manager appointed by the Bupati will be responsible for the operation and maintenance of the equipment. Accordingly the Equipment Coordinator appointed from the staff of the Regional Public Works (Kantor Wilayah) by Bina Marga as a coordinator between the Governor and the Bupati will be responsible for delivery, effectual utilization and maintenance of the equipment.

The standard organization of DPUK consists of a minimum of four sections, i.e. Road Section, Housing and City Planning Section, Irrigation Section and Administration Section. For execution of the Project it is strongly recommended that the structural organization of DPUK is established. It will be necessary not only to organize new sections but also to reorganize the current structure through a review of the roles and responsibilities of each inter-related section.

It is recommended that the workshop is newly organized to consist of three sub-sections, i.e. maintenance and repair of equipment, operation and materials, and administration to execute the main tasks described in Clause 3.5.


The sub-section of laboratory would be under the relevant Road Section. The proposed organization is shown in Fig. 6-2-1.

6.2.2 Construction System

For the construction of Kabupaten roads with a ten year effective design life, it has been recommended in Clause 3.4 that the equipment intensive method should be adopted for earth work and pavement work with the exception of surface dressing.

Fig. 6-2-1

PROPOSED ORGANIZATION



⇓ : Equipment delivery flow

▭ : New position/subsection

Current road construction in the Kabupatens is obliged to rely upon the traditional labour intensive method. It is therefore assumed that both the DPUK and the local contractors in the Kabupatens do not have sufficient experience and technique for the equipment intensive method of road construction.

For realization of the Local Road Development Project the GOI has ensured availability of the required human resources of DPUK and intends to conduct training programmes for those human resources as described in Clause 8.3 of the Main Report. This means that the GOI intends the Kabupatens to have the ability to execute the Project by force account (Swakelola).

It should be recognized from the experiences in the first local road project, which was assisted by OECF, ADB and IBRD, that because of their poor construction management and traditional labour intensive methods most of the road construction by local contractors could not be completed within the contract periods. Therefore execution of the road improvement by force account is desirable as recommended from their experience by the consultants for the first local road project.

It is strongly recommended that except for labourers the staff of the force account team should not be hired by the day as it would then not be able to consolidate the foundations for development of self reliability.

However, it will be very difficult to execute all the Projects by force account because of the need for many Kabupaten staff. The GOI has emphasized the need to promote the employment of local weak contractors in order to up-grade their capability in the road project schemes within the Fourth Five-Year Plan (REPELITA)

Taking into consideration the conditions mentioned above it is strongly recommended that the DPUK is obliged to lend some equipment with skilled operators to the local contractors in the Kabupatens for the execution of a part of the road improvement works.

The types of work executed only by force account are recommended as follows:

- Routine maintenance work for the Kabupaten roads
- Laboratory tests
- Production of crushed stone
- Technical service for the equipment

APPENDIX

Appendix A-2 Engineering Data

ROAD LINK DATA

PROVINCE : Nusa Tenggara Timur

KABUPATEN: Ngada

LINK NO.	BEGINNING POINT (DESA NAME)	END POINT (DESA NAME)	LENGTH (KM)	THROUGH THE KEC. NAME & LENGTH		REMARKS
				KEC. NAME	LENGTH (KM)	
01	Bajawa	Ngoranale	5	Kopeta Bajawa	5	12
02	Aimere	Waebela	16	Aimere	16	8
03	Mangulewa	Jerubuu	16	Aimere	15	13
				Mogomangulewa	1	
04	Maumbawa	Mauponggo	7	Mogomangulewa	7	1
05	Raja	Maunori	18	Mauponggo	14	11
				Boawae	4	
06	Nangaroro	Maunura	8	Nangaroro	8	23
07	Rowa	Waepana	20	Mogomangulewa	13	3
				Bajawa	7	
08	Dadiwuwu	Kaburea	43	Aesesa	43	10
09	Danga	Pausolek	20	Riung	4	14
				Aesesa	16	
10	Poma	Mboras	34	Riung	34	5
11	Pausolek	Marotauk	34	Riung	34	15
12	Waepana	Mbazang	28	Bajawa	20	4
				Riung	8	
13	Boawae	Piga	25	Boawae	15	7
				Bajawa	10	
14	Aemali	Danga	47	Boawae	20	
				Aesesa	27	
15	Ndekundenu	Towak	41	Riung	6	16
				Aesesa	35	
16	Riung	Terong	15	Riung	15	
17	Jerebuu	Waebela	13	Aimere	13	18
18	Mataloko	Jerebuu	22	Aimere	17	
				Mogomangulewa	5	
19	Lindi	Tanalain	50	Riung	50	19
20	Rega	Sawu	20	Mauponggo	16	20
				Boawae	4	
21	Maunori	Maunura	8	Mauponggo	3	
				Nangaroro	5	
22	Sawu	Dombe	25	Mauponggo	25	
23	Malanuza	Zepe	10	Mogomangulewa	10	21
24	Maropokot	Aeramo	20	Aesesa	20	

Please note the priority No. in the Remarks of this list for each links No. according to the each Kabupaten's development plan.

ROAD LINK DATA

PROVINCE : Nusa Tenggara Timur

KABUPATEN: Ngada

LINK NO.	BEGINNING POINT (DESA NAME)	END POINT (DESA NAME)	LENGTH (KM)	THROUGH THE KEC. NAME & LENGTH		REMARKS
				KEC. NAME	LENGTH (KM)	
25	Nila	Maropokot	16	Aesesa	16	2
26	Surisina	Tarawaja	15	Bajawa	7	6
				Kopeta Bajawa	8	
27	Watuajaji	Bena	6	Aimere	1	22
				Kopeta Bajawa	5	
28	Dadho	Maukeli	15	Mogomangulewa	15	
29	Waeluja	Waebela	38	Aimere	38	
30	Fataleke	Kaburea	25	Nangaroro	8	
				Aesesa	17	
31	Raterunu	Watuapi	10	Aesesa	10	
32	Boamaso	Anakoli	25	Nangaroro	5	
				Aesesa	20	
33	Bajawa	Ekoheto	4	Kopeta Bajawa	4	24
34	Basiko	Surisina	7	Kopeta Bajawa	7	
35	Wolosambi	Mauwaru	7	Mogomangulewa	7	
36	Bajawa	Radawea	12	Bajawa	5	9
				Kopeta Bajawa	7	
37	Mengeruda	Nagerawe	12	Bajawa	2	
				Boawae	10	
38	Maladhena	Surisina	9	Mogomangulewa	1	25
				Kopeta Bajawa	8	
39	Khuruboko	Mawu	15	Bajawa	15	
40	Wogo	Reko	4	Mogomangulewa	4	
41	Aimere	Ranamoi	56	Aimere	27	
				Bajawa	29	
42	Doka	Utaseko	12	Mogomangulewa	12	
43	Mangulewa	Were	8	Aimere	6	
				Mogomangulewa	2	
44	Sarasedu	Laja	6	Mogomangulewa	6	
45	Mangulewa	Dorarapu	18	Mogomangulewa	18	
46	Boua	Langa	7	Kopeta Bajawa	7	
47	Maronggela	Munting	30	Riung	30	
48	Simp. Jalan Negara	Boamaso	18	Boawae	18	

Please note the priority No. in the Remarks of this list for each links No. according to the each Kabupaten's development plan.





What Kind of Design Criteria has being applied for the new road construction and the improvement for the Kabupaten Road ?

Kriteria Perencanaan yang dipakai pada program penanganan jalan Kabupaten, baik untuk jalan lama maupun pembangunan baru.

Please draw the Typical Cross Section of the Kabupaten Road.

Buat gambar dan penjelasan dari: Typical cross section yang dipakai pada program penanganan jalan selama ini (baik untuk jalan lama, maupun pembangunan baru)

TYPICAL CROSS SECTION.




EXISTING ORGANIZATION IN KABUPATEN

Struktur Organisasi yang ada dari P.U Kabupaten

Please draw the Cart of the Existing Organization in the Kabupaten.

Harap digambar bagan organisasi dari DPUK.



EXISTING STAFF RESOURCES OF BINA MARGA OF PU KABUPATEN

Tenaga Dinas PUK yang ada

PROPINSI: Nusa Tenggara TimurKABUPATEN: Ngada

DESCRIPTION /Uraian	NUMBER / Jumlah	REMARKS Keterangan
CONTROLLING STAFF Staff teknis PUK	_____	_____
DPUK ENGINEER Sarjana Teknik	-	-
ASSISTANT ENGINEER Sarjana Muda Teknik	1	-
TECHNICIAN STAFF Staff Teknik (STM)	8	8
ADMINISTRATION Tenaga Administrasi	9	-
SUPERVISOR Tenaga Pengawas	11	-
WORKING FORCE Tenaga Pelaksana Lapangan	_____	_____
OPERATORS Operators	6	5
DRIVERS Supir	2	-
MECHANICS Mechanic	3	3
TRADESMAN Tukang	-	-
LABOUR Buruh / Pekerja	8	1
OTHERS Lain-lain		
TOTAL / JUMLAH	48	17

Catatan ; Untuk kolom keterangan harap diisi berapa orang yang telah mendapat Training.

LOCATION AND AREA OF DPUK WORKSHOP

E-06

Lokasi Workshop DPUK

PROPINSI : Nusa Tenggara Timur

KABUPATEN: Ngada

LOCATION Lokasi	AREA (m2) Luas	NUMBER Jumlah	REMARKS Keterangan
Ogi	13.000		

PROPINSI: Nusa Tenggara Timur

E-07

KABUPATEN: Ngada

LAND ACQUISITION COST

Daftar harga pembebasan tanah

DESCRIPTION Uraian	UNIT Satuan	RATE (RP) Harga	REMARKS Keterangan
CITY/kota	M2	3,000	
VILLAGE / desa	M2	1,250	
RICE FIELD/sawah	M2	850	
DRY FIELD/ladang	M2	400	
MIX CROPS/panen	M2	400	
FOREST/hutan	M2	200	
SWAMP / rawa	M2	200	
OTHERS / lain-lain	M2	200	

LIST OF EXISTING EQUIPMENT OF LOCAL CONTRACTOR

Name of contractor

NAME OF EQUIPMENT Jenis peralatan	EXISTING CONDITION/ Kondisi Peralatan					REASON OF BAD CONDT TION/Sebab Kerusakan	REQUIRE - MENT / Ke- butuhan peralatan baru
	TYPE/ Tipe	P.Y	NUMBER / Jumlah				
			GOOD Baik	BAD Rusak	TOTAL Jumlah		
Bulldozer							
Motor Grader							
Tyre Roller							
Steel Whell Roller							
Vibration Roller							
Wheel Loader							
Front End Loader and Backhoe							
Mobile Crane							
Concrete Mixer							
Stone Crusher							
Portable Compressor							
Hydraulic Excavator							
Asphalt Paving Machine							
Asphalt Sprayer							
Asphalt Mixing Machine							
Mobile Workshop							
Mechanic Rammer							
Plate Tamper							
Pile Driver							
Leg Drill							
Hand Hammer							
Farm Tractor							
Dump Truck							
Water Tank Truck							
Fuel Tank Truck							
Pick Up							
Jeep							
Motorcycle			28	-	28		
Generator							
Water Pump							
Others							

LIST OF EXISTING EQUIPMENT OF P.U KABUPATEN

NAME OF EQUIPMENT Jenis peralatan	EXISTING CONDITION/ Kondisi Peralatan					REASON OF BAD CONDI TION/Sebab Kerusakan	REQUIRE - MENT / Ke- butuhan peralatan baru
	TYPE/ Tipe	P.Y	NUMBER / Jumlah				
			GOOD Baik	BAD Rusak	TOTAL Jumlah		
Bulldozer							
Motor Grader							
Tyre Roller							
Steel Wheel Roller							
Vibration Roller							
Wheel Loader							
Front End Loader and Backhoe							
Mobile Crane							
Concrete Mixer							
Stone Crusher			1	1	2		
Portable Compressor							
Hydraulic Excavator							
Asphalt Paving Machine							
Asphalt Sprayer			1	-	1		
Asphalt Mixing Machine							
Mobile Workshop							
Mechanic Rammer							
Plate Tamper							
Pile Driver							
Leg Drill							
Hand Hammer							
Farm Tractor							
Dump Truck							
Water Tank Truck							
Fuel Tank Truck							
Pick Up							
Jeep			1	-	1		
Motorcycle			1	-	1		
Generator							
Water Pump							
Others							

PROV : NUSA TENGGARA TIMUR KAB : NBADA

LINK NO : 30 (IIIB-2) LENGTH : 25 Km

UPGRADE : 6.0m road bed, 4.0m road with surface Base Course

(Rp)

ITEM	UNIT	QUANTITY	UNIT COST		COST		TOTAL	
			LOCAL	FOREIGN	LOCAL	FOREIGN		
Site Clearance in Light Bush	m2	0.0	153	91	0	0	0	
Subgrade Preparation	m2	150000.0	19	11	2,850,000	1,650,000	4,500,000	
Normal Fill	m3	1050.0	1,576	865	1,654,800	908,250	2,563,050	
Fill in Swamp	m3	0.0	2,325	1,054	0	0	0	
Normal Excavation to Spoil	m3	4299.0	926	523	3,980,874	2,248,377	6,229,251	
Sub Base Course	m3	14000.0	2,984	1,350	41,776,000	18,900,000	60,676,000	
Base Course	m3	6000.0	4,100	2,303	24,600,000	13,818,000	38,418,000	
Shoulder	m2	50000.0	273	146	13,650,000	7,300,000	20,950,000	
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0	
Surface Dressing (Single)	m2	0.0	843	766	0	0	0	
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0	
Earth Drain	m	40500.0	629	119	25,474,500	4,819,500	30,294,000	
Earth Drain in Swamp (by machine)	m3	0.0	1,065	474	0	0	0	
Pipe Culvert 80cm	m	154.0	36,882	76,576	5,679,828	11,792,704	17,472,532	
Masonry Culvert 180x80cm	m	0.0	47,364	53,860	0	0	0	
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0	
Retaining Wall and Wing Wall (Masonry)	m3	38.4	32,773	12,077	1,258,483	463,756	1,722,239	
Gabion Protection	m3	0.0	11,004	121	0	0	0	
New Bridge (Timber)	SET	1.0	--	--	21,315,586	1,763,374	23,078,960	
New Bridge (Concrete)	SET	1.0	--	--	0	0	0	
					Sub Total	142,240,071	63,663,961	205,904,032
Overhead (15%)						21,336,010	9,549,594	30,885,604
					TOTAL COST	163,576,081	73,213,555	236,789,636

Manual routine maintenance of road	Km	25.0	96,920	7,260	2,423,000	181,500	2,604,500
Routine maintenance of gravel road	Km	25.0	176,065	88,186	4,401,625	2,204,650	6,606,275
			Sub Total		6,824,625	2,386,150	9,210,775
Maintenance of Timber Bridge (New)	m2	136.0	9,334	954	1,269,424	129,744	1,399,168
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement Unit Cost (Rp/Km)	:	8,409,953
Timber Bridge Unit Cost (Rp/m2)	:	195,153
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	30,338,000
Maintenance Rate without Bridge (X)	:	4.38
New Bridge Cost Rate (X)	:	11.21

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 26 (111B-2) LENGTH : 15 Km

UPGRADE : 6.0m road bed, 4.0m road with surface Base Course

(Rp)

ITEM	UNIT	QUANTITY	UNIT COST		COST		TOTAL	
			LOCAL	FOREIGN	LOCAL	FOREIGN		
Site Clearance in Light Bush	m2	0.0	153	91	0	0	0	
Subgrade Preparation	m2	90000.0	19	11	1,710,000	990,000	2,700,000	
Normal Fill	m3	600.0	1,576	865	945,600	519,000	1,464,600	
Fill in Swamp	m3	0.0	2,325	1,054	0	0	0	
Normal Excavation to Spoil	m3	2316.0	926	523	2,144,616	1,211,268	3,355,884	
Sub Base Course	m3	8400.0	2,984	1,350	25,065,600	11,340,000	36,405,600	
Base Course	m3	3600.0	4,100	2,303	14,760,000	8,290,800	23,050,800	
Shoulder	m2	30000.0	273	146	8,190,000	4,380,000	12,570,000	
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0	
Surface Dressing (Single)	m2	0.0	843	766	0	0	0	
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0	
Earth Drain	m	20400.0	629	119	12,831,600	2,427,600	15,259,200	
Earth Drain in Swamp (by machine)	m3	0.0	1,065	474	0	0	0	
Pipe Culvert D80cm	m	84.0	36,882	76,576	3,098,088	6,432,384	9,530,472	
Masonry Culvert (80x80cm)	m	0.0	47,364	53,860	0	0	0	
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0	
Retaining Wall and Wing Wall (Masonry)	m3	16.0	32,773	12,077	524,368	193,232	717,600	
Gabion Protection	m3	0.0	11,004	121	0	0	0	
New Bridge (Timber)	SET	1.0	--	--	10,069,889	784,652	10,854,541	
New Bridge (Concrete)	SET	1.0	--	--	0	0	0	
					Sub Total			
						79,339,761	36,568,936	115,908,697
Overhead (15%)						11,900,964	5,485,340	17,386,304
					TOTAL COST	91,240,725	42,054,276	133,295,001

Manual routine maintenance of road	Km	15.0	96,920	7,260	1,453,800	108,900	1,562,700
Routine maintenance of gravel road	Km	15.0	176,065	88,186	2,640,975	1,322,790	3,963,765
			Sub Total		4,094,775	1,431,690	5,526,465
Maintenance of Timber Bridge (New)	m2	72.0	9,334	954	672,048	68,688	740,736
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	24.0	8,203	2,322	196,872	55,728	252,600
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement Unit Cost (Rp/Km)	:	8,054,152
Timber Bridge Unit Cost (Rp/m2)	:	173,371
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	18,202,800
Maintenance Rate without Bridge (%)	:	4.57
New Bridge Cost Rate (%)	:	9.36

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 25 (IIIC) LENGTH : 16 Km

UPGRADE : 6.0m road bed, 4.0m road with surface Subbase Course (Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		TOTAL	
			LOCAL	FOREIGN	LOCAL	FOREIGN		
Site Clearance in Light Bush	m2	0.0	153	91	0	0	0	
Subgrade Preparation	m2	0.0	19	11	0	0	0	
Normal Fill	m3	0.0	1,576	865	0	0	0	
Fill in Swamp	m3	0.0	2,325	1,054	0	0	0	
Normal Excavation to Spoil	m3	0.0	926	523	0	0	0	
Sub Base Course	m3	200.0	2,984	1,350	596,800	270,000	866,800	
Base Course	m3	3840.0	4,100	2,303	15,744,000	8,843,520	24,587,520	
Shoulder	m2	32000.0	273	146	8,736,000	4,672,000	13,408,000	
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0	
Surface Dressing (Single)	m2	0.0	843	766	0	0	0	
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0	
Earth Drain	m	0.0	629	119	0	0	0	
Earth Drain in Swamp (by machine)	m3	0.0	1,065	474	0	0	0	
Pipe Culvert 80cm	m	0.0	36,882	76,576	0	0	0	
Masonry Culvert (80x80cm)	m	0.0	47,364	53,860	0	0	0	
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0	
Retaining Wall and Wing Wall (Masonry)	m3	0.0	32,773	12,077	0	0	0	
Babion Protection	m3	0.0	11,004	121	0	0	0	
New Bridge (Timber)	SET	1.0	--	--	0	0	0	
New Bridge (Concrete)	SET	1.0	--	--	0	0	0	
					25,076,800	13,785,520	38,862,320	
Overhead (15%)					3,761,520	2,067,828	5,829,348	
					TOTAL COST	28,838,320	15,853,348	44,691,668

Manual routine maintenance of road	Km	16.0	96,920	7,260	1,550,720	116,160	1,666,880
Routine maintenance of gravel road	Km	16.0	176,065	88,186	2,817,040	1,410,976	4,228,016
			Sub Total		4,367,760	1,527,136	5,894,896
Maintenance of Timber Bridge (New)	m2	0.0	9,334	954	0	0	0
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	33.5	3,900	2,705	130,650	90,617	221,267

Earthwork & Pavement Unit Cost (Rp/Km)	:	2,793,229
Timber Bridge Unit Cost (Rp/m2)	:	
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	346,720
Maintenance Rate without Bridge (%)	:	13.19
New Bridge Cost Rate (%)	:	

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 24 (IIR-2) LENGTH : 20 Km

UPGRADE : 6.0m road bed, 4.0m road with surface Base Course

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		TOTAL	
			LOCAL	FOREIGN	LOCAL	FOREIGN		
Site Clearance in Light Bush	m2	0.0	153	91	0	0	0	
Subgrade Preparation	m2	120000.0	19	11	2,280,000	1,320,000	3,600,000	
Normal Fill	m3	0.0	1,576	865	0	0	0	
Fill in Swamp	m3	0.0	2,325	1,054	0	0	0	
Normal Excavation to Spoil	m3	3080.0	926	523	2,852,080	1,610,840	4,462,920	
Sub. Base Course	m3	11200.0	2,984	1,350	33,420,800	15,120,000	48,540,800	
Base Course	m3	4800.0	4,100	2,303	19,680,000	11,054,400	30,734,400	
Shoulder	m2	40000.0	273	146	10,920,000	5,840,000	16,760,000	
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0	
Surface Dressing (Single)	m2	0.0	843	766	0	0	0	
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0	
Earth Drain	m	26700.0	629	119	16,794,300	3,177,300	19,971,600	
Earth Drain in Swamp (by machine)	m3	0.0	1,065	474	0	0	0	
Pipe Culvert 80cm	m	120.0	36,882	76,576	4,425,840	9,189,120	13,614,960	
Masonry Culvert (80x80cm)	m	0.0	47,364	53,860	0	0	0	
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0	
Retaining Wall and Wing Wall (Masonry)	m3	32.0	32,773	12,077	1,048,736	386,464	1,435,200	
Gabion Protection	m3	0.0	11,004	121	0	0	0	
New Bridge (Timber)	SET	1.0	--	--	9,441,052	749,912	10,190,964	
New Bridge (Concrete)	SET	1.0	--	--	0	0	0	
					Sub Total	100,862,008	48,448,036	149,310,844
Overhead (15%)						15,129,421	7,267,205	22,396,626
					TOTAL COST	115,992,229	55,715,241	171,707,470

Manual routine maintenance of road	Km	20.0	96,920	7,260	1,938,400	145,200	2,083,600
Routine maintenance of gravel road	Km	20.0	176,065	88,186	3,521,300	1,763,720	5,285,020
			Sub Total		5,459,700	1,908,920	7,368,620
Maintenance of Timber Bridge (New)	m2	60.0	9,334	954	560,040	57,240	617,280
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement Unit Cost (Rp/Km)	:	7,999,393
Timber Bridge Unit Cost (Rp/m2)	:	195,327
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	24,270,400
Maintenance Rate without Bridge (%)	:	4.61
New Bridge Cost Rate (%)	:	6.83

PROV : NUSA TENGGARA TIMUR KAB : NUNDA

LINK NO : 20 (IIIB-2) LENGTH : 20 Km

UPGRADE : 4.5m road bed, 3.5m road with surface Base Course

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		TOTAL	
			LOCAL	FOREIGN	LOCAL	FOREIGN		
Site Clearance in Light Bush	m2	52500.0	153	91	8,032,500	4,777,500	12,810,000	
Subgrade Preparation	m2	130000.0	19	11	2,470,000	1,430,000	3,900,000	
Normal Fill	m3	360.0	1,576	865	567,360	311,400	878,760	
Fill in Swamp	m3	3206.3	2,325	1,054	7,454,647	3,379,440	10,834,087	
Normal Excavation to Spoil	m3	2463.0	926	523	2,290,738	1,289,149	3,568,887	
Sub Base Course	m3	9800.0	2,984	1,350	29,243,200	13,230,000	42,473,200	
Base Course	m3	4200.0	4,100	2,303	17,220,000	9,672,600	26,892,600	
Shoulder	m2	60000.0	273	146	16,380,000	8,760,000	25,140,000	
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0	
Surface Dressing (Single)	m2	0.0	843	766	0	0	0	
Surface Dressing (Double)	m2	0.0	1,991	1,207	0	0	0	
Earth Drain	m	36000.0	629	119	22,644,000	4,284,000	26,928,000	
Earth Drain in Swamp (by machine)	m3	30000.0	1,065	474	31,950,000	14,220,000	46,170,000	
Pipe Culvert 80x80cm	m	37.0	36,882	76,576	1,364,634	2,833,312	4,197,946	
Masonry Culvert (80x80cm)	m	18.0	47,364	53,860	852,552	969,480	1,822,032	
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0	
Retaining Wall and Wing Wall (Masonry)	m3	126.5	32,773	12,077	4,145,784	1,527,740	5,673,524	
Gabion Protection	m3	0.0	11,004	121	0	0	0	
New Bridge (Timber)	SET	1.0	--	--	10,389,426	803,548	11,192,974	
New Bridge (Concrete)	SET	1.0	--	--	0	0	0	
					Sub Total			
						154,994,841	67,487,169	222,482,010
Overhead (15%)						23,249,226	10,123,075	33,372,301
					TOTAL COST	178,244,067	77,610,244	255,854,311

Manual routine maintenance of road	Km	20.0	96,920	7,260	1,938,400	145,200	2,083,600
Routine maintenance of gravel road	Km	20.0	176,065	88,186	3,521,300	1,763,720	5,285,020
			Sub Total		5,459,700	1,908,920	7,368,620
Maintenance of Timber Bridge (New)	m2	80.0	9,334	954	746,720	76,320	823,040
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement Unit Cost (Rp/Km)	:	12,149,120
Timber Bridge Unit Cost (Rp/m2)	:	160,899
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	21,236,600
Maintenance Rate without Bridge (%)	:	3.03
New Bridge Cost Rate (%)	:	5.03

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 14 (IIB-1) LENGTH : 47 Km

UPGRADE : 4.0m road bed, 4.0m road with surface Dressing (1)

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL	
			LOCAL	FOREIGN	LOCAL	FOREIGN		
Site Clearance in Light Bush	m2	0.0	153	91	0	0	0	
Subgrade Preparation	m2	282000.0	19	11	5,358,000	3,102,000	8,460,000	
Normal Fill	m3	0.0	1,576	865	0	0	0	
Fill in Swamp	m3	348.0	2,325	1,054	809,100	366,792	1,175,892	
Normal Excavation to Spoil	m3	5327.0	926	523	4,932,802	2,786,021	7,718,823	
Sub Base Course	m3	26320.0	2,984	1,350	78,538,888	35,532,000	114,070,888	
Base Course	m3	13160.0	4,100	2,303	53,956,000	30,307,480	84,263,480	
Shoulder	m2	94000.0	273	146	25,662,000	13,724,000	39,386,000	
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0	
Surface Dressing (Single)	m2	188000.0	843	766	158,484,000	144,008,000	302,492,000	
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0	
Earth Drain	m	73700.0	629	119	46,357,300	8,770,300	55,127,600	
Earth Drain in Swamp (by machine)	m3	2400.0	1,065	474	2,556,000	1,137,600	3,693,600	
Pipe Culvert Ø80cm	m	10.0	36,882	76,576	368,820	765,760	1,134,580	
Masonry Culvert (80x80cm)	m	84.0	47,364	53,860	3,978,576	4,524,240	8,502,816	
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0	
Retaining Wall and Wing Wall (Masonry)	m3	40.0	32,773	12,077	1,310,920	483,080	1,794,000	
Babion Protection	m3	0.0	11,004	121	0	0	0	
New Bridge (Timber)	SET	1.0	--	--	26,508,313	1,765,638	28,273,951	
New Bridge (Concrete)	SET	1.0	--	--	0	0	0	
					Sub Total	408,820,711	247,272,911	656,093,622
Overhead (15%)						61,323,106	37,090,936	98,414,042
					TOTAL COST	470,143,817	284,363,847	754,507,664

Manual routine maintenance of road	Ka	47.0	96,920	7,260	4,555,240	341,220	4,896,460
Routine maintenance of asphalt road	Ka	47.0	293,800	151,400	13,808,600	7,115,800	20,924,400
			Sub Total		18,363,840	7,457,020	25,820,860
Maintenance of Timber Bridge (New)	m2	220.0	9,334	954	2,053,480	209,880	2,263,360
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement Unit Cost (Rp/Km)	:	15,361,545
Timber Bridge Unit Cost (Rp/m2)	:	147,796
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	96,702,312
Maintenance Rate without Bridge (%)	:	3.58
New Bridge Cost Rate (%)	:	4.31

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 13 (IIIB-1) LENGTH : 25 Km

UPGRADE : 6.0m road bed, 4.0m road with surface Dressing (1)

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Site Clearance in Light Bush	m2	40000.0	153	91	6,120,000	3,640,000	9,760,000
Subgrade Preparation	m2	150000.0	19	11	2,050,000	1,650,000	4,500,000
Normal Fill	m3	0.0	1,576	865	0	0	0
Fill in Swamp	m3	1923.8	2,328	1,054	4,472,835	2,027,685	6,500,520
Normal Excavation to Spoil	m3	6895.0	926	523	6,384,770	3,606,085	9,990,855
Sub Base Course	m3	14000.0	2,984	1,350	41,776,000	18,900,000	60,676,000
Base Course	m3	7000.0	4,100	2,303	28,700,000	16,121,000	44,821,000
Shoulder	m2	50000.0	273	146	13,650,000	7,300,000	20,950,000
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0
Surface Dressing (Single)	m2	100000.0	843	766	84,300,000	76,600,000	160,900,000
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0
Earth Drain	m	29500.0	629	119	18,555,500	3,510,500	22,066,000
Earth Drain in Swamp (by machine)	m3	18000.0	1,065	474	19,170,000	8,532,000	27,702,000
Pipe Culvert Ø80cm	m	900.0	36,882	76,576	33,193,800	68,918,400	102,112,200
Masonry Culvert 180x80cm	m	0.0	47,364	53,860	0	0	0
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0
Retaining Wall and Wing Wall (Masonry)	m3	336.0	32,773	12,077	11,011,728	4,057,872	15,069,600
Sablon Protection	m3	0.0	11,004	121	0	0	0
New Bridge (Timber)	SET	1.0	--	--	21,293,071	1,629,956	22,923,027
New Bridge (Concrete)	SET	1.0	--	--	0	0	0
					Sub Total		
					291,477,704	216,493,498	507,971,202
Overhead (15%)					43,721,655	32,474,024	76,195,679
					TOTAL COST		
					335,199,359	248,967,522	584,166,881

Manual routine maintenance of road	Km	25.0	96,920	7,260	2,423,000	181,500	2,604,500
Routine maintenance of asphalt road	Km	25.0	293,800	151,400	7,345,000	3,785,000	11,130,000
			Sub Total		9,768,000	3,966,500	13,734,500
Maintenance of Timber Bridge (New)	m2	152.0	9,334	954	1,418,768	145,008	1,563,776
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement Unit Cost (Rp/Km)	:	22,312,216
Timber Bridge Unit Cost (Rp/m2)	:	173,431
Concrete Bridge Unit Cost (Rp/m2)	:	
Survived Value (Rp)	:	51,437,400
Maintenance Rate without Bridge (%)	:	2.46
New Bridge Cost Rate (%)	:	4.51

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 4 (111B-2) LENGTH : 7 Km

UPGRADE : 6.0m road bed, 4.0m road with surface Base Course

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Site Clearance in Light Bush	m ²	3000.0	153	91	459,000	273,000	732,000
Subgrade Preparation	m ²	0.0	19	11	0	0	0
Normal fill	m ³	350.0	1,576	865	551,600	302,750	854,350
Fill in Swamp	m ³	0.0	2,325	1,054	0	0	0
Normal Excavation to Spoil	m ³	270.0	926	523	250,020	141,210	391,230
Sub Base Course	m ³	868.5	2,984	1,350	2,591,604	1,172,475	3,764,079
Base Course	m ³	1440.0	4,100	2,303	5,904,000	3,316,320	9,220,320
Shoulder	m ²	14000.0	273	146	3,822,000	2,044,000	5,866,000
Asphalt Patching	m ²	33.0	2,939	1,514	96,954	49,962	146,916
Surface Dressing (Single)	m ²	0.0	843	766	0	0	0
Surface Dressing (Double)	m ²	0.0	1,001	1,207	0	0	0
Earth Drain	m	9120.0	629	119	5,736,480	1,085,280	6,821,760
Earth Drain in Swamp (by machine)	m ³	0.0	1,065	474	0	0	0
Pipe Culvert Ø80cm	m	3.0	36,882	76,576	110,646	229,728	340,374
Masonry Culvert (80x80cm)	m	0.0	47,364	53,860	0	0	0
Retaining Wall and Wing Wall (Timber)	m ²	0.0	15,772	246	0	0	0
Retaining Wall and Wing Wall (Masonry)	m ³	0.0	32,773	12,077	0	0	0
Babion Protection	m ³	0.0	11,004	121	0	0	0
New Bridge (Timber)	SET	1.0	--	--	20,619,158	1,199,334	21,818,492
New Bridge (Concrete)	SET	1.0	--	--	0	0	0
					Sub Total		
					40,141,462	9,814,059	49,955,521
Overhead (15%)					6,021,219	1,472,108	7,493,327
					TOTAL COST		
					46,162,681	11,286,167	57,448,848

Manual routine maintenance of road	Km	7.0	96,920	7,260	678,440	50,820	729,260
Routine maintenance of gravel road	Km	7.0	176,865	88,186	1,232,455	617,302	1,849,757
			Sub Total		1,910,895	668,122	2,579,017
Maintenance of Timber Bridge (New)	m ²	200.0	9,334	954	1,866,800	190,800	2,057,600
Maintenance of Concrete Bridge (New)	m ²	0.0	1,872	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m ²	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m ²	188.0	3,900	2,705	733,200	508,540	1,241,740

Earthwork & Pavement	Unit Cost (Rp/Km)	:	4,622,512
Timber Bridge	Unit Cost (Rp/m ²)	:	125,456
Concrete Bridge	Unit Cost (Rp/m ²)	:	
Survived Value	(Rp)	:	1,882,039
Maintenance Rate without Bridge	(%)	:	7.97
New Bridge Cost Rate	(%)	:	43.68

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 2 (IIB-2) LENGTH : 16 Km

UPGRADE : 6.5m road bed, 4.0m road with surface Base Course

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Site Clearance in Light Bush	m2	37500.0	153	91	5,737,500	3,412,500	9,150,000
Subgrade Preparation	m2	104000.0	19	11	1,976,000	1,144,000	3,120,000
Normal Fill	m3	1900.0	1,576	865	2,994,400	1,643,500	4,637,900
Fill in Swamp	m3	0.0	2,325	1,054	0	0	0
Normal Excavation to Spoil	m3	2490.0	926	523	2,305,740	1,302,270	3,608,010
Sub Base Course	m3	8960.0	2,984	1,350	26,736,640	12,096,000	38,832,640
Base Course	m3	3840.0	4,100	2,303	15,744,000	8,843,520	24,587,520
Shoulder	m2	40000.0	273	146	10,920,000	5,840,000	16,760,000
Asphalt Patching	m2	0.0	2,938	1,514	0	0	0
Surface Dressing (Single)	m2	0.0	843	766	0	0	0
Surface Dressing (Double)	m2	0.0	1,001	1,207	0	0	0
Earth Drain	m	3180.0	629	119	2,000,220	378,420	2,378,640
Earth Drain in Swamp (by machine)	m3	0.0	1,065	474	0	0	0
Pipe Culvert 80x80cm	m	426.0	36,882	76,576	15,711,732	32,621,376	48,333,108
Masonry Culvert (80x80cm)	m	0.0	47,364	53,860	0	0	0
Retaining Wall and Wing Wall (Timber)	m2	0.0	15,772	246	0	0	0
Retaining Wall and Wing Wall (Masonry)	m3	160.0	32,773	12,077	5,243,680	1,932,320	7,176,000
Gabion Protection	m3	0.0	11,004	121	0	0	0
New Bridge (Timber)	SET	1.0	--	--	25,411,819	1,849,104	27,260,923
New Bridge (Concrete)	SET	1.0	--	--	0	0	0
				Sub Total	114,781,731	71,063,010	185,844,741
Overhead (15%)					17,217,259	10,659,451	27,876,710
				TOTAL COST	131,998,990	81,722,461	213,721,451

Manual routine maintenance of road	Km	16.0	96,920	7,260	1,550,720	116,160	1,666,880
Routine maintenance of gravel road	Km	16.0	176,065	88,188	2,817,040	1,410,976	4,228,016
			Sub Total		4,367,760	1,527,136	5,894,896
Maintenance of Timber Bridge (New)	m2	192.0	9,334	954	1,792,128	183,168	1,975,296
Maintenance of Concrete Bridge (New)	m2	0.0	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.0	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.0	3,900	2,705	0	0	0

Earthwork & Pavement	Unit Cost	(Rp/Km)	:	11,398,212
Timber Bridge	Unit Cost	(Rp/m2)	:	163,282
Concrete Bridge	Unit Cost	(Rp/m2)	:	
Survived Value		(Rp)	:	19,416,320
Maintenance Rate without Bridge		(%)	:	3.23
New Bridge Cost Rate		(%)	:	14.67

CONSTRUCTION AND MAINTENANCE QUANTITIES
FOR ALL PROPOSED ROAD LINKS
(CONSTRUCTION)

PROV : NUSA TENGGARA TIMUR KAB : NGADA

I T E M	UNIT	(1988)	(1989)	(1990)	(1991)	(1992)	(TOTAL)
EQUIPMENT :							
Bulldozer/Ripper	hr	157.4	523.0	442.2	1120.4	1028.5	3271.5
Swap Bulldozer	hr	3.4	29.1	30.2	12.8	106.8	182.3
Motor Grader	hr	678.4	1462.5	1385.9	2592.2	2374.9	8493.9
Hand-guide Vib. Roller	hr	120.4	680.5	720.7	1496.8	805.6	3824.0
Tire Roller	hr	469.9	803.3	959.9	166.6	0.0	2399.7
Vibratory Roller (D&T)	hr	555.0	1138.6	1152.6	2189.6	2066.9	7102.7
Hydraulic Excavator; Wheel	hr	57.0	597.0	616.0	270.0	2252.1	3792.1
Wheel Loader	hr	838.2	2024.2	1891.4	3360.1	3051.9	11165.8
Water Tank Truck	hr	392.1	780.7	815.2	1481.5	1376.7	4846.2
Dump Truck	hr	7925.5	17772.1	17775.2	29910.9	30177.3	103561.0
Flat Bed Truck with Crane	hr	99.7	539.3	572.7	1359.5	554.6	3125.8
Flat Bed Truck	hr	600.6	1189.9	1390.2	705.8	257.1	4143.6
Portable Crusher/Screening	hr	190.8	467.1	395.3	520.4	405.8	1979.4
Concrete Mixer	hr	26.0	168.3	177.0	300.2	148.8	820.3
Water Pump	hr	18.7	134.1	140.4	245.3	112.3	650.8
Concrete Vibrator	hr	4.2	65.9	67.4	135.5	39.2	312.2
Asphalt Sprayer	hr	469.9	803.3	959.9	166.6	0.0	2399.7
LABOUR :							
Mandur	man day	826.3	2014.7	2165.5	3705.4	3264.9	11976.8
Skilled Labourer	man day	881.7	1941.1	2235.0	5591.8	2528.7	13178.3
Carpenter	man day	317.6	666.0	772.1	2708.3	1286.0	5750.0
Mason	man day	36.2	170.6	182.7	274.5	182.8	846.8
Labourer	man day	10066.3	21175.5	23492.7	35842.3	37449.6	127826.4
Driver	man day	1664.5	3628.2	3719.4	5821.4	5683.9	20517.4
Operator	man day	699.9	1874.4	1804.7	2874.1	2675.9	9929.0
MATERIAL :							
Bitumen	l	96349.9	164683.3	196799.9	34211.1	0.0	492044.2
Asphalt Oil	l	19270.0	32936.6	39360.0	6833.3	0.0	98399.9
Kerosene	l	23029.9	39363.3	47039.9	8171.5	0.0	117604.6
Sand	m ³	299.1	844.1	943.9	852.2	238.0	3177.3
Cement	bag	76.3	1027.4	1052.8	2080.8	642.3	4879.6
River Stone	m ³	36.2	170.6	182.7	274.5	182.8	846.8
Steel Moulds	set	3.0	363.0	364.0	790.6	213.4	1734.0
Tiaber	m ³	28.6	58.3	67.9	241.9	115.6	512.3
Faint	l	182.0	391.0	451.6	1609.1	832.0	3465.7
Reinforcing Steel	kg	465.4	11949.4	12104.5	25220.1	7071.4	56810.8
Tying Wire	kg	4.1	108.5	109.9	229.2	64.2	515.9
Equivalent Royalty	m ³	14888.9	30903.4	31779.6	53003.5	48488.0	179063.4

CONSTRUCTION AND MAINTENANCE QUANTITIES
FOR ALL PROPOSED ROAD LINKS
(MAINTENANCE)

PROV : NUSA TENGGARA TIMUR KAB : NGADA

ITEM	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
EQUIPMENT :							
Bulldozer/Ripper	hr	0.0	0.0	0.0	0.0	0.0	0.0
Swamp Bulldozer	hr	0.0	0.0	0.0	0.0	0.0	0.0
Motor Grader	hr	675.9	1315.8	1342.4	1178.5	1318.5	5831.1
Hand-guide Vib. Roller	hr	7.5	15.0	15.0	712.5	1080.0	1830.0
Tire Roller	hr	675.9	1315.8	1342.4	1178.5	1318.5	5831.1
Vibratory Roller (D&T)	hr	0.0	0.0	0.0	0.0	0.0	0.0
Hydraulic Excavator; Wheel	hr	0.0	0.0	0.0	0.0	0.0	0.0
Wheel Loader	hr	127.6	242.7	255.4	304.8	396.9	1327.4
Water Tank Truck	hr	0.0	0.0	0.0	0.0	0.0	0.0
Dump Truck	hr	781.5	1486.9	1563.2	3253.7	4540.9	11626.2
Flat Bed Truck with Crane	hr	358.8	700.4	717.6	621.3	784.9	3183.0
Flat Bed Truck	hr	2590.0	5047.9	5142.4	5049.2	5843.3	23672.8
Portable Crusher/Screening	hr	63.9	121.5	127.8	153.7	200.6	667.5
Concrete Mixer	hr	1.2	2.3	2.4	2.1	2.4	10.4
Water Pump	hr	1.2	2.3	2.4	2.1	2.4	10.4
Concrete Vibrator	hr	1.2	2.3	2.4	2.1	2.4	10.4
Asphalt Sprayer	hr	0.0	0.0	0.0	0.0	0.0	0.0
LABOUR :							
Mandur	man day	776.1	1512.4	1541.6	1778.5	2177.4	7786.0
Skilled Labourer	man day	16.8	33.4	33.8	496.7	884.6	1465.3
Carpenter	man day	5.5	11.0	11.1	10.2	86.7	124.5
Mason	man day	0.0	0.0	0.0	0.0	0.0	0.0
Labourer	man day	9308.9	18140.1	18484.2	21360.8	25971.2	93265.2
Driver	man day	634.8	1231.9	1263.8	1509.5	1896.3	6536.3
Operator	man day	268.0	519.9	533.0	495.4	573.1	2389.4
MATERIAL :							
Bitumen	l	67.5	135.0	135.0	6412.5	9720.0	16470.0
Asphalt Oil	l	0.0	0.0	0.0	0.0	0.0	0.0
Kerosene	l	7.5	15.0	15.0	712.5	1080.0	1830.0
Sand	m ³	2.4	4.8	4.9	120.8	182.4	315.3
Cement	bag	17.9	34.9	35.8	30.8	35.8	155.2
River Stone	m ³	0.0	0.0	0.0	0.0	0.0	0.0
Steel Moulds	set	0.0	0.0	0.0	0.0	0.0	0.0
Tiiber	m ³	0.4	0.8	0.8	0.7	7.6	10.3
Paint	l	1.5	3.1	3.1	3.1	52.0	62.8
Reinforcing Steel	kg	92.1	179.7	184.3	158.4	184.3	798.8
Tying Wire	kg	0.8	1.6	1.6	1.4	1.6	7.0
Equivalent Royalty	m ³	1810.2	3440.4	3620.6	4319.7	5624.6	18815.5

CONSTRUCTION AND MAINTENANCE QUANTITIES
FOR ALL PROPOSED ROAD LINKS
(TOTAL)

PROV : NUSA TENGGARA TIMUR KAB : NGADA

I T E M	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
EQUIPMENT :							
Bulldozer/Ripper	hr	157.4	523.0	442.2	1120.4	1028.5	3271.5
Swamp Bulldozer	hr	3.4	29.1	30.2	12.8	106.8	182.3
Motor Grader	hr	1354.3	2778.3	2728.3	3770.7	3693.4	14325.0
Hand-guide Vib. Roller	hr	127.9	695.5	735.7	2209.3	1885.6	5654.0
Tire Roller	hr	1145.8	2119.1	2302.3	1345.1	1318.5	8230.8
Vibratory Roller (D&T)	hr	555.0	1138.6	1152.6	2189.6	2066.9	7102.7
Hydraulic Excavator; Wheel	hr	57.0	597.0	616.0	270.0	2252.1	3792.1
Wheel Loader	hr	965.8	2266.9	2146.8	3664.9	3448.8	12493.2
Water Tank Truck	hr	392.1	780.7	815.2	1481.5	1376.7	4846.2
Duap Truck	hr	8707.0	19259.0	19338.4	33184.6	34718.2	115187.2
Flat Bed Truck with Crane	hr	458.5	1239.7	1290.3	1980.8	1339.5	6308.8
Flat Bed Truck	hr	3190.6	6237.8	6532.6	5755.0	6100.4	27816.4
Portable Crusher/Screening	hr	254.7	588.6	523.1	674.1	606.4	2666.9
Concrete Mixer	hr	27.2	170.6	179.4	302.3	151.2	830.7
Water Pump	hr	19.9	136.4	142.8	247.4	114.7	661.2
Concrete Vibrator	hr	5.4	68.2	69.8	137.6	41.6	322.6
Asphalt Sprayer	hr	469.9	803.3	959.9	166.6	0.0	2399.7
LABOUR :							
Manjur	man day	1602.4	3527.1	3707.1	5483.9	5442.3	19762.8
Skilled Labourer	man day	898.5	1974.5	2268.8	6088.5	3413.3	14643.6
Carpenter	man day	323.1	677.0	783.2	2718.5	1372.7	5874.5
Mason	man day	36.2	170.6	182.7	274.5	182.8	846.8
Labourer	man day	19375.2	39315.6	41976.9	57003.1	63420.8	221091.6
Driver	man day	2299.3	4860.1	4983.2	7330.9	7580.2	27053.7
Operator	man day	967.9	2394.3	2337.7	3369.5	3249.0	12318.4
MATERIAL :							
Bitumen	l	96417.4	164818.3	196934.9	40623.6	9720.0	508514.2
Asphalt Oil	l	19270.0	32936.6	39360.0	6833.3	0.0	98399.9
Kerosene	l	23037.4	39378.3	47054.9	8884.0	1080.0	119434.6
Sand	m ³	301.5	848.9	948.8	973.0	420.4	3492.6
Cement	bag	94.2	1062.3	1088.6	2111.6	678.1	5034.8
River Stone	m ³	36.2	170.6	182.7	274.5	182.8	846.8
Steel Moulds	set	3.0	363.0	364.0	790.6	213.4	1734.0
Tiaber	m ³	29.0	59.1	68.7	242.6	123.2	522.6
Paint	l	183.5	394.1	454.7	1612.2	884.0	3528.5
Reinforcing Steel	kg	557.5	12129.1	12288.8	25378.5	7255.7	57609.6
Tying Wire	kg	4.9	110.1	111.5	230.6	65.8	522.9
Equivalent Royalty	m ³	16699.1	34343.8	35400.2	57323.2	54112.6	197878.9

Appendix A-5

CONSTRUCTION AND MAINTENANCE COSTS
FOR ALL PROPOSED ROAD LINKS
(CONSTRUCTION)

PROV : NUSA TENGGARA TIMUR

KAB : NGADA

(1000 Rp)

I T E M	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
EQUIPMENT :		91,504	215,038	211,640	332,895	334,531	1,186,408
Bulldozer/Ripper	15758	2,480	8,241	6,968	17,655	16,207	51,551
Swamp Bulldozer	11617	39	338	350	148	1,240	2,115
Motor Grader	13465	9,134	19,692	18,661	34,903	31,978	114,368
Hand-guide Vib. Roller	1575	189	1,071	1,135	2,357	1,268	6,020
Tire Roller	10676	5,016	8,576	10,247	1,778	0	25,617
Vibratory Roller (D&T)	6724	3,731	7,655	7,750	14,722	13,897	47,755
Hydraulic Excavator; Wheel	12601	718	7,522	7,762	3,402	28,378	47,782
Wheel Loader	16660	13,964	33,723	31,510	55,979	50,844	186,020
Water Tank Truck	3912	1,533	3,054	3,189	5,795	5,385	18,956
Dump Truck	5389	42,710	95,773	95,790	161,189	162,625	558,087
Flat Bed Truck with Crane	4981	496	2,686	2,852	6,771	2,762	15,567
Flat Bed Truck	3265	1,960	3,885	4,539	2,304	839	13,527
Portable Crusher/Screening	43673	8,332	20,399	17,263	22,727	17,722	86,443
Concrete Mixer	8879	230	1,494	1,571	2,665	1,321	7,281
Water Pump	477	8	63	66	117	53	307
Concrete Vibrator	310	1	20	20	42	12	95
Asphalt Sprayer	2050	963	1,646	1,967	341	0	4,917
LABOUR :		19,592	43,390	46,755	78,262	71,709	259,708
Mandur	1500	1,239	3,022	3,248	5,558	4,897	17,964
Skilled Labourer	1300	1,146	2,523	2,905	7,269	3,287	17,130
Carpenter	2000	635	1,332	1,544	5,416	2,572	11,499
Mason	2000	72	341	365	549	365	1,692
Labourer	1100	11,072	23,293	25,841	39,206	41,194	140,606
Driver	2000	3,329	7,256	7,438	11,642	11,367	41,032
Operator	3000	2,899	5,623	5,414	8,622	8,027	29,785
MATERIAL :		85,860	180,005	207,621	158,651	56,498	688,643
Bitumen	400	30,539	65,873	78,719	13,684	0	196,815
Asphalt Oil	1500	28,905	49,404	59,040	10,249	0	147,598
Kerosene	250	5,757	9,840	11,759	2,042	0	29,398
Sand	5000	1,495	4,220	4,719	4,261	1,190	15,885
Cement	5500	419	5,650	5,790	11,444	3,532	26,835
River Stone	4000	144	682	730	1,098	731	3,385
Steel Moulds	8500	25	3,085	3,094	6,720	1,813	14,737
Timber	200000	5,720	11,660	13,580	48,380	23,120	102,460
Paint	1750	318	684	790	2,815	1,456	6,063
Reinforcing Steel	1750	814	20,911	21,182	44,135	12,374	99,416
Tying Wire	2500	10	271	274	573	160	1,288
Equivalent Royalty	250	3,722	7,725	7,944	13,250	12,122	44,763

CONSTRUCTION AND MAINTENANCE COSTS
FOR ALL PROPOSED ROAD LINKS
(MAINTENANCE)

PROV : NUSA TENGGARA TIMUR KAB : NGADA

(1000 Rp)

I T E M	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
EQUIPMENT :		35,705	69,138	71,073	78,492	96,381	350,789
Bulldozer/Ripper	15758	0	0	0	0	0	0
Swamp Bulldozer	11617	0	0	0	0	0	0
Motor Grader	13465	9,100	17,717	18,075	15,868	17,753	78,513
Hand-guide Vib. Roller	1575	11	23	23	1,122	1,701	2,880
Tire Roller	10676	7,215	14,047	14,331	12,581	14,076	62,250
Vibratory Roller (D&T)	6724	0	0	0	0	0	0
Hydraulic Excavator; Wheel	12601	0	0	0	0	0	0
Wheel Loader	16660	2,125	4,043	4,254	5,077	6,612	22,111
Water Tank Truck	3912	0	0	0	0	0	0
Dump Truck	5389	4,211	8,012	8,424	17,534	24,470	62,651
Flat Bed Truck with Crane	4981	1,787	3,488	3,574	3,094	3,909	15,852
Flat Bed Truck	3265	8,456	16,481	16,789	16,485	19,078	77,289
Portable Crusher/Screening	43673	2,790	5,306	5,581	6,712	8,760	29,149
Concrete Mixer	8879	10	20	21	18	21	90
Water Pump	477	0	1	1	1	1	4
Concrete Vibrator	310	0	0	0	0	0	0
Asphalt Sprayer	2050	0	0	0	0	0	0
LABOUR :		13,508	26,309	26,835	31,333	38,667	136,652
Mandur	1500	1,164	2,268	2,312	2,667	3,266	11,677
Skilled Labourer	1300	21	43	43	645	1,149	1,901
Carpenter	2000	11	22	22	20	173	248
Mason	2000	0	0	0	0	0	0
Labourer	1100	10,239	19,954	20,332	23,496	28,568	102,589
Driver	2000	1,269	2,463	2,527	3,019	3,792	13,070
Operator	3000	804	1,559	1,599	1,486	1,719	7,167
MATERIAL :		835	1,615	1,673	5,020	8,609	17,752
Bitumen	400	27	54	54	2,565	3,888	6,588
Asphalt Oil	1500	0	0	0	0	0	0
Kerosene	250	1	3	3	178	270	455
Sand	5000	12	24	24	604	912	1,576
Cement	5500	98	191	196	169	196	850
River Stone	4000	0	0	0	0	0	0
Steel Moulds	8500	0	0	0	0	0	0
Timber	200000	80	160	160	140	1,520	2,060
Paint	1750	2	5	5	5	91	108
Reinforcing Steel	1750	161	314	322	277	322	1,396
Tying Wire	2500	2	4	4	3	4	17
Equivalent Royalty	250	452	860	905	1,079	1,406	4,702

CONSTRUCTION AND MAINTENANCE COSTS
FOR ALL PROPOSED ROAD LINKS
(TOTAL)

PROV : NUSA TENGGARA TIMUR

KAB : NBADA

(1000 Rp)

I T E M	UNIT	< 1988 >	< 1989 >	< 1990 >	< 1991 >	< 1992 >	< TOTAL >
EQUIPMENT :		127,209	284,976	282,713	411,387	430,912	1,537,197
Bulldozer/Ripper	15758	2,480	8,241	6,988	17,655	16,207	51,551
Swamp Bulldozer	11617	39	338	350	148	1,240	2,115
Motor Grader	13465	18,234	37,409	36,736	50,771	49,731	192,881
Hand-guide Vib. Roller	1575	200	1,094	1,158	3,479	2,969	8,900
Tire Roller	10676	12,231	22,623	24,578	14,359	14,076	87,867
Vibratory Roller (D&T)	6724	3,731	7,655	7,750	14,722	13,897	47,755
Hydraulic Excavator; Wheel	12601	718	7,522	7,762	3,402	28,378	47,782
Wheel Loader	16660	16,089	37,766	35,764	61,056	57,456	208,131
Water Tank Truck	3912	1,533	3,054	3,189	5,795	5,385	18,956
Dump Truck	5389	46,921	103,785	104,214	178,723	187,095	620,738
Flat Bed Truck with Crane	4981	2,283	6,174	6,426	9,865	6,671	31,419
Flat Bed Truck	3265	10,416	20,366	21,328	18,788	19,917	90,816
Portable Crusher/Screening	43673	11,122	25,705	22,844	29,439	26,482	115,592
Concrete Mixer	8879	240	1,514	1,592	2,683	1,342	7,371
Water Pump	477	8	64	67	118	54	311
Concrete Vibrator	310	1	20	20	42	12	95
Asphalt Sprayer	2050	963	1,646	1,967	341	0	4,917
LABOUR :		33,100	69,699	73,590	109,595	110,376	396,360
Mandur	1500	2,403	5,290	5,560	8,225	8,163	29,641
Skilled Labourer	1300	1,167	2,566	2,948	7,914	4,436	19,031
Carpenter	2000	646	1,354	1,566	5,436	2,745	11,747
Mason	2000	72	341	365	549	365	1,692
Labourer	1100	21,311	43,247	46,173	62,702	69,762	243,195
Driver	2000	4,598	9,719	9,965	14,661	15,159	54,102
Operator	3000	2,903	7,182	7,013	10,108	9,746	36,952
MATERIAL :		86,703	181,620	209,294	163,671	65,107	706,395
Bitumen	400	38,566	65,927	78,773	16,249	3,888	203,403
Asphalt Oil	1500	28,905	49,404	59,040	10,249	0	147,598
Kerosene	250	5,758	9,843	11,762	2,220	270	29,853
Sand	5000	1,507	4,244	4,743	4,865	2,182	17,461
Cement	5500	517	5,841	5,986	11,613	3,728	27,685
River Stone	4000	144	682	730	1,098	731	3,385
Steel Moulds	8500	25	3,085	3,094	6,720	1,813	14,737
Timber	200000	5,800	11,820	13,740	48,520	24,640	104,520
Paint	1750	320	689	795	2,820	1,547	6,171
Reinforcing Steel	1750	975	21,225	21,504	44,412	12,696	100,812
Tying Wire	2500	12	275	278	576	164	1,305
Equivalent Royalty	250	4,174	8,585	8,849	14,329	13,528	49,465

Appendix A-6

QUANTITIES OF BRIDGE ON PROPOSED ROAD LINKS

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO	BRIDGE NAME	Km	From	<< TYPE >>		DESIGN LOAD	SPAN CLASS	LENGTH (m)	SPAN NO	SPAN LENGTH (m)	WIDTH (m)	AREA	AREA	PIER (no)	ABUT (no)	ROAD CLASS
				(EXIST)	(NEW)							(EXIST) (m ²)	(NEW) (m ²)			
2	LEKODOKO	1	AIMR	KK	TH	10T	(C)	8.00	1	8.00	4.00	24.00	32.00	0	2	111B-2
	WAEBUA	1	AIMR	--	TH	10T	(B)	10.00	2	5.00	4.00	0.00	40.00	1	2	
	WAELAKO	5	AIMR	--	TH	10T	(C)	16.00	2	8.00	4.00	0.00	64.00	1	2	
	NGABALENA	12	AIMR	--	TH	10T	(C)	14.00	2	7.00	4.00	0.00	56.00	1	2	
4	AEKOKO	6	MPGG	GB				26.00	1	26.00	4.00	104.00		0	2	111B-2
	MAUKELI	7	MPGG	GB				12.00	1	12.00	4.00	48.00		0	2	
	AETORO	10	MPGG	--	TH	10T	(C)	50.00	7	7.14	4.00	0.00	200.00	6	2	
	MAUNBAWA	10	MPGG	KB				12.00	1	12.00	3.00	36.00		0	2	
13	OLAKILE	5	BOWE	--	TH	10T	(C)	12.00	2	6.00	4.00	0.00	48.00	1	2	111B-1
	WAENUTU I	11	BOWE	--	TH	10T	(B)	10.00	2	5.00	4.00	0.00	40.00	1	2	
	WAENUTU II	11	BOWE	--	TH	10T	(B)	9.00	2	4.50	4.00	0.00	36.00	1	2	
	MENGERUDA	21	BOWE	--	TH	10T	(C)	7.00	1	7.00	4.00	0.00	28.00	0	2	
14	GERO I	2	ANLI	--	TH	10T	(C)	15.00	2	7.50	4.00	0.00	60.00	1	2	111B-1
	GERO II	3	ANLI	--	TH	10T	(C)	25.00	4	6.25	4.00	0.00	100.00	3	2	
	JAWAKISA II	12	ANLI	--	TH	10T	(C)	15.00	2	7.50	4.00	0.00	60.00	1	2	
20	LOKADO	10	REGA	--	TH	10T	(B)	10.00	2	5.00	4.00	0.00	40.00	1	2	111B-2
	H.I	20	REGA	--	TH	10T	(B)	10.00	2	5.00	4.00	0.00	40.00	1	2	
24	H.I	3	MRPK	--	TH	10T	(C)	8.00	1	8.00	4.00	0.00	32.00	0	2	111B-2
	H.I	15	MRPK	--	TH	10T	(C)	7.00	1	7.00	4.00	0.00	28.00	0	2	
25	MBAY I	1	DNBA	KB				4.00	1	4.00	3.50	14.00		0	2	111C
	MBAY II	11	DNBA	KB				3.00	1	3.00	3.50	10.50		0	2	
	MBAY	14	DNBA	KB				3.00	1	3.00	3.00	9.00		0	2	
26	H.I	2	SRSN	LL				6.00	1	6.00	4.00	24.00		0	2	111B-2
	H.I	5	SRSN	--	TH	10T	(C)	8.00	1	8.00	4.00	0.00	32.00	0	2	
	H.I	7	SRSN	--	TH	10T	(B)	10.00	2	5.00	4.00	0.00	40.00	1	2	
30	H.I	3	FTLK	--	TH	10T	(B)	5.00	1	5.00	4.00	0.00	20.00	0	2	111B-2
	H.I	6	FTLK	--	TH	10T	(C)	6.00	1	6.00	4.00	0.00	24.00	0	2	
	H.I	11	FTLK	--	TH	10T	(B)	9.00	2	4.50	4.00	0.00	36.00	1	2	
	H.I	12	FTLK	--	TH	10T	(B)	10.00	2	5.00	4.00	0.00	40.00	1	2	
	H.I	19	FTLK	--	TH	10T	(B)	4.00	1	4.00	4.00	0.00	16.00	0	2	

PROV : NUSA TENGGARA TIMUR KAB : NAGADA

LINE NO : 4 (IIIB-2) LENGTH : 7 Km

(Rp)

I T E M	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber; Span 3a; 101)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber; Span 5a; 101)	m2	0.00	58,376	3,012	0	0	0
Superstructure (Timber; Span 8a; 101)	m2	200.00	77,325	3,961	15,465,000	792,200	16,257,200
Superstructure (Timber; Span 3a; BHSO)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber; Span 5a; BHSO)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber; Span 8a; BHSO)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete; Span 3a; BHSO)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete; Span 5a; BHSO)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete; Span 8a; BHSO)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete; Span 10a; BHSO)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete; Span 15a; BHSO)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier; for Timber; 101)	NO	6.00	458,897	25,168	2,753,382	151,008	2,904,390
Substructure (Abut; for Timber; 101)	NO	2.00	1,200,388	128,063	2,400,776	256,126	2,656,902
Substructure (Pier; for Timber; BHSO)	NO	0.00	674,875	37,224	0	0	0
Substructure (Abut; for Timber; BHSO)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier; for Concrete; BHSO)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut; for Concrete; BHSO)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	200.00	9,334	954	1,866,800	190,800	2,057,600
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	188.00	3,900	2,705	733,200	508,540	1,241,740
<hr/>							
(Without Overhead)		TOTAL COST (Timber Bridge)		20,619,158	1,199,334	21,818,492	
		(Concrete Bridge)		0	0	0	
		TOTAL COST (without Maintenance)		20,619,158	1,199,334	21,818,492	
<hr/>							
(Overhead : 15%)		TOTAL COST (Timber Bridge)		23,712,032	1,379,234	25,091,266	
		(Concrete Bridge)		0	0	0	
		TOTAL COST (without Maintenance)		23,712,032	1,379,234	25,091,266	

PROV : NUSA TENGGARA TIMUR KAD : NGADA

LINK NO : 13 (IIIB-1) LENGTH : 25 Km

(Rp)

I T E M	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber; Span 3m; 10T)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber; Span 5m; 10T)	m2	76.00	58,376	3,012	4,436,576	228,912	4,665,488
Superstructure (Timber; Span 8m; 10T)	m2	76.00	77,325	3,961	5,876,700	301,036	6,177,736
Superstructure (Timber; Span 3m; BMSO)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber; Span 5m; BMSO)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber; Span 8m; BMSO)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete; Span 3m; BMSO)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete; Span 5m; BMSO)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete; Span 8m; BMSO)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete; Span 10m; BMSO)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete; Span 15m; BMSO)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier; for Timber; 10T)	NO	3.00	458,897	25,168	1,376,691	75,504	1,452,195
Substructure (Abut; for Timber; 10T)	NO	8.00	1,200,388	128,063	9,603,104	1,024,504	10,627,608
Substructure (Pier; for Timber; BMSO)	NO	0.00	674,875	37,224	0	0	0
Substructure (Abut; for Timber; BMSO)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier; for Concrete; BMSO)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut; for Concrete; BMSO)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	152.00	9,334	954	1,418,768	145,008	1,563,776
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.00	3,900	2,705	0	0	0
(Without Overhead)			TOTAL COST (Timber Bridge)		21,293,071	1,629,956	22,923,027
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		21,293,071	1,629,956	22,923,027
(Overhead : 15%)			TOTAL COST (Timber Bridge)		24,487,032	1,874,449	26,361,481
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		24,487,032	1,874,449	26,361,481

PROV : NUSA TENGGARA TIMUR KAB : NOADA

LINK NO : 14 (IITB-1) LENGTH : 47 Km

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber; Span 3m; IOT)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber; Span 5m; IOT)	m2	0.00	58,376	3,012	0	0	0
Superstructure (Timber; Span 8m; IOT)	m2	220.00	77,325	3,961	17,011,500	871,420	17,882,920
Superstructure (Timber; Span 3m; BHSO)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber; Span 5m; BHSO)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber; Span 8m; BHSO)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete; Span 3m; BHSO)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete; Span 5m; BHSO)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete; Span 8m; BHSO)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete; Span 10m; BHSO)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete; Span 15m; BHSO)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier; for Timber; IOT)	NO	5.00	458,897	25,168	2,294,485	125,840	2,420,325
Substructure (Abut; for Timber; IOT)	NO	6.00	1,200,388	128,063	7,202,328	768,378	7,970,706
Substructure (Pier; for Timber; BHSO)	NO	0.00	674,875	37,224	0	0	0
Substructure (Abut; for Timber; BHSO)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier; for Concrete; BHSO)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut; for Concrete; BHSO)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	220.00	9,334	954	2,053,480	209,880	2,263,360
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.00	3,900	2,705	0	0	0
(Without Overhead)			TOTAL COST (Timber Bridge)		26,508,313	1,765,638	28,273,951
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		26,508,313	1,765,638	28,273,951
(Overhead : 15%)			TOTAL COST (Timber Bridge)		30,484,560	2,030,484	32,515,044
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		30,484,560	2,030,484	32,515,044

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 20 (IIIB-2) LENGTH : 20 Km

(Rp)

ITEM	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber; Span 3a; IOT)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber; Span 5a; IOT)	m2	80.00	58,376	3,012	4,670,080	240,960	4,911,040
Superstructure (Timber; Span 8a; IOT)	m2	0.00	77,325	3,961	0	0	0
Superstructure (Timber; Span 3a; BMSO)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber; Span 5a; BMSO)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber; Span 8a; BMSO)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete; Span 3a; BMSO)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete; Span 5a; BMSO)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete; Span 8a; BMSO)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete; Span 10a; BMSO)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete; Span 15a; BMSO)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier; for Timber; IOT)	N0	2.00	458,897	25,168	917,794	50,336	968,130
Substructure (Abut; for Timber; IOT)	N0	4.00	1,200,388	128,063	4,801,552	512,252	5,313,804
Substructure (Pier; for Timber; BMSO)	N0	0.00	674,875	37,224	0	0	0
Substructure (Abut; for Timber; BMSO)	N0	0.00	1,362,835	140,846	0	0	0
Substructure (Pier; for Concrete; BMSO)	N0	0.00	1,393,463	487,788	0	0	0
Substructure (Abut; for Concrete; BMSO)	N0	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	80.00	9,334	954	746,720	76,320	823,040
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.00	3,900	2,705	0	0	0
<hr/>							
(Without Overhead)	TOTAL COST (Timber Bridge)		10,389,426		803,548	11,192,974	
	(Concrete Bridge)		0		0	0	
	TOTAL COST (without Maintenance)		10,389,426		803,548	11,192,974	
<hr/>							
(Overhead : 15%)	TOTAL COST (Timber Bridge)		11,947,840		924,080	12,871,920	
	(Concrete Bridge)		0		0	0	
	TOTAL COST (without Maintenance)		11,947,840		924,080	12,871,920	

PROV : NILISA TENGGARA TIMUR KAB : NGADA

LINK NO : 24 (IIIB-2) LENGTH : 20 Km

(Rp)

I T E N	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber; Span 3m; IOT)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber; Span 5m; IOT)	m2	0.00	58,376	3,012	0	0	0
Superstructure (Timber; Span 8m; IOT)	m2	60.00	77,325	3,961	4,639,500	237,660	4,877,160
Superstructure (Timber; Span 3m; BHSO)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber; Span 5m; BHSO)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber; Span 8m; BHSO)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete; Span 3m; BHSO)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete; Span 5m; BHSO)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete; Span 8m; BHSO)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete; Span 10m; BHSO)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete; Span 15m; BHSO)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier; for Timber; IOT)	NO	0.00	458,897	25,160	0	0	0
Substructure (Abut; for Timber; IOT)	NO	4.00	1,200,388	128,063	4,801,552	512,252	5,313,804
Substructure (Pier; for Timber; BHSO)	NO	0.00	674,875	37,224	0	0	0
Substructure (Abut; for Timber; BHSO)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier; for Concrete; BHSO)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut; for Concrete; BHSO)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	60.00	9,334	954	560,040	57,240	617,280
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.00	3,900	2,705	0	0	0
(Without Overhead)			TOTAL COST (Timber Bridge)		9,441,052	749,912	10,190,964
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		9,441,052	749,912	10,190,964
(Overhead : 15%)			TOTAL COST (Timber Bridge)		10,857,210	862,399	11,719,609
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		10,857,210	862,399	11,719,609

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 25 (IIIC) LENGTH : 16 Km

(Rp)

I T E M	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber;Span 3m;10T)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber;Span 5m;10T)	m2	0.00	58,376	3,012	0	0	0
Superstructure (Timber;Span 8m;10T)	m2	0.00	77,325	3,961	0	0	0
Superstructure (Timber;Span 3m;BN50)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber;Span 5m;BN50)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber;Span 8m;BN50)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete;Span 3m;BN50)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete;Span 5m;BN50)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete;Span 8m;BN50)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete;Span 10m;BN50)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete;Span 15m;BN50)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier;for Timber;10T)	NO	0.00	458,897	25,168	0	0	0
Substructure (Abut;for Timber;10T)	NO	0.00	1,200,388	128,063	0	0	0
Substructure (Pier;for Timber;BN50)	NO	0.00	674,875	37,224	0	0	0
Substructure (Abut;for Timber;BN50)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier;for Concrete;BN50)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut;for Concrete;BN50)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	0.00	9,334	954	0	0	0
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	33.50	3,900	2,705	130,650	90,617	221,267
<hr/>							
(Without Overhead)	TOTAL COST (Timber Bridge)				0	0	0
	(Concrete Bridge)				0	0	0
	TOTAL COST (without Maintenance)				0	0	0
<hr/>							
(Overhead : 15%)	TOTAL COST (Timber Bridge)				0	0	0
	(Concrete Bridge)				0	0	0
	TOTAL COST (without Maintenance)				0	0	0

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 26 (IIIB-2) LENGTH : 15 Km

(Rp)

I T E M	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber;Span 3a;10T)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber;Span 5a;10T)	m2	40.00	58,376	3,012	2,335,040	120,480	2,455,520
Superstructure (Timber;Span 8a;10T)	m2	32.00	77,325	3,961	2,474,400	126,752	2,601,152
Superstructure (Timber;Span 3a;BMSO)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber;Span 5a;BMSO)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber;Span 8a;BMSO)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete;Span 3a;BMSO)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete;Span 5a;BMSO)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete;Span 8a;BMSO)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete;Span10a;BMSO)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete;Span15a;BMSO)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier;for Timber;10T)	NO	1.00	458,897	25,168	458,897	25,168	484,065
Substructure (Abut;for Timber;10T)	NO	4.00	1,200,388	128,063	4,801,552	512,252	5,313,804
Substructure (Pier;for Timber;BMSO)	NO	0.00	674,875	37,224	0	0	0
Substructure (Abut;for Timber;BMSO)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier;for Concrete;BMSO)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut;for Concrete;BMSO)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	72.00	9,334	954	672,048	68,688	740,736
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	24.00	8,203	2,322	196,872	55,728	252,600
Maintenance of Concrete Bridge (Exist)	m2	0.00	3,900	2,705	0	0	0
<hr/>							
(Without Overhead)	TOTAL COST (Timber Bridge)				10,069,889	784,652	10,854,541
	TOTAL COST (Concrete Bridge)				0	0	0
	TOTAL COST (without Maintenance)				10,069,889	784,652	10,854,541
<hr/>							
(Overhead : 15%)	TOTAL COST (Timber Bridge)				11,580,372	902,350	12,482,722
	TOTAL COST (Concrete Bridge)				0	0	0
	TOTAL COST (without Maintenance)				11,580,372	902,350	12,482,722

PROV : NUSA TENGGARA TIMUR KAB : NGADA

LINK NO : 30 (IIIB-2) LENGTH : 25 Km

(Rp)

I T E M	UNIT	QUANTITY	<<< UNIT COST >>>		<<<<< COST >>>>>		>>>>> TOTAL
			LOCAL	FOREIGN	LOCAL	FOREIGN	
Superstructure (Timber; Span 3m; IOT)	m2	0.00	52,702	2,727	0	0	0
Superstructure (Timber; Span 5m; IOT)	m2	112.00	58,376	3,012	6,538,112	337,344	6,875,456
Superstructure (Timber; Span 8m; IOT)	m2	24.00	77,325	3,961	1,855,800	95,064	1,950,864
Superstructure (Timber; Span 3m; BH50)	m2	0.00	65,349	3,373	0	0	0
Superstructure (Timber; Span 5m; BH50)	m2	0.00	71,346	3,658	0	0	0
Superstructure (Timber; Span 8m; BH50)	m2	0.00	90,487	4,632	0	0	0
Superstructure (Concrete; Span 3m; BH50)	m2	0.00	52,924	171,810	0	0	0
Superstructure (Concrete; Span 5m; BH50)	m2	0.00	53,980	192,600	0	0	0
Superstructure (Concrete; Span 8m; BH50)	m2	0.00	55,318	210,151	0	0	0
Superstructure (Concrete; Span 10m; BH50)	m2	0.00	60,222	239,232	0	0	0
Superstructure (Concrete; Span 15m; BH50)	m2	0.00	64,324	282,524	0	0	0
Substructure (Pier; for Timber; IOT)	NO	2.00	458,897	25,168	917,794	50,336	968,130
Substructure (Abut; for Timber; IOT)	NO	10.00	1,200,388	128,063	12,003,880	1,280,630	13,284,510
Substructure (Pier; for Timber; BH50)	NO	0.00	674,875	37,274	0	0	0
Substructure (Abut; for Timber; BH50)	NO	0.00	1,362,835	140,846	0	0	0
Substructure (Pier; for Concrete; BH50)	NO	0.00	1,393,463	487,788	0	0	0
Substructure (Abut; for Concrete; BH50)	NO	0.00	2,948,676	1,017,596	0	0	0
Demolition of Bridge (Timber->Timber)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Timber->Concrete)	m2	0.00	14,316	1,106	0	0	0
Demolition of Bridge (Concrete)	m2	0.00	73,686	121,003	0	0	0
Maintenance of Timber Bridge (New)	m2	136.00	9,334	954	1,269,424	129,744	1,399,168
Maintenance of Concrete Bridge (New)	m2	0.00	1,822	4,303	0	0	0
Maintenance of Timber Bridge (Exist)	m2	0.00	8,203	2,322	0	0	0
Maintenance of Concrete Bridge (Exist)	m2	0.00	3,900	2,705	0	0	0
(Without Overhead)			TOTAL COST (Timber Bridge)		21,315,586	1,763,374	23,078,960
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		21,315,586	1,763,374	23,078,960
(Overhead : 15%)			TOTAL COST (Timber Bridge)		24,512,924	2,027,880	26,540,804
			(Concrete Bridge)		0	0	0
			TOTAL COST (without Maintenance)		24,512,924	2,027,880	26,540,804

JICA