


付 属 資 料



目 次


付 属 資 料 1

1-1	中間報告書	115
1-2	Record of Discussion	139
1-3	WARC 周波数割当	143
1-4	放送区域〔60 dB ($\mu\text{V}/\text{m}$)〕推定の根拠	149
1-5	電測データ	151
1-6	プロフィール図	155
1-7	大地導電率測定データ	163
1-8	付帯工事費	167
1-9	ボーリングラボテスト結果	171
1-10	消費者物価指数	187
1-11	気象データ	191

付 属 資 料 2

	要員および訓練計画	201
--	-----------	-----

付 属 資 料 1



17 June, 1979

Mr. Bhogya Prasad Shah,
Acting Director General,
Department of Broadcasting,
Ministry of Communications,
His Majesty's Government of Nepal.

Dear Sir,

Re: Establishment Programme of Medium Wave
Broadcasting Network in the Kingdom of
Nepal

I have the honour to submit herewith the Interim Report
of the Preliminary Design Study on the afore mentioned
subject.

Yours faithfully,

Seikichi Sakakibara,
The Leader,
Japanese Study Team.

INTERIM REPORT OF THE PRELIMINARY DESIGN STUDY
ON
THE ESTABLISHMENT PROGRAM OF MEDIUM WAVE BROADCASTING NETWORK
IN
THE KINGDOM OF NEPAL

JUNE 1979

JAPAN INTERNATIONAL COOPERATION AGENCY

CONTENTS

1. INTRODUCTION
2. RESULT OF STUDY
 - 2-1. BASIC PLAN
 - 2-2. FACILITY PLAN
 - 2-3. BUILDING PLAN
 - 2-4. SERVICE AREA ESTIMATION
 - 2-5. CONSTRUCTION SCHEDULE
 - 2-6. PERSONNEL PLAN & TRAINING PROGRAM
 - 2-7. INFRA STRUCTURE

APPENDIX

1. CONSTRUCTION SITE

INTRODUCTION

In response to the request of His Majesty's Government of Nepal, the Government of Japan despatched a mission to the Kingdom of Nepal from the 24th of May to the 22nd of June, 1979, for Preliminary design study on the establishment programme of Medium Wave Broadcasting Network in the Kingdom of Nepal. The survey team, with the cooperation of Radio Nepal Staff, carried out the necessary field survey and studies over three weeks to obtain the data to make up a preliminary design report for the establishment programme.

As for the matter of the result of the survey is concerned, according to the Scope of Work for the Preliminary Design Study on the programme, completed in the Draft Final Report, and a team will be despatched to the Kingdom of Nepal for supplementary explanation of the said report.

It is expected that the result of this survey will be useful not only for the establishment programme of the Broadcasting services, but also for the enhancement of friendly cooperation between the Kingdom of Nepal and Japan.

Finally, the members of the survey team wish to express their sincere thanks to the staff of the Department of Broadcasting, Ministry of Communications, and all other organizations concerned for the friendly cooperation they have provided to the Mission.

2-1 BASIC PLAN

According to the Objective of Study Which is established in the Scope of Work for Preliminary Design Study on the programme:

- 1) Transmitter Station of 100 KW with an emergency transmitter is planned in Kathmandu and Pokhara, based upon field measurement survey and other essential survey, for expansion of the Medium Wave Broadcasting Service in Central and Western Development Zone.

As for the Studio facility:

- 2) A Studio centre of 1000 m² class accommodating 5 Studios is planned in Kathmandu to meet increasing demand of broadcasting production capacity. And the Studio Centre will be annexed to the existing Broadcasting House as far as broadcasting operation is concerned.
- 3) In Pokhara Transmitter Station, a production studio is planned to meet a need of local continuity operation or recording programme.
- 4) In addition, a Sound O.B. (Out side Broadcasting) Wagon is planned for a demand of O.B. recording programme covering Far Western Development Zone.
- 5) A STL and Engineering link is planned with UHF & VHF facility between studio center and transmitter station in Kathmandu because the site of transmitter lies on suburb of Kathmandu, and of the length of the span between them.

(3)

2-2 FACILITY PLAN

The plan of each complex is listed as follows, which is classified in group:

(4)

(1) KATHMANDU TRANSMITTER STATION

<u>NO:</u>	<u>DESCRIPTION</u>	<u>QUANTITY</u>
(1-1)	1. Transmitter 100KW	1
	2. Transmitter (Stand-by) 10KW	1
(1-2)	Attached Equipment	1 set.
(1-3)	Antenna (100 m Guyed Mast)	1
(1-4)	Power supply Equipment & Engine Generator (35KVA)	1 set.
(1-5)	STL (UHF Multiplex & VHF Engineering Link)	1 set.
(1-6)	-	-
(1-7)	Measuring Equipment & Tool	1 set.
(1-8)	Installation Material	1 set.
(1-9)	Spare Parts	1 set.
(1-10)	Building 600 Sq.m class.	1

(5)

(2) POKHARA TRANSMITTER STATION

<u>NO:</u>	<u>DESCRIPTION</u>	<u>QUANTITY</u>
(2-1)	1. Transmitter 100KW	1
	2. Transmitter (stand-by) 10KW	1
(2-2)	Attached Equipment	1 set
(2-3)	Antenna (100 m Guyed Mast)	1
(2-4)	Power Supply Equipment & Engine Generator (35 KVA)	1 set
(2-5)	-	-
(2-6)	Studio Facility	1 set
(2-7)	Measuring Equipment & Tool	1 set
(2-8)	Installation Material	1 set
(2-9)	Spare Parts	1 set
(2-10)	Building 600 Sq.m class	1
(2-11)	O.B. Van	1 set

(6)

(3) KATHMANDU STUDIO CENTRE

<u>NO:</u>	<u>DESCRIPTION</u>	<u>QUANTITY</u>
(3-1)	Master Control Facility (with X-tal Clock System & Continuity Production Facility)	1 set
(3-2)	Studio Control Facility	4 set
(3-3)	Power Supply Equipment & Engine Generator (50 KVA Effective)	1 set
(3-4)	Measuring Equipment & Tool	1 set
(3-5)	Installation Material	1 set
(3-6)	Spare Parts	1 set
(3-7)	Building 1000 sq.m class.	1

2-3 BUILDING PLAN

2-3.1 Fundamental Design Concept

- a. The basic building plan of the Studio Centre and the Transmitter Stations are based upon the result of the survey.
- b. The plan of Preliminary Design will be completed according to the basic building plan. However, should modification and/or amendments take place by Engineering design and/or by the arrangement of equipment, except considerable modifications in floor area and/or number of rooms.
- c. Furniture for the above mentioned building will not be included in the drawing of preliminary design.

2-3.2 Site Plan & Survey Map

As for the plan concerned, refer to attached drawings (Fig. 1 - Fig. 6). The site area shown on the Survey Maps occupy minimum area for the purpose.

2-3.3 Floor Plan

As for the plan concerned, refer to attached drawings (Fig. 7 - Fig. 9). The Studio Centre and Transmitter Stations are designed one-storied building.

2-3.4 STRUCTURE PLAN

1. Applied Standards

- a. A.I.J.* Standards of reinforced concrete Structures.
 - b. A.I.J. Standards of Steel structures.
 - c. A.I.J. Standards of foundation structures.
 - d. J.I.S.**
 - e. Other applicable Japanese standards.
- * A.I.J. (Architectural Institute of Japan)
** J.I.S. (Japan Industrial Standards)

2. Type of Structures:

a. Building.

Frame, roof and floor slab, foundation and quake resisting wall will be of reinforced concrete structure.

b. Tower. (Guy Type)

Mast and Guy will be of steel. Foundation will be of reinforced concrete structure.

3. Allowable Soil Bearing Capacity

Allowable soil bearing capacity will be decided according to the result of soil investigation or other data.

2-3.5 Finishing

The material of all external and internal finish will be selected on the point of functional and economical.

Special acoustic treatment is required in every Studio and Control Room.

2-3.6 BUILDING EQUIPMENT PLAN

1. Airconditioning, Heating & Ventilation

The airconditioning system will be provided for Musical Studio and Master Control Room. The mechanical ventilation and heating system will be installed for other various rooms. The heating source will be supplied by electricity.

2. Plumbing

Water will be supplied by city-water. Sewage pipe will be connected to a septic-tank, and after it is purified, water will be lead to existing drain-gutter with another drainage pipe.

Fire hydrant equipment will be provided too.

3. Power Arrangement

The following equipment will be provided:

- a. Lighting and Plug socket system.
- b. Motor power distribution system.
- c. Earthing and Lightning Conductor system.
- d. Alarm system.
- e. Main line conduit works for Broadcasting.
- f. Conduit works for telephone system.
- g. Conduit and wiring works for clock system.
- h. Installation of various broadcasting boards.

2-4 SERVICE AREA ESTIMATION

To estimate service area in case that 100 KW transmitting station were established in Kathmandu and Pokhara, the field strength of existing Kathmandu Station (FC = 792 KHZ, Po = 100KW) was measured in Southern Terai District and on the way to Pokhara at several points. The field strength was calculated based upon Ground Conductivity which was estimated by Mr. Hendriks, I.T.U. Expert; and the data which was the result of measurement done by the Study Mission.

Table 1 shows the result of the field strength measurement of existing Kathmandu Station.

Ground Conductivity of 3 sites was measured in proposed Kathmandu, Pokhara Transmitter Station. The summary is shown as follows:

KATHMANDU (Prop. Site)	POKHARA (Prop. Site)	JANAKPUR (JADP)
About 1m ^S /m	About 0.5m ^S /m	About 1.5 m ^S /m

The result of estimated service area in field strength 1 micro V/m (60 dB/micro V/m is shown on Fig. 10.

TABLE 1

Survey of Field Strength
Kathmandu Station
(792 KHz, 100KW)

NUMBER (c.f. map)	PLACE	TIME	FIELD STRENGTH (dB/micro V/m)	REMARKS
1	10km from NAUBISE	D	61	
2	PALUNG	D	63	
3	DAMAN VIEW TOWER	D	70	
4-1	HETAUDA	M	53±5	
4-2	"	D	43 *1	*1 Behind the mountain.
4-3	"	E	55	
4-4	"	N	59±5	
5	ADHABAR	D	44 *2	*2 In the Jungle
6-1	BIRGUNJ	E	57	
6-2	"	N	59	
7	BAGMATI RIVER	D	53	
8-1	MAHUWA (JADP)	D	50	
8-2	"	E	48±5	
9	JANAKPUR	D	51	
10	NAUBISE	D	80	
11	SIMPANI	D	62	
12	BENIGHAT	D	55	
13	KURINGHAT	D	51	
14	POKHARA	E	45±5	

* Symbols are as follows:

M : Morning Time.
D : Day Time.
E : Evening Time.
N : Night Time.

(12)

2-5 CONSTRUCTION SCHEDULE


The construction schedule is attached herewith.

The total construction period is estimated 24 months from the date of Contract on the program.

TABLE 2

CONSTRUCTION SCHEDULE

PROJECT \ MONTH	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
1. KATHMANDU STUDIO CENTER																									
1 EQUIPMENT																									
2 BUILDING																									
2. KATHMANDU TRANSMITTER STATION																									
1 EQUIPMENT																									
2 BUILDING																									
3 ANTENNA																									
4 ANTENNA FOUNDATION																									
3. POKHARA TRANSMITTER STATION																									
1 EQUIPMENT																									
2 BUILDING																									
3 ANTENNA																									
4 ANTENNA FOUNDATION																									



(14)

- 2-6 Personnel Plan and Training Program.
2-6-1 Personnel Plan

Requested Staff Organization Chart to cope with the expansion of the broadcasting services due to the construction project, a tentative plan is proposed from Radio Nepal, which is listed as follows:

(1) New Studio Complex	Grand total	63		
Engineer (in-charge)		1		
(1-1) Operation Group	Total	40		
	M.	D.	N.	Sub total
1) Assistant Engineer (one per shift)	1	1	1	3
2) Supervisors	1	1	1	3
3) Technical Assistant	5	5	5	15
4) Junior Tech. Asst.	4	4	4	12
5) Mechanics	1	1	1	3
6) Peon	1	2	1	4
(1-2) Maintenance & O.B. Group	Total	22		
1) Asst. Engineer				2
2) Technical Assistants				10
3) Junior Tech. Assistants				6
4) Mechanics				2
5) Peon				2
(2) Pokhara Studio	Grand Total	16		
(2-1) Operation Group	Total	9		
	M.	D.	N.	Sub Total
1) Shift Supervisor (Technician)	1	1	1	3
2) Tech. Assistant	1	1	1	3
3) Junior Tech. Assistants	1	1	1	3
(2-2) Maintenance & O.B. Group	Total	7		
1) Asst. Engineer (Studio Maintenance)				1
2) Tech. Asst.				2
3) Junior Tech. Asst.				2
4) Mechanics				2

(15)

(3) M.W. Transmitter Station Kathmandu/Pokhara Grand Total
123 Engineer (in-charge)

Each Station Total 61

(3-1)	Operation Group	Total 24	M.	D.	N.	Sub total
	1) Shift Engineer		1	1	1	3
	2) Shift Supervisor (Technician)		1	1	1	3
	3) Tech. Assistant		2	2	2	6
	4) Junior Tech. Asst.		2	2	2	6
	5) Mech. J.T.A.		1	1	1	3
	6) Mechanics		1	1	1	3
(3-2)	Maintenance Group	Total 18				
	1) Asst. Engineer (Maintenance)	1				
	2) Tech. Asst. (Radio)	3				
	3) Tech. Asst. (Electrical)	2				
	4) Tech. Asst. (Mechanical)	2				
	5) Junior Tech. Asst.	4				
	6) Mech. J.T.A.	2				
	7) Mechanics	4				
(3-3)	Tech. Administration Group	Total 19				
	1) Senior Clerk (NASU) (Administration)	1				
	2) Senior Clerk (NASU) (Stores)	1				
	3) Junior Clerk (Administration)	2				
	4) Junior Clerk (Stores)	4				
	5) Typist	2				
	6) Driver	1				
	7) Gardener	2				
	8) Peon	6				
						Grand Total
						of the Staff - 202

2-6-2 Training Program.

To cope with the expansion of the broadcasting service, following plan was proposed from Radio Nepal:

1) Pre-Installation Training

	Studio Center	Kathmandu TX	Pokhara TX	Concurrent	Total
1) Engineer	2	2	2	2	8
2) Technician	3	1	6		9

(2) Post - installation training (each year for 5 consecutive years)

- 1) Engineer 2
- 2) Technician 4

(3) Program producer training.

1st year	4
2nd year	2
3rd "	2
4th "	2
5th "	2
Total	12

(4) In - country training.

Expert service will be requested from the Government of Nepal to the Government of Japan. The service will cover the operation, maintenance and planning of the broadcasting system and facilities in addition to the in-country trainings. Terms and conditions are confirmed on the service.

2-7 INFRASTRUCTURE

As for the infrastructure which is required for the programme, fundamentally, construction schedule does not cover its arrangement and budget. However, the capacity of some supply is estimated as follows:

1. Electric Main Supply:

Kathmandu Studio Centre - 150 KVA
 Kathmandu Transmitter Station - 600 KVA
 Pokhara Transmitter Station - 600KVA

2. City Water Supply: (cf. P.74)

Kathmandu Studio Centre - 10 Ton/day
 Kathmandu Transmitter Station - 5 Ton/day
 Pokhara Transmitter Station - 5 Ton/day

The following items are to be completed prior to the beginning of the schedule:

1. Each construction site shall be cleared completely.
2. Land leveling of the site.
3. Access road.
4. If necessary, fence around the site and the gate.
5. Electric power supply shall be completed at a top point (6600V).
6. Necessary telecommunication channels are to be provided to the site.
7. Water supply and incidental drainage arrangement including complete sanitary facility.

APPENDIX 1

The place of the construction site

(1) Kathmandu Transmitter Station (Sainbu)

- 1) Location: Lalitpur, Kathmandu
- 2) Longitude: 85 degree 18' 30" E
- 3) Latitude: 27 degree 39' 10" N
- 4) Altitude: 1351 m A.S.L.*

(2) Pokhara Transmitter Station


- 1) Location: Male patan, Pokhara
- 2) Longitude: 83 degree 59' 00" E
- 3) Latitude: 28 degree 13' 10" N
- 4) Altitude: 902 m A.S.L.

(3) Kathmandu Studio Centre

- 1) Location: Singh Durbar, Kathmandu
- 2) Longitude: 85 degree 19' 35" E
- 3) Latitude: 27 degree 41' 45" N
- 4) Altitude: 1285 m A.S.L.

The above listed indication are decided by Radio Nepal, While, altitude of each site is referred to map sheet 10 (Kathmandu) which is a blue print sheet in Radio Nepal, and map sheet 7 (Pokhara) which is a blue print sheet in Department of Housing & physical Planning, H.M.C.

* A.S.L. (Above sea level)




RECORD OF DISCUSSION BETWEEN THE JAPANESE
STUDY TEAM AND THE DEPARTMENT OF BROADCASTING
HMG OF NEPAL FOR THE PRELIMINARY DESIGN STUDY
ON THE ESTABLISHMENT PROGRAMME OF MEDIUM WAVE
BROADCASTING NETWORK IN THE KINGDOM OF NEPAL.

Attached herewith is the "Record of discussion" that
has been agreed between the Japanese Study Team and the Department of
Broadcasting, H. M. G. of Nepal for afore-mentioned subject.

It should be noted that this "Record of Discussion" does
not legally bind both Governments.



Seikichi Sakakibara
The Leader
Japanese Study Team



Bhogya Prasad Shah
Acting Director General
Department of Broadcasting
(Radio Nepal)
Ministry of Communications
His Majesty's Government of Nepal.

Kathmandu

Dated the 18th June 1979.

RECORD OF DISCUSSION

Following points were discussed and agreed upon by the Preliminary Design Survey Team (24th May to 22nd June 1979) of the Japan International Co-operation Agency and the Officials of the Department of Broadcasting, His Majesty's Government of Nepal.


- 1) Based upon Field Measurement Survey, Transmitting Stations of the 100 KW Power each complete with necessary equipments and Building have been planned at Kathmandu and Pokhara with emergency Transmitters of 10 KW power backed up by Engine Generator for expansion of the Medium Wave Broadcasting Service in the Central and Western Development Regions.
- 2) A studio Centre accomodating 5 studios with all necessary equipments and building has been planned in Kathmandu to meet the increasing demand of broadcasting production capacity. This will also have Standby Engine Generator.
- 3) In Pokhara Transmitting Station, a production studio has been planned to meet the needs of local continuity operation or recording programme. In addition, a sound outside broadcasting wagon has also been planned for Pokhara station.
- 4) A studio to transmitter link and engineering link with UHF and VHF facility between Studio Centre and the proposed transmitting station in Kathmandu has been planned.
- 5) The following requirements of the Department of Broadcasting, HMG of Nepal were taken note of by the Japanese Team : -
 - i) Studio complex at separate location in Pokhara.
 - ii) Sound Outside Broadcasting Wagon for Kathmandu Studio Centre.
 - iii) Necessary equipment for news monitoring.
 - iv) Requirement of station vehicles during and after installation.

- 6) Personnel Plan and Training Programme to cope with the expansion of the broadcasting services were also discussed. It was agreed that an official request should be made by HMG through proper channels to the Japanese Government for the training of Radio Nepal's technical and production staff in Japan and for the services of an Expert for in-country training as well as to assist the Department in operation, maintenance and planning for a period of 2 years.
- 7) The total construction period of the project was estimated as 24 months from the date of contract on the programme.
- 8) As for the infrastructure, which is required for the Programme, the following items are to be completed by HMG Nepal prior to the beginning of the construction schedule :
 - i) Acquisition of necessary land area at construction sites.
 - ii) Access Roads.
 - iii) Site Clearance, levelling and drainage.
 - iv) Security Fencing and gate.
 - v) Water supply and facility.
 - vi) Electric Power Supply at drop point. The drop point should be, according to Japanese Standard, either at 400 V, or 3.3 KV or 6.6 KV but not 11 KV.
 - vii) Necessary Programme and Engineering Link (including necessary converter equipments) from Kathmandu Studio Centre to Pokhara Transmitting Station shall be arranged and provided.
- 9) Necessary ancillary equipment, test and measuring equipment, tools and spare parts have been planned for the three stations.



付属資料 1 - 3 WARC周波数割当

主官庁会議，最終文書，第1付属書に基づく，ネパール王国への周波数割当て。



M/F CHANNEL PLAN


Table A1-3-1

Final Acts of the Regional administrative LF/MF Broadcasting Conference (Regions 1 and 3) Geneva, 1975.
Annex 1, Plan for the Assignment of Frequencies to Broadcasting Stations in the Medium Frequency Bands.
(other than to stations using Low-Power Channels)

	Assigned frequency (kHz)	Name of transmitting station	Country symbol	Geographical coordinates of transmitting station	Necessary bandwidth (kHz)	Carrier power (kw)	Authorized radiation		Restrictions on radiation (For directional antennas only)		Antenna		Ground conductivity (mS/m)	Hours of operation (GMT)	Remarks
							Maximum radiation (dB)	Azimuth of maximum radiation	Azimuths defining the sector of limited radiation	Maximum radiation in the sector (dB)	Type	Height (m)			
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
36	792	KATMANDU	NPL	85E20 27N45	A20	100	20.4				A	100	4	2200-1900	
46	1503	KATMANDU	NPL	85E20 27N45	A20	50	17.4				A	50	4	2200-1900	
39	684	POKHRA	NPL	83E58 28N16	C 9	100	20.4				A	120	4	2200-1900	
23	855	POKHRA	NPL	83E58 28N16	A20	10	10.6				A	120	4	2200-1900	
32	576	SURKHET	NPL	81E38 28N36	A20	100	20.4				A	120	4	2200-1900	
51	900	SURKHET	NPL	81E38 28N36	A20	20	13.6				A	120	4	2200-1900	
44	648	DHANKUTA	NPL	87E19 27N00	A20	100	20.4				A	120	4	2200-1900	
30	765	DHANKUTA	NPL	87E19 27N00	A20	100	20.6				A	120	4	2200-1900	
31	810	DANDEL DHURA	NPL	80E35 27N18	A20	10	10.4				A	60	4	2200-1900	
53	1143	DHALKEBAR	NPL	86E02 26N58	A20	10	10.4				A	60	4	2200-1900	
24	729	BUTAWAL	NPL	83E29 27N42	A20	1	0.4				A	60	4	2200-1900	

Appendix 1 to the Plan, Frequency Assignments to Stations in the Low-Power Channels.

	Assigned frequency (kHz) (Channel number)	Name of transmitting station	Country symbol	Geographical coordinates of transmitting station	Necessary bandwidth (kHz)	Carrier power (kw)	Effective monopole radiated power (e.m.r.p.) (kw)	Antenna height (m)	Ground conductivity (mS/m)	Hours of operation (GMT)	Remarks
	1	2	3	4	5	6	7	8	9	10	11
1	1485	BAJURA	NPL	81E22 29N22	A20	1	0.50	60	5	2200-1900	
2	(107)	GORKHA	NPL	84E38 27N02	A20	1	0.50	60	5	2200-1900	
3	1485	KAIGAON	NPL	82E48 29N02	A20	1	0.50	60	5	2200-1900	
4	1485	RAMECHHAP	NPL	86E04 27N20	A20	1	0.50	60	5	2200-1900	
51	1584	BAJURA	NPL	81E22 29N22	A20	1	0.50	60	5	2200-1900	
52	1584	GORKHA	NPL	84E38 28N02	A20	1	0.50	60	5	2200-1900	
53	1584	KAIGAON	NPL	82E48 29N02	A20	1	0.50	60	5	2200-1900	
54	1584	RAMECHHAP	NPL	86E04 27N20	A20	1	0.50	60	5	2200-1900	
12	1602	BAJURA	NPL	81E22 29N22	A20	1	0.50	60	5	2200-1900	
13	1602	GORKHA	NPL	84E38 28N02	A20	1	0.50	60	5	2200-1900	
14	1602	KAIGAON	NPL	82E48 29N02	A20	1	0.50	60	5	2200-1900	
15	1602	RAMECHHAP	NPL	8-E04 27N20	A20	1	0.50	60	5	2200-1900	



付属資料 1-4 放送区域 (60 dB ($\mu\text{V}/\text{m}$)) 推定の根拠

主官庁会議、付属技術資料で提案された方法により計算したネパール王国における電界強度の最小値は $60\text{ dB}/0\text{ dB} = 1\ \mu\text{V}$ (at 1MHz), 公称実用電界強度 (E_{nom}) は, 昼間地表サービス値 63 dB , 夜間地表サービス値は, 田園地帯に於いて 71 dB , 都市地域に於いては 77 dB となっている。

また日本に於ける受信機の種別感度を調べた結果を下表に示した。また今回調査した南部 Terai 地域における実聴結果などを総合して, 放送サービス区域を電界強度 60 dB ($0\text{ dB} = 1\ \mu\text{V}/\text{m}$) の範囲と推定した。

Table A 1-4-1

機 種	ポータブル形	カセットテープ レコーダ付ラジオ	ホームラジオ	カーラジオ
(注) 雑音制限感度 (dB)	49 ~ 76	54 ~ 60	58 ~ 59	35 ~ 37

(注) $S/N = 30\text{ dB}$ で標準出力を得る最低の信号入力 ($0\text{ dB} = 1\ \mu\text{V}/\text{m}$)

「標準放送用受信機の性能調査 (電波技術協会, 調査委員会 1977.5)」より抜すい。

付属資料 1-5 電測データ

Kathmandu～南部Terai 地域に至る電測結果

Table A 1-5-1 Kumartar 10KW (Kathmandu) 電波電測結果。

Table A 1-5-2 同地域に於ける外来電波の強度電測結果。

Table A1-5-1

Survey of Field Strength (Kathmandu Station 792 kHz, 10 KW)

- 30. May ~ 9. Jun/1979 -

Item No: cf. Map	Place	Time	Field Strength (dB/μV)	Remarks
1.	Metrang.	D 10:50 ~	61	Naubise → 10 km South
2.	Palung	" 11:55 ~	63	120 km to Raxaul
3.	Bhase Dhobau	" " "	70	Himalaya View Tower top (≈ 8000 ft high)
4.- (1)	Hetauda	M 6:00 ~ 45	53±5	Fading
-(2)	"	D 13:25 ~	43	at the River, Behind the mountain (Cf. Fig. A6-1)
-(3)	"	E 18:15 ~ 45	55	17:00 E=54 dB
-(4)	"	N 21:45 ~	59±5	Fading
5.	Adhabar	D 9:55 ~	44	In the jungle
6.- (1)	Birganj	D 16:15 ~ 30	57	Hotal SAMJANA top (Cf. Fig. A6-2)
-(2)	"	N 21:30 ~	59	Light Fading
7.	Bagmati River	D 12:10 ~ 30	53	River West Side (Cf. Fig. A6-3)
8.- (1)	Mahuwa (JADP)	D 11:00 ~	50	
-(2)	"	E 18:55 ~	48±5	Fading (4 ~ 5" cycle), about 1 kHz Beet.
9.	Janakpur	D 13:40 ~	51	Airport
10.	Naubise	D 10:20 ~	80	(Cf. Fig. A6-4)
11.	Simpani	" 11:00 ~	62	
12.	Benighat	" 12:00 ~	55	
13.	Kuringhat	" 12:41 ~	51	
14.	Pokhara	E 18:30 ~	45±5	

Table A1-5-2

Survey of Field Strength (Another Station)

Item No:	Place & Time	Frequency (kHz) *1	Field Strength (dB/μV)	Remarks				other freq. nothing						
	Hetauda M (6:00 ~)	915	50 ~ 60	Fading	Bagmati Rv. (Birganj-Janak.) D (12:10)	675	37							
		1243	39 ~ 46	"										
		1340	25	"										
	E (18:15 ~)	1449	30 ~ 35	"	Janakpur (JADP) E (18:55 ~)	660	55 ~ 70							
		915	62	Prog. India	(Air Port) D (13:40 ~)	695	64							
		1135	65	"		1140	58							
	D (13:25 ~) River	915	62	40	Prog. India China?	Pokhara E (18:40 ~)	620	60	(Kathmandu)					
			1135	40	"									
			1340	40	"									
		N (21:45)	915	49	49					With about 1 kHz Beet				
				595	~ 50 ~					Prog. India, Fading	620	54±2		
				715	53					"	660	51±3		
840				43±2	" , Calcutta?					695	50±1	Noisy, Fading		
915				70±3	"					820	43±3	Fading		
975				~ 63 ~	"					915	50±5			
1135				~ 73	"					985	41±2			
3425				70±10	"					1010	51			
5005				60±10	"					1060	50			
Birganj D (16:15 ~) N (21:30 ~)	595			55	55	Prog. India								
				915	72	"	1140	70±5	Noisy					
				985	60±2	"	1240	47±2	Fading (3 ~ 5" cycle)					
		1090	55±1	"	1270	42±5	Noisy							
		1140	75±4	"	1300	47±10	Fading (deep)							
		3425	75±7	"	1340	52±2								
		5005	70±5	"	1450	51±3								
					1600	40	Noisy							
					3425	75±6	R. Nepal							
					5005	75±8	Fading (0.5 ~ 1" cycle)							

付属資料 1-6 プロフィール

Kathmandu 盆地内に送信所を置いた場合のプロフィール例。

Fig. A 1-6-1	Kathmandu	→	Hetauda .
Fig. A 1-6-2	Kathmandu	→	Birganj .
Fig. A 1-6-2'	Kathmandu	→	Uuti - Birganj .
Fig. A 1-6-3	Kathmandu	→	Malangwa .
Fig. A 1-6-3'	Kathmandu	→	Anti - Malangwa .
Fig. A 1-6-4	Kathmandu	→	Gurka, Pokhara .




Fig. 1-6-1. Profile of Kathmandu → Hetauda Section




Fig. 1-6-2. Profile of Kathmandu to Birganj Section

Height (ASL)
(m + 914m)




Fig. 1-6-2'. Profile of Kathmandu → Anti-Birganj Section




Fig. 1-6-3. Profile of Kathmandu → Malangwa Section




Fig. 1-6-3'. Profile of Kathmandu → Anti-Malangwa Section







Fig. 1-6-4. Profile of Kathmandu → Gurkha, Pokhara Section 240

付属資料 1-7 大地導電率測定データ

Kathmandu, Pokhara および Janakpur に於ける大地導電率測定結果。

Fig. A 1-7-1 Result of Grand-Conductivity Measurement.






Note:

Measurement Instrument : Type 3244 (Yokogawa Electric Co.)

Fig. A1-7-1. Result of Grand Conductivity Measurement



付属資料 1-8 付帯工事費概算

(1) 給電点(Drop Point)迄の配電線工事および給電点における接続工事

Kathmandu 演奏所

配電線	0.5 Km × 60,000 Rs	=	30,000 Rs
引込関係	50 m × 1,000 Rs	=	50,000 Rs
トランス	150 KVA 11KV/400V	=	100,000 Rs
			計 180,000 Rs

Kathmandu 送信所

配電線	1.5 Km × 90,000 Rs	=	135,000 Rs
引込関係	150 m × 1,000 Rs	=	150,000 Rs
トランス	600 KVA 11KV/400V	=	200,000 Rs
			計 485,000 Rs

Pokhara 送信所

配電線	1.0 Km × 60,000 Rs	=	60,000 Rs
引込関係	200 m × 1,000 Rs	=	200,000 Rs
トランス	600KVA 11KV/400V	=	200,000 Rs
			計 460,000 Rs

小計 1,125 Th. Rs

(20,812,5千円)

(2) 給水工事および給水点における接続工事。

Kathmandu 演奏所	50 m × 200 Rs	=	10,000 Rs
Kathmandu 送信所	2,000 m × 120 Rs	=	240,000 Rs
Pokhara 送信所	1,000 m × 120 Rs	=	120,000 Rs
			計 370 Th. Rs

(6,845千円)

(3) 建設現場の土地取得関係費

Kathmandu 送信所	$\frac{44,400}{506.25}$	Ropani × 10 Th. Rs =	877 Th. Rs
---------------	-------------------------	----------------------	------------

Pokhara 送信所	$\frac{50,870}{506.25}$	Ropani \times 20 Th. Rs = 2,010 Th. Rs
		計 2,887 Th. Rs
		(53,409.5 千円)

(4) 建設現場の土木工事

Kathmandu 演奏所	$1,300 \text{ m}^2 \times 30 \text{ Rs} =$	39, Th. Rs
Kathmandu 送信所	$\frac{44,400}{506.25}$	Ropani \times 1, Th. Rs = 88, Th. Rs
Pokhara 送信所	$\frac{50,870}{506.25}$	Ropani \times 1, Th. Rs = 100, Th. Rs
		計 227, Th. Rs
		(4,199.5 千円)

(5) 取付道路

Kathmandu 演奏所	$5 \text{ m} \times 1, \text{Th. Rs} =$	5, Th. Rs
Kathmandu 送信所	$170 \text{ m} \times 1, \text{Th. Rs} =$	170, Th. Rs
Pokhara 送信所	$250 \text{ m} \times 1, \text{Th. Rs} =$	250, Th. Rs
		計 425 Th. Rs
		(7,862.5 千円)

(6) 柵および門柱

Kathmandu 演奏所		0
Kathmandu 送信所	(柵) $810 \text{ m} \times 310 \text{ Rs} =$	251,100 Rs
	(門柱) 1ヶ所	25,000 Rs
Pokhara 送信所	$950 \text{ m} \times 380 \text{ Rs} =$	361,000 Rs
		計 662 Th. Rs
		(12,247 千円)

(7) 電気通信回線

ライン布設費

演奏所 ~ Kathmandu T. C. C.

6 Km 10P ケーブルを布設

材 料 費	150,000 Rs
工 事 費	120,000 Rs
	計 270,000 Rs

Pokhara T.C.C. ~ 送信所

4 Km

材 料 費	100,000 Rs
工 事 費	40,000 Rs
計	140,000 Rs

Channel Translator

1 対向 (MOD & DEM)

材 料 費	190,000 Rs
工 事 費	179,000 Rs
計	369,000 Rs
小 計	779 Th. Rs

(14,411.5 千円)

(8) 排水設備, 浄化槽および接続工事

Kathmandu 演奏所

排 水	150 m × 400 Rs =	60,000 Rs
浄化槽および排水		= 100,000 Rs

Kathmandu 送信所

排 水	500 m × 200 Rs =	100,000 Rs
浄 化 槽		= 30,000 Rs

Pokhara 送信所

排 水	150 m × 200 Rs =	30,000 Rs
浄 化 槽		= 30,000 Rs

計 350 Th. Rs


(6,475 千円)

合 計 6,825 Th. Rs

(12,626.25 千円)

付属資料 1-9 ボーリング ラボテスト結果


Tribhuwan University
Institute of Engineering
The Central Material Testing Laboratory




Report
on
Soil Investigation Programme of Medium Wave
Broadcasting Network Construction Site
Bhaisepati, Kathmandu.

Kathmandu Nepal

1979



Ref. No.




TRIBHUVAN UNIVERSITY
INSTITUTE OF ENGINEERING
CONSULTANCY SERVICES
ANANDANIKETAN, PULCHOWK
LALITPUR, NEPAL. Ph. 21636

Date

CONTENTS

<u>S.No.</u>		<u>Page No.</u>
1.	Introduction	1
2.	Purpose of Investigation Work.	1
3.	Site Inspection.	1
4.	Field Work.	2
5.	Ground Water Position.	2
6.	Description of Soil Strata.	2
7.	Recommendation.	3
8.	Appendix - 1	
9.	Appendix - 2	



TRIBHUVAN UNIVERSITY
INSTITUTE OF ENGINEERING
CONSULTANCY SERVICES
ANANDA NIKETAN, PULCHOWK
LALITPUR, NEPAL. Ph. 21636

No.

Date

Final Report
on
Soil Investigation Programme of Medium Wave
Broadcasting Network Construction Site
Bhaisepati, Kathmandu.

1) Introduction.

On the request of Japan International Co-operation Agency, Japan, The Institute of Engineering, Central Material Testing Laboratory proposed a programme of sub-soil investigation work of Medium Wave Broadcasting Network Construction Site at Bhaisepati in Kathmandu. The programme was approved by JICA, Japan and the work was carried out by the staff of Central Material Testing Laboratory. The approved programme included:

- a) Site Inspection.
- b) Field Work.
- c) Laboratory Testing.
- d) Recommendation.


2) Purpose of Investigation Work.

The purpose of soil investigation work was to reveal the soil conditions and obtain necessary data required to determine the bearing capacity of soil.

3) Site Inspection.

The site is located on a raised more or less level ground at a distance about 5 km. from Lalitpur town. It lies at the lower reach of Mahabharat range towards north and mainly is being used as a gravel quarry for local road construction.

F.T.O.



// 2 //

TRIBHUVAN UNIVERSITY
INSTITUTE OF ENGINEERING
CONSULTANCY SERVICES
ANANDANIKETAN, PULGHOWK
LALITPUR, NEPAL. Ph. 21636

Ref. No.

Date

4) Field Work.

The field work was started on 2nd June 1979 and completed on 14th June, 1979. A hard gravel stratum was encountered at elevation between 5.8 m to 15.5 m, so it was decided to terminate the bore hole at that point. An undisturbed sample was taken at elevation between 5.0 m to 5.8 m for direct shear test and at other elevations undisturbed samples could not be retrieved. The standard penetration test was conducted at every meter depth and altogether 13 disturbed samples were taken for laboratory tests.


5) Ground Water Position.

Position of ground water table could not be traced out upto investigated depth.

The laboratory testing work was done as per client's requirement. The results of laboratory testing has been supplied in the data summary sheet in the Appendix - 1.

7) Description of Soil Strata.

Between elevation 3.7 m to 5.0 m there is a layer of silt and clay sandwiched between two gravel layers at the top and underneath. The bore hole logs supplied in the Appendix - 2 gives the best representation of soil stratification, SPT values and natural moisture content.



// 3 //

TRIBHUVAN UNIVERSITY
INSTITUTE OF ENGINEERING
CONSULTANCY SERVICES
ANANDANIKETAN, POLCHOWK
LALITPUR, NEPAL. Ph. 21636

Ref. No.

Date

Recommendation

It is suggested to put down the foundation below elevation 5.0 m. The no. of blows at this depth is 27. Based on this value and using the curve prescribed by Terzaghi's and Peck for a 3 m. wide foundation, the safe bearing capacity for a maximum settlement of 25 mm comes to be 25 tons/m².

Again from the direct shear test made on the sample obtained at this depth, the value of $C = 1.7 \text{ ton/m}^2$ & $\phi = 37^\circ$.

For $\phi = 37^\circ$, the Terzaghi's Bearing Capacity Factors for local shear failure are :

$$N_c' = 30$$


$$N_q' = 14$$

$$N_r' = 10$$

Substituting relevant data in Terzaghi's equation we get,

$$\begin{aligned} \text{ult} &= 1.3 CN_c' + \gamma D_f N_q' + \frac{1}{2} b \gamma N_r' \\ &= 1.3 \times 1.7 \times 30 + 1.8 \times 5 \times 14 + \frac{1}{2} \times 3 \times 1.8 \times 10 \\ &= 66.3 + 126 + 27 \\ &= 219.3 \\ \therefore q_{\text{safe}} &= \frac{219.3}{3} \\ &= 73.3 \text{ t/m}^2 > 25 \text{ t/m}^2 \end{aligned}$$

\therefore Adopt safe bearing capacity = 25 t/m².



TRIBHUVAN UNIVERSITY
INSTITUTE OF ENGINEERING
CONSULTANCY SERVICES
ANANDANIKETAN, PULCHOWK
LALITPUR, NEPAL. Ph. 21636

Ref. No.

Date

APPENDIX - 1

TEST RESULT SHEET


Bore Hole No.:- 1 Project:- Medium Wave Broadcasting Net Work
 Location:- Bhaisan Patni. Radio Nepal
 Date:-

S. No	Depth in. m.	Sieve Analysis % passing				Atterberg Limits			Natural	Density		S.P.T. blows	Sp.Gr	Direct Shear		Consolidation			Compaction	
		Gravel %	Sand %	silt %	clay %	L.L.	P.L.	P.I.		Yw	Yd			C	σ_v	e_v	c_v	k		
2.	0.60 to 2.15	26	22	39	13							2.65								
3.	2.15 to 3.70	49	13	15	23							2.70								
4.	3.70 to 4.15	0.12	5.88	59	35	29.5	17.35	12.15				2.62								
5.	4.15 to 4.75	0.76	9.24	55	35	29.4	16.55	12.85				2.62								
6.	4.75 to 5.00	1.26	14.74	48	36	24.9	16.44	8.46				2.68								
7.	5.00 to 5.80	1.54	14.46	61	23	28	-	-				2.65	0.17	37°						
8.	5.80 to 6.75	47.45	9.55	18	25	-	-	-				2.645								

TEST RESULT SHEET

Bore Hole No.: - **1** Project: - **Medium Wave Broadcasting Net Work**
 Location: - **Dhaisen Fati.** Date: - **Radio Nepal**

S. No.	Depth m.	Sieve Analysis % passing			Atterberg Limits			Netu -ral	Density		S.P.T. Sp. Cr. blows	Direct Shear		Consolidation			Compaction
		Gravel %	Sand %	silt clay %	L.L.	P.L.	P.I.		W _v	Y _d		C kg/cm ²	Ø	a _v	m _v	e _v	
9	8.75 to 11.75	58.75	9.25	9	23						2.69						
10.	11.75 to 12.40	20	18	44	18						2.67						
11.	12.40 to 12.75	44	29	10	17						2.65						
12.	12.75 to 15.00	37	13	29	21						2.635						
13.	15.00 to 15.50	34.44	23.56	22	20						2.69						



TRIBHUVAN UNIVERSITY
INSTITUTE OF ENGINEERING
CONSULTANCY SERVICES
ANANDA NIKETAN, PULCHOWK
LALITPUR, NEPAL. Ph. 21636

Ref. No.

Date

APPENDIX - 2

MEDIUM WAVE BROADCASTING NETWORK
CONSTRUCTION SITE
BHAISENPATI, KATHMANDU

BORE HOLE LOG

1

1	2	3	4	5	6	7	8
SCALE OF DEPTH IN METER	DEPTH IN METER	THICKNESS OF STRATA IN METER	SOIL DESCRIPTION	SYMBOL	S. P. T. N. VALUE	N.C. /	REMARK
	0-60	0-60	VEGETABLE TOP SOIL	[Symbol]		10.71	
1.0		1-55	YELLOWISH GREY SILT WITH SOME SAND AND GRAVEL AND LITTLE CLAY	[Symbol]	N=28	9.64	WE TAKE S.P.T. AT EVERY 1 METER
2.0	2-15			[Symbol]	15CM/50 BLOWS 1CM/NEXT 5 BLOWS	28-24	
3.0		1-55	YELLOWISH GREY GRAVEL WITH LITTLE SAND AND SILT AND SOME CLAY	[Symbol]	17-5CM/50 BLOWS 0-5CM/NEXT 5 BLOWS	21-42	[Symbol] IT DENOTES S.P.T. AT THAT METER
4.0	3-70			[Symbol]	N=9	22-57	
5.0		1-30	BLACK TO YELLOWISH BROWN SILT AND CLAY WITH LITTLE SAND AND TRACES OF GRAVEL	[Symbol]	N=27	23-88	N INDICATES NO. OF BLOWS
6.0	5-80	0-80	YELLOWISH BROWN CLAYEY SILT WITH LITTLE SAND	[Symbol]	10-5CM/50 BLOWS 0-5CM/NEXT 5 BLOWS	8-42	
7.0				[Symbol]	12CM/50 BLOWS 0-5CM/NEXT 5 BLOWS	14-41	
8.0			YELLOWISH GREY SILT WITH SOME SAND AND LITTLE CLAY AND SOME GRAVEL	[Symbol]	9-8CM/50 BLOWS 0-2CM/NEXT 5 BLOWS	13-99	
9.0				[Symbol]	7CM/50 BLOWS 0-3CM/NEXT 5 BLOWS	12-34	
10.0				[Symbol]	20CM/50 BLOWS 0-8CM/NEXT 5 BLOWS	15-38	
BORE HOLE NO. 1			PREPARED BY THE CENTRAL MATERIAL TESTING LABORATORY	DRAWN BY: R. PANT			
			I. E. C. S.	CHECKED BY: R. K. POUDEL			
				DATE: 035/4/14			

BORE HOLE LOG CONTD.

2

1	2	3	4	5	6	7	8
11.0	5-95				0-8CM/50 BLOWS 0-0CM/NEXT 5 BLOWS	10-08	
12.0	11-75	0-65	BLACK TO YELLOWISH GREY SILT WITH LITTLE SAND GRAVEL AND CLAY		6-0CM/50 BLOWS 0-2CM/NEXT 5 BLOWS	15-66	
13.0	12-40				8-5CM/50 BLOWS 0-3CM/NEXT 5 BLOWS	12-12	
14.0		3-10	YELLOWISH WHITE TO LIGHT BLUE GRAVEL WITH SAND SILT AND CLAY		7-8CM/50 BLOWS 0-4CM/NEXT 5 BLOWS	10-12	
15.0	15-50				17CM/50 BLOWS 0-3CM/NEXT 5 BLOWS	20-35	
16.0							


BORE HOLE NO. 1	PREPARED BY	C. M. T. L.	DRAWN BY	R. PANT
		I. E. C. S.	CHECKED BY	R. K. POUDEL
			DATE	036/4/14


BORE HOLE NO.

DEPTH - 5.40m

C - 0.17 KG/CM²

θ - 37°






[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]

付属資料 1 - 10 消費者物価指数


(a) NATIONAL URBAN CONSUMER PRICE INDEX

(Base: FY 1972/73=100)




(b) URBAN CONSUMER PRICE INDEX
FOR
KATHMANDU

(Base: FY 1972/73 = 100)



(c) URBAN CONSUMER PRICE INDEX
FOR
POKHARA
(Base: FY1972/73=100)



[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]

Month	INDEX NO. 1030 STATION KATHMANDU AIRPORT YEAR 1971										PRECIPITATION mm.				
	AIR TEMPERATURE °C					RELATIVE HUMIDITY %		Total	Maximum in 24 hrs & date	Number of rainy days					
	Max.	Min.	Daily	Absolute extreme	Number of days	Observed at	≥ 30°			Max.	Min.	≥ 1.0	10.0	25.0	50.0
JAN	17.4	2.0	9.7	21.0 24.1	0	93	54	3	9/22	1	0	0	0	0	
FEB	19.2	2.7	11.0	22.9 16.2	0	84	45	6	6/28	1	0	0	0	0	
MAR	24.0	7.4	15.7	27.7 21.1	0	79	40	28	20/11	4	1	0	0	0	
APR	22.7	13.0	17.8	27.0 28.1	0	85	68	181	46/12	18	5	1	0	0	
MAY	25.1	15.1	20.1	28.2 29.1	0	79	62	110	19/15	17	3	0	0	0	
JUN	26.2	19.6	22.9	28.8 27.7	0	84	81	608	84/12	24	9	4	8	0	
JUL	26.9	20.0	23.4	29.6 28.1	0	83	79	205	30/14	25	17	7	1	0	
AUG	26.5	19.6	23.0	28.2 26.1	0	86	81	253	61/26	22	15	4	2	0	
SEP	26.2	17.9	22.0	28.5 20.1	0	85	78	36	11/5	9	6	1	0	0	
OCT	24.1	13.6	19.8	28.4 28.1	0	86	74	81	47/18	9	7	1	0	0	
NOV	20.6	6.7	13.6	23.2 25.5	0	92	65	0	0	0	0	0	0	0	
DEC	18.2	2.8	10.5	21.0 12.1	0	95	63	0	0	0	0	0	0	0	
Year	23.1	11.7	17.4	29.6 17.4	0	86	66	1511	84 Jun	190	87	26	13	4	

Month	INDEX NO. 1030 STATION KATHIMANDU AIRPORT YEAR 1972										PRECIPITATION mm.						
	AIR TEMPERATURE °C					RELATIVE HUMIDITY %					Total	Maximum in 24 hrs & date	Number of rainy days				
	Max	Min	Mean	Daily	Absolute extreme	Max. date	Min. date	Max. $\geq 30^\circ$	Min. $\leq 0^\circ$	Observed at			1.0	10.0	25.0	50.0	99.9
JAN	17.5	3.2	10.4	10.4	20.2	-0.7	23	0	2	0840	1740	1	1/16	0	0	0	0
FEB	17.6	3.1	10.4	10.4	24.8	-1.2	26	0	1	89	51	26	11/4	4	3	1	0
MAR	24.1	8.0	16.0	16.0	27.3	2.0	23	0	0	80	45	80	34/27	5	2	2	1
APR	26.3	10.5	18.4	18.4	30.4	6.8	29	1	0	67	37	24	16/6	4	3	1	0
MAY	29.3	16.1	22.7	22.7	32.4	11.0	13	15	0	63	40	57	19/20	6	3	3	0
JUN	28.6	18.1	23.4	23.4	33.0	15.2	12	0	0	73	62	157	23/22	16	8	8	0
JUL	27.3	20.2	23.8	23.8	30.6	18.8	13	1	0	85	79	481	103/28	24	10	6	7
AUG	27.3	19.4	23.4	23.4	29.6	18.0	10	0	0	83	78	155	26/13	17	11	5	1
SEP	25.3	17.6	21.4	21.4	29.0	15.6	25	0	0	86	78	174	42/4	15	11	2	2
OCT	23.4	12.5	18.0	18.0	27.6	5.8	25	0	0	89	72	86	52/30	4	1	2	0
NOV	21.0	7.3	14.2	14.2	23.9	3.1	25	0	0	93	68	20	14/27	2	1	1	0
DEC	19.3	1.9	10.6	10.6	22.8	-0.5	24	2	0	92	63	0	0	0	0	0	0
Year	23.9	11.5	17.7	17.7	33.0	-1.2	29	5	5	83	62	1261	103 Jul	97	53	31	11

INDEX NO. 1030 STATION KATHMANDU AIRPORT YEAR 1973

Month	AIR TEMPERATURE °C						RELATIVE HUMIDITY %		PRECIPITATION mm.							
	Mean		Absolute extreme		Number of days		Observed at	1740	Total	Maximum in 24 hrs & date	Number of rainy days					
	Max.	Min.	Max. date	Min. date	Max. ≥ 30°	Min. ≤ 0°					≥ 1.0	9.9	10.0	25.0	50.0	≥ 100.0
JAN	17.2	3.4	19.6	-0.0	0	4	92	68	24	9/9	5	5	0	0	0	0
FEB	19.0	4.5	22.5	1.4	0	0	90	58	32	23/28	3	2	1	0	0	0
MAR	23.3	6.4	29.9	1.9	0	0	80	43	48	36/77	5	4	0	1	0	0
APR	26.0	11.9	31.7	8.3	7	0	64	45	25	13/26	3	1	2	0	0	0
MAY	26.7	15.9	29.9	12.2	0	0	76	60	61	20/9	15	13	2	0	0	0
JUN	26.9	19.0	29.3	15.4	0	0	80	76	340	67/18	20	10	6	2	2	0
JUL	27.0	19.0	29.2	18.0	0	0	83	80	456	102/25	21	10	6	2	2	1
AUG	27.5	19.4	30.9	17.5	1	0	85	83	336	93/11	22	11	0	2	1	0
SEP	26.2	18.2	29.4	13.6	0	0	88	84	321	47/26	19	8	6	5	0	0
OCT	24.4	14.0	27.4	9.2	0	0	88	78	119	64/13	8	5	1	1	1	0
NOV	21.3	6.6	24.0	3.6	0	0	91	72	16	10/2	3	2	1	0	0	0
DEC	18.0	11.7	20.8	-1.6	0	7	96	70	0	0	0	0	0	0	0	0
Year	24.0	11.7	31.7	-1.6	8	11	84	68	1798	102 Jul	124	71	33	13	6	1

Month	AIR TEMPERATURE °C						RELATIVE HUMIDITY %		PRECIPITATION m.m.							
	Mean		Absolute extreme		Number of days		Observed at		Total	Maximum in 24 hrs & date	Number of rainy days					
	Max.	Min.	Max. date	Min. date	Max. ≥ 30°	Min. ≠ 0°	0840	1740			≥ 1.0	10.0	25.0	≥ 50.0		
JAN	16.0	1.4	19.7	-2.0	0	3	96	67	17	15/15	2	1	1	0	0	0
FEB	20.1	3.0	25.2	-0.8	0	4	87	47	6	6/13	1	1	0	0	0	0
MAR	23.9	7.8	27.9	5.0	0	0	81	54	23	10/30	3	2	1	0	0	0
APR	27.3	13.0	31.7	8.0	7	0	74	55	31	14/30	6	5	1	0	0	0
MAY	26.8	16.2	30.4	13.1	6	0	78	65	108	30/10	10	5	4	1	0	0
JUN	28.2	18.9	30.6	14.2	3	0	79	68	75	32/7	6	4	1	1	0	0
JUL	26.3	19.9	29.4	18.5	0	0	86	83	340	50/31	23	10	9	3	1	0
AUG	26.6	20.1	28.8	18.9	0	0	89	85	364	71/21	21	12	4	4	1	0
SEP	25.4	17.6	28.0	14.4	0	0	91	84	205	62/11	15	9	3	2	1	0
OCT	25.8	15.6	27.8	8.5	0	0	90	78	46	38/7	4	3	0	1	0	0
NOV	22.3	6.2	25.5	3.6	0	0	92	70	0	0	0	0	0	0	0	0
DEC	16.5	1.2	19.2	-0.9	0	8	97	64	11	5/17	3	3	0	0	0	0
Year	23.8	11.8	31.7	-2.0	16	15	87	68	1226	71 Aug	94	55	24	12	13	0

INDEX NO. 1030 STATION KATHMANDU AIRPORT YEAR 1974

INDEX NO. 1030 STATION KATHMANDU AIRPORT YEAR 1975

Month	AIR TEMPERATURE °C					RELATIVE HUMIDITY %		PRECIPITATION mm.							
	Mean		Absolute extreme		Number of days		Observed at	Total	Maximum in 24 hrs & date	Number of rainy days			≥ 100.0		
	Max.	Min.	Max. date	Min. date	Max. ≥ 30°	Min. ≤ 0°				≥ 1.0	10.0	25.0		50.0	
JAN	16.2	1.4	19.5 21	-1.7 13	0	11	0840 1740	31	10/2	6	0	0	0	0	
FEB	10.9	4.1	23.4 20	0.2 3	0	0	95	25	11/2	5	4	1	0	0	
MAR	23.0	6.9	26.9 23	4.6 13	0	0	78	8	4/31	2	2	0	0	0	
APR	20.2	11.4	31.0 8	5.9 16	5	0	68	36	15/26	5	3	2	0	0	
MAY	28.2	15.3	30.6 2	11.4 23	5	0	75	75	12/26	10	6	4	0	0	
JUN	27.9	18.9	31.4 11	16.0 1	8	0	78	138	41/21	13	8	4	1	0	
JUL	26.1	19.7	20.8 9	18.0 22	0	0	86	436	80/1	23	11	7	3	0	
AUG	27.3	19.6	29.6 27	18.2 21	0	0	84	379	89/3	20	9	7	2	0	
SEP	25.3	18.1	29.4 23	15.9 29	0	0	90	268	41/8	19	9	7	3	0	
OCT	25.7	14.7	27.8 7	9.4 29	0	0	90	34	13/7	5	3	2	0	0	
NOV	20.8	6.3	23.0 1	1.3 28	0	0	96	0	0	0	0	0	0	0	
DEC	17.8	2.5	21.5 5	0.0 29	0	1	96	0	0	0	0	0	0	0	
Year	23.8	11.6	31.4 Jun	-1.7 Jan	18	12	86	1430	89 Aug	108	61	34	9	4	0

Month	AIR TEMPERATURE °C										RELATIVE HUMIDITY %		PRECIPITATION mm.					
	Mean			Absolute extreme		Number of days		Observed at		Total	Maximum in 24 hrs & date	Number of rainy days						
	Max.	Min.	Daily	Max. date	Min. date	Max. $\geq 30^\circ$	Min. $\leq 0^\circ$	0840	1740			≥ 1.0	1.0	9.9	10.0	25.0	50.0	≥ 100.0
	Max.	Min.	Daily	Max. date	Min. date	Max. $\geq 30^\circ$	Min. $\leq 0^\circ$	0840	1740									
JAN	19.7	6.3	13.0	23.0	3.4	0	0	81	41	0	0	0	0	0	0	0	0	
FEB	21.4	6.9	14.3	26.0	3.0	0	0	71	37	11	10/28	1	0	1	0	0	0	
MAR	26.4	10.7	18.5	33.0	5.0	8	0	58	31	41	18/6	4	2	2	0	0	0	
APR	26.1	11.0	18.5	30.0	6.0	2	0	70	55	226	48/30	10	0	8	2	0	0	
MAY	27.6	13.5	20.5	31.0	8.0	4	0	71	58	348	55/18	17	7	4	4	2	0	
JUN	28.7	15.6	22.1	31.5	12.0	14	0	85	68	699	45/12	22	0	7	15	0	0	
JUL	29.3	16.3	22.8	32.0	13.0	11	0	85	67	534	71/17	27	11	9	3	4	0	
AUG	28.5	18.0	23.2	30.1	13.8	6	0	87	72	584	90/6	24	11	3	7	3	0	
SEP	28.1	20.6	24.3	30.0	19.0	3	0	83	67	437	101/30	19	9	4	4	1	1	
OCT	25.6	16.6	21.1	29.8	11.4	0	0	82	66	329	59/18	15	3	7	4	1	0	
NOV	21.9	11.0	16.4	25.8	7.2	0	0	81	55	67	22/18	7	4	1	0	0	0	
DEC	19.3	7.5	13.4	22.0	5.4	0	0	84	52	0	0	0	0	0	0	0	0	
Year	25.2	12.8	19.0	33.0	3.0	48	0	78	56	3276	101 Sep	146	47	48	39	11	1	

Month	AIR TEMPERATURE °C										RELATIVE HUMIDITY %		PRECIPITATION m.m.						
	Mean			Absolute extreme		Number of days		Observed at		Total	Maximum in 24 hrs. & date	Number of rainy days							
	Max.	Min.	Daily	Max. date	Min. date	Max. ≥ 30°	Min. ≤ 0°	0840	1740			≥ 1.0	1.0 - 9.9	10.0 - 24.9	25.0 - 49.9	50.0 - 99.9	≥ 100.0		
JAN	19.0	7.6	13.3	21.0 24	5.0 17	0	0	84		21	21/29	1	0	1	0	0			
FEB	19.0	7.9	13.4	25.3 27	4.0 18	0	0	77		46	24/14	4	2	2	0	0			
MAR	26.0	12.8	19.4	29.8 22	6.3 6	0	0	73		106	38/28	5	0	3	2	0			
APR	28.8	14.7	21.7	32.1 30	10.0 10	10	0	80		75	27/17	8	4	3	1	0			
MAY	31.0	19.7	25.3	34.4 11	15.6 4	20	0	63		397	114/26	11	3	3	2	1			
JUN	30.0	20.6	25.3	33.4 11	16.3 6	13	0	73		534	158/18	19	6	5	7	0			
JUL	28.6	22.2	25.4	32.4 13	20.6 8	11	0	87		1099	128/25	26	5	5	7	2			
AUG	29.2	21.8	25.5	31.8 21	20.8 28	9	0	85		413	76/10	18	7	6	3	0			
SEP	26.9	20.1	23.5	30.2 20	18.3 15	1	0	86		408	82/4	10	10	1	4	0			
OCT	24.9	16.3	20.6	28.6 3	10.4 24	0	0	84		77	33/30	7	4	2	1	0			
NOV	22.5	11.6	17.0	24.9 6	8.3 25	0	0	80		32	8/27	6	6	0	0	0			
DEC	19.8	7.7	13.7	23.3 3	5.4 30	0	0	81		0	0	0	0	0	0	0			
Year	25.4	15.2	20.3	34.4 May	4.0 Feb	64	0	79		3208	158 Jun	123	47	31	27	14			

Month	AIR TEMPERATURE °C										RELATIVE HUMIDITY %		PRECIPITATION mm.				
	Mean		Absolute extreme		Number of days		Observed at		Total	Maximum in 24 hrs & date	Number of rainy days						
	Max.	Min.	Max. date	Min. date	Max. $\geq 30^\circ$	Min. $\leq 0^\circ$	0840	1740			≥ 1.0	1.0 - 9.9	10.0 - 24.9	25.0 - 49.9	≥ 50.0		
	Min.	Daily	Max. date	Min. date	Max. $\geq 30^\circ$	Min. $\leq 0^\circ$	0840	1740	≥ 1.0	1.0 - 9.9	10.0 - 24.9	25.0 - 49.9	≥ 50.0				
JAN	10.4	9.6	20.9	5.0	0	0	87	72	40	12/16	8	7	1	0	0		
FEB	22.0	10.1	25.0	6.5	0	0	79	54	36	22/28	4	3	1	0	0		
MAR	26.1	12.1	33.1	7.5	7	0	65	40	43	29/7	4	3	0	1	0		
APR	32.1	17.5	35.0	14.7	27	0	53	41	50	16/23	6	3	3	0	0		
MAY	28.8	19.3	31.6	15.6	7	0	77	66	383	56/25	24	14	5	3	2		
JUN	28.7	22.0	30.9	18.6	10	0	86	76	628	75/17	23	7	6	4	6		
JUL	30.1	22.6	32.3	20.0	22	0	84	76	839	173/26	20	5	6	0	8		
AUG	29.4	22.2	32.4	20.8	13	0	88	76	846	132/18	21	5	4	6	5		
SEP	26.2	21.0	31.0	18.2	8	0	87	80	722	144/17	17	4	4	3	5		
OCT	20.7	16.6	28.8	13.5	0	0	85	79	460	136/13	12	4	3	0	4		
NOV	22.8	11.2	25.6	8.3	0	0	82	74	49	35/5	3	2	0	1	0		
DEC	19.3	7.1	20.8	4.5	0	0	84	67	0	0	0	0	0	0	0		
Year	25.5	15.9	35.0	4.5	94	0	80	67	4096	173 Jul	142	57	33	10	30		

INDEX NO. 0004 STATION POKHARA AIRPORT YEAR 1973

INDEX NO. 0804 STATION POKHARA AIRPORT YEAR 1974

Month	AIR TEMPERATURE °C					RELATIVE HUMIDITY %		PRECIPITATION mm.								
	Mean		Absolute extreme		Number of days		Observed at	Total	Maximum in 24 hrs & date	Number of rainy days			Number of rainy days			
	Max.	Min.	Max. date	Min. date	Max. ≥30°	Min. ≤0°	0040			1740	≥ 1.0	10.0	25.0	50.0	≥ 100.0	
JAN	10.9	6.7	12.0	21.3 26	2.6 16	0	0	82	19	12/15	2	1	1	0	0	0
FEB	22.1	8.0	15.0	28.2 23	3.9 9	0	0	73	4	3/13	1	1	0	0	0	0
MAR	26.8	13.1	20.0	30.6 17	10.4 2	3	0	62	66	24/26	7	4	3	0	0	0
APR	29.3	17.1	23.2	33.2 26	12.6 10	12	0	68	136	34/29	9	4	3	2	0	0
MAY	29.1	18.4	23.8	32.3 28	14.4 23	10	0	73	384	57/5	20	10	3	6	1	0
JUN	29.8	20.3	25.0	32.3 16	17.9 8	14	0	79	892	140/15	23	6	4	7	4	2
JUL	28.4	21.6	25.0	31.0 12	19.8 3	4	0	88	862	102/29	29	11	5	7	5	1
AUG	28.6	21.5	25.0	31.4 10	20.3 20	10	0	89	1429	205/2	27	8	6	4	7	5
SEP	27.2	20.0	23.6	30.2 8	18.0 11	2	0	86	511	86/4	19	7	3	6	3	0
OCT	27.6	18.4	23.0	29.4 18	12.6 30	0	0	84	293	76/15	15	3	10	1	1	0
NOV	23.8	16.1	17.0	26.3 1	7.1 30	0	0	75	0	0	0	0	6	0	0	0
DEC	17.9	6.0	12.0	20.4 1	3.0 20	0	0	85	9	8/16	1	1	0	0	0	0
Year	25.8	15.1	20.4	33.2 Apr	2.6 Jan	55	0	79	4605	205 Aug	153	53	38	33	21	8

Month	INDEX NO. 0804 STATION POKHARA AIRPORT YEAR 1975										PRECIPITATION mm.					
	AIR TEMPERATURE °C					RELATIVE HUMIDITY %					Total	Maximum in 24 hrs & date	Number of rainy days			
	Mean		Absolute extreme		Number of days		Observed at		≥ 1.0	10.0			25.0	50.0	≥ 100.0	
	Max.	Min.	Max. date	Min. date	Max. ≥ 30°	Min. ≤ 0°	0840	1740								
JAN	10.0	6.0	20.0	2.8	0	0	84	62	38	10/25	7	5	2	0	0	0
FEB	20.9	8.4	24.6	3.4	0	0	80	54	37	10/28	6	5	1	0	0	0
MAR	26.4	11.6	29.8	8.9	0	0	63	38	42	14/7	4	1	3	0	0	0
APR	31.5	15.7	37.4	12.0	25	0	54	36	118	55/20	4	1	1	1	1	0
MAY	29.8	17.8	33.1	15.0	17	0	69	68	446	135/16	19	7	6	5	0	1
JUN	29.7	20.4	32.6	17.0	16	0	81	69	704	115/15	20	6	5	4	4	1
JUL	28.2	20.7	30.7	18.4	9	0	88	81	1177	171/1	28	4	9	6	8	1
AUG	29.6	21.2	32.2	19.0	16	0	86	77	650	110/3	21	5	8	4	3	1
SEP	27.4	19.6	30.0	17.6	1	0	88	83	1096	149/19	26	6	8	3	5	4
OCT	27.2	17.1	29.3	12.4	0	0	82	78	359	50/10	12	2	2	6	2	0
NOV	22.4	10.0	24.3	5.6	0	0	80	68	0	0	0	0	0	0	0	0
DEC	19.5	7.5	21.2	5.9	0	0	86	65	0	0	0	0	0	0	0	0
Year	25.9	14.7	37.4	2.8	84	0	78	65	4667	171 Jul	147	42	45	29	23	8

付属資料 1-12 建設主要資材単価表

主要資材の標準的単価を Department of Housing & Physical Planning から入手した資料を元に算出して下記に示す。これらには下請経費も含まれている。

(1 ネパール・ルピーを20円として換算)

☆ 建築関係

(1) 根 伐 (Ordinary Soil)	m ³	134 円
(2) 埋 戻 し (盛 土)	m ³	1,192
(3) 基礎, 床, 1級品レンガ平敷き	m ²	247
(4) 壁, 1級品レンガ積セメント目地 (1:6)	m ³	7,037
(5) " " (1:4)	"	7,943
(6) " " (1:3)	"	8,724
(7) 石 の 割 栗	m ³	2,508
(8) 自然石積セメント目地 (1:6)	m ³	7,094
(9) 全 上 ライムモルタル (1:1)	m ³	4,692
(10) 仕上石積セメント目地	m ³	9,239
(11) 無筋コンクリート (1:2:4)	m ³	16,820
(12) " (1:3:6)	"	13,264
(13) " (1:4:8)	"	11,366
(14) ライム・コンクリート (1:1:1:6)	m ³	5,197
(15) 屋根ライム・コンクリート (3:3:10)	m ³	6,083
(16) 防水モルタル (1:2:4) 厚さ1 1/2"	m ²	840
(17) セメントコンクリート床 (1:2:4) 厚さ1 1/2"	m ²	741
(18) " " " 2"	"	892
(19) " " " 3"	"	1,317
(20) " " " 4"	"	-
(21) 床, 人研 (1:2:4) 厚さ1"	m ²	1,866
(22) 床, 人研色付 (1:2) " 3/4"	"	1,918
(23) 2" 割栗石, 上端セメントモルタル (1:4)	"	2,316
(24) サローウッド建具枠	m ³	67,460

No. 5720

(25)	厚さ1 1/2" シャッター (Panelled Shutter)	m ²	4,214
(26)	" (Glazed Shutter)	"	4,359
(27)	厚さ1 1/2" フラッシュ戸 (3mm厚ベニア両面貼)	m ²	4,578
(28)	" (3mm厚チーク or ローズウッドベニア)	m ²	6,103
(29)	パーティション (プライウッド両面貼)	m ²	1,962
(30)	天井 サローウッド野縁 (3mmプライウッド貼)	m ²	1,598
(31)	" (1" サルウッド貼)	"	2,252
(32)	サルウッド 梁, 柱, まぐさ等 (付属金具共)	m ³	61,977
(33)	厚さ1" 軒板	m ²	1,308
(34)	スチール・ローリング・シャッター	m ²	15,984
(35)	アコーディオン・スチール・シャッター	m ²	8,719
(36)	スチール・グリル (1/8" × 3/4")	m ²	2,906
(37)	" (3/16" × 1")	m ²	5,231
(38)	有刺鉄線塀	m	54
(39)	鉄筋コンクリート (1:2:4)	m ³	17,449
(40)	鉄筋 (加工共)	Kg	127
(41)	型枠	m ²	744
(42)	2 1/2" 厚屋上レンガ手摺 (1:3)	m ²	878
(43)	Sheet Roofing (G.I. シート)	m ²	1,866
(44)	" (G.I. Plain シート)	"	1,329
(45)	" (アスベスト・セメント・シート)	m	1,732
(46)	屋根, 天然スレート	m ²	1,358
(47)	" Red Clay Tiles (Roof)	m ²	488
(48)	" " (Ridge)	m	98
(49)	" ポリエチレン・シート	m ²	195
(50)	床, 壁, 天井, 1/2" セメントプラスター (1:2)	m ²	477
(51)	" " " (1:3)	"	390
(52)	" " " (1:4)	"	323
(53)	" " " (1:6)	"	247
(54)	" 3/4" " (1:4)	"	448
(55)	" " " (1:6)	"	363

(56)	防水セメントペイント	2回塗	m ²	189		
(57)	ホワイトウォッシュ	2回塗	"	32		
(58)	Distemper	"	"	81		
(59)	プライマー	1回塗の上, エナメル	m ²	317		
(60)	エマルジョンペイント	2回塗	"	305		
(61)	木部	チャプラ	3回塗	"	224	
(62)	"	D. B Linseed Oil	2回塗	"	76	
(63)	"	フレンチ	ポリッシュ	2回塗	"	102
(64)	鉄部	プライマー	1回塗の上, アルミペイント	2回塗	m ²	210
(65)	コールター	ールペイント	2回塗	m ²	55	
(66)	屋上防水	タール・フェルト	m ²	959		
(67)	基礎	"	"	1,598		

☆ 設備関係単価

(1)	オリッサパン	23" (陶製, インド型)	個	28,944
(2)	大便器	(ロータンク付) 20"	個	22,680
(3)	"	(ハイタンク付) 20"	"	12,420
(4)	大便器	洗い流し (陶製, 洋式)	"	26,595
(5)	"	(")	"	32,697
(6)	洗面器	22"×16"	"	10,125
(7)	"	20"×16"	"	9,855
(8)	"	18"×12"	"	6,912
(9)	医療流し	23"×17"	"	16,848
(10)	実験流し	18"×12"×6"	個	6,831
(11)	"	21"×17"×7"	"	13,770
(12)	台所流し	24"×18"×8"	"	22,140
(13)	"	24"×18"×10"	"	24,165

(14)	小型小便器 (フラットバック) 18" × 14" × 10 1/2"	個	5,670 円
(15)	" (アングルバック) 17" × 14 1/2" × 13 1/2"	"	5,670
(16)	小便器 (Squatting Plate) 23 1/2" × 13 3/4"	"	6,480
(17)	" (Large Flat Back) 24" × 16" × 15"	"	19,980
(18)	ビ デ	"	39,366
(19)	自動洗滌 シスターン (1 ガロン) 鋳鉄製	個	4,050
(20)	" (2 ガロン) "	"	4,860
(21)	" (3 ガロン) "	"	6,210
(22)	" (1 ガロン) 陶磁製	"	6,615
(23)	" (2 ガロン) "	"	9,180
(24)	" (3 ガロン) "	"	12,015
(25)	水 槽 (G. I. Sheet) 100 ガロン	個	12,150
(26)	" " 200 ガロン	"	22,280
(27)	" " 300 ガロン	"	37,800
(28)	" " 400 ガロン	"	60,350
(29)	電動ポンプ 1" × 1/2 HP	台	54,270
(30)	" 1" × 1 HP	"	74,520
(31)	" 2" × 2 HP	"	115,155
(32)	ペーパーホルダー (陶磁製)	個	1,350
(33)	" (クローム・メッキ製)	"	594
(34)	石鹸受け (クローム・メッキ)	個	594
(35)	水石鹸入れ (")	"	1,458
(36)	タオル掛け (クローム・メッキ) 1/2" × 24"	"	810
(37)	" (") 1/2" × 18"	"	675
(38)	化粧棚 $\ell = 22"$ (陶磁製)	"	1,215
(39)	" $\ell = 24"$ (ガラス製)	"	945
(40)	タンブラー&歯ブラシ, ホルダー 6" × 3"	"	1,431
(41)	化粧鏡 22" × 16"	"	2,295
(42)	" 20" × 16"	"	2,025
(43)	" 18" × 12"	"	1,701
(44)	シャワーローズ 4"	個	1,593

(45)	シャワーローズ	3"	個	1,890円
(46)	水栓	1/2" (クローム・メッキ)	"	810
(47)	"	" (真ちゅう)	"	540
(48)	ストップ弁	1/2" (クローム・メッキ)	"	810
(49)	"	1/2" (真ちゅう)	"	540
(50)	2人立, 小便器	パイプセット	組	5,400
(51)	ゲート弁 (砲金製)	1/2"	個	540
(52)	"	" 3/4"	"	945
(53)	"	" 1"	"	1,620
(54)	"	" 1 1/4"	"	2,052
(55)	"	" 1 1/2"	"	2,727
(56)	"	" 2"	"	3,780
(57)	"	" 2 1/2"	"	9,072
(58)	チャッキ弁 (砲金製)	1/2"	個	378
(59)	"	" 3/4"	"	594
(60)	"	" 1"	"	1,080
(61)	"	" 1 1/4"	"	1,350
(62)	"	" 1 1/2"	"	1,890
(63)	"	" 2"	"	2,970
(64)	"	" 2 1/2"	"	4,725
(65)	排水目皿 (クローム・メッキ)	4"	個	270
(66)	" (")	5"	"	324
(67)	铸铁管	2"	m	1,594
(68)	"	3"	"	1,727
(69)	"	4"	"	1,860
(70)	铸铁管 (Rain Water 用)	3"	m	1,151
(71)	" (")	4"	"	1,373
(72)	" (")	6"	"	2,923
(73)	ストーン・ウェア管	4"	m	1,063
(74)	"	6"	"	1,683
(75)	"	9"	"	2,391

(76)	白ガス管	(Aクラス) 1/2" (Long lineの場合25%引)	材工共	m	620円
(77)	"	(") 3/4"	"	"	974
(78)	"	(") 1"	"	"	1,151
(79)	"	(") 1 1/4"	"	"	1,329
(80)	"	(") 1 1/2"	"	"	1,683
(81)	"	(") 2"	"	"	2,126
(82)	鑄鉄接手	(チーズ, ベンド等)		2"	個 675
(83)	"	(")		3"	" 810
(84)	"	(")		4"	" 1,080
(85)	"	(") 雨水用		3"	" 675
(86)	"	(") "		4"	" 945
(87)	"	(") "		6"	" 1,620
(88)	鉛接合	(鑄鉄2"管)			個 459
(89)	"	(" 3")			" 675
(90)	"	(" 4")			" 891
(91)	浄化槽	(10人)			個 34,830
(92)	"	(20人)			" 93,040
(93)	"	(30人)			" 128,740
(94)	"	(50人)			" 169,000
(95)	"	(100人)			" 202,500
(96)	浸透槽	(1,000ガロンタンク)			" 37,720

☆ 電気設備関係

(1)	Main Switch Board	630Amp (フューズ付)		面	138,510
(2)	0~500V A.C	ボルトメーター (セレクタースイッチ付)		個	8,100
(3)	ボルトメーター,	アンメーター両用			27,000
(4)	Iron Clad Switch	400Amp 3相 (H.R.Cフューズ付)		個	87,210
(5)	"	300 " (")		"	67,500
(6)	"	200 " (")		"	51,705
(7)	"	200 " (Rewirableフューズ付)		"	27,945
(8)	"	100 " "		"	24,300

(9)	Iron Clad Switch	100 Amp	单相 (H.R.C フューズ付)	個	34,020 円
(10)	"	100	" (Rewirable フューズ付)	"	20,925
(11)	"	60	3 相 (H.R.C フューズ付)	"	22,140
(12)	"	60	" (Rewirable フューズ付)	"	19,845
(13)	"	60	单相 (H.R.C フューズ付)	"	18,549
(14)	"	60	" (Rewirable フューズ付)	"	10,260
(15)	"	30	3 相 (H.R.C フューズ付)	"	9,720
(16)	"	30	" (Rewirable フューズ付)	"	8,235
(17)	"	30	单相 (H.R.C フューズ付)	"	4,995
(18)	"	30	" (Rewirable フューズ付)	"	8,235
(19)	"	15	3 相 (")	"	7,020
(20)	"	15	单相 (")	"	2,700
(21)	サーキット・ブレーカー	60 Amp	3 相	個	15,417
(22)	"	"	单相	"	3,780
(23)	"	30	3 相	"	14,580
(24)	"	"	单相	"	3,780
(25)	"	15	"	"	3,780
(26)	"	10	"	"	3,780
(27)	"	5	"	"	3,645
(28)	"	2	"	"	4,050
(29)	"	1	"	"	4,050
(30)	配電盤	N way 15/30/60 Amp	Box 型	セット	5,967×N 6,210×" 7,830×"
(31)	"	1 way 10/15/up to 60 Amp	"	"	1,809 1,890 2,430
(32)	"	N way 15/30/60 Amp	木製板型	"	675×N 810×" 1,620×"
(33)	コンセント (スイッチ付)	3pin 15A, 2pin 5A	結合型	動力用 個	1,890 取付共
(34)	" (")	3 pin 15A	フラッシュ型	" "	1,755 "
(35)	" (スイッチなし)	"	"	" "	1,350 "
(36)	" (スイッチ付)	"	Surface 型	" "	1,080 "

(37)	コンセント	(スイッチなし)	3pin 15A	Surface型	動力用	個	945円	取付共
(38)	"	(スイッチ付)	3pin 5A	フラッシュ型	"	"	918	"
(39)	"	(スイッチなし)	"	"	"	"	999	"
(40)	"	(スイッチ付)	"	Surface型	"	"	945	"
(41)	"	(スイッチなし)	"	"	"	"	756	"
(42)	"	"	2pin 5A	フラッシュ型	照明用	"	972	"
(43)	"	"	"	Surface型	"	"	627	"
(44)	"	(スイッチ付)	"	フラッシュ型	"	"	1,134	"
(45)	"	"	"	Surface型	"	"	891	"
(46)	電話用アウトレット	(スイッチなし)	2pin	Surface型	"	"	621	"
(47)	"	"	"	フラッシュ型	"	"	972	"
(48)	蛍光灯	40W×1	アクリカカバー付	フラッシュ型	"	セット	16,119	"
(49)	"	"	"	Surface型	"	"	15,444	"
(50)	"	"	ルーバー付	フラッシュ型	"	"	14,175	"
(51)	"	"	"	Surface型	"	"	13,500	"
(52)	"	40W×2	アクリカカバー付	フラッシュ型	"	"	22,980	"
(53)	"	"	ルーバー付	Surface型	"	"	21,090	"
(54)	"	"	アクリカカバー付	"	"	"	22,300	"
(55)	"	"	ルーバー付	フラッシュ型	"	"	22,980	"
(56)	"	20W×2	"	Surface型	"	"	21,600	"
(57)	"	20W×4	アクリカカバー付	フラッシュ型	"	"	33,615	"
(58)	"	"	"	Surface型	"	"	32,940	"
(59)	"	"	ルーバー付	フラッシュ型	"	"	28,485	"
(60)	"	"	"	Surface型	"	"	27,945	"
(61)	"	20W×6	アクリカカバー付	フラッシュ型	"	"	37,611	"
(62)	"	"	"	Surface型	"	"	37,071	"
(63)	"	"	ルーバー付	フラッシュ型	"	"	30,402	"
(64)	"	"	"	Surface型	"	"	29,997	"
(65)	"	40W×1	(Industrial)	"	"	"	13,770	"
(66)	"	40W×2	"	"	"	"	16,200	"
(67)	"	20W×1	(Ordinary)	"	"	"	3,375	"

(68)	蛍光灯	20W×2	(Ordinary)	セット	7,641円	取付共
(69)	"	40W×1	(")	"	6,750	"
(70)	"	40W×2	(")	"	9,639	"
(71)	白熱灯	100W	(12" Flat Dome 型)	"	2,700	"
(72)	"	60W	(8" ")	"	2,349	"
(73)	"	"	(12" Round Dome 型)	"	2,700	"
(74)	"	"	(8" ")	"	2,349	"
(75)	"	"	(6" ")	"	1,350	"
(76)	"	60W	ブラケット型 (カラー・ガラス)	"	1,215	"
(77)	"	60W×2	" (")	"	3,105	"
(78)	"	60W	" (アルミ, リフレクター付)	"	1,215	"
(79)	"	60W	ペンダント (fancy shade)	"	2,700	"
(80)	"	60W	" (普通型) リフレクター付	"	675	"
(81)	"	"	" " リフレクターなし	"	540	"
(82)	投光照明	白熱	1,000W	セット	97,200	"
(83)	"	ハロゲン	1,000W	"	48,600	"
(84)	"	白熱	150W	"	8,100	"
(85)	"	水銀灯	400W	"	8,100	"
(86)	外 灯	60W	(Weather Proof)	"	2,160	"
(87)	街 灯 (ポール付)	水銀灯	80W×1 (Post top)	セット	24,300	"
(88)	"	"	" 80W×2 (")	"	-	"
(89)	"	"	" 125W×1 (")	"	28,080	"
(90)	"	"	" 125W×2 (")	"	-	"
(91)	"	"	" 80W (Side entry)	"	21,600	"
(92)	"	"	" 125W (")	"	22,950	"
(93)	"	"	" 250W (")	"	52,650	"
(94)	"	"	" 400W (")	"	55,350	"
(95)	Spot & Display 灯	半露出スポット型		セット	5,400	"
(96)	"	天井スポット型		"	5,130	"
(97)	"	短距り投光用		"	6,750	"
(98)	天井ファン	48" φ		"	16,200	"

(99)	天井ファン	42" φ			セット	16,200円
(100)	"	36" φ			"	16,200
(101)	排気ファン	18" φ			"	31,725
(102)	"	12" φ			"	28,620
(103)	電気ベル	(普通型)	インジケータ付		"	4,320
(104)	電気ブザー				"	1,890
(105)	電気ベル	(普通型)			"	1,350
(106)	配線, 銅	単線 (PVC管内)	材工共	1.5 mm ²	m	95
(107)	"	"	"	2.5 mm ²	"	110
(108)	"	"	"	4.0 mm ²	"	162
(109)	"	"	"	6.0 mm ²	"	203
(110)	"	"	"	10 mm ²	"	284
(111)	"	"	"	16 mm ²	"	432
(112)	"	"	"	25 mm ²	"	486
(113)	"	アルミ単線 (PVC管内)	材工共	1.5 mm ²	m	69
(114)	"	"	"	2.5 mm ²	"	72
(115)	"	"	"	4.0 mm ²	"	102
(116)	"	"	"	6.0 mm ²	"	110
(117)	"	"	"	10 mm ²	"	135
(118)	"	"	"	25 mm ²	"	220
(119)	"	"	"	35 mm ²	"	908
(120)	"	"	(コンジット管内)	1.5 mm ²	m	165
(121)	"	"	"	2.5 mm ²	"	168
(122)	"	"	"	4.0 mm ²	"	176
(123)	"	"	"	6.0 mm ²	"	184
(124)	"	"	"	10 mm ²	"	273
(125)	"	"	"	25 mm ²	"	338
(126)	"	銅	単線 (コンジット管内)	1.5 mm ²	m	191
(127)	"	"	"	2.5 mm ²	"	206
(128)	"	"	"	4.0 mm ²	"	237
(129)	"	"	"	6.0 mm ²	"	277

(130)	配線, 銅単線 (コンジット管内)	材工共	10 mm ²	m	347 円
(131)	"	"	16 mm ²	"	558
(132)	"	"	25 mm ²	"	604
(133)	"	(Surface Wiring) 材工共	1.5 mm ²	"	76
(134)	"	"	2.5 mm ²	"	91
(135)	"	"	4.0 mm ²	"	122
(136)	"	"	6.0 mm ²	"	162
(137)	"	"	10 mm ²	"	243
(138)	"	"	25 mm ²	"	389
(139)	"	アルミ単線 (Surface Wiring)	1.5 mm ²	"	50
(140)	"	"	2.5 mm ²	"	53
(141)	"	"	4.0 mm ²	"	61
(142)	"	"	6.0 mm ²	"	69
(143)	"	"	10 mm ²	"	95
(144)	"	"	25 mm ²	"	160
(145)	アース銅線 (アース銅板共)	ゲージ No. 18		m	48
(146)	"	" No. 16		"	54
(147)	"	" No. 12		"	351
(148)	"	" No. 8		"	1,080
(149)	避雷器	トランス避雷器		個	6,615
(150)	地下埋設被覆電力ケーブル (アルミ) 2 core ケーブル		2.5 mm ²	m	702 工共
(151)	"	"	4 mm ²	"	729 "
(152)	"	"	6 mm ²	"	783 "
(153)	"	"	10 mm ²	"	864 "
(154)	"	"	16 mm ²	"	1,053 "
(155)	"	"	25 mm ²	"	1,404 "
(156)	"	"	35 mm ²	"	1,620 "
(157)	"	"	50 mm ²	"	1,890 "
(158)	"	3 core ケーブル	2.5 mm ²	"	756 "
(159)	"	"	4 mm ²	"	783 "
(160)	"	"	6 mm ²	"	810 "


(161)	地下埋設被覆電力ケーブル (アルミ) 3 core ケーブル	10 mm ²	m	972円	工共
(162)	"	"	"	1,215	"
(163)	"	"	"	1,539	"
(164)	"	"	"	1,782	"
(165)	"	"	"	1,971	"
(166)	"	"	"	2,714	"
(167)	"	"	"	3,362	"
(168)	"	3 1/2 core ケーブル	25 mm ²	1,728	"
(169)	"	"	"	1,890	"
(170)	"	"	"	2,376	"
(171)	"	"	"	3,173	"
(172)	"	"	"	3,767	"
(173)	"	"	"	5,225	"
(174)	"	"	"	5,333	"
(175)	"	"	"	6,413	"
(176)	"	"	"	6,413	"
(177)	"	"	"	8,438	"
(178)	"	"	"	9,437	"
(179)	"	"	"	13,379	"
(180)	"	4 core ケーブル	2.5 mm ²	783	"
(181)	"	"	"	845	"
(182)	"	"	"	953	"
(183)	"	"	"	1,088	"
(184)	"	"	"	1,412	"
(185)	"	"	"	1,790	"
(186)	"	"	"	2,114	"
(187)	"	"	"	2,492	"
(188)	トランス	25 KVA	T. P. N	基	565,137
(189)	"	50 KVA	"	"	483,561
(190)	"	63 KVA	"	"	716,688
(191)	"	100 KVA	"	"	1,081,080


(192)	11 KV	100A Drop	カットアウトフューズ	基	30,591円
(193)	トランス用ポール	35 ft			27,000
(194)	トランス	150 KVA			595,490
(195)	"	400 KVA			2,644,000
(196)	"	500 KVA			-
(197)	1/44	Pre Single Core	銅コイル	91 m	2,000
(198)	3/029	"	"	"	2,560
(199)	3/036	"	"	"	3,400
(200)	7/029	"	"	"	5,000
(201)	7/036	"	"	"	7,400
(202)	7/044	"	"	"	13,500
(203)	7/064	"	"	"	24,000
(204)	電	球	15 W	個	105
(205)	"		25 W	"	105
(206)	"		40 W	"	110
(207)	"		60 W	"	115
(208)	"		100 W	"	135

以上

[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]

付 属 資 料 2





付属資料 2 要員および訓練計画

要員計画については、本建設計画に伴ない放送業務が拡張される分野の人員構成と現在の状況を比較し、増員が必要な分野を次に表示する。結論としては、124名の増員が必要であり、その中で事務関係が33名を占めるが、之は増員枠の約27%となっている。人員構成についてはRadio Nepal から日本側基本設計調査団に提案された要員構成表(参考資料1-1, P14, 2-6-1, Personnel Plan 参照)を用いた。

	Existing Staff	Required Staff after the project	Increase in number
(1) Engineer in charge	0	2	2
(2) Asst. Engineer or Shift Engineer	5	14	9
(3) Tech. Officer	2	0	-2
(4) Supervisor or Technician	0	12	12
(5) Tech. Asst. R		48	
E	30	4	26
M		4	
(6) Junior Tech. Asst. R		43	
M	28	10	25
(7) Mechanics	2	21	19
以上技術関係者 小計	67	158	91
(8) Senior Clerk Adm.	0	2	2
Str.	0	2	2
(9) Junior Clerk Adm.	0	4	4
Str.	0	8	8
(10) Typist	0	4	4
(11) Driver	2	2	0
(12) Gardener	1	4	3
(13) Peon	8	18	10
合計	78	202	124

訓練計画については、Radio Nepal から日本側基本設計調査団に提案されたものがある（付属資料 1-1, P16, 2-6-2 Training Program 参照）。その合計数を次に示す。

1. 技術部門

(1) 建設前研修	(合計)		
1) Engineer	8	スタジオ技術	2
		送信技術	4
		総合	2
2) Technician	10	スタジオ技術	3
		送信技術	7
(2) 建設後研修 (毎年連続5年間)			
	(計)	(合計)	
1) Engineer	2	10	
2) Technician	4	20	
(1) + (2) の総計		(総計)	
1) Engineer		18	
2) Technician		30	

この総計の人員数と、前項の要員計画の人員数を次に比較する。この両者の差は、建設後5年間の増員計画数と云える。

	訓練計画	人員計画	差
1) Engineer or Asst. Engineer	18	11	7
2) Supervisor or Technician	30	12	18

2. 番組部門 …… Program Producer の研修

第1年度	4
第2年度	2
第3年度	2
第4年度	2
第5年度	2
計	12

現在の Radio Nepal の番組関係部門における国家公務員3等級 (Gazetted Third Class) 以上の人員数は次のとおりであり、上記の研修要員に該当すると思われる。

1) Programming Section	7
2) News Section	5
計	12

訓練計画に関する検討

(1) 国外における訓練は、元来、国内における訓練より更に高度な水準又は、新しい分野について受けるべき性格のものであり、ラジオ技術およびラジオ番組制作の分野については Radio Nepal は世界各国と同等の水準を保持していると云える。

(2) 今回のラジオ放送網整備拡充計画に伴ない、Radio Nepalが国外訓練計画を企図する理由は次の2点にあると云える。

1) 外国の放送事情およびこれに関連する事業を調査し、将来における放送事業の動向を研究すること。

2) 関係する専門分野において、外国の関係者と意見の交換を行うこと。

(3) 上記の条件により、訓練計画を検討すれば、帰国後、その分野において国内研修の指導に当ることができる者が望ましく、資格上から云えば、国家公務員3等級以上の要員に選ばれて来ることが考えられる。これは、技術部門では Assistant Engineer 以上の要員となる。


(4) 建設前訓練については、現在の或る部門の責任者の全員（例えば Assistant Engineer 全員）を一時に外国訓練に派遣することは組織運用の上から不可能であり、最大限にみても、半数毎の訓練となる。

(5) そこで当面する訓練計画としては、現在の在席要員のみに限ることとすれば次のようになる。


	Engineer or Asst. Engineer	Program Producer or News Man
第1年度	4	2
第2年度	4	2
第3年度	2	2
第4年度	2	2
第5年度	2	2
第6年度	2	2
計	16	12

ただし、

- 1) 第2年度迄を建設前訓練とする。
 - 2) Engineering 訓練は、第2年度迄訓練した8名を第3年度以降において、再度前回派遣した外国以外の国へ派遣し、技術的視野を広めることを仮定している。
- (6) 要員数が増加した場合は、訓練計画を修正又は延長する必要がある。



[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]



1111