

APPENDICES

1. MEMBER LIST AND SCHEDULE OF THE BASIC DESIGN STUDY TEAM.....	72
2. MINUTES OF DISCUSSIONS ON THE BASIC DESIGN STUDY.....	76
3. MEMBERS LIST OF THE PHILIPPINE COUNTERPARTS.....	84
4. BORING DATA.....	87
5. SURVEYED MAP OF CONSTRUCTION SITE AND EXISTING FACILITIES.....	129

I. MEMBER LIST AND SCHEDULE OF THE BASIC DESIGN STUDY TEAM

MEMBER LIST OF THE BASIC DESIGN STUDY TEAM

Team Leader	Yasuo SAITO	Deputy Director Second Economic Cooperation Div. Economic Cooperation Bureau, MFA
Project Coordinator	Masanori YAMAUCHI	Project Management Div. Grant Aid Dept., JICA
Acting Leader Planner	Junichi ITANO	Nikken Sekkei Ltd.
Architect	Yoshihisa TANAKA	Nikken Sekkei Ltd.
Elec. & Mech. Engineer	Hiroshi YOSHIDA	Nikken Sekkei Ltd.
Training Equipment	Uichi IRIHARA	Nikken Sekkei Ltd.
Medical Equipment	Kiyoshi OTANI	Nikken Sekkei Ltd.

SCHEDULE OF THE BASIC DESIGN STUDY TEAM

<u>Date</u>	<u>Day</u>	<u>Description</u>
Jan. 16	Sun	- Tokyo to Manila JL 741
17	Mon	- Meeting with Japanese Embassy (Mr. Suzuki, Mr. Takahara) & JICA (Mr. Arai) - Inception report presentation (National Housing Authority; NHA)
18	Tue	- Inception report presentation (Ministry of Foreign Affairs, MFA) - Inception report presentation (UNHCR) - Meeting with boring subcontractor and receiving their estimation - Leave Manila for PRPC, Morong, to attend site survey (Primary) and meeting with PRPC authorities (Team members + Mr. Suzuki, Japanese Embassy)

<u>Date</u>	<u>Day</u>	<u>Description</u>
Jan. 19	Wed	<ul style="list-style-type: none"> - Inception report presentation, discussion (PRPC) - Preparation for Minutes of Discussions (M/D) - Survey on site & existing facilities - (Mr. Takahara arrives in PRPC)
20	Thu	<ul style="list-style-type: none"> - Explanation of M/D (Draft) - Discussion on details of equipment lists - Attend a survey by UNHCR engineers on the current conditions of infrastructure - Instruction and discussion with boring sub-contractor - (Mr. Saito of MFA, Mr. Takahara and Mr. Suzuki depart from PRPC)
21	Fri	<ul style="list-style-type: none"> - Discussion on details of equipment lists - Attend a survey by UNHCR engineers on the current conditions of infrastructure - Survey on site and existing facilities
22	Sat	<ul style="list-style-type: none"> - Report & explanation on the results of survey and discussions (PRPC) - Mr. Yamauchi & 5 other members depart from PRPC.
23	Sun	<ul style="list-style-type: none"> - Preparation for M/D - Compiling the results of survey and discussions - Internal meeting - Meeting with Japanese Embassy (Mr. Suzuki) and JICA (Mr. Arai)
24	Mon	<ul style="list-style-type: none"> - Discussion and exchange of M/D (NHA) - Report and explanation of M/D and results of survey and discussions (U.S. Embassy) - Report and explanation of M/D and results of survey and discussions (MFA) - Preparation for site survey & meeting with PRPC (Secondary)

<u>Date</u>	<u>Day</u>	<u>Description</u>
Jan. 25	Tue	- Preparation for site survey & meeting with PRPC (Secondary) - Internal meeting - (Mr. Saito of MFA departs from Manila by TG 621)
26	Wed	- Preparation for site survey & meeting with PRPC (Secondary) - Internal meeting
27	Thu	- Preparation for site survey & meeting with PRPC (Secondary) - Internal meeting - Mr. Itano and 4 other members leave Manila for PRPC to attend site survey and meeting with PRPC (Secondary) - (Mr. Yamauchi of JICA leaves Manila by NW 002) - Received Boring Data
28	Fri	- Discussion on details of equipment lists (PRPC) - Survey on site & existing facilities - Report and explanation of the results of survey and discussions (PRPC)
29	Sat	- Supplementary survey and discussions (PRPC) - All 5 members depart from PRPC
30	Sun	- Compiling the results of survey and discussions - Internal meeting
31	Mon	- Summarizing an Outline Report - Meeting with PRPC staff arriving in Manila


<u>Date</u>	<u>Day</u>	<u>Description</u>
Feb. 1	Tue	<ul style="list-style-type: none"> - Summarizing an Outline Report - Internal meeting - Meeting for obtaining information from planners and designers of existing PRPC facilities
2	Wed	<ul style="list-style-type: none"> - Summarizing an Outline Report - Internal meeting
3	Thu	<ul style="list-style-type: none"> - Submitting and explaining on Outline Report (in English) - (Mr. Miura and Mr. Arai of JICA, including copies for Japanese and U.S. Embassies) - Internal meeting
4	Fri	<ul style="list-style-type: none"> - Submitting and explaining on Outline Report (NHA) - Reporting the results of the survey on the conditions of infrastructure (UNHCR) - Leave Manila by JL 742

2. MINUTES OF DISCUSSIONS ON THE BASIC DESIGN STUDY

MINUTES OF DISCUSSIONS


The Government of Japan has sent, through Japan International Cooperation Agency which is an official agency, implementing the technical cooperation of the Government of Japan, a team headed by Mr. Yasuo Saito, Deputy Director of the Second Economic Cooperation Division, Economic Cooperation Bureau, Ministry of Foreign Affairs, to conduct the basic design survey on the project for the expansion of the Philippine Refugee Processing Center (hereinafter called the "Project") from January 16 to February 4, 1983.

The team had a series of discussions and exchanged views with the officials concerned of the Government of the Republic of the Philippines. Both parties have agreed to recommend to their respective Governments and authorities concerned to examine the results of the survey attached herewith toward the realization of the Project.



YASUO SAITO

January 24, 1983




GAUDENCIO V. TOBIAS

Attachments

1. The objective of the Project is to provide necessary buildings, facilities and equipment for upgrading PRPC's training and health programs.
2. The proposed site of the Project is located within PRPC, Morong, Bataan.
3. Based upon the site survey, the Japanese team confirmed that the items mentioned in the Memorandum of Understanding signed by the representatives of the Governments of the Republic of the Philippines, Japan and the United States of America, and UNHCR on December 11, 1982, are technically feasible. (See Annex-1)
4. The Task Force on International Refugee Assistance and Administration of the Government of the Republic of the Philippines is the responsible agency for the Project, and will take necessary measures for contracting with the Japanese consultant which participated in this basic design survey and with the Japanese construction company which will be selected through bidding, after the Exchange of Notes is signed to the effect of realizing the Japanese Grant.
5. Proposed implementing schedule of the Project is shown in Annex-2

6. The Task Force on International Refugee Assistance and Administration of the Government of the Republic of the Philippines will take necessary measures after the grant assistance by the Government of Japan is extended for the Project.

- 1) to provide data and information necessary for the detailed design and construction,
- 2) to secure lots of land necessary for the construction,
- 3) to ensure prompt unloading at the ports in the Republic of the Philippines and help facilitate internal transportation therein of the materials and equipment for the Project, and
- 4) to exempt any and all Japanese nationals involved in the Project from any custom duties, internal taxes and fiscal levies which may be imposed in the Republic of the Philippines with respect to the implementation of the Project.



I. Training Programs

1) Schoolhouses

a) Facilities

: Five (5) schoolhouses

Each 6 classrooms (180 sq. m),

30 sq. m/classroom

Location: Phase II

Floor area: 180 sq. m x 5 = 900 sq. m

b) Equipment

: Basic Food Services

Janitorial Services

Building Maintenance/Handyman Services

Cashier Training

Landscaping/Gardening

Hotel/Motel Aid Training

2) Mess Hall Kitchen

and Guest House

a) Facilities

: Expansion of the existing facilities

Location: Administration Complex

Floor Area: 150 sq. m

b) Equipment

: Food Service and Mess Hall equipment

Guest House equipment

3) Office

a) Equipment


: Necessary office furniture and
equipment

4) Staff Dormitories

a) Facilities

: Four (4) staff dormitories which
accommodate 56 persons

Location: Dormitory Complex




Floor Area: 150 sq. m x 4 = 600 sq. m

: Necessary furniture and equipment.

b) Equipment

5) Audio-Visual Students

Service Center

a) Facilities

: Two (2) Audio-Visual Students Service Center

Location: Phase I and II

Floor Area: 250 sq. m x 2 = 500 sq. m

(SSC 50 sq. m + AV 200 sq. m)

b) Equipment

Necessary office furniture and equipment

Audio-Visual Education Equipment

6) Centralized Public Address

System

a) Facilities

: Central P. A. Monitoring Station at the Administration Building

b) Equipment

: Necessary P. A. System Equipment

7) Transportation Vehicles

for staff use

: Two (2) vehicles (12 passengers) for staff use

8) Buses

: Four (4) buses with standard seating arrangement

Health Services

1) Medical-Dental Processing

Center

a) Facilities

: Extension of existing Processing Center


Location: Phase I

Area: 200 sq. m

- b) Equipment : Necessary Equipment
- 2) Medical-Dental Dispensary
 - a) Facilities : Extension of existing Dispensary
Location: Phase I and II
 - b) Equipment : Necessary equipment
- 3) Dental Laboratory
 - a) Facilities : Extension of the existing Hospital
Location: Hospital Complex
 - b) Equipment : Necessary equipment
- 4) Staff Housing
 - a) Facilities : Four (4) staff dormitories which
accommodate 56 persons
Location: Dormitory Complex
 - b) Equipment : Necessary furniture and equipment
- 5) Hospital
 - a) Equipment : Physiotherapy equipment
EENT Clinic Equipment (except frames,
lenses and hearing aid)
Medical Laboratory Equipment
Emergency Room Equipment
Additional Hospital Equipment
Two (2) ambulance cars with air
conditioning
- 6) Others
 - a) Equipment : Supplies to support 1, 2, 3, 5 above
(necessary supplies requirement for
one (1) year)



PHILIPPINE REFUGEE PROCESSING CENTER SABANG, MORONG, BATAAN




- | TRAINING | HEALTH SERVICES |
|--|------------------------------------|
| ① AUDIO-VISUAL STUDENTS SERVICE CENTER | ⑦ MEDICAL-DENTAL PROCESSING CENTER |
| ② AUDIO-VISUAL STUDENTS SERVICE CENTER | ⑧ MEDICAL-DENTAL DISPENSARY |
| ③ MESS HALL KITCHEN & GUESTHOUSE | ⑨ MEDICAL-DENTAL DISPENSARY |
| ④ (5) SCHOOLHOUSES | ⑩ DENTAL LABORATORY |
| ⑤ CENTRALIZED PUBLIC ADDRESS SYSTEM | ⑪ (4) STAFF DORMITORIES |
| ⑥ (4) STAFF DORMITORIES | |

1.8 -

4.2.2

TENTATIVE OVERALL SCHEDULE



3. MEMBER LIST OF THE PHILIPPINE COUNTERPARTS

TASK FORCE ON INTERNATIONAL REFUGEE ASSISTANCE AND ADMINISTRATION

Chairman	Minister of Human Settlements
Member	Minister of Foreign Affairs
	Minister of National Defense
	Minister of Public Works
	Minister of Public Highways
	Minister of Local Government and Community Development
	Minister of Natural Resources
	Minister of Health
	Minister of Agriculture
	Minister of Education and Culture
	Minister of Transportation and Communication
	Acting Minister of Social Services and Development
Secretariat	Deputy Minister of Human Settlements
	Deputy Minister of Public Works
	Flag Officer in command of the Philippine Navy
	General Manager of National Housing Authority

MINISTRY OF FOREIGN AFFAIRS

- MR. ANTONIO K. MANGUIAT - Chief, Security Unit and Intelligence
and Research Division
(Ministry's Refugee Coordinator)
- MR. REYNALDO A. CATAPANG - Principal Assistant, Security Unit
and Intelligence and Research Division
- MS. MARIA LUISA LANGCAUON - Assistant Chief, Security Unit
and Intelligence and Research Division

U.S. EMBASSY

- MR. WILLIAM STUBBS - First Secretary
U.S. Refugee Programs Coordinator
- MR. LORING WAGGONER - Refugee Affairs Officer
- DR. ADA ADLER - Office of the U.S. Coordinator for
Refugee Affairs

UNITED NATIONS HIGH COMMISSIONER FOR REFUGEES

- MS. PERRITZ MITHA - Representative in the Philippines
(UNHCR)
- MR. JOE YOUNG - Program Officer, Manila
- MR. BRUCE McLEAN - Field Officer, PRPC
- MR. JACOB AMMANN - Engineer (UNHCR)
- MR. ABDUL AWAL - Engineer (UNICEF)

PHILIPPINE REFUGEE PROCESSING CENTER ADMINISTRATIVE OFFICE

MAJ. GEN. GAUDENCIO V. TOBIAS - Administrator
General Manager of NHA

COL. JOSE S. BUSTOS - Acting Deputy Administrator
Chief, Executive Staff

DR. CLARO M. NUÑEZ - Assistant Administrator (Health)
Health Services Group (HSG)

MS. IDA MAY BAGASAO - Assistant Administrator (Training)
Community Action and Social
Services Development Group
(CASSEDEG)

COL. JOSE BANZON - Assistant Administrator
General Services Group (GSG)

COL. PETRONILO P. TATARO - Assistant Administrator
Food Services Group (FSG)

MS. TERESITA A. BARCELON - Consulting for Social Services
and Training

ATTY. ANTONIO CLAUDIO - Consultant for Legal Matters

DR. ELPIDIO C. PANGANIBAN - Consultant for Food and
Health Services

MR. JOHNNY CASTILLO - Consultant for Finance

COL. ANTONIO FERNANDO - Consultant for Strategic/Policy
Planning

MS. FIDES F. BAGASAO - CASSEDEG

MS. TERESITA C. NAVATO - CASSEDEG

4. BORING DATA

GEOTESTING (INTERNATIONAL) INC.
GEOTECHNICAL & MATERIALS TESTING ENGINEERS

SUITE 101, 1679 DIAN ST., MAKATI, M. M.
TEL. NO 85-61-42

REF.: GII-32582-317-83

DATE: January 25, 1983

Japan International Corporation Agency
c/o Mr. Jun-ichi Itano
Mandarin Hotel
Makati, Metro Manila

Subject : REPORT-SOIL INVESTIGATION FOR VARIOUS STRUCTURES
AT PHILIPPINE REFUGEE PROCESSING CENTER, MORONG,
BATAAN.

Gentlemen :

This report presents the results of the soil investigation we performed for the Philippine Refugee Processing Center at Morong, Bataan.

The purpose of our soil investigation is to explore the sub-surface condition of the project sites by test borings, perform laboratory tests and evaluation to provide foundation recommendations.

FIELD INVESTIGATION

To explore the sub-surface condition of the site, we drilled eleven (11) test borings to a maximum depth of 3.0 meter each hole. The exact location of the test borings are shown on the attached borehole location map. Disturbed samples were taken every one (1) meter interval using a Standard Penetration Test (SPT) split spoon sampler. The sampler was driven with a 63.64 kg hammer falling freely through a distance of 76.2 cm. The number of blows were recorded for the 30 cm. penetration.

LABORATORY TESTING

The samples obtained from the test borings were brought to our laboratory for further examination. Selected samples were tested to determine their moisture contents, liquid limits, plasticity index and particle size distribution. The samples were classified using the Unified Soil Classification System.

SUB-SURFACE CONDITIONS

The sites investigated is generally underlain by stiff to very stiff silty clay except on some areas where clayey sand and silty sand were encountered (BH-2, BH-6, BH-8 and BH-11).

The water table was not encountered at 3.0 meters deep in all the boreholes drilled.

RECOMMENDATIONS

We understand that the following structures will be constructed in the site as represented by test borings.

Test Borings No.	Structure
BH-1	Library
BH-2	Assembly Hall
BH-3	Mess Hall
BH-4A	ICMC Vocational Training Center
BH-4B	ICMC Vocational Training Center
BH-6	Staff dormitories
BH-7	Medical-Dental Processing Center
BH-8	Medical-Dental Dispensary
BH-9	Medical-Dental Dispensary
BH-10	Dental Prosthetic Laboratory
BH-11	Staff Dormitories

All the structures to be constructed can be supported on continuous spread footings or individual footings tied with grade beams. Footings should be at least 30 cm. wide and bottomed at least 30 cm. below lowest adjacent final grade.

The footings can be designed for 1.0 kg/cm² dead loads and 1.25 kg/cm² total design loads.

The enclosures complete this soil investigation report for the Philippine Refugee Processing Center, Morong, Bataan.

Very truly yours,

GEOTESTING (INTERNATIONAL) INC.

DOMINADOR R. FERMIN, JR.
President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No data Hole No. BH-1
 Project Library Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meter
 Date Begun Jan. 19, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 19, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m.	Log	Penetration Resistance blows per foot				
							10	20	30	40	50
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long				Silty Clay, dark brown stiff, high plasticity moist in place (CH)							
	100	9	SPT-1		1.0						
	100	8	SPT-2		2.0						
					3.0						
				End of Boring							

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-2
 Project Assembly Hall Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 19, 1983 Weight of Hammer 63.64 kgs Coordinates See borehole
 Date Finished Jan. 19, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot				
							10	20	30	40	50
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	7	SPT-1	Silty Clay, brown, stiff medium plastic, moist in place (CL)	1.0						
	100	8	SPT-2	Silty sand, yellowish brown, medium dense low plasticity, moist in place with traces of gravel (SM)	2.0						
	100	14	SPT-3	End of Boring	3.0						

Checked by: E. RAMIREZ / Materials Testing Engr.

Noted by: D. R. FERMIN, JR. / President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-3
 Project Mess Hall Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 19, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 19, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m.	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	6	SPT-1	Silty Clay, brown, medium stiff to stiff, high plasticity, moist in place (CH)	1.0	-				
	100	8	SPT-2		2.0					
	100	9	SPT-3		3.0					
				End of Boring						

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-4A
ICMC Vocational
 Project Training Center Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long		00 11	SPT-1	Silty Clay, dark brown, stiff to very stiff, high plasticity, moist in place (CH)	1.0					
		00 29	SPT-2		2.0					
		00 28	SPT-3	3.0	End of Boring					

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-4B
~~ICMC Vocational~~
 Project Training Center Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long		11	SPT-1	Silty Clay, dark brown stiff to hard, high plasticity, moist in place (CH)	1.0					
		30	SPT-2		2.0					
		33	SPT-3		3.0					
				End of Boring						

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-6
 Project Staff Dormitories Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long				Silty Clay, light brown stiff, high plasticity, moist in place. (CL)	1.0					
	100	11	SPT-1	Clayey Sand, yellowish brown, low plasticity moist in place with traces of gravel (SC)	2.0					
	100	8	SPT-2	Silty Sand, yellowish, brown, low plasticity, moist in place with traces of gravel (SM)	3.0					
	100	16	SPT-3	End of Boring						

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-7
 Project Medical Dental Processing Center Water Table Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger	100	7	SPT-1	Silty Clay, dark brown, medium stiff to very stiff, high plasticity, moist in place (CH)	1.0					
SPT Sampler	100	11	SPT-2		2.0					
5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	23	SPT-3		3.0					
				End of Boring						

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Feature Phil. Refugee Processing Center Ground Elevation No Data Hole No. BH-8
 Project Medical Dental Dispensary Water table Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole location plan
 Date Finished Jan. 20, 1983 Height of Drop 0.762

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot				
							10	20	30	40	
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	10	SPT-1	Silty Clay, dark brown stiff, high plasticity, moist in place (CH)	1.0						
	100	7	SPT-2	Clayey Sand, yellowish brown, medium dense, moist in place with gravel	2.0						
	100	12	SPT-3		3.0						
				End of Boring							

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Feature Phil. Refugee Processing Center Ground Elevation No Data Hole No. BH-9
 Project Medical Dental Dispensary Water table Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole location plan
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	7	SPT-1	Silty Clay, dark brown medium, stiff to stiff, high plasticity, moist in place (CH)	1.0					
	100	5	SPT-2		2.0					
	100	11	SPT-3		3.0					
				End of Boring						

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. /President

SUBSURFACE EXPLORATION LOG

Phil. Refugee
 Feature Processing Center Ground Elevation No Data Hole No. BH-10
 Project Dental Prosthetic Lab. Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs. Coordinates See borehole
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters location plan

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot			
							10	20	30	40
10 cm. Ø Hand Auger SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	12	SPT-1	Silty Clay, reddish brown, stiff, high plasticity, moist in place (CH)	1.0					
	100	16	SPT-2		2.0					
	100	9	SPT-3		3.0					
				End of Boring						

Checked by: E. RAMIREZ Materials Testing Engr.

Noted by: D. R. FERMIN, JR. President

SUBSURFACE EXPLORATION LOG


Feature Phil. Refugee Processing Center Ground Elevation No Data Hole No. BH-11
 Project Staff Dormitories Watertable Elev. None Location Morong, Bataan
 Hole Logged By F. Alcaraz Date gaged - Depth of Hole 3.0 meters
 Date Begun Jan. 20, 1983 Weight of Hammer 63.64 kgs Coordinates See borehole location plan
 Date Finished Jan. 20, 1983 Height of Drop 0.762 meters

Notes Type & Size of hole Type of Sampler Loss of Drilling Water	Recovery, %	No. of Blows	Sample taken	Description and Classification of Material	Depth, m	Log	Penetration Resistance blows per foot						
							10	20	30	40			
10 cm. Ø Hand Auger	100	10	SPT-1	Silty Clay, dark brown, stiff, high plasticity, moist in place (CH)	1.0								
SPT Sampler 5.08 cm. O.D. 3.50 cm. I.D. 60 cm. long	100	8	SPT-2	Silty Sand, yellowish brown, medium dense, moist in place with traces of gravel (SM)	2.0								
	100	16	SPT-3	End of Boring	3.0								

Checked by: E. RAMIREZ Materials Testing Engr.


Noted by: D. R. PERMIN, JR. / President

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-1




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : PHILIPPINE Refugee Processing Center
 BOREHOLE NO. : BH-2




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-3




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-4A



GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)


PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-4B



GRAIN SIZE DISTRIBUTION


(UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : PHILIPPINE Refugee Processing Center
 BOREHOLE NO. : BH-6




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-7




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-8




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-9




GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
BOREHOLE NO. : BH-10



GRAIN SIZE DISTRIBUTION
(UNIFIED SOIL CLASSIFICATION SYSTEM)

PROJECT : Philippine Refugee Processing Center
 BOREHOLE NO. : BH-11



GRAIN SIZE DISTRIBUTION
 (UNIFIED SOIL CLASSIFICATION SYSTEM)

LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS


TRN :

Date :

PROJECT Philippine Refugee Processing Center	LAB. NO.
MATERIAL BH-1 - SPT-1, SPT-2, SPT-3	T. R. NO.
TESTED BY ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	15	9	A	13 A	12
WT. OF CAN AND WET SOIL	23.32	25.25	25.19	15.26	13.12
WT. OF CAN AND DRY SOIL	18.98	19.82	19.69	14.05	11.93
WT. OF WATER	4.34	5.43	5.50	1.21	1.19
WT. OF CAN	9.73	9.81	9.69	9.73	7.68
WT. OF DRY SOIL	9.25	10.01	10.00	4.32	4.25
PERCENT MOISTURE	46.92	54.25	55.00	28.01	28.00
NO. OF BLOWS	35	24	12	Average = 28.01	

FLOW CURVE



LIQUID LIMIT 54	PLASTIC LIMIT 28	PLASTICITY INDEX 26
COMPUTED BY REP	DATE 1/24/83	CHECKED BY ETR
		DATE 1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-2 - (0.7 - 1.0)	T. R. NO.
TESTED BY	ROSEMARIE E. PAJARES/Sr. Lab. Technician	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	16	8	18	23	25
WT. OF CAN AND WET SOIL	22.78	21.15	22.41	14.24	11.75
WT. OF CAN AND DRY SOIL	18.66	16.51	16.59	13.32	10.83
WT. OF WATER	4.12	4.64	5.82	0.92	0.92
WT. OF CAN	9.70	6.95	6.20	10.05	7.54
WT. OF DRY SOIL	8.96	9.56	10.39	3.27	3.29
PERCENT MOISTURE	45.98	48.54	56.02	28.13	27.96
NO. OF BLOWS	36	27	12	Average = 28.05	

FLOW CURVE



LIQUID LIMIT	49	PLASTIC LIMIT	28	PLASTICITY INDEX	21
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
		DATE	1/25/83		

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.	
MATERIAL	BH-2 - SPT-2, SPT-3	T. R. NO.	
TESTED BY	ROSEMARIE E. PAJARES/Sr. Lab. Technician	DATE	Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT		
	1	2	3	1	2	
CAN NO.	5	6	19	3	6 A	
WT. OF CAN AND WET SOIL	23.06	24.35	26.54	18.03	15.39	
WT. OF CAN AND DRY SOIL	19.81	20.43	21.90	16.39	13.83	
WT. OF WATER	3.25	3.92	4.64	1.64	1.56	
WT. OF CAN	9.96	9.23	9.99	9.98	7.54	
WT. OF DRY SOIL	9.85	11.20	11.91	6.41	6.29	
PERCENT MOISTURE	32.99	35.00	38.96	25.59	24.80	
NO. OF BLOWS	30	20	10	Average = 25.20		

FLOW CURVE



LIQUID LIMIT	34	PLASTIC LIMIT	25	PLASTICITY INDEX	9
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
				DATE	1/25/83


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-3, SPT-1, SPT-2, SPT-3	T. R. NO.
TESTED BY	ROSEMARIE E. PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT		
	1	2	3	1	2	
CAN NO.	E	24	9	18 A	10	
WT. OF CAN AND WET SOIL	22.03	22.59	23.70	12.00	13.15	
WT. OF CAN AND DRY SOIL	17.68	17.99	18.38	10.88	12.05	
WT. OF WATER	4.35	4.60	5.32	1.12	1.10	
WT. OF CAN	9.31	9.70	9.77	6.27	7.47	
WT. OF DRY SOIL	8.37	8.29	8.61	4.61	4.58	
PERCENT MOISTURE	51.97	55.49	61.79	24.30	24.02	
NO. OF BLOWS	39	26	14	Average = 24.16		

FLOW CURVE



LIQUID LIMIT	56	PLASTIC LIMIT	24	PLASTICITY INDEX	32
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
					DATE
					1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT Philippine Refugee Processing Center	LAB. NO.
MATERIAL BH-4A, SPT-1, SPT-2, SPT-3	T. R. NO.
TESTED BY ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	25	16	12	4 A	7
WT. OF CAN AND WET SOIL	21.16	23.40	21.90	13.36	13.48
WT. OF CAN AND DRY SOIL	16.00	18.14	16.22	12.15	12.29
WT. OF WATER	5.16	5.26	5.68	1.21	1.19
WT. OF CAN	7.51	9.70	7.63	7.37	7.53
WT. OF DRY SOIL	8.49	8.44	8.59	4.78	4.76
PERCENT MOISTURE	60.78	62.32	66.12	25.32	25.00
NO OF BLOWS	34	23	10	Average = 25.16	

FLOW CURVE



LIQUID LIMIT 62	PLASTIC LIMIT 25	PLASTICITY INDEX 37
COMPUTED BY REP	DATE 1/24/83	CHECKED BY ETR
		DATE 1/25/83


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-4B, SPT-1, SPT-2, SPT-3	T. R. NO.
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	23	11 A	19 A	15	8
WT. OF CAN AND WET SOIL	22.99	23.62	20.90	15.24	12.25
WT. OF CAN AND DRY SOIL	18.17	18.08	15.09	14.08	11.15
WT. OF WATER	4.82	5.54	5.81	1.16	1.10
WT. OF CAN	10.03	9.25	6.42	9.70	6.92
WT. OF DRY SOIL	8.14	8.83	8.67	4.38	4.23
PERCENT MOISTURE	59.21	62.74	67.01	26.48	26.00
NO. OF BLOWS	34	20	12	Average = 26.24	

FLOW CURVE



LIQUID LIMIT	61	PLASTIC LIMIT	26	PLASTICITY INDEX	35
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
				DATE	1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-6, SPT-1 (0.7 - 1.0 M)	T. R. NO.
TESTED BY	Rosemarie Pajares/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT		
	1	2	3	1	2	
CAN NO.	4	10	18 A	19	23	
WT. OF CAN AND WET SOIL	21.57	19.13	17.87	13.57	17.09	
WT. OF CAN AND DRY SOIL	17.41	14.89	13.33	12.04	15.59	
WT. OF WATER	4.16	4.24	4.54	1.53	1.50	
WT. OF CAN	9.71	7.47	6.27	6.42	10.03	
WT. OF DRY SOIL	7.70	7.42	7.06	5.62	5.56	
PERCENT MOISTURE	54.03	57.14	64.31	27.22	26.98	
NO. OF BLOWS	32	22	11	Average = 27.10		

FLOW CURVE



LIQUID LIMIT	56	PLASTIC LIMIT	27	PLASTICITY INDEX	29
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
				DATE	1/25/83


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-6, SPT-2 (1.7 - 2.0 m)	T. R. NO.
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	15	9	18 A	25	E
WT. OF CAN AND WET SOIL	20.69	20.64	16.65	14.47	16.16
WT. OF CAN AND DRY SOIL	17.55	17.39	13.19	12.86	14.58
WT. OF WATER	3.14	3.25	3.46	1.61	1.58
WT. OF CAN	9.70	9.77	6.27	7.51	9.31
WT. OF DRY SOIL	7.85	7.62	6.92	5.35	5.27
PERCENT MOISTURE	40.00	42.65	50.00	30.09	29.98
NO. OF BLOWS	33	24	11	Average = 30.04	

FLOW CURVE



LIQUID LIMIT	42	PLASTIC LIMIT	30	PLASTICITY INDEX	12
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ER
				DATE	1/25/83


NPPSBO GUAM

LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-6, SPT-3 (2.7 - 3.0 m)	T. R. NO.
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	25	23	18	12	A
WT. OF CAN AND WET SOIL	21.19	26.09	21.43	12.91	14.86
WT. OF CAN AND DRY SOIL	17.79	21.97	16.79	11.79	13.76
WT. OF WATER	3.40	4.12	4.64	1.12	1.10
WT. OF CAN	7.54	10.05	6.20	7.68	9.69
WT. OF DRY SOIL	10.25	11.92	10.59	4.11	4.07
PERCENT MOISTURE	33.17	34.56	43.81	27.25	27.03
NO. OF BLOWS	31	26	11	Average = 27.14	



LIQUID LIMIT	35	PLASTIC LIMIT	27	PLASTICITY INDEX	8
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
					DATE
					1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT Philippine Refugee Processing Center	LAB. NO.
MATERIAL BH-7, SPT-1, SPT-3, SPT-2	T. R. NO.
TESTED BY ROSEMARIE PAJRES/Sr. Lab. Tech.	DATE Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	15	6	3	12	23
WT. OF CAN AND WET SOIL	23.55	23.61	26.02	12.13	14.44
WT. OF CAN AND DRY SOIL	18.41	18.13	19.52	11.15	13.48
WT. OF WATER	5.14	5.48	6.50	0.98	0.96
WT. OF CAN	9.73	9.23	9.98	7.68	10.05
WT. OF DRY SOIL	8.68	8.90	9.54	3.47	3.43
PERCENT MOISTURE	59.22	61.57	68.13	28.24	27.99
NO OF BLOWS	32	24	12	Average = 28.12	

FLOW CURVE



LIQUID LIMIT 61	PLASTIC LIMIT 28	PLASTICITY INDEX 33
COMPUTED BY REP	DATE 1/24/83	CHECKED BY ETR
		DATE 1/25/83

NPPSBO GUA


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-8, SPT-1, SPT-2	T. R. NO.
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	25	23	8	24 A	1 B
WT. OF CAN AND WET SOIL	19.35	22.78	19.29	11.05	10.86
WT. OF CAN AND DRY SOIL	15.10	18.14	14.37	10.07	9.90
WT. OF WATER	4.25	4.64	4.92	0.98	0.96
WT. OF CAN	7.51	10.03	6.92	6.33	6.21
WT. OF DRY SOIL	7.59	8.11	7.45	3.74	3.69
PERCENT MOISTURE	55.99	57.21	66.04	26.20	26.02
NO. OF BLOWS	33	27	12	Average = 26.1	

FLOW CURVE



LIQUID LIMIT	58	PLASTIC LIMIT	26	PLASTICITY INDEX	32
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
					DATE
					1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT Philippine Refugee Processing Center	LAB. NO.
MATERIAL BH-8, SPT-3	T. R. NO.
TESTED BY ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT		
	1	2	3	1	2	
CAN NO.	8	14	7	16	24	
WT. OF CAN AND WET SOIL	19.16	21.36	20.99	17.07	17.06	
WT. OF CAN AND DRY SOIL	15.74	17.87	16.75	15.43	15.46	
WT. OF WATER	3.42	3.49	4.24	1.64	1.60	
WT. OF CAN	6.92	9.47	7.53	9.70	9.70	
WT. OF DRY SOIL	8.82	8.40	9.22	5.73	5.76	
PERCENT MOISTURE	38.78	41.55	45.99	28.62	27.78	
NO. OF BLOWS	32	20	11	Average = 28.20		

FLOW CURVE



LIQUID LIMIT 40	PLASTIC LIMIT 28	PLASTICITY INDEX 12
COMPUTED BY REP	DATE 1/24/83	CHECKED BY ETR
		DATE 1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-9, SPT-1, SPT-2, SPT-3	T. R. NO.
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT		
	1	2	3	1	2	
CAN NO.	13 A	10	24 A	12	1 B	
WT. OF CAN AND WET SOIL	23.78	21.87	20.20	15.20	13.68	
WT. OF CAN AND DRY SOIL	18.66	16.51	14.56	13.59	12.09	
WT. OF WATER	5.12	5.36	5.64	1.61	1.59	
WT. OF CAN	9.68	7.47	6.33	7.68	6.20	
WT. OF DRY SOIL	8.98	9.04	8.23	5.91	5.89	
PERCENT MOISTURE	57.02	59.29	68.53	27.24	26.99	
NO OF BLOWS	34	27	12	Average = 27.12		

FLOW CURVE



LIQUID LIMIT	60	PLASTIC LIMIT	27	PLASTICITY INDEX	33
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
				DATE	1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.
MATERIAL	BH-10, SPT-1, SPT-2, SPT-3	T. R. NO.
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE
		Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	25	A	12	4	24
WT. OF CAN AND WET SOIL	21.44	23.55	22.42	17.44	17.36
WT. OF CAN AND DRY SOIL	16.30	18.30	16.30	15.83	15.78
WT. OF WATER	5.14	5.25	6.12	1.61	1.58
WT. OF CAN	7.54	9.69	7.68	9.71	9.70
WT. OF DRY SOIL	8.76	8.61	8.62	6.12	6.08
PERCENT MOISTURE	58.68	60.98	71.00	26.31	25.99
NO. OF BLOWS	35	28	12	Average = 26.15	

FLOW CURVE



LIQUID LIMIT	62	PLASTIC LIMIT	26	PLASTICITY INDEX	36
COMPUTED BY	REP	DATE	1/25/83	CHECKED BY	ETR
					DATE
					1/25/83

NPPSHQ GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT Philippine Refugee Processing Center	LAB. NO.
MATERIAL BH-11, SPT-1, SPT-2	T. R. NO.
TESTED BY ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	2	13	25	9	6
WT. OF CAN AND WET SOIL	18.55	20.32	20.87	18.02	17.37
WT. OF CAN AND DRY SOIL	14.42	15.90	15.73	16.31	15.69
WT. OF WATER	4.13	4.42	5.14	1.71	1.68
WT. OF CAN	6.19	7.65	7.54	9.81	9.23
WT. OF DRY SOIL	8.23	8.25	8.19	6.50	6.46
PERCENT MOISTURE	50.18	53.58	62.76	26.31	26.01
NO. OF BLOWS	34	26	13	Average = 26.16	

FLOW CURVE



LIQUID LIMIT 54	PLASTIC LIMIT 26	PLASTICITY INDEX 28
COMPUTED BY REP	DATE 1/24/83	CHECKED BY ETR
		DATE 1/25/83

NPPSBO GUAM


LIQUID LIMIT, PLASTIC LIMIT & PLASTICITY INDEX OF SOILS

TRN :
 Date :

PROJECT	Philippine Refugee Processing Center	LAB. NO.	
MATERIAL	BH-11, SPT-3 (2.7 - 3.0 m)	T. R. NO.	
TESTED BY	ROSEMARIE PAJARES/Sr. Lab. Tech.	DATE	Jan. 22, 1983

TRIAL NO.	LIQUID LIMIT			PLASTIC LIMIT	
	1	2	3	1	2
CAN NO.	3	10	A	24 A	11 A
WT. OF CAN AND WET SOIL	22.47	20.16	21.87	15.84	18.81
WT. OF CAN AND DRY SOIL	19.37	16.90	18.41	13.92	16.91
WT. OF WATER	3.10	3.26	3.46	1.92	1.90
WT. OF CAN	9.98	7.47	9.69	6.33	9.25
WT. OF DRY SOIL	9.39	9.43	8.72	7.59	7.66
PERCENT MOISTURE	33.01	34.57	39.68	25.30	24.80
NO. OF BLOWS	30	23	10	Average = 25.05	

FLOW CURVE



LIQUID LIMIT	34	PLASTIC LIMIT	25	PLASTICITY INDEX	9
COMPUTED BY	REP	DATE	1/24/83	CHECKED BY	ETR
					DATE
					1/25/83


NPPSBO GUAM

GEOTESTING

PROJECT : Philippine Refugee Processing Center,
Morong, Bataan

MOISTURE CONTENT RESULTS

	<u>Sample</u>	<u>Moisture Content, %</u>
BH-1	SPT-1	25.43
	SPT-2	24.69
	SPT-3	31.11
BH-2	SPT-1	25.42
	SPT-2	22.50
	SPT-3	25.34
BH-3	SPT-1	26.47
	SPT-2	33.52
	SPT-3	36.16
BH-4A	SPT-1	18.89
	SPT-2	35.79
	SPT-3	15.46
BH-4B	SPT-1	22.46
	SPT-2	13.87
	SPT-3	24.00
BH-6	SPT-1	23.17
	SPT-2	19.09
	SPT-3	18.91
BH-7	SPT-1	35.48
	SPT-2	35.68
	SPT-3	35.78
BH-8	SPT-1	30.27
	SPT-2	31.86
	SPT-3	37.00
BH-9	SPT-1	22.52
	SPT-2	27.84
	SPT-3	31.46
BH-10	SPT-1	29.61
	SPT-2	27.02
	SPT-3	39.41
BH-11	SPT-1	18.12
	SPT-2	20.97
	SPT-3	31.06




PHILIPPINE REFUGEE
PROCESSING CENTER

LOCATION OF BOREHOLES
DRAWN NOT TO SCALE

DRAWN BY:
FREDDIE J. ALCARAZ
JR. MATERIALS ENGINEER

5. SURVEYED MAP OF CONSTRUCTION SITE AND EXISTING FACILITIES




SITE PLAN

① AUDIO-VISUAL STUDENTS SERVICE CENTER

S. 1/500



ROAD




SITE PLAN

s. 1/500


② AUDIO-VISUAL STUDENTS SERVICE CENTER

LOCATION : PHASE - II

- 130 - NBHD - 9




③ MESS HALL SITE PLAN S.1/200




EXISTING CONDITION OF
 ③ MESS HALL KITCHEN S. 1/100
 - 132 -
 LOCATION: CENTRAL AREA


T



③ GUEST HOUSE PLAN S. V200
 EXISTING CONDITION





③ PROPOSED GUEST HOUSE
 KITCHEN PLAN
 TO BE IMPROVED 5/30
 FLOOR AREA: 22.5 M²



③ PROPOSED GUEST HOUSE LOUNGE PLAN
TO BE IMPROVED s. 1/50


FLOOR AREA : 52 M²



PLAN OF EXISTING CONDITION

⑤ P.A. SYSTEM CONTROL ROOM


LOCATION : ADMINISTRATION BLDG.
CENTRAL AREA




S. 1/500

⑦ MEDICAL-DENTAL PROCESSING CENTER

LOCATION : PHASE - I
 - 137 - NBHD - 2
 FLOOR AREA : PROCESSING CENTER 216 M²
 COVERED PASSAGE 27 M² } 243 M²



⑧ MEDICAL-DENTAL DISPENSARY s. 1/500



⑨ MEDICAL-DENTAL DISPENSARY

S. 1/800

LOCATION: PHASE - II
NBHD - 3

ROAD
73.5M

36.5M

ROAD

5.5M

12.4M

21M

5MM

WET MARKET
8.5M

DITCH
W600

MANGO TREE



25M

MEDICAL-DENTAL DISPENSARY

WAITING AREA

PATH

PATH

PATH


STL-RD. LEVEL + 800

67.1M

ROAD

11.5M
5.5M



40.8 M / 10 SPAN




OPENING - SLIDING DOOR
 W 3.980
 H 2.400


⑩ STORAGE FOR MEDICAL SUPPLIES
 TO BE IMPROVED
 LOCATION : PHASE-I, OPERATION CENTER
 FLOOR AREA : 80 M²

WOODEN TRUSS



SECTION 5/1200





⑩ HOSPITAL PLAN OF EXISTING CONDITION S. 1/300

LOCATION : CENTRAL AREA

FLOOR AREA : 2088 M²

JICA