

(7) HVDC system protection (Fig. 6-16)

i) Equipment and bus protection on AC side

The standardized protection system will be adopted.

- AC bus bar (including Naga C/S - Naga S/S)

Differential protection

- Station service transformer

Overcurrent and differential protection

- Shunt capacitor

Overcurrent and voltage differential protection

- 20 kV and 3.3 kV bus

Overcurrent and differential protection

ii) HVDC system protection

a) Filter

- AC filter

Overcurrent and differential protection

- DC filter and surge capacitor

Overcurrent protection

b) Valve, transformer for converter and DC main circuit

- Converter transformer

Overcurrent and differential protection

- Valve short circuit and grounding

Overcurrent protection

- Commutation failure

Differential protection and marginal angle  
detecting protection






Fig.6-16 HVDC SYSTEM PROTECTION BLOCK DIAGRAM (MONOPOLE )(BIPOLE)



|          |                              |
|----------|------------------------------|
| 37D,37DE | DC UNDER CURRENT             |
| 45D      | DC OVER VOLTAGE              |
| 51       | AC OVER CURRENT              |
| 51 T     | TRANS OVER CURRENT           |
| 51 TN    | NEUTRAL OVER CURRENT         |
| 76 D     | DC OVER CURRENT              |
| 80D      | DC OVER VOLTAGE              |
| 87 DG    | DC GROUND FAULT DETECTOR     |
| 87 T     | TRANS PROTECTION             |
| 87 V     | VALVE PROTECTION             |
| 95 D     | POWER FREQUENCY DETECTOR     |
| 27       | AC UNDER VOLTAGE             |
| 59       | AC OVER VOLTAGE              |
| CFD      | COMMUTATION FAILURE DETECTOR |
| 93EL     | OPEN CIRCUIT DETECTOR        |

SAME AS ABOVE



- Grounding fault on the output side of the valve
  - Overcurrent protection
- Grounding fault of main DC circuit
  - Differential protection
- Abnormal pulse
  - Pulse missing protection
- c) Fault in control system
  - Abnormal current control
    - Overcurrent and under current protection
  - Abnormal voltage control
    - Overvoltage and under voltage protection
- d) DC transmission line and electrode line
  - DC transmission line
    - Ground fault and line breaking protection
  - Electrode line
    - Mainly for protection of line breaking

(8) Operation of AC filter

- i) Converter station will be provided with 5th, 7th, 11th, 13th and HP filters at the 1st stage and additional 11th, 13th and HP filters at the 2nd stage.
- ii) Purposes of filter installation are:
  - To absorb high harmonic current emerging from converter

- To generate part of reactive power to be required for converter
- iii) Number of filter branches can be determined from filtration effect of filters.
- iv) Wave form distortion D of the bus line in converter station can be attained as follows from realistic values for the HVDC plan:

$$D = \frac{\sum U_f}{u_1} \leq 3 \sim 4\%$$

$U_f$  : Higher harmonic wave voltage

$u_1$  : Fundamental wave voltage

For certain higher harmonic voltage

$$\frac{U_f}{u_1} \leq 1\%$$

Those target values can be fully satisfied if optional converter load and continuous frequency variation could be restrained within  $\pm 0.2$  Hz in the AC system.

(9) Operation of DC filter

- i) Converter station will be provided with 6th and HP filters at the 1st stage and no more addition to them at the following stage.
- ii) Purpose of filter installation is:
  - To absorb higher harmonic waves to emerge from converter into DC side

In order to ensure same degree of filtration effect as AC filters, the value of high harmonic current to be outflow into DC transmission line may be set as follows, being regarded same as realistic value being used for HVDC plan in Japan.

$$PSO = \sqrt{\sum (Xf \times If)^2} \leq 1 \sim 2A$$

Xf : Weighing factor specified by CCITT Standard

If : Higher harmonic current

#### 6.4.6 Insulation Coordination

##### (1) Generating source of overvoltage

##### i) Overvoltage emerged on AC side

- Surge on transmission line
- Switching surge from on and off of lines and AC filters
- Ferro-resonance overvoltage by on and off of AC filters or transformers and AC system
- Overvoltage due to one pole temporary blocking of HVDC system

##### ii) Overvoltage emerged on DC side

- Surge on DC transmission line
- Overvoltage due to commutation failure

iii) Overvoltage emerged in converter

- Normal switching surge emerged by valve operation
- Overvoltage emerged from commutation failure
- Overvoltage to emerged from short circuit or grounding fault in converter output side

(2) Arrester arrangement

i) Arrester in primary side of transformer

Limitation of lightning and switching surge emerging from AC side and protection of transformer, filter, bus and other AC side equipment

ii) Valve arrester

Limitation of lightning surge emerging from both AC and DC sides and switching surge in DC side of converter and protection of thyristor valve

iii) Valve bridge arrester

Limitation of lightning and switching surge and protection of DC bus and transformer in coordination with valve arrester referred to above.

iv) DC line arrester

Limitation of lightning and switching surge and protection of DC reactor on line side, DC filter, DC bus and other DC side equipment.



[The page contains extremely faint and illegible text, likely due to low contrast or scanning quality. No specific content can be transcribed.]

Fig.6-17 LAYOUT OF JARO CONVERTER STATION (FIRST STAGE)






Fig.6-18 LAYOUT OF NAGA CONVERTER STATION (FIRST STAGE)





v) Electrode line arrester

Limitation of lightning surge emerging from electrode line and protection of DC equipment on electrode line side.

vi) Arrester on DC reactor valve side

Limitation to lightning and switching surge emerging from AC and DC sides and protection of DC reactor valve side.

#### 6.4.7 Converter Station Layout (Fig. 6-17, 6-18)

(1) Layout

i) Site area for construction of Converter Station for both 1st and 2nd stages are as follows:

Naga C/S about 65,000 m<sup>2</sup>

Jaro C/S about 62,000 m<sup>2</sup>

ii) At the 1st stage, two (2) valve halls will be provided with control room in between them and two (2) more valve halls will be added at the 2nd stage.

iii) Equipment on both AC and DC sides will be separated by control room and valve hall in the center.

iv) Transformer for converter will be installed in contact with valve hall wall.

(2) Valve hall

- i) Equipment in the valve hall are valves, arrester for valve protection, earthing device and secondary bushing of converter transformer.
- ii) Air in valve hall should be kept clean at positive pressure.
- iii) Valve constitutes 2 arms in series of air insulation and air cooled.
- iv) Inner side of valve hall will be provided with shielding deck plate, so as to prevent outgoing of radio noise created in converter.
- v) Cooling system including valve-cooling fan etc. will be provided in the under ground room.

Valve cooling system should preferably be designed as air (valve) - cooling water - air (outdoor) system.

(3) Control room

- i) Control room will be divided into following component room.
  - Control room
  - Switchboard room
  - Communication equipment room
  - Auxiliary equipment room
  - Cable room

ii) Communication equipment room will be shielded with iron plate.

(4) Station service system

i) Station service system will be separated by poles.

ii) Engine generator will serve for emergency power supply during stoppage of station service at Jaro converter station.

Naga converter station will receive emergency power supply from Naga substation. DC power for control and communication will be supplied by rectifier and converter station battery.

iii) Converter station battery is capable as emergency and security power source for about one hour and is utilized also for start-up of engine generator.

iv) Transformers for auxiliary equipment are separated by purposes.

6.4.8 Converter Station Equipment

(1) Main equipment rating (1st stage)

i) Thyristor valve

- No. of unit : 12 per each terminal (2-arm lamination)
- Type : Air insulated, air cooling system
- Structure : 2-arm lamination

- Rated DC voltage : 175 kV/1-arm
  - Rated direct current : 1,290 A
  - Rated DC output : 225 MW/group x 2
  - Cooling system : Forced air/water cooling
- ii) Transformer for converter
- No. of unit : 2/each terminal
  - Type : 3 phase outdoor forced oil air-cooled  
With on load tap changer
  - Rated voltage : Jaro 138 kV/154 kV  
Naga 230 kV/154 kV
  - Rated current : Jaro 1,145A/1,053A  
(Primary/secondary) Naga 687A/1,053A
  - Rated capacity : 280 MVA/280 MVA (at 20% impedance)  
(Primary/secondary)
- iii) DC reactor
- No. of unit : 2 per each end
  - Type : Outdoor forced-oil air-cooled
  - Rated voltage : DC 350 kV
  - Rated current : 1,290A
  - Inductance : Approx. 0.8 H
- iv) AC filter
- Composition : 5th, 7th, 11th, 13th, and HP
  - Rated circuit voltage : Jaro 138 kV  
Naga 230 kV



|                               |          |          |
|-------------------------------|----------|----------|
| - Rated capacitive capacity : | Jaro C/S | Naga C/S |
| 5th                           |          |          |
| 7th                           |          |          |
| 11th                          | 135 MVA  | 135 MVA  |
| 13th                          |          |          |
| HP                            |          |          |

v) DC filter and surge capacitor

- Compositional : 6th, HP and surge capacitor/  
each terminal
- Rated circuit voltage: DC 350 kV

vi) Shunt reactor                      Jaro C/S                      Naga C/S

- No. of unit :                      -                      3
- Rated voltage :                      -                      Approx. 20 kV
- Rated lagging capacity :                      -                      30 MVA/unit

vii) Station service transformer

- No. of unit :                      2/each terminal
- Type :                      Outdoor 3-phase forced-oil air-cooled  
  
With on load tap changer
- Rated voltage :  
(Primary/secondary/  
tertiary)

|      |                     |
|------|---------------------|
| Jaro | 138 kV/3.3 kV       |
| Naga | 230 kV/20 kV/3.3 kV |

Naga Converter Station will be connected with shunt reactor on its secondary side.

|   |          |                     |
|---|----------|---------------------|
| - Rated capacity :<br>(Primary/secondary)<br>/tertiary) | Jaro     | 3 MVA/3 MVA         |
|   | Naga     | 90 MVA/90 MVA/3 MVA |
| viii) AC circuit breaker                                | Jaro     | Naga                |
| - No. of unit :   | 11 units | 6 units             |
| - Type :  | GCB type | GCB type            |
| - Rated voltage :                                       | 145 kV   | 245 kV              |
| - Rated breaking current :                              | 20 kV    | 25 kV               |

## 6.5 Communication System

The construction of the HVDC transmission system will be executed as divided into stage 1 and stage 2. In case the construction of the communication system is divided into two stages, the construction to be executed in stage 2 is only a slight addition of the information transmission equipment. Therefore the communication system should be entirely completed in stage 1.

### 6.5.1 Design Conditions

The communication equipment required for this project will be designed based on the following conditions.

#### (1) Microwave radio equipment

- As for the frequency, the frequency band of 7 GHz is to be used with the topography, weather and so forth taken into account.

For the propagation path over the sea or coastline, the diversity reception system is adopted in order to avoid the fading of radio wave.

- In order to obtain the reliability required for transmission of protection and control signals available for the DC transmission system, the interruption rate of the telecommunication line should be  $1 \times 10^{-4}$  or less.
- The equipment of 300 CH capacity type is to be used to provide sufficient channel capacity with expansion of channels in the future taken into account.

(2) Information transmission equipment for control and protection

- The transmission speed is 42 k bits/sec, since high speed transmission is required for control and protection signals.
- The dual systems is to be provided for transmission between both converter stations, because particularly high reliability is required.

(3) Information transmission equipment for supervision

- Although high transmission speed of signals is not particularly required, the high reliability and the numerous data transmission is required between both converter stations. Therefore, dual systems of transmission speed of 1,200 bits/sec are to be provided. Single system for low speed of 200 bits/sec is to be provided between Tongonan S/Y and Jaro C/S.

(4) Transmission line fault locator

- The transmission line fault locator in the section of overhead transmission line between Naga C/S and Jaro C/S is only taken up in this study. The section between Jaro C/S and Tongonan S/Y, is to be excluded from this project, because it is desirable that the system should be made collectively with in transmission lines which

are installed in Tongonan S/Y side under separate project.

(5) Power supply facilities for communication equipment

a) For repeating station

Since each repeating station is located without distribution lines, a power supply facilities composed of solar cells and storage batteries is to be provided with ease of maintenance and economy taken into account. It is desirable that the power supply capacity is designed based on the solar radiation intensity (langley/day) of each point, but in this plan the capacity that supply of power even on cloudy or rainy day was selected referring similar data used.

b) Tongonan S/Y, Naga C/S and Jaro C/S

DC uninterruptible power system using floating charge system is adopted, and telephone lines for load dispatching and for maintenance are secured even on occurrence of house power service interruption.

(6) Others

a) Selection of locations of repeating stations

In this study the sites of repeating stations are selected on the map based on the results of field surveys in

Pasacao, Legaspi, Colomutan, Calbayog, Catbalogan and Bagahapi proposal so as to connect between Naga C/S and Jaro C/S.

For final selection of sites, however, it is necessary to carry out more detailed field surveys regarding topography, road conditions, path profil and so forth.

- b) For the purpose of control, protection and supervision of Tongonan P/S, an information transmission equipment between Tongonan P/S ~ Tongonan S/Y is required, but it should be excluded from this study since it will be done in other planning.

#### 6.5.2 Required Equipment

The equipment required for this project are as shown in Table 6-5. The specifications of these equipment are as follows.

##### (1) Microwave radio installation

##### a) Microwave radio equipment

Frequency : 7 GHz band  
Transmitting power : 0.1 W, 0.5 W  
Channel capacity : 300 CH  
Redundancy method : Twin pass system

##### b) Carrier terminal equipment

Multiplication method : Frequency division system





Table 6-5 TELECOMMUNICATION EQUIPMENT LIST (Preliminary)

| Use of Communication   | Telecommunication Equipment                | Naga C/S | Pasacao R/S | Legaspi R/S | Calorant/Magdalen R/S | Santa C/T | Lipaata C/T | Calbayog R/S | Catbalogan R/S | Jaro C/S | Tongonan S/Y | Equipment Specification   |
|--|--|----------|-------------|-------------|-----------------------|-----------|-------------|--------------|----------------|----------|--------------|---|
| Communication Circuit for Telephone, Signal Transmission   | Micro wave Radio Equipment (Terminal type) | 2        | 4           | 4           | 4                     |           |             | 4            | 4              | 4        | 2            | 7GHz band, 300ch Twin-Path Heterodyne Repeating Transmitting output 0.1~0.5W With Antenna Wave guide. |
|  | Multiplex Terminal Equipment               | 2        |             |             |                       |           |             |              |                | 3        | 1            | Frequency Division Multiplex System   |
|  | Local Terminal Equipment                   | 1        |             |             | 1                     |           |             |              | 1              | 1        | 1            |   |
| Repeater Station Supervision   | Supervisory Equipment                      | 1        | 1           | 1           | 1                     |           |             | 1            | 1              | 1        | 1            | With Order Wire Telephone   |
| Mobile Radio Telephone   | VHF Radio Equipment (Base Station Type)    | 1        |             |             |                       |           |             |              |                | 1        |              | 150 MHz band Press to talk System Transmitter output Base   |
|  | (Mobile Type)                              | 4        |             |             |                       |           |             |              |                | 4        |              | Mobile } 10W Portable } 1W With Antenna Cable   |
|  | (Portable Type)                            | 10       |             |             |                       |           |             |              |                | 10       |              |   |
|  | Base Station Control Equipment             | 1        |             |             | 1                     |           |             |              |                | 1        | 1            |   |
| Telephone for Maintenance, Operation Work  | Telephone set                              | 2        |             |             |                       |           |             |              |                | 3        | 2            | Party Line System Common Battery System.  |
| Administrative Telephone   | Automatic Telephone Exchange               | 1        |             |             |                       |           |             |              |                | 1        |              | Subscribers Capacity 20L  |
| Control Protection Signal Transmission for Converter Station, Power Station and AC Transmission Line | CDT Equipment (High Speed Type)            | 2        |             |             |                       |           |             |              |                | 3        | 1            | Cyclic Digital Transmission System Transmission Speed High Speed 42 kb/s Low Speed 1200 b/s 200 b/s   |
|  | (Low Speed Type)                           | 2        |             |             |                       |           |             |              |                | 3        | 1            |   |
| DC Power Supply for Telecommunication Equipment  | Battery and Battery Charger                | 2        |             |             |                       |           |             |              |                | 2        | 1            | DC 24V DC 48V   |
|  | Solar Cell and Battery                     |          | 1           | 1           | 1                     | 1         | 1           | 1            | 1              |          |              | DC 24V  |
| Other Necessary Contructs  | Antenna Tower                              | 1        | 1           | 1           | 1                     |           |             | 1            | 1              | 1        | 1            | Self-Supporting Type  |
|  | Repeater Station Building                  |          | 1           | 1           | 1                     |           |             | 1            | 1              |          |              | Floor Space 4 x 4 m <sup>2</sup>  |
|  | Reflector                                  |          |             |             |                       |           |             |              |                |          | 2            |   |
|  | Fault Locator                              | 1        |             |             |                       |           |             |              |                | 1        |              | Pulse rader Type  |
|  | Line Trap                                  | 2        |             |             |                       |           |             |              |                | 2        |              |   |
|  | Coupling Capacitor                         | 2        |             |             |                       |           |             |              |                | 2        |              |   |





- c) Antenna
  - Parabolic antenna : 3 m dia., 4 m dia
- d) Reflector
  - 6 m x 8 m : Two units
- e) Repeating station
  - Number of stations : 6

The outline of each repeating station is shown in Fig. 6-19.

(2) Data transmission equipment for control, protection

- Transmission speed : 42 k bits/sec
- Signalling system : FS

Number of words

- Naga C/S to Jaro C/S : 11 words
- Jaro C/S to Naga C/S : 11 words
- Jaro C/S to Tongonan S/Y : 11 words
- Tongonan S/Y to Jaro C/S : 11 words

(3) Data transmission equipment for supervision

- Transmission speed : 1,200 bits/sec or 200 bits/sec
- Signalling system : FS


Number of words


- Naga C/S to Jaro C/S : 31 words
- Jaro C/S to Naga C/S : 31 words
- Jaro C/S to Tongonan S/Y : 6 words
- Tongonan S/Y to Jaro C/S : 12 words



[The page contains extremely faint and illegible text, likely due to low contrast or scanning quality. The text is arranged in several paragraphs, but the individual words and sentences cannot be discerned.]

Fig. 6-19 TELECOMMUNICATION SYSTEM DIAGRAM (Preliminary)





- (4) Telephone equipment for maintenance and administration
- a) Party-line telephone
- Place of installation : Naga C/S, Jaro C/S, and  
Tongonan S/Y
- b) Automatic switchboard
- Capacity : 20 lines
- (5) Overhead transmission line fault locating equipment
- Method of orientation : Pulse radar system
- Orientating area : from Naga C/S to Santa  
and Magdalena C/T  
from Jaro C/S to Lipata C/T
- (6) Submarine cable oil pressure supervising device
- a) VHF radio unit
- Frequency : 150 MHz band
- Transmitting power : 10 W
- b) Power supply device for the above
- Solar cell : DC 24 V, 100 W
- Storage battery : 170 AH
- (7) Mobil wireless telephone equipment for line maintenance
- Maintenance : 150 MHz band
- Frequency : For base station : 10 W  
For mobil station: 10 W  
For portable station: 1 W
- Method of speech : Press-to-talk system

(8) Power supply device for telecommunication

a) For repeating station

Solar cell : DC 24 V, 300 W or 400 W  
Storage battery : 800 AH or 1,200 AH

b) Naga C/S, Jaro C/S, Tongonan S/Y

Battery charger

24 V 150 A : Jaro C/S  
100 A : Naga C/S  
75 A : Tongonan S/Y  
48 V 3 A : Jaro C/S and Naga C/S

Storage battery

24 V 700 AH : Jaro C/S  
500 AH : Naga C/S  
400 AH : Tongonan S/Y  
28 V 210 AH : Jaro C/S and Naga C/S

(9) Dispatching communication equipment


Common battery system

Place of installation : Naga C/S - Jaro C/S  
and  
Jaro C/S - Tongonan S/Y



## **CHAPTER 7**

### **SYSTEM ANALYSIS**



## CHAPTER 7 SYSTEM ANALYSIS

In order to ensure stable transmission from the Leyte geothermal power plants into the Luzon power grid, studies have been made with regard to power flow and voltage at normal operation and stability at ground fault of the transmission line to the HVDC interconnected system.

In the case of power transmission from the Leyte geothermal power plant through the HVDC system, there would exist no fear factor essentially involved in stability of synchronized operation between the said geothermal plant and the Luzon grid.

However, it should be noted that Naga Converter Station as the power receiving end of the HVDC system is situated on the sending end of the EHV 500 kV transmission system for Tiwi and Manito geothermal power plants at the southern part of Luzon.

Because of this situation, power to be generated from the Leyte geothermal power plants, along with generated power at Tiwi and Manito, will be transmitted through the EHV 500 kV (230 kV) over a distance of about 300 km, by way of Kalayaan, to San Jose. Therefore, the transmission capacity of the HVDC system will be determined depending mainly upon the degree of stability in the southern part of Luzon grid including Tiwi and Manito.

As the result of system analysis, it has been confirmed that the power of 400 MW in 1986 and 900 MW in 1993 will be able to send without any problem, by installing power system stabilizer at Tiwi, Manito and other power plants.

## 7.1 Premises

### 7.1.1 System Conditions

#### (1) Power System

Luzon - Samar - Leyte grid (Fig. 7.1)

#### (2) Demand

As per demand forecast presented by NAPOCOR (Table 7.1 and 7.2)

Power factor is set at 95 percent uniformity.

#### (3) Power Supply

Operation priorities are given as follows to power generating sources of different patterns:

- ① Hydro power      ② Nuclear power      ③ Geothermal power  
④ Coal-fired power      ⑤ Oil-fired power

#### (4) Years Under Study

|      |  |
|------|--|
| 1986 | 400 MW HVDC transmission power             |
| 1991 | 600 MW                                   " |
| 1993 | 900 MW                                   " |





Fig. 7-1 Luzon Grid Single Line Diagram ~ 1993



[The page contains extremely faint and illegible text, likely due to low contrast or scanning quality. The text is arranged in several paragraphs, but the individual words and sentences cannot be discerned.]

Table 7-1. (1) Bulk Substation Forecasted Load (NAPOCOR Area)

(MW)

| Substations        | 1979 | 1980 | 1981 | 1982 | 1983 | 1984 | 1985 | 1986 | 1987 | 1988 | 1989 | 1990 | 1991 | 1992 | 1993 | 1994 | 1995 |
|--------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|
| Ballesteros        |      |      |      |      |      |      |      |      |      | 9.5  | 10   | 10.5 | 11   | 12   | 13   | 14   | 14   |
| San Estaban        | -    | -    | 30   | 37   | 43   | 49   | 56   | 64   | 72   | 82   | 93   | 96   | 102  | 109  | 116  | 123  | 132  |
| Bauang             |      | 43   | 22   | 24   | 25   | 27   | 29   | 41   | 44   | 52   | 66   | 81   | 86   | 92   | 98   | 104  | 111  |
| Baguio             |      | 65   | 70   | 77   | 78   | 83   | 91   | 98   | 102  | 108  | 110  | 111  | 117  | 124  | 132  | 141  | 150  |
| Ambukiao *(Beckel) |      | 30   | 30   |      |      |      |      |      |      |      |      |      |      |      |      |      |      |
| Mankayan           | -    | -    | -    | 41   | 48   | 50   | 53   | 53   | 54   | 56   | 58   | 58   | 62   | 66   | 70   | 75   | 80   |
| Lubagan            | -    | -    | 9    | 9    | 9    | 9    | 10   | 12   | 15   | 20   | 25   | 37   | 40   | 42   | 45   | 48   | 51   |
| Lal-Lo             | -    | -    | -    | 3    | 4    | 4    | 4    | 5    | 5    | 5    | 6    | 6    | 6    | 7    | 7    | 8    | 8    |
| Tuguegarao         | -    | -    | 9    | 10   | 13   | 15   | 19   | 23   | 25   | 16   | 16   | 14   | 15   | 16   | 17   | 18   | 19   |
| Santiago           | -    | -    | 13   | 17   | 17   | 19   | 20   | 18   | 19   | 21   | 22   | 24   | 26   | 27   | 29   | 31   | 33   |
| Solano             | -    | -    | 1    | 2    | 3    | 3    | 3    | 3    | 6    | 8    | 9    | 11   | 12   | 12   | 13   | 14   | 15   |
| San Manuel         |      | 48   | 51   | 35   | 36   | 39   | 42   | 43   | 42   | 44   | 46   | 49   | 52   | 56   | 59   | 63   | 67   |
| Labrador           |      | -    | -    | 22   | 25   | 27   | 30   | 33   | 36   | 40   | 44   | 49   | 52   | 56   | 59   | 63   | 67   |
| Botolan            |      | -    | 9    | 10   | 12   | 14   | 15   | 16   | 17   | 18   | 18   | 19   | 20   | 22   | 23   | 24   | 26   |
| Olongapo           |      | 93   | 91   | 93   | 94   | 95   | 101  | 102  | 104  | 105  | 106  | 108  | 115  | 122  | 131  | 139  | 148  |
| Prado              |      | 24   | 24   | 25   | 26   | 28   | 29   | 31   | 33   | 34   | 36   | 38   | 41   | 43   | 46   | 49   | 52   |
| BTTP               |      | 32   | 33   | 34   | 35   | 36   | 37   | 39   | 40   | 41   | 43   | 44   | 47   | 50   | 53   | 57   | 60   |
| EPZA               |      | 20   | 23   | 27   | 31   | 34   | 36   | 38   | 40   | 41   | 44   | 45   | 48   | 51   | 55   | 58   | 62   |
| Mexico             |      | 83   | 88   | 92   | 94   | 100  | 104  | 111  | 116  | 123  | 131  | 139  | 148  | 158  | 168  | 179  | 191  |



Table 7-1.(2) Bulk Substation Forecasted Load (NAPOCOR Area)

(MW)

| Substations        | 1979 | 1980 | 1981 | 1982 | 1983 | 1984 | 1985 | 1986 | 1987 | 1988   | 1989 | 1990   | 1991 | 1992 | 1993 | 1994 | 1995 |
|--------------------|------|------|------|------|------|------|------|------|------|--------|------|--------|------|------|------|------|------|
| Teriac             |      | 28   | 29   | 30   | 31   | 33   | 34   | 36   | 38   | 40     | 42   | 44     | 47   | 50   | 53   | 57   | 60   |
| Cabanatuan         |      | 36   | 41   | 46   | 50   | 57   | 66   | 76   | 89   | 105    | 123  | 146    | 155  | 166  | 177  | 188  | 200  |
| Angat (34.5 kW)    |      | 36   | -    | -    | -    | -    | -    | -    | -    | -      | -    | -      | -    | -    | -    | -    | -    |
| San Jose (34.5 kV) |      | 40   | 42   | 43   | 45   | 47   | 49   | 50   | 57   | 54     | 56   | 58     | 62   | 66   | 70   | 75   | 80   |
| Kalayaan           |      | -    | -    | 15   | 16   | 17   | 19   | 20   | 22   | 23     | 25   | 27     | 29   | 31   | 33   | 35   | 37   |
| Caliraya           |      | 7    | 10   | -    | -    | -    | -    | -    | -    | -      | -    | -      | -    | -    | -    | -    | -    |
| Mak-Ban            |      | 18   | 19   | 20   | 21   | 23   | 24   | 25   | 27   | 39     | 32   | 35     | 37   | 40   | 42   | 45   | 48   |
| Dasmariñas         |      | 20   | 23   | 25   | 28   | 30   | 32   | 36   | 39   | 43     | 45   | 50     | 53   | 56   | 60   | 64   | 69   |
| Batangas           |      | 42   | 45   | 49   | 50   | 54   | 58   | 61   | 66   | 72     | 81   | 90     | 96   | 102  | 109  | 116  | 123  |
| Gumaca             |      | 6    | 7    | 8    | 9    | 9    | 10   | 11   | 12   | 13     | 15   | 15     | 16   | 17   | 18   | 19   | 21   |
| Labo               |      | 4    | 4    | 7    | 9    | 9    | 10   | 10   | 11   | 11     | 12   | 12     | 13   | 14   | 15   | 15   | 17   |
| Naga               |      | 17   | 18   | 20   | 21   | 23   | 26   | 29   | 31   | 34     | 36   | 40     | 44   | 45   | 48   | 51   | 55   |
| Lagaspi            |      | 20   | 22   | 24   | 26   | 24   | 27   | 29   | 32   | 34     | 37   | 41     | 44   | 46   | 50   | 53   | 56   |
| NAPOCOR Total      |      | 699  | 763  | 845  | 899  | 958  | 1034 | 1113 | 1189 | 1282.5 | 1387 | 1497.5 | 1595 | 1698 | 1809 | 1926 | 2052 |

Table 7-2 Bulk Substation Forecasted Load (MERALCO Area)

(MW)

| Substation           | Year | 1980 | 1981 | 1982 | 1983 | 1984 | 1985 | 1986 | 1987 | 1988   | 1989 | 1990   | 1991 | 1992 | 1993 | 1994 | 1995 |
|----------------------|------|------|------|------|------|------|------|------|------|--------|------|--------|------|------|------|------|------|
| Total Load           |      | 2100 | 2240 | 2400 | 2565 | 2745 | 2940 | 3145 | 3365 | 3600   | 3850 | 4120   | 4390 | 4670 | 4975 | 5300 | 5645 |
| NAPOCOR Load         |      | 699  | 763  | 845  | 899  | 958  | 1034 | 1113 | 1189 | 1282.5 | 1387 | 1497.5 | 1595 | 1698 | 1809 | 1926 | 2052 |
| MECO Load            |      | 1401 | 1477 | 1555 | 1666 | 1787 | 1906 | 2032 | 2176 | 2317.5 | 2463 | 2622.5 | 2795 | 2972 | 3166 | 3374 | 3593 |
| Sucat group          |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Balibago, Calauan    |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Cardner, Malibay     |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Rockwell, Taguig     |      | 505  | 529  | 551  | 591  | 631  | 669  | 713  | 760  | 808    | 861  | 921    | 981  | 1045 | 1118 | 1185 | 1262 |
| San Jose group       |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Balintawak, Bocaue   |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Malinta, N-Port      |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Novaliches, Sta Mesa |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Tegen                |      | 630  | 672  | 709  | 762  | 819  | 875  | 934  | 1006 | 1070.5 | 1136 | 1202.5 | 1283 | 1362 | 1446 | 1548 | 1648 |
| Dolores group        |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Dolores, Marikina    |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Rosario, St. Antony  |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Teresa               |      | 235  | 244  | 257  | 272  | 293  | 313  | 331  | 350  | 373    | 396  | 424    | 451  | 480  | 512  | 545  | 580  |
| Malaya group         |      |      |      |      |      |      |      |      |      |        |      |        |      |      |      |      |      |
| Malaya, Botocan      |      | 31   | 32   | 33   | 36   | 38   | 43   | 47   | 53   | 58     | 62   | 66     | 71   | 75   | 80   | 85   | 91   |
| Toyabas              |      | -    | -    | 5    | 5    | 6    | 6    | 7    | 7    | 8      | 8    | 9      | 9    | 10   | 10   | 11   | 12   |

## 7.1.2 Calculation Conditions

### (1) Power Flow Calculation

- Voltage, to satisfy requirement of 100 ± 5% in each bus
- Generator, not exceeding its specified power factor
- To be within limit of specified thermal capacity for transmission line and transformer

### (2) Short-Circuit Capacity

- Transient reactance ( $X_d'$ ) is used as generator reactance.
- Load and back impedance in the DC system are assumed to be infinite.

### (3) Stability

#### 1) Protective conditions against fault

- One circuit 3LG of EHV 500 kV-designed line at the inverter station (NAGA)
- Fault clearing time : 0.1 sec. (6 Hz)
- DC system block - deblock (300 ms)
- No high-speed reclosing

#### 2) Conditions for stable operation

- Swing curve of all generators, to show a damping tendency
- DC system, to be kept free from hunting
- No large fluctuation of voltage and frequency after fault cleared.

Refer to Fig. 7.1 for power plant generating capacity, substation capacity and line length and Fig. 7.2 for impedance map of Luzon grid.

## 7.2 Calculation Results

### 7.2.1 Year 1986

Peak power flow and short-circuit capacity in the year 1986 are shown in Fig. 7.3 and Table 7.4 respectively. No problems involved in both thermal capacity and breaking capacity.

In the meantime, the calculation result on stability at grounding fault on 3-phases in one circuit of EHV 500 kV-designed transmission line between Kalayaan and Naga assures sufficient stability as shown in Fig. 7.5.

Although the HVDC system may block its operation during the time of failure due to drop of AC voltage, it would resume operation to its original capacity of 400 MW upon reinstatement of AC voltage after fault cleared.

From the result above, it is fully assured that by 1986 the EHV 500 kV transmission line will be able to serve well even if operated at 230 kV. Incidentally, since frequency at Leyte geothermal power plants may be apt to rise up largely during restriction upon the transmission power of the HVDC system at

Fig. 7-2 Impedance Map In 1993

{ % at 1000 MVA BASE (T/L, Trf)  
% at Machine BASE (Gen, Gen's Trf) }




Fig. 7-3 Peak Power Flow In 1986

V% /deg  
 p<sub>MW</sub> + jQ<sub>MVAR</sub>




Fig.7-4 Short Circuit Current In 1986 (A)




Table 7-3 Capacity of Phase Modifire at C/S MVA  
(Filter MVA)

Approx. value\*

| Site \ Year          | 1986                          | 1991                   | 1993                        |
|----------------------|-------------------------------|------------------------|-----------------------------|
| Naga C/S             | (135) Filter<br>-90 (Reactor) | (225)<br>-50 (Reactor) | (225)<br>150<br>(Condenser) |
| Jaro C/S             | (135)                         | (225)                  | (225)                       |
| Tongonan<br>Pf = 0.9 | 50                            | 80                     | 100                         |
| Pf = 0.95            | 90                            | 140                    | 180                         |

Table 7-4 Short-circuit Capacity at Major C/S MVA (KA)\*\*


| Site \ Year     | 1986                | 1993                |
|-----------------|---------------------|---------------------|
| San Jose 500 kV | -                   | 5,000 MVA ( 5.8 KA) |
| " 230 kV        | 4,400 MVA (11.0 KA) | 5,100 (12.8)        |
| Kalayaan 500 kV | -                   | 5,000 ( 5.8)        |
| " 230 kV        | 4,500 (11.3)        | 5,000 (12.6)        |
| Naga 500 kV     | -                   | 3,600 ( 4.2)        |
| " 230 kV        | 2,300 ( 5.8)        | 3,600 ( 9.0)        |
| Mak-Ban 230 kV  | 4,900 (12.3)        | 5,200 (13.1)        |
| Binan 230 kV    | 4,900 (12.3)        | 5,000 (12.6)        |
| Rockwell 115 kV | 4,400 (22.1)        | 4,500 (22.6)        |
| Jaro 138 kV     | 900 ( 3.7)          | 1,900 ( 8.1)        |

Note: \* Required capacity in Jaro C/S will change by power factor of Tongonan P/S HVDC System is assumed to operate under rated power at night and peak.

\*\* Transient reactance is used as generator reactance.



Fig. 7-5 Stability In 1986 (HVDC)



the time of fault, it is necessary to provide coordinated control between the Leyte power plants and HVDC system by such way possible as putting the HVDC system into overload operation for a few seconds after recovery from fault.


Besides the above requirement, it is advisable that in order to ensure stabilized operation of the Luzon grid the power system stabilizer should be introduced, from this target year on, into each proposed power plant of Calaca Coal, Tiwi and Mak-ban. No power system stabilizer will be required at Tongonan.

#### 7.2.2 Year 1991

It is planned that by 1991 the HVDC system transmission capacity will be increased to 900 MW ( $\pm 350$  kV in bipole). In fact, however, since the generating capacity to be developed at the Leyte geothermal power source is estimated at 660 MW, the real HVDC transmission power will be at a level of 600 MW or so.

As noted from the stability calculation result shown in Fig. 7.6, it is necessary that the 500 kV-designed EHV transmission line should be stepped up to 500 kV between Kalayaan and Naga.

Fig. 7-6 Stability In 1991  
(EHV 230kv Operation)



### 7.2.3 Year 1993

Fig. 7.7 shows the future power flow map envisaging 900 MW transmission through the HVDC system in 1993. The calculation result at 3-phase fault on one circuit of the EVH 500 kV transmission line between Kalayaan and Naga suggests that stability will be assured by installation of the power system stabilizer at Manito in addition to Calaca Coal, Tiwi and Mak-Ban.

Such power system stabilizer will not be required, for Tongonan as it will be operated almost independently.

Fig. 7-7 Peak Power Flow In 1993




Fig. 7-8 Short Circuit Current In 1993 (A)








Fig. 7-9 Stability In 1993 (HVDC)



- 1. 3 Manilo
- 2. 4 Tiwi
- 3. 5 MakBan



LUZON POWER TRANSM. PROJ. CASE 900.5 Pole 1




PHILIPPIN 1993 3LG AT NAGA  
 BASE GENERATOR P11 PRPP



- 1= TONKUNAN
- 2= MANITO
- 3= TIWI
- 4= CALADAOAL
- 5= MAK-BAN
- 6= SANDER
- 7= PRPP
- 8= MASIRAY
- 9= SAN-ROQUE
- A= NAGA





### 7.3 Summary and Conclusion

- (1) The 400 MW Transmission by the Leyte HVDC system at the first stage toward 1986 is entirely feasible without any difficulty under the system constitution as proposed by NAPOCOR Plan. The EHV 500 kV-designed transmission line of San Jose - Kalayaan - Naga linkage can serve well even at operating voltage of 230 kV.
- (2) At the time of 600 MW transmission in 1991 at the 2nd stage, total transmission power from the southern part of Luzon to Kalayaan and San Jose will reach about 1400 MW on the generating side, including 660 MW at Tiwi and 220 MW at Manito together with 660 MW from the Leyte geothermal power plants. Therefore, in view of total system stability, it is considered necessary that the designed voltage of the transmission line should be stepped up to 500 kV operating voltage by 1991.
- (3) To improve stability of Tiwi, Manito and other power generating plants, it is advisable that by 1986 the power system stabilizer should be provided for each generating unit at Tiwi, Manito, Mak-Ban and Calaca Coal. Especially, Tiwi and Manito generating sources, at least, scheduled for initial operation in the near future should require installation of the ultra rapid response AVR with the power system stabilizer.

- (4) It is recommended that main new power plants, in addition to Tiwi, Manito and Mak-Ban, which are scheduled for future commercial operation, should preferably be provided with power system stabilizers. If power system stabilizers can be installed at the beginning of plant construction, their merit is that they can serve effectively for significant improvement of stability, in addition to the fact that such installation cost is nearly negligible as compared with the cost for the main part of generator. However, since Tongonan can be regarded as the independent generation source for the time being, the plant will not require installation of the power system stabilizer.
- (5) Control for the HVDC system at normal and abnormal operation will require full coordination with the Leyte geothermal power source, so that any fluctuation of frequency and voltage in the Leyte-Samar system will be acceptable to the Leyte geothermal power plant. Because of such requirement, study must be made, at the detailed design stage, for full coordination with performance characteristics of AVR, governor and protective device of the Leyte geothermal power plants.
- (6) System design should be considered so as to enable interconnection of both Leyte-Samar system and HVDC system at Tongonan Switch Yard. By this arrangement the running reserve


capacity will be jointly made available by both Luzon grid and Leyte-Samar grid, so that surplus geothermal power in the Leyte-Samar system can be utilized effectively (for transmission to Luzon grid).

- (7) Whether oil-fired power plants existing in Manila and its environs should remain in operation or should be abolished must be decided after extensive study to determine their serviceability as the reserve capacity to be required in case of forced or scheduled outage of large power generating units of nuclear (620 MW) and coal-firing (300 MW) and the Leyte HVDC system and also after full review of power flow and voltage conditions at normal or abnormal operation of the power system. It is considered necessary, however, that those oil-fired power plants should still be operated appropriately, for the 115 kV transmission system in particular, as countermeasures against any possible overload and voltage drop until drastic measures will have been completed for the 115 kV system.
- (8) Short-circuit capacity for the Luzon, Leyte and Samar EHV systems is estimated at 5,000 MVA at maximum by 1993. Short-circuit capacity for 230 kV Naga Converter Station and 138 kV Jaro Converter Station is estimated at 3,600 MVA and 1,900 MVA respectively, which would not cause any problem at all with regard to breaking capacity.



## **CHAPTER 8**

# **CONSTRUCTION COST AND SCHEDULE**



## CHAPTER 8 CONSTRUCTION COST AND SCHEDULE

### 8.1 Construction Cost

#### (1) Basic Conditions

##### i) General

In calculating the construction cost of the Leyte Power Transmission Project, labor charges and prices as of March 1981 were used and considerations were given to the natural and regional conditions of the routes for overhead transmission lines and submarine cables, landing point of the submarine cable, planned cable terminal and electrodes, electrode line route and planned converter station sites.

Out of the construction cost, expenses on items that are available in the Philippines were calculated on Peso basis and the others were calculated in a foreign currency.

##### ii) Calculation range of construction cost

The construction cost were calculated in the following range. Quantity for each construction phase was calculated based on the preliminary design of the project, and in addition to the direct expenses calculated for contracting, indirect expenses necessary to execute this project were calculated in.



Since the project is divided into the first stage and second stage, execution range was determined and the construction cost was calculated for each period.

a) Calculation Range of Construction Cost

|  | <u>1st Stage</u>                                    | <u>2nd Stage</u>                   |
|--|---|------------------------------------|
| - AC 138 KV overhead transmission lines  | 26 km   | 80 km                              |
| - DC ±350 KV overhead transmission lines | 406 km  | -                                  |
| - DC ±350 KV submarine cables            | 23 km   | -                                  |
| - Converter Station                      | Installation of Jaro C/S and Naga C/S               | Expansion of Jaro C/S and Naga C/S |
| - Electrodes                             | Managasnas and Pasacao electrodes                   | -                                  |
| - Electrode lines                        | 60 km   | -                                  |
| - Telecommunications equipment           | Microwave from Tongonan S/Y to Naga C/S, and others | -                                  |

b) Expenses for Electrical Equipment

All converter equipment (converter and telecommunications equipment such as thyristor valves, transformers, filters and switchgears) and transmission line materials (towers, conductors, insulators, submarine cables, electrodes, etc.) shall be manufactured and supplied by foreign countries.

For expenses on these imported items, FOB Japan prices which can be internationally competitive, maritime transportation expenses and insurance fees were calculated into the foreign currency part.

The unloading expenses and inland transportation expenses of these items in the Philippines and expenses on materials and installation that are obtainable in the country were calculated in the domestic currency.

The submarine cables, converter station equipment, electrodes and telecommunications equipment shall be supplied with installation and test. Expenses necessary for the installation and test such as expenses accrued in obtaining services of foreign country manufacturers' engineers, design expenses of special structures (valve halls, control rooms, etc.), and special materials for them, were calculated in the foreign currency part. Expenses on land formation and buildings were calculated into the domestic currency.

c) Temporary Facility and Others

Expenses for temporary buildings needed for construction management of this project and vehicles were calculated in the domestic currency.

d) Engineering and Administrative Expenses

On these expenses, expenses for detailed design (DS) of this project and supervision (SV) by consultants that would be forthcoming were calculated in the foreign currency part. Expenses needed for construction management by NAPOCOR were calculated into the domestic currency. Expenses necessary for detailed surveys of submarine cables and electrode sites required for detailed design (DS) were calculated in the foreign currency part.

e) Training Cost

Expenses required for training of NAPOCOR engineers on the operation and management of HVDC system were calculated in the foreign currency part.

f) Contingency

An amount equivalent to 5% of the foreign currency and 15% of the domestic currency for the DC  $\pm 350$  KV transmission lines (inclusive of submarine cables), AC 138 KV overhead transmission lines, converter stations, electrodes, electrode lines and telecommunications equipment is added as contingency.

g) Interest During the Construction

Interest rates of 3% per annum and 10% per annum are calculated into the foreign currency and Pesos

respectively as the interests of the fund needed for execution of this project.

h) Escalation of Construction Cost

Escalation as outlined in the following was calculated to the foreign and domestic currency to the direct construction expenses of 1981, based on agreement with NAPOCOR in estimating the construction cost of this project:

| <u>Year</u>    | <u>Foreign Currency</u> | <u>Domestic Currency</u> |
|----------------|-------------------------|--------------------------|
| 1981           | 10%                     | 15%                      |
| 1982           | 9%                      | 15%                      |
| 1983           | 8%                      | 15%                      |
| 1984           | 7%                      | 15%                      |
| 1985           | 7%                      | 15%                      |
| 1986<br>onward | the same                | the same                 |

(2) Total Construction Cost and Construction Cost by Year

The total construction cost was calculated based on the construction schedule, implementation plan and estimation conditions of construction cost of the first and second stage. The total construction cost based on 1981 prices is shown below:

(Unit: US\$1,000)

|              | Foreign<br>Currency | Domestic<br>Currency | Total   |
|--------------|---------------------|----------------------|---------|
| First stage  | 185,365             | 67,502               | 252,867 |
| Second stage | 86,923              | 21,795               | 108,718 |
| Total        | 272,288             | 89,297               | 361,585 |

4 years and 3 years are scheduled for the first and second stage of this project, and the total construction cost was distributed (as shown in Tables 8-1 and 8-2) assuming the following payment terms for the foreign currency and domestic currency.

|  | At the time of          |     |         |            |
|--|-------------------------|-----|---------|------------|
|  | Contract                | FOB | Arrival | Completion |
| Foreign Currency   |                         |     |         |            |
| Overhead lines and materials & equipment for electrode lines | 10%                     | 60% | 30%     | -          |
| Submarine cables and electrodes                              | 10%                     | 60% | -       | 30%        |
| Converter and telecommunications equipment                   | 10%                     | 80% | -       | 10%        |
| Domestic Currency  |                         |     |         |            |
| Materials and labor costs                                    | Work accomplished basis |     |         |            |




Table 8-1 Fund Requirement at First Stage

Unit: 1,000 U.S. Dollars


| Item                                | 1982  |      |       | 1983   |        |        | 1984    |        |         | 1985   |        |        | Construction cost |         |         |
|-------------------------------------|-------|------|-------|--------|--------|--------|---------|--------|---------|--------|--------|--------|-------------------|---------|---------|
|                                     | F.C.  | D.C. | Total | F.C.   | D.C.   | Total  | F.C.    | D.C.   | Total   | F.C.   | D.C.   | Total  | F.C.              | D.C.    | Total   |
| A. Converter stations               |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| Naga Station                        |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| DC equipment                        | --    | --   | --    | 3,224  | 0      | 3,224  | 25,786  | 0      | 25,786  | 3,224  | 0      | 3,224  | 32,234            | 0       | 32,234  |
| AC equipment                        | --    | --   | --    | 400    | 0      | 400    | 3,186   | 0      | 3,186   | 400    | 0      | 400    | 3,986             | 0       | 3,986   |
| Civil works & building              | --    | --   | --    | 124    | 1,567  | 1,691  | 862     | 3,119  | 3,981   | 0      | 1,071  | 1,071  | 986               | 5,757   | 6,743   |
| Installation & others               | --    | --   | --    | 29     | 29     | 58     | 1,657   | 1,276  | 2,933   | 1,043  | 471    | 1,514  | 2,729             | 1,776   | 4,505   |
| Jaro Station                        |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| DC equipment                        | --    | --   | --    | 3,162  | 0      | 3,162  | 25,286  | 0      | 25,286  | 3,162  | 0      | 3,162  | 31,610            | 0       | 31,610  |
| AC equipment                        | --    | --   | --    | 214    | 0      | 214    | 1,714   | 0      | 1,714   | 214    | 0      | 214    | 2,142             | 0       | 2,142   |
| Civil works & building              | --    | --   | --    | 133    | 1,790  | 1,923  | 862     | 3,214  | 4,076   | 0      | 1,271  | 1,271  | 995               | 6,275   | 7,270   |
| Installation & others               | --    | --   | --    | 29     | 29     | 58     | 1,676   | 1,314  | 2,990   | 1,076  | 495    | 1,571  | 2,781             | 1,838   | 4,619   |
| Sub-total                           |       |      |       | 7,315  | 3,415  | 10,730 | 61,029  | 8,923  | 69,952  | 9,119  | 3,308  | 12,427 | 77,463            | 15,646  | 93,109  |
| B. Transmission lines               |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| DC line                             |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| DC 350 kV overhead line             |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| Materials                           | --    | --   | --    | 8,207  | 0      | 8,207  | 29,102  | 0      | 29,102  | 3,954  | 0      | 3,954  | 41,263            | 0       | 41,263  |
| Installation                        | --    | --   | --    | 432    | 3,467  | 3,899  | 1,722   | 18,881 | 20,603  | 256    | 5,190  | 5,446  | 2,410             | 27,538  | 29,948  |
| DC 350 kV submarine cable           |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| Materials                           | --    | --   | --    | 2,800  | 0      | 2,800  | 16,803  |        | 16,803  | 8,487  | 0      | 8,487  | 28,090            | 0       | 28,090  |
| Installation                        | --    | --   | --    | 148    | 0      | 148    | 883     | 381    | 1,264   | 442    | 143    | 585    | 1,473             | 524     | 1,997   |
| AC 138 kV line                      |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| Materials                           | --    | --   | --    | 390    | 0      | 390    | 3,492   | 0      | 3,492   | 0      | 0      | 0      | 3,882             | 0       | 3,882   |
| Installation                        | --    | --   | --    | 20     | 0      | 20     | 184     | 1,000  | 1,184   | 0      | 1,005  | 1,005  | 204               | 2,005   | 2,209   |
| Electrode & electrode lines         | --    | --   | --    | 286    | 0      | 286    | 1,210   | 999    | 2,209   | 348    | 538    | 886    | 1,884             | 1,537   | 3,381   |
| Sub-total                           |       |      |       | 12,283 | 3,467  | 15,750 | 53,396  | 21,261 | 74,657  | 13,487 | 6,876  | 20,363 | 79,166            | 31,604  | 110,770 |
| C. Telecommunication facility       | --    | --   | --    | 606    | 73     | 679    | 1,843   | 66     | 1,909   | 3,013  | 590    | 3,603  | 5,462             | 729     | 6,191   |
| D. Temporary facility & others      |       |      |       |        | 271    | 271    |         | 271    | 271     |        | 267    | 267    |                   | 809     | 809     |
| Direct cost (A+B+C+D)               |       |      |       | 20,204 | 7,226  | 27,430 | 116,268 | 30,521 | 146,789 | 25,619 | 11,041 | 36,660 | 162,091           | 48,788  | 210,879 |
| E. Contingency                      |       |      |       | 1,010  | 1,084  | 2,094  | 5,813   | 4,578  | 10,391  | 1,281  | 1,656  | 2,937  | 8,104             | 7,318   | 15,422  |
| F. Engineering & adm. costs         | 2,152 | 100  | 2,252 | 1,400  | 952    | 2,352  | 1,780   | 952    | 2,732   | 1,752  | 952    | 2,704  | 7,084             | 2,956   | 10,040  |
| G. NPC's engineer educational cost  | --    | --   | --    | --     | --     | --     | 78      | 0      | 78      | 78     | 0      | 78     | 156               | 0       | 156     |
| Sub-total                           | 2,152 | 100  | 2,252 | 2,410  | 2,036  | 4,446  | 7,671   | 5,530  | 13,201  | 3,111  | 2,608  | 5,719  | 15,344            | 10,274  | 25,618  |
| Total cost (A through G)            | 2,152 | 100  | 2,252 | 22,614 | 9,262  | 31,876 | 123,939 | 36,051 | 159,990 | 28,730 | 13,649 | 42,379 | 177,435           | 59,062  | 236,497 |
| H. Interest during the construction | 32    | 5    | 37    | 404    | 473    | 877    | 2,602   | 2,739  | 5,341   | 4,892  | 5,223  | 10,115 | 7,930             | 8,440   | 16,370  |
| Indirect cost (E+F+G+H)             | 2,184 | 105  | 2,289 | 2,814  | 2,509  | 5,323  | 10,273  | 8,269  | 18,542  | 8,003  | 7,831  | 15,834 | 23,274            | 18,714  | 41,988  |
| I. Total construction cost          | 2,184 | 105  | 2,289 | 23,018 | 9,735  | 32,753 | 126,541 | 38,790 | 165,331 | 33,622 | 18,872 | 52,494 | 185,365           | 67,502  | 252,867 |
| in 1981 price                       |       |      |       |        |        |        |         |        |         |        |        |        |                   |         |         |
| J. Escalation                       | 269   | 21   | 290   | 5,041  | 3,651  | 8,692  | 39,101  | 22,537 | 61,638  | 13,482 | 15,456 | 28,938 | 57,893            | 41,665  | 99,558  |
| K. Total cost required (I+J)        | 2,453 | 126  | 2,579 | 28,059 | 13,386 | 41,445 | 165,642 | 61,327 | 226,969 | 47,104 | 34,328 | 81,432 | 243,258           | 109,167 | 352,425 |

Table 8-2 Fund Requirement at Second Stage

Unit: 1,000 U.S. Dollars

| Item   | 1988   |       |        | 1989    |        |         | 1990   |        |        | Construction cost |        |         | Total (1st & 2nd) |         |         |
|--|--------|-------|--------|---------|--------|---------|--------|--------|--------|-------------------|--------|---------|-------------------|---------|---------|
|  | F. C.  | D. C. | Total  | F. C.   | D. C.  | Total   | F. C.  | D. C.  | Total  | F. C.             | D. C.  | Total   | F. C.             | D. C.   | Total   |
| <b>A. Converter stations</b>                     |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| Naga Station                                     |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| DC equipment                                     | 2,519  | 0     | 2,519  | 20,176  | 0      | 20,176  | 2,519  | 0      | 2,519  | 25,214            | 0      | 25,214  | 57,448            | 0       | 57,448  |
| AC equipment                                     | 424    | 0     | 424    | 3,419   | 0      | 3,419   | 424    | 0      | 424    | 4,267             | 0      | 4,267   | 8,253             | 0       | 8,253   |
| Civil works & building                           | 19     | 76    | 95     | 1,048   | 2,428  | 3,476   | 0      | 214    | 214    | 1,067             | 2,718  | 3,785   | 2,053             | 8,475   | 10,528  |
| Installation & others                            | 14     | 9     | 23     | 1,376   | 1,086  | 2,462   | 852    | 367    | 1,219  | 2,242             | 1,462  | 3,704   | 4,971             | 3,238   | 8,209   |
| Jaro Station                                     |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| DC equipment                                     | 2,495  | 0     | 2,495  | 19,967  | 0      | 19,967  | 2,495  | 0      | 2,495  | 24,957            | 0      | 24,957  | 56,567            | 0       | 56,567  |
| AC equipment                                     | 124    | 0     | 124    | 976     | 0      | 976     | 124    | 0      | 124    | 1,224             | 0      | 1,224   | 3,366             | 0       | 3,366   |
| Civil works & building                           | 19     | 76    | 95     | 1,048   | 2,352  | 3,400   | 0      | 214    | 214    | 1,067             | 2,642  | 3,709   | 2,062             | 8,917   | 10,979  |
| Installation & others                            | 14     | 9     | 23     | 1,352   | 1,105  | 2,457   | 857    | 367    | 1,224  | 2,223             | 1,481  | 3,704   | 5,004             | 3,319   | 8,323   |
| Sub-total  | 5,628  | 170   | 5,798  | 49,362  | 6,971  | 56,333  | 7,271  | 1,162  | 8,433  | 62,261            | 8,303  | 70,564  | 139,724           | 23,949  | 163,673 |
| <b>B. Transmission lines</b>                     |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| DC line  |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| DC 350 kV overhead line                          |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| Materials  | --     | --    | --     | --      | --     | --      | --     | --     | --     | --                | --     | --      | 41,263            | 0       | 41,263  |
| Installation                                     | --     | --    | --     | --      | --     | --      | --     | --     | --     | --                | --     | --      | 2,410             | 27,538  | 29,948  |
| DC 350 kV submarine cable                        |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| Materials  | --     | --    | --     | --      | --     | --      | --     | --     | --     | --                | --     | --      | 28,090            | 0       | 28,090  |
| Installation                                     | --     | --    | --     | --      | --     | --      | --     | --     | --     | --                | --     | --      | 1,473             | 524     | 1,997   |
| AC 138 kV line                                   |        |       |        |         |        |         |        |        |        |                   |        |         |                   |         |         |
| Materials  | 1,371  | --    | 1,371  | 8,234   | 0      | 8,234   | 4,113  | 0      | 4,113  | 13,718            | 0      | 13,718  | 17,600            | 0       | 17,600  |
| Installation                                     | 72     | --    | 72     | 433     | 2,834  | 3,267   | 216    | 4,254  | 4,470  | 721               | 7,088  | 7,809   | 925               | 9,093   | 10,018  |
| Electrode & electorde lines                      | --     | --    | --     | --      | --     | --      | --     | --     | --     | --                | --     | --      | 1,844             | 1,537   | 3,381   |
| Sub-total  | 1,443  | 0     | 1,443  | 8,667   | 2,834  | 11,501  | 4,329  | 4,254  | 8,583  | 14,439            | 7,088  | 21,527  | 93,605            | 38,692  | 132,297 |
| <b>C. Telecommunication facility</b>             | --     | --    | --     | --      | --     | --      | --     | --     | --     | --                | --     | --      | 5,462             | 792     | 6,191   |
| <b>D. Temporary facility &amp; others</b>        | --     | 71    | 71     | --      | 71     | 71      | --     | 67     | 67     | 0                 | 209    | 209     | 0                 | 1,018   | 1,018   |
| Direct cost (A+B+C+D)                            | 7,071  | 241   | 7,312  | 58,029  | 9,876  | 67,905  | 11,600 | 5,483  | 17,083 | 76,700            | 15,600 | 92,300  | 238,791           | 64,388  | 303,179 |
| <b>E. Contingency</b>                            | 354    | 36    | 390    | 2,901   | 1,482  | 4,383   | 580    | 822    | 1,402  | 3,835             | 2,340  | 6,175   | 11,939            | 9,658   | 21,597  |
| <b>F. Engineering &amp; adm. costs</b>           | 961    | 576   | 1,537  | 890     | 476    | 1,366   | 876    | 476    | 1,352  | 2,727             | 1,528  | 4,255   | 9,811             | 4,484   | 14,295  |
| <b>G. NPC's engineer educational cost</b>        | --     | --    | --     | 26      | 0      | 26      | 26     | 0      | 26     | 52                | 0      | 52      | 208               | 0       | 208     |
| Sub-total  | 1,315  | 612   | 1,927  | 3,817   | 1,958  | 5,775   | 1,482  | 1,298  | 2,780  | 6,614             | 3,868  | 10,482  | 21,958            | 14,142  | 36,100  |
| Total cost (A through G)                         | 8,386  | 853   | 9,239  | 61,846  | 11,834 | 73,680  | 13,082 | 6,781  | 19,863 | 83,314            | 19,468 | 102,782 | 260,749           | 78,530  | 339,279 |
| <b>H. Interest during the construction</b>       | 126    | 43    | 169    | 1,180   | 677    | 1,857   | 2,303  | 1,607  | 3,910  | 3,609             | 2,327  | 5,936   | 11,539            | 10,767  | 22,306  |
| Indirect cost (E+F+G+H)                          | 1,441  | 655   | 2,096  | 4,997   | 2,635  | 7,632   | 3,785  | 2,905  | 6,690  | 10,223            | 6,195  | 16,418  | 33,497            | 24,909  | 58,406  |
| <b>I. Total construction cost in 1981 prices</b> | 8,512  | 896   | 9,408  | 63,026  | 12,511 | 75,537  | 15,385 | 8,388  | 23,773 | 86,923            | 21,795 | 108,718 | 272,288           | 89,297  | 361,585 |
| <b>J. Escalation</b>                             | 6,103  | 1,582 | 7,685  | 52,753  | 27,286 | 80,039  | 14,847 | 22,295 | 37,142 | 73,703            | 51,163 | 124,866 | 131,596           | 92,828  | 224,424 |
| <b>K. Total cost required (I+J)</b>              | 14,615 | 2,478 | 17,093 | 115,779 | 39,797 | 155,576 | 30,232 | 30,683 | 60,915 | 160,626           | 72,958 | 233,584 | 403,884           | 182,125 | 586,009 |





The indirect cost, which mainly consist of engineering fees, administrative expenses, educational expenses, contingency and interest during the construction, are US\$41,988,000 for the first stage and US\$16,418,000 for the second stage, a total of US\$58,406,000, which is 19.3% of the total direct construction expenses.

Assuming that the construction progresses smoothly and the construction for the first period is completed by the end of 1985 and that for the second stage by the end of 1990, increases of 39.4% and 114.9% to the first and second stages respectively by escalation are estimated over the construction cost calculated based on 1981 prices. In other words, the total construction cost in anticipation of the escalation is US\$325,425,000 for the first stage and US\$233,584,000 for the second stage. These amounts can be broken down to foreign currency and domestic currency as US\$243,258,000 and US\$109,167,000 for the first stage and US\$160,626,000 and US\$72,958,000 for the second stage, respectively.

## 8.2 Construction Schedule

Figs. 8-1 and 8-2 show the first and second stage construction schedules, respectively.

For the purposes of lowering dependency on petroleum and utilization of natural resources, early realization of the project is most desirable, and along with the Tongonan geothermal power generation project, the completion of this project is projected to 1985 for the first stage and 1990 for the second stage.

The construction period, starting from detailed designing and preparation of specifications up to completion of the construction, is determined as 45 months for the first stage and 36 months for the second stage. About 33 months are estimated for construction of the converter stations starting from contracting up to completion of the construction, and during the 33 months designing, manufacturing, transportation, installation and testing on the transmission lines, electrodes, electrode lines and telecommunications equipment must be completed.

The following basic points were taken into consideration when determining the construction schedule.

1. The first part of the document discusses the importance of maintaining accurate records of all transactions and activities. It emphasizes that proper record-keeping is essential for transparency and accountability, particularly in the context of public administration and financial management. The text highlights that records should be maintained in a clear, organized, and accessible manner, ensuring that all relevant information is captured and preserved for future reference.

2. The second part of the document focuses on the role of technology in enhancing record-keeping processes. It notes that the adoption of digital tools and systems can significantly improve the efficiency and accuracy of data collection and storage. The text suggests that organizations should invest in robust IT infrastructure and training to ensure that their records are secure, up-to-date, and easily retrievable. Additionally, it mentions that digital records can facilitate better communication and collaboration among different departments and stakeholders.

3. The third part of the document addresses the challenges associated with record-keeping, such as data loss, corruption, and unauthorized access. It provides several strategies to mitigate these risks, including regular backups, data encryption, and strict access controls. The text also emphasizes the importance of having a clear policy in place regarding the retention and disposal of records, ensuring that only necessary information is kept for the required duration.

4. The fourth part of the document discusses the legal and regulatory requirements related to record-keeping. It notes that various laws and regulations govern the collection, storage, and sharing of records, and organizations must ensure full compliance with these requirements. The text highlights that failure to adhere to these regulations can result in significant penalties and reputational damage. Therefore, it is crucial for organizations to stay updated on the latest legal developments and consult with legal counsel as needed.

5. The fifth part of the document concludes by reiterating the importance of record-keeping as a fundamental aspect of good governance and financial management. It encourages organizations to adopt a proactive approach to record-keeping, ensuring that all activities are properly documented and reported. The text also suggests that regular audits and reviews of record-keeping practices can help identify areas for improvement and ensure ongoing compliance with relevant standards and regulations.

Fig. 8-1 Schedule Leyte Power Transmission Project (First Stage)





Fig. 8-2. Schedule Layte Power Transmission Project (Second Stage)

| Description                 | Year | 1988  |   |   |   |   |   |   |   |   |    |    |    | 1989  |   |   |   |   |   |   |   |   |    |    |    | 1990 |   |   |   |   |   |   |   |   |    |    |    | Remarks |
|-----------------------------|------|-------|---|---|---|---|---|---|---|---|----|----|----|-------|---|---|---|---|---|---|---|---|----|----|----|------|---|---|---|---|---|---|---|---|----|----|----|---------|
|                             |      | 1     | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 1     | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 1    | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |         |
| Detailed Design             |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Technical Specifications    |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Transmission Lines          |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Converter Station           |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Construction                |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Transmission Lines          |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Bidding & Award of Contract |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Designing & Manufacturing   |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Delivery                    |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Installation                |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Converter Station           |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Civil Works                 |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Bidding & Award of Contract |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Designing                   |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Foundation, etc.            |      |       |   |   |   |   |   |   |   |   |    |    |    | ===== |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Building Works              |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Bidding & Award of Contract |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Designing                   |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Valve hall, etc.            |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Electrical Equipment        |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Bidding & Award of Contract |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Designing                   |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Manufacturing               |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Delivery                    |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Installation Testing        |      | ===== |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Test and Trial Operation    |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |
| Commissioning               |      |       |   |   |   |   |   |   |   |   |    |    |    |       |   |   |   |   |   |   |   |   |    |    |    |      |   |   |   |   |   |   |   |   |    |    |    |         |



(1) Overhead Transmission Line Installation

During the first stage, overhead transmission lines of AC 138 KV (26 km) and DC  $\pm 350$  kV (406 km) shall be installed simultaneously.

i) Amount of Work and Construction Schedule

The amount and sections of construction are as shown below.

| <u>Construction Section</u>  |            | <u>Amount</u> |
|--|------------|---------------|
| AC 138 KV overhead transmission lines  | 1 section  | 26 km         |
| DC $\pm 350$ KV overhead transmission lines (within the Leyte and Samar islands) | 2 sections | 218 km        |
| DC $\pm 350$ KV overhead transmission lines (within the Luzon island)            | 2 sections | 186 km        |
| DF $\pm 350$ KV, crossing the San Juanico strait                                 | 1 section  | 1.7 km        |

Based on progress of installing about 6 km per month upon study of the construction schedule, it takes about 20 months to complete installing the DC  $\pm 350$  KV overhead transmission lines including final test within the Leyte and Samar islands.

ii) Transportation Period of Equipment and Materials

Materials for towers, conductors and insulators shall be



imported and 2 months are estimated for maritime and overland transportation.

iii) Manufacturing of Steel Tower

About 3 months are needed before the manufacturer starts making the towers after receiving an order. During the 3 months the towers are designed, materials are arranged, a model is built and tests on them are conducted.

The estimated amount of iron for the towers is about 16,000 tons, and the manufacturing period in the factory is about 16 months based on production capacity of average 1,000 tons a month.

(2) Submarine Cable Installation Schedule

As described in the preliminary design clause of Chapter 6, installation of the DC  $\pm 350$  KV submarine cables is a special work. The final submarine cable route and installation schedule are determined based on detailed geological survey. However, detailed survey on the marine phenomena and sea bottom conditions at the scheduled route of the submarine cables should be conducted beforehand so that basic points of installation route, cable terminal positions and cable types should be predetermined.

1) Field Survey and Final Design

the contractor for the submarine cable shall receive the order based on the NAPOCOR construction specifications,

conduct supplementary surveys on the designated cable route and cable terminal location, complete final designs of the installation work and receive approval on the cable test piece from NAPOCOR. The period required for these works is set as 10 months.

The preferable season of the submarine geological survey is from April to June due to the meteorological conditions in the region.

ii) Cable Manufacturing Process

The cables shall be manufactured in a unit length of 1,000 m and connected for the number required for the route lengths.

Since 7 days are needed to make one connection, if two of single core cables are to be installed, the time required in the plant for cable connection is about 7 months.

iii) Cable Installation

Prior to start installing the cable, about 5 months are needed for preparation of the cable landing and cable terminal sites.

November is selected for the installation as the sea phenomena is comparative favorable for the work, and one month is planned for the installation in consideration of trial cruising.

4 months are planned for protection work of the cables, connection to the cable terminal and testing. This makes a total of 10 months for the cable installation work.

(3) Installation of Electrodes and Electrode Lines

As described in the preliminary design clause of Chapter 6, installation of electrodes is a special work, and the final electrode type (on land or in the sea) and electrode site are determined based on detailed surveys of the planned electrode installation site.

However, the detailed surveys of the planned electrode installation site should be conducted beforehand and determination of the electrode type and electrode installation site is made prior to starting the construction work for this project.

The electrode and electrode line works shall be conducted in series at each side of Jaro C/S and Naga C/S and the installation timing is matched to that of the transmission lines.

(4) Converter Station Construction Schedule

Construction related to converter stations, among construction of DC series facilities, can be divided into two categories; one is related to civil engineering work and the other is electrical. The electrical work, the main

part of which is installation of electrical equipment like converter, requires the longest time and how soon the equipment can be installed is a decisive factor to the total construction time.

Since it is possible to completely prepare the building and outdoor facilities to contain the equipment which is manufactured in overseas before they are delivered to the site, construction schedule for the entire equipment can be determined by the time lengths for designing, manufacturing, transportation, installation and tests of HVDC equipment.

i) Designing

The design work shall be started immediately after concluding the contracts. The time length required for designing greatly varies by the type of equipment.

Generally, it can be said that 4 to 6 months are needed for thyristor valves and converter transformer and 10 to 12 months are needed for control and protection equipment.

ii) Manufacturing

Manufacturing requires the longest time, i.e., 12 to 15 months for thyristor valves, 8 to 10 months for converter transformers and DC reactors, and 8 to 12 months for switchboard and switchgears.

All of them must be manufactured under well prepared circumstance and severe quality control setup.

### iii) Transportation and Installation

Transportation arrangement must be made coping to the installation schedule of each equipment so that there would be no waste of time and work at the field.

Especially, on the heavy items to the Jaro C/S, the transportation must be carried out systematically based on prior surveys.

Since many devices containing semiconductors are used, like thyristor valves, the installation must be supervised very carefully so as not to degrade the quality of these devices.

3 to 5 months are planned for the installation process.

### iv) Field Tests

Various testings shall be conducted after installing the equipment. The testing will be conducted on individual device first, and when all tests in the converter stations end, the whole DC transmission system shall be tested. The system performance is then adjusted, set to the normal operation state, and the performance is checked.

Accordingly, to obtain electricity for these testings is essential to realize smooth execution of all processes.

6 months are planned for testing of all equipment assuming that all construction and installation are completed as planned.

(5) Construction of Telecommunications Equipment

Designing, manufacturing, installation and testing of telecommunications equipment shall be carried out matching to construction of the converter stations, and the telecommunications equipment shall be completed by 1985 in the timing of the project completion.

However, in order to realize this, the formal procedures related to approval of microwave system as required by the Philippines authority must be managed by NAPOCOR under the responsibility of NAPOCOR and the approval will have been obtained in time of the construction schedule.

Further surveys are needed to check the location of the repeating stations, and to confirm existence of no obstacles between repeating stations and possibility of installing the repeating station in advance.

(6) Second Stage Construction Schedule

The main work in the second stage, which is tentatively scheduled for 1990 completion, is additional installation of HVDC main circuit and the final equipment of  $\pm 350$  KV, 900 MW shall be installed.

Additional installation of AC 138 KV switching equipment, AC filters, Var compensator and AC 138 KV transmission lines are needed and scheduled as the necessary equipment resulting from additional installation of the above mentioned HVDC circuit.

These installation schedules are planned in the same way as those for the first stage.