

#### 4.3.8 Improvement of the existing fence

The existing fence which is located along the southern boundary of the Sindhuli Agriculture Farm will be required the improvement works, since the existing fence has been superannuated and has been allowed invasion of strangers. Improved fence will be provided the wetstone masonry footing and wall with barbed wire fence. Total length of improved fence is 209.5 m.

Principal features of the improved fence are as follows:

Length : 209.5 m

##### Wall

Foundation width : 0.6 m

Wall height : 1.0 m

##### Barbed wire fence

Height : 1.258 m

Interval of poles : 3.0 m

Table 4.1 Calculation Results of Peak Water Requirements


Description	Grapes	Junar Nursery
Crop water requirement, CWR (mm/day)	4.97	2.60
Field water requirement, FWR (mm/day)	5.84	4.00
Irrigation water requirement, IWR (mm/day)	6.50	5.00
Application interval (days)	5	5
CWR for once interval (mm)	24.85	13.00
FWR for once interval (mm)	29.20	20.00
IWR for once interval (mm)	32.50	25.00

AREA OF HORTICULTURAL FARM

1) First Stage Implementation		4.29 ha	
BLOCK I - 1	0.48 ha		
BLOCK I - 2	0.48 ha		
BLOCK II - 1 - (1)	0.25 ha		
BLOCK II - 1 - (2)	0.21 ha		
BLOCK II - 2	0.45 ha		
BLOCK II - 3	0.37 ha		
BLOCK II - 4	0.46 ha		
BLOCK III - 1 - (1)	0.15 ha		
BLOCK III - 1 - (2)	0.13 ha		
BLOCK III - 2	0.35 ha		
BLOCK III - 3	0.44 ha		
BLOCK III - 4	0.52 ha		
2) Second Stage Implementation			3.46 ha
BLOCK IV - 1	0.52 ha		
BLOCK IV - 2	0.45 ha		
BLOCK IV - 3	0.38 ha		
BLOCK IV - 4 - (1)	0.20 ha		
BLOCK IV - 4 - (2)	0.11 ha		
BLOCK V - 1	0.51 ha		
BLOCK V - 2	0.41 ha		
BLOCK V - 3	0.47 ha		
BLOCK V - 4 - (1)	0.28 ha		
BLOCK V - 4 - (2)	0.13 ha		

LEGEND

- Hydrant on Branch Irrigation Pipeline
- Branch or Bend of Pipeline
- Main Irrigation Pipeline
- Branch Irrigation Pipeline
- Farm Ditch
- Drainage Culvert
- Main Drain
- Collector Drain
- Main Farm Road
- Secondary Farm Road
- Road
- House
- Orchard (Lemon, Litchi & Mango)
- Banana Tree
- Dry Field
- Grass Land
- Bush
- Depression
- Ridge
- Border
- Ditch
- Stream
- Fence
- Transmission or Distribution Line



LIST OF IRRIGATION PIPELINES

1) First Stage Implementation	
- Main Irrigation Pipeline (MIP)	174.50m
- Branch Irrigation Pipeline (BIP)	531.33m
BIP - 1	227.50m
BIP - 2	150.00m
BIP - 3	153.83m
2) Second Stage Implementation	
- Main Irrigation Pipeline (MIP)	130.18m
- Branch Irrigation Pipeline (BIP)	313.49m
BIP - 4	155.66m
BIP - 5	157.83m

LIST OF DRAINAGE CANALS

1) First Stage Implementation	
- Main Drain (MD)	520.03m
- Collector Drain (CD)	755.02m
CD - 1	221.00m
CD - 4	213.00m
CD - 5	181.02m
CD - 7	140.00m
- Field Ditch	849.00m
2) Second Stage Implementation	
- Collector Drain (CD)	356.00m
CD - 2	119.00m
CD - 3	124.00m
CD - 6	113.00m
- Field Ditch	528.00m





Fig 4.1 (1/3) Layout Map of Nepalgunj Sub-center

Note : L1: The construction of Main Drain and improvement of Belhantia stream and existing farm roads shall be made under the First Stage Implementation.

L2: Sub-surface drains shall be provided in only the block where the vine trellis is provided.

L3: Elevations and distances in this plate are expressed in meter.

HIS MAJESTY'S GOVERNMENT OF NEPAL HORTICULTURAL DEVELOPMENT PROJECT NEPALGUNJ SUB-CENTER			
TITLE: GENERAL LAYOUT (1/3) HORTICULTURAL FARM			
DATE	MAR. 1986	D.W.G. NO.	N 100 - 02
JAPAN INTERNATIONAL COOPERATION AGENCY			



River Improvement Portion	120.00 m
Short Cut Portion	143.92 m
<b>Total</b>	<b>263.92 m</b>

**LEGEND**


- Road
- River / Stream
- Grass land
- Depression
- Ditch
- Fence
- Ridge
- 0.5m contour line
- 1.0m contour line
- BL** River base elevation

Note : All the elevation and distance in the drawing is expressed in meter.



Fig 4.1 (2/3) Layout Map of Nepalgunj Sub-center

HIS MAJESTY'S GOVERNMENT OF NEPAL HORTICULTURAL DEVELOPMENT PROJECT NEPALGUNJ SUB-CENTER			
TITLE:  GENERAL LAYOUT (2/3) BELHANIYA STREAM			
DATE	MAR. 1986	D.W.G. NO.	N100 - 03
JAPAN INTERNATIONAL COOPERATION AGENCY			



TYPICAL CROSS SECTION OF APPROACH ROAD

LEGEND

- Approach Road
- Road
- House
- Border
- Fence
- Transmission or Distribution Line
- Depression
- Ditch
- Stream or Creek
- Bridge
- Grass Land

Note : All the elevation and distance in the drawing is expressed in meter





Fig 4.1 (3/3) Layout Map of Nepalgunj Sub-center.

HIS MAJESTY'S GOVERNMENT OF NEPAL HORTICULTURAL DEVELOPMENT PROJECT NEPALGUNJ SUB-CENTER			
TITLE :			
GENERAL LAYOUT ( 3/3 ) APPROACH ROAD			
DATE	MAR. 1986	D.W.G. NO.	N 100 - 04
JAPAN INTERNATIONAL COOPERATION AGENCY			






**Note**

Irrigation interval is 5-days at peak period.  
 The farm is divided into five blocks, and  
 one block is irrigated in a day


**LEGEND**

- (P) ; Pump Station
- ; Pipeline.
- ; Hydrant
- ▒ ; One Plot Area (0.48 ha)


Fig. 4.2 Irrigation Diagram for Grapes at The Nepalgunj Sub - center




**LEGEND**



Main Drain (MD)



Collector Drain (CD)



Direct Flow-in

a : Catchment Area (ha) , b : Design Discharge ( $m^3/sec$ )

Fig. 4.3 Drainage Diagram for Nepalgunj Sub-center





### LIST OF IRRIGATION PIPELINE

- Discharge Pipeline	185.72 m
- Main Irrigation Pipeline (MIP)	136.85 m
- Branch Irrigation Pipeline (BIP)	359.63 m
- BIP - 1	59.57 m
- BIP - 2	87.71 m
- BIP - 3	82.91 m
- BIP - 4	129.44 m

### LIST OF DRAINAGE CANAL

- Main Drain (MD)	148.49 m	- MD-2-2	151.85 m
- MD - 1	121.37 m	Catch Drain	126.64 m
- MD - 2	27.12 m	- CD - 1	32.27 m
- Minor Drain (MD)	420.53 m	- CD - 1-1	29.72 m
- MD - 1-1	82.33 m	- CD - 1-2	64.65 m
- MD - 1-2	111.97 m		
- MD - 2-1	74.38 m		

### LEGEND

	Drop
	Branch or Bend on Pipeline
	Hydrant
	Culvert
	Irrigation Pipeline
	Drainage Canal
	Farm Road and Approach Road
	Road
	Footpath
	Office & Quarters
	Irrigation Canal
	Ditch
	Border
	Fence
	Orchard (Mango, Litchi etc.)
	Pineapple
	Nursery of Junar etc.
	Dry Field
	Paddy Field
	Bush




Fig 4.4 Layout Map of Sindhuli Sub-center

HIS MAJESTY'S GOVERNMENT OF NEPAL HORTICULTURAL DEVELOPMENT PROJECT SINDHULI SUB-CENTER			
TITLE  GENERAL LAYOUT			
DATE	MAR. 1986	D.W.G. NO.	S 100 - 02
JAPAN INTERNATIONAL COOPERATION AGENCY			






Fig. 4.5 Irrigation Diagram for Junar Nursery at The Sindhuji Sub-center.




Fig. 4.6 Drainage Diagram for Sindhuli Sub - center

V. CONSTRUCTION PLAN



## V. CONSTRUCTION PLAN

### 5.1 General

The construction plan is made based on the detail design and also under the following conditions:

- The whole construction works will be performed on the contract basis,
- The construction works will be carried out by local contractor,
- The construction works will be done in one dry season,
- Pump equipments with accessories, P.V.C. pipes with related valves for pipelines, sprinkler sets and some materials of vine trellis, etc. will be supplied from Japan by Japanese Government, and
- Timber pole for vine trellis, cement and concrete pipes, which are procured in local, are supplied by Japanese Government.

### 5.2 Principal Features for Construction Works

#### 5.2.1 Nepalgunj Sub-center

The principal features for construction works of the Nepalgunj Sub-center are tabulated below:

<u>Works</u>	<u>Q'ty</u>	<u>Remarks</u>
1. Pumping facilities		
- Submergible pump	1 unit	Cleaning of the existing deep well and installation of submergible pump  Submergible pump: ø80, 0.65 m <sup>3</sup> /min. H = 19 m, 3.7 kW
- Delivery pump	1 unit	Installation of a delivery pump  Delivery pump: ø80 x 65, 1.13 m <sup>3</sup> /min. H = 36 m, 15 kW
- Pump house	1 no.	Space: 17.5 m <sup>2</sup>



Works	Q'ty	Remarks
2. Farm pond	1 no.	Effective stage capacity: 625 m <sup>3</sup> Embankment volume: 1,500 m <sup>3</sup> Excavation volume: 620 m <sup>3</sup>
3. Irrigation facilities		
- Main irrigation pipeline	170 m	Ø150 mm
- Branch irrigation pipeline	530 m	Ø150, 100, 75 mm
4. Drainage facilities		
- River improvement		Excavation: 800 m <sup>3</sup>
- Main drain	520 m	Embankment: 4,250 m <sup>3</sup> Excavation: 650 m <sup>3</sup>
- Collector drain and farm ditch	1,600 m	Excavation: 1,800 m <sup>3</sup>
- Sub-surface drain	2,700 m	Excavation: 2,600 m <sup>3</sup>
5. Farm road	2,900 m	Gravel : 820 m <sup>3</sup> Embankment: 1,900 m <sup>3</sup> Excavation: 700 m <sup>3</sup>
6. Land grading	4.3 ha	
7. Vine trellis	7 blocks	2.7 ha
8. Farm house	1 no.	Space: 48 m <sup>2</sup>

Procurement list of the equipment is shown in Table 5.1.

#### 5.2.2 Sindhuli Sub-center

The principal features for construction works of the Sindhuli Sub-center are tabulated below:

Works	Q'ty	Remarks
1. Pumping facilities		
- Delivery pump	1 unit	Installation of delivery pump Delivery pump: Ø65x50, 0.44 m <sup>3</sup> /min. H = 36 m, 9 P.S.
- Pump house	1 no.	Space: 4 m <sup>2</sup>
- Shallow well	1 no.	Ø1.5 m, H = 8 m
- Discharge pipeline	180 m	Ø80 mm

Works	Q'ty	Remarks
2. Farm pond	1 no.	Effective storage capacity: 50 m <sup>3</sup>
3. Irrigation facilities		
- Main irrigation pipeline	135 m	Ø100
- Branch irrigation pipeline	350 m	Ø100, 75, 50
4. Drainage facilities		
- Collector drain	800 m	Excavation: 790 m <sup>3</sup>
5. Farm road	980 m	Embankment: 550 m <sup>3</sup> Excavation: 120 m <sup>3</sup>
6. Grafting house	1 no.	Space: 120 m <sup>2</sup>
7. Improvement of fence	210 m	

Procurement list of the equipment is shown in Table 5.1.

### 5.3 Construction Time Schedule

The construction works will be carried out by a contractor selected through a competitive bidding. The construction periods of the Nepalgunj Sub-center and the Sindhuli Sub-center are estimated to be 5.5 months and 5 months, respectively. The proposed construction time schedule is shown in Fig. 5.1.



Table 5.1 Procurement List of the Equipments

Equipment	Q'ty
<u>1. Nepalgunj Sub-center</u>	
(1) Submergible pump motor set with accessories	2 sets
(2) Sluice and check valves for submergible pump motor	L.S.
(3) Delivery pump motor set with accessories	1 set
(4) Sluice and check valves for delivery pump motor	L.S.
(5) Steel pipes with fitting for discharge water from well to pond and from pond to delivery pump	1 set
(6) Generator with accessories	1 set
(7) Control panel and distribution materials	1 set
(8) Chain block	2 nos.
(9) Blow-off valve and steel pipe $\phi$ 100 mm	1 set
(10) Gate valve and steel pipe $\phi$ 100 mm	1 set
(11) Spare parts for the pump equipments	L.S.
(12) PVC pipe $\phi$ 150, 100, 75 mm with fittings	610 m
(13) Steel pipe $\phi$ 50 mm with fittings	67 m
(14) Air valve	1 no.
(15) Hydrants $\phi$ 50 mm	20 nos.
(16) Fitting materials	L.S.
(17) Spare parts for PVC pipes	L.S.
(18) Sprinkler sets with spare parts	2 sets
(19) Trellis materials	L.S.
<u>2. Sindhuli Sub-center</u>	
(1) Intake engine pump set with accessories	1 set
(2) Valves and pressure gauge	1 set
(3) Chain block	1 no.
(4) Steel pipe with fitting, $\phi$ 80 mm	180 m
(5) Blow-off valve and steel pipe $\phi$ 100 mm	1 set
(6) Gate valves and steel pipe, $\phi$ 100 mm	1 set
(7) Spare parts for pump equipments	L.S.
(8) PVC pipe, $\phi$ 100, 75, 50 mm with fittings	490 m
(9) Steel pipe $\phi$ 100, 50 mm with fittings	45 m
(10) Hydrants, $\phi$ 1/2" mm	16 nos.
(11) Air valves	2 nos.
(12) Fitting materials	L.S.
(13) Spare parts for PVC pipes	L.S.



WORK ITEM	1986				1987				REMARKS				
	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb		Mar	Apr		
I. TENDER													
Tender Announce													
Tender Close													
Tender Evaluation													
Award of Tender													
Signing of Contract													
Commencement													
II. CONSTRUCTION													
1. Preparatory Works													
2. Pump Station Facilities													
3. Farm Pond													
4. Irrigation Pipeline													
5. Drainage Works													
6. Road Works													
7. Land Grading													
8. Vine Trellis													
9. Farm House													
III. PROCUREMENT OF EQUIPMENTS AND MATERIALS													
1. Pumping Equipment													
2. Steel Pipes, P.V.C Pipes, Valves and Hydrants w/ Fitting													
3. Trellis Materials Sprinkler Sets													

HIS MAJESTY'S GOVERNMENT OF NEPAL  
 HORTICULTURAL DEVELOPMENT PROJECT  
 NEPALGUNJ SUB-CENTER

TITLE: CONSTRUCTION TIME SCHEDULE

DATE: MAR. 1986 DWG. NO. N700 - 01  
 JAPAN INTERNATIONAL COOPERATION AGENCY

Fig. 5.1 Construction Time Schedule of Nepalgunj Sub-center

WORK ITEM	1986					1987					REMARKS	
	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.		
<b>I. TENDER</b>												
Tender Announce												
Tender Close												
Tender Evaluation												
Award of Tender												
Signing of Contract												
Commencement												
<b>II. CONSTRUCTION</b>												
1. Preparatory works												
2. Pump Station Facilities												
3. Farm Pond												
4. Irrigation Pipeline												
5. Drainage Works												
6. Road Works												
7. Grating House												
8. Fencing Works												
<b>III. PROCUREMENT OF EQUIPMENT AND MATERIALS</b>												
1. Pumps, Equipments												
2. Steel Pipes, P.V.C. Pipes, Valves and Hydrants w/ Fitting												

HIS MAJESTY'S GOVERNMENT OF NEPAL  
 AGRICULTURAL DEVELOPMENT PROJECT  
 SINDHULI SUB-CENTER

TITLE: CONSTRUCTION TIME SCHEDULE

DATE: MAR. 1986    DWG. NO: S 700-01  
 JAPAN INTERNATIONAL COOPERATION AGENCY

Fig. 5.2 Construction Time Schedule of Sindhuli Sub-center









JICA