

AFRICAN DEVELOPMENT BANK
GOVERNMENT OF MAURITIUS

CONTRACT
FOR
CONSTRUCTION
OF
BEAU BASSIN - PORT LOUIS LINK ROAD

CONFIDENTIAL VOLUME

SEPTEMBER 1980

Japan International Cooperation Agency

S D F

80-100

JICA LIBRARY



1063045[7]

AFRICAN DEVELOPMENT BANK
GOVERNMENT OF MAURITIUS

CONTRACT
FOR
CONSTRUCTION
OF
BEAU BASSIN - PORT LOUIS LINK ROAD

CONFIDENTIAL VOLUME

SEPTEMBER 1980

Japan International Cooperation Agency

国際協力事業団

受入 月日 84.5.15	410
登録No. 14544	61.4
	SDF

INDEX

LIST OF TABLES	i
LIST OF ILLUSTRATIONS	vi
REFERENCES	vii
1. INTRODUCTION	1
2. CONSTRUCTION PLANNING	2
3. ESTIMATE OF CONSTRUCTION COST	58
ANNEX TO PRICED B.Q.	

LIST OF TABLES

<u>Table No.</u>		<u>Page</u>
2.2-1	Average number of days per month on which rainfall reached or exceeded the specified value	6
2.2-2	Working days rate for earthwork and bridge substructure work	9
2.2-3	ditto, for bridge superstructure work	10
2.3-1	Roadway excavation and mean haulage distance	13
2.4-1	Summary of construction period of bridge	17
2.4-2	Schedule analysis of bridge, G.R.N.W. B-Le.	18
2.4-3	ditto, G.R.N.W. B-Le.	19
2.4-4	ditto, ST.L.Ri. A-Le.	20
2.4-5	ditto, ST.L.Ri. B-Le.	21
2.4-6	ditto, B-Rp. Br.	22
2.4-7	ditto, Mwyo Jun. G-Rp. Br.	23
2.4-8	ditto, Cor. Int. E-Rp.	24
2.4-9	ditto, Cor. Int. F-Rp.	25
2.4-10	ditto, Pailles Ov. Br.	26
2.4-11	ditto, A-1 Road Ov. Br.	27
2.4-12	ditto, Coromandel Ov. Br.	28
2.4-13	ditto, Cor. Int. H-Rp.	29
2.4-14	ditto, Sta. 22 Ov. Br.	30
2.4-15	ditto, Hin. Temple Ped.	31
2.4-16	ditto, B.B. Ped. Br.	32
2.4-17	ditto, Mwy. Jun. A-Le. 1 Br.	33
2.4-18	ditto, B-Le. 1 Br.	34
2.4-19	ditto, A-Le. 2 Br.	35

<u>Table No.</u>		<u>Page</u>
2.4-20	Schedule analysis of bridge, B-Le. 2 Br.	36
2.4-21	ditto, A-Le, 3 Br.	37
2.4-22	ditto, B-Le. 3 Br.	38
2.4-23	ditto, Mwy. Jun. E-Rp. Br.	39
2.4-24	Excavating and collecting material rate	40
2.4-25	Actual working day analysis for earth-moving section, sta. 0+00 ~ 34 + 80 and Access road	43
2.4-26	ditto, Sta. 34+20 ~ 60+78 and Coromandel I.C.	44
2.4-27	ditto, Sta. 62+82 ~ 76 + 13 and M ₁ M ₂ Road	45
2.4-28	Summary of construction period for box culvert	46
2.4-29	Actual working day analysis for one span of box culvert	47
2.4-30	Schedule analysis of Pavement work, Sta. 0+00 ~ 76 + 13	48
2.4-31	ditto, Phased construction part of Link Road	49
2.4-32	ditto, Coromandel I.C.	50
2.4-33	ditto, Motorway Junction	51
2.4-34	ditto, Phased construction part of Motorway Junction	52
2.4-35	ditto, Access road	53
2.4-36	Proposed work schedule	55
2.4-37	Arrangement schedule of main constructional equipment	57
3.2-1	Hourly wages by labour category in Sugar Millers' Estate	66
3.2-2	Hourly wages by labour category in the Central Government	67
3.2-3	Analysis of labour cost	68

<u>Table No.</u>		<u>Page</u>
3.2-4	Analysis of ratio of fringe benefits for basic wage ..	69
3.2-5	Analysis of income tax ratio for hourly labour cost	70
3.2-6	Cost component of hourly labour cost	71
3.3-1	Hourly cost in market of main construction equipment	75
3.3-2	CIF value of construction equipment in Port Louis in September 1979	78
3.3-3	Classification of Construction equipment by import duties and hourly cost factors	79
3.3-4	Classification of imported materials and equipment by import duties	80
3.3-5	Customs tariff - import duties in September of 1979	82
3.3-6	Classification of construction equipment by import duties and depreciation factors	88
3.3-7	Depreciation period based on application and operating conditions	90
3.3-8	Hourly cost estimate of construction equipment in category 1, Komatsu D355A-3	91
3.3-9	ditto, D155A-1	92
3.3-10	ditto, D85A-18	93
3.3-11	ditto, D75S-3	94
3.3-12	ditto, D65S-1	95
3.3-13	ditto, Asphalt plant set	96
3.3-14	ditto, Portable air compressor	97
3.3-15	ditto, Concrete mixer	98
3.3-16	ditto, Komatsu GD655A-1	99
3.3-17	ditto, Truck mixer	100
3.3-18	ditto, Handy compactor	101

<u>Table No.</u>		<u>Page</u>
3.3-19	Hourly cost estimate of construction equipment in category 4, Portable generator	102
3.3-20	ditto, Electric welding appliance	103
3.3-21	ditto, Dump truck, Komatsu HD200-2	104
3.3-22	ditto, Belt conveyer	105
3.3-23	ditto, Truck 11 t	106
3.3-24	ditto, Land Rover	107
3.3-25	Ratio of taxes for total tax component for hourly cost, Komatsu D355A-3	108
3.3-26	ditto, Concrete mixer	109
3.3-27	ditto, Asphalt plant set	110
3.3-28	ditto, Portable generator	111
3.3-29	ditto, Electric welding appliance	112
3.3-30	ditto, Dump truck	113
3.3-31	ditto, Belt conveyer	114
3.3-32	ditto, Truck 11 t	115
3.3-33	ditto, Rover	116
3.3-34	Summary of hourly cost of construction equipment	117
3.4-1	Investigation of market price for main construc- tion material in September of 1979	124
3.4-2	Classification of imported material by import duties	128
3.4-3	Tariff schedule of fares for goods vehicles	129
3.4-4	Analysis of cost component for construction material in Category 2, bitumen	130
3.4-5	ditto, Diesel oil	131
3.4-6	ditto, Structural shaped steel	132

<u>Table No.</u>		<u>Page</u>
3.4-7	Delivered price of main imported materials for construction cost estimate	133
3.4-8	Cost component of imported material	134
3.4-9	Ratio of foreign and tax cost component for delivered piece (%)	138
3.4-10	Ratio of import duties and corporate tax for total tax component	138
3.4-11	Delivered price of imported material for construc- tion cost estimate	139
3.4-12	Unit price analysis of material, coarse aggregate	143
3.4-13	Delivered price of aggregated and local timber	145
3.4-14	Unit price analysis of material, reinforcement bar	146
3.4-15	Analysis of cost component for constructional material in Category 1, steel sheet bar	147
3.4-16	ditto, PVC pipe	148
3.4-17	Delivered price of reinforcement bar and PVC pipe	149
3.4-18	Unit price analysis of material, ready-mixed concrete	150
3.4-19	Delivered price of ready-mixed concrete and concrete products	151
3.5-1	Sum of Bill "B" to "H" on Base Date	153
3.5-2	Anticipated phased expenditure for construction	159

LIST OF ILLUSTRATIONS

<u>Fig. No.</u>		<u>Page</u>
2.2-1	Monthly means for evaporation and rainfall, Plaisance	8
2.3-1	Materials hauling diagram	12
2.4-1	Hauling system and hourly production	41
2.4-2	Embankment system and hourly production	42
3.1-1	Taxes separately shown cost element analysis	61
3.2-1	Mark-up trend of basic wage (including COLA and end of year bonus)	65
3.3-1	Factor of interest and insurance	89
3.4-1	CIF Value and foreign cost component of delivered price for imported materials and equipment	135
3.4-2	CIF Value and tax cost component of delivered price for imported materials and equipment	136
3.4-3	CIF Value and ratio of import duties/corporate tax	137

REFERENCE

- R-1 Annual Report of the Ministry of Works for the year ended
30th June, 1972
ditto, 30th June, 1973
ditto, 30th June, 1974
- R-2 Suggestions for a Brighter Future 1980-85, A socio-economic
Report Prepared by the Joint Economic Committee, July, 1979
- R-3 Capital Budget with Memorandum as passed by the Legislative
Assembly, 1978 - 1979
ditto, 1979 - 1980
- R-4 Estimates with Memorandum as passed by the Legislative Assembly,
1978 - 1979
ditto, 1979 - 1980
- R-5 Bi-Annual Digest of Statistics, Dec. 1978, Ministry of Economic
Planning and Development
- R-6 Mauritius Economic Review, 1975 - 1977
- R-7 International Travel and Tourism, June, 1972,
Ministry of Economic Planning and Development
- R-8 Bi-Annual Survey of Employment and Earnings in Large Establish-
ment, Ministry of Economic Planning and Development,
Sept., 1976
ditto, Sept., 1977
ditto, Sept., 1978
- R-9 Brief on Investment Conditions in Mauritius, Public Relations
and Industrial Promotion Div. Ministry of Commerce and Industry,
1978
- R-10 Fact Sheet No. 1, Basic Data on the National Economy, July, 1978,
ditto

- R-11 F.S. No. 2, Investment Incentives - Industrial Priorities,
July, 1978, ditto
- R-12 F.S. No. 3, Labour Regulations and Remuneration, July, 1979, ditto
- R-13 F.S. No. 4, Consumables, Electricity - Water - Petroleum Products,
July, 1978
- R-14 F.S. No. 5, Communications, July, 1978, ditto
- R-15 F.S. No. 6, Taxation - Financial Services July, 1978, ditto
- R-16 F.S. No. 7, Formalities to be effected before starting a New
Industry, July, 1978, ditto
- R-17 Government Notice No. 167 of 1979, The Central Water Authority
Act. 1971
- R-18 A Consolidated Version of the Labour Act 1975
- R-19 Government Notice No.194 of 1979, The National Pensions Act 1976
- R-20 The Income Tax Bill, No. XXX VII of 1974
- R-21 Annual Report of the Ministry of Labour and Industrial Relations,
1977-78
- R-22 General Notice No. 1377 of 1977, Holiday in 1979, (The Public
Holidays Act No. 22 of 1968 as ammended)
- R-23 Analysis of % Mark-up Provision on Labour Cost for Fringe
Benefits, 5 June, 1978, Builders Association of Mauritius
- R-24 Analysis of Standing Increase, ditto
- R-25 Government Notice No. 57 of 1979, The Relations Act, 1973
- R-26 Government Notice No. 101 of 1975, The Relations Act, 1973
- R-27 Government Notice No. 154 of 1976, ditto

- R-28 Income Tax Relief to Foreign Technicians, 4th April, 1977, Ministry of Commerce and Industry
- R-29 Individual (Joint), Income Tax Annual Return Year of Assessment 1979 - 1980
- R-30 The Concrete Pipes and Products Ltd.,
Price List, 22, Dec., 1977
- R-31 United Basalt Products, Price List, ditto
- R-32 Government Notice No. 230 of 1978, The Supplies Control Act 1974
- R-33 Junior Secondary Schools (Formerly Centralized Labs), Basic List of Prices for Materials as at June 15, 1979
- R-34 Concrete Pipes & Products Ltd.,
Price List, 2 Oct, 1979

Ireland Bluth Ltd. Price List, 4 June, 1979
Desboro International Ltd., Price List, 12, Oct., 1978
ditto, June, 1979
- R-35 Price List of Aggregate & Hollow Concrete Blocks as from 20th June, 1979, Randabel & Sons Ltd.
- R-36 ditto, as from 3rd November, 1977
- R-37 Price List of Ready-Mixed Concrete as from 20th August, 1979, ditto
- R-38 Grewals Ltd., Price List of Products, as from the 19th Sept., 1977
- R-39 Millars Mazhwerey, Mixing Capacity 15th Dec., 1977
- R-40 Price list of Steel Bars, Desboro June, 1979
- R-41 Catalogue of MRC Wire Products Ltd.
Price List of Products
- R-42 Desboro, Ribbod Torsteel

- R-43 Government Notice No. 157 of 1977
The Supplies Control Act, 1974
- R-44 Government Notice No. 114 of 1978
The Supplies Control Act, 1974
- R-45 The Customs Tariff Act, 1969
(as subsequently amended, 1979)
- R-46 ditto, 1978
- R-47 Prix de transport de Machinery
June, 1976, Randabell and Sons Ltd.
- R-48 Hire Rate of Plant, 1st Aug., 1979
Randabell and Sons Ltd.
- R-49 ditto, 1977
- R-50 Feasibility Study Report, "Access Road to the New Air Port,
Ministry of Works, BCEOM, February, 1976
- R-51 Contract for Construction of The Relief Road to the North,
Volume A, July 1976, BCEOM
- R-52 ditto, Addendum to Volume A
- R-53 ditto, Volume C, Confidential Documents
- R-54 ditto, Adjusted B/Q list, Oct, 1979
- R-55 ditto, Instructions for Contractors wishing to apply for
Prequalification
- R-56 Official Journal of the European Communities, vol 16, No. L287,
14 October, 1973
- R-57 Autoroute Terre Rouge - Mapou Prequalification Rapport

- R-58 Port Louis Northern Entrance Road
Report on Tenders, Sir Alexduder Gibbs & Partners (Mauritius),
June, 1978
- R-59 List of Major Projects awarded recently (Road Works), Ministry
of Works, Sept, 1979
- R-60 List of Registered Contractor
(Quantity Surveyer)
- R-61 Conditions of Contract (international) for Works of Civil
Engineering Construction, March, 1977, FIDIC
- R-62 Notes on Documents for Civil Engineering contracts, March, 1977,
FIDIC
- R-63 Civil Engineering Standard Method of Measurement, Institution
of Engineers, 1976
- R-64 Specification for Road and Bridge Works, Her Majesty Offices, 1969
- R-65 Meteorological Observations and Climatological Summaries,
April, 1974
- R-66 Climate of Mauritius, Meteorological Services
- R-67 Explosives Ordinance, 12th Dec., 1959
- R-68 ditto, 1960
- R-69 Report of the Auditors to the Members, (Randabel and Sons Limited),
Oct. 11, 1978

TABLE OF CONTENTS

	<u>Page</u>
1. INTRODUCTION	1
2. CONSTRUCTION PLANNING	2
2.1 General	2
2.2 Analysis of Working Days Rate	2
2.2.1 Number of holidays	2
2.2.2 Number of unworkable days due to weather conditions	3
2.2.3 Working days rate	5
2.3 Distribution Plan of Excavated Materials	11
2.4 Construction Schedule Analysis	14
2.4.1 Bridge works	14
2.4.2 Earthworks	14
2.4.3 Box culverts works	14
2.4.4 Pavement works	15
2.4.5 Recommended construction schedule	16
3. ESTIMATE OF CONSTRUCTION COST	58
3.1 General	58
3.1.1 Bill classification	58
3.1.2 Cost estimate	58
(1) Labour cost	59
(2) Equipment cost	59
(3) Material cost	59
(4) Taxes	60
3.1.3 Adjustment of construction cost.....	60
3.2 Labour Cost	62
3.2.1 Description	62
3.2.2 Mark-up trend of basic wage	63
3.2.3 Classification of labourer and labour cost	63
3.2.4 Income tax rate for labour cost	64
3.3 Equipment Cost	72
3.3.1 Description	72
3.3.2 Current hourly cost of main construction equipment	72
3.3.3 CIF Port Louis value of imported construction equipment ...	72

	<u>Page</u>
3.3.4 Classification of construction equipment	73
3.3.5 Relationship between CIF Port Louis value and delivered price	73
3.3.6 Depreciation system	73
3.3.7 Hourly cost of equipment for the project	73
3.4 Materials Cost	121
3.4.1 Description	121
3.4.2 Current prices of materials	121
3.4.3 Price structure of materials	121
(1) Imported materials	121
(2) Local products of which raw materials are locally produced	122
(3) Local products of which raw materials are imported	123
(4) Composed materials	123
3.5 Construction Cost	152
3.5.1 Construction cost on base date	152
3.5.2 Estimate of construction cost in July of 1981	154
(1) Influence by participation of foreign contractors	154
(2) Influence by currency devaluation of Rupee	154
(3) Influence by inflation factor of cost element	156
(4) Appreciation of adjusted cost	156
(5) Priced bills of quantities	157
(6) Phased expenditure for construction	158
3.5.3 Land acquisition cost	160

ANNEX TO PRICED B.Q.

1. INTRODUCTION

This confidential volume is aimed to build up construction planning and a cost estimate for the Beau Bassin - Port Louis Link Road Project.

Taking into account the period for land acquisition, prequalification or other tender preparations, the prospective award time will be around July of 1981. The construction of project of this magnitude will require at least 36 months from so as to distribute the various works moderately in both the constructional period and space from the common sense of civil works.

The schedule of each work item will be analyzed in detail in Chapter 2 based on an appropriate operation system considering the weather conditions.

In order to make a fair and reasonable cost estimate, the unit price analysis method is employed for each cost item. The analysis covers both the Cost Elements (labour, equipment, materials cost, and overhead/profit) and Cost Components (foreign exchange, local currency cost and taxes).

It is based on the price level in September of 1979 (Base Date), so an adjustment of construction cost will be made for the prospective award time. The procedure is presented in detail in Chapter 3.

In every aspect the cost estimate policy is compared with those of present or previous projects of a similar nature.

In order to assist in the evaluation of the construction period and future budget needs, the recommended construction schedule is prepared together with anticipated phased expenditures.

2. CONSTRUCTION PLANNING

2.1 General

The fundamental concept for construction method of each work is presented in the Unit Price Analysis Sheet appended to this volume. Using the production rates or operation systems thereof, the construction term of each work will be analyzed and arranged in proper order in the recommended construction schedule.

A moderate total construction period will be estimated as 3 years considering the various working conditions such as the "density of work in time and space" and working days rate, etc.

As viewed from the standpoing of financing, some of structures, earthworks and other ancillary works within or around Motorway Junction shall be executed in the latter part of the total contract period. (Phased Construction) The constructional procedure for the "Phased Construction will be given in detail in the Drawings.

2.2 Analysis of Working Days Rate

2.2.1 Number of holidays

The following shows the number of public holidays subject to the "General Notice No. 1377 of 1977, Holidays in 1979." If Sunday overlaps on the public holiday, it will not be counted twice for the analysis of working days rate.

Date	Nos. of Public Holiday
Monday	1st January
Tuesday	2nd January
Sunday	28th January
Saturday	10th February
*Saturday	10th February
Sunday	25th February
Monday	12th March
Wednesday	14th March
Thursday	29th March

Date		Nos. of Public Holiday
Saturday	14th April	2 days
Monday	16th April	
Tuesday	1st May	1 day
Wednesday	15th August	3 days
Saturday	25th August	
Monday	27th August	
Friday	5th October	3 days
Saturday	20th October	
Wednesday	24th October	
Thursday	1st November	2 days
Thursday	1st November	
Sunday	4th November	3 days
Tuesday	25th December	
Wednesday	26th December	

2.2.2 Number of unworkable days due to weather conditions

The influential factors for the workability of the project are the intensity and duration of rainfall. Table 2.2-1 shows the average number of days per month on which rainfall reaches or exceeds the specified values on the 8 stations adjacent to the project road. These data derive from the Meteorological Service of Mauritius during the period 1931 ~ 1960. And also shown in Fig. 2.2-1 is a relationship between the monthly average for evaporation and rainfall at Plaisance Station during the same period. Hence, the weather conditions can be divided into the following 4 phases depending on the above relationship.

Phase	Month	Rainfall	Evaporation
I	September	increasing	increasing
	November		
II	December	increasing (large)	decreasing (large)
	February		
III	March	decreasing (small)	increasing (small)
	May		
IV	June	decreasing	decreasing
	July		

The unworkable condition occurs on the rainy days and their succeeding, but not rainy days due to the characteristics both of rainfall and evaporation. So, the number of unworkable days during the period for each phase is summarized as follows according to the statistical data shown in "A Guide to Road Construction, 1976, Japan Road Association".

In case of earth-moving works:

Rainfall (mm)	Phase I		Phase II		Phase III		Phase IV	
	Nos. of unworkable days		Nos. of unworkable days		Nos. of unworkable days		Nos. of unworkable days	
	Rainy day	Succeeding day	Rainy day	Succeeding day	Rainy day	Succeeding day	Rainy day	Succeeding day
5-10	0	0	0.5	0	0	0	0.5	0
10-25	0.5	0	1	0.5	0.5	0	1	0.5
above 25	1	0.5	1	1.5	1	0.5	1	1.5

In case of bridge super-structure works:

5-10	0	0	0	0	0	0	0	0
10-25	0.5	0	0.5	0	0.5	0	1	0
Above 25	1	0	1	0	1	0	1	0

2.2.3 Working days rate

From the analysis, the working days rate for earth-moving works and bridge superstructure works are shown in Table 2.2-2 and 2.2-3 respectively. In the tables, it is assumed that some of the unworkable days be absorbed in the number of holidays given in the percentage of holidays against calendar days. In Phase II, the working days rate is very low and in particular lowest during the period from September to November. This tendency was verified in the performance of the Northern Entrance Road project by site investigation in March of this year. The annual number of working days is 218, the annual mean working days ratio comes to approximately 60 % for the earth-moving works. On the other hand, for the bridge superstructure works the number of working days is 254 and the rate is approximately 70 %.

Table 2.2-1 Average Number of Days per Month on Which Rainfall Reached or Exceeded the Specified Values

Station : Albion		Latitude : 20° 12.7'S					Longitude : 57° 24.0'E					Altitude : 40 feet	
Month Rainfall	J	F	M	A	M	J	J	A	S	O	N	D	Year
0.1 mm	8.1	10.7	13.0	7.9	5.0	5.2	5.5	4.0	3.0	3.6	4.2	8.6	78.8
1	6.3	9.0	6.3	6.3	4.2	2.9	3.0	2.5	1.8	2.2	2.9	8.0	60.2
5	3.7	4.5	5.6	3.3	1.5	1.5	1.2	0.5	0.6	0.6	1.6	4.4	29.1
10	2.2	2.9	4.0	1.7	0.8	0.9	0.5	0.2	0.5	0.2	0.8	2.9	17.6
25	0.8	0.9	1.2	0.7	0.1	0.2	0.0	0.0	0.1	0.0	0.3	1.4	5.7
50	0.7	0.5	0.4	0.1	0.0	0.0	0.0	0.0	0.1	0.0	0.1	0.7	2.6

Station : Plaine Lauzun		Latitude : 20° 10.1'S					Longitude : 57° 28.4'E					Altitude : 80 feet	
Month Rainfall	J	F	M	A	M	J	J	A	S	O	N	D	Year
0.1 mm	7.5	9.3	10.6	6.4	3.9	3.7	5.4	4.1	3.7	3.6	4.1	8.1	70.4
1	7.1	9.1	10.4	6.2	3.9	3.6	5.0	3.8	3.5	3.1	4.1	7.6	67.5
5	6.5	7.7	8.2	5.1	3.2	2.2	3.1	2.3	1.7	2.2	2.8	5.3	50.3
10	4.6	5.7	6.5	3.4	2.5	1.4	2.2	1.1	0.9	1.3	2.1	4.1	35.0
25	3.0	3.0	3.6	1.5	1.2	0.8	1.0	0.3	0.4	0.3	0.9	2.8	18.8
50	1.9	1.2	1.4	0.5	0.5	0.1	0.5	0.0	0.1	0.1	0.2	0.9	7.4

Station : Reduit		Latitude : 20° 13.9'S					Longitude : 57° 29.3'E					Altitude : 1.	
Month Rainfall	J	F	M	A	M	J	J	A	S	O	N	D	Year
0.1 mm	17.5	18.7	21.1	16.9	17.1	18.0	22.3	21.6	16.0	15.5	12.4	15.8	212.9
1	14.5	15.2	17.6	12.4	11.4	13.3	17.5	15.5	11.4	10.3	8.8	13.1	161.0
5	7.6	7.1	10.1	5.5	3.7	4.7	5.1	3.5	2.2	2.0	3.9	6.1	61.5
10	4.0	5.0	5.7	2.9	1.5	1.7	1.4	0.8	1.2	0.9	3.0	4.6	37.3
25	2.1	3.0	2.1	1.1	0.3	0.4	0.5	0.3	0.1	0.3	1.1	2.1	13.4
50	1.0	1.2	0.8	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.0	4.1

Station : Mon Desert (Alma)		Latitude : 20° 13.3'S					Longitude : 57° 31.6'E					Altitude : 1.27 feet	
Month Rainfall	J	F	M	A	M	J	J	A	S	O	N	D	Year
0.1 mm	21.1	19.3	23.5	18.6	17.1	19.4	22.7	22.7	22.1	15.2	14.0	17.7	223.4
1	17.6	16.3	20.7	16.7	14.9	16.6	20.1	19.6	13.4	12.6	10.9	15.8	195.4
5	10.6	9.7	12.3	9.1	7.3	6.9	8.6	6.1	4.5	3.8	4.6	9.2	92.7
10	6.1	6.6	7.4	4.5	3.4	3.5	2.9	2.3	1.7	1.3	2.2	5.9	47.8
25	3.1	3.1	3.6	1.8	0.6	0.9	0.6	0.3	0.3	0.4	0.9	2.8	18.4
50	1.5	1.1	1.3	0.3	0.1	0.2	0.2	0.1	0.2	0.1	0.2	1.3	6.6

Station : La Ferme Latitude : 20° 15.2'S Longitude : 57° 24.3'E Altitude : 460 feet													
Month	J	F	M	A	M	J	J	A	S	O	N	D	Year
Rainfall													
0.1 mm	10.8	12.0	13.0	8.4	6.5	7.7	7.9	6.7	6.0	6.0	5.9	10.6	101.5
1	9.0	10.9	12.4	8.0	4.9	5.8	5.0	4.8	3.2	4.3	5.1	9.7	83.1
5	4.5	6.0	7.5	3.8	1.6	1.9	1.3	1.0	1.0	1.3	2.5	5.9	38.3
10	3.2	3.9	5.1	2.4	0.8	1.0	0.6	0.4	0.5	0.5	0.5	3.7	23.8
25	1.6	1.8	1.9	0.5	0.2	0.2	0.1	0.1	0.3	0.0	0.3	1.9	9.1
50	0.8	0.5	0.8	0.1	0.0	0.1	0.0	0.0	0.1	0.0	0.2	0.6	3.2

Station : Vaccas Latitude : 20° 17.6'S Longitude : 57° 29.4'E Altitude : 1,390 feet													
Month	J	F	M	A	M	J	J	A	S	O	N	D	Year
Rainfall													
0.1 mm	22.3	20.9	24.7	19.7	21.0	22.1	24.9	24.9	20.1	18.3	16.8	20.2	255.9
1	17.6	16.1	20.3	4.8	14.1	16.0	20.4	19.6	13.5	12.6	11.1	14.4	191.0
5	9.8	9.3	13.2	8.1	6.0	8.0	10.2	8.5	5.3	4.7	4.4	8.5	96.1
10	6.6	6.6	8.5	4.5	2.6	4.1	4.8	2.9	1.9	1.9	2.7	5.3	52.4
25	2.9	3.5	3.6	1.7	0.7	0.6	0.7	0.9	0.2	0.4	1.4	2.6	19.2
50	1.4	1.5	1.3	0.8	0.1	0.2	0.0	0.0	0.2	0.0	0.3	1.1	6.9

Station : assin Latitude : 20° 17.7'S Longitude : 57° 26.8'E Altitude : 1,030 feet													
Month	J	F	M	A	M	J	J	A	S	O	N	D	Year
Rainfall													
0.1 mm	13.0	15.0	17.1	12.5	10.9	12.9	14.8	12.5	8.8	8.8	8.8	11.7	146.8
1	11.8	14.2	16.1	11.1	8.6	11.8	13.5	10.9	7.5	7.6	7.8	11.3	131.2
5	5.2	8.0	10.1	4.8	3.3	3.6	3.9	2.2	2.3	1.6	3.7	6.9	55.6
10	3.6	4.7	7.0	3.3	1.6	1.6	1.1	0.5	0.5	0.4	2.7	4.6	31.6
25	1.8	1.5	2.3	1.4	0.5	0.2	0.3	0.2	0.2	0.0	1.0	2.0	11.2
50	0.6	0.6	1.1	0.5	0.1	0.1	0.0	0.0	0.2	0.0	0.0	0.6	3.8

Station : Henrietta Latitude : 20° 19.9'S Longitude : 57° 28.1'E Altitude : 1,540 feet													
Month	J	F	M	A	M	J	J	A	S	O	N	D	Year
Rainfall													
0.1 mm	17.9	16.2	19.0	14.6	15.1	17.6	22.5	20.7	14.7	12.9	12.3	15.0	198.5
1	14.7	15.1	18.0	11.6	13.7	14.6	19.5	17.0	11.0	19.5	10.6	12.6	177.9
5	9.1	9.1	12.4	6.3	6.0	5.4	9.6	7.9	4.9	3.5	3.8	7.1	87.1
10	5.9	6.6	8.5	4.2	2.9	3.0	4.4	2.5	2.2	1.3	3.3	5.5	50.5
25	2.4	2.8	3.8	2.1	0.9	1.0	0.2	0.4	0.1	0.1	1.0	2.7	17.5
50	1.3	0.7	0.7	0.6	0.1	0.2	0.0	0.0	0.1	0.0	0.2	0.1	4.9

Fig. 2.2-1 Monthly Means for Evaporation and Rainfall
(PLAISANCE)




Table 2.2-2 Working Days Rate for Earthwork and Bridge Substructure Work

Month	Calend. days (1)	Holidays (2)	Calend. days excl. Holiday (3)	Ratio of Holi- days (3)	Rainy days			Unworkable days due to rain				Unwork- able days but over- lapped on Holidays (3)X(4)	Work- ing days (rate)
					5-10m/m	10-25m/m	above 25m/m	5-10m/m	10-25m/m	above 25m/m	Total (4)		
Jan	31	6	25	0.19	7.1	4.6	3.4	3.6	6.9	8.5	19.0	-3.7	9.7 (31%)
Feb	28	6	22	0.21	7.7	5.3	3.4	3.9	8.0	8.5	20.4	-4.4	6.0 (21%)
Mar	31	7	24	0.23	9.9	6.6	3.7	0	3.3	5.6	8.9	-2.0	17.1 (55%)
Apr	30	6	24	0.20	5.8	3.4	1.7	0	1.7	1.7	4.3	-0.9	20.6 (69%)
May	31	5	26	0.16	4.1	2.0	0.7	0	1.0	1.1	2.1	-0.3	24.2 (78%)
Jun	30	4	26	0.13	4.3	2.2	0.7	2.2	3.3	1.8	7.3	-1.0	19.7 (66%)
Jul	31	4	27	0.13	5.4	2.2	0.5	2.7	3.3	1.3	7.3	-0.9	20.6 (66%)
Aug	31	7	24	0.23	4	1.3	0.3	2.0	2.0	0.8	4.8	-1.1	20.3 (65%)
Sep	30	4	26	0.13	2.8	1.2	0.3	0	0.6	0.5	1.1	-0.1	25.0 (83%)
Oct	31	7	24	0.23	2.5	1.0	0.2	0	0.5	0.3	0.8	-0.2	23.4 (75%)
Nov	30	6	24	0.20	3.4	2.2	1.0	0	1.1	1.5	2.6	-0.5	21.9 (73%)
Dec	31	6	25	0.19	6.7	4.6	3.2	3.3	6.9	8.0	18.2	-3.5	10.3 (33%)
Total	365	67	298	0.18									218.6 (60%)

Table 2.2-3 Working Days Rate for Bridge Superstructure Work

Month	Calend. days (1)	Holidays (2)	Calend. days excl. Holiday days (3)	Ratio of Holi- days (3)	Rainy days			Unworkable days due to rain				Unwork- able days but over- lapped on - Holidays (3) X (4)	Work- ing days (rate)
					5-10m/m	10-25m/m	above 25m/m	5-10m/m	10-25m/m	above 25m/m	Total (4)		
Jan	31	6	25	0.19	7.1	4.6	3.4	0	2.3	3.4	8.7	-1.7	17.0 (55%)
Feb	28	6	22	0.21	7.7	5.3	3.4	0	2.7	3.4	6.1	-1.3	17.2 (61%)
Mar	31	7	24	0.23	9.9	6.6	3.7	0	3.3	3.7	7.0	-1.6	18.6 (60%)
Apr	30	6	24	0.20	5.8	3.4	1.7	0	1.7	1.7	3.4	-0.7	21.3 (71%)
May	31	5	26	0.16	4.1	2.0	0.7	0	1.0	0.7	1.7	-0.3	24.6 (79%)
Jun	30	4	26	0.13	4.3	2.2	0.7	0	1.1	0.7	1.8	-0.2	24.4 (81%)
Jul	31	4	27	0.13	5.4	2.2	0.5	0	1.1	0.5	1.6	-0.2	25.6 (83%)
Aug	31	7	24	0.23	4	1.3	0.3	0	0.7	0.3	1.0	-0.2	23.2 (75%)
Sep	30	4	26	0.13	2.8	1.2	0.3	0	0.6	0.3	0.9	-0.1	25.2 (84%)
Oct	31	7	24	0.23	2.5	1.0	0.2	0	0.5	0.2	0.7	-0.2	23.5 (76%)
Nov	30	6	24	0.20	3.4	2.2	1.0	0	1.1	1.0	2.1	-0.4	22.3 (74%)
Dec	31	6	25	0.19	6.7	4.6	3.2	0	2.3	3.2	5.5	-1.1	11.4 (34%)
Total	365	67	298	0.18									254.3 (70%)

2.3 Distribution Plan of Excavated Materials

Fig. 2.3-1 shows schematically a distribution plan of materials from the roadway and structure excavations subject to the mass curve shown in the Drawings. In order to minimize the haulage distance, surplus materials shall be deposited in the areas near the projected road. Two deposit areas are tentatively allocated in the crown lands around Sta. 45 and Motorway Junction. The Employer shall prepare those deposit areas parallel to the land acquisitions before the work starts.

The quantity of deposited materials will reach to approximately 188,000 m³, of which 162,000 m³ will be originated in the section Sta. 55+80 - Sta. 59+80, 15,000 m³ in the section Sta. 62+82 - Sta. 65+57 and 9,000 m³ in the realignment excavation existing Motorway as shown in the Drawings.

Viewed from the point of material distribution, sectioning of earth-moving will be as follows:

- Section 1: Sta. 0 - Sta. 34+20 and Access Road
(Excavation and embankment materials are balanced within the section)
- Section 2: Sta. 34+20 - Sta. 60+78 and Coromandel I.C.
(Surplus materials)
- Section 3: Sta. 60+78 - Sta. 76+13, Motorway Junction and improvement of M₁ M₂ Road
(Surplus materials)

Table 2.3-1 summarized the haulage distance and quantity of materials subject to the haulage system. In the phased construction stage, the stockpiled materials within or around the Motorway Junction will be used to accomplish the works as specified in the Drawings and stipulations of the Contract.

Two temporary working roads will be proposed, crossing Grand River Northwest and St. Louis River respectively for the execution of the bridges' substructure. The latter road aims to serve the hauling of materials (Approx. 15,000 m³) from the section Sta. 62+82 - Sta. 65+57 to the deposit area tentatively established in the vicinity of the Motorway Junction.

Fig. 2.3-1 Materials Hauling Diagram




Table 2.3-1 Roadway Excavation and Mean Haulage Distance

Hauling Distance (m)	Hauling Equipment	Sta0+00 - Sta34+20 & Access Road	Sta34+20 - Sta60+78 & Coromandal I C	Sta60+78 - Sta76+13 & ML M2 Road	Total Q'ty & Mean Haulage Distance (D̄)
D<50	Bulldozer	18,500m ³	5,200m ³	5,400m ³	29,100m ³
	Bulldozer	2,300m ³ D̄=80m	2,100m ³ D̄=80m	5,100m ³ D̄=70m	9,500m ³ D̄=75m
50<D<100	Dozer shovel & Dump truck	—	—	89,800m ³ D̄=110m	89,800m ³ D̄=110m
100<D<500	ditto	16,700m ³ D̄=270m	20,400m ³ D̄=220m	65,300m ³ D̄=350m	101,400m ³ D̄=310m
500<D<1000	ditto	83,800m ³ D̄=620m	—	—	83,800m ³ D̄=620m
1000<D<1500	ditto	27,800m ³ D̄=1,320m	162,000m ³ D̄=1,300m	15,300m ³ D̄=1,060m	205,100m ³ D̄=1,290m
1500<D<2000	ditto	—	102,300m ³ D̄=1,760m	—	102,300m ³ D̄=1,760m
Total Q'ty		149,100m ³ D̄=633m	292,000m ³ D̄=1,355m	180,900m ³ D̄=274m	621,000m ³ D̄=870m

This analysis is exclusive of the haulage of material in the phased construction period.

2.4 Construction Schedule Analysis

2.4.1 Bridge works

The schedule analysis for major bridges is shown in Table 2.4-1 to 2.4-23. In the analysis, the required construction term for each bridge is calculated on the actual working days basis, hereupon, it is converted to the calendar days basis using the working days rate (70%) as above discussed. An hourly production rate for equipment or labour derives from assumptions established in the Unit Price Analysis Sheet respectively, which are attached hereto as an appendix.

2.4.2 Earthworks

The operation system of earthworks and production rate are assumed as shown in Table 2.4-24, and Fig. 2.4-1 and 2.4.2. Based on those assumptions the construction term for each section is represented in Table 2.4-25, 2.4-26, and 2.4-2.

2.4.3 Box culverts works

The schedule analyses for execution of box culverts are shown in the Table 2.4-28 and 2.4-29. The production rate of each work item such as concreting, form work or reinforcement bar work is based on the production speed set forth in the Unit Price Analysis Sheet, which is as follows.

Item	Equipment & Labourer	Nos.	Production rate
<u>Foundation</u>			
Excavation	Back hoe, 0.5 m ³	1 unit	40 m ³ /h
Bedding	Labourer	5 men	1.2 m ³ /h
Levelling concrete	Labourer	10 men	30 m ³ /h
Reinforcement bar	Wheel crane, 5t Truck, 6t Labourer	1 unit 1 unit 10 men	0.25 t/h
Formwork	Truck, 6t Labourer	1 unit 5 men	3 m ² /h

Item	Equipment & Labourer	Nos.	Production rate
<u>Concreting</u>			
Scaffolding	Wheel crane, 5t	1 unit	20 m ³ /h
	Truck, 6t	1 unit	
	Labourer	5 men	
Formworks	Wheel crane, 5t	1 unit	20 m ² /h
	Truck, 6t	1 unit	
	Labourer	10 men	
Reinforcement bar	Wheel crane, 5t	1 unit	0.25 t/h
	Truck, 6t	1 unit	
	Labourer	10 men	
Concreting	Concrete pump truck, 60 m ³ /h	1 unit	40 m ³ /h
	Concrete vibrator 4 kg	3 unit	
	Labourer	10 men	

2.4.4 Pavement works

The preparation on subgrade preceding subbase work will be performed by the combination of a Motor grader (Blade width 3.7 m) and a 20 ton Tire roller, so that the hourly production is assumed to be approximately 500 m²/h x 8 hr/day = 4,000 m²/h.

The hourly production rate for the subbase work is assumed as 1,000 m³/day and 500 m³/day respectively for the carriageway and shoulder. The operational arrangement is as follows.

<u>Item</u>	<u>Required number per 1,000 m³/day</u>
Motor grader, 3.7 m class	2 units
Tire roller, 20 t class	2 units
Tire roller, 28 t class	1 unit
Macadam roller, 12 t class	1 unit
Vibrating roller, 1 t class	2 units
Water lorry, 5,000 l class	1 unit
Labourer	15 men

The hourly production rate for the asphalt binder and wearing course work is estimated as 390 ton/day, for which following equipment and labourers are required.

<u>Item</u>	<u>Required number per 390 ton/day</u>
Asphalt finisher, 4.5 m class	4 units
Macadam roller, 12 t class	4 units
Tandem roller, 20 t class	4 units
Tire roller, 28 t class	4 units
Labourer	30 men

As based upon the above production rates the construction term is shown in Table 2.4-30 to 2.4-35.

2.4.5 Recommended construction schedule

The recommended construction schedule is presented in Table 2.4-36 subject to the detailed analyses of construction term for main structures or sections of the project. From the contractual consideration the works around the Motorway Junction are to be assigned within the latter part of period for completion. (Phased construction)

In considering common civil engineering practices it will require at least three years for the completion of the project in order to distribute each work element over the project time and space.

In addition, the main equipment can be scheduled approximately as shown in Table 2.4-37.

Table 2.4-1 Summary of Construction Period of Bridge




Table 2.4-2 Schedule Analysis of Bridge (Link Road Bridge)

Name of Bridge		Width	Length	Type		
G.R.N.W. B-Ie.		8.2 m	192.9 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1			Improvement of Existing Structures		
	A 2					
Pier	P 1					
	P 2					
	P 3					
	P 4					
	P 5					
	P 6					
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	1580	26.8m x 35 pcs.		Erection Girder	Truck Crane	Staging
				x		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure	A 1		█						
	A 2			█					
	P 1		█	█					
	P 2		█	█					
	P 3		█	█					
	P 4 - P 6		█	█					
Super-Structure	Preparation								
	Production of Girder								
	Erection								
	Deck concrete etc.								
	Cleaning								
Pavement									
Ancillary Works									

Table 2.4-3 Schedule Analysis of Bridge (Link Road Bridge)

Name of Bridge		Width	Length	Type		
G.R.N.W.B-Le		8.2 m	192.9 m	Simple post-tentioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	7.5	Reverse T	Cofferdam Back hoe Dozer shovel	Concrete pump truck	
	A 2	10.0	"			
Pier	P 1	23.0	Column T			
	P 2	25.0	"			
	P 3	24.5	"			
	P 4	25.5	"			
	P 5	25	"			
	P 6	23.5	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
		Erection Girder	Truck Crane	Staging		
	1580	26.8m x 35pcs.		x		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization									
Sub-Structure	A 1								
	A 2								
	P 1								
	P 2								
	P 3								
	P 4 - P 6								
Super-Structure	Preparation								
	Production of Girder								
	Erection								
	Deck concrete etc.								
	Cleaning								
Pavement									
Ancillary Works									

Table 2.4-4 Schedule Analysis of Bridge (Link Road Bridge)

Name of Bridge		Width	Length	Type		
ST.L.Ri.A-le.		8.2	27.6 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment			Improvement of Existing	Abutment		
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
		Erection Girder	Truck Crane	Staging		
	220	26.8m x 5 pcs.		x		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration (day)	30	60	90	120	150	180	210	240
		Mobilization	0-10						
Sub-Structure	A 1	10-25							
	A 2	15-25							
Super-Structure	Preparation	0-10							
	Production of Girder		10-30						
	Erection		20-40						
	Deck concrete etc.			40-50					
	Cleaning				50-55				
Pavement									
Ancillary Works									

Table 2.4-5 Schedule Analysis of Bridge (Link Road Bridge)

Name of Bridge		Width	Length	Type		
ST.L.Ri.B-Le.		8.2 m	82.7 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	10	Reverse T	Cofferdam Back hoe	Concrete pump truck	
	A 2	12	"			
Pier	P 1	14.2	Column T			
	P 2	14.5	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
				Erection Girder	Truck Crane	Staging
	659	26.8m x 15 pcs.		x		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure	A 1		█						
	A 2		█						
	P 1		█						
	P 2		█						
Super-Structure	Preparation	█							
	Production of Girder		█						
	Erection		█						
	Deck concrete etc.		█						
	Cleaning				█				
Pavement									
Ancillary Works									

Table 2.4-6 Schedule Analysis of Bridge (Rampway Bridge)

Name of Bridge		Width	Length	Type		
Mwy. Jun. B-Rp. Br.		9.1 m	53.8 m	2 continuous, simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	4.5	Gravity			
	A 2	4.5	"			
Pier	P 1	8.7	Rigid frame			
	P 2	8.6	"			
	P 3	10.0	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	490			Erection Girder	Truck Crane	Staging
					x	
					2200 m ³ in space	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization									
Sub-Structure	A 1								
	A 2								
	P 1								
	P 2								
	P 3								
Super-Structure	Preparation								
	Deck concrete etc.								
Pavement									
Ancillary Works									

Table 2.4-7 Schedule Analysis of Bridge (Rampway Bridge)

Name of Bridge		Width	Length	Type		
Mwy.Jun.G-Rp.Br.		7.8 m	39.35 m	2 continuous span, & simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	4.5	Gravity			
	A 2	12.5	Reverse T			
Pier	P 1	8.0	Rigid frame			
	P 2	9.0	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	306			Erection Girder	Truck Crane	Staging
					x	
				2300 m ³ in space		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization									
Sub-Structure	A 1								
	A 2								
	P 1								
	P 2								
				total: 85 days					
Super-Structure	Preparation								
	Deck concrete etc.								
				total: 60 days					
Pavement									
Ancillary Works									

Table 2.4-8 Schedule Analysis of Bridge (Rampway Bridge)

Name of Bridge		Width	Length	Type		
Cor. Int. E-Rp.		9.5 m	45.7 m	2 continuous span, simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	4.0	Gravity	Back hoe, Dozer shovel	Concrete pump truck	
	A 2	4.0	"			
Pier	P 1	9.0	Rigid frame			
	P 2	8.5	"			
	P 3	9.5	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	434			Erection Girder	Truck Crane	Staging
					x	
					1500 m ³	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure	A 1			█					
	A 2			█					
	P 1	█	█						
	P 2		█	█					
	P 3	█	█						
Super-Structure	Preparation	█							
	Slab concrete		█	█					
Pavement									
Ancillary Works									

Table 2.4-9 Schedule Analysis of Bridge (Rampway Bridge)

Name of Bridge		Width	Length	Type		
Cor.Int.F-Rp.		9.5 m	47.2 m	2 continuous span, simple RC voided Slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	4.0	Gravity	Back hoe, Dozer shovel	Concrete pump truck	
	A 2	4.0	"			
Pier	P 1	9.5	Rigid frame			
	P 2	9.0	"			
	P 3	10.5	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	449			Erection Girder	Truck Crane	Staging
					x	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization									
Sub-Structure									
		To be deemed same with Cor.Int.E-Rp.							
Super-Structure									
Pavement									
Ancillary Works									

Table 2.4-10 Schedule Analysis of Bridge (Over Bridge)

Name of Bridge		Width	Length	Type		
PAILLES Ov.Br.		7.2 m	55.5 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	5	Wall			
	A 2	5	"			
Pier	P 1	9	Rigid frame			
	P 2	9	"			
	P 3	11	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	533	20.3m x 10 pcs.		Erection Girder	Truck Crane	Staging
		7.0 x 5			x	
		5.05 x 5			(preferable)	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure	A 1			█					
	A 2			█					
	P 1	█	█						
	P 2		█	█					
	P 3	█	█	█					
Super-Structure	Preparation	█							
	Production of girder		█	█					
	Erection			█	█				
	Deck concrete etc.			█	█				
	Cleaning					█			
Pavement									
Ancillary Works									

Table 2.4-11 Schedule Analysis of Bridge (Over Bridge)

Name of Bridge		Width	Length	Type		
A-1 Road Ov.		25.5 m	57.9 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	4.0	Gravity	Back hoe, Dozer shovel	Concrete pump truck	To commence after detouring A-1 Rd.
	A 2	5.0	Reverse T			
Pier	P 1	8.0	Rigid frame			
	P 2	9.5	"			
	P 3	12.0	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
				Erection Girder	Truck Crane	Staging
		8.35m x 10 pcs.			x	
		19.9 x 10				
		21.4 x 12				
		5.3 x 12				

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		■							
Sub-Structure	A 1			■					
	A 2			■					
	P 1	■							
	P 2	■							
	P 3	■							
Super-Structure	Preparation	■							
	Production of Girder		■						
	Erection		■						
	Deck concrete etc.			■					
	Cleaning					■			
Pavement									
Ancillary Works									

Table 2.4-12 Schedule Analysis of Bridge (Over Bridge)

Name of Bridge		Width	Length	Type		
COROMANDEL Ov.Br.		5.91 m	69.1 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	5.0	Reverse T	Back hoe, Dozer shovel	Concrete pump truck	
	A 2	5.0	"			
Pier	P 1	8.5	Rigid frame			
	P 2	9.5	"			
	P 3	9.3	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder				
	587	27.7m x 8 pcs. 4.4 x 4 6.25 x 4		Erection Girder	Truck Crane	Staging
				x		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration (day)	30	60	90	120	150	180	210	240
		Mobilization	0-10						
Sub-Structure	A 1			60-90					
	A 2			70-90					
	P 1	30-60				total: 100 days			
	P 2	30-60							
	P 3	30-60							
Super-Structure	Preparation	0-10							
	Production of girder	10-30							
	Erection	30-60				total: 95 days			
	Deck concrete etc.	30-60							
	Cleaning	60-70							
Pavement									
Ancillary Works									

Table 2.4-13 Schedule Analysis of Bridge (Over Bridge)

Name of Bridge		Width	Length	Type		
Cor.Int.H-Rp.		5.5 m	22.1 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	5.0	Reverse T			
	A 2	4.0	Gravity			
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
		Erection Girder	Truck Crane	Staging		
	121	21.3m x 4 pcs.		x	x	
				(preferable)		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration (day)	30	60	90	120	150	180	210	240	
		Mobilization	■							
Sub-Structure	A 1	■	total: 30 days							
	A 2	■								
Super-Structure	Preparation	■								
	Production of Girder	■								
	Erection	■	total: 55 days							
	Deck concrete		■							
	Cleaning			■						
Pavement										
Ancillary Works										

Table 2.4-14 Schedule Analysis of Bridge (Over Bridge)

Name of Bridge		Width	Length	Type		
Sta. 22 Ov. Br.		5.5 m	46.0 m	2 continuous span, simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	4.0	Gravity	Back hoe, Dozer shovel	Concrete pump truck	
	A 2	4.5	"			
Pier	P 1	9.0	Rigid frame			
	P 2	9.0	"			
	P 3	10.0	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	308			Erection Girder	Truck Crane	Staging
					x	
					2000 m ³ in space	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration (day)								
		30	60	90	120	150	180	210	240
Mobilization	10								
Sub-Structure	A 1			85					
	A 2			75					
	P 1	35	65						
	P 2	40	70						
	P 3	35	65						
Super-Structure	Preparation	10							
	Slab concrete	35	65						
Pavement									
Ancillary Works									

Table 2.4-15 Schedule Analysis of Bridge (Pedestrian Bridge)

Name of Bridge		Width	Length	Type		
Hin. Temple Ped.		2.4 m	38.1 m	2 continuous span, RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	6.5	Reverse T	Back hoe, Dozer shovel	Concrete Pump truck	
	A 2	5.5	"			
Pier	P 1	7.3	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	137			Erection Girder	Truck Crane	Staging
					x	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization									
Sub-Structure	A 1	total: 55 days							
	A 2								
	P 1								
Super-Structure	Preparation	total: 35 days							
	Slab concrete								
Pavement									
Ancillary Works									

Table 2.4-16 Schedule Analysis of Bridge (Pedestrian Bridge)

Name of Bridge		Width	Length	Type		
B.B. Ped. Br.		2.4 m	19.1 m	Simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	8.5	Reverse T			
	A 2	8.5	"			
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder	Erection of Girder			
			Erection Girder	Truck Crane	Staging	
				x		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure			█						
			█						
Super-Structure		█							
			█						
Pavement									
Ancillary Works									

Table 2.4-17 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy. Jun. A-Le. 1 Br.		8.9 m	30.1 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	10.2	Reverse T			
	A 2	12.5	"			
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	268	30m x 5 pcs		Erection Girder	Truck Crane	Staging
				x (preferable)	x	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration (day)	Duration (day)								
		30	60	90	120	150	180	210	240	
Mobilization										
Sub-Structure	A 1				total: 80 days					
	A 2									
Super-Structure	Preparation									
	Production of Girder									
	Erection				total: 110 days					
	Deck concrete etc.									
	Cleaning									
Pavement										
Ancillary Works										

Table 2.4-18 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy. Jun. B-Le. 1 Br		8.9 m	20.1 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	10.7	Reverse T			
	A 2	12.5	"			
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
		Erection Girder	Truck Crane	Staging		
	179	19.4m x 5 pcs.		x (Preferable)	x	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration									
	(day)	30	60	90	120	150	180	210	240	
Mobilization		█								
Sub-Structure	A 1	█			total: 60 days					
	A 2	█								
Super-Structure	Preparation	█								
	Production of Girder		█							
	Erection		█		total: 100 days					
	Deck concrete etc.			█						
	Cleaning				█					
Pavement										
Ancillary Works										

Table 2.4-19 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy. Jun. A-Le. 2 Br.		8.9 m	89.2 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	14.0	Buttress			
	A 2	13.0	"			
Pier	P 1	18.4	Column T			
	P 2	16.3	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	794	26.8m x 10 pcs. 33.2 x 5		Erection Girder	Truck Crane	Staging
				x (Preferable)	x	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure	A 1	█	█						
	A 2		█	█		total: 95 days			
	P 1		█	█					
	P 2		█	█					
Super-Structure	Preparation	█							
	Production of Girder		█	█					
	Erection			█	█		total: 145 days		
	Deck concrete etc.			█	█				
	Cleaning					█			
Pavement									
Ancillary Works									

Table 2.4-20 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy. Jun. B-Le. 2 Br		8.9 m	91.7 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	14.5	Buttress			After roadway excavation
	A 2	14.0	"			
Pier	P 1	19.5	Column T			
	P 2	15.8	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
				Erection Girder	Truck Crane	Staging
	818	26.8m x 5 pcs. 29.2 x 5 33.2 x 5		x (Preferable)	x	

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration (day)	30	60	90	120	150	180	210	240
		Mobilization	0-10						
Sub-Structure	A 1	10-30							
	A 2	10-30							
	P 1	10-30	30-60						
	P 2	10-30	30-60						
Super-Structure	Preparation	0-10							
	Production of Girder	10-30	30-60						
	Erection	30-60	60-90						
	Deck concrete etc.	60-90	90-120						
	Cleaning	120-130							
Pavement								240-250	
Ancillary Works									

Table 2.4-21 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy.Jun.A-Le. 3 Br		15.9 m	17.1 m	Simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	11.5	Buttress			
	A 2	8.5				
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder		
	267	Erection Girder	Truck Crane	Staging		
			x	1300 m ³ in space		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration	(day) 30	60	90	120	150	180	210	240
	Mobilization								
Sub-Structure	A 1								
	A 2								
Super-Structure	Preparation								
	Deck concrete etc.								
Pavement									
Ancillary Works									

Table 2.4-22 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy.Jun.B-Le. 3 Br.		8.9 m	17.1 m	Simple RC voided slab		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	13	Buttress			
	A 2	9	Reverse T			
Pier						
Super-Structure	Area of Bridge (m ²)	Nos. of Girder		Erection of Girder	Truck Crane	Staging
					x	
				800 m ³ in space		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization									
Sub-Structure	A 1								
	A 2								
Super-Structure	Preparation								
	Deck concrete								
Pavement									
Ancillary Works									

Table 2.4-23 Schedule Analysis of Bridge (Motorway Junction Bridge)

Name of Bridge		Width	Length	Type		
Mwy. Jun. E-Rp. Br.		6.1 m	85 m	Simple post-tensioned girder		
Sub-Structure	No.	Height (m)	Type	Execution of Foundation	Execution of Concrete	Remarks
Abutment	A 1	8.0	Reverse T			
	A 2	13.0	Buttress			
Pier	P 1	15.5	Collumn T			
	P 2	18.5	"			
Super-Structure	Area of Bridge (m ²)	Nos. of Girder	Erection of Girder			
			Erection Girder	Truck Crane	Staging	
				x (preferable)		

Analysis of Construction Duration (Actual Working Day Basis)

Item	Duration								
	(day)	30	60	90	120	150	180	210	240
Mobilization		█							
Sub-Structure	A 1	█							
	A 2	█	█						
	P 1		█	█					
	P 2		█	█					
Super-Structure	Preparation	█							
	Production of girder		█	█					
	Erection			█	█				
	Deck concrete etc.			█	█				
	Cleaning				█				
Pavement									
Ancillary Works									

Table 2.4-24 Excavating and Collecting Material Rate

Materials	Combination of Equipment	Hourly Production
Excavation of Soil Material (D1 = 5Dm)	Bulldozer 34 ton, 1 unit	65m ³ /h
	Bulldozer 24 ton, 1 unit	35m ³ /h
	Bulldozer 17 ton, 1 unit	30m ³ /h
Excavation of Unsound Rock by ripping (D1 = 50m)	Bulldozer 34 ton, 1 unit	45m ³ /h
	Bulldozer 24 ton, 1 unit	30m ³ /h
	Bulldozer 17 ton, 1 unit	20m ³ /h
Excavation of Sound Rock by blasting (D1 = 50m)	Jackhammer 20 kg, 8 units	20m ³ /h
	Air compressor 7.5m ³ /min, units	
	Bulldozer 17 ton, 1 unit	
		130m ³ /h 1040m ³ /day (1 day = 8 h) Average 113m ³ /h (=900m ³ /day)
		95m ³ /h (=760m ³ /day)
		20m ³ /h (=160m ³ /day)

Fig. 2.4-1 Hauling System and Hourly Production




Fig. 2.4-2 Embankment System and Hourly Production




Table 2.4-25 Actual Working Day Analysis for Earth-moving Section

Section	Sta.0+00 ~ Sta.34+80 & Access Road	Excavation	Embankment	149,000 m ³
Actual Working Day Basis				
	30 60 90 120 150 180 210 240 270 300 330 360 390 420 450			Mean Daily Product
Duration	184 days			900 m ³ /day for excavation
	unit day unit.day 1 x 184 = 184			
Excavation	34 ton Bulldozer	1 x 184 = 184		
	24 ton Bulldozer	1 x 184 = 184		
	17 ton Bulldozer	1 x 184 = 184		810 m ³ /day for embankment
	20 kg Jack hammer	8 x 10 = 80		
	7.5 m ³ /min Air compressor	2 x 10 = 20		
Main Equipment	34 ton Bulldozer	1 x 184 = 184		
	24 ton Bulldozer	1 x 184 = 184		
	17 ton Bulldozer	1 x 184 = 184		
	2.0 m ³ Dozer shovel	1 x 184 = 184		
	20 ton Dump truck	3 x 184 = 552		
	28 ton Tire roller	1 x 184 = 184		
	20 ton Tire roller	1 x 184 = 184		
	2.6 ton Vibrating roller	1 x 184 = 184		
Hauling and Embankment				

1 Volume of sound rock: 6,400 m³

Table 2.4-26 Actual Working Day Analysis for Earth-moving Section

Section	Sta. 34+20 ~ Sta. 60+78 & Coromandel I.C.	Excavation	322,000 m ³	Embankment	292,000 m ³	
Actual Working Day Basis						
Duration	30 60 90 120 150 180 210 240 270 300 330 360 390 420 450	360 days				Mean Daily Product
Main Equipment	Excavation	34 ton Bulldozer	unit day unit.day 1 x 360 = 360			
		24 ton Bulldozer	1 x 360 = 360			
		17 ton Bulldozer	1 x 360 = 360			
		20 kg Jack hammer	8 x 80 = 640			
		7.5 m ³ /min Air compressor	2 x 80 = 160			
	Hauling and Embankment	34 ton Bulldozer	1 x 360 = 360			
		24 ton Bulldozer	1 x 360 = 360			
		2.0 m ³ Dozer shovel	2 x 360 = 720			
		20 ton Dump truck	5 x 360 = 1,800			
		28 ton Tire roller	1 x 360 = 360			
20 ton Tire roller	1 x 360 = 360					
2.6 ton Vibrating roller	1 x 360 = 360					

/1 Volume of sound rock: 12,500 m³

Table 2.4-27 Actual Working Day Analysis for Earth-moving Section

Section	Sta.62+82 ~ Sta.76+13 & M1-M2 Road	Excavation	125,000 m ³	Embankment	167,000 m ³	
Actual Working Day Basis						
Duration	30 60 90 120 150 180 210 240 270 300 330 360 390 420 450	206 days				Mean Daily Product
Main Equipment	Excavation	34 ton Bulldozer	unit	1		
		24 ton Bulldozer	1			
		17 ton Bulldozer	1			
		20 kg Jack hammer	unit	8 x 22 = 176		
		7.5 m ³ /min Air compressor	2 x 22 = 44			
	Hauling and Embankment	34 ton Bulldozer	unit	1		
		24 ton Bulldozer	1			
		17 ton Bulldozer	1			
		2.0 m ³ Dozer shovel	$\frac{760}{70 \times 8 \text{ h}} = 2 \text{ unit}$			
		20 ton Dump truck	$\frac{760}{53 \times 8 \text{ h}} = 2 \text{ unit}$			
	28 ton Tire roller	1 unit				
	20 ton Tire roller	1				
	2.6 ton Vibrating roller	1				
/1 Volume of sound rock: 3,500 m ³						

Table 2.4-28 Summary of Construction Period for Box Culvert

S T A.	Dimension	Nos. of span	(Calendar day basis)
9 + 37.20	4.0 x 4.8 x 49.66	4	100
13 + 95.00	5.5 x 4.8 x 28.40	2	60
15 + 13.40	2.5 x 1.5 x 40.60	3	85
15 + 66.00	2.5 x 1.5 x 39.60	3	85
27 + 22.00	1.5 x 1.5 x 31.82	2	60
30 + 73.20	5.5 x 4.8 x 32.03	2	60
38 + 20.00	4.3 x 5.4 x 28.40	2	60
Feeder Road 2 + 65.00	4.3 x 3.0 x 17.36	1	38
Feeder Road 8 + 00	1.8 x 1.8 x 18.13	1	38
68 + 88.00	5.5 x 4.8 x 28.22	4	100

Table 2.4-29 Actual Working Day Analysis for One Span of Box Culvert

		Mean Q'ty for 1 span	Duration for 1 span (Actual Working day basis)			
			5	10	15	20
Foundation	Excavation	375.4 M3	█			
	Foundation & Leveling Concrete	14.3 M3 7.2 M3	█			
	Formwork	65.0 M2	█			
	Reinforcement	870.0 Kg	█			
	Concreting	31.0 M3		█		
Structure	Scaffolding	361.4 M3		█		
	Formwork	301.0 M2		█		
	Reinforcement	7.86 Ton		█		
	Concreting	93.3 M3			█	
	Curing & Removal of Form				█	
	total		8 days	13 days		
	Duration for 1 Box Culvert			8 days + (13days x Nos. of span)		

Table 2.4-30 Schedule Analysis of Pavement Work,
Sta.0 + 00 ~ 76 + 13




Table 2.4-31 Schedule Analysis of Pavement Work,
Phased Construction Part of Link Road




Table 2.4-32 Schedule Analysis of Pavement Work, Coromandel I.C.

Works	Daily Production	0	50	100
Preparation on subgrade	4,000 m ² /day	5		
Subbase course	1,000 m ³ /day	5		
Base course (carriage way)	1,000 m ³ /day	2		
Base course (shoulder)	500 m ³ /day	2		
Asphalt binder course	390 ton/day	5		
Asphalt wearing course & surface course	390 ton/day	6		
Others			20	
Total				45

Table 2.4-33 Schedule Analysis of Pavement Work,
Motorway Junction




Table 2.4-34 Schedule Analysis of Pavement Work,
Phased Construction Part of Motorway Junction

Works	Daily Production	0	50	100
Preparation on subgrade	4,000 m ² /day	2		
Subbase course	1,000 m ³ /day			
Base course (carriage way)	1,000 m ³ /day	2		
Base course (shoulder)	500 m ³ /day	1		
Asphalt binder course	390 ton/day	2		
Asphalt wearing course & surface course	390 ton/day	2		
Others			15	
Total				21

Table 2.4-35 Schedule Analysis of Pavement Work, Access Road

Works	Daily Production	0	50	100
Preparation on subgrade	4,000 m ² /day	4		
Subbase course	1,000 m ³ /day	4		
Base course (carriage way)	1,000 m ³ /day	4		
Base course (shoulder)	500 m ³ /day			
Asphalt binder course	390 ton/day			
Asphalt wearing course & surface course	390 ton/day	7		
Others			20	
Total				39

Table 2.4-36 Proposed Work Schedule

Bill No.	Works	The 1st Half Year					2nd					3rd					4th					5th					6th										
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
A. GENERAL ITEMS	Mobilization																																				
	DEMOLITION AND CLEARANCE																																				
	Clearance, etc.																																				
	Phased Construction Part of the Above																																				
C. EARTH WORKS	Roadway Excavation and Ancillary Works	Sta. 0+0 ~ Sta. 34+20																																			
	Phased Construction Part of the Above	Sta. 34+20 ~ Sta. 60+78 & Coromandel I.C. Sta. 62+82 ~ Sta. 76+13 & Motorway Junc.																																			
	Structure Excavation and Ancillary Works																																				
	Phased Construction Part of the Above																																				
D. STRUCTURAL CONCRETE AND ANCILLARIES	Box Culverts and Ancillary works	Sta. 9+37.2																																			
	Link Road Bridges	Sta. 13+95																																			
	G.R.N.W. Bridge (2 nr) and Ancillaries	Sta. 15+13.4																																			
	ditto	Sta. 15+60																																			
E. PAVEMENT AND ANCILLARY WORKS	Pavement, etc.	Sta. 27+82																																			
	Phased Construction Part of the Above	Sta. 30+71.2																																			
	Pipe Culverts	Sta. 38+20																																			
	Other Drainage	Sta. 68+88																																			
F. STORM DRAINAGE WORKS	Pipe Culverts																																				
	Other Drainage																																				
	Phased Construction Part of the Above																																				
	Motorway Junction																																				
	Phased Construction Part of the Above																																				
	Masonry Works																																				
	All Structures and Ancillaries																																				
	Phased Construction Part of the Above																																				
	Lighting Installations																																				
	Point aux Sable / Coromandel Interchange																																				
	Phased Construction Part of the Above																																				
	Mortorway Junction																																				
Phased Construction Part of the Above																																					
G. MASONRY WORKS	Mortorway Junction																																				
	Phased Construction Part of the Above																																				
	Link Road Bridges	A-1e Br.																																			
	G.R.N.W. Bridge (2 nr) and Ancillaries	B-1e Br.																																			
	ditto	A-1e Br.																																			
	St. Louis River Bridge (2 nr) and Ancillaries	B-1e Br.																																			
	Rampway Bridges (4 nr) and Ancillaries	Cor. Int. F-Rp. Br.																																			
	Over Bridges (5 nr) and Ancillaries	Mwy. Jun. G-Rp. Br.																																			
	Pedestrian Bridges (2 nr)	Mwy. Jun. E-Rp. Br.																																			
	Aqueduct Bridges (2 nr) and Ancillaries	Cor. Int. H-Rp. Div. Br.																																			
	Motorway Junction Bridges	A-1 Road. Ov. Br.																																			
	A-Le 1 Br.	Sta. 57 Aq.																																			
B-Le 1 Br.	Sta. 22 Aq.																																				
A-Le 2 Br.	Hi. Temple Rd. Br.																																				
A-Le 3 Br.	B.B. Ped. Br.																																				
B-Le 3 Br.	Sta. 22 Over Br.																																				
E-Ramp Br.	Coromandel Ov. Br.																																				
Ancillary Works incl. R. Wall, etc.	Pailles Ov. Br.																																				
Any other Works of Phased Construction																																					
H. LIGHTING INSTALLATIONS	Any other Works of Phased Construction																																				
	Pavement, etc.	Sta. D+00 ~ Sta. 76+13																																			
	Phased Construction Part of the Above	Coromandel I.C.																																			
	Pipe Culverts	Access Road																																			
	Other Drainage	Mwy. Junction																																			
	Phased Construction Part of the Above																																				

Table 2.4-37 Arrangement Schedule of Main Constructional Equipment

Item	Accum. Calendar Month																																						
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36			
Bulldozer 34 ton			4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	2	2												
ditto 24 ton				2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	1	1												
ditto 17 ton				4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	2	2												
Dozer Shovel 2.0m ³				3	3	3	3	3	3	3	3	3	4	4	4	4	4	4	4	4	4	4	4	4	4	2	2	2	2	2	2	2	2	2	2	2	2	2	
Dump truck 20 ton				8	8	8	8	8	8	8	8	8	8	7	7	7	7	7	7	7	7	7	7	7	7	3	3	3	3	3	3	3	3	3	3	3	3	3	
Tire Roller 28 ton				2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	4	4	4	4	4	4	4	4	4	4	4	4	4	
ditto 20 ton				2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	5	5	5	5	5	5	5	5	5	5	5	5	5	
Vibrating Roller 2.6 ton				2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	1	1												
ditto 1 ton																									2	2	2	2	2	2	2	2	2	2	2	2	2	2	
Motor Grader 3.7m																									2	2	2	2	2	2	2	2	2	2	2	2	2	2	
Macadam Roller 12 ton																									4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Water Tank Lorry 5000																									1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Asphalt Finisher 4.5m																									4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Back Hol 1.5m ³																									1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
ditto 1.0m ³																									1	1	1	1	1	1	1	1	1	1	1	1	1	1	
ditto 0.5m ³																									2	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Truck Crane 80 ton																																							
Wheel Crane 10-20 ton																																							
ditto 5-10 ton																																							
Truck 6 ton																																							
Erection Girder 35 ton																																							
ditto 50 ton																																							

3. ESTIMATE OF CONSTRUCTION COST

3.1 General

3.1.1 Bill classification

With respect to the Clause 4.3.5 Construction Quantities of Scope of Work, it is recommended that the bill classification be modified as below in order to cover the characteristics of works in more detail for both the contracts of Roadway and Bridge Sections.

- (a) General items
- (b) Demolition and clearance works
- (c) Earthworks
- (d) Structural concrete and concrete ancillaries works
- (e) Pavements and road ancillaries works
- (f) Storm drainage works
- (g) Masonry works
- (h) Lighting installations
- (i) Daywork schedules

3.1.2 Cost estimate

The cost estimate of the project stands on the basis of the price level of September, 1979 (Base Date). In connection with the consultancy service of the Clause 4.3.6 Cost Estimate Scope of Work, the following unit price analysis method is employed. The Unit Price Analysis of Work Item Sheet appended to this volume consists of:

Cost elements vertically on the analysis sheet;

- (a) Equipment cost
- (b) Labour cost
- (c) Material cost
- (d) Overhead cost, and
- (e) Profit

Elements (d) and (e) are fixed as 20% and 5% of the sum of (a) to (c) respectively for all work items.

Cost components horizontally on the sheet;

- (a) Local currency cost
- (b) Foreign currency cost, and
- (c) Taxes (to be included in local cost component)

In the cost element column, the fuel consumption cost will be shown separately to conduct the sensibility analysis of its impact on total cost by inflation or any other reason, and as for the taxes in the cost component row they will be analyzed into import duties, corporate taxes and income taxes to give the option for financial cost reduction from the amount of the construction cost by the Employer.

(1) Labour costs

The basic data is wholly obtained from local sources. The costs by categorized labour are shown in Table 3.2-6. They include allowances and fringe benefits, but exclude indirect overburdens for the performance of work, almost all of which are billed in relevant items of General Items.

(2) Equipment costs

All information is derived from the Site investigation in September of 1979. Additional information is from the effective makers of plant/equipment in Japan or other countries.

The costs are all indicated on the delivered hourly cost basis, but exclude the operator's hourly wages and allowances which are included in the labour cost element.

The results are summarized in Table 3.3-34 attached thereto and correspond well to the realistic prices of Mauritius at the Base Date.

(3) Material Costs

The material costs are shown on the basis of delivered cost to the Site. The material costs are classified into:

Imported material (e.g. cement)

Domestic products of which raw materials are imported (e.g. reinforcing steel bar)

Domestic products of which raw materials are produced locally
(e.g. aggregate)

Domestic products which consist of the above material elements
(e.g. concrete)

Imported materials are classified into several classes by their rate of import duties. Analyses of cost components for materials are made in a manner principally the same as those for Work Items. The equipment cost which relates to the manufacturing or transporting process of materials will be taken into account.

(4) Taxes

The tax components shown separately on the Analysis Sheet are corporate tax, income tax and import duties. The technical possibility to extract the 3 tax factors from the tax cost element is shown schematically in the attached figures.


3.1.3 Adjustment of construction cost

All costs are expressed in Mauritius Rupee and are based on the price level of September 1979 (Base Date). Therefore, the financial analysis for the adjustment of the estimated amount so as to correspond to the influence of price fluctuations which may, for any reason occur. By the results of Unit Price Analysis, the following variation factors will be considered.

- (a) Influences of the currency devaluation in October of 1979
- (b) Influences of annual inflation factor
- (c) Influences of the remittance of foreign contractors:

The unit price analysis is based on the assumption that the construction is performed solely by local contractors. So, the rate of contract amount of the total amount for prospective foreign contractors shall be taken into consideration and reasonable adjustment for the foreign portion will be prepared.

Fig. 3.1-1 Taxes separately shown on Cost Element Analysis



3.2 Labour Cost

3.2.1 Description

The Labour Cost means the cost of the labour element computed in the Unit Price Analysis of Work Item Sheets, which is required for the performance of a specified quantity of itemized work. The labour cost shall be shown in an appropriate classification according to the quality of labour. For the sake of convenience of analysis, each classified labour cost will be shown on an hourly cost basis.

The Labour Cost will be inclusive of hourly distributed wages, fringe benefits and expenses whatever directly or indirectly paid to the employee, but it excludes indirect overburden costs for the work performance such as labour control costs, insurances, facility costs for labourers, etc. These latter expenditures will be summed up in the overhead costs of each work item or separately in the relevant items of General Item of Bills of Quantities.

An analysis of labour cost is based on the information and data collected during Site Investigations in Mauritius in September of 1979.

Consequently, the applicable labour cost at the prospective time of construction will be forecast on the basis of the above data.

The cost will be therefore reviewed and modified, if necessary, in another part of this volume for the proposed commencement date of construction taking into consideration the cost fluctuation factors such as the annual mark-up trend inflation, etc. which are in effect after the abovementioned base date for the analyses.

At the first step of analysis, almost all of the labour cost may be deemed as a local currency cost component on the assumption that the Contract be awarded only to a local contractor(s). In this respect, an additional review for the component analysis will be made together with contractual considerations for the awarding policies.

3.2.2 Mark-up trend of basic wage

Fig. 3.2-1 derives from the analyzed data during the period 1975 to 1978 by the Builders' Association of Mauritius. From this, the mark-up trend of the basic wage for each category of labour may be approximately 6 per cent per annum, so the wage level of 1979 and thereafter can be forecast as shown respectively in parentheses. Those forecast figures will be checked reckoning with the actual mark-up trend after the base date.

3.2.3 Classification of labour and labour cost

Table 3.2-1 shows the amount of labour employed in the construction field of Sugar Millers' Estate, and their lowest and highest monthly wages both in 1977 and 1978 subject to the labour category.

In the table, the wages of 1979 are forecasted by multiplying 1.06 to the figures of 1978. Also the hourly wages are based on an assumption that the number of working days of a calendar month is 26 and working hours of a calendar day is 8.

In a same manner, the information on the wages by category for the constructional labour of the Central Government are arranged in Table 3.2-2. The wage level shown above is deemed to be inclusive of the fringe benefits.

Table 3.2-3 shows the analyzed result of labour costs depending on the governmental guided basic wage in the Notice of 1979. The cost includes fringe benefits shown in Table 3.2-4 which are based on the analysis concept by Builders' Association of Mauritius.


In the table labour is classified into seven groups based on the hourly cost level. Also the various kinds of labourer in both the Sugar Estates and Central Government discussed above are classified into relevant classes by cost level.

3.2.4 Income tax rate for labour cost

The calculation of the income tax rate against labour cost is attempted in a manner as shown in the Table 3.2-5, which is referred to "A Consolidated Version of the Labour Act 1975" and "Year of Assessment 1979-1980, Notes for the Completion of Year Return."

From these foregoing analyses the hourly labour costs and income tax component rates are concluded as in the Table 3.2-6.

Fig. 3.2-1 MARK-UP TREND OF BASIC WAGE (including COLA and end of year bonus)



[1] Source: Builders' association of Mauritius
 Analysis of standing increase, 6 Sep. 1978

Table 3.2-1 Hourly Wages by Labour Category in Sugar Millers' Estate

Category	Grade	1977 /1			1978 /1			Monthly salaries (mean)		1979		
		Nos. employed	Monthly salaries (Rs)		Nos. employed	Monthly salaries (Rs)		1977 (Rs)	1978 (Rs)	1978/1977 (mean)	Hourly wage (Rs)	Hourly wage (mean) (Rs)
			Lowest	Highest		Lowest	Highest					
Motor mechanic (automobile)	Chief	14	1,456.50	1,865.00	11	1,539.50	1,539.50	1,660.75	1,539.50	0.927	7.85	
	Superior	84	1,108.00	1,254.24	81	1,185.00	1,481.22	1,181.12	1,333.11	1.129	6.79	5.69
	I	97	983.75	1,010.30	99	1,056.75	1,056.90	997.03	1,056.83	1.060	5.39	
	II	62	777.50	777.66	78	835.50	983.84	777.58	909.67	1.170	4.64	
Welder	Chief	13	1,177.50	1,237.35	14	1,254.50	1,316.38	1,207.43	1,285.44	1.065	6.55	
	Superior	41	1,108.00	1,133.00	41	1,185.00	1,210.00	1,120.50	1,197.50	1.069	6.10	5.38
	I	50	983.75	1,034.90	46	1,056.75	1,115.00	1,009.33	1,085.88	1.076	5.53	
	II	54	777.50	880.88	69	835.00	978.90	829.19	906.95	1.094	4.62	
Carpenter	Chief	20	1,048.50	1,319.22	20	1,123.50	1,214.61	1,186.86	1,214.06	1.026	6.19	
	I	94	815.75	965.38	100	877.75	1,036.44	890.57	958.10	1.076	4.88	4.66
	II	79	749.00	749.00	91	803.00	803.14	749.00	803.07	1.072	4.09	
Driver (heavy mechanical unit)	Superior	66	899.50	1,057.42	53	998.00	1,170.00	978.46	1,084.00	1.108	5.52	
	I	96	761.00	899.34	90	840.00	965.00	830.17	902.50	1.087	4.60	4.75
	II	37	687.00	737.00	38	762.25	819.00	712.00	790.63	1.110	4.03	
Driver (lorries, vans, buses, cars, rollers, wheel tractors, light loaders)	Superior	33	844.25	1,077.35	30	927.00	998.00	960.80	962.50	1.002	4.91	
	I	942	761.00	915.88	931	840.00	906.25	838.44	873.13	1.041	4.45	4.37
	II	214	687.00	728.00	327	762.25	835.64	707.50	798.95	1.129	4.07	
Fitter	Chief	33	1,177.50	1,456.50	32	1,254.50	1,539.50	1,317.00	1,397.00	1.061	7.12	
	Superior	90	1,108.00	1,163.75	97	1,185.00	1,240.72	1,135.88	1,212.86	1.068	6.18	5.58
	I	91	983.75	1,034.90	93	1,056.75	1,121.00	1,009.33	1,086.88	1.079	5.55	
	II	104	777.50	894.50	104	835.50	962.00	836.00	898.75	1.075	4.58	

/1 Source: BI-ANNUAL DIGEST OF STATISTICS, December 1978, Ministry of Economic Planning and Development, Central Statistical Office.

Table 3.2-2 Hourly Wages by Labour Category in the Central Government

Category	Daily wages lowest (Rs)		Daily wages highest (Rs)		Hourly wages
	1977	1978	1977	1978	
Fitter	28.88	31.11	49.96	53.00	5.26
Mechanic	28.88	31.11	49.96	53.00	5.26
Carpenter	28.88	31.11	49.96	53.00	5.26
Mason	28.88	31.11	49.96	53.00	5.26
Driver	25.53	27.50	40.65	43.53	4.44
Skilled labourer	19.73	21.26	25.53	27.50	3.05
Unskilled labourer	18.88	20.26	23.50	25.30	2.85

Table 3.2-3 Analysis of Labour Cost

Category	Daily basic wage in 1978 (Rs)	Supposed daily basic wage in 1979 (1)x1.06 (Rs)	Fringe benefit in 1979 (2)x0.53 (Rs)	Daily supposed payment in 1979 (2)+(3) (Rs)	Hourly cost (4)/8 hr (Rs)	Classification		Remarks
						Class	Rounded up hourly cost (Rs)	
	(1)	(2)	(3)	(4)	(5)		(6)	
Chief forman	50.5	53.16	28.17	81.33	10.17	1	10.5	
Foreman (2nd year)	34.15	36.20	19.19	55.39	6.92			
Stone mason	31.61	33.51	17.76	51.27	6.41	2	7.0	
Loading hand artisan	30.18	31.99	16.96	48.95	6.12			
Mechanic grade 1, Driver grade 1	26.72	28.32	15.01	43.33	5.42			** Welder (5.38) ** Motor Mechanic (5.69) ** Fitter (5.58) * Fitter (5.58) * Mechanic (5.58) * Carpenter (5.58) * Mason (5.58)
Black smith, Carpenter, Mason, Painter, Plumber grade 1	26.12	27.69	14.67	42.36	5.30	3	5.5	
Bar bender grade 1	25.37	26.89	14.25	41.14	5.14			
Mechanic grade 2, Driver grade 2, Black smith, Carpenter, Mason, Painter, Plumber grade 2	22.69	24.05	12.75	36.08	4.60			** Carpenter (4.66) ** Driver, Heavy Unit (4.75) * Driver (4.71) * Driver (4.37)
Bar bender grade 2	21.72	23.02	12.20	35.22	4.40	4	5.0	
Driver (others)	19.18	20.33	10.78	31.11	3.89			* Specialized labourer (3.23)
Plant operator	19.56	20.73	10.99	31.72	3.97	5	4.0	
Skilled labourer (Semiskilled labourer)	18.88	20.01	10.61	30.62	3.83			
Unskilled labourer	15.20	16.11	8.54	24.65	3.08	6	(3.5)	
						7	3.0	* Unskilled labourer (3.02)

[1] Data for Labour Classification and Daily Basic Wage derive from the Governmental Notice No. 5 of 1979.

[2] In column "Remark", the Hourly Wages for both Sugar Millers' Estate and Central Government employees are shown as references marked by * and * respectively.

Table 3.2-4 Analysis of Ratio of Fringe Benefits for Basic Wage

	<u>Effective working hours</u>	<u>Effective pay hours</u>
Normal working hours in the year : assumed 52 weeks x 45 hours/week ;	2,340	2,340
Extra working hours : assumed 5% of the above hours ;	<u>117</u> 2,457	<u>176</u> 2,516
Less : Statutory paid leave		
Public holidays ; 20 x 8	-160	-
Annual leave ; 12 x 8	- 96	-
Sick leave		
on full pay ; 12 x 8	- 96	-
on half pay ; <u>24 x 8</u>	<u>-192</u>	<u>-96</u>
	1,889	2,420
Add :		
Severance allowance ; 15 x 8	-	120
End of year bonus ; 26 x 8	-	208
6% contribution to National Pension Fund : assumed 6% x 2,420 hours ;	<u>-</u>	<u>145</u>
	1,889	2,893

The following ratio is considered with effect from 1 July 1978;

Table 3.2-5 Analysis of Income Tax Ratio for Hourly Labour Cost

Description	Category	Local							Expa- triate
		1	2	3	4	5	6	7	
Hourly cost	(1)	10.5	7.0	5.5	4.0	3.5	3.0	3.0	45.0
Annual net income (1) x 2748 hrs	(2)	Rs 28,854	19,236	15,114	13,740	10,992	9,618	8,244	123,660
Deductions									
. Emolument relief 5% of (1), but limited to Rs5,000		Rs 1,443	962	756	687	550	481	412	5,000
. Unmarried dependent children, assume 2 in nos., Rs4,500		Rs 4,500	4,500	4,500	4,500	4,500	4,500	4,500	4,500
. Dependent relatives assume 1 in nos., Rs1,000		Rs 1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000
. Contribution to N.P.F., assume (1) x 73 hrs		Rs 767	511	402	365	292	256	219	3,285
. Medical expenses & contribution, assume 5% of (1), but limit to Rs1,500		Rs 1,443	962	756	687	550	481	412	1,500
. Provision for retire- mentannuities, 10% of (1), but limit to Rs5,000		Rs 2,885	1,924	1,511	1,374	1,099	962	824	5,000
. Relief for Life insurance premiums, 3.3%, but limit to Rs5,000		Rs 952	535	499	453	363	317	272	1,000
Total of deduction	(3)	Rs 12,990	10,394	9,424	9,066	8,354	7,997	7,639	21,285
Chargeable income	(4)	Rs 15,864	8,842	5,690	4,674	2,638	1,621	605	102,375
Tax payable									
5% of first Rs5,000		Rs 250	250	250	234	132	81	30	
10% of next Rs5,000		Rs 500	384	69					
20% of next Rs10,000		Rs 1,173							
Total of tax payable	(5)	Rs 1,923	634	319	234	132	81	30	41,281
Taxation ratio (5)/(2)		6.6	3.3	2.1	1.7	1.2	0.8	0.4	33.3

Table 3.2-6 Cost Component of Hourly Labour Cost

Category	Hourly labour cost (Rs)	Component		
		Local (Rs)	Foreign (Rs)	Tax (Rs)
Local				
Class 1	10.5	100% 10.5	0	7% 0.7
Class 2	7.0	100% 7.0	0	3% 0.2
Class 3	5.5	100% 5.5	0	2% 0.1
Class 4	5.0	100% 5.0	0	2% 0.1
Class 5	4.0	100% 4.0	0	0
Class 6	3.5	100% 3.5	0	0
Class 7	3.0	100% 3.0	0	0
Expatriate	45.0	47% 21.0	53% 24.0	33% 14.9

/1 Local component includes taxes.

3.3 Equipment Cost

3.3.1 Descriptions

The Equipment Cost means the cost of equipment element put into the Unit Price Analysis Sheet, which is required for the performance of specified quantity of itemized work. The cost will be analyzed on an hourly cost basis on assumptions that the equipment is delivered on to Site and ready for normal operations.

3.3.2 Current hourly cost of main construction equipment

The Table 3.3-1 shows the prevailing hourly use rate of main construction equipment at the base date i.e. September of 1979, which are obtained from the interviews with local contractors and the analyses of tender documents of previously executed projects in Mauritius.

In the table, it is noted that the mark-up trend of hourly costs between 1977 to 1979 is approximately 20-30 per cent. The tendency gives an index to the estimate of cost of construction equipment for the Works.

3.3.3 CIF Port Louis value of imported construction equipment

The Table 3.3-2 shows the CIF values at Port Louis in September 1979 of heavy equipment, which are quoted by a major Japanese construction machine maker. The relationship between the delivered price in Japan and FOB value in Japan, or the rate of insurances/freight costs against the FOB value in Japan may be useful for the estimation of CIF value in Port Louis of general equipment.

So far as limited in the table, the CIF value goes 10 to 20 per cent higher than the FOB value in Japan, and the freight/insurance cost accounts for approximately 20 per cent of the FOB value in Japan. By comparing the CIF value at Port Louis with the delivered price in Japan for each item, the rate of increase becomes approximately 10 per cent. The trial calculation of hourly costs of main equipment which may be imported from Japan coincide with the prevailing cost levels in Mauritius shown in the Table 3.3-1.