


Outline of Construction Procedure



7-07 QUALITY CONTROL

Frequency of quality control of works shall be performed as shown in the following table.

Construction Control of Sand Compaction Pile Method

Item of Control	Control Method	Frequency of Control
Pile materials	Mechanical analysis	1time/50m ³
Location of piling	Topo-survey to set up pile	each pile
Depth of piling	Apoint marked on a casing	each pile
Quantity of pile material to be filled in	Bucket	each compaction
Strength of pile	Standard penetration test	1time/30 piles, depth of every 1m
Strength of original ground	Unconfimed Compression test	1time/30 piles, thin wall sampling

PART 8 IMPROVEMENT WORKS OF FOUNDATION BY SOIL CEMENT
COLUMN METHOD

8-01 GENERAL

After the field experimental construction mentioned in the clause 6-03, the improvement works of foundation by soil cement column method shall be carried out at the location as shown in the drawings.

8-02 WORK QUANTITY

The quantity of the works shall be as follows except for the variation order from the Inspection Committee.

Quantity of work by Soil Cement Column

Position	Excavation Length	Column Length	Number of Column	Total Excavation Length	Total Column Length
Upper part	6.89 ^m	5.50 ^m	53 columns	365.17 ^m	291.50 ^m
Lower part	17.92	13.79	70	1,254.40	965.30
Total			123 columns	1,619.57 ^m	1,256.80 ^m

8-03 DIAMETER OF MIXING COLUMN

The diameter of mixing column shall be 1.0 meter.

8-04 CEMENT MATERIAL

Improvement material shall be cement slurry made of ordinary Portland cement with a specific gravity of 3.15. Water content ratio (W/C) shall be 100% in weight ratio.

8-05 VOLUME OF CEMENT

For 1.00 m³ of original clay, 198 liter of improvement materials equivalent to 150 Kg of ordinary portland cement shall be used, however the precise amount shall be decided based on the actual data obtained from mixing tests in a laboratory before the construction.

8-06 CONSTRUCTION EQUIPMENT


The construction equipment shall be based upon the following class. The Contractor shall submit his list of construction equipment with the same manner in accordance with the clause 7-05 of this technical specifications.

Name	Standard Specification	unit	Nos.	Remarks
Base Machine	Crawler crane, 35 ^t class	Nos.	1	
Leader	Mixing machine guide	Set.	1	
Earth Auger with Attachment	D-60k class	Nos.	1	
Mixing Rod	φ 200 ^m / _m	'	1	Lmax = 25m
Mixing Vane	φ 1000 ^m / _m , double type	'	1	
Auger Head	φ 600 ^m / _m	'	1	
Generator	125KVA class	Nos.	1	for Earth Auger
Mixer	750ℓx2 class	'	1	
Grouting Pump	150ℓ/min	'	1	
Water Tank	2m ³	'	1	
Submergible Motor Pump	2inches	'	1	

8-07 PROCEDURE OF CONSTRUCTION

The procedure of the construction shall be conformed to the following flow chart. In case of other construction procedures, the same formalities shall be needed in accordance with the specifications described in the clause 7-06.

Outline of Construction Procedure



8-08 QUALITY CONTROL

(a) With regard to the construction of soil cement column, the Contractor shall pay special attention to the following points.

- To control quantity of cement slurry, penetration and extraction velocities of mixing rod shall be checked strictly so as to supply cement slurry to each depth precisely.
- To maintain perpendicularity of the mixing rod.
- To grasp the capacity of a agitating mixer and to set its control standard for rate of rotation, agitating torque, up- down speed of agitating, etc.
- Safety of base machine should be well considered so as not to lower the work efficiency for the construction being carried out on the soft soil foundation.

(b) The Contractor shall perform the following control at the construction period.

- Concentration and amount of cement slurry to be injected
- Mix proportion of slurry shall be 1:1 for water and cement in weight ratio.
- The specific gravity of slurry shall be controlled using control charts and it's measurement frequency shall be once in the morning and in the afternoon.
- Amount of cement to be injected shall be 150kg/m^3 per 1m^3 of original clay.
- Perpendicular construction speed for penetration and

extraction of soil cement column shall be 1.5 meter per minutes respectively.

- The speed of a rod up and down shall be set at 1.5 meter per minutes each, at the same time the construction speed shall be controlled by the use of marks made on the rod and staff.
- The rate of rotation of agitating vane shall be gained by eye-measurement.
- Vertical and horizontal inclination of the leader shall be measured by a theodolite.
- In order to check the strength of constructed soil cement columns, unconfined compression test and measurement of unit weight shall be carried out using samples taken by core boring the rates of one column to 30 columns. Sampling of cores shall be done for every 1 meter's depth.

8-09 MIXING TEST IN LABOLATORY

- (a) For the determination of the amount of cement slurry to confirm the designed strength, 2.9 Kg/cm^2 , mixing test of cement slurry shall be performed.
- (b) The standard specifications for the mixing test in a laboratory shall be as follows.

The Standard Specifications for the Mixing Test

Item	Standard Specificatins
Kind of material for improvement	Ordinary portland cement
Water-cement ratio(%)	100
Amount of cement to be mixed (kg/m ³)	100, 150 and 200
Mixing time required (min)	10
Age (days)	7, 14 and 28
Molding size	φ 5cm height 10cm
Number of mold for one sample (Nos.)	2

(c) Testing items of the mixing test in a laboratory shall be as follows.

-Test for physical property

- Unit weight : 3 samples according to 3 kinds of mixture, 100Kg/1m³, 150Kg/1m³, 200Kg/1m³.

-Test for mechanical property

- Unconfined compression test : 18 samples according to each mold

PART 9 IMPROVEMENT WORKS OF FOUNDATION BY GRAVEL
COMPACTION PILE METHOD

9-01 GENERAL

Implementation of the construction by this work method shall be decided in accordance with the results of field experimental construction described in the PART 6 of this specifications after comparing with the result of sand compaction pile method.

9-02 STANDARD OF PILE

The size of gravel compaction piles shall be decided by the field experimental construction, however the guideline is as follows.

Length of penetration; 7.88 meter

Improved length ; 5.00 meter

Improved diameter ; 0.50 meter

9-03 CONSTRUCTION EQUIPMENT

The construction equipment shall be same with the case of the sand compaction pile method mentioned the part 7 in this specifications.

9-04 CONSTRUCTION CONTROL

The method of construction control shall be same with the clause 7-07 of Part 7 in this specifications.

PART 10 OTHER RELATED CONSTRUCTION WORKS

10-01 GENERAL

The construction of model infrastructure improvement works include, under this Contract, miscellaneous works besides main earth work and foundation improvement works such as installation of displacement piles, installation of wooden staging for observation, protection work of measurement instruments and cable, and movement works of existing houses. The majority of the miscellaneous works shall be either small concrete structure or wooden works, which shall be constructed by means of the combination of earth works, concrete works and wooden works. From the view point stated above, the specifications contained in this part describes mainly special conditions for each work.

10-02 DISPLACEMENT AND FIXED PEGS

The Contractor shall install reinforced concrete pegs for fixed points of measurement and wooden pegs for displacement observation. The scale shall be as follows

-Reinforced concrete peg with a nail screw: 8 Nos

Size : 20" x 20" x 100"

Wooden pegs with a nail : 133 Nos

Size : 10" x 10" x 100"

10-03 WOODEN STAGING

The Contractor shall construct the following wooden staging to walk for the observation of the testing canal facility.

Material : wooden plate and pegs

Construction length : 230 m

Width of wooden plate : 50 cm

Mean height of staging : 30cm

10-04 PROTECTION WORKS

The Contractor shall perform in the protection works such as concrete pipe works for monitoring cable under the temporary construction road, installation of colour flags on the cable line and installation of bamboo protector for monitoring instruments, etc.

10-05 MOVEMENT OF EXISTING HOUSE

The Contractor shall move the following two existing houses to the designated places.

One wooden two stories house, 192m²

One wooden two stories house, 28m²


10-06 OTHERS

The monitoring instruments shall be procured by JICA and the installation works shall be carried out by the supplier of JICA under the specifications and instructions of manufacturers or Inspection Committee.


The Contractor shall maintain all monitoring instruments

installed at the job site during construction period and the cost shall be included in the item of temporary works as indicated in the Bill of Quantities.


CHAPTER 9 ATTACHED DRAWINGS




SECTION (A)-(A) S=1:300




SECTION (B)-(B) S=1:300



TYPICAL SECTION OF DRAINAGE DITCH S=1:100



TYPICAL SECTION OF COFFER DAM S=1:100




ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT


GENERAL PLAN OF
TESTING CANAL FACILITY

JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO


DWG. NO. 1




STA. X 6





STA. X 7



STA. X7+20



STA. X8+80




ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT

CROSS SECTIONS OF TESTING
CANAL FACILITY (1/2)


JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO

ENC. NO.
2


STA. X2





STA. X3+20



STA. X4



STA. X5





ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

CROSS SECTIONS OF TESTING
 CANAL FACILITY (2/2)

JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

DWG. NO.
 3


PLAN S=1:200




ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

PILE ARRANGEMENT
 FOR FOUNDATION IMPROVEMENT WORK


JAPAN INTERNATIONAL COOPERATION AGENCY Dwg. No.
 TOKYO 4




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6



PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6



PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6




PILE LENGTH	COMPACTION PILE LENGTH	ELEVATION OF BOTTOM OF PILE	NON-TREATMENT PILE LENGTH	ELEVATION OF TOP OF PILE	GROUND ELEVATION	STATION
						X1
						X2
						X3
						X4
						X5
						X6

ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

PROFILES OF SOIL CEMENT COLUMNS

JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

DWG. NO.
 6




PLAN

ITEM AND QUANTITIES OF IN-SITU TESTS FOR THE EXPERIMENTAL CONSTRUCTION


Item of Test	Sand Compaction Pile	Gravel Compaction Pile	Soil Cement Column
Standard penetration test (Inside the piles)	*Location :Center of pile, 1 hole *Boring depth :7 m *Number of test:7 times (Depth:every 1 m)	Same as the left	-
Core boring (Inside the piles)	-	-	*Location:Center of pile, 1 hole *Boring depth:6 m *Core sampling: 6 samples (Depth:every 1 m)
Thin wall sampling (Clay of original ground)	*Location:Center between pile and pile, 1 hole *Boring depth:7 m *Core sampling:4 sample *Sampling depth: -1,-3,-5,6-7 m	Same as the left	-
Field density test	*Location:Center of pile, 2 holes *Number of tests:2 time	Same as the left	-

ITEMS AND QUANTITIES OF LABORATORY TESTS FOR THE EXPERIMENTAL CONSTRUCTION


Item of Test	Sand Compaction Pile	Gravel Compaction Pile	Soil Cement Column
Test of physical property *Natural moisture ratio *Wet density	*Pile material:2samples *Clay :7samples *Clay :4samples	*Pile material:2samples *Clay :7samples *Clay :4samples	-
Mechanical test *Unconfined compression test	*Clay :4samples	*Clay :4samples	*Pile :6samples



Sand Compaction Piles



Gravel Compaction Piles




Soil Cement Columns

ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT

EXPERIMENTAL CONSTRUCTION FOR
FOUNDATION IMPROVEMENT WORKS


JAPAN INTERNATIONAL COOPERATION AGENCY DISC. NO.
TOKYO 7




LEGEND

- Extensometer
- Inclinator
- Settlement Gauge
- Piezometer
- Displacement Pile
- Fixed Point


PLAN FOR ARRANGEMENT OF MONITORING INSTRUMENT
S = 1 : 500




INCLINOMETER
(Aut Measuring)




INCLINOMETER
(Manual Reading)



PIEZOMETER



SETTLEMENT GAUGE




FIXED POINT


ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT.

**INSTALLATION PLAN AND
INSTALLATION METHOD OF
MONITORING INSTRUMENT**


JAPAN INTERNATIONAL COOPERATION AGENCY DNO. NO.
TOKYO 8




Non-treatment Slope for Short Term Slope Stability (1:4)



Non-treatment Slope for Long Term Slope Stability (1:6)



Improved Slope by Sand Compaction Piles (1:4)



Improved Slope by Soil Cement Columns (1:3)

LEGEND

- +—+—+— Settlement gauge
- *—*—*—*— Inclinator
- Piezometer
- |—|—|— Extensometer


ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT

ARRANGEMENT OF MONITORING
INSTRUMENT ON EACH SLOPE


JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO

DWG. NO.
9

SECTION A-A




PLAN




ROYAL IRRIGATION DEPARTMENT THE MOOL INFRASTRUCTURE PROJECT OF SOFT SOIL FOUNDATION FOR THE IRRIGATION ENGINEERING CENTER PROJECT	
(REFERENCE DRAWING) GEOLOGICAL PROFILE OF PROJECT SITE (1/2)	
JAPAN INTERNATIONAL COOPERATION AGENCY TOKYO	DRG. NO. 10

SECTION B-B



PLAN





ROYAL IRRIGATION DEPARTMENT
 THE HOLOGE INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT


(REFERENCE DRAWING)
 GEOLOGICAL PROFILE OF
 PROJECT SITE (2/2)

JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

DATE: 11



TYPICAL CROSS SECTION OF ACCESS ROAD



SCALE 1:500

ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

(REFERENCE DRAWING)
 PLAN OF TEMPORARY WORK

JAPAN INTERNATIONAL COOPERATION AGENCY DWO. NO. 12
 TOKYO

ATTACHED DATA AVAILABLE

1. Member of Detailed Design Team
2. List of Personnel Concerned
3. Results of In-situ and Laboratory Tests
4. Basic Plan

1. Member of Detail Design Team

Name	Assignment	Position
Mr. Noritada KAWAGUCHI	Leader	Chief; 1st Lab. Construction, National Research Institute of Agricultural Engineering, MAAF
Mr. Noriharu USUKI	Coordinator	Deputy Head; Agricultural Development Div. Agricultural Development Cooperation Dept., JICA
Mr. Hirotaka OCHI	Soft Soil Foundation Planning	Technical Adviser; Overseas Engineering Dept., Japan Irrigation & Reclamation Consultants Co., Ltd. (JIRCO)
Mr. Yoichiro GOMYO	Drainage Designing	Chief of Second Div., Overseas Engineering Dept., Japan Irrigation & Reclamation Consultants Co., Ltd. (JIRCO)
Mr. Takahiko TATEISHI	Adviser of Consultant firm	Deputy Chief of System Development Section, Nippon Giken Inc.

2. List of Personnel Concerned

LIST OF PERSONNEL CONCERNED

Royal Irrigation Department

Mr. Suha Thanomsingha Director General of
Royal Irrigation Department

The Advisory Committee

Mr. Choompon Chaveesuk Director of Engineering
Development Division,
Chairman

Mr. Lumsak Tejasen Director of Research and
Laboratory Division,
Member

Mr. Nipon Saihom Director of Geo-Technic
Division,
Member

Mr. Roongrueng Chulajata Director of Large Project
Construction Division,
Member

Dr. Boonyok Vadhanaphuti Director of Project Planning
Division,
Member

Mr. Skulwattana Director of Irrigation
Chantharabol Regional Office 10,
Member

Mr. Vichai Srivaraponse Project Manager of Mae Klong
Yai,
Member

Mr. Kanob Tingsombutyut Technical Inspector Section,
Member and Secretary

The Implementation and Coordinating Working Committee

Mr. Ruangrit Ammawat Deputy Director of Engineering
Development Division,
Chairman

Dr. Supol Chirapan Chief of Special Engineering,
Chairman Assistant

Dr. Siripong Hungsapruk Chief of Criteria Development,
Member

Mr. Montien Kangsasitien	Chief of Soil Engineering Laboratory Section, Member
Mr. Sanan Sirior	Chief of Irrigation Design in South Part Section, Member
Mr. Phonpong Kararum	Chief of Irrigation Design Work 10, Member
Mr. Sawat Naipramot	Chief of Saline Water Protection, Mae Klong Yai Project, Member
Dr. Thanu Harnpatanapanich	Secretary and Member
Mr. Sanit Natidhamakun	Technical for Operation & Maintenance Project, Member

Irrigation Engineering Center (IEC)

Mr. Charuk Nonthatham	Director of IEC
Mr. Suthi Songvoravit	Deputy Director of IEC

Embassy of Japan

Mr. Katsutoshi Nagayama	First Secretary
-------------------------	-----------------

JICA Thailand Office

Mr. Ben Saito	Resident Representative
Mr. Takahito Hino	Assistant President Representat

Japanese Expert of Irrigation Engineering Center Project

Mr. Kazushige Matsuo	Team Leader of IEC Project
Mr. Takuji Nakano	Expert of Design Criteria
Mr. Hitoshi Sunazawa	Expert of Construction Material and Analysis
Mr. Masaru Sasaki	Expert of Hydraulic Model
Mr. Haruoki Ebe	Expert of System Development
Mr. Youji Ebihara	Coordinator

Colombo Plan Expert

Mr. Hiroshi Kudou

Mr. Narumi Ymada

Mr. Yuji Ozaki

Royal Irrigation Department

Royal Irrigation Department

Royal Irrigation Department

STS Engineering Consultants Co., Ltd

Mr. Veera Vasinvarthana Technical Manager

Mr. Choochart Project Engineer

Kietkajo

3. Results of In-situ and Laboratory Tests

SUMMARY OF TEST RESULTS

STS ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT		Model Infrastructure Project		LOCATION		Charoenraj Pumping Station, Bang Bo, Samut Prakan Province										
DATE	16/1/88	BORING No.	B-1.FV-1	JOB No.	1433	BY	CK									
DEPTH		ATTENBERG LIMIT %		SIEVE ANALYSIS % FINER		UNDRAINED SHEAR STRENGTH v_{um}			SPECIFIC GRAVITY, G							
SAMPLE No.	M.															
	FROM	TO	LL	PL	SL	WET UNIT WEIGHT γ_{wet}	No. 3/8"	No. 10	No. 40	No. 200	FIELD VANE SHEAR	POCKET PENETRATION $1/4 Q_p$				
						Su	Su'	Suv	Sub							
PST-1	1.00	1.80	83.2	94.6	35.3	14.4	1.47				1.63	0.21	1.74	0.89	1.25	2.66
PST-2	3.00	3.80	85.2				1.47				0.96	0.29	1.18	0.40	2.5	2.65
PST-3	5.00	5.80	84.9	90.8	35.8	10.2	1.47				1.24	0.37	0.75	4.16	2.5	2.68
PST-4	7.00	7.80	89.7				1.44				1.67	0.49	0.99	5.09	2.5	2.65
PST-5	9.00	9.80	95.8	105.7	40.3		1.40				1.95	0.59	1.08	7.10	2.5	2.63
PST-6	11.00	11.80	98.1				1.41				2.38	0.55	1.27	8.94	3.75	2.65
PST-7	13.30	14.10	94.7	119.0	41.6		1.43				2.99	0.78	1.18	13.73	5.0	2.68
PST-8	15.00	15.80	70.9				1.54				4.65	1.30	3.70	10.13	5.0	2.67

(1) (6) (2)

SJS ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT Model Infrastructure Project		LOCATION Chareonraj Pumping Station, Bang Bo, Samut Prakan Province		JOB No. 1488		BORING No. B-2, FV-2		DATE 29/1/88		BY CK		OBSERVED W.L. -0.25 m.								
SAMPLE No.	DEPTH M.		WATER CONTENT %		ATTERBERG LIMIT %			WET UNIT WEIGHT γ_{wet}	SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH γ_{m^2}					SPECIFIC GRAVITY, G	
	FROM	TO	LL	PL	SL	No. 1/8"	No. 4	No. 10	No. 40	No. 100	S _u	S _{u'}		S _{uv}	S _{uh}	POCKET PENETRATION				
PST-1	1.00	1.80	87.5	32.6	20.8			1.49						CH	0.92	0.31	0.90	1.03	1.25	2.65
PST-2	1.95	2.75												CH	1.79	0.31	2.63	-3.35	-	
PST-3	2.80	3.50												CH	0.96	0.23	0.47	3.85	-	
PST-4	4.00	4.80												CH	1.00	0.35	0.56	3.57	1.25	
PST-5	5.00	5.80	92.6	34.9	17.5			1.43						CH	1.28	0.41	1.13	2.16	1.25	2.67
PST-6	6.00	6.80												CH	1.28	0.43	0.80	4.13	2.5	
PST-7	7.00	7.80	87.8					1.45						CH	1.30	0.43	0.80	4.28	2.5	2.66
PST-8	8.10	8.90												CH	1.65	0.53	1.22	4.14	2.5	
PST-9	9.10	9.90	97.2	107.4	36.8			1.45						CH	1.67	0.63	1.18	4.56	2.5	2.65
PST-10	10.10	10.90												CH	2.08	0.72	0.99	8.51	2.5	
PST-11	11.00	11.80	102.5					1.43						CH	2.50	0.68	1.93	5.83	3.75	2.65
PST-12	12.20	13.00												CH	2.68	0.82	1.98	6.82	5.0	
PST-13	13.00	13.80												CH	3.05	0.78	2.03	9.07	5.0	
PST-14	14.00	14.80	88.9	112.4	42.3			1.45						CH	3.45	0.96	1.87	12.79	5.0	2.64
PST-15	15.00	15.80												CH	3.75	1.08	2.90	8.73	5.0	

STS ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT		Model Infrastructure Project		LOCATION		Chareonraj Pumping Station, Bang Bo, Samut Prakan Province																
DATE	29/1/88	BORING No.	B-3, FV-3	JO# No.	1488	BY	CK															
							OBSERVED W.L. +0.45 m.															
SAMPLE No.	DEPTH M.		WATER CONTENT %			ATTERBERG LIMIT %			WEIGHT UNIT WEIGHT γ_s			SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH γ_{vm}^2				POCKET PENETRATION	SPECIFIC GRAVITY, G
	FROM	TO	%	LL	PL	SL	No. 1/4"	No. 10	No. 40	No. 200	Su	Su'	Suv	Sh	Su		Su'	Suv	Sh			
PST-1	1.00	1.80	94.2	92.5	34.4	18.6	1.44				CH	0.96	0.23	0.99	0.75	1.25	1.25	2.65				
PST-2	2.00	2.80									CH	0.88	0.23	0.61	2.44	1.25						
PST-3	3.00	3.80									CH	1.06	0.29	0.52	4.29	2.5						
PST-4	4.00	4.80									CH	1.16	0.41	0.66	4.14	2.5						
PST-5	5.00	5.80	90.3	86.2	35.5	22.7	1.47				CH	1.16	0.37	0.52	4.98	1.25	2.65					
PST-6	6.00	6.80									CH	1.41	0.41	0.89	4.42	1.25						
PST-7	7.00	7.80									CH	1.71	0.49	1.55	2.58	2.5						
PST-8	8.00	8.80									CH	1.83	0.51	1.27	5.12	2.5						
PST-9	9.00	9.80	98.4	109.	38.2		1.44				CH	2.38	0.68	1.93	4.98	2.5	2.70					
PST-10	10.00	10.80									CH	2.58	0.59	2.17	4.98	2.5						
PST-11	11.00	11.80									CH	2.74	0.80	1.79	8.40	3.75						
PST-12	12.00	12.80									CH	2.74	0.55	1.04	12.90	3.75						
PST-13	13.00	13.80	92.3	119.8	42.1		1.44				CH	3.35	0.86	2.30	9.52	3.75	2.65					
PST-14	13.90	14.70									CH	4.25	1.08	3.40	9.21	3.75						
PST-15	15.00	15.60									CH	4.45	1.20	3.40	10.65	5.0						

SP/

15

15

7/5

777

SUMMARY OF TEST RESULTS

PROJECT Model Infrastructure Project		BORING No. B-4, EV-4		JOB No. 1488		BY CK		OBSERVED W.L. -0.20 m.											
DATE 8/3/88		LOCATION Chaeonraj Pumping Station, Bang Bo, Samut Prakan Province.		CLASSIFICATION		UNDRAINED SHEAR STRENGTH σ_{vm}		FIELD VANE SHEAR		POCKET PENETRATION		SPECIFIC GRAVITY, G							
SAMPLE No.	DEPTH M.		WATER CONTENT %		ATTERBERG LIMIT %		WET UNIT WEIGHT γ_w		SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR	FIELD VANE SHEAR	POCKET PENETRATION	SPECIFIC GRAVITY, G		
	FROM	TO	LL	PL	SL	No. 3/8"	No. 4	No. 10	No. 40	No. 75	S_u	$S_{u'}$						S_u	$S_{u'}$
PST-1	1.00	1.80	66.4	36.3	21.8	1.35								0.69	0.12	0.88	-0.41	1.25	2.67
	2.50													0.77	0.16				
PST-2	2.96	3.76	79.4	33.2	19.6	1.52							0.8	**	**			1.25	2.68
	3.66													0.06	0.10				
PST-3	5.00	5.80	73.8	33.9		1.65								0.85	0.22	1.02	-0.14		
	6.20													0.85	0.16			1.25	2.65
	7.00													0.54	0.26	0.09	3.19		
PST-4	6.99	7.79	85.3	31.5		1.50							0.7	1.09	0.36	1.11	0.97	2.5	2.65
	7.80													1.11	0.18				
	9.00													1.19	0.39				
PST-5	9.00	9.80												1.29	0.40	0.92	3.47	2.5	
	9.80													1.49	0.26				
PST-6	11.00	11.80	96.2			1.45							1.2	1.94	0.31			2.5	
	12.83													2.20	0.34	0.65	11.51		
PST-7	13.05	13.85																3.75	
	14.41													2.4	0.46	2.59	1.25		
PST-8	15.02	15.82	74.3			1.57							2.5					5.0	

552
553
10
10
573

SYSTEMS ENGINEERING
SUMMARY OF TEST RESULTS

PROJECT Model Infrastructure Project
 DATE 29/1/88
 BORING No. EV-5
 JOB No. 1488
 LOCATION Chareonraj Pumping Station, Bang Bo, Samut Prakan Province
 BY CK OBSERVED W.L. +0.42 m.

SAMPLE No.	DEPTH		WATER CONTENT %	ATTERBERG LIMIT %			WET UNIT WEIGHT γ_w	SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH σ_{vm}				SPECIFIC GRAVITY, G			
	M.	TO		LL	PL	PI		No. 3/8"	No. 4	No. 10	No. 40		No. 75 μ	FIELD VANE SHEAR						
														Su	S _{u1}	S _{uv}		S _{uh}	S _u	S _{u1}
		1.50												0.68	0.18	0.38	2.44			
		3.50												0.96	0.23	0.56	3.29			
		5.50												1.34	0.37	1.02	2.86			
		7.50												1.93	0.51	1.79	2.72			
		9.50												2.22	0.41	1.04	9.22			
		11.50												2.58	0.55	1.60	8.37			
		12.50												3.45	0.96	2.20	10.8			
		15.50												4.45	1.16	3.76	8.39			

STSENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT		Model Infrastructure Project		LOCATION		Chareonraj Pumping Station, Bang Bo, Samut Prakan Province														
DATE		14/3/88		JOB No.		1488														
BORING No.		B-5, PV-5		BY		CK														
OBSERVED W.L.		-0.40 m.																		
SAMPLE No.	DEPTH M.		WATER CONTENT %		ATTERBERG LIMIT %			WET UNIT WEIGHT t/m ³	SIEVE ANALYSIS % FINER					CLASSIFICATION	UNDRAINED SHEAR STRENGTH t/m ²					SPECIFIC GRAVITY, G
	FROM	TO	LL	PL	SL	No. 3/8"	No. 4		No. 10	No. 40	No. 100	S _u	S _{uv}		S _{uh}	POCKET 1/2 Q _u	GRAVITY, G			
PST-1	1.00	1.80	66.8	85.0	33.3	19.3	1.57							CH	0.54	0.26	0.46	0.97	1.25	2.64
PST-2	2.00	2.80	77.5	82.8	31.7									CH	0.69	0.16			1.25	
PST-3	3.00	3.80	93.0	95.5	36.2	21.9	1.44							CH	0.77	0.30	1.02	-0.69	1.25	2.65
PST-4	4.00	4.80	82.6	96.5	36.0									CH	0.85	0.16			-	
PST-5	5.00	5.80	90.0	97.0	36.6		1.46							CH	0.79	0.26	0.65	1.67	1.25	2.66
PST-6	6.00	6.80	88.2	98.5	35.5									CH	0.99	0.24			1.25	
PST-7	7.00	7.80	85.4	94.4	35.8		1.50							CH	1.13	0.26	0.97	2.08	2.5	2.65
PST-8	8.00	8.80	84.9	95.0	35.2									CH	1.19	0.26			2.5	
PST-9	9.00	9.80	93.1	116.4	38.9		1.45							CH	1.33	0.30	1.57	-0.12	2.5	2.63
PST-10	10.00	10.80	91.0	110.6	36.4									CH	1.49	0.42			3.75	
PST-11	11.00	11.80	98.8	119.5	41.8		1.40							CH	1.86	0.36	2.13	0.28	3.75	2.65
PST-12	12.00	12.80	94.2	123.9	41.0									CH	2.12	0.44			3.75	
PST-13	13.00	13.80	100.2	115.6	42.2		1.42							CH	2.32	0.57	1.76	5.69	3.75	2.64
PST-14	14.00	14.80	93.5	122.9	39.4									CH	2.71	0.61			5.0	
PST-15	15.00	15.80	79.2	110.4	38.0		1.50							CH	2.83	0.58	2.03	7.63	5.0	2.68
PST-16	16.00	16.80	87.5	116.5	36.2									CH					6.25	
PST-17	17.00	17.80	70.9	91.1	34.9		1.58							CH					7.5	2.69


LOG OF BORING

LOG OF BORING No. B-1, FV-1

PROJECT NAME. Model Infrastructure

LOCATION. Samut Prakan

OWNER



WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.D.
WL.	B.C.R. A.C.R.
WL.	+ 0.68 m. 24 HRS. AFTER BORING.

STS.
 Engineering Consultants Co., Ltd.
 BANGKOK.

BORING STARTED. 12/1/88	
BORING COMPLETED. 13/1/88	
RIG. Acker	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JOB No. 1408	SHEET. 1/1

LOG OF BORING No. B-2, FV-2

PROJECT NAME. Model Infrastructure LOCATION. Samut Prakan

OWNER

DEPTH, M.	SAMPLE No.	TYPE OF SAMPLE	SAMPLE DIST. RECOVERY	DESCRIPTION OF MATERIAL	○ Natural Water Content x Plastic Limit Δ Liquid Limit (%)		○ Qu/2 ● Qu/2 Δ QV ▲ QV' X Qp/2 (t/m ²) 2.5 5 7.5 10 □ SPT, R (Blow/ft)												
							20	40	60	80									
0																			
1	PST			CLAY some shell fragment															
2	PST			and organic matter, dark grey,															
3	PST			very soft to soft.															
4	PST			(CH)															
5	PST																		
6	PST																		
7	PST																		
8	PST																		
9	PST																		
10	PST																		
11	PST				12.0 m.														
12	PST			CLAY some shell fragment,															
13	PST			greenish grey, medium stiff,															
14	PST			(CH)	15.8 m.														
				↑ END OF BORING															
20																			

WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.D.
WL.	B.C.R. A.C.R.
WL.	-0.25 m. 24 HRS. AFTER
	BORING.


STS.
 Engineering Consultants Co., Ltd.
BANGKOK.

BORING STARTED. 23/1/00	
BORING COMPLETED. 24/1/00	
RIG, Acker	FOREMAN, SK
DRAWN. SRY	APPROVED. CK
JCB No. 14118	SHEET. 1/1

LOG OF BORING No. B-3, FV-3

PROJECT NAME. Model Infrastructure LOCATION. Samut Prakan

OWNER



WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.O.
WL.	B.C.R. A.C.R.
WL.	+0.45 m 24 HRS. AFTER BORING.

STS.
Engineering Consultants Co., Ltd.
BANGKOK.

BORING STARTED. 17/1/88	
BORING COMPLETED. 19/1/88	
RIG.	ACKER
DRAWN.	SRV
JOB No.	14888
FOREMAN.	SK
APPROVED.	CK
SHEET.	1/1

LOG OF BORING No. B-4, FV-4

PROJECT NAME. Model Infrastructure LOCATION. Samut Prakan

OWNER

DEPTH, M.	SAMPLE No.	TYPE OF SAMPLE	SAMPLE - DIST. RECOVERY.	DESCRIPTION OF MATERIAL	O Natural Water Content x Plastic Limit Δ Liquid Limit (%)			
					○ Ou/2	● Ou/2	Δ Qv	▲ Qv
0					X Op/2 (t/m ²) 2.5 5 7.5 10 □ SPT, N (Blow/ft) 20 40 60 80			
1		PST		CLAY some shell fragment and organic matter, dark grey, very soft to soft.	X	○	Δ	▲
2		PST		(CH)	X	○	Δ	▲
3		PST			X	○	Δ	▲
4		PST			X	○	Δ	▲
5		PST						
6		PST						
7		PST		CLAY some shell fragment, greenish grey, medium stiff.				
8		PST		(CH)				
				END OF BORING				

WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.D
WL.	B.C.R. A.C.R.
WL.	-0.2 m 24 HRS. AFTER
BORING.	

STS.
 Engineering Consultants Co., Ltd.
BANGKOK.


BORING STARTED. 26/2/88	
BORING COMPLETED. 28/2/88	
RIG. ACKER	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JOB No. 1488	SHEET. 1/1

LOG OF BORING No. B-5

PROJECT NAME. Model Infrastructure

LOCATION. Samut Prakan

OWNER



WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.D
WL.	B.C.R. A.C.R.
WL.	-0.40 m 24 HRS. AFTER BORING.

STS.
 Engineering Consultants Co., Ltd.
BANGKOK.

BORING STARTED. 7/3/88	
BORING COMPLETED. 9/3/88	
RIG. ACKER	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JOB No. 1488	SHEET. 1/1

DUTCH CONE PENETRATION TEST RESULTS

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG DO

TEST NO D-1

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO. OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	4.40	7.20	5.10	.21	4.11
.60	2	.37	5.80	9.60	6.65	.28	4.21
.80	2	.37	6.00	12.00	6.87	.44	6.40
1.00	2	.37	2.80	5.00	3.33	.16	4.80
1.20	2	.37	3.20	5.40	3.77	.16	4.24
1.40	3	.50	2.60	4.40	3.24	.13	4.01
1.60	3	.50	1.60	3.40	2.10	.13	6.09
1.80	3	.50	1.60	2.40	2.13	.06	2.81
2.00	3	.50	1.20	2.20	1.69	.07	4.14
2.20	3	.50	1.00	1.80	1.46	.06	4.09
2.40	3	.50	1.20	1.80	1.69	.04	2.37
2.60	4	.64	1.40	2.20	2.05	.06	2.92
2.80	4	.64	1.20	2.00	1.93	.06	3.38
3.00	4	.64	1.00	2.00	1.60	.07	4.35
3.20	4	.64	1.20	1.80	1.83	.04	2.19
3.40	4	.64	1.00	1.80	1.60	.06	3.73
3.60	5	.78	1.20	2.00	1.97	.06	3.05
3.80	5	.78	1.00	1.80	1.74	.06	3.43
4.00	5	.78	1.00	1.80	1.74	.06	3.43
4.20	5	.78	1.00	1.80	1.74	.06	3.43
4.40	5	.78	.80	1.60	1.52	.06	3.93
4.60	6	.91	.80	1.60	1.65	.06	3.62
4.80	6	.91	1.20	2.00	2.10	.06	2.86
5.00	6	.91	1.00	1.80	1.87	.06	3.19
5.20	6	.91	1.00	2.00	1.87	.07	3.73
5.40	6	.91	1.00	2.00	1.87	.07	3.73
5.60	7	1.05	1.40	2.40	2.46	.07	2.84
5.80	7	1.05	1.60	2.60	2.68	.07	2.61
6.00	7	1.05	1.60	2.60	2.68	.07	2.61
6.20	7	1.05	1.80	2.60	2.90	.06	2.07

STS ENGINEERING CONSULTANTS CO., LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-1

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTIO RATIO, %
6.39	7	1.05	1.80	2.60	2.90	.06	2.07
6.59	8	1.19	2.00	3.20	3.26	.09	2.76
6.79	8	1.19	2.00	3.20	3.26	.09	2.76
6.99	8	1.19	1.80	2.40	3.04	.04	1.31
7.19	9	1.19	1.80	2.60	3.04	.06	1.97
7.39	9	1.32	1.60	2.40	2.95	.06	2.03
7.59	9	1.32	1.60	2.40	2.95	.06	2.03
7.79	9	1.32	1.80	2.60	3.17	.06	1.89
7.99	9	1.32	1.60	2.00	2.95	.09	3.05
8.19	9	1.32	1.00	2.20	2.28	.09	3.93
8.39	10	1.46	1.20	2.20	2.65	.07	2.64
8.59	10	1.46	1.20	2.40	2.65	.09	3.40
8.79	10	1.46	1.40	2.60	2.87	.09	3.13
8.99	10	1.46	1.20	2.60	2.65	.10	3.77
9.19	10	1.46	1.40	2.80	2.87	.10	3.48
9.39	11	1.60	1.20	2.40	2.79	.09	3.23
9.59	11	1.60	1.60	2.60	3.23	.07	2.17
9.79	11	1.60	2.00	3.20	3.67	.09	2.45
9.99	11	1.60	1.80	3.20	3.45	.10	2.89
10.20	11	1.60	1.60	2.80	3.23	.09	2.78
10.40	12	1.73	2.00	3.40	3.80	.10	2.63
10.60	12	1.73	2.20	3.40	4.02	.09	2.23
10.80	12	1.73	2.20	3.80	4.02	.12	2.96
11.00	12	1.73	2.20	3.40	4.02	.09	2.23
11.20	12	1.73	2.20	3.60	4.02	.10	2.48
11.40	13	1.87	2.00	3.60	3.94	.12	3.04
11.60	13	1.87	2.40	3.80	4.38	.10	2.36
11.80	13	1.87	2.40	3.80	4.38	.10	2.36
12.00	13	1.87	2.20	3.60	4.16	.10	2.40
12.20	13	1.87	3.00	4.20	5.05	.09	1.78

STS ENGINEERING CONSULTANTS CO., LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-1

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONES/JACKET READING, kn/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.40	14	2.00	3.00	4.50	5.18	.11	2.12
12.60	14	2.00	3.20	4.50	5.40	.10	1.95
12.80	14	2.00	2.90	4.20	4.96	.10	2.02
13.00	14	2.00	2.40	3.80	4.51	.10	2.21
13.20	14	2.00	3.40	4.30	5.62	.07	1.24
13.40	15	2.14	3.40	5.60	5.76	.16	2.77
13.60	15	2.14	2.80	5.20	5.10	.18	3.53
13.80	15	2.14	3.20	5.80	5.54	.19	3.43
14.00	15	2.14	3.20	5.80	5.54	.19	3.43
14.20	15	2.14	3.20	6.40	6.20	.19	3.06
14.40	16	2.28	3.20	6.40	6.34	.19	2.99
14.60	16	2.28	3.80	6.80	6.34	.22	3.46
14.80	16	2.28	3.60	6.80	6.12	.18	2.94
15.00	16	2.28	4.20	6.80	6.79	.19	2.80
15.20	17	2.41	4.40	8.80	7.14	.32	4.48
15.40	17	2.41	4.80	10.20	7.58	.40	5.27
15.60	17	2.41	4.20	9.60	6.92	.40	5.78
15.80	17	2.41	4.20	8.80	6.92	.34	4.91
16.00	17	2.41	4.20	8.60	6.92	.32	4.62
16.20	17	2.41	4.60	9.40	7.36	.35	4.75
16.40	18	2.55	4.40	9.60	7.28	.31	4.26
16.60	18	2.55	4.40	8.20	7.28	.28	3.84
16.80	18	2.55	5.20	10.40	8.17	.38	4.65
17.00	18	2.55	5.40	9.80	8.39	.32	3.81
17.20	18	2.55	5.80	10.80	8.83	.37	4.19
17.40	19	2.69	7.00	12.00	10.30	.37	3.59
17.60	19	2.69	6.40	12.80	9.63	.47	4.88
17.80	19	2.69	6.20	11.20	9.41	.37	3.93
18.00	19	2.69	5.60	10.60	8.75	.37	4.23
18.20	19	2.69	6.40	11.80	9.63	.40	4.15

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO


TEST NO B-1

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	8.40	13.00	11.98	.40	3.34
18.60	20	2.82	8.40	13.00	11.98	.40	3.34
18.80	20	2.82	8.20	15.00	11.76	.56	4.76
19.00	20	2.82	9.00	15.00	12.64	.50	3.95
19.20	20	2.82	8.00	14.00	11.54	.44	3.81
19.40	21	2.96	6.00	11.00	9.46	.37	3.91
19.60	21	2.96	6.00	12.00	11.68	.38	2.57
19.80	21	2.96	18.00	25.00	39.34	1.00	2.55
20.00	21	2.96	20.00	29.00	43.65	1.29	2.96
20.20	21	2.96	16.00	29.00	35.04	1.86	5.33
20.40	22	3.10	16.00	30.00	35.18	2.01	5.71
20.60	22	3.10	19.00	34.00	41.64	2.15	5.17



STS ENGINEERING CONSULTANTS CO., LTD.

TEST NO D-1

LOCAL FRICTION, QF (KBC)


0 0.5 1 1.5 2 2.5 3

CONE RESISTANCE, QC (KBC)

0 5 10 15 20 25 30 35 40

FRICTION RATIO, %

0 1 2 3 4 5 6 7 8



STE ENGINEERING CONSULTANTS CO., LTD.

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT: MODEL INFRASTRUCTURE

LOCATION: BANG BO

TEST NO: D-2

DATE: 30 JAN 88

TESTED BY: PS

APPROVED BY: AH

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	COHE READING, kg/cm ²	COHE&JACKET READING, kn/cm ²	COHE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	2.20	3.90	2.66	.12	4.50
.60	2	.37	2.20	3.80	2.66	.12	4.50
.80	3	.50	1.80	3.20	2.35	.10	4.25
1.00	3	.50	1.60	2.80	2.13	.09	4.22
1.20	3	.50	1.40	2.60	1.91	.09	4.71
1.40	3	.50	1.60	2.80	2.13	.09	4.22
1.60	3	.50	1.20	2.20	1.69	.07	4.14
1.80	4	.64	1.00	1.80	1.60	.06	3.73
2.00	4	.64	1.20	2.20	1.83	.07	3.83
2.20	4	.64	.90	1.80	1.38	.07	5.05
2.40	4	.64	1.00	2.00	1.60	.07	4.35
2.60	4	.64	1.60	3.00	2.27	.10	4.40
2.80	5	.78	.80	1.80	1.52	.07	4.58
3.00	5	.78	1.20	2.20	1.97	.07	3.55
3.20	5	.78	1.20	2.20	1.97	.07	3.55
3.40	5	.78	1.00	2.00	1.74	.07	4.00
3.60	5	.78	1.00	2.00	1.74	.07	4.00
3.80	6	.91	.90	1.80	1.65	.07	4.22
4.00	6	.91	1.00	1.80	1.87	.06	3.19
4.20	6	.91	1.00	1.80	1.87	.06	3.19
4.40	6	.91	.90	1.60	1.65	.06	3.62
4.60	6	.91	.90	1.60	1.65	.06	3.62
4.80	6	.91	.90	1.60	1.65	.06	3.62
4.80	7	1.05	.80	1.80	1.79	.07	3.90
5.00	7	1.05	.80	1.80	1.79	.07	3.90
5.20	7	1.05	.80	1.80	1.79	.07	3.90
5.40	7	1.05	1.00	1.80	2.01	.06	2.97
5.60	7	1.05	1.00	1.80	2.01	.06	2.97
5.60	7	1.05	1.00	1.80	2.01	.06	2.97
5.60	7	1.05	1.00	1.80	2.01	.06	2.97
5.60	7	1.05	1.00	1.80	2.01	.06	2.97
5.60	7	1.05	1.00	1.80	2.01	.06	2.97
5.80	8	1.19	1.20	2.00	2.38	.06	2.52
5.80	8	1.19	1.20	2.00	2.15	.06	2.78
6.00	8	1.19	1.00	1.80	2.15	.06	2.78
6.20	8	1.19	.80	1.60	1.93	.06	3.10

STS ENGINEERING CONSULTANTS CO., LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-2

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.39	8	1.19	1.20	2.00	2.38	.06	2.52
6.59	8	1.19	1.20	2.00	2.38	.06	2.52
6.79	9	1.32	1.20	2.20	2.51	.07	2.79
6.99	9	1.32	1.20	2.20	2.51	.07	2.79
7.19	9	1.32	1.20	2.20	2.51	.07	2.79
7.39	9	1.32	1.20	2.20	2.51	.07	2.79
7.59	9	1.32	1.20	2.20	2.51	.07	2.79
7.79	10	1.46	1.20	2.20	2.65	.07	2.64
7.99	10	1.46	1.20	2.20	2.65	.07	2.64
8.19	10	1.46	1.20	2.40	2.65	.09	3.40
8.39	10	1.46	1.20	2.40	2.65	.09	3.40
8.59	10	1.46	1.20	2.40	2.65	.09	3.40
8.79	11	1.60	1.20	2.40	2.79	.09	3.23
8.99	11	1.60	1.20	2.40	2.79	.09	3.23
9.19	11	1.60	1.20	2.40	2.79	.09	3.23
9.39	11	1.60	1.40	2.60	3.01	.09	2.99
9.59	11	1.60	1.40	2.60	3.01	.09	2.99
9.79	12	1.73	1.40	2.60	3.14	.09	2.86
9.99	12	1.73	1.40	2.60	3.14	.09	2.86
10.20	12	1.73	1.40	2.60	3.14	.09	2.86
10.40	12	1.73	1.60	3.40	3.36	.13	3.87
10.60	12	1.73	1.40	3.20	3.14	.13	4.14
10.80	13	1.87	1.80	3.80	3.72	.15	4.03
11.00	13	1.87	1.80	3.80	3.72	.15	4.03
11.20	13	1.87	1.80	3.80	3.72	.15	4.03
11.40	13	1.87	2.00	4.20	3.94	.16	4.05
11.60	13	1.87	2.20	4.60	4.16	.18	4.32
11.80	14	2.00	2.40	4.80	4.51	.18	3.98
12.00	14	2.00	2.20	4.60	4.29	.18	4.19
12.20	14	2.00	2.40	4.60	4.51	.16	3.54

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
LOCATION BANG BO
TEST NO D-2
TESTED BY PS

DATE 30 JAN 88
APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	COHE READING, kg/cm ²	COHE&JACKET READING, kg/cm ²	COHE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.40	14	2.00	2.60	4.80	4.74	.16	3.38
12.60	14	2.00	2.60	4.80	4.74	.16	3.38
12.80	15	2.14	2.60	4.80	4.89	.16	3.28
13.00	15	2.14	2.80	5.20	5.10	.18	3.53
13.20	15	2.14	3.00	5.40	5.32	.18	3.38
13.40	15	2.14	3.20	5.80	5.54	.19	3.43
13.60	15	2.14	3.20	6.20	5.54	.22	3.97
13.80	16	2.28	3.40	6.60	5.90	.24	4.06
14.00	16	2.28	3.20	6.40	5.68	.24	4.22
14.20	16	2.28	3.20	6.00	5.68	.21	3.69
14.40	16	2.28	4.00	6.80	6.57	.21	3.20
14.60	16	2.28	4.00	7.40	6.57	.25	3.80
14.80	17	2.41	3.40	7.20	6.03	.28	4.64
15.00	17	2.41	3.80	7.00	6.47	.24	3.70
15.20	17	2.41	3.80	7.00	6.47	.24	3.70
15.40	17	2.41	3.80	7.20	6.47	.25	3.86
15.60	17	2.41	3.60	6.80	6.25	.24	3.83
15.80	18	2.55	3.80	7.20	6.61	.25	3.78
16.00	18	2.55	4.00	7.20	6.84	.24	3.51
16.20	18	2.55	4.60	8.00	7.50	.25	3.33
16.40	18	2.55	4.40	7.80	7.28	.25	3.43
16.60	18	2.55	4.80	8.60	7.72	.28	3.62
16.80	19	2.69	5.80	9.80	8.97	.30	3.34
17.00	19	2.69	5.80	10.40	8.97	.34	3.79
17.20	19	2.69	6.00	10.80	9.19	.35	3.81
17.40	19	2.69	6.60	11.40	9.86	.35	3.55
17.60	19	2.69	6.20	11.80	10.08	.37	3.67
17.80	20	2.82	7.00	12.40	10.43	.40	3.83
18.00	20	2.82	7.40	12.80	10.87	.40	3.68
18.20	20	2.82	8.00	14.00	11.54	.44	3.81

STS ENGINEERING CONSULTANTS CO., LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-2

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AN


DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	6.40	12.40	9.76	.44	4.50
18.60	20	2.82	7.20	11.40	10.65	.31	2.91
18.80	21	2.96	8.00	14.00	11.68	.44	3.77
19.00	21	2.96	8.40	14.60	12.12	.46	3.73
19.20	21	2.96	9.40	15.80	13.23	.47	3.55
19.40	21	2.96	10.00	17.00	13.89	1.55	11.18
19.60	21	2.96	10.00	17.00	13.89	1.55	11.18
19.80	22	3.10	9.20	15.80	13.15	.49	3.73
20.00	22	3.10	10.00	16.00	14.03	1.40	10.04
20.20	22	3.10	10.00	16.00	14.03	1.40	10.04
20.40	22	3.10	26.00	34.00	56.71	1.14	2.03
20.60	22	3.10	26.00	37.00	56.71	1.57	2.78

TESTING D-2

LOCAL FRICTION, QF (KSC)

FRICTION RATIO, %


CONE RESISTANCE, QC (KSC)




STS ENGINEERING CONSULTANTS CO., LTD.

TEST NO D-2

LOCAL FRICTION, GF (KBC)



FRICITION RATIO, X



DEPTH FROM GROUND SURFACE (M)

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG 80

TEST NO D-3

DATE 29 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.60	2	.37	1.20	2.60	1.56	.10	6.41
.80	3	.50	2.20	4.80	2.79	.19	6.79
1.00	3	.50	2.40	4.20	3.01	.13	4.31
1.20	3	.50	1.20	2.40	1.69	.09	5.33
1.40	3	.50	1.20	2.40	1.69	.09	5.33
1.60	3	.50	1.20	2.40	1.69	.09	5.33
1.80	4	.64	1.40	2.20	2.05	.06	2.92
2.00	4	.64	.80	1.80	1.32	.07	5.05
2.20	4	.64	.80	1.20	1.38	.03	2.16
2.40	4	.64	.60	1.00	1.16	.03	2.57
2.60	4	.64	.60	1.20	1.16	.04	3.43
2.80	5	.78	.60	1.20	1.30	.04	3.06
3.00	5	.78	.60	1.20	1.30	.04	3.06
3.20	5	.78	.60	1.40	1.30	.06	4.60
3.40	5	.78	.40	1.20	1.08	.06	5.53
3.60	5	.78	.40	.80	1.08	.03	2.77
3.80	6	.91	.40	.80	1.21	.03	2.47
4.00	6	.91	.40	.80	1.21	.03	2.47
4.20	6	.91	.60	.80	1.43	.01	.70
4.40	6	.91	.80	1.80	1.65	.07	4.22
4.60	6	.91	.80	2.00	1.65	.09	5.43
4.80	7	1.05	.80	1.80	1.79	.07	3.90
5.00	7	1.05	.80	1.80	1.79	.07	3.90
5.20	7	1.05	.80	1.80	1.79	.07	3.90
5.40	7	1.05	.80	2.00	1.79	.09	5.01
5.60	7	1.05	.80	2.00	1.79	.09	5.01
5.80	8	1.19	.80	1.80	1.93	.07	3.61
6.00	8	1.19	.80	1.60	1.93	.06	3.10
6.20	8	1.19	.80	1.40	1.93	.04	2.07
6.39	8	1.19	.80	1.80	1.93	.07	3.61

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-3

DATE 29 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.59	8	1.19	.80	1.80	1.93	.07	3.61
6.79	9	1.32	.80	1.80	2.06	.07	3.39
6.99	9	1.32	1.00	2.00	2.20	.07	3.06
7.19	9	1.32	.80	1.80	2.06	.07	3.39
7.39	9	1.32	.80	2.00	2.06	.09	4.35
7.59	9	1.32	1.20	2.20	2.51	.07	2.79
7.79	10	1.46	1.00	2.00	2.42	.07	2.88
7.99	10	1.46	1.20	2.20	2.65	.07	2.64
8.19	10	1.46	1.20	2.20	2.65	.07	2.64
8.39	10	1.46	1.20	2.20	2.65	.07	2.64
8.59	10	1.46	1.20	2.20	2.65	.07	2.64
8.79	11	1.60	1.00	2.00	2.56	.07	2.73
8.99	11	1.60	1.00	2.00	2.56	.07	2.73
9.19	11	1.60	1.20	2.20	2.79	.07	2.51
9.39	11	1.60	1.40	2.20	3.01	.06	1.99
9.59	11	1.60	1.40	2.40	3.01	.07	2.32
9.79	12	1.73	1.60	2.60	3.36	.07	2.88
9.99	12	1.73	1.60	2.80	3.36	.09	2.68
10.20	12	1.73	1.60	2.80	3.36	.09	2.68
10.40	12	1.73	1.60	2.80	3.36	.09	2.68
10.60	12	1.73	1.80	3.80	3.58	.15	4.18
10.80	13	1.87	1.40	3.00	3.28	.12	3.66
11.00	13	1.87	1.50	4.00	3.72	.16	4.30
11.20	13	1.87	2.00	4.00	3.94	.15	3.80
11.40	13	1.87	2.00	4.00	3.94	.15	3.80
11.60	13	1.87	2.00	4.00	3.94	.15	3.80
11.80	14	2.00	2.00	4.00	4.07	.15	3.68
12.00	14	2.00	2.20	4.20	4.29	.15	3.48
12.20	14	2.00	2.40	4.60	4.51	.16	3.54
12.40	14	2.00	2.60	4.60	4.74	.15	3.16

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-3

DATE 29 JAN 88

TESTED BY PS

APROVED BY AM

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.60	14	2.00	2.60	4.80	4.74	.16	3.38
12.80	15	2.14	2.60	4.60	4.88	.15	3.07
13.00	15	2.14	3.20	5.40	5.54	.16	2.89
13.20	15	2.14	3.60	5.80	5.98	.16	2.67
13.40	15	2.14	3.60	6.40	5.98	.21	3.51
13.60	15	2.14	3.40	6.40	5.76	.22	3.82
13.80	16	2.28	3.40	6.40	5.90	.22	3.72
14.00	16	2.28	4.20	7.80	6.79	.27	3.97
14.20	16	2.28	3.80	6.80	6.34	.22	3.46
14.40	16	2.28	3.20	6.60	5.68	.25	4.40
14.60	16	2.28	2.80	6.40	5.24	.27	5.15
14.80	17	2.41	3.80	6.80	6.47	.22	3.40
15.00	17	2.41	4.20	6.40	6.92	.16	2.31
15.20	17	2.41	4.60	6.40	7.36	.13	1.76
15.40	17	2.41	4.40	6.40	7.14	.15	2.10
15.60	17	2.41	4.20	8.00	6.92	.28	4.04
15.80	18	2.55	4.60	8.00	7.50	.25	3.33
16.00	18	2.55	5.00	9.00	7.94	.30	3.77
16.20	18	2.55	4.80	8.80	7.72	.30	3.88
16.40	18	2.55	5.00	8.80	7.94	.28	3.52
16.60	18	2.55	5.00	8.80	7.94	.28	3.52
16.80	19	2.69	4.20	8.40	7.20	.31	4.30
17.00	19	2.69	5.60	9.40	8.75	.28	3.20
17.20	19	2.69	5.20	9.40	8.31	.31	3.73
17.40	19	2.69	5.00	9.20	8.88	.31	3.83
17.60	19	2.69	6.40	10.20	9.63	.28	2.90
17.80	20	2.82	6.20	10.20	9.54	.30	3.14
18.00	20	2.82	7.00	13.80	16.42	.50	4.79
18.20	20	2.82	6.00	10.80	9.32	.35	3.75
18.40	20	2.82	6.40	9.40	9.76	.22	2.25

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
LOCATION BANG BO
TEST NO D-3 DATE 29 JAN 83
TESTED BY PS APPROVED BY AN


DEPTH, m.	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.60	20	2.82	6.20	9.60	9.54	.25	2.62
18.80	21	2.96	6.80	9.80	10.35	.22	2.13
19.00	21	2.96	7.80	13.80	11.45	.44	3.84
19.20	21	2.96	7.80	13.80	11.45	.44	3.84
19.40	21	2.96	7.20	12.80	10.79	.41	3.80
19.60	21	2.96	7.60	13.20	11.23	.41	3.65
19.80	22	3.18	8.20	14.40	12.04	.46	3.82
20.00	22	3.18	14.00	21.00	18.46	1.83	9.92
20.20	22	3.18	15.00	27.00	19.57	2.61	13.38
20.40	22	3.18	18.00	29.00	39.48	1.57	4.00

TEST NO D-8

LOCAL FRICTION, GF (KBC) 1 1.5 2 2.5 3

CONE RESISTANCE, QC (KBC) 0 5 10 15 20 25 30 35


FRICTION RATIO, % 0 3 6 9 12 15




SOIL ENGINEERING CONSULTANTS CO., LTD.

TEST NO D-3


LOCAL FRICTION, GF (KSC)



CONE RESISTANCE, QC (KSC)



FRICTION RATIO, %



DEPTH FROM GROUND SURFACE, M

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG B0

TEST NO D-4

DATE 31 JAN 86

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	1.20	2.60	1.56	.10	6.41
.60	2	.37	1.20	2.60	1.56	.10	6.41
.80	3	.50	1.00	2.00	1.46	.07	4.77
1.00	3	.50	1.20	2.20	1.69	.07	4.14
1.20	3	.50	.60	1.60	1.02	.07	6.83
1.40	3	.50	.60	1.40	1.02	.06	5.85
1.60	3	.50	.60	1.40	1.02	.06	5.85
1.80	4	.64	.80	1.80	1.38	.07	5.05
2.00	4	.64	1.60	2.60	2.27	.07	3.08
2.20	4	.64	.80	1.80	1.38	.07	5.05
2.40	4	.64	.80	1.80	1.38	.07	5.05
2.60	4	.64	.60	1.60	1.38	.06	4.33
2.80	5	.78	.80	1.60	1.52	.06	3.93
3.00	5	.78	.60	1.40	1.30	.06	4.60
3.20	5	.78	.60	1.20	1.30	.04	3.06
3.40	5	.78	.60	1.40	1.52	.04	2.62
3.60	5	.78	.60	1.40	1.30	.06	4.60
3.80	6	.91	.60	1.60	1.43	.07	4.88
4.00	6	.91	.60	1.20	1.43	.04	2.79
4.20	6	.91	.60	1.20	1.43	.04	2.79
4.40	6	.91	.60	1.40	1.43	.06	4.18
4.60	6	.91	.80	1.60	1.65	.06	3.62
4.80	7	1.05	.80	1.60	1.79	.06	3.34
5.00	7	1.05	.80	1.60	1.79	.06	3.34
5.20	7	1.05	1.00	1.80	2.01	.06	2.97
5.40	7	1.05	.80	1.60	1.79	.06	3.34
5.60	7	1.05	.80	1.60	1.79	.06	3.34
5.80	8	1.19	.80	1.60	1.93	.06	3.10
6.00	8	1.19	.80	1.80	1.93	.07	3.61
6.20	8	1.19	.80	1.60	1.93	.06	3.10

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-4

DATE 31 JAN 88

TESTED BY PS

APROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kn/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.59	9	1.19	1.00	2.20	2.15	.09	4.17
6.59	9	1.19	1.00	2.20	2.15	.09	4.17
6.79	9	1.32	1.00	2.00	2.28	.07	3.06
6.99	9	1.32	1.00	2.00	2.28	.07	3.06
7.19	9	1.32	1.20	2.00	2.51	.06	2.39
7.39	9	1.32	1.20	2.20	2.51	.07	2.79
7.59	9	1.32	1.20	2.30	2.51	.07	2.79
7.79	10	1.46	1.20	2.20	2.65	.07	2.64
7.99	10	1.46	1.20	2.20	2.65	.07	2.64
8.19	10	1.46	1.20	2.40	2.65	.09	3.40
8.39	10	1.46	1.20	2.40	2.65	.09	3.40
8.59	10	1.46	1.20	2.40	2.65	.09	3.40
8.79	11	1.60	1.40	2.40	3.01	.07	2.32
8.99	11	1.60	1.40	2.40	3.01	.07	2.32
9.19	11	1.60	1.40	2.60	3.01	.09	2.99
9.39	11	1.60	1.40	2.60	3.01	.09	2.99
9.59	11	1.60	1.40	2.80	3.01	.10	3.32
9.79	12	1.73	1.20	2.60	2.92	.10	3.42
9.99	12	1.73	1.40	2.80	3.14	.10	3.16
10.20	12	1.73	1.20	2.60	2.92	.10	3.42
10.40	12	1.73	1.20	2.60	2.92	.10	3.42
10.60	12	1.73	1.40	2.60	3.14	.09	2.66
10.80	13	1.87	1.40	3.20	3.28	.13	3.96
11.00	13	1.87	1.40	3.20	3.28	.13	3.96
11.20	13	1.87	1.40	3.60	3.28	.16	4.63
11.40	13	1.87	1.20	3.80	3.72	.15	4.02
11.60	13	1.87	1.60	3.60	3.50	.15	4.28
11.80	14	2.00	2.40	4.20	4.51	.13	2.88
12.00	14	2.00	2.20	4.20	4.29	.15	3.49
12.20	14	2.00	2.00	4.00	4.07	.15	3.68

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-4

DATE 31 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, 2 kg/cm	CONE READING, 2 kg/cm	CONE&JACKET READING, 2 kn/cm	CONE RESISTANCE, 2 kg/cm	LOCAL FRICTION, 2 kg/cm	FRICTION RATIO, %
12.40	14	2.00	2.29	4.40	4.29	.16	3.72
12.60	14	2.00	2.40	4.80	4.51	.16	3.98
12.80	15	2.14	2.80	5.40	5.10	.19	3.72
13.00	15	2.14	2.80	5.40	5.10	.19	3.72
13.20	15	2.14	3.80	6.40	6.20	.19	3.06
13.40	15	2.14	3.60	6.40	5.98	.21	3.51
13.60	15	2.14	3.40	6.40	5.76	.22	3.82
13.80	16	2.28	3.60	6.40	6.12	.21	3.43
14.00	16	2.28	3.40	6.40	5.90	.22	3.72
14.20	16	2.28	4.00	7.20	6.57	.24	3.65
14.40	16	2.28	4.40	7.60	7.01	.24	3.42
14.60	16	2.28	4.00	7.00	6.57	.22	3.35
14.80	17	2.41	3.60	6.40	6.25	.21	3.36
15.00	17	2.41	3.40	6.00	6.03	.19	3.15
15.20	17	2.41	4.20	7.00	6.92	.21	3.03
15.40	17	2.41	4.80	8.20	7.58	.25	3.30
15.60	17	2.41	4.00	8.00	6.70	.30	4.48
15.80	18	2.55	3.80	7.60	6.61	.28	4.23
16.00	18	2.55	4.00	7.80	6.84	.28	4.09
16.20	18	2.55	4.60	7.80	7.50	.24	3.20
16.40	18	2.55	4.40	7.80	7.28	.25	3.43
16.60	18	2.55	5.20	8.20	8.17	.22	2.69
16.80	18	2.55	5.20	8.20	8.08	.30	3.71
16.80	19	2.69	5.00	9.00	8.31	.28	3.37
17.00	19	2.69	5.20	9.00	7.86	.31	3.94
17.20	19	2.69	4.80	9.00	8.75	.24	2.74
17.40	19	2.69	5.60	9.80	7.86	.28	3.56
17.60	19	2.69	4.80	8.60	9.76	.30	3.07
17.80	20	2.82	6.40	10.40	10.21	.28	2.74
18.00	20	2.82	6.80	10.60	9.54	.31	3.25
18.20	20	2.82	6.20	10.40			

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG EO

TEST NO D-4

DATE 31 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	7.00	11.80	10.43	.35	3.35
18.60	20	2.82	7.80	12.40	11.31	.34	3.00
18.80	21	2.96	7.00	12.20	10.57	.39	3.59
19.00	21	2.96	6.80	11.20	10.35	.32	3.09
19.20	21	2.96	6.40	10.80	9.90	.32	3.23
19.40	21	2.96	7.00	11.20	10.57	.31	2.93
19.60	21	2.96	7.00	11.40	10.57	.32	3.03
19.80	22	3.10	12.00	19.00	16.25	1.69	10.42
20.00	22	3.10	17.00	25.00	37.33	1.14	3.08
20.20	22	3.10	17.00	25.00	37.33	1.14	3.08
20.40	22	3.10	17.00	30.00	37.33	1.86	5.00
20.60	22	3.10	22.00	36.00	48.10	2.01	4.18

TEST NO P114

LOCAL FRICTION, q_f (KSC)

2.5

1

1.5

2

CONE RESISTANCE, q_c (KSC)

FRICTION RATIO, α

12

10

8

6

4

2

0

40

20

0

20

40

60

80

100

120

140

160

180

200

220

q_c

q_f

DEPTH FROM GROUND SURFACE, M

STS ENGINEERING CONSULTANTS CO., LTD.

TEST NO D-4

2.5

LOCAL FRICTION, QF (KPC)

2

1.5

1

0

CONE RESISTANCE, QC (KPC)

40

30

20

10

0

FRICTION RATIO, X

12

10


8

6

4

2

0



DEPTH FROM GROUND SURFACE (M)

0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
LOCATION BANG BO
TEST NO D-5 DATE 31 JAN 88
TESTED BY PS APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, 2 kg/cm	CONE READING, 2 kg/cm	CONE&JACKET READING, 2 kn/cm	CONE RESISTANCE, 2 kg/cm	LOCAL FRICTION, 2 kg/cm	FRICTION RATIO, %
.40	2	.37	1.00	3.00	2.22 /	.15	6.74
.60	2	.37	1.00	2.00	1.33	.07	5.23
.80	3	.50	.00	1.00	1.24	.07	5.61
1.00	3	.50	.60	1.60	1.02 /	.07 /	6.03
1.20	3	.50	.60	1.40	1.02	.06	5.85
1.40	3	.50	.60	1.40	1.02	.06	5.85
1.60	3	.50	.60	1.40	1.02	.06	5.85
1.80	4	.64	.60	1.40	1.16	.06	5.15
2.00	4	.64	.80	1.80	1.38 /	.06 /	4.33
2.20	4	.64	.60	1.40	1.16	.06	5.15
2.40	4	.64	.80	1.40	1.38	.04	2.88
2.60	4	.64	.40	1.20	.94	.06	6.36
2.80	5	.78	.40	1.50	1.08	.09	8.30
3.00	5	.78	.80	1.40	1.52 /	.04	2.62
3.20	5	.78	.60	1.20	1.30	.04	3.06
3.40	5	.78	.60	1.20	1.30	.04	3.06
3.60	5	.78	1.00	1.50	1.74	.06	3.43
3.80	6	.91	1.00	1.80	1.87	.06	3.19
4.00	6	.91	.80	1.60	1.65 /	.06 /	3.62
4.20	6	.91	.60	1.40	1.43	.06	4.18
4.40	6	.91	.60	1.40	1.43	.06	4.18
4.60	6	.91	.60	1.40	1.43	.06	4.18
4.80	7	1.05	.80	1.60	1.79	.06	3.34
4.80	7	1.05	.80	1.80	1.79 /	.07	3.90
5.00	7	1.05	.80	1.80	1.79	.07	3.90
5.20	7	1.05	.80	1.80	1.79	.07	3.90
5.40	7	1.05	1.00	2.00	2.01	.07	3.47
5.40	7	1.05	1.20	2.60	2.24	.06	2.63
5.60	7	1.05	1.20	2.20	2.39	.07	2.34
5.80	8	1.19	1.20	2.20	1.93 /	.09	4.65
6.00	8	1.19	.00	2.00	2.15	.09	4.17
6.20	8	1.19	1.00	2.20	2.15	.09	4.17

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BØ

TEST NO D-5

DATE 31 JAN 83

TESTED BY PS

APPROVED BY AM

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.39	8	1.19	1.20	2.20	2.38	.07	2.94
6.59	8	1.19	1.20	2.20	2.38	.07	2.94
6.79	9	1.32	1.40	2.40	2.73	.07	2.56
6.99	9	1.32	1.20	2.00	2.51	.06	2.39
7.19	9	1.32	1.20	2.20	2.51	.07	2.79
7.39	9	1.32	1.40	2.20	2.73	.06	2.20
7.59	9	1.32	1.40	2.20	2.73	.06	2.20
7.79	10	1.46	1.40	2.40	2.87	.07	2.44
7.99	10	1.46	1.20	2.00	2.65	.06	2.26
8.19	10	1.46	1.40	2.20	2.87	.06	2.09
8.39	10	1.46	1.60	3.40	3.09	.13	4.20
8.59	10	1.46	2.00	3.00	3.53	.07	1.98
8.79	11	1.60	1.60	2.40	3.23	.06	1.86
8.99	11	1.60	1.60	2.20	3.23	.04	1.24
9.19	11	1.60	1.60	2.40	3.23	.06	1.86
9.39	11	1.60	1.60	2.40	3.23	.06	1.86
9.59	11	1.60	1.80	2.80	3.45	.07	2.03
9.79	12	1.73	2.20	3.80	4.02	.12	2.98
9.99	12	1.73	1.80	3.20	3.58	.10	2.79
10.20	12	1.73	1.80	3.40	3.58	.12	3.35
10.40	12	1.73	1.80	3.60	3.58	.13	3.63
10.60	12	1.73	2.00	3.86	3.80	.13	3.42
10.80	13	1.87	2.20	4.00	4.16	.13	3.12
11.00	13	1.87	2.00	3.60	3.94	.12	3.04
11.20	13	1.87	2.20	3.80	4.16	.12	2.88
11.40	13	1.87	2.46	4.00	4.38	.12	2.73
11.60	13	1.87	2.26	4.00	4.16	.13	3.12
11.80	14	2.00	2.20	4.20	4.29	.15	3.49
12.00	14	2.00	2.00	3.80	4.07	.13	3.19
12.20	14	2.00	2.80	4.60	4.96	.13	2.62

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-5

DATE 31 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, 2 kg/cm	COHE READING, 2 kg/cm	COHE&JACKET READING, 2 kg/cm	COHE RESISTANCE, 2 kg/cm	LOCAL FRICTION, 2 kg/cm	FRICTION RATIO, %
12.40	14	2.00	3.20	5.40	5.40	.16	2.96
12.60	14	2.00	3.00	5.60	5.18	.19	3.67
12.80	15	2.14	2.60	4.80	4.88	.16	3.28
13.00	15	2.14	2.40	4.60	4.65	.16	3.43
13.20	15	2.14	3.20	5.40	5.54	.16	2.89
13.40	15	2.14	3.20	5.60	5.54	.18	3.25
13.60	15	2.14	3.40	6.20	5.76	.21	3.64
13.80	16	2.28	3.20	6.20	5.68	.22	3.87
14.00	16	2.28	3.60	6.20	6.12	.19	3.10
14.20	16	2.28	3.60	6.60	6.12	.22	3.59
14.40	16	2.28	4.00	6.60	6.57	.19	2.89
14.60	16	2.28	3.80	6.80	6.34	.22	3.46
14.80	17	2.41	3.40	6.80	6.03	.25	4.14
15.00	17	2.41	4.40	7.40	7.14	.22	3.88
15.20	17	2.41	5.20	8.40	8.03	.24	2.99
15.40	17	2.41	4.80	9.20	7.58	.32	4.22
15.60	17	2.41	4.00	8.20	6.70	.31	4.63
15.80	17	2.41	3.80	7.80	6.61	.30	4.53
16.00	18	2.55	5.00	8.60	7.94	.27	3.40
16.20	18	2.55	5.60	9.20	8.61	.31	3.60
16.40	18	2.55	6.00	11.20	9.05	.38	4.20
16.60	18	2.55	5.20	10.20	8.17	.37	4.53
16.80	19	2.69	6.40	12.40	9.63	.44	4.56
17.00	19	2.69	6.40	11.80	9.63	.40	4.15
17.20	19	2.69	7.60	13.40	10.96	.43	3.92
17.40	19	2.69	6.40	12.40	9.63	.44	4.56
17.60	19	2.69	6.60	12.60	9.86	.44	4.46
17.80	19	2.69	5.80	11.60	9.10	.43	4.72
18.00	20	2.82	6.20	11.40	9.54	.38	3.98
18.20	20	2.82	5.80	10.60	9.10	.35	3.84

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-5

DATE 31 JAN 98

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	5.80	11.00	9.10	.38	4.17
18.60	20	2.82	7.20	11.40	10.65	.31	2.91
18.80	21	2.96	7.00	11.80	10.57	.35	3.31
19.00	21	2.96	8.60	13.60	12.34/	.37/	3.00
19.20	21	2.96	7.40	13.60	11.01	.46	4.18
19.40	21	2.96	8.00	13.60	11.68	.41	3.51
19.60	21	2.96	7.60	12.40	11.23	.35	3.11
19.80	22	3.10	14.00	23.00	18.46/	2.11	11.48
20.00	22	3.10	18.00	34.00	30.48/	2.29/	5.82
20.20	22	3.10	20.00	35.00	43.79	2.15	4.92
20.40	22	3.10	20.00	35.00	43.79	2.15	4.92

TEST NO P-8

LOCAL FRICTION, QF (KBC)


0 0.5 1 1.5 2 2.5

CONE RESISTANCE, QC (KBC)

0 5 10 15 20 25 30 35 40

FRICTION RATIO, X

0 2 4 6 8 10 12



0 10 20 30 40 50 60 70 80 90 100 110 120

TEST NO D-3

LOCAL FRICTION, QF (KSC)

2.5

1

1.5

2

FRICTION RATIO, %

3

4

5

6

7

8

9

10

11

12

CONE RESISTANCE, QC (KSC)

15

10


5

0

QC

QF

DEPTH FROM GROUND SURFACE, M




STB ENGINEERING CONSULTANTS CO., LTD.

CONSOLIDATION TEST RESULTS

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping station		Job No. 1488
Boring No. B-1		Bang Bo, Samut Prakan Province		
Sample No. PST-1		Depth 1.00-1.80 m.	Date 18/1/88	



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_c, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{q}_m = 0.25 \text{ ksc}$	
					initial	Final
					Height of Sample, H cm	2.5
					Water Content, W %	83.2
					Degree of Saturation, S %	96
0.125	10.24	21.1	3.36	1.99	Solid Height of Sample, H _s cm	0.76
0.25	25.0	8.3	1.57	4.36	Diameter of Sample, D cm	6.35
0.50	43.56	4.3	1.13	10.71	Wet Unit Weight, γ g/cc	1.47
1	38.44	4.2	0.56	17.60	Dry Unit Weight, γ_d g/cc	0.80
2	30.0	4.6	0.29	23.88	Liquid Limit, LL %	94.6
4					Plastic Limit, PL %	35.3
8					Compression Ratio CR	0.24
16					Recompression Ratio RR	0.08
					Specific Gravity, G	2.66

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping Station, Bang Bo, Samut Prakan Province		Job No 1488
Boring No. B-1	Sample No. PST-2	Depth 3.00-3.90 m.	Date 16/1/88	



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.28 \text{ ksc}$	
					initial	Final
Initial	—	—	—	—	Height of Sample, H cm	2.5
					Water Content, W %	95.2
					Degree of Saturation, S %	96
0.125	14.44	14.9	2.75	2.31	Solid Height of Sample, H _s cm	0.75
0.25	17.64	11.7	2.21	4.67	Diameter of Sample D cm	6.35
0.50	60.0	3.1	0.86	11.64	Wet Unit Weight γ_t g/cc	1.47
1	64.0	2.5	0.36	18.77	Dry Unit Weight γ_d g/cc	0.79
2	27.04	5.0	0.33	25.4	Liquid Limit LL %	
4					Plastic Limit PL %	
8					Compression Ratio CR	0.24
16					Recompression Ratio RR	0.07
					Specific Gravity G	2.65

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping Station Bang Bo, Samut Prakan		Job No. 1488
Boring No. B-1	Sample No. PST-3	Province		Date 16/1/88
		Depth	5.00-5.80 m.	



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.4 \text{ ksc}$	
					Height of Sample, H cm	Water Content, W %
Initial	—	—	—	—	Degree of Saturation, S %	26
0.125	14.44	15.1	1.27	1.05	Solid Height of Sample, H_s cm	9.74
0.25	25.0	8.5	1.07	2.62	Diameter of Sample, D cm	6.35
0.50	29.16	6.9	1.07	6.48	Wet Unit Weight, γ_1 g/cc	1.47
1	54.76	3.2	0.63	16.25	Dry Unit Weight, γ_d g/cc	0.99
2	21.16	6.8	0.41	22.35	Liquid Limit, LL %	90.8
4					Plastic Limit, PL %	35.8
8					Compression Ratio CR	0.31
16					Precompression Ratio RR	0.06
					Specific Gravity, G	2.68

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project Location Chareonraj Pumping Station
 Bang Bo, Samut Prakan Job No 1488
 Boring No. B-1 Sample No. PST-4 Province
 Depth 7.00-7.80 m. Date 16/1/88



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm/sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.45 \text{ ksc}$	
					initial	Final
					Height of Sample, H cm	2.5
					Water Content, W %	89.7
Initial	—	—			Degree of Saturation, S %	98
0.125	4.0	54.8	3.20	0.73	Solid Height of Sample, H _s cm	0.72
0.25	15.0	14.2	2.22	2.68	Diameter of Sample, D cm	6.35
0.50	36.0	5.6	0.90	6.24	Wet Unit Weight, γ g/cc	1.44
1	54.76	3.2	0.52	14.36	Dry Unit Weight, γ_d g/cc	0.76
2	49.0	3.0	0.27	23.36	Liquid Limit, LL %	
4					Plastic Limit, PL %	
8					Compression Ratio CR	0.70
16					Recompression Ratio RR	0.06
					Specific Gravity, G	2.64

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project Location Chareonraj Pumping Station, Bang Bo, Samut Prakan Job No. 1488
 Boring No. B-1 Sample No. PST-5 Province Depth 9.00-9.80 m. Date 16/1/88



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.7 \text{ ksc}$	
					Height of Sample, H cm	Final
Initial	—	—	—	—	Water Content, W %	95.8
Initial	—	—	—	—	Degree of Saturation, S %	93
0.125	2.25	97.9	1.88	0.24	Solid Height of Sample, H_s cm	0.68
0.25	9.0	24.2	1.74	1.14	Diameter of Sample ϕ cm	6.35
0.50	18.49	11.5	0.76	2.30	Wet Unit Weight γ_1 g/cc	1.40
1	33.44	5.1	0.61	8.80	Dry Unit Weight γ_d g/cc	0.71
2	77.44	2.1	0.26	21.17	Liquid Limit LL %	105.7
4					Plastic Limit PL %	40.3
8					Compression Ratio CR	0.41
16					Recompression Ratio RR	0.028
					Specific Gravity G_s	2.63

CONSOLIDATION TEST RESULTS

Project Model Infrastructure Project		Location Chareonraj Pumping Station Bang Bo, Samut Prakan		Job No. 1488
Boring No. B-1	Sample No. PST-6	Province	Depth 11.00-11.80 m.	Date 18/1/88




Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm/sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{va} = 0.72 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 99.1
Initial	—	—			Degree of Saturation, S	% 96
0.125	2.25	97.3	6.93	0.39	Solid Height of Sample, H_s	0.67 cm.
0.25	4.84	44.3	3.90	1.99	Diameter of Sample D	6.35 cm.
0.50	15.0	13.9	1.04	3.66	Wet Unit Weight γ_t	1.11 g/cc
1	36.0	5.3	0.67	10.16	Dry Unit Weight γ_d	0.71 g/cc
2	60.0	2.6	0.27	20.57	Liquid Limit LL	%
4	49.0	2.5	0.11	29.46	Plastic Limit PL	%
8					Compression Ratio CR	0.36
16					Recompression Ratio RR	0.04
					Specific Gravity G	2.65

STS ENGINEERING CONSULTANTS CO. LTD.

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping Station Bang Bo, Samut Prakan		Job No. 1488
Boring No. B-1	Sample No. PST-8	Province Depth 15.00-15.80 m.		Date 18/1/08



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 1.4 \text{ ksc}$	
					Height of Sample, H cm	Water Content, W %
Initial	—	—	—	—	Degree of Saturation, S %	96
0.125	—	—	—	0.21	Solid Height of Sample, H_s cm	0.84
0.25	1.0	218.7	9.8	0.77	Diameter of Sample, D cm	6.35
0.50	4.0	53.8	2.02	1.71	Wet Unit Weight, γ_1 g/cc	1.54
1	9.0	23.3	0.83	3.5	Dry Unit Weight, γ_s g/cc	0.90
2	33.44	5.1	0.24	8.12	Liquid Limit, LL %	
4	60.0	2.8	0.14	18.18	Plastic Limit, PL %	
8	40.96	3.2	0.07	27.18	Compression Ratio CR	0.32
16					Preconsolidation Ratio PR	0.02
					Specific Gravity, G	2.57

CONSOLIDATION TEST RESULTS

Project Model Infrastructure Project	Location Chareonraj Pumping station Bang. Bo. Samut Prakan Province	Job No. 1488
Boring No. B-2	Sample No. PST-1	Depth 1.00-1.80 m. Date 9/3/88



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} cm/sec$	Vertical Strain, ϵ %			initial	Final
					Height of Sample, H	cm.	2.5	
					Water Content, W	%	87.5	
Initial	—	—			Degree of Saturation, S	%	100	
0.06	79.21	2.8	0.14	0.31	Solid Height of Sample, H_s	cm.	0.75	
0.125	43.56	4.8	2.81	4.12	Diameter of Sample, D	cm.	6.35	
0.25	42.25	4.6	1.50	8.20	Wet Unit Weight, γ_1	g/cc	1.49	
0.50	54.02	3.2	0.56	12.54	Dry Unit Weight, γ_d	g/cc	0.80	
1	42.90	3.5	0.29	18.12	Liquid Limit, LL	%	86.2	
2	53.29	2.4	0.15	24.48	Plastic Limit, PL	%	32.6	
8					Compression Ratio CR			
16					Precompression Ratio PR			
					Specific Gravity, G		2.65	