





第9章 添付図面




SECTION (A)-(A) S=1:300




SECTION (B)-(B) S=1:300



TYPICAL SECTION OF DRAINAGE DITCH S=1:100



TYPICAL SECTION OF COFFER DAM S=1:100




ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT

GENERAL PLAN OF
TESTING CANAL FACILITY


JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO

ENG. NO.
1


STA. X 6





STA. X 7



STA. X7+20



STA. X8+80




ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

CROSS SECTIONS OF TESTING
 CANAL FACILITY (1/2)


JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

DWG. NO.
 2


STA. X2





STA. X3+20



STA. X4



STA. X5





ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT

CROSS SECTIONS OF TESTING
CANAL FACILITY (2/2)

JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO

DWG. NO.
3


PLAN S=1:200




ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

PILE ARRANGEMENT
 FOR FOUNDATION IMPROVEMENT WORK


JAPAN INTERNATIONAL COOPERATION AGENCY DMG. NO.
 TOKYO 4




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	



PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	



PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	




PILE LENGTH	
COMPACTION PILE LENGTH	
ELEVATION OF BOTTOM OF PILE	
NON-TREATMENT PILE LENGTH	
ELEVATION OF TOP OF PILE	
GROUND ELEVATION	
STATION	

ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

PROFILES OF SOIL CEMENT COLUMNS

JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

ENG. NO.
 6




ITEM AND QUANTITIES OF IN-SITU TESTS FOR THE EXPERIMENTAL CONSTRUCTION


Item of Test	Sand Compaction Pile	Gravel Compaction Pile	Soil Cement Column
Standard penetration test (Inside the piles)	*Location :Center of pile, 1 hole *Boring depth :7 m *Number of test:7 times (Depth;every 1 m)	Same as the left	-
Core boring (Inside the piles)	-	-	*Location:Center of pile, 1 hole *Boring depth:6 m *Core sampling: 6 samples (Depth:every 1 m)
Thin wall sampling (Clay of original ground)	*Location:Center between pile and pile, 1 hole *Boring depth:7 m *Core sampling:4 sample *Sampling depth: -1,-3,-5,&-7 m	Same as the left	-
Field density test	*Location:Center of pile, 2 holes *Number of tests:2 time	Same as the left	-

ITEMS AND QUANTITIES OF LABORATORY TESTS FOR THE EXPERIMENTAL CONSTRUCTION


Item of Test	Sand Compaction Pile	Gravel Compaction Pile	Soil Cement Column
Test of physical property *Natural moisture ratio *Wet density	*Pile material:2samples *Clay :7samples *Clay :4samples	*Pile material:2samples *Clay :7samples *Clay :4samples	-
Mechanical test *Unconfined compression test	*Clay :4samples	*Clay :4samples	*Pile :6samples



Sand Compaction Piles



Gravel Compaction Piles




Soil Cement Columns

ROYAL IRRIGATION DEPARTMENT
THE HOLOG INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT

EXPERIMENTAL CONSTRUCTION FOR
FOUNDATION IMPROVEMENT WORKS

JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO

7




LEGEND


- Extensometer
- Incliner
- Settlement Gauge
- Piezometer
- Displacement Pile
- Fixed Point

PLAN FOR ARRANGEMENT OF MONITORING INSTRUMENT


S = 1 : 500




INCLINOMETER (Aut Measuring)




INCLINOMETER (Manual Reading)



PIEZOMETER



SETTLEMENT GAUGE




FIXED POINT

ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT.


**INSTALLATION PLAN AND
INSTALLATION METHOD OF
MONITORING INSTRUMENT**

JAPAN INTERNATIONAL COOPERATION AGENCY
TOKYO


DWG. NO.
8




Non-treatment Slope for Short Term Slope Stability (1:4)



Non-treatment Slope for Long Term Slope Stability (1:6)



Improved Slope by Sand Compaction Piles (1:4)



Improved Slope by Soil Cement Columns (1:3)

LEGEND


- +—+—+— Settlement gauge
- x—x—x—x— Inclinometer
- Piczometer
- |—|—|— Extensometer

ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

ARRANGEMENT OF MONITORING
 INSTRUMENT ON EACH SLOPE


JAPAN INTERNATIONAL COOPERATION AGENCY DNG. NO. 9
 TOKYO

SECTION A-A



1/100
1/500

PLAN




ROYAL IRRIGATION DEPARTMENT
THE MODEL INFRASTRUCTURE PROJECT OF
SOFT SOIL FOUNDATION FOR
THE IRRIGATION ENGINEERING CENTER PROJECT


(REFERENCE DRAWING)
GEOLOGICAL PROFILE OF
PROJECT SITE (1/2)

JAPAN INTERNATIONAL COOPERATION AGENCY TOKYO DWS. NO. 10

SECTION B-B



PLAN






ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 SOFT SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

(REFERENCE DRAWING)
 GEOLOGICAL PROFILE OF
 PROJECT SITE (2/2)

JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

FIG. NO.
 11



TYPICAL CROSS SECTION OF ACCESS ROAD.

ROYAL IRRIGATION DEPARTMENT
 THE MODEL INFRASTRUCTURE PROJECT OF
 BOPF SOIL FOUNDATION FOR
 THE IRRIGATION ENGINEERING CENTER PROJECT

(REFERENCE DRAWING)
 PLAN OF TEMPORARY WORK

JAPAN INTERNATIONAL COOPERATION AGENCY
 TOKYO

DWG. NO.
 12

そ の 他 添 付 資 料

1. 調査団派遣の経緯と目的
2. 調査団の構成
3. 調査の経緯と日程
4. 調査関係者
5. 土質調査・試験結果
6. Basic Plan

1. 調査団派遣の経緯と目的

(1) かんがい技術センター (Irrigation Engineering Center, IEC) は、タイ国における食糧増産のための農業基盤整備事業の推進に寄与するため、かんがい排水施設の計画、設計、施工にかかる適正技術を開発、整備し、併せて中堅かんがい技術者の育成する事を目的に、1985年 3月農業協同組合省王室かんがい局 (Royal Irrigation Department, RID) と実施調査団との間で署名された討議議事録 (Record of Discussion R/D) に基づきプロジェクト方式技術協力に実施、運営されている。

協力は、1985年 4月 1日から開始され、協力期間は5ヶ年であるが協力に至る経過は次の通りである。

- 1982. 1. タイ国政府によるかんがい技術センター建設とプロジェクト方式技術協力の要請
- 11. 事前調査団派遣
- 1983. 4. 基本設計調査団派遣
- 6. E/N交換 “かんがい技術センターの施設建設のための贈与に関する書簡”
- 10. 事前調査団派遣
- 1984. 10. 長期調査員派遣
- 1985. 3. 実施協議調査団派遣
- 4. プロジェクト協力開始

(2) RIDでは過去、海岸地帯の軟弱地盤上に排水路や構造物の建設を行っているが、沈下、崩壊などの種々の問題が生じている。

特に、排水路は掘削した法面勾配が非常な緩勾配であるにもかかわらず、ずへりが発生している。この様な事からRIDでは、この地域の地盤は特に強度の低い特異な性質の粘土から構成されている可能性と判断している。

(3) RIDでは、本プロジェクト協力の一環として、軟弱地盤上に農業水利施設を構築するに当たり、調査の手法、計画、設計規準の確立に関し、技術的諸問題を明らかにする為の試験水路の建設をモデルインフラ整備事業として行う事を要請した。

(4) 本実施設計調査団の派遣に先立ち、国際協力事業団 (Japan International Cooperation Agency, JICA) は、1987年11月29日より同年12月28日まで短期専門家を派遣

し、本実施設計調査の予備調査，試験水路の位置及び基本構想の策定を行った。

(5) 本調査の目的は、短期専門家の策定した基本構想に基づき、試験水路建設の為の実施設計を行うものである。

2. 調査団の構成

<u>氏名</u>	<u>担当分野</u>	<u>派遣期間</u>	<u>所属</u>
川口 徳忠	総括	63. 2. 13 ～63. 2. 26	農林水産省 農業土木 試験場 造構部 造構第一研究室長
白 杵 宣 春	業務調整	63. 2. 13 ～63. 2. 26	国際協力事業団 農業開発協力部 農業開発課長代理
越 智 博 孝	軟弱地盤 調査計画	63. 2. 13 ～63. 3. 23	(株)日本農業土木コンサ ルトンツ 海外部参事
五 明 陽一郎	排水路設計	63. 2. 13 ～63. 3. 30	(株)日本農業土木コンサ ルトンツ 海外部海外第二課長

3. 調査の経過と日程

(1) 調査の経過

調査は、基本方針 (Basic Plan) の樹立と実施設計調査の2段階に分けて行われた。基本方針は、短期専門家が策定した基本構想に基づき、IECプロジェクト専門家及びRID関係者と協議を行い取りまとめRID関係者、タイ国日本大使館及びJICAタイ事務所に報告、提出した。

その後基本方針に基づき予備設計作業に入り、RID関係者及びIECプロジェクト専門家の協力のもと試験水路法面の予備解析、予定地点の追加測量、関係資料の収集等を行った。

この予備設計の結果はフィールドレポートとしてまとめられ、RID関係者に報告、協議を行い、RID関係者、日本大使館及びJICAタイ事務所に提出した。現地での調査結果は、RID関係者のコメントを考慮し、国内での実施設計業務によって整理し、本報告書の作成を行った。

(2) 現地調査の日程

月 日	曜 日	調 査 内 容
2月13日	(土)	TG641便にてバンコク着
2月14日	(日)	TEC日本人長期専門家と打合わせ
2月15日	(月)	実施設計調査方針について団員打合わせ 資料作成
2月16日	(火)	JICAタイ事務所及び日本大使館表敬
2月17日	(水)	RIDアドバイザリーコミティ及びIEC日本人専門家、調査団 と合同会議
2月18日	(木)	プロジェクトサイト調査
2月19日	(金)	RID作業委員会、IEC日本人専門家及び調査団と合同会議
2月20日	(土)	基本方針について団員打合わせ
2月21日	(日)	基本方針案作成
2月22日	(月)	基本方針案作成、土質調査指示

月 日	曜 日	調 査 内 容
2月23日	(火)	R I D作業委員会と基本方針について打合わせ、基本方針案の修正
2月24日	(水)	R I Dアドバイザー委員会、I E C日本人専門家及び調査団と基本方針について合同会議 予備解析業務についてI E C日本人専門家及び団員で打合わせ
2月25日	(木)	R I D関係者に基本方針を提出 J I C Aタイ事務所、大使館へ基本方針の説明、提出
2月26日	(金)	団長及び業務調整帰国 現地追加測量開始 予備解析用プログラム修正開始
2月27日	(土)	予備設計作業方針の作成
2月28日	(日)	予備解析方法の取りまとめ
2月29日	(月)	I E Cコンピューターを使用し、予備解析用プログラムテストラ ン開始、現地追加測量終了 地質調査・試験結果整理
3月 1日	(火)	予備解析方法についてR I D作業委員会と打合わせ、予備解析 開始
3月 2日	(水)	予備解析用資料整理
3月 3日	(木)	現地施工業者より資料収集
3月 4日	(金)	追加測量成果整理
3月 5日	(土)	追加現場調査
3月 6日	(日)	資料整理
3月 7日	(月)	フィールドレポート作成準備
3月 8日	(火)	資料収集
3月 9日	(水)	資料収集
3月10日	(木)	施工計画案の立案
3月11日	(金)	比較検討図作成
3月12日	(土)	地盤改良工法概算工事費の算出

月 日	曜 日	調 査 内 容
3月13日	(日)	概算工事費の算出
3月14日	(月)	積算バックデータ整理 工事費比較表の作成
3月15日	(火)	フィールドレポート作成準備 予備解析継続及び取りまとめ準備
3月16日	(水)	R I D作業委員会と打合わせ
3月17日	(木)	フィールドレポート作成
3月20日	(日)	
3月21日	(月)	R I D作業委員会と打合わせ
3月22日	(火)	フィールドレポート修正
3月23日	(水)	調査団員1名(軟弱地盤調査計画)帰国
3月24日	(木)	フィールドレポート作成
3月25日	(金)	R I D関係者にフィールドレポート提出
3月26日	(土)	資料整理
3月27日	(日)	同上
3月28日	(月)	R I Dアドバイザーコミッティ, I E C専門家, 調査団で合同 会議
3月29日	(火)	J I C Aタイ事務所, 大使館にフィールドレポート提出, A I 3 1 6便にてバンコク発
3月30日	(水)	A Z 3 1 6便にて成田着

4. 調査関係者

LIST OF PERSONNEL CONCERNED

Royal Irrigation Department

Mr. Suha Thanomsingha Director General of
Royal Irrigation Department

The Advisory Committee

Mr. Choompon Chaveesuk Director of Engineering
Development Division,
Chairman

Mr. Lumsak Tejasen Director of Research and
Laboratory Division,
Member

Mr. Nipon Saihom Director of Geo-Technic
Division,
Member

Mr. Roongrueng Chulajata Director of Large Project
Construction Division,
Member

Dr. Boonyok Vadhanaphuti Director of Project Planning
Division,
Member

Mr. Skulwattana
Chantharobol Director of Irrigation
Regional Office 10,
Member

Mr. Vichai Srivaraponse Project Manager of Mae Klong
Yai,
Member

Mr. Kanob Tingsombutyut Technical Inspector Section,
Member and Secretary

The Implementation and Coordinating Working Committee

Mr. Ruangrit Ammawat Deputy Director of Engineering
Development Division,
Chairman

Dr. Supol Chirapan Chief of Special Engineering,
Chairman Assistant

Dr. Siripong Hungsapruk Chief of Criteria Development,
Member

Mr. Montien Kangsasitien	Chief of Soil Engineering Laboratory Section, Member
Mr. Sanan Siriorn	Chief of Irrigation Design in South Part Section, Member
Mr. Phonpong Kararum	Chief of Irrigation Design Work 10, Member
Mr. Sawat Naipramot	Chief of Saline Water Protection, Mae Klong Yai Project, Member
Dr. Thanu Harnpatanapanich	Secretary and Member
Mr. Sanit Natidhamakun	Technical for Operation & Maintenance Project, Member

Irrigation Engineering Center(IEC)

Mr. charuk Nonthatham	Director of IEC
Mr. Suthi Songvoravit	Deputy Director of IEC

Embassy of Japan

Mr. Katsutoshi Nagayama	First Secretary
-------------------------	-----------------

JICA Thailand Office

Mr. Ben Saito	Resident Representative
Mr. Takahito Hino	Assistant President Representat

Japanese Expert of Irrigation Engineering Center Project

Mr. Kazushige Matsuo	Team leader of IEC Project
Mr. Takuji Nakano	Expert of Design Criteria
Mr. Hitoshi Sunazawa	Expert of Construction Material and Analysis
Mr. Masaru Sasaki	Expert of Hydraulic Model
Mr. Haruoki Ebe	Expert of System Development
Mr. Youji Ebihara	Coordinator

Colombo Plan Expert

Mr. Hiroshi Kudou

Royal Irrigation Department

Mr. Narumi Ymada

Royal Irrigation Department

Mr. Yuji Ozaki

Royal Irrigation Department

STS Engineering Consultants Co., Ltd

Mr. Veera Vasinvarthana

Technical Manager

Mr. Choochart

Project Engineer

Kietkajo

5. 土質調査・試験結果

SUMMARY OF TEST RESULTS

STS ENGINEERING CONSULTANTS CO., LTD.

SUMMARY OF TEST RESULTS

PROJECT		Model Infrastructure Project		LOCATION		Charsonraj Pumping Station, Bang Bo, Samut Prakan Province.											
DATE	16/1/88	BORING No.	B-1, FV-1	JOB No.	1438	BY	CK										
				OBSERVED W.L.		= + 0.68 m.											
SAMPLE No.	DEPTH M.		WATER CONTENT %		ATTERBERG LIMIT %		WET UNIT WEIGHT γ_w	SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH γ_{m^2}				SPECIFIC GRAVITY, G_s
	FROM	TO	(LL)	(PL)	(SH)	No. 3/8"		No. 4	No. 10	No. 40	No. 200		Su	Su'	Suv	Suh	
PST-1	1.00	1.80	83.2	94.6	35.3	14.4	1.47				CH	1.63	0.21	1.74	0.89	1.25	2.66
PST-2	3.00	3.80	85.2				1.47				CH	0.96	0.29	1.18	0.40	2.5	2.65
PST-3	5.00	5.80	84.9	96.8	35.8	10.2	1.47				CH	1.24	0.37	0.75	4.16	2.5	2.68
PST-4	7.00	7.80	89.7				1.44				CH	1.67	0.49	0.99	5.09	2.5	2.65
PST-5	9.00	9.80	95.8	105.7	40.3		1.40				CH	1.95	0.59	1.08	7.10	2.5	2.63
PST-6	11.00	11.80	98.1				1.41				CH	2.38	0.55	1.27	8.94	3.75	2.65
PST-7	13.30	14.10	94.7	119.0	41.6		1.43				CH	2.99	0.78	1.18	13.73	5.0	2.68
PST-8	15.00	15.80	70.9				1.54				CH	4.65	1.30	3.70	10.13	5.0	2.67

SFS ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT Model Infrastructure Project

LOCATION Chareoniaj Pumping Station, Bang Bo, Samut Prakan Province

DATE 29/1/88

BORING No. B-2, FV-2

JOB No. 1488

BY CK

OBSERVED W.L. -0.25 m.

SAMPLE No.	DEPTH M.		WATER CONTENT %		ATTERBERG LIMIT %			WET UNIT WEIGHT g/cm ³				SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH v. v_{vm}^2					SPECIFIC GRAVITY, G
	FROM	TO	LL	PL	SH	No. 3/8"	No. 4	No. 10	No. 40	No. 200	FIELD VANE SHEAR			POCKET PENETRATION	Su		Su ₁	Su _v	Su _h			
											Su	Su ₁	Su _v							Su _h	1/2 Qp	
PST-1	1.00	1.80	87.5	32.6	20.8	1.49					CH	0.92	0.31	0.90	1.03	1.25	2.65					
PST-2	1.95	2.75									CH	1.79	0.31	2.63	-3.35	-						
PST-3	2.80	3.50									CH	0.96	0.23	0.47	3.85	-						
PST-4	4.00	4.80									CH	1.00	0.35	0.56	3.57	1.25						
PST-5	5.00	5.80	92.6	34.9	17.5	1.43					CH	1.28	0.41	1.13	2.16	1.25	2.67					
PST-6	6.00	6.80									CH	1.28	0.43	0.80	4.13	2.5						
PST-7	7.00	7.80	87.8			1.45					CH	1.30	0.43	0.80	4.28	2.5	2.66					
PST-8	8.10	8.90									CH	1.65	0.53	1.22	4.14	2.5						
PST-9	9.10	9.90	97.2	36.8	107.4	1.45					CH	1.57	0.63	1.18	4.56	2.5	2.65					
PST-10	10.10	10.90									CH	2.08	0.72	0.99	8.51	2.5						
PST-11	11.00	11.80	102.5			1.43					CH	2.50	0.68	1.93	5.83	3.75	2.65					
PST-12	12.20	13.00									CH	2.68	0.82	1.98	6.82	5.0						
PST-13	13.00	13.80									CH	3.05	0.78	2.03	9.07	5.0						
PST-14	14.00	14.80	88.9	42.3	112.4	1.45					CH	3.45	0.96	1.87	12.79	5.0	2.64					
PST-15	15.00	15.80									CH	3.75	1.08	2.90	8.73	5.0						

236
10
1/7
2/1
106
20/

STS ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT		Model Infrastructure Project		LOCATION		Charoengraj Pumping Station, Bang Bo, Samut Prakan Province											
DATE	29/1/88	BORING No.	B-3, FV-3	JOB No.	1488	BY	CK										
				OBSERVED W.L.		+0.45 m.											
SAMPLE No.	DEPTH M.		ATTERBERG LIMIT %			WET UNIT WEIGHT kN/m ³	SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH kN/m ²				POCKET PENETRATION 1/2 Q _p z	SPECIFIC GRAVITY, G
	FROM	TO	LL	PL	SL		No. 3/8"	No. 4	No. 10	No. 40		No. 200	S _u	S _u '	S _{uv}		
PST-1	1.00	1.80	94.2	34.4	18.6	1.44					CH	0.96	0.23	0.99	0.75	1.25	2.65
PST-2	2.00	2.80									CH	0.88	0.23	0.61	2.44	1.25	
PST-3	3.00	3.80									CH	1.06	0.29	0.52	4.29	2.5	
PST-4	4.00	4.80									CH	1.16	0.41	0.66	4.14	2.5	
PST-5	5.00	5.80	90.3	35.5	22.7	1.47					CH	1.16	0.37	0.52	4.98	1.25	2.65
PST-6	6.00	6.80									CH	1.41	0.41	0.89	4.42	1.25	
PST-7	7.00	7.80									CH	1.71	0.49	1.55	2.58	2.5	
PST-8	8.00	8.80									CH	1.83	0.51	1.27	5.12	2.5	
PST-9	9.00	9.80	98.4	109.1	38.2	1.44					CI	2.38	0.68	1.93	4.98	2.5	2.70
PST-10	10.00	10.80									CH	2.58	0.59	2.17	4.98	2.5	
PST-11	11.00	11.80									CH	2.74	0.80	1.79	8.40	3.75	
PST-12	12.00	12.80									CH	2.74	0.55	1.04	12.90	3.75	
PST-13	13.00	13.80	92.3	119.8	42.1	1.44					CH	3.35	0.86	2.30	9.52	3.75	2.65
PST-14	13.90	14.70									CH	4.25	1.08	3.40	9.21	3.75	
PST-15	15.00	15.80									CH	4.45	1.20	3.40	10.65	5.0	

52/

10 - 1

7/5

227

SAMPLE No.	DATE		BORING No.	B-4, FV-4	JOB No.	1488	BY	CK	OBSERVED W.L.	-0.20 m.		UNDRAINED SHEAR STRENGTH c_u m.²		POCKET PENETRATION	SPECIFIC GRAVITY, G														
	DEPTH M.									WATER CONTENT %	ATTERBERG LIMIT %		WET UNIT WEIGHT γ_w			SIEVE ANALYSIS % FINER	CLASSIFICATION	UNCONFINED SHEAR			FIELD VANE SHEAR								
	FROM	TO									LL	PL						SL	No. 3/8"	No. 4	No. 10	No. 40	No. 200	Su	Su'	Su	Su'	Su _v	Su _h
PST-1	1.00	1.80	66.4	92.0	36.3	21.8	1.52							0.69	0.12	0.88	-0.41	1.25	2.67										
	2.50													0.77	0.16														
PST-2	2.96	3.76	79.4	87.0	33.2	19.6	1.52							**	**				1.25	2.68									
	3.66													0.05	0.10														
PST-3	5.00	5.80	73.8	95.4	33.9		1.65							0.85	0.22	1.02	-0.14												
	6.20													0.85	0.16			1.25	2.65										
	7.00													0.54	0.26	0.09	3.19												
PST-4	6.99	7.79	85.3	89.3	31.5		1.50							0.97	0.14														
	7.80													0.7	0.36	1.11	0.97	2.5	2.65										
	9.00													1.09	0.18														
PST-5	9.00	9.80												1.11	0.39														
	9.80													1.29	0.40	0.92	3.47	2.5											
PST-6	11.00	11.80	96.2				1.45							1.49	0.26														
	12.83													1.94	0.31			2.5											
PST-7	13.05	13.85												2.20	0.34	0.65	11.51												
	14.41																		3.75										
PST-8	15.02	15.82	74.3				1.57							2.4	0.46	2.59	1.25												
														2.5				5.0											

Note: * use vane size 75x75 mm; ** During remol, the vane rod was sunk down.

**S.T.S ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS**

PROJECT Model Infrastructure Project				LOCATION Chareonraj Pumping Station, Bang Bo, Samut Prakan Province																		
DATE 29/1/88		BORINGNo.	FV-5	JOBNo.	1488	BY CK	OBSERVED W.L. +0.42 m.															
SAMPLE No.	DEPTH M.		WATER CONTENT %			ATTENBERG LIMIT %			WET UNIT WEIGHT W/m ³	SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH U/m ²							SPECIFIC GRAVITY, G
	FROM	TO	LL	PL	PL	PI	No. 3/8"	No. 4	No. 10	No. 40	No. 75	Su	S _{u1}		S _{uv}	S _{uh}	POCKET PENETRATION 1/2 Qp					
		1.50										0.68	0.18	0.38	2.44							
		3.50										0.96	0.23	0.56	3.29							
		5.50										1.34	0.37	1.08	2.86							
		7.50										1.93	0.51	1.79	2.72							
		9.50										2.22	0.41	1.04	9.22							
		11.50										2.58	0.55	1.60	8.37							
		12.50										3.45	0.96	2.20	10.8							
		15.50										4.45	1.16	3.76	8.39							

SIS ENGINEERING CONSULTANTS CO., LTD.
SUMMARY OF TEST RESULTS

PROJECT		Model Infrastructure Project		LOCATION		Chareonraj Pumping Station, Bang Bo, Samut Prakan Province												
DATE	14/3/88	BORING No.	B-5, FV-5'	JOB No.	1488	BY	CK											
				OBSERVED W.L.		-0.40 m.												
SAMPLE No.	DEPTH M.		WATER CONTENT %		ATTERBERG LIMIT %		WET UNIT WEIGHT γ_w	SIEVE ANALYSIS % FINER				CLASSIFICATION	UNDRAINED SHEAR STRENGTH c_u					SPECIFIC GRAVITY, G
	FROM	TO	LL	PL	SL	No. 3/8"		No. 4	No. 10	No. 40	No. 200		S_u	S_{uv}	S_{uh}	$\frac{1}{2} Q_p$	PENETRATION	
PST-1	1.00	1.80	66.8	33.3	19.3	1.57					CH	0.54	0.26	0.46	0.97	1.25	2.64	
PST-2	2.00	2.80	77.5	31.7							CH	0.69	0.16			1.25		
PST-3	3.00	3.80	93.0	36.2	21.9	1.44					CH	0.77	0.30	1.02	-0.69	1.25	2.65	
PST-4	4.00	4.80	82.6	36.0							CH	0.85	0.16					
PST-5	5.00	5.80	90.0	36.6		1.46					CH	0.79	0.26	0.65	1.67	1.25	2.66	
PST-6	6.00	6.80	88.2	35.5							CH	0.99	0.24			1.25		
PST-7	7.00	7.80	95.4	35.8		1.50					CH	1.13	0.26	0.97	2.08	2.5	2.65	
PST-8	8.00	8.80	84.9	35.2							CH	1.19	0.26			2.5		
PST-9	9.00	9.80	93.1	38.9		1.45					CH	1.33	0.30	1.57	-0.12	2.5	2.63	
PST-10	10.00	10.80	91.0	36.4							CH	1.49	0.42			3.75		
PST-11	11.00	11.80	98.8	41.8		1.40					CH	1.86	0.36	2.13	0.28	3.75	2.65	
PST-12	12.00	12.80	94.2	41.0							CH	2.12	0.44			3.75		
PST-13	13.00	13.80	100.2	42.2		1.42					CH	2.32	0.57	1.76	5.69	3.75	2.64	
PST-14	14.00	14.80	93.5	39.4							CH	2.71	0.61			5.0		
PST-15	15.00	15.80	79.2	38.0		1.50					CH	2.83	0.58	2.03	7.63	5.0	2.68	
PST-16	16.00	16.80	87.5	36.2							CH					6.25		
PST-17	17.00	17.80	70.9	34.9		1.58					CH					7.5	2.69	

Note: Undrained shear strength from "maruto" vane shear test size 75x150 and 75x75 mm.


LOG OF BORING

LOG OF BORING No. B-1, FV-1

PROJECT NAME. Model Infrastructure

LOCATION. Samut Prakan

OWNER



WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.D
WL.	B.C.R. A.C.R.
WL.	+ 0.68 m. 24 HRS. AFTER BORING.

STS.
Engineering Consultants Co., Ltd.
BANGKOK.

BORING STARTED. 12/1/88	
BORING COMPLETED. 13/1/88	
RIG. Acker	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JOB No. 1408	SHEET. 1/1

LOG OF BORING No. B-2, FV-2

PROJECT NAME. Model Infrastructure	LOCATION. Samut Prakan
OWNER	

DEPTH, M.	SAMPLE No.	TYPE OF SAMPLE	SAMPLE COST RECOVERY.	DESCRIPTION OF MATERIAL	○ Natural Water Content x Plastic Limit △ Liquid Limit (%)					○ $q_u/2$ △ q_v X $q_{o/2}$ (1/m ²) □ SPT, N (Blow/ft)										
					20	40	60	80	100	20	40	60	80							
1	PST			CLAY some shell fragment and organic matter, dark grey, very soft to soft. (CH)																
2	PST																			
3	PST																			
4	PST																			
5	PST																			
6	PST																			
7	PST																			
8	PST																			
9	PST																			
10	PST																			
11	PST				12.0 m.															
12	PST			CLAY some shell fragment, greenish grey, medium stiff. (CH)																
13	PST																			
14	PST				15.8 m.															
				↑ END OF BORING																

WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.O.
WL.	B.C.R. A.C.R.
WL.	-0.25 m. 24 HRS. AFTER BORING.

STS.
 Engineering Consultants Co., Ltd.
BANGKOK.


BORING STARTED. 25/1/88	
BORING COMPLETED. 24/1/88	
RIG. Acker	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JCB No. 1488	SHEET. 1/1

LOG OF BORING No. B-3, EV-3

PROJECT NAME. Model Infrastructure

LOCATION. Samut Prakan

OWNER



WATER LEVEL OBSERVATIONS	
W.S. OR W.D.	
B.C.R.	A.C.R.
+0.45 m 24 HRS. AFTER BORING.	


STS.
 Engineering Consultants Co., Ltd.
BANGKOK.

BORING STARTED. 17/1/88	
BORING COMPLETED. 19/1/88	
RIG. ACKER	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JOB No. 1488	SHEET. 1/1

LOG OF BORING No. B-4, EV-4

PROJECT NAME. Model Infrastructure LOCATION. Samut Prakan

OWNER



WATER LEVEL OBSERVATIONS	
WL.	W.S. OR W.D.
WL.	B.C.R. A.C.R.
WL.	-0.2 m 24 HRS. AFTER BORING.

STS.
Engineering Consultants Co., Ltd.
BANGKOK.

BORING STARTED. 20/2/88	
BORING COMPLETED. 28/2/88	
RIG. ACKER	FOREMAN. SK
DRAWN. SRY	APPROVED. CK
JCB No. 1488	SHEET. 1/1

LOG OF BORING No. B-5

PROJECT NAME. Model Infrastructure LOCATION. Samut Prakan

OWNER

DEPTH, M. ELEVATION, M.	SAMPLE No.	TYPE OF SAMPLE	SAMPLE DIST RECOVERY.	DESCRIPTION OF MATERIAL	O Natural Water Content x Plastic Limit Δ Liquid Limit (%)					○ Qu/2 ● Qu/2 Δ Qv ▲ Qv X Qp/2 (1/m ²) 2.5 5 7.5 10 □ SPT, N (Blow/ft) 20 40 60 80									
					20	40	60	80	100	20	40	60	80						
0																			
1	1	PST		CLAY some shell fragment and	X														
2	2	PST		organic matter, dark grey,	X														
3	3	PST		very soft to soft.	X														
4	4	PST		(CH)	X														
5	5	PST			X														
6	6	PST			X														
7	7	PST			X														
8	8	PST			X														
10	9	PST		10.0 m.	X														
10	10	PST			X														
11	11	PST		CLAY some shell fragment,	X														
12	12	PST		greenish grey, medium stiff.	X														
13	13	PST		(CH)	X														
15	14	PST			X														
15	15	PST			X														
16	16	PST			X														
17	17	PST		17.8 m.	X														
20				END OF BORING															

WATER LEVEL OBSERVATIONS		STS. Engineering Consultants Co., Ltd. BANGKOK.	BORING STARTED. 7/3/88	
WL.	W.S. OR W.D.		BORING COMPLETED. 9/3/88	
WL.	B.C.R. A.C.R.		RIG. ACKER	FOREMAN. SK
WL.	-0.40 m 24 HRS. AFTER BORING.		DRAWN. SRY	APPROVED. CK
			JOB No. 1488	SHEET. 1/1

DUTCH CONE PENETRATION TEST RESULTS

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-1

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	4.40	7.20	5.10	.21	4.11
.60	2	.37	5.80	9.60	6.65	.28	4.21
.90	2	.37	6.00	12.00	6.97	.44	6.40
1.00	2	.37	2.80	5.00	3.33	.16	4.80
1.20	2	.37	3.20	5.40	3.77	.16	4.24
1.40	3	.50	2.60	4.40	3.24	.13	4.01
1.60	3	.50	1.60	3.40	2.13	.13	6.09
1.80	3	.50	1.60	2.40	2.13	.06	2.91
2.00	3	.50	1.20	2.20	1.69	.07	4.14
2.20	3	.50	1.00	1.80	1.46	.06	4.09
2.40	3	.50	1.20	1.80	1.69	.04	2.37
2.60	4	.64	1.40	2.20	2.05	.06	2.92
2.80	4	.64	1.20	2.00	1.83	.06	3.28
3.00	4	.64	1.00	2.00	1.60	.07	4.35
3.20	4	.64	1.20	1.80	1.83	.04	2.19
3.40	4	.64	1.00	1.80	1.60	.06	3.73
3.60	5	.78	1.20	2.00	1.97	.06	3.05
3.80	5	.78	1.00	1.80	1.74	.06	3.43
4.00	5	.78	1.00	1.80	1.74	.06	3.43
4.20	5	.78	1.00	1.80	1.74	.06	3.43
4.40	5	.78	.80	1.60	1.52	.06	3.93
4.60	6	.91	.60	1.60	1.65	.06	3.62
4.80	6	.91	1.20	2.00	2.10	.06	2.86
5.00	6	.91	1.00	1.80	1.87	.06	3.19
5.20	6	.91	1.00	2.00	1.87	.07	3.73
5.40	6	.91	1.00	2.00	1.87	.07	3.73
5.60	7	1.05	1.40	2.40	2.46	.07	2.84
5.80	7	1.05	1.60	2.60	2.68	.07	2.61
6.00	7	1.05	1.60	2.60	2.68	.07	2.61
6.20	7	1.05	1.80	2.60	2.90	.06	2.07

STS ENGINEERING CONSULTANTS CO., LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG SO

TEST NO D-1

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.39	7	1.85	1.80	2.60	2.90	.06	2.07
6.59	8	1.19	2.00	3.20	3.26	.09	2.76
6.79	8	1.19	2.00	3.20	3.26	.09	2.76
6.99	8	1.19	1.80	2.40	3.04	.04	1.31
7.19	8	1.19	1.90	2.60	3.04	.06	1.97
7.39	9	1.32	1.60	2.40	2.95	.06	2.03
7.59	9	1.32	1.60	2.40	2.95	.06	2.03
7.79	9	1.32	1.80	2.60	3.17	.06	1.83
7.99	9	1.32	1.60	2.80	2.95	.09	3.05
8.19	9	1.32	1.00	2.20	2.20	.09	3.93
8.39	10	1.46	1.20	2.20	2.65	.07	2.64
8.59	10	1.46	1.20	2.40	2.65	.09	3.40
8.79	10	1.46	1.40	2.60	2.87	.09	3.13
8.99	10	1.46	1.20	2.60	2.65	.10	3.77
9.19	10	1.46	1.40	2.80	2.87	.10	3.48
9.39	11	1.60	1.20	2.40	2.79	.09	3.23
9.59	11	1.60	1.60	2.60	3.23	.07	2.17
9.79	11	1.60	2.00	3.20	3.67	.09	2.45
9.99	11	1.60	1.80	3.20	3.45	.10	2.89
10.20	11	1.60	1.60	2.80	3.23	.09	2.79
10.40	12	1.73	2.00	3.40	3.80	.10	2.63
10.60	12	1.73	2.20	3.40	4.02	.09	2.23
10.80	12	1.73	2.20	3.80	4.02	.12	2.99
11.00	12	1.73	2.20	3.40	4.02	.09	2.23
11.20	12	1.73	2.20	3.60	4.02	.10	2.48
11.40	13	1.87	2.00	3.60	3.94	.12	3.04
11.60	13	1.87	2.40	3.80	4.38	.10	2.28
11.80	13	1.87	2.40	3.80	4.38	.10	2.28
12.00	13	1.87	2.20	3.60	4.16	.10	2.40
12.20	13	1.87	3.00	4.20	5.05	.09	1.78

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-1

DATE 30 JAN 88

TESTED BY PS


APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kn/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.40	14	2.00	3.00	4.50	5.18	.11	2.12
12.60	14	2.00	3.20	4.50	5.40	.10	1.85
12.80	14	2.00	2.80	4.20	4.96	.10	2.02
13.00	14	2.00	2.40	3.80	4.51	.10	2.21
13.20	14	2.00	3.40	4.30	5.62	.07	1.24
13.40	15	2.14	3.40	5.60	5.76	.16	2.77
13.60	15	2.14	2.80	5.20	5.10	.18	3.53
13.80	15	2.14	3.20	5.80	5.54	.19	3.43
14.00	15	2.14	3.20	5.80	5.54	.19	3.43
14.20	15	2.14	3.80	6.40	6.20	.19	3.06
14.40	16	2.28	3.80	6.40	6.34	.19	2.99
14.60	16	2.28	3.80	6.80	6.34	.22	3.46
14.80	16	2.28	3.60	6.00	6.12	.18	2.94
15.00	16	2.28	4.20	6.80	6.79	.19	2.80
15.20	17	2.41	4.40	8.80	7.14	.32	4.48
15.40	17	2.41	4.80	10.20	7.58	.40	5.27
15.60	17	2.41	4.20	9.60	6.92	.40	5.78
15.80	17	2.41	4.20	8.80	6.92	.34	4.91
16.00	17	2.41	4.20	8.60	6.92	.32	4.62
16.20	17	2.41	4.60	9.40	7.36	.35	4.75
16.40	18	2.55	4.40	8.60	7.28	.31	4.26
16.60	18	2.55	4.40	8.20	7.28	.28	3.84
16.80	18	2.55	5.20	10.40	8.17	.38	4.65
17.00	18	2.55	5.40	9.80	8.39	.32	3.81
17.20	18	2.55	5.80	10.80	8.83	.37	4.19
17.40	19	2.69	7.00	12.00	10.30	.37	3.59
17.60	19	2.69	6.40	12.80	9.63	.47	4.88
17.80	19	2.69	6.20	11.20	9.41	.37	3.93
18.00	19	2.69	5.60	10.60	8.75	.37	4.23
18.20	19	2.69	6.40	11.80	9.63	.40	4.15

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
 LOCATION BANG B0
 TEST NO D-1 DATE 30 JAN 88
 TESTED BY PS APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	8.40	13.80	11.98	.48	3.34
18.60	20	2.82	8.40	13.80	11.98	.48	3.34
18.80	20	2.82	8.20	15.80	11.76	.56	4.76
19.00	20	2.82	9.00	15.80	12.64	.50	3.95
19.20	20	2.82	8.00	14.00	11.54	.44	3.81
19.40	21	2.96	6.00	11.00	9.46	.37	3.91
19.60	21	2.96	8.00	12.00	11.68	.38	2.57
19.80	21	2.96	18.00	25.00	39.34	1.00	2.55
20.00	21	2.96	20.00	29.00	43.65	1.29	2.96
20.20	21	2.96	16.00	29.00	35.04	1.86	5.33
20.40	22	3.10	16.00	30.00	35.13	2.01	5.71
20.60	22	3.10	19.00	34.00	41.64	2.15	5.17



STS ENGINEERING CONSULTANTS CO., LTD.


TEST NO D-1

LOCAL FRICTION, GF (KSC) 3 2.5 2 1.5 1 0.5 0

DEPTH FROM GROUND SURFACE, M 15 10 5 0

CONE RESISTANCE, QC (KSC) 40 35 30 25 20 15 10 5 0

FRICTION RATIO, % 8 7 6 5 4 3 2 1 0



STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-2

DATE 30 JAN 83

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	2.20	3.80	2.66	.12	4.50
.60	2	.37	2.20	3.80	2.66	.12	4.50
.80	3	.50	1.80	3.20	2.35	.10	4.25
1.00	3	.50	1.60	2.80	2.13	.09	4.22
1.20	3	.50	1.40	2.60	1.91	.09	4.71
1.40	3	.50	1.60	2.80	2.13	.09	4.22
1.60	3	.50	1.20	2.20	1.69	.07	4.14
1.80	4	.64	1.00	1.80	1.60	.06	3.73
2.00	4	.64	1.20	2.20	1.83	.07	3.83
2.20	4	.64	.90	1.80	1.39	.07	5.05
2.40	4	.64	1.00	2.00	1.60	.07	4.35
2.60	4	.64	1.60	3.00	2.27	.10	4.40
2.80	5	.78	.80	1.80	1.52	.07	4.58
3.00	5	.78	1.20	2.20	1.97	.07	3.55
3.20	5	.78	1.20	2.20	1.97	.07	3.55
3.40	5	.78	1.00	2.00	1.74	.07	4.00
3.60	5	.78	1.00	2.00	1.74	.07	4.00
3.80	6	.91	.80	1.80	1.65	.07	4.22
4.00	6	.91	1.00	1.80	1.87	.06	3.19
4.20	6	.91	1.00	1.80	1.87	.06	3.19
4.40	6	.91	.80	1.60	1.65	.06	3.62
4.60	6	.91	.80	1.60	1.65	.06	3.62
4.80	7	1.05	.80	1.80	1.79	.07	3.90
5.00	7	1.05	.80	1.80	1.79	.07	3.90
5.20	7	1.05	.80	1.80	1.79	.07	3.90
5.40	7	1.05	1.00	1.80	2.01	.06	2.97
5.60	7	1.05	1.00	1.80	2.01	.06	2.97
5.80	7	1.05	1.00	1.80	2.30	.06	2.52
5.90	8	1.19	1.20	2.00	2.15	.06	2.78
6.00	8	1.19	1.00	1.80	2.15	.06	2.78
6.20	8	1.19	.80	1.60	1.93	.06	3.10

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-2

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS. kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.39	8	1.19	1.20	2.00	2.38	.06	2.52
6.59	8	1.19	1.20	2.00	2.38	.06	2.52
6.79	9	1.32	1.20	2.20	2.51	.07	2.79
6.99	9	1.32	1.20	2.20	2.51	.07	2.79
7.19	9	1.32	1.20	2.20	2.51	.07	2.79
7.39	9	1.32	1.20	2.20	2.51	.07	2.79
7.59	9	1.32	1.20	2.20	2.51	.07	2.79
7.79	10	1.46	1.20	2.20	2.65	.07	2.64
7.99	10	1.46	1.20	2.20	2.65	.07	2.64
8.19	10	1.46	1.20	2.40	2.65	.09	3.40
8.39	10	1.46	1.20	2.40	2.65	.09	3.40
8.59	10	1.46	1.20	2.40	2.65	.09	3.40
8.79	11	1.60	1.20	2.40	2.79	.09	3.23
8.99	11	1.60	1.20	2.40	2.79	.09	3.23
9.19	11	1.60	1.20	2.40	2.79	.09	3.23
9.39	11	1.60	1.40	2.60	3.01	.09	2.99
9.59	11	1.60	1.40	2.60	3.01	.09	2.99
9.79	12	1.73	1.40	2.60	3.14	.09	2.86
9.99	12	1.73	1.40	2.60	3.14	.09	2.86
10.20	12	1.73	1.40	2.60	3.14	.09	2.86
10.40	12	1.73	1.60	3.40	3.36	.13	3.87
10.60	12	1.73	1.40	3.20	3.14	.13	4.14
10.80	13	1.87	1.80	3.80	3.72	.15	4.03
11.00	13	1.87	1.80	3.80	3.72	.15	4.03
11.20	13	1.87	1.80	3.80	3.72	.15	4.03
11.40	13	1.87	2.00	4.20	3.94	.16	4.05
11.60	13	1.87	2.20	4.60	4.16	.18	4.32
11.80	14	2.00	2.40	4.80	4.51	.18	3.98
12.00	14	2.00	2.20	4.60	4.29	.18	4.19
12.20	14	2.00	2.40	4.60	4.51	.16	3.54

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-2

DATE 30 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.40	14	2.00	2.60	4.80	4.74	.16	3.38
12.60	14	2.00	2.60	4.80	4.74	.16	3.38
12.80	15	2.14	2.60	4.80	4.88	.16	3.28
13.00	15	2.14	2.80	5.20	5.10	.18	3.53
13.20	15	2.14	3.00	5.40	5.32	.18	3.38
13.40	15	2.14	3.20	5.80	5.54	.19	3.43
13.60	15	2.14	3.20	6.20	5.54	.22	3.97
13.80	16	2.28	3.40	6.60	5.90	.24	4.06
14.00	16	2.28	3.20	6.40	5.68	.24	4.22
14.20	16	2.28	3.20	6.80	5.68	.21	3.69
14.40	16	2.28	4.00	6.80	6.57	.21	3.20
14.60	16	2.28	4.00	7.40	6.57	.25	3.80
14.80	17	2.41	3.40	7.20	6.03	.28	4.64
15.00	17	2.41	3.80	7.80	6.47	.24	3.70
15.20	17	2.41	3.80	7.80	6.47	.24	3.70
15.40	17	2.41	3.80	7.20	6.47	.25	3.86
15.60	17	2.41	3.60	6.80	6.25	.24	3.83
15.80	18	2.55	3.80	7.20	6.61	.25	3.78
16.00	18	2.55	4.00	7.20	6.84	.24	3.51
16.20	18	2.55	4.60	8.80	7.50	.25	3.33
16.40	18	2.55	4.40	7.80	7.28	.25	3.43
16.60	18	2.55	4.80	8.60	7.72	.28	3.62
16.80	19	2.69	5.80	9.80	8.97	.30	3.34
17.00	19	2.69	5.80	10.40	8.97	.34	3.79
17.20	19	2.69	6.00	10.80	9.19	.35	3.81
17.40	19	2.69	6.60	11.40	9.86	.35	3.55
17.60	19	2.69	6.80	11.80	10.08	.37	3.67
17.80	20	2.82	7.80	12.40	10.43	.40	3.83
18.00	20	2.82	7.40	12.80	10.87	.40	3.68
18.20	20	2.82	8.00	14.00	11.54	.44	3.81

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
LOCATION BANG BO
TEST NO D-2 DATE 30 JAN 88
TESTED BY PS APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	6.40	12.40	9.76	.44	4.50
18.60	20	2.82	7.20	11.40	10.65	.31	2.91
18.80	21	2.96	8.00	14.00	11.68	.44	3.77
19.00	21	2.96	8.40	14.60	12.12	.46	3.79
19.20	21	2.96	9.40	15.80	13.23	.47	3.55
19.40	21	2.96	10.00	17.00	13.89	1.55	11.18
19.60	21	2.96	10.00	17.00	13.89	1.55	11.18
19.80	22	3.10	9.20	15.80	13.15	.49	3.73
20.00	22	3.10	10.00	16.00	14.03	1.40	10.04
20.20	22	3.10	10.00	16.00	14.03	1.40	10.04
20.40	22	3.10	26.00	34.00	56.71	1.14	2.03
20.60	22	3.10	26.00	37.00	56.71	1.57	2.70

TEST NO. D-2

LOCAL FRICTION, SF (KSC)

.5

1

1.5

2

FRICTION RATIO, %

CONE RESISTANCE, QC (KSC)

0

10

20

30

40

50

60

70

80

10

15

20

25

30

35

40

45

50

55

60

65

70

75

80

85

90

95

100

105

110

115

120

125

130

QC


SF

DEPTH FROM GROUND SURFACE, M


SIS ENGINEERING CONSULTANTS CO., LTD.

TEST NO. D-2


LOCAL FRICTION, QF (KSC)



CONE RESISTANCE, QC (KSC)



FRICTION RATIO, %



DEPTH FROM GROUND SURFACE, M

STE ENGINEERING CONSULTANTS CO., LTD.

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-3

DATE 29 JAN 88

TESTED BY FS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.60	2	.37	1.20	2.60	1.56	.10	6.41
.80	3	.50	2.20	4.80	2.79	.19	6.79
1.00	3	.50	2.40	4.20	3.81	.13	4.31
1.20	3	.50	1.20	2.40	1.69	.09	5.33
1.40	3	.50	1.20	2.40	1.69	.09	5.33
1.60	3	.50	1.20	2.40	1.69	.09	5.33
1.80	4	.64	1.40	2.20	2.05	.06	2.92
2.00	4	.64	.80	1.80	1.38	.07	5.05
2.20	4	.64	.90	1.20	1.38	.03	2.16
2.40	4	.64	.60	1.80	1.16	.03	2.57
2.60	4	.64	.60	1.20	1.16	.04	3.43
2.80	5	.78	.60	1.20	1.30	.04	3.06
3.00	5	.78	.60	1.20	1.30	.04	3.06
3.20	5	.78	.60	1.40	1.30	.06	4.60
3.40	5	.78	.40	1.20	1.08	.06	5.53
3.60	5	.78	.40	.80	1.08	.03	2.77
3.80	6	.91	.40	.80	1.21	.03	2.47
4.00	6	.91	.40	.80	1.21	.03	2.47
4.20	6	.91	.60	.80	1.43	.01	.70
4.40	6	.91	.80	1.80	1.65	.07	4.22
4.60	6	.91	.80	2.00	1.65	.09	5.43
4.80	7	1.05	.80	1.80	1.79	.07	3.90
5.00	7	1.05	.80	1.80	1.79	.07	3.90
5.20	7	1.05	.80	1.80	1.79	.07	3.90
5.40	7	1.05	.80	2.00	1.79	.09	5.01
5.60	7	1.05	.80	2.00	1.79	.09	5.01
5.80	8	1.19	.80	1.80	1.93	.07	3.61
6.00	8	1.19	.80	1.60	1.93	.05	3.10
6.20	8	1.19	.80	1.40	1.93	.04	2.87
6.39	8	1.19	.80	1.80	1.93	.07	3.61

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-3

DATE 29 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.59	8	1.19	.80	1.80	1.93	.07	3.61
6.79	9	1.32	.80	1.80	2.06	.07	3.39
6.99	9	1.32	1.00	2.00	2.29	.07	3.06
7.19	9	1.32	.80	1.80	2.06	.07	3.39
7.39	9	1.32	.80	2.00	2.06	.09	4.35
7.59	9	1.32	1.20	2.20	2.51	.07	2.79
7.79	10	1.46	1.00	2.00	2.42	.07	2.89
7.99	10	1.46	1.20	2.20	2.65	.07	2.64
8.19	10	1.46	1.20	2.20	2.65	.07	2.64
8.39	10	1.46	1.20	2.20	2.65	.07	2.64
8.59	10	1.46	1.20	2.20	2.65	.07	2.64
8.79	11	1.60	1.00	2.00	2.56	.07	2.73
8.99	11	1.60	1.00	2.00	2.56	.07	2.73
9.19	11	1.60	1.20	2.20	2.79	.07	2.51
9.39	11	1.60	1.40	2.20	3.01	.06	1.99
9.59	11	1.60	1.40	2.40	3.01	.07	2.32
9.79	12	1.73	1.60	2.60	3.36	.07	2.88
9.99	12	1.73	1.60	2.80	3.36	.09	2.68
10.20	12	1.73	1.60	2.80	3.36	.09	2.68
10.40	12	1.73	1.60	2.80	3.36	.09	2.68
10.60	12	1.73	1.80	3.00	3.59	.15	4.18
10.80	13	1.87	1.40	3.00	3.28	.12	3.66
11.00	13	1.87	1.80	4.00	3.72	.16	4.20
11.20	13	1.87	2.00	4.00	3.94	.15	3.80
11.40	13	1.87	2.00	4.00	3.94	.15	3.80
11.60	13	1.87	2.00	4.00	3.94	.15	3.80
11.80	14	2.00	2.00	4.00	4.07	.15	3.68
12.00	14	2.00	2.20	4.20	4.29	.15	3.49
12.20	14	2.00	2.40	4.60	4.51	.16	3.54
12.40	14	2.00	2.60	4.60	4.74	.15	3.16

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-3

DATE 29 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, $\frac{kg}{cm^2}$	CONE READING, $\frac{kg}{cm}$	CONE&JACKET READING, $\frac{kg}{cm}$	CONE RESISTANCE, $\frac{kg}{cm^2}$	LOCAL FRICTION, $\frac{kg}{cm^2}$	FRICTION RATIO, %
12.60	14	2.00	2.60	4.80	4.74	.16	3.38
12.80	15	2.14	2.60	4.60	4.88	.15	3.07
13.00	15	2.14	3.20	5.40	5.54	.16	2.89
13.20	15	2.14	3.60	5.80	5.98	.16	2.67
13.40	15	2.14	3.60	6.40	5.99	.21	3.51
13.60	15	2.14	3.40	6.40	5.76	.22	3.82
13.80	16	2.28	3.40	6.40	5.90	.22	3.72
14.00	16	2.28	4.20	7.80	6.79	.27	3.97
14.20	16	2.28	3.80	6.80	6.34	.22	3.46
14.40	16	2.28	3.20	6.60	5.68	.25	4.40
14.60	16	2.28	2.80	6.40	5.24	.27	5.15
14.80	17	2.41	3.80	6.80	6.47	.22	3.40
15.00	17	2.41	4.20	6.40	6.92	.16	2.31
15.20	17	2.41	4.60	6.40	7.36	.13	1.76
15.40	17	2.41	4.40	6.40	7.14	.15	2.10
15.60	17	2.41	4.20	8.00	6.92	.28	4.04
15.80	18	2.55	4.60	8.00	7.50	.25	3.33
16.00	18	2.55	5.00	9.00	7.94	.30	3.77
16.20	18	2.55	4.80	8.80	7.72	.30	3.88
16.40	18	2.55	5.00	8.80	7.94	.28	3.52
16.60	18	2.55	5.00	8.80	7.94	.28	3.52
16.80	19	2.69	4.20	8.40	7.20	.31	4.30
17.00	19	2.69	5.60	9.40	8.75	.28	3.20
17.20	19	2.69	5.20	9.40	8.31	.31	3.73
17.40	19	2.69	5.00	9.20	8.88	.31	3.83
17.60	19	2.69	6.40	10.20	9.63	.28	2.90
17.80	20	2.82	6.20	10.20	9.54	.30	3.14
18.00	20	2.82	7.00	13.80	16.43	.50	4.79
18.20	20	2.82	6.80	10.80	9.32	.35	3.75
18.40	20	2.82	6.40	9.40	9.76	.22	2.25

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO


TEST NO D-3

DATE 29 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS. kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.60	20	2.82	6.20	9.60	9.54	.25	2.62
18.80	21	2.96	6.80	9.80	10.35	.22	2.13
19.00	21	2.96	7.80	13.80	11.45	.44	3.84
19.20	21	2.96	7.80	13.80	11.45	.44	3.84
19.40	21	2.96	7.20	12.80	10.79	.41	3.80
19.60	21	2.96	7.60	13.20	11.23	.41	3.65
19.80	22	3.10	8.20	14.40	12.04	.46	3.82
20.00	22	3.10	14.00	21.00	18.46	1.83	9.92
20.20	22	3.10	15.00	27.00	19.57	2.61	13.38
20.40	22	3.10	18.00	29.00	39.48	1.57	4.00



S.T.S. ENGINEERING CONSULTANTS CO., LTD.

TEST NO D-3

LOCAL FRICTION, QF (KSC)

0 0.5 1 1.5 2 2.5 3


CONE RESISTANCE, QC (KSC)

0 5 10 15 20 25 30 35 40

FRICTION RATIO, %

0 3 6 9 12 15

DEPTH FROM GROUND SURFACE, M



STB ENGINEERING CONSULTANTS CO., LTD.

STS ENGINEERING CONSULTANTS CO., LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
LOCATION BANG BO
TEST NO D-4
TESTED BY PS

DATE 31 JAN 88
APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	1.20	2.60	1.56	.10	6.41
.60	2	.37	1.20	2.60	1.56	.10	6.41
.80	3	.50	1.00	2.00	1.46	.07	4.77
1.00	3	.50	1.20	2.20	1.69	.07	4.14
1.20	3	.50	.60	1.60	1.02	.07	6.83
1.40	3	.50	.60	1.40	1.02	.06	5.85
1.60	3	.50	.60	1.40	1.02	.06	5.85
1.80	4	.64	.80	1.80	1.38	.07	5.05
2.00	4	.64	1.60	2.60	2.27	.07	3.08
2.20	4	.64	.80	1.80	1.38	.07	5.05
2.40	4	.64	.80	1.80	1.38	.07	5.05
2.60	4	.64	.80	1.60	1.38	.06	4.33
2.80	5	.78	.80	1.60	1.52	.06	3.93
3.00	5	.78	.60	1.40	1.30	.06	4.60
3.20	5	.78	.60	1.20	1.30	.04	3.06
3.40	5	.78	.80	1.40	1.52	.04	2.62
3.60	5	.78	.60	1.40	1.30	.06	4.60
3.80	6	.91	.60	1.60	1.43	.07	4.88
4.00	6	.91	.60	1.20	1.43	.04	2.79
4.20	6	.91	.60	1.20	1.43	.04	2.79
4.40	6	.91	.60	1.40	1.43	.06	4.18
4.60	6	.91	.80	1.60	1.65	.06	3.62
4.80	7	1.05	.80	1.60	1.79	.06	3.34
5.00	7	1.05	.80	1.60	1.79	.06	3.34
5.20	7	1.05	1.00	1.80	2.01	.06	2.97
5.40	7	1.05	.80	1.60	1.79	.06	3.34
5.60	7	1.05	.80	1.60	1.79	.06	3.34
5.80	8	1.19	.80	1.60	1.93	.06	3.10
6.00	8	1.19	.80	1.80	1.93	.07	3.61
6.20	8	1.19	.80	1.60	1.93	.06	3.10

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-4

DATE 31 JAN 88

TESTED BY PS

APPROVED BY AN

DEPTH, m.	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.39	9	1.19	1.00	2.20	2.15	.09	4.17
6.59	9	1.19	1.00	2.20	2.15	.09	4.17
6.79	9	1.32	1.00	2.00	2.28	.07	3.06
6.99	9	1.32	1.00	2.00	2.28	.07	3.06
7.19	9	1.32	1.20	2.00	2.51	.06	2.39
7.39	9	1.32	1.20	2.20	2.51	.07	2.79
7.59	9	1.32	1.20	2.20	2.51	.07	2.79
7.79	10	1.46	1.20	2.20	2.65	.07	2.64
7.99	10	1.46	1.20	2.20	2.65	.07	2.64
8.19	10	1.46	1.20	2.40	2.65	.09	3.40
8.39	10	1.46	1.20	2.40	2.65	.09	3.40
8.59	10	1.46	1.20	2.40	2.65	.09	3.40
8.79	11	1.60	1.40	2.40	3.01	.07	2.32
8.99	11	1.60	1.40	2.40	3.01	.07	2.32
9.19	11	1.60	1.40	2.60	3.01	.09	2.99
9.39	11	1.60	1.40	2.60	3.01	.09	2.99
9.59	11	1.60	1.40	2.80	3.01	.16	3.32
9.79	12	1.73	1.20	2.60	2.92	.10	3.42
9.99	12	1.73	1.40	2.80	3.14	.10	3.18
10.20	12	1.73	1.20	2.60	2.92	.10	3.42
10.40	12	1.73	1.20	2.60	2.92	.10	3.42
10.60	12	1.73	1.40	2.60	3.14	.09	2.86
10.80	13	1.87	1.40	3.20	3.28	.13	3.96
11.00	13	1.87	1.40	3.20	3.28	.13	3.96
11.20	13	1.87	1.40	3.60	3.28	.16	4.88
11.40	13	1.87	1.80	3.80	3.72	.15	4.03
11.60	13	1.87	1.60	3.60	3.50	.15	4.28
11.80	14	2.00	2.40	4.20	4.51	.13	2.88
12.00	14	2.00	2.20	4.20	4.29	.15	3.49
12.20	14	2.00	2.00	4.00	4.07	.15	3.68

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE
LOCATION BANG BO
TEST NO D-4
TESTED BY PS

DATE 31 JAN 88
APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.40	14	2.00	2.20	4.40	4.29	.16	3.72
12.60	14	2.00	2.40	4.80	4.51	.18	3.98
12.80	15	2.14	2.80	5.40	5.10	.19	3.72
13.00	15	2.14	2.80	5.40	5.10	.19	3.72
13.20	15	2.14	3.80	6.40	6.20	.19	3.86
13.40	15	2.14	3.60	6.40	5.98	.21	3.51
13.60	15	2.14	3.40	6.40	5.75	.22	3.82
13.80	16	2.28	3.60	6.40	6.12	.21	3.43
14.00	16	2.28	3.40	6.40	5.90	.22	3.72
14.20	16	2.28	4.00	7.20	6.57	.24	3.65
14.40	16	2.28	4.40	7.60	7.01	.24	3.42
14.60	16	2.28	4.00	7.00	6.57	.22	3.35
14.80	17	2.41	3.60	6.40	6.25	.21	3.36
15.00	17	2.41	3.40	6.00	6.03	.19	3.15
15.20	17	2.41	4.20	7.00	6.92	.21	3.03
15.40	17	2.41	4.80	8.20	7.58	.25	3.30
15.60	17	2.41	4.00	8.00	6.70	.30	4.48
15.80	18	2.55	3.90	7.80	6.61	.28	4.23
16.00	18	2.55	4.00	7.80	6.84	.28	4.09
16.20	18	2.55	4.60	7.80	7.50	.24	3.20
16.40	18	2.55	4.40	7.80	7.28	.25	3.43
16.60	18	2.55	5.20	8.20	8.17	.22	2.63
16.80	19	2.69	5.00	9.00	8.88	.30	3.71
17.00	19	2.69	5.20	9.00	8.31	.29	3.37
17.20	19	2.69	4.80	9.00	7.86	.31	3.94
17.40	19	2.69	5.60	8.80	8.75	.24	2.74
17.60	19	2.69	4.80	8.60	7.86	.28	3.56
17.80	20	2.82	6.40	10.40	9.76	.30	3.07
18.00	20	2.82	6.80	10.60	10.21	.28	2.74
18.20	20	2.82	6.20	10.40	9.54	.31	3.25

STS ENGINEERING CONSULTANTS CO., LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG EO


TEST NO D-4

DATE 31 JAN 88

TESTED BY PS

APROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	7.00	11.80	10.43	.35	3.35
18.60	20	2.82	7.80	12.40	11.31	.34	3.00
18.80	21	2.96	7.00	12.20	10.57	.38	3.59
19.00	21	2.96	6.80	11.20	10.35	.32	3.09
19.20	21	2.96	6.40	10.80	9.90	.32	3.23
19.40	21	2.96	7.00	11.20	10.57	.31	2.93
19.60	21	2.96	7.00	11.40	10.57	.32	3.03
19.80	22	3.10	12.00	19.00	16.25	1.69	10.42
20.00	22	3.10	17.00	25.00	37.33	1.14	3.08
20.20	22	3.10	17.00	25.00	37.33	1.14	3.08
20.40	22	3.10	17.00	30.00	37.33	1.86	5.00
20.60	22	3.10	22.00	36.00	48.10	2.01	4.18



STS ENGINEERING CONSULTANTS CO., LTD.

TEST NO. D-4

LOCAL FRICTION, QF (KSC)

2.5

1

1.5

2

CONE RESISTANCE, QC (KSC)

FRICTION RATIO, %

12

10

8

6

4

2

DEPTH FROM GROUND SURFACE, M

15

14

13

12

11

10

9

8

7

6

5

4

3

2

1

0 0.5 1 1.5 2 2.5 3 3.5 4 4.5 5 5.5 6 6.5 7 7.5 8 8.5 9 9.5 10 10.5 11 11.5 12

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-5

DATE 31 JAN 88

TESTED BY PS

APPROVED BY AH

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kn/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
.40	2	.37	1.80	3.80	2.22 /	.15	6.74
.60	2	.37	1.80	2.00	1.33	.07	5.23
.80	3	.50	.80	1.90	1.24	.07	5.61
1.00	3	.50	.60	1.60	1.02 /	.07	6.83
1.20	3	.50	.60	1.40	1.02	.06	5.85
1.40	3	.50	.60	1.40	1.02	.06	5.85
1.60	3	.50	.60	1.40	1.02	.06	5.85
1.80	4	.64	.60	1.40	1.16	.06	5.15
2.00	4	.64	.80	1.60	1.38 /	.06 /	4.33
2.20	4	.64	.60	1.40	1.16	.06	5.15
2.40	4	.64	.80	1.40	1.38	.04	2.88
2.60	4	.64	.40	1.20	.94	.06	6.36
2.80	5	.78	.40	1.60	1.08	.09	8.30
3.00	5	.78	.80	1.40	1.52 /	.04	2.62
3.20	5	.78	.60	1.20	1.30	.04	3.06
3.40	5	.78	.60	1.20	1.30	.04	3.06
3.60	5	.78	1.00	1.80	1.74	.06	3.43
3.80	6	.91	1.00	1.80	1.87	.06	3.19
4.00	6	.91	.80	1.60	1.65 /	.06 /	3.62
4.20	6	.91	.60	1.40	1.43	.06	4.18
4.40	6	.91	.60	1.40	1.43	.06	4.18
4.60	6	.91	.60	1.40	1.43	.06	4.18
4.80	7	1.05	.80	1.60	1.79	.06	3.34
5.00	7	1.05	.80	1.80	1.79 /	.07	3.90
5.20	7	1.05	.60	1.80	1.79	.07	3.90
5.40	7	1.05	1.00	2.00	2.01	.07	3.47
5.60	7	1.05	1.20	2.00	2.24	.06	2.68
5.80	7	1.05	1.20	2.20	2.38	.07	2.94
6.00	8	1.19	.80	2.00	1.93 /	.09	4.65
6.20	8	1.19	1.00	2.20	2.15	.09	4.17

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-5

DATE 31 JAN 83

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
6.39	9	1.19	1.20	2.20	2.38	.07	2.94
6.59	9	1.19	1.20	2.20	2.38	.07	2.94
6.79	9	1.32	1.40	2.40	2.73	.07	2.56
6.99	9	1.32	1.20	2.00	2.51	.06	2.39
7.19	9	1.32	1.20	2.20	2.51	.07	2.79
7.39	9	1.32	1.40	2.20	2.73	.06	2.20
7.59	9	1.32	1.40	2.20	2.73	.06	2.20
7.79	10	1.46	1.40	2.40	2.87	.07	2.44
7.99	10	1.46	1.20	2.00	2.65	.06	2.26
8.19	10	1.46	1.40	2.20	2.87	.06	2.09
8.39	10	1.46	1.60	3.40	3.09	.13	4.20
8.59	10	1.46	2.00	3.00	3.53	.07	1.98
8.79	11	1.60	1.60	2.40	3.23	.06	1.86
8.99	11	1.60	1.60	2.20	3.23	.04	1.24
9.19	11	1.60	1.60	2.40	3.23	.06	1.86
9.39	11	1.60	1.60	2.40	3.23	.06	1.86
9.59	11	1.60	1.80	2.80	3.45	.07	2.03
9.79	12	1.73	2.20	3.20	4.02	.12	2.98
9.99	12	1.73	1.80	3.20	3.58	.10	2.79
10.20	12	1.73	1.80	3.40	3.58	.12	3.35
10.40	12	1.73	1.80	3.60	3.58	.13	3.63
10.60	12	1.73	2.00	3.80	3.80	.13	3.42
10.80	13	1.87	2.20	4.00	4.16	.13	3.12
11.00	13	1.87	2.00	3.60	3.94	.12	3.04
11.20	13	1.87	2.20	3.80	4.16	.12	2.88
11.40	13	1.87	2.40	4.00	4.38	.12	2.73
11.60	13	1.87	2.20	4.00	4.16	.13	3.12
11.80	14	2.00	2.20	4.20	4.29	.15	3.49
12.00	14	2.00	2.00	3.80	4.07	.13	3.19
12.20	14	2.00	2.80	4.60	4.96	.13	2.62

STS ENGINEERING CONSULTANTS CO. LTD.
DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG SO

TEST NO D-5

DATE 31 JAN 68

TESTED BY PS

APPROVED BY AN

DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
12.40	14	2.00	3.20	5.40	5.40	.16	2.96
12.60	14	2.00	3.00	5.60	5.18	.19	3.67
12.80	15	2.14	2.60	4.80	4.89	.16	3.28
13.00	15	2.14	2.40	4.60	4.65	.16	3.43
13.20	15	2.14	3.20	5.40	5.54	.16	2.89
13.40	15	2.14	3.20	5.60	5.54	.18	3.25
13.60	15	2.14	3.40	6.20	5.76	.21	3.64
13.80	16	2.28	3.20	6.20	5.69	.22	3.87
14.00	16	2.28	3.60	6.20	6.12	.19	3.10
14.20	16	2.28	3.60	6.50	6.12	.22	3.59
14.40	16	2.28	4.00	6.60	6.57	.19	2.89
14.60	16	2.28	3.80	6.80	6.34	.22	3.46
14.80	17	2.41	3.40	6.80	6.03	.25	4.14
15.00	17	2.41	4.40	7.40	7.14	.22	3.08
15.20	17	2.41	5.20	8.40	8.03	.24	2.99
15.40	17	2.41	4.00	9.20	7.58	.32	4.22
15.60	17	2.41	4.00	8.20	6.70	.31	4.63
15.80	18	2.55	3.80	7.80	6.61	.30	4.53
16.00	18	2.55	5.00	8.60	7.94	.27	3.40
16.20	18	2.55	5.60	9.80	8.61	.31	3.68
16.40	18	2.55	6.00	11.20	9.05	.38	4.20
16.60	18	2.55	5.20	10.20	8.17	.37	4.53
16.80	19	2.69	6.40	12.40	9.63	.44	4.56
17.00	19	2.69	6.40	11.80	9.63	.40	4.15
17.20	19	2.69	7.60	13.40	10.96	.43	3.92
17.40	19	2.69	6.40	12.40	9.63	.44	4.56
17.60	19	2.69	6.60	12.60	9.86	.44	4.46
17.80	20	2.82	5.80	11.60	9.10	.43	4.72
18.00	20	2.82	6.20	11.40	9.54	.38	3.98
18.20	20	2.82	5.80	10.60	9.10	.35	3.84

STS ENGINEERING CONSULTANTS CO. LTD.

DUTCH CONE PENETRATION TEST RESULTS

PROJECT MODEL INFRASTRUCTURE

LOCATION BANG BO

TEST NO D-5

DATE 31 JAN 98


TESTED BY PS

APROVED BY AN


DEPTH, m	NO OF ROD	ROD PRESS, kg/cm ²	CONE READING, kg/cm ²	CONE&JACKET READING, kg/cm ²	CONE RESISTANCE, kg/cm ²	LOCAL FRICTION, kg/cm ²	FRICTION RATIO, %
18.40	20	2.82	5.80	11.00	9.10	.38	4.17
18.60	20	2.82	7.20	11.40	10.65	.31	2.91
18.80	21	2.96	7.00	11.80	10.57	.35	3.31
19.00	21	2.96	8.60	13.60	12.34/	.37/	3.00
19.20	21	2.96	7.40	13.60	11.01	.46	4.18
19.40	21	2.96	8.00	13.60	11.68	.41	3.51
19.60	21	2.96	7.60	12.40	11.23	.35	3.11
19.80	22	3.10	14.00	23.00	18.46/	2.11	11.48
20.00	22	3.10	18.00	34.00	39.48	2.29/	5.82
20.20	22	3.10	20.00	35.00	43.79	2.15	4.92
20.40	22	3.10	20.00	35.00	43.79	2.15	4.92

TEST NO. D-5

LOCAL FRICTION, QF (KSC)



S.T.S. ENGINEERING CONSULTANTS CO., LTD.




STS ENGINEERING CONSULTANTS CO., LTD.

CONSOLIDATION TEST RESULTS

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping station		Job No. 1488	
		Bang Bo Samut Prakan			
Boring No. B-1		Sample No. PST-1		Province	
		Depth 1.00-1.80 m.		Date 18/1/88	



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{q}_{vm} = 0.25 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 83.2
					Degree of Saturation, S	% 96
Initial					Solid Height of Sample, H_s	0.76 cm.
0.125	10.24	21.1	3.36	1.99	Diameter of Sample ϕ	6.35 cm.
0.25	25.0	8.3	1.57	4.36	Wet Unit Weight γ_t	1.47 g/cc
0.50	43.56	4.3	1.13	10.21	Dry Unit Weight γ_d	0.80 g/cc
1	38.44	4.2	0.56	17.60	Liquid Limit LL	94.6 %
2	30.0	4.6	0.29	23.88	Plastic Limit PL	35.3 %
4					Compression Ratio CR	0.24
8					Recompression Ratio RR	0.08
16					Specific Gravity G	2.66

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping Station Bang Bo, Samut Prakan		Job No 1488
Boring No B-1	Sample No PST-2	Province	Depth 3.00-3.80 m.	Date 16/1/88



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm}/\text{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.28 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 85.2
					Degree of Saturation, S	% 96
0.125	14.44	14.9	2.75	2.31	Solid Height of Sample, H_s	0.75 cm.
0.25	17.64	11.7	2.21	4.67	Diameter of Sample D	6.35 cm.
0.50	60.0	3.1	0.86	11.64	Wet Unit Weight γ	1.47 g/cc
1	64.0	2.5	0.36	18.77	Dry Unit Weight γ_d	0.79 g/cc
2	27.04	5.0	0.33	25.4	Liquid Limit LL	%
4					Plastic Limit PL	%
8					Compression Ratio CR	0.24
16					Recompression Ratio RR	0.07
					Specific Gravity G	2.65

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping Station Bang Bo, Samut Prakan		Job No. 1488
Boring No. B-1	Sample No. PST-3	Province	Depth 5.00-5.80 m.	Date 16/1/89



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm}/\text{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.4 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 54.9
Initial	—	—			Degree of Saturation, S	% 96
0.125	14.44	15.1	1.27	1.05	Solid Height of Sample, H_s	0.74 cm.
0.25	25.0	8.5	1.07	2.62	Diameter of Sample D	6.35 cm.
0.50	29.16	6.9	1.07	6.48	Wet Unit Weight γ_1	1.47 g/cc
1	54.76	3.2	0.63	16.25	Dry Unit Weight γ_d	0.80 g/cc
2	21.16	6.8	0.41	22.35	Liquid Limit LL	90.8 %
4					Plastic Limit PL	35.8 %
8					Compression Ratio CR	0.31
16					Recompression Ratio RR	0.06
					Specific Gravity G	2.68

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project	Location Chareonraj Pumping Station Bang Bo, Samut Prakan	Job No 1488
Boring No. B-1	Sample No. PST-4	Province Depth 7.00-7.80 m. Date 16/1/88



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm/sec}$	Vertical Strain, ϵ %	$\bar{\alpha}_{vm} = 0.45 \text{ ksc}$	
					initial	Final
Initial	—	—	—	—	Height of Sample, H	cm. 2.5
0.125	4.0	54.8	3.20	0.73	Water Content, W	% 89.7
0.25	15.0	14.2	2.22	2.68	Degree of Saturation, S	% 98
0.50	36.0	5.6	0.80	6.24	Solid Height of Sample, H_s	0.72 cm.
1	54.76	3.2	0.52	14.36	Diameter of Sample, D	6.35 cm.
2	49.0	3.0	0.27	23.36	Wet Unit Weight γ_t	1.44 g/cc
4					Dry Unit Weight γ_d	0.76 g/cc
8					Liquid Limit LL	%
16					Plastic Limit PL	%
					Compression Ratio CR	0.30
					Recompression Ratio RR	0.06
					Specific Gravity G	2.64

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project		Location Chareonraj Pumping Station Bang Bo, Samut Prakan		Job No. 1483
Boring No. B-1	Sample No. PST-5	Province	Depth 9.00-9.80 m.	Date 16/1/88



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm}^2/\text{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 0.7 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 95.8
					Degree of Saturation, S	% 93
Initial	—	—			Solid Height of Sample, H _s	0.68 cm.
0.125	2.25	97.9	1.88	0.24	Diameter of Sample, D	6.35 cm.
0.25	9.0	24.2	1.74	1.14	Wet Unit Weight, γ_1	1.40 g/cc
0.50	18.49	11.5	0.76	2.30	Dry Unit Weight, γ_d	0.71 g/cc
1	33.44	5.1	0.61	8.80	Liquid Limit, LL	105.7 %
2	77.44	2.1	0.26	21.17	Plastic Limit, PL	40.3 %
4					Compression Ratio CR	0.41
8					Recompression Ratio RR	0.028
16					Specific Gravity, G	2.63

CONSOLIDATION TEST RESULTS


Project Model Infrastructure Project Location Charconraj Pumping Station
 Bang Bo, Samut Prakan Job No. 1488
 Boring No. B-1 Sample No. PST-6 Province
 Depth 11.00-11.80 m. Date 18/1/38



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \frac{cm^2}{sec}$	Coef. of Permeability $K, 10^{-7} \frac{cm}{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{v1} = 0.72 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 93.1
Initial					Degree of Saturation, S	% 96
0.125	2.25	97.3	6.93	0.39	Solid Height of Sample, H_s	0.67 cm.
0.25	4.84	44.3	3.90	1.99	Diameter of Sample, D	6.35 cm.
0.50	15.0	13.9	1.04	3.86	Wet Unit Weight, γ_t	1.11 g/cc
1	36.0	5.3	0.67	10.16	Dry Unit Weight, γ_d	0.71 g/cc
2	60.0	2.6	0.27	20.57	Liquid Limit, LL	%
4	49.0	2.5	0.11	29.46	Plastic Limit, PL	%
8					Compression Ratio CR	0.36
16					Recompression Ratio RR	0.04
					Specific Gravity, G	2.65

CONSOLIDATION TEST RESULTS

Project Model Infrastructure Project Location Chareonraj Pumping Station
 Bang Bo, Samut Prakan Job No. 1488
 Boring No. B-1 Sample No. PST-8 Province Depth 15.00-15.80 m. Date 18/1/08



Pressure Ksc	90% Consol. Time min	Coef. of Consolidation $C_v, 10^{-4} \text{ cm}^2/\text{sec}$	Coef. of Permeability $K, 10^{-7} \text{ cm}/\text{sec}$	Vertical Strain, ϵ %	$\bar{\sigma}_{vm} = 1.4 \text{ ksc}$	
					initial	Final
					Height of Sample, H	cm. 2.5
					Water Content, W	% 77.9
Initial	—	—			Degree of Saturation, S	% 96
0.125	-	-	-	0.21	Solid Height of Sample, H_s	0.34 cm.
0.25	1.0	218.7	9.8	0.77	Diameter of Sample D	6.35 cm.
0.50	4.0	53.8	2.02	1.71	Wet Unit Weight γ_t	1.54 g/cc
1	9.0	23.3	0.83	3.5	Dry Unit Weight γ_d	0.90 g/cc
2	38.44	5.1	0.24	8.12	Liquid Limit LL	%
4	60.0	2.8	0.14	18.18	Plastic Limit PL	%
8	10.96	3.2	0.07	27.18	Compression Ratio CR	0.32
16					Recompression Ratio RR	0.02
					Specific Gravity G	2.67