CHAPTER 9 CONCLUSION AND RECOMMENDATION

CHAPTER 9 CONCLUSION AND RECOMMENDATION

9-1 Conclusion

As a main point of its economic policy, the Government of Sri Lanka with the aid of foreign countries is implementing large scale public investments referred to as "Lead Projects" such as The MAHAVELI River Development Project, The Housing City Development Project, and The Improvement Project for the Investment Promotion Zone.

The improvement of the traffic network is necessary to smoothly carry forward these projects as well as to handle the growing traffic accompanying the success of these projects and economic development. From this point of view, the Government of Sri Lanka has set a five-year programme for road improvements and is aggressively implementing the improvement of its road traffic network. Among the various projects, the Victoria Bridge Project has been accorded such great importance and urgency that it has been given top priority.

Since the restriction of traffic on the Victoria Bridge started in 1986, only the New Kelani Bridge has been available for heavy vehicle traffic passing over the Kelani River. Considering the heavy traffic volume crossing the Kelani River, the heavy traffic congestion, the limit to handling future growth, in traffic volume, the Kelani Bridge's structural defects that need repair, and the doubtfulness of the Victoria

Bridge's durability, it is clearly necessary to construct a new bridge to replace the current one and restore the functions of the Victoria Bridge.

The preparations in Sri Lanka to implement the concerned project have been made and they are ready to start at any time.

As mentioned above, considering the current situation in Sri Lanka and the impact of the Project, the implementation of the concerned project under grant-aid assistance from the Government of Japan will be significantly worthwhile, and will also contribute to the development of the economy of Sri Lanka. Consequently it should by all means be realized.

9-2 Recommendations

We recommend the following for the immediate realization of the Project.

(1) The immediate implementation of the work to be done by Sri Lanka -

For the early commencement of the works, it is desirable that the work to be done by Sri Lanka should be carried out. In particular, problems such as site purchasing, compensation problems, and customs clearance procedures for construction materials that are to be brought from Japan must be solved.

(2) The acceleration of the implementation procedure -

As mentioned in the conclusion, it is necessary to immediately construct a new bridge to replace the current one immediately and the preparation to do that have been done the Sri Lanka. Consequently, it is desirable to carry out the remaining procedures smoothly and promptly so that early commencement of the work will be possible.

ANNEXED DATA

ANNEXED DATA 1

1-1	Minutes (July 1988)	74
	Minutes (Sept. 1988)	
1-3	Member List of the Study Team	82
1-4	Record of Site Visits	
1-5	List of Concerned Personnage Met During Visits	85
1-6	Natural Conditions	
1-7	Geological Data	87
1-8	Data for Approach Road Design	100
1-9	Photos	
	ANNEXED DATA 2	
2-1	Drawings	109
2-2	Data List	130

1-1 Minutes (July 1988)

THE MINUTES OF DISCUSSIONS ON

THE BASIC DESIGN STUDY ON

THE PROJECT FOR RECONSTRUCTING

THE VICTORIA BRIDGE IN

THE DEMOCRATIC SOCIALIST REPUBLIC OF

SRI LANKA

In response to the request of the Government of the Democratic Socialist Republic of Sri Lanka, the Government of Japan decided to conduct a basic design study on the Project for Reconstructing the Victoria Bridge (hereinafter referred to as "the Project"), and entrusted the study to the Japan International Cooperation Agency (hereinafter referred to as "JICA"). JICA sent the Basic Design Study Team headed by Mr. Shoichi Saeki, Director, Structure and Bridge Dept., Public Works Research Institute, Ministry of Construction to carry out the study from July 9 to August 4, 1988.

The Japanese Team had a series of discussions on the Project with the officials concerned of Sri Lanka, and conducted the field survey at the Project Site.

As a result of the study, both parties agreed to recommend to their respective Government authorities that the major points of understanding reached between them, attached herewith, should be examined towards the realization of the Project.

July 15, 1988

Shoichi Saeki

Leader,

Basic Design Study Team;

JICA

R. Paskaralingam

Chairman,

Road Development Authority and Secretary, Ministry of Highways

ATTACHMENT

1. Objective of the Project

The objective of the Project is to reconstruct the Victoria Bridge close to the existing old bridge in order to smoothen and improve the safety of the traffic flow.

2. Implementing Body


Ministry of Highways is responsible for the implementation of the Project.

3. Construction Site of the Project

The Construction site of the Project is down side of existing Victoria Bridge located at the Kelani River, eastern part of Colombo City as shown in Annex I.

- 4. Outline of the Project is as follows.
 - (1) New Victoria Bridge
 length: About 240m
 carriage way width: 7.5m
 pedestrian way width: 3.0m
 - (2) Approach road: About 350m (total length of both sides including some improvement work of existing roads)
- 5. The Government of the Democratic Socialist Republic of Sri Lanka will take the necessary measures listed in Annex II on condition that the Grant Aid by the Government of Japan is extended to the Project.
- 6. Both sides confirmed that the Japanese Study Team explained the Japanese Grant Aid Programme and the Sri Lanka side understood it.
- 7. Sri Lanka side insisted on the necessity that the number of the lanes of new Victoria Bridge be increased to four or more in the future in accordance with the growth of traffic flow. Japanese Study Team understood the future necessity. Both sides agreed that the Basic Design for the Project should not interrupt the above possibility.
- 8. Sri Lanka side mentioned the second stage cooperation of additional bridge (2 or 4 lanes) construction to Japanese team and the team promised to report their expectations to the Government of Japan.





A

ANNEX II

Necessary measures to be taken by the Government of the Democratic Socialist Republic of Sri Lanka.

- 1. To secure land necessary for the execution of the Project and provide enough space for such construction as temporary offices, working area, stockyard and others.
- To ensure that river area necessary for the construction of the facilities be freely accessible.
- 3. To provide necessary facilities for construction such as electricity, water supply, telephone and other incidental facilities up to the Project site.
- 4. To ensure prompt unloading, tax exemption, customs clearance at ports of disembarkation in Sri Lanka and prompt internal transportation. to be paid under the Grant, therein of the products purchased under the Grant.
- 5. To exempt Japanese nationals from customs duties, international taxes and other fiscal levies which may be imposed in Sri Lanka with respect to the supply of the products and services under the verified contracts.
- 6. To accord Japanes nationals whose services may be required in connection with the supply of the products and the services under the verified contract such facilities as may be necessary for their entry into Sri Lanka and stay herein for the performance of their work.
- To maintain and use properly and effectively the facilities constructed provided under the Grant Aid.
- 8. To vacate all existing buildings inside the Project site (see ANNEX-I) and clean the site by the start of the Project.



--- 77 ---

1-2 Minutes (Sept. 1988)

THE MINUTES OF DISCUSSIONS ON
THE BASIC DESIGN STUDY ON
THE PROJECT FOR RECONSTRUCTING
THE VICTORIA BRIDGE IN
THE DEMOCRATIC SOCIALIST REPUBLIC OF
SRI LANKA

In response to the request of the Government of the Democratic Socialist Republic of Sri Lanka, the Government of Japan decided to conduct a basic design study of the Project for Reconstructing the Victoria Bridge (hereinafter referred to as 'the Project'), and entrusted the Japan International Co-operation Agency (hereinafter referred to as 'JICA'). JICA sent the Basic Design Study Team headed by Mr. Shoichi Saeki, Director, Structure and Bridge Dept., Public Works Research Institute, Ministry of Construction to carry out the study from July 9 to August 4, 1988.

As a result of the study, JICA prepared a draft report and despatched a team headed by Mr. Shoichi Saeki to explain and discuss it from September 24 to October 2, 1988.

Both parties had a series of discussions on the report and agreed to recommend to their respective Governments that the major points of understandings reached between them on September 29, 1988, attached herewith should be examined towards the realization of the Project.

Shoichi Saeki

Leader

Basic Design Study Team Japan International

Co-operation Agency

R. Paskaralingam

Chairman

Road Development Authority and Secretary, Ministry of Highways


29th September, 1988

ATTACHMENT

- The Government of Sri Lanka agreed in principle to the basic design proposed in the Draft Final Report.
- 2. The Government of Sri Lanka has reconfirmed the Minutes of the meetings held from 11th to 15th July, 1988 and signed on 15th July, 1988.
- 3. The Government of Sri Lanka assured the provision of the necessary budget for the adequate works such as site clearance, etc. for the project execution and the personnel services, maintenance and operation expenses for the new bridge.
- 4. The Government of Sri Lanka has agreed to be responsible for the undertaking of works as shown in Annex I, such as provision of power and water supply to the site, space for workshop, etc.
- 5. The Government of Sri Lanka has agreed to obtain the right-of-way for the Project and report the situation to the Embassy of Japan in Sri Lanka by the end of November, 1988.
- 6. The Final Report (10 copies in English) will be submitted to the Government of Sri Lanka in November, 1988.

SAP

(





 $\int_{\mathcal{A}}$

(I) Assembly yard for E.C. bar & Re-bar

@ leaporary Jetty

	21.6 180 21.6 180 21.6 180 21.6 180 10 180 10 180 5 5 180 7.5 180	
	Office Tarehouse Tarehouse Tarehouse Office for Local subconfactor T.2 × Container for Material & Tools Garpenter's shop Bar-bender's shop Repair shop Mortor Pool Materials stock yard Cuard Box Guard Box Guard Box Sometials stock yard Sometials stock yard	
r Temporary Facilities		
(B) Arrangement for	Temporary drainage Temporary drainage Temporary drainage Temporary drainage Telecommunication connections Too international tel. lines o One international Fax. line	
	Left Bank Sign	
	Electric power supply point point point	$\hat{\beta}$

1-3 Member List of Study Team

(1) On-site study of basic design

Name	Assignment	Affiliation
Shoichi Saeki	Team leader	Ministry of Construction
Yoshitaka Yoshida	Construction plan supervisor	Honshu and Shikoku Bridge Authority
Shigeyukì Seto	Project Coordinator	ЛСА
Shunji Inomata	Bridge planner	Japan Bridge & Structure Institute, Inc. (JBSI)
Masahisa Komiya	Bridge designer	JBSI
Kiminori Matsumoto	Construction planner	JBSI
Shoji Yamaguchi	Road designer	JBSI
Junji Anai	Geological surveyer	Kokusai Kogyo Co., Ltd.

(2) On-site explanation of final draft report

Shoichi Saeki	Team Leader	Ministry of Construction
Shunji Inomata	Bridge planner	JBSI
Masahisa Komiya	Bridge designer	JBSI
Kiminori Matsumoto	Construction planner	JBSI
Shoji Yamaguchi	Road designer	JBSI

1-4 Record of First Site Visit

9	Sat.	PM	0:00	Leave Narita Airport
10	Sun.			Arrive in Sri Lanka.
11	Mon.	AM	9: 00	JICA
			10:00	Embassy
			11:00	External Resources
		PM	3: 00	RDA
12	Tue.	AM	9: 00	RDA
		PM	1:00	Bridge Site
13	Wed.	AM	9:00	RDA
		PM	1:00	Visit the Kalutara Bridge.
14	Thu.	AM	9: 00	RDA
		PM	3: 00	External Resources
15	Fri.	PM	1:00	Sign the minutes.
16	Sat.	Japanese	governme	nt survey team returns to Japan.
17	Sun.			No. 5 boring work starts.
18	Mon.	٨M	9:00	RDA
19	Tue.	AM	9:00	RDA Survey the bridge site.
		PM	1:00	Visit a ready-fixed concrete plant.
20	Wed.	AM	9:00	RDA No. 5 boring work completed. 21
				Thu. AM 10:00 Visit the SDCC. No. 6
				boring work starts.
		-	11:00	Visit the Civil Engineering Research
				Center
				Fabricate a platform.
22	Fri.	AM	9: 00	RDA
23	Sat.			
24	Sun.			
25	Mon.	AM	9: 00	RDA Install a platform for No. 6
				boring
26	Tue.	AM	9: 00	RDA No. 6 boring work starts.
27	Wed.	AM	9:00	RDA
28	Thu.			Holiday No. 6 boring work completed.
	Fri.	AM	9: 00	RDA
				Visit the Kalutara Bridge.
1	_	AM	9: 00	RDA
4		PM	3: 00	Visit the embassy.
2	Tue.	PM	1:00	RDA
3	Wed.	PM	1:00	Leave Sri Lanka.
4	Thu.	PM	7: 30	Arrive at Narita.
	10 11 12 13 14 15 16 17 18 19 20 22 23 24 25 26 27 28 29 30 31 1	10 Sun. 11 Mon. 12 Tue. 13 Wed. 14 Thu. 15 Fri. 16 Sat. 17 Sun. 18 Mon. 19 Tue. 20 Wed. 22 Fri. 23 Sat. 24 Sun. 25 Mon. 26 Tue. 27 Wed. 27 Wed. 28 Thu. 29 Fri. 30 Sat. 31 Sun. Aug. 1 Mon. 2 Tue. 3 Wed.	10 Sun. 11 Mon. AM AM PM 12 Tue. AM PM PM 13 Wed. AM PM 15 Fri. PM 16 Sat. Japanese 17 Sun. 18 Mon. AM PM 20 Wed. AM AM AM PM 21 Wed. AM 22 Fri. AM 23 Sat. 24 Sun. 25 Mon. AM 26 Tue. AM AM 27 Wed. AM 28 Thu. 29 Fri. AM 30 Sat. 31 Sun. Aug. 1 Mon. AM PM 2 Tue. PM 3 Wed. PM 3 Wed	10 Sun. 11 Mon. AM 9: 00 10: 00 11: 00 PM 3: 00 PM 1: 00

RDA: Road Development Authority
SDCC: State Development Construction Corporation 1-4 Visitor List

Record of Second Site Visit

Sept.	. 24	Sat.	Leave Narita Airport
•	25	Sun.	Arrive in Sri Lanka.
	26	Mon.	Meetings with N.P.E.R.,
			M.O.H., R.D.A.
	27	Tue.	Explanation of the Draft
			Final Report and Check of Project Site
	28	Wed.	Discussions on the Draft
			Final Report with RDA
	29	Thu.	Signing of Minutes
	30	Fri.	Team Leader Leaves for Tokyo, remaining members
			Continue technical discussions
Oct.	1	Sat.	Remaining members leave Colombo
	2	Sun.	Arrive in Narita Airport

1-5 List of Concerned Personage Met During Visits

ROAD DEVELOPMENT AUTHORITY (R.D.A)

- Mr. B.M. de Soysa (General Manager)
- · Mr. G.S. Hattotuwegama (Director/Engineering Services)
- Dr. Asoka de Silva (Deputy Director/Bridge Design)
- · Mrs. N.D. Peiris (Assistant Director/Bridge Design)
- Mrs. M.G.S. Perera (Deputy Director/Highway Design)
- · Mr. S.R. Somaskandan (Senior Engineer/Highway Design)

2. MINISTRY OF HIGHWAYS

- Mr. R. Paskaralingam (Secretary/Highways)
- Mr. D.J. Amarasinghe (Addi Secretary/Highways)

3. DEPARTMENT OF EXTERNAL RESOURCES

- · Mr. M.A. Mohamed (Director/External Resources)
- Mr. S. Weeraparna (Additional Director/External Resources)

4. URBAN DEVELOPMENT AUTHORITY

· N.D. Dickson (Director Planning)

5. EMBASSY OF JAPAN

Mr. Yasuya Hamamoto Ambassador Mr. Toshihisa Takada Counsellor Mr. Kazuhiko Maruyama

First Secretary


6. JICA SRI LANKA OFFICE


Resident Representative


Mr. Jiro Hashiguchi Mr. Hiroshi Niino

Staff









SOIL INVESTIGATION OF VICTORIA BRIDGE - KELANIYA

B.H. NO. 5

RESULTS OF MOISTURE CONTENT TESTS

Depth (m)	Elevation	M.C. %
1.00	+ 0.75	22
3.00	- 1.25	30
4.00	- 2.25	57
7,00	- 5.25	22
8.00	- 6.25	24
10.00	- 8.25	26
13.00	- 11.25	18
14.00	- 12.25	14
16.00	- 14.25	10
18.00	- 16.25	11

SOIL INVESTIGATION FOR RECONSTRUCTION OF VICTORIA BRIDGE RESULTS OF SPECIFIC GRAVITY TESTS

B.H. NO. 5

Depth (m)	Elevation	Specific Gravity
1.00	+ 0.75	2.671
3.00	- 1.25	2.691
4.00	- 2.25	2.453
7.00	- 5.25	2.619
8.00	- 6.25	2.687
10.00	- 8.25	2.611
13.00	- 11.25	2.800
14.00	- 12.25	2.664
16.00	- 14.25	2.730
18.00	- 16.25	2.502

SOIL INVESTIGATION OF VICTORIA BRIDGE - KELANIYA

B.H.NO. 5

RESULTS OF ATTERBURG'S LIMIT TESTS :


Depth (m)	Elevation	L.L. %	P.L. %	P.I. %
1.00	+ 0.75	- Non	Plastic	_
3.00	- 1.25	37	20	17
4,00	- 2.25	- Non	Plastic	
7.00	- 5.25	- Non	Plastic	_
8,00	- 6.25	23	18	05
10.00	- 8.25	44	20	24
13.00	- 11.25	. 40	33	07
14.00	- 12.25	32	28	04
16.00	- 14.25	– Non	Plastic	- -
18.00	- 16.25	60	37	23

SOIL INVESTIGATION OF VICTORIA BRIDGE

B.H. NO. 5

RESULTS OF SIEVE ANALYSIS

Depth (m)	Elevation	Remarks
1.00	+ 0.75	Curve attached
3.00	- 1.25	- do -
4.00	- 2.25	- do -
7.00	- 5.25	- do -
8.00	- 6.25	- do -
10.00	- 8.25	- do -
13.00	-11.25	- do -
14.00	-12.25	- do -
16.00	-14.25	– do –
18.00	-16.25	– do –



SOIL INVESTIGATION FOR RECONSTRUCTION OF VICTORIA BRIDGE

RESULTS OF UNCONFINED COMPRESSION TEST

BOREHOLE NO. 5

DEPTH

5.00 m

TEST NO. 1+ 2

Sample___ Description ;- Clayey, silty fine sand. Black in colour.

		Test No. 1	Test No. 2
Unconfined Compressive Strength	lbs/in ²	3.25	3.84
	kN/m ²	22	26
Failure Strain %		10	11
Shear Stress	lbs/in ²	1.62	1.92
	kN/m ²	11	13
Moisture Content	%	54	60
Wet Density	lbs/ft ³	100.5	99.05
	Mg/m ²	1.608	1.584
Dry Density	lbs/ft ³	65	61.77
	${\rm Mg/m}^2$	1.039	0.988

SOIL INVESTIGATION FOR RECONSTRUCTION OF VICTORIA BRIDGE RESULTS OF UNCONFINED COMPRESSION TEST

BOREHOLE NO. 5

DEPTH

12 m

TEST NO. - 1

Sample Description

:- Moist soft lateritic clay with fine sand. Brown in colour.

		Test No. 1
Unconfined Compressive Strength	lbs/in ²	0.85
	kN/m^2	6
Failure Strain %	•	6
Shear Stress	lbs/in ²	0.45
	kN/m^2	3
Moisture Content %	·	27
Wet Density	lbs/ft ³	128
	Mg/m^3	2.05
Dry Density	lbs/ft ³	98
	Mg/m^3	1.57

RE CONSTRUCTION OF VICTORIA BRIDGE - KELANIYA

RESULTS OF MOISTURE CONTENT TESTS

B.H.NO. 6

Depth (m)	Elevation	Moisture Content%
1.00	- 4.30	13
3.00	- 6.30	11
5.00	- 8.30	18
7.00	- 10.30	09
9.00	- 12.30	19
10.00	- 13.30	26
11.00	- 14.30	32
12.00	- 15.30	23
14.00	- 17.30	23
15,00	- 18.30	26

RESULTS OF SPECIFIC GRAVITY TESTS

B.H.No. 6

Depth (m)	Elevation	Specific Gravity
1.00	- 4.30	2•746
3.00	- 6.30	2•585
5.00	 8•30	2•513
7.00	- 10.30	2.708
9.00	- 12•30	2•635
10.00	- 13•30	2.545
11.00	14.30	2•287
12.00	- 15•30	2•660
14.00	17.30	2.640
15•00	- 18.30	2•651

SOIL INVESTIGATION OF VICTORIA BRIDGE

B.H.No. 6

RESULTS OF ATTERBURG LIMITS

Depth (m)	Elevation	Rem	arks	
1.00	- 4.30	Non	plas	tic
3.00	- 6.30	-	do	2 43
5.00	~ 8.30	\$604	do	wo4
7.00	- 10.30		do	,
9.00	- 12•30	•••	do	-
10.00	- 13.30		do	para.
11.00	- 14.30		do	
12.00	- 15•30	,	do	0.0
14.00	- 17.30	646	фo	-
15•00	- 18.30	••	do	g-rae


GROUP PUGLIFERING LABORATORIES LTD

SOIL INVESTIGATION OF VICTORIA BRIDGE


B.H.No. 6

RISULTS OF SIEVE ANALYSIS


	•	· · · · · · · · · · · · · · · · · · ·
Depth (m)	Elevation	Remarks
1.00	- 4.30	Curve attached
3.00	- 6.30	- do -
5.00	≈ 8.30	- do -
7.00	- 10.30	- do -
9.00	12+30	- do -
10.00	- 13.30	do
11.00	 14.30	do
12.00	- 15•30	do
14.00	- 17.30	⊷ do ⊷
15.00	- 18.30	- do -




	がし、いったとしいった。	T.P.C.
		Sample no. Att 11 4 H 22 (vil. o. Depth
		Specimen no. Description (alexche Sell
Equipment	Test on recompacted specime.	Cherator
1. 193.8 - 61. 193.8 - 61. 193.8 - 61. 193.8 - 61. 1001.	quantities required 10 Main	13/10/87
distraction (S2. Q time	Harstiffe content required	
· ; Surve(Vm)	mass ilsoit required	
2. Of mouth and the supplete		•
Marking of load rap ov	ביאנווות שאפפ פן אישופו וח פטככושפח אייייי אייאל פראיווים שאפפ פן אישופו וח פטככושפח	
	G	
Test on undisturbed specimen	Method of compaction	
unsoaked	(iex Jppreziale box)	Density calculations
Mass of mould, baseplyce and soul (m,)	quantities used.	unsoaked /
Mass of mould are flats eplate (ma)	Mass of mould, baseplate and wet soil (m,) (8582.	Folk density = my-m; My m; (a)
Final moistude content it not soaked (W.)	Mass of mould and base place (m.,) 14137	
soaked	Find moisture content (W.)	soaked
muss of moudd. Easephale and soil after soaking (ir.,)	Mass of mouth, baseplate and soil 1957 H. a	Bulk density and the Marin's (p) Vini
magge (soul after a conditing (me - m _b) I mali model we contrade a southerny (W.J. ¹⁶)	Mass of soil after soaking (m m.)	Dry deusity and ESP




1.9 Photos




Victoria Bridge




Victoria Bridge



Victoria Bridge



Victoria Bridge




New Kelani Bridge




New Kelani Bridge


2-1 Drawings

List of Drawings	
Dimension Details (No.1 No. 2)	111
Reinforcement Bar Arrangement	115
Arrangement of Prestressing Cables	
Sectional View of Approach Road	
Proposed Drainage System of the Approach Road	
Stage Construction	
. •	








REINFORCEMENT BAR ARRANGEMENT \$=1:20





ARRANGEMENT OF PRESTRESSING CABLES S.1 20

















Proposed Drainage System Of The Approach Road (Colombo Side)

Stage Construction







2-2 Data List

- 1. ANNUAL REPORT FOR THE YEAR 1986 (RDA) (RDA PROJECT BUDGET EXPENSES REPORT)
- 2. ANNUAL REPORT FOR THE YEAR 1987 (RDA) (RDA PROJECT BUDGET EXPENSES REPORT)
- 3. BUDGET ESTIMATE-1989,1988,1987
- 4. DAYWORK RATES AND ELEMENTS
- 5. KALUTARA BRIDGES PROJECT SRI LANKA DATA ON MACHINERY LEASE
- 6. METEOROLOGICAL DATA ON COLOMBO
- 7. CONCRETE PRODUCT UNIT PRICE
- 8. GOVERNMENT ORGANIZATIONAL CHART
 - RDA MOH
 - ORGANIZATIONAL CHART OF PROJECT
- 9. MANUFACTURES ANALYSIS & TEST CERTIFICATE
- 10. UTILITY PLAN
- 11. DRAFT STANDARD SPECIFICATION FOR CONSTRUCTION AND MAINTENANCE OF ROADS AND BRIDGES
- 12. SRI LANKA ROAD BRIDGE REHABILITATION PROJECT TEMPER DOCU-MENTS
- 13. SRI LANKA ROAD AND BRIDGE REHABILITATION PROJECT BILL OF QUANTITIES
 (FINANCE BY THE INTERNATIONAL BANK FOR RECONSTRUCTION AND DEVELOPMENT)
- 14. PUBLIC UTILITY SERVICE TO BE LAID ON BRIDGE

