

8. RECOMMENDATIONS

8.1 Early Implementation of the Project

The Malir basin has played an important role for a long time in supplying agricultural products such as fruit, vegetables, etc. and in supplying potable water to Karachi city. Despite the fact that demand for such agricultural products is increasing due to rapid population growth of Karachi, agricultural land in the project area is decreasing year by year mainly due to overdraft of groundwater from the potential aquifers in the basin, which will further be accelerated unless appropriate countermeasures are provided for augmentation of recharge to and proper management of the aquifers.

The Water Resources Development Project in the Malir basin is verified herein as technically, and economically as well as financially feasible. It is, therefore, recommended that the necessary arrangements for early implementation of the project be taken as soon as possible.

8.2 Establishment of Pilot Demonstration Farm

Fruit and vegetable crop yields achieved by producers in the project area are significantly lower than those generally achieved in Sindh and much below national averages. The restoration of a reliable and properly managed supply of water under the proposed project will create the conditions for development of more intensive fruit and vegetable production systems in the project area.

The project itself will make only a limited contribution to intensification of crop production in the project area through augmentation of recharge to the aquifers. It is therefore essential to establish a pilot demonstration farm in order to achieve the desired increase in crop yields through adaptive research including testing of crop packages, alternative technologies, including irrigation techniques and management practices to meet the needs of farmers in the area. The proposed Pilot Demonstration Farm should be implemented under the project.

8.3 Groundwater Management

Proper groundwater management should be strictly carried out for the sustainable groundwater use in order to prevent serious groundwater mining and deterioration of water quality, in connection with the implementation of the project. Otherwise, decrease of potential groundwater resources as seen at present in the project area may occur again in the future, even if increased recharge to the aquifers can be provided by the project.

The continuous groundwater monitoring including observation of groundwater level, pumping amount, and water quality is essential for the groundwater management. In the course of this study, two (2) automatic groundwater level recorders were installed. However, it is recommended to add at least three (3) automatic recorders, and ten (10) monthly

observation wells, distributed in the project area. Monthly EC and pH observations at the above 15 wells are also recommended for long-term groundwater monitoring. Moreover, extraction amounts by pumping should be monitored in terms of energy consumption or other appropriate means such as water gauging meters, or information of cropped area, etc., through the proposed Groundwater Users' Association.

No legal framework for the groundwater resources development exists in the province or in the project area. It is strongly recommended that a section of IPD be established for proper groundwater management, including development of the necessary regulations for groundwater resources development to monitor and maintain the aquifer level/status in the project area as well as to ensure proper utilization of potential groundwater resources, in collaboration with the proposed Groundwater Users Association.

LIST OF REFERENCES

- 01 Water Resources Development in Malir Basin, Feasibility Study, WAPDA, 1979 (updated in 1982)
- 02 Karachi Flood Control Plan, Feasibility Report, WAPDA, 1985
- 03 Water Resources Development in Malir Basin, Project Document, National Engineering Services (Pakistan) Ltd., 1984
- 04 River and Climatological Data of Malir and Layari River Basins, WAPDA, 1989
- 05 Water Sector Investment Planning Study (Draft), Provincial Plan Sindh, Nov. 1989, UNDP, WB
- 06 Crop Water Requirement, Irrigation and Drainage Paper No. 24, FAO, 1977

TABLES

Table 1 PARTICIPANTS IN THE STUDY

Name	Position
A. Advisory Committee	
1. Dr. M. Wada	Chairman of Advisory Committee (MAFF)
2. Dr. T. Sugawara	Member, Geology (MAFF)
3. Mr. T. Tachibana	Member, Irrigation and Drainage (MAFF)
4. Mr. M. Tabata	Member, Agriculture (MAFF)
5. Mr. K. Sawada	Member, Agriculture (MAFF)
B. Study Team	
1. Mr. K. Irie	Team Leader
2. Mr. S. Muramoto	Irrigation and Drainage Engineer (Deputy Team Leader)
3. Mr. K. Kotoo	Hydrogeologist/(Groundwater Engineer)
4. Mr. M. Okamoto	Groundwater Engineer
5. Mr. T. Murakami	Hydrologist
6. Mr. M. Taki	Dam Engineer
7. Mr. K. Kameyama	Engineering Geologist
8. Mr. F. Nagao	Agronomist
9. Mr. John D. Pell	Agro-economist
10. Mr. K. Kyoizumi	Structural Design Engineer
11. Mr. T. Kimijima	Project Economist
C. Counterpart Personnel	
1. Mr. Syed I. A. Shah	Advisor, Chief Engineer, Irrigation and Power Dept.
2. Mr. Seth A. Fazal	Team Leader, Director of Design, Irrigation and Power Dept.
3. Mr. Muhammad I. Khan	Deputy Team Leader, Executive Eng., Irrigation and Power Dept.
4. Mr. Muhammad A. Shaikh	Civil Eng. Assistant Executive Engineer, Irrigation and Power Dept.
5. Mr. Noor A. Memon	Design Eng. Assistant Executive Engineer, Irrigation and Power Dept
6. Mr. Chandio S. Nawaz	Groundwater Specialist, Professor, Mehran University
7. Mr. Ali M. Jokyo	Geologist, Assistant Professor, University of Sindh
8. Dr. Muhammad Y. Memon	Agro-economist, Assistant Professor, Sindh Agriculture University
9. Mr. Shamsudin Mangi	Agronomist, Assistant Professor, Sindh Agriculture University
10. Mr. Muhammad I. Panhwer	Project Economist, Assistant Professor, University of Sindh

Table 2 SALIENT FEATURES OF KHADEJI AND MOL DAMS
PROPOSED BY WAPDA

	Unit	Khadeji Dam	Mol Dam
a) General			
Location		7.2 km upstream of Super Highway Bridge at a distance of about 50 km from Karachi.	8.3 km upstream of Super Highway Bridge.
River		Khadeji tributary of Maril River	Mol tributary of Maril River
Type of dam		Concrete Gravity	Earthfill (Homogenous)
Purpose		Groundwater recharge (Irrigation +Flood+ Drinking Water Supply)	Groundwater recharge (Irrigation +Flood+ Drinking Water Supply)
b) Hydrology			
Catchment area	km ²	567	611
Mean annual rainfall	mm	217	217
Mean annual runoff	MCM	31.2	33.7
c) Reservoir			
Live storage	MCM	32.3	33.2
Flood control storage	MCM	22.4	17.8
Dead storage	MCM	7.2	7.7
Gross storage	MCM	61.9	58.7
Maximum reservoir area	km ²	14.2	6.3
d) Dam			
Type		Concrete Gravity	Earthfill (Homogenous)
Maximum height	m	39.0	44.2
Length of crest	m	381	2,347
Top width	m	9.1	12.2
Top elevation of dam	EL. m	168.6	177.1
Normal full water level	EL. m	162.6	170.7
Maximum water level	EL. m	166.3	174.7
Slope: Upstream		1 : 0.1	1 : 3.0
Downstream		1 : 0.7	1 : 2.0
e) Spillway			
Type		Overflow (gated)	Submerged weir (ungated)
Gates	No. x m x m	5 x 12.2 x 6.1	-
Capacity	m ³ /sec	3,830	3,720
Reservoir absorption	MCM	48.6	23.2
Surcharge for design flood	m	3.7	4.0
Crest elevation	EL. m	156.5	170.7
Energy dissipation		Stilling Basin (energy dissipation by hydraulic jump)	No Stilling Basin
f) Off-take Structure			
		1.8 m dia circular conduit with 1.8 m x 1.8 m control gate at inlet end through middle of overflow section discharge directly into main stilling basin.	1.8 m dia tunnel with control gate at outlet end and emergency control gate at inlet end with stilling basin on downstream end.
Outfall Channel		-	6.5 ft. wide channel with 1-1/2 : 1 side slope discharging into natural Nullah.
g) Irrigation System			
		Recharging aquifer by controlled releases from Khadeji & Mol Dams	
h) Cropping Area			
Drinking Water Supply	ha	5,670	
	MCM	13.4	

Source : Ref. 01

Table 3 PRESENT CROP PRODUCTION IN THE STUDY AREA

Crops	Summer Season			Winter Season			Annual Production (tons)
	Area (ha)	Unit Yield (t/ha)	Production (tons)	Area (ha)	Unit Yield (t/ha)	Production (tons)	
A. Fodder Crops							
Sorghum	210	11.5	2,415				2,415
Lucerne	150	13.9	2,085				2,085
Maize	50	10.6	530	50	10.6	530	1,060
Others	80	12.3	981	30	12.3	369	1,350
All Fodder	<u>490</u>	(12.3)	<u>6,011</u>	<u>80</u>	(11.2)	<u>899</u>	<u>6,910</u>
B. Vegetables							
Solanaceous							
Tomato	480	3.3	1,584				1,584
Eggplant	110	4.9	539	50	4.9	245	784
Chilli	10	1.0	10	40	1.0	40	50
Cucurbits							
Sponge Gourd	130	3.1	403	70	3.1	217	620
Bottle Gourd	100	4.7	470	50	4.7	235	705
Bitter Gourd	30	4.0	120	5	4.0	20	140
Cucumber	20	2.0	40				40
Water Melon	30	3.0	90				90
Musk Melon	10	2.9	29				29
Cole Crops, Green, Herbs							
Cauliflower	120	13.3	1,596				1,596
Spinach	60	2.6	156	60	2.6	156	312
Root Crops							
Carrot	100	5.4	540	50	5.4	270	810
Radish	60	4.0	240	45	4.0	180	420
Turnip	50	6.6	330	15	6.6	99	429
Legumes, others							
Peas	100	2.6	260	5	2.6	13	273
Others	110	4.5	521	30	4.5	155	676
All Vegetables	<u>1,520</u>	(4.6)	<u>6,928</u>	<u>420</u>	(3.9)	<u>1,630</u>	<u>8,558</u>
C. Fruits							
Guava	280	3.8	1,064				1,064
Mango	570	6.1	3,477				3,477
Chikoo	80	2.3	184				184
Coconut Palm	90	2.7	243				243
Papaya	50	7.3	365				365
Dates Palm	40	2.8	112				112
Custard Apple	10	3.0	30				30
Banana	10	8.2	82				82
Others	70	4.9	424				424
All Fruit	<u>1,200</u>	(5.0)	<u>5,981</u>				<u>5,981</u>
D. Other Crops							
Sesame Seed	5						
Rose Flower	5						
Others				10			
All Others	<u>10</u>	2.5	<u>25</u>	<u>10</u>	2.5	<u>25</u>	<u>50</u>
Total	3,220		18,945	510		2,554	21,499

Remarks: Refer to ANNEX-E.

Table 4 PRESENT LAND USE IN THE PROJECT AREA

Name of Deh / Union Council	Total Area	Agricultural Land				Fallow Area	Total	Unit : ha
		Irrigated Field		Rainfed Upland	Non- Agricultural Land			
		Orchard	Upland					
DARSANO CAHANO								
1) Bail	*	120	5	5	0	0	10	110
2) Kathore	*	1,200	170	165	15	410	760	440
3) Amilano		1,150	60	65	10	135	270	880
4) Khadeji	*	220	0	5	0	5	10	210
5) Chuhar	*	650	20	20	20	55	115	535
6) Kotero	*	330	30	45	5	75	155	175
Sub-total		<u>3,670</u>	<u>285</u>	<u>305</u>	<u>50</u>	<u>680</u>	<u>1,320</u>	<u>2,350</u>
KANKAR								
1) Bazar		2,200	200	200	35	415	850	1,350
2) Darsano Channo	*	1,480	70	255	0	295	620	860
3) Kharkharo	*	1,170	80	85	0	135	300	870
4) Malh		1,590	220	105	0	330	655	935
Sub-total		<u>6,440</u>	<u>570</u>	<u>645</u>	<u>35</u>	<u>1,175</u>	<u>2,425</u>	<u>4,015</u>
LANDHI								
1) Kharkhar		990	50	115	15	200	380	610
2) Sanhro		1,010	50	160	0	275	485	525
3) Landhi	*	880	115	100	0	240	455	425
4) Khanto	*	250	25	30	0	65	120	130
Sub-total		<u>3,130</u>	<u>240</u>	<u>405</u>	<u>15</u>	<u>780</u>	<u>1,440</u>	<u>1,690</u>
THANO								
1) Thano		660	85	65	0	165	315	345
Sub-total		<u>660</u>	<u>85</u>	<u>65</u>	<u>0</u>	<u>165</u>	<u>315</u>	<u>345</u>
Total		13,900	1,180	1,420	100	2,800	5,500	8,400
Percentage			(8.5%)	(10.2%)	(0.7%)	(20.1%)	39.6%	60.4%

Remarks: Refer to ANNEX-E.

Table 5 SUMMARY OF PRODUCTION WELLS IN THE PROJECT AREA

Union No.	Council	Deh	No. of Wells shown on Map			Well Nos. in Project Area for Simulation	Agri. Electric. Consumer's Record (KESC)	Study Area					
			Production Wells	Abandon. Wells	Total			Well Inventory in Oct. 1989					
							Total	-1940's	1950's	1960's	1970's	1980's	
1	Darsano Chano	Amlano	21	1	22	27	31	27	3	3	10	7	4
		Chuhar	4	1	5	13	12	13	1		7	2	3
		Kothore	45	8	53	34	4	34	4	4	17	10	3
		Kotiraro	2	12	14	28	24	28	7	6	6	5	4
		Sub-total	72	22	94	102	71	102	11	13	40	24	14
2	Konkar	Bazar	58	4	62	29	24	29		7	14	4	4
		Darsano Chano	59	7	66	51	60	51	8	5	18	10	10
		Khar Kharo	24	3	27	35	34	35	10	4	13	2	6
		Konkar	12	3	15	0		50	11	1	8	8	22
		Malh	115	4	119	70	133 *	70	24	15	20	10	1
		Thado	1	1	2	9	9	9		1	4		4
		Tore	2		2	7		7					7
		Sub-total	271	22	293	201	260	251	53	33	77	34	54
3	Laundhi	Khakhar	2	2	4	29	30	29	8	4	2	9	6
		Khanto			0	0	7						
		Laundhi	39		39	47	55	47	16	5	11	7	8
		Sanhro	53		53	40	41	40	7	6	19	6	2
		Sub-total	94	2	96	116	133	116	31	15	32	22	16
4	Thano	Thano	27		27	47	47	47	31	7	5	3	1
			464	46	510	466	511	516	126	68	154	83	85
			{ 406 }	{ 108 }	{ 514 }								

Remarks: * including wells in Konkar and Tore Union Councils.
{ } shows well numbers estimated by WAPDA in 1977.
Refer to ANNEX-G.

Table 6 SALIENT FEATURES OF EXISTING WEIRS

	Location	River	Crest		Flood Water Level	
			Height EL. m	Length m	Upstream EL. m	Downstream EL. m
1. Upper *	Menon G.	Malir	45.1	470	47.2	46.3
2. Lower	Thano	Malir	25.9	152	28.7	n.a
3. Sukkan	Jam Kanda	Sukkan	n.a.	98	n.a	n.a

Remarks: * Under construction and to be completed in the late 1990.
n.a. Data are not available.
Refer to ANNEX-G.

Table 7 NATURAL RECHARGE AND ARTIFICIAL RECHARGE BY DAMS

		Unit: MCM						
Mol :	Natural	Case-1	Case-2	Case-3	Case-4	Case-5	Case-6	Case-7
Khadeji :	Recharge	43.8 MCM	35.0 MCM	43.8 MCM	35.0 MCM	30.0 MCM	-	-
(Year)		35.5 MCM	35.5 MCM	-	-	-	35.5 MCM	30.0 MCM
1929	12.9	12.9	12.9	12.9	12.9	12.9	12.9	12.9
1930	137.9	184.7	180.8	170.8	166.4	164.1	165.6	163.3
1931	6.9	6.9	6.9	6.9	6.9	6.9	6.9	6.9
1932	111.0	159.2	155.4	145.7	141.4	139.1	140.6	138.4
1933	152.2	232.8	235.6	225.3	220.9	218.5	215.1	212.8
1934	55.0	104.1	97.3	79.8	79.8	77.5	72.1	72.1
1935	12.3	12.3	12.3	12.3	12.3	12.3	12.3	12.3
1936	20.4	21.7	21.7	21.7	21.7	21.7	21.7	21.7
1937	70.1	108.6	105.2	107.9	110.5	111.9	109.9	111.5
1938	23.2	24.1	24.1	24.1	24.1	24.1	24.1	24.1
1939	5.6	5.6	5.6	5.6	5.6	5.6	5.6	5.6
1940	22.1	22.1	22.1	22.1	22.1	22.1	22.1	22.1
1941	7.5	7.5	7.5	7.5	7.5	7.5	7.5	7.5
1942	96.3	134.1	130.4	120.5	116.5	114.1	115.9	113.3
1943	12.1	12.1	12.1	12.1	12.1	12.1	12.1	12.1
1944	203.8	292.6	296.9	297.7	293.7	291.3	282.7	280.3
1945	32.6	68.2	60.2	51.3	51.3	51.3	44.6	44.6
1946	25.1	25.1	25.1	25.1	25.1	25.1	25.1	25.1
1947	13.4	13.4	13.4	13.4	13.4	13.4	13.4	13.4
1948	7.0	7.0	7.0	7.0	7.0	7.0	7.0	7.0
1949	80.0	132.6	134.6	128.4	130.1	131.3	122.3	124.3
1950	21.0	29.5	25.2	25.2	25.2	25.2	25.2	25.2
1951	10.1	10.1	10.1	10.1	10.1	10.1	10.1	10.1
1952	40.5	81.2	81.2	65.0	65.0	64.8	57.0	57.0
1953	72.4	107.5	108.2	113.1	115.8	91.9	115.1	90.9
1954	47.9	87.3	84.0	71.3	71.3	71.3	62.9	62.9
1955	22.1	35.7	35.7	36.4	36.4	36.4	35.9	35.9
1956	58.8	109.1	109.1	95.7	95.7	95.7	86.6	86.7
1957	8.1	8.1	8.1	8.1	8.1	8.1	8.1	8.1
1958	26.9	55.1	55.1	47.8	47.8	47.8	42.1	42.1
1959	201.6	250.6	261.4	257.8	253.7	251.5	249.6	247.3
1960	20.6	46.3	38.3	20.6	20.6	20.6	20.6	20.6
1961	123.6	224.8	211.9	214.1	210.0	207.6	204.2	202.0
1962	66.1	134.4	126.3	96.6	96.6	96.6	88.0	88.0
1963	14.7	14.7	14.7	14.7	14.7	14.7	14.7	14.7
1964	29.0	34.7	34.7	34.7	34.7	34.7	34.7	34.7
1965	21.0	39.6	39.6	40.3	40.3	40.3	33.6	33.6
1966	17.6	19.4	19.4	19.4	19.4	19.4	19.4	19.4
1967	168.7	260.0	262.6	252.7	248.2	245.8	246.3	243.8
1968	14.4	21.2	14.4	14.4	14.4	14.4	14.4	14.4
1969	11.3	11.3	11.3	11.3	11.3	11.3	11.3	11.3
1970	83.6	146.4	148.9	144.6	141.1	139.8	116.1	115.5
1971	16.3	33.6	25.5	16.3	16.3	16.3	16.3	16.3
1972	8.2	8.2	8.2	8.2	8.2	8.2	8.2	8.2
1973	56.5	107.6	96.8	84.0	82.2	82.0	81.0	81.4
1974	5.3	5.3	5.3	5.3	5.3	5.3	5.3	5.3
1975	16.9	22.5	22.5	22.5	22.5	22.5	22.5	22.5
1976	31.8	55.0	55.0	55.9	55.9	55.9	55.3	55.3
1977	72.5	115.0	115.0	112.6	112.6	112.6	109.8	110.3
1978	112.8	163.4	163.4	152.2	151.1	151.2	147.0	148.3
1979	22.1	32.5	26.7	26.7	26.7	26.7	26.7	26.7
1980	12.7	12.7	12.7	12.7	12.7	12.7	12.7	12.7
1981	28.0	49.6	49.6	37.8	37.8	37.8	50.1	50.1
1982	11.3	21.6	21.6	21.6	21.6	21.6	21.6	21.6
1983	22.4	40.4	40.4	35.7	35.7	35.7	41.0	41.0
1984	107.6	144.8	145.6	135.6	131.5	129.0	130.6	128.3
1985	22.2	29.0	24.3	24.3	24.3	24.3	24.3	24.3
1986	20.4	31.8	31.8	32.3	32.3	32.3	32.0	32.0
1987	3.3	3.3	3.3	3.3	3.3	3.3	3.3	3.3
1988	28.5	41.9	41.9	42.1	42.1	42.1	41.9	41.9
Average	46.5	70.6	69.3	65.4	64.7	63.9	62.7	62.1

Remarks: Refer to ANNEX-D.

Table 8 POTENTIAL AND ANTICIPATED CROP YIELD

Crops	Potential Yield			Anticipated Yield		
	Crop Guide (1) (t/ha)	HRI (2) Mirpurkhas (t/ha)	Hyderabad District (3) (t/ha)	Present (t/ha)	Without Project (t/ha)	With Project (t/ha)
A. Fodder Crops						
Lucerne	20 - 30	-	25.4	13.9	13.9	26.0
Maize	18 - 23	-	16.4	10.6	10.6	18.0
B. Vegetables						
Solanaceous						
Tomato	5 - 10	23.2	6.0	3.3	3.3	7.0
Eggplant	5 - 10	19.1	7.8	4.9	4.9	9.0
Chilli	5 - 10	7.2	2.3	1.0	1.0	2.5
Cucurbits						
Sponge Gourd	10 - 15	-	9.8	3.1	3.1	11.0
Bottle Gourd	8 - 15	22.2	5.9	4.7	4.7	8.0
Cole Crops, Green, Herbs						
Cauliflower	13 - 18	23.1	9.7	13.3	13.3	16.0
Spinach	10 - 13	-	4.9	2.6	2.6	6.0
Root Crops						
Carrot	10 - 13	14.2	10.1	5.4	5.4	11.0
Radish	18 - 20	16.8	11.0	4.0	4.0	13.0
Turnip	13 - 20	12.2	13.8	6.6	6.6	15.0
Legunes, others						
Peas	8 - 10	6.2	3.9	2.6	2.6	5.0
C. Fruits						
Guava	-	-	6.3	3.8	3.8	7.0
Mango	-	-	8.5	6.1	6.1	9.0
Chikoo	-	-	2.7	2.3	2.3	3.0
Coconut	-	-	-	2.7	2.7	4.0
Papaya	-	-	6.9	7.3	7.3	8.5

Sources : 1) Crop Guide ; Agricultural Extension Department, Government of Sindh
2) HRI ; Vegetable Research Station, Horticulture Research Institute, Mirpurkhas
3) Hyderabad District , 1987/88 ; Bureau of Statistics, Planning and Development Department, Government of Sindh

Remarks : Refer to ANNEX-E

Table 9 INCREMENTAL CROP PRODUCTION WITHOUT AND WITH PROJECT

Crops	Without Project			With Project			Incremental Production (tons)
	Cropped Area (ha)	Unit Yield (t/ha)	Production (tons)	Cropped Area (ha)	Unit Yield (t/ha)	Production (tons)	
A. Fodder Crops							
Lucerne	100	13.9	1,390	100	26.0	2,600	1,210
Maize, others	90	10.6	954	100	18.0	1,800	846
All Fodder	<u>190</u>	(12.3) *	<u>2,344</u>	<u>200</u>	(22.0) *	<u>4,400</u>	<u>2,056</u>
B. Vegetables							
Tomato	400	3.3	1,320	1,000	7.0	7,000	5,680
Eggplant	140	4.9	686	500	9.0	4,500	3,814
Chilli	20	1.0	20	350	2.5	875	855
Sponge Gourd	160	3.1	496	1,000	11.0	11,000	10,504
Bottle Gourd	120	4.7	564	400	8.0	3,200	2,636
Cauliflower	100	13.3	1,330	300	16.0	4,800	3,470
Spinach	110	2.6	286	300	6.0	1,800	1,514
Carrot	120	5.4	648	200	11.0	2,200	1,552
Radish	70	4.0	280	150	13.0	1,950	1,670
Turnip	50	6.6	330	150	15.0	2,250	1,920
Peas	80	2.6	208	200	5.0	1,000	792
Others	170	4.5	788	750	8.9	6,071	5,283
All Vegetables	<u>1,540</u>	(4.5) *	<u>6,956</u>	<u>5,300</u>	(8.8) *	<u>46,646</u>	<u>39,690</u>
C. Fruits							
Guava	280	3.8	1,064	280	7.0	1,960	896
Mango	390	6.1	2,379	390	9.0	3,510	1,131
Chikoo	80	2.3	184	80	3.0	240	56
Coconut	90	2.7	243	90	4.0	360	117
Papaya	50	7.3	365	50	8.5	425	60
Others	110	4.8	523	110	6.9	761	238
All Fruit	<u>1,000</u>	(4.8) *	<u>4,758</u>	<u>1,000</u>	(7.3) *	<u>7,256</u>	<u>2,498</u>
Total	<u>2,730</u>		<u>14,058</u>	<u>6,500</u>		<u>58,302</u>	<u>44,244</u>

Remarks : (*) ; weighted average.
Refer to ANNEX-E

Table 10 UNIT NET INCOME WITHOUT AND WITH PROJECT

Crops	Without Project				With Project			
	Unit Yield (tons/ha)	Gross Income (Rs./ha)	Product. Cost (Rs./ha)	Net Income (Rs./ha)	Unit Yield (tons/ha)	Gross Income (Rs./ha)	Product. Cost (Rs./ha)	Net Income (Rs./ha)
A. Fodder Crops								
Lucerne	13.9	5,838	3,785	2,053	26.0	10,920	5,539	5,381
Maize, others	10.6	3,392	2,546	846	18.0	5,760	3,596	2,164
B. Vegetables								
Tomato	3.3	11,418	7,471	3,947	7.0	24,220	9,440	14,780
Eggplant	4.9	12,005	6,447	5,558	9.0	22,050	9,033	13,017
Chilli	1.0	7,660	5,759	1,901	2.5	19,150	8,560	10,590
Sponge Gourd	3.1	10,261	5,258	5,003	11.0	36,410	6,770	29,640
Bottle Gourd	4.7	13,536	5,841	7,695	8.0	23,040	7,190	15,850
Cauliflower	13.3	40,698	6,843	33,855	16.0	48,960	8,681	40,279
Spinach	2.6	4,498	4,274	224	6.0	10,380	6,145	4,235
Carrot	5.4	8,424	5,822	2,602	11.0	17,160	8,744	8,416
Raddish	4.0	7,800	6,200	1,600	13.0	25,350	8,807	16,543
Tunip	6.6	14,652	6,400	8,252	15.0	33,300	8,954	24,346
Peas	2.6	9,568	5,754	3,814	5.0	18,400	7,526	10,874
Others	4.5	12,991	6,289	6,702	8.8	24,196	8,124	16,072
C. Fruit								
Mango (2)	6.1	8,982	4,650	4,332	9.0	25,263	6,019	19,244
Guava (2)	3.8	8,071	4,954	3,117	7.0	19,824	6,299	13,525
Chikoo (2)	2.3	4,830	3,878	952	3.0	9,100	4,577	4,523
Coconut (2)	2.7	5,940	4,531	1,409	4.0	19,338	4,932	14,406
Papaya	7.3	15,257	10,159	5,098	8.5	12,584	6,471	6,113
Others	4.8	8,360	4,974	3,387	1.9	20,788	5,893	14,894

Remarks: Refer to ANNEX-F.

Table 11 INCREMENTAL NET INCOME WITHOUT AND WITH PROJECT

Crops	Unit : Rs ,000						
	Without Project			With Project			Incremental Value
	Gross Income	Total Cost	Net Income	Gross Income	Total Cost	Net Income	
A. Fodder Crops							
Lucerne	584	379	205	1,092	554	538	333
Maize, others	305	229	76	576	360	216	140
Sub-total	<u>889</u>	<u>608</u>	<u>281</u>	<u>1,668</u>	<u>914</u>	<u>755</u>	<u>473</u>
B. Vegetables							
Tomato	4,567	2,988	1,579	24,220	9,440	14,780	13,201
Eggplant	1,681	903	778	11,025	4,517	6,509	5,730
Chilli	153	115	38	6,703	2,996	3,707	3,668
Sponge Gourd	1,642	841	800	36,410	6,770	29,640	28,840
Bottle Gourd	1,624	701	923	9,216	2,876	6,340	5,417
Cauliflower	4,070	684	3,386	14,688	2,604	12,084	8,698
Spinach	495	470	25	3,114	1,844	1,271	1,246
Carrot	1,011	699	312	3,432	1,749	1,683	1,371
Radish	546	434	112	3,803	1,321	2,481	2,369
Turnip	733	320	413	4,995	1,343	3,652	3,239
Peas	765	460	305	3,680	1,505	2,175	1,870
Others	2,208	1,069	1,139	18,147	6,093	12,054	10,915
Sub-total	<u>19,495</u>	<u>9,685</u>	<u>9,810</u>	<u>139,432</u>	<u>43,057</u>	<u>96,375</u>	<u>86,564</u>
C. Fruit							
Guava	6,522	1,960	4,561	9,853	2,348	7,505	2,944
Mango	3,013	1,460	1,554	5,551	1,764	3,787	2,234
Chikoo	558	322	236	728	366	362	126
Coconut	1,176	374	802	1,740	444	1,297	495
Papaya	540	261	279	629	324	306	27
Others	1,460	541	919	2,287	648	1,638	720
Sub-total	<u>13,269</u>	<u>4,918</u>	<u>8,351</u>	<u>20,788</u>	<u>5,893</u>	<u>14,894</u>	<u>6,544</u>
Total	33,653	15,211	18,442	161,888	49,864	112,024	93,581

Remarks : Refer to ANNEX-F.

Table 12 SUMMARY OF IRRIGATION WATER DEMAND

Item	Unit:MCM	
	Irrigation Water Demand WAPDA Report*1	JICA Estimate*2 (1929 - 1988)
1 WAPDA Report (1982) (Without Project Condition)		
- Condition in 1977	62.0	65.3 *3
- Projection in 1987	-	53.1 *3
- Projection in 2002	-	35.6 *3
2 Present Cropping Pattern in 1987/88	-	42.0
3 Pumped Volume in 1987/88 Estimated based on KESC's Data	-	35.5

Remarks: *1 Pan evaporation data (1960-1966) were used in estimating irrigation demand.
 *2 Only field application efficiency of 60% is considered, since irrigation area is limited to only 5-20 ha.
 *3 Shows average irrigation water demand (1929 - 1988).

Refer to ANNEX-G.

Table 13 IRRIGATION WATER DEMAND - PROPOSED CROPPING PATTERN (1/3)

Summary of Crop and Basic Assumption

No.	C r o p	Application Efficiency	Percolation Loss Code	Land preparation Code	Pre-irrigation Code	Growing Stages
1	1 Crucifers	0.60	0	0	1	6
2	2 Cucumber	0.60	0	0	1	8
3	3 Tomatoes	0.60	0	0	1	9
4	4 Melon	0.60	0	0	1	8
5	5 Raddish	0.60	0	0	1	6
6	6 Fodder (Maize)	0.60	0	0	1	6
7	7 Alphalfa	0.60	0	0	1	24
8	8 Chillies	0.60	0	0	1	9
9	9 Beans (green)	0.60	0	0	1	6
10	10 Orchard (Citrus) 70%	0.60	0	0	0	24
11	11 Orchard (citrus) 20%	0.60	0	0	0	24
12	12 Upland Crops	0.60	0	0	1	6

No.	C r o p	Crop Coefficient (by growing stage)													
1	1 Crucifers	0.42	0.50	0.70	0.95	0.95	0.85								
2	2 Cucumber	0.40	0.45	0.70	0.90	0.92	0.92	0.92	0.85						
3	3 Tomatoes	0.42	0.42	0.55	0.80	1.00	1.05	1.05	0.95	0.70					
4	4 Melon	0.38	0.40	0.60	0.90	0.98	0.98	0.98	0.90						
5	5 Raddish	0.45	0.55	0.80	1.05	1.05	0.75								
6	6 Fodder (Maize)	0.45	0.55	0.85	1.05	1.05	0.95								
7	7 Alphalfa	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85	0.85
8	8 Chillies	0.65	0.75	0.85	0.95	1.00	1.00	1.00	0.95	0.90					
9	9 Beans (green)	0.45	0.52	0.75	0.95	0.95	0.90								
10	10 Orchard (Citrus) 70%	0.75	0.75	0.75	0.75	0.70	0.70	0.70	0.70	0.70	0.70	0.70	0.65	0.65	0.65
11	11 Orchard (citrus) 20%	0.65	0.65	0.65	0.65	0.65	0.65	0.65	0.70	0.70	0.70	0.70	0.70	0.70	0.70
		0.55	0.55	0.55	0.55	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.45	0.45	0.45
12	12 Upland Crops	0.45	0.45	0.45	0.45	0.45	0.45	0.45	0.45	0.50	0.50	0.50	0.50	0.50	0.50
		1.00	1.00	1.00	1.00	1.00	1.00								

Remarks; 1 growing stage = 15 days

Summary of crop and basic assumption in Malir Project (Proposed Cropping P., C.I=1.50)

No.	C r o p	Cultiva. Area(ha)	Date of Water Issue	Land Preparation Period (stages)
1	1 Crucifers	600.	7/ 1	6
3	3 Tomatoes	1500.	7/ 1	6
5	5 Raddish	500.	8/ 1	6
6	6 Fodder (Maize)	50.	8/ 1	4
7	7 Alphalfa	100.	7/ 1	12
9	9 Beans (green)	600.	8/ 1	6
10	10 Orchard (Citrus) 70%	1000.	7/ 1	12
2	2 Cucumber	1400.	1/ 1	8
3	3 Tomatoes	350.	1/ 1	8
6	6 Fodder (Maize)	50.	1/ 1	4
9	9 Beans (green)	350.	1/ 1	8
	Total Project Area	4350.		

Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Potential ET (mm)	110.0	125.0	192.0	224.0	253.0	233.0	193.0	176.0	179.0	166.0	123.0	101.0
Conveyance Efficiency	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Return Flow Factor	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15	0.15

Unit:mm

Code	1	2	3	4	5	6	7	8	9	10
Land Preparation	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Percolation Losses	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
Pre-irrigation	50.	0.	0.	0.	0.	0.	0.	0.	0.	0.

Table 13 IRRIGATION WATER DEMAND - PROPOSED CROPPING PATTERN (2/3)

Diversions Water Requirement for Malir Project (Proposed Cropping P., C.I=1.50)
 (Total Area : 4350. ha)

Unit : MCM

Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
1929	3.29	3.24	5.87	8.15	9.00	7.23	4.49	5.83	7.85	8.89	5.22	3.44	72.50
1930	3.07	3.24	5.87	8.06	9.00	5.66	0.03	5.96	7.85	8.89	6.31	3.95	67.89
1931	3.29	3.13	5.71	8.15	9.00	7.23	5.71	5.96	7.85	8.89	6.31	3.95	75.17
1932	3.20	3.24	5.87	8.15	9.00	7.23	0.29	5.17	7.85	8.89	6.31	3.95	69.15
1933	3.29	3.21	5.87	8.10	8.79	7.23	0.01	3.84	6.55	8.89	6.31	3.95	66.06
1934	3.31	3.24	5.80	8.15	9.00	6.26	1.92	5.83	7.85	8.89	6.31	3.69	70.25
1935	2.97	2.64	5.87	7.02	9.00	7.23	5.63	5.86	7.85	8.89	6.31	3.95	73.23
1936	3.29	2.94	5.84	8.15	9.00	6.67	4.15	5.99	7.85	8.89	6.31	3.89	72.96
1937	3.31	2.74	5.87	8.15	9.00	7.23	1.16	5.99	7.85	8.89	6.31	2.23	68.74
1938	3.31	3.24	5.87	8.10	8.87	7.20	4.75	4.14	7.85	8.89	6.31	3.80	72.33
1939	3.31	2.22	4.27	8.06	9.00	7.23	5.82	5.99	7.85	8.89	6.12	3.95	72.72
1940	1.96	2.58	4.54	8.15	9.00	6.91	4.49	4.46	7.85	8.89	6.31	3.69	68.83
1941	3.26	3.24	5.87	8.15	9.00	7.23	4.68	5.99	7.85	8.89	6.31	3.95	74.43
1942	2.99	2.68	5.74	8.15	9.00	7.23	0.63	5.45	7.85	8.89	6.31	3.66	68.59
1943	2.93	3.24	5.87	8.15	9.00	7.13	4.56	5.93	7.85	8.89	6.31	3.95	73.80
1944	3.20	2.30	5.87	8.15	9.00	7.23	0.33	0.07	7.85	8.89	6.31	3.92	63.11
1945	2.28	3.24	5.87	8.15	9.00	7.23	3.24	5.93	7.71	8.89	6.31	3.89	71.74
1946	3.31	3.24	5.87	8.15	9.00	7.16	4.44	4.81	7.85	8.89	6.31	3.95	72.98
1947	3.31	3.21	5.87	8.15	9.00	7.23	5.82	4.65	7.75	8.89	6.31	3.74	73.95
1948	3.31	2.70	4.99	8.15	9.00	6.00	4.92	5.99	7.85	8.89	6.31	3.74	71.85
1949	3.31	3.24	5.87	8.15	9.00	7.23	2.51	1.14	7.85	8.89	6.31	3.95	67.45
1950	3.07	3.24	5.87	8.15	9.00	7.23	4.01	5.99	7.85	8.89	6.31	3.95	73.57
1951	3.31	3.24	5.87	8.06	9.00	7.23	4.82	5.03	7.80	8.89	6.31	3.95	73.52
1952	3.31	2.53	5.87	8.15	9.00	7.23	2.01	5.99	6.86	8.89	6.31	3.86	70.02
1953	3.29	3.24	5.87	8.15	9.00	6.00	5.79	0.74	7.85	8.89	6.31	3.74	68.87
1954	2.93	2.62	5.87	8.15	9.00	7.23	4.44	5.00	2.24	8.89	6.31	3.95	66.64
1955	3.09	2.98	5.87	8.15	9.00	7.23	5.82	5.12	4.18	8.89	6.31	3.86	70.50
1956	2.87	3.24	5.87	7.98	9.00	5.94	2.08	3.53	7.85	4.29	6.31	3.95	62.90
1957	3.24	3.24	5.87	7.94	9.00	7.23	5.39	5.80	7.85	8.89	6.12	3.80	74.39
1958	3.18	3.19	5.87	8.15	9.00	7.23	2.67	5.99	6.55	8.89	6.26	2.56	69.55
1959	3.24	3.19	5.87	8.15	9.00	7.23	0.85	4.68	0.01	8.89	3.02	3.92	58.06
1960	3.26	3.24	4.93	8.15	9.00	7.23	4.73	5.17	7.85	8.89	6.31	3.33	72.10
1961	2.95	2.18	5.87	7.71	9.00	6.73	1.83	1.11	1.68	8.89	6.31	3.92	58.17
1962	3.31	3.24	5.87	8.15	9.00	7.23	3.82	4.78	2.31	8.89	6.31	3.77	66.70
1963	3.31	3.24	5.87	8.10	9.00	7.23	5.79	5.71	7.85	8.89	5.06	3.95	74.01
1964	3.26	3.13	5.87	8.15	9.00	7.16	3.92	4.59	7.71	8.89	6.31	3.95	71.95
1965	3.31	3.24	5.87	8.02	9.00	7.23	3.22	5.45	7.85	8.89	6.31	3.95	72.35
1966	3.31	3.24	5.84	8.15	9.00	7.23	4.13	5.99	7.85	8.89	6.31	3.95	73.89
1967	3.31	3.24	2.31	7.24	9.00	6.88	0.00	3.29	7.85	8.89	6.08	3.55	61.63
1968	3.07	3.15	5.87	8.15	9.00	7.23	5.82	5.83	7.85	8.89	6.31	3.77	74.95
1969	3.31	3.21	5.87	8.15	9.00	7.23	4.85	5.99	7.85	8.89	6.31	3.95	74.62
1970	3.16	3.08	4.11	8.15	9.00	7.06	2.21	1.81	4.54	8.89	6.31	3.95	62.28
1971	3.24	3.24	5.87	8.15	9.00	7.23	4.97	5.12	7.85	8.89	6.31	3.92	73.78
1972	3.31	3.17	5.87	8.15	9.00	6.61	5.39	5.99	7.85	8.89	6.31	3.83	74.37
1973	3.31	3.24	5.87	8.15	9.00	7.23	1.47	5.40	7.85	8.89	6.31	3.71	70.43
1974	3.31	3.24	5.87	8.15	9.00	7.23	5.82	5.99	7.85	8.89	6.31	3.80	75.47
1975	3.03	2.80	4.99	8.15	9.00	7.23	5.82	3.87	6.98	8.89	6.31	3.95	71.02
1976	2.00	3.02	4.99	8.15	9.00	7.23	1.04	4.95	6.10	8.89	6.31	3.95	65.63
1977	3.09	3.24	5.87	8.06	9.00	6.20	0.18	4.73	4.47	8.89	6.08	3.95	63.77
1978	3.01	3.15	5.87	8.15	9.00	7.03	1.58	1.30	7.85	8.89	6.31	3.95	66.09
1979	3.29	1.38	5.87	8.15	9.00	7.13	5.82	0.33	7.85	8.72	6.31	3.58	67.43
1980	3.31	3.24	5.56	8.15	9.00	5.94	4.68	5.99	7.85	7.73	6.04	2.28	69.77
1981	3.31	2.72	3.81	8.02	9.00	7.23	4.80	4.76	7.85	8.89	6.31	3.95	70.65
1982	3.26	2.74	5.87	8.15	9.00	7.23	5.12	3.11	7.85	8.89	6.31	3.92	71.45
1983	3.31	3.17	5.87	6.74	9.00	7.23	4.46	1.71	6.82	8.89	6.31	3.95	67.47
1984	3.31	3.24	5.87	8.15	9.00	7.23	5.32	0.40	7.67	8.89	6.31	3.95	69.34
1985	3.31	3.24	5.87	6.42	9.00	7.23	3.85	5.26	7.85	8.89	6.31	3.95	71.17
1986	3.31	3.24	5.53	8.15	9.00	6.70	5.82	4.24	7.85	8.89	6.31	3.95	72.99
1987	3.31	3.24	5.87	8.15	9.00	7.23	5.82	5.99	7.85	8.89	6.31	3.95	75.62
1988	3.29	3.24	5.87	8.15	9.00	7.23	3.99	3.63	7.85	8.89	6.31	3.95	71.40
Ave.	3.17	3.04	5.62	8.04	9.00	7.03	3.73	4.59	7.12	8.79	6.20	3.79	70.10

Table 13 IRRIGATION WATER DEMAND - PROPOSED CROPPING PATTERN (3/3)

Deep Percolation of Malir Project (Proposed Cropping P., C.I=1.50)
(Total Area : 4350. ha)

Unit : MCM

Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
1929	0.49	0.49	0.88	1.22	1.35	1.08	0.67	0.88	1.18	1.33	0.78	0.52	10.87
1930	0.46	0.49	0.88	1.21	1.35	0.85	0.00	0.89	1.18	1.33	0.95	0.59	10.18
1931	0.49	0.47	0.86	1.22	1.35	1.08	0.86	0.89	1.18	1.33	0.95	0.59	11.28
1932	0.48	0.49	0.88	1.22	1.35	1.08	0.04	0.78	1.18	1.33	0.95	0.59	10.37
1933	0.49	0.48	0.88	1.22	1.32	1.08	0.00	0.58	0.98	1.33	0.95	0.59	9.91
1934	0.50	0.49	0.87	1.22	1.35	0.94	0.29	0.88	1.18	1.33	0.95	0.55	10.54
1935	0.45	0.40	0.88	1.05	1.35	1.08	0.84	0.88	1.18	1.33	0.95	0.59	10.98
1936	0.49	0.44	0.88	1.22	1.35	1.00	0.62	0.90	1.18	1.33	0.95	0.58	10.94
1937	0.50	0.41	0.88	1.22	1.35	1.08	0.17	0.90	1.18	1.33	0.95	0.33	10.31
1938	0.50	0.49	0.88	1.22	1.33	1.08	0.71	0.62	1.18	1.33	0.95	0.57	10.85
1939	0.50	0.33	0.64	1.21	1.35	1.08	0.87	0.90	1.18	1.33	0.92	0.59	10.91
1940	0.29	0.39	0.68	1.22	1.35	1.04	0.67	0.67	1.18	1.33	0.95	0.55	10.32
1941	0.49	0.49	0.88	1.22	1.35	1.08	0.70	0.90	1.18	1.33	0.95	0.59	11.16
1942	0.45	0.40	0.86	1.22	1.35	1.08	0.10	0.82	1.18	1.33	0.95	0.55	10.29
1943	0.44	0.49	0.88	1.22	1.35	1.07	0.68	0.89	1.18	1.33	0.95	0.59	11.07
1944	0.48	0.34	0.88	1.22	1.35	1.08	0.05	0.01	1.18	1.33	0.95	0.59	9.47
1945	0.34	0.49	0.88	1.22	1.35	1.08	0.49	0.89	1.16	1.33	0.95	0.58	10.76
1946	0.50	0.49	0.88	1.22	1.35	1.07	0.67	0.72	1.18	1.33	0.95	0.59	10.95
1947	0.50	0.48	0.88	1.22	1.35	1.08	0.87	0.70	1.16	1.33	0.95	0.56	11.09
1948	0.50	0.41	0.75	1.22	1.35	0.90	0.74	0.90	1.18	1.33	0.95	0.56	10.78
1949	0.50	0.49	0.88	1.22	1.35	1.08	0.38	0.17	1.18	1.33	0.95	0.59	10.12
1950	0.46	0.49	0.88	1.22	1.35	1.08	0.60	0.90	1.18	1.33	0.95	0.59	11.04
1951	0.50	0.49	0.88	1.21	1.35	1.08	0.72	0.75	1.17	1.33	0.95	0.59	11.03
1952	0.50	0.38	0.88	1.22	1.35	1.08	0.30	0.90	1.03	1.33	0.95	0.58	10.50
1953	0.49	0.49	0.88	1.22	1.35	0.90	0.87	0.11	1.18	1.33	0.95	0.56	10.33
1954	0.44	0.39	0.88	1.22	1.35	1.08	0.67	0.75	0.34	1.33	0.95	0.59	10.00
1955	0.46	0.45	0.88	1.22	1.35	1.08	0.87	0.77	0.63	1.33	0.95	0.58	10.58
1956	0.43	0.49	0.88	1.20	1.35	0.89	0.31	0.53	1.18	0.64	0.95	0.59	9.43
1957	0.49	0.49	0.88	1.19	1.35	1.08	0.81	0.87	1.18	1.33	0.92	0.57	11.16
1958	0.48	0.48	0.88	1.22	1.35	1.08	0.40	0.90	0.98	1.33	0.94	0.38	10.43
1959	0.49	0.48	0.88	1.22	1.35	1.08	0.13	0.70	0.00	1.33	0.45	0.59	8.71
1960	0.49	0.49	0.74	1.22	1.35	1.08	0.71	0.78	1.18	1.33	0.95	0.50	10.81
1961	0.44	0.33	0.88	1.16	1.35	1.01	0.27	0.17	0.25	1.33	0.95	0.59	8.73
1962	0.50	0.49	0.88	1.22	1.35	1.08	0.57	0.72	0.35	1.33	0.95	0.57	10.00
1963	0.50	0.49	0.88	1.22	1.35	1.08	0.87	0.86	1.18	1.33	0.76	0.59	11.10
1964	0.49	0.47	0.88	1.22	1.35	1.07	0.59	0.69	1.16	1.33	0.95	0.59	10.79
1965	0.50	0.49	0.88	1.20	1.35	1.08	0.48	0.82	1.18	1.33	0.95	0.59	10.85
1966	0.50	0.49	0.88	1.22	1.35	1.08	0.62	0.90	1.18	1.33	0.95	0.59	11.08
1967	0.50	0.49	0.35	1.09	1.35	1.03	0.00	0.49	1.18	1.33	0.91	0.53	9.24
1968	0.46	0.47	0.88	1.22	1.35	1.08	0.87	0.88	1.18	1.33	0.95	0.57	11.24
1969	0.50	0.48	0.88	1.22	1.35	1.08	0.73	0.90	1.18	1.33	0.95	0.59	11.19
1970	0.47	0.46	0.62	1.22	1.35	1.06	0.33	0.27	0.68	1.33	0.95	0.59	9.34
1971	0.49	0.49	0.88	1.22	1.35	1.08	0.75	0.77	1.18	1.33	0.95	0.59	11.07
1972	0.50	0.48	0.88	1.22	1.35	0.99	0.81	0.90	1.18	1.33	0.95	0.57	11.16
1973	0.50	0.49	0.88	1.22	1.35	1.08	0.22	0.81	1.18	1.33	0.95	0.56	10.56
1974	0.50	0.49	0.88	1.22	1.35	1.08	0.87	0.90	1.18	1.33	0.95	0.57	11.32
1975	0.45	0.42	0.75	1.22	1.35	1.08	0.87	0.58	1.05	1.33	0.95	0.59	10.65
1976	0.30	0.45	0.75	1.22	1.35	1.08	0.16	0.74	0.91	1.33	0.95	0.59	9.84
1977	0.46	0.49	0.88	1.21	1.35	0.93	0.03	0.71	0.67	1.33	0.91	0.59	9.57
1978	0.45	0.47	0.88	1.22	1.35	1.05	0.24	0.20	1.18	1.33	0.95	0.59	9.91
1979	0.49	0.21	0.88	1.22	1.35	1.07	0.87	0.05	1.18	1.31	0.95	0.54	10.11
1980	0.50	0.49	0.83	1.22	1.35	0.89	0.70	0.90	1.18	1.16	0.91	0.34	10.46
1981	0.50	0.41	0.57	1.20	1.35	1.08	0.72	0.71	1.18	1.33	0.95	0.59	10.60
1982	0.49	0.41	0.88	1.22	1.35	1.08	0.77	0.47	1.18	1.33	0.95	0.59	10.72
1983	0.50	0.48	0.88	1.01	1.35	1.08	0.67	0.26	1.02	1.33	0.95	0.59	10.12
1984	0.50	0.49	0.88	1.22	1.35	1.08	0.80	0.06	1.15	1.33	0.95	0.59	10.40
1985	0.50	0.49	0.88	0.96	1.35	1.08	0.58	0.79	1.18	1.33	0.95	0.59	10.68
1986	0.50	0.49	0.83	1.22	1.35	1.00	0.87	0.64	1.18	1.33	0.95	0.59	10.95
1987	0.50	0.49	0.88	1.22	1.35	1.08	0.87	0.90	1.18	1.33	0.95	0.59	11.34
1988	0.49	0.49	0.88	1.22	1.35	1.08	0.60	0.54	1.18	1.33	0.95	0.59	10.71
Ave.	0.47	0.46	0.84	1.21	1.35	1.05	0.56	0.69	1.07	1.32	0.93	0.57	10.52

Table 14 SALIENT FEATURES OF MOL DAM

	Unit	Mol Dam
a) General		
Location		8.3 km upstream of Super Highway Bridge.
River		Mol tributary of Maril River
Type of dam		Rockfill (Zone type)
Purpose		Groundwater recharge (Irrigation + Domestic Water Supply)
b) Hydrology		
Catchment area	km ²	596
Mean annual rainfall	mm	231
Mean annual runoff	MCM	44.9
c) Reservoir		
Live storage	MCM	35.0
Flood control storage	MCM	0.0
Dead storage	MCM	10.7
Gross storage	MCM	45.7
Maximum reservoir area	km ²	5.5
d) Dam		
Type		Rockfill (Zone type)
Maximum height	m	48.8
Length of crest	m	2,347
Top width	m	10.0
Crest elevation of dam	EL. m	175.3
Normal full water level	EL. m	169.6
Maximum water level	EL. m	173.0
Slope: Upstream		1 : 2.5
Downstream		1 : 2.0
Dam volume	10 ³ m ³	1,730
e) Spillway		
Type		Submerged weir (ungated)
Portable maximum flood	m ³ /sec	4,280
Design capacity	m ³ /sec	4,100
Surcharge for design flood	m	3.4
Crest elevation	EL. m	169.6
Energy dissipation		No Stilling Basin
f) Off-take Structure		
		2.4 m dia tunnel with control gate at outlet end and emergency control gate at inlet end with stilling basin on downstream end.
Outfall Channel		Channel into natural Nullah.
g) Irrigation System		
		Recharging aquifer by controlled releases from Mol Dam
h) Irrigation Area (Cropped area) ha		
		4,350 (6,500)
Domestic Water Supply	MCM	3.3

Refer to ANNEX-H

Table 15 SUMMARY OF PROJECT COST

Unit: Rs.10⁶

Item	Foreign Currency	Local Currency	Total
1. Direct Construction Cost			
1.1 Preparatory Works	27.0	5.9	32.9
1.2 Mol Dam	362.6	76.8	439.4
A. Main Dam	212.3	36.5	248.8
B. Saddle Dam	10.9	2.0	12.9
C. Spillway	51.8	16.7	68.5
D. Intake Facility	68.9	13.2	82.1
E. Diversion Works	9.9	3.5	13.4
F. Access Road	8.8	3.8	12.6
G. Land Acquisition	0.0	1.1	1.1
1.3 Causeway	2.4	3.8	6.2
1.4 Pilot Demonstration Farm	10.4	2.9	13.3
1.5 Project Office	0.4	0.8	1.2
Sub-total	402.8	90.2	493.0
2. Procurement of O & M Equipment	10.3	0.0	10.3
3. Physical Contingency	58.2	12.8	71.0
4. Administration Cost	0.0	6.7	6.7
5. Engineering Services	59.6	16.4	76.0
Sub-total	530.9	126.1	657.0
6. Price Contingency	0.0	28.6	28.6
Grand Total	530.9	154.7	685.6

Table 16 BREAKDOWN OF DIRECT CONSTRUCTION COST FOR MOL DAM (35 MCM)

Work Item	Unit	Unit Rate (Rs.)		Qty	Amount (1000 Rs.)		Total
		F/C	L/C		F/C	L/C	
I. Direct Construction Cost							
1.1 Preparatory Works				7%	27,029	5,903	32,933
1.2 Mol Dam					362,656	76,840	439,496
A. Main Dam							
1) Excavation							
a) Common (Backhoe)	m3	39.0	6.5	38,100	1,486	248	1,734
b) Common (Bulldozer) (1)	m3	57.7	7.4	44,500	2,568	329	2,897
c) Common (Bulldozer) (2)	m3	57.7	7.4	44,400	2,562	329	2,890
d) W. Rock (1)	m3	88.7	10.8	36,900	3,273	399	3,672
e) W. Rock (2)	m3	40.1	4.8	86,000	3,449	413	3,861
f) Rock (1)	m3	129.2	24.5	15,800	2,041	387	2,428
g) Rock (2)	m3	76.1	26.9	36,800	2,800	990	3,790
2) Filling							
a) Zone 1 (Core)	m3	119.9	16.4	298,900	35,838	4,902	40,740
b) Zone 2 (Random) (1)	m3	63.7	9.1	154,300	9,829	1,404	11,233
c) Zone 2 (Random) (2)	m3	63.7	9.1	99,300	6,325	904	7,229
d) Zone 2 (Random) (3)	m3	87.4	11.7	312,400	27,304	3,655	30,959
e) Zone 3 (Rock) (1)	m3	81.9	10.0	81,100	6,642	811	7,453
f) Zone 3 (Rock) (2)	m3	81.9	10.0	162,000	13,268	1,620	14,888
g) Zone 3 (Rock) (3)	m3	136.4	23.5	323,800	44,166	7,609	51,776
h) Rock facing	m3	136.4	23.5	83,000	11,321	1,951	13,272
i) Filter	m3	168.5	21.1	181,100	30,515	3,821	34,337
3) Foundation Treatment							
a) Curtain Grouting	m	555.8	421.6	9,500	5,280	4,005	9,285
b) Blanket Grouting	m	555.8	421.6	6,600	3,668	2,783	6,451
Total (A)					212,336	36,558	248,895
B. Saddle Dam							
1) Excavation							
a) Common (Bulldozer) (1)	m3	57.7	7.4	5,200	300	38	339
b) Common (Bulldozer) (2)	m3	16.1	2.4	5,100	82	12	94
c) W. Rock (1)	m3	88.7	10.8	15,400	1,366	166	1,532
d) W. Rock (2)	m3	40.1	4.8	35,900	1,440	172	1,612
e) Rock (1)	m3	129.2	24.5	12,300	1,589	301	1,891
f) Rock (2)	m3	76.1	26.9	28,800	2,192	775	2,966
2) Filling							
a) Zone 1 (Core)	m3	119.9	16.4	24,800	2,974	407	3,380
b) Zone 3 (Rock)	m3	81.9	10.0	4,200	344	42	386
c) Rock Facing	m3	136.4	23.5	4,400	600	103	704
Total (B)					10,886	2,018	12,904
C. Spillway							
1) Excavation							
a) Common (1)	m3	57.7	7.4	35,600	2,054	263	2,318
b) Common (2)	m3	16.1	2.4	35,600	573	85	659
c) W. Rock (1)	m3	88.7	10.8	32,000	2,838	346	3,184
d) W. Rock (2)	m3	40.1	4.8	74,800	2,999	359	3,359
e) Rock (1)	m3	129.2	24.5	53,400	6,899	1,308	8,208
f) Rock (2)	m3	63.8	16.8	124,600	7,949	2,093	10,043
2) Concrete Works							
a) Concrete (210 kg/cm2)	m3	1435.1	503.7	1,400	2,009	705	2,714
b) Concrete (180 kg/cm2)	m3	1134.4	405.9	18,800	21,327	7,631	28,958
c) Reinforcement bar	ton	13003.4	9827.1	400	5,201	3,931	9,132
Total (C)					51,851	16,722	68,573
D. Intake Facilities							
1) Earth Works							
a) Common Excavation	m3	57.7	7.4	14,900	860	110	970
b) W. Rock	m3	88.7	10.8	124,100	11,008	1,340	12,348
c) Rock	m3	133.5	33.8	53,200	7,102	1,798	8,900
2) Concrete Works							
a) Concrete (210kg/cm2)	m3	1435.1	503.7	11,100	15,930	5,591	21,521
b) Reinforcement bar	ton	13003.4	9827.1	440	5,721	4,324	10,045
c) Steel pipe	ton	28600.0	0.0	100	2,860	0	2,860
d) High pressure gate	set			2	11,424	0	11,424
e) Gates	set			4	14,000	0	14,000
Total (D)					68,905	13,164	82,068
E. Diversion Works					9,900	3,540	13,440
F. Access Road					8,778	3,762	12,540
G. Land Acquisition					0	1,076	1,076
1.3 Causeway	Nos.	605,328	946,553	4	2,421	3,786	6,208
1.4 Pilot Demonstration Farm					10,393	2,869	13,262
1.5 Project Office					360	840	1,200
2. O & M Equipment		10,300	0		10,300	0	10,300
3. Physical Contingency					58,152	12,750	70,902
4. Administration Cost					0	6,700	6,700
5. Engineering Services					59,600	16,400	76,000
Total(1-5)					530,912	126,088	657,000

Table 17 ANNUAL DISBURSEMENT SCHEDULE

Work Item	(Unit: Rs.10 ⁶)								
	Amount			1,991			1,992		
	F/C	L/C	Total	F/C	L/C	Total	F/C	L/C	Total
1. Preparatory Works	27,029	5,903	32,933	-	-	-	27,029	5,903	32,933
2. Mol Dam									
A. Main Dam	212,336	36,558	248,895	-	-	-	15,479	4,254	19,733
B. Saddle Dam	10,886	2,018	12,904	-	-	-	-	-	-
C. Spillway	51,851	16,722	68,573	-	-	-	16,320	3,119	19,438
D. Intake Facilities	68,905	13,164	82,068	-	-	-	26,103	4,665	30,768
E. Diversion Works	9,900	3,540	13,440	-	-	-	9,900	3,540	13,440
F. Access Road	8,778	3,762	12,540	-	-	-	8,778	3,762	12,540
G. Land Acquisition	0	1,076	1,076	0	538	538	0	538	538
Sub-total(2)	362,656	76,840	439,496	0	538	538	76,579	19,878	96,457
3. Causeway	2,421	3,786	6,208	-	-	-	-	-	-
4. Pilot Demonstration Farm	10,393	2,869	13,262	-	-	-	-	-	-
5. Project Office	360	840	1,200	-	-	-	360	840	1,200
6. O & M Equipment	10,300	0	10,300	-	-	-	-	-	-
Total (2-6)	386,131	84,335	470,465	0	538	538	76,939	20,718	97,657
7. Physical Contingency	58,152	12,750	70,902	0	81	81	11,564	3,118	14,682
Total (1 - 7)	471,311	102,989	574,300	0	619	619	115,533	29,739	145,272
8. Administration Cost	0	6,700	6,700	-	-	-	0	1,675	1,675
9. Engineering Services	59,600	16,400	76,000	10,575	3,600	14,175	14,900	4,100	19,000
Total (1 - 8)	530,912	126,088	657,000	10,575	4,219	14,794	130,433	35,514	165,947
10. Price Contingency	0	28,642	28,642	0	295	295	0	5,146	5,146
Grand Total	530,912	154,730	685,642	10,575	4,514	15,089	130,433	40,660	171,093

Work Item	1,993			1,994			1,995		
	F/C	L/C	Total	F/C	L/C	Total	F/C	L/C	Total
1. Preparatory Works	-	-	-	-	-	-	-	-	-
2. Mol Dam									
A. Main Dam	91,524	16,191	107,715	82,183	12,778	94,961	23,151	3,335	26,486
B. Saddle Dam	-	-	-	10,886	2,018	12,904	-	-	-
C. Spillway	24,830	9,003	33,833	10,701	4,600	15,302	-	-	-
D. Intake Facilities	42,801	8,499	51,300	-	-	-	-	-	-
E. Diversion Works	-	-	-	-	-	-	-	-	-
F. Access Road	-	-	-	-	-	-	-	-	-
G. Land Acquisition	-	-	-	-	-	-	-	-	-
Sub-total(2)	159,155	33,693	192,848	103,771	19,396	123,167	23,151	3,335	26,486
3. Causeway	0	0	0	2,421	3,786	6,208	-	-	-
4. Pilot Demonstration Farm	10,393	2,869	13,262	-	-	-	-	-	-
5. Project Office	-	-	-	-	-	-	-	-	-
6. O & M Equipment	-	-	-	10,300	0	0	-	-	-
Total (2-6)	169,548	36,562	206,110	116,492	23,182	129,374	23,151	3,335	26,486
7. Physical Contingency	25,524	5,524	31,049	17,543	3,507	21,050	3,521	520	4,041
Total (1 - 7)	195,072	42,086	237,159	134,035	26,690	160,724	26,672	3,855	30,527
8. Administration Cost	0	2,233	2,233	0	2,233	2,233	0	558	558
9. Engineering Services	15,167	3,867	19,033	15,167	3,867	19,033	3,792	967	4,758
Total (1 - 8)	210,239	48,186	258,425	149,201	32,790	181,991	30,463	5,380	35,843
10. Price Contingency	0	10,844	10,844	0	10,191	10,191	0	2,166	2,166
Grand Total	210,239	59,030	269,269	149,201	42,980	192,182	30,463	7,545	38,009

Table 18 STRUCTURE OF FINANCIAL AND ECONOMIC COST

Cost Component	Unit: %								Weighted Conversion Factor
	Financial Cost				Economic Cost				
	Foreign Cost	Transfer Payment	Local Cost Un-skilled labour	Others	Foreign Cost	Transfer Payment	Local Cost Un-skilled labour	Others	
A. Capital Cost									
1. Preparatory Works	82	0	4	14	82	0	3	12	97
2. Mol Dam	83	0	4	13	83	0	3	11	97
3. Causeway	39	0	14	47	39	0	10	40	89
4. Pilot Demonstration Farm	78	0	5	17	78	0	4	14	96
5. Project Office	30	0	17	54	30	0	12	45	87
6. O&M Equipment	100	0	0	0	100	0	0	0	100
7. Physical Contingency	82	0	4	14	82	0	3	12	97
8. Administration Cost	0	0	24	76	0	0	16	65	81
9. Engineering Servoces	78	0	5	17	78	0	4	14	96
B. O&M Cost									
1. Administration Staff	0	0	0	100	0	0	0	85	85
2. Operation Cost of O&M Equipment	0	0	0	100	0	0	0	85	85
3. Office Operation Cost	0	0	0	100	0	0	0	85	85

Table 19 ECONOMIC COST AND BENEFIT FLOW

EIRR= 10.60%
 NPV(8%)= 196.4 million Rs.
 B/C(8%)= 1.36

Unit: Rs.1,000

Year	Cost			Benefit		Total	Balance	
	Investment	Annual O&M	Replacement	Irrigation	Well Ope.			
1 1991	13,662			0		0	-13,662	
2 1992	159,528			0		0	-159,528	
3 1993	249,731			0		0	-249,731	
4 1994	175,373			0		0	-175,373	
5 1995	34,507			0		0	-34,507	
6 1996		4,335		4,335	50,137	2,551	52,688	48,353
7 1997		4,335		4,335	63,210	2,551	65,761	61,426
8 1998		4,335		4,335	76,283	2,551	78,833	74,498
9 1999		4,335		4,335	84,998	2,551	87,548	83,213
10 2000		4,335		4,335	93,713	2,551	96,264	91,929
11 2001		4,335		4,335	93,713	4,450	98,163	93,828
12 2002		4,335		4,335	93,713	4,450	98,163	93,828
13 2003		4,335		4,335	93,713	4,450	98,163	93,828
14 2004		4,335		4,335	93,713	4,450	98,163	93,828
15 2005		4,335	10,300	14,635	93,713	4,450	98,163	83,528
16 2006		4,335		4,335	93,713	1,203	94,916	90,581
17 2007		4,335		4,335	93,713	1,203	94,916	90,581
18 2008		4,335		4,335	93,713	1,203	94,916	90,581
19 2009		4,335		4,335	93,713	1,203	94,916	90,581
20 2010		4,335		4,335	93,713	1,203	94,916	90,581
21 2011		4,335		4,335	93,713	1,203	94,916	90,581
22 2012		4,335		4,335	93,713	1,203	94,916	90,581
23 2013		4,335		4,335	93,713	1,203	94,916	90,581
24 2014		4,335		4,335	93,713	1,203	94,916	90,581
25 2015		4,335	10,300	14,635	93,713	1,203	94,916	80,281
26 2016		4,335		4,335	93,713	1,203	94,916	90,581
27 2017		4,335		4,335	93,713	1,203	94,916	90,581
28 2018		4,335		4,335	93,713	1,203	94,916	90,581
29 2019		4,335		4,335	93,713	1,203	94,916	90,581
30 2020		4,335	25,500	29,835	93,713	1,203	94,916	65,081
31 2021		4,335		4,335	93,713	1,203	94,916	90,581
32 2022		4,335		4,335	93,713	1,203	94,916	90,581
33 2023		4,335		4,335	93,713	1,203	94,916	90,581
34 2024		4,335		4,335	93,713	1,203	94,916	90,581
35 2025		4,335	10,300	14,635	93,713	1,203	94,916	80,281
36 2026		4,335		4,335	93,713	1,203	94,916	90,581
37 2027		4,335		4,335	93,713	1,203	94,916	90,581
38 2028		4,335		4,335	93,713	1,203	94,916	90,581
39 2029		4,335		4,335	93,713	1,203	94,916	90,581
40 2030		4,335		4,335	93,713	1,203	94,916	90,581
41 2031		4,335		4,335	93,713	1,203	94,916	90,581
42 2032		4,335		4,335	93,713	1,203	94,916	90,581
43 2033		4,335		4,335	93,713	1,203	94,916	90,581
44 2034		4,335		4,335	93,713	1,203	94,916	90,581
45 2035		4,335	10,300	14,635	93,713	1,203	94,916	80,281
46 2036		4,335		4,335	93,713	1,203	94,916	90,581
47 2037		4,335		4,335	93,713	1,203	94,916	90,581
48 2038		4,335		4,335	93,713	1,203	94,916	90,581
49 2039		4,335		4,335	93,713	1,203	94,916	90,581
50 2040		4,335		4,335	93,713	1,203	94,916	90,581
51 2041		4,335		4,335	93,713	1,203	94,916	90,581
52 2042		4,335		4,335	93,713	1,203	94,916	90,581
53 2043		4,335		4,335	93,713	1,203	94,916	90,581
54 2044		4,335		4,335	93,713	1,203	94,916	90,581
55 2045		4,335		4,335	93,713	1,203	94,916	90,581

Table 20 INCREMENTAL GROSS MARGIN OF OWNER AND TENANT OPERATED FARMS AT VARIOUS SCALES

Item	Holding Size (ha)					Unit : Rs.
	1.0	3.0	5.0	10.0	20.0	
1 Owner Operated Farm						
A. Without Project						
Gross income	6,851	20,552	34,253	68,505	137,011	
Production cost incl. labor cost	3,094	9,282	15,469	30,939	61,878	
Gross margin	<u>3,757</u>	<u>11,270</u>	<u>18,783</u>	<u>37,567</u>	<u>75,133</u>	
B. With project						
Gross income	30,794	92,383	153,971	307,942	615,884	
Production cost incl. labor cost	10,483	31,448	52,414	104,827	209,654	
Gross margin	<u>20,311</u>	<u>60,934</u>	<u>101,557</u>	<u>203,115</u>	<u>406,229</u>	
C. Increment						
Gross income	23,944	71,831	119,718	239,436	478,873	
Production cost incl. labor cost	7,389	22,166	36,944	73,888	147,777	
Gross margin	<u>16,555</u>	<u>49,664</u>	<u>82,774</u>	<u>165,548</u>	<u>331,096</u>	
2 Tenant Operated Farm						
A. Without Project						
Gross income	3,425	10,276	17,126	34,253	68,505	
Production cost incl. labor cost	2,926	8,779	14,631	29,263	58,526	
Family labor cost	1,379	4,138	6,897	13,793	27,587	
Farmer's income	<u>1,878</u>	<u>5,635</u>	<u>9,392</u>	<u>18,783</u>	<u>37,567</u>	
B. With project						
Gross income	15,397	46,191	76,985	153,971	307,942	
Production cost incl. labor cost	9,978	29,933	49,888	99,775	199,551	
Family labor cost	4,736	14,209	23,681	47,362	94,724	
Farmer's income	<u>10,156</u>	<u>30,468</u>	<u>50,779</u>	<u>101,557</u>	<u>203,115</u>	
C. Increment						
Gross income	11,972	35,915	59,859	119,718	239,436	
Production cost incl. labor cost	7,051	21,154	35,256	70,513	141,025	
Family labor cost	3,357	10,071	16,784	33,569	67,137	
Farmer's income	<u>8,278</u>	<u>24,833</u>	<u>41,387</u>	<u>82,775</u>	<u>165,548</u>	

Refer to ANNEX - J

FIGURES






Fig.1 Meteorological Characteristics

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY




ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY


MOL RIVER AT DAM SITE



KHADEJI RIVER AT DAM SITE



MALIR RIVER AT SUPER HIGHWAY BRIDGE



MALIR RIVER AT NATIONAL HIGHWAY BRIDGE





Fig.3 Simulated Annual River Runoff at Major Control Points

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY

MOL RIVER AT DAM SITE



KHADEJI RIVER AT DAM SITE




Fig.4 River Runoff Pattern and Masscurves at Mol and Khadeji Damsites

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY







Fig.5 Location Map of Hydrogeological Investigations



Station	1977	1989	1977	1989	1977	1989	1977	1989	1977	1989
E9	38.0	35.0	38.0	35.0	38.0	35.0	38.0	35.0	38.0	35.0
E8	35.0	32.0	35.0	32.0	35.0	32.0	35.0	32.0	35.0	32.0
E7	32.0	29.0	32.0	29.0	32.0	29.0	32.0	29.0	32.0	29.0
E6	29.0	26.0	29.0	26.0	29.0	26.0	29.0	26.0	29.0	26.0
E5	26.0	23.0	26.0	23.0	26.0	23.0	26.0	23.0	26.0	23.0
E4	23.0	20.0	23.0	20.0	23.0	20.0	23.0	20.0	23.0	20.0
E3	20.0	17.0	20.0	17.0	20.0	17.0	20.0	17.0	20.0	17.0
E2	17.0	14.0	17.0	14.0	17.0	14.0	17.0	14.0	17.0	14.0
E1	14.0	11.0	14.0	11.0	14.0	11.0	14.0	11.0	14.0	11.0
E0	11.0	8.0	11.0	8.0	11.0	8.0	11.0	8.0	11.0	8.0



Station	1977	1989	1977	1989	1977	1989	1977	1989	1977	1989
E10	55.0	52.0	55.0	52.0	55.0	52.0	55.0	52.0	55.0	52.0
E11	52.0	49.0	52.0	49.0	52.0	49.0	52.0	49.0	52.0	49.0
E12	49.0	46.0	49.0	46.0	49.0	46.0	49.0	46.0	49.0	46.0
E13	46.0	43.0	46.0	43.0	46.0	43.0	46.0	43.0	46.0	43.0
E14	43.0	40.0	43.0	40.0	43.0	40.0	43.0	40.0	43.0	40.0
E15	40.0	37.0	40.0	37.0	40.0	37.0	40.0	37.0	40.0	37.0
E16	37.0	34.0	37.0	34.0	37.0	34.0	37.0	34.0	37.0	34.0
E17	34.0	31.0	34.0	31.0	34.0	31.0	34.0	31.0	34.0	31.0
E18	31.0	28.0	31.0	28.0	31.0	28.0	31.0	28.0	31.0	28.0
E19	28.0	25.0	28.0	25.0	28.0	25.0	28.0	25.0	28.0	25.0
E20	25.0	22.0	25.0	22.0	25.0	22.0	25.0	22.0	25.0	22.0
E21	22.0	19.0	22.0	19.0	22.0	19.0	22.0	19.0	22.0	19.0
E22	19.0	16.0	19.0	16.0	19.0	16.0	19.0	16.0	19.0	16.0
E23	16.0	13.0	16.0	13.0	16.0	13.0	16.0	13.0	16.0	13.0
E24	13.0	10.0	13.0	10.0	13.0	10.0	13.0	10.0	13.0	10.0
E25	10.0	7.0	10.0	7.0	10.0	7.0	10.0	7.0	10.0	7.0
E26	7.0	4.0	7.0	4.0	7.0	4.0	7.0	4.0	7.0	4.0
E27	4.0	1.0	4.0	1.0	4.0	1.0	4.0	1.0	4.0	1.0
E28	1.0	-2.0	1.0	-2.0	1.0	-2.0	1.0	-2.0	1.0	-2.0
E29	-2.0	-5.0	-2.0	-5.0	-2.0	-5.0	-2.0	-5.0	-2.0	-5.0
E30	-5.0	-8.0	-5.0	-8.0	-5.0	-8.0	-5.0	-8.0	-5.0	-8.0
E31	-8.0	-11.0	-8.0	-11.0	-8.0	-11.0	-8.0	-11.0	-8.0	-11.0
E32	-11.0	-14.0	-11.0	-14.0	-11.0	-14.0	-11.0	-14.0	-11.0	-14.0
E33	-14.0	-17.0	-14.0	-17.0	-14.0	-17.0	-14.0	-17.0	-14.0	-17.0
E34	-17.0	-20.0	-17.0	-20.0	-17.0	-20.0	-17.0	-20.0	-17.0	-20.0
E35	-20.0	-23.0	-20.0	-23.0	-20.0	-23.0	-20.0	-23.0	-20.0	-23.0



Station	1977	1989	1977	1989	1977	1989	1977	1989	1977	1989
E35	95.0	92.0	95.0	92.0	95.0	92.0	95.0	92.0	95.0	92.0
E33	92.0	89.0	92.0	89.0	92.0	89.0	92.0	89.0	92.0	89.0
E34	89.0	86.0	89.0	86.0	89.0	86.0	89.0	86.0	89.0	86.0
E32	86.0	83.0	86.0	83.0	86.0	83.0	86.0	83.0	86.0	83.0
E31	83.0	80.0	83.0	80.0	83.0	80.0	83.0	80.0	83.0	80.0
E30	80.0	77.0	80.0	77.0	80.0	77.0	80.0	77.0	80.0	77.0
E29	77.0	74.0	77.0	74.0	77.0	74.0	77.0	74.0	77.0	74.0
E28	74.0	71.0	74.0	71.0	74.0	71.0	74.0	71.0	74.0	71.0
E27	71.0	68.0	71.0	68.0	71.0	68.0	71.0	68.0	71.0	68.0
E26	68.0	65.0	68.0	65.0	68.0	65.0	68.0	65.0	68.0	65.0
E25	65.0	62.0	65.0	62.0	65.0	62.0	65.0	62.0	65.0	62.0
E24	62.0	59.0	62.0	59.0	62.0	59.0	62.0	59.0	62.0	59.0
E23	59.0	56.0	59.0	56.0	59.0	56.0	59.0	56.0	59.0	56.0
E22	56.0	53.0	56.0	53.0	56.0	53.0	56.0	53.0	56.0	53.0
E21	53.0	50.0	53.0	50.0	53.0	50.0	53.0	50.0	53.0	50.0
E20	50.0	47.0	50.0	47.0	50.0	47.0	50.0	47.0	50.0	47.0
E19	47.0	44.0	47.0	44.0	47.0	44.0	47.0	44.0	47.0	44.0
E18	44.0	41.0	44.0	41.0	44.0	41.0	44.0	41.0	44.0	41.0
E17	41.0	38.0	41.0	38.0	41.0	38.0	41.0	38.0	41.0	38.0
E16	38.0	35.0	38.0	35.0	38.0	35.0	38.0	35.0	38.0	35.0
E15	35.0	32.0	35.0	32.0	35.0	32.0	35.0	32.0	35.0	32.0
E14	32.0	29.0	32.0	29.0	32.0	29.0	32.0	29.0	32.0	29.0
E13	29.0	26.0	29.0	26.0	29.0	26.0	29.0	26.0	29.0	26.0
E12	26.0	23.0	26.0	23.0	26.0	23.0	26.0	23.0	26.0	23.0
E11	23.0	20.0	23.0	20.0	23.0	20.0	23.0	20.0	23.0	20.0
E10	20.0	17.0	20.0	17.0	20.0	17.0	20.0	17.0	20.0	17.0
E9	17.0	14.0	17.0	14.0	17.0	14.0	17.0	14.0	17.0	14.0
E8	14.0	11.0	14.0	11.0	14.0	11.0	14.0	11.0	14.0	11.0
E7	11.0	8.0	11.0	8.0	11.0	8.0	11.0	8.0	11.0	8.0
E6	8.0	5.0	8.0	5.0	8.0	5.0	8.0	5.0	8.0	5.0
E5	5.0	2.0	5.0	2.0	5.0	2.0	5.0	2.0	5.0	2.0
E4	2.0	-1.0	2.0	-1.0	2.0	-1.0	2.0	-1.0	2.0	-1.0
E3	-1.0	-4.0	-1.0	-4.0	-1.0	-4.0	-1.0	-4.0	-1.0	-4.0
E2	-4.0	-7.0	-4.0	-7.0	-4.0	-7.0	-4.0	-7.0	-4.0	-7.0
E1	-7.0	-10.0	-7.0	-10.0	-7.0	-10.0	-7.0	-10.0	-7.0	-10.0
E0	-10.0	-13.0	-10.0	-13.0	-10.0	-13.0	-10.0	-13.0	-10.0	-13.0




Periods	Symbol	Hydrogeology	True Resistivities of individual layers, unit: ohm-meters
Quaternary deposits		Aquifer	100 ~ 3000
		Aquitard	20 ~ 100
		Aquiclude	5 ~ 20
Pliocene-tertiary		Aquifuge	0.4 ~ 40
		Manchar formation	
Miocene-tertiary		Aquifuge	7 ~ 20
		Gas formation	(30 ~ 70)

ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF SIND

FEASIBILITY STUDY ON
WATER RESOURCES DEVELOPMENT PROJECT
IN THE MALIR BASIN

JAPAN INTERNATIONAL COOPERATION AGENCY

Fig.6 Hydrogeological Profiles (1/2)



Period	Symbol	Hydrogeology	True Resistivities of Individual layers, salt-ohm-meters
Quaternary deposits		Aquifer	100 - 3000
		Aquiclude	20 - 150
		Aquiclude	5 - 20
Pliocene-Tertiary		Aquifer	0.4 - 40
		Aquifer	1 - 20
Pliocene-Tertiary		Aquifer	(10 - 70)

ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF SIND

FEASIBILITY STUDY ON
WATER RESOURCES DEVELOPMENT PROJECT
IN THE MALIR BASIN

JAPAN INTERNATIONAL COOPERATION AGENCY

Fig.6 Hydrogeological Profiles (2/2)




Fig.7 Groundwater Contour Map in 1977 and 1989

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.8 Density of Production Well

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY









Fig.9 History of Well Construction in the Study Area

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY





Fig.10 Depth of Production Dugwells in Each Decade

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY



1. Natural Condition (1929 - 1988)

2. Natural Condition (1977 - 1988)

Fig.11 Water Balance (Natural Condition)





Fig.12 Relationship Between River Runoff and Recharge to Aquifer

ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF SIND

FEASIBILITY STUDY ON
WATER RESOURCES DEVELOPMENT PROJECT
IN THE MALIR BASIN

JAPAN INTERNATIONAL COOPERATION AGENCY




LEGEND

RIVER POINT NAME	
CA	CATCHMENT AREA (KM ²)
R	AREA RAINFALL (MCM/YR)
Qi	INFLOW (MCM/YR)
qe	CONTROLLED RELEASE FROM DAM (MCM/YR)
qs	SPILLOUT (MCM/YR)
Qr	RUNOFF (MCM/YR)
R	RECHARGE (MCM/YR)


Case-4 Mol Dam : 35 MCM
(1929 - 1988)

Fig.13 Water Balance with Mol Dam
(Case 4 ; 35MCM)

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY



NATURAL RECHARGE VOLUME
(WITHOUT DAM)



ARTIFICIAL RECHARGE VOLUME
(Case 4, Mol: 35.0 MCM)




Fig.14 Masscurves of Natural and Artificial Recharge by Mol Dam (Case 4 ; 35 MCM)

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.15 Artificial Recharge by Dam
(Case 4 ; Mol : 35.0 MCM)

ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF SIND

FEASIBILITY STUDY ON
WATER RESOURCES DEVELOPMENT PROJECT
IN THE MALIR BASIN

JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.16 Calculated Groundwater Table and Movement (without Dam)

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.17 Predicted Groundwater Table and Movement (with Mol Dam ; 35 MCM)

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.18 Present Land Use Map

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.19 Project Boundary and Land Use




Fig.20 Present Cropping Pattern in the Project Area

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.21 Proposed Cropping Pattern (with Project)

ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF SIND
FEASIBILITY STUDY ON
WATER RESOURCES DEVELOPMENT PROJECT
IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.22 Geological Map of Mol Damsite




Fig.23 Geological Section of Mol Dam Axis (Looking Downstream)

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY

Drilling log: HAPDA report(1979)




Fig.24 General Plan of Mol Dam

ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF SIND
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT IN THE MALIR BASIN
JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.25 Standard Section of Mol Dam

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.26 General Layout of Pilot Demonstration Farm

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY





Fig.27 Project Implementation Schedule

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY



Remarks : SE ; Superintending Engineer
 XEN ; Executive Engineer

Fig.28 Organization for Project Implementation

ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SINDH
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY




Fig.29 Organization for Operation and Maintenance of the Project


ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF SIND
 FEASIBILITY STUDY ON
 WATER RESOURCES DEVELOPMENT PROJECT
 IN THE MALIR BASIN
 JAPAN INTERNATIONAL COOPERATION AGENCY

ATTACHMENTS

SCOPE OF WORK
FOR
THE FEASIBILITY STUDY
WATER RESOURCES DEVELOPMENT PROJECT
IN
MALIR BASIN

AGREED UPON BETWEEN
THE GOVERNMENT OF SIND
ISLAMIC REPUBLIC OF PAKISTAN
AND
THE JAPAN INTERNATIONAL COOPERATION AGENCY

Karachi, February 6, 1989



Ghulam Mustafa Abro
Chief Water and Power,
Planning and Development:
Government of Sind



Mr. Norio UCHIYAMA
Leader of the Preliminary
Survey Team
Japan International
Cooperation Agency.



Mr. Akhtar Iqbal
Deputy Secretary,
Economic Affairs Division,
Ministry of Finance & Economics,
The Government of Pakistan,
Islamabad.

I. INTRODUCTION

In response to the request of the Government of the Islamic Republic of Pakistan (hereinafter referred to as "Pakistan"), the Government of Japan decided to conduct the feasibility study on Water Resources Development in Malir Basin (hereinafter referred to as "the Study") in accordance with the relevant laws and regulations in force in Japan.

Accordingly, Japan International Cooperation Agency (hereinafter referred to as "JICA"), the official agency responsible for the implementation of technical cooperation programmes of the Government of Japan, will undertake the Study in close cooperation with the authorities concerned of Pakistan. The present document sets forth the Scope of Work with regard to the Study.

II. OBJECTIVES OF THE STUDY

The objectives of the Study are:

1. to formulate the Agricultural and Water Resources Development project in Malir Basin and verify the feasibility of the project
2. to undertake technology transfer to the counterpart personnel in the course of the study

III. STUDY AREA

The study area is to cover the Malir River Basin, about 30,000ha, including agricultural land, (map attached)

IV. SCOPE OF THE STUDY

The study to be undertaken by the team will be carried out in two phases as follows:

Phase 1

- (1) Collection of data and information and review of the various studies already conducted.

Handwritten signature *M. M.*
Contd..P/2.

-::2::-

- a) Physical conditions
 - Topography
 - Meteorology and hydrology
 - Geology and soil mechanics
 - Ground Water Survey
 - Hydrogeological survey, (electrical resistivity if needed)
 - Vegetation

- b) Socio-economic status
 - Demographic conditions
 - Regional and national economy
 - Rural infrastructure
 - Municipal water demand

- c) Agriculture
 - Agriculture
 - Agro-economy and institutional arrangement.
 - Land use
 - Soil
 - Irrigation and drainage

(2) Home Office Work

analysis of the result of field survey and investigation

Rev. N.M.

Contd..P/3.

-:3:-

Phase 2

- (1) Supplement field survey and investigations
 - Soil land use and land capability
 - Irrigation and drainage survey
 - Agro-economy and institutional arrangement.
 - Regional economy
 - Geological investigation at dam site
 - Construction material and cost
- (2) Establishment of basic concept
 - Outline of agricultural development plan
 - Outline of ground water recharge plan
 - Basic layout of major structures
 - Rough cost estimation
 - Strategy for implementation
- (3) Home Office Work
 - Analysis of the field survey and investigations including the following work items
 - Final delineation of the project area paying particular attention to the results of ground water study
 - Formulation of agriculture development, water resources development and management plan
 - Layout of the project works including preliminary design of major structure
 - Establishment of implementation plan and schedule
 - Benefit and cost estimation
 - Economic evaluation


Contd..P/4.

-:4:-

V. WORKING SCHEDULE

The Study will be executed in accordance with the attached tentative schedule.

VI. RE-PORTS

JICA will prepare and submit the following reports in English to the Government of Pakistan.

(1) Inception Report

Thirty (30) copies at the commencement of the first stage of the work

(2) Progress Report

Thirty (30) copies at the middle of the field work.

(3) Interim Report

Thirty (30) copies at the end of the field work.

(4) Draft Final Report

Thirty (30) copies within one (1) month after the end of the second stage home office work.

The Government of Pakistan will provide its comments on the draft final report within one (1) month after its reception.


(5) Final Report

Fifty (50) copies within two (2) months after the receipt of the comments on the draft final report.

VII. UNDERTAKING OF THE GOVERNMENT OF PAKISTAN

1. To facilitate smooth conduct of the Study, the Government of Pakistan will take necessary measures;

- (1) to secure the safety of the Japanese study team,



Contd..P/5.

-:5:-

- (2) to permit the members of the Japanese study team to enter, leave and sojourn in Pakistan for the duration of their assignment therein, and exempt them from alien registration requirements and cons-ular fees.
 - (3) to exempt the members of the Japanese study team from taxes, duties, fees and other charges on equipment, machinery and other materials brought into Pakistan for the conduct of the study,
 - (4) to exempt the members of the Japanese Study team from income tax and other charges of any kind imposed on or in connection with any emoluments or allowance paid to the members of the Japanese study team for their services in connection with the implementation of the Study,
 - (5) to provide necessary facilities to the Japanese study team for remittances as well as utilization of the funds introduced into Pakistan from Japan in connection with implementation of the Study.
 - (6) to secure permission for entry into private properties or restricted areas for the conduct of the Study,
 - (7) to secure permission for the Japanese team to take all data and documents (including photographs) related to the Study out of Pakistan to Japan by the Japanese study team, and
 - (8) to provide medical services as needed. Its expenses will be chargeable on the members of the Japanese study team.
2. The Government of Pakistan shall bear claims, if any arises, against the members of the Japanese study team resulting from, occurring in the course of, or otherwise connected with the discharge of their duties in the implementation of the Study, except when such claims arise from gross negligence or wilful misconduct on the part of the members of the Japanese study team.

Law. M. M.
Contd..P/6.

-:6:-

3. Irrigation Department, the Government of Sind (hereinafter referred to as "the Department") shall act as a counterpart agency to the Japanese study team and also as a coordinating body to other relevant organizations for the smooth implementation of the Study.
4. The Department shall provide or arrange the Japanese study team with the following, in cooperation with other agencies concerned.
 - (1) Available data and information related to the Study
 - (2) Counterpart personnel
 - (3) Suitable office with necessary equipment and furniture
 - (4) Credentials or ID cards
 - (5) Necessary number of vehicles with drivers

VIII. UNDERTAKING OF JICA

For the implementation of the Study, JICA shall take following measures:

1. To dispatch, at its own expense, the study teams
2. To pursue technology transfer to the Pakistani counterpart personnel in the course of the Study

IX. OTHERS

JICA and the Department shall consult with each other in respect of any matter that arise from or in connection with the Study.

Aw. N.U.


TENTATIVE SCHEDULE

Item Month	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	
WORK IN PAKISTAN	(Phase I)			(Phase II)															
	▬▬▬▬▬			▬▬▬▬▬											▬	○			
WORK IN JAPAN	▭					▬▬▬						▬▬▬▬▬							
REPORTS	△				△		△					△				△			
	Inc. R				P. R. 1		P. R. 2		Int. R			D. F. R.				F. R.			

(Remarks) Inc. R. : Inception Report P. R. : Progress Report
 Int. R. : Interim Report D. F. R. : Draft Final Report
 F. R. : Final Report
 ○ Comments on D. F. R. by Pakistan side


▬▬▬▬▬ : Field Work
 ▬▬▬▬▬ : Home Office Work

LOCATION MAP



LEGEND

- Project Area
- Catchment Area
- Proposed Dam Site
- Metalled Road
- Railway Line
- Rain Gage
- Meteorological Station




MINUTES OF MEETING
FOR
THE FASIBILITY STUDY
WATER RESOURCES DEVELOPMENT PROJECT IN MALIR RIVER BASIN
IN
THE ISLAMAIC REPUBLIC OF PAKISTAN

KARACHI, FEBRUARY 6, 1989



Ghulam Mustafa Abro
Chief Water and Power,
Planning and Development
Government of Sind.



Norio UCHIYAMA
Leader of the Preliminary
Survey Team
Japan International
Cooperation Agency.

The preliminary survey team for the Feasibility Study of Water Resources Development project in Malir Basin sent by JICA had series of discussions on the above mentioned project with the relevant officials of the Government of Sind from 30th January, 1989 to 10th February, 1989. The followings are summarized conclusions of the discussions.

1. The both sides agreed that this project sets the highest priority on irrigation.
2. The team requested to carry out the following items by the time of commencement of the study.

(1) Hydrology

- . to obtain copies of the data observed by the Surface Water and Hydrology Division WAPDA concerning with the Malir River
- . to obtain the basic data from WAPDA in Lahore concerning with the dam, justifying the proposed sediment volume and scale of spillway
- . to observe the front line of the surface water in the Malir River in case of any occurrence of the flood

(2) Ground Water

- . to prepare the geological map, concerning the whole study area about 30,000 ha
- . to obtain detailed map of the solution cavities or solution channels of KHADEJI dam from WAPDA

3. The team suggested as follows :

(1) Hydrology

- . that it would be necessary to repair the automatic rain gauge at the metrological observation station on super highway

(2) Ground Water

- . that the Govt. of Sind, Irrigation Department, would record the long term fluctuation of ground water level and quality
- . that the Govt of Sind would make contour map of ground water surface in rainy and dry season respectively.

(3) Agriculture

- . that the Govt. of Sind would study the possibility of expanding the planted area

J. N. U.


4. The team recommended that the Govt. of Sind carry out the pumping tests.
5. Pakistan side requested that the study would include the application of new irrigation method in relation to the scope of work IV. phase 2. (3).
6. Pakistan side requested that the Govt. of Japan would provide the necessary vehicles and measuring equipment for the study.

Jaw. M.U.


Minutes of Meeting
on
Draft Final Report
of
Feasibility Study
on
Water Resources Development Project
in
Malir Basin


Agreed upon Between
The Government of Sindh
Islamic Republic of Pakistan
and
Japan International Cooperation Agency

Karachi, Dated 25th August, 1990


25.8.90

MOHAMMED IDRESS RAJPUT
Additional Secretary,
Irrigation and Power Dept.
The Government of Sindh


KUNIO IRIE
Team Leader
JICA Study Team



Witness
DR. MASAYUKI WADA
Chairman of JICA
Advisory Committee

PRESENTATION OF THE DRAFT FINAL REPORT OF
FEASIBILITY STUDY ON WATER RESOURCES DEVELOPMENT PROJECT
IN MALIR BASIN


Date : August 23, 1990

Place : 9:00 - The Conference Room of Planning and Development Dept.
12:00 - The Office of Secretary of Agriculture and Livestock Dept.
14:30 - The Office of Additional Secretary of Irrigation and Power Dept.

Attendants : As per annexure

In accordance with the Scope of Works for Feasibility Study on Water Resources Development Project in Malir Basin signed on February 6, 1989 between the Japan International Cooperation Agency (JICA) and the Government of Sindh (GOS), Islamic Republic of Pakistan, the JICA Study Team (the Team) carried out the Study. As a result of the Study, the Team prepared and submitted the Draft Final Report on August 22nd and meeting was held for the discussion on the Draft Final Report presenting the results of the Study. Both parties have mutually confirmed the following:

1. The JICA Study Team briefly explained the results of the Study, and the Draft Final Report describing results of the Study was accepted by GOS.
2. GOS requested to describe the staffing and O & M costs of the proposed Pilot Demonstration Farm. The Team agreed to do it in the Final Report.
3. GOS requested to submit eighty (80) copies of the Final Report, instead of 50 copies stipulated in the Scope of Work. The Team agreed to transfer the GOS's request to JICA.
4. GOS is keen to implement the project as early as possible, in due consideration of the socio-economic conditions in the project area.
5. GOS will send comments if any before September 21st, 1990 in accordance with the Scope of Work agreed upon between JICA and GOS on February 06, 1989. The Team expressed to receive comments if any as early as possible, and prepare the Final Report in due consideration of comments if necessary within two (2) months after receiving comments.
6. GOS expressed thanks to the Team for their dedicated works on this project, and is pleased to receive the Final Report for early implementation.



LIST OF ATTENDANTS

A. The Government of Sindh

A.1 9:00 -

- | | |
|--------------------------|---|
| 1. Mr. Fazlullah Qureshi | Additional Chief Secretary (Dev),
P & D Dept. |
| 2. Mr. Munmir A. Qazi | Chief (Agriculture),
P & D Dept. |
| 3. Mr. Ghulam M. Abro | Chief (Water & Power),
P & D Dept. |
| 4. Mr. Khair M. Soomro | Deputy Secretary (Technical)
Agriculture & Livestock Dept. |
| 5. Mr. G. Sarwar Khero | Chief (Foreign Aid)
P & D Dept. |
| 6. Mr. Allah B. Kalhoro | Assistant Chief (Foreign Aid)
P & D Dept. |
| 7. Mr. M. Iqbal Shaikh | Executive Engineer
Irrigation & Power Dept. |

A-2 12:00 -

- | | |
|----------------------------|---|
| 1. Mr. Kamaluddin Qureshi | Secretary,
Agriculture & Livestock Dept. |
| 2. Mr. Shaukat Rahmo | Deputy Secretary (Technical)
Agriculture & Livestock Dept. |
| 3. Mr. Khair M. Soomro | Deputy Secretary (Technical)
Agriculture & Livestock Dept. |
| 4. Mr. Masood Ahmed Bhutto | Director, Agricultural
Engineering, Sindh, Hyderabad. |
| 5. Mr. M. Arif Ali | Section Officer,
Agriculture & Livestock Dept. |
| 6. Mr. M. Arif Khairi | Section Officer,
Agriculture & Livestock Dept. |

A-3 14:30-


- | | |
|---------------------------|--|
| 1. Mr. Mohammed I. Rajput | Additional Secretary,
Irrigation and Power Dept. |
| 2. Mr. Iqbal Shaikh | Executive Engineer
Irrigation & Power Dept. |
| 3. Mr. Noor Ahmed Memon | Assistant Ex. Engineer
Irrigation and Power Dept. |

B. JICA Advisory Committee

- | | |
|---------------------|---|
| 1. Dr Masayuki Wada | Chairman of Advisory Committee,
MAFF |
|---------------------|---|

C. JICA Study Team

- | | |
|--------------------------|--------------------|
| 1. Mr. Kunio Irie | Team Leader |
| 2. Mr. Shunichi Muramoto | Deputy Team Leader |
| 3. Mr. Motoo Taki | Dam Engineer |



JICA