THE PEOPLE'S REPUBLIC OF BANGLADESH.

BANGLADESH WATER DEVELOPMENT BOARD

ON

THE KURIGRAM

IRRIGATION AND FLOOD CONTROL PROJECT

- NORTH UNIT --

VOLUME 1
MAIN REPORT

OCTOBER 1990

JAPAN INTERNATIONAL COOPERATION AGENCY

THE PEOPLE'S REPUBLIC OF BANGLADESH BANGLADESH WATER DEVELOPMENT BOARD

FEASIBILITY STUDY ON THE KURIGRAM IRRIGATION AND FLOOD CONTROL PROJECT — NORTH UNIT —



VOLUME 1

MAIN REPORT

OCTOBER 1990

JAPAN INTERNATIONAL COOPERATION AGENCY



PREFACE

In response to a request from the Government of the People's Republic of Bangladesh, the Japanese Government decided to conduct a Feasibility Study on the Kurigram Irrigation and Flood Control Project (North Unit) and entrusted the Study to the Japan International Cooperation Agency (JICA).

JICA sent to Bangladesh a study team headed by Mr. Toshihisa MURATA, Taiyo Consultants Co., Ltd., from August, 1989 to March, 1990.

The team held discussions with the officials concerned of the Government of Bangladesh and conducted field surveys. After the team returned to Japan, further studies were made and the present report was prepared.

I hope that this report will contribute to the development of the project and to the promotion of friendly relations between our two countries.

I wish to express my sincere appreciation to the officials concerned of the Government of Bangladesh for their close cooperation extended to the team.


October, 1990

Kensuka Va

Kensuke YANAGIYA

President

Japan International Cooperation Agency





SUMMARY

INTRODUCTION

- 1. In response to the request made by the Government of Bangladesh, the Japan International Cooperation Agency ("JICA") concluded the Scope of Work ("S/W") with the Bangladesh Water Development Board ("BWDB") for the implementation of a Feasibility Study on the Kurigram Irrigation and Flood Control Project-North Unit ("the Study") in February, 1989. Based on the S/W, a Feasibility Study Team ("the Team") conducted the field works in Bangladesh from August through October in 1989 and from January through March in 1990. The Team studied in Japan to formulate a development plan based on all the results which had been collected and analyzed through the field works. A draft final report was prepared to present these study results and a meeting was held between the BWDB and the Team for explanation and discussion on the draft final report in August, 1990. Taking into consideration the discussion results and the comments from the BWDB, this final report was completed.
- 2. In 1969, a feasibility study was conducted for an irrigation, drainage and flood control project for the Kurigram Area including the Study area as its part. The project was started in 1973 and some works including a part of embankment and drainage regulators have been constructed up to now. However, the progress is at a very slow pace mainly due to financial constraint.

On the Third National Five-Year Development Plan, the Government of Bangladesh has put emphasis on accomplishment of food self-sufficiency and improvement of productive employment. Following this policy, the Government decided to accelerate the Kurigram Irrigation and Flood Control Project. The Project area was divided into two units, of which the North Unit was proposed for first implementation of a feasibility study based on updated natural, social and technical aspects.

THE PROJECT AREA

3. From administrative point of view, the Study area is located in four upazilas; namely Kurigram, Bhurangamari, Fulbari and Nageswari which are included in the Kurigram District, adjoining the West Bengal of India. The gross extent

of the Study area is approximately 42,800 hectares. The land of the study area displays a typical type of alluvial plain in the Teesta delta, bordered by the Dudhkumar, Brahmaputra and Dharla rivers, and is about between 65-128 ft (EL.20-39 m) above the sea level. The land is flat and has inundation problem. The soil varies from loam to clay and has low to moderate fertility.

4. The average annual rainfall in the Study area falls between 2,300 and 3,200 mm. This amount is generally supposed to be no less than sufficient for cultivation. However, the precipitation is not distributed enough for crop cultivation during the dry period from

December to May, while 80% of that is concentrated in the monsoon period from June to October.

- 5. The population of the Study area is approximately 350 thousands and the estimated annual population growth rate is about 2.5%. 90% of the population lives on agriculture. 52% of the total farmers are independent farmers, 48% landless farmers. Most farmers are of small scale. The average farm size is approximately 0.9 hectares.
- 6. Of 42,800 hectares of the Study area, the net cultivated area is about 35,100 hectares. Most of the available land, or 82 % of the total area, has been exploited for cultivation.

As for cropping in the study area, paddy production is dominant. Other than paddy, jute, wheat and minor crops such as small grains (kaun, cheena, etc.), pulses, vegetables, potato, mustard and other crops are grown.

The present cropping intensity of the study area is about 177 %, which is relatively high as compared with the national average rate of 154 %. This high rate is mainly attributed to double cropping, owing to rain-fed cultivation in the pre-monsoon and to irrigated cultivation by small scale shemes in a part of the area in the dry period in addition to cultivation in the monsoon period.

DEVELOPMENT STRATEGY

7. Under the above-mentioned natural and social conditions, the agriculture in the Study area has stagnated at a relatively low productivity level, lagging

Wheat HYV DEC. Pulses Wheat NOV. Winter Vegetables T - Aman Pajam OCT. Potato Mustard T - Aman HYV T - Aman L SEP. Summer Vegetables AUG. Mixed JUL. Aman Aus -J S.S. B - Aman MAY T - Aus L Jute HYV B-Aus L Fig. S-1 Present Cropping Patterns Jute L Wheat APR. Boro Boro HYV MAR. FEB. > H X winter Veg. -Potato Wheat Nustard Pulses JAN Area 8 % 80 8 Percentage Cropped ĵ0

Table S-1 Estimated Crop Production in the Project Area (Major Crops Only)

unit: ton, ha.

Crops	Planted Area	Average Production	Total Yield
B-Aus L	14,239	0.79	11,361
T-Aus L	391	2.12	830
T-Aus HYV	2,115	1.68	3,561
B-Aman L	477	1.15	550
T-Aman L	17,930	1.44	25,898
T-Aman P	2,787	2.12	5,886
T-Aman HYV	5,814	2.41	14,037
Boro HYV	5,871	2.81	16,525
Aus Aman Mx	1,364	1.69	2,310
Paddy	50,988	1.59	80,958
Jute L	2,802	1.38	3,869
Jute HYV	2,052	1.50	3,083
Mustard	620	0.84	521
Kaun	1,237	0.63	786
Wheat L	1,082	1.33	1,444
Wheat HYV	2,281	1.78	4,058
Sw. potato	211	7.75	1,636
Potato	600	8.89	5,338
Vegetable	349		4,339

Source: estimated from the data by BBS Rangpur Office (five year 1984 - 1989)

behind on the introduction of improved cultivation technologies such as high yielding rice varieties and fertilizer applications.

The most significant and fundamental factor which restricts the development of agriculture in the Study area seems to be its unfavorable water conditions. Flood water levels in the three outer rivers along the Study area are so high above the lands in the lower reaches of the Study area as to cause annual inland flooding. This not only brings about damages to crop production but also hinders the practice of improved technologies, which includes new varieties and fertilizer applications, requiring stable water conditions.

In the rainy season, crops are grown in principle by rain-fed water, while, in the dry season, the cropping area is limited to only about 28 % of the total cultivable land, which is equipped with small scale irrigation pumps. In this situation, the basic way to develop agriculture seems to be to increase productivity in the rainy season and/or to expand the cropping area in the dry season. And, the most fundamental measure to be taken for that purpose is considered to be irrigation.

Among the other restricting factors are the lack of technical know-how and resources of farmers as well as insufficient infrastructures for transportation and marketing. The countermeasures would be strengthening the extension activities for improved technologies, promoting cooperative activities, improving and constructing roads and warehouses, etc..

- 8. The objectives of the proposed development plan are to increase agricultural production and to raise farmers' incomes and thus to contribute to increase of employment opportunities, regional economical development and improvement of people's living standards, through comprehensive implementation of countermeasures to sweepingly eliminate the above-mentioned constraints on agricultural development. For these objectives, the proposed development plan contains construction of irrigation and drainage systems and flood protecting embankment together with related measures including road network improvement and agricultural supporting services strengthening.
- 9. At present, a large number of depressions and meandering channels existing in the Study area function as natural flood control reservoirs. Therefore, in principle, the current natural drainage system from farm to main channel level is to be left as it is. Approximately 80 % of the embankment for the

Study area has been already constructed. The unfinished sections of the embankment are to be built and the existing sections to be rehabilitated.

- 10. Irrigation water is planned to be taken in mainly by pumping up from the Duhdkumar river. Supplementary water intake by installing a reversible pump station for the southern part of the Study area is to be studied for an efficient drainage plan. The irrigation system is to be studied taking into consideration minimizing banking hight, crossing points with settlements and drainage channels and the total pumping energy cost.
- 11. The proposed development plan aims at making it possible to significantly expand cropping area in the dry period and to raise productivity in the monsoon period. Introduction of high yield varieties and profitable crops as well as application of improved technologies are to be studied so that they will be of optimum level for farmers in the Study area.
- 12. It is important for successful and effective implementation of irrigation and drainage development to be incorporated with indispensable measures for supporting farmers' cultivation. In this respect, the construction of roads and warehouses for input supply and marketing as well as strengthening extension services are to be studied comprehensively.
- 13. In the planning, emphasis is to be placed on lowering the construction cost as well as the future operation and maintenance cost by employing appropriate technology.

The implementation schedule is to be discussed as to asure the development investments to bear fruit as soon as possible. Considering this aspect, a step-by-step development method will be studied.

AGRICULTURAL PRODUCTION PLAN

14. The proposed land use for every category is shown in Table S-2, in which the land category distribution is to be in principle as it is at present. Based on the studies on the available river discharge and layout of the irrigation system, it is proposed that the present cultivated land area will be irrigated in the "with project" except for the area used for the planned canal sites.

Table S-2 Proposed Land Use for different categories

Land Use	Area (ha)	(%)
Gross area	42,800	100
Settlements	5,290	12.3
Grass land	350	0.8
Char land	120	0.3
Water bodies	1,940	4.6
Proposed canals	2,300	5.4
Cultivated land	32,800	76.6

15. Taking into consideration mainly staple food self sufficiency in the Kurigram district including the Study area, crop diversification under the rather unfavorable marketing condition of this area and crop suitability to land and climatical conditions, a limited number of crops were selected for the proposed cropping patterns. They are staple food crops i.e. paddy and wheat which are suitable crops for irrigation, jute to maintain present share, oil crops, pulses and other comparatively storable vegetables and potatoes. High yield varieties of these crops should be adopted as far as possible to elevate yield levels, for they are the only input responsive ones. Under the proposed cropping patterns, high yielding paddy again inevitably play a major role in so far as it is the most suitable and safest crop assuming that the flood submersion condition will to some extent remain even with the flood control measures by the project.

16. The proposed cropping patterns were figured out as shown in Fig. S-2, considering the following points:

- To be optimum for different land drainage conditions improved by the project.
- To increase crop production mainly by means of crop intensification during the dry peiod and the replacement of local varieties with high yield varieties.
- Economized use of the limited available water.
- To preserve soil fertility.

Through the implementation of the proposed cropping patterns, the cropping development shown in Table S-3 and the crop production shown in Table S-4 will be expected.

DEC. Wheat Potato Mustard Late T-Aman HYV NOV. Summer Vegetables-OCT. - Aman Local Fodder Maize Mung bean T - Aman HYV Summer Fallow SEP. AUG. JUL. JUN. T - Aus HYV Local MAY Green Manure Jute HYV B-Aus APR. Boro HYV MAR. Khesari Bean FEB. Wheat HYV Vinter Veqetables Mustard Percent oge Percent oge Mustard JAN. рэ1A 8 % Cropped % 8 80% <u>Jo</u> 9

Fig. S-2 Proposed Cropping Patterns

unit: ha. %

	Current La	and Use	nd Use Without-Project With-Project				
Season/Crop	Area	%*	Area	%*	Area	%*	
Kharif							
Total Crops	49,971	142	48,123	137	43,050	131	
Food-grains	45,117	128	43,166	123	32,775	100	
Cash Crops	4,854	14	4,957	14	8,750	27	
Other Crops	0	0	0	0	1,525	4	
Rabi						•	
Total Crops	12,251	35	14,099	40	37,050	113	
Food-Grains**	10,471	30	12,088	34	27,750	85	
Cash Crops	1,569	4	1,561	4	9,300	28	
Other Crops	211	1	1,450	2	0	0	
Crop Coverage		177		177		244	
Share of Kharif***	•	80		77		54	
Share of Rabi***		20		23	:	46	

Note: * percentages to the cropping land area (without $P=35100\,$ ha. with-P $=32800\,ha$).

^{**} including pulses

^{***} percentage to the total annual crop coverage excluding G.M.

Table S-4 Planned Crop Production (With Project) unit: ha. ton/ha. ton

	Area under Yield Production Difference (with-P-v			without-P)		
Crops	Crop(ha.)	(ton/ha.)	(ton)	Area(ha.)		Production ton)
B-Aus Local	3,075	2.0	6,150	-10,167	+1.17	- 4,840
T-Aus HYV	12,450	3.0	37,350	+ 9,694	+0.87	+31,480
T-Aman HYV	10,475	4.0	41,900	- 470	+1.25	+12,629
T-Aman Local	1,975	2.8	5,530	-12,499	+1.23	-17,194
Late T-Aman H	4,800	3.0	14,400	+4,800	+0.52	+14,400
Boro HYV	7,100	4.5	31,950	+ 1,355	+1.41	+14 198
Other Paddy	-	-	-	- 3,621	-	-5 313
Paddy	39,875	3.4	137,280	-11,358	+1.6	+45,360
Wheat HYV	7,875	3.5	27,562	+4,579*	+1.25	+20,841
Jute HYV	7,875	2.3	18,112	+ 3,118*	+0.61	+10,743
Potato HYV	1,425	20.0	28,500	+ 765	+9.78	+21,755
Mustard HYV	7,650	1.3	9,945	+ 7,049*	+0.44	+ 9,428
Khesari(Pulses)	7,100	1.0	7,100	+ 6,850	+0.10	+ 6,875
Mungbean	5,675	0.9	5,107	+ 5,675		+ 5,675
S.Vegetables	875	25.0	21,875	+ 675	+15.00	+19,875
W.Vegetbls	225	40.0	9,000	- 75	+25.00	+ 3,600
Fodder Crop	1,525	90.0	137,250	+ 1,525	-	+ 137,250
Kaun	-		·	- 1,175	-	- 928
Sweet Potato	-	-	-	- 200		1,550
		.' .			· ·	<u> </u>
The second second						*
Cropped T.	80,100	-	-	+17,878	-	-
Dhoincha	1,975	30.0	59,250	•	-	

IRRIGATION PLAN

- 17. Criteria for irrigation water requirements are as follows:
 - Consumptive use; calculation based on the modified Penman's method.
 - Irrigation lossese;
 The coveyance efficiency for canals 0.85,
 The field efficiency for upland crops 0.70,
 The field efficiency for paddy 0.85, besides, the percolation rate of 6 mm/day is added.
 - Puddling watwer for paddy; 150 mm depth of water is supplied during 30 days.
 - Effective rainfall; 80% of daily rainfall depth exceeding 5mm is effective. Only in the case of paddy, 80 mm per day exceeding the water requirements can be stored.

Based on the above criteria, the proposed cropping patterns and the planned land use, diversion water requirements were obtained. The maximum diversion water requirements for the proposed two intakes for 10 years from 1979 to 1988 are given as shown in Table S-5.

For irrigation canals, the design unit water requirements are given bellow.

Canals	Unit design water requirements
Main canals	1.453 l/s/ha
Secondary canals	1.453 l/s/ha

- 18. The existing small scale irrigation facilities might be kept to supplement the planned irrigation system which is to utilize the nearby river water. However, it is proposed that the irrigation system fully depend on surface water from rivers based on the following points:
 - The wster diversification from the Dudhkumar and Brahmaputra rivers is available to cover the whole cultivated area.

- It will be efficient from investment cost, operation and maintenance viewpoints that the planned irrigation system covers the whole project area incorporating the existing irrigated area by small scale pumps. It is also advantageous for better specifying and administration of beneficiaries.
- 19. Among available three rivers around the project area, the Dharla river is supposed to be reserved for irrigation for Kuriguram South Unit area in accordance to the the BWDB's basic development strategy for the whole Kurigram area. Following this strategy, the proposed irrigation system is to mainly take water from the Dudhkumar river.

To take irrigation water from the Dudhkumar River, a main pump station is planned for installation at Pateswari, on the downstream side of the abolished railway bridge. The proposed site is considered to be the most suitable situation, since it commands the most upstream and highest position to the irrigated area as well as it faces the relatively stable river bank.

The justifiability for installing a reversible pump station for the dual usage of drainage and supplementary irrigation for the southern part of the project area was studied from the following viewpoints:

- To reduce the total cost of irrigation and drainage pumps.
- To decrease the intake water from the Dudhkumar river which has a limited available discharge in the drought period, by taking a part of the total required water from the Brahmaputra river.

As a result, a reversible pump station which commands 3,350 ha for irrigation is proposed for installation at the Tangonmari regulator. Basic design features for the two pump stations are given in Table S-5.

Table S-5 Irrigation Facilities

(a) Pumping Stations

en bringsbeg fellerbobbe

Items	Pateswati Pump Station	Tangonmari Pump Station
1) Design Discharge	42,78 m ³ /sec	4.87 m ³ /s
2) Pump Type	Vertical Mixed Flow Pump	-do-
3) Pump Bore	ø 2,200 mm	ø 900 mm
4) Pump Numbers	4 Nos	3 Nos
5) Pump Capacity	$10.70 \mathrm{m}^3$ / sec / unit	$1.63\mathrm{m}^3\mathrm{/}\mathrm{s}$
6) Pump Head	8.6 m	8.0 m
7) Moter Pawer	1,220 kw/unit	200 kw/unit
8) Total Moter Power	4,880 kw	600 kw

(b) Canals

Canals	T. Length(km) D	ischarge(m³/s)	Slope	Type
1) Main Canals	47.4	42.8~4.5	1/12,000 ~1/5,000	Unlined
2) Secondary Canals	156.3	4.4~0.5	1/7,000 ~1/3,000	-do-
3) Tertiary Canals	354.0	0.4~0.1	1/1,000~	-do-

(c) Major Appurtenant Structures

Structures	Number
1) Diversion Structure	215 nos.
2) Escape	39 nos.
3) Syphon	3 nos.
4) Aqueduct	26 nos.
5) Drainage Culvert	244 nos.
6) Road Cross Structures	721 nos.

20. The layout of the irrigation canal routes was studied so as to minimize banking height and to avoide crossings with settlements, rivers and roads as far as possible.

Further studies for water conveyance systems were done based on results of the route survey, while focusing on the stability of earth structures as well as on the minimization of construction costs and land acquisition. As for the western part of the study area, whose altitude is relatively high, alternative plans to supply water from the Pateswari intake were discussed to lower canal banking and to decrease the total pumping energy cost for the whole system. Consequently, an optimum plan of water conveyance system was worked out.

DRAINAGE AND FLOOD CONTROL PLAN

21. Criteria for drainage planning are as follows:

- Design rainfall for inland runoff; 5-year return period, 5-day consecutive rainfall.
- Allowable submergence for crops; over 0.30 m standing water over the datum field level for no more than 5 days.
- Beneficial area by flood protection and drainage improvement; submerge area, except depressions and river courses, caused by a one-in-5-year flood in the outer rivers in the present conditions with embankment gaps and therefore receive less submergence by some improvement measures.
- 22. A mathematical simulation model, in which inland runoff was calculated with the "Integrated Unit-hydrograph Method", has been employed for drainage analysis. The results from the various alternative studies have finally been compiled into Table S-6, in which the case for protection of 80 % of beneficial area is proposed as a economically acceptable plan.

Table S-6 Results from Drainage Analysis

(Regulators and Pumps needed for Drainage Improvement)

Protected Area	over 80% of area		over 90% of area	
Allowable Submerge Criteria	< 5-day	< 3-day	< 5-day	< 3-day
No. of vents of regulator	89	90	89	89
Total pumping capacity (cms)	10	18	28	37
No. of pumping plant	2	3	3	3

- 23. Some basic policies for plan formulation has to be established in order to meet technical, social, economic and local requirements as follows:
 - The existing drainage systems including natural depressions and meandering channels will be left as they are at present. This is because the improvement of drainage channel networks would bring about worse drainage in the lower reaches of the project area.
 - Drainage by pumping is the most costly measures that a pumping plant of 5 m³/sec for both irrigation and drainage, which can be much advantageous in cost allocation, is proposed to be installed in the Tangonmari-Old Girai Block. Another pump station of 5 m³/sec will be constructed in the South Tail Block.

24. Criteria for Planning of Embankment are as follows:

Rivers	Design water level	Freeboard
Dharla River	of one-in-50-year flood	1.20 m
Dudhkumar River	of one-in-50-year flood	$1.20\mathrm{m}$
Brahmaputra River	of one-in-100-year flood	1.50 m

(N.B. For the Dharla and Dudhkumar, 0.30 m freeboard for future rise of river bed is included)

25. As of date 61.9 km out of 84 km of the planned embankment has been built. The completion of the unfinished embankment of 22.1 km length is accordingly the first priority.

The embankment shall be planned to be durable against ordinary intensive rainfall, wind, water table, traffic etc.. The embankment may be located 300 - 500 m apart from river water ridges to escape flood flow so as to avoid expensive long river bed and slope protection works.

Neccessary reconstruction and repairs for the completed embankment will be implemented.

MARKETING AND AGRICULTURAL SUPPORTING SERVICES

26. When farming aiming at high harvesting of crops according to the proposed cropping patterns and farming criteria under irrigation is realized, a lot of fertilizers, pesticides and improved crop seeds will be needed. In order to respond to these increasing demands smoothly, it is necessary to strengthen the distribution system for crop production materials. For this purpose, it is considered to be most appropriate to expand the organization of UCCA/KSS/BSS/MBSS system in the project area under the full cooperation of the BRDB and to encourage immediate participation of those cooperatives in both the wholesale and retail sectors. Moreover, as a part of the UCCAs' economic activities, the stationing of proper godowns and primary distribution centers with proper storage capacities should be promoted. At the same time, it is necessary to improve transportation and communication facilities.

27. As long as the Government's policy for its foodgrain procurement remains unchanged, the considerable portion of the increased paddy production brought about by the project implementation is expected to be marketed in the open market. Besides, as a result of expanded irrigation, the production of cash crops such as vegetables is also expected to increase and to be marketed in the open market. In order to meet this situation, it is necessary to set up or improve marketing facilities for farmers, including rice and wheat mills with large capacities which can deal with increased products, godowns which can keep increased products in high quality, transporting means such as boats, trucks etc., and marketing information networks.

It is necessary that the UCCA/KSS/BSS/MBSS systemswill be organized for small scale farmers, who have been left unfavorable for marketing, to obtain stronger stance for profitable marketing.

At the same time, it is necessary to provide or to improve the social infrastructure including the municipally-run markets in urban areas, the road network and the transportation facilities for crossing the Dharla River. A construction plan of roads is to be proposed on the basis of studies focusing on the usage for operation of the irrigation and dranage systems as well as considering the usage for the agricultural material supply and marketing.

28. In order to achieve agricultural target production after the implementation of the project, it is important to formulate the adaptable irrigated cultivation methods of paddy and upland crops based on accumulated research results and to transfer them to farmers in the project area. For this purpose, it is proposed to establish a model farm situated at a representative point in the project area as follows:

- Land area: 7ha (leased land system)
- Farm: divided into 3(three) blocks (irrigated);
 - 1) First block (2ha) --- for experiments.
 - 2) Second block (3ha) --- for demonstration.
 - 3) Third block (1ha) for training of farmers.
- Buildings; an office (including experimentation room, working room and training room) and a warehouse.

Organization	Number of staff
1) Chief (an agronomist)	1
2) Subject matter specialist	2
(plant protection, water managen	nent)
3) Extension overseer	1
(additional of training officer)	
4) Assistant	2
5) Junior	2
6) Farm labourers	20-22

29. In order to practice satisfactory extension service activities responding to the expansion of the cropped area, the diversification of crops and the introduction of improved irrigated farming techniques after the implementation of the project, it is evident that staff and equipment for extension services will have to be strengthened from their present status. It is proposed to train and newly assign the personnel concerned, and to provide equipmentand facilities including vehicles.

THE PROJECT COST

- 30. The project cost is estimated under the following conditions.
 - The project cost is estimated on the basis of the market price as of March, 1990.
 - Civil works are to be done on the local contract basis, mechanical and electrical works in the pumping stations are on the foreign contract basis.
 - The unit prices of materials, labours and civil works are mainly based on "Schedule of Rates for Project-IV, BWDB, Rangpur (Oct. 1989)".
 - Data on taxes and inland transportation charges on the imported materials and equipment are quoted from "Customs and Sales Tax, 1989, Ministry of Finance" and "Schedule of Rates for Transportation, 1989-90, Ministry of Food".
 - The price of the land acquisition is based on the actual rates in the works of BWDB, Kurigram 1988 to 1989.
 - The physical contingency is set at 10 % to the construction and associated costs.
 - The price escalation rate is predicted at 10 % for local portion and 7.0 % for foreign portion considering the recent tendency.
 - The exchange rate between Bangladesh Taka and US dollar is adopted at US\$1.00 = Taka 33.0.
- 31. The summary of the project cost is shown in Table S-7.
- 32. The summary of the annual operation and maintenance cost is shown in Table S-8.

PROJECT IMPLEMENTATION SCHEDULE

33. The project implementation schedule is proposed as shown in Fig. S-3.

Table S-7 Summary of Project Cost

(Unit; \times 1,000 Tk) L/C F/C Tax Item Total 1. Construction cost a. Pump stations 241,176 685,026 260,830 1,187,032 146,559 b. Irrigation canals 146,559 c. Irrigation facilities 190,890 74,673 265,563 d. Flood embankments 51,100 51,100 24,449 62,199 e. Drainage regulators 37,750 f. Roads 8,078 8,078 g. On-farm facilities 105,287 14,169 119,456 h. Transmission and 4,805 17,530 7,997 30,332 telephone lines Sub-total 785,645 815,847 268,827 1,870,319 2. Associated cost 3,201 57,258 27,519 87,978 a. Construction machines 6,605 b. Agricultural extension 12,765 1,865 21,235 facilities c. Land acquisition 146,674 146,674 199,207 235,815 d. Consulting service 36,608 e. Project administration 87,986 11,552 1,630 101,168 Sub-total 592,870 287,234 274,622 31,014 299,841 Total(1+2)1,072,879 1,090,469 2,463,189 3. Physical contingency 78,884 87,311 29,635 195,830 4. Price escalation 602,198 354,844 194,703 52,651 Grand total 1,506,607 1,372,483 382,127 3,261,217

Table S-8 Summary of Annual Operation and Maintenance Cost

(Unit; × 1,000 Tk)

Description	Pateswari Pump Station Area	Tangonmari &Begomganj Pump Station Area	Total
1. Pump stations		en de la companya de La companya de la co	Section (1997)
a. Mechanical	8,144	3,320	11,464
b. Electricity	42,041	6,867	48,908
c. Civil work	120	240	360
d. Dredging	252	362	614
Sub-total	<u>50,557</u>	10,789	61,346
2. Irrigation and			
drainage facilities			en e
a. Canals	4,300	385	4,685
b. On-farm	2,654	294	2,948
c. Hydraulic structures	1,392	132	1,524
d. Embankment	1,260	141	1,401
e. Regulators	72	30	102
Sub-total	9,678	982	10,660
3. Miscellaneous	<u>3,011</u>	<u>588</u>	<u>3,599</u>
4. Administration	<u>4,584</u>		4,584
Total	67,830	12,359	80,189

Fig. S-3 Project Implementation Schedule

		Ħ	
	Year	Ħ	
	7th. Year		
		H	
٠.	ı.		
<	n. Year	Ħ	
	6th.	I	
٠.		Ш	
٠.	Year	Ħ	
	5th.	н	
		Ħ	
). 1:1		
	ı. Year	п	
	4th.	}1	
		Ш	
	Year	П	
	3rd.	herel	
	÷	Ħ	
	<u>.</u>		
	ıd. Year	П	
	2nd	ъ	
	-	Ħ	
	Year	п	
	lst.	٠	
		L	
	ar.		g ties ties ea ities ion sion
	Year		gn anai acili acili acili Exten Bxten Stat Exten
	: /	/, -	Detailed Design Tendering Loan Procedure Construction Land Acquisition Land Acquisition Bquipment Procuring Main Pump Area (1) Pump Station (2) Irrigation Canai (3) Irrigation Racilities (4) Road (5) On-Farm (6) Transmission Line (7) Irrigation Canai (8) Irrigation Canai (9) Irrigation Canai (1) Pump Station (2) Irrigation Facilities (4) Road (5) On-Farm (6) Transmission Line (7) Load Embankment (8) Irrigation Facilities (9) Transmission Line (1) Transmission Line (2) On-Farm (3) Irrigation Station (4) Road (5) On-Farm (6) Transmission Line (7) Agaicultural Extension Tender Mandange Pump Station Tender Mandange Ten
		Ю	Detailed Desi Tendering Loan Procedur Construction Land Acquisil Bequipment Pro Main Pump Artion (1) Pump Station (2) Irrigation (3) Irrigation (4) Road (5) On-Farm (6) Transmission (7) Irungation (8) Irrigation (9) Irrigation (1) Pump Station (1) Pump Station (2) Irrigation (3) Irrigation (4) Road (5) On-Farm (6) Transmission (7) Road (7) Lond Embank (7) Drainage Regi Drainage Pump (8) Agricultural (9) Agricultural (1) Agricultural (1) Agricultural (2) Consulting S
		ltems	I. Detailed Design II. Coan Procedure IV. Construction I. Land Acquisition I. Land Acquisition I. Equipment Procuring II. Main Pump Area II. Pump Station II. Pump Station II. Irrigation Facilities II. Trigation Facilities II. Pump Station III. Pump Station
	/		< 8 d 6 5 5 6 5 6 5 6 6 6 6 6 6 6 6 6 6 6 6

PROJECT JUSTIFICATION

34. The evaluation of this project is proposed to be conducted as per a widely accepted cost-benefit analysis based on market prices for financial analysis and on economic prices for economic analysis.

Prerequisites for cost estimation are in principle the same as those mentioned regarding the project cost in the section 30 except for the economic prices for economic analysis.

The economic prices are given as border prices for traded commodities. The conversion factor of 0.82 is used to obtain economic prices for non-traded commodities. The opportunity costs of unskilled labor are supposed to be 75 % of market wages. Economic costs exclude transfer items such as taxes, financial interest, water charges, subsidies, imputed capital costs and land acquisition expenses.

35. For both financial and economic bases, the investment costs, the annual operation/recurring expenditures and the benefits were calculated. The distribution of annual investment and that of net benefits were supposed based on the project implementation schedule.

On the basis of the above-mentioned conditions, the following indicaters were finally obtained.

Indicaters	Financial	Economic
Net present value (NPV) Mil.Taka (15 % discount rate)	△ 659.8	456.5
Benefit-cost ratio (BCR)		
(10 % discount rate)	0.953	1.785
(15 % discount rate)	0.685	1.286
Internal rate of return (IRR) %	9.6	19.7

△ ;minus

36. Among various socio-economical secondary and intangible benefits which are expected from the project implementation, the most important is the increase of employment opportunities shown below.

Labor requirement (thousand man-days)
 for the project implementation (for 7 years); 7,403
 for the operation and maintenance; annually 330

for crop cultivation; annual increase

RECOMMENDATION

37. On the basis of the results from the Study for the Kurigaram Irrigation and Flood Control Project - North Unit, its economic feasibility and technical soundness was ascertained in this report.

4,090

This project not only has relatively high investment efficiency as shown in the above-mentioned indicaters but also is expected to extend a significant regional development impact to the surrounding area, which has rather lagged behind in implementation of various development shemes, being situated in a remote region in Bangladesh.

Accordingly, early implementation of the project is strongly recommended.

- 38. For detailed design and implementation, the latest topographical maps of 1:10,000 scale will be required to cover the whole project area. Detailed geological surveys will also be needed at the proposed pump station sites and at other major structure sites.
- 39. Surveys to know river bank and cross section shifting will be needed peoriodically at the proposed sites for Pateswari Pump Station and Tangonmari Pump Station.
- 40. It is important for successful and effective implementation to be incorporated with indispensable measures regarding agricultural extension services, input supply, marketing, communication and so on for supporting farmers' cultivation. In this respect, it is recommended that the BWDB discuss the project implementation with concerned agencies in order to gain their full cooperation.



TABLE OF CONTENTS

PREFACE			
PROJECT MAP			
SUMMARY			
GLOSSARY AND ABBREVIATIONS			

			Page
CHAPTER	1.	INTRODUCTION	. 1.
	1-1, 1-2, 1-3, 1-4.	General Background Objectives of the Study Activities of the Study Team (a) Activities (b) Personnel Involved in the Study	1 3 3
CHAPTER	2.	AGRICULTURE AND THE GOVERNMENTAL POLICIES IN BANGLADESH	10
		Agriculture	10 13
CHAPTER	3.	THE PROJECT AREA	21
	3-1.	Physical Conditions	21 21 27 34
	3-2,	Social Conditions	40 40 43 44 47
		Agriculture (a) Land Use (b) Cropping Pattern and Farming Practices (c) Livestock Production (d) Fishery Production (e) Agricultural Economy (f) Agricultural Supporting Services (g) Farmers Organization	50 50 53 62 64 67 73 84
	3-4.	Irrigation and Drainage	86 86 88

CHAPTER	4.	DEVELOPMENT PLAN	96
	4-1.	General	. 96
		(a) Constraints on Agricultural Development	96
		(b) Development Objectives	97
		(c) Development Strategy	97
	4-2.	Proposed Land Use	99
		(a) Land Suitability Classification	99
		(b) Proposed Land Use	. 99
	4-3.	Agricultural Production	103
		(a) Basic Cropping Pattern Concepts	103
		(b) Proposed Crops	103
		(c) Recommended Cropping Patterns	105
		(d) Target Yields and Cropping Techniques	114
		(e) Crop Production Estimation and Input Demand .	115
		(f) Livestock Production	119
		(g) Farm Management Improvement Plan	121
	4-4.	Irrigation Plan	122
		(a) Proposed Irrigated Area	122
		(b) Irrigation Water Requirements	122
		(c) Water Source for Irrigation	125
		(d) Water Intake	126
		(e) Water Conveyance System	127
	4-5.	Drainage and Flood Protection Plan	132
		(a) Drainage Improvement Plan	132
		(b) Flood Protection Planning	135
	4-6.	Marketing and Agricultural Supporting Services	143
		(a) Agricultural Input Supply	143
		(b) Marketing of Agricultural Products	143
		(c) Agricultural Supporting Services	145
	4-7.	Environmental Impacts	147
CHAPTER	5.	MAIN FACILITY PLANNING	153
	5-1.	Pateswari Pumping Station	153
		(a) Intake Work	153
		(b) Pumping Station	155
	5-2.	Tangonmari Reversible Pumping Station	159
		(a) River Conditions at Intake Point	159
		(b) Design Intake Water Level	160
		(c) Reversible Pump Station Plan	163
	5-3.	Begomganj Drainage Pumping Station	166
		(a) Basic Dimensions of Drainage Plan	166
		(b) Design Dimensions of Drainage Pump station	167
			•

	5-4.	Irrigation Canals	170
		(a) Selection of Canal Cross Sections	173
		(b) Standard Canal Cross Sections	178
	5-5.	· · · · · · · · · · · · · · · · · · ·	178
		(a) Bifurcations	178
		(b) Check Gates	178
		(c) Isscapes	178
•		(d) River Crossing Structures	178
		(e) Road Crossing Structures	179
	5-6.	. "	179
	5-7.		180
	5-8,		180
CHAPTER	6.	COST ESTIMATE	185
	6-1.	Condition of Cost Estimation	185
	6-2,	Project Cost	186
		(a) Project Cost Components	186
•		(b) Project Cost	186
		(c) Annual Disbursement Schedule	188
	6-3.	Operation and Maintenance Cost	188
CHAPTER	7.	IMPLEMENTATION PLAN	190
	7-1.	Organization for Project Implementation	190
	7-2.	Financing	190
	7-3.	Construction Mode	193
	7-4.	Implementation Schedule	193
CHAPTER	8.	OPERATION AND MAINTENACE PLAN	196
	8-1.	OPERATION AND MAINTENANCE WORKS	196
		(a) Pump Stations	196
		(b) Canals and Embankments	196
		(c) Communication System	196
	8-2.	Organization for Operation and Maintenance	196
	8-3.	Irrigators' Association	197
CHAPTER	9.	PROJECT JUSTIFICATION	201
	9-1.	General	201
	9 2.	Project Cost Estimation	202
• '	9-3.	Project Benefit Estimation	205
	9-4.	Project Justification	208
	9.5	Socio-economic Impact of the Project	210

LIST OF TABLES

		·	Page
Table	2-1	Growth and Structure of GDP	11
Table	2-2	Cropping Intensity	12
Table	2-3	Value Added from Agricultural	
		Crops at Current Prices	12
Table	2-4	GDP Composition	16
Table	2-5	Major Sectoral Targets	17
Table	2-6	Employment Target	19
Table	2-7	Foodgrain Production	19
Table	2-8	Government Foodgrain Operations	20
Table	3-1	Land Types Defined on the Basis of Flood Depth	21
Table	3-2	Land Classification based on Flood Depth	
		in the Project Area	22
Table	3-3	Soil Mapping Units and Their Extent	
		in the Project Area	24
Table	3-4	Rainfall Data	27
Table	3-5	Probable Consecutive Rainfall at Bhurungamari	30
Table	3-6	Probable Minimum Annual Rainfall	31
Table	3-7	Probable Maximum Drought Days	31
Table	3-8	Monthly Evapotranspiration	32
Table	3-9	Discharge Records	36
Table	3-10	Water Level Records	36
Table	3-11	Probable Flood Runoff	37
Table	3-12	Probable Minimum Runoff	37
Table	3-13	Population Characteristics	42
Table	3-14	Working Population	42
Table	3-15	Literacy ratio and Attendance Status of Primary Schools	44
Table	3-16	Gross Domestic Product of Rangpur Region	•
		at Current Market Price	49
Table	3-17	Present Land Use in the Project Area	50
Table	3-18	Estimated Crop Production in the Project Area	54
Table	3-19	Livestock in the Project Area	63
Table	3-20	Estimated Annual Fishery Production	65
Table	3-21	Distribution of Farm Households	70

Table	3-22	Distribution of Cultivated Areas	
	•	by Class of Farm Households	70
Table	3-23	Distribution of Landless Farmers	71
Table	3-24	Upazila-wise Distribution of Interviewed Farmers	76
Table	3-25	Village-wise Distribution of Interviewed Farmers	77
Table	3-26	Farm Household Income and Expenditures	79
Table	3-27	Drainage Area by Drainage Blocks	94
Table	3-28	Drainage Regulators in the Project Area	95
Table	3-29	Flood Embankment Construction	95
Table	4-1	Land Suitability Mapping Unit	100
Table	4-2	Present and Proposed Land Use in the Project Area	101
Table	4-3	Planned Acreage under the Proposed Cropping Patterns	109
Table	4-4	Cropping Development	110
Table	4-5	Planned Crop Production	117
Table	4-6	Total Input Requirements	118
Table	4-7	Land Use for Different Categories	122
Table	4-8	Regulators and Pumps Needed for Drainage Improvement.	138
Table	4-9	Results of Drainage Simulation Analysis	139
Table	4-10	List of Structures for Drainage Improvement	138
Table	4-11	Gaps of Embankment	141
Table	4-12	Needs for Repair for Flood Embankment	142
Table	5-1	River 10 Daily Average Discharge (March and April)	154
Table	5-2	River Intake Ratio	154
Table	5-3	Comparative Study Results for Different Types of Pumps	157
Table	5-4	Comparative Study Results for the Quantity of Pumps	158
Table	5-5	Water Level and River Bed Movement	161
Table	5-6	Design Dimensions of the Tangonmari Pump Station	164
Table	5-7	Dimensions of Main Irrigation Canals	176
Table	5-8	Dimensions of Secondary and Sub-secondary Canals	177
Table	6-1	Summary of Project Cost	187
Table	6-2	Annual Disbursement Schedule	188
Table	6-3	Summary of Annual Operation and Maintenance Cost	189
Table	7-1	Alternative Two-stage Investment Plan	194

•

Table	9-1	Project Investment Costs	204
Table	9-2	Annual Operating / Recurring Project Expenditures	205
Table	9-3	Market Price and Economic Price for Project	
	•	Benefit Calculation	206
Table	9.4	Summary of Renefit Computation	207
Table	9-5	Annual Distribution Investment Cost in the Project	208
Table	9-6	Labour Requirements for the Project	211

LIST OF FIGURES

		•	Pag
Fig.	3-1	Soil Map of Project Area	25
Fig.	3-2	Schematic Cross section of Landscape and Soil	26
Fig.	3-3	Total Annual Rainfall	28
Fig.	3-4	Monthly Average Rainfall	29
Fig.	3-5	Monthly Average Meteorological Data	33
Fig.	3-6	Water Surface Profile of Rivers	35
Fig.	3-7	Administrative Chart of Bangladesh	46
Fig.	3-8	Land Use of Project Area	51
Fig.	3-9	Present Cropping Patterns in the Project Area	57
Fig.	3-10	Marketing Channels of Crops and Livestock Products	
-		in Open Market Systems	72
Fig.	3-11	Kurigram District Agricultural Extension Organization	75
Fig.	3-12	Watersheds Around the Project Area	89
Fig.	3-13	Drainage Blocks of the Project Area	90
Fig.	3-14	Standard Cross-section of Flood Embankment	95
Fig.	<i>1</i> 1	Land Suitability of Project Area	102
Fig.		Proposed Cropping Patterns	111
Fig.		Land Type Distribution of the Project Area	113
Fig.		Plan of Irrigation System	128
Fig.		Network of Irrigation Water Distribution	129
Fig.		Longitudinal Profile of Main Canals	130
Fig.		Drainage Plan	140
		when the second	
Fig.	5-1	Layout of the Pateswari Pump Station	168
Fig.	5-2	Layout of the Tangonmari Pump Station	170
Fig.	5-3	Layout of the Begomganj Drainage Pump Station	172
Fig.	5-4	Typical Cross Section of Main Irrigation Canals	176
Fig.	5-5	Typical Cross Section of Secondary	
		and Sub-secondary Canals	177
Fig.	5-6	Proposed Flood Embankment Cross section	181
Fig.	5-7	Profile of Dharla Left Embankment	182
Fig.	5-8	Profile of Dudhkumar Right Embankment	183
Fig.	5-9	Method of Repair / Rehabilitation of Flood Embankment	184
Fig.	5-10	Typical Cross Section of Girai-Nilkamal Pass	184

Fig,	7-1	Proposed Organization Chart of Implementation for the	
		Kurigram Irrigation and Flood Control Project	191
Fig.	7-2	Structure of BWDB for Kurigram Irrigation	•
		and Flood Control Project	192
Fig.	7-3	Project Implementation Schedule	195
Fig.	8-1	Proposed Organization Chart of Operation	
		and Maintenance for the Project	200

GLOSSARY

Aman: The main rice crop. Generally, broadcast Aman is sown in

March -April and harvested in Novemberg-December.

Transplanted Aman is transplanted in mid-July -early

September and harvested in Novembere-December.

March -April and harvested in November -December.

Aus : The pre-monsoon rice, generally sown or transplanted in

Boro : The winter rice crop, generally transplanted in December-

February and harvested in April -June.

Kharif: The monsoon season.

Rabi : The dry (winter) season.

Taka : The bangladesh currency unit (Us 1 dollar = 33 Taka).

Upazila: A basic local government in Bangladesh.

ABBREVIATIONS

BADC: Bangladesh Agriculture Development Corporation

BARC : Bangladesh Agriculture Research Council BARI : Bangladesh Agricultural Reserch Institute

BB : Bangladesh Bank

BBS : Bangladesh Bureau of Statistics
BJRI : Bangladesh Jute Research Institute

BKB : Bangladesh Krishi Bank

BRDB : Bangladesh Rural Development Board BRRI : Bangladesh Rice Research Institute

BS : Block superviser

BSRIT : Bangladesh Sugarcane Research and Training Institute

BSS: Bhumiheen-bityaheen samabaya samity (Landless/assetless cooperative society)

BWDB : BangladeshWater Development Board

B. Aus : Broadcast Aus CF : Contact farmers

DAE : Department of Agriculture Extension

DTW: Deep tube-well

HYV : High-yielding variety

IRDP : Integrated Rural Development ProgramJICA : Japan International Cooperation Agency

KSS : Krishak samabaya samity (Farmers' cooperative society)

LLP : Low-lift pump

MBSS : Mahila bhumiheen-bityaheen samabaya samity

(Women's Cooperative Society)

MOA: Ministry of Agriculture

MOF : Ministry of Food

MLGRDC: Ministry of Local Government, Rural Development and

Cooperatives

NLRI : National Livestock Research Institute

SB: Sonali Bank

SMS : Subject matter specialist

SRDI : Soil Resources Development Institute

SRTI : Sugarcane Research and Training Institute

STW : Shallow tube-well

TCCA: Thana central cooperative association

TFYP : Third Five Year Plan

TK: Taka (Bangladesh currency unit)

T. Aman : Transplanted Aman

UCCA : Upazila central cooperative association

UAO : Upazila Agriculture Officer

ABBREVIATIONS OF MEASUREMENTS

Length					<u>Volume</u>				
mm	=	millimeter		•	lit.	:=:	liter		
cm	-	centimeter			cm ³	==	cubic centimet	er	
	==	0.39 in.			m^3	==	cubic meter		
m	==	meter	==	1.09yd.		===	1,000 lit.		
	=	3.28 ft			MCM	==	million m ⁸		
km	=	kilometer	==	0.62ml.		==	$1\times10^3\mathrm{m}^3$		
in.	==	inch	. ==	2.54cm	ft³	=	cubic feet	=	$0.028~\mathrm{m^3}$
ft.	==	foot	==	30.48cm			28.32 lit.		
yd.	==	yard	=	91.44cm	ac-in.	=	acre inch	==	$88.05 \mathrm{m}^3$
ml.	=	mile	=	1.61km	ac-ft.	==	acre feet	=	$1,234 \mathrm{m}^3$
Area					<u>Weight</u>				
$ m cm^2$	=	square centim	ietei	•	g	==	gram		
m^2	=	square meter			kg	=	kilogram		
km^2	•==	square kilome	eter		t	==	metric ton	==	1,000kg
	=	100ha			lb	=	pound	=	375g
ha	=	hectare	=	0.01 km²					
		2.5ac			Time				
ac	=	acre	=	0.41 ha	sec	=	second		
	-	4,050 m ²			min	=	minute	=	60 seconds
$\mathrm{ft^2}$	=	square feet			hr	=	hour	==	60 minuits
	. ==	0.03 m^2				=	3,600 seconds		
$mile^2$	=	square mile	=	$2.59 \mathrm{km^2}$	day	==	24hrs	==	1,440 minutes
						==	86,400 seconds	3	
					yr	=	year		
Electric	cal N	<u>leasures</u>			Derived	Mρ	9511r0c		
KW		kilowatt	_	1,000 watt			cubic meter pe	r er	neand
MW	=	megawatt		1,000 Watt	III / Sec	_	(Cumec)	11 50	cond
GW	=	gigawatt	=	4 3	ft³/ sec	=	cubic foot per s	nen	nd
KV	=	kilovolt	=	1,000 wolt	10 / 500		(Cusec)	icco.	na -
72.1		***************************************		1,000 1010			(Ouseo)		
Other N	<u> Ieas</u>	ures			Monetar	<u>. y</u>			
%		percent			US\$	=	US dollar		
0	==	degree			¥	=	Japanese yen		
• •		minute			TK	=	Taka		
"	=	second		•	US\$1	==	Tk 33.0	=	¥ 148.5
°C	=	degree in cent	igra	de					
crore	= '.	10 million							
lakh	==	0.1 million							

CHAPTER 1

INTRODUCTION

CHAPTER 1 INTRODUCTION

1-1. General

In response to the request made by he Government of the People's Republic of Bangladesh (hereinafter referred to as "the Government of Bangladesh"), the Government of Japan entrusted the implementation of a Feasibility Study on the Kurigram Irrigation and Flood Control Project-North Unit (hereinafter referred to as "the Study") to the Japan International Cooperation Agency (hereinafter referred to as "JICA"). From the 3rd to the 15th of February 1989, JICA dispatched a Preliminary Survey Team to Bangladesh and concluded the Scope of Work (S/W) for the Study with the Bangladesh Water Development Board (hereinafter referred to as "BWDB").

Based on the S/W, a Feasibility Study Team (hereinafter referred to as "the Team") conducted the field work in Bangladesh for the Phase I Study from July the 31st through October the 28th in 1989, and afterwards the home office work to analyze the collected data and to formulate basic concept for a development plan. These results were incorporated in the Interim Report.

The Team again visited Bangladesh to conduct the field work for the Phase II Study from January 10th through March 30th, 1990. Upon returning to Japan, the Team studied to formulate a development plan based on all the results which had been collected and analyzed through the previous works. The Draft Final Report was prepared to present these study results, which was explained and discussed at a meeting between the BWDB and the Team in August, 1990. Taking the discussion results into consideration, the Draft Final Report was rivised and elaborated. As a result this Final Report was completed.

1-2. Background

From administrative point of view, the Study area is located in four upazilas; namely Kurigram, Bhurangamari, Fulbari and Nageswari which are included in the Kurigram District, adjoining the West Bengal of India.

The land of the study area displays a typical type of alluvial plain in the Tista delta, bordered by the Dudhkumar, Brahmaputra and Dharla rivers, and is about

between 65-128 ft (EL.20-39 m) above the sea level. The land is flat and has inundation problem.

The gross extent of the Study area is approximately 42,800 hectares, of which the net cultivated area is about 35,100 hectares. Most of the available land has been exploited for cultivation.

The population of the Study area is approximately 350 thousands and the estimated annual population growth rate is about 2.5%. 90% of the population lives on agriculture. 52% of the total farmers are independent farmers, 48% landless farmers.

The average annual rainfall in the Study area falls between 2,300 and 3,200 mm. This amount is generally supposed to be no less than sufficient for cultivation. However, the precipitation is not distributed enough for crop cultivation during the dry period from December to May, while 80% of that is concentrated in the monsoon period from June to October.

The present cropping intensity of the study area is about 177 %, which is relatively high as compared with the national average rate of 154 %. This igh ate is mainly attributed to double cropping, in addition to cultivation in the monsoon period, owing to rain-fed cultivation in the pre-monsoon and to irrigated cultivation in the dry period. Approximately 28 % of the total cultivable land is cropped under irrigation either by pumping from beels, creeks and wells or by manual labor.

Under the above-mentioned natural and social conditions, the agriculture in the Study area has stagnated in relatively low productivity, lagging behind on introduction of improved cultivation technology such as high yield rice varieties and fertilizer application. The most fundamental and significant factor which constrains agricultural development in the Study area seems to be its unfavorable water conditions.

Being aimed at complete improvement of the water conditions in the Kuriguram area including the Study area, a feasibility study was conducted for an irrigation and drainage project under the initiative and administration of the East Pakistan Water & Power Development Authority. The project was started in 1973 and some works including a part of embankment and drainage regulators

have been constructed until now. However, the progress is at a very slow pace mainly due to financial constraint.

On the Third National Five-Year Development Plan, the Government of Bangladesh has put emphasis on accomplishment of food self-sufficiency and improvement of productive employment. Following this policy, the Government decided to accelerate the Kurigram Irrigation and Flood Control Project. The Project area was divided into two units, of which the North Unit was proposed for first implementation of a feasibility study based on updated natural, social and technical aspects.

1-3. Objectives of the Study

The objectives of the Study are to formulate plans for irrigation and drainage development as well as flood control for the Kurigram North Unit, which will be justified from technical feasibility, economic viability and socio-economic acceptability viewpoints, toward the increase and improvement of agricultural productions.

1-4. Activities of the Study Team

(a) Activities

The Study were implemented in two phases, namely, the Phase I Study (July 1989 to December 1989, approximately 6 months) and the Phase II Study (January 1990 to August 1990, approximately 8 months).

1) Phase I Study (Study in the rainy season)

The Phase I Study consisted of preliminary home office work, field work for data collection and survey (July to October, 1989), and home office work for data analyses and the formulation of a basic concept for a development plan (November to December, 1989).

At the beginning of the Study, on August the 5th, a meeting was held between the BWDB and the Team in the presence of JICA's advisory committee for explanations and discussions on the Inception Report, which had been prepared by the Team to present the basic concept, plan of operation and schedules of the Study. Both the parties agreed that the Study be conducted as per the laid down program in the Inception Report.

Data and information, including maps, aerial photographs, the existing feasibility study reports (Kurigram Flood Control and Irrigation Project, initially worked out in 1969 and revised in 1975) and statistics, necessary for grasping the present situation of the Study Area and for studying the development plan, were collected successfully as scheduled in the Inception Report. Field investigations, including a reconnaissance survey on major facilities, a water requirement test, surveys on present conditions of land use, farming, irrigation and drainage and an inquiry-survey with farmers, were carried out. In addition, a boring survey and a topographical survey at the proposed site for a main pumping station, as well as topographical surveys for the main irrigation canals and four sampled areas of 40 ~50 ha each, were conducted, which had initially been scheduled in the Phase II Study.

On October the 24th, a meeting was held between the BWDB and the Team for explanations and discussions of the Progress Report (I).

After having returned to Japan, the Team analyzed the collected data and the surveyed results through the field work in Bangladesh. In addition, based on the analyses, the Team formulated a basic concept for agricultural production, irrigation, drainage and flood control plans. These results were incorporated in the Interim Report.

2) Phase II Study (Study in the dry season)

The Phase II Study comprised field work for supplementary surveys and additional data collections (January to March, 1990), home office work for data analyses and the formulation of plans (May to July, 1990).

On the 13th and 14th in January, a meeting was held between BWDB and the Study Team for the explanation and discussions on the Interim Report.

Field surveys and data collection were conducted. Major works were soil survey and analyses, additional investigation on the existing tube well irrigation to know the present condition of irrigation and the actual water consumption, topographical surveys for the Dudhkumar river's cross sections and for major structures, analysis of the results from the interview survey of sampled farmers,

measurement of the river discharge to examine the availability of irrigation water intake as well as data collection on agronomy, agro-economy, drainage, Preliminary design of major structures, construction cost estimation and project evaluation.

Meetings were held between the concerned experts from the Bangladesh side and the Study Team, respectively on irrigation planning on the 29th in January, on cropping patterns on the 3rd in February and on drainage planning on the same day.

On the basis of surveyed results, collected and analyzed data and discussions with the BWDB side concerned officials, the outline of plans for the respective components were studied.

Major results from the Phase II field work and policies for planning were incorporated in the Progress Report (II). A meeting was held for explanation and discussions on this report on the 25th in March.

After having returned to Japan, the Team carried out the home office work including the following items:

- Review of all the previous field work results and data analyses.
- Confirmation of basic plans referring to the previous discussions with the BWDB.
- Completion of plans for irrigation, drainage and flood control systems.
- Estimation of costs and benefits of the development plan.
- Formation of plans for operation and maintenance.
- Evaluation of the development plan in view of economic, financial and sensitivity analyses.
- Formation of the implementation plan and schedule.
- Preparation of recommendations.

The results of the above-mentioned work were incorporated in the Draft Final Report, which was sent to the BWDB at the end of July, 1990. A meeting was held between the BWDB and the Team for the explanation of the Draft Final Report in August, 1990. Taking the discussion results into consideration, the Draft Final Report was rivised and elaborated. As a result this Final Report was completed.

(b) Personnel Involved in the Study

During the Feasibility Study period, the following personnel were involved in the Study.

Members of the Feasibility Study Team

Name

Mr. MURATA Toshihisa Team Leader

Mr. IWAI Isao Irrigation Planning/Co-Leader

Mr. MAHBUB A. K. M. Reza Hydrology/Meteorology

Mr. BANNO Kiyoshi Drainage Planning

Mr. OOSAWA Takeshi Pumping Facilities Planning

Mr. SHIBATA Toshihide Agriculture

Mr. KOTO Akira Soil/Land Use

Mr. INADA Sho Agro-Economy

Mr. HORI Shinwa Facilities Design

Mr. YAMASHITA Masanobu Project Evaluation

Advisory Committee

Name

Speciality

Speciality

Mr. KIMURA Kazuo Leader, Advisory Committee.

Mr. NAMBA Teruhisa Member, Avvisory Committee.

BWDB Counterpart Personnel

Name

Designation

Mr. Shamsur Rahman	Member, Planning, BWDB.
Mr. Mabinuddin Chaudhury	Chief Engineer, Planning, BWDB, Dhaka.
Mr. Majidul Islam	Chief Engineer, Planning, BWDB, Dhaka.
Mr. M. A. Razzaque	Chief Engineer, Planning, BWDB, Dhaka.
Mr. Khaliquzzaman	Director, Planning (General), BWDB, Dhaka.
Mr. Md. Lutfur Eahman	Director, Planning (General), BWDB, Dhaka.
Mr. Emam Hossain Khan	Chief and Agricultural Survey Officer, Office of Director, Planning(General), BWDB,Dhaka.
Mr. A. K. M. Anisur Rahman	Superinending Engineer, Canal Circle- II, BWDB, Rangpur.

BWDB Officials Contacted during the Study

Name	
------	--

Designation

Name	Designation
Mr. M.A. Matin	Director, Planning Schemes-I, BWDB, Dhaka.
Mr. A. A. Ansari	Director, Planning Schemes-II, BWDB, Dhaka.
Mr. Syed Shahadat Hossain	Director, Surface Water Hydrology-I,BWDB, Dhaka.
Mr. Md. Alam Mia	Director, Surface Water Hydrology-II,BWDB, Dhaka.
Mr. M. A. Sattar	Director, Land and Water Use, BWDB, Dhaka.
Mr. Md. Hasan Zubair	Executive Engineer, Kurigram W.D. Division-II, BWDB, Kurigram.
Mr. Abu Jaffar Howlader	Executive Engineer, Kurigram W.D. Division-II, BWDB, Kurigram.
Mr. Badiur Rahman	Chief Soil and Agricultural Survey Officer, Office of Chief Engineer, Planning, BWDB, Dhaka.
Mr. M. A. Mannan	Sr.Agril. Planning Officer, BWDB, Dhaka.
Mr. Raihan Ali Miah	Executive Engineer, Design, BWDB, Dhaka.

Mr. N. Chakravarty Economist, Directorate of Planning

Scheme-I, BWDB, Dhaka.

Mr. Md. Abdus Salam Executive Engineer, Planning Schemes-II,

BWDB, Dhaka.

Mr. Md. Obaidul Islam Executive Engineer, Planning (General),

BWDB, Dhaka.

Mr. Shoffuddin Ahmed Executive Engineer, Planning (General),

BWDB, Dhaka.

Mr. A. K. M. Halimur Rahman Executive Engineer, Design Circle- II,

BWDB, Dhaka.

Mr. M. A. Rashid Executive Engineer, Office of the Chief

Engineer, Design-II, BWDB, Dhaka.

Mr. Syed Manzoor Towheed Dy. Chief Agronomist, Dte. Land & Water

Use, BWDB, Dhaka

Mr. Md. Jamshed Ali Sub-Divnl, Engineer, Kurigram W.D. Divn-

II, BWDB, Kurigram.

Mr. Md. Farook Ahmed Sub-Divnl, Engineer, Kurigram W.D. Divn-

II, BWDB, Kurigram.

Mr. Md.A.Majid Sub-Divnl, Engineer, Kurigram W.D.

Other Officers Contacted during the Study

Name Position

Mr. Sk. Amir Ali Superintending Engineer, MPO, Banani,

Dhaka.

Mr. Azizul Haque Chief Agronomist, MPO, Banani, Dhaka.

Mr. Md. Jahurul Huq Dy. Director, Directorate of Agril.

Extension.

Mr. Md. Shajahan Former Associate Professor, Department of

Economics of Carmichael University

Collage, Rangpur.

Mr. Mohd. Idris Ali Principal Scientific Officer, Regional Office,

SRDI.

Mr. Khabir Hossain Scientific Officer, Regional Office, SRDI.

Deputy Dir., Bangladesh Meteology Dept. Mr. Mahtabuddin Ahmed Deputy Director, Directorate of Agril. Mr. Wasiuzzaman Extention, Kurigram. Mr. Abdur Rouf Assistant Statistical Officer, Rangpur. Assistant Engineer, BADC, Nageswari. Mr. Jainal Abedin Mr. Shamsul Haque Choudhury Chairman, Bhurungamari Upazila Parishad. Mr. A.S.M. Abdul Hamid Bhurungamari Upazila Nirbahi Officer. Mr. Rustam Ali Mondal Bhurungamari Upazila Agriculture Officer. Bhurungamari Upazila Engineer. Mr. Ismail Hossain Bhurungamari Upazila Fishery Officer. Mr. Nurul Islam Choudhury Bhurungamari Upazila Cooperative Officer. Mr. Rabindranath Deb Bhurungamari Upazila Statistical Officer. Mr. Shaban Ali Mr. Saifur Rahman Chairman, Nageswari Upazila Parishad. Nageswari Upazila Nirbahi Officer. Mr. Monsin Khan Mr. Abdul Khaleque Nageswari Upazila Engineer. Mr. Bhupen Kumar Mondal Nageswari Upazila Additional Agriculture Officer. Nageswari Upazila Fishery Officer. Mr. M.A. Quddus Akanda SSAE(IRRI), BADC, Nageswari. Mr. M.A.Rashid Mr. Abul Asad Miah Nageswari Project Implementation Officer. Nageswari Upazila Statistical Officer. Mr. Abu Tayeb Sarder Mr. A.k.M. Shamsudoha Chairman, Kurigram Upazila. Mr. Md.Muazzem Hossain Kurigram Upazila Nirbahi Officer. Mr. Md. Hassan Ali Kurigram Upazila Agriculture Officer. Mr. Abdul Malegue Sarker Kurigram Upazila Engineer. Mr. Dobiruddin Kurigram Upazila Statistical Officer. Mr. Md. Shahadat Hussain Chairman, Fulbari Upazila.

Mr. Md. Rafigul Islam

Mr. Jafor Ali Sorker

Mr. Md. Abdul Karim Mandal

Fulbari Upazila Nirbahi Officer.

Fulbari Upazila Agricultural Officer.

Fulbari Upazila Statistical Officer.

CHAPTER 2

AGRICULTURE AND THE GOVERNMENTAL POLICIES IN BANGLADESH

CHAPTER 2 AGRICULTURE AND THE GOVERNMENTAL POLICIES IN BANGLADESH

2-1. Agriculture

The cultivated area in Bangladesh amounts to 63% of the total land area. 85% of the total households as well as 85% of the total population are in rural areas. Agriculture provides the highest portion of employment (61%). Even in the industrial sector, the main industries achieving significant development are those related to agriculture, for example, jute and cotton textile industries which use agricultural crops as raw materials. Although an annual real growth rate in the agricultural sector dropped to 3.8% from 1976 to 1985, the agricultural sector occupied a large portion of the GDP, i.e., 54.3% in 1984/85 as shown in Table 2-1. These facts show that Bangladesh is primarily an agricultural country.

According to the 1983/84 agricultural census, the number of farm households in the country was 10,045,299, which accounted for 73% of the total households. Of them, small scale farmers (less than 1.0 ha) occupied 70%, medium scale farmers (1.0~3.0 ha) 25% and large scale farmers (more than 3.0 ha) 5%. The net cultivated land area was 8,157,786 ha, i.e., 70% of the total land area (excluding reserved forests and river areas). The net cultivated area per farm household was 0.8 ha, while the operated area for that was 0.9 ha.

According to the above census, the landless farmers in the country occupied 49% of the total households. Out of them, the landless I (having no land) occupied 9% of the total, the landless II (having homestead land but no cultivable land) 14% and the landless III (having homestead land and up to 0.2 ha of cultivable land) 26%. These landless farmers form the poor in rural areas and have an important meaning as the dearth of basic human needs, unemployment, social uneasiness in urban areas and the backwardness of agricultural productivity.

In 1986/87, the total cropped area was 14,117,000 ha, of which 4,363,000 ha were single cropped, 3,719,000 ha were double cropped and 772,000 ha were triple cropped as shown in Table 2-2. Accordingly, the cropping intensity was 159% in the country. As for crops, the cropped area of rice was 10,323,000 ha (73.1% of the total cropped area), of wheat 597,000 ha (4.2%), of jute 512,000 ha (3.6%), of pulses 737,000 ha (5.2%), of oilseeds 537,000 ha (3.9%), of condiments and spices 210,000 ha (1.5%) and of tobacco 47,000 ha (0.3%). Crop yields per ha were 1.5 t of rice, 18

t of wheat, 1.7 t of jute and 43 t of sugercane. Accordingly, rice is Predominant in Bangladesh agriculture. The production of food grains (rice and wheat) amounted to 17,039 thousand tons in 1987/88. Besides, the area of rice cropped under irrigation was 1,717,000 ha, which occupied 16.6% of the total cropped area of rice.

On the other hand, the share for agriculture was 39% of the country's GDP in 1987/88. Cereal crops occupied 74.6% of the agriculture GDP, jute 4.6%, fruits 5.5%, beverages 1.9%, oil seeds 2.2%, pulses 2.6%, spices 2.3%, sugercane 3.0% vegetables 2.9% and others 0.3% as shown in Table 2-3.

Table 2-1 Growth and Structure of GDP (At 1972/73 factor cost)

(Unit: Tk. in crore)

			Annual	Share of C	DP of (%)
Sectors	GDP of 1972/73	GDP of 1984/85	Growth Rate (%)	1972/73	1984/85
i) Agriculture	2,722.0	4,248.0	3.8	60.1	54.3
ii) Industries	329.8	676.8	6.2	7.3	8.6
iii) Other sectors	1,478.2	2,903.6	5.8	32.6	37.1
Total	4,530.0	7,829.0	4.7	100.0	100.0

Source: Third Five-Tear Plan, 1985-90

Table 2-2 Cropping Intensity (1986-87)

	Cropped	Double Cropped Area		1	Total Cropped Area	Intensity of Cropping
	'000'ha	'000'ha	'000'ha	'000'ha	'000'ha	%
Country	4,363	3,719	772	8,854	14,117	159.4
200					<u> </u>	

Source: 1989 Statistical Yearbook of Bangladesh

Note: Intensity of cropping of 1984-85 is 152.2% and 154.5%

respectively

Table 2-3 Value Added from Agricultural Crops at Current Prices (1987-88)

	Cereals	Beve- rages	Fi- bers	Frui- ts	Oil- seeds	Pul- ses	Spi- ces	Sugar -cane	Vege- tables	Othe rs	Total
Value Added (Million Taka)	127,002	3,393	7,848	9,318	3,797	4,354	3,979	5,104	4,946	471	170,212
Percentage(%)	74.6	2.0	4.6	5.5	2.2	2.6	2.3	3.0	2.9	0.3	100.0

Source: The above

2-2. The Government's Policy

Bangladesh has followed the course of planned development since her independence, and the Government policy was implemented based on that plans.

As a national development plan for the period of 1985 through till 1990, the Third Five Year Plan (TFYP) was enforced. The ultimate object of the TFYP was set to be poverty alleviation as had been in the preceding plans, considering the present social and economic situation. The problem of poverty, however, seemed to be so serious and complicated that it needed comprehensive countermeasures formulated based on a long perspective as well as on relative priorities considering the limit of available resources, administrative capabilities and the cultural characteristics of the society. In line with this aspect, the major objectives of the TFYP were given as follows:

- 1) Reduction of population growth.
- 2) Expansion of productive Employment.
- 3) Universal primary education and human resource development.
- 4) Development of a technological base for bringing about long term structural changes.
- 5) Food self-sufficiency.
- 6) Satisfaction of the minimum basic needs of the people.
- 7) Acceleration of economic growth.
- 8) Promotion of self-reliance.

The TFYP aims at an average annual real growth rate in gross domestic products of 5.4%, while the annual population growth rate is projected to decrease from the current 2.4% to 1.8% at the end of the TFYP. For the agricultural sector, a 4.0% annual growth rate is targeted (Table 2-4).

The main objective given to the agricultural sector in the TFYP is to attain self-sufficiency in foodgrain production. For this, foodgrain production needs to grow at a 5.2% annual rate from the bench mark production, 16.1 million tons (1984/85) to 20.7 million tons, the target in the terminal year (1989/90) of the TFYP. This target is set to ensure the food availability of 16 oz, (453 g) per capita per day (Table 2-5).

The employment target of the TFYP is set as 243.8 1ac in the terminal year at a 4.8% growth rate (Table 2-6). This means that 50.9 1ac men-years of fresh employment will be generated, and it is pointed out that approximately 67.2% of the additional employment will arise from expanded activities in the agricultural sector during the TFYP.

However, the Government has envisaged serious difficulties for the achievement of the TFYP due to the unprecedented floods in 1987 and 1988, resource constraints and occasional natural calamities after the TFYP was launched.

In 1987/88, serious damages from severe floods caused a reduction in foodgrain production down to 16.46 million tons (rice 15.4 million tons, wheat 1.05 million tons), which was considerably less than 17.51 million tons of the target production (Table 2-7). As a result, the actual annual growth rate for the first three years of the TFYP has been approximately 0.7% against the target rate of 4.5% (Table 2-8).

In 1988/89, foodgrain production again suffered record damages from natural disasters such as excessive rainfall in May, excessive rain fall and floods in June and July, severe floods in August and September and a cyclone in November. These damages brought about a reduction of food grain production by 3,163 thousand tons (rice 3,135 thousand tons, wheat 28 thousand tons).

To cope with the above serious corcumstances, the Government has been continuing efforts to increase crop production and to attain self-sufficiency in foodgrains. One of the taken measures was a project named "Flood Rehabilitation Program", which was implemented in 1987/88.

Meanwhile, the main development objectives in the agricultural sector in 1987/88 and 1988/89 were given as follows:

- 1) To attain self-sufficiency in foodgrain production by increasing the per acre yield.
- 2) To increase the production of various types of crops on the same land per year.
- 3) To assist in the increase of foodgrain production through the distribution of improved quality seeds.

- 4) To ensure water and water resources through the utilization of necessary agricultural inputs.
- 5) To assist with the physical and financial conditions of the farmers to increase foodgrain production in the agricultural sector.

Table 2-4 GDP Composition (constant factor cost of 1984/85)

(Unit: Tk. in crore)

	1984/85		198	9/90	
		Shares		Shares	Annual
	GDP	of GDP	GDP	of GDP	Growth Rate
		(%)		(%)	(%)
1. Agriculture	16,538	50.4	20,052	46.9	4.0
2. Industries	3,125	9.5	5,063	11.9	10.1
3. Gas and Electricity	238	0.7	376	0.9	9.6
4. Construction	761	2.3	965	2.3	4.9
5. Transport & Communication	1,722	5.2	2,407	5.6	6.9
6. Trade & Other Services	7,319	22.4	9,975	23.3	6.4
7. Housing Services	986	3.0	1,182	2.8	3.7
8. Public Services	2,145	6.5	2,690	6.3	4.6
Total	32,834	100	42,710	100	5.4

Source: The Third Five-year Plan, 1985-90

Table 2-5 Major Sectoral Targets of the TFYP

Constitution of the consti		4554454	1666
Items	Units	1984/85	1989/90
		(Actual)	(Target)
Agriculture			
1. Foodgrains/1	ml. metric tons	16.1	20.7
(a) Rice	-do-	14.6	18.0
(b) Wheat	-do-	1.5	2.6
(c) Others	-do-	_	0.1
2. Jute	ml. bales	4.6	6.0
3. Tea	ml. lb	96.8	115.0
4. Sugarcane	lakh tons	70.0	82.0
5. Pulses/1	-do-	2.0	3.0
6. Oil Seeds	-do-	2.0	3.5
7. Potato	-do-	13.0	17.0
8. Fish/1	'000 tons	774	1000
Industries			
1. Jute Textiles	'000 tons	561	650
2. Cotton Textiles			
(a) Yarn	ml, kg.	59.4	95.0
(b) Cloth	ml. metre	771.0	1215.0
3. Fertilizer	'000 metric tons	806	21.5
4. Paper and Newsprint	-do-	90	105
5. Sugar	-do-	88	225
6. Cement	'000 metric tons	240	850
7. Basic Metals (Steel)	-do-	101	230
Energy			
1. Electricity			
(a) Generation	GWH	4545	899
(b) Sales	GWH	2840	7146
(c) Villages/1	'000 numbers	7.9	22.1
2. Gas			
(a) Output	MMCFD	450	750
(b) Customs Connections	'000 numbers	240	400
(c) Development Wells	Numbers	21	38
Transport and Communication			
1. Paved Roads	Km	4,830	6,118

(to be continued on next page)

·	Items	Units	1984/85 (Actual)	1989/90 (Target)
PPH				
1.	Rural Drinking Water Supply/1	'000 of hand	618.8	792.8
:		tubewells/*		
Edu	cation			
	Primary School Enrolment/1	1akh students	89.2	116
2.		-do-	24.8	27.5
3.	College Education Enrolment	-do-	4.3	4.4
4.	University Education Enrolment	'000 students	25.0	38.6
5.		-do-	20.4	22.0
6.	Vocational Educatition Enrolment	-do-	554	756
	(including community schools)			
7.	Madrasa Education Enrolment	-do-	319	350
Hea				
	No. of Hospital beds/1	'000 numbers	27.6	40.7
	No. of Doctors	-do-	16.0	22.5
	No. of Nurses	-do-	6.5	10.2
	ılation Control			
	Population Growth Rate	%	2.4	1.8
	Contraceptive Prevalence Rate	-do-	25	40
	(CPR)			

^{/*} \cdots This includes shallow, deep and deepsat hand tubewells.

Source: Third Five-Year Plan (TFYP), 1985-90

^{/1 ···} Basic Needs Supplies (Output)

Table 2-6 Employment Target

(Unit: lac of men-year)

Sector	1984/85 (Benchmark)	1989/90 (Target)	Increase over Benchmark	Percentage of Increase
1. Agriculture	116.4	150.6	34.2	67.2
2. Industries	19.0	24.3	5.3	10.4
3. Public Utilities	16.9	18.7	1.8	3.5
4. Construciton	5.9	7.3	1.4	2.8
5. Public Services	20.0	25.2	5.2	10.2
6. Trade and others	14.7	17.7	3.0	5.9
Total	192.9	243.8	50.9	100.0

Source: Third Five-year Plan (1985-90)

Table 2-7 Foodgrain Production

(In million tons)

Crop	s		Year	1984/85	1985/86	1986/87	1987/88	1989/90 Plan target
Aus	4 4	••	• •	2.78	2.83	3.12	2.99	3.42
Aman	••		••	7.93	8.54	8.26	7.72	9.18
Boro	••	••	••	3.91	3.67	4.03	4.70	5.40
Rice	••	••	••	14.62	15.04	15.41	15.41	18.00
Wheat	••	••	••	1.46 0.03	1.04 0.04	$\begin{array}{c} 1.07 \\ 0.02 \end{array}$	1.05 0.04	$\begin{array}{c} 2.60 \\ 0.10 \end{array}$
	Toı	ral	**	16.11	16.12	16.50	16.50	20.70

Source: Mid-Term Review of the Third Five Year Plan 1985-90

Table 2-8 Government Foodgrain Operations

(Figure in lakh tons)

	Description		1983-84	1984-85	1985-86	1986-87	1987-88
			(Actual)	(Actual)	(Actual)	(Actual)	(Estimated)
	1		2	3	4	5	6
1.	Population (crore)	••	9.67	9.92	10.17	10.41	10.74
2.	Foodgrain requirement		154.60	163.00	166.00	169.70	173.60
3.	(a) Aus ·· ··	••	31.71	27.80	28.30	31,30	29.93 (Actual)
	(b) Aman		78.11	79.30	85.40	82.67	76.89
	(c) Boro	••	35.00	39.10	36.70	40.00	46.64
	(d) Wheat	••	11.90	14.60	10.40	11.00	10.50
	Total production ··	••	156.72	160.80	160.80	164.97	163.96
4.	Net availability of foodgrains		140.72	144.80	144.80	148.50	148.00
5.	Food deficit/surplus	••	13.88	18.20	21.20	21.20	25.60
6.	Government foodgrain operations						
	(a) Opening stock		6.88	8.68	11,46	10.58	8.33
	(b) Internal procurement (+)	••	2.68	3.49	3.50	2.18	2.00
	(c) External procurement (+)	••	20.57	25.89	11.95	17.68	30.73
	Total foodgrain stock ··		30.13	38.06	26,91	30.44	41.06
7.	Foodgrain distribution (-)		20.51	25.63	15.40	21.20	28.00
8.	Stock loss (-)		0.94	0.97	0.93	0.91	1.00
	Foodgrain closing stocks	-	8.68	11.46	10.58	8.33	12.06

NR

Source: Food Division

- (a) Total production \times 0.90 (10% for seed, feed and waste) = net production
- (b) Foodgrain requirements (-) Net production = Food deficit/Surplus
- (c) Foodgrain opening stock (+) Internal procurement (+) External procurement
 - = Foodgrain total stock
- (d) Foodgrain total stock (-) Foodgrain distributions and Stock loss = Foodgrain closing stock

Source; Ministry of Finance, Bangladesh Economic Survey 1987/88