

5.2.2 Sediment run-off disaster prevention works

The construction works for sediment run-off disaster prevention works comprise three (3) categories; Sabo dam construction, channel works and ground sill works.

The construction plan for the above major works is as follows:

(1) Sabo dam

Major work items and quantities of Sabo dams are tabulated below.

Contract Package	Sabo Basin No.	Work Quantity (m ³)	
		Excavation	Concrete
Package-A	2	35,200	22,000
	3	8,500	9,800
	Subtotal	43,700	31,800
Package-B	7	13,900	9,400
	8	6,400	3,700
	subtotal	20,300	13,100
Package-C	10	600	1,100
	11	4,400	7,300
	12	3,900	4,900
	subtotal	8,900	13,300
Total		72,900	58,200

The total work quantity of excavation was estimated at around 72,900 m³, distributed as follows: 43,700 m³ for Package-A, 20,300 m³ for Package-B, and 8,900 m³ for Package-C. Meanwhile, the total work quantity of concrete was approximately estimated at 58,200 m³, distributed as follows: 31,800 m³ for Package-A, 13,100 m³ for Package-B and 13,300 m³ for Package-C.

Excavation was planned to be carried out by medium class construction equipment owing to limited site conditions. The excavated materials were to be transported to spoil banks which were basically planned in the vicinity of each dam. Hauling distance from dam site to the spoil banks was approximately 1 km on average.

Following the excavation of dam foundation, Sabo dam construction was planned with due consideration for foundation treatment and against expected flood during construction. Temporary construction plant was exclusively designed in each Package for secure concrete supply, which meets design mix proportion.

(2) Channel works

Major work items and quantities of channel works are tabulated below.

Contract Package	Sabo Basin No.	Work Quantity	
		Length (m)	Excavation (m ³)
Package-A	2	530	70,800
	3	490	31,200
	subtotal	1,020	102,000
Package-B	7	250	39,400
	8	440	23,200
	subtotal	690	62,600
Package-C	10	-	-
	11	410	12,300
	12	750	64,000
	subtotal	1,160	76,300
Total		2,870	240,900

The total channel length was estimated at around 2,870 m, distributed as follows; 1,020 m for Package-A, 690 m for Package-B, and 1,160 m for Package-C. Meanwhile, the total work quantity of excavation was approximately estimated at 240,900 m³, distributed as follows; 102,000 m³ for Package-A, 62,600 m³ for Package-B, and 76,300 m³ for Package-C.

The channel works, which were designed at the downstream of each Sabo dam except for basin No. 10, comprise channel excavation, gravel backsill, concrete block installation, wet masonry and gabion mattress.

(3) Groundsill

Major work items and quantities of groundsill works are tabulated below.

Contract	Sabo Basin	Work Quantity		
		No.	Nos.	Excavation (m ³) Concrete (m ³)
Package-A	2	4	15,700	1,210
	3	1	120	230
	subtotal	5	15,200	1,440
Package-B	7	5	10,500	1,040
	8	4	4,000	370
	subtotal	9	14,500	1,410
Package-C	10	-	-	-
	11	11	15,700	1,100
	12	9	19,000	900
	subtotal	20	34,700	2,000
Total		34	65,020	4,850

The total groundsills amount to 34 numbers; 5 nos. for Package-A, 9 nos. for Package-B, and 20 nos. for Package-C. The total work quantity of excavation was estimated at around 65,020 m³, distributed as follows; 15,820 m³ for Package-A, 14,500 m³ for Package-B, and 34,700 m³ for Package-C. The total work quantity of concrete was approximately estimated at 4,850 m³, distributed as follows; 1,440 m³ for Package-A, 1,410 m³ for Package-B, and 2,000 m³ for Package-C.

Construction of groundsill with maximum height of 5 m, arranged in each river channel, was planned to be executed together with channel works. Construction works were to be carried out, taking into full account sequence of the works, restricted site conditions, and combination of the equipment.

5.2.3 Flood Disaster Prevention Works

The construction works for flood disaster prevention works comprise dike construction, new channel excavation of around 1 km, dredging, and relocation works of road and railway bridges.

The general feature of the priority project of flood disaster prevention works are summarized below:

Component	Type of Structure	Quantity
Dike		265,000 m ³
Excavation		334,000 m ³
Dredging		141,000 m ³
Revetment	Wet masonry	9,800 m ²
Culvert		1.5m x 1.5m (6 sites) 2.0m x 2.5 m(1 site)
Intake Weir	Concrete	
Parapet Wall	Concrete	
Road Bridge		40.8 m
Railway Bridge		130.5 m

The construction plan for the major works is as follows:

(1) Dike

The dike construction of 265,000 m³ was planned to be carried out in parallel with a new channel excavation and dredging works. Approximately one-third of embankment volume was to be directly hauled from excavation site, whereas around 60% was transported from stock yard where excavated materials were to be treated. Remaining embankment material was planned from borrow pit in the upstream of the Moji river.

(2) Channel excavation

The new channel excavation of the Moji river amounting to 334,000 m³ was planned by combination of conventional excavation and dredging method. The excavation above water level was basically to be performed by medium class construction equipment. Meanwhile, dredging was also planned for excavation below water level and where applicable, to save excavation cost.

Excavation volume of around 100,000 m³ was planned to be directly hauled for dike embankment. Another 100,000 m³ was to be transported to stock yard for material treatment and remaining 134,000 m³ was envisaged to spoil bank.

(3) Dredging

Around 141,000 m³ of channel dredging was basically planned to be carried out using pump suction dredger. The dredged material obtained from the upper sediment of riverbed material was designed to be hauled to stock yard to exert material treatment for dike embankment. On the other hand, the sediment material mainly consisting of silty deposits from the lower portion of the riverbed was planned to spoil bank for future land reclamation.

(4) Relocation of existing bridge construction

The existing road bridges and Federal railway (RFFSA) were planned to be relocated in the early stage of construction works. Both relocation works were designed with due care for local traffic and consideration during construction and for future permanent use.

5.3 Cost Estimate

5.3.1 Unit cost revised

The unit costs for major works were revised based on the basic data such as labor wage, material and equipment cost. These figures were obtained with a little difference from unit costs estimated in the master plan stage. The unit costs revised are indicated in Table 20.

5.3.2 Construction cost for priority project

The construction cost for the priority project was estimated based on the preliminary design and construction plan. The basic assumptions and conditions adopted for the cost estimate are basically the same as that of master plan stage as follows:

- a) price level --- the end of June 1990
- b) official exchange rate --- US\$ 1.0 = Cr\$ 60 = ¥ 150
- c) currency of cost estimate --- foreign and local currency
- d) labor wage, materials and equipment cost
- e) constitution of capital cost

The construction costs for the priority projects in the financial

basis were estimated for the sediment run-off and flood disaster prevention works. The summary of financial cost for the sediment run-off disaster prevention works was estimated at US\$ 25.7 million as presented in Table 21. The direct and indirect costs were estimated at US\$ 17.0 million and US\$ 8.7 million, respectively.

The financial cost for the flood disaster prevention works of the Moji river was estimated at US\$ 11.4 million as shown in Table 22. The direct and indirect costs were estimated at US\$ 7.4 million and US\$ 4.0 million, respectively. The financial cost for the priority projects is tabulated in Table 22 altogether.

Total construction cost for the sediment run-off and flood disaster prevention works, therefore, was estimated to amount to US\$ 37.1 million; direct cost of US\$ 24.4 million and indirect cost of US\$ 12.7 million.

Construction Cost for Priority Project

(Unit : million US\$)

Item	Sediment Disaster			Flood Disaster Prevention Works Moji River		
	F/C	L/C	TOTAL	F/C	L/C	TOTAL
I Preparatory Work (5-15% of II)	1.0	1.2	2.2	0.2	0.1	0.3
II Construction Cost	7.0	7.8	14.8	4.0	3.1	7.1
III Compensation Cost		0.1	0.1		0.2	0.2
IV Administration Cost (5% of I + II)		0.9	0.9		0.4	0.4
V Engineering Service (10% of I + II)	1.4	0.3	1.7	0.6	0.1	0.7
VI Physical Contingency (15% of I+II+III+IV+V)	1.4	1.5	2.9	0.7	0.6	1.3
VII Price Contingency (F/C 3%, L/C 3%)	1.5	1.6	3.1	0.8	0.6	1.4
Total	12.3	13.4	25.7	6.3	5.1	11.4

(Unit : million US\$)

Works	Construction Cost		
	Direct	Indirect	Total
(1) Sediment run-off disaster prevention works	17.0	8.7	25.7
Basin 2	6.0	3.0	9.0
" 3	2.7	1.3	4.0
" 7	2.7	1.4	4.1
" 8	1.1	0.8	1.9
" 10	0.3	0.1	0.4
" 11	2.2	1.1	3.3
" 12	2.0	1.0	3.0
(2) Flood disaster prevention works	7.4	4.0	11.4
Total	24.4	12.7	37.1

5.4 Project Economic Evaluation

5.4.1 Economic cost

The constitution and concept of the economic cost for the priority project was assumed to be the same as applied in the master plan. Hence, the financial cost was converted into the economic costs by adjustment based on the conditions and assumptions.

The economic cost for the sediment run-off disaster prevention works was estimated at US\$ 20.0 million comprising US\$ 15.1 million for direct cost, US\$ 0.02 million for compensation cost, US\$ 0.8 million for administration cost, US\$ 1.5 million for engineering services and US\$ 2.6 million for physical contingency.

The economic cost for the flood disaster prevention works in the Moji river basin was estimated at US\$ 9.0 million comprising US\$ 6.8 million for direct cost, US\$ 0.06 million for compensation cost, US\$ 0.3 million for administration cost, US\$ 0.7 million for engineering services, and US\$ 1.2 million for physical contingency.

Operation and maintenance(O&M) costs are incurred annually during the project life after completion of construction. The rate of 1.0 % of the construction cost was assumed to be O&M cost for the sediment run-off disaster prevention works and 0.5 % of that for the flood disaster prevention works. From the above, O & M costs for the sediment run-off and flood disaster prevention works were estimated at US\$ 0.15 million and US\$ 0.03 million annually.

The economic cost of the priority project is summarised below.

Economic Cost of Priority Project

(Unit: million US\$)

Works	Economic Cost		
	Direct	Indirect	Total
(1) Sediment run-off disaster prevention works	15.1	4.9	20.0
Basin 2	5.4	1.7	7.1
" 3	2.3	0.8	3.1
" 7	2.4	0.8	3.2
" 8	1.1	0.3	1.4
" 10	0.2	0.1	0.3
" 11	1.9	0.6	2.5
" 12	1.8	0.6	2.4
(2) Flood disaster prevention works	6.8	2.2	9.0
Total	21.9	7.1	29.0

5.4.2 Economic benefit

The economic benefits were estimated as the reduction in damages or losses to damageable properties, which will be brought about by implementation of the designed disaster prevention works. With the design scale of about a 25-year return period for the sediment run-off disaster prevention works for the proposed project selected among the master plan stage, the benefits were considered to be commensurate with the reducible amount of annual mean sediment run-off damages corresponding to the design scale.

Meanwhile, the benefit of the flood protection works of the Moji river basin consisting of channel excavation and flood dike construction with the design scale of 10-year return period was estimated on the basis of the effect of reduction in annual mean flood damages to assets and properties in and around the flood protection areas. In addition, the benefit was also estimated on the basis of conceivable socio-economic projections up to the year 2020 in the study area.

(1) Sediment run-off damages

Most of the target properties which would be vulnerable to the sediment run-off disaster were identified as the industrial establishments located in the foot of Serra do Mar. Large scale petrochemical refinery establishments, in particular, are the most serious targets, followed by the substation facilities and state highway.

Taking into account the identification of damageable properties above, the sediment run-off damage was estimated for each establishment. Damageable properties of respective industrial establishments were estimated on the basis of depreciable assets and inventory stocks, which were basically valuated from the sector-wise asset holdings in the state, and value of production of each establishment, adjusted by the price index. Damage rates to properties was assumed to be 50% for buildings, equipment and installations, and 80% for moveables, vehicles and inventory stocks.

Probable sediment run-off damages and annual damages were estimated for 7 Sabo subbasins of the selected priority project under the present conditions below.

Probable Sediment Run-off Damages and Annual Damages

					(Unit: US\$ million)
Sabo Subbasin	Return Period				Annual Damage (*)
	5	25	50	100	
2	1.2	6.0	7.0	7.7	0.7
3	0.3	4.6	6.2	8.1	0.4
7	1.9	3.6	4.6	6.3	0.6
8	0.7	0.8	1.1	1.4	0.2
10	0.1	0.6	1.4	1.9	0.1
11	1.4	2.2	2.7	3.1	0.4
12	1.0	3.0	8.6	11.4	0.4

Note: (*) Annual damage with the design scale of approximately 25-year return period.

1 US\$ = 60 Cr\$

(2) Flood Damage

Damageable properties in the flood protection area of the Moji river basin were identified from the topographic maps, aerial photographs and field investigation, by using a mesh survey with a grid of 500m interval squares. The potential flood damage was then estimated as the product of three(3) components: number of properties by type, unit value of each property and damage rate corresponding to the inundation depth.

In the flood protection area of around 8.0 km² in Moji river basin, the following damageable properties were identified: 250 residences, 10 small scale commerce and services shops, and nine(9) major industrial establishments.

Probable flood damages and annual damages were estimated for the Moji river basin as a reduction in damages and losses with river improvement works designed for a 10-year return period and without the project, as summarized below.

Probable Flood Damages and Annual Damages

							(Unit: US\$ million)
Basin	Return Period						Annual Damage
	2	5	10	25	50	100	
Moji	0.9	1.5	2.0	2.1	2.4	2.5	1.0

Note: Annual damage with the design scale of 10-year return period.

1 US\$ = 60 Cr\$

5.4.3 Economic evaluation

An economic evaluation was carried out to ascertain the economic viability of the proposed projects by comparing the economic costs and benefits. The Economic Internal Rate of Return (EIRR) was applied as a criterion for economic evaluation.

Based on the cost stream disbursed in accordance with the construction schedule, and the benefit flow to be accrued from the proposed project, the EIRR was separately calculated for the sediment run-off disaster prevention works and the Moji river improvement works.

Overall economic evaluation of the Sabo works, consisting of 7 Sabo sub-basins, showed an EIRR of 18.2%. Of the above, sub-basin No.7, 10, 11 and 12 were analyzed to exhibit quite high economic return of more than 20%. On the other hand, the Moji river improvement works showed an EIRR of 11.1%.

The economic analysis of the priority project is summarized below.

Economic Evaluation of Proposed Projects

Works/Sabo Sub-basin	EIRR (%)
<u>Sabo Works</u>	
2	13.3
3	17.8
7	23.5
8	16.8
10	30.1
11	21.2
12	22.3
Total	18.2
<u>River Improvement Works</u>	11.1

5.5 Environmental Impact Assessment

The checklist method was applied as the basic tool for identification of impacts which may be caused by the selected priority projects.

The four(4) effects, such as state park, soil erosion, water quality deterioration and damages on forest are expected to be mainly caused during the construction of stage of the priority projects.

The environmental effects caused by the priority projects are considered mainly during the construction stage. However, those magnitudes are not expected so serious, it is considered that the priority projects are acceptable through the viewpoint of the environment.

The environmental effects of the priority projects will be generally limited to the construction stage. However, the magnitude are expected to be small, because the impacts are tentative and effective countermeasures will be taken during construction of the projects.

5.6 Project justification

Based upon the results of the economic evaluation above, the

proposed projects for the sediment run-off prevention works with a design scale of an about 25-year return period could be justified. Moreover, taking into account unmeasurable social impacts and intangible damage which could be caused by sediment run-off disasters, these proposed projects were judged to be highly viable for implementation.

With regard to the proposed project for flood protection works in the Moji river basin, major industrial establishments are at high risk of repeated frequent inundation by overflowing from the Moji river and its tributaries. If future land use in the Moji river basin is taken into consideration, the probable flood damage will be significantly higher than that of the present projection. If the above situation and economic evaluation are taken into account, the flood protection works of the Moji river basin will be seen to be as highly justified as the proposed project with a design scale of a 10-year return period.

VI. RECOMMENDATION

1. The proposed priority project for the sediment run-off and flood disaster prevention works is strongly recommended to be implemented at the earliest possible time because of eminent social request from high potential of disaster, as shown that the project is technically feasible and economically viable with high economic return.

2. It is well known that the forest restoration plan is very important to protect industrial establishments and inhabitants from sediment run-off and flood disasters. Therefore, basic study on the relationship between vegetation changes and air pollution, and monitoring on the aeroplantation should be carried out in continuous and effective methods as applied presently.

In considering uncertainty and difficulty in predicting accurate time and location of occurrence for the sediment run-off disasters, the present civil defense plan and forest restoration program are also strongly requested to be continued as effective countermeasures which are complementary to the proposed priority project in order to restore forest in Serra do Mar.

3. Prior to the detailed design and during the construction, it is also recommended that geotechnical investigations for bearing capacity of foundation, cutting slope stability and bank materials should be carried out because of complex geological conditions in the project area of the priority project.

4. Other projects in the Master plan especially diversion tunnel works including open channel through the marsh area, which were not selected as the priority project, could seem to cause relatively serious impact on mangrove and its neighboring environment. From the above, detailed environmental impact assessment should be undertaken before the project is implemented.

TABLES

TABLE 1 LIST OF MEMBERS OF THE COORDINATING BODY AND THE
COUNTERPART AGENCY

Member	Agency
<u>(1) Coordinating Body</u>	
(General) - Ana Lúcia Segamarchi	SMA
- Célia Castello	CETESB
- Marcia Jungmann Cardoso	SMA
- Célia Albuquerque	CETESB
(Technical) - Roque Monteleone Neto	SMA
- Sussumu Niyama	IPT
<u>(2) Counterpart Agency</u>	
- Sussumu Niyama	IPT
- Celso Carvalho dos Santos	
- Marco Antonio Palermo	DAEE
- Dorcas Florêncio Domingues	
- Paulo Tetuia Hasegawa	CETESB
- Sergio Luiz Pompéia	
- Mizue Kirizawa	IBt
- Marcia Inês M. S. Lopes	

TABLE 2 LIST OF MEMBERS OF THE ADVISORY COMMITTEE
AND JICA COORDINATOR

Name	Position and Agency
<u>(1) Advisory Committee</u>	
- Mr. H. Kobayashi (Chairman)	Senior Officer for Engineering Affairs, Slope Conservation Division, Sediment Control Department, River Bureau, Ministry of Construction, Japan
- Mr. H. Ohno	Senior Officer of River Division, Kinki Regional Construction Bureau, Ministry of Construction, Japan
- Mr. K. Okuda	Deputy Director of River Planning Division, Chubu Regional Construction Bureau, Ministry of Construction, Japan
<u>(2) JICA Coordinator</u>	
- Mr. H. Takama	Japan International Cooperation Agency (JICA Tokyo)
- Mr. K. Noritake	Japan International Cooperation Agency (JICA Tokyo)
- Mr. S. Murata	Japan International Cooperation Agency (JICA Tokyo)
- Mr. Y. Hongo	Japan International Cooperation Agency (JICA Brazilia)
- Mr. M. Habu	Japan International Cooperation Agency (JICA São Paulo)
- Mr. H. Sasaki	Japan International Cooperation Agency (JICA São Paulo)

TABLE 3 LIST OF MEMBERS OF THE STUDY TEAM

Name	Position and Assignment
M. Ooishi	Team Leader
Y. Tomida	Co-Leader/ Sediment runoff Disaster Prevention
T. Nobe	Flood Disaster Prevention
N. Jituhiro	Sediment Hydraulics
Y. Kato	Hydrology
T. Shibatani	Topography, Geology
K. Narita	Vegetation, Soil
K. Ishizuka	Topographic Survey
Y. Shimano	Construction Plan and Design
M. Watanuki	Socio-economy, Disaster Investigation
Y. Iwai	Environment

TABLE 4 POPULATION GROWTH AND LABOR FORCE

Item	Population			Average Annual Growth Rate (%)			
	1960	1970	1980	1990(87)	'60-'70	'70-'80	'80-90(87)
(1) BRAZIL							
1. Population	70,070,457	93,139,037	119,002,706	150,367,841	2.89	2.48	2.37
2. Male	35,065,457	46,331,343	59,123,361	74,992,111	2.83	2.47	2.41
3. Female	35,015,000	46,807,694	59,879,345	75,375,730	2.95	2.49	2.33
4. Urban	31,303,034	52,084,934	80,436,409	112,743,732	5.22	4.44	3.43
5. Rural	38,767,423	41,054,053	38,566,297	37,624,109	0.57	-0.63	-0.25
6. Economically Active	48,740,564	65,683,745	87,577,224	(104,311,844)	3.03	2.93	2.51
7. Labor Force	22,750,100	29,557,224	43,235,712	(59,542,958)	2.65	3.88	4.68
8. Labor Force Participation(%)	46.7	45.0	49.3	57.1	-0.37	0.92	2.12
(2) Sao Paulo							
1. Population	12,809,231	17,771,948	25,040,772	(31,124,350)	3.33	3.49	3.16
2. Male	6,480,421	8,931,380	12,519,890	(15,416,521)	3.26	3.49	3.02
3. Female	6,328,810	8,840,568	12,520,882	(15,707,829)	3.40	3.54	3.29
4. Urban	8,019,743	14,276,239	22,196,378	(28,202,067)	5.94	4.51	3.48
5. Rural	4,789,488	3,495,709	2,844,334	(2,922,283)	-3.20	-2.08	0.27
6. Economically Active	9,308,538	13,334,701	19,327,707	(24,231,757)	3.66	3.78	3.28
7. Labor Force	4,517,600	6,372,842	10,411,726	(14,249,629)	3.50	5.03	4.58
8. Labor Force Participation(%)	48.5	47.8	53.9	58.8	-0.15	1.21	1.25
(3) Cubatao							
1. Population	25,166	51,009	79,162	105,547	7.32	4.49	2.92
2. Male	-	27,342	43,208	58,950	-	4.68	3.16
3. Female	-	23,667	35,954	46,597	-	4.27	2.63
4. Urban	-	37,255	78,569	105,547	-	7.75	3.00
5. Rural	-	13,754	593	0	-	-36.94	-
6. Economically Active	-	35,598	59,177	(76,571)	-	5.21	3.75
7. Labor Force	-	15,822	31,576	-	-	7.15	-
8. Labor Force Participation(%)	-	44.5	53.4	-	-	1.86	-

Source : Anuario Estatístico do Brasil 1989: IBGE
 Estatísticas Históricas do Brasil 1988: IBGE
 Anuario Estatístico do Estado de São Paulo 1988: IBGE
 Boletim Informativo de Cubatao: P.M.C
 Secretaria de Ciência, Tecnologia e Desenvolvimento Econômico

Remark : *1 Quoted in 1990 are projected population.
 *2 Figures in parentheses are projected data in 1987.
 *3 Economically active population is defined as persons aged 10 years and over.
 *4 (71)/(6)

TABLE 5 GROSS DOMESTIC PRODUCT

Year	Gross domestic Product				Gross Domestic Product per Capita			
	Current Price (Cr\$ 1,000)	Constant Price at 1980(Cr\$1,000)	Annual Growth Rate (%)	Current Price (US\$ million)	Current Price (Cr\$)	Constant Price at 1980(Cr\$)	Annual Growth Rate (%)	Current Price (US\$)
1970	194	5,419	-	34,034	0.002	0.057	-	355.18
1971	258	6,037	11.3	39,529	0.003	0.061	8.7	402.43
1972	347	6,754	11.9	45,704	0.003	0.067	9.3	454.21
1973	512	7,698	14.0	55,329	0.005	0.074	11.3	536.91
1974	745	8,326	8.2	66,403	0.007	0.079	5.7	629.32
1975	1,050	8,756	5.2	76,219	0.01	0.081	2.7	705.52
1976	1,634	9,654	10.3	88,896	0.01	0.087	7.6	803.78
1977	2,493	10,130	4.9	99,342	0.02	0.089	2.5	877.53
1978	3,617	10,634	5.0	112,205	0.03	0.092	2.5	968.46
1979	5,961	11,352	6.8	133,338	0.05	0.096	4.3	1,124.71
1980	12,402	12,402	9.2	165,264	0.10	0.102	6.8	1,362.60
1981	24,654	11,859	-4.4	174,334	0.20	0.096	-6.6	1,405.15
1982	51,025	11,939	0.7	186,311	0.40	0.094	-1.6	1,468.35
1983	118,927	11,531	-3.4	185,737	0.92	0.089	-5.6	1,431.32
1984	393,647	12,111	5.0	203,505	2.97	0.091	2.8	1,534.05
1985	1,413,312	13,111	8.3	228,137	10.43	0.097	6.0	1,682.87
1986	3,708,949	14,099	7.5	250,123	26.78	0.102	5.3	1,806.03
1987	11,899,911	14,611	3.6	268,663	84.13	0.103	1.5	1,899.32
1988	91,952,490	14,613	0.0	279,492	636.67	0.101	-2.0	1,935.16
1989*	1,366,421,000	15,139	3.6	303,452	9,270.00	0.103	1.5	2,058.64

Source: Anuario Estatístico do Brasil, 1989 : IBGE

Relatório, 1989: Banco Central do Brasil

Remarks: * Provisional estimate by IBGE

TABLE 6 NUMBER OF MANUFACTURING ESTABLISHMENTS
AND PRODUCTION VALUE

(Unit: Cr\$)

Type of Industrial Sub-sector	Sao Paulo						Cubatão						Share of Cubatão to Sao Paulo (%)
	1975			1980			1975			1980			
	Nos.	Amount	Nos.	Amount	Nos.	Amount	Nos.	Amount	Nos.	Amount			
Mining	778	930	871	7,519	8	155	4	59	16.7	0.8			
Non-metal products	6,823	14,297	8,147	158,693	8	206	7	1,832	1.4	1.1			
Metallurgy	6,433	56,075	6,251	679,102	5	4,222	7	91,085	7.5	13.4			
Machinery	4,824	43,534	5,516	497,404	10	327	18	6,270	0.8	1.3			
Electric & communication products	1,752	29,326	2,110	331,434	1	-	-	-	-	-			
Vehicles	1,794	57,473	1,504	563,288	1	-	-	-	-	-			
Timber	2,281	3,444	1,860	36,427	1	-	1	-	-	-			
Furniture	3,540	6,405	3,081	65,579	1	-	-	-	-	-			
Paper	821	11,249	892	145,099	1	-	1	-	-	-			
Rubber	495	10,423	514	112,415	1	-	-	-	-	-			
Leather	347	1,078	357	13,145	1	-	-	-	-	-			
Chemistry	1,536	65,218	1,553	906,593	42	10,175	44	191,270	15.6	21.1			
Medicine	237	7,894	222	68,715	-	-	-	-	-	-			
Soap & Perfume	328	5,231	309	53,735	-	-	-	-	-	-			
Plastic products	1,412	8,836	1,721	117,695	-	-	-	-	-	-			
Textile	3,458	29,034	3,194	320,038	2	2	-	-	-	-			
Clothing	5,425	13,855	6,747	172,228	-	-	2	-	-	-			
Food products	11,038	49,122	10,540	533,039	23	13	25	133	-	-			
Beverage	646	3,875	575	34,839	-	-	-	-	-	-			
Tobacco	8	1,389	6	8,668	-	-	-	-	-	-			
Printing	2,732	8,660	3,263	77,427	3	-	2	-	-	-			
Others	6,117	11,788	7,066	155,941	24	525	26	7,503	4.5	4.8			
Total	60,378	439,138	62,426	5,059,027	131	15,625	126	298,152	3.6	5.9			

Source: Censo Industrial, 1975: IBGE
Censo Industrial, 1980: IBGE

TABLE 7 ESTIMATED PROBABLE DISCHARGES

PRESENT CHANNEL CONDITION						
Return Period (Year)	2	5	10	25	50	100
CUBATAO RIVER SYSTEM (Feb.24.1971 Flood Type, 2DAY-Rainfall=301.8mm)						
Probable Rainfall (mm)	206	282	331	394	441	488
Scale factor	0.683	0.934	1.100	1.309	1.465	1.617
of total rainfall						
Probable Discharges at Major Points (m3/s)						
-River Mouth (29)	916	1301	1555	1876	2121	2366
-After Pereque (28)	915	1302	1552	1877	2128	2376
-Pereque River (27)	212	321	382	460	519	581
-Before Pereque (20)	724	1033	1231	1489	1690	1890
-	(19)	748	1056	1530	1743	1956
-Anchieta Bridge(17)	586	878	1070	1330	1534	1739
-Imigrantes Brq.(14)	537	828	1022	1289	1498	1708
-After Piloes (10)	570	868	1062	1320	1521	1725
-Piloes River (9)	173	282	356	455	532	609
-Before Piloes (4)	397	586	706	865	1018	1172

IMPROVED CONDITION OF EXISTING CHANNEL						
Return Period (Year)	2	5	10	25	50	100
CUBATAO RIVER SYSTEM (Feb.24.1971 Flood Type, 2DAY-Rainfall=301.8mm)						
Probable Rainfall (mm)	206	282	331	394	441	488
Scale factor	0.683	0.934	1.100	1.309	1.465	1.617
of total rainfall						
Probable Discharges at Major Points (m3/s)						
-River Mouth (29)	920	1346	1617	1970	2242	2515
-After Pereque (28)	915	1326	1589	1933	2199	2467
-Pereque River (27)	209	324	395	488	558	627
-Before Pereque (20)	724	1058	1270	1549	1767	1988
-	(19)	751	1069	1278	1556	1774
-Anchieta Bridge(17)	589	891	1090	1356	1565	1776
-Imigrantes Brq.(14)	537	827	1022	1279	1482	1687
-After Piloes (10)	570	868	1062	1320	1521	1725
-Piloes River (9)	173	282	356	455	532	609
-Before Piloes (4)	397	586	706	865	1018	1172

MOJI RIVER						
(Jan.22.1985 Flood Type, 2DAY-Rainfall=286.5mm)						
Probable Rainfall (mm)	182	250	295	351	393	435
Scale factor	0.639	0.873	1.030	1.229	1.375	1.568
of total Rainfall						
Probable Discharges at Major Points (m3/s)						
-River Mouth (49)	213	345	438	551	658	706
-After Piagag. (48)	273	443	578	759	897	949
-Piaguera R. (44)	79	128	168	227	274	292
-Before Piagag. (41)	228	378	503	676	810	864
-After Indio R. (38)	231	377	487	632	740	778
-Indio River (34)	28	44	58	79	95	101
-Before Indio (33)	218	359	466	609	716	755
-Intake Weir (30)	240	421	570	788	955	1040

IMPROVED CONDITION OF EXISTING CHANNEL						
Return Period (Year)	2	5	10	25	50	100
CUBATAO RIVER SYSTEM (Feb.24.1971 Flood Type, 2DAY-Rainfall=301.8mm)						
Probable Rainfall (mm)	206	282	331	394	441	488
Scale factor	0.683	0.934	1.100	1.309	1.465	1.617
of total rainfall						
Probable Discharges at Major Points (m3/s)						
-River Mouth (29)	920	1346	1617	1970	2242	2515
-After Pereque (28)	915	1326	1589	1933	2199	2467
-Pereque River (27)	209	324	395	488	558	627
-Before Pereque (20)	724	1058	1270	1549	1767	1988
-	(19)	751	1069	1278	1556	1774
-Anchieta Bridge(17)	589	891	1090	1356	1565	1776
-Imigrantes Brq.(14)	537	827	1022	1279	1482	1687
-After Piloes (10)	570	868	1062	1320	1521	1725
-Piloes River (9)	173	282	356	455	532	609
-Before Piloes (4)	397	586	706	865	1018	1172
MOJI RIVER (Jan.22.1985 Flood Type, 2DAY-Rainfall=286.5mm)						
Probable Rainfall (mm)	182	250	295	351	393	435
Scale factor	0.639	0.873	1.030	1.229	1.375	1.568
of total Rainfall						
Probable Discharges at Major Points (m3/s)						
-River Mouth (49)	213	345	438	551	658	706
-After Piagag. (48)	273	443	578	759	897	949
-Piaguera R. (44)	79	128	168	227	274	292
-Before Piagag. (41)	228	378	503	676	810	864
-After Indio R. (38)	231	377	487	632	740	778
-Indio River (34)	28	44	58	79	95	101
-Before Indio (33)	218	359	466	609	716	755
-Intake Weir (30)	240	421	570	788	965	1040

TABLE 8 PAST MAJOR SLOPE FAILURES

Area: Unit (10E-2 Km2)

Division		1962		1971		1976		1980		1985		1988		1962-1989	
Name		Nos.	Area	Nos.	Area	Nos.	Area	Nos.	Area	Nos.	Area	Nos.	Area	Nos.	Area
MOJI RIVER BASIN															
MR-1	3	0.98		100 (1)	34.07	77 (6)	21.25	45 (9)	12.21	302 (29)	61.05	26 (2)	5.13	664	161.7
MR-2	7	1.1		7 (1)	3.79	43 (3)	12.82	16 (4)	3.42	57 (9)	12.45	10 (2)	1.75	155	39.34
MR-3	2	0.49		13 (0)	2.67	88 (1)	19.9	31 (7)	10.5	136 (10)	27.23	40 (10)	5.86	342	73.06
MR-4	0	0		0	0	2 (0)	0.73	0	0	0	0	0	0	2	0.73
MR-5	0	0		0	0	0	0	0	0	8 (0)	1.22	0	0	18	1.22
ML-1	9	2.56		38 (0)	16.85	7 (1)	18.8	10 (8)	8.42	118 (16)	35.29	12 (8)	2.56	252	109.74
Sub-Total	21	5.13		158 (2)	57.38	217 (11)	73.5	102 (28)	34.55	621 (64)	137.24	88 (22)	15.30	1433	385.79
CUBATAO RIVER BASIN															
CR-1	4	0.2		20 (0)	3.33	16 (3)	2.92	0	0	1 (0)	0.73	0	0	43	5.86
CR-2	0	0		12 (0)	1.88	10 (0)	1.88	2 (0)	1.56	1 (0)	0.73	2 (0)	1.59	26	3.79
CR-3	0	0		0	0	0	0	0	0	4 (0)	2.13	0	0	4	2.56
CL-1	1	0.1		4 (0)	0.38	0	0	8 (0)	1.46	3 (0)	0.79	2 (0)	1.59	21	2.81
CL-2	3	0.2		1 (0)	0.1	1 (0)	0.16	5 (0)	1.04	6 (0)	2.13	11 (1)	3.79	32	8.18
CL-3	5	0.33		3 (0)	0.31	2 (0)	0.16	4 (0)	3.25	16 (1)	3.05	21 (1)	4.5	64	8.01
CL-4	0	0		0	0	0	0	0	0	3 (0)	1.59	24 (0)	3.3	45	8.15
CL-5	0	0		0	0	0	0	2 (0)	1.71	26 (0)	3.42	14 (1)	1.71	68	11.63
CL-6	0	0		4 (0)	1.47	1 (0)	0.73	1 (0)	1.22	44 (1)	7.2	14 (1)	2.32	114	23.05
CL-7	6	1.59		16 (0)	5.74	56 (1)	15.26	63 (10)	13.8	172 (15)	34.19	39 (4)	5.37	446	96.23
CL-8	0	0		0	0	0	0	0	0	6 (0)	1.10	0	0	8	1.47
Sub-Total	19	2.42		60 (0)	13.21	86 (4)	21.11	85 (10)	24.04	282 (17)	55.96	127 (8)	24.17	871	171.74
Total	40	7.55		218 (2)	70.59	303 (15)	94.61	187 (38)	58.59	903 (81)	193.2	215 (30)	39.47	2304	557.53

Note: () Shows number of slope failures that occurred again at the same places compared with previous aerial photographs interpretation results.

Note: () Shows number of slope failures that occurred again at the same places compared with previous aerial photographs interpretation results.

TABLE 9 SEDIMENT YIELD OF SABO SUB-BASIN

Number of Sabo Sub-Basin	Catchment Area (km ²)	Sediment Yield of Slope Failures (10 ³ Ja3)				Sediment Yield of Torrent Deposit (10 ³ Ja3)				Potential Sediment Yield			
		1/5	1/25	1/50	1/100	1/5	1/25	1/50	1/100	1/5	1/25	1/50	1/100
1	2.39	66.3	112.9	132.3	151.4	35.1	44.2	46.8	47.2	101.4	157.1	179.1	198.6
2	3.79	105.1	119.1	209.9	210.1	67.6	85.8	91.4	91.8	172.7	264.9	301.3	331.9
3	1.29	35.8	61.0	71.4	81.7	20.6	26.1	27.6	27.7	56.4	87.1	99.0	109.4
4	8.42	121.4	228.7	273.5	317.7	253.0	328.0	353.9	362.7	374.4	556.7	627.4	680.4
5	0.90	13.0	24.4	29.2	34.0	10.9	13.5	14.3	14.5	23.9	37.9	43.5	48.5
6	1.73	24.9	47.0	56.2	65.3	31.1	39.0	41.4	41.7	56.0	86.0	97.6	107.0
7	2.64	38.1	71.7	85.1	99.6	50.5	62.9	66.5	67.0	88.6	134.6	152.2	166.6
8	0.41	4.2	7.8	9.3	10.8	3.5	4.3	4.5	4.5	7.7	12.1	13.8	15.3
9	0.13	1.4	13.9	16.6	19.3	6.3	7.9	8.3	8.4	13.7	21.8	24.9	27.7
10	1.26	12.8	21.0	28.7	33.3	15.0	18.6	19.7	19.8	27.8	42.6	48.4	53.1
11	0.62	6.3	11.8	14.1	16.4	8.4	10.5	11.1	11.1	14.7	22.3	25.2	27.5
12	1.11	11.3	21.1	25.3	29.4	13.2	16.2	17.2	17.4	24.5	37.3	42.5	46.8

TABLE 10 DESIGN SEDIMENT RUN-OFF DISCHARGE

Sabo Sub-basin	Design Sediment Run-off Discharge			
	1/5	1/25	1/50	1/100
1(2.39)	0	0	0	0
2(3.79)	77,600	124,200	142,900	159,400
3(1.29)	56,400	87,100	99,000	109,400
4(8.42)	72,900	119,800	139,900	158,700
5(0.90)	19,100	30,200	34,600	38,700
6(1.73)	38,400	62,100	71,600	80,100
7(2.64)	83,000	130,500	149,800	166,600
8(0.41)	7,500	11,800	13,600	15,200
9(0.17)	13,700	21,800	24,900	27,700
10(1.26)	18,700	29,400	33,700	37,700
11(0.62)	13,000	20,400	23,400	26,100
12(1.11)	24,500	37,300	42,500	46,800

Note ; () means Sabo sub-basin area in km²

TABLE 11 DIMENSION OF STRUCTURAL MEASURES

(Unit: m³)

Sub-basin No.	Sediment Run-off Discharge	Existence Structural Measures			Design Sediment Run-off Discharge	Proposed Structural Measures (Sabo-dam)					
		1st	2nd	3rd		1st	2nd	3rd	4th	5th	6th
		Total	Total	Total		Total	Total	Total	Total	Total	Total
1	155,500	(H=8) 24,800 (H=4) 138,200	(H=10) 44,200	(H=10) 207,200	0	(H=10)* 7,400 (H=7) 124,800	(H=10)* 16,200	(H=10)* 19,300			7,400
2	159,400	70,000 (H=4)			159,400	(H=10) 85,800	(H=10)* 28,500				160,300
3	109,400	82,000			109,400	(H=8) 120,000	(H=10)* 45,000				114,300
4	158,700				158,700	(H=10) 38,100	(H=5)* 2,300				165,000
5	38,700				38,700	(H=10) 35,700	(H=10)* 2,400				40,400
6	80,100				80,100	(H=10) 44,600	(H=10)* 20,300	(H=10)* 35,700	(H=10)* 8,500	(H=10)* 8,500	80,700
7	166,600				166,600	(H=7) 12,000	(H=10)* 3,600				167,200
8	15,200				15,200	(H=10) 21,800	(H=10)* 3,500	(H=10)* 3,300			15,600
9	27,700				27,700	(H=8) 34,000	(H=10)* 4,000				28,700
10	37,700				37,700	(H=10) 20,000	(H=10)* 6,000	(H=10)* 2,000			38,000
11	26,100				26,100	(H=9) 37,800	(H=10)* 5,500	(H=10)* 4,500			28,300
12	46,800				46,800						47,800

Note : * : means control amount

TABLE 12 FINANCIAL COST FOR SEDIMENT DISASTER PREVENTION WORKS

Item	Unit	Quantity	Foreign Currency		Local Currency		Total (1,000US\$)
			Amount		Amount		
			Unit Cost	(1,000US\$)	Unit Cost	(1,000US\$)	
I. Preparatory Works (15% of II)				2,879		3,102	5,980
II. Construction Cost							
II.1 Sabo dam (32 sites)	m3	179,600	95.0	17,062	95.0	17,062	34,124
II.2 Channel works (11 sites)	m2	70,800	15.0	1,062	35.0	2,478	3,540
II.3 Groundsill (2 Nos.)	m3	1,700	90.0	153	90.0	153	306
II.4 Miscellaneous (5% of Total II.1 - II.3)				914		985	1,899
Total of II				19,191		20,678	39,869
III. Compensation Cost							
III.1 Residence	Nos.	12			400	5	5
III.2 Residential Area	m2	960			2.5	2	2
III.3 Non-Residential Area	m2	11,200			0.7	8	8
III.4 Factory Area	m2	132,700			1.3	173	173
Total of III						188	188
IV. Administration Cost (5% of I + II)						2,292	2,292
V. Engineering Service (10% of I + II)				3,668		917	4,585
VI. Physical Contingency (15% of I + II + III + IV + V)				3,861		4,076	7,937
VII. Price Contingency (P/C 3%, L/C 3%)				6,901		7,289	14,190
Total				36,499		38,542	75,041

TABLE 13 SUMMARY OF FINANCIAL COST (EXCLUDING PRICE CONTINGENCY)
FOR SEDIMENT DISASTER PREVENTION WORKS IN EACH BASIN

Unit : 1,000 US\$

Item	Basin 1			Basin 2			Basin 3			Basin 4			Basin 5			Basin 6		
	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL
I Preparatory Work (15% of II)	51	81	132	429	456	885	222	210	462	343	373	717	148	162	311	249	284	533
II Construction Cost	341	542	883	2,860	3,043	5,903	1,479	1,503	3,082	2,289	2,439	4,728	989	1,083	2,072	1,661	1,894	3,555
III Compensation Cost	28	28	56	11	11	22	10	10	20	47	47	94	15	15	30	35	35	70
IV Administration Cost (5% of I + II)	51	51	102	339	339	678	177	177	354	275	275	550	119	119	238	204	204	408
V Engineering Service (10% of I + II)	81	20	102	513	136	649	284	71	354	440	110	549	191	48	238	327	82	409
VI Physical Contingency (15% of I+II+III+IV+V)	71	108	179	575	598	1,173	298	315	613	461	494	955	199	214	413	336	375	710
Total	544	831	1,375	4,407	4,583	8,990	2,282	2,417	4,699	3,533	3,788	7,321	1,527	1,641	3,168	2,573	2,874	5,447

Item	Basin 7			Basin 8			Basin 9			Basin 10			Basin 11			Basin 12		
	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL
I Preparatory Work (15% of II)	387	400	787	129	142	271	201	215	415	81	81	162	306	321	627	325	345	670
II Construction Cost	2,580	2,568	5,148	861	945	1,806	1,338	1,430	2,768	539	539	1,078	2,039	2,138	4,177	2,165	2,304	4,469
III Compensation Cost	9	9	18	4	4	8	1	1	2	0	0	0	13	13	26	15	15	30
IV Administration Cost (5% of I + II)	302	302	604	104	104	208	159	159	318	62	62	124	240	240	480	257	257	514
V Engineering Service (10% of I + II)	483	121	604	166	42	208	255	64	318	99	25	124	384	96	480	411	103	514
VI Physical Contingency (15% of I+II+III+IV+V)	517	525	1,042	173	185	358	269	280	549	108	108	214	409	421	831	435	454	889
Total	3,967	4,025	7,992	1,330	1,422	2,751	2,062	2,149	4,211	827	813	1,640	3,139	3,229	6,368	3,336	3,478	6,814

TABLE 14 FINANCIAL COST FOR FLOOD DISASTER PREVENTION WORKS (1/2)

ALTERNATIVE C-2(2)

Item	Unit	Quantity	Foreign Currency		Local Currency		Total (1,000US\$)
			Amount		Amount		
			Unit Cost (1,000US\$)		Unit Cost (1,000US\$)		
I. Preparatory Works (5% of II)				695		520	1,215
II. Construction Cost							
II.1 Dike	m3	157,000	2.1	330	1.4	220	550
II.2 Excavation	m3	256,000	1.8	461	1.2	307	768
II.3 Dredging	m3	256,000	2.7	691	1.8	461	1,152
II.4 Revetment	m2	6,700	15.0	101	35.0	235	335
II.5 Culvert (11 Nos.)	L.S.	1		384		256	640
II.6 Diversion Weir	L.S.	1		240		160	400
II.7 Overflow Weir	L.S.	1		130		90	220
II.8 Diversion Channel (Cubatao)	L.S.	1		530		850	1,380
II.9 Tunnel (2 Nos.)	m	1,200	7,800	9,360	5,200	6,240	15,600
II.10 Diversion Channel (Sao Vicente)	L.S.	1		340		640	980
II.11 Road Bridge (2 Nos.)	L.S.	1		192		120	312
II.12 Railway Bridge (1 Nos.)	L.S.	1		300		210	510
II.13 Protection Dike	L.S.	1		143		87	230
II.14 Riverbed Protection	L.S.	1		36		24	60
II.15 Miscellaneous (5% of Total II.1 - II.14)				662		495	1,157
Total of II				13,899		10,394	24,293
III. Compensation Cost							
III.1 Residence	Nos.	10			400	4	4
III.2 Factory	L.S.	1				0	0
III.3 Residential Area	m2	800			2.5	2	2
III.4 Non-Residential Area	m2	248,000			0.7	174	174
Total of III						180	180
IV. Administration Cost (5% of I + II)						1,275	1,275
V. Engineering Service (10% of I + II)				2,041		510	2,551
VI. Physical Contingency (15% of I + II + III + IV + V)				2,495		1,932	4,427
VII. Price Contingency (P/C 3%, L/C 3%)				5,242		4,058	9,300
Total				24,372		18,869	43,241

TABLE 14 FINANCIAL COST FOR FLOOD DISASTER PREVENTION WORKS (2/2)

ALTERNATIVE K-2

Item	Unit	Quantity	Foreign Currency		Local Currency		Total (1,000US\$)
			Amount		Amount		
			Unit Cost	(1,000US\$)	Unit Cost	(1,000US\$)	
I. Preparatory Works (5% of II)				378		283	661
II. Construction Cost							
II.1 Dike	m3	250,000	2.1	525	1.4	350	875
II.2 Excavation	m3	846,000	1.8	1,523	1.2	1,015	2,538
II.3 Dredging	m3	584,000	2.7	1,577	1.8	1,051	2,628
II.4 Revetment	m2	24,800	15.0	372	35.0	868	1,240
II.5 Culvert (7 Nos.)	L.S.	1		240		160	400
II.6 Intake Weir (1 No.)	L.S.	1		72		48	120
II.7 Groundsill (4 Nos.)	L.S.	1		120		80	200
II.8 Road Bridge	L.S.	1		1,000		700	1,700
II.9 Railway Bridge	L.S.	1		1,600		1,000	2,600
II.10 Repair of Riprap Dike (4 Nos.)	L.S.	1		174		116	290
II.11 Miscellaneous (5% of Total II.1 - II.10)				360		269	630
Total of II				7,563		5,658	13,221
III. Compensation Cost							
III.1 Residence	Nos.	0			400	0	0
III.2 Factory	L.S.	1				0	0
III.3 Residential Area	m2	0			2.5	0	0
III.4 Non-Residential Area	m2	354,000			0.7	248	248
Total of III						248	248
IV. Administration Cost (5% of I + II)						694	694
V. Engineering Service (10% of I + II)				1,111		278	1,388
VI. Physical Contingency (15% of I + II + III + IV + V)				1,358		1,074	2,432
VII. Price Contingency (F/C 3%, L/C 3%)				2,299		1,801	4,100
Total				12,708		10,035	22,743

TABLE 15 SUMMARY OF FINANCIAL COST (EXCLUDING PRICE CONTINGENCY)
FOR FLOOD DISASTER PREVENTION WORKS

Unit : 1,000 US\$

Item	Alternative C - 1			Alternative C - 2 (1)			Alternative C - 2 (2)			Alternative K - 1			Alternative K - 2		
	P/C	L/C	TOTAL	P/C	L/C	TOTAL	P/C	L/C	TOTAL	P/C	L/C	TOTAL	P/C	L/C	TOTAL
I Preparatory Work (5% of II)	543	399	942	951	699	1,650	695	520	1,215	450	337	788	378	283	661
II Construction Cost	10,865	7,975	18,840	19,015	13,988	33,003	13,899	10,394	24,293	9,009	6,748	15,757	7,563	5,658	13,221
III Compensation Cost		19,343	19,343		180	180		180	180		698	698		248	248
IV Administration Cost (5% of I + II)		989	989		1,733	1,733		1,275	1,275		827	827		694	694
V Engineering Service (10% of I + II)	1,583	396	1,978	2,772	693	3,465	2,041	510	2,551	1,324	331	1,654	1,111	278	1,388
VI Physical Contingency (15% of I+II+III+IV+V)	1,949	4,365	6,314	3,411	2,594	6,005	2,495	1,932	4,427	1,617	1,341	2,959	1,358	1,074	2,432
Total	14,939	33,467	48,406	26,149	19,887	46,036	19,130	14,811	33,941	12,400	10,283	22,683	10,409	8,235	18,644

TABLE 16 FINANCIAL COST FOR MASTER PLAN

Unit: 1,000 US\$

Item	Sediment Disaster Prevention Works			Flood Disaster Prevention Works			(Sediment-Flood) Disaster Prevention Works								
	Cubatao			Koji			(Cubatao + Koji)								
	P/C	L/C	TOTAL	P/C	L/C	TOTAL	P/C	L/C	TOTAL	P/C	L/C	TOTAL			
I Preparatory Work (5-15% of II)	2,878	3,102	5,980	695	520	1,215	378	283	661	1,073	803	1,876	3,952	3,994	7,856
III Construction Cost	19,131	20,678	39,809	13,899	10,394	24,293	7,563	5,658	13,221	21,462	16,052	37,514	40,653	36,730	77,383
III Compensation Cost		188	188		180	180		248	248		428	428		616	616
IV Administration Cost (5% of I + II)		2,292	2,292		1,275	1,275		694	694		1,969	1,969		4,262	4,262
V Engineering Service (10% of I + II)	3,668	917	4,585	2,041	510	2,551	1,111	278	1,388	3,151	788	3,939	5,819	1,705	8,524
VI Physical Contingency (15% of I+II+III+IV+V)	3,861	4,077	7,937	2,435	1,932	4,427	1,358	1,074	2,432	3,853	3,006	6,859	7,714	7,083	14,796
VII Price Contingency (P/C 3%, L/C 3%)	5,901	7,289	14,190	5,242	4,058	9,300	2,299	1,891	4,100	7,541	5,859	13,400	14,442	13,148	27,580
Total	36,499	38,543	75,042	24,372	18,869	43,241	12,708	10,036	22,744	37,880	28,995	65,985	73,579	67,448	141,027

TABLE 17 LATE SECONDARY AND CLIMAX SPECIES FOR THE REPLANTATION

SPECIE	FAMILY	SPECIE	FAMILY
Alchornea triplinervia	EUPHORBIACEAE	Posoqueria acutifolia	RUBIACEAE
Aspidosperma olivaceum	APOCYNACEAE	Pouteria torta	SAPOTACEAE
Cabralia canjerana	MELIACEAE	Prunus sellowii	ROSACEAE
Cariniana estrellensis	LEGUMINOSAE	Pseudobombax grandiflorum	BOMBACEAE
Chrysophyllum flexuosum	SAPOTACEAE	Roupala brasiliensis	PROTEACEAE
Chrysophyllum viride	SAPOTACEAE	Schizolobium parahyba	LEG.-CAESALPINIOIDEAE
Cordia alliodora	BORAGINACEAE	Sclerolobium denudatum	LEG.-CAESALPINIOIDEAE
Coussarea nodosa	RUBIACEAE	Sigaruna brasiliensis	MONIMIACEAE
Cryptocarya moschata	LURACEAE	Sloanea guianense	ELAEAGNACEAE
Cupania obtusifolia	SAPINDACEAE	Sloanea monosperma	ELAEAGNACEAE
Didymopanax calvum	ARALIACEAE	Swartzia langsdorffii	LEG.-FABOIDEAE
Drymis brasiliensis	WINTERACEAE	Syagrus pseudococcus	PALMAE
Eriotheca pentaphylla	BOMBACEAE	Tabebuia alba	BIGNONIACEAE
Eugenia brasiliensis	MYRTACEAE	Tabebuia heptaphylla	BIGNONIACEAE
Eugenia cerasifolia	MYRTACEAE	Tapirira guianensis	ANACARDIACEAE
Eugenia involucrata	MYRTACEAE	Virola obovatifolia	MYRISTICACEAE
Eugenia myrsinifolia	MYRTACEAE	Virola olifera	MYRISTICACEAE
Eugenia pyriformis	MYRTACEAE	Vochysia magnifica	VOCHYSIACEAE
Euplasis cantabrigiae	PROTEACEAE	Vochysia sellowii	VOCHYSIACEAE
Euterpe edulis	PALMAE	Xylopia brasiliensis	ANNONACEAE
Guatteria australis	ANNONACEAE		
Guatteria dusenii	ANNONACEAE		
Guatteria polycarpa	ANNONACEAE		
Hieronyma alchorneoides	EUPHORBIACEAE		
Hyrtella hebecarpa	CHRYSOBALANACEAE		
Ilex paraguariensis	AQUIFOLIACEAE		
Ilex theezans	AQUIFOLIACEAE		
Inga sessilis	LEG.-MIMOSIOIDEAE		
Licania kunthiana	CHRYSOBALANACEAE		
Lonchocarpus denudatus	LEG.-FABOIDEAE		
Manilkara subsericea	SAPOTACEAE		
Matauba guianensis	SAPINDACEAE		
Matauba junglandifolia	SAPINDACEAE		
Maytenus evonymoides	CELASTRACEAE		
Micropholis cuneata	SAPOTACEAE		
Nectandra puberula	LURACEAE		
Nectandra rigida	LURACEAE		
Ocotea aciphylla	LURACEAE		
Ocotea catharinensis	LURACEAE		
Ocotea elegans	LURACEAE		
Ocotea odorifera	LURACEAE		
Ocotea paranapiacabensis	LURACEAE		
Ocotea paulensis	LURACEAE		
Ocotea porosa	LURACEAE		
Ocotea pulchella	LURACEAE		
Ocotea teleiandra	LURACEAE		
Paivaea langsdorffii	MYRTACEAE		
Pera glabrata	EUPHORBIACEAE		
Persa alba	LURACEAE		
Podocarpus sellowii	PODOCARPACEAE		

TABLE 18 WORK QUANTITIES FOR SEDIMENT RUN-OFF
DISASTER PREVENTION WORKS

Unit : m3

Dam No.	Item	Dam	Channel	Groundsill	Total
2-1	V	22,000	(530 m)	1,200	23,200
	Ve	35,200	70,800	15,700	121,700
3-1	V	9,800	(490 m)	200	10,200
	Ve	8,500	31,200	100	39,800
7-1	V	3,600	(250 m)	1,000	4,600
	Ve	10,300	39,400	10,500	60,200
7-3	V	3,800	(0 m)	-	3,800
	Ve	2,400	-	-	2,400
7-4	V	2,000	(0 m)	-	2,000
	Ve	1,200	-	-	1,200
Sub-total	V	9,400	(250 m)	1,000	10,400
	Ve	13,900	39,400	10,500	63,800
8-1	V	3,700	(440 m)	400	4,100
	Ve	6,400	23,200	4,000	33,600
10-1	V	1,100	(0 m)	-	1,100
	Ve	600	-	-	600
11-1	V	7,300	(410 m)	1,100	8,400
	Ve	4,400	12,300	15,700	32,400
12-1	V	4,900	(750 m)	900	5,800
	Ve	3,900	64,000	19,000	86,900
Total	V	58,200	(2,870 m)	4,800	63,000
	Ve	72,900	240,900	65,000	378,800

Note : V ; volume of structure

Ve ; excavation volume

TABLE 19 WORK QUANTITIES FOR FLOOD DISASTER
PREVENTION WORKS

	Item	Unit	Quantity
(1)	Dike (L=9.3km)		
	1) Gravel metalling	m3	6,600
	2) Excavation	m3	329,000
	3) Dredging	m3	141,000
	4) Embankment	m3	255,000
	5) Sod Facing	m2	111,600
(2)	Revetment (L=1.45km)		
	1) Wet stone masonry	m2	9,800
	2) Concrete block	m3	170
	3) Berm concrete	m3	120
	4) Gabion	m3	2,900
(3)	Culvert (6 Sites)		
	1) Excavation	m3	2,300
	2) Concrete	m3	550
	3) Reinforcement bar	ton	30
	4) Form	m2	960
	5) RC pile	m	136
	6) Gate	ton	8
(4)	Intake Weir (1 Site)		
	1) Excavation	m3	2,000
	2) Concrete	m3	270
	3) Wet stone masonry	m2	460
	4) Concrete block	m3	840
(5)	Parapet wall (1 Site)		
	1) Excavation	m3	680
	2) Concrete	m3	310
	3) Reinforcement bar	ton	25
	4) Form	m2	870
(6)	Road Bridge (1 Site)		
	1) Embankment	m3	5,100
	2) Super structure (Steel)	ton	74
	3) Sub structure (Concrete)	m3	350
	4) Steel pile	m	450
(7)	Railway Bridge (1 Site)		
	1) Embankment	m3	5,240
	2) Ballast	m3	550
	3) Super structure (Steel)	ton	270
	4) Sub structure (Concrete)	m3	440
	5) Steel pile	m	620

TABLE 20 UNIT COST REVISED

Item	Unit	Unit Cost (US\$)		Total
		F/C	L/C	
(For Sediment Control)				
(1) Excavation	m3	1.7	1.8	3.5
(2) Outer Concrete	m3	76.7	83.3	160.1
(3) Inner Concrete	m3	71.3	80.4	151.6
(4) Form	m2	7.7	15.4	23.1
(5) Wetstone Masonry	m2	13.6	23.4	36.9
(6) Concrete Block	m3	60.9	94.6	155.5
(7) Berm Concrete	m3	60.9	94.6	155.5
(8) Gabion	m3	18.4	30.3	48.7
(For Flood Control)				
(9) Gravel Metalling	m3	12.1	18.4	30.4
(10) Excavation	m3	2.1	1.3	3.4
(11) Dredging	m3	2.4	1.6	4.0
(12) Embankment	m3	2.2	1.4	3.6
(13) Sod Facing	m2	0.2	0.6	0.7
(14) Concrete	m3	74.0	81.8	155.8
(15) Reinforcement Bar	ton	642.2	488.2	1130.4
(16) RC Pile	m	12.0	8.0	20.0
(17) Gate	ton	3000.0	2000.0	5000.0
(18) Steel Pile	m	162.0	108.0	270.0
(19) Ballast	m3	16.2	35.7	51.8
(For Compensation)				
(20) Residence	m2		400	400
(21) Residential Area	m2		2.5	2.5
(22) Non-Residential Area	m2		0.7	0.7
(23) Factory Area	m2		1.3	1.3

TABLE 21 SUMMARY OF FINANCIAL COST FOR SEDIMENT DISASTER PREVENTION
WORKS IN EACH BASIN (FOR PRIORITY PROJECT)

Unit : 1,000 US\$

Item	Basin 2			Basin 3			Basin 7			Basin 8		
	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL
I Preparatory Work (15% of II)	368	413	781	160	183	343	168	188	356	74	86	160
II Construction Cost	2,453	2,751	5,204	1,068	1,218	2,286	1,120	1,253	2,373	495	573	1,068
III Compensation Cost		11	11		10	10		9	9		4	4
IV Administration Cost (5% of I + II)		299	299		131	131		136	136		61	61
V Engineering Service (10% of I + II)	479	120	598	210	53	263	218	55	273	98	25	123
VI Physical Contingency (15% of I+II+III+IV+V)	495	539	1,034	216	239	455	226	246	472	100	112	212
VII Price Contingency (F/C 3%,L/C 3%)	527	574	1102	230	255	485	241	262	503	107	120	226
Total	4,322	4,707	9,029	1,884	2,089	3,973	1,973	2,149	4,122	874	981	1,855

Item	Basin 10			Basin 11			Basin 12			Total		
	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	Total
I Preparatory Work (15% of II)	15	17	32	132	150	281	122	141	263	1,039	1,177	2,216
II Construction Cost	102	114	216	878	997	1,875	810	940	1,750	6,926	7,846	14,772
III Compensation Cost		0	0		13	13		15	15		62	ERR
IV Administration Cost (5% of I + II)		12	12		108	108		101	101		849	ERR
V Engineering Service (10% of I + II)	20	5	25	173	43	216	161	40	201	1,359	340	1,699
VI Physical Contingency (15% of I+II+III+IV+V)	21	22	43	177	197	374	164	186	349	1,399	1,541	2,940
VII Price Contingency (F/C 3%,L/C 3%)	22	24	46	189	209	398	175	198	372	1,490	1,642	3,133
Total	180	194	374	1,549	1,717	3,265	1,431	1,620	3,051	12,213	13,457	25,670

TABLE 22 FINANCIAL COST FOR PRIORITY PROJECT

Unit : 1,000 US\$

Item	Sediment Disaster Prevention Works			Flood Disaster Prevention Works Moji River			(Sediment+Flood) Disaster Prevention Works		
	F/C	L/C	TOTAL	F/C	L/C	TOTAL	F/C	L/C	TOTAL
I Preparatory Work (5-15% of II)	1,039	1,177	2,216	198	156	354	1,237	1,333	2,570
II Construction Cost	6,926	7,846	14,772	3,959	3,125	7,084	10,885	10,971	21,856
III Compensation Cost		62	62		180	180		242	242
IV Administration Cost (5% of I + II)		849	849		372	372		1,221	1,221
V Engineering Service (10% of I + II)	1,359	340	1,699	595	149	744	1,954	489	2,443
VI Physical Contingency (15% of I+II+III+IV+V)	1,399	1,541	2,940	713	597	1,310	2,111	2,138	4,250
VII Price Contingency (F/C 3%, L/C 3%)	1,490	1,642	3,133	760	637	1,396	2,250	2,279	4,529
Total	12,213	13,457	25,670	6,224	5,216	11,440	18,437	18,673	37,111

FIGURES








FIG. 1
LOCATION MAP OF MAJOR
INDUSTRIAL ESTABLISHMENTS
IN CUBATÃO

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY











Guide Line Curves of Warning System



Source : Divisão de Operações de Risco (EO) in Cetesb

Action Flow Chart of Civil Defence Plan

Criteria on Changing Stages




Source: Secretariat of Environment (SMA) and CETESB

FIG. 6
GUIDE LINES OF WARNING SYSTEMS
OF CUBATÃO RIVER BASIN

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO

JAPAN INTERNATIONAL COOPERATION AGENCY

FIG. 7
GEOLOGICAL MAP OF THE STUDY AREA



GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY




FIG. 8
GEOLOGICAL PROFILES OF THE
STUDY AREA

GOVERNMENT OF FEDERATIVE
 REPUBLIC OF BRAZIL
 THE STUDY ON THE DISASTER PREVENTION AND
 RESTORATION PROJECT IN SERRA DO MAR,
 CUBATÃO REGION, STATE OF SÃO PAULO

JAPAN INTERNATIONAL COOPERATION AGENCY







FIG.10
LONGITUDINAL PROFILES OF
CUBATÃO AND MOJI RIVERS

GOVERNMENT OF FEDERATIVE
 REPUBLIC OF BRAZIL
 THE STUDY ON THE DISASTER PREVENTION AND
 RESTORATION PROJECT IN SERRA DO MAR,
 CUBATÃO REGION, STATE OF SÃO PAULO
 JAPAN INTERNATIONAL COOPERATION AGENCY


Cubatão River



Perequê River



Moji River



Note:

- 1- Water level is Calculated by Nonuniform Flow Method.
- 2- Discharge Rating Curve Shown in Fig. I.16 is Adopted.
- 3- Bankful Capacity is Estimated as Capacity of Channel Below the Lower Bank Elevation of Both Banks
- 4- Distance and its Sections are Presented in Figs F18 and F19

The Details are Presented in Data Book

FIG.11
ESTIMATED CARRYING CAPACITY
OF CHANNEL

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY






FIG.12
MONTHLY DISTRIBUTION OF RAINFALL

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY



AVAILABILITY OF RAINFALL RECORDS





FIG.13
 LOCATION MAP OF RAINFALL
 STATIONS AND THEIR RECORD
 AVAILABILITY

GOVERNMENT OF FEDERATIVE
 REPUBLIC OF BRAZIL
 THE STUDY ON THE DISASTER PREVENTION AND
 RESTORATION PROJECT IN SERRA DO MAR,
 CUBATÃO REGION, STATE OF SÃO PAULO

JAPAN INTERNATIONAL COOPERATION AGENCY

DIVISION OF RIVER BASIN FOR ESTIMATION OF FLOOD RUNOFF



FLOOD RUNOFF ESTIMATION MODEL DIAGRAM







FIG.14
DIVISION OF RIVER BASIN FOR
ESTIMATION OF FLOOD RUNOFF

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO

JAPAN INTERNATIONAL COOPERATION AGENCY



Legend

- Sato - Kikkawa - Ashida Formula
- Brown Formula
- Englund - Hansen Formula
- M #

FIG.15
SEDIMENT TRANSPORT CAPACITY
IN EXISTING CHANNEL

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY




FIG.16
DISTRIBUTION MAP OF TOTAL
SLOPE FAILURES OF 1962-1989

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO

JAPAN INTERNATIONAL COOPERATION AGENCY




FIG. 17
DISTRIBUTION MAP OF INDIVIDUAL
PAST MAJOR SLOPE FAILURES

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY





FIG.18
CLASSIFICATION MAP OF
SLOPE FAILURES

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO


JAPAN INTERNATIONAL COOPERATION AGENCY



Note: Asf. : Total Slope Failure Area (Unit: $10^3 \times m^2$)
 Rmax. : Maximum Rainfall (Unit: mm.)
 r : Correlation Coefficient

FIG. 20
 CORRELATION OF TOTAL AREA OF
 SLOPE FAILURES AND N-HOUR
 RAINFALL


GOVERNMENT OF FEDERATIVE
 REPUBLIC OF BRAZIL
 THE STUDY ON THE DISASTER PREVENTION AND
 RESTORATION PROJECT IN SERRA DO MAR,
 CUBATÃO REGION, STATE OF SÃO PAULO
 JAPAN INTERNATIONAL COOPERATION AGENCY



Source: Rain-Induced Landslides in Southeastern Brazil:
(Wolfe 1988)

FIG. 21
SCHEMATIC PROFILE OF
TYPICAL SLOPE FAILURE

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY






FIG.23
THE OUTLINE OF FOREST RESTORATION
PLAN FOR CUBATÃO REGION

GOVERNMENT OF FEDERATIVE
 REPUBLIC OF BRAZIL
 THE STUDY ON THE DISASTER PREVENTION AND
 RESTORATION PROJECT IN SERRA DO MAR,
 CUBATÃO REGION, STATE OF SÃO PAULO
 JAPAN INTERNATIONAL COOPERATION AGENCY




FIG.24
ANNUAL CHANGE OF INDUSTRY PRODUCTS
AND SO₂/SO₃ CONCENTRATION

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO

JAPAN INTERNATIONAL COOPERATION AGENCY






FIG. 25 DISTRIBUTION OF THE POLLUTION INTENSITY IN THE STUDY AREA

Source: JICA Study Team

FIG.25
DISTRIBUTION OF AIR
POLLUTION INTENSITY AREA

GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL.
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY



GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY






FIG.28
INUNDATION AREA OF DESIGN SEDIMENT
RUN-OFF DISCHARGE

GOVERNMENT OF FEDERATIVE
 REPUBLIC OF BRAZIL
 THE STUDY ON THE DISASTER PREVENTION AND
 RESTORATION PROJECT IN SERRA DO MAR,
 CUBATÃO REGION, STATE OF SÃO PAULO
 JAPAN INTERNATIONAL COOPERATION AGENCY



(1) Sabo Dam (Groundsill)



(2) Channel Works





FIG.30
TYPICAL DESIGN OF STRUCTURES
FOR SEDIMENT RUN-OFF
DISASTER PREVENTION WORKS


GOVERNMENT OF FEDERATIVE
REPUBLIC OF BRAZIL
THE STUDY ON THE DISASTER PREVENTION AND
RESTORATION PROJECT IN SERRA DO MAR,
CUBATÃO REGION, STATE OF SÃO PAULO
JAPAN INTERNATIONAL COOPERATION AGENCY



Cubatão River System

Alternative C-1


Excavation of Existing Channel and Dike Construction



Moji River System

Alternative M-1


Excavation of Existing Channel and Dike Construction



Alternative C-2


C-2 (1) Diversion Discharge 1,200 m³/s
C-2 (2) Diversion Discharge 900 m³/s

Construction of Diversion Channel and Minor Improvement of Existing Channel



Alternative M-2

Channel Shifting of Lower Moji and Excavation of Existing Channel and Dike Construction



Note : Stretch to be Improved

FIG.32
ALTERNATIVE SCHEMES OF
OPTIMUM PLAN