

付 属 資 料

付属資料 I 調査団の構成

付属資料 II 調査日程

付属資料 III 主要面談者リスト

付属資料 IV 討議議事録

付属資料 V 図表

付属資料 VI 検討資料

VI-1 事業運営収支

VI-2 2000年需要に対応した設定規模の充足度

付属資料 VII 参考資料

VII-1 年風図、等

VII-2 潮流潮位分析結果

VII-3 深淺測量分析結果

VII-4 ボーリング結果

VII-5 現地調達材料の品質

付属資料Ⅰ 調査団の構成

Ⅰ-1 基本設計調査

氏名	担当分野	所 属
中山 哲蔵	総 括	水産庁 漁港部計画課 漁港計画官
佐々木 克宏	計 画 管 理	国際協力事業団 無償資金協力調査部 基本設計調査第二課
石本 恵生	漁 港 計 画	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社
波木 守	港 湾 土 木	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社
島田 宗宏	漁 業 一 般	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社
新谷 真人	設 備 設 計	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社
高橋 昭好	自然条件調査	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社
土屋 政美	積 算	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社

Ⅰ-2 ドラフトファイナルレポート説明

氏名	担当分野	所 属
中山 哲蔵	総 括	水産庁 水産工学研究所 主任研究官
川田 晃弘	計 画 管 理	国際協力事業団 林業水産開発協力部 水産技術協力室
石本 恵生	漁 港 計 画	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社
波木 守	港 湾 土 木	オーバーシーズ・アグロフィッシュャリーズ コンサルタンツ株式会社

付属資料Ⅱ 調査日程

Ⅱ-1 基本設計調査

日順	月日	行 程	業 務 内 容
1.	1月26日(土)	成田~バンコック	移動(中山、佐々木、石本、波木、島田、高橋)
2.	1月27日(日)	バンコック~ダッカ	移動、JICA事務所表敬
3.	1月28日(月)	ダッカ	日本大使館表敬、団内打合せ
4.	1月29日(火)	ダッカ	BIWTA(バングラデシュ内水面運輸公社)表敬・協議 BFDC(バングラデシュ水産開発公社)表敬・協議
5.	1月30日(水)	ダッカ~チッタゴン	BFDC チッタゴン支局表敬・協議、計画地踏査
6.	1月31日(木)	チッタゴン	零細漁業水揚場・魚市場視察 CPA(チッタゴン港湾局)協議 チッタゴン商港、コンテナヤード、造船修理施設視察
7.	2月 1日(金)	チッタゴン~ダッカ	移動
8.	2月 2日(土)	チッタゴン	自然条件調査開始
		ダッカ	BFDC協議、水産牧畜省表敬・協議
9.	2月 3日(日)	バンコック~ダッカ	設備設計団員(新谷)調査団に合流
		ダッカ	BFDC協議、ミニッツ内容打合せ BFDCパグラ流通センター視察
10.	2月 4日(月)	チッタゴン	ボーリング調査開始
		ダッカ	大蔵省表敬・協議、ミニッツ署名
11.	2月 5日(火)	ダッカ~バンコック	官団員(中山、佐々木)バングラデシュ出国
		ダッカ	BFDC協議、造船所視察、気象庁協議
12.	2月 6日(水)	ダッカ~チッタゴン	移動、BFDC チッタゴン支局協議
		チッタゴン	潮流計・流速計設置、観測開始
13.	2月 7日(木)	チッタゴン	水産局チッタゴン支局協議、CPA協議
14.	2月 8日(金)	チッタゴン	音響水深測量

日順	月 日	行 程	業 務 内 容
15.	2月9日(土)	チッタゴン	水揚・流通調査開始、製氷施設調査
16.	2月10日(日)	チッタゴン	BFDCチッタゴン支局協議、周辺土木工事現場視察
17.	2月11日(月)	チッタゴン~ コックスバザール	陸路移動、卸売市場、水揚施設、水産加工施設視察
18.	2月12日(火)	コックスバザール~ チッタゴン	陸路移動、BFDC チッタゴン支局協議
19.	2月13日(水)	ダッカ	BFDC協議、水産局統計課協議
20.	2月14日(木)	チッタゴン	造船施設等視察
		ダッカ~ジェソール	クルナへ空路・陸路移動、BFDC卸売市場、 水揚施設視察、政府造船所視察、 水産局品質管理研究所視察
21.	2月15日(金)	チッタゴン	ボーリング調査終了・撤収
		ジェソール~ダッカ	クルナより陸路・空路移動
		チッタゴン~ダッカ	移動
22.	2月16日(土)	ダッカ	BFDC 最終協議
23.	2月17日(日)	ダッカ~バンコック	JICA事務所報告、バングラデシュ出国
24.	2月18日(月)	ダッカ	資料整理
25.	2月19日(火)	バンコック~成田	帰国 (石本、波木、島田、新谷)
		ダッカ	資料収集
26.	2月20日(水)	ダッカ~バリサル	船便で移動
27.	2月21日(木)	バリサル	BFDC水揚げセンター、水産加工場視察
28.	2月22日(金)	バリサル~ダッカ	移動
29.	2月23日(土)	ダッカ~バンコック	バングラデシュ出国
30.	2月24日(日)	バンコック~成田	帰国 (高橋)

II-2 ドラフトファイナルレポート説明

日順	月 日	行 程	業 務 内 容
1.	7月 1日(日)	成田~バンコック	移動
2.	7月 2日(火)	バンコック~ダッカ	移動、JICA事務所表敬
3.	7月 3日(水)	ダッカ	水産牧畜省表敬、大蔵省表敬、 BFDC (バン格拉デシュ水産開発公社) 表敬・協議
4.	7月 4日(木)	ダッカ~チッタゴン	移動、CPA (チッタゴン港湾局) 協議 BFDC チッタゴン支局協議
5.	7月 5日(金)	チッタゴン~ダッカ	カルナフリ河 サイクロン被害状況視察、移動
6.	7月 6日(土)	ダッカ	BFDC協議、ミニッツ打合せ
7.	7月 7日(日)	ダッカ	BFDCミニッツ打合せ
8.	7月 8日(月)	ダッカ	日本大使館表敬、ダッカ魚市場視察、ミニッツ署名 JICA報告
9.	7月 9日(火)	ダッカ~バンコック	移動
10.	7月10日(水)	バンコック~成田	移動

付属資料Ⅲ 主要面談者リスト

Ⅲ-1 基本設計調査

1. 水産牧畜省

Mr. Muhammad Lutfullahi Majid Secretary
Mr. Luqueman Ahmad Joint Chief (Planning cell)

2. バングラデシュ水産開発公社 (BFDC : Bangladesh Fisheries Development Corporation)

1) ダッカ本局

Brigadier Chowdhury K. Laman Chairman
Mr. M. Muzaffar Hussain Director, Purchase & Marketing
Mr. A. K. M. Shanidul Islam Manager, Planning Division
Mr. S. M. Yashin Manager, Implementation
Ms. Kha Lutfunnessa Statistical Analyst

2) チッタゴン支局

Mr. Khwaja M. Hassan General Manager, Fish Harbour Complex
Mr. M. A. Hye Manager, Trawler Fleet
Mr. Matiur Rahman Sarker Manager (Administration)
Mr. Kazi Nurun Nabi Project Manager
Mr. Zakaria Mamoon Senior Stores Officer
Mr. Rowshon Ali Refrigeration Engineer
Mr. Harun-or Rashid Electrical Engineer
Mr. Habibur Rahman Executive Engineer
Mr. Mohamed Islaque Senior Purchase Officer
Mr. Mozammel Hussain Assistant Manager (Administration)
Mr. Abdul Halim Sarkin Stores Officer

3) コックスバザール支局

Mr. Golah Murtaza Manager, Wholesale Fish Market

Mr. Nuran Nabi

Manager, Fish Processing Unit

4) クルナ支局

Mr. Mesbahul Islam

Manager, Wholesale Fish Market

Mr. M. A. Momen

Manager, Fish Net Factory

3. 水産局 (Department of Fisheries)

1) ダッカ本局

Mr. Nazrul Islam

Deputy Chief, Planning

Mr. Kasha Banik

Senior Scientific Officer, Resource Survey

2) チッタゴン支局

Md. Harun-or Rashid

Deputy Director, Marine Fisheries Department

Mr. S. M. Shamsul Huda

Inspector, Marine Fisheries Department

3) チッタゴン品質管理研究所

Md. Akhtar Ali

Deputy Director, Fish Inspection and Quality Co

ntrol

Md. Abdul Khaleque

Fish Inspection and Quality Control Officer

4) クルナ品質管理研究所

Md. Kelal Uddin

Deputy Director, Fish Inspection and Quality Co

ntrol

4. チッタゴン港湾局 (C P A : Chittagong Port Authority)

Capt. M. Zakaria

Chairman, Chittagong Port Authority

Md. Jahirul Hoque

Member (Engineering & Dev.)

Dr. Shafaat Hossain Khan

Deputy Chief Engineer

Brigadier Chowdhury K. Laman	Chairman
Mr. A. K. M. Shanidul Islam	Manager, Planning Division
Mr. S. M. Yashin	Manager, Implementation
Mr. M. D. Fakhrul Alam	Executive Engineer

2) チッタゴン支局

Mr. Khwaja M. Hassan	General Manager, Fish Harbour Complex
Mr. Kazi Nurun Nabi	Senior Marketing Officer
Mr. Abdul Hannan	Executive Engineer
Mr. Purna Chandra Sarker	Assistant Civil Engineer

3. チッタゴン港湾局 (CPA : Chittagong Port Authority)

Capt. Lahiruddin Mahmood	Chairman
Md. Jahirul Hoque	Member (Engineer & Dev.)

4. 大蔵省 (Ministry of Finance)

Mr. Ahmed Shanar Chowdhury	Deputy secretary, Economic Relations Devison (ERD)
Mr. Rafiqul Islam	Senior Assistant Secretary, ERD

5. 日本大使館

伊藤公使	
Mr. Takeshi Ota	First Secretary

6. JICAダッカ事務所

Mr. Takeshi Imazu	所長
Mr. Takeshi Naruse	Deputy Resident Representative
Mr. Kenichirou Tominaga	Assistant Resident Representative

1. 基本設計調査時

MINUTES OF DISCUSSIONS
OF
THE BASIC DESIGN STUDY
ON
THE PROJECT FOR ESTABLISHMENT OF FISH LANDING,
PRESERVATION AND DISTRIBUTION FACILITIES
AT MONOHARKHALI
IN THE PEOPLE'S REPUBLIC OF BANGLADESH


In response to the request of the Government of the People's Republic of Bangladesh (Bangladesh), the Government of Japan decided to conduct a basic design study (the Study) on the Project for Establishment of Fish Landing, Preservation and Distribution Facilities at Monoharkhali (the Project) and entrusted the Study to the Japan International Cooperation Agency (JICA). JICA sent to Bangladesh the Study Team headed by Mr. Akiyoshi NAKAYAMA, Deputy Director, Fishing Port Planning Division, Fishing Port Department, Fisheries Agency, Ministry of Agriculture, Forestry and Fisheries, from January 26 to February 24, 1991. The Team had a series of discussions on the Project with the officials concerned of the Government of Bangladesh headed by Brig. Chowdhury Khalequzzaman (Retd.) and conducted field surveys. Chairman, BFDC.

As a result of the discussions, both parties agreed the fundamental factors for conducting the Study as attached herewith.

Dhaka, February 04, 1991

中山哲巖

Akiyoshi NAKAYAMA
Team Leader,
Basic Design Study Team,
Japan International Cooperation
Agency (JICA)
JAPAN



Brig. Chowdhury Khalequzzaman (Retd.)
Chairman
Bangladesh Fisheries Dev. Corporation,
Dhaka, Bangladesh.

ATTACHMENT

1. Objectives of the Project

The objective of the Project is to improve fish landing operation, preservation and distribution of fishes caught by mechanized and local fishing boats for supply of fishes to Chittagong, Dhaka and other areas through establishment of the most appropriate fish landing, preservation and distribution facilities to be recommended by the Study.

2. Organization

Executing and Implementing Agency : Bangladesh Fisheries Development Corporation,
the Ministry of Fisheries and Livestock

3. Project site

The site of the Project is located at Monoharkhali in Chittagong, Bangladesh as shown in ANNEX - 1.

4. Major items requested by the Government of Bangladesh for the Project

The outline of the facilities and major equipment is shown in the ANNEX - 2.

5. Japan's Grant Aid Program

The Government of Bangladesh has understood the system of Japan's Grant Aid Program explained by the Team, which includes a principle and the role of the Japanese consultants and Japanese firms for the implementation of the Project.

6. Provision of Necessary Budget and Personnel

The Government of Bangladesh will assure the necessary budget and personnel for the operation and maintenance of the facilities and equipment provided, on condition that

→ P 11

the Grant Aid by the Government of Japan is extended to the Project.

7. Measures to be taken by the Government of Bangladesh
The Government of Bangladesh will take necessary measures as listed in ANNEX - 3, on condition that the Grant Aid by the Government of Japan would be extended to the Project.
8. The Bangladesh side requested for outline Draft study by end of March, 1991.
9. The Bangladesh side suggested that the design of the project be done in such a manner that land reclamation cost is not incurred.
10. Both side agreed to observe financial clauses as mentioned, subject to the approval of both the Govt.

中山

ANNEX - 2

Request made by the Government of Bangladesh

- 1) Facility for fish landing of mechanized and local fishing boats; wharf, pontoon, gangway
- 2) Facility for preservation of fish ; ice plant, cold storage
- 3) Facility for distribution of fish ; fish market
- 4) Administration facility
- 5) Fisheries equipment for fish handling and distribution
- 6) Others

The Bangladesh side requested that appropriate minimum required facilities only may be studied/ incorporated in order to minimize the project cost. 6

✓ P ↓

ANNEX - 3

Necessary measures to be taken by the Government of Bangladesh are as follows ;

1. To secure the ownership and/or the right to use the Project site.
2. To clear, level and reclaim the Project site, when needed, prior to the commencement of the Project.
3. To construct wall and fences around the Project site.
4. To improve the access road to the Project site.
5. To provide facilities for the distribution of the electricity, water supply, drainage, telephone line and other incidental facilities.
6. To bear advising commission of the Authorization to Pay (A/P) and payment commission to the Japanese foreign exchange bank for banking services based upon the Banking Arrangement (B/A).
7. To ensure prompt unloading, tax exemption, and custom clearance of the goods for the Project at port of disembarkation.
8. To accord Japanese nationals whose services may be required in connection with the supply of the products and services under the verified contract such facilities as may be necessary for their entry into Bangladesh and stay therein for the performance of their work.
9. To exempt Japanese national from customs duties, internal taxes to other fiscal levies which may be imposed in Bangladesh with respect to the supply of the products and services under the verified contracts.
10. To maintain and use properly and effectively the facilities constructed and equipment under the verified contracts.
11. To bear all the expenses other than those to be borne by the Grant, necessary for construction of the facilities as well as for the transportation and installation of the equipment.

ΦΔ
L

12. To coordinate and solve any matters related which may arise with third party and inhabitants living in the Project area during implementation of the Project.

~PDA

E

MINUTES OF DISCUSSIONS
BASIC DESIGN STUDY
ON
THE PROJECT FOR ESTABLISHMENT OF FISH LANDING, PRESERVATION AND
DISTRIBUTION FACILITIES AT MONOHARKHALI
IN THE PEOPLE'S REPUBLIC OF BANGLADESH
(CONSULTATION ON DRAFT REPORT)

In July 1991, the Japan International Cooperation Agency (JICA) dispatched the Basic Design team on the Project for Establishment of Fish Landing, Preservation and Distribution Facilities at Monoharkhali (hereinafter referred to as "the Project") to the People's Republic of Bangladesh, and through discussions, field survey and technical examination of the results in Japan, has prepared the draft report of the study.

In order to explain and to consult the Bangladesh side on the components of the draft report, JICA sent to Bangladesh a study team, which is headed by Mr. Akiyoshi Nakayama, Senior Researcher, Aquaculture and Fishing Port Engineering Division, National Institute of Fisheries Engineering, Fisheries Agency, Ministry of Agriculture, Forestry and Fisheries and is scheduled to stay in the country from July 2 to 9, 1991.

As a result of discussions, both side confirmed the main items described on the attached sheets.

Dhaka, July 08, 1991

中山 哲 巖

Akiyoshi Nakayama
Leader

Draft Report Explanation Team
JICA



Brig. Chowdhury Khalequzzaman (Retd.)
Chairman

Bangladesh Fisheries Dev. Corp.
Dhaka, Bangladesh.

ATTACHMENT

1. Components of Draft Report

The Government of Bangladesh agreed and accepted in principle the component of the Draft Report proposed by the team.

2. Japan's Grant Aid Program

(1) The Government of Bangladesh has understood the system of Japanese Grant Aid explained by the team.

(2) The Government of Bangladesh will take necessary measures, described in ANNEX I, for smooth implementation of the Project on condition that the Grant Aid Assistance by the Government of Japan is extended to the Project.

3. Products required for the project and available in Bangladesh shall not be exported from Japan.

4. Further Schedule

(1) The team will make the Final Report in accordance with the confirmed items, and send it to the Government of Bangladesh by the middle of September 1991.

中山

Annex-I: Necessary measures to be taken by the Government of Bangladesh in case Japan's Grant Aid is extended.

1. To secure the site for the Project.
2. To clear the debris and wrecked ships brought by the cyclone on the site, prior to the commencement of the Project.
3. To undertake incidental outdoor works such as gardening, fencing, gates and exterior lighting in and around the site, when needed.
4. To take necessary control measure or make arrangement to alleviate traffic condition during construction period.
5. To provide facilities for the distribution of the electricity, water supply, drainage, telephone line and other incidental facilities to the Project site.
 - 1) Electricity distributing line to the site.
 - 2) City water distribution main to the site.
 - 3) Drainage city main to the site.
 - 4) Telephone trunk line to the main distribution panel of building.
 - 5) General furniture such as carpets, curtains, tables, chairs and others.
6. To bear commissions to the Japanese foreign exchange bank for the banking services based upon the Banking Arrangement as per prevailing rule of the Govt. of Bangladesh.
7. To exempt taxes and to take necessary measures for customs clearance of the materials and equipment brought for the project at port of disembarkation as per prevailing rule of the Govt. of Bangladesh.
8. To accord Japanese nationals whose services may be required in connection with the supply of the products and services under the verified contract such facilities as may be necessary for their entry into Bangladesh and stay therein for the performance of their work as per prevailing rule of the Govt. of Bangladesh.
9. To maintain and use properly and effectively the facilities constructed and equipment purchased under the Grant.
10. To bear all the expenses other than those to be borne by the Grant, necessary for construction of the facilities as well as for the transportation and installation of the equipment.

Handwritten marks: a signature or initials on the left and a checkmark on the right.

表 2 - 1 漁業別生産量

(単位：トン／年)

	1983年度	1987年度
1. 内水面漁業	471,595	423,598
2. 内水面養殖	117,025	175,925
3. 海面商業漁業	14,500	10,395
4. 海面零細漁業	150,382	217,187
計	753,502	827,105

(出所：水産牧畜省水産局)

表 2 - 2 海面零細漁業 漁法別生産量 (1987年度)

漁 法	生産量 (トン／年)
1. 刺 網	(132,890)
動力船	118,276
無動力船	14,614
2. 袋 待 網	(63,464)
季節型	45,000
通年型	18,464
3. 延 縄	(6,118)
動力船	4,817
その他	1,301
4. そ の 他	(14,715)
合 計	217,187

(出所：水産牧畜省水産局)

表2-3 海面零細漁業 地域別漁船数

地 域	動力漁船数(隻)	無動力漁船数(隻)
コックスバザール	1,822	2,089
チッタゴン	1,128	5,272
ノクハリ	179	1,860
バリサル	81	1,852
プトクハリ	98	2,044
クルナ	9	897
	3,317	14,014

(出所：水産局 1984年度漁家調査)

表2-4 刺網動力船の月別稼働実績(1988年度)

	稼働船数(隻)	月当り平均稼働数	1船当り平均漁獲高(kg)	漁獲高(トン)
1988年 7月	570	3	453	775
8月	1,680	3	1,862	9,386
9月	2,692	3	2,752	22,225
10月	2,810	3	2,197	18,521
11月	2,570	3	2,511	19,360
12月	1,952	3	1,865	10,921
1989年 1月	1,750	3	1,910	10,028
2月	1,430	3	1,423	6,104
3月	1,305	3	1,327	5,196
4月	1,398	3	1,892	7,935
5月	1,145	3	1,815	6,236
6月	715	3	1,164	2,497
年間計	20,017		21,171	119,184
月当り平均	1,668		1,764	

(出所：水産局統計課)

表2-5 BFDC コックスバザール卸売市場年間取扱量

年 度	1985	1986	1987	1988	1989
年間取扱量(トン)	2,115	4,832	5,062	7,136	6,581

(出所：BFDC)

表2-6 BFDC コックスバザール卸売市場 月別取扱量

(単位：トン)

月	1989年度	1990年度
7	83	12
8	368	404
9	1,140	829
10	789	612
11	534	335
12	682	535
1	569	362
2	469	—
3	491	—
4	655	—
5	592	—
6	209	—

(出所：BFDC)

表2-7 BFDC クルナ卸売市場 年間取扱量

年 度	1985	1986	1987	1988	1989
年間取扱量(トン)	3,294	2,858	2,495	2,866	1,933

(出所：BFDC)

表2-8 BFDC クルナ卸売市場 月別取扱量 (トン)

月	1989年度
7	211
8	484
9	982
10	283
11	206
12	190
1	174
2	99
3	26
4	14
5	36
6	161

(出所：BFDC)

表3-1 計画地内の市水分析結果

BANGLADESH UNIVERSITY OF ENGINEERING & TECHNOLOGY, DHAKA
DEPARTMENT OF CIVIL ENGINEERING
ENVIRONMENTAL ENGINEERING LABORATORY


ANALYSIS OF WATER SAMPLE


Our Ref. No. : BRTC - 1920/90-91 Dated: 16/02/91
Your Ref. No. : TC/06/91 Dated: 16/02/91
Sent by : Tecnocosult International Ltd.
Sena Kalyan Bhaban 7th floor 195, Motijheel C/A, Dhaka
Location : BFDC office, Bridge Ghat, Chittagong
Date of Test: 17th & 18th February, 1991

TEST RESULTS

Sl. No.	Water quality parameters	Unit	Concentration present	Drinking water standards	
				WHO guide line values (1984)	Tentative Bangladesh standards
1.	Total Dissolved Solids	mg/l	136	1000	1500
2.	Turbidity	NTU	2.5	5	25
3.	Colour	mg/l	5	15	30
4.	pH	-	6.80	6.5-8.5	6.5-9.2
5.	Total Hardness as CaCO ₃	mg/l	55	500	250(Max. 400)
6.	Calcium, Ca	mg/l	7		
7.	Magnesium, Mg	mg/l	9		
8.	Chloride, Cl	mg/l	23	250	600(Max. 1000)
9.	Fluoride, F1	mg/l	0.15	1.5	1(Max. 2)
10.	Iron, Fe	mg/l	0.10	0.3	1(Max. 5)
11.	Manganese, Mn	mg/l	Nil	0.1	0.5
12.	Nitrate, Nitrogen, NO ₃	mg/l	6	10	45(Max. 50)
13.	Carbondioxide, CO ₂	mg/l	17		
14.	Alkalinity	mg/l	67		

Note: The maximum value in Bangladesh standard is for small diameter handpump tubewell water in absence of a better source.

Countersigned by: 

Test performed by:  20/2/91

PROFESSOR
Department of Civil Engineering
Bangladesh University of
Engineering & Technology, Dhaka

表3-2 モノハカリより2 km以内に立地する製氷工場

場 所	工場数	実産出能力
1. モノハカリ水揚場付近	6工場	40トン
2. Fisheries Ghat 水揚場付近	10工場	100トン
3. その他の2 km以内	7工場	50トン
計	23工場	190トン

(出所：BFDC)

表4-1 BFDCの保有施設

施設名	施設数	能力
1. 漁港	1 港	—
2. 水揚施設	9 ヲ所	—
3. 卸売市場	7 市場	—
4. 製氷工場	13 工場	日産225トン生産
5. 氷蔵庫	11 ヲ所	665トン収容
6. 凍結設備	5 ヲ所	日産64トン凍結
7. 冷蔵庫	5 ヲ所	1,410トン収容
8. 魚粉工場	4 工場	日産8トン生産
9. トロール漁船	8 隻	—
10. 漁網工場	3 工場	年産42万ポンド生産
11. 漁船修理工場	1 工場	—
12. 上架施設	2 ヲ所	—
13. 小規模修船場	3 ヲ所	—

(出所：BFDC)

表4-2 BFDCの運営中の個別プロジェクト

実施地名	プロジェクト名
1. チッタゴン	チッタゴン漁業コンプレックス
2. チッタゴン	トロール漁業プロジェクト
3. ランガマティ	カプタイ湖漁業開発及び流通センター
4. モングラ	水産加工、及び流通センター
5. コックスバザール	水産加工、及び流通センター
6. バグラ	水産加工、及び流通センター
7. コックスバザール	水揚施設、及び卸売市場
8. クルナ	水揚施設、及び卸売市場
9. ラジェシヤヒ	水揚施設、及び卸売市場
10. バリサル	水揚施設、及び卸売市場
11. ケブパラ	水揚施設、及び卸売市場
12. パサルガタ	水揚施設、及び卸売市場
13. ダボルガット	水揚施設、及び卸売市場
14. コミラ	漁網工場
15. チッタゴン	漁網工場
16. モングラ	漁網工場

(出所：BFDC)

表5-1 計画地周辺の水質分析結果

		中央部							
		PH	E.C.	CL	S.S	TALKALI	T.S	BOD	COD
89	JAN	7.25	95	1.0	0.1	52.0	73.0	2.1	42.0
	FEB	7.20	140	2.0	1.0	46.0	74.0	2.8	40.0
	MAR	7.00	100	1.5	0.8	64.0	69.0	2.2	40.0
	APR	7.20	110	0.5	0.4	68.0	71.0	0.4	36.0
	MAY	7.80	95	2.5	0.2	96.0	79.0	1.8	42.0
	JUN	7.80	140	2.5	0.4	96.0	22.0	0.9	45.0
	JUL	7.40	130	4.0	1.0	70.0	102.0	0.7	35.0
	AUG	7.20	90	2.0	1.1	56.0	100.0	0.4	20.0
88	DEC	6.20	80	1.5	0.1	44.0	65.0	2.2	
	OCT	7.60	178	2.2	0.1		80.0	0.3	
	APR								
		周辺部							
		PH	E.C.	CL	S.S	TALKALI	T.S	BOD	COD
89	JAN	7.40	100	2.5	0.4	60.0	79.0	3.8	48.0
	FEB	7.20	145	7.5	0.1	48.0	129.0	2.6	62.0
	MAR	7.30	135	4.0	1.2	64.0	108.0	2.1	58.0
	APR	7.40	130	2.0	1.2	64.0	112.0		64.0
	MAY	7.60	120	4.0	1.1		98.0	2.9	70.0
	JUN	7.60	160	6.5	0.9	92.0	187.0	2.5	50.0
	JUL	7.70	140	3.0	1.1	76.0	121.0	0.6	45.0
	AUG	7.40	120	1.5	1.8	68.0	128.0	0.4	30.0
88	DEC	6.10	110	6.5	0.1	47.0	28.0	2.0	
	OCT	7.50	181	25.5	0.1		85.0	3.8	
	APR	6.40	180	2.0		6.0		1.2	

NOTE ; KARNAPHLI RIVER WATER
 SS ; SETTING SOLID (cc/l)
 T.ALKALI ; TOTAL SOLID (mg/l)
 BOD/COD ; PPM
 EC ; (μs/cms)
 CL ; CHLORIRE (mg/l)

图 2-1 水産局組織図




圖 2 - 2 B F D C 組織圖






図3-1 チッタゴンの年間気温変動




(出所： Bangladesh 統計年鑑)

図3-2 チッタゴンの月間気温変動 (1988年)




(出所： Bangladesh 統計年鑑)

図3-3 チッタゴンの月間湿度変動 (1988年)




(出所： Bangladesh 統計年鑑)

図3-4 チッタゴンの年間降雨量変動



(出所： Bangladesh 統計年鑑)


図3-5 チッタゴンの月間降雨量変動 (1986~89年平均値)



(出所: バングラデシュ統計年鑑)


(AVE:1986-1989)

図3-6 チッタゴンの月別水位変動 (1985~89年平均値)




(出所: バングラデシュ統計年鑑)

図 3-7 計画地周辺の水質、水温




(出所：現地調査時解析結果)

図 3 - 8 計画地周辺の河川底質成分



(出所: 現地調査時解析結果)

図 3-9 チッタゴンの月別サイクロン災害頻度 (最近42年間での累計値)



(出所：バングラデシュ統計年鑑)

付属資料 VI-1 事業収支

計画年における年間収支

(1) 収支要素

1) 年間水揚量	: 30,475トン
2) 1日当り平均水揚漁船数	: 48隻/日
3) 接岸料	: 100タカ/隻・日
4) 年間卸売荷捌量	: 39,690トン
5) 市場使用料	: 成約金額の2%
6) 平均魚価	: 22タカ/kg
7) せり入室賃貸料	: 900タカ/月
8) 製氷施設の生能能力	: 日産32トン
9) 氷の販売価格	: 平均550タカ/トン
10) 人件費	: (4-3-5章 要員計画表参照)
11) 電気代	: 2.01タカ/KWH
12) 水道料	: 14タカ/m ³

(2) 年間収入 25,981,200タカ/年

1) 接岸料収入

$$48\text{隻/日} \times 360\text{日} \times 100\text{タカ/隻} \cdot \text{日} = 1,728,000\text{タカ/年}$$

2) 市場使用料収入

$$39,690\text{トン/年} \times 22\text{タカ/kg} \times 2\% = 17,463,600\text{タカ/年}$$

3) せり入室賃貸収入

$$42\text{室} \times 900\text{タカ/月} \times 12\text{月} = 453,600\text{タカ/年}$$

4) 角氷販売収入

$$32\text{トン/日} \times 550\text{タカ/トン} \times 360\text{日} = 6,336,000\text{タカ/年}$$

(3) 年間支出 19,299,400タカ/年

1) 人件費 年間 2,135,000タカ

(内訳)

- ①所長室 149,500タカ/年
- ②管理課 780,000タカ/年
- ③会計課 247,000タカ/年
- ④市場課 188,500タカ/年
- ⑤製氷課 338,000タカ/年
- ⑥臨時雇用 432,000タカ/年 (24名/日×50タカ/日×360日)

2) 電気料 年間 3,169,400タカ

- ①製氷・冷蔵施設 $4,080\text{KWH}/\text{日} \times 360\text{日} \times 2.01\text{タカ}/\text{KWH} = 2,952,300$
- ②電灯類 $50\text{KW}/\text{時} \times 6\text{時間}/\text{日} \times 360\text{日} \times 2.01\text{タカ}/\text{KWH} = 217,100$

3) 水道代

$$100\text{m}^3/\text{日} \times 360\text{日} \times 14\text{タカ}/\text{m}^3 = 504,000\text{タカ}/\text{年}$$

4) 保守費 年間 4,800,000タカ

- ①建物保守 $3,000\text{m}^2 \times 100\text{タカ}/\text{m}^2 \cdot \text{年} = 300,000\text{タカ}/\text{年}$
- ②製氷・冷蔵設備保守 2,500,000タカ/年
 - 冷凍機油、冷媒補充費 2,000,000
 - 修理、部品代 500,000
- ③浮棧橋保守 2,000,000タカ/年 (1,000,000タカ/1基)

5) 事務経費 年間1,000,000タカ

6) 減価償却費 7,691,000タカ

- ①製氷・冷蔵設備 $35,000,000\text{タカ} \div 10\text{年償却} = 3,500,000\text{タカ}/\text{年}$
- ②浮棧橋 $12,000,000 \div 20\text{年償却} \times 3\text{基} = 1,800,000\text{タカ}/\text{年}$
- ③魚函買換費 $1,830\text{函} \times 1,200\text{タカ}/\text{函} = 2,196,000\text{タカ}/\text{年}$
- ④荷車買換費 $39\text{台} \div 2\text{年償却} \times 10,000\text{タカ}/\text{台} = 195,000\text{タカ}/\text{年}$

付属資料 VI-2

2000年時の需要に対応した設定規模の充足度

(1) 2000年時の需要予測 (4-3-2項参照)

1) 動力漁船による年間水揚量

刺網 (動力漁船)	47,990	
袋待網 (季節型)	18,327	
延縄 (動力漁船)	1,971	
計画地水揚量	68,288	トン/年

2) 計画地での年間荷捌量

水揚量	68,288	
カブタイ湖の搬入量	2,034	
他の内水面漁獲の搬入量	3,973	
内水面養殖の搬入量	3,629	
計画地荷捌量	77,924	トン/年

(2) 水揚施設

1) 水揚施設利用の需要

①水揚予測量 : 68,288トン/年

②1日当り水揚平均量 : 190トン/日 (68,288トン/年÷360日)

③1日当り水揚漁船数 : 76隻 (190トン/日÷2.5トン/隻)

(漁船の漁槽容積を有効利用した2.5トンの水揚が実現すると判断する。)

2) 施設の対応能力

①水揚時間帯 : 午前 1:30~7:30の6時間

②水揚速度 : 1.4時間/1隻 (2,500kg÷30kg/分=83分)

③水揚可能漁船数 : 69隻 (4÷1.4時間×16隻/回転)

従って、計画水揚施設の対応能力にやや不足が予想される。しかし、計画により導入される荷車、魚函等の活用を促進すれば、水揚速度をより一層迅速に行うことは可能であり、十分対応可能な範囲の不足と判断する。

(3) 荷捌施設

1) 荷捌施設利用の需要


- ① 荷捌量 : 77,924トン
- ② 1日当たり平均荷捌需要 : 216トン/日 [77,924÷360日]

2) 施設の対応能力


- ① 荷捌時間帯 : 午前 3:00～9:00の6時間
- ② 卸売市場の回転使用率 : 3回転
- ③ 卸売場標準取扱量 : 70kg/m² (魚函平積み70kg/m²の定着)
- ④ 卸売場実質面積 : 1,000m²
- ⑤ 荷捌可能量 : 210トン/日 (1,000m²×70kg/m²×3回転)

従って、本施設の荷捌可能量は、2000年時に予測される計画地での荷捌に対応したものと判断される。

Ⅶ-1 年風図、等



年間風向図 (1989年、8回測定/日)



日最大風速風向図 (1989年)

潮流・潮位の調和分解結果について

潮流・潮位を2月6日14時40分から2日間にわたって調和分解した。

1. 潮流

潮流の調和定数を下に示す。


	東方成分		北方成分	
	流速(cm/sec)	遅角(rad)	流速(cm/sec)	遅角(rad)
日周潮	10.0	0.047	0.8	0.139
半日周潮	43.6	0.592	4.5	0.804

2. 潮位


潮位の調和定数を下に示す。


	潮位(cm)	遅角(rad)
日周潮	27.2	1.104
半日周潮	110.4	1.941

潮流楕円図



VII-3 深淺測量分析結果





TECHNOCONSULT INT'L LTD. DHAKA.

GRAIN SIZE ANALYSIS		ATTERBERG LIMITS		WATER CONTENT % (g/cm ³)		DENSITY PCF		CONSOLIDATION SHEAR TEST DATA				ASPT		DEPTH		PROJECT			
Sand %	Silt %	L.L.	P.I.	S.L.	At Test	In Place	Bulk	Dry	Void Ratio	Compr. Index	σ _v PSF	σ _v kN/m ²	Strain %	At Failure	Applied Stress	Blows/0.33 M	Depth M	Location	Date
									e ₀	C _c			%	kN/m ²				MONORKHALI, CTG.	
11	73	16														90	18	(SILTSTONE)	22
																48	19	060 ± 0.015 m.m.	24
																30	20		
																45	22		
																46			
7	67	26														50	24	060 ± 0.01 m.m. Grey very hard SILT with clay trace sand.	26
																48			
4	66	30														48	26	060 ± 0.0075 m.m.	28
																46			
																52	28		30

DRAWN BY DATE..... CHECKED BY..... DATE..... APPROVED BY DATE.....

TECHNOCONSULT INT'L LTD. DHAKA.

GRAIN SIZE ANALYSIS		ATTERBERG LIMITS		WATER CONTENT %		DENSITY (PCF)		CONSOLIDATION SHEAR TEST DATA			ASPT		DEPTH		PROJECT	
Sand %	Silt %	Clay %	L.L. %	P.L. %	S.L. %	A ₁ Test	In. Piece	Bulk D _{ry}	A ₁ PSF	Laterals Stress PSF	AI Failure Stress Applied kN/m ²	Blows/0.33 M	Depth M	LOG OF BORING NO.	Location	PROJECT
									Compr. Index	Void Ratio	CC					
4	65	31										74	+3.679	3	MONOHORHALLI, CHITLAGONG	FISH LANDING PROJECT
6	65	29										86	+2	3		
8	67	25										50 (br 6)	+1	3		
												60 (br 6)	0	3		
												66 (br 6)	-1	3		
												55 (br 4)	-2	3		
8	65	27										50 (br 4)	-4	3		
												45 (br 3)	-6	3		
24	62	14				20	131 (2.10)	109 (1.75)	0	0	0	50 (br 3)	-6	3		
												60 (br 2)	-8	3		
												70 (br 6)	-8	3		
												60 (br 6)	-10	3		
5	64	31										40 (br 2)	-10	3		
												50 (br 3.5)	-10	3		
												56 (br 4)	-12	3		
												52 (br 2)	-12	3		
												50 (br 3)	-14	3		
6	65	29										56 (br 6)	-14	3		
												56 (br 6)	-16	3		
4	67	29										60 (br 6)	-16	3		

D₆₀ = 0.007 mm.
 D₆₀ = 0.0085 mm.
 Grey very hard SILT with clay (Laminated SILTSTONE and SHALE)
 D₆₀ = 0.014 mm.
 D₆₀ = 0.011 mm.
 D₆₀ = 0.032 mm.
 Grey very hard clayey SILT with sand (SILTSTONE and SHALE)
 D₆₀ = 0.008 mm.
 Grey very hard SILT with clay little to trace sand.
 (Laminated Siltstone and Shale)
 D₆₀ = 0.0095 mm.
 D₆₀ = 0.01 mm.

DRAWN BY DATE CHECKED BY DATE APPROVED BY DATE

サンプリング資料の土質試験結果

表層地盤 (N値 < 10)

		BH-1	BH-4		BH-5	備考
CDL 基準		-3m	+0.65m	-1.35m	-0.6m	1. PSF=4.88kgf/m ² 2. PCF=16.0kgw/m ²
粒度 (%)	砂	38	10	78	21	
	シルト	48	69	22	67	
	粘土	14	21	—	12	
含水量(%wt)		36	30	29	28	
密度 (T/m ³)	湿潤	1.856	1.936	1.920	1.968	
	/乾燥	/1.360	/1.472	/1.504	/1.520	
比重		2.67	2.65	2.65	2.66	
圧密 試験	eo	0.735	—	0.698	—	
	Cc	0.151	—	0.067	—	
一軸 圧縮	強度qu(T/m ²)	2.13	5.30	4.25	8.14	
	歪み(%)	15	17	2	15	

(出所：現地調査時ボーリング調査)

付属資料Ⅶ-4 (表2)

サンプリング資料の土質試験結果

基盤 (N値 ≥ 10)

		BH-1		BH-2		BH-3	BH-4
CDL 基準		-4m	-8m	-4m	-9m	-14m	-6.35m
粒度 (%)	砂	11	4	5	4	24	4
	シルト	65	61	66	65	62	66
	粘土	24	35	29	31	14	30
含水量(%wt)		24	32	23	23	20	25
密度 (T/m ³)	湿潤	2.016	1.904	2.048	2.032	2.096	2.016
	/乾燥	/1.632	/1.584	/1.664	/1.664	/1.744	/1.600
比重		2.67	2.67	2.67	2.67	2.68	2.68
圧密 試験	eo	—	0.673	0.643	—	—	—
	Cc	—	0.284	0.123	—	—	—
一軸 圧縮	qu(T/m ²)	64.7	—	43.5	21.3	24.7	41.0
	ひずみ(%)	5.5	—	10	8.5	7.5	6.5

(出所：現地調査時ボーリング調査)

付属資料Ⅶ-5 現地調達材料の品質

(1) 盛土用土砂

計画地对岸の肥料工場建設用土取場における砂、及び粘土混じりシルトの締固め試験結果（表Ⅶ-5-1）によると、粘土混じりシルト（河川の表面堆積泥に近い）でも、若干乾燥させると湿潤密度 $1.7\text{ton}/\text{m}^3$ 程度（砂で $1.8\text{ton}/\text{m}^3$ ）に締まることが判明する。計画地の土の土質試験結果（付属資料Ⅶ-4）では、計画地周辺の河川表土は、粘土含有分がこれより低い（20%以下）砂質シルトであるから、脱水しやすく、砂と混ぜて盛土材として利用できるかと判断する。

(2) 石材、等

擁壁の裏込め、基礎捨石、舗装用路盤材としては、以下のものが現地で入手可能である。

裏込め材：軽量のレンガチップが入手可能。

基礎捨石：摩耗に強い、硬質れき岩の手割砕石（粒径 $20\sim 40\text{mm}$ ）が入手可能。

舗装用路盤材：現地では（砂+レンガチップ）又は（砂+砕石）の粒度調整材が多く用いられる。

張石：シレット産の河川玉石、コックスバザール産、カプタイ産の角ばったれき岩か鉱さい塊が入手可能。コックスバザール産、カプタイ産のものがCPAでの使用実績が多い。

(3) コンクリート用骨材

コンクリート用砕石としては、建築用はレンガチップ、土木用は玉石砕石が主に用いられている。手割の場合粒径が単一になりがちなので、粒径別に分けた上で所定粒度に再混合する必要がある。

砂はシレット産が粗目（ $\text{FM}=3.8$ ）、チッタゴン周辺では川砂も山砂も細目（ $\text{FM}=1.9$ 以下）で若干のシルト分（5%以下）を含む。このためシレット産とチッタゴン産を混合して粒度分布を基準曲線に合わせている。（表Ⅶ-5-2）

(4) セメントの品質

国営企業CHITTAGON CEMENT CLINKER GRINDING CO. LTD.がインドネシア、ヨルダン、パキスタン、中国等からクリンカーを輸入し、これを粉碎し麻袋に詰めて国内向けに供給している。クリンカーの品質も安定せず、粉末度も若干粗目で、かつ透水性の袋詰めのため荷こぼれ、風化が激

しく、数量／品質共に問題があると言われる。

品質試験結果（表Ⅶ-5-3）は、国際基準〔BS-12/1978、JIS-R5210（186）〕を満足するが、設計基準強度 $280\text{kg}/\text{cm}^2$ 以上のコンクリートの場合、単位セメント量が $400\text{kg}/\text{m}^3$ を越える。高強度コンクリート用には、セメントの輸入か、コンクリート製品の輸入の必要がある。

（5）コンクリートの品質

日本でのコンクリート配合基準とチッタゴンでの配合例を比較すると、粗骨材が手割碎石のため十分な粒度調節をなされていないためか、粗骨材の容積（VG）が日本の基準の62%～72%に対して、44%～50%と著しく低い。このため、セメント使用量が多いにもかかわらず強度発現はそれ程ではない。設計に際し十分な考慮を必要とする。

（6）鉄筋／鋼材（鋼板、型钢）

国営企業CHITTAGON STEEL MILLSが製造している。

鉄筋は丸棒／異形の両方を製造しており、単価は日本の約2倍と言われる（関税85%）。品質はBS、ASTM、JIS規格のいずれにも合格する。鋼材としては、板材（厚さ3.2～6.0mm）、山型钢（35mm、50mm、75mm）を製造しているが鉄筋と同じく高い。注文生産（1ロット/100ton）で、納期は1～2ヵ月である。鋼板類の品質、精度も国産品は若干劣り、造船用ロイド級の場合、輸入に頼っている。

国営企業CHITTAGON DRY DOCKでは、これらの素材を利用して、鋼管杭（直径500～600mm、板厚9mm以下）、浮棧橋、組立橋梁、高架水槽を製作している。

表 VII-5-1 土砂の締固め試験結果 (SOILTECH/KAFCCO土取場)

SAMPLE NO.	1	2	3	4	5	6
DEPTH OF SAMPLE	Below - 1m	Below - 1m	Below - 1m	Below - 1m	Below - 1m	Below - 1m
MOISTURE CONTENT (%)	--	--	--	29.18	27.22	24.62
MAXIMUM DENSITY (TON/m ³)	1.84	1.82	1.78	1.68	1.69	1.72
OPTIMUM MOISTURE CONTENT (%)	14.50	13.80	17.50	18.00	20.60	18.00
FINENESS MODULUS (F.M.)	1.51	1.83	1.65	--	--	--
GRAIN SIZE ANALYSIS	95	97	96	2	--	2
SAND(2mm~0.06)	5	3	4	69	57	59
SILT	--	--	--	29	43	39
CLAY(2μ以下)						

(出所: Soiltech)

表Ⅶ-5-2 コンクリート用骨材の判定

	砕 石				砂			
	J I S	日本	外国	ワカ砕石	J I S	日本	シレット	白砂/黒砂
絶 乾 比 重	2.5以上	2.5~ 2.7		2.0	2.5以上	2.3~ 2.65		
吸 水 率 (% w t)	3以下	0.3~ 2.5		20以下	3以下	0.6~ 6.0	4.5	
安 定 性 (% w t)	12以下	—		—	10以下	—	—	
洗い試験で 失われる量(%wt)	1以下	—		—	7以下	—	—	5
すりへり減量(%wt)	40以下	—	小	中	—	—	—	
粒径判定実績率 (%)	55以上	55~ 60		56	53以上	62~ 67	—	
単 位 容 積 重 量 (TON/m ³)	—	1.45~ 1.55		1.13 (軽い)	—	1.60~ 1.75	—	
塩 分 (% w t)	0.1以下	—		—	—	—	—	

(備考) JIS A5004、JIS A5005、JIS A5308

表Ⅶ-5-3 セメントの品質評価／普通ポルトランドセメント

	単位	JIS-R5210('86)	標準品(日本)	バングラ産	
0) 比重	—	—	3.16	—	
1) 比表面積	cm ² /g	≥2,500	3,360	2,600~3,300	
2) 凝結 始発	min.	>60	2 hr. 34min.	130~180min.	
終結	hr.	<10 膨張による	3 hr. 32min.	170~220min.	
3) 安定性	—	0%膨張なし	—	0.5~2.0	
4) 圧縮強さ 3日		≥70	150	232~281	
5) 化学成分	7日	kg/cm ²	≥150	245	295~352
	28日		≥300	407	387~457
	CaO	% not	—	63.7	62.5~65.0
6) 組成化合物	SiO ₂		—	21.6	20.5~22.0
	Al ₂ O ₃		—	5.1	4.5~6.5
	Fe ₂ O ₃		—	3.0	2.5~4.0
	MgO		≤5	1.7	1.0~3.0
	SO ₃		≤3	2.0	1.5~3.0
	Ign Loss		≤3	1.0	1.0~3.0
混和材	C ₃ S		—	50	16~52
	C ₂ S		—	26	20~29
	C ₃ S		—	9	7~10
	LSF			—	0.88~0.94
		%	≤5	—	—

NOTE : Chittagon Cement Clinker Grinding Co., Ltd. (BS-12/1978)

[The page contains extremely faint and illegible text, likely due to low contrast or scanning quality. The text is arranged in several paragraphs, but the individual words and sentences cannot be discerned.]

JICA