

permeable and capable of supplying oxygen to the root zone, and they also have high moisture and fertilizer holding capacities. The ratio of coarse soils to the geographical area is used as an index to evaluate the productivity of the soil in this categorization.

(c) Land Use

The cultivated area in the related districts of the Sharda canal command amounts to about 2.4 million ha or 70% of the geographical area. While, the alkalinity and salinity affected area is estimated to be 98 thousand ha or 4% of the geographical area. To prevent the cultivated area from degrading, the area with higher ratio of cultivated area in related district will be given high priority for development. Then, the ratio of the cultivated area to the geographical area is taken as an index of the categorization of the Study area.

The result of categorization of salinity/alkalinity affected condition is as shown in Table I.3.

1.2 Categorization from Socio-Economic Conditions

(1) Farm Economy Condition

(a) Farm Income

Although the main crops in the Study area are wheat, paddy and sugar cane, the cropping patterns differ much with locations. In Hardoi and Rae Bareli districts, wheat cultivation prevails, with the ratio of 5 to 10 times of wheat cropping areas to paddy cropping areas. Whereas, in Pilibhit, Shahjahanpur, Lucknow and Unnao districts, paddy cropping area is much greater, by about 2 times. Sugar cane cultivation which requires annual irrigation is much practiced in Pilibhit, Shahjahanpur, Kheri and the northern part of Hardoi district. Since cropping systems are closely related to farm income, the gross income of these three main crops is used to evaluate farm economic conditions.

(b) Farm holdings

The average operational holding in the Study area is less than 1 ha, except in Pilibhit and Kheri Districts which are located upstream of the Hardoi Branch. Marginal operational holdings of less than 1 ha tended to increase in all districts during the 5 years from 1980/81 to 1985/86, at rates of 2% to 12%. The average holding and rate of increase of marginal operational holdings are used as another index for evaluation of farm economic conditions.

(2) Agricultural Support Service Conditions

(a) Fertilizer Storage and Fertilizer Use

The fertilizer supply service is an important agricultural support service. To evaluate the present development condition of this service, the capacity of the fertilizer storage provided in the area and fertilizer use actually introduced are employed.

(3) Social Infrastructure Development Conditions

(a) Rural electrification

Rural electrification is evaluated by use of the rate of electrified villages to the total numbers of villages.

(b) Rural water supply facility development conditions

The development condition of rural water supply facilities is evaluated by the numbers of wells and taps.

The results of categorization of socio-economic conditions is as shown in Table I.4.

2. Selection of the Representative Areas

2.1 Selection Criteria for Representative Area

(1) Selection procedure

The priority ranking for selection of the representative areas is determined by means of a scoring system on the basis of the results of the categorization, as shown below.

- (a) to determine the parameters for selection on the basis of the categorization of the Study area,
- (b) to calculate the scores for respective parameters and to determine the priority ranking according to the calculation formula with weighting to each parameter
- (c) To check the items such as CAD work progress, environmental impacts through a screening method
- (d) to select the representative area on the canal system basis with a view to making possible efficient water management

(2) Selection Criteria

Development of the representative areas is aimed to sufficiently and effectively promote the Sharda Canal CAD Project. Therefore, the basic factors that the representative areas to be selected should meet as a model development are established as follows:

- (a) Strong development wish in terms of development strategy of the Government of India and Uttar Pradesh State Government and farmers
- (b) No existence of on-going works of CAD program
- (c) Representative model area for implementation of Sharda Canal CAD Project
- (d) Area requiring modernization of the existing irrigation facilities to ensure efficient operation and maintenance
- (e) No adverse environmental effect upon implementation
- (f) Urgency of the development
- (g) High economic effect of the development
- (h) Strong development impact with a view of social and economic aspects

The above-mentioned basic factors are duly taken into account the scores of parameters to be used in determination of priority ranking. The relationship between the basic factors and selection parameters is shown in the matrix in Table I.5, together with the scores thus determined.

(3) Scoring method of priority ranking

The priority ranking for selection of the representative areas is determined by the following calculation formula:

Formula for scoring:

$$PR = 50\%TS + 50\%SE$$

where, PR : Total marks for selection

TS : Marks for technical aspects

These marks are determined for irrigation condition, poor drainage condition and alkalinity/salinity condition

SE : Marks for socio-economic aspects

(a) parameters and marks of technical aspects

i) Irrigation condition

$$TSi = 35\%AI + 35\%FC + 15\%GC + 15\%DG$$

where, TS_i : Total marks to be determined from irrigation conditions

AI : Actual irrigation rate

FC : Facilities condition

GC : Irrigation rate by government canals

DG : Dependency of ground water in irrigation

ii) Poor drainage condition

$$TSd = 35\%DI + 35\%PD + 30\%DC$$

where, TS_d : Total marks to be determined from poor drainage condition

DI : Drainability index

PD : Poor drainage area rate

DC : Drainage canal density

iii) Salinity and alkalinity condition

$$TSs = 60\%SA + 20\%CS + 20\%CA$$

where, TSs : Total marks to be determined from salinity/alkalinity condition
SA : Salt affected soil rate
CS : Coarse soil rate
CA : Cultivated area rate

(b) Parameters and marks for socio-economic aspects

$$SE = 40\%FE + 30\%AS + 30\%SI$$

where, SE : Total marks to be determined from socio-economic aspect
FE : Farm economy index
AS : Agricultural support service condition
SI : Social infrastructure development condition

The result of the evaluation are shown in Table I.1 to Table I.4. The priority ranking for selection is as shown in Table I.6, and the locations of the priority areas of the respective categories are as shown in Fig. I.2 to Fig. I.4.

(4) Screening by parameters

(a) Progress of OFD works

The OFD works of Sharda Canal Command are being executed. The progress of OFD works in the respective blocks in the Study area as of September 1990 is as shown in Table I.7. In accordance with the result of the Minutes of Meeting of the Steering Committee held on October 16, 1990, the on-going areas of OFD works are excluded from selection of the representative areas through the screening procedure.

(b) Adverse environmental effect upon implementation

The adverse environmental effects upon implementation are preliminarily assessed in terms of the physical, ecological and human activity aspects.

The prediction of effects of the influence of the physical condition is related to the impacts of drainage, and the water quality of the marshy areas and their surroundings. The marshy areas and their surroundings which are located far from the main drainage streams and topographically depressed are difficult to sufficiently drain and are, therefore, susceptible to expansion of water logging and water contamination with introduction of advanced irrigation farming.

The impacts of the ecological aspect is assessed with respect to the effect on the ground water regime. The parameter used in the ground water regime is the recovery of the ground water tables. The ground water tables of post monsoon in the driest year 1987 in some areas did not recover up to the levels of the preceding pre-monsoon. To avoid an adverse effect on the ground water regime in extremely less recovered areas, groundwater development in such areas as conjunctive use will be avoided.

No significant adverse effect on human activity is predicted under the present Study.

The result of the prediction of the above effects is shown in Table I.8

2.2 Selection of Representative Areas

Based on the results of the priority ranking, the representative area in terms of the canal system is determined as shown in Table I.9. Consequently, the following areas with the total CCA of 57,301 ha are selected as the representative areas, of which locations are as shown in Fig. I.5.

- 1) Representative area for improvement of irrigation condition
 - District : Lucknow
 - Block : Sarojini Nagar
 - Canal system : Lucknow Branch
Amausi Distributary
 - CCA : 14,862 ha

2) Representative area for improvement of poor drainage condition

District : Hardoi
Block : Sursa
Canal system : Hardoi Branch
Badaicha Distributary
CCA : 17,313 ha

3) Representative area for salinity and alkalinity affected area

District : Unnao
Block : Purwa
Canal system : Purwa Branch
Purwa Distributary
CCA : 12,252 ha

The general features of the selected 3 representative areas are described below:

(1) Sarojini Nagar (Lucknow District)

Sarojini Nagar is located in the downstream reaches of the Lucknow Branch and is irrigated by the Amausi Distributary. The CCA is 14,862 ha, of which 21% is annually irrigated by the Sharda irrigation system. On the other hand, tubewells for irrigation which are densely distributed in this area shows high dependency of irrigation on ground water as a supplemental irrigation water source. The total length of irrigation canals amounts to 105 km of which 42% has reduced functions due to insufficient O/M and require rehabilitation.

Major drainage rivers of this area are the Sai River which flows along the western edge of this area and tributaries of the Gomti River which flow along the eastern edge. The distance to the major drainage rivers is comparatively far in this area, which is one of the constraints for development of proper drainage in conjunction with the high midland percentage (74%) of this area. Poor drainage and waterlogging/marshy land occupies 4.1% of the midland, where drainage improvement is insufficient due to the above-mentioned constraints. The cultivated area rate in this area is 48% which is relatively low among other areas in the Hardoi Branch Command Area. 35% of the cultivated area has alkaline soil most of which pH is 8.5 to 9.0, and 25% of the cultivated area has coarse textured soil which has fine porosity and high water/nutrient holding capacity. Alkalinity or salinity problems in this area are not very serious due to these soil characteristics.

Wheat cultivation is predominant in this area and the cropping system and farming practices largely depend on upland crop cultivation as a consequence. Sugarcane is also extensively cultivated here and farmers' income is about average for the Hardoi Branch Command.

(2) Sursa (Hardoi District)

This area is located in the middle part of the Hardoi Branch Command and is irrigated by the Hardoi Branch (direct) and Badaicha Distributary. CCA of this area is 17,313 ha and the annual irrigation rate to C.C.A is 43%. The Sharda Canal System irrigate relatively low percentage of CCA with 94 km irrigation canals in total. On the other hand, ground water is not utilized for irrigation very much. Judging from these, it can be said that farming in this area largely depends on rainfall, which results in low irrigation sufficiency of 61% in Kharif and 18% in Rabi.

The main drainage river of this area is the Sai River and 86% of the total area is located in the mid-land where drainage improvement is relatively difficult comparing with upland and lowland. Drainage canal density is high (133 m/ha), but waterlogging and marshy land still occupies 3.1% of the total area, which means that present drainage system does not function well.

The cultivated area rate of this area is 61%, of which 30.4% has alkaline soil. Alkaline soil consists of 13.2% strong alkaline (over pH9.0) and 17.2% alkaline (pH8.5-pH9.0) soil. Coarse textured soil is less distributed (14.5%) in the area. Judging from the above-mentioned conditions, drainage improvement is a high priority in this area so as to prevent farmland from deterioration. The major crop is paddy and sugarcane cultivation is rare. Farmers' income is relatively low in the Hardoi Branch Command.

(3) Purwa (Unnao District)

This area lies in the middle part of the Purwa Branch Command irrigated by the Purwa Branch (direct) and the Purwa distributary. CCA of this area is 12,252 ha of which 49% is annually irrigated by the Sharda Canal. Consequently dependency on ground water is low. The total length of the irrigation canal is 97 km of which 22% has reduced functions and requires rehabilitation.

The main drainage river of this area is the Loni River. The percentage of midland is high (88%). Waterlogging or marshy land occupies 2.7% of the total area and the drainage

canal density is medium (67 m/ha) in the Hardoi Branch Command which shows that the drainage improvement has not been done properly.

The cultivated area rate of this area is 60% of which 39% has alkaline soil, and half of alkaline soil shows strong alkalinity (pH over 9.0).

Though the cultivated area of wheat and paddy is almost the same, it is taken as the paddy area in the Hardoi Branch Command. Farmers' income levels are low and the land holding size is small.

In addition to the above-mentioned three selected areas, Sataon area with a CCA of about 8,000 ha under District Rae Bareli was included as a representative CAD area for improvement of irrigation condition according to the result of discussion in the Steering Committee of the Study held on December 27, 1990.

The field works of Stage II and agricultural planning was carried out for those four Representative CAD areas.

TABLES

Table I.2 Priority Ranking for Selection of Representative Area by Drainage

Sl. No.	Name of Block	Name of District	1. Drainage Index			2. River Drainage Area Base			3. Drainage Canal Density			Village/ Ward	Ranking
			(A) Geographical Area (Sq. Km.)	(B) Midland Area (Sq. Km.)	(C) (A/B) Percentage (%)	(D) Midland Area (Sq. Km.)	(E) (D/B) Percentage (%)	(F) (D/C) Percentage (%)	(G) (D/B) Percentage (%)	(H) (D/C) Percentage (%)	(I) Canal Length (Km.)		
1	Panapur	Puducherry	121.574	75.992	62.5	40	794	38.3	48.2	40	40	50	
2	Barid	Puducherry	46.801	32.162	68.7	40	32.162	72.8	48.2	100	54	54	
3	Puduvai	Puducherry	30.681	20.453	66.7	40	20.453	23.9	15.9	100	54	54	
4	Shivajinagar	Puducherry	32.168	18.254	56.8	40	18.254	34.6	23.4	100	61	61	
5	Rameswaram	Puducherry	31.928	22.027	69.0	40	22.027	29.3	22.6	60	47	47	
6	Pattanam	Puducherry	47.170	34.109	72.3	60	34.109	21.3	42.3	40	66	66	
7	Pattanam	Puducherry	33.655	24.861	73.9	60	24.861	41.2	17.2	100	67	67	
8	Shivajinagar	Puducherry	30.681	21.467	70.0	60	21.467	54.2	17.7	100	67	67	
9	Shivajinagar	Puducherry	34.673	25.006	72.1	60	25.006	61.4	0.0	20	46	46	
10	Haravan	Puducherry	29.025	22.332	77.0	60	22.332	72.8	24.8	40	52	52	
11	Thiruvananthapuram	Puducherry	31.233	23.369	74.8	60	23.369	62.2	15.4	100	67	67	
12	Haravan	Puducherry	32.827	25.994	79.2	60	25.994	50.2	65.9	97.4	60	60	
13	Shivajinagar	Puducherry	31.278	17.869	57.1	30	17.869	1.85	0.0	20	44	44	
14	Shivajinagar	Puducherry	37.782	20.276	53.7	30	20.276	1.1	0.0	100	66	66	
15	Shivajinagar	Puducherry	33.683	28.777	85.5	30	28.777	87.1	12.1	100	67	67	
16	Shivajinagar	Puducherry	33.683	23.085	68.6	40	23.085	1.92	5.3	20	54	54	
17	Kottayam	Puducherry	29.485	19.473	66.1	40	19.473	5.7	9.4	80	23	23	
18	Kottayam	Puducherry	24.864	21.688	87.2	30	21.688	1.31	31.7	20.3	66	66	
19	Madhavaram	Puducherry	28.016	20.202	72.1	30	20.202	5.9	43.9	40	52	52	
20	Madhavaram	Puducherry	31.069	23.827	76.7	30	23.827	4.7	65.5	100	67	67	
21	Madhavaram	Puducherry	31.962	23.075	72.2	30	23.075	1.895	43.1	27	69	69	
22	Madhavaram	Puducherry	27.842	21.620	77.7	30	21.620	1.788	68.4	33.3	40	40	
23	Madhavaram	Puducherry	31.140	17.906	57.5	30	17.906	1.25	6.6	40	67	67	
24	Madhavaram	Puducherry	25.382	21.364	84.2	30	21.364	2.45	36.4	100	73	73	
25	Madhavaram	Puducherry	21.892	13.786	62.5	40	13.786	5.9	33.1	62.2	61	61	
26	Madhavaram	Puducherry	22.324	18.023	80.8	30	18.023	6.6	29.1	62.2	61	61	
27	Madhavaram	Puducherry	33.435	28.358	84.8	30	28.358	1.150	21.3	18.7	20	20	
28	Madhavaram	Puducherry	35.975	28.478	79.2	30	28.478	2.01	15.2	75.6	51	51	
29	Madhavaram	Puducherry	34.652	25.672	74.1	30	25.672	8.03	0.0	0.0	20	20	
30	Madhavaram	Puducherry	25.701	21.795	84.8	30	21.795	8.09	82.5	102.0	87	87	
31	Madhavaram	Puducherry	22.428	17.895	79.8	30	17.895	6.63	40.6	62.2	61	61	
32	Madhavaram	Puducherry	27.950	21.026	75.3	30	21.026	1.622	26.1	29.0	20	20	
33	Madhavaram	Puducherry	27.950	21.124	75.6	30	21.124	7.72	55.2	45.6	40	40	
34	Madhavaram	Puducherry	34.177	27.825	80.5	30	27.825	5.8	25.2	101.4	73	73	
35	Madhavaram	Puducherry	27.331	21.713	79.1	30	21.713	1.47	46.6	55.3	60	60	
36	Madhavaram	Puducherry	25.683	13.023	50.7	20	13.023	1.701	20.4	14.7	20	20	
37	Madhavaram	Puducherry	27.903	22.511	80.7	30	22.511	7.14	63.9	89.5	80	80	
38	Madhavaram	Puducherry	33.483	31.162	93.1	100	31.162	9.72	46.2	46.2	60	60	
39	Madhavaram	Puducherry	33.422	18.827	56.3	20	18.827	7.8	29.7	102.8	69	69	
40	Madhavaram	Puducherry	24.859	14.129	56.9	20	14.129	6.47	29.6	45.7	55	55	
41	Madhavaram	Puducherry	28.823	20.226	70.2	30	20.226	1.081	23.1	26.9	40	40	
42	Madhavaram	Puducherry	23.227	20.308	87.4	30	20.308	5.84	37.0	56.8	60	60	
43	Madhavaram	Puducherry	33.881	28.054	83.1	30	28.054	8.19	20.2	24.7	20	20	
44	Madhavaram	Puducherry	25.556	16.725	65.5	40	16.725	1.89	10.4	100	61	61	
45	Madhavaram	Puducherry	28.922	14.724	50.9	20	14.724	3.77	52.3	38.0	60	60	
46	Madhavaram	Puducherry	25.550	19.792	77.5	30	19.792	8.5	49.2	49.2	60	60	
47	Madhavaram	Puducherry	22.204	17.746	79.9	30	17.746	6.47	14.9	20.0	20	20	
48	Madhavaram	Puducherry	22.276	13.216	59.4	20	13.216	7.1	14.2	300.0	100	100	
49	Madhavaram	Puducherry	25.511	17.733	69.5	40	17.733	30	6.4	213.3	100	100	
50	Madhavaram	Puducherry	26.474	18.291	70.0	30	18.291	2.84	84.6	228.8	67	67	
Total/Average			1,525,626	1,150,149	75.2		79,995	33,995	1,995	56.3			

100-90	100
80-90	80
60-90	60
40-90	40
20-90	20

100-50	100
75-100	75
50-100	50
25-50	25
0-50	0

100-50	100
75-100	75
50-100	50
25-50	25
0-50	0

100-50	100
75-100	75
50-100	50
25-50	25
0-50	0

Table I.3 Priority Ranking for Selection of Representative Area by Alkalinity

Sl. No.	Name of Block	Name of District	1. Soil Acidity Soil			2. Organic Soil Rate			3. Chlorides Area Rate			Weighted Index	Ranking	
			(A) Cation Exchange Capacity (meq/100g)	(B) Exchangeable Sodium Percentage (ESP)	(C) Modern Sodium pH 9.0-9.5 (meq/100g)	(D) (B/A) Percentage	(E) (C/A) Percentage	(F) (D-E) Percentage	(G) Geographical Mark (CS)	(H) Organic Soil (meq/100g)	(I) (G-H) Percentage			(J) (I-H) Percentage
1	Prantpur	Purbhli	21.055	1.181	21.055	1.6	24.2	60	131.574	21.691	21.6	60	60	73
2	Barda	Subathapur	38.652	573	11.016	2.4	28.3	33	46.851	12.004	24.6	60	109	10
3	Prantpur	Subathapur	24.650	575	4.822	2.3	19.6	24	30.601	8.622	28.2	60	92.7	10
4	Subhali	Subathapur	22.664	598	3.620	2.2	22.9	28	29.188	8.828	30.3	60	90.4	22
5	Bhuvakhem	Subathapur	24.386	757	6.217	3.1	25.1	32	31.928	8.497	26.6	60	76.4	15
6	Prantpur	Subathapur	26.652	1687	10.884	2.9	27.9	34	67.879	19.178	40.4	100	77.3	60
7	Prantpur	Subathapur	21.066	5184	5.184	2.5	25.7	30	31.685	8.271	24.0	60	71.4	60
8	Talapat	Subathapur	21.832	349	5.834	1.6	21.9	29	30.621	8.176	26.7	60	70.5	80
9	Subhali	Subathapur	25.859	694	6.181	2.7	23.9	29	34.673	7.906	22.3	60	74.6	34
10	Harvaeran	Subathapur	17.621	990	3.662	5.6	20.7	32	29.033	6.098	21.0	60	60.9	60
11	Talapat	Subathapur	20.004	616	3.442	3.2	16.7	23	31.233	6.924	20.6	60	64.0	48
12	Barda	Subathapur	21.474	638	6.820	2.8	26.5	32	32.827	6.978	28.0	60	71.5	15
13	Subhali	Subathapur	21.873	1438	1.438	5.9	6.3	13	31.478	1.438	38.8	80	69.3	60
14	Alimul	Subathapur	25.216	888	5.222	3.3	24.3	32	37.700	7.277	19.3	40	67.1	60
15	Subhali	Subathapur	20.240	674	6.272	3.3	31.6	38	33.628	4.876	14.5	40	60.5	60
16	Subhali	Subathapur	21.653	1164	2.922	5.4	13.5	24	40.339	9.712	28.7	60	64.0	48
17	Kodvran	Subathapur	19.227	692	1.842	3.5	9.4	16	29.482	8.251	29.0	60	67.0	60
18	Kodvran	Subathapur	13.472	1611	1.611	12.0	38.8	64	24.824	3.880	14.8	40	54.0	60
19	Mudharel	Subathapur	9.676	450	1.664	4.7	17.4	27	28.316	6.706	22.4	60	33.3	20
20	Subathapur	Subathapur	21.083	1687	5.219	5.1	38.4	41	31.689	7.022	22.6	60	67.4	60
21	Subhali	Subathapur	16.733	1467	6.973	9.0	39.1	47	31.458	7.528	24.1	60	57.4	2
22	Bardar	Subathapur	16.312	1681	4.422	10.3	27.1	48	27.842	6.097	21.9	60	38.6	40
23	Harvaeran	Subathapur	14.455	838	2.802	4.1	18.0	28	40.214	3.229	22.6	60	50.1	60
24	Mal	Subathapur	17.623	61	4.801	2.4	27.2	32	25.382	3.172	12.5	40	49.4	60
25	Malharel	Subathapur	14.733	1469	3.187	8.8	21.6	41	21.629	6.897	32.7	80	69.5	60
26	Bardar	Subathapur	16.450	2485	2.485	6.7	16.4	30	24.850	3.924	17.5	40	40.0	60
27	Subathapur	Subathapur	18.385	2428	3.158	13.2	17.4	44	38.455	5.647	24.1	60	47.8	20
28	Malharel	Subathapur	21.137	3406	2.307	16.1	16.9	49	35.920	5.394	15.3	40	39.0	60
29	Garvran	Subathapur	17.653	4176	1.76	23.7	12	48	36.672	7.381	21.3	60	20.9	40
30	Alimul	Subathapur	14.972	1626	4.255	11.0	29.2	51	25.700	4.985	12.1	40	56.7	60
31	Garvran	Subathapur	16.621	333	1.925	4.8	18.4	22	23.628	4.832	19.3	40	38.2	60
32	Subathapur	Subathapur	18.517	1182	2.950	6.0	15.4	28	27.996	5.706	16.6	40	46.2	60
33	Prantpur	Subathapur	15.242	666	2.427	3.4	12.4	19	27.996	5.091	28.9	60	69.8	60
34	Harvaeran	Subathapur	20.916	1430	4.261	7.6	20.4	35	34.177	3.926	17.4	40	45.0	60
35	Harvaeran	Subathapur	17.778	2797	2.201	15.7	12.4	40	27.131	4.045	14.8	40	55.0	60
36	Subathapur	Subathapur	15.084	1602	2.453	10.6	16.3	28	25.683	4.787	42.0	100	58.7	60
37	Harvaeran	Subathapur	18.054	2455	1.710	18.0	2.4	43	27.893	4.949	17.8	40	64.9	60
38	Bardar	Subathapur	18.792	5468	3.665	27.8	27.1	83	33.493	4.118	12.3	40	55.4	60
39	Subathapur	Subathapur	21.120	1478	2.116	6.3	19.0	23	33.628	15.028	42.4	100	63.3	60
40	Subathapur	Subathapur	21.212	1184	3.4	5.8	1.7	70	34.698	15.892	45.3	100	69.8	60
41	Subathapur	Subathapur	17.880	4014	3.166	22.5	17.7	63	28.095	8.522	29.5	60	61.9	60
42	Prantpur	Subathapur	14.190	2422	3.074	17.1	10.2	56	23.977	3.317	14.1	40	50.2	60
43	Subhali	Subathapur	19.892	2478	2.426	14.5	12.2	41	33.880	5.760	17.0	40	38.7	40
44	Subhali	Subathapur	16.465	2481	1.248	15.1	7.6	38	25.526	7.897	30.9	60	64.4	60
45	Subathapur	Subathapur	16.921	1437	6.929	9.0	3.7	22	26.929	10.826	40.3	100	63.1	60
46	Subathapur	Subathapur	18.667	1465	1.465	8.2	6.0	24	24.538	6.490	24.4	60	70.7	80
47	Subathapur	Subathapur	14.917	1612	1.612	12.1	8.5	34	23.206	5.059	21.8	60	65.1	60
48	Subathapur	Subathapur	13.923	666	7.64	4.3	5.3	13	22.776	1.407	20.7	80	60.7	60
49	Subathapur	Subathapur	13.872	483	1.264	3.6	9.3	16	25.511	1.108	28.1	60	53.3	40
50	Subathapur	Subathapur	17.692	1499	4.192	7.4	18.5	22	26.628	2.254	21.4	60	66.4	60
Total/Average			1,022,651	71,540	195,651	7.2	19.5	34	1,497,636	324,738	38.6	100	64.2	60

Ranking: 100, 80, 60, 40, 20, 0

Weighted Index: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Percentage: 100, 80, 60, 40, 20, 0

Table I.4 Priority Ranking for Selection of Representative Area by Socio-Economic(2/2)

Sl. No.	Name of District	3. Social Infrastructure Index										Weighted Index	Ranking	
		A. Essential Village					B. Welfare/Health							Weighted Index (SI)
		Total Village (No.)	Electrified Village (No.)	Percentage (%)	Mark (SI)	Population	Water Supply (No.)	Health (No.)	Type (No.)	Total (No.)	Density (Per Sq Km)			
1	Pargana	388	277	71	59	60	21,933	0	9	9	34,937	100	80	27
2	Pargana	182	61	33	32	30	107,721	40	0	40	2,697	50	70	42
3	Pargana	172	70	41	37	80	82,023	137	0	137	590	20	50	50
4	Shahdol	169	62	37	30	80	94,111	64	0	64	1,420	40	60	36
5	Shahdol	163	54	33	33	80	117,263	139	0	139	807	20	50	48
6	Pargana	156	106	68	46	80	141,301	202	0	202	701	61	80	21
7	Pargana	125	38	30	30	80	112,687	121	0	121	924	20	50	51
8	Togaon	114	38	33	33	80	101,513	111	0	111	915	20	50	39
9	Shahdol	111	64	57	41	80	104,083	128	0	128	732	20	50	31
10	Shahdol	91	50	55	44	80	116,184	88	0	88	1,321	40	60	31
11	Pargana	88	47	53	40	60	107,008	87	0	87	1,238	40	60	31
12	Pargana	154	44	29	31	80	176,851	124	0	124	1,040	40	60	23
13	Saon	98	49	51	40	60	93,891	83	0	83	1,055	40	60	31
14	Shahdol	96	44	46	46	80	111,916	93	0	93	1,418	40	60	20
15	Saon	80	36	45	43	80	121,676	83	0	83	1,484	40	60	23
16	Shahdol	172	81	47	39	80	110,651	121	0	121	881	20	50	40
17	Kolhan	86	51	59	50	80	101,844	86	0	86	1,184	40	60	23
18	Kolhan	46	36	78	40	60	91,690	46	0	46	1,993	40	60	44
19	Malhan	100	38	38	38	80	105,573	86	0	86	1,080	40	60	44
20	Malhan	97	24	24	24	80	106,829	97	0	97	1,101	40	60	19
21	Saon	97	45	46	46	80	105,912	95	0	95	1,115	40	60	22
22	Shahdol	80	38	47	47	80	105,283	80	0	80	1,173	40	60	23
23	Pargana	82	61	74	74	80	71,493	74	0	74	1,077	40	60	44
24	Malhan	87	47	54	54	80	97,904	87	0	87	1,075	40	60	38
25	Malhan	100	36	36	36	80	100,226	98	0	98	1,092	40	60	47
26	Kolhan	101	67	66	66	80	99,893	81	0	81	1,229	40	60	29
27	Saon	106	51	48	48	80	109,036	90	0	90	1,278	40	60	22
28	Malhan	113	61	54	54	80	115,873	113	0	113	1,213	40	60	39
29	Shahdol	117	74	63	63	80	109,750	114	0	114	861	20	40	49
30	Aura	91	50	55	55	80	97,053	91	0	91	1,038	40	60	7
31	Shahdol	85	37	43	43	80	90,731	77	0	77	1,243	40	60	2
32	Pargana	76	48	63	63	80	97,246	66	0	66	1,392	40	60	15
33	Pargana	105	49	47	47	80	97,286	60	1	61	1,093	40	60	7
34	Shahdol	143	21	15	15	100	106,254	135	0	135	769	20	70	2
35	Shahdol	133	50	37	37	80	102,650	132	0	132	777	20	50	15
36	Shahdol	158	37	24	24	80	98,424	88	1	89	1,081	40	60	11
37	Shahdol	129	47	36	36	80	103,103	115	1	116	911	20	50	11
38	Shahdol	94	50	53	53	80	115,906	67	0	67	1,215	40	60	15
39	Shahdol	79	39	49	49	80	107,942	74	0	74	1,429	40	60	15
40	Shahdol	111	27	24	24	100	124,121	90	3	93	1,307	40	60	2
41	Shahdol	118	28	24	24	100	97,468	90	0	90	1,029	40	60	2
42	Pargana	100	51	51	51	80	93,988	111	0	111	787	100	70	31
43	Shahdol	67	31	46	46	80	104,577	64	1	65	1,059	40	60	2
44	Shahdol	118	22	19	19	100	93,841	115	0	115	833	20	50	7
45	Shahdol	114	33	29	29	80	100,044	133	1	134	723	20	50	11
46	Shahdol	70	69	99	99	40	98,278	0	12	12	8,228	100	70	10
47	Shahdol	84	33	39	39	40	94,658	0	26	26	3,451	80	60	14
48	Shahdol	88	30	34	34	40	93,724	0	67	67	1,324	40	60	38
49	Shahdol	173	14	94	94	40	112,754	0	124	124	509	20	30	51
50	Shahdol	172	12	99	99	40	94,820	16	38	74	1,231	40	60	47
Total/Average		5,827	2,869	49			5,195,413	4,720	307	4,937	1,189			

Density (Per Sq Km) (SI) 100 80 60 40 20
 Index (SI) 100 80 60 40 20
 Index (SI) 100 80 60 40 20
 Index (SI) 100 80 60 40 20

Percentage Mark (SI) 100 75 50 25
 Index (SI) 100 75 50 25
 Index (SI) 100 75 50 25

Table I.5 Relation between Basic Factors and Selection Parameters by Matrix

Description	Selection Criteria								Weighting				Each item	
	1	2	3	4	5	6	7	8	Irr.	Drain	Soil	Socio		
I. SELECTION PARAMETERS														
A Natural Conditions														
1. Irrigation Condition	X		X						50					100
1) Irrigation Rate						X	X	X						35
2) Canal Conditions				X		X	X							35
3) Irrigation Rate by Government Canal						X								15
4) Dependency on Ground Water Irrigation						X								15
2. Poor Drainage Condition	X		X						50					100
1) Drainability							X	X						35
2) Poor Drainage Area Rate						X	X							35
3) Drainage Canal Rate						X	X							30
3. Salinity/Alkalinity Affected Condition	X										50			100
1) Alkalinity						X	X	X						60
2) Soil Texture							X	X						20
3) Land Use							X							20
B Socio-Economy Conditions														
1. Farm Economy Conditions	X								50	50	50	100		100
1) Farm Income						X	X	X						50
2) Farm Holding						X	X	X						50
2. Agricultural Support Service Condition	X											30		100
1) Fertilizer Storage								X						50
2) Fertilizer Use								X						50
3. Social Infrastructure Development Condition	X											30		100
1) Rural Electrification								X						50
2) Rural Water Supply Facility								X						50
Development Conditions														
Total									100	100	100			
II. SCREENING														
1. Progress of CAD Works		X												
2. Adverse Environmental Effects					X									

Remarks : x : item concerned

Selection Criteria

1. Strong development wish of Central and State Government and farmers
2. Non-existence of on-going works of CAD program
3. Representing a model for implementation of Sharda CAD Project
4. Area requiring modernization of existing irrigation facilities
5. No adverse environmental effect upon implementation
6. Urgency of the development
7. High economic effect of the development
8. Strong development impact from viewpoint of social and economic aspects

Table I.6 Priority Area for Selection of Representative Area

Sl. No.	Name of Block	Name of District	Weighted Mark				Final Mark					
			Irrigation	Drain	Soil	Socio-economy	Irrigation Mark	Irrigation Ranking	Drain Mark	Drain Ranking	Soil(Alkalinity) Mark	Soil(Alkalinity) Ranking
1.	Puranpur	Pilibhit	65	40	60	58	61.5	9	49.0	47	59.0	27
2.	Banda	Shahajhanpur	44	54	68	52	48.0	40	53.0	40	60.0	23
3.	Puwayan	Shahajhanpur	44	54	56	43	43.5	48	48.5	49	49.5	44
4.	Sindhauri	Shahajhanpur	35	61	60	55	45.0	47	58.0	34	57.5	31
5.	Bhawalkhera	Shahajhanpur	39	47	64	46	42.5	49	46.5	50	55.0	34
6.	Pasgawan	Kheri	41	46	72	61	51.0	29	53.5	38	66.5	11
7.	Pihani	Hardoi	63	67	64	56	59.5	12	61.5	23	60.0	23
8.	Todarpur	Hardoi	29	67	52	53	41.0	50	60.0	25	52.5	40
9.	Shahabad	Hardoi	38	46	52	56	47.0	44	51.0	46	54.0	37
10.	Hariyawan	Hardoi	39	53	60	56	47.5	42	54.5	36	58.0	30
11.	Tadiyawan	Hardoi	54	67	48	56	55.0	20	61.5	23	52.0	41
12.	Bawan	Hardoi	42	60	64	59	50.5	33	59.5	30	61.5	20
13.	Sandi	Hardoi	53	48	40	56	54.5	22	52.0	43	48.0	46
14.	Ahiraori	Hardoi	43	66	56	62	52.5	25	64.0	17	59.0	27
15.	Sursa	Hardoi	43	87	56	59	51.0	29	73.0	5	57.5	31
16.	Bilgram	Hardoi	59	54	48	53	56.0	18	53.5	38	50.5	42
17.	Kothawan	Hardoi	46	61	36	59	52.5	25	60.0	23	47.5	47
18.	Kachhona	Hardoi	47	66	76	50	48.5	39	58.0	34	63.0	15
19.	Madhogani	Hardoi	52	53	40	50	51.0	29	51.5	44	45.0	49
20.	Malawan	Hardoi	33	67	72	63	48.0	40	65.0	14	67.5	9
21.	Sandila	Hardoi	42	60	80	60	51.0	29	60.0	25	70.0	5
22.	Behdar	Hardoi	39	67	68	59	49.0	37	63.0	20	63.5	14
23.	Bharawan	Hardoi	48	67	48	50	49.0	37	58.5	31	49.0	45
24.	Mal	Lucknow	55	73	56	54	54.5	22	63.5	18	55.0	34
25.	Malihabad	Lucknow	45	61	76	48	46.5	45	54.5	36	62.0	18
26.	Kakori	Lucknow	66	60	44	57	61.5	9	58.5	31	50.5	42
27.	Sarojini Nagar	Lucknow	73	60	64	60	66.5	3	60.0	25	62.0	18
28.	Mohanlalganj	Lucknow	73	53	64	53	63.0	6	53.0	40	58.5	29
29.	Gosaiganj	Lucknow	84	53	68	45	64.5	5	49.0	47	56.5	33
30.	Auras	Unnao	29	87	76	72	50.5	33	79.5	1	74.0	3
31.	Ganjmuradabad	Unnao	49	67	44	75	62.0	7	71.0	6	59.5	25
32.	Bangarnau	Unnao	49	60	44	66	57.5	15	63.0	20	55.0	34
33.	Fatchpur Chaurasi	Unnao	32	60	36	72	52.0	27	66.0	12	54.0	37
34.	Hasanganj	Unnao	36	73	56	75	55.5	19	74.0	3	65.5	13
35.	Mayaganj	Unnao	33	73	68	66	49.5	36	69.5	8	67.0	10
36.	Safirpur	Unnao	35	48	64	69	52.0	27	58.5	31	66.5	11
37.	Nawabganj	Unnao	49	80	68	69	59.0	13	74.5	2	68.5	7
38.	Bichhiya	Unnao	26	72	76	66	46.0	46	69.0	9	71.0	4
39.	Sikandarpur Sirosi	Unnao	42	69	56	66	54.0	24	67.5	10	61.0	21
40.	Sikandarpur Khan	Unnao	55	55	44	75	65.0	4	65.0	14	59.5	25
41.	Asoha	Unnao	49	67	84	75	62.0	7	71.0	6	79.5	2
42.	Purwa	Unnao	37	66	80	81	59.0	13	73.5	4	80.5	1
43.	Hilauli	Unnao	76	52	64	75	75.5	2	63.5	18	69.5	6
44.	Bighapur	Unnao	42	61	64	72	57.0	16	66.5	11	68.0	8
45.	Sumerpur	Unnao	26	62	56	69	47.5	42	65.5	13	62.5	17
46.	Sataon	Raebareli	97	60	52	70	83.5	1	65.0	14	61.0	20
47.	Khcero	Raebareli	55	53	60	67	61.0	11	60.0	25	63.5	14
48.	Lalganj	Raebareli	55	48	40	55	55.0	20	51.5	44	47.5	47
49.	Sareni	Raebareli	62	54	32	51	56.5	17	52.5	42	41.5	50
50.	Dalmau	Raebareli	42	67	48	58	50.0	35	62.5	22	53.0	39

50 50 50
50 50 50

Table I.7 Progress of On-Farm Works Under CAD Program
in Hardoi Command Area

Sl. No.	Name of Block	Name of District	Progress of OFD Works under CAD Program
1.	Puranpur	Pilibhit	Under Implementation
2.	Banda	Shahajhanpur	No Progress
3.	Puwayan	Shahajhanpur	No Progress
4.	Sindhauri	Shahajhanpur	Under Implementation
5.	Bhawalkhera	Shahajhanpur	Under Implementation
6.	Pasgawan	Kheri	No Progress
7.	Pihani	Hardoi	No Progress
8.	Todarpur	Hardoi	Under Implementation
9.	Shahabad	Hardoi	Under Implementation
10.	Hariyawan	Hardoi	No Progress
11.	Tadiyawan	Hardoi	No Progress
12.	Bawan	Hardoi	No Progress
13.	Sandi	Hardoi	No Progress
14.	Ahiraori	Hardoi	No Progress
15.	Sursa	Hardoi	No Progress
16.	Bilgram	Hardoi	No Progress
17.	Kothawan	Hardoi	No Progress
18.	Kachhona	Hardoi	No Progress
19.	Madhogani	Hardoi	No Progress
20.	Malawan	Hardoi	No Progress
21.	Sandila	Hardoi	No Progress
22.	Behdar	Hardoi	No Progress
23.	Bharawan	Hardoi	No Progress
24.	Mal	Lucknow	No Progress
25.	Malihabad	Lucknow	No Progress
26.	Kakori	Lucknow	No Progress
27.	Sarojini Nagar	Lucknow	No Progress
28.	Mohanlalgaoni	Lucknow	No Progress
29.	Gosaigani	Lucknow	No Progress
30.	Auras	Unnao	No Progress
31.	Ganjmuradabad	Unnao	No Progress
32.	Bangarmau	Unnao	No Progress
33.	Fatehpur Chaurasi	Unnao	No Progress
34.	Hasangani	Unnao	No Progress
35.	Mayagani	Unnao	No Progress
36.	Safirpur	Unnao	No Progress
37.	Nawabgani	Unnao	No Progress
38.	Bichhiya	Unnao	No Progress
39.	Sikandarpur Sirosi	Unnao	No Progress
40.	Sikandarpur Khan	Unnao	No Progress
41.	Asoha	Unnao	No Progress
42.	Purwa	Unnao	No Progress
43.	Hilauli	Unnao	No Progress
44.	Bighapur	Unnao	No Progress
45.	Sumerpur	Unnao	No Progress
46.	Sataon	Raebareli	No Progress
47.	Kheero	Raebareli	No Progress
48.	Lalgani	Raebareli	No Progress
49.	Sareni	Raebareli	No Progress
50.	Dalmau	Raebareli	No Progress

Table I.8 Prediction of Environmental Adverse Effects on Implementation

Sl No.	Name of Block	Name of District	Physical Aspect Drainage Condition	Ecological Aspect Ground water regime	Human Activity Aspect Employment structure
1.	Puranpur	Pilibhit	-	-	-
2.	Banda	Shahajhanpur	-	-	-
3.	Puwayan	Shahajhanpur	-	-	-
4.	Sindhauli	Shahajhanpur	-	-	-
5.	Bhawalkhera	Shahajhanpur	-	-	-
6.	Pasgawan	Kheri	-	SA	-
7.	Pihani	Hardoi	-	-	-
8.	Todarpur	Hardoi	-	-	-
9.	Shahabad	Hardoi	-	EA	-
10.	Hariyawan	Hardoi	-	-	-
11.	Tadiyawan	Hardoi	-	-	-
12.	Bawan	Hardoi	-	-	-
13.	Sandi	Hardoi	-	-	-
14.	Ahiraury	Hardoi	-	-	-
15.	Sursa	Hardoi	-	-	-
16.	Bilgram	Hardoi	-	-	-
17.	Kothawan	Hardoi	-	-	-
18.	Kachhona	Hardoi	-	-	-
19.	Madhoganj	Hardoi	-	-	-
20.	Malawan	Hardoi	-	-	-
21.	Sandila	Hardoi	-	-	-
22.	Behdar	Hardoi	-	-	-
23.	Bharawan	Hardoi	-	-	-
24.	Mal	Lucknow	-	-	-
25.	Malihabad	Lucknow	-	-	-
26.	Kakori	Lucknow	-	-	-
27.	Sarojini Nagar	Lucknow	-	-	-
28.	Mohanlalganj	Lucknow	-	-	-
29.	Gosaiganj	Lucknow	-	-	-
30.	Auras	Unnao	-	-	-
31.	Ganjmuradabad	Unnao	-	-	-
32.	Bangarmau	Unnao	-	-	-
33.	Fatehpur Chaurasi	Unnao	-	-	-
34.	Hasanganj	Unnao	SA	-	-
35.	Mayaganj	Unnao	SA	-	-
36.	Safirpur	Unnao	-	-	-
37.	Nawabganj	Unnao	EA	-	-
38.	Bichhiya	Unnao	-	-	-
39.	Sikandarpur Sirosi	Unnao	-	-	-
40.	Sikandarpur Khan	Unnao	-	-	-
41.	Asoha	Unnao	EA	-	-
42.	Purwa	Unnao	SA	SA	-
43.	Hilauli	Unnao	SA	EA	-
44.	Bighapur	Unnao	-	-	-
45.	Sumerpur	Unnao	-	-	-
46.	Sataon	Raebareli	-	EA	-
47.	Kheero	Raebareli	-	-	-
48.	Lalganj	Raebareli	-	-	-
49.	Sareni	Raebareli	-	-	-
50.	Dalmau	Raebareli	-	-	-

NOTE

EA : Extremely affected

SA : Slightly affected

Table I.9 Overall Selection of Representative Area

No	Block Name	District Name	Priority	Overall Marking	Related Branch	Related Distr'y & Minor	Selection
IRRIGATION							
1	Sataon	Raebareli	1st	83.5	Lower end of Asiwan	Maurawan Dy.	not recommended from environmental aspect
2	Hulauli	Unnao	1st	75.5	Lower end of Asiwan	Maurawan Dy.	not recommended from environmental aspect
3	Sarojini Nagar	Lucknow	1st	66.5	Lower end of Lucknow	Amausi Dy.	to be selected
4	Sikandarapur Khan	Unnao	1st	65.0	Upper part of Unnao	Mrs.	not recommended due to small size of related irrigation canals
DRAINAGE							
1	Auras	Unnao	1st	79.5	Middle part of Lucknow	Auras Dy. & Mrs.	not recommended due to small size of related irrigation canals
2	Nawabganj	Unnao	1st	74.5	Middle part of Asiwan	Bhauri Dy. & Mrs	not recommended due to small size of related irrigation canals
3	Hasanganj	Unnao	1st	74.0	Middle part of Asiwan	Hasanganj Dy. & Mrs	not recommended due to small size of related irrigation canals
4	Purwa	Unnao	1st	73.5	Middle part of Purwa	Tikar Dy. & Mrs	given priority for Alkalinity/Salinity
5	Sursa	Hardoi	1st	73.0	Middle part of Hardoi	Bhadaya Dy.	to be selected
6	Ganjmulabad	Unnao	1st	71.0	Middle part of Hardoi	Mrs	not recommended due to small size of related irrigation canals
7	Asoha	Unnao	1st	71.0	Middle part of Asiwan	Asoha Dy. & Mrs	given priority for Alkalinity/Salinity
SALINITY/ALKALINITY							
1	Purwa	Unnao	1st	80.5	Middle part of Purwa	Tikar Dy. & Mrs	to be selected
2	Asoha	Unnao	1st	79.5	Middle part of Asiwan	Asoha Dy. & Mrs	not recommended from environmental aspect
3	Auras	Unnao	1st	74.0	Middle part of Lucknow	Auras Dy. & Mr.	lower priority than the above
4	Bichhiya	Unnao	1st	71.0	Upper part of Purwa	Raipur Dy. & Mrs	lower priority than the above
5	Sandila	Hardoi	1st	70.0	Middle part of Sandila	Sandila Dy. & Mrs	lower priority than the above

FIGURES




Fig. I.1 Work Flow Chart of Selection of Representative Areas




Fig. I.2 Priority Area of Selection of Representative Area (Irrigation)



Fig. I.3 Priority Area of Selection of Representative Area (Drainage)



Fig. I.4 Priority Area of Selection of Representative Area (Alkalinity/Salinity)



Fig. I.5 Priority Area of Selection of Representative Area

ANNEX-J
IMPLEMENTATION PLAN AND
PROJECT COST

FEASIBILITY STUDY ON
IRRIGATION AND DRAINAGE DEVELOPMENT OF
SHARDA CANAL CAD PROJECT

ANNEX-J
PROJECT IMPLEMENTATION PLAN AND PROJECT COST

TABLE OF CONTENTS

	<u>Page</u>
1. Project Implementation.....	J - 1
1.1 Principal Approach to Project Implementation	J - 1
1.2 Implementation Schedule	J - 3
1.3 Organization of Project Implementation.....	J - 5
2 Project Cost	J - 8
2.1 Basic Conditions.....	J - 9
2.2 Estimate of Project Cost.....	J - 9
2.3 Breakdown of Project Cost.....	J - 10
2.4 Annual Disbursement Schedule.....	J - 11
2.5 Unit Cost Analysis.....	J - 12
2.6 Annual Operation and Maintenance Cost.....	J - 12
2.7 Cost of Replacement of Project Facilities	J - 12

LIST OF TABLES

		<u>Page</u>
Table J.1	Project Cost	J - 13
Table J.2	Breakdown of Direct Construction Cost of Sarojini Nagar Area	J - 14
Table J.3	Breakdown of Direct Construction Cost of Sataon Area (1/2 - 2/2)...	J - 15
Table J.4	Breakdown of Direct Construction Cost of Sursa Area.....	J - 17
Table J.5	Breakdown of Direct Construction Cost of Purwa Area.....	J - 18
Table J.6	Land Acquisition Cost	J - 19
Table J.7	List of Supporting Equipment.....	J - 20
Table J.8	Administration Cost	J - 21
Table J.9	Required Man-Months of Consultant Engineer	J - 22
Table J.10	Cost of Engineering Service.....	J - 23
Table J.11	Annual Disbursement Schedule.....	J - 24
Table J.12	Breakdown of Annual Disbursement Schedule (1/2 - 2/2)	J - 25
Table J.13	Unit Cost of Labour and Construction Materials	J - 27
Table J.14	List of Unit Price of Major Work Items.....	J - 28
Table J.15	Annual Operation and Maintenance Cost	J - 29
Table J.16	Replacement Cost.....	J - 30

LIST OF FIGURES

		<u>Page</u>
Fig. J.1	Project Implementation Schedule	J - 31
Fig. J.2	Organization Chart of Project Implementation	J - 32

ANNEX-J PROJECT IMPLEMENTATION PLAN AND PROJECT COST

1. Project Implementation

1.1 Principal Approach to Project Implementation

The development plan of the Project herein formulated includes various schemes for improvement/establishment of agricultural infrastructures in the command area as well as reinforcement/activation of farmers' association and agricultural supporting functions. These development components consist of the following work items :

I. Improvement/establishment of irrigation and drainage systems

This will consist of the following components;

- Modernization of existing irrigation canal systems
- Provision of adequate drainage system
- On-farm development works
- Development of groundwater for conjunctive use

II. Water and Agro-management

The main components of this item will include the following to attain the intensive development of irrigated agriculture.

- Operation and maintenance of irrigation system from the offtaking to minor canals up to outlets
- Establishment of water users' association and introduction of osrabandi system in the command
- provision of agricultural extension services and activation/formation of farmers' agro-management societies

III. Training, Adaptive Research, and Monitoring and Evaluation

The main components of this group will include the following:

- Training of Project staff, farmers including women farmers

- Surface water and groundwater management in the schemes of conjunctive use
- Setting up and operation of adaptive trial farms
- Input and output monitoring of sub-project areas

The implementation of these development components will be arranged so as to effectively realize the development objectives and to ensure the development effects to the other areas in the Sharda Canal CAD project. The following principal approach is adopted in implementation plan :

(1) Early establishment of farmers' association

Farmers participation to the project is prerequisite in attaining the efficient water management within outlet command. Prior to the commencement of the construction works, the water user' association is established in every outlet command so that the farmers can participate in the project works from the planning stage.

(2) Harmonized sequence of implementation of the Representative Areas

The implementation of construction works of the Representative Areas will be executed with the following concept:

- (a) Survey, planning and design will be carried out with employment of technical firms to effectively execute a large amount of those works with the limited time.
- (b) Modernization of irrigation and drainage systems will be executed on the basis of the job order to Irrigation Department.
- (c) On-farm development will be executed stagewise according to the progress of the design works.
- (d) Groundwater development will first be commenced from pilot demonstration farm, and then tubewell construction will follow on the basis of the result of pilot farm operation.

(3) Operation, maintenance water management of irrigation system

After completion of modernization works and on-farm works, the operation, maintenance and water management of the minor canal system will be carried out by the CADA. In order to effectively execute the water delivery to the every outlet command, osrabandi system will be introduced initially in the every outlet command under the guidance of the CADA.

(4) Agro-management

Immediately after the completion of the improvement of canal system and on-farm works, extension services will be provided by the CADA staff with cooperation of the existing governmental organization concerned.

(5) Training

Training will be provided by CADA during the Project operation period to the farmers including female farmers, canal inspector, CADA staff.

(6) Monitoring and evaluation of irrigated farm

At the final stage, the monitoring and evaluation of agricultural productivity under irrigated farm, conjunctive use of the surface water and groundwater, agro-economic impact will be executed.

1.2 Implementation Schedule

The implementation schedule of the Project is shown in Fig. J.1. It includes the preparatory works, construction works, research works, guidance services and monitoring and evaluation. The preparatory works include the establishment of farmers association, survey, design, tendering and project mobilization for implementation, and it will last 22 months in the initial stage. The construction works will last 50 months for the modernization works of the main irrigation and drainage systems and on-farm development works. All the work will be completed in the 6th year.

The topographic survey and subsequent designing work of on-farm works will be continued and the tendering will follow the completion of the design. The design will be completed in the 4th year.

Establishment of the farmers association in the command will also be commenced in the first year with the guidance from the CADA so as to ensure actual participation of the farmers from the planning stage of the on-farm development works. Introduction of the osrabandi will be promoted for the area where the on-farm works have been completed.

Modernization works of irrigation and drainage systems will be started in the second year after selection of the contractors through competitive bidding, and be completed in the last 6th year. All of the work in the respective representative areas will be concurrently commenced.

On-farm development works will be implemented with stage wise construction along with the progress of the design works. The result of the design will be brought into the construction step by step. The work will be commenced in the second year and all of the work will be completed in the last 5th year.

Wireless communication system will be established in the 4th year after site investigation and manufacturing and the monitoring and evaluation of the water management of the Sharda canal system will be commenced thereafter.

The groundwater development will first be commenced from the pilot farm construction of the tubewell and pipe drain schemes in the Purwa and Sursa areas together with observation and evaluation of the investigation results. Then the construction of the tubewells will be executed in the 4th year.

The adaptive trial farms will be established in the second year so as to utilize the result of the investigation in the actual water and farm management in the completed areas of the on-farm development.

The survey and design works will be carried out by the survey and design firms under the supervision of the CADA to utilize the limited time. All the construction works will be executed by the contractor(s) through competitive bidding. On-farm development works for lining canals will be executed by the contractors selected through competitive bidding, whereas earth canals will be executed by the farmers associations concerned for the command areas of on-farm works on the contract basis with CADA. The modernization of irrigation and drainage systems will be executed by the supervision of the CADA or with the job contract with Irrigation Department which is presently conducting O & M of those systems.

1.3 Organization of Project Implementation

Implementation of the Projects as a model development will be managed basically in accordance with the present organization of the CADA.

Implementation of the Project will need the multi-disciplinary working team. The fundamental components of the Project have to be directly performed by the CADA. Some other components will be carried out by the concerned departments and the CADA will prepare the implementation programme and its budget for implementation, and coordinate and monitor the progress of the works in accordance with the present governmental practice rules.

From the view point of the above, in order to effectively implement the Project, the organization structure of the Project is proposed as shown in Fig. J.2 and it will consist of the following :

The CADA will be headed by the Commissioner/Administrator under the direct supervision of the Uttar Pradesh State Agricultural Production Commissioner. The Commissioner /Administrator will be assisted by a full-time Project Manager who will be responsible for construction, operation, maintenance and extension services of the project activities and will be assisted by the following divisions.

(1) Administration and Accounting Division

This will undertake all administrative, financial, and legal services, i.e., accounting, treasury, personnel, records, other general services.

(2) Construction Division

This Division will consist of the following Sub-divisions which will be directly responsible for construction works of the Project at the respective Representative Areas.

(a) Irrigation and Drainage Modernization Sub-division

- to carry out survey, planning and design
- to supervise the modernization works of irrigation and drainage systems

The staff of this Sub-division have to be arranged from the present working staff of the Irrigation Department.

(b) Canal Maintenance Sub-division

- to provide the maintenance services for the minor canal facilities in the command of the concerned minor canals in coordinating with the operation and maintenance offices concerned of Irrigation Department or in contract with them

The staff of this Sub-division have to be arranged from the presently working staff of the operation and maintenance offices concerned of Irrigation Department

(c) Water Supply Sub-division

- to organize farmers' associations and provide guidance in introduction of osrabandi system
- to carry out water management down from the offtaking structures of minor canals

The staff of this Sub-division have to be strengthened by introduction of the engineering staff from operation and maintenance offices concerned in the Irrigation Department

(3) Land and Water Management Division

This Division will consist of the following Sub-divisions:

(a) Soil Survey Sub-division

- to carry out soil survey
- to carry out the guidance in soil management

The staff of this Sub-division is arranged from the presently working staff of CADA.

(b) On-farm Development Sub-division

- to carry out survey, planning and design
- to supervise on-farm development works

The staff of this Sub-division will be strengthened by transferring technical staff of Sub-divisional offices under the Irrigation Department

(c) Groundwater Sub-division

- to carry out investigation planning, design and construction supervision of groundwater development in coordination with Groundwater Department, UP.

(d) On-farm Work Maintenance Sub-division

- to carry out the guidance in maintenance works of on-farm works to water users association

(4) Agro-management Division

This Division will consist of the following Sub-divisions to provide intensive agricultural supporting services to farmers' associations.

(a) Crop Loan Sub-division

(b) Farm Input Sub-division

(c) Marketing and Storage Sub-division

(d) Agro-Processing Sub-division

The staff of these Sub-divisions have to be arranged from the Departments of Agriculture Cooperative and other related departments.

(5) Training, Action Research, Monitoring and Evaluation Division

Main Division will consist of the following Sub-divisions:

- Extension Sub-division
- Adaptive Research and Trial Farm Sub-division
- Monitoring and Evaluation Sub-division

The function of this unit will be to carry out planning and implementation of:

- (i) training of farmers and CADA staff,
- (ii) adaptive trial,

- (iii) monitoring and evaluation of groundwater development pilot farm for conjunctive use
- (iv) monitoring and evaluation of agricultural productivity with the Project.

The staff of this Division have to be arranged from the Department of Agriculture, Groundwater Department and the works are carried out in cooperation with the concerned departments.

2. Project Cost

2.1 Basic Conditions

The costs of implementation of the Project are estimated on the basis of the following conditions:

- 1) The exchange rate used in the cost estimate is shown as follows:
US\$ 1.0 = Rs.25.90
- 2) The main construction works will be carried out by contractor(s) selected through competitive bidding.
- 3) The unit price of the works are divided into foreign currency portion and local currency portion. Local currency portion is estimated with reference to the current market prices in the early 1991, the cost data obtained from similar on-going works around the Project area and price rate fixed by the government agencies concerned. Foreign currency portion of materials and equipment to be imported is estimated on the basis of CIF Calcutta.

The classification of local currency portion and foreign currency portion is carried out by the following basis:

Local currency portion

- Land acquisition cost
- Labor force
- Reinforcement bars (Local Currency Portion)
- Structural steel (Local Currency Portion)
- Fuel and lubricants (Local Currency Portion)

- Wooden materials
- Concrete aggregates
- Cement
- Brick
- Pumping equipment
- Supporting equipment
- Inland transportation
- Administration expenses
- Expenses and fees of engineering services by local consultant

Foreign currency

- Reinforcement bars (Foreign Currency Portion)
- Structural steel (Foreign Currency Portion)
- Fuel and lubricants (Foreign Currency Portion)
- Wireless communication equipment
- Depreciation of construction equipment and machinery
- Contractors' general expenses and profit of the contractors
- Expenses and fees of engineering services by foreign consultants

- 5) Physical contingency of the cost estimate is 10% of the construction cost. Price contingency applied is : 7% per annum for the local currency portion and 3% per annum for the foreign currency portion.

2.2 Estimate of Project Cost

The project cost consists of direct construction cost, procurement cost of supporting equipment, land acquisition cost, engineering services and administration cost, and contingencies. The total cost is estimated to be Rs. 3, 351 million, consisting of the foreign currency portion of Rs. 571 million and the local currency portion of Rs. 2,780 million as summarized below. The breakdown is shown in Table J.1.

Project Cost

Unit: Rs. million

	Description	Foreign Currency	Local Currency	Total
A.	Wireless Communication System	58.9	6.5	65.4
B.	Representative Areas			
	B-1 Sarojini Nagar Area			
	1. Main system	31.5	148.0	179.5
	2. On-farm development works	33.3	149.0	182.3
	3. Land acquisition	0.0	5.3	5.3
	Sub-total (B-1)	64.8	302.3	367.1
	B-2 Sataon Area			
	1. Main system	32.1	363.1	355.2
	2. On-farm development works	28.9	131.1	160.0
	3. Land acquisition	0.0	7.4	7.4
	Sub-total (B-2)	61.0	461.6	522.6
	B-3 Sursa Area			
	1. Main system	51.4	258.2	309.6
	2. On-farm development works	38.9	180.5	219.4
	3. Land acquisition	0.0	8.6	8.6
	Sub-total (B-3)	90.3	447.3	537.7
	B-4 Purwa Area			
	1. Main system	39.8	155.3	195.1
	2. On-farm development works	27.5	124.8	152.3
	3. Land acquisition	0.0	3.0	3.0
	Sub-total (B-4)	67.3	283.1	350.4
	Sub-Total (B)	283.4	1,494.3	1,777.6
C.	Procurement of Supporting Equipment	0.0	8.4	8.4
D.	Administration Cost	0.0	148.7	148.7
E.	Engineering Service	103.8	118.6	222.4
F.	Contingencies			
	1. Physical	44.6	177.7	222.3
	2. Price	80.3	825.9	906.2
	Total	571.0	2,780.1	3,351.1

2.3 Breakdown of Project Cost

(1) Direct Construction Cost

Direct construction cost is estimated for the individual item by unit cost basis as mentioned in the following sub-section 2.5. The breakdowns of each representative areas are shown in Tables J.2 to J.5.

(2) Land Acquisition Cost

Land acquisition cost for four(4) representative areas is Rs. 24 million for the new minor canals parallel to distributary canals and new drainage canal systems. The breakdown is shown in Table J.6.

(3) Supporting Equipment

Supporting equipment would be procured for the operation and maintenance works of the canals and related structures, extension works by the staff of CADA and experimental research. The breakdown is shown in Table J.7.

(4) Administration Cost

Administration cost comprises the costs of the operation and maintenance for the main irrigation and drainage system by the Irrigation Department, and on-farm development works along with the extension work, operation of the adaptive trial farm and experimental research by the CADA. The breakdown is shown in Table J.8.

(5) Engineering Service Cost

Engineering services by foreign consultant would be required for the detailed design, farm guidance and construction supervision. Some special equipment such as vehicle, motorcycle, computer etc., would be also required for the smooth operation. The required man-months of consultant engineers including local consultants are 410 M/M for the detailed design and farm guidance and 1,424 M/M for the construction supervision and farm guidance. The breakdown of the engineering service cost and required man-month are shown in Tables J.9 and J.10.

2.4 Annual Disbursement Schedule

The annual disbursement is worked out according to the implementation schedule as shown below. The breakdown of total cost is as shown in Table J.11 and breakdown of each Representative Area is shown in Table J.12.

Annual Disbursement Schedule

Unit: Million Rs.

Year	Foreign Currency	Local Currency	Total
1993	13.8	66.2	80.0
1994	37.5	171.4	208.9
1995	100.6	514.7	615.3
1996	206.6	750.6	967.2
1997	124.4	741.1	865.5
1998	88.2	526.1	614.3

2.5 Unit Cost Analysis

Construction cost is worked out by use of detailed unit cost. Each unit cost is composed of the basic unit cost such as labour and construction materials and working rate and/or construction machinery. Basic cost of labour and materials surveyed are shown in Table J.13. Hourly operation cost of machinery is also worked out based on the CIF prices of the major construction machinery and equipment, and their depreciation costs, operation and maintenance costs. According to these costs, unit cost is calculated, whose summary is shown in Table J.14.

2.6 Annual Operation and Maintenance Cost

Operation and maintenance costs at the full operation stage of the Project are estimated at Rs. 39.1 million, comprising the operation and maintenance of the Project facilities. The breakdown of annual maintenance cost is as shown in Table J.15.

2.7 Cost of Replacement of Project Facilities

Pumping equipment of irrigation, metal works of irrigation canal related structures and supporting equipment are periodically to be replaced. The economic life and the replacement cost used in the estimate are shown in Table J.16.

TABLES

Table J.1 Project Cost

Description	Unit: 1,000 Rs		
	Foreign	Local	Total
A. Wireless Communication System			
A-1 HF Radio System	10,350	1,150	11,500
A-2 VHF Radio System	27,450	3,050	30,500
A-3 Data Processing Unit	21,060	2,340	23,400
Sub-Total (A)	<u>58,860</u>	<u>6,540</u>	<u>65,400</u>
B. Representative Areas			
B-1 Sarojini Nagar Study Area			
1) Irrigation System	4,145	63,138	67,283
2) Drainage System	20,035	38,045	58,079
3) Augumentation Facility	1,185	12,741	13,926
4) On-farm Facility	33,345	148,997	182,342
5) Improvement of Service Road	6,032	34,067	40,099
Sub-Total (B-1)	<u>64,742</u>	<u>296,986</u>	<u>361,728</u>
B-2 Sataon Study Area			
1) Irrigation System	10,701	227,665	238,366
2) Drainage System	13,484	21,949	35,433
3) Augumentation Facility	1,480	15,449	16,929
4) On-farm Facility	28,897	131,136	160,034
5) Improvement of Service Road	6,464	58,038	64,502
Sub-Total (B-2)	<u>61,027</u>	<u>454,237</u>	<u>515,263</u>
B-3 Sursa Study Area			
1) Irrigation System	3,904	96,125	100,029
2) Drainage System	35,078	62,641	97,719
3) Augumentation Facility	7,164	75,519	82,683
4) On-farm Facility	38,858	180,471	219,329
5) Improvement of Service Road	5,331	23,951	29,282
Sub-Total (B-3)	<u>90,335</u>	<u>438,707</u>	<u>529,042</u>
B-4 Purwa Study Area			
1) Irrigation System	2,101	58,746	60,847
2) Drainage System	32,865	50,733	83,598
3) Augumentation Facility	465	23,131	23,596
4) On-farm Facility	27,481	124,811	152,292
5) Improvement of Service Road	4,422	22,681	27,103
Sub-Total (B-4)	<u>67,334</u>	<u>280,101</u>	<u>347,435</u>
Sub-Total (B)	<u>283,437</u>	<u>1,470,031</u>	<u>1,753,468</u>
C. Procurement of Supporting Equipment	0	8,410	8,410
D. Land Acquisition	0	24,213	24,213
E. Administration Cost	0	148,700	148,700
F. Engineering Service	103,800	118,600	222,400
G. Contingency	<u>124,873</u>	<u>1,003,597</u>	<u>1,128,470</u>
Physical	44,610	177,649	222,259
Price	80,263	825,948	906,211
Total	<u>570,970</u>	<u>2,780,091</u>	<u>3,351,061</u>

Table J.2 Breakdown of Direct Construction Cost of Sarojini Nagar Area

Description	Unit	Unit Rate		Quantity	Amount(1000Rs.)			Remarks	
		F/C	L/C		F/C	L/C	Total		
A. Irrigation System									
A-1 Improvement of Canal									
1) Excavation	m3	0	28	21,150	0	592	592	E-06	
2) Embankment	m3	7	47	183,880	1,287	8,642	9,930	E-08	
3) Brick Tile Lining	m2	0	206	180,040	0	37,088	37,088	C-22	
4) Related Structures									
- Head Regulator	Type-C	no.	2,500	40,590	1	3	41	43	MST-05-2
- Offtaking Structure of Minor Canals	nos.	1,630	55,900	19	31	1,062	1,093	MST-03	
- Outlet	nos.	250	4,150	292	73	1,212	1,285	MST-04	
- Drainage Crossing	Type-A (14m)	no.	1,110	58,950	1	1	59	60	MST-06-1
	Type-B (7m)	nos.	430	31,510	2	1	63	64	MST-06
- Rehabilitation Work of Existing Facilities	L.S.			5%	5	122	127		
A-2 Construction of Parallel Canal along Amausi Disty.									
1) Striping	m2	11	3	155,800	1,714	467	2,181	E-02	
2) Excavation	m3	19	3	39,340	747	118	865	E-03	
3) Embankment	m3	7	47	23,100	162	1,086	1,247	E-08	
4) Brick Tile Lining	m2	0	206	38,800	0	7,993	7,993	C-22	
5) Related Structure									
- Offtaking Structure	nos.	1,630	55,900	10	16	559	575	MST-03	
- Outlet	nos.	250	4,150	73	18	303	321	MST-04	
- Bridge	Type-C(7.5 m)	nos.	5,080	197,800	2	10	396	406	MST-11
	Type-D(5m)	nos.	3,400	145,880	22	75	3,209	3,284	MST-12
- Drainage Crossing	Type-B(7m)	nos.	430	31,510	4	2	126	128	MST-06
Sub-total (A)					<u>4,145</u>	<u>63,138</u>	<u>67,283</u>		
B. Drainage System									
B-1 Main Drainage System									
1) Striping	m2	11	3	224,020	2,464	672	3,136	E-02	
2) Excavation	m3	21	4	564,660	11,858	2,259	14,117	E-04	
3) Embankment	m3	7	19	508,200	3,557	9,656	13,213	E-07	
4) Related Structure									
- Bridge	Type-A (30m)	no.	24,500	880,540	0	0	0	MST-09	
	Type-B (15m)	nos.	11,300	380,400	13	147	4,945	5,092	MST-10
	Type-C (7.5 m)	nos.	5,080	197,800	15	76	2,967	3,043	MST-11
	Type-D (5m)	nos.	3,400	145,880	28	95	4,085	4,180	MST-12
E-2 Tertiary Drainage System									
1) Excavation	m3	0	28	289,810	0	8,115	8,115	E-06	
2) Embankment	m3	7	19	260,830	1,826	4,956	6,782	E-07	
3) Related Structure									
- Foot Path	nos.	50	1,760	222	11	391	402	MST-13	
Sub-total (B)					<u>20,035</u>	<u>38,045</u>	<u>58,079</u>		
C. Augmentation Facility									
Pump Station at the Sai River									
1) Pump House	1 lot				1	53	54	MST-15	
2) Intake & Outlet Structure					430	2,886	3,316	MST-17	
3) Pump Equipment and Power Supply System	1 lot				754	9,802	10,556	MST-16	
Sub-total (C)					<u>1,185</u>	<u>12,741</u>	<u>13,926</u>		
D. On-farm Facility									
D-1 Watercourse									
1) Lining	km	30,310	420,570	294	8,911	123,648	132,559	OF-01	
2) Earth Canal	km	10,000	60,000	159	1,590	9,540	11,130	OF-02	
D-2 Field Drain	km	0	21,000	368	0	7,728	7,728	OF-04	
D-3 Related Structure									
1) Turnout	nos.	0	280	2,082	0	583	583	OF-03	
2) Road Crossing	Type-A	nos.	70	2,820	66	5	186	191	OF-06
	Type-B	nos.	20	300	694	14	208	222	OF-07
3) Transition	nos.	0	110	496	0	55	55	OF-09	
4) Aqueduct	Type-A	nos.	20	4,320	79	2	341	343	OF-10
	Type-B	nos.	20	4,090	119	2	487	489	OF-10-1
5) Drop	nos.	10	1,480	231	2	342	344	OF-11	
6) Drainage Culvert	Type-A	nos.	40	2,380	0	0	0	OF-05	
	Type-B	nos.	20	1,380	956	19	1,319	1,338	OF-05-1
D-4 Farm Road	km	50,000	10,000	456	22,800	4,560	27,360	MST-08	
Sub-total (D)					<u>33,345</u>	<u>148,997</u>	<u>182,342</u>		
E. Improvement of Service Road									
E-1 Distributory Canal	km	60,000	610,000	55	3,297	33,520	36,817	MST-07	
E-2 Minor Canal	km	50,000	10,000	55	2,735	547	3,282	MST-08	
Sub-total (E)					<u>6,032</u>	<u>34,067</u>	<u>40,099</u>		
Total					<u>64,742</u>	<u>296,986</u>	<u>361,728</u>		

Table J.3 Breakdown of Direct Construction Cost of Sataon Area (1/2)

Description	Unit	Unit Rate		Quantity	Amount(1000Rs.)			Remarks	
		F/C	L/C		F/C	L/C	Total		
A. Irrigation System									
A-1 Improvement of Canal									
A-1-1 Asiwani Branch Canal									
- Head Regulator	Type-A	nos.	780	14,970	15	12	225	236	MST-05
	Type-B	nos.	1,450	26,270	2	3	53	55	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
A-1-2 Maurawan Disty. Canal from Head to M28-0-600									
1) Excavation		m3	0	28	19,730	0	552	552	E-06
2) Embankment		m3	7	47	98,660	691	4,637	5,328	E-08
3) Brick Tile Lining		m2	0	211	299,800	0	63,258	63,258	C-22
4) Related Structures									
- Head Regulator	Type-A	nos.	780	14,970	21	16	314	331	MST-05
	Type-B	nos.	1,450	26,270	0	0	0	0	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
- Outlet		nos.	420	4,220	1	0	4	5	MST-04
A-1-3 Maurawan Disty. Canal from M28-0-0 to Tail End									
1) Excavation		m3	0	28	10,860	0	304	304	E-06
2) Embankment		m3	7	47	54,310	380	2,553	2,933	E-08
3) Brick Tile Lining		m2	0	211	215,400	0	45,449	45,449	C-22
4) Related Structures									
- Head Regulator	Type-A	nos.	780	14,970	9	7	135	142	MST-05
	Type-B	nos.	1,450	26,270	0	0	0	0	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
- Offtaking Structure of Minor Canals		nos.	1,630	58,170	1	2	58	60	MST-03
- Outlet		nos.	420	4,220	183	77	772	849	MST-04
- Drainage Crossing	Type-A (14m)	no.	1,110	61,320	0	0	0	0	MST-06-1
	Type-B (7m)	no.	430	32,810	1	0	33	33	MST-06
- Rehabilitation Work of Existing Facilities		L.S.			5%	4	50	54	
Sub-total (A-1)						1,192	118,392	119,589	
A-2 Construction of Parallel Canal									
A-2-1 Asiwani Branch									
1) Striping		m2	11	3	30,600	337	92	428	E-02
2) Excavation		m3	19	3	101,000	1,919	303	2,222	E-03
3) Embankment		m3	7	47	218,000	1,526	10,246	11,772	E-08
4) Brick Tile Lining		m2	0	211	152,000	0	32,072	32,072	C-22
5) Related Structure									
- Head Regulator	Type-A	nos.	780	14,970	25	20	374	394	MST-05
	Type-B	nos.	1,450	26,270	0	0	0	0	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
- Offtaking Structure		nos.	1,630	58,170	17	28	989	1,017	MST-03
- Outlet		nos.	420	4,220	329	138	1,388	1,527	MST-04
- Bridge	Type-C(7.5 m)	nos.	5,080	204,560	21	107	4,296	4,402	MST-11
	Type-D(5m)	nos.	3,400	150,580	58	197	8,734	8,931	MST-12
- Drainage Crossing	Type-A(14m)	nos.	430	32,810	8	3	262	266	MST-06
	Type-B(7m)	nos.	1,110	61,320	13	14	797	812	MST-06-1
A-2-2 Maurawan Disty. from Head to M28-0-0									
1) Striping		m2	11	3	143,090	1,574	429	2,003	E-02
2) Excavation		m3	19	3	48,590	923	146	1,069	E-03
3) Embankment		m3	7	47	107,910	755	5,072	5,827	E-08
4) Brick Tile Lining		m2	0	211	98,060	0	20,691	20,691	C-22
5) Related Structure									
- Head Regulator	Type-A	nos.	780	14,970	10	8	150	158	MST-05
	Type-B	nos.	1,450	26,270	0	0	0	0	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
- Offtaking Structure		nos.	1,630	58,170	10	16	582	598	MST-03
- Outlet		nos.	420	4,220	159	67	671	738	MST-04
- Bridge	Type-C(7.5 m)	nos.	5,080	204,560	7	36	1,432	1,467	MST-11
	Type-D(5m)	nos.	3,400	150,580	26	88	3,915	4,003	MST-12
- Drainage Crossing	Type-A(14m)	nos.	430	32,810	5	2	164	166	MST-06
	Type-B(7m)	nos.	1,110	61,320	8	9	491	499	MST-06-1
A-2-3 Maurawan Disty. from M28-0-0 to Tail End									
1) Striping		m2	11	3	65,790	724	197	921	E-02
2) Excavation		m3	19	3	18,910	359	57	416	E-03
3) Embankment		m3	7	47	80,820	566	3,799	4,364	E-08
4) Brick Tile Lining		m2	0	211	41,050	0	8,662	8,662	C-22
5) Related Structure									
- Head Regulator	Type-A	nos.	780	14,970	4	3	60	63	MST-05
	Type-B	nos.	1,450	26,270	0	0	0	0	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
- Offtaking Structure		nos.	1,630	58,170	2	3	116	120	MST-03
- Outlet		nos.	420	4,220	46	19	194	213	MST-04
- Bridge	Type-C(7.5 m)	nos.	5,080	204,560	6	30	1,227	1,258	MST-11
	Type-D(5m)	nos.	3,400	150,580	10	34	1,506	1,540	MST-12
- Drainage Crossing	Type-A(14m)	nos.	430	32,810	1	0	33	33	MST-06
	Type-B(7m)	nos.	1,110	61,320	2	2	123	125	MST-06-1
Sub-total (A-2)						9,509	109,268	118,777	
Sub-total (A)						10,701	227,665	238,366	

Table J.3 Breakdown of Direct Construction Cost of Sataon Area (2/2)

Description	Unit	Unit Rate		Quantity	Amount(1000Rs.)			Remarks	
		F/C	L/C		F/C	L/C	Total		
B. Drainage System									
B-1 Main Drainage System									
1) Striping	m2	11	3	102,130	1,123	306	1,430	E-02	
2) Excavation	m3	21	4	426,400	8,954	1,706	10,660	E-04	
3) Embankment	m3	7	19	383,760	2,686	7,291	9,978	B-07	
4) Related Structure									
- Bridge	Type-A (30m)	no.	24,500	912,510	0	0	0	MST-09	
	Type-B (15m)	nos.	11,300	393,710	10	113	3,937	4,050	MST-10
	Type-C (7.5 m)	nos.	5,080	204,560	10	51	2,046	2,096	MST-11
	Type-D (5m)	nos.	3,400	150,580	19	65	2,861	2,926	MST-12
B-2 Tertiary Drainage System									
1) Excavation	m3	0	28	76,460	0	2,141	2,141	E-06	
2) Embankment	m3	7	19	68,820	482	1,308	1,789	B-07	
3) Related Structure									
- Foot Path	nos.	50	1,830	193	10	353	363	MST-13	
Sub-total (B)					13,484	21,949	35,433		
C. Augmentation Facility									
1) Pump House	lot			1	1	55	56	MST-15	
2) Intake & Outlet Structure	lot			1	430	2,954	3,384	MST-17	
3) Pump Equipment and Power Supply System	lot			1	1,049	12,440	13,489	MST-16	
Sub-total (C)					1,480	15,449	16,929		
D. On-farm Facility									
D-1 Watercourse									
1) Lining	km	30,310	429,010	255	7,729	109,398	117,127	OF-01	
2) Earth Canal	km	10,000	60,000	138	1,380	8,280	9,660	OF-02	
D-2 Field Drain	km	0	21,000	318	0	6,678	6,678	OF-04	
D-3 Related Structure									
1) Turnout	nos.	0	290	658	0	191	191	OF-03	
2) Road Crossing	Type-A	nos.	70	2,910	57	4	166	170	OF-06
	Type-B	nos.	20	300	601	12	180	192	OF-07
3) Transition	nos.	0	120	429	0	51	51	OF-09	
4) Aqueduct	Type-A	nos.	20	4,490	69	1	310	311	OF-10
	Type-B	nos.	20	4,250	103	2	438	440	OF-10-1
5) Drop	nos.	10	1,540	200	2	308	310	OF-11	
6) Drainage Culvert	Type-A	nos.	40	2,460	0	0	0	OF-05	
	Type-B	nos.	20	1,430	830	17	1,187	1,204	OF-05-1
D-4 Farm Road	Type-A	km	50,000	10,000	395	19,750	3,950	23,700	MST-08
Sub-total (D)					28,897	131,136	160,034		
E. Improvement of Service Road									
E-1 Distributary Canal	km	60,000	630,000	91.82	5,509	57,847	63,356	MST-07	
E-2 Minor Canal	km	50,000	10,000	19.10	955	191	1,146	MST-08	
Sub-total (E)					6,464	58,038	64,502		
Total					61,027	454,237	515,263		

Table J.4 Breakdown of Direct Construction Cost of Sursa Area

Description	Unit	Unit Rate		Quantity	Amount(1000Rs.)			Remarks	
		F/C	L/C		F/C	L/C	Total		
A. Irrigation System									
A-1 Improvement of Canal									
1) Excavation	m3	0	28	17,660	0	494	494	E-06	
2) Embankment	m3	7	47	109,390	766	5,141	5,907	E-08	
3) Brick Tile Lining	m2	0	218	227,330	0	49,558	49,558	C-22	
4) Related Structures									
- Head Regulator	Type-A	no.	780	12,690	1	13	13	MST-05	
	Type-B	no.	1,450	26,840	0	0	0	MST-05-1	
	Type-C	no.	2,500	42,040	1	42	45	MST-05-2	
- Offtaking Structure of Minor Canals	nos.	1,630	61,200	11	18	673	691	MST-03	
- Outlet	nos.	420	4,370	269	113	1,176	1,289	MST-04	
- Drainage Crossing	Type-A (14m)	no.	1,110	64,530	3	194	197	MST-06-1	
	Type-B (7m)	nos.	430	34,580	3	104	105	MST-06	
- Siphon	no.	33,790	354,510	1	34	355	388	MST-20	
- Rehabilitation Work of Existing Facilities	L.S.			5%	9	128	136		
A-2 Construction of Parallel Canal									
1) Striping	m2	11	3	110,560	1,216	332	1,548	E-02	
2) Excavation	m3	19	3	45,760	869	137	1,007	E-03	
3) Embankment	m3	7	47	102,960	721	4,839	5,560	E-08	
4) Brick Tile Lining	m2	0	218	127,720	0	27,843	27,843	C-22	
5) Related Structure									
- Offtaking Structure	nos.	1,630	61,200	5	8	306	314	MST-03	
- Outlet	nos.	420	4,370	117	49	511	560	MST-04	
- Bridge	Type-C(7.5 m)	nos.	5,080	213,410	3	15	640	655	MST-11
	Type-D(5m)	nos.	3,400	156,720	23	78	3,605	3,683	MST-12
- Drainage Crossing	Type-A(14m)	nos.	430	34,580	1	0	35	35	MST-06
Sub-total (A)					<u>3,904</u>	<u>96,125</u>	<u>100,029</u>		
B. Drainage System									
B-1 Main Drainage System									
1) Striping	m2	11	3	259,450	2,854	778	3,632	E-02	
2) Excavation	m3	21	4	873,760	18,349	3,495	21,844	E-04	
3) Embankment	m3	7	19	816,380	5,715	15,511	21,226	E-07	
4) Related Structure									
- Bridge	Type-A (30m)	no.	24,500	954,700	2	49	1,909	1,958	MST-09
	Type-B (15m)	nos.	11,300	411,220	20	226	8,224	8,450	MST-10
	Type-C (7.5 m)	nos.	5,080	213,410	29	147	6,189	6,336	MST-11
	Type-D (5m)	nos.	3,400	156,720	13	44	2,037	2,082	MST-12
B-2 Tertiary Drainage System									
1) Excavation	m3	0	28	337,600	0	9,453	9,453	E-06	
2) Embankment	m3	7	19	303,850	2,127	5,773	7,900	E-07	
3) Related Structure									
- Foot Path	nos.	50	1,920	262	13	503	516	MST-13	
B-3 Sub-surface Drainage System along Hardoi Branch Canal									
1) Sub-surface Pipe	1 lot				5,523	8,386	13,909	MST-14	
2) Pump House	1 lot				1	63	64	MST-15	
3) Suction Pond	1 lot				1	59	61	MST-17	
4) Equipment & Power Supply	1 lot				29	259	288	MST-16	
Sub-total (B)					<u>35,078</u>	<u>62,641</u>	<u>97,720</u>		
C. Augmentation Facility									
Cluster Shallow Well									
1) Pump House	nos.	460	50,790	900	414	45,711	46,125	MST-18	
2) Equipment and Boring with Casing	nos.	6,300	22,300	900	5,670	20,070	25,740	MST-21	
3) Power Supply	set	1,200	10,820	900	1,080	9,738	10,818	MST-19	
Sub-total (C)					<u>7,164</u>	<u>75,519</u>	<u>82,683</u>		
D. On-farm Facility									
D-1 Watercourse									
1) Lining	km	30,310	438,950	343	10,396	150,560	160,956	OF-01	
2) Earth Canal	km	10,000	60,000	186	1,860	11,160	13,020	OF-02	
D-2 Field Drain	km	0	21,000	428	0	8,988	8,988	OF-04	
D-3 Related Structure									
1) Turnout	nos.	0	300	2,425	0	728	728	OF-03	
2) Road Crossing	Type-A	nos.	70	3,030	77	5	233	239	OF-06
	Type-B	nos.	20	310	808	16	250	267	OF-07
3) Transition	nos.	0	120	577	0	69	69	OF-09	
4) Aqueduct	Type-A	nos.	20	4,740	92	2	436	438	OF-10
	Type-B	nos.	20	4,490	139	3	624	627	OF-10-1
5) Drop	nos.	10	1,630	269	3	438	441	OF-11	
6) Drainage Culvert	Type-A	nos.	40	2,590	0	0	0	0	OF-05
	Type-B	nos.	20	1,500	1,116	22	1,674	1,696	OF-05-1
D-4 Farm Road	km	50,000	10,000	531	26,550	5,310	31,860	MST-08	
Sub-total (D)					<u>38,858</u>	<u>180,471</u>	<u>219,329</u>		
E. Improvement of Service Road									
E-1 Distributary Canal	km	60,000	670,000	35	2,087	23,303	25,389	MST-07	
E-2 Minor Canal	km	50,000	10,000	65	3,244	649	3,893	MST-08	
Sub-total (E)					<u>5,331</u>	<u>23,951</u>	<u>29,282</u>		
Total					90,335	438,707	529,042		

Table J.5 Breakdown of Direct Construction Cost of Purwa Area

Description	Unit	Unit Rate		Quantity	Amount(1000Rs.)			Remarks	
		F/C	L/C		F/C	L/C	Total		
A. Irrigation System									
A-1 Improvement of Canal									
1) Excavation	m3	0	28	11,780	0	330	330	E-06	
2) Embankment	m3	7	47	102,810	720	4,832	5,552	E-08	
3) Brick Tile Lining	m2	0	211	175,180	0	36,963	36,963	C-22	
4) Related Structures									
- Head Regulator	Type-A	nos.	780	14,970	3	2	45	47	MST-05
	Type-B	nos.	1,450	26,270	1	1	26	28	MST-05-1
	Type-C	nos.	2,500	41,230	0	0	0	0	MST-05-2
- Offtaking Structure of Minor Canals		nos.	1,630	58,170	10	16	582	598	MST-03
- Outlet		nos.	420	4,220	234	98	987	1,086	MST-04
- Drainage Crossing	Type-A (14m)	no.	1,110	61,320	0	0	0	0	MST-06-1
	Type-B (7m)	nos.	430	32,810	1	0	33	33	MST-06
- Rehabilitation Work of Existing Facilities	L.S.			5%	6	84	90		
A-2 Construction of Parallel Canal along Disty. Canals									
1) Striping	m2	11	3	49,340	543	148	691	E-02	
2) Excavation	m3	19	3	17,360	330	52	382	E-03	
3) Embankment	m3	7	47	39,360	276	1,850	2,125	E-08	
4) Brick Tile Lining	m2	0	211	42,600	0	8,989	8,989	C-22	
5) Related Structure									
- Offtaking Structure		nos.	1,630	58,170	8	13	465	478	MST-03
- Outlet		nos.	420	4,220	57	24	241	264	MST-04
- Bridge	Type-C(7.5 m)	nos.	5,080	204,560	2	10	409	419	MST-11
	Type-D(5m)	nos.	3,400	150,580	18	61	2,710	2,772	MST-12
- Drainage Crossing	Type-A(14m)	nos.	430	32,810	0	0	0	0	MST-06
Sub-total (A)					2,101	58,746	60,847		
B. Drainage System									
B-1 Main Drainage System									
1) Striping	m2	11	3	75,270	828	226	1,054	E-02	
2) Excavation	m3	21	4	1,072,680	22,526	4,291	26,817	E-04	
3) Embankment	m3	7	19	965,420	6,758	18,343	25,101	E-07	
4) Related Structure									
- Bridge	Type-A (30m)	no.	24,500	912,510	2	49	1,825	1,874	MST-09
	Type-B (15m)	nos.	11,300	393,710	13	147	5,118	5,265	MST-10
	Type-C (7.5 m)	nos.	5,080	204,560	16	81	3,273	3,354	MST-11
	Type-D (5m)	nos.	3,400	150,580	36	122	5,421	5,543	MST-12
B-2 Tertiary Drainage System									
1) Excavation	m3	0	28	238,910	0	6,689	6,689	E-06	
2) Embankment	m3	7	19	215,020	1,505	4,085	5,591	E-07	
3) Related Structure									
- Foot Path	nos.	50	1,830	184	9	337	346	MST-13	
B-3 Sub-surface Drainage System									
1) Sub-surface Pipe	ha	20980	28,110	40	839	1,124	1,964	MST-14	
Sub-total (B)					32,865	50,733	83,598		
C. Augmentation Facility									
Shallow Well with Strainer									
1) Pump House	nos.	460	48,190	280	129	13,493	13,622	MST-18	
2) Boring & Equipment	set	0	23,600	280	0	6,608	6,608	MST-20	
3) Power Supply	set	1,200	10,820	280	336	3,030	3,366	MST-19	
Sub-total (C)					465	23,131	23,596		
D. On-farm Facility									
D-1 Watercourse									
1) Lining	km	30,310	429,010	242	7,335	103,820	111,155	OF-01	
2) Earth Canal	km	10,000	60,000	131	1,310	7,860	9,170	OF-02	
D-2 Field Drain									
	km	0	21,000	303	0	6,363	6,363	OF-04	
D-3 Related Structure									
1) Turnout	nos.	0	290	1,716	0	498	498	OF-03	
2) Road Crossing	Type-A	nos.	70	2,910	54	4	157	161	OF-06
	Type-B	nos.	20	300	572	11	172	183	OF-07
3) Transition		nos.	0	120	409	0	49	49	OF-09
4) Aqueduct	Type-A	nos.	20	4,490	65	1	292	293	OF-10
	Type-B	nos.	20	4,250	98	2	417	418	OF-10-1
5) Drop		nos.	10	1,540	191	2	294	296	OF-11
6) Drainage Culvert	Type-A	nos.	40	2,460	0	0	0	0	OF-05
	Type-B	nos.	20	1,430	790	16	1,130	1,146	OF-05-1
D-4 Farm Road	Type-A	km	50,000	10,000	376	18,800	3,760	22,560	MST-08
Sub-total (D)					27,481	124,811	152,292		
E. Improvement of Service Road									
E-1 Distributary Canal	km	60,000	630,000	35.27	2,116	22,220	24,336	MST-07	
E-2 Minor Canal	km	50,000	10,000	46.11	2,306	461	2,767	MST-08	
Sub-total (E)					4,422	22,681	27,103		
Total					67,334	280,101	347,435		

Table J.6 Land Acquisition Cost

Area	Work Item	Unit Rate of Land /1 (Rs./m2)	Quantity (1,000m2)	Amount (1,000Rs.)
1. Sarojini Nagar	Irrigation Facility	4.50	156	702
	Drainage Facility	3.00	1,518	4,554
2. Sataon	Irrigation Facility	5.76	497	2,863
	Drainage Facility	4.08	1,117	4,557
3. Sursa	Irrigation Facility	5.60	111	622
	Drainage Facility	4.40	1,808	7,955
4. Purwa	Irrigation Facility	4.00	49	196
	Drainage Facility	2.00	1,382	2,764
Total			6,638	24,213

Remarks /1 : Unit rate of land is collected from the Tehsil concerned.

Table J.7 List of Supporting Equipment

Item	Unit Price (1,000 Rs)	Required Number	Amount (1,000 Rs)	
I. Equipment for O & M Works				
1 Vehicle	small jeep, 4WD	300.0	16	4,800
2 Motorcycle	350 cc	10.0	24	240
Sub-total (I)			<u>5,040</u>	
II. Equipment for Training				
1 Audio-visual Equipemnt				
-	Sound System	150.0	4	600
-	Overhead Projectors	35.0	4	140
-	Slide Projector	35.0	4	140
-	Screen	10.0	4	40
2 Printing Equipment				
-	Photocopy Machine	200.0	4	800
3 Office Equipment				
-	Air Condition	50.0	4	200
Sub-total (II)			<u>1,920</u>	
III. Equipment for Experimental Research		L.S.	<u>1,450</u>	
Total			<u>8,410</u>	

Table J.8 Administration Cost

Item	Required Number	Required M/M	Monthly Rate(Rs.)	Amount (1,000 Rs.)
A-1 Main System (Irrigation Department)				
1) O & M Staff				
- Executive Engineer	4	12	15,000	720
- Assistant Executive Engineer	4	12	12,000	576
- Junior Engineer	14	12	9,000	1,512
- Other staff	L.S.			1,000
- Labour	L.S.			200
- Driver	8	12	6,000	576
2) Equipment operation cost	4	12	15,000	720
3) Office operation cost	4	12	15,000	720
4) Miscellaneous	L.S.			76
Sub-total (A-1)				<u>6,100</u>
A-2 On-farm Works and Farm Management Works				
1) O & M Staff				
- Executive Engineer	4	12	15,000	720
- Assistant Executive Engineer	4	12	12,000	576
- Junior Engineer	8	12	9,000	864
- Soil Conservation Officer	8	12	6,000	576
- Extension Worker	100	12	6,000	7,200
- Water Management Staff	100	12	6,000	7,200
- Driver	8	12	6,000	576
- Labor	L.S.			500
2) Equipment operation cost	4	12	15,000	720
3) Office operation cost	4	12	15,000	720
4) Miscellaneous	L.S.			48
Sub-total (A-2)				<u>19,700</u>
Total				25,800

Table J. 9 Required Man-Months of Consultant Engineer

Specialist	Man-Month		Total
	Foreign Consultant	Local Consultant	
I. Detailed Design (4 years)			
1. Project Director	4	-	4
2. Chief Engineer	48	-	48
3. Design Engineer for Main System	12	36	48
4. Design Engineer for On-farm System	16	192	208
5. Geology/Geo-hydrologist	6	-	6
6. Agronomist	6	18	24
7. Water Management Expert	6	6	12
8. Extension Expert	12	18	30
9. Chief Surveyor	6	-	6
10. Specialist as Required	12	12	24
Sub-total (I)	<u>128</u>	<u>282</u>	<u>410</u>
II. Construction Supervision and Farm Guidance (5 years)			
1. Project Director	5	-	5
2. Chief Engineer	60	-	60
3. Construction Engineer for Main System	12	144	156
4. Construction Engineer for On-farm System	24	240	264
5. Groundwater Specialist	12	96	108
6. Agronomist	24	240	264
7. Water Management Expert	24	240	264
8. Extension Expert	24	240	264
9. Specialist as Required	15	24	39
Sub-total (II)	<u>200</u>	<u>1,224</u>	<u>1,424</u>
Total	328	1,506	1,834

Table J.10 Cost of Engineering Service

Description	Unit : 1,000 Rs.		
	Foreign Currency	Local Currency	Total
I. Detailed Design			
1. Remuneration (Foreign 128 M/M)	30,700	-	30,700
2. Remuneration (Local 282 M/M)	-	2,800	2,800
3. Direct Cost	9,200	900	10,100
4. Special Equipment			
- Vehicle	-	4,000	4,000
- Motorcycle	-	200	200
- Photocopy Machine	-	300	300
- Personnel Computer with Printer	600	-	600
5. Cost of Survey Works for On-farm Design	-	90,000	90,000
Sub-total (I)	<u>40,500</u>	<u>98,200</u>	<u>138,700</u>
II. Construction Supervision			
1. Remuneration (Foreign 200 M/M)	48,200	-	48,200
2. Remuneration (Local 1,224 M/M)	-	12,200	12,200
3. Direct Cost	14,500	3,700	18,200
4. Special Equipment			
- Vehicle	-	4,000	4,000
- Motorcycle	-	200	200
- Photocopy Machine	-	300	300
- Personnel Computer with Printer	600	-	600
Sub-total (II)	<u>63,300</u>	<u>20,400</u>	<u>83,700</u>
Total	103,800	118,600	222,400

Table J.11 Annual Disbursement Schedule

Description	Unit: Million Rs.												
	Amount			1993			1994			1995			
	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	
A. Direct Construction Cost													
1) Irrigation System	20.9	445.7	466.5	0.0	0.0	0.0	0.8	17.8	18.7	4.2	89.1	93.3	
2) Drainage System	101.5	173.4	274.8	0.0	0.0	0.0	4.1	6.9	11.0	20.3	34.7	55.0	
3) Augmentation Facility	10.3	126.8	137.1	0.0	0.0	0.0	0.0	0.0	0.0	1.7	21.1	22.9	
4) On-farm Facility	128.6	585.4	714.0	0.0	0.0	0.0	5.1	23.4	28.6	25.7	117.1	142.8	
5) Improvement of Service Road	22.2	138.7	161.0	0.0	0.0	0.0	0.9	5.5	6.4	4.4	27.7	32.2	
6) Wireless Communication System	58.9	6.5	65.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Sub-total (A)	342.3	1,476.6	1,818.9	0.0	0.0	0.0	10.9	53.7	64.7	56.3	289.8	346.1	
B. Procurement of Supporting Equipment	0.0	8.4	8.4	0.0	4.2	4.2	0.0	4.2	4.2	0.0	0.0	0.0	
C. Land Acquisition	0.0	24.2	24.2	0.0	0.0	0.0	0.0	12.1	12.1	0.0	12.1	12.1	
D. Administration Cost	0.0	148.7	148.7	0.0	19.7	19.7	0.0	25.8	25.8	0.0	25.8	25.8	
E. Engineering Service	103.8	118.6	222.4	11.8	28.6	40.5	20.3	31.4	51.6	24.9	29.3	54.2	
Sub-total (A - E)	446.1	1,776.5	2,222.6	11.8	52.5	64.4	31.2	127.2	158.4	81.2	357.0	438.2	
F. Contingency													
Physical Contingency	10%	44.6	177.6	222.3	1.2	5.3	6.4	3.1	12.7	15.8	8.1	35.7	43.8
Price Contingency													
F/C	3%	80.3	825.9	906.2	0.8	8.4	9.2	3.2	31.5	34.7	11.2	122.0	133.3
L/C	7%												
TOTAL		571.0	2,780.1	3,351.1	13.8	66.2	80.0	37.5	171.4	208.9	100.6	514.7	615.3

Description	1996			1997			1998			
	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	
A. Direct Construction Cost										
1) Irrigation System	5.8	124.8	130.6	5.8	124.8	130.6	4.2	89.1	93.3	
2) Drainage System	28.4	48.5	77.0	28.4	48.5	77.0	20.3	34.7	55.0	
3) Augmentation Facility	5.1	63.4	68.6	3.4	42.3	45.7	0.0	0.0	0.0	
4) On-farm Facility	36.0	163.9	199.9	36.0	163.9	199.9	25.7	117.1	142.8	
5) Improvement of Service Road	6.2	38.8	45.1	6.2	38.8	45.1	4.4	27.7	32.2	
6) Wireless Communication System	58.9	6.5	65.4	0.0	0.0	0.0	0.0	0.0	0.0	
Sub-total (A)	140.5	446.1	586.5	79.9	418.4	498.3	54.6	268.6	323.3	
B. Procurement of Supporting Equipment	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
C. Land Acquisition	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
D. Administration Cost	0.0	25.8	25.8	0.0	25.8	25.8	0.0	25.8	25.8	
E. Engineering Service	21.5	21.1	42.6	14.8	4.8	19.5	10.6	3.4	14.0	
Sub-total (A - E)	162.0	493.0	655.0	94.7	448.9	543.6	65.2	297.8	363.0	
F. Contingency										
Physical Contingency	10%	16.2	49.3	65.5	9.5	44.9	54.4	6.5	29.8	36.3
Price Contingency										
F/C	3%	28.4	218.3	246.7	20.2	247.3	267.5	16.5	198.5	214.9
L/C	7%									
TOTAL		206.6	760.6	967.2	124.4	741.1	865.5	88.2	526.1	614.3

Table J.12 Breakdown of Annual Disbursement Schedule (1/2)

Description	Amount			1993			1994			1995			1996			1997			1998			
	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	
																						Unit: Rs million
I. Sarojini Nagar Area																						
I-A Direct Construction Cost																						
1) Irrigation System	4.1	63.1	67.3	0.0	0.0	0.0	0.2	2.5	2.7	0.8	12.6	13.5	1.2	17.7	18.8	1.2	17.7	18.8	0.8	12.6	13.5	
2) Drainage System	20.0	38.0	58.1	0.0	0.0	0.0	0.8	1.5	2.3	4.0	7.6	11.6	5.6	10.7	16.3	5.6	10.7	16.3	4.0	7.6	11.6	
3) Augmentation Facility	1.2	12.7	13.9	0.0	0.0	0.0	0.0	0.0	0.0	0.2	2.1	2.3	0.6	6.4	7.0	0.4	4.2	4.6	0.0	0.0	0.0	
4) On-farm Facility	37.3	149.0	182.3	0.0	0.0	0.0	1.3	6.0	7.3	6.7	29.8	36.5	9.3	41.7	51.1	9.3	41.7	51.1	6.7	29.8	36.5	
5) Improvement of Service Road	6.0	34.1	40.1	0.0	0.0	0.0	0.2	1.4	1.6	1.2	6.8	8.0	1.7	9.5	11.2	1.7	9.5	11.2	1.2	6.8	8.0	
6) Wireless Communication System	15.3	1.7	17.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	15.3	1.7	17.0	0.0	0.0	0.0	0.0	0.0	0.0	
Sub-Total (I-A)	80.0	298.7	378.7	0.0	0.0	0.0	2.5	11.4	13.9	12.2	52.0	71.2	33.7	87.7	102.0	18.2	83.8	102.0	12.7	56.8	69.6	
I-B Procurement of Supporting Equipment	0.0	2.2	2.2	0.0	1.1	1.1	0.0	1.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
I-C Land Acquisition	0.0	5.3	5.3	0.0	0.0	0.0	0.0	2.6	2.6	0.0	2.6	2.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
I-D Administration Cost	0.0	38.6	38.6	0.0	5.1	5.1	0.0	6.7	6.7	6.7	6.7	6.7	0.0	6.7	6.7	0.0	6.7	6.7	6.7	6.7	6.7	
I-E Engineering Service	26.9	30.8	57.7	3.1	7.4	10.5	5.3	8.1	13.4	6.5	7.6	14.1	5.6	5.5	11.1	3.8	1.2	5.1	2.7	0.9	3.6	
Sub-Total	106.2	375.4	481.6	3.1	13.6	16.7	7.8	29.2	37.2	19.4	75.9	95.3	39.2	99.8	139.1	22.0	91.8	113.8	15.4	64.4	79.8	
I-F Contingency	10.7	37.5	48.2	0.3	1.4	1.7	0.8	3.0	3.8	1.9	7.6	9.5	3.9	10.0	13.9	2.2	9.2	11.4	1.5	6.4	8.0	
Physical Contingency	19.2	173.2	192.4	0.2	2.2	2.4	0.8	7.4	8.2	2.7	25.9	28.6	6.9	44.2	51.1	4.7	50.5	55.2	3.9	42.9	46.8	
Price Contingency	136.8	586.2	723.0	3.6	17.2	20.7	9.4	40.3	49.2	24.0	109.4	133.4	50.0	154.0	204.0	28.2	151.5	180.4	20.9	113.8	134.7	
Total	136.8	586.2	723.0	3.6	17.2	20.7	9.4	40.3	49.2	24.0	109.4	133.4	50.0	154.0	204.0	28.2	151.5	180.4	20.9	113.8	134.7	
II. Saton Area																						
II-A Direct Construction Cost																						
1) Irrigation System	10.7	227.7	238.4	0.0	0.0	0.0	0.4	9.1	9.5	2.1	45.5	47.7	3.0	63.7	66.7	3.0	63.7	66.7	2.1	45.5	47.7	
2) Drainage System	13.5	21.9	35.4	0.0	0.0	0.0	0.5	0.9	1.4	2.7	4.4	7.1	3.8	6.1	9.9	3.8	6.1	9.9	2.7	4.4	7.1	
3) Augmentation Facility	1.5	15.4	16.9	0.0	0.0	0.0	0.0	0.0	0.0	0.2	2.6	2.8	0.7	7.7	8.5	0.5	5.1	5.6	0.0	0.0	0.0	
4) On-farm Facility	28.9	131.1	160.0	0.0	0.0	0.0	1.2	5.2	6.4	5.8	26.2	32.0	8.1	36.7	44.8	8.1	36.7	44.8	5.8	26.2	32.0	
5) Improvement of Service Road	6.5	58.0	64.5	0.0	0.0	0.0	0.3	2.3	2.6	1.3	11.6	12.9	1.8	16.3	18.1	1.8	16.3	18.1	1.3	11.6	12.9	
6) Wireless Communication System	13.2	1.5	14.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	13.2	1.5	14.7	0.0	0.0	0.0	0.0	0.0	0.0	
Sub-Total (I-A)	74.3	455.7	530.0	0.0	0.0	0.0	2.4	17.6	19.2	12.2	90.3	102.5	30.6	132.1	162.7	17.2	128.0	145.2	11.9	87.8	99.7	
II-B Procurement of Supporting Equipment	0.0	1.9	1.9	0.0	0.9	0.9	0.0	0.9	0.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
II-C Land Acquisition	0.0	7.4	7.4	0.0	0.0	0.0	0.0	3.7	3.7	0.0	3.7	3.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
II-D Administration Cost	0.0	35.4	35.4	0.0	4.4	4.4	0.0	5.8	5.8	5.8	5.8	5.8	5.8	5.8	5.8	0.0	5.8	5.8	5.8	5.8	5.8	
II-E Engineering Service	23.3	26.6	50.0	2.7	6.4	9.1	4.6	7.0	11.6	5.6	6.6	12.2	4.8	4.7	9.6	3.3	1.1	4.4	2.4	0.8	3.1	
Sub-Total	97.6	525.1	622.6	2.7	11.8	14.5	5.2	35.0	42.0	17.7	106.4	124.2	35.5	142.6	178.1	20.3	134.2	155.4	14.2	94.2	108.6	
II-F Contingency	9.8	52.5	62.3	0.3	1.2	1.4	0.7	3.5	4.2	1.8	10.6	12.4	3.5	14.3	17.8	2.0	13.5	15.5	1.4	9.4	10.9	
Physical Contingency	17.5	247.2	264.8	0.2	1.9	2.1	0.7	8.7	9.4	2.5	36.4	38.8	6.2	63.1	69.4	4.4	74.3	78.7	3.6	62.8	66.5	
Price Contingency	124.9	824.8	949.7	3.1	14.9	18.0	8.3	47.2	55.6	22.0	153.5	175.4	45.2	220.0	265.2	26.9	222.7	249.6	19.3	166.6	185.9	
Total	124.9	824.8	949.7	3.1	14.9	18.0	8.3	47.2	55.6	22.0	153.5	175.4	45.2	220.0	265.2	26.9	222.7	249.6	19.3	166.6	185.9	

Table J.12 Breakdown of Annual Disbursement Schedule (2/2)

Description	Amount			1993			1994			1995			1996			1997			1998			
	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	Foreign	Local	Total	
																						Unit: Rs million
III. Surua Area																						
III-A Direct Construction Cost																						
1) Irrigation System	3.9	96.1	100.0	0.0	0.0	0.0	0.2	3.8	4.0	0.8	19.2	20.0	1.1	26.9	28.0	0.8	19.2	20.0	0.8	19.2	20.0	
2) Drainage System	35.1	62.6	97.7	0.0	0.0	0.0	1.4	2.5	3.9	7.0	12.5	19.5	9.8	17.5	27.4	7.0	12.5	19.5	9.8	17.5	27.4	
3) Augmentation Facility	7.2	75.5	82.7	0.0	0.0	0.0	0.0	0.0	0.0	1.2	12.6	13.8	3.6	37.8	41.3	2.4	25.2	27.6	0.0	0.0	0.0	
4) On-farm Facility	38.9	180.5	219.3	0.0	0.0	0.0	1.6	7.2	8.8	7.8	36.1	43.9	10.9	50.5	61.4	7.8	36.1	43.9	7.8	36.1	43.9	
5) Improvement of Service Road	5.3	24.0	29.3	0.0	0.0	0.0	0.2	1.0	1.2	1.1	4.8	5.9	1.5	6.7	8.2	1.1	4.8	5.9	1.1	4.8	5.9	
6) Wireless Communication System	17.8	2.0	19.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	17.8	2.0	19.8	0.0	0.0	0.0	0.0	0.0	0.0	
Sub-Total (I-A)	108.1	440.7	548.8	0.0	0.0	0.0	2.3	14.5	17.2	17.8	85.2	103.1	44.7	141.4	186.1	25.7	126.9	152.5	16.6	72.6	89.3	
III-B Procurement of Supporting Equipment																						
III-C Land Acquisition	0.0	2.5	2.5	0.0	1.3	1.3	0.0	1.3	4.3	0.0	4.3	4.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
III-D Administration Cost	0.0	44.9	44.9	0.0	6.0	6.0	0.0	7.8	7.8	0.0	7.8	7.8	0.0	7.8	7.8	0.0	7.8	7.8	0.0	7.8	7.8	
III-E Engineering Service	31.4	35.8	67.2	3.6	8.7	12.2	6.1	9.5	15.6	7.5	8.9	16.4	6.5	6.4	12.9	4.5	1.4	5.9	3.2	1.0	4.2	
Sub-Total	139.5	522.6	672.0	3.6	15.9	19.4	9.4	37.4	46.8	25.3	106.2	131.5	51.2	155.6	206.8	30.1	136.1	166.2	19.8	81.5	101.3	
III-F Contingency																						
Physical Contingency	13.9	53.3	67.2	0.4	1.6	1.9	0.9	3.7	4.7	2.5	10.6	13.2	5.1	15.6	20.7	3.0	13.6	16.6	2.0	8.1	10.1	
Price Contingency	25.1	246.2	271.3	0.2	2.5	2.8	1.0	9.2	10.2	3.5	36.3	39.8	9.0	68.9	77.9	6.4	75.0	81.4	5.0	54.3	59.3	
Total	178.5	832.0	1,010.6	4.2	20.0	24.2	11.4	50.3	61.7	31.4	153.1	184.5	65.2	240.1	305.3	39.6	224.7	264.3	26.8	143.9	170.7	
IV. Purwa Area																						
IV-A Direct Construction Cost																						
1) Irrigation System	2.1	58.7	60.8	0.0	0.0	0.0	0.1	2.3	2.4	0.4	11.7	12.2	0.6	16.4	17.0	0.6	16.4	17.0	0.4	11.7	12.2	
2) Drainage System	32.9	50.7	83.6	0.0	0.0	0.0	1.3	2.0	3.3	6.6	10.1	16.7	9.2	14.2	23.4	6.6	10.1	16.7	6.6	10.1	16.7	
3) Augmentation Facility	0.5	23.1	23.6	0.0	0.0	0.0	0.0	0.0	0.0	0.1	3.9	3.9	0.2	11.6	11.8	0.2	7.7	7.9	0.0	0.0	0.0	
4) On-farm Facility	27.5	124.8	152.3	0.0	0.0	0.0	1.1	5.0	6.1	5.5	25.0	30.5	7.7	34.9	42.6	7.7	34.9	42.6	5.5	25.0	30.5	
5) Improvement of Service Road	4.4	22.7	27.1	0.0	0.0	0.0	0.2	0.9	1.1	0.9	4.5	5.4	1.2	6.4	7.6	1.2	6.4	7.6	0.9	4.5	5.4	
6) Wireless Communication System	12.6	1.4	14.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	12.6	1.4	14.0	0.0	0.0	0.0	0.0	0.0	0.0	
Sub-Total (I-A)	79.2	281.5	360.7	0.0	0.0	0.0	2.7	10.3	13.0	13.5	55.2	68.7	31.5	84.2	116.5	18.2	79.7	98.5	13.4	51.4	64.8	
IV-B Procurement of Supporting Equipment																						
IV-C Land Acquisition	0.0	1.8	1.8	0.0	0.9	0.9	0.0	0.9	1.5	0.0	1.5	1.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
IV-D Administration Cost	0.0	31.8	31.8	0.0	4.2	4.2	0.0	5.5	5.5	0.0	5.5	5.5	0.0	5.5	5.5	0.0	5.5	5.5	0.0	5.5	5.5	
IV-E Engineering Service	22.2	25.4	47.6	2.5	6.1	8.6	4.3	6.7	11.0	5.3	6.3	11.6	4.6	4.5	9.1	3.2	1.0	4.2	2.3	0.7	3.0	
Sub-Total	102.1	253.4	355.5	2.5	11.2	13.8	7.0	24.9	31.2	18.3	68.5	87.3	36.1	94.9	131.1	22.0	86.2	108.2	15.6	57.6	73.3	
IV-F Contingency																						
Physical Contingency	10.2	34.3	44.5	0.3	1.1	1.4	0.7	2.5	3.2	1.9	6.9	8.7	3.6	9.5	13.1	2.2	8.6	10.8	1.6	5.8	7.3	
Price Contingency	18.5	159.3	177.8	0.2	1.8	2.0	0.7	6.2	6.9	2.6	23.4	26.0	6.3	42.0	48.4	4.7	47.5	52.2	4.0	38.4	42.4	
Total	130.8	537.1	672.8	2.9	14.1	17.1	8.4	33.2	41.9	23.2	98.8	122.0	46.1	146.5	192.6	28.9	142.3	171.2	21.1	101.8	123.0	

Table J.13 Unit Cost of Labour and Construction Materials

No.	Item	Unit	Cost (Rs.)	Component		Unit Price		Remarks
				F (%)	L (%)	F (Rs.)	L (Rs.)	
A. Labour								
1.	Foreman	man-day	100	0%	100%	0	100	L-01
2.	Skilled Labour	man-day	55	0%	100%	0	55	L-02
3.	Common Labour	man-day	35	0%	100%	0	35	L-03
4.	Mason	man-day	60	0%	100%	0	60	L-04
5.	Carpenter	man-day	50	0%	100%	0	50	L-05
6.	Black Smith	man-day	50	0%	100%	0	50	L-06
7.	Painter	man-day	60	0%	100%	0	60	L-07
8.	Bar bender	man-day	65	0%	100%	0	65	L-08
9.	Welder	man-day	65	0%	100%	0	65	L-09
10.	Mechanic	man-day	90	0%	100%	0	90	L-10
11.	Electrician	man-day	70	0%	100%	0	70	L-11
12.	Plumber	man-day	65	0%	100%	0	65	L-12
13.	Driver	man-day	60	0%	100%	0	60	L-13
14.	Operator	man-day	70	0%	100%	0	70	L-14
15.	Assistant Operator	man-day	55	0%	100%	0	55	L-15
16.	Heavy Machine Mechanic	man-day	90	0%	100%	0	90	L-16
B. Construction Materials								
1.	Sand	m3	250	0%	100%	0	250	M-01
2.	Coarse Gravel	m3	380	0%	100%	0	380	M-02
3.	Boulder	m3	550	0%	100%	0	550	M-03
4.	Portland Cement	ton	1,965	0%	100%	0	1,965	M-04
5.	Brick	1,000 nos.	900	0%	100%	0	900	M-05
6.	Brick Tile	1,000 nos	1,200	0%	100%	0	1,200	M-34
7.	Timber	m3	10,600	0%	100%	0	10,600	M-06
8.	Plywood	m2	165	0%	100%	0	165	M-07
9.	Reinforced iron bar	ton	10,200	10%	90%	1,020	9,180	M-08
10.	Structural Steel	kg	12	10%	90%	1	11	M-09
11.	R.C.C pipe, Dia 100 mm	m	56	0%	100%	0	56	M-10
12.	R.C.C pipe, Dia 150 mm	m	67	0%	100%	0	67	M-11
13.	R.C.C pipe, Dia 200 mm	m	91	0%	100%	0	91	M-12
14.	R.C.C pipe, Dia 250 mm	m	99	0%	100%	0	99	M-13
15.	R.C.C pipe, Dia 300 mm	m	148	0%	100%	0	148	M-14
16.	R.C.C pipe, Dia 300 mm	m	163	0%	100%	0	163	M-14-1
17.	R.C.C pipe, Dia 400 mm	m	188	0%	100%	0	188	M-15
18.	R.C.C pipe, Dia 450 mm	m	225	0%	100%	0	225	M-16
19.	R.C.C pipe, Dia 500 mm	m	259	0%	100%	0	259	M-17
20.	R.C.C pipe, Dia 600 mm	m	362	0%	100%	0	362	M-18
21.	R.C.C pipe, Dia 700 mm	m	432	0%	100%	0	432	M-19
22.	R.C.C pipe, Dia 800 mm	m	579	0%	100%	0	579	M-20
23.	R.C.C pipe, Dia 900 mm	m	720	0%	100%	0	720	M-21
24.	R.C.C pipe, Dia 1,000 mm	m	877	0%	100%	0	877	M-22
25.	R.C.C pipe, Dia 1,100 mm	m	1,023	0%	100%	0	1,023	M-23
26.	R.C.C pipe, Dia 1,200 mm	m	1,183	0%	100%	0	1,183	M-24
27.	P.V.C. pipe, Dia. 20 mm	m	6	20%	80%	1	5	M-25
28.	P.V.C. pipe, Dia. 50 mm	m	24	20%	80%	5	19	M-26
29.	P.V.C. pipe, Dia. 100 mm	m	66	20%	80%	13	53	M-27
30.	P.V.C. pipe, Dia. 150 mm	m	208	20%	80%	42	166	M-28
31.	P.V.C. pipe, Dia. 200 mm	m	346	20%	80%	69	277	M-29
32.	Fuel	lit.	13	40%	60%	5	8	M-30
33.	Diesel	lit.	6	40%	60%	2	3	M-31
34.	Kerosine	lit.	4	40%	60%	2	3	M-32
35.	Lubricant	lit.	31	40%	60%	12	18	M-33

Source : JICA survey in the early 1991

Table J.14 List of Unit Prices of Major Work Items

Work Item	Unit	Unit : Rs.			Remarks
		Foreign Currency	Local Currency	Total	
1. EARTH WORKS					
- Clearing and grubbing	m2	0	1	1	E-01
- Stripping of top soil	m3	11	3	14	E-02
- Excavation of irrigation canals(machine)	m3	19	3	22	E-03
- Excavation in drains by machine	m3	21	4	25	E-04
- Excavation in natural rivers	m3	30	4	34	E-05
- Excavation(manpower)	m3	0	28	28	E-06
- Embankment with excavated material	m3	7	19	26	E-07
- Embankment with borrowed material	m3	7	47	54	E-08
- Backfill for structures	m3	7	19	26	E-09
- Embankment for Road	m3	54	12	66	E-10
2. CONCRETE WORKS					
- Concrete, Type-A (1:1.5:3)	m3	50	1903	1,953	C-01
- Concrete, Type-B(1:2:4)	m3	50	1715	1,765	C-02
- Concrete, Type-C(1:3:6)	m3	50	1382	1,432	C-03
- Concrete, Type-D(1:4:8)	m3	50	1361	1,411	C-03-1
- Formwork	m2	0	289	289	C-04
- Reinforcement steel	ton	1308	12760	14,068	C-05
- Structural steel	ton	1594	15335	16,929	C-05-1
3. BRICK WORKS					
- Brick masonry	m3	0	1155	1,155	B-01
- Brick Pitching	m3	0	1188	1,188	B-02
- Plastering	m2	0	47	47	B-03
- Removal of Brickwork	m3	0	254	254	B-04
- Dry Brick Pitching	m3	0	775	775	B-05
- Ruled Pointing	m2	0	21	21	B-06
- Brick Lining/one tile with plaster with top	m2	0	200	200	C-22
4. PIPE WORKS					
- Precast concrete pipe, 200 mm dia.	m	0	163	163	C-06
- Precast concrete pipe, 250 mm dia.	m	0	180	180	C-07
- Precast concrete pipe, 300mm dia.	m	0	247	247	C-08
- Precast concrete pipe, 350mm dia.	m	0	266	266	C-08-1
- Precast concrete pipe, 400 mm dia.	m	0	298	298	C-09
- Precast concrete pipe, 500 mm dia.	m	34	396	430	C-10
- Precast concrete pipe, 600 mm.dia.	m	34	542	576	C-11
- Precast concrete pipe, 700 mm dia.	m	34	642	676	C-12
- Present concrete pipe, 800 mm dia.	m	34	837	871	C-13
- Precast concrete pipe, 900 mm dia.	m	34	1025	1,059	C-14
- Precast concrete pipe, 1000 mm dia.	m	34	1219	1,253	C-15
- Precast concrete pipe, 1100 mm.dia.	m	34	1433	1,467	C-16
- Precast concrete pipe, 1200 mm dia.	m	34	1634	1,668	C-17
- Precast concrete unit for outlet	nos	277	1,134	1,411	C-20
5. OTHERS					
- Installation of PVC 50mm	m	7	30	37	C-23
- Installation of PVC 100mm	m	20	81	101	C-24

Remarks : Above unit prices are worked out based on the prices in Lucknow city. The unit prices of the representative areas are calculated in consideration of the transportation cost of the construction materials.

Table J. 15 Annual Operation and Maintenance Cost

Description	Unit : 1,000 Rs
	O & M Cost
I. Sarojini Nagar Area	
A. Main system	
1 Irrigation Facility	
- Canal	1,300
- Augumentation Facility	700
2 Drainage Facility	1,200
3 Service Road	800
B. On-farm system	3,600
Total	<u>7,600</u>
II. Sataon Area	
A. Main system	
1 Irrigation Facility	
- Canal	4,800
- Augumentation Facility	800
2 Drainage Facility	700
3 Service Road	1,300
B. On-farm system	3,200
Total	<u>10,800</u>
III. Sursa Area	
A. Main system	
1 Irrigation Facility	
- Canal	2,000
- Augumentation Facility	4,100
2 Drainage Facility	2,000
3 Service Road	600
B. On-farm system	4,400
Total	<u>13,100</u>
IV. Purwa Area	
A. Main system	
1 Irrigation Facility	
- Canal	1,200
- Augumentation Facility	1,200
2 Drainage Facility	1,700
3 Service Road	500
B. On-farm system	3,000
Total	<u>7,600</u>
Total	39,100

Table J.16 Replacement Cost

Item	Useful Life (year)	Replacement Cost (Rs. 1,000)
I. Sarojini Nagar Area		
1. Irrigation System		
- Pumping equipment	20	10,560
- Gate	10	20
2. Supporting Equipment	10	2,180
II. Sataon Area		
1. Irrigation System		
- Pumping equipment	20	13,500
- Gate	10	250
2. Supporting Equipment	10	1,890
III. Sursa Area		
1. Irrigation System		
- Pumping equipment	10	36,170
- Gate	10	20
2. Supporting Equipment	10	2,540
IV. Purwa Area		
1. Irrigation System		
- Pumping equipment	10	9,980
- Gate	10	30
2. Supporting Equipment	10	1,800

FIGURES




Fig. J.1 Project Implementation Schedule

INDIA
 FEASIBILITY STUDY ON
 IRRIGATION AND DRAINAGE DEVELOPMENT OF
 SHARDA CANAL CAD PROJECT
 JAPAN INTERNATIONAL COOPERATION AGENCY




Fig. J.2 Organization Chart of Project Implementation

INDIA
FEASIBILITY STUDY ON IRRIGATION AND DRAINAGE DEVELOPMENT OF SHARDA CANAL CAD PROJECT
JAPAN INTERNATIONAL COOPERATION AGENCY

ANNEX-K
PROJECT EVALUATION

FEASIBILITY STUDY ON
IRRIGATION AND DRAINAGE IMPROVEMENT OF
SHARDA CANAL CAD PROJECT

ANNEX - K
PROJECT EVALUATION

TABLE OF CONTENTS

	<u>Page</u>
1. General.....	K-1
2. Economic Evaluation.....	K-1
2.1 Basic Assumption	K-1
2.2 Economic Factors.....	K-1
2.3 Economic Benefits.....	K-2
2.4 Economic Costs.....	K-3
2.5 Economic Evaluation.....	K-5
2.6 Sensitivity Analysis.....	K-5
3. Financial Analysis	K-6
3.1 Farm Budget Analysis.....	K-6
3.2 Capacity to Pay.....	K-7
3.3 Repayment.....	K-7
4. Socio-economic Impact	K-8
5. Project Justification.....	K-9

LIST OF TABLES

Table K.1	Derivation of Economic Farmgate Prices in 1995	K-11
Table K.2	Economic Benefit per ha under With and Without Project Conditions	K-12
Table K.3	Breakdown of the Expected Economic Project Benefit	K-13
Table K.4	Annual Economic Disbursement Schedule	K-14
Table.K.5	Economic Cash Flow (1/5) - Sarojini Nagar Area -	K-15
Table.K.5	Economic Cash Flow (2/5) - Sataon Area -.....	K-16
Table.K.5	Economic Cash Flow (3/5) - Sursa Area -.....	K-17
Table.K.5	Economic Cash Flow (4/5) - Purwa Area -.....	K-18
Table.K.5	Economic Cash Flow (5/5) - Overall Area -.....	K-19
Table.K.6	Farm Budget Analysis of Marginal Farmers	K-20
Table.K.7	Financial Cash Flow Statement of the Project.....	K-21

ANNEX K. PROJECT EVALUATION

1. General

The project is to be evaluated through an assessment of its feasibility in view of economic and financial aspects. The economic feasibility is evaluated by calculating the internal rate of return. A sensitivity analysis is also made to elucidate an economic viability of the project against the changes in the benefit and project cost.

Financial evaluation is carried out by analysing the effect of the project on the farm economy for a typical type of farmers and by preparing the repayment schedule of the project capital cost.

2. Economic Evaluation

2.1 Basic Assumption

The economic evaluation is made on the following basic assumptions;

- (1) The economic useful life of the project is 50 years.
- (2) All prices are expressed in constant 1990 prices.
- (3) The exchange rate of US\$1.00=Rs.25.9 is applied.

2.2 Economic Factors

Traffic and trade restrictions introduce a distortion in the price relationship between trade goods and non-trade goods. In order to evaluate the project costs and benefits with respect to world market prices, a standard conversion factor of 0.8 is applied to the price of non-traded goods and services.

From the viewpoint of international economy, the transfer of payment such as contract tax, duty, subsidy and interest are considered as a domestic monetary movement without direct productivity. These transfer payment are excluded from the project cost.

Economic prices of traded agricultural output (cereals and pulses) and farm inputs (urea, triple super phosphate (TSP) and potassium chloride (KCl)) are estimated on the basis of IBRD projection of world market prices for 1995 in constant 1985 terms. The domestic

cost elements such as transport, handling and processing down to the farm gate level were multiplied by the standard conversion factor (0.8).

The shadow price of 0.667 is applied for unskilled labors considering the present employment situation.

Economic prices of cereals and pulses, and inputs are shown in Table K.1.

2.3 Economic Benefits

The project benefit is born as a result of irrigation and drainage development as well as agricultural extension works. Present cultivated area is expected to increase productivity while currently fallow land due to water logging or alkalinity problem recovers its fertility. Non-irrigated area within CCA will also be expected to increase productivity as a result of introduction of better farming practice through extension works.

Expected benefit is defined as the difference of primary profit from crop production between future with project and without project conditions. Crop budget in future under with project condition is estimated irrespective of holding sizes, based on the proposed farming practices. On the other hand, crop budget under without project condition is estimated by holding sizes, assuming that the present farming practices will not change in future under the condition. The results of crop budgets are summarized in Table K.2. It may be a conservative assumption considering that further exploitation of groundwater will result in the increase of production cost as well as in the decrease of water yield, and thereby in the decrease of net benefit. The incremental benefit is expected to increase year by year and reach the full benefit in certain years after the completion of irrigation and drainage facilities. The build-up period to the full benefit is assumed to be 5 years.

As mentioned in the previous chapter, the area-wise development for the project is planned to be carried out as follows:

Accumulated Development Areas

Unit: ha

Construction year	Sarojini Nagar	Sataon	Sursa	Purwa
1	0	0	0	0
2	594	515	693	490
3	3,566	3,090	4,156	2,940
4	7,727	6,695	9,004	6,371
5	11,888	10,300	13,852	9,802
6	14,862	12,874	17,313	12,252

As a result, irrigation and drainage benefit is expected to be born from the 3rd construction year. The annual incremental benefit at the full development stage is estimated at Rs.488.5 million (refer to Tables K.3) as shown below:

Unit: Rs.million

Condition	Sarojini Nagar	Sataon	Sursa	Purwa	Total
With Project					
Kharif	105.4	89.5	116.1	86.8	397.8
Rabi	127.1	107.9	139.8	105.8	480.6
Perennial	-	-	2.9	-	2.9
Total (A)	232.4	197.4	258.8	192.6	881.3
Without Project					
Kharif	39.4	25.5	45.5	35.0	145.4
Rabi	54.9	56.1	94.9	36.3	242.2
Perennial	-	-	5.2	-	5.2
Total (B)	94.3	81.7	145.6	71.3	392.8
Incremental (A) - (B)	138.2	115.8	113.2	121.3	488.5

2.4 Economic Costs

The economic project cost is estimated based on the financial project cost, taking account of transfer payment and standard conversion factor for non-traded goods within the financial construction cost. The economic project costs is estimated at Rs.2,124.4 million for four Representative Areas (refer to Table K.4), being broken down into the following:

Economic Cost for Initial Investment

Unit: Rs.10⁶

Description	Sarojini Nagar	Sataon	Sursa	Purwa	Total
1. Direct Construction Cost	320.3	444.2	463.1	307.4	1,535.1
2. Procurement of Supporting Equipment	1.5	1.3	1.7	1.2	5.8
3. Land Acquisition	4.2	5.9	5.7	2.4	19.4
4. Administration Cost	38.6	33.4	44.9	31.8	148.7
5. Engineering Services	57.7	50.0	67.2	47.5	222.4
Sub-total	<u>422.3</u>	<u>534.8</u>	<u>583.8</u>	<u>390.4</u>	<u>1,931.3</u>
6. Contingency	42.2	53.5	58.4	39.0	193.1
Total	464.5	588.3	642.2	429.4	2,124.4

The total annual economic operation and maintenance cost at the full development stage is estimated at Rs.33.4 million in total, as shown below:

Annual Economic O&M Cost

Unit: Rs.1,000

Description	Sarojini Nagar	Sataon	Sursa	Purwa	Total
1. Main system					
a. Irrigation Facility					
- Canal	1,060	3,930	1,640	980	7,610
- Augmentation Facilities	670	760	3,930	1,150	6,510
b. Drainage Facilities	1,050	610	1,760	1,490	4,910
c. Service Roads	680	1,100	510	420	2,710
2. On-farm system	2,950	2,620	3,600	2,460	11,630
Total	6,410	9,020	11,440	6,500	33,370

Some equipment of the irrigation and drainage system are replaced at certain intervals of periods. Useful life and costs of those equipment are as shown below:

Useful Life and Replacement Costs

Description	Sarojini Nagar		Sataon		Sursa		Purwa	
	Useful life	Cost (Rs.10 ³)	Useful life	Cost (Rs.10 ³)	Useful life	Cost (Rs.10 ³)	Useful life	Cost (Rs.10 ³)
1. Irrigation system								
a. pumping equipment	20	10,348	20	13,230	10	28,936	10	7,984
b. Gate	10	16	10	200	10	16	10	24
2. Supporting equipment	10	1,744	10	1,512	10	2,032	10	1,440

2.5 Economic Evaluation

The economic internal rate of return for the project is calculated based on the economic cost and benefit and the project implementation schedule. The results are as shown on Table K.5 and summarized below:

Sarojini Nagar	19.2%
Sataon	13.7%
Sursa	12.0%
Purwa	18.4%
Overall	15.5%

The results show that the project is economically feasible with an internal rate of return of 15.5% for the overall area, ranging from 19.2% for the Sarojini Nagar area to 12.0% for the Sursa area.

2.6 Sensitivity Analysis

A sensitivity analysis is carried out to evaluate the soundness of the project against possible adverse changes in the future for the following cases; (i) reduction of project benefit by 10% due to unexpected decrease in forecast prices, (ii) project cost overrun by 10% and (iii) combination by cases (i) and (ii). The result is presented below:

Unit: %

Description	Sarojini Nagar	Sataon	Sursa	Purwa	Overall
1. Case (i)	17.7	12.5	10.8	16.9	14.1
2. Case (ii)	17.9	12.7	11.0	17.1	14.4
3. Case (iii)	16.4	11.5	9.9	15.7	13.1

The result of sensitivity analysis indicates that the economic viability of the project is rather insensitive to the possible adverse changes.

3. Financial Analysis

A financial analysis of the project is made by the analysis of the typical farm budgets and assessment for repayment of the project construction cost.

3.1 Farm Budget Analysis

In order to evaluate the project feasibility from farmer's household economy, typical farm budgets of marginal farmers are prepared for the future with and without conditions as shown below (refer to Table K.6):

Unit: Rupees

Area	With Project			Without Project			Incremental Benefit
	Kharif	Rabi	Total	Kharif	Rabi	Total	
Sarojini Nagar (0.58ha)	3,195	3,099	6,294	2,082	2,065	4,147	2,147
Sataon (0.58ha)	3,118	3,001	6,119	910	1,868	2,778	3,341
Sursa (0.53ha)	2,839	2,679	5,518	1,627	2,028	3,655	1,863
Purwa (0.56ha)	3,119	2,818	5,937	2,090	1,785	3,875	2,062

As seen from the above table, the income of marginal farmers is expected to increase by 50% to 120%. Their economic situations are sure to be improved.

3.2 Capacity to Pay

After the implementation of the project, operation and maintenance cost of the irrigation and drainage systems as well as of on-farm facilities is shouldered to beneficial farmers. Those costs are estimated as shown below:

Annual Financial O&M Costs

Description	Sarojini Nagar		Sataon		Sursa		Purwa	
	Total (Rs.10 ³)	Per ha (Rs.)	Total (Rs.10 ³)	Per ha (Rs.)	Total (Rs.10 ³)	Per ha (Rs.)	Total (Rs.10 ³)	Per ha (Rs.)
1. Main System	4,000	276	7,600	590	8,700	502	4,600	375
2. On-farm facilities	3,600	242	3,200	249	4,400	254	3,000	245
Total	7,600	518	10,800	839	13,100	756	7,600	620

O&M costs for the main system will have to be paid as water charge while those for on-farm facilities are recovered as labor force.

On the other hand, incremental benefit of a farmer is estimated at Rs.3,500 to Rs.5,760 per ha. Water charges which farmers will have to shoulder are only 15% at maximum, which proves that farmers could pay water charge easily.

3.3 Repayment

Fund requirement for construction of the project is estimated at Rs.3,351 million. Based on the estimated fund requirement, a cash flow statement is prepared under an assumption of the following conditions:

- (a) 80% of fund requirement is financed by the international organization with loan service fee of 2.5% per annum and a repayment period of 30 years including a grace period of 10 years.
- (b) Remaining local currency is financed by the budget allocation of the Government with no interest and no repayment.

The cash flow statement is shown in Table K.7.

The project brings about a great improvement in farm budget and gives an incentive to the farmers in the project area. The government should subsidize about Rs.1.6 million to Rs.230.5 million including loan repayment, loan service fee and a part of O&M cost annually for the project during the repayment of 30 years.

4. Socio-economic Impact

The following socio-economic impacts are expected through the implementation of the project.

(1) Increase of crop production

The project bring about considerable increase of crop production. As shown in ANNEX E AGRICULTURE, expected incremental production of crops are: 59,000 tons for paddy, 38,000 tons for wheat, 10,200 tons for oilseeds, 19,000 tons for pulses, 39,000 tons for potatoes, etc. Considerable production increase of oilseeds and pulses will induce agro-processing industry which will contribute to the diversification of economic activity.

(2) Alleviation of poverty and improvement of nutritious status

Upon attainment of reliable irrigation water supply and introduction of new farming technology with new cropping patterns, productivity of crops remarkably increases, which leads to improvement of nutritious status of people. Even marginal farmer having six family members with 0.4 ha of cultivable land is able to attain self-sufficiency in cereals in calorie basis. Pulses and oilseed crops are also harvested more, which results in the improvement of nutritious status of family.

(3) Employment opportunity

During the construction stage, about 10.3 million man-days, equivalent to Rs.361.0 million of employment opportunity is generated. Laborers are recruited from adjacent villages. This employment opportunity are sure to stimulate economic activity in rural area. Also are expected employment opportunity for agricultural laborer through production increase.

(4) **Women's development**

As a part of training programme, women are educated to learn how to read and write. Once get educated, they have another incentive to learn more. They are expected to play a vital role in agriculture production through agricultural extension programme.

(5) **Brick making industry**

The project requires vast amount of bricks for canal lining, structural material and road pavements. The required amount of bricks are usually produced near the construction sites. Brick factories produce more bricks as required, which generates other employment opportunities.

(6) **Environment**

Ground water table in Sarojini Nagar and Sataon Areas has been lowered in recent years. Augmentation of canal water is only a possible way to avoid further deterioration of ground water condition.

Inundation of water in Purwa Area has been a very serious concern from the view point not only of agricultural production but also of the environment of human life. Proposed drainage plan improves present agriculture productivity, and early drainage reduces current problem of higher rate of water-born diseases.

5. Project Justification

Internal rate of return (IRR) of the project in respective Representative Areas shows different value ranging from 12.0% for Sursa to 19.2% for Sarojini Nagar. The IRR of overall project shows 15.5%.

The project in the Sarojini Nagar area shows the highest IRR of 19.2% among four Representative Areas. Augmentation of irrigation water supply will increase irrigation area and reduce further deterioration of groundwater level. The project will also contribute to equitable distribution of water through on-farm development and thereby to equitable development which is one of the objectives of State Development Plan.

The project in the Sataon area shows IRR of 13.7%. The project include canal improvement of Asiwan branch canal, whose benefit will be expected to be born from other

areas commanded by the branch when on-farm development works will be carried out. If this cost is allocated proportionally to beneficial command areas, the IRR would further be increased. The same effect as Sarojini Nagar area will be expected with regards to even distribution of canal water and preventing the deterioration of ground water level.

The project in the Sursa area shows the lowest IRR of 12.0%, reflecting relatively better yield level of crops under the present condition. Irrigation water supply by canal will be reduced from present over supply condition to the proposed volume determined by the Roster, which may reduce benefit to the area but contribute to the augmentation of irrigation water volume to downstream area. Drainage improvement will increase Kharif cropping area drastically. Even distribution of water and improvement of nutritious status of farmers are expected from the project.

The project in the Purwa area shows the IRR of 18.4%, following Sarojini Nagar area. Drainage improvement will bring about the increase of cropped area as well as yield increase through the improvement of soil condition. Traffic condition will also be improved, and occurrence of water born diseases will be reduced through the reduction of inundation area and duration.

The IRR of the overall project shows 15.5%. The results of financial analysis reveals the improvement of farm income with repayability of water charge. Considering this IRR and positive socio-economic impacts as mentioned above, in light with the objectives of the State Five-Year Development Plan, all projects can be justified.

TABLES

Table K.1 Derivation of Economic Farmgate Prices in 1995

for Major Crops

ITEM	Unit	Commodity					
		Wheat	Paddy	Maize	Sorghum	Groundnut	Sugarcane
World Market Price 1995 1/	US\$	160	263	98	93	371	173
Quality Adjustment	%	100	75	100	100	100	100
World Market Price, Adjusted	US\$	160	198	98	93	371	173
Ocean Freight & Insurance 2/	US\$					51	0
Domestic Border Price	US\$	160	198	98	93	422	173
Exchange Rate	Rs/US\$	25.90	25.90	25.90	25.90	25.90	25.90
Domestic Border Price	Rs	4,138	5,116	2,550	2,415	10,938	4,473
Domestic Handling & Transport 3/	Rs	400	400	400	400	400	400
Wholesale Price	Rs	4,538	5,516	2,950	2,815	11,338	4,873
Processing 3/	Rs	0	-169	0	0	-200	-95
Processing Ratio	%	0	67	0	0	40	7
Sales of By-products	Rs		70			3,281	
Transport from Farmgate 3/	Rs	-80	-80	-80	-80	-80	-80
Economic Farmgate Price	Rs	4,458	3,572	2,870	2,735	7,657	414
Financial Farmgate Price	Rs	2,310	1,880	1,880	1,880	5,150	310
Conversion Factor		1.930	1.900	1.526	1.455	1.487	1.337

Remarks: 1/ From "Commodity Price Forecasts --December 1990 (IBRD, Economic Analysis and Projections Department) commodity prices projected for 1995 in current US Dollars have been deflated by the MUV index to obtain price projections in constant prices of 1990:

Wheat: Canadian No.1, Western Red Spring, FOB Thunder Bay

Paddy: Rice: Thai, milled, 5% broken, FOB Bangkok

Maize: US No.2, Yellow, FOB Gulf ports;

Sorghum: US No.2, Milo Yellow, FOB Gulf ports

2/ With India on the margin of self-sufficiency in foodgrains, it is assumed that, depending on the size of the annual harvests, exports or imports will occur in the short- and medium-term, and international transport costs have therefore been omitted.

3/ Adjusted with Standard Conversion Factor of 0.8

for Fertilizer

ITEM	Unit	Fertilizer			
		UREA	TSP	DAP	KCI
Projected 1995 world market price 1/	US\$	111	98	125	62
International shipping/handling charge	US\$	42	42	44	39
CIF price at Calcutta	US\$	153	140	170	102
Exchange Rate	Rs/US\$	25.90	25.90	25.90	25.90
Value equivalent to Rs./ton	Rs	3,969	3,633	4,390	2,630
Domestic transport/handling to wholesale point	Rs	400	400	400	400
Price at Lucknow	Rs	4,369	4,033	4,790	3,030
Transport/handling to farmgate 2/	Rs	80	80	80	80
Farmgate economic price	Rs	4,449	4,113	4,870	3,110
Price per ton of nutrient	Rs	9,671	8,569		5,184
		N	P2O5		K2O

Remarks: 1/ From "Commodity Price Forecasts --December 1990 (IBRD, Economic Analysis and Projections Department) commodity prices projected for 1995 in current US Dollars have been deflated by the MUV index to obtain price projections in constant prices of 1990:

2/ Adjusted with Standard Conversion Factor of 0.8

Table K.2 Economic Benefit per ha under With and Without - Project Conditions

Holding Size Classes	Cropping Season	Sarojini Nagar												Net Benefit
		Sauron				Surga				Purwa				
		Distribution by Size	Gross Benefit	Production Cost	Net Benefit	Distribution by Size	Gross Benefit	Production Cost	Net Benefit	Distribution by Size	Gross Benefit	Production Cost	Net Benefit	
With-Project Condition														
Marginal	Khariif	9,962	2,873	3,007	6,955	9,565	2,697	6,868	9,908	2,823	7,085	9,908	2,823	7,085
	Rabi	11,047	2,497	2,506	7,889	10,019	2,363	7,657	10,394	2,252	8,143	10,394	2,252	8,143
	Perennial					12,420	5,686	6,734						
	Total	21,008	5,369	5,513	14,843	19,405	5,075	14,330	20,302	5,074	15,228	20,302	5,074	15,228
Small	Khariif	6,522	2,544	3,738	3,037	6,931	2,530	4,401	7,865	3,023	4,842	7,865	3,023	4,842
	Rabi	7,479	2,015	2,613	5,737	9,213	2,542	6,671	7,255	1,914	5,341	7,255	1,914	5,341
	Perennial					10,764	5,251	5,513						
	Total	14,001	4,559	6,351	8,774	15,806	5,084	10,722	15,120	4,937	10,183	15,120	4,937	10,183
Semi-medium	Khariif	7,279	2,766	3,599	2,629	7,001	2,246	4,755	8,126	1,651	6,475	8,126	1,651	6,475
	Rabi	9,094	2,141	2,268	6,013	9,805	2,325	7,480	7,288	1,829	5,459	7,288	1,829	5,459
	Perennial					10,764	4,965	5,799						
	Total	16,373	4,907	5,867	8,642	16,427	4,597	11,830	15,414	3,480	11,934	15,414	3,480	11,934
Medium	Khariif	6,150	2,300	3,550	5,289	7,457	2,601	4,856	7,423	2,900	4,523	7,423	2,900	4,523
	Rabi	7,989	2,515	2,491	7,573	9,613	2,226	7,387	7,001	1,859	5,142	7,001	1,859	5,142
	Perennial					10,764	5,251	5,251						
	Total	14,139	4,815	6,041	12,862	16,671	4,870	11,801	14,424	4,759	9,665	14,424	4,759	9,665
Total Weighted	Khariif	7,453	2,215	3,224	3,907	6,304	1,817	4,487	7,783	2,498	5,285	7,783	2,498	5,285
	Rabi	8,677	2,964	2,672	6,065	9,202	2,120	7,082	7,654	1,920	5,734	7,654	1,920	5,734
	Perennial					10,764	5,751	5,013						
	Total	16,130	5,179	5,896	9,972	15,868	4,056	11,156	15,437	4,418	11,019	15,437	4,418	11,019
Incremental	Khariif	6,775	2,515	3,601	3,508	6,967	2,339	4,628	7,822	2,546	5,276	7,822	2,546	5,276
	Rabi	8,225	2,282	2,505	6,234	9,469	2,323	7,146	7,265	1,879	5,386	7,265	1,879	5,386
	Perennial					10,764	5,340	5,424						
	Total	15,000	4,797	6,105	9,742	16,080	4,706	11,373	15,087	4,425	10,662	15,087	4,425	10,662
Incremental	Khariif	3,186	358	-594	3,446	2,598	338	2,240	2,086	277	1,809	2,086	277	1,809
	Rabi	2,822	215	1	1,655	550	40	511	3,129	372	2,757	3,129	372	2,757
	Perennial	0	0	0	0	1,656	346	1,310	0	0	0	0	0	0
	Total	6,009	573	-593	5,101	3,325	369	2,956	5,215	649	4,566	5,215	649	4,566

Table K.3 Breakdown of the Expected Project Benefit

Area	Cropping Season	Project Area (ha)	With Project Condition				Without Project Condition				Incremental Benefit (Rs.million)
			Cultivated Area (ha)	Gross Income (Rs.million)	Production Cost (Rs.million)	Primary Profit (Rs.million)	Cultivated Area (ha)	Gross Income (Rs.million)	Production Cost (Rs.million)	Primary Profit (Rs.million)	
1 Sarojini Nagar	Kharif	14,862	14,862	148.1	42.7	105.4	9,237	62.6	23.2	39.4	66.0
	Rabi	14,862	14,862	164.2	37.1	127.1	9,275	76.3	21.4	54.9	72.1
	Annual			312.2	79.8	232.4		138.9	44.6	94.3	138.2
2 Sataon	Kharif	12,874	12,874	128.2	38.7	89.5	7,274	51.7	26.2	25.5	64.0
	Rabi	12,874	12,874	142.2	34.3	107.9	9,006	78.7	22.6	56.1	51.8
	Annual			270.5	73.0	197.4		130.4	48.7	81.7	115.8
3 Sursa	Kharif	17,313	16,880	161.7	45.6	116.1	9,834	68.5	23.0	45.5	70.6
	Rabi	16,880	16,880	180.1	40.3	139.8	13,280	125.7	30.9	94.9	44.9
	Perennial	433	433	5.4	2.5	2.9	960	10.3	5.1	5.2	-2.3
	Annual			347.2	88.3	258.8		204.6	59.0	145.6	113.2
4 Purwa	Kharif	12,252	12,252	121.4	34.6	86.8	6,638	51.9	16.9	35.0	51.8
	Rabi	12,252	12,252	135.3	29.5	105.8	6,735	48.9	12.7	36.3	69.5
	Annual			256.7	64.1	192.6		100.9	29.6	71.3	121.3
Total		57,301	57,301	1186.6	305.3	881.3	32,983	574.7	181.9	392.8	488.5

Table K.4 Annual Economic Disbursement Schedule

Unit: Rs.1,000

Description	Amount	1993	1994	1995	1996	1997	1998
I Sarojini Nagar Study Area							
I-1 Direct Construction Cost	320,346	0	11,619	60,303	104,581	85,749	58,094
I-2 Procurement of Supporting Equipment	1,496	748	748	0	0	0	0
I-3 Land Acquisition	4,205	0	2,102	2,102	0	0	0
I-4 Administration Cost	38,568	5,110	6,692	6,692	6,692	6,692	6,692
I-5 Engineering Service	57,683	10,492	13,387	14,059	11,061	5,065	3,618
Sub-Total	<u>422,298</u>	<u>16,350</u>	<u>34,548</u>	<u>83,156</u>	<u>122,334</u>	<u>97,506</u>	<u>68,404</u>
I-6 Physical Contingency	42,230	1,635	3,455	8,316	12,233	9,751	6,840
Total	<u>464,528</u>	<u>17,985</u>	<u>38,003</u>	<u>91,472</u>	<u>134,567</u>	<u>107,257</u>	<u>75,244</u>
II Sataon Study Area							
II-1 Direct Construction Cost	444,197	0	16,542	85,418	138,316	121,210	82,711
II-2 Procurement of Supporting Equipment	1,296	648	648	0	0	0	0
II-3 Land Acquisition	5,936	0	2,968	2,968	0	0	0
II-4 Administration Cost	33,409	4,426	5,797	5,797	5,797	5,797	5,797
II-5 Engineering Service	49,967	9,089	11,596	12,178	9,582	4,388	3,134
Sub-Total	<u>534,805</u>	<u>14,163</u>	<u>37,551</u>	<u>106,361</u>	<u>153,694</u>	<u>131,394</u>	<u>91,642</u>
II-6 Physical Contingency	53,481	1,416	3,755	10,636	15,369	13,139	9,164
Total	<u>588,286</u>	<u>15,579</u>	<u>41,306</u>	<u>116,997</u>	<u>169,064</u>	<u>144,534</u>	<u>100,806</u>
III Sursa Study Area							
III-1 Direct Construction Cost	463,072	0	14,886	86,357	159,343	128,054	74,432
III-2 Procurement of Supporting Equipment	1,743	871	871	0	0	0	0
III-3 Land Acquisition	6,862	0	3,431	3,431	0	0	0
III-4 Administration Cost	44,928	5,952	7,795	7,795	7,795	7,795	7,795
III-5 Engineering Service	67,196	12,223	15,595	16,378	12,885	5,901	4,215
Sub-Total	<u>583,801</u>	<u>19,046</u>	<u>42,578</u>	<u>113,961</u>	<u>180,024</u>	<u>141,750</u>	<u>86,442</u>
I-6 Physical Contingency	58,380	1,905	4,258	11,396	18,002	14,175	8,644
Total	<u>642,182</u>	<u>20,951</u>	<u>46,836</u>	<u>125,357</u>	<u>198,026</u>	<u>155,925</u>	<u>95,086</u>
IV Purwa Study Area							
VI-1 Direct Construction Cost	307,439	0	10,933	58,067	100,438	83,334	54,667
VI-2 Procurement of Supporting Equipment	1,233	617	617	0	0	0	0
VI-3 Land Acquisition	2,368	0	1,184	1,184	0	0	0
VI-4 Administration Cost	31,795	4,212	5,517	5,517	5,517	5,517	5,517
VI-5 Engineering Service	47,553	8,650	11,036	11,590	9,119	4,176	2,983
Sub-Total	<u>390,388</u>	<u>13,479</u>	<u>29,286</u>	<u>76,358</u>	<u>115,073</u>	<u>93,026</u>	<u>63,166</u>
I-6 Physical Contingency	39,039	1,348	2,929	7,636	11,507	9,303	6,317
Total	<u>429,427</u>	<u>14,827</u>	<u>32,215</u>	<u>83,993</u>	<u>126,580</u>	<u>102,329</u>	<u>69,483</u>
TOTAL PROJECT COST							
A. Direct Construction Cost	1,535,054	0	53,980	290,145	502,678	418,347	269,904
B. Procurement of Supporting Equipment	5,768	2,884	2,884	0	0	0	0
C. Land Acquisition	19,371	0	9,685	9,685	0	0	0
D. Administration Cost	148,700	19,700	25,800	25,800	25,800	25,800	25,800
E. Engineering Service	222,400	40,454	51,614	54,205	42,647	19,530	13,950
Sub-total	<u>1,931,293</u>	<u>63,038</u>	<u>143,964</u>	<u>379,835</u>	<u>571,125</u>	<u>463,677</u>	<u>309,654</u>
F. Contingency	193,129	6,304	14,397	37,984	57,112	46,368	30,965
TOTAL	<u>2,124,422</u>	<u>69,342</u>	<u>158,360</u>	<u>417,819</u>	<u>628,237</u>	<u>510,045</u>	<u>340,619</u>