

The detailed design is carried out by the consultant to establish the detailed plan for the facilities and equipment, based upon the field survey in the sites involved in the Project. During the field survey, special attention is paid to clarify the situation of land to be used for the construction work, particularly concerning the courses of pipelines, with the cooperation and coordination of the RWS and the LCCDs so that no questions would be raised among villagers during the actual work. The results of the detailed design are reflected in the subsequent preparation of tender documents, and the schedule of the tender is decided with the consent of concerned offices and agencies of the government of Japan. The consultant administers and controls the process of tendering for and on behalf of the executing agency, evaluates its results and assists the executing agency in concluding the contract with an eligible Japanese firm.

As a first step during the construction stage, the consultant's staff carries out the transfer of the Project sites to the construction firm, and as the work proceeds, they engage in supervising it with the cooperation and coordination of the concerned offices and agencies as well as the executing agency on the Yemeni side. When the construction of the facilities is completed, they conduct the inspection and direct technological transfer on the operation and maintenance. Upon completion and delivery of facilities, the final completion report is prepared by the consultant.

5.5.3 Procurement Plan

(1) Local Procurement

In Yemen the supply of oil products is stable thanks to the currently vigorous development in this sector. In addition, cement, its main industrial product other than oil, has steadily been supplied, and can be obtained without difficulty. As a result of the survey of the local market, the following materials are recommended to be procured in this country for the execution of the Project.

1) Cement

Cement is produced by the Basil Plant with its annual capacity of 250 thousand tons completed with the Soviet assistance and the Amran Plant with a 500 thousand ton capacity constructed by a Japanese firm, which maintain the stable supply in the market.

2) Concrete Block

Concrete blocks as building material are being supplied in abundance by small house industries across the country.

3) Aggregate and Water

Aggregate in general is of degraded quality, with coarse aggregate made of crushed basaltic rock and fine one containing much silt. However, a steady supply, relatively good in quality, is found in the suburbs of the capital, and procurement mainly in this area is planned for the Project. The water used for the work can be obtained in and around the sites.

4) Fuel

Although prices have been raised, the production and supply of petroleum and diesel oil have been stable, and are expected to hardly raise problems for the operation of construction vehicles and equipment.

5) Vertical Shaft Pumps

The great majority of deep well pumps in this country are shared by diesel engine driven vertical shaft pumps, imported from European countries such as Italy, Denmark, Cyprus, etc. Since the procurement of their spare parts are much easier and local conditions for maintenance are better than with submersible motor pumps, this type of pumps are planned to be purchased locally for use in the facilities where high-lifting capacities are not required. Diesel engines for the pumps are to be procured, based upon the recommendation of the pump

manufacturer.

(2) Procurement in Japan

Most of equipment and materials for the construction of water supply facilities are imported ones in Yemen, and their procurement has long been in difficult conditions due to severe import restrictions by the government, deriving from shortages of foreign reserves. To make the matter worse, progressive inflation since the outbreak of the Gulf war has sent market prices of all imported products skyrocketing. Under the present circumstances, therefore, main equipment and materials are planned to be procured in Japan, since they are stable both in quality and prices. These products are listed as follows:

- 1) Materials for water well construction
Well casing and well screen
- 2) Pumps
Submersible motor pumps for deep wells and multi-stage volute pumps for booster pumps (Vertical shaft pumps shall be locally purchased, as described in the foregoing section.)
- 3) Power drive units
Diesel engine driven generator (Diesel engines for vertical shaft pumps shall be procured with pumps as an assembly as recommended by pump manufacturers.)
- 4) Steel panel tanks
- 5) Plumbing materials
Steel pipe, fittings and valves

(3) Construction Equipment and Vehicles

The Project sites are dispersed countrywide, with the construction work planned to proceed simultaneously in two separate sites. Under such a situation, the headquarters for construction work is planned to be stationed in capital of Sana'a where the main office of the RWSD is located for the purpose of developing the most effective and efficient controlling of the work. For the

headquarters' management and control of the quality and progress of work, cargo trucks for transportation of equipment/materials and 4-wheel drive vehicles, etc. are required as well as for the execution of work developed in vast areas of the sites. In addition, one unit of crane truck is necessary for handling heavy equipment/materials. Local acquisition of such construction equipment/vehicles is not easy either through procurement or through lease. In this view, they are proposed to be procured in Japan.

(4) Temporary Facilities

For temporary facilities such as offices and lodgings quarters, etc., both in Sana'a and in the sites, a similar difficult situation is prevalent. These facilities are planned to be procured in Japan as well.

5.5.4 Implementation Schedule

The implementation schedule of the Project with grant aid from the government of Japan is to proceed in accordance with the procedure as described hereunder.

- 1) Exchange of Notes between the governments of Japan and the Republic of Yemen
- 2) Consulting contract
- 3) Detailed design and preparation of tender documents
- 4) Tendering and conclusion of the contract
- 5) Procurement of equipment and materials
- 6) Shipping of procured equipment and materials and their customs clearance
- 7) Field construction work
- 8) Delivery of completed facilities

The pre-construction stage in this procedure from the Exchange of Notes to the conclusion of the contract takes about four (4) months, and the subsequent process for the procurement, about five (5) months until equipment/materials are delivered for the site construction.

The contractor's field construction as the final stage consists of diverse types of works including drilling, civil and mechanical works, and the periods necessary for construction in the respective five (5) sites, selected on the basis of priority as well as their cost-effectiveness for investment, are estimated to range from 10 to 12 months after the conclusion of the contract, requiring a full construction team covering such diverse works. Taking this situation into account, it is judged to be necessary to divide the entire construction work into phases. The most pertinent division is planned to be three (3) phases, based upon priority and contents of the work, with the arrangement of the five sites in the three phases proposed as follows:

Phase I Al Mallaheeth (Sa'dah) and Iyal Qasim (Sana'a)

Phase II Al Usfyn (Taizz)

Phase III Aflah Al Yaman (Hajjah) and Al Ghudu (Marib)

The detailed implementation schedule in each phase thus divided is shown in Fig. 5.10.

Table 5.10 IMPLEMENTATION SCHEDULE

| | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | | | | |
|-----------|----------------------------|------------------------------|----------|---|----------|----------|---|---|---|---|-----------------|-----------------|----|--|--|--|--|
| 1st phase | Detailed Design | ★ Contract for Consultant | | | | | | | | | | | | | | | |
| | | Field survey | | | | | | | | | | | | | | | |
| | | Homework | | | | | | | | | | | | | | | |
| | | Tender & Evaluation | | | | | | | | | | | | | | | |
| 1st phase | Procurement & Construction | ★ Contract for Construction | | | | | | | | | | | | | | | |
| | | Procurement & Transportation | | | | | | | | | | | | | | | |
| | Al Mallaheeth | | | | | Drilling | | | | | | Mechanical work | | | | | |
| | | | | | | | | | | | | Civil work | | | | | |
| 2nd Phase | Detailed Design | ★ Contract for Consultant | | | | | | | | | | | | | | | |
| | | Field survey | | | | | | | | | | | | | | | |
| | | Homework | | | | | | | | | | | | | | | |
| | | Tender & Evaluation | | | | | | | | | | | | | | | |
| 2nd Phase | Procurement & Construction | ★ Contract for Construction | | | | | | | | | | | | | | | |
| | | Procurement & Transportation | | | | | | | | | | | | | | | |
| | Al Usfyn | | | | Drilling | | | | | | | Mechanical work | | | | | |
| | | | | | | | | | | | | Civil work | | | | | |
| 3rd Phase | Detailed Design | ★ Contract for Consultant | | | | | | | | | | | | | | | |
| | | Field survey | | | | | | | | | | | | | | | |
| | | Homework | | | | | | | | | | | | | | | |
| | | Tender & Evaluation | | | | | | | | | | | | | | | |
| 3rd Phase | Procurement & Construction | ★ Contract for Construction | | | | | | | | | | | | | | | |
| | | Procurement & Transportation | | | | | | | | | | | | | | | |
| | Aflah | | Drilling | | | | | | | | | Mechanical work | | | | | |
| | Al Yaman | | | | | | | | | | Civil work | | | | | | |
| 3rd Phase | | | | | | | | | | | Plumbing | | | | | | |
| | Al Ghudu | | Drilling | | | | | | | | Mechanical work | | | | | | |
| | | | | | | | | | | | Civil work | | | | | | |
| | | | | | | | | | | | Plumbing | | | | | | |

5.5.5 Scope of Responsibilities

The responsibilities of both the Yemen and the Japanese sides for the implementation of the Project are summarized as follows:

(1) Responsibilities of the Yemen Side

- 1) To acquire, clean and grade the land necessary for the construction of the water supply facilities including water wells, pump stations, water tanks, pipelines with service facilities and others as well as for the contractor's temporary facilities such as site offices, lodgings, yards, etc., in the respective sites.
- 2) To provide and maintain access roads to the locations of facilities to be constructed within the sites and to improve and repair roads within the premises of the sites where such measures are required for the construction work.
- 3) To install distribution lines using piping materials supplied under the Project in the four (4) sites out of five (5) included in the Project.
- 4) To construct other facilities than those included in this basic design study, the installation of which might be decided on the Yemeni side.

(2) Responsibilities of the Japanese Side

- 1) To construct the water supply systems consisting of:
 - a. water source (s),
 - b. intake facilities such as deep well pump stations,
 - c. transmission facilities such as booster pump stations,
 - d. distribution facilities such as water reservoirs,
 - e. and service facilities such as public fountains,

as planned in the basic design study for the Project in the five (5) sites located in Yemen as designated hereunder:

- a. Al Mallaheeth (Sa'dah governorate),
 - b. Iyal Qasim (Sana'a governorate)
 - c. Al Usfyn (Taizz governorate)
 - d. Aflah Al Yaman (Hajjah governorate)
 - e. Al Ghudu (Marib governorate)
- 2) To bear the cost of all equipment and materials, temporary facilities, construction equipment and vehicles and others necessary for accomplishing the work other than those to be borne by the Yemeni side.
 - 3) To provide vehicles for operation and maintenance, including two (2) units of water tankers to be used for Al Usfyn for serving water to the mountainous villages.
 - 4) To supply piping materials for the extension of distribution lines from the ends of those planned to be installed by the Japanese side to villages in the four (4) Projects sites other than Al Usfyn.
 - 5) To provide the consulting service to supervise the constructionwork of the Project.

CHAPTER VI

PROJECT EVALUATION AND CONCLUSION

CHAPTER VI PROJECT EVALUATION AND CONCLUSION

6.1 PROJECT EVALUATION

This Project is aimed at construction water supply facilities at five (5) sites ranking higher in the priority list of the Yemen government involving the present population of 39,500 for the planned served population of 57,600 in total. It has an effect to contribute to one of the government's top-priority policies to promote the rural water supplies through the activities of the RWSD of the MEW.

In the Project sites, painstaking labor by women and children for daily water fetching through long, rugged mountainous paths has been continuing from ancient times. The construction of facilities near dwelling areas of inhabitants can save much of such hard work and help to switch saved labor to other productive activities. As one of the largest effects resulting from the implementation of the Project, the improvement of sanitation and health in environment of sites will stabilize and upgrade the rural life. In addition, the commencement of management and operation of facilities by the local communities themselves is expected to contribute to bracing the communal life, enhancing cooperation and coordination among inhabitants. Various effects anticipated from the Project implementation are compared with the present conditions as follows:

Table 6.1 Effects of the Project/Extent of Improvement

| Current Situation/ Difficulties | Measures Taken by the Project | Anticipated Effects/ Improvement Range |
|---|--|---|
| The 5 Projects sites are typical mountainous villages where no water supply facilities exist. Inhabitants of 39,500 in total depend upon costly water to sell | The Project is planned to construct water supply systems in the respective sites for the planned served population of 57,600, composed of deep well sources in wadi low- | Upon completion, the inhabitants can receive safe and stable water service in premises of their dwelling areas in mountainsides. A rate of consumption is |

| Current Situation/ Difficulties | Measures Taken by the Project | Anticipated Effects/ Improvement Range |
|--|---|---|
| <p>for their drinking and cooking water, but main water sources remain to be un-sanitary cisterns and hand-dug wells likely to run dry in dry seasons, with their consumption limited to less than 20 lit. per capita per day. This water practice has been the main cause of incidence of waterborne infectious diseases, among inhabitants, producing chronic spread of bilharzia.</p> | <p>land, transmission facilities extending from the sources up to mountains, distribution and service facilities in the mountainous dwelling areas. A planned supply rate is 30 lit. per capita per day (40 lit. for Al Mallaheeth and Aflah Al Yaman where demand increases, due to dominant tropical weather), except Al Usfyn where a water source development scheme is planned with appurtenant supply facilities.</p> | <p>increases from 10 - 20 lit./c/d to 30 - 40 lit./c/d. This Project directly meets the BHN of the inhabitants, and improves sanitation and health in the mountainous dwelling areas, keeping the incidence of epidemics in check.</p> |
| <p>The current prices of water for drinking and cooking range from YR100 - YR200 on the average. Since average monthly incomes per household are YR1,600 to YR3,000, the purchase of water by an ordinary household is limited to 2 or 3 times in a month. Such spending for water amounts to more than 10% in their incomes, causing a heavy burden on inhabitants.</p> | <p>The respective LCCDs are to establish operation and maintenance systems for the completed facilities, which are locally managed through water billing to beneficiaries.</p> | <p>The estimated cost for operation & maintenance composed of operators' salaries and fuel cost, etc., is YR13 at its highest, mostly 1/10 of the current water prices. A share of one household for the O/M cost is estimated to be less than 4% in its income, in compliance with the IRDB/IDA's recommendations that the share of spending for water in the income of the poorer classes should be less than 5% in developing countries.</p> |

6.2 CONCLUSION

As one of the top-priority policies in the National Development Planning, the government of the Republic of Yemen is promoting to expand the coverage of water supply for the rural population making up over 80% of the entire nation for the improvement of the quality of their life as well as the regional development through activities of the concerned offices and agencies supported by bilateral assistance. However, its progress is lagging behind with the present coverage hovering around 50% because of technical difficulty as well as a financial constraint in the construction of facilities in harsh natural conditions.

This Project is aimed at urgently providing safe and stable domestic water to five (5) mountainous sites dispersedly located in five (5) governorates of the country where the shortages of water are acute, by means of constructing water supply facilities composed mainly of deep well sources in wadi lowlands, transmission facilities which pump up water to mountainsides and distribution facilities including reservoirs and part of distribution lines connected with service facilities. This measure is expected to improve environment in these mountainous areas a great deal with direct effects on the promotion of health and sanitation of inhabitants in these sites. Moreover, since they are relying their drinking and cooking water mostly on the costly water to sell in the mountains, the installation of facilities will result in drastically alleviating their current economic burden. Further, it will result in saving of labor in current practice of water fetching from distant sources, which may be turned over to other productive activities in rural areas, invigorating and upgrading rural life.

The implementation of the project is controlled by the Rural Water Supply Department (RWSD) of the Ministry of Electricity and Water (MEW), which is responsible for the planning, surveying and construction of the countrywide rural water supply projects. Upon completion, the facilities are to be transferred to the Local Councils for Cooperation and Development (LCCDs) under the Ministry of Local Administration (MLA), which are in charge of local development enterprises in the respective regions, for their operation and

maintenance to be supported by the RWSD's technical service. This style is the ongoing administration system of rural water facilities throughout the country, and was employed by the communities in the previous projects with assistance from Japan as well, where the respective systems have been run autonomously, collecting water bills from beneficiaries based upon the agreements among inhabitants within the communities. The facilities to be installed under this Project are also anticipated to stimulate the development of autonomous activities of the local communities.

The implementation of the Project not only meets the BHN of inhabitants in the concerned communities but is anticipated to make a contribution to one of the top-priority policies in the National Development Planning. In view of these benefits, the Project is judged to be worthwhile and feasible for the extension of grant aid by the government of Japan.

6.3 RECOMMENDATIONS

The implementation of the Project is expected to produce benefits such as improved sanitary environment, upgrading of living standards and contribution to the regional development. To maintain sustained operation of the respective facilities in an effective manner for the intended purpose, the recommendations are presented as follows:

- (1) The government's agencies and local communal bodies concerned should cooperate to review and improve the ongoing system and organization for operation and maintenance for better management of water facilities. It is recommended in particular that a measure for the establishment of a responsible organization for repairing facilities on occasions of troubles be promptly taken.
- (2) In this Project, a flow meter and a water level measurement equipment are installed in each of the deep well stations for the effective control and maintenance of the deep well sources. The agencies responsible for operation and maintenance are advised to

direct its operators to establish a practice to measure and keep daily records of yields and drawdowns of the wells so that the data could provide basic information to be used for the future planning for the extension of facilities as well as the operation program.

- (3) The continuous efforts of the responsible authorities are encouraged for promoting the education of the rural population on the meaning of a stable supply of safe water and for inspiring them towards understanding the significance of conserving sanitary environment through effective use of water.
- (4) The RWSD is required to make arrangements for the earlier resumption of the training course for the local operators in charge of the facilities to improve and upgrade their capabilities.
- (5) One of the trend in the rural water supplies is that a project plan is required to cover an increasingly extensive area for supply, in places involving a regional development of groundwater resources. The RWSD which is responsible for the countrywide rural supply projects is recommended to keep a close tie with the High Water Council, and to formulate an effective and efficient program for the promotion of the projects in consistency with the comprehensive water resources development and conservation plan which may be established soon through the coordination of concerned agencies with the High Water Council.

APPENDIX

- I. SITE SURVEY**
- II. NATURAL / SOCIAL ENVIRONMENT**
- III. WATER SOURCE**
- IV. WATER SUPPLY FACILITIES**
- V. BASIC DESIGN DRAWINGS**

APPENDIX I
SITE SURVEY

APPENDIX I - a Minutes of Meeting

MINUTES OF DISCUSSIONS

**BASIC DESIGN STUDY ON THE PROJECT FOR
RURAL WATER SUPPLY PROJECT
IN THE REPUBLIC OF YEMEN**

In response to a request from the Government of the Republic of Yemen, the Government of Japan decided to conduct a Basic Design Study on the Project for Rural Water Supply (hereinafter referred to as "the Project") and entrusted the study to the Japan International Cooperation Agency (JICA).

JICA sent to Yemen a study team, which is headed by Mr. Takeshi Sakai, Chief Engineer, Engineer Section, Saitama Prefectural Showa Water Filtration Plant, and is scheduled to stay in the country from April 23 to June 22, 1991.


The team held discussions with the officials concerned of the Government of Yemen and conducted a field survey at the study area.

In the course of discussions and field survey, both parties have confirmed the main items described on the attached sheets. The team will proceed to further works and prepare the Basic Design Study report.

Sana'a, June 18, 1991



Mr. Takeshi Sakai
Team Leader
Basic Design Study Team
JICA



Mr. Abdul Bari Saleh
Director General
Rural Water Supply Dept.
Ministry of Electricity and
Water
Republic of Yemen

ATTACHMENT

1. Objective

The objective of the Project is to construct water supply facilities for the people in order to improve and stabilize the social condition of the rural areas of the Republic of Yemen.

2. Project Sites

The Project sites are listed as follows, with their construction priorities affixed in the order of the listing:

| Priority | Site No. | Name of Site |
|----------|----------|-------------------|
| 1 | (14) | Al Mallaheeth |
| 2 | (1) | Iyal Qasim |
| 3 | (3) | Khamis Bany Hajaj |
| 4 | (6) | Al Usfyn |
| 5 | (5) | Al Husha |
| 6 | (11) | Aflah Al Yaman |
| 7 | (9) | Al Ghudu |
| 8 | (12) | Bait Al Sultan |
| 9 | (4) | Bani Afif |
| 10 | (7) | Al Jaboob |
| 11 | (2) | Mahalat Nagar |


3. Executing Agency

The Ministry of Electricity and Water is responsible for the land acquisition, water rights, implementation, operation and maintenance of the Project.

4. Items Requested by the Government of Yemen

After discussions with the Basic Design Study Team, the following items were finally requested by the Yemen side.

- 1) Construction of water facilities in the aforementioned Project sites.

 T. S.

- 2) Procurement of materials and equipment for construction of water facilities in the above Project.
- 3) Procurement of services for the implementation of the Project.

However, the final components of the Project will be decided after further studies.

5. Japan's Grant Aid System

- (1) The Government of Yemen has understood the system of Japanese Grant Aid explained by the team.
- (2) The Government of Yemen will take necessary measures, described in Annex I for the smooth implementation of the Project, on condition that the Grant Aid Assistance by the Government of Japan is extended to the Project.

6. Schedule of the Study

- (1) Based on the Minutes of Discussions and technical examination of the study results, JICA will prepare the draft report in English and dispatch a mission in order to explain its contents around September 1991.
- (2) In case the contents of the report is accepted in principle by the Yemen side, JICA will complete the final report and send it to the government of Yemen by December 1991.

* * * * *




ANNEX I

UNDERTAKINGS BY THE GOVERNMENT OF YEMEN

1. To provide data and information necessary for the Project
2. To provide, secure, clear and level land and access at each construction site prior to the commencement of construction of water facilities.
3. To ensure speedy unloading, tax exemption, customs clearance at the port of disembarkation and prompt inland transportation, of products purchased for the Project in accordance with the agreement to be concluded between the Government of the Republic of Yemen and the Government of Japan.
4. To make necessary arrangements for the entry into and stay in the Republic of Yemen, of Japanese nationals whose services may be required in connection with the supply of the products and the services under the verified contracts for the Project.
5. To exempt Japanese nationals involved in the Project from customs duties, internal taxes and other fiscal levies which may be imposed in the Republic of Yemen with respect to the supply of equipment/machines and services under the verified contracts for the Project in accordance with the agreement to be concluded between the Government of the Republic of Yemen and the Government of Japan.
6. To bear commissions to the Japanese foreign exchange bank for the banking services based upon the Banking Arrangement for the Project.
7. To bear all expenses, other than those to be borne by the Grant Aid necessary for the execution of the Project.
8. To assign exclusive counterpart staff in the Ministry of Electricity and Water for the execution of the Project including siting, drilling, installation of water facilities, etc. prior to the commencement of the Project.
9. To maintain and use properly and effectively the facilities constructed and equipment purchased under the Grant Aid for the Project.

* * * * *



T. S.

**SUPPLEMENTARY AGREEMENT
FOR BASIC DESIGN STUDY
FOR RURAL WATER SUPPLY PROJECT
IN THE REPUBLIC OF YEMEN**

In reference to the minutes of discussions for the Basic Design Study on the Rural Water Supply Project in the Republic of Yemen which was signed by the representatives of the Rural Water Supply Dept., Ministry of Electricity and Water, the Republic of Yemen and JICA Basic Design Study Team on June 18, 1991, both parties have hereby agreed on the scope to be undertaken by the Japanese side concerning the two sub-projects of a large scale as follows:

(1) Site No. 5 Al Husha (Taizz)


Scope of water supply facilities planned to be constructed by the Japanese side under this phase of the Project:

From the new deep wells for water sources in Wadi Tuban to the water tank for the supply system for the city of Doulan (Central area supply system as shown in the drawing submitted on June 16, 1991)

(2) Site No. 6 Al Usfyn (Taizz)

Scope of water supply facilities planned to be constructed by the Japanese side under this phase of the Project:

From the deep wells for water sources in Wadi Attaryan to the water tank near Taizz-Al Rahidah Road, the design of which will be proposed in the Draft Final Report


A handwritten signature and the initials 'T.S.' are present in the bottom right corner of the page.


SUPPLEMENTARY AGREEMENT

JUNE 18, 1991

PAGE - 2 -

In case any alterations concerning the scope of the works for the above-sites are required by the Yemeni side, such matters shall be requested to the Government of Japan through the official channel.

In witness of the above statement, both parties have signed hereunder on this date of June 18, 1991.



Mr. Takeshi Sakai
Team Leader
Basic Design Study Team
JICA



Mr. Abdul Bari Saleh
Director General
Rural Water Supply Dept.
Ministry of Electricity and
Water, Republic of Yemen

MISUTES OF DISCUSSIONS


BASIC DESIGN STUDY ON THE PROJECT
FOR THE RURAL WATER SUPPLY
IN THE REPUBLIC OF YEMEN
(CONSULTATION ON DRAFT REPORT)

In April 1991, the Japan International Cooperation Agency (JICA) dispatched a basic design study team on the Project for the Rural Water Supply in the Republic of Yemen (hereinafter referred to as "the Project") to the Republic of Yemen, and through discussions, field survey, and technical examination of the results in Japan, has prepared the draft report of the study.


In order to explain and to consult the Republic of Yemen on the components of the draft report, JICA sent to Yemen a study team, which is headed by Mr. Shinichi Mori, Team Leader, the Basic Design Study Team, JICA, and is scheduled to stay in the country from November 3 to November 11, 1991.

As a result of discussions, both parties confirmed the main items described on the attached sheets.

Sana'a, November 10, 1991



Mr. Shinichi Mori
Team Leader
Basic Design Study Team
JICA



Mr. Abdul Bari Saleh
Director General
Rural Water Supply Department
Ministry of Electricity and Water,
Republic of Yemen

ATTACHMENT

1. Components of Draft Report

The Government of the Republic of Yemen has agreed and accepted in principle the components of the Draft Report proposed by the team.

2. Japan's Grant Aid System

- a. The Government of Yemen has understood the system of Japanese Grant Aid explained by the team.
- b. The Government of Yemen will take the necessary measures, described in Annex I, for smooth implementation of the Project on condition that the Grant Aid assistance by the Government of Japan is extended to the Project.

3. Further Schedule

The team will make the final report in accordance with the confirmed items, and send it to the Government of Yemen by the end of December 1991.

* * * * *


~~JWA~~
SM

ANNEX 1

NECESSARY MEASURES TO BE TAKEN
BY THE GOVERNMENT OF THE REPUBLIC OF YEMEN

1. To clear and level the land necessary for the facilities prior to the commencement of construction in the sites.
2. To construct the access roads to the locations of facilities prior to the commencement of construction in the sites.
3. To bear commissions to the Japanese foreign exchange bank for the banking services based upon the Banking Arrangement.
4. To exempt taxes and to take necessary measures for customs clearance of the materials and equipment brought for the Project at the port of disembarkation under the laws and regulations of the Republic of Yemen.
5. To accord Japanese nationals whose services may be required in connection with the supply of products and the services under the verified contract such facilities as may be necessary for their entry into the Republic of Yemen and stay therein for the performance of their work.
6. To assign exclusive counterpart staff in the Ministry of Electricity and Water for the execution of the Project including siting, drilling, installation of water facilities, etc., prior to the commencement of the Project.
7. To maintain and use properly and effectively the facilities constructed and equipment purchased under the Grant.
8. To bear all the expenses other than those to be borne by the Grant, necessary for the construction of facilities as well as for the transportation and the installation of the equipment.

* * * * *


S.M.

APPENDIX I - b Itinerary of Field Survey

| No. | Date | Week | Stay at : | Activity |
|-----|---------|------|-------------------|---|
| 1 | Apr. 23 | Tue | | Leave Tokyo for Frankfurt |
| 2 | 24 | Wed | | Leave Frankfurt for Sana'a |
| 3 | 25 | Thu | Sana'a | Courtesy call to Embassy of Japan, MPD and RWSD |
| 4 | 26 | Fri | Sana'a | Preparation for Site Survey |
| 5 | 27 | Sat | Sana'a | Meeting with RWSD |
| 6 | 28 | Sun | Iyal Qasim | Site Survey in No.1 Iyal Qasim |
| 7 | 29 | Mon | Iyal Qasim | Site Survey in No.1 Iyal Qasim |
| 8 | 30 | Tue | Iyal Qasim | Site Survey in No.1 Iyal Qasim |
| 9 | May 1 | Wed | Mahalat Najr | Site Survey in No.2 Mahalat Najr |
| 10 | 2 | Thu | Sana'a | Data Collection and Analysis |
| 11 | 3 | Fri | Sana'a | Data Collection and Analysis |
| 12 | 4 | Sat | Khamis Bani Hajaj | Site Survey in No.3 Khamis Bani Hajaj |
| 13 | 5 | Sun | Khamis Bani Hajaj | Site Survey in No.3 Khamis Bani Hajaj |
| 14 | 6 | Mon | Sana'a | Meeting with RWSD |
| 15 | 7 | Tue | Ash Sharaq | Site Survey in No.10 Ash Sharaq |
| 16 | 8 | Wed | Ash Sharaq | Site Survey in No.10 Ash Sharaq |
| 17 | 9 | Thu | Aflah Al Yaman | Site Survey in No.11 Aflah Al Yaman |
| 18 | 10 | Fri | Aflah Al Yaman | Site Survey in No.11 Aflah Al Yaman |
| 19 | 11 | Sat | Aflah Al Yaman | Site Survey in No.11 Aflah Al Yaman |
| 20 | 12 | Sun | Al Mallaheeth | Site Survey in No.14 Al Mallaheeth |
| 21 | 13 | Mon | Al Thaiah | Site Survey in No.13 Al Thaiah |
| 22 | 14 | Tue | Sana'a | Trip from Hudaydah to Sana'a |
| 23 | 15 | Wed | Sana'a | Data Collection and Analysis |
| 24 | 16 | Thu | Sana'a | Meeting with RWSD |
| 25 | 17 | Fri | Sana'a | Meeting within Team |
| 26 | 18 | Sat | Sana'a | Meeting with MPD and RWSD |
| 27 | 19 | Sun | Marib | Trip from Sana'a to Marib |
| 28 | 20 | Mon | Al Ghudu | Site Survey No.9 Al Ghudu |
| 29 | 21 | Tue | Majzar | Site Survey No.8 Majzar |
| 30 | 22 | Wed | Sana'a | Data collection & Analysis |

| No. | Date | Week | Stay at : | Activity |
|-----|--------|------|-----------------|--|
| 31 | May 23 | Thu | Sana'a | Meeting with RWSD |
| 32 | 24 | Fri | Sana'a | Data Collection and Analysis |
| 33 | 25 | Sat | Sana'a | Meeting with RWSD |
| 34 | 26 | Sun | Al Jabub | Site Survey in No.7 Al Jabub |
| 35 | 27 | Mon | Al Jabub | Site Survey in No.7 Al Jabub |
| 36 | 28 | Tue | Al Husha | Site Survey in No.5 Al Husha |
| 37 | 29 | Wed | Al Husha | Site Survey in No.5 Al Husha |
| 38 | 30 | Thu | Al Husha | Site Survey in No.5 Al Husha |
| 39 | 31 | Fri | Bani Afif | Site Survey in No.4 Bani Afif |
| 40 | June 1 | Sat | Bani Afif | Site Survey in No.4 Bani Afif |
| 41 | 2 | Sun | Bani Afif | Site Survey in No.4 Bani Afif |
| 42 | 3 | Mon | Sana'a | Data Collection and Analysis |
| 43 | 4 | Tue | Sana'a | Data Collection and Analysis |
| 44 | 5 | Wed | Sana'a | Data Collection and Analysis |
| 45 | 6 | Thu | Sana'a | Courtesy call to Embassy and RWSD |
| 46 | 7 | Fri | Sana'a | Meeting within Team |
| 47 | 8 | Sat | Sana'a | Meeting with RWSD |
| 48 | 9 | Sun | Bait Al Sultan | Site Survey in No.12 Bait Al Sultan |
| 49 | 10 | Mon | Sana'a | Meeting with RWSD |
| 50 | 11 | Tue | Al Usfyn | Site Survey in No.6 Al Usfyn |
| 51 | 12 | Wed | Al Usfyn | Site Survey in No.6 Al Usfyn |
| 52 | 13 | Thu | Al Usfyn | Site survey in No.6 Al Usfyn |
| 53 | 14 | Fri | Al Usfyn | Site Survey in No.6 Al Usfyn |
| 54 | 15 | Sat | Sana'a | Trip from Aden to Sana'a |
| 55 | 16 | Sun | Sana'a | Meeting with RWSD and Embassy of Japan |
| 56 | 17 | Mon | Sana'a | Meeting with RWSD |
| 57 | 18 | Tue | Sana'a | Signing of Minutes of discussions |
| 58 | 19 | Wed | Sana'a | Meeting with RWSD |
| 59 | 20 | Thu | Leave Sana'a | Leave Sana'a for Frankfurt |
| 60 | 21 | Fri | Leave Frankfurt | Leave Frankfurt for Tokyo |
| 61 | 22 | Sat | Arrive Tokyo | Arrive at Tokyo |

APPENDIX I - c Member List of The Study Team

| BADIC DESIGN STUDY TEAM FOR THE PROJECT FOR THE RURAL WATER SUPPLY IN THE REPUBLIC OF YEMEN | | |
|---|-------------------|--|
| Assignment | Name | Affiliation |
| Team Leader | Takeshi SAKAI | Showa Water Plant, Water Works Department, Public Enterprise Bureau, Prefectural Government of Saitama, Japan |
| Project Coordinator | Eiji INUI | First Basic Design Study Division, Grant Aid Study and Design Department, Japan International Cooperation Agency |
| Water Supply Planner | Tetsuji NIWANO | Japan Techno Co., Ltd. |
| Hydrogeologist | Akira SATOH | Japan Techno Co., Ltd. |
| Water Supply Planner | Masaru NAKAYAMA | Japan Techno Co., Ltd. |
| Facilities Planner | Yositaka HAMANAKA | Japan Techno Co., Ltd. |
| Cost Estimation | Shoji TAKAMATSU | Japan Techno Co., Ltd. |

| DRAFT FINAL MISSION TEAM | | |
|--------------------------|----------------|---|
| Assignment | Name | Affiliation |
| Team Leader | Shinichi MORI | Grant Aid Div., Economic Assistance Bureau, Ministry of Foreign Affairs |
| Water Supply Planner | Tetsuji NIWANO | Japan Techno Co., Ltd. |

APPENDIX I - d List of Persons Visited

1. MINISTRY OF PLANNING AND DEVELOPMENT

Vice Minister : Mr. Mutaheer Assaiedi
Deputy Minister : Mr. Abdul Wali S. Al Agel
Director of Japan/Australia Div.
Bilateral Department : Mr. Hisham Sharaf Abdalla

2. MINISTRY OF ELECTRICITY AND WATER

Minister : Dr. Abdul-Wahab Mahmood
Vice Minister: Mr. Mohammed Abdul Aleem Alwan

Rural Water Supply Department

General Director: Mr. Abdul Bari Saleh
Deputy Director : Mr. Ibrahim Al Shami
Project Div. : Mr. Mohadi Mohammed Mohadi (Director)

Public Relations Div.: Mr. Mohamad Al Jabry (Director)
Mr. Abdul Latif Salah (Deputy)

Bilateral Div.: Mr. Fawzy Al Khirbash (Director)
Mr. Abdul Momen Mutaheer (Civil Engineer)
Mr. Hamud Gilan (Coordinator)

Drilling & Hydrogeology Div.:
Mr. Abdullar Abdul Mullick (Director)
Mr. Ahmed Hussein Al Shahary (Deputy)
Mr. Abdul Hakim Al Ramah (Hydrogeologist)

3. CENTRAL BANK OF YEMEN

Manager of Foreign Relation Dept.: Mr. Mahmoud Qaid

Deputy Manager of Foreign Relation Dept.: Mr. Kamal Y. Al Rabei

Research Department/Financial & Monetary Studies Div.:
Mr. Hassan Mohassin

4. REPRESENTATIVES OF LOCAL BODIES

Chairman of the Iyal Surayh LCCD: Mr. Abdullah Ahjmed Rageh

Governor of the Marib Governorate: Mr. Yahia Al Shami

District Director of the Majzl District: Mr. Abdul Ahmed

5. EMBASSY OF JAPAN

Ambassador Extraordinary and Plenipotentiary:
Mr. Kazuo Wanibuchi
(at the time of the Draft Final Mission)
Mr. Masaki Noguchi
(at the time of the Basic Design Survey)

Charge d'affaire: Mr. Yuichi Ishii

First Secretary: Mr. Yasuo Nakano

APPENDIX II
NATURAL / SOCIAL ENVIRONMENT

APPENDIX II-a Economic Structure (1986-1990)

| Macroeconomic indicators | Yemen:the North | | | | Yemen:the South | | | | United Yemen 1990 ^A |
|---|-----------------|---------|-------------------|--------------------|-----------------|--------|--------|--------------------|--------------------------------|
| | 1986 | 1987 | 1988 | 1989 | 1986 | 1987 | 1988 | 1989 | |
| GDP at producer' prices \$ mn | 3,983 | 4,212 | 5,907 | 6,865 ^A | 1,159 | 1,246 | 1,275 | 1,304 ^A | 11,231 |
| Real GDP growth % | 9.4 | 4.8 | 19.2 ^B | 12.0 ^A | -9.0 | 3.5 | 0.3 | 2.0 ^A | 8.0 |
| GDP par a person | 430 | 441 | 601 | 678 | 522 | 547 | 545 | 539 | 869 |
| Consumer price inflation % ^A | 29.3 | 21.8 | 22.0 | 22.0 | 1.0 | 3.0 | 2.5 | 5.0 | 30.0 |
| Exports FOB \$ mn ^C | 16.1 | 48.2 | 447.0 | 606.0 | 30.4 | 70.9 | 82.2 | 113.8 | 800.0 |
| Imports FOB \$ mn ^C | 796.6 | 1,189.4 | 1,309.4 | 1,282.7 | 447.9 | 456.9 | 596.1 | 553.9 | 1,900.0 |
| Current account \$ mn | -125.3 | -452.2 | -694.3 | -579.0 | -175.7 | -129.7 | -404.5 | -416.6 | -1,000.0 |
| Reserves excl gold \$ mn | 431.7 | 539.5 | 285.1 | 279.2 | 138.0 | 97.1 | 79.9 | 45.2 | - |
| Total external debt \$ mn | 2,366 | 2,636 | 3,034 | 3,324 | 1,733 | 1,936 | 2,240 | 2,505 | - |
| Exchange rate(av) 1\$= YR/YD | 9.639 | 10.342 | 9.772 | 9.760 | 0.345 | 0.345 | 0.345 | 0.345 | 12.020 |

March 4, 1991 1 \$=11.997YR^D, 1 \$=0.461YD^E

A: Estimates, B: World Bank estimate, C: Balance of payments basis,
D: Devalued on February 19, 1990, E: Devalued on May 10, 1990

| Origins of gross domestic product (%) | Yemen: the North ^A (1987) | Yemen: the South ^B (1989) | Components of gross domestic product (1988, %) | Yemen: the North |
|---------------------------------------|--------------------------------------|--------------------------------------|--|------------------|
| Agriculture, forestry & fisheries | 27.9 | 14.1 | Personal consumption | 80.2 |
| Mining & quarrying | 1.6 | 9.5 | Government consumption | 19.6 |
| Manufacturing | 11.1 | | Investment | 12.2 |
| Electricity & water | 1.1 | | 9.7 | Change in Stocks |
| Construction | 3.3 | 11.8 | | Exports |
| Trade | 11.9 | 1.0 | Imports | -28.6 |
| Hotels & restaurants | | | | |
| Transport & communications | 10.9 | 1.0 | | |
| Finance, insurance & real estate | | 24.3 | | |
| Gouvernement & other services | | 29.6 | | |
| Indirect taxes less subsidies | | 13.3 | | |
| GDP incl others at producers' prices | 100.0 | 100.0 | GDP | 100.0 |

| Principal exports (1988) \$mn | Yemen: the North ^A | Yemen: the South | Principal imports (cif) (1988) \$mn | Yemen: the North ^A | Yemen: the South ^D |
|-----------------------------------|-------------------------------|-------------------------------|-------------------------------------|-------------------------------|-------------------------------|
| Food & beverages & live animals | 56.5 | 22.6 | Food & beverages | 460.8 | 206.7 |
| Mineral fuels & lubricants | 397.9 | | Manufactured goods | 371.1 | 131.2 |
| Raw materials | 12.5 | | Mineral fuels & lubricants | 197.3 | 113.2 |
| Petroleum products | | 48.4 | Machinery & Transport equipments | 189.2 | 137.5 |
| GDP incl others | 471.5 | 82.2 | Total incl others | 1,384.0 | 653.2 |
| Main destinations of exports 1989 | Yemen: the North ^C | Yemen: the South ^E | Main origins of imports 1989 | Yemen: the North ^C | Yemen: the South ^E |
| West Germany | 28.7 | 21.5 | Soudi Arabia | 12.5 | 4.5 |
| USA | 25.9 | | France | 5.9 | |
| Italy | 12.3 | 13.4 | Australia | 5.1 | |
| Japan | 9.8 | 8.6 | USA | 4.6 | |
| Singapore | 5.9 | | West Germany | 4.3 | |
| North Yemen | | 17.0 | Ethiopia | | 5.7 |
| India | | 7.2 | UK | | 5.1 |
| | | | Denmark | | 4.6 |
| | | | Singapore | | 4.5 |

A: Estimated by AFESD, Arab Countries: Economic Indicators, 1989

B: Provisional, C: IMF, Direction of Trade Statistics.

D: Not including petroleum re-exported after processing.

E: IMF, Direction of Trade Statistics, not including trade with USSR.

Appendix II-b

Allocations of Sectorial Investments in Five-Year Plans of North Yemen

(%)

| | First Three Year Plan 1973/74-75/76 actual | First Five Year Plan (1976/77-80/81) | | Second Five Year Plan (1982-86) | | Third Five Year Plan (1987- 1991) planned |
|-------------------------------|---|--|--------|---------------------------------------|--------|---|
| | | planned | actual | planned | actual | |
| Agriculture | 14.8 | 14.3 | 7.5 | 15.8 | 11.6 | 8.0 |
| Manufacturing | 9.8 | 22.2 | 24.9 | 36.5 | 30.7 | 38.6 |
| Electricity & water | - | - | 7.5 | 8.3 | 15.8 | 6.7 |
| Mining & quarrying | - | - | 0.6 | 3.2 | 1.6 | 14.1 |
| Construction | 10.4 | 2.8 | 7.4 | 2.3 | 1.6 | 0.5 |
| Housing | - | 13.1 | 28.4 | 13.3 | 17.1 | 8.0 |
| Trade | 4.4 | 3.9 | - | 10.2 | 4.1 | 5.1 |
| Transport & communications | 31.2 | 30.8 | 26.4 | 16.5 | 14.8 | 12.5 |
| Banking & finance | - | 0.6 | - | 0.4 | 1.1 | 0.8 |
| Services | 29.4 | 12.3 | 13.8 | 17.5 | 25.7 | 35.4 |
| Total * investment | 936 | 16,550 | 11,558 | 28,100 | 19,871 | 38,582 |

* YR million

Source: Central Planning Organisation

Appendix II-c Record of Japanese Financial Assistance to Republic of Yemen (1976-1990)

Loan Aid

Unit = 100 million yen

| YEAR | YEMEN ARAB REPUBLIC | | PEOPLE'S DEMOCRATIC REPUBLIC OF YEMEN | |
|------|--|--------|--|--------|
| | DESCRIPTION | AMOUNT | DESCRIPTION | AMOUNT |
| 1977 | Rural Water Supply Project | 38.80 | — | — |
| 1978 | — | — | — | — |
| 1979 | Las Katib Thermoelectric | 82.00 | — | — |
| 1980 | Power Plant | — | — | — |
| 1981 | — | — | — | — |
| 1982 | Construction Project for the 7th berth of Hodeidah Port | 82.00 | — | — |
| 1983 | — | — | — | — |
| 1984 | — | — | — | — |
| 1985 | — | — | — | — |
| 1986 | — | — | — | — |
| 1987 | — | — | — | — |
| 1988 | Construction Project for the Mafrag Cement Factory | 220.70 | — | — |
| 1989 | — | — | Aden City Telecommunication Network Expansion Project | 69.69 |

Grant Aid

| YEAR | YEMEN ARAB REPUBLIC | | PEOPLE'S DEMOCRATIC REPUBLIC OF YEMEN | |
|------|--|--------|---------------------------------------|--------|
| | DESCRIPTION | AMOUNT | DESCRIPTION | AMOUNT |
| 1976 | Food Aid | 3.08 | Food Aid | 0.92 |
| 1977 | Food Aid | 3.63 | Fishery Training Boat | 4.50 |
| | | | Food Aid | 2.59 |
| 1978 | Food Aid | 4.21 | Food Aid | 1.64 |
| 1979 | Aid for Increased Food Production | 5.00 | — | — |
| | Debt Relief | 0.05 | — | — |
| 1980 | Debt Relief | 0.16 | — | — |
| 1981 | Rural Water Supply Project I | 5.00 | — | — |
| | Food Aid | 2.78 | — | — |
| | Debt Relief | 0.25 | — | — |
| 1982 | Rural Water Supply Project II | 5.00 | Disaster Relief (for flood) | 0.57 |
| | Aid for Increased Food Production | 5.00 | | |
| | Debt Relief | 0.66 | — | — |
| | Disaster Relief (for earthquake) | 1.17 | — | — |
| | Study Equipment for Sana'a University | 0.45 | — | — |

| YEAR | YEMEN ARAB REPUBLIC | | PEOPLE'S DEMOCRATIC REPUBLIC OF YEMEN | |
|------|--|--------|--|--------|
| | DESCRIPTION | AMOUNT | DESCRIPTION | AMOUNT |
| 1983 | Rural Water Supply Project III | 6.00 | Food Aid | 1.41 |
| | Reconstruction Project for Earthquake Disaster | 8.00 | | |
| | Aid for Increased Food Production | 5.00 | | |
| | Debt Relief | 0.84 | | |
| 1984 | Expansion of the National Tuberculosis Center I | 9.18 | - | - |
| | Reconstruction Project for Earthquake Disaster | 2.50 | | |
| | Aid for Increased Food Production | 6.00 | | |
| | Debt Relief | 0.47 | | |
| 1985 | Expansion of the National Tuberculosis Center II | 10.80 | Fisheries Culturing Research Center | 9.41 |
| | Aid for Increased Food Production | 5.00 | | |
| | Debt Relief | 1.55 | | |
| | Scanning Electron Microscope for Sana'a Univ. | 0.41 | | |
| 1986 | Rural Water Supply Project IV | 3.19 | - | - |
| | Aid for Increased Food Production | 5.00 | | |
| | Debt Relief | 1.06 | | |
| 1987 | Rural Water Supply Project V | 9.15 | - | - |
| | Aid for Increased Food Production | 5.00 | | |
| | Debt Relief | 2.00 | | |
| 1988 | Rural Water Supply Project VI | 9.61 | Rehabilitation project for Fishery Training Boat | 1.95 |
| | Aid for Increased Food Production | 4.00 | | |
| | Debt Relief | 2.90 | | |
| 1989 | Rural Telecommunication Network Expansion Project | 5.40 | Disaster Relief (for flood) | 0.14 |
| | Aid for Increased Food Production | 2.50 | | |
| | Debt Relief | 1.72 | | |
| | Debt Relief | 2.86 | | |
| | Equipment for Producing Educational and Cultural Programs to the National Television Corporation | 0.47 | | |
| | Small-Scale Grant Aid | 0.11 | | |
| | REPUBLIC OF YEMEN (after unification) | | | |
| 1990 | Rural Telecommunication Network Expansion Project | | | 6.63 |

APPENDIX II - d Infection Diseases Reported During 1975-1986

| | 1975 | 1976 | 1977 | 1978 | 1979 | 1980 | 1981 | 1982 | 1983 | 1984 | 1985 | 1986 | TOTAL |
|----------------------|--------|--------|--------|--------|---------|---------|---------|---------|---------|---------|---------|--------|-----------|
| ENTERITIS | 17,909 | 29,028 | 33,226 | 31,574 | 112,170 | 123,174 | 104,721 | 169,978 | 159,177 | 221,111 | 116,262 | 92,795 | 1,211,125 |
| MALARIA | 8,118 | 15,078 | 22,542 | 30,907 | 74,508 | 45,079 | 59,980 | - | 179,155 | 180,104 | 13,677 | 15,712 | 644,860 |
| AMEEBIC DYSENTERY | 6,289 | 3,053 | 2,512 | 6,208 | 26,410 | 53,155 | 30,417 | 71,828 | 69,986 | 95,928 | 42,494 | 40,492 | 448,772 |
| BLIHARSI | 3,932 | 4,706 | 4,245 | 11,733 | 14,561 | 35,427 | 37,924 | 34,044 | 27,439 | 35,961 | 43,754 | 43,634 | 297,360 |
| MEASLES | 801 | 2,654 | 9,983 | 6,531 | 18,692 | 14,254 | 10,355 | 20,045 | 25,707 | 34,389 | 9,387 | 10,849 | 163,647 |
| WHOOPING | 1,888 | 2,904 | 5,971 | 5,854 | 11,587 | 13,488 | 13,533 | 25,490 | 27,534 | 20,309 | 16,053 | 9,753 | 154,364 |
| T. B. LEPROST | 2,705 | 4,540 | 7,714 | 7,604 | 10,895 | 17,078 | 16,060 | 18,561 | 32,755 | 24,130 | 2,078 | 2,175 | 146,295 |
| INFECTIONS HEPATITIS | 537 | 1,988 | 2,369 | 3,288 | 5,434 | 6,652 | 5,308 | 7,779 | 9,986 | 14,111 | 1,112 | 9,689 | 68,253 |
| MUMPS | 119 | 358 | 1,247 | 1,179 | 2,882 | 2,902 | 3,780 | 5,131 | 7,134 | 9,533 | 4,831 | 5,809 | 44,905 |
| CHICKEN POX | 79 | 88 | 112 | 18 | 214 | 702 | 1,337 | 936 | 2,301 | 6,141 | 2,808 | 3,680 | 18,416 |

APPENDIX II - e Climate Data at Major Stations in North Yemen

| STATION | ITEM | JAN. | | | | | FEB. | | | | | MAR. | | | | | APRIL | | | | | MAY | | | | | JUNE | | | | | | | | | |
|----------|------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|------|------|------|------|------|
| | | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 |
| Sana'a | R | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | T | 13.2 | 14.6 | 12.8 | 12.6 | 15.0 | 14.2 | 15.2 | 15.9 | 15.4 | 16.9 | 17.7 | 17.8 | 18.6 | 18.2 | 19.6 | 20.6 | 18.2 | 17.3 | 19.3 | 18.8 | 20.4 | 19.7 | 21.3 | 20.6 | 21.5 | 22.4 | 21.1 | 22.8 | 23.0 | 22.9 | | | | | |
| | H | - | 39 | 42 | 44 | - | 43 | 56 | 44 | 56 | 44 | 52 | 55 | 55 | 56 | 56 | 65 | 66 | 66 | 51 | 51 | 54 | 42 | 42 | 37 | 37 | 51 | 42 | 42 | 32 | - | | | | | |
| | P | 783.9 | 784.1 | 787.4 | 789.0 | 788.1 | 783.6 | 784.5 | 785.9 | 788.0 | 787.4 | 783.3 | 784.4 | 786.6 | 786.9 | 787.9 | 783.2 | 784.4 | 786.1 | 788.4 | 787.3 | 782.7 | 784.2 | 786.4 | 787.6 | 787.8 | 781.3 | 783.2 | 784.4 | 786.5 | 786.1 | | | | | |
| Taizz | R | 0.0 | 0.0 | 0.0 | 0.5 | 0.5 | 1.6 | 10.8 | 3.9 | 9.1 | 18.0 | 48.8 | 28.0 | 137.6 | 9.9 | 0.0 | 73.2 | 63.7 | 35.3 | 42.1 | 118.2 | 34.3 | 49.0 | 114.8 | 72.0 | 34.3 | 110.1 | 48.6 | 16.2 | 71.4 | | | | | | |
| | T | 17.3 | 19.1 | 16.9 | 17.5 | 17.8 | 19.0 | 18.2 | 18.9 | 18.7 | 19.8 | 22.5 | 20.9 | 21.5 | 20.6 | 22.3 | 22.2 | 22.3 | 22.2 | 21.4 | 22.7 | 22.9 | 24.6 | 23.8 | 22.5 | 24.6 | 24.9 | 25.2 | 24.6 | 24.6 | 24.4 | | | | | |
| | H | - | 69 | 68 | 61 | - | 66 | 67 | 55 | 55 | - | 49 | 53 | 71 | 71 | 59 | 62 | 60 | 60 | 60 | 53 | 60 | 60 | 68 | 58 | 51 | 56 | - | - | - | | | | | | |
| | P | 858.0 | 857.6 | 857.1 | 859.0 | - | 857.3 | 856.8 | - | 857.7 | 856.2 | 856.7 | 857.9 | 856.5 | 855.8 | - | 856.1 | 855.8 | 855.9 | 856.7 | 854.9 | 853.9 | 854.6 | 855.5 | 855.1 | - | 853.4 | 852.4 | 854.0 | 852.7 | - | | | | | |
| Hudaydah | R | 2.3 | 0.0 | 0.0 | 0.8 | - | 0.0 | 0.0 | 8.5 | 0.0 | 0.0 | 0.0 | 4.0 | 12.0 | 0.0 | 0.0 | 0.0 | 0.0 | 15.0 | 32.5 | 39.0 | 0.0 | 9.9 | 0.0 | 2.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | T | 24.5 | 25.2 | 24.4 | 24.6 | 25.8 | 24.9 | 25.5 | 26.2 | 25.3 | 27.2 | 26.6 | 27.1 | 26.7 | 27.4 | 28.8 | 29.5 | 30.0 | 29.1 | 29.2 | 29.9 | 31.3 | 30.9 | 31.2 | 31.2 | 31.9 | 32.4 | 32.0 | 32.9 | 32.5 | 33.4 | | | | | |
| | H | - | 88 | 85 | 81 | - | 82 | 90 | 86 | 86 | - | 88 | 92 | 85 | 85 | 88 | 88 | 94 | 78 | 78 | 84 | 83 | 83 | 82 | - | 79 | 80 | 80 | 82 | - | | | | | | |
| | P | 1009.3 | 1013.5 | - | 1013.3 | 1011.0 | 1012.7 | 1012.2 | - | 1011.0 | 1009.0 | 1005.3 | 1007.4 | 1010.9 | 1007.5 | - | 1009.1 | 1008.9 | 1008.3 | 1007.9 | 1005.2 | 1007.5 | 1007.0 | 1008.0 | 1005.2 | 1004.5 | 1004.3 | 1005.4 | 1003.5 | - | 1002.0 | | | | | |
| Mocha | R | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.6 | 0.0 | 0.0 | 0.0 | 0.0 | 1.6 | 1.8 | 0.0 | 0.0 | 0.0 | 12.1 | 29.7 | 0.0 | 0.0 | 14.9 | 0.0 | 27.0 | 3.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | T | 25.0 | 26.7 | 23.9 | 25.2 | 25.9 | 25.0 | 26.5 | 25.9 | 25.1 | 27.1 | 26.8 | 28.7 | 26.8 | 27.0 | 27.8 | 29.2 | 30.5 | 28.9 | 28.7 | 28.7 | 31.3 | 32.4 | 30.8 | 30.6 | 31.1 | 32.2 | 33.1 | 31.5 | 31.5 | 32.3 | | | | | |
| | H | - | 69 | 90 | - | - | 70 | 77 | 77 | - | - | 65 | 76 | 76 | - | 64 | 77 | 77 | - | - | 69 | 79 | 79 | - | - | 71 | 80 | - | - | - | | | | | | |
| | P | 1015.2 | 1013.9 | 1012.3 | 1013.9 | 1011.0 | 1013.6 | 1011.1 | 1011.1 | 1009.2 | 1009.0 | 1008.6 | 1008.3 | 1008.3 | 1008.5 | - | 1009.1 | 1009.4 | 1009.7 | 1008.3 | 1005.1 | 1007.5 | 1007.9 | 1008.4 | 1005.3 | 1004.7 | 1004.8 | 1005.8 | 1004.0 | 1003.2 | 1002.1 | | | | | |
| Marib | R | 0.0 | 0.0 | 0.0 | 0.0 | - | 0.0 | 0.0 | 20.0 | 0.0 | - | 0.0 | 0.0 | 9.0 | 68.8 | - | 0.0 | 23.3 | 111.6 | 46.2 | - | 0.0 | 5.0 | - | 0.0 | - | 0.0 | - | 1.5 | 0.0 | - | | | | | |
| | T | 18.1 | 21.1 | 18.7 | 18.0 | 18.6 | - | 20.3 | 22.3 | 22.2 | 22.9 | - | 25.7 | 25.5 | 26.5 | 25.4 | 27.8 | 28.3 | 26.3 | 25.9 | 26.8 | 28.7 | 31.2 | - | - | 29.1 | - | 30.0 | 32.5 | 32.3 | 31.1 | | | | | |
| | H | - | 54 | 35 | - | - | 38 | 46 | 46 | - | - | 33 | 44 | 44 | - | 40 | 53 | 53 | - | - | 30 | 30 | - | - | - | - | - | 24 | - | - | | | | | | |
| | P | 896.8 | 890.4 | - | 898.0 | - | 887.2 | 893.7 | 894.2 | - | - | 886.0 | 893.9 | 891.6 | - | - | 891.0 | 889.6 | 891.7 | 893.5 | - | 885.3 | - | - | - | - | - | - | 887.1 | 885.7 | - | | | | | |

R: Rainfall (Months) H: Humidity (Average)
 T: Temperature (Average) P: Atmospheric Pressure (Average)

APPENDIX II - e Climate Data at Major Stations in North Yemen

| STATION | ITEM | JAN | | | | FEB | | | | MAR | | | | APR | | | | MAY | | | | JUN | | | | | | | | |
|----------|------|------|------|------|------|-------|------|-------|-------|-------|------|-------|-------|-------|------|-------|------|-------|------|------|------|------|------|-------|------|-------|------|-------|------|------|
| | | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | | | | |
| Al Hazem | R | - | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.5 | - | 0.0 | 50 | 10.3 | 0.0 | - | 12.2 | - | 2.8 | 26.0 | - | 37.6 | 0.0 | - | 0.0 | - | 0.0 | 0.0 | 0.0 | | |
| | T | - | - | 18.2 | 19.1 | 19.5 | - | 22.6 | 21.8 | 25.0 | - | 25.9 | 26.3 | 26.4 | - | - | - | - | 26.9 | 26.9 | - | - | 30.1 | - | 30.9 | - | 31.7 | 30.0 | 32.0 | |
| | H | - | - | 39 | - | - | 33 | - | - | - | 42 | - | - | - | - | - | - | - | - | - | - | - | 33 | - | - | - | 31 | - | - | |
| | P | - | - | - | - | 891.0 | - | 886.4 | 889.4 | 889.2 | - | - | 885.3 | 887.6 | - | - | - | - | - | - | - | - | - | 878.6 | - | 886.2 | - | 874.0 | - | - |
| Damar | R | - | - | 0.0 | 0.4 | 0.0 | - | 23.1 | 39.2 | 15.2 | - | 42.5 | 78.0 | 5.2 | - | - | 68.2 | 62.1 | 93.8 | - | - | - | - | 21.2 | 6.9 | - | 5.0 | 12.8 | 26.0 | |
| | T | - | - | - | 11.1 | 12.8 | - | 13.7 | 13.5 | 13.9 | - | 16.3 | 14.9 | 16.3 | - | - | 16.4 | 16.0 | 16.9 | - | - | - | - | 18.5 | 19.6 | - | 19.4 | 20.7 | 20.3 | |
| | H | - | - | - | 47 | - | - | 40 | - | - | - | 64 | - | - | - | - | - | 55 | - | - | - | - | - | 49 | - | - | - | 44 | - | |
| | P | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | |
| Albolin | R | - | - | - | 0.0 | 0.0 | - | - | 0.0 | 38.9 | - | - | 5.8 | 0.0 | - | - | - | 22.0 | 61.1 | - | - | - | - | 20.5 | 0.0 | - | - | 2.3 | 2.1 | |
| | T | - | - | - | - | 14.3 | - | - | 15.0 | 17.0 | - | - | 17.6 | 18.0 | - | - | - | 18.3 | 18.0 | - | - | - | - | 20.1 | 19.4 | - | - | 21.3 | 20.8 | |
| | H | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | |
| | P | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| Sa'dah | R | - | 0.0 | 0.0 | - | 1.2 | - | 0.0 | 0.0 | - | 3.0 | 0.0 | 25.0 | - | 0.0 | 0.0 | 47.1 | - | 26.6 | - | 5.2 | 3.6 | - | - | 0.0 | - | 20.6 | 1.2 | - | 1.0 |
| | T | - | 18.2 | 13.2 | - | 15.2 | - | 19.0 | 16.7 | - | 17.5 | 21.6 | 19.9 | 20.7 | - | 20.1 | 19.0 | - | 20.4 | - | 22.2 | 23.4 | - | - | 23.8 | - | 23.9 | 24.8 | - | 24.6 |
| | H | - | - | 54 | 47 | - | - | 46 | 43 | - | - | 50 | 53 | - | 60 | 58 | 49 | - | - | - | 71 | 46 | 40 | - | - | 57 | 33 | 29 | - | - |
| | P | - | - | - | - | - | - | 810.3 | - | - | - | 808.7 | - | 813.7 | - | 813.0 | - | 813.5 | - | - | - | - | - | - | - | 814.0 | - | - | - | - |
| Jehana | R | - | - | - | - | 20.3 | - | - | - | 5.3 | - | - | - | 1.8 | - | - | - | - | 63.1 | - | - | - | - | - | - | - | - | - | 0.0 | |
| | T | - | - | - | - | 14.9 | - | - | - | 17.0 | - | - | - | 18.9 | - | - | - | - | 19.1 | - | - | - | - | - | 20.2 | - | - | - | 22.1 | |
| | H | - | - | - | - | - | - | - | 46 | - | - | - | 62 | - | - | - | 54 | - | - | - | - | - | - | 38 | - | - | - | 31 | - | |
| | P | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | |

R: Rainfall (Month) H: Humidity (Average)
 T: Temperature (Average) P: Atmospheric Pressure (Average)

APPENDIX II - e Climate Data at Major Stations in North Yemen

| STATION | ITEH | JULY | | | | | | | AUG. | | | | | | | SEP. | | | | | | | OCT. | | | | | | | NOV. | | | | | | | DEC. | | | | | | |
|----------|------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|--|--|--|--|--|
| | | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | 1984 | 1985 | 1986 | 1987 | 1988 | | | | | | | |
| Al Hazem | R | 0.0 | 0.0 | 0.0 | 0.0 | 2.5 | 0.0 | 3.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | | |
| | T | 32.0 | 32.0 | 33.4 | 32.9 | 32.9 | 31.8 | 31.8 | 28.0 | 29.4 | 31.1 | 31.1 | 31.1 | 31.1 | 31.1 | 25.5 | 25.2 | 25.5 | 25.2 | 27.1 | 27.1 | 27.1 | 27.1 | 27.1 | 20.4 | 20.4 | 22.2 | 22.8 | 21.0 | 20.4 | 20.4 | 20.4 | 20.4 | 20.4 | 20.4 | 17.4 | | | | | | | |
| | H | 30 | 30 | 30 | 30 | 30 | 31 | 31 | 22 | 31 | 31 | 31 | 31 | 31 | 31 | 32 | 29 | 32 | 29 | 32 | 38 | 38 | 38 | 38 | 38 | 38 | 38 | 38 | 33 | 33 | 33 | 33 | 33 | 33 | 33 | 33 | 33 | | | | | | |
| | P | 873.4 | 873.4 | 873.4 | 873.4 | 882.1 | 873.1 | 873.1 | 873.1 | 873.1 | 873.1 | 873.1 | 873.1 | 873.1 | 873.1 | 882.1 | 888.4 | 888.4 | 888.4 | 889.6 | 889.6 | 889.6 | 889.6 | 889.6 | 889.6 | 882.4 | 882.4 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | 884.3 | | | | | |
| Damar | R | 54.6 | 54.6 | 18.2 | 18.2 | 38.0 | 112.5 | 74.2 | 38.0 | 5.8 | 24.8 | 36.5 | 36.5 | 36.5 | 36.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 17.0 | | | | | | |
| | T | 20.0 | 20.0 | 21.7 | 21.7 | 18.4 | 19.2 | 19.1 | 18.4 | 17.4 | 18.0 | 17.6 | 17.6 | 17.6 | 17.6 | 15.2 | 15.9 | 15.2 | 15.9 | 15.0 | 15.0 | 15.0 | 15.0 | 15.0 | 11.9 | 11.9 | 14.3 | 12.1 | 11.9 | 11.9 | 11.9 | 11.9 | 11.9 | 11.9 | 11.9 | 11.9 | 12.6 | | | | | | |
| | H | 53 | 53 | 50 | 50 | 50 | 52 | 59 | 50 | 43 | 44 | 44 | 44 | 44 | 44 | 43 | 36 | 40 | 36 | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 37 | 37 | 37 | 37 | 37 | 37 | 42 | | | | | | | |
| | P | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Albolin | R | | | | | 56.9 | 24.9 | 56.9 | 24.9 | 39.7 | 68.6 | 39.7 | 39.7 | 39.7 | 39.7 | | | | | | | | | | | | | | | | | | | | | | 17.6 | | | | | | |
| | T | | | | | 21.5 | 22.2 | 21.5 | 21.5 | 21.0 | | | | | | | | | | | | | | | | | | | | | | | | | | | 13.3 | | | | | | |
| | H | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | P | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sa'dah | R | 3.2 | 16.5 | 16.5 | 16.5 | 40.6 | 15.2 | 19.8 | 15.2 | 8.1 | 0.0 | 7.0 | 7.0 | 7.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 2.8 | 0.0 | | | | | | | |
| | T | 25.1 | 24.7 | 24.7 | 24.7 | 23.7 | 25.3 | 24.0 | 23.8 | 23.8 | 22.2 | 23.0 | 23.0 | 23.0 | 23.3 | 19.5 | 19.8 | 19.5 | 19.8 | 19.1 | 19.1 | 19.1 | 19.1 | 19.1 | 14.9 | 14.9 | 17.4 | 17.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.8 | 15.1 | 12.5 | | | | | | | | |
| | H | 45 | 45 | 45 | 45 | 35 | 50 | 50 | 50 | 50 | 35 | 29 | 29 | 29 | 35 | 36 | 30 | 36 | 30 | 31 | 31 | 31 | 31 | 31 | 45 | 45 | 45 | 50 | 41 | 41 | 41 | 43 | 52 | 45 | 45 | | | | | | | | |
| | P | | | | | 813.3 | | | | 811.5 | 811.5 | 811.5 | 811.5 | 811.5 | 809.1 | | | | | 809.5 | 809.5 | 809.5 | 809.5 | 809.5 | 811.5 | 811.5 | 812.9 | 812.9 | 811.5 | 811.5 | 811.5 | 811.5 | 815.3 | 818.0 | | | | | | | | | |
| Jehana | R | | | | | | | | | 1.9 | | | | | | | | | | | | | | | | | | | | | | | | | | | 0.0 | | | | | | |
| | T | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | H | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | P | | | | | | | | | 43 | | | | | | | | | | | | | | | | | | | | | | | | | | | 45 | | | | | | |

R: Rainfall (Month) H: Humidity (Average)
T: Temperature (Average) P: Atmospheric Pressure (Average)

Coverage Monthly Climatic Data at Major Stations (1984 - 1988)

| STATION | ITEM | 1984~1988 | | 1984~1988 | | 1984~1988 | | 1984~1988 | | 1984~1988 | | 1984~1988 | | 1984~1988 | | 1984~1988 | |
|----------|------|-----------|--------|-----------|--------|-----------|--------|-----------|--------|-----------|--------|-----------|--------|-----------|--|-----------|--|
| | | JAN. | FEB. | MAR. | APRIL | MAY | JUNE | JULY | AUG. | SEP. | OCT. | NOV. | DEC. | | | | |
| Sana'a | R | 0.0 | 8.2 | 11.1 | 38.1 | 24.4 | 11.1 | 16.3 | 21.1 | 6.5 | 0.0 | 0.0 | 6.8 | | | | |
| | T | 13.6 | 15.5 | 18.4 | 18.8 | 20.7 | 22.4 | 22.9 | 22.3 | 20.6 | 16.8 | 14.6 | 13.6 | | | | |
| | H | 41.6 | 47.6 | 54.3 | 60.7 | 44.3 | 41.6 | 40.0 | 48.3 | 41.0 | 39.0 | 39.0 | 43.7 | | | | |
| | P | 786.5 | 785.9 | 785.8 | 785.9 | 785.7 | 784.3 | 783.4 | 783.9 | 785.6 | 787.7 | 787.6 | 787.0 | | | | |
| Taizz | R | 0.2 | 6.3 | 11.0 | 42.9 | 77.7 | 56.2 | 48.5 | 85.0 | 63.7 | 10.8 | 0.0 | 2.6 | | | | |
| | T | 17.7 | 18.9 | 18.4 | 22.2 | 23.7 | 24.7 | 24.4 | 24.1 | 22.5 | 21.3 | 18.9 | 18.1 | | | | |
| | H | 66.0 | 62.7 | 57.7 | 60.3 | 60.0 | 53.5 | 58.3 | 60.3 | 57.7 | 54.7 | 57.7 | 66.0 | | | | |
| | P | 857.9 | 857.0 | 856.7 | 855.9 | 854.8 | 853.1 | 851.9 | 852.4 | 854.3 | 856.7 | 857.8 | 858.1 | | | | |
| Hudaydah | R | 1.6 | 1.7 | 3.2 | 17.3 | 2.1 | 0.0 | 5.5 | 12.3 | 5.5 | 0.0 | 0.0 | 0.9 | | | | |
| | T | 24.9 | 25.8 | 27.3 | 29.5 | 31.1 | 32.6 | 32.8 | 32.5 | 31.9 | 30.1 | 27.1 | 25.5 | | | | |
| | H | 84.7 | 86.0 | 88.3 | 86.7 | 83.0 | 80.3 | 80.3 | 81.0 | 72.7 | 80.3 | 78.7 | 82.7 | | | | |
| | P | 1011.8 | 1011.2 | 1007.8 | 1007.9 | 1006.5 | 1003.8 | 1002.7 | 1002.6 | 1004.4 | 1008.1 | 1011.3 | 1012.5 | | | | |
| Mocha | R | 0.0 | 2.3 | 0.7 | 8.4 | 9.0 | 0.0 | 6.0 | 4.0 | 0.0 | 1.0 | 0.0 | 9.4 | | | | |
| | T | 25.3 | 25.9 | 27.4 | 29.2 | 31.2 | 32.1 | 32.2 | 32.1 | 31.8 | 29.5 | 27.5 | 26.2 | | | | |
| | H | 79.5 | 73.55 | 70.5 | 70.5 | 74.0 | 75.5 | 73.5 | 75.5 | 75.5 | 74.0 | 74.0 | 76.5 | | | | |
| | P | 1013.4 | 1011.9 | 1009.7 | 1008.3 | 1007.0 | 1004.0 | 1003.3 | 1003.6 | 1005.5 | 1009.4 | 1011.1 | 1012.6 | | | | |
| Marib | R | 0.0 | 5.0 | 19.5 | 45.3 | 1.7 | 0.5 | 0.0 | 1.3 | 0.0 | 0.0 | 0.0 | 3.4 | | | | |
| | T | 18.9 | 21.9 | 25.8 | 27.0 | 29.7 | 31.5 | 32.4 | 32.6 | 29.8 | 25.4 | 21.6 | 18.9 | | | | |
| | H | 44.5 | 42.0 | 38.5 | 46.5 | 30.0 | 24.0 | 27.0 | 31.0 | 31.5 | 34.5 | 33.5 | 9.20 | | | | |
| | P | 859.1 | 891.7 | 890.5 | 891.5 | 885.3 | 886.4 | 886.5 | 871.3 | 890.3 | 894.0 | 894.8 | 896.7 | | | | |

R: Rainfall (Month) H: Humidity (Average)
 T: Temperature (Average) P: Atmospheric Pressure (Average)

Coverage Monthly Climatic Data at Major Stations (1984 - 1988)

| STATION | ITEM | 1984~1988 | | | | | | | | | | | | | |
|---------|------|-----------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----|-----|
| | | JAN. | FEB. | MAR. | APRIL | MAY | JUNE | JULY | AUG. | SEP. | OCT. | NOV. | DEC. | | |
| Al | R | 0.0 | 2.9 | 15.1 | 13.7 | 12.5 | 0.0 | 0.6 | 0.9 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.5 |
| | T | 18.9 | 23.1 | 26.2 | 26.9 | 30.5 | 31.2 | 32.8 | 31.8 | 29.9 | 25.9 | 21.6 | 18.9 | — | — |
| | H | 39.0 | 33.0 | 42.0 | — | 33.0 | 31.0 | 30.0 | 31.0 | 26.5 | 30.5 | 35.5 | — | — | — |
| | P | 891.0 | 881.3 | 886.5 | — | 882.4 | 874.0 | 873.4 | 877.6 | — | 889.0 | 888.4 | — | — | — |
| Damar | R | 0.1 | 25.8 | 41.9 | 74.7 | 14.1 | 14.6 | 36.4 | 74.9 | 22.4 | 0.0 | 0.0 | 17.0 | — | — |
| | T | 11.9 | 13.7 | 15.8 | 16.3 | 19.1 | 20.1 | 20.6 | 18.9 | 17.7 | 15.4 | 12.8 | 12.6 | — | — |
| | H | 47.0 | 40.0 | 64.0 | 55.0 | 49.0 | 44.0 | 52.0 | 55.5 | 43.5 | 38.0 | 38.5 | 42.0 | — | — |
| | P | — | — | — | — | — | — | 40.9 | — | — | — | — | — | — | — |
| Albolin | R | 0.0 | 19.5 | 2.9 | 41.6 | 10.0 | 2.2 | 21.9 | 54.2 | 18.8 | 0.5 | 0.0 | 17.6 | — | — |
| | T | 14.3 | 16.0 | 17.8 | 18.2 | 19.8 | 21.4 | 21.9 | 21.0 | 19.8 | — | 13.1 | 13.3 | — | — |
| | H | — | — | — | 36.9 | — | — | — | — | — | — | — | — | — | — |
| | P | — | — | — | — | — | — | — | — | — | — | — | — | — | — |
| Sa'dah | R | 0.4 | 1.0 | 8.3 | 24.6 | 2.9 | 7.6 | 20.1 | 14.4 | 2.3 | 0.0 | 0.0 | 0.8 | — | — |
| | T | 15.5 | 17.7 | 20.7 | 19.8 | 23.1 | 24.4 | 24.5 | 24.4 | 22.8 | 19.5 | 16.7 | 14.1 | — | — |
| | H | — | 44.5 | 51.5 | 55.7 | 52.3 | 39.7 | 40.0 | 50.0 | 32.0 | 32.3 | 45.3 | 46.7 | — | — |
| | P | — | 810.3 | 812.2 | 813.3 | 814.0 | — | 813.3 | 811.5 | 809.1 | 809.5 | 812.2 | 816.7 | — | — |
| Jahana | R | 20.3 | 5.3 | 1.8 | 63.1 | — | — | — | 1.5 | 20.5 | 0.0 | 0.0 | 0.0 | — | — |
| | T | 18.9 | 17.0 | 18.9 | 19.1 | 20.2 | 22.1 | — | — | 19.1 | 16.2 | 12.8 | — | — | — |
| | H | — | 46.0 | 62.0 | 54.0 | 38.0 | 31.0 | 36.0 | 43.0 | 33.0 | 43.0 | 45.0 | 45.0 | — | — |
| | P | — | — | — | — | — | — | — | — | — | — | — | — | — | — |

R: Rainfall (Month) H: Humidity (Average)
 T: Temperature (Average) P: Atmospheric Pressure (Average)

Appendix II-f List of Villages Composing The Project Site

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|--------------------------|
| Site Number | 1 | | | |
| Priority order | ② | | | |
| Site name | Iyal Qasim | | | |
| Governorate | Sana'a | | District | Dahi-bin |
| Population | Present total (1991) | 1,500 | Planned Service pop. (2006) | 2,200 |
| Number of Villages | 9 | Planned Area for Water Service | 7.5km ² | Population density |
| | | | | 293pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Bait Al-Nafaish | 25 | 180 | 263 |
| 2 | Al-Agluu | 40 | 270 | 394 |
| 3 | Bitan | 35 | 180 | 263 |
| 4 | Al-Hayyit | 45 | 270 | 394 |
| 5 | Bait Daghar | 20 | 110 | 160 |
| 6 | Bait Al-Azant | 20 | 110 | 160 |
| 7 | Bait Saliman | 20 | 140 | 204 |
| 8 | Bait Marish | 30 | 180 | 263 |
| 9 | Al-Sahamah | 10 | 60 | 88 |
| Total | 9 | 245 | 1,500 | ⇨ 2,200 |

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|--|
| Site Number | 2 | | | |
| Priority order | ① | | | |
| Site name | Mahalat Najr | | | |
| Governorate | Sana'a | | District | Amran |
| Population | Present total (1991) | 2,000 | Planned Service pop. (2006) | 2,900 |
| Number of Villages | 1 | Planned Area for Water Service | 3km ² | Population density 967pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Najr | 200 | 2,000 | 2,918 |
| Total | 1 | 200 | 2,000 | 2,900 |

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|--|
| Site Number | 3 | | | |
| Priority order | ③ | | | |
| Site name | Khamis Bani Hajaj | | | |
| Governorate | Sana'a | | District | Thila |
| Population | Present total (1991) | 5,400 | Planned Service pop. (2006) | 7,900 |
| Number of Villages | 7 | Planned Area for Water Service | 8km ² | Population density 988pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Ash Shim | 50 | 600 | 875 |
| 2 | Al-Mahali | 35 | 350 | 511 |
| 3 | Ad Darb | 150 | 1,600 | 2,334 |
| 4 | Bani Uqayf | 40 | 450 | 657 |
| 5 | Bait Ar Rabui | 50 | 600 | 875 |
| 6 | Bait Umar | 35 | 300 | 438 |
| 7 | Al-Ayn | 150 | 1,500 | 2,189 |
| Total | 7 | 510 | 5,400 | 7,900 |

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|--------------------------|
| Site Number | 4 | | | |
| Priority order | ⑨ | | | |
| Site name | Bani Afif | | | |
| Governorate | Taizz | | District | Turbat Al Mawasit |
| Population | Present total (1991) | 7,300 | Planned Service pop. (2006) | 10,700 |
| Number of Villages | 9 | Planned Area for Water Service | 14km ² | Population density |
| | | | | 764pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Al-Minam | 130 | 960 | 1,401 |
| 2 | Al-Areth | 320 | 2,340 | 3,414 |
| 3 | Al-Maqam | 60 | 550 | 802 |
| 4 | Al-Ujaylah | 90 | 690 | 1,007 |
| 5 | Arradah | 40 | 280 | 409 |
| 6 | Annaberah | 60 | 550 | 802 |
| 7 | Al-Quhaym | 80 | 830 | 1,211 |
| 8 | Al-Miqtar | 40 | 410 | 598 |
| 9 | Suwamah | 80 | 690 | 1,007 |
| Total | 9 | 900 | 7,300 | ≈ 10,700 |

| | | | | |
|--------------------|-----------------------------|--------------------------------|-----------------------------|--------------------------|
| Site Number | 5 | | | |
| Priority order | ⑤ | | | |
| Site name | Al Husha | | | |
| Governorate | Taizz | | District | Al Husha |
| Population | Present total (1991) | 13,000 | Planned Service pop. (2006) | 19,000 |
| Number of Villages | 3 Areas (about 60 Villages) | Planned Area for Water Service | 120km ² | Population density |
| | | | | 158pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Eastern area | | 5,000 | 7,295 |
| 2 | Central area * | | 5,000 | 7,295 |
| 3 | Western area | | 3,000 | 4,377 |
| Total | | | 13,000 | ≈ 19,000 |

* This project area is only the central area.

| | | | | | |
|--------------------|----------------------|--------------------------------|--------------------|-----------------------------|--------------------------|
| Site Number | 6 | | | | |
| Priority order | ④ | | | | |
| Site name | Al Usfyn | | | | |
| Governorate | Taizz | | | District | Al Qabaitah |
| Population | Present total (1991) | 28,500 | | Planned Service pop. (2006) | 41,600 |
| Number of Villages | 20 | Planned Area for Water Service | 160km ² | Population density | 260pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Ashariqah | | | |
| 2 | Jabal Annaby | | | |
| 3 | Daish | | | |
| 4 | Al-Rabyn | | | |
| 5 | Wadi Thamran | | | |
| 6 | Najd Thamran | | | |
| 7 | Al-Ayfoa * | | | |
| 8 | Qarath | | | |
| 9 | Aireem | | | |
| 10 | Al-Aqrath | | | |
| 11 | Al-Hallageno | | | |
| 12 | Al-Karb ** | | | |
| 13 | Arrazoq | | | |
| 14 | Wadi Al-Hanakah | | | |
| 15 | Al-Laqa | | | |
| 16 | Tabab | | | |
| 17 | Al-Marabha | | | |
| 18 | Al-Akrob | | | |
| 19 | Al-Jalliha | | | |
| 20 | Al-Qaidah | | | |
| Total | 20 | 20 | 28,500 | 41,600 |

* Al-Ayfoa (Al-Jabl), ** Al-Karb (Anafat)

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|------------------------------------|
| Site Number | 7 | | | |
| Priority order | ⑩ | | | |
| Site name | Al Jabub | | | |
| Governorate | Ibb | | District | Ar Radmah |
| Population | Present total (1991) | 2,000 | Planned Service pop. (2006) | 2,900 |
| Number of Villages | 6 | Planned Area for Water Service | 10kad | Population density 290pers./kad |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Hirrimah | 35 | 270 | 394 |
| 2 | Aqham * | 50 | 330 | 481 |
| 3 | Al-Jabub | 20 | 220 | 321 |
| 4 | Kawlat Bahal | 50 | 540 | 788 |
| 5 | Al-Khubaniyah** | 30 | 320 | 467 |
| 6 | Habar *** | 25 | 320 | 467 |
| Total | 6 | 210 | 2,000 | ≈ 2,900 |

* Aqham & Al-Mallahah, ** Al-Khubaniyah & Qarn Ambari, *** Habar & Bait Badr

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|--------------------------|
| Site Number | 9 | | | |
| Priority order | ⑦ | | | |
| Site name | Al Ghudu | | | |
| Governorate | Marib | | District | Sirwah |
| Population | Present total (1991) | 1,770 | Planned Service pop. (2006) | 2,600 |
| Number of Villages | 14 | Planned Area for Water Service | 15km ² | Population density |
| | | | | 173pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Al-Faras | 15 | 100 | 146 |
| 2 | Al-Agrab | 10 | 80 | 117 |
| 3 | Al-Oblly | 8 | 60 | 88 |
| 4 | Al-Qaran | 10 | 80 | 117 |
| 5 | Al-Attweal | 10 | 80 | 117 |
| 6 | Al-Hazienn | 20 | 150 | 219 |
| 7 | Al-Saleh | 15 | 130 | 190 |
| 8 | Al-Saif | 15 | 140 | 204 |
| 9 | Al-Had * | 20 | 150 | 219 |
| 10 | Abu Aeen | 10 | 100 | 146 |
| 11 | Mohal Athail | 10 | 100 | 146 |
| 12 | Al-Ahmed ** | 15 | 150 | 219 |
| 13 | Mahal Al-Faheed | 20 | 200 | 292 |
| 14 | Mahal *** | 25 | 250 | 365 |
| Total | 14 | 203 | 1,770 | ≈ 2,600 |

* Al-Had & Al-Dowoqh, ** Al-Ahmed Hassien, *** Mahal Al-Waqatayn

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|--|
| Site Number | 11 | | | |
| Priority order | ⑥ | | | |
| Site name | Aflah Al Yaman | | | |
| Governorate | Hajja | | District | Aflah Al Yaman |
| Population | Present total (1991) | 4,500 | Planned Service pop. (2006) | 6,600 |
| Number of Villages | 22 | Planned Area for Water Service | 7.5km ² | Population density 880pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Al-Qaadh | 25 | 170 | 248 |
| 2 | Al-Qhareb | 90 | 670 | 977 |
| 3 | Assahl | 30 | 250 | 365 |
| 4 | Assoaq | 15 | 130 | 190 |
| 5 | Qaddat * | 20 | 170 | 248 |
| 6 | Al-Manather | 15 | 130 | 190 |
| 7 | Al-Athariah | 20 | 130 | 190 |
| 8 | Morssa | 20 | 170 | 248 |
| 9 | Al-Anad | 25 | 210 | 306 |
| 10 | Bait Saleh | 25 | 240 | 350 |
| 11 | Al-Mahrabah | 25 | 170 | 248 |
| 12 | Addeer | 15 | 80 | 117 |
| 13 | Al-Dakhwazh | 30 | 250 | 365 |
| 14 | Adharr | 35 | 300 | 438 |
| 15 | Assoadamh | 15 | 130 | 190 |
| 16 | Al-Akawrrh | 12 | 80 | 117 |
| 17 | Al-Kawllah | 10 | 80 | 117 |
| 18 | Al-Handy | 40 | 340 | 496 |
| 19 | Asswady | 30 | 210 | 306 |
| 20 | Arrubu | 20 | 130 | 190 |
| 21 | Astrabah | 30 | 210 | 306 |
| 22 | Al-Kanah | 30 | 250 | 365 |
| Total | 22 | 577 | 4,500 | ≈ 6,600 |

* Qaddat Al-Thallath

| | | | | |
|--------------------|----------------------|--------------------------------|-----------------------------|---|
| Site Number | 12 | | | |
| Priority order | ⑧ | | | |
| Site name | Bait Al Sultan | | | |
| Governorate | Ar Rajam | | District | Al Mahweet |
| Population | Present total (1991) | 3,600 | Planned Service pop. (2006) | 5,300 |
| Number of Villages | 11 | Planned Area for Water Service | 14km ² | Population density 379pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Bait Al-Sultan | 85 | 600 | 875 |
| 2 | Bait Abu Qail | 40 | 300 | 438 |
| 3 | Bait Qahwash | 50 | 350 | 511 |
| 4 | Al-Lutha | 50 | 350 | 511 |
| 5 | Dar Milh | 35 | 250 | 365 |
| 6 | Al-Waqeayn | 40 | 350 | 511 |
| 7 | Al-Arkaz | 35 | 300 | 438 |
| 8 | Bani Shahab | 45 | 450 | 657 |
| 9 | Al-Half | 30 | 200 | 292 |
| 10 | Al-Manarah | 30 | 200 | 292 |
| 11 | Bait Mazzad | 30 | 250 | 365 |
| Total | 11 | 470 | 3,600 | 5,300 |

| | | | | | |
|--------------------|----------------------|--------------------------------|-------------------|-----------------------------|--------------------------|
| Site Number | 14 | | | | |
| Priority order | ① | | | | |
| Site name | Al Mallaheeth | | | | |
| Governorate | Sa'dah | | | District | Al Dhaher |
| Population | Present total (1991) | 3,180 | | Planned Service pop. (2006) | 4,600 |
| Number of Villages | 9 | Planned Area for Water Service | 14km ² | Population density | 329pers./km ² |

| Location No. | Name of Villages | No. of Houses | Population in 1991 | Estimated Population in 2006 |
|--------------|------------------|---------------|--------------------|------------------------------|
| 1 | Al-Mallaheeth | 200 | 1,200 | 1,751 |
| 2 | Al-Marwy:Alalla | 40 | 400 | 584 |
| 3 | Al-Marwy:Assfal | 60 | 420 | 613 |
| 4 | Assaqen * | 40 | 280 | 409 |
| 5 | Al-Matla ** | 35 | 350 | 511 |
| 6 | Al-Ladh | 10 | 50 | 73 |
| 7 | Assafia *** | 35 | 200 | 292 |
| 8 | Tarrany | 20 | 160 | 233 |
| 9 | Marrwa | 15 | 120 | 175 |
| Total | 9 | 455 | 3,180 | 4,640 |

* Ashaqen & Assabbar, ** Al-Matla & Al-Mathamy, *** Assafia & Al-Naqrh


APPENDIX II - g Road Conditions from Sana'a to The Project Sites

| SITE NAME | Paved | Feeder | M. | Total |
|----------------------|--|--------|----|-------|
| 1. Iyal Qasim | 70 | 20 | 10 | 100 |
| | Sana'a — Al-Raidah — Ga Shams — Iyal Qasim | | | |
| 2. Mahalat Najr | 50 | 0 | 2 | 52 |
| | Sana'a — Amran — Mahalat Najr | | | |
| 3. Khamis Bani Hajaj | 55 | 0 | 4 | 59 |
| | Sana'a — Thuila — Al-Shaim | | | |
| 4. Bani Afif | 320 | 0 | 7 | 327 |
| | Sana'a — Taizz — Ash ShamSarah — Bani Afif | | | |
| 5. Al Husha | 226 | 0 | 45 | 271 |
| | Sana'a — Yarim — Qatabah — Zuran | | | |
| 6. Al Usfyn | 290 | 0 | 0 | 290 |
| | Sana'a — Taizz — Ar Rahidah | | | |
| 7. Al Jabub | 176 | 0 | 0 | 176 |
| | Sana'a — Yarim — Al Jabub | | | |
| 8. Majzar | 140 | 0 | 0 | 140 |
| | Sana'a — Al Farda — Barakish | | | |
| 9. Al Ghudu | 145 | 0 | 15 | 160 |
| | Sana'a — Al Jidan — Al Ghudu | | | |
| 10. Ash Sharaq | 120 | 0 | 18 | 138 |
| | Sana'a — Hajjah — Alhan | | | |
| 11. Aflah Al Yaman | 170 | 60 | 20 | 250 |
| | Sana'a — Hajjah — Al Khashim — Shafal — Bani Yus | | | |
| 12. Bait Al Sultan | 50 | 60 | 0 | 110 |
| | Sana'a — Shibam — Ar Rajam | | | |
| 13. Al Thajah | 230 | 133 | 0 | 363 |
| | Sana'a — Hajjah — Harad — Al Mallaheeth — Al Thaia | | | |
| 14. Al Mallaheeth | 230 | 115 | 0 | 345 |
| | Sana'a — Hajjah — Harad — Al Khashim — Harad — Al Mallaheeth | | | |

— Paved Road — Feeder Road — M, Mountainous Road — Distance (km)

APPENDIX III
WATER SOURCE

APPENDIX III - a LITHOLOGY OF BOERHOLES IN THE PROJECT AREA



APPENDIX III - b Geoelectric Prospecting

During the field survey, the geoelectric prospecting was carried out. The results are shown as follows:

1. Objective

The objective of the prospecting is to obtain basic data for on the geological structure determining the well depths in the respective sites.

2. Outline of the survey

- A.) Equipment: a. Type ESG1 Specific Earth Resistance Tester
b. Type MCOHM Specific Earth Resistance Tester

B.) Prospecting points and depth

| Site name | Number of prospecting points | Measuring Depth(m) |
|---------------------|------------------------------|--------------------|
| No.2 MAHALAT NAJR | 1 | 120 |
| No.4 BANI AFIF | 1 | 170 |
| No.5 AL-HUSHA | 4 | 200 |
| No.7 AL-JABUB | 2 | 200 |
| *No.13 AL-THAIAH | 2 | 130 |
| No.14 AL-MALLAHEETH | 1 | 150 |

* canceled site

C.) Measuring method: Wenner's 4-electrode configuration

Electrode separation:

| | |
|------|-------------------|
| 1 m | interval 0-4 m |
| 2 m | interval 4-32 m |
| 4 m | interval 32-100 m |
| 10 m | interval 100m - |

Analysis: Sundberg's standard curve method combined with direct

reading method

3. Results of prospecting

No.2: MAHALAT NAJR

The curve shows 4 layers

| Resistivity layer | Depth(m) | Resistivity value($\Omega \cdot m$) | Geological Features | Formation Group |
|-------------------|----------|---------------------------------------|--|---------------------------|
| No.1 | 0 - 4 | 12.8 | Wadi deposits composed of clayey fine sand | Alluvium |
| No.2 | 4 - 12 | 20.2 | Weathered and clayey deposits | Quaternary volcanic rocks |
| No.3 | 12 - 100 | 130-1000 | Basalt lava with interbeds of tuff breccia | |
| No.4 | 100 - | 94 | Limestone | Amran series |

According to the analysis, a depth of 56-84m in the layer of No.3 is judged to be a fractured zone of basalt, indicating the aquifer ranges from 40 to 100m in depth. The depth of a new well is determined to be 100m.

No.4: BANI AFIF

The curve shows 7 layers

| Resistivity layer | Depth(m) | Resistivity value($\Omega \cdot m$) | Geological Features | Formation Group |
|-------------------|----------|---------------------------------------|---|--------------------|
| No.1 | 0 - 4 | 100 | Wadi deposits composed of sand | Alluvium |
| No.2 | 6 - 10 | 480 | Basalt lava | Yemen Volcanics |
| No.3 | 10 - 28 | 84-124 | Weathered clayey basalt | |
| No.4 | 28 - 76 | 300 - ? (High) | Basalt lava | |
| No.5 | 76 - 92 | 112 | Fractured zone of basalt | |
| No.6 | 92 - 150 | 120 - 600 | Basalt lava with interbeds of fractured zones | |
| No.7 | 150 - | 110 | Fractured zone of basalt | |

Fractured zones are analyzed to occur in No.5(76-92m), No.6(115-130m) and No.7(150m-), indicating the aquifer ranges from 70 to 170m in depth. In consideration of the conditions of existing well, the depth of a new well is recommended to be 150m.

No.5: AL-HUSHA

In this site, the measurements at 4 prospecting points (depth=250m) were carried out. The apparent resistivity curves show different shapes from one another, suggesting the facies of Yemen volcanics composing this site are quite complex.

Prospecting point (1)

| Resistivity layer | Depth(m) | Resistivity value($\Omega \cdot m$) | Geological Features | Formation Group |
|-------------------|-----------|---------------------------------------|---|--------------------|
| No.1 | 0 - 10 | 54 - 100 | Wadi deposits composed of sand-clayey sand, gravel, clay | Alluvium |
| No.2 | 10 - 110 | 4 - 96 | To 22m: Weathered zone of clay 32-44m, 72-76m, 84-110m Fractured zone | Yemen Volcanics |
| No.3 | 110 - 150 | 72 | Slightly hard basalt | |
| No.4 | 150 - 170 | 14 | Fractured zone | |
| No.5 | 170 - | 40 | Slightly hard basalt | |

At this point the aquifer starts at a depth of 44m. The two existing wells(W-6, W-7) near this point are supposed to tap this aquifer.

Prospecting point (2)

| Resistivity layer | Depth(m) | Resistivity value($\Omega \cdot m$) | Geological Features | Formation Group |
|-------------------|-----------|---------------------------------------|--|--------------------|
| No.1 | 0 - 8 | 6 - 57 | Wadi deposits composed of sand and clay | Alluvium |
| No.2 | 8 - 22 | 9 - 37 | Clayey - brecciated basalt by weathering | Yemen Volcanics |
| No.3 | 22 - 80 | 56 - 110 | Slightly hard basalt Fractured zone (52-56m) | |
| No.4 | 80 - 120 | 42 - 56 | Slightly hard basalt(80-92m) Fractured zone (92-120m) | |
| No.5 | 120 - 140 | 170 | Hard basalt | |
| No.6 | 140 - 160 | 46 | Fractred zone | |
| No.7 | 160 - | 74 | Slightly hard basalt | |

The aquifer is judged to lie from 50 to 160m in depth, and the depth of a new well is recommended to be 200m.

Prospecting point (3)

| Resistivity layer | Depth(m) | Resistivity value($\Omega \cdot m$) | Geological Features | Formation Group |
|-------------------|-----------|---------------------------------------|---|--------------------|
| No.1 | 0 - 10 | 12 - 92 | Wadi deposits composed of sand and clay | Alluvium |
| No.2 | 10 - 52 | 22 - 30 | Clayey deposits by weathering | Yemen Volcanics |
| No.3 | 52 - 84 | 320 | Hard basalt | |
| No.4 | 84 - 120 | 18 | Fractured zone | |
| No.5 | 120 - 150 | 240 | Hard basalt | |
| No.6 | 150 - 170 | 120 | Fractured zone | |
| No.7 | 170 - | 84 | Slightly hard basalt | |

The aquifer is judged to lie at 50-60m, 80-90m, 110-125m 150-180m in depth, and the depth of a new well is recommended to be 200m.

Prospecting point (4)

| Resistivity layer | Depth(m) | Resistivity value($\Omega \cdot m$) | Geological Features | Formation Group |
|-------------------|-----------|---------------------------------------|--|--------------------|
| No.1 | 0 - 4 | 50 | Wadi deposits composed of sand | Alluvium |
| No.2 | 4 - 10 | 148 | Wadi deposits composed of gravel | Yemen Volcanics |
| No.3 | 10 - 80 | 18 -260 | Weathered clay (10-30m) Hard basalt (30-36m) Fractured zone (36-80m) | |
| No.4 | 80 - 110 | 500 | Hard basalt | |
| No.5 | 110 - 140 | 8 | Fractured zone | |
| No.6 | 140 - 160 | 380 | Hard basalt | |
| No.7 | 160 - 180 | 16 | Fractured zone | |
| No.8 | 180 - | 320 | Hard basalt | |

The aquifer is judged to lie from 35 to 180m in depth, and the depth of a new well is recommended to be 200m.