

5.6.3 Economic Benefit

Economic benefit is evaluated as follows:

(1) Benefit of Flood Control Project

The economic benefit of the flood control project is presented as an effect of reduction in the flood damage to assets, agricultural products and economic activities in the river basins. The average annual flood damage shown in Section 3.1 is given as an average annual benefit of flood control project after completion of the construction work.

The average annual benefit is estimated at Rp. 40,215 million for the Deli-Percut River System as a sum of both benefits of the Deli river flood control project and the Percut river flood control project, and it is estimated at Rp. 8,961 million for the Padang river flood control project. The annual flows of these benefits are given in Table 5-3.

(2) Benefit of Water Supply Project

Economic benefit of the water supply project is generally estimated by multiplying an effective water quantity by an economic price of water. The urgent water supply project formulated in the present study is only construction of the Lausimeme Dam, excluding construction of water supply facilities such as treatment plant, transmission and distribution pipes and other facilities connected to users. Accordingly, the water price and produced quantity at the dam site are adopted as the basic values for estimating the economic benefit.

In the present study, the water price and its rise are respectively assumed to be Rp. 50/m³ in 1993 and the annual rate of 5% during the period of project life, as discussed in Section 4.4.

On the other hand, the quantity of water produced at the Lausimeme dam site is estimated at 3,700 l/s, i.e., 116.68 million m³ per annum. Under the conditions described in Section 4.4, the annual benefit of the water supply project is expected to accrue during the project life as follows:

Annual Benefit of Water Supply Project

Year		Benefit (mil.Rp.)	Annual		Year Annual (mil.Rp.)
From	To		From	To	
1993	1997	6,447	2023	2027	27,865
1998	2002	8,229	2028	2032	35,563
2003	2007	10,502	2033	2037	45,389
2008	2012	13,403	2038	2042	57,929
2013	2017	17,107	2043	2047	73,934
2018	2022	21,833	2048	-	94,360

(3) Benefit of the Integrated Project

The economic benefit of the integrated project for the Deli-Percut River System is given as a sum of both benefits of the flood control project and the water supply project, and the average annual benefit is indicated in Table 5-3.

5.6.4 Cost-Benefit Analysis

Results of cost-benefit analysis for the urgent flood control project and the water supply project are given in Table 5-4, and the EIRR is summarized as follows:

Economic Internal Rate of Return	
Project	EIRR (%)
1. Deli-Percut River System	
1.1 Integrated	14.35
1.2 Flood Control	17.90
1.3 Water Supply	9.90
2. Padang River Flood Control	11.86

In the results shown above, the flood control project is economically feasible. The EIRR of water supply project is nearly 10%, which is a fairly high rate compared with those of similar domestic water supply projects. This shows that the water supply project is feasible from the socioeconomic point of view.

Sensitivity Test

Various conditions and assumptions have been set in the careful study based on professional experience and appropriate judgment of experts, but there always remains the problem as to the degree of reliability of inputs. Therefore, a test is carried out for sensitivity of the EIRR to variations in the economic cost and benefit estimated.

Sensitivity tests are made on the EIRRs with 5% and 10% increase in the economic cost and with 5% and 10% decrease in the economic benefit. The results are given in Table 5-5.

The results show that the EIRRs of the integrated project and the flood control project are still maintained at more than 10% even if the cost goes up by 10% or the benefit comes down by 10%, which means that the economic feasibility of these projects is justifiable. The water supply project also maintains an EIRR of more than 9% even if the cost or benefit increase to 10% or decreases to 10%, respectively, which means that the project satisfies the condition of socioeconomic feasibility.

5.7 Social and Environmental Assessment

5.7.1 Social Impact

An environmental impact study was carried out in and around the urgent project area from two (2) viewpoints, social impacts and natural impacts. According to the results of the study, project implementation may bring about both beneficial and adverse social and environmental impacts before and during construction, and after completion of the project. On the long run, however, the beneficial effects could outweigh the adverse ones leading to stimulation of socioeconomic activities and unimpeded development of the region as a whole.

Stimulation of Socioeconomic Activities

Investment for and construction of the urgent project will not only increase economic activities but also stimulate the social atmosphere therearound. The urgent project will bring many business opportunities to the project area and give various incentives for advancement. Such stimulation of socioeconomic activities will result in technology development and educational improvement, together with the development of transportation and tourism which will further derive more benefits for the region.

Public Awareness and Participation

Lausimeme Dam and Medan Floodway, which will be constructed near Medan City, the capital of North Sumatra Province, are expected to become significant structures. For efficient operation and maintenance of the structures, public awareness of their important role in flood control and water supply is expected, and this could materialize with proper educational campaigns explaining such matters and obtaining public support and cooperation, including the public's participation in such activities. Through proper management of project implementation, it is also expected that the private sector will come into the development activities related to the project works and the area.

5.7.2 Environmental Impact

The main subjects regarding the construction of a dam are biological aspects. There are 37 species of terrestrial flora, 20 kinds of wild animals and 29 kinds of birds observed in the dam project area. Several of them are specifically protected under government regulations, and none of them are endangered by implementation of the project.

The route of the floodway is almost covered by paddy and bushes, but the main environmental impact of the floodway will arise after construction. In the dry season, the floodway may become a dumping site for solid waste or household garbage if not properly managed.

The main subjects in the environmental impact of river improvement for Deli, Percut and Padang are the aquatic flora and fauna, house evacuation and land acquisition. There are only 11 to 15 kinds of terrestrial flora and 14 types of fishes observed in the Padang, Deli and Percut rivers. No protected species is observed. The required house evacuation is estimated at about 1,500 houses. Results of

impact analyses using the matrix method are summarized as follows:

Environmental Impact Analysis

Project	Basic Evaluation on Environment			Change of Environmental Beauty
	Importance of Resources	Environment Condition	Sensitivity of Management	
Lausimeme Dam	very high scale of 5	good scale of 5	medium scale of 3	-1 (-15%)
Medan Floodway	very high scale of 5	good scale of 4	medium scale of 3	-1 (-12%)
Deli River Improvement	high scale of 5	good scale of 4	medium scale of 3	-1 (-19%)
Percut River Improvement	high scale of 5	good scale of 4	medium scale of 3	-1 (-14%)
Padang River Improvement	high scale of 5	good scale of 4	medium scale of 3	-1 (-17%)

For the above basic evaluation, the following scaling criteria are applied:

Scale Criteria

Kind of Evaluation	Scale	Characteristics
Importance of Resource	1 2 3 4 5	Not important Less important Moderate Important Most Important
Environmental Condition	1 2 3 4 5	Bad Not too bad Medium Good Very good
Sensitivity of Management	1 2 3 4 5	Very Difficult Difficult Quite Difficult Easy Very easy

The results of the environmental impact study was submitted to KOMPUS AMDAL-PU (the Central Commission of Environmental Impact Assessment, Ministry of Public Works) on February 10, 1992, for its perusal. Then, a meeting among representatives of KOMPUS AMDAL-PU, P3SA of DPUP North Sumatra and LATMI-USU, the firm which conducted the environmental impact study under subcontract with JICA, was held in Jakarta on February 15, 1992. Although some comments were made indicating the necessity of other relevant information, the necessary steps will be undertaken by the Project Proponent, DGWRD, to realize project implementation as soon as possible.

To maximize the positive impact and minimize the negative impact of project works, the environmental management plan (RKL) and the environmental monitoring plan (RPL) shall be arranged when the proposed project is implemented.

5.8 Project Implementation

5.8.1 Implementation Schedule

The urgent plan is divided into two (2) areas, the Deli-Percut River System and the Padang River Basin. The former is tentatively named as Deli-Percut River Flood Control and Water Supply Project and the latter is Padang River Improvement Project.

The financial project cost is estimated at Rp. 493,373 million for the Deli-Percut and Rp. 73,574 million for the Padang, totaling approx. Rp. 567 billion including price escalation (at 1991 prices). Therefore, the annual average fund required for the project implementation is approx. Rp. 95 billion which corresponds to 2.2% of the projected GRDP of Rp. 4,370 billion in the study area in 1991, while the projected budget expenditure of the North Sumatra Provincial Government will amount to about Rp. 450 billion in 1991. Therefore, it is assumed that project implementation is to be financed by international funding institutions.

The invitation for prequalification of construction contractors for the Deli River Improvement Works which has been proposed in the flood control component of MUDP II, was made on November 12, 1991. Channel improvement, lining levee embankment and ancillary works will be undertaken for a total stretch of 25,309 m of the Deli mainstream up to the confluence with Babura River. Construction works started in 1992 and are expected to be completed in 1995.

In view of the implementation of the Deli River Improvement Works mentioned above, implementation of the Deli-Percut River Flood Control and Water Supply Project is divided into two (2) portions. One is the Deli River Improvement Works and the other portion consists of the Percut River Improvement Works, the construction of Medan Floodway and the construction of Lausimeme Dam. The financial project cost for the former is Rp. 226,630 million and the latter is Rp. 266,743 million.

The annual average fund required for the implementation of the Deli- Percut River Flood Control and Water Supply Project excluding the Deli River Improvement Works is estimated at approx. Rp. 38 billion. As for the Padang River Improvement Project, it is estimated at Rp. 12 billion.

In compliance with the construction schedule stated in Subsection 5.5.1, priority of implementation is given to the Deli-Percut River Flood Control and Water Supply Project. On the assumption that the detailed design for the project excluding the Deli River Improvement Works is carried out after this feasibility study, the implementation schedule is prepared based on the priority of project components, with the target year 2000, as shown in Fig. 5-17.

5.8.2 Recommendation to Pursue the Urgent Project

Development of Tourism and Recreation

Lake Toba is well known as a resort among the people in Medan and its vicinity. However, the location is far and only those who can financially afford visit the lake for leisurely activities.

The proposed Lausimeme Dam is only 32 km away from the center of Medan. The surrounding area is gifted with natural vegetation, flora and fauna, and topographically superior scenery. Construction of the dam will create an artificial lake which has many possibilities for recreational activities such as fishery, camping, swimming, boat rowing and other water-related amusements. With its easy accessibility and the abundant natural resources, the Lausimeme Dam could be a promising resort for tourism development.

In this connection, it is recommended that land resources development be studied and implemented simultaneously with the implementation of the urgent project.

Participation of Private Sector

In accordance with the procedure for a large-scale water supply development project in Indonesia, water sources are developed by the central government, i.e., the DGWRD, Ministry of Public Works, as part of multipurpose water resources development. Water for municipal/domestic uses is allocated to the DGCK and to local governments which are responsible for water supply projects at the producer's price.

Then, a kind of state enterprise (PDAM) manages the water supply system after the construction of main structures and the transfer of operation/administration from the BPAM. As a private sector organization, the state enterprise has to gain some profits for cost of operation/maintenance of the system and for cost of future improvement and expansion of services. The storage capacity of the proposed reservoir is allocated mostly for water supply, which is estimated at 29,500,000 m³ or 90% of the effective storage capacity.

The proposed Lausimeme Dam, as stated in the foregoing, is expected to have secondary benefits by promoting tourism development and increasing opportunities for leisure and recreation of people in Medan and its vicinity. Although Lausimeme Dam will have an important effect on flood control of the Deli-Percut River System, the dam and reservoir as well as the impounded water will contribute much to the area of Medan and its vicinity for the betterment of people's living standard. Therefore, it is recommended that the participation of the private sector is not only on operation/maintenance but also on project implementation.

Further Study

(1) Survey

The optimum floodway route is selected in this study using the topographic map with a scale of 1:5,000. Therefore, detailed river survey or topographical survey is recommended to be conducted in the detailed design stage. Furthermore, detailed topographic survey with a scale of 1:500 is required for the proposed Lausimeme dam site and additional aerophoto mapping with a scale of 1:5,000 is necessary for possible quarry sites around the reservoir.

(2) Geological Investigation

In this present study, a total of 150 m of drilling, in-situ permeability test and some uniaxial compression of drilling core were undertaken for the proposed Lausimeme Dam. Detailed geological investigation of additional drilling for the dam site and saddle portion of the reservoir are necessary for the detailed design. Investigation of core and rock materials and other soil mechanics tests shall be carried out before the detailed design.

(3) Environmental Impact Analysis

During the feasibility study, environmental impact study (ANDAL) was conducted for the urgent project. Although the study shows only small negative impacts to occur during the construction of urgent project as stated in Section 5.7, a more detailed environmental impact assessment has to be conducted by the authorized commission before the detailed design with simultaneous preparation of the environmental management plan and the environmental monitoring plan.

TABLES

Table 2-1 MEAN MONTHLY RAINFALL AT REPRESENTATIVE STATION, 1969-88

(Unit : mm)

Station	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Year
No. 1.01	103.2	108.4	107.8	141.3	188.1	151.3	149.5	182.4	248.6	299.1	251.6	223.5	2,154.4
No. 1.09	80.5	69.1	89.4	110.4	155.6	100.2	124.2	167.2	209.9	241.2	220.6	182.1	1,750.0
No. 1.16	95.2	91.6	96.2	142.8	195.4	134.0	169.9	197.4	259.1	289.9	241.2	190.9	2,103.6
No. 1.19	98.5	56.7	66.2	87.9	136.0	110.7	119.8	153.8	230.8	261.3	217.3	203.7	1,742.4
No. 1.23	85.6	60.8	88.2	129.6	186.0	150.4	153.9	180.5	231.5	272.2	241.8	201.7	1,982.1
No. 3.03	93.1	74.4	99.3	133.3	180.3	133.8	153.6	190.7	260.9	284.2	252.7	201.3	2,057.3
No. 3.06	151.3	141.5	100.1	176.0	242.5	199.4	216.5	250.0	292.9	330.6	275.1	232.4	2,608.3
No. 3.14	118.5	105.8	105.9	160.6	174.5	162.3	168.4	206.7	273.2	291.4	262.6	215.6	2,245.5
No. 3.22	68.9	57.0	84.6	95.3	131.8	106.2	138.7	136.2	184.8	198.5	186.6	172.6	1,561.0
No. 3.32	172.3	167.9	155.9	189.0	314.3	187.9	248.7	248.1	308.2	357.8	289.3	264.3	2,903.6
No. 4.02	123.9	109.4	130.8	214.8	299.1	172.2	225.1	217.4	349.6	361.9	273.4	217.6	2,695.1
No. 4.03	97.0	70.9	79.7	141.1	155.5	122.3	153.1	160.7	207.8	235.1	167.6	149.7	1,740.5
No. 4.05	121.0	121.7	107.0	207.8	227.4	157.8	195.8	185.2	290.1	273.4	250.9	204.8	2,342.9
No. 4.07	121.3	106.9	115.6	201.1	228.8	177.2	203.1	187.9	301.4	297.5	262.8	203.4	2,407.1
No. 4.17	81.6	69.9	91.8	126.8	138.6	107.7	127.9	148.7	213.5	227.7	177.0	150.6	1,661.9

Table 2-2(1/2) ANNUAL MAXIMUM DISCHARGE RECORDS (AUTOMATIC GAUGE)

Year	Date	H (m)	Q (m ³ /s)	Date	H (m)	Q (m ³ /s)																
1980	X	X	X	30/Oct	2.43	79.1	X	X	X	X	X	X	X	X	X	X	X	X	X	31/Dec	2.81	170.0
1981	X	X	X	16/Dec	2.42	78.3	X	X	X	X	X	X	X	X	X	X	X	X	X	6/May	2.84	172.9
1982	16/Sep	3.80	270.0	29/Dec	2.49	79.8	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
1983	8/Nov	2.46	151.0	30/Sep	2.53	84.9	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
1984	3/Dec	3.04	211.2	X	X	X	30/Oct	3.06	83.2	9/Feb	2.47	177.4	8/Nov	1.52	7.8	X	X	X	X	X	X	X
1985	21/May	3.59	260.9	6/Oct	2.90	101.4	21/May	3.49	105.0	19/Dec	2.34	161.4	19/Dec	1.73	11.0	17/Dec	2.47	146.0				
1986	7/Dec	4.34	352.1	6/Dec	3.01	103.2	7/Dec	4.67	178.0	7/Dec	2.54	186.4	18/Apr	1.76	11.4	14/Apr	2.46	146.0				
1987	7/May	3.05	214.8	16/Sep	2.43	80.8	10/Dec	4.45	162.9	26/Jul	3.24	288.0	10/Dec	2.49	26.8	8/Dec	1.83	108.0				
1988	X	X	X	19/Sep	2.48	83.8	1/Apr	2.97	79.0	15/Feb	2.16	140.4	3/Sep	1.96	15.0	30/Sep	2.23	132.0				
1989	23/Nov	4.46	359.7	24/Sep	2.12	73.0	19/Dec	4.24	149.2	X	X	X	11/Sep	1.88	13.5	24/Oct	1.83	108.0				

X : No data available

Table 2-2(2/2) ANNUAL MAXIMUM DISCHARGE RECORDS
(STAFF GAUGE STATION)

Station	Kampung Lalang			Helvetia			Pulau Tagor		
Area	(254 km ²)			(341 km ²)			(1031 km ²)		
River	Belawan			Deli			Ular		
H - Q	Q = from Table			Q = from Table			Q = from Table		
Year	Date	H (m)	Q (m ³ /s)	Date	H (m)	Q (m ³ /s)	Date	H (m)	Q (m ³ /s)
1980	10/Oct	4.00	122.0	6/Dec	3.90	90.2	21/Dec	2.68	387.0
1981	18/Nov	4.50	137.0	29/Oct	3.58	79.5	11/May	1.60	230.0
1982	17/Sep	2.45	55.5	X	X	X	2/Feb	1.80	242.0
1983	13/Oct	3.55	99.0	X	X	X	X	X	X
1984	X	X	X	27/Jul	4.35	101.0	24/Apr	1.97	253.0
1985	X	X	X	6/Nov	4.60	110.0	18/Dec	1.78	243.0
1986	X	X	X	3/Feb	4.75	112.0	8/Jan	1.22	146.0
1987	X	X	X	X	X	X	X	X	X
1988	X	X	X	X	X	X	X	X	X
1989	9/Aug	4.00	117.0	24/Nov	4.55	104.0	24/Sep	2.44	254.0

Table 2-3 CENSUS POPULATION IN THE STUDY AREA,
NORTH SUMATRA PROVINCE AND INDONESIA
(Unit : 1,000 persons)

Administrative Units	Population				Average Annual Growth Rate (%)		
	1961	1971	1980	1990	1961-1971	1971-1980	1980-1990
Indonesia	97,085	118,368	147,490	179,322	2.10	2.32	1.97
North Sumatra Province	4,965	6,622	8,361	10,256	2.95	2.60	2.06
Study Area	-	2,233	2,870	3,629	-	2.83	2.37
Kab. Deli Serdang	972	1,431	1,241	1,603	3.99	-1.55	2.59
Kab. Simalungun *1	-	136	158	178	-	1.68	1.23
Kodya Medan	479	636	1,379	1,731	2.90	12.99	2.30
Kodya Tebing Tinggi	26	30	92	117	1.47	2.69	2.40

Sources: - Hasil Sensus Penduduk 1990, Indonesia, Sumatera Utara,
Kab.Deli Serdang, Kodya. Medan and Kodya. Tebing Tinggi.
- Statistical Year Book of Indonesia, 1990, Biro Pusat Statistik.

Note : *1 Seven Kecamatans in the Study Area.

Table 2-4 LAND USE IN KABUPATEN DELI SERDANG,
1976 and 1985

No. Land Use	1976		1985		Changes
	(ha)	%	(ha)	%	
1. Residential Area	17,883	4.02	20,022	4.49	+ 11.96
2. Paddy Field					
1 x Paddy /Year	71,000	15.95	47,371	10.63	- 33.31
2 x Paddy /Year	22,067	4.96	45,419	10.19	+ 105.82
3. Large Scale Plantation	136,768	30.72	135,461	30.40	- 0.96
4. Public Plantation	31,397	7.05	33,458	7.51	+ 6.65
5. Dry Land	81,002	18.19	84,112	18.88	+ 3.84
6. Forest	76,200	17.12	73,153	16.42	- 3.99
7. Pond	940	0.21	1,073	0.24	+ 14.15
8. Swampy Area	3,216	0.72	2,568	0.58	- 30.72
9. Scrub, Alang-alang Grass	4,742	1.07	2,407	0.54	- 49.24
10. Special Use	-	-	510	0.11	- 100.00
Total	445,215	100.00	445,554	100.00	

Table 2-5 BUDGET OF CENTRAL GOVERNMENT, INDONESIA

(Unit : Rp Billion)

Year	Receipt			Expenditure		
	Routine	Development	Total	Routine	Development	Total
1985/86	19,252	3,572	22,824	11,951	10,873	22,824
1986/87	16,141	5,752	21,893	13,559	8,332	21,891
1987/88	20,803	6,158	26,961	17,482	9,477	26,959
1988/89	23,004	9,991	32,995	20,739	12,251	32,990
1989/90	28,740	9,429	38,169	24,331	13,834	38,165
Average Annual Growth Rate (%)	10.54	27.46	13.72	19.45	6.21	13.72

Source : Statistical Year Book of Indonesia, 1989 & 1990, Biro Pusat Statistik.

Table 2-6 GROSS DOMESTIC PRODUCT (GDP) AT CURRENT MARKET PRICES
BY INDUSTRIAL ORIGIN, INDONESIA

(Unit : Rp. Billion)

Industrial Origin	Year					Average Annual Growth Rate (%) (1985-1989)
	1985	1986	1987	1988	1989	
1. Agriculture, Forestry & Fishery	22,413.2 (23.7)	24,750.5 (24.1)	29,116.0 (23.3)	34,193.4 (24.1)	38,998.4 (23.4)	14.9
2. Mining & Quarrying	15,403.6 (16.3)	11,502.8 (11.2)	17,266.8 (13.8)	17,161.8 (12.1)	21,729.6 (13.1)	9.0
3. Manufacturing Industries	12,903.8 (13.6)	17,184.7 (16.8)	21,150.4 (16.9)	26,252.4 (18.5)	30,573.3 (18.4)	24.1
4. Electricity, Gas & Water Supply	781.3 (0.8)	647.1 (0.6)	746.9 (0.6)	869.0 (0.6)	1,008.3 (0.6)	6.6
5. Construction	5,301.8 (5.6)	5,313.8 (5.2)	6,087.4 (4.9)	7,169.2 (5.0)	8,884.2 (5.3)	13.8
6. Trade, Hotel & Restaurant	14,697.5 (15.5)	17,083.4 (16.7)	21,048.3 (16.9)	24,379.2 (17.2)	28,314.1 (17.0)	17.8
7. Transportation & Communication	6,050.5 (6.4)	6,406.9 (6.2)	7,442.6 (6.0)	8,139.6 (5.7)	9,085.0 (5.5)	10.7
8. Banking & Other Financial Intermediaries	2,802.4 (3.0)	4,058.8 (4.0)	4,795.1 (3.8)	5,322.4 (3.7)	6,550.8 (3.9)	23.6
9. Ownership of Dwelling	2,443.0 (2.6)	2,976.0 (2.9)	3,349.1 (2.7)	3,736.0 (2.6)	4,154.9 (2.5)	14.2
10. Public Administration & Defence	7,925.1 (8.4)	8,307.3 (8.1)	8,911.8 (7.1)	9,446.2 (6.7)	11,174.2 (6.7)	9.0
11. Services	3,998.6 (4.2)	4,314.6 (4.2)	4,902.5 (3.9)	5,351.1 (3.8)	5,856.7 (3.5)	10.0
G D P	94,720.8 (100)	102,545.9 (100)	124,816.9 (100)	142,020.3 (100)	166,329.5 (100)	15.1

Source : Statistical Year Book of Indonesia, 1988 & 1989, Biro Pusat Statistik.

Note : Figures in Parenthesis indicate distribution in percent.

Table 2-7 TREND OF EXTERNAL TRADE OF INDONESIA,
1980-1990

(Unit : Million US\$)

Year	Including Petroleum and Gas			Excluding Petroleum and Gas		
	Exports (1)	Import (2)	Balance (4)=(2)-(3)	Exports (5)	Import (6)	Balance (7)=(5)-(6)
1980	23,950.4	10,834.4	13,116.0	6,168.8	9,085.9	(2,917.1)
1981	25,164.5	13,272.1	11,892.4	4,501.3	11,550.4	(7,049.1)
1982	22,328.3	16,858.9	5,469.4	3,929.2	13,314.1	(9,384.9)
1983	21,145.9	16,351.8	4,794.1	5,005.3	12,207.0	(7,201.7)
1984	21,887.8	13,882.1	8,005.7	5,869.7	11,185.3	(5,315.6)
1985	18,586.7	10,259.1	8,327.6	5,868.8	8,987.5	(3,118.7)
1986	14,805.0	10,718.4	4,086.6	6,528.4	9,632.0	(3,103.6)
1987	17,135.6	12,370.3	4,765.3	8,579.5	11,302.3	(2,722.8)
1988	19,218.5	13,248.5	5,970.0	11,536.9	12,339.4	(802.5)
1989	22,158.9	16,359.6	5,799.3	13,480.1	15,164.4	(1,684.3)
1990	25,801.2	20,103.8	5,697.4	14,679.3	18,696.5	(4,017.2)

Source : Statistical Year Book of Indonesia, 1990, Biro Pusat Statistik

Note : Figures in parenthesis indicate negative.

Table 2-8 GROSS REGIONAL DOMESTIC PRODUCT (GRDP) OF NORTH SUMATRA PROVINCE BY INDUSTRIAL ORIGIN AT CURRENT MARKET PRICES

(Unit : Rp Million)

Industrial Origin	Year						Average Annual Growth Rate (%)
	1983	1984	1985	1986	1987	1988	
1. Agriculture, Forestry & Fishery	1,135.2 (32.7)	1,407.0 (32.3)	1,580.0 (33.6)	1,790.9 (34.6)	2,311.4 (35.9)	2,779.2 (36.6)	19.6
2. Mining & Quarrying	187.8 (5.4)	277.8 (6.4)	240.7 (5.1)	181.4 (3.5)	206.2 (3.2)	196.5 (2.6)	0.9
3. Manufacturing Industries	466.2 (13.4)	636.5 (14.6)	700.9 (14.9)	803.9 (15.5)	999.4 (15.5)	1,220.3 (16.1)	21.2
4. Electricity, Gas & Water Supply	25.0 (0.7)	35.8 (0.8)	46.3 (1.0)	55.1 (1.1)	63.7 (1.0)	76.6 (1.0)	25.1
5. Construction	158.9 (4.6)	172.2 (3.9)	174.9 (3.7)	179.6 (3.5)	194.9 (3.0)	225.0 (3.0)	7.2
6. Trade, Hotel & Restaurant	538.2 (15.5)	638.1 (14.6)	663.3 (14.1)	745.7 (14.4)	1,055.2 (16.4)	1,256.9 (16.6)	18.5
7. Transportation & Communication	371.3 (10.7)	456.4 (10.5)	498.7 (10.6)	530.7 (10.2)	590.3 (9.2)	689.5 (9.1)	13.2
8. Financial Intermediaries, Ownership of Dwelling and Business Services	211.6 (6.1)	256.1 (5.9)	288.8 (6.1)	322.9 (6.2)	392.2 (6.1)	451.3 (5.9)	16.4
9. Social Community & Personal Services	379.4 (10.9)	482.2 (11.1)	508.2 (10.8)	571.8 (11.0)	626.6 (9.7)	696.9 (9.2)	12.9
GRDP	3,473.6 (100.0)	4,362.1 (100.0)	4,701.8 (100.0)	5,182.0 (100.0)	6,439.9 (100.0)	7,592.2 (100.0)	17.1

Source : North Sumatra in Figures, 1988 & 1989, Statistical Office of North Sumatra Province.

Note : Figures in parenthesis indicate distribution in percent.

Table 2-9 GDP OF INDONESIA, AND GRDP OF NORTH SUMATRA PROVINCE AND THE STUDY AREA

(Unit : Rp Billion)

Region	Year						Average Annual Growth Rate%(1983-1988)
	1983	1984	1985	1986	1987	1988	
I. At Current Prices							
Indonesia	-	87,054.8	94,720.8	102,545.9	124,816.9	142,020.3	13.1
		(-)	(8.8)	(8.3)	(21.7)	(13.8)	
North Sumatra Prov.	3,473.7	4,362.1	4,701.8	5,182.1	6,439.9	7,592.3	17.1
	(-)	(25.6)	(7.8)	(10.2)	(24.3)	(17.9)	
Study Area	1,294.8	1,583.8	1,717.1	1,917.1	2,384.0	2,765.1	16.5
	(-)	(22.3)	(8.4)	(11.6)	(24.4)	(16.0)	
Kab. Deli Serdang	379.8	487.4	546.4	614.6	774.1	893.7	18.9
	(-)	(28.3)	(12.1)	(12.5)	(26.0)	(15.5)	
Kodya. Medan	871.3	1,041.9	1,110.4	1,236.4	1,533.2	1,782.8	15.6
	(-)	(19.6)	(6.6)	(11.3)	(24.0)	(16.3)	
Kodya. Tebing Tinggi	43.7	54.5	60.3	66.1	76.7	88.6	15.3
	(-)	(24.7)	(10.6)	(9.6)	(16.0)	(15.5)	
II. At 1983 Constant Prices							
Indonesia	-	78,144.4	80,119.6	90,013.6	94,517.8	99,936.0	6.4
		(-)	(2.5)	(12.3)	(5.0)	(5.7)	
North Sumatra Prov.	3,473.7	3,734.7	3,886.5	4,131.7	4,439.4	4,759.8	6.5
	(-)	(7.5)	(4.1)	(6.3)	(7.4)	(7.2)	
Study Area	1,294.8	1,377.2	1,428.7	1,524.3	1,654.2	1,756.0	6.3
	(-)	(6.4)	(3.7)	(6.7)	(8.5)	(6.2)	
Kab. Deli Serdang	379.8	422.2	453.9	496.9	536.6	562.7	8.2
	(-)	(11.2)	(7.5)	(9.5)	(8.0)	(4.9)	
Kodya. Medan	871.3	907.7	924.7	974.6	1,062.8	1,135.3	5.5
	(-)	(4.2)	(1.9)	(5.4)	(9.0)	(6.8)	
Kodya. Tebing Tinggi	43.7	47.3	50.1	52.8	54.8	58.0	5.8
	(-)	(8.2)	(5.9)	(5.4)	(3.8)	(5.8)	

Sources : Statistical Year Book of Indonesia, 1989 & 1990, Biro Pusat Statistik.

North Sumatra in Figures, 1988 & 1989, Statistical Office of North Sumatra Province.

Note : Figures in parenthesis indicate a growth rate in percent every year.

Table 2-10 . . AREA HARVESTED, PRODUCTION AND YIELD RATE OF
MAJOR FOOD CROPS IN NORTH SUMATRA PROVINCE

Crops	1984	1985	1986	1987	1988	1989
1. Paddy						
Area harvested(1.000 ha)	583.06	612.35	582.46	656.65	672.89	679.42
Production (1.000 tons)	2,022.00	2,148.92	2,067.88	2,319.19	2,482.94	2,540.87
Yield rate(tons/ha)	3.47	3.51	3.55	3.53	3.89	3.74
2. Wetland Paddy						
Area harvested(1.000 ha)	496.25	525.43	505.83	569.45	592.78	599.52
Production (1.000 tons)	1,843.08	1,977.87	1,913.33	2,152.15	2,318.14	2,369.84
Yield rate(tons/ha)	3.71	3.76	3.78	3.78	3.91	3.95
3. Dryland Paddy						
Area harvested(1.000 ha)	86.81	86.92	76.52	87.20	80.11	79.90
Production (1.000 tons)	178.92	171.06	154.50	167.05	164.80	171.03
Yield rate(tons/ha)	2.06	1.97	2.02	1.92	2.06	2.14
4. Maize						
Area harvested(1.000 ha)	33.85	46.91	58.87	63.79	82.76	86.82
Production (1.000 tons)	64.35	90.68	109.37	140.68	168.28	175.99
Yield rate(tons/ha)	1.90	1.93	1.86	2.21	2.03	2.03
5. Cassava						
Area harvested(1.000 ha)	21.88	19.02	19.79	20.82	26.77	37.88
Production (1.000 tons)	255.96	230.12	247.36	245.17	327.66	488.69
Yield rate(tons/ha)	11.70	12.10	12.50	11.80	12.24	12.90
6. Sweet Potato						
Area harvested(1.000 ha)	15.86	14.84	14.34	13.66	16.00	18.61
Production (1.000 tons)	147.53	137.99	131.88	129.79	155.44	182.94
Yield rate(tons/ha)	9.30	9.30	9.20	9.50	9.71	9.83
7. Peanut						
Area harvested(1.000 ha)	11.84	13.08	12.24	18.97	24.64	26.81
Production (1.000 tons)	13.23	15.45	14.96	20.13	28.50	31.30
Yield rate(tons/ha)	1.12	1.18	1.22	1.06	1.16	1.17
8. Soyabean						
Area harvested(1.000 ha)	8.05	11.40	21.97	26.01	29.96	24.21
Production (1.000 tons)	6.77	10.13	20.27	27.99	29.98	24.76
Yield rate(tons/ha)	0.84	0.89	0.92	1.08	1.00	1.02

Source : North Sumatra in Figures, 1988 & 1989, Statistical Office of North Sumatra Province

Table 2-11 : AREA HARVESTED, PRODUCTION AND YIELD RATE OF MAJOR FOOD CROPS IN THE STUDY AREA, 1988 AND 1989

Crops	Kab. Deli Serdang		Kab. Simalungun		Kodya. Medan	
	1988	1989	1988	1989	1988	1989
1. Paddy						
Area harvested(1.000 ha)	134.3	137.9	82.7	94.2	5.7	5.8
Production (1.000 tons)	535.2	567.2	307.1	352.5	23.2	24.1
Yield rate(tons/ha)	3.99	4.12	3.71	3.74	4.07	4.18
2. Wetland Paddy						
Area harvested(1.000 ha)	128.6	134.2	67.3	73.2	5.7	5.8
Production (1.000 tons)	523.6	559.5	276.4	308.6	23.2	24.1
Yield rate(tons/ha)	4.07	4.17	4.11	4.22	4.07	4.18
3. Dryland Paddy						
Area harvested(1.000 ha)	5.7	3.6	15.4	21.0	-	-
Production (1.000 tons)	11.6	7.7	30.7	44.0	-	-
Yield rate(tons/ha)	2.04	2.12	2.00	2.10	-	-
4. Maize						
Area harvested(1.000 ha)	8.3	9.4	30.2	38.6	0.17	0.25
Production (1.000 tons)	14.9	17.0	67.6	86.5	0.30	0.46
Yield rate(tons/ha)	1.79	1.81	2.24	2.25	1.79	1.81
5. Cassava						
Area harvested(1.000 ha)	6.6	10.9	3.6	7.0	0.27	0.43
Production (1.000 tons)	93.0	154.8	58.9	119.5	3.83	6.08
Yield rate(tons/ha)	14.07	14.22	16.42	17.05	14.13	14.17
6. Sweet Potato						
Area harvested(1.000 ha)	1.4	1.7	1.9	1.9	0.18	0.25
Production (1.000 tons)	14.8	18.7	28.8	29.8	2.03	2.69
Yield rate(tons/ha)	10.98	11.00	15.53	15.66	11.02	10.99
7. Peanut						
Area harvested(1.000 ha)	2.3	2.1	7.4	8.8	0.18	0.21
Production (1.000 tons)	2.7	2.7	8.2	9.9	0.21	0.28
Yield rate(tons/ha)	1.18	1.31	1.10	1.13	1.16	1.32
8. Soyabean						
Area harvested(1.000 ha)	1.8	2.0	4.7	3.5	0.07	0.12
Production (1.000 tons)	2.2	2.6	5.6	4.3	0.09	0.15
Yield rate(tons/ha)	1.21	1.28	1.20	1.24	1.18	1.27

Source : North Sumatra in Figures, 1988 & 1989, Statistical Office of North Sumatra Province.

Table 2-12 PLANTED AREA, PRODUCTION AND YIELD RATE OF RUBBER AND OIL PALM IN NORTH SUMATRA PROVINCE, 1988 -1989

Holders	Rubber				Oil Palm			
	Planted Area(ha)*1	Production (tons)	Yield Rate (kg/ha)	Planted Area(ha)*1	Production (tons)		Yield Rate (kg/ha)	
					MS *2	IS *3	MS *2	IS *3
	1988	1989	1988	1989	1988	1989	1988	1989
Small Holders	310,293	325,540	117,261	120,227	378	369	58,299	66,893
Private Estates	103,814	208,634	-	114,874	-	551	147,914	172,582
Estate Enterprises	107,490	112,394	99,975	100,043	930	886	333,072	330,396
Total	521,597	647,068	-	355,144	-	518	539,285	569,871

Source : North Sumatra in Figures, 1988 & 1989, Statistical Office of North Sumatra Province.

Note : *1 includes non - productive areas.

*2 MS means crude palm oil.

*3 IS means palm kernel.

Table 2-13 NUMBER OF ESTABLISHMENTS AND EMPLOYEES BY INDUSTRIAL ORIGIN
IN NORTH SUMATRA PROVINCE AND THE STUDY AREA, 1986

Industrial Origin	Number of Establishments						Number of Employees					
	Study Area			North Sumatra			Study Area			Total		
	North Sumatra	Deli Serdang	Medan	Tebing Tinggi	Total	North Sumatra	Deli Serdang	Medan	Tebing Tinggi	Total		
1 Mining & Quarrying	1,581	195	13	7	215	5,885	822	101	66	989		
2 Manufacturing Industry	30,994	4,572	5,523	296	10,391	164,861	32,864	40,939	3,581	77,384		
3 Electricity, Gas & Water Supply	2,787	498	13	6	517	8,789	763	3,659	43	4,465		
4 Construction	4,144	292	1,101	164	1,557	18,032	1,422	6,567	474	8,463		
5 Trade, Hotel & Restaurant	208,711	30,755	53,605	3,988	88,348	310,147	42,061	92,651	5,686	140,398		
6 Transport & Communication	31,984	2,926	13,194	1,288	17,408	51,639	4,564	20,795	1,590	26,949		
7 Banking & Financial Intermediaries	4,044	336	1,677	38	2,051	14,836	506	8,592	214	9,312		
8 Services	42,594	6,031	13,823	932	20,786	101,324	14,171	39,138	2,663	55,972		
Total	326,839	45,605	88,949	6,719	141,273	675,513	97,173	212,442	14,317	323,932		

Source : North Sumatra in Figures, 1989. Statistical Office of North Sumatra Province.

Table 2-14 INCOME AND EXPENDITURE OF NORTH SUMATRA
AUTONOMY GOVERNMENT, 1980/81-1988/89

(Unit : Rp Million)

Year	Income			Expenditure		
	Routine	Development	Total	Routine	Development	Total
1980/81	73,320	20,429	93,749	66,209	21,600	87,809
1981/82	93,467	16,823	110,290	83,184	20,985	104,169
1982/83	106,004	12,452	118,456	96,779	23,172	119,951
1983/84	127,085	13,554	140,639	112,955	21,210	134,165
1984/85	128,785	13,300	142,085	109,581	20,008	129,589
1985/86	169,015	14,463	183,478	147,014	26,220	173,234
1986/87	180,030	16,691	196,721	155,427	31,037	186,464
1987/88	199,140	18,935	218,075	168,853	36,348	205,201
1988/89	279,702	23,133	302,835	245,681	44,674	290,356
Average Annual Growth Rate (%)	18.22	1.57	15.79	17.81	9.51	16.12

Source : North Sumatra in Figures, 1988, Statistical
Office of North Sumatra Province.

Table 3-1 OUTLINE OF THE DPUP FLOOD CONTROL PLAN

No.	Item	Deli R. Downstream	Deli R. Upstream	Babura R.	Percut R.	Serdang R. (Belumai R.)	Batugingging R.	Padang R.
1. Year of Planning		1985	1988	1988	1988	1983	1983	1988
2. Location		River mouth to Babura R.	Babura R. to Titi Kuning	Deli R. to Selayang 2	River mouth to Sidoorejo	River mouth to national road	Serdang R. to national road	Manggadua to national road
3. Length (km)		28	12	14	20	9 (13)**	10	15
4. Return Period (year)		10	10	10	10	10	10	20
5. Design Discharge (m ³ /s)		455(408)*	267	139	379	630 (260)**	410	1450
6. Standard Cross Section of River Channel								
(1) Section	Double and Single	Single	Single	Double and Single	Double(Single)**	Single	Single	Double
(2) Width (m)	38 to 63	27 to 36	21 to 33	25 to 57	65(44)**	55	55	150
(3) Depth (m)	6	4 to 7	4 to 8	6 to 10	5	5	5	5 to 6
(4) Slope of Dike	1 : 1.5	1 : 1.5	1 : 1.5	1 : 1 (Protection with concrete block)	1 : 2 (Sandy Soil)	1 : 2 (Sandy Soil)	1 : 1	1 : 1
(5) Crown Width of Dike (m)	3	4	4	3	3	3	3	4
(6) Freeboard (m)	0.6	0.6	0.6	0.6	0.6	0.6	0.6	0.6
7. Roughness Coefficient: n	0.03	0.03	0.03	0.03 for low channel 0.035 for high channel	0.025	0.025	0.025	0.025
8. Design Bed Slope	1/2830 to 1/890	1/2400 to 1/280	1/1210 to 1/380	1/2460 to 1/610	1/1630 to 1/1080	1/2070	1/2070	1/1020
9. Schedule of Construction	Start in 1989	1995 to 2007	1995 to 2007	1995 to 2007	Not fixed	Not fixed	Not fixed	Not fixed
10. Financial Source for Construction	OECF and ADB	Foreign loan	Foreign loan	Foreign loan	Foreign loan	Foreign loan	Foreign loan	Foreign loan

Note

* : The design discharge of the upstream of confluence with Sikambing R. is 408 m³/s, and that of the down stream is 455 m³/s.

** : The figure in parenthesis shows the one for Belumai R.

Table 3-2 CALCULATION RESULTS OF PROBABLE RAINFALL

(Unit : mm/day)

Year	Belawan	Deli	Percut	Serdang	Ular	Belutu	Padang
2	68.9	66.3	67.9	60.4	86.6	59.6	79.9
3	78.6	76.0	77.2	66.7	101.7	67.5	92.2
5	89.4	86.8	87.6	73.8	118.6	76.3	105.9
8	98.7	96.1	96.5	79.9	133.2	83.9	117.7
10	103.0	100.4	100.6	82.7	139.9	87.4	123.2
20	116.0	113.5	113.1	91.3	160.2	98.0	139.7
30	123.5	121.0	120.3	96.2	172.0	104.1	149.2
50	132.8	130.4	129.2	102.4	186.6	111.8	161.1
60	136.2	133.7	132.4	104.6	191.8	114.5	165.4
80	141.4	139.0	137.5	108.0	200.0	118.7	172.0
100	145.4	143.0	141.4	110.7	206.4	122.0	177.2
150	152.8	150.4	148.4	115.5	217.9	128.0	186.5
200	158.0	155.6	153.4	118.9	226.0	132.3	193.2

Table 3-3 PROBABLE FLOOD DISCHARGES

River/ Reference Point	Catchment Area (km ²)	Probable Flood Discharge (m ³ /s)						
		2-yr.	5-yr.	10-yr.	20-yr.	30-yr.	50-yr.	100-yr.
1. Belawan								
- Lalang	254	250	340	410	470	510	550	610
2. Deli								
- Titi Kuning	180	160	220	260	300	320	340	380
- Helvetia*	341	280	390	460	530	570	620	690
3. Percut								
- Tembakau	171	140	190	230	260	280	300	340
4. Serdang								
- Baru	671	470	590	680	750	800	850	940
Batugingging								
- Gang Melaya	343	280	340	390	420	450	480	520
Belumai								
- Buntu	262	190	230	270	290	310	330	360
5. Ular								
- Pulau Tagor	1013	430	600	710	820	890	970	1070
6. Belutu								
- Bakaran Batu	243	110	140	160	180	190	210	230
- Sei Rampah*	423	180	220	260	290	310	340	370
7 . Padang								
- Brohol	759	390	530	620	720	770	840	940

* Sub-Reference Point

Table 3-4 APPRAISED VALUE OF ASSETS

1. Buildings and Household Effects

(Unit: Thousand Rp.)

Kind	Building	Household Effects
Farmhouse	3,000	1,500
Residential	5,000	3,000
Shop	8,000	11,000
Office	70,000	75,000
School	40,000	10,000
Hospital	30,000	12,000
Factory	30,000	25,000
Mosque (or Church)	15,000	4,000

2. Agricultural Crops

Crops	ton/ha	Rp/ton (Mill.)	Rp/ha (Mill.)
Paddy (Rainfed)	4.1	0.407	1.669
Paddy (Tidal Irrig.)	2.0	0.407	0.814
Rubber	1.0	0.143	0.143
Coconut	1.0	0.102	0.102
Palm oil	0.86	0.687	0.591
Palm kernel	0.16	0.402	0.064
Cacao	0.5	2.062	1.031
Tobacco	0.5	4.300	2.150
Maize	1.8	0.185	0.333
Cassava	14.1	0.084	1.184
Potato	11.0	0.106	1.165
Peanut	1.2	0.720	0.864
Soyabean	1.2	0.688	0.826
Green Pea	0.8	0.989	0.791

Table 3-5 DAMAGE RATE TO SUBMERGED ASSETS

(1) Buildings

Water Level Above Floor (meter)		Damage Rate
0.00 - 0.49		0.037
0.50 - 0.99		0.064
1.00 - 1.49		0.099
1.50 - 1.99		0.137
2.00 - 2.49		0.179

(2) Household Effects

Kind of Building	Water Level Above Floor (meter)						
	0 - 0.5	0.5 - 1.0	1.0 - 1.5	1.5 - 2.0	2.0 - 2.5	2.5 - 3.0	over 3.0
Farm house	0.448	0.621	0.656	0.676	0.690	0.690	0.690
Residential	0.407	0.600	0.642	0.622	0.683	0.690	0.690
Shop	0.251	0.448	0.543	0.561	0.579	0.597	0.597
Office, etc.(1)	0.411	0.575	0.613	0.626	0.632	0.632	0.632

(1 : Office, school, hospital, factory, mosque, church and kiosk.)

(3) Paddy

Submergence	Tillering Stage	Boiling Stage	Heading Stage		Ripening Stage	Unit : %			
			Depth	Duration (day)	0 - 70 th day (0 - 54 %)	71 - 87 th (55 - 67 %)	88 - 100 th (68 - 77 %)	101 - 130 th (78 - 100 %)	
Case (A)	1 to 2	10			70		30		5
Over	3 to 4	20			80		80		20
Plant	5 to 6	30			85		90		30
Height	Over 7	35			95		100		30
Case (B)	1 to 2	6			40		10		4
75 % of	3 to 4	9			46		23		15
Plant	5 to 6	14			49		26		23
Height	Over 7	16			55		30		23
Case (B)	1 to 2	4			37		8		2
50 % of	3 to 4	9			42		22		4
Plant	5 to 6	13			45		25		6
Height	Over 7	15			50		28		6

(4) Tree Crops

Inundation Depth (m)	Damage Rate (%)
0.00 - 0.49	5
0.50 - 0.99	10
1.00 - 1.49	20
1.50 - 1.99	40
2.00 - 2.49	80
over 2.50	100

(5) Upland Crops

Inundation Depth (m)	Damage Rate (%)
Depth (m)	Duration (days)
0.00 - 0.49	3 - 5
0.50 - 0.99	4 - 6
1.00 - 1.49	5 - 7
1.50 - 1.99	5 - 7
2.00 - 2.49	over 7

Table 3-6(1/2) FLOOD DAMAGE BY VARIOUS FLOODS

*** Belawan River ***

(Unit : Mill. Rp.)

RETURN PERIOD (Year)	Wet Paddy	Farm Land	Palm Oil	Rubber	Cacao	Other Plantation	House	Factory	School	Office	Hospital	Mosque/ Church	Public Works	TOTAL
100	130.60	410.85	2.81	0.00	0.00	114.70	8,006.15	34.83	185.98	175.41	17.82	71.77	2,887.27	12,038.18
50	130.60	390.13	2.36	0.00	0.00	94.08	6,690.40	23.22	127.68	154.02	0.00	56.79	2,397.72	10,066.99
30	130.60	390.13	2.36	0.00	0.00	91.50	6,486.47	23.22	127.68	154.02	0.00	56.79	2,328.38	9,791.15
20	110.15	339.22	1.77	0.00	0.00	78.61	6,067.15	0.00	119.70	102.68	0.00	56.79	2,157.75	9,033.83
10	110.15	257.22	0.89	0.00	0.00	65.73	4,288.10	0.00	79.80	102.68	0.00	41.02	1,533.94	6,479.53

*** Deli River ***

(Unit : Mill. Rp.)

RETURN PERIOD (Year)	Wet Paddy	Farm Land	Palm Oil	Rubber	Cacao	Other Plantation	House	Factory	School	Office	Hospital	Mosque/ Church	Public Works	TOTAL
100	12.52	109.22	0.15	0.04	1.29	10.31	58,152.36	2,175.16	842.78	1,287.10	0.00	316.76	21,343.21	84,250.89
50	10.85	106.26	0.15	0.04	1.29	10.31	56,229.80	1,943.98	813.44	1,211.82	0.00	307.86	20,572.35	81,208.14
30	10.85	106.26	0.15	0.04	1.29	10.31	52,640.54	1,853.38	774.78	1,190.43	0.00	291.17	19,295.10	76,174.30
20	10.85	106.26	0.15	0.04	1.29	9.02	49,588.94	1,716.61	683.32	1,036.41	0.00	281.71	18,124.37	71,558.96
10	10.85	106.26	0.15	0.04	0.00	7.73	42,560.10	1,525.01	543.22	862.61	0.00	236.72	15,547.40	61,400.08
5	10.85	81.99	0.15	0.04	0.00	7.73	41,367.42	1,412.13	531.56	834.27	0.00	231.35	15,088.09	59,565.57
2	10.85	72.52	0.15	0.04	1.29	7.73	30,239.15	951.15	413.72	586.13	0.00	166.69	11,001.32	43,450.73

*** Percut River ***

(Unit : Mill. Rp.)

RETURN PERIOD (Year)	Wet Paddy	Farm Land	Palm Oil	Rubber	Cacao	Other Plantation	House	Factory	School	Office	Hospital	Mosque/ Church	Public Works	TOTAL
100	338.81	51.80	0.44	0.00	5.16	69.59	11,530.80	46.44	143.02	0.00	0.00	82.95	4,013.09	16,282.09
50	338.81	51.80	0.44	0.00	2.58	59.28	10,475.10	46.44	143.02	0.00	0.00	82.95	3,654.15	14,854.57
30	325.46	41.44	0.44	0.00	2.58	51.55	10,205.83	46.44	139.34	0.00	0.00	80.06	3,560.36	14,453.49
20	313.35	31.08	0.30	0.00	2.58	51.55	9,937.32	11.61	139.34	0.00	0.00	78.61	3,456.74	14,022.47
10	289.99	31.08	0.30	0.00	1.29	48.97	7,409.50	11.61	131.36	0.00	0.00	59.68	2,588.13	10,571.91
5	284.56	31.08	0.30	0.00	1.29	45.11	6,705.87	11.61	103.74	0.00	0.00	55.08	2,337.94	9,576.58

Table 3-6(2/2) FLOOD DAMAGE BY VARIOUS FLOODS

*** Serdang River ***

(Unit : Mill. Rp.)

RETURN PERIOD (Year)	Wet Paddy	Farm Land	Palm Oil	Rubber	Cacao	Other Plantation	House	Factory	School	Office	Hospital	Mosque/ Church	Public Works	TOTAL Structure
100	1,224.63	71.63	8.72	0.11	0.00	0.00	14,656.69	447.91	259.62	372.21	0.00	91.09	5,381.35	22,513.95
50	1,151.19	62.16	8.72	0.11	0.00	0.00	13,884.61	402.61	248.58	372.21	0.00	88.20	5,098.71	21,317.09
30	1,121.15	62.16	8.72	0.11	0.00	0.00	13,400.19	348.25	230.18	329.43	0.00	83.86	4,893.25	20,477.29
20	1,091.94	62.16	8.72	0.11	0.00	0.00	13,195.63	343.20	230.18	329.43	0.00	83.86	4,821.98	20,167.21
10	1,072.33	51.80	8.42	0.11	0.00	0.00	12,724.51	331.59	206.24	329.43	0.00	83.86	4,649.71	19,458.00
5	1,040.62	41.44	7.83	0.07	0.00	0.00	11,835.18	331.59	174.94	329.43	0.00	77.82	4,334.64	18,173.56
2	890.83	31.08	7.39	0.00	0.00	0.00	10,283.63	238.71	166.96	329.43	0.00	62.04	3,767.46	15,777.53

*** Belutu River ***

(Unit : Mill. Rp.)

RETURN PERIOD (Year)	Wet Paddy	Farm Land	Palm Oil	Rubber	Cacao	Other Plantation	House	Factory	School	Office	Hospital	Mosque/ Church	Public Works	TOTAL Structure
100	629.63	236.50	4.43	0.00	2.58	0.00	2,848.86	13.05	99.10	56.55	0.00	51.15	1,043.36	4,985.22
50	602.09	236.50	4.14	0.00	2.58	0.00	2,795.60	12.45	93.40	56.55	0.00	51.15	1,023.45	4,878.91
30	553.27	195.95	3.55	0.00	2.58	0.00	2,619.60	12.45	82.00	56.55	0.00	49.00	958.66	4,533.61
20	545.35	175.23	3.40	0.00	2.58	0.00	2,578.76	12.45	82.00	56.55	0.00	49.00	944.78	4,450.09
10	514.89	154.51	3.10	0.00	2.58	0.00	1,938.32	12.45	64.00	43.70	0.00	34.75	711.69	3,479.99
5	486.10	144.15	2.96	0.00	2.58	0.00	1,891.52	12.45	64.00	43.70	0.00	32.60	695.05	3,375.10
2	461.06	51.80	2.36	0.00	2.58	0.00	1,657.82	12.45	58.30	38.55	0.00	28.45	610.49	2,923.87

*** Padang River ***

(Unit : Mill. Rp.)

RETURN PERIOD (Year)	Wet Paddy	Farm Land	Palm Oil	Rubber	Cacao	Other Plantation	House	Factory	School	Office	Hospital	Mosque/ Church	Public Works	TOTAL Structure
100	1,305.99	201.28	4.58	1.14	0.00	0.00	15,086.15	594.06	520.04	350.82	21.75	160.70	5,689.40	23,935.91
50	1,291.81	201.28	4.43	1.14	0.00	0.00	13,336.49	375.48	461.74	248.14	17.82	142.83	4,958.05	21,039.21
30	1,260.51	201.28	4.43	1.14	0.00	0.00	12,868.31	375.48	454.38	248.14	17.82	141.39	4,795.87	20,368.75
20	1,177.48	190.92	4.43	1.14	0.00	0.00	12,561.94	375.48	444.68	248.14	17.82	141.39	4,688.41	19,851.83
10	1,084.85	180.56	4.43	1.14	0.00	0.00	10,175.78	308.37	310.12	102.68	8.91	102.11	3,742.71	16,021.67
5	950.50	161.62	4.43	1.14	0.00	0.00	9,041.00	250.32	263.48	102.68	8.91	86.60	3,316.02	14,186.69
2	886.66	161.62	4.28	0.82	0.00	0.00	8,462.89	238.71	251.82	102.68	8.91	78.35	3,108.74	13,305.47

Table 3-7 PRESENT WATER SUPPLY SYSTEM UNDER PDAM MEDAN

Code No.	Paying Consumers	Number	Consumption (m3/d)
1.	Mosque, Church, etc., and Public Tap	918	4,111
2-a.	House Connection	84,431	97,418
2-b.	Government Connection	888	6,910
3-a.	Small Commercial Establishment	4,259	6,125
3-b.	Big Commercial Establishment	6,413	11,203
4-a.	Small Industry	34	161
4-b.	Big Industry	102	893
5.	Special Use (Fire Tap, Others)	36	356
Total		97,081	127,177

Table 3-8 WATER TARIFF COLLECTION OF PDAM MEDAN IN MAY 1990

Item	Number of Units	Consumption (m3/day)	Ratio (%)
Domestic Water	84,616	95,058 (1,100)	75
Non-Domestic Water	11,696	32,836 (380)	25
- Institutional	888	6,710 (78)	
- Commercial	10,672	16,769 (194)	
- Industrial	136	1,020 (12)	
- Others	-	8,337 (96)	
Total	96,312	127,894 (1,480)	100

Note: Amounts in parentheses are in 1/s.

Table 3-9 POSSIBLE DAM SITES AND THEIR FEATURES

Possible Dam Site	River System/ River	Location	Catchment Area (km2)	Distance from Estuary (km)	Road Distance from Medan/ Tebing Tinggi (km)	Present Condition		
						Topography	Land Use	Access
Tembengan	Belawan/Belawan	N3°27'E98°33'	76	60	25, Medan	Wide gorge	Paddy	No Good
Namobatang	Deli/Petani	N3°21'E98°37'	93	58	30, Medan	Wide gorge	Paddy	Good
Lausimeme	Percut/Seruai	N3°21'E98°39'	105	50	32, Medan	Narrow gorge Hilly land	Forest Dry field	No Good
Beranti	Serdang/Belumai	N3°21'E98°43'	159	52	33, Medan	Narrow gorge Hilly land	Forest Dry field	No Good
Buaya	Ular/Buaya	N3°21'E98°52'	428	44	60, Medan 45, T.Tinggi	Wide gorge	Paddy	Good
Karai	Ular/Karai	N3°21'E98°54'	500	44	65, Medan 38, T.Tinggi	Wide gorge	Paddy	No Good
Sibakudu	Belutu/Belutu	N3°14'E98°53'	64	60	35, T.Tinggi	Wide gorge	Paddy	No Good
Sampanan	Padang/Padang	N3°12'E99°03'	370	48	24, T.Tinggi	Wide gorge	Plantation	Fair

Table 3-10 TECHNICAL AND ECONOMICAL COMPARISON OF PLANNED DAMS

River System	Damsite Area	1) Catchment Possible Reservoir Storage Capacity	2) Topographically Possible Capacity	3) Sedimentation Possibility	4)-2)-3)	5) Annually Secured Effective Storage Capacity	6)-3)+5)	7) Required Total Reservoir Height	8) Impounding Surface Area Required For 6)	9) Quantity of Dam Body Required For 6)	10) Estimated Construction Cost	11)-10)/5) Construction Cost/Annually
Belawan	Tembangan	76	25.0	2.3	22.7	12.5	14.8	33	1.4	953	76.2	6.1
Deli	Namobatang	93	15.0	0.9	14.1	14.1	15.0	41	0.8	672	53.8	3.8
Percut	Lausimene	105	60.0	1.1	58.9	19.5	20.6	61	1.1	750	60.0	3.1
Serdang	Beranti	159	15.0	8.0	7.0	7.0	15.0	38	0.9	668	53.4	7.6
Ular	Buaya	428	48.0	21.4	26.6	26.6	48.0	19	4.1	296	23.8	0.9
Ular	Karai	500	85.0	25.0	60.0	60.0	85.0	30	8.0	360	28.8	0.5
Belutu	Sibakudu	64	45.0	1.3	43.7	12.4	13.7	18	2.3	189	15.1	1.2
Padang	Sampanan	370	31.0	18.5	12.5	12.5	31.0	34	2.4	382	47.4	3.8

Note : *1 Accumulated sedimentation volume for a period of 100 years.(Refer to "Section 3.3.2")

*2 On condition that each reservoir is planned to be annually recovered to full.

*3 Quantity estimated considering a dam type as rock-fill.

Table 4-1 ECONOMIC COMPARISON OF FLOOD MITIGATION EFFECT OF STRUCTURES

River System & Flood Mitigation Structure	Catchment Area (km ²)	Possible Flood Control Storage Capacity * (MCM)	Required Construction Cost (million RP.)	Reference Point & Catchment Area (km ²)	Flood Mitigation Effect at R.P. W/O (m ³ /S)	Required Construction Cost for Unit Flood Mitigation Effect (million Rp./m ³ /S)
1. Belawan River(50-Yr.)						
Tembangan Dam	76	1.8	30,000	Lalang 254	550	410
Sembahé Baru Retarding Basin	155	5.1	116,300		550	150
2. Deli River(100-Yr.)						
Namobatang Dam	93	2.5	23,339	Helvetica 341	690	580
3. Percut River(100-Yr.)						
Lausimene Dam	105	2.8	21,182	Tembakau 171	340	180
4. Serdang River(50-Yr.)						
Berantai Dam	159	3.3	38,800	Baru 671	850	690
Punden Retarding Basin	262	1.6	47,800		850	670
5. Ular River(50-Yr.)						
Buaya Dam	428	16.7	20,790	Pulau Togor 1,023	970	640
Kara i Dam	500	19.5	21,600		970	590
6. Belutu River(50-Yr.)						
Sibakudu Dam	64	1.5	4,000	Sei Rampah 423	340	310
Bakaran Batu Retarding Basin	243	5.5	69,700		340	170
7. Padang River(50-Yr.)						
Sampaanan Dam	370	12.4	45,000	Brohol 759	840	500
Tebing Tinggi Retarding Basin	414	5.0	91,000		840	590

Note : * : This value is defined from flood regulation analysis by applying max. 80% reduction of the standard Project Flood or possible storage capacity under its topographic or landuse condition.

Table 4-2 POPULATION PROJECTION , 1995-2010

Region	Population ('000) 1995			Annual Growth Rate (%) 1990-1995		
	C-1	C-2	C-3	C-1	C-2	C-3
Study A.	4,070	4,082	4,048	2.32	2.38	2.21
D+M	3,753	3,761	3,730	2.40	2.44	2.27
Deli S.	1,818	1,821	1,806	2.55	2.59	2.42
Medan	1,935	1,939	1,923	2.26	2.30	2.13
Tebing T.	130	132	131	2.19	2.40	2.23
Simal.	186	189	188	0.93	1.23	1.06
Region	2000			1995-2000		
	C-1	C-2	C-3	C-1	C-2	C-3
Study A.	4,556	4,591	4,471	2.28	2.38	2.01
D+M	4,218	4,242	4,131	2.37	2.44	2.07
Deli S.	2,058	2,069	2,016	2.52	2.59	2.22
Medan	2,160	2,172	2,116	2.22	2.30	1.93
Tebing T.	144	148	144	2.05	2.39	2.02
Simal.	193	201	196	0.73	1.22	0.85
Region	2005			2000-2005		
	C-1	C-2	C-3	C-1	C-2	C-3
Study A.	5,092	5,165	4,892	2.25	2.38	1.81
D+M	4,735	4,784	4,531	2.34	2.44	1.87
Deli S.	2,327	2,351	2,227	2.48	2.58	2.01
Medan	2,408	2,433	2,304	2.19	2.29	1.72
Tebing T.	159	167	158	1.91	2.39	1.82
Simal.	199	214	202	0.53	1.22	0.65
Region	2010			2005-2010		
	C-1	C-2	C-3	C-1	C-2	C-3
Study A.	5,681	5,811	5,300	2.21	2.38	1.62
D+M	5,306	5,396	4,922	2.31	2.44	1.67
Deli S.	2,626	2,671	2,436	2.45	2.58	1.81
Medan	2,680	2,725	2,485	2.16	2.29	1.52
Tebing T.	173	188	171	1.77	2.39	1.62
Simal.	202	227	207	0.33	1.22	0.45

Note : Study A. : Study Area
D+M : Kab. Deli Serdang and Kodya. Medan
Deli S. : Kab. Deli Serdang
Medan : Kodya. Medan
Tebing T. : Kodya. Tebing Tinggi
Simal. : Seven Kecamatans in Kab. Simalungun, Silima Kuta,
Purba, Raya, Dolok Silau, Silau Kahean,
Raya Kahean and Batu Nanggar.

C-1, C-2 and C-3 mean Cases 1, 2 and 3, respectively.

Table 4-3 ANNUAL DISBURSEMENT SCHEDULE FOR MASTER PLAN

(Unit : Million Rp)

Project	Quantity	Unit	Total	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000
1. Belawan River Improvement (50-Yr)	21.7	km	31,261										
2. Deli-Percut River System (100-Yr)			403,130										
(a) Deli River Improvement	37.4	km	118,608	3,794	11,665	22,701	14,831	22,434	22,434	14,176	17,571	12,300	
(b) Medan Floodway	3.8	km	30,035	1,058	2,730	8,315	6,644	6,644	6,644	6,644	6,644	6,573	
(c) Namobatang Multipurpose Dam	63.5%	site	63,554										
(d) Percut River Improvement	28.0	km	47,589	1,436	5,770	16,351	12,016	12,016	12,016	12,016	12,016	5,727	
(e) Lausimene Multipurpose Dam	1	site	141,344	5,564	6,798	33,171	31,937	31,937	31,937	31,937	31,937	3,395	
3. Serdang River (50-Yr)			153,850										
(a) Serdang River Improvement	25.4	km	114,675										
(b) Belumai Aqueduct	5.5	km	39,175										
4. Utar River (50-Yr)/Karai Flood Control Dam	1	site	16,076										
5. Belutu River Improvement (50-Yr)	32.7	km	56,401										
6. Padang River Improvement (50-Yr)	29.5	km	100,544										
Total			761,262										
Project				2001	2002	2003	2004	2005	2006	2007	2008	2009	2010
1. Belawan River Improvement (50-Yr)													
2. Deli-Percut River System (100-Yr)													
(a) Deli River Improvement													
(b) Medan Floodway													
(c) Namobatang Multipurpose Dam													
(d) Percut River Improvement													
(e) Lausimene Multipurpose Dam													
3. Serdang River (50-Yr)													
(a) Serdang River Improvement													
(b) Belumai Aqueduct													
4. Utar River (50-Yr)/Karai Flood Control Dam													
5. Belutu River Improvement (50-Yr)													
6. Padang River Improvement (50-Yr)													
Total			30,829	42,584	49,059	39,582	35,546	35,382	39,285	21,513	21,513	21,513	

Note : Project costs exclude price escalation.

Table 4-4(1/4) ANNUAL FLOW OF ECONOMIC COST AND BENEFIT FOR FLOOD CONTROL AND WATER SUPPLY

** Flood Control Project **
 1.1 Belawan River(10-Year) 1.2 Belawan River(20-Year) 1.3 Belawan River(30-Year) 1.4 Belawan River(50-Year) 2.1 Deli-Percut River System(10-Year) 2.2 Deli-Percut River System(20-Year) 2.3 Deli-Percut River System(30-Year) 2.3 Deli-Percut River System(50-Year) 2.5 Deli-Percut River System(100-Year)
 Unit : Million Rp

Year	Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost											
	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit								
1	642	0	642	0	805	0	805	0	911	0	911	0	1,017	0	1,017	0	5,128	0	5,128	0	6,241	0	6,241	0	8,064	0	8,064	0	8,527	0	8,527	0	8,448	0	8,448	0
2	1,473	0	1,473	0	2,355	0	2,355	0	2,933	0	2,933	0	3,523	0	3,523	0	14,279	0	14,279	0	17,664	0	17,664	0	19,020	0	19,020	0	20,047	0	20,047	0	19,673	0	19,673	0
3	5,230	0	5,230	0	6,553	0	6,553	0	7,418	0	7,418	0	8,282	0	8,282	0	31,069	0	31,069	0	43,082	0	43,082	0	44,031	0	44,031	0	47,356	0	47,356	0	45,980	0	45,980	0
4	5,230	42	5,272	108	6,553	53	6,606	237	7,418	60	7,478	290	8,282	67	8,349	334	21,919	233	22,152	8,137	31,659	322	31,981	10,304	33,075	327	33,402	10,443	35,835	352	36,187	10,943	34,755	330	36,085	9,897
5	5,230	85	5,315	216	6,553	106	6,659	475	7,418	119	7,537	579	8,282	133	8,415	667	29,057	397	29,454	13,878	38,798	559	39,357	17,876	40,212	573	40,785	18,288	42,974	619	43,593	19,223	41,892	579	42,471	17,378
6	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	18,327	775	19,102	27,076	14,223	1,053	15,276	33,650	14,357	1,100	15,457	35,097	14,402	1,173	15,575	36,453	16,628	1,101	17,729	33,081
7	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	11,190	912	12,102	31,876	7,084	1,159	8,243	37,052	7,220	1,206	8,426	38,503	7,264	1,280	8,544	39,781	10,686	1,220	11,906	36,660
8	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	4,044	1,297	5,341	38,960	
9	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	4,044	1,326	5,370	39,831
10	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	4,044	1,335	5,399	40,701
11	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	4,044	1,384	5,428	41,572
12	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	4,044	1,413	5,422	42,442
13	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
14	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
15	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
16	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
17	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
18	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
19	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
20	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,001	0	996	996	34,807	0	1,212	1,212	38,746	0	1,260	1,260	40,215	0	1,334	1,334	41,459	0	1,413	1,413	42,442
21	0	127	127	324	0	159	159	712	0	179	179	869	0	200	200	1,																				

Table 4-4(2/4) ANNUAL FLOW OF ECONOMIC COST AND BENEFIT FOR FLOOD CONTROL AND WATER SUPPLY

** Flood Control Project **										Unit : Million Rp																			
3.1 Serdang River(10-Year)				3.2 Serdang River(20-Year)				3.3 Serdang River(30-Year)				3.4 Serdang River(50-Year)				4.1 Ular River(20-Year)				4.2 Ular River(30-Year)									
Year	Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost							
	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit	Const.	OMR	Total	Economic Benefit					
1	2,711	0	2,711	0	2,954	0	2,954	0	3,128	0	3,128	0	3,336	0	3,336	0	178	0	178	0	1,306	0	1,306	0	1,393	0	1,393	0	1
2	11,347	0	11,347	0	11,669	0	11,669	0	11,931	0	11,931	0	12,299	0	12,299	0	178	0	178	0	1,883	0	1,883	0	2,009	0	2,009	0	2
3	21,892	0	21,892	0	23,154	0	23,154	0	24,100	0	24,100	0	25,270	0	25,270	0	1,444	0	1,444	0	3,663	0	3,663	0	3,907	0	3,907	0	3
4	13,256	156	13,412	3,191	14,439	167	14,606	3,408	15,298	174	15,472	3,461	16,305	183	16,489	3,498	1,444	12	1,456	153	3,663	26	3,689	360	3,907	28	3,935	507	4
5	13,256	251	13,507	5,123	14,439	270	14,709	5,533	15,298	285	15,583	5,658	16,305	302	16,608	5,755	1,444	23	1,467	307	3,663	53	3,716	720	3,907	56	3,963	1,013	5
6	13,256	345	13,601	7,055	14,439	374	14,813	7,658	15,298	396	15,694	7,854	16,306	420	16,726	8,013	0	35	35	460	0	79	79	1,080	0	84	84	1,520	6
7	13,256	440	13,696	8,987	14,439	478	14,917	9,784	15,298	506	15,804	10,051	16,306	539	16,845	10,270	0	35	35	460	0	79	79	1,080	0	84	84	1,520	7
8	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	8
9	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	9
10	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	10
11	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	11
12	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	12
13	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	13
14	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	14
15	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	15
16	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	16
17	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	17
18	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	18
19	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	19
20	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	20
21	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	21
22	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	22
23	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	23
24	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	24
25	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460	0	79	79	1,080	0	84	84	1,520	25
26	0	534	534	10,919	0	582	582	11,909	0	617	617	12,248	0	657	657	12,527	0	35	35	460</td									

Table 4-4(3/4) ANNUAL FLOW OF ECONOMIC COST AND BENEFIT FOR FLOOD CONTROL AND WATER SUPPLY

** Flood Control Project **																Unit : Million Rp																					
5.1 Belutu River(10-Year)				5.2 Belutu River(20-Year)				5.3 Belutu River(30-Year)				5.4 Belutu River(50-Year)				6.1 Padang River(10-Year)				6.2 Padang River(20-Year)				6.3 Padang River(30-Year)				6.4 Padang River(50-Year)									
Year	Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost									
	Const.	OHR	Total	Economic	Benefit		Const.	OHR	Total	Economic	Benefit		Const.	OHR	Total	Economic	Benefit		Const.	OHR	Total	Economic	Benefit		Const.	OHR	Total	Economic	Benefit		Const.	OHR	Total	Economic	Benefit	Year	
1	1,415	0	1,415	0	1,519	0	1,519	0	9,243	0	9,243	0	9,348	0	9,348	0	1,693	0	1,693	0	2,409	0	2,409	0	2,840	0	2,840	0	3,082	0	3,082	0	3,386	0	3,386	0	1
2	9,070	0	9,070	0	9,174	0	9,174	0	11,751	0	11,751	0	11,751	0	11,751	0	7,915	0	7,915	0	8,346	0	8,346	0	8,588	0	8,588	0	8,892	0	8,892	0	2				
3	6,912	0	6,912	0	7,415	0	7,415	0	7,751	0	7,751	0	8,267	0	8,267	0	11,751	0	11,751	0	11,549	0	11,549	0	12,540	0	12,540	0	11,808	0	11,808	0	3				
4	6,912	56	6,968	404	7,415	60	7,475	443	7,751	62	7,813	458	8,267	67	8,334	471	11,751	95	11,846	1,792	11,751	190	11,941	3,584	11,549	186	11,735	3,286	12,540	202	12,742	3,398	11,808	190	11,993	2,991	5
5	6,912	112	7,024	808	7,415	120	7,535	887	7,751	125	7,876	917	8,267	133	8,400	942	11,751	284	12,035	5,377	11,549	280	11,829	4,929	12,540	304	12,844	5,097	11,808	285	12,093	4,487	6				
6	6,912	167	7,079	1,211	7,415	179	7,594	1,330	7,751	187	7,938	1,375	8,267	200	8,467	1,412	11,751	379	12,130	7,169	11,549	373	11,922	6,571	12,540	405	12,945	6,795	11,808	381	12,189	5,982	7				
7	6,912	223	7,135	1,615	7,415	239	7,654	1,774	7,751	250	8,001	1,834	8,267	266	8,533	1,883	11,751	0	474	474	8,961	0	466	12,015	8,214	12,540	506	13,046	8,494	11,808	476	12,284	7,478	8			
8	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	9				
9	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	10				
10	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	11				
11	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	12				
12	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	13				
13	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	14				
14	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	15				
15	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	16				
16	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	17				
17	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	18				
18	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	19				
19	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	20				
20	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961	0	559	559	9,857	0	607	607	10,193	0	666	666	10,469	21				
21	0	279	279	2,019	0	299	299	2,217	0	312	312	2,292	0	333	333	2,354	0	474	474	8,961</																	

**Table 4-4(4/4) ANNUAL FLOW OF ECONOMIC COST AND BENEFIT
FOR FLOOD CONTROL AND WATER SUPPLY**

** Water Supply Project **				7.1 Lausimeme Dam				7.2 Namobatang Dam				7.3 Belumai Aqueduct				Unit: Million Rp				
Year	Economic Cost			Economic Cost			Economic Cost			Economic Cost			Economic Cost			Const.	OMR	Total	Economic Benefit	
	Const.	OMR	Total	Const.	OMR	Total	Const.	OMR	Total	Const.	OMR	Total	Const.	OMR	Total					
1	3,629	0	3,629	0	2,329	0	2,329	0	1,396	0	1,396	0	1,396	0	1,396	0	1,396	0	0	
2	4,550	0	4,550	0	3,068	0	3,068	0	1,836	0	1,836	0	1,836	0	1,836	0	1,836	0	0	
3	28,216	0	28,216	0	10,126	0	10,126	0	6,847	0	6,847	0	6,847	0	6,847	0	6,847	0	0	
4	27,295	0	27,295	0	9,387	0	9,387	0	6,847	0	6,847	0	6,847	0	6,847	0	6,847	0	0	
5	27,295	0	27,295	0	9,387	0	9,387	0	6,847	0	6,847	0	6,847	0	6,847	0	6,847	0	0	
6	27,295	0	27,295	0	9,387	0	9,387	0	6,847	0	6,847	0	6,847	0	6,847	0	6,847	0	0	
7	0	890	890	8,229	0	294	294	4,449	0	829	829	5,783	0	829	829	5,783	0	829	829	5,783
8	0	890	890	8,229	0	294	294	4,449	0	829	829	5,783	0	829	829	5,783	0	829	829	5,783
9	0	890	890	8,229	0	294	294	4,449	0	829	829	5,783	0	829	829	5,783	0	829	829	5,783
10	0	890	890	8,229	0	294	294	4,449	0	829	829	5,783	0	829	829	5,783	0	829	829	5,783
11	0	890	890	10,502	0	294	294	5,678	0	829	829	7,381	0	829	829	7,381	0	829	829	7,381
12	0	890	890	10,502	0	294	294	5,678	0	829	829	7,381	0	829	829	7,381	0	829	829	7,381
13	0	890	890	10,502	0	294	294	5,678	0	829	829	7,381	0	829	829	7,381	0	829	829	7,381
14	0	890	890	10,502	0	294	294	5,678	0	829	829	7,381	0	829	829	7,381	0	829	829	7,381
15	0	890	890	10,502	0	294	294	5,678	0	829	829	7,381	0	829	829	7,381	0	829	829	7,381
16	0	890	890	13,403	0	294	294	7,246	0	829	829	9,420	0	829	829	9,420	0	829	829	9,420
17	0	890	890	13,403	0	294	294	7,246	0	829	829	9,420	0	829	829	9,420	0	829	829	9,420
18	0	890	890	13,403	0	294	294	7,246	0	829	829	9,420	0	829	829	9,420	0	829	829	9,420
19	0	890	890	13,403	0	294	294	7,246	0	829	829	9,420	0	829	829	9,420	0	829	829	9,420
20	0	890	890	13,403	0	294	294	7,246	0	829	829	9,420	0	829	829	9,420	0	829	829	9,420
21	0	890	890	17,107	0	294	294	9,248	0	829	829	12,022	0	829	829	12,022	0	829	829	12,022
22	0	890	890	17,107	0	294	294	9,248	0	829	829	12,022	0	829	829	12,022	0	829	829	12,022
23	0	890	890	17,107	0	294	294	9,248	0	829	829	12,022	0	829	829	12,022	0	829	829	12,022
24	0	890	890	17,107	0	294	294	9,248	0	829	829	12,022	0	829	829	12,022	0	829	829	12,022
25	0	890	890	17,107	0	294	294	9,248	0	829	829	12,022	0	829	829	12,022	0	829	829	12,022
26	0	890	890	21,833	0	294	294	11,803	0	829	829	15,344	0	829	829	15,344	0	829	829	15,344
27	0	890	890	21,833	0	294	294	11,803	0	829	829	15,344	0	829	829	15,344	0	829	829	15,344
28	0	890	890	21,833	0	294	294	11,803	0	829	829	15,344	0	829	829	15,344	0	829	829	15,344
29	0	890	890	21,833	0	294	294	11,803	0	829	829	15,344	0	829	829	15,344	0	829	829	15,344
30	0	890	890	21,833	0	294	294	11,803	0	829	829	15,344	0	829	829	15,344	0	829	829	15,344
31	0	890	890	27,865	0	294	294	15,064	0	829	829	19,583	0	829	829	19,583	0	829	829	19,583
32	0	890	890	27,865	0	294	294	15,064	0	829	829	19,583	0	829	829	19,583	0	829	829	19,583
33	0	890	890	27,865	0	294	294	15,064	0	829	829	19,583	0	829	829	19,583	0	829	829	19,583
34	0	890	890	27,865	0	294	294	15,064	0	829	829	19,583	0	829	829	19,583	0	829	829	19,583
35	0	890	890	27,865	0	294	294	15,064	0	829	829	19,583	0	829	829	19,583	0	829	829	19,583
36	0	890	890	35,563	0	294	294	19,226	0	829	829	24,993	0	829	829	24,993	0	829	829	24,993
37	0	890	890	35,563	0	294	294	19,226	0	829	829	24,993	0	829	829	24,993	0	829	829	24,993
38	0	890	890	35,563	0	294	294	19,226	0	829	829	24,993	0	829	829	24,993	0	829	829	24,993
39	0	890	890	35,563	0	294	294	19,226	0	829	829	24,993	0	829	829	24,993	0	829	829	24,993
40	0	890	890	35,563	0	294	294	19,226	0	829	829	24,993	0	829	829	24,993	0	829	829	24,993
41	0	890	890	45,389	0	294	294	24,538	0	829	829	31,898	0	829	829	31,898	0	829	829	31,898
42	0	890	890	45,389	0	294	294	24,538	0	829	829	31,898	0	829	829	31,898	0	829	829	31,898
43	0	890	890	45,389	0	294	294	24,538	0	829	829	31,898	0	829	829	31,898	0	829	829	31,898
44	0	890	890	45,389	0	294	294	24,538	0	829	829	31,898	0	829	829	31,898	0	829	829	31,898
45	0	890	890	45,389	0	294	294	24,538	0	829	829	31,898	0	829	829	31,898	0	829	829	31,898
46	0	890	890	57,929	0	294	294	31,318	0	829	829	40,711	0	829	829	40,711	0	829	829	40,711
47	0	890	890	57,929	0	294	294	31,318	0	829	829	40,711	0	829	829	40,711	0	829	829	40,711
48	0	890	890	57,929	0	294	294	31,318	0	829	829	40,711	0	829	829	40,711	0	829	829	40,711
49	0	890	890	57,929	0	294	294	31,318	0	829	829	40,711	0	829	829	40,711	0	829	829	40,711
50	0	890	890	57,929	0	294	294	31,318	0	829	829	40,711	0	829	829	40,711	0	829	829	40,711
51	0	890	890	73,934	0	294	294	39,970	0	829	829	51,959	0	829	829	51,959	0	829	829	51,959
52	0	890	890	73,934	0	294	294	39,970	0	829	829	51,959	0	829	829	51,959	0	829	829	51,959
53	0	890	890	73,934	0	294	294	39,970	0	829	829	51,959	0	829	829	51,959	0	829	829	51,959
54	0	890	890	73,934	0	294	294	39,970	0	829	829	51,959	0	829	829	51,959	0	829	829	51,959
55	0	890	890	73,934	0	294	294	39,970	0	829	829	51,959	0	829	829	51,959	0	829	829	51,959
56	0	890	890	94,360	0	294	294	51,013	0	829	829	66,314	0	829	829	66,314	0	829	829	66,314
57	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
58	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
59	0	0	0	0	0															

Table 4-5 RESULTS OF ECONOMIC ANALYSIS FOR FLOOD CONTROL AND WATER SUPPLY

1. Flood Control Project
(1) Belawan River

Evaluation Factor	Return Period				
	10-year	20-year	30-year	50-year	100-year
IRR (%)	-1.99	0.84	1.20	1.33	-
NPV (Million Rps.)					
Discount 12 %	(10,717)	(12,211)	(13,696)	(15,327)	-
Rate 10 %	(11,211)	(12,387)	(13,807)	(15,413)	-
8 %	(11,635)	(12,252)	(13,521)	(15,032)	-
5 %	(11,891)	(10,738)	(11,431)	(12,526)	-
1 %	(9,623)	(847)	1,228	2,299	-
B/C					
Discount 12 %	0.14	0.24	0.25	0.26	-
Rate 10 %	0.16	0.28	0.30	0.31	-
8 %	0.20	0.34	0.37	0.38	-
5 %	0.29	0.50	0.53	0.55	-
1 %	0.56	0.97	1.04	1.06	-

(2) Deli-Percut River System

Unit : Million Rp

Evaluation Factor	Return Period				
	10-year	20-year	30-year	50-year	100-year
IRR (%)	20.03	18.49	18.09	17.66	16.80
NPV (Million Rps.)					
Discount 12 %	67,920	67,711	67,602	66,425	58,036
Rate 10 %	109,255	113,639	115,135	115,214	106,081
8 %	174,687	186,394	190,498	192,658	183,656
5 %	366,572	399,779	411,714	420,220	418,216
1 %	1,169,699	1,292,353	1,337,683	1,373,560	1,464,432
B/C					
Discount 12 %	1.70	1.56	1.53	1.49	1.41
Rate 10 %	2.03	1.86	1.82	1.78	1.69
8 %	2.50	2.29	2.25	2.19	2.08
5 %	3.69	3.37	3.31	3.23	3.10
1 %	7.35	6.73	6.63	6.46	6.37

(3) Serdang River

Evaluation Factor	Return Period				
	10-year	20-year	30-year	50-year	100-year
IRR (%)	11.02	11.20	10.96	10.59	-
NPV (Million Rps.)					
Discount 12 %	(4,736)	(4,140)	(5,605)	(7,983)	-
Rate 10 %	6,249	7,886	6,622	4,306	-
8 %	24,421	27,754	26,886	24,774	-
5 %	79,742	88,170	88,686	87,475	-
1 %	316,251	346,247	353,295	356,917	-
B/C					
Discount 12 %	0.92	0.93	0.91	0.88	-
Rate 10 %	1.10	1.12	1.09	1.06	-
8 %	1.35	1.37	1.35	1.30	-
5 %	1.99	2.02	1.98	1.91	-
1 %	3.99	4.04	3.95	3.81	-

(4) Ular River

Evaluation Factor	Return Period				
	10-year	20-year	30-year	50-year	100-year
IRR (%)	-	8.79	6.54	8.92	-
NPV (Million Rps.)					
Discount 12 %	-	(812)	(4,373)	(2,712)	-
Rate 10 %	-	(388)	(3,467)	(1,195)	-
8 %	-	-	328	(1,883)	1,315
5 %	-	-	2,520	3,116	8,885
1 %	-	-	11,742	24,587	40,312
B/C					
Discount 12 %	-	-	0.75	0.57	0.75
Rate 10 %	-	-	0.89	0.68	0.90
8 %	-	-	1.09	0.84	1.11
5 %	-	-	1.57	1.24	1.63
1 %	-	-	3.01	2.47	3.26

(5) Belutu River

Evaluation Factor	Return Period				
	10-year	20-year	30-year	50-year	100-year
IRR (%)	2.94	3.14	3.12	2.95	-
NPV (Million Rps.)					
Discount 12 %	(20,046)	(20,817)	(21,603)	(23,067)	-
Rate 10 %	(19,610)	(20,259)	(21,046)	(22,589)	-
8 %	(18,127)	(18,539)	(19,291)	(20,900)	-
5 %	(11,543)	(11,136)	(11,687)	(13,315)	-
1 %	23,713	27,958	28,607	27,521	-
B/C					
Discount 12 %	0.32	0.34	0.34	0.33	-
Rate 10 %	0.39	0.41	0.40	0.39	-
8 %	0.48	0.50	0.50	0.49	-
5 %	0.72	0.74	0.74	0.72	-
1 %	1.44	1.49	1.48	1.44	-

(6) Padang River

Evaluation Factor	Return Period				
	10-year	20-year	30-year	50-year	100-year
IRR (%)	11.54	10.82	10.36	9.66	-
NPV (Million Rps.)					
Discount 12 %	(1,692)	(4,837)	(7,187)	(10,741)	-
Rate 10 %	7,261	4,323	2,092	(2,019)	-
8 %	22,069	19,770	17,744	13,148	-
5 %	67,174	67,718	66,769	61,587	-
1 %	260,214	276,487	281,316	277,763	-
B/C					
Discount 12 %	0.96	0.90	0.87	0.81	-
Rate 10 %	1.15	1.08	1.03	0.97	-
8 %	1.41	1.33	1.27	1.19	-
5 %	2.08	1.95	1.87	1.75	-
1 %	4.09	3.83	3.66	3.42	-

2. Water Supply Project

Evaluation Factor	Lauisi-meme Dam	Namobatang Dam	Belumai Aqueduct
	10-year	20-year	30-year
IRR (%)	9.69	12.12	14.77
NPV (Million Rps.)			
Discount 12 %	(22,757)	502	10,361
Rate 10 %	(4,217)	11,817	25,105
8 %	32,300	33,099	52,838
5 %	170,844	111,071	155,533
1 %	958,928	544,669	742,821
B/C			
Discount 12 %	0.71	1.02	1.41
Rate 10 %	0.95	1.38	1.88
8 %	1.35	1.97	2.64
5 %	2.58	3.79	4.83
1 %	7.56	11.32	12.24

Note: () shows a minus sign.

Table 4-6(1/2) ANNUAL FLOW OF ECONOMIC COST AND BENEFIT FOR MASTER PLAN

1. Flood Control Project					Unit : Million Rp																									
1.1 Belawan River(50-Year)				1.2 Deli-Percut River System (100-Year)				1.3 Serdang River (50-Year)				1.4 Ular River (50-Year)				1.5 Belutu River (50-Year)				1.6 Padang River (50-Year)				1.7 Integrated Flood Control						
Year	Economic Cost			Economic Benefit	Economic Cost			Economic Benefit	Economic Cost			Economic Benefit	Economic Cost			Economic Benefit	Economic Cost			Economic Benefit	Economic Cost			Economic Benefit	Economic Cost					
	Const.	OHR	Total		Const.	OHR	Total		Const.	OHR	Total		Const.	OHR	Total		Const.	OHR	Total		Const.	OHR	Total		Const.	OHR	Total			
1 1993	0	0	0	0	8,448	0	8,448	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1 1993	8,448	0	8,448	0
2 1994	0	0	0	0	19,673	0	19,673	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2 1994	23,059	0	23,059	0
3 1995	0	0	0	0	45,980	0	45,980	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3 1995	54,872	0	54,872	0
4 1996	0	0	0	0	34,755	330	35,085	9,897	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4 1996	46,563	330	46,893	9,897
5 1997	0	0	0	0	41,892	579	42,471	17,378	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5 1997	53,700	674	54,374	18,874
6 1998	0	0	0	0	31,057	879	31,936	26,396	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	6 1998	42,865	1,069	43,934	29,387
7 1999	0	0	0	0	16,628	1,101	17,729	33,081	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	7 1999	28,436	1,387	29,823	37,567
8 2000	0	0	0	0	10,686	1,220	11,906	36,660	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	8 2000	22,494	1,601	24,095	42,642
9 2001	0	0	0	0	4,044	1,297	5,341	38,980	3,336	0	3,336	0	0	0	0	0	0	0	0	0	0	0	0	0	9 2001	19,188	1,773	20,961	46,438	
10 2002	0	0	0	0	4,044	1,326	5,370	39,831	12,299	0	12,299	0	0	0	0	0	0	0	0	0	0	0	0	0	10 2002	28,151	1,897	30,048	48,804	
11 2003	0	0	0	0	4,044	1,355	5,399	40,701	25,270	0	25,270	0	0	0	0	0	0	0	0	0	0	0	0	0	11 2003	29,314	2,021	31,335	51,170	
12 2004	0	0	0	0	4,044	1,384	5,428	41,572	16,306	183	16,489	3,498	0	0	0	0	1,693	0	1,693	0	0	0	0	0	0	12 2004	22,043	2,233	24,276	55,539
13 2005	0	0	0	0	0	1,413	1,413	42,442	16,306	420	16,726	8,013	1,393	0	1,393	0	8,267	0	8,267	0	0	666	666	10,469	0	13 2005	25,654	2,381	28,035	58,666
14 2006	1,017	0	1,017	0	0	1,413	1,413	42,442	16,306	539	16,845	10,270	2,009	0	2,009	0	8,267	67	8,334	471	0	666	666	10,469	0	14 2006	26,983	2,499	29,482	60,924
15 2007	3,523	0	3,523	0	0	1,413	1,413	42,442	16,306	657	12,527	3,907	0	3,907	0	8,267	133	8,400	942	0	666	666	10,469	0	15 2007	30,105	2,684	32,789	63,652	
16 2008	8,282	0	8,282	0	0	1,413	1,413	42,442	0	657	657	12,527	3,907	28	3,935	507	8,267	200	8,467	1,412	0	666	666	10,469	0	16 2008	20,456	2,869	23,325	66,380
17 2009	8,282	67	8,349	334	0	1,413	1,413	42,442	0	657	657	12,527	3,907	56	3,963	1,013	8,267	266	8,533	1,883	0	666	666	10,469	0	17 2009	20,456	3,030	23,486	67,691
18 2010	8,282	133	8,415	667	0	1,413	1,413	42,442	0	657	657	12,527	3,907	56	3,963	1,013	8,267	266	8,533	1,883	0	666	666	10,469	0	18 2010	20,456	3,192	23,648	69,002
19 2011	0	200	200	1,001	0	1,413	1,413	42,442	0	657	657	12,527	0	84	84	1,520	0	333	333	2,354	0	666	666	10,469	0	19 2011	0	3,353	3,353	70,313
20 2012	0	200	200	1,001	0	1,413	1,413	42,442	0	657	657	12,527	0	84	84	1,520	0	333	333	2,354	0	666	666	10,469	0	20 2012	0	3,353	3,353	70,313
21 2013	0	200	200	1,001	0	1,413	1,413	42,442	0	657	657	12,527	0	84	84	1,520	0	333	333	2,354	0	666	666	10,469	0	21 2013	0	3,353	3,353	70,313
22 2014	0	200	200	1,001	0	1,413	1,413	42,442	0	657	657	12,527	0	84	84	1,520	0	333	333	2,354	0	666	666	10,469	0	22 2014	0	3,353	3,353	70,313
23 2015	0	200	200	1,001	0	1,413	1,413	42,442	0	657	657	12,527	0	84	84	1,520	0	333	333	2,354	0	666	666	10,469	0	23 2015	0	3,353	3,353	70,313
24 2016	0	200	200	1,001	0	1,413	1,413	42,442	0	657	657	12,527	0	84	84															

Table 4-6(2/2) ANNUAL FLOW OF ECONOMIC COST AND BENEFIT FOR MASTER PLAN

Unit : Million Rp

2. Water Supply Project					2.2 Namobatang Dam					2.3 Belumut Aqueduct					2.4 Integrated Water Supply					3.1 Deli-Percut River System (F+H)					3.2 Integrated Flood Control and Water Supply																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
2.1 Lausime Dam																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
Year	Economic Cost				Economic Cost				Economic Cost				Economic Cost				Economic Cost				Economic Cost				Economic Cost																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
	Const.	OHR	Total	Benefit	Const.	OHR	Total	Benefit	Const.	OHR	Total	Benefit	Const.	OHR	Total	Benefit	Const.	OHR	Total	Benefit	Const.	OHR	Total	Benefit	Const.	OHR	Total	Benefit																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
1 1993	3,629	0	3,629	0	0	0	0	0	0	0	0	0	3,629	0	3,629	0	1 1993	12,077	0	12,077	0	12,077	0	0	12,077	0	12,077	0	0	12,077	0	12,077	0																																																																																																																																																																																																																																																																																																																																																																																																																																																													
2 1994	4,550	0	4,550	0	0	0	0	0	0	4,550	0	4,550	0	2 1994	24,223	0	24,223	0	27,609	0	0	27,609	0	27,609	0	0	27,609	0	27,609	0																																																																																																																																																																																																																																																																																																																																																																																																																																																																
3 1995	28,216	0	28,216	0	0	0	0	0	0	28,216	0	28,216	0	3 1995	74,196	0	74,196	0	83,088	0	0	83,088	0	83,088	0	0	83,088	0	83,088	0																																																																																																																																																																																																																																																																																																																																																																																																																																																																
4 1996	27,295	0	27,295	0	0	0	0	0	0	27,295	0	27,295	0	4 1996	62,050	330	62,380	9,897	73,858	330	74,188	9,897	73,858	330	74,188	9,897	5 1997	69,187	579	69,766	17,378	80,995	674	81,669	18,874	80,995	674	81,669	18,874																																																																																																																																																																																																																																																																																																																																																																																																																																																							
5 1997	27,295	0	27,295	0	0	0	0	0	0	27,295	0	27,295	0	6 1998	58,352	879	59,231	26,396	70,160	1,069	71,229	29,387	70,160	1,069	71,229	29,387	7 1999	18,957	1,991	20,948	41,310	30,765	2,277	33,042	45,796	30,765	2,277	33,042	45,796																																																																																																																																																																																																																																																																																																																																																																																																																																																							
6 1998	27,295	0	27,295	0	0	0	0	0	0	27,295	0	27,295	0	8 2000	13,754	2,110	15,864	44,889	25,562	2,491	28,053	50,871	25,562	2,491	28,053	50,871	9 2001	14,170	2,187	16,357	47,189	30,710	2,663	33,373	54,667	30,710	2,663	33,373	54,667																																																																																																																																																																																																																																																																																																																																																																																																																																																							
7 1999	0	890	890	8,229	2,329	0	2,329	0	0	2,329	890	3,219	8,229	10 2002	13,431	2,216	15,647	48,060	39,374	2,787	42,161	57,033	39,374	2,787	42,161	57,033	9 2001	0	890	890	8,229	10,126	0	1,396	0	11,522	890	12,412	8,229	10 2002	0	890	890	8,229	9,387	0	1,836	0	11,223	890	12,113	8,229	11 2003	0	890	890	10,502	9,387	0	6,847	0	16,234	890	17,124	10,502	12 2004	0	890	890	10,502	9,387	0	6,847	0	16,234	890	17,124	10,502	13 2005	0	890	890	10,502	0	294	294	4,449	6,847	0	6,847	1,184	8,031	14,951	14 2006	0	890	890	10,502	0	294	294	4,449	6,847	0	6,847	1,184	8,031	14,951	15 2007	0	890	890	10,502	0	294	294	4,449	6,847	0	6,847	1,184	8,031	14,951	16 2008	0	890	890	13,403	0	294	294	4,449	0	829	829	5,783	0	2,013	2,013	23,635	17 2009	0	890	890	13,403	0	294	294	5,678	0	829	829	5,783	0	2,013	2,013	24,864	18 2010	0	890	890	13,403	0	294	294	5,678	0	829	829	5,783	0	2,013	2,013	26,462	19 2011	0	890	890	13,403	0	294	294	5,678	0	829	829	7,381	0	2,013	2,013	26,462	20 2012	0	890	890	13,403	0	294	294	5,678	0	829	829	7,381	0	2,013	2,013	30,166	21 2013	0	890	890	17,107	0	294	294	5,678	0	829	829	7,381	0	2,013	2,013	31,734	22 2014	0	890	890	17,107	0	294	294	7,246	0	829	829	7,381	0	2,013	2,013	31,734	23 2015	0	890	890	17,107	0	294	294	7,246	0	829	829	9,420	0	2,013	2,013	33,773	24 2016	0	890	890	17,107	0	294	294	7,246	0	829	829	9,420	0	2,013	2,013	33,773	25 2017	0	890	890	17,107	0	294	294	7,246	0	829	829	9,420	0	2,013	2,013	33,773	26 2018	0	890	890	21,833	0	294	294	7,246	0	829	829	9,420	0	2,013	2,013	38,499	27 2019	0	890	890	21,833	0	294	294	9,248	0	829	829	9,420	0	2,013	2,013	40,501	28 2020	0	890	890	21,833	0	294	294	9,248	0	829	829	9,420	0	2,013	2,013	40,501	29 2021	0	890	890	21,833	0	294	294	9,248	0	829	829	12,022	0	2,013	2,013	43,103	30 2022	0	890	890	21,833	0	294	294	9,248	0	829	829	12,022	0	2,013	2,013	43,103	31 2023	0	890	890	27,865	0	294	294	9,248	0	829	829	12,022	0	2,013	2,013	49,135	32 2024	0	890	890	27,865	0	294	294	11,803	0	829	829	12,022	0	2,013	2,013	51,690	33 2025	0	890	890	27,865	0	294	294	11,803	0	829	829	12,022	0	2,013	2,013	51,690	34 2026	0	890	890	27,865	0	294	294	11,803	0	829	829	15,344	0	2,013	2,013	55,012	35 2027	0	890	890	27,865	0	294	294	11,803	0	829	829	15,344	0	2,013	2,013	55,012	36 2028	0	890	890	35,563	0	294	294	11,803	0	829	829	15,344	0	2

Table 4-7 RESULTS OF ECONOMIC ANALYSIS FOR MASTER PLAN

Evaluation Items	Integrated Flood Control	Deli-Percut River System (F+W)	Integrated Water Supply	Integrated Project (F+W)
IRR (%)	13.92	13.55	10.70	12.52
NPV (Million Rp.)				
Discount Rate	12 %	34,455	35,533	(18,318) 16,136
	10 %	93,520	108,534	14,164 107,684
	8 %	195,184	236,814	81,705 276,889
	5 %	526,206	671,943	358,998 885,204
	1 %	2,128,995	2,936,463	2,158,014 4,287,009
B/C				
Discount Rate	12 %	1.15	1.15	0.82 1.05
	10 %	1.35	1.42	1.12 1.28
	8 %	1.63	1.84	1.62 1.63
	5 %	2.34	2.99	3.17 2.59
	1 %	4.51	7.27	9.40 5.96

Note: () means a negative value.

Table 4-8 ANNUAL WATER SUPPLY BENEFIT

1. LAUSIMEME DAM				2. NAMOBATANG DAM				3. BELUMAI AQUEDUCT				4. LAUSIMEME & NAMOBATANG DAMS				5. INTEGRATED PROJECT			
No.	Year	Production (1+r) ⁿ⁻¹	Average by 5-Year (mill. Rp)	Year															
1	1993	1,000	5,834	1,000	3,154	1,000	4,100	1,000	8,988	1,000	13,087	1,000	13,087	1,000	13,087	1993			
2	1994	1,050	6,126	1,050	3,312	1,050	4,305	1,050	9,437	1,050	13,741	1,050	13,741	1,050	13,741	1994			
3	1995	1,102	6,432	6,447	1,102	3,477	3,486	1,102	4,520	4,531	1,102	9,909	9,933	1,102	14,428	14,463	1995		
4	1996	1,158	6,754	1,158	3,651	1,158	4,746	1,158	10,405	1,158	15,150	1,158	15,150	1,158	15,150	1996			
5	1997	1,216	7,091	1,216	3,834	1,216	4,984	1,216	10,925	1,216	15,907	1,216	15,907	1,216	15,907	1997			
6	1998	1,276	7,446	1,276	4,025	1,276	5,233	1,276	11,471	1,276	16,703	1,276	16,703	1,276	16,703	1998			
7	1999	1,340	7,818	1,340	4,227	1,340	5,494	1,340	12,045	1,340	17,538	1,340	17,538	1,340	17,538	1999			
8	2000	1,407	8,209	8,229	1,407	4,438	4,449	1,407	5,769	5,783	1,407	12,647	12,677	1,407	18,415	18,459	2000		
9	2001	1,477	8,619	1,477	4,660	1,477	6,058	1,477	13,279	1,477	19,335	1,477	19,335	1,477	19,335	2001			
10	2002	1,551	9,050	1,551	4,893	1,551	6,360	1,551	13,943	1,551	20,302	1,551	20,302	1,551	20,302	2002			
11	2003	1,629	9,503	1,629	5,138	1,629	6,678	1,629	14,641	1,629	21,317	1,629	21,317	1,629	21,317	2003			
12	2004	1,710	9,978	1,710	5,394	1,710	7,012	1,710	15,373	1,710	22,383	1,710	22,383	1,710	22,383	2004			
13	2005	1,796	10,477	10,502	1,796	5,664	5,678	1,796	7,363	7,381	1,796	16,141	16,180	1,796	23,502	23,558	2005		
14	2006	1,886	11,001	1,886	5,947	1,886	7,731	1,886	16,948	1,886	24,677	1,886	24,677	1,886	24,677	2006			
15	2007	1,980	11,551	1,980	6,245	1,980	8,118	1,980	17,796	1,980	25,911	1,980	25,911	1,980	25,911	2007			
16	2008	2,079	12,128	2,079	6,557	2,079	8,524	2,079	18,685	2,079	27,207	2,079	27,207	2,079	27,207	2008			
17	2009	2,183	12,735	2,183	6,885	2,183	8,950	2,183	19,620	2,183	28,567	2,183	28,567	2,183	28,567	2009			
18	2010	2,292	13,372	13,403	2,292	7,229	7,246	2,292	9,397	9,420	2,292	20,601	20,650	2,292	29,996	30,067	2010		
19	2011	2,407	14,040	2,407	7,590	2,407	9,867	2,407	21,631	2,407	31,495	2,407	31,495	2,407	31,495	2011			
20	2012	2,527	14,742	14,742	2,527	7,970	7,970	2,527	10,360	10,360	2,527	22,712	22,712	2,527	33,070	33,070	2012		
21	2013	2,653	15,479	2,653	8,369	2,653	10,879	2,653	23,848	2,653	34,724	2,653	34,724	2,653	34,724	2013			
22	2014	2,786	16,253	2,786	8,787	2,786	11,422	2,786	25,040	2,786	36,460	2,786	36,460	2,786	36,460	2014			
23	2015	2,925	17,066	17,107	2,925	9,226	9,248	2,925	11,994	12,022	2,925	26,292	26,355	2,925	38,283	38,374	2015		
24	2016	3,072	17,919	3,072	9,688	3,072	12,593	3,072	27,607	3,072	40,197	3,072	40,197	3,072	40,197	2016			
25	2017	3,225	18,815	18,815	3,225	10,172	10,172	3,225	13,223	13,223	3,225	28,987	28,987	3,225	42,207	42,207	2017		
26	2018	3,386	19,756	3,386	10,681	3,386	13,884	3,386	30,437	3,386	44,317	3,386	44,317	3,386	44,317	2018			
27	2019	3,556	20,744	3,556	11,215	3,556	14,578	3,556	31,958	3,556	46,533	3,556	46,533	3,556	46,533	2019			
28	2020	3,733	21,781	21,833	3,733	11,775	11,803	3,733	15,307	15,344	3,733	33,556	33,636	3,733	48,860	48,976	2020		
29	2021	3,920	22,870	3,920	12,364	3,920	16,073	3,920	35,234	3,920	51,303	3,920	51,303	3,920	51,303	2021			
30	2022	4,116	24,014	24,014	4,116	12,982	12,982	4,116	16,876	16,876	4,116	36,996	36,996	4,116	53,886	53,886	2022		
31	2023	4,322	25,214	4,322	13,631	4,322	17,720	4,322	38,846	4,322	56,561	4,322	56,561	4,322	56,561	2023			
32	2024	4,538	26,475	4,538	14,313	4,538	18,606	4,538	40,788	4,538	59,389	4,538	59,389	4,538	59,389	2024			
33	2025	4,765	27,799	27,865	4,765	15,029	15,064	4,765	19,536	19,583	4,765	42,827	42,929	4,765	62,359	62,507	2025		
34	2026	5,003	29,189	5,003	15,780	5,003	20,513	5,003	44,969	5,003	65,477	5,003	65,477	5,003	65,477	2026			
35	2027	5,253	30,648	30,648	5,253	16,569	16,569	5,253	21,539	21,539	5,253	47,217	47,217	5,253	68,751	68,751	2027		
36	2028	5,516	32,180	5,516	17,398	5,516	22,616	5,516	49,578	5,516	72,188	5,516	72,188	5,516	72,188	2028			
37	2029	5,792	33,789	5,792	18,267	5,792	23,746	5,792	52,057	5,792	75,797	5,792	75,797	5,792	75,797	2029			
38	2030	6,081	35,479	35,563</td															

Table 5-1 PROJECT COST OF URGENT PROJECT

Item	Feature	Unit	Quantity	Cost (million Rp.)		
				F.C.	L.C.	Total
1. Construction Base Cost						
1.1 Deli River Improvement	L = 37.4 km			43,924	32,915	76,839
Preparatory Works	L/S			7,320	5,486	12,806
Excavation	1000 m ³		2,352	9,351	4,201	13,552
Embankment	1000 m ³		492	3,901	2,009	5,910
Revetment	1000 m ²		545	12,157	17,487	29,644
Parapet Wall	m		2,500	2,220	740	2,960
Sluiceway	site		5	487	162	649
Drain	site		97	856	286	1,142
Bridge	site		19	7,632	2,544	10,176
1.2 Medan Floodway	L = 3.8 km			13,233	8,118	21,351
Preparatory Works	L/S			1,203	738	1,941
Excavation	1000 m ³		1,166	4,665	2,096	6,761
Embankment	1000 m ³		16	124	64	188
Revetment	1000 m ²		97	2,035	2,811	4,846
Weir (Floodway Side)	site		1	1,061	701	1,762
Weir (Deli River Side)	site		1	1,139	706	1,845
Bridge	site		7	3,006	1,002	4,008
1.3 Percut River Improvement	L = 28.0 km			20,348	8,729	29,077
Preparatory Works	L/S			1,850	794	2,644
Excavation	1000 m ³		1,433	5,734	2,576	8,310
Embankment	1000 m ³		370	3,798	1,799	5,597
Revetment	1000 m ²		6	131	182	313
Weir	site		1	2,136	1,145	3,281
Sluiceway and Water Gate	site		5	1,571	524	2,095
Drain	site		56	495	165	660
Bridge	site		13	4,633	1,544	6,177
1.4 Lausimeme Dam				67,246	34,988	102,234
Preparatory Works	L/S			11,208	5,831	17,039
Excavation	1000 m ³		150	654	329	983
Foundation Treatment (Grouting)	1000 m		6	678	222	900
Embankment	1000 m ³		1,750	44,800	25,200	70,000
Concrete Works	1000 m ³		20	6,000	2,000	8,000
Diversion Tunnel (Dia. 6 m)	m		500	3,063	1,313	4,376
Relocation Road	m		2,500	844	94	938
1.5 Padang River Improvement	L = 29.5 km			33,503	15,955	49,458
Preparatory Works	L/S			3,046	1,450	4,496
Excavation	1000 m ³		3,422	13,695	6,153	19,848
Embankment	1000 m ³		848	6,716	3,460	10,176
Revetment	1000 m ²		23	499	882	1,381
Weir	site		1	3,616	2,033	5,649
Parapet Wall (Bahilang River)	m		600	540	180	720
Sluiceway	site		4	663	218	871
Drain	site		14	124	41	165
Bridge	site		6	4,614	1,538	6,152
Sub-total of 1.				178,254	100,705	278,959
2. Engineering Services				36,966	6,404	43,370
3. Compensation				0	34,226	34,226
4. Administration *1)				0	19,527	19,527
Sub-total of 2 to 4				36,966	60,157	97,123
5. Price Escalation *2)				0	92,470	92,470
6. Physical Contingency *3)				21,521	25,333	46,854
7. Value Added Tax *4)				0	51,541	51,541
Grand Total				236,741	330,206	566,947

Notes :

- 1) 7 % of 1. Construction Base Cost
- 2) Foreign Currency : 0 %, Local Currency 8 %
- 3) 10 % of 1 to 5
- 4) 10 % of 1 to 6

Table 5-2 ANNUAL DISBURSEMENT SCHEDULE FOR URGENT PROJECT

(Unit : Millions Rp)

Description	Total		1993		1994		1995		1996		1997		1998		1999		2000			
	Total	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.	L.C.	F.C.		
1. CONSTRUCTION BASE COST	351,161	178,254	172,907	0	0	0	0	21,712	33,702	24,107	40,403	30,461	44,248	36,800	37,466	35,038	13,141	14,281	9,295	10,508
1.1 Deli River Improvement	76,839	43,924	32,915	0	0	0	0	6,800	5,086	6,800	5,086	10,645	7,691	10,645	6,440	4,983	2,595	2,595	2,378	
1.2 Medan Flodeway	21,351	13,233	8,116	0	0	0	0	3,308	2,030	3,308	2,030	3,308	2,030	3,308	2,030	0	0	0	0	
1.3 Percur River Improvement	29,077	20,348	8,729	0	0	0	0	0	6,783	2,910	6,783	2,910	0	0	0	0	0	0	0	
1.4 Lausimee Dam	102,234	67,246	34,988	0	0	0	0	0	16,812	8,747	16,812	8,747	16,812	8,747	16,812	8,747	0	0	0	
1.5 Padang River Improvement	49,458	33,503	15,955	0	0	0	0	0	0	0	0	6,701	3,191	6,701	3,191	6,701	3,191	6,701	3,191	
1.6 Price Escalation: F.C. 0% & L.C. 8%	72,262	0	72,202	0	0	0	0	21,712	0	5,335	0	8,498	0	12,232	0	13,379	0	6,107	0	4,939
2. ENGINEERING SERVICES COST	45,503	36,966	8,537	9,309	—	1,625	11,090	2,284	3,849	993	2,544	620	2,544	659	2,544	723	2,544	781	2,544	843
2.1 Detailed Design	26,022	22,180	3,842	9,309	1,476	11,090	1,921	1,781	445	0	0	0	0	0	0	0	0	0	0	
2.2 Construction Supervision	17,348	14,786	2,562	0	0	0	0	0	2,069	328	2,544	447	2,544	447	2,544	447	2,544	447	2,544	
2.3 Price Escalation: F.C. 0% & L.C. 8%	2,133	0	2,133	0	149	0	363	0	220	0	173	0	222	0	276	0	334	0	396	
3. COMPENSATION COST	42,636	0	42,636	0	0	0	16,456	0	26,181	0	0	0	0	0	0	0	0	0	0	
3.1 House Evacuation & Land Acquisition	34,226	0	34,226	0	0	0	13,840	0	20,307	0	0	0	0	0	0	0	0	0	0	
3.2 Price Escalation: F.C. 0% & L.C. 8%	8,410	0	8,410	0	0	0	2,616	0	5,794	0	0	0	0	0	0	0	0	0	0	
4. ADMINISTRATION COST	29,232	0	29,252	0	0	0	0	0	0	4,717	0	6,055	0	7,215	0	6,695	0	2,607	0	1,963
4.1 Administration (% of 1.1+1.2+1.3+1.4+1.5)	19,527	0	19,527	0	0	0	0	0	3,673	0	4,366	0	4,817	0	4,139	0	1,492	0	1,040	
4.2 Price Escalation: F.C. 0% & L.C. 8%	9,725	0	9,725	0	0	0	0	0	1,044	0	1,689	0	2,398	0	2,556	0	1,115	0	923	
5. TOTAL (1+2+3+4)	468,532	215,220	253,332	9,309	1,625	11,090	40,452	37,551	55,998	42,946	37,136	46,792	44,564	40,009	42,455	15,684	17,668	11,839	13,314	
6. PHYSICAL CONTINGENCY	46,854	21,521	25,333	931	153	1,169	4,045	3,755	5,600	4,294	3,713	4,679	4,469	4,001	4,245	1,568	1,767	1,184	1,331	
6.1 Physical Contingency: 10% of 4.	35,117	17,826	17,291	0	0	0	0	2,171	3,370	2,411	4,040	3,946	4,425	3,680	3,747	3,504	1,314	1,428	930	1,051
6.2 Physical Contingency: 10% of 2.	4,548	3,695	853	931	163	1,169	228	385	99	254	62	254	67	72	72	254	78	234	84	
6.3 Physical Contingency: 10% of 3.	4,264	0	4,264	0	0	0	1,646	0	2,618	0	0	0	0	0	0	0	0	0	0	
6.4 Physical Contingency: 10% of 4.	2,925	0	2,925	0	0	0	0	0	0	472	0	605	0	722	0	669	0	261	0	196
7. TOTAL (5+6)	515,406	236,741	278,565	10,240	1,788	12,199	44,497	41,306	61,598	47,240	40,849	51,471	49,153	44,010	46,700	17,252	19,435	12,023	14,645	
8. VAT: 10% of 7.	51,541	0	51,541	0	1,203	0	5,670	0	10,290	0	8,809	0	10,062	0	9,071	0	3,669	0	2,767	
9. GRAND TOTAL (7+8)	566,947	236,741	330,206	10,240	2,991	12,199	50,167	41,306	71,888	47,240	49,668	51,471	50,215	44,010	55,771	17,252	23,104	13,023	17,412	

Table 5-3 ANNUAL FLOW OF ECONOMIC COST AND BENEFIT FOR URGENT PROJECT

1. Deli-Percut River System (Urgent)								2. Padang River (Urgent)									
Year	1.1 Integrated (30-Year)				1.2 Flood Control (30-Year)				1.3 Water Supply				Year	Flood Control (10-Year)			
	Const.	OHR	Total	Economic Benefit	Const.	OHR	Total	Economic Benefit	Const.	OHR	Total	Economic Benefit		Const.	OHR	Total	Economic Benefit
1 1993	11,701	0	11,701	0	6,969	0	6,969	0	4,732	0	4,732	0	1 1993	0	0	0	0
2 1994	23,880	0	23,880	0	18,308	0	18,308	0	5,573	0	5,573	0	2 1994	0	0	0	0
3 1995	73,129	0	73,129	0	46,942	0	46,942	0	26,711	0	26,711	0	3 1995	0	0	0	0
4 1996	60,950	271	61,221	10,584	35,604	271	35,875	10,584	25,871	0	25,871	0	4 1996	2,399	0	2,399	0
5 1997	68,102	477	68,579	18,611	42,756	477	43,233	18,611	25,871	0	25,871	0	5 1997	8,160	0	8,160	0
6 1998	57,235	724	57,959	28,251	31,890	724	32,614	28,251	25,871	0	25,871	0	6 1998	19,477	0	19,477	0
7 1999	15,218	1,601	16,819	43,670	14,165	908	15,073	35,441	0	715	715	8,229	7 1999	19,477	135	19,612	2,987
8 2000	8,063	1,695	9,758	46,863	7,011	990	8,001	38,634	0	715	715	8,229	8 2000	19,477	269	19,746	5,974
9 2001	0	1,745	1,745	48,444	0	1,030	1,030	40,215	0	715	715	8,229	9 2001	0	404	404	8,961
10 2002	0	1,745	1,745	48,444	0	1,030	1,030	40,215	0	715	715	8,229	10 2002	0	404	404	8,961
11 2003	0	1,745	1,745	50,717	0	1,030	1,030	40,215	0	715	715	10,502	11 2003	0	404	404	8,961
12 2004	0	1,745	1,745	50,717	0	1,030	1,030	40,215	0	715	715	10,502	12 2004	0	404	404	8,961
13 2005	0	1,745	1,745	50,717	0	1,030	1,030	40,215	0	715	715	10,502	13 2005	0	404	404	8,961
14 2006	0	1,745	1,745	50,717	0	1,030	1,030	40,215	0	715	715	10,502	14 2006	0	404	404	8,961
15 2007	0	1,745	1,745	50,717	0	1,030	1,030	40,215	0	715	715	10,502	15 2007	0	404	404	8,961
16 2008	0	1,745	1,745	53,618	0	1,030	1,030	40,215	0	715	715	13,403	16 2008	0	404	404	8,961
17 2009	0	1,745	1,745	53,618	0	1,030	1,030	40,215	0	715	715	13,403	17 2009	0	404	404	8,961
18 2010	0	1,745	1,745	53,618	0	1,030	1,030	40,215	0	715	715	13,403	18 2010	0	404	404	8,961
19 2011	0	1,745	1,745	53,618	0	1,030	1,030	40,215	0	715	715	13,403	19 2011	0	404	404	8,961
20 2012	0	1,745	1,745	53,618	0	1,030	1,030	40,215	0	715	715	13,403	20 2012	0	404	404	8,961
21 2013	0	1,745	1,745	57,322	0	1,030	1,030	40,215	0	715	715	17,107	21 2013	0	404	404	8,961
22 2014	0	1,745	1,745	57,322	0	1,030	1,030	40,215	0	715	715	17,107	22 2014	0	404	404	8,961
23 2015	0	1,745	1,745	57,322	0	1,030	1,030	40,215	0	715	715	17,107	23 2015	0	404	404	8,961
24 2016	0	1,745	1,745	57,322	0	1,030	1,030	40,215	0	715	715	17,107	24 2016	0	404	404	8,961
25 2017	0	1,745	1,745	57,322	0	1,030	1,030	40,215	0	715	715	17,107	25 2017	0	404	404	8,961
26 2018	0	1,745	1,745	62,048	0	1,030	1,030	40,215	0	715	715	21,833	26 2018	0	404	404	8,961
27 2019	0	1,745	1,745	62,048	0	1,030	1,030	40,215	0	715	715	21,833	27 2019	0	404	404	8,961
28 2020	0	1,745	1,745	62,048	0	1,030	1,030	40,215	0	715	715	21,833	28 2020	0	404	404	8,961
29 2021	0	1,745	1,745	62,048	0	1,030	1,030	40,215	0	715	715	21,833	29 2021	0	404	404	8,961
30 2022	0	1,745	1,745	62,048	0	1,030	1,030	40,215	0	715	715	21,833	30 2022	0	404	404	8,961
31 2023	0	1,745	1,745	68,080	0	1,030	1,030	40,215	0	715	715	27,865	31 2023	0	404	404	8,961
32 2024	0	1,745	1,745	68,080	0	1,030	1,030	40,215	0	715	715	27,865	32 2024	0	404	404	8,961
33 2025	0	1,745	1,745	68,080	0	1,030	1,030	40,215	0	715	715	27,865	33 2025	0	404	404	8,961
34 2026	0	1,745	1,745	68,080	0	1,030	1,030	40,215	0	715	715	27,865	34 2026	0	404	404	8,961
35 2027	0	1,745	1,745	68,080	0	1,030	1,030	40,215	0	715	715	27,865	35 2027	0	404	404	8,961
36 2028	0	1,745	1,745	75,778	0	1,030	1,030	40,215	0	715	715	35,563	36 2028	0	404	404	8,961
37 2029	0	1,745	1,745	75,778	0	1,030	1,030	40,215	0	715	715	35,563	37 2029	0	404	404	8,961
38 2030	0	1,745	1,745	75,778	0	1,030	1,030	40,215	0	715	715	35,563	38 2030	0	404	404	8,961
39 2031	0	1,745	1,745	75,778	0	1,030	1,030	40,215	0	715	715	35,563	39 2031	0	404	404	8,961
40 2032	0	1,745	1,745	75,778	0	1,030	1,030	40,215	0	715	715	35,563	40 2032	0	404	404	8,961
41 2033	0	1,745	1,745	85,604	0	1,030	1,030	40,215	0	715							

Table 5-4 RESULTS OF ECONOMIC ANALYSIS FOR URGENT PROJECT

Evaluation Items	1. Deli-Percut River System			2. Padang River
	Integrated 30-year	Flood Control 30-year	Water Supply	Flood Control 10-Year
IRR (%)	14.35	17.90	9.90	11.86
NPV (Million Rp)				
Discount 12 %	46,596	66,530	(20,315)	(404)
Rate 10 %	113,286	114,227	(1,295)	6,923
8 %	226,082	189,914	35,859	19,825
5 %	588,307	412,244	175,899	61,695
1 %	2,311,513	1,343,415	968,821	253,095
B/C				
Discount 12 %	1.23	1.51	0.73	0.99
Rate 10 %	1.51	1.80	0.98	1.18
8 %	1.93	2.22	1.40	1.45
5 %	3.08	3.29	2.70	2.12
1 %	7.21	6.71	8.11	4.18

Note: () means a negative value.


Table 5-5 SENSITIVITY TEST OF EIRR

(Unit : %)

Item	Deli-Percut			Padang
	Integrated	Flood Control	Water Supply	Flood Control
Increase + 5 %	13.75	17.08	9.60	11.28
in Cost +10 %	13.20	16.34	9.34	10.75
Decrease - 5 %	13.72	17.04	9.59	11.25
in Benefit -10 %	13.08	16.18	9.28	10.63

FIGURES

05
6
11








Fig.2-2





AREA - 1

- D.P.P.H /1
- DANDAR BARU /4
- DANDAR KLIPPA
- BELAWAN ESTATE /4
- BELAWAN (PORT.) /4
- BULU CIHA
- GLUCUR
- HELVETIA
- KLANDIR LIWA
- KLUMPANG
- MADAI
- HARIENDAL
- HEDAN ESTATE
- HEDAN PUIRI /2
- PAYA BAKONG
- PATUHDAK
- SEI SENAYANG A.
- SACHIS
- SAHPALI
- SERUMAI
- SEI HENCIRIH /4
- SEI SEKANDING
- DINAS TRACTOR
- TANDEH
- TANDEH ULLIR
- TIHONG LANGKAT
- TUNTUNGAN /4
- RAKYAT HEDAN
- SEI SIKAHING
- KHL. PNP. LII
- HARIENDAL
- COKLAT
- GLUCUR KHOUKE
- DANDAR BARU /4
(DAIRY)

AREA - 2

- ADOLINA ILIR /3
- ADOLINA ULU
- AEK PANCUR
- BANDAR KWALA
- BANDAR NEGERI
- BANDAR PIHANG
- DATANG KWIS
- DAIU GINGGING
- DAU RATA
- BANGUN PURDA
- DECERPANG
- BENGADING
- DELI MUDA
- GREAHAN
- SEI KARANG
- KHALA NAMU
- LIMAU KUNCKUR
- LELATI
- PACAR MARAU
- RAMUNIA /4
- SEGAJADE
- SEI KARI
- SEI KERAI
- SEI PANCUR /4
- SEI PULUH
- SEI LUAN /4
- TANJONG GARIBUS
- TANJONG HERAWA
- KANAN
- TANJONG PINDA
- TIHONG DELI
- TANAH ADANG
- KOTAKI
- SILINDA

AREA - 4

- BAHILANG
- DANDAR BEJAHOU
- DANGUN BANDAR /2
- SINA KASIH
- GUNUNG MONAKO
- GUNUNG PAMELA
- GUNUNG PARA
- KEVEA EST.
- HATA FAO
- NAGA RAJA
- PAOTAU /2
- PAYA MADAR
- SEI BULUH
- PAYA PIHANG
- PRIOK
- RAHOUTAH
- RANDUKA AFQ.V
- LIDERIA
- RAHODONG EST.
- RAHODONG SIALANG
- RAHODONG SIALANG
- DIV.V FIRDAUS
- SARANG GINTING
- SEI DAUDAH —
- SEI DIBUNG
- SEI PARTI
- SEI RAMPAI
- SEI DIJAH
- SILAU DURIA
- TANAH DESIH
- TANJUNG MARIA
- TANAH RAJA
- RATNA (EX
MENDAKIS D)
- MENDAKIS A

NOTE

- With observation of solar radiation and temperature
- With observation of solar radiation
- With observation of temperature
- Observation of rainfall interrupted

THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT
IN THE REPUBLIC OF INDONESIA

JAPAN INTERNATIONAL COOPERATION AGENCY

LOCATION OF RAINFALL STATIONS UNDER
RISPA

Fig.2-4





Fig.2-5

1954 - 1968 (15 STATION)



AREA - 1

1. B.P.P.M. /1
6. GLUGUR
9. KLUMPANG
19. SERUWAI
23. TANDEM HILIR

AREA - 3

3. AEK PANCUR
6. BANDAR PINANG
8. BATU GINGGING
14. SEI KARANG
26. TANJONG GARBUS


AREA - 4

2. BANDAR BEJAMBU
3. BANGUN BANDAR /2
5. GUNUNG MONAKO
10. NAGA RAJA
16. RAMBONG EST.

NOTE

- /1 WITH OBSERVATION OF SOLAR RADIATION AND TEMPERATURE
 /2 WITH OBSERVATION OF TEMPERATURE

1969 - 1988 (15 STATION)



AREA - 1

1. B.P.P.M. /1
9. KLUMPANG
16. SEI SEMAYANG A.
19. SERUWAI
23. TANDEM HILIR

AREA - 3

3. AEK PANCUR
6. BANDAR PINANG
14. SEI KARANG
22. SEI MERAH
32. SILINDA

AREA - 4

2. BANDAR BEJAMBU
3. BANGUN BANDAR /2
5. GUNUNG MONAKO
7. GUNUNG PARA
17. RAMBONG SIALANG

NOTE


- /1 WITH OBSERVATION OF SOLAR RADIATION AND TEMPERATURE
 /2 WITH OBSERVATION OF TEMPERATURE

THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT
 IN THE REPUBLIC OF INDONESIA

JAPAN INTERNATIONAL COOPERATION AGENCY

LOCATION OF REPRESENTATIVE RAINFALL
 STATIONS

Fig. 2-6











Fig. 2-8












THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT IN THE REPUBLIC OF INDONESIA


IN THE REPUBLIC OF INDONESIA





IN THE REPUBLIC OF INDONESIA




INUNDATION AREA OF NOVEMBER 1990 FLOOD




Fig. 3-1





















THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT
IN THE REPUBLIC OF INDONESIA

JAPAN INTERNATIONAL COOPERATION AGENCY

DESIGN STORM PATTERN

Fig.3-6






LEGEND

— River Course



△ Reference Point

(000) Catchment Area (km²)





LEGEND	
	River Course
	Reference Point
(ooo)	Catchment Area (km ²)




THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT
IN THE REPUBLIC OF INDONESIA

JAPAN INTERNATIONAL COOPERATION AGENCY

MESH MAP OF INUNDATION AREA

Fig.3-8(1/3)





THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT
IN THE REPUBLIC OF INDONESIA

JAPAN INTERNATIONAL COOPERATION AGENCY

MESH MAP OF INUNDATION AREA

Fig.3-8(2/3)



THE STUDY ON BELAWAN-PADANG INTEGRATED RIVER BASIN DEVELOPMENT
IN THE REPUBLIC OF INDONESIA

JAPAN INTERNATIONAL COOPERATION AGENCY

MESH MAP OF INUNDATION AREA

Fig.3-8(3/3)

