Contract The second sec

New Hydroelectric Power Development Techniques

2.1

As a research into the development techniques to promote hydroelectric power development, the New Energy foundation (NEF) has been conducting the following surveys as consigned by the Ministry of International Trade and Industry:

(1) 5th Hydroelectric Power Resources Potential Survey

This survey was carried out as a six-year plan starting in 1980

and ending in 1985.

(a) Objective

As part of the governmental policy to promote the diversification of power supplies aimed at getting rid of petroleum, the survey had an objective of clarifying the entirety of hydroelectric power resources potential in Japan and of promoting a reasonable development of the hydroelectric power resources which can be secured most stably out of the resources reserved in the country.

(b) What was Surveyed

Sites hydroelectrically undeveloped were surveyed as described below and a power generation plan was worked out at every site surveyed.

- Schematic plan
- Field survey
- Power generation plan
- Evaluating economic aspects of the plan

3 - 19

Section 2 : Measures to Promote Hydroelectric Power Development

(c) Findings

As a result of the surveys, it could be gathered that 2,811 sites were found applicable to conventional hydroelectric power developments, having a potential of 13.01 million kilowatts and an annual power generation potential of 49.7 billion kilowatt-hours for undeveloped hydroelectric power potential. And Japan was found having a total hydroelectric power potential as shown in a Table 4, including the hydroelectric power plants both in operation and under construction. These surveys have clarified the entirety of hydroelectric power resources potential in Japan. Based on the findings successfully gathered, reasonable hydroelectric power developments have been being promoted here in Japan.

Table 4 Hydroelectric Power Potential in Japan

Installed Capacity	Annual Generation
(kW)	(GWh)
32,746	130,924

* The Figures are as of March 31, 1985.

(2) Survey into Techniques of Developing MiniatureHydroelectric Power Plants

This survey was carried out as a four-year plan starting in 1986 and ending in 1989.

1999年1月1日1月1日。

AP12 - 188

Section 2: Measures to Promote Hydroelectric Power Development

(a) Objective

in a constant of the second

To make effective use of the scatteringly distributed water energies by developing private hydroelectric power generation, thereby contributing to promotion in a region.

(b) What was Surveyed

Hydroelectric power characteristics, such as a supply fluctuation due to a change in stream discharge, and demand characteristics in farm and mountain areas, including local industries, were analyzed. And a survey was carried out into the techniques to harmonize demand and supply for miniature hydroelectric power generation mainly with a capacity of 1,000 kilowatts or less, including the means of using the power so generated.

(c) Findings

A manual was prepared, showing the steps involved in the techniques to develop a miniature hydroelectric power plant. Findings of this survey have accelerated the development of private miniature hydroelectric power, especially contributing to regional promotion.

(3) Survey into Series Developments to Reduce Construction Cost

1990) makapan kaling manana direk kaling manang manang manang manang manang manang manang manang manang manang

per legislation la secolar des la secolar de la complete de la secolar

and the state of the state of the state of the

This survey was carried out as a six-year plan starting in 1985 and ending in 1990.

AP12 - 189

Section 2: Measures to Promote Hydroelectric Power Development

(a) Objective

Recently, hydroelectric power development sites have been being smaller and smaller sized, precluding an expectation of scale merits. As a result, a construction cost has turned relatively high. As a solution to this problem, a technique was established to reduce the construction cost by conducting developments in series, aiming at a significant decrease in cost.

(b) What was Surveyed
1) Setting our eyes on the fact that sites hydroelectrically undeveloped have similar characteristics, a number of sites in a similar size located nearby or existing in an identical water system were grouped to bring about some cost reduction effects as enumerated below. Thus, the

survey was carried out to decrease a construction cost by making effective use of such effects.

Standardize the specifications of headrace and headtank structures, construction equipment, etc.

Standardize the specifications of hydroelectric power equipment (hydraulic turbines and generators).

Jointly and otherwise properly apply construction machinery and falseworks.

Centralize the supervision of works (so that every work can be supervised in a single construction work office).

and the set backback been

2)

The survey was carried out to decrease a construction cost by taking reasonable design with new technologies.

3 - 22

and see a second second seal of a brack Section 2 : Measures to Promote Hydroelectric Manager and Anna San **Power Development**

(c) Findings en fra de la calencia de la calencia

> It was found that developments in series would allow a construction cost to be saved by approximately 5% as compared with an individually designed development.

It was found that a reasonable design with new technologies employed would allow an approximately 15% decrease in construction cost as compared with a conventional design.

And some sites have been already developed by making effective use of the findings in this survey. And it could be expected much that a future hydroelectric power development would be accelerated in a great measure. and the second second second second second second second

(4) Survey into Methods of Effectively Gaging Stream Discharge at a Developing Site From an Existing Gaging Station

This survey was carried out as a five-year plan starting in 1986 and ending in 1990.

> (a) Objective

and the second to the second

2. QB的过去分词 - 1

In Japan, stream discharge data relating to a point to be hydroelectrically developed have been being prepared through a direct calculation of the stream discharge from a nearby gaging station if it is located near the point. Despite the fact that there are many gaging stations all where the second over the nation, however, there are also many points about which the important stream discharge data cannot be calculated for a study of the development size and economic aspects because there is no gaging station nearby. This survey, therefore, was made into the methods of converting

3 - 23

an an ann an an Arthreachan	Section 2 : Measures to	Promote Hydroelectric Power Development

and calculating stream discharge also from the data relating to any gaging stations other than the one nearby.

(b) What was Surveyed

This survey did not only build up a stream discharge data collected at gaging stations all over the nation but

developed a method of calculating stream discharge.

A hydroelectrically developing point has its stream discharge calculated and prepared through a conversion from the stream discharge data obtained in an existing gaging station nearby with a catchment area ratio (a ratio of the catchment area at a gaging station to the catchment area at a point to develop). The survey, however, employed another method of correcting the stream discharge with a rainfall ratio (a ratio of the catchment rainfall at a gaging station to the one at a developing point) so that a conversion could be made from the data gathered at not only a newly gazing station but also every one.

(c) Findings

general sectors and

In addition to the conversion with a catchment area ratio, converting a stream discharge with a rainfall ratio was found improving the accuracy in calculating the stream discharge. As a result, one gaging station has had a range of its applications expanded, allowing us to expect that a reasonable stream discharge can be calculated through the new technique in the future.

3 – 24

and a standard and a standard and the standard and a standard and a standard and a standard a standard a standa A standard a

a far se statistica e a constituir and farther a second

Section 2: Measures to Promote Hydroelectric Power Development

(5) Survey into Methods of Calculating Stream Discharge at a Developing site, Using Remote Sensing Data

This survey has been currently carried out as a three-year plan starting in 1991.

(a) Objective

Concerning those points whose stream discharge could not be calculated through the survey referred to in (4) above, this survey is being made into the methods of correcting a calculated stream discharge with remote sensing data.

(b) What is being Surveyed

and the state of the second of the second

A stream discharge data relating to a point to be hydroelectrically developed are calculated and prepared by converting the stream discharge data gathered at an existing gaging station with a catchment area ratio. Although an applicable range of a gaging station has been expanded by the survey referred to in (4) above, this survey is being made into a method of correcting a stream discharge with the remote sensing data, in addition to the rainfall ratio correction method.

For remote sensing, LANDSAT data are used. Based on these data, the plant situations around the basin of a river are taken to grasp the characteristics of each catchment. Another remote sensing (weather satellite NOAA, etc.) is utilized to grasp the snowfall in the catchment of a river. At the same time, methods are also studied to convert and calculate a streamed discharge.

N.0

Section 2 : Measures to Promote Hydroelectric Power Development

(6) Survey into Techniques of Redeveloping a Power Plant in Operation

This survey has been being currently carried out as a three-year plan starting in 1990.

(a) Objective

An old power plant generally is not making satisfactory use of the hydroelectric power energy that a river has, since it has a small working stream discharge. From the viewpoint of effective hydroelectric power energy utilization, therefore, the survey is aimed at establishing a technique of redeveloping such an old power plant.

(b) What is being Surveyed

This survey covers four items as specified below. From a new point of view, a redevelopment technique tries to be established, based on those items:

and the second second

A fact-finding survey into conventional hydroelectric power plants both in operation and under construction.
 A study of the techniques for evaluating the redevelopment, with consideration given to the effective use of both water power resources and existing equipment.

A study to rationalize the design and work execution plan of a redevelopment.

Working out a development planning manual to determine what redevelopment should be carried out, judging from the actual situations of an existing power plant.

3 – 26

Section 2: Measures to Promote Hydroelectric 输入 医内侧关节 计转移输入 **Power Development**

(7) Survey to Establish a Power Generation Design Support System by Use of Computer Systems

> This survey has been being currently carried out as a four-year plan starting in 1990.

Objective (a)

> To support a prompt design for a power generation by establishing a detail power generation design system with computers utilized.

What is being Surveyed (b)

Those surveys which have been already carried out, including the fifth hydroelectric power resources potential survey and the ones referred to above, are to be configured into a data base to establish a computer-aided power generation design system, which will make effective use of the needs in detail power generation designs.

(8) Survey to Evaluate Environmental Effects of a Power Plant Installation in a Water-reduced Level Section of a River

> This survey has been being carried out as a seven-year plan starting in 1985 and scheduled to end this year (1992).

 $(143) \times (147) \times (143) \times (143) \times (143) \times (143) \times (147) \times (147$

station (for a boot objective in the back of a contract of a set ngha ng haite baltangka den kendulang disebut sebut ana a

and the she

To establish a system allowing use to forecast and evaluate the effects of a hydroelectric power plant installation upon the aquatic creatures, water qualities, natural landscapes, etc. in a water-reduced level section, thereby promoting the location of hydroelectric power plants while

Section 2 : Measures to Promote Hydroelectric Power Development

paying due consideration to the preservation of environments.

(b)

What is being Surveyed

At hydroelectrically undeveloped site, a fact-finding survey is being carried out into the ecosystem of aquatic creatures, water qualities and natural landscapes in a section whose water level has been lowered. And a study has been being made to clarify what effects a water level reduction has brought about or concerning evaluation methods involved and evaluation manuals.

2.2 Measures to Reduce Costs through Technical Developments

To reduce the construction costs incurred on hydroelectric power generation by rationalizing and saving the labor for the medium-and small-sized hydroelectric power generating equipment and work execution, the New Energy Foundation has been making a new technology development survey into the equipment, work execution and new materials as referred to below as consigned by the Ministry of International Trade and Industry.

(1) Utilization Technology for Inflatable Rubber Weir

A bag made of synthetic rubber is made to rise and fall, with water or air filled or discharged under pressure. This allows us to remove the effects of back ware and deposited sand on the upstream of a weir.

Besides, the weir permits the cost to be reduced as compared with the concrete one. (For details, see "NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT")

ender excelling the second of the second of the second section 2 : Measures to Promote Hydroelectric Power Development

An outline of the inflatable weir is shown in Fig. 3.

Fig. 3 Inflatable Rubber Weir

(2) Rationalization of Dam Foundation Treatment in Low-head Project

Two foundation treatment engineering processes have been developed; one is the dam foundation treatment engineering process with an underground wall made of concrete mixed with bentonite and the other is a foundation treatment engineering process with wet minute cement (WMC) grouted.

These engineering process permit us to reduce their costs for constructing an intake dam. (For detailed, see "NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT")

3 - 29

Section 2 : Measures to Promote Hydroelectric Power Development

Fig. 4 depicts a comparison of the conventional engineering process with the new technology for a dam foundation treatment.





(3) Adoption of the TBM Method

An all-geology type TBM (Tunnel Boring Machine) is capable of excavating three or four times as compared with the existing blasting method. As a result, it is possible to reduce both term of work and costs, with labor saved. (For detailed, see "NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT")

化化物 化化物物 网络小说是个个人的变形的 医鼻子

in the property was to

计 在行行时 化氯化乙酸

Fig. 5 shows a tunnel boring machine.

3 - 30

Barran rengijan kala karan kara sara sa sa sa sa sa sa nana nadisi ng tak kara sa kara sa sang jar 1998 kakar sarata kara kara na sa sa sa sa sa sa

Section 2: Measures to Promote Hydroelectric Power Development



Fig. 5 TBM (Tunnel Boring Machine)

(4) Rationalization of Civil Facilities Such as Elimination of Spillways

and the second second

In the case of a Francis hydraulic turbine, spillways are omissible by discharging the ware through a discharge valve located in the lower part of a penstock and by operating at the intake gate.

In the case of a Perton hydraulic turbine, spillways are also omissible by establishing deflector and operating the intake gate. (For details, see "NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT")

(5) Application of FRPM Pipe to Penstock

e presentado en presentado a construição de termo de construição do construição do construição do construição e

An FRPM (Fiber-glass Reinforced Plastic Mortar) pipe is highly resistant to both acids and corrosives. Applying this pipe is aimed at creating the fallibility to a displacement of the ground, reducing the penstock weight and penstock equipment.

Habina in a shall the shad

Fig. 6 shows an FRPM pipe.

Section 2 : Measures to Promote Hydroelectric
Power Development



(6) Mechanical Joints for Penstock

The penstock has been conventionally joined by welding. With a mechanical joint of bolting applied, however, the penstock is capable of flowing a settlement of the ground with safety. This permits us to expect of a reduction of both term and cost for installation of the penstock.

(7) Package Turbine Generator

This generator is applicable at an effective head of 3 through 20 meters, stream discharge of 0.5 through 4.0 cubic meters per second and output of 10 through 600 kilowatts. The turbine unit comprises a fixed vane propeller, a fixed guide vane, and a squirrel cage type induction generator. Rotors are incorporated on the circumference of the runner vanes of a hydraulic turbine. And they are turning jointly on a concentric circle.

The generator is aimed at reducing costs by simplifying and standardizing the equipment. (For details, see "SMALL SCALE HYDROELECTRIC POWER GENERATING FACILITIES OWNED BY LOCAL PUBLIC ORGANIZATION IN JAPAN)

and the state of the second of

AP12 - 200

二、银行 单

Section 2: Measures to Promote Hydroelectric Power Development

Fig. 7 shows a package turbine generator.



Fig. 7 Package Turbine Generator

(8) Light-load Francis Turbine

This hydraulic turbine is applicable to a run-of-river type power plant with a medium-high head (approximately 50 through 300 meters) and with stream discharge fluctuating in a great measure.

This power plant is operable in a zone with a low stream discharge. A light-load Francis turbine of low specific speed (150 meter-kilowatts) type is operable up to a stream discharge of 25% on the maximum usable discharge. And a high specific speed (200 meter-kilowatts) type is operable up to 40% of the maximum usable discharge.

> une ferfetete and her state to the extend fragment factor. Set entry and the state of each of each of each of e 1 − 3 − 33

Section 2 : Measures to Promote Hydroelectric Power Development

This hydraulic turbine itself is costly and aimed at reducing the cost per unit power generation by increasing the quantity of power generated.

(9) Very-low-head Hydroelectric Power Generating Facility

A power plant is to be developed, which employs a straight-flow turbine shaped into a flow channel applicable to a very low head.

The very-low-head hydroelectric power plant is applicable to the site which satisfies the following conditions:

Head : 2 through 25 meters Working discharge : 30 through 100 cubic meters Output : 500 through 21,000 kilowatts

(10) Others

2.3 Fostering and Assisting Developers

To promote the development of hydroelectric power, the New Energy Foundation has been conducting the following projects with the fiscal subsidies granted from the Ministry of International Trade and Industry:

 Technical Guidance for Medium- and Small-scale Hydroelectric Power Development (to Develop a Power Plant with an Output of 50,000 kilowatts and below)

and the second of the meridian we are set of the

To foster and strengthen the public electric utilities and private power generating installation developers, the New Energy Foundation has been conducting a guidance relating to technical and managerial challenges, etc. concerning those hydroelectric

na eta sono da cana a	Section 2: Measures to Promote Hydroelectric Power Development
e de la construit.	power development plants which are considered promising or likely
a an	to succeed in their project. In addition, a fiscal subsidy is
	granted to cover a certain percentage of the costs required for
	planning and/or surveying for such project.
(2)	Interest subsidy System for Construction of Hydroelectric Power
	Development
and an and a second	
e til en som	Those public electric utilities and other electric enterprises,
	which try to install medium- and small-scale hydroelectric power
	plants, are subsidized with the interest payable for construction
ants in the de-	costs for a certain period following a startup of hydroelectric
	power plant operations. Thus, the system is aimed at promoting
	the hydroelectric power development by reducing the initial power
	generating cost, with a burden of the interest lightened.

In addition, the New Energy Foundation has been opening hydroelectric power-related training courses as one of the Foundation's autonomous projects.

Section 3 : Conclusion

Outlined above are the actual trends of hydroelectric power development in our country, including the measures taken for the promotion of such development. From now on, it will be essentially necessary to develop the hydroelectric power which is clean and renewable from a global point of view.

In Japan, the National Government make five times hydroelectric power potential surveys starting in 1910 to clarify the entirely of hydroelectric power development sites all over the nation. As a result, a reasonable development has been being promoted. And the findings of the surveys have been considerably supporting the development still at the present. Japan, moreover, is a minor country from the viewpoint of natural resources. As a result, the Japanese Government has been taking a wide variety of measures for developments.

n an an the an time sector of the sector of the

To promote an immense extension of the development from now on, the Provincial Government of Saba is also recommended to develop hydroelectric power reasonably, with state-of-the-art technologies introduced. To this end, a hydraulic power potential survey should be preferably made to establish a comprehensive development plan, first of all, with the future taken into consideration.

AP12 - 204

.

NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT

4 - 1

Summary

This paper will give some examples of new technology adopted for small scale hydroelectric power development. One is the example for typical run-of-river project in Japan which includes: (a) an inflatable rubber weir; (b) Burried underground penstocks; (c) Adoption of a tunnel boring machine; (d) Turbinegenerators with different sizes.

The other is a low head power project with a reregulating pondage. The project was constructed on deep alluvial deposits and the technologies adopted include: (a) Bentonite concrete diaphram cut off wall; (b) Wet milled cement; (c) A large size tubular turbine.

Some examples out of Japan include: (a) A L-shape waterway layout; (b) Adoption of a tunnel boring machine; (c) Elimination of an head tank; (d) Fiber reinforced plastic penstocks.

2

Junichi ASANO Manager Marketing & Consulting Division Overseas Engineering Department Electric Power Development Company, Ltd. (EPDC) JAPAN

Mr. Asano graduated in Civil Engineering from the Muroran Institute of Technology in early 1972. He joined EPDC after the graduation and has been involved in the development of hydroelectric power projects in Japan and abroad. He is presently the Manager of the Marketing and Consulting Division, Overseas Engineering Department.

Between 1984 and 1989 he was in charge of planning of small-scale hydroelectric power projects as an assistant manager of the planning section. In 1985, he was involved in the Pahang Small-Scale Hydroelectric Development Study in Malaysia. He has been actively involved in feasibility studies of hydroelectric power projects in Lao P.D.R., Myanmar, Thailand and Vietnam since 1989.

> 4 — 3 AP12 — 207

and a state of the state of the

Section 1 : Adoption on New Technology Example 1 - Kurotani Project

and the second

1887.54

1.1 Outline of the Power Project

The Kurotani Hydroelectric Project is a run-of-river power development project with an installed capacity of 19,600 kW, located on the Kurotani River, a small tributary of the Ina River, itself a tributary of the Tadami River in the Agano River System.

The Kurotani Intake Dam, made of a large-scale inflatable rubber weir of 6 m high is located at a point approximately 16 km upstream from the confluence of the Kurotani River and the Ina River. The project consists of three intake dams, a 8,200 m long headrace tunnel, a 450 m long penstock, and a semi-underground powerhouse. Its installed capacity is 19,600 kW with maximum discharge of 12 m^3/s and effective head of 194 m.

The power generated is to be interconnected with the bus of the Tagokura Power Station of EPDC by a transmission line (66 KV, 1 cct, length approximately 13 km). The energy is to be supplied to Tohoku Electric Power Co., Inc. for distribution.

and the second second

The project located in a heavy snowfall area (accumulated average annual snow-fall is more than 15 m), and access to intake dam site during snow season from December to April is very difficult. This is one reason that we adopted a small size tunnel boring machine to excavate the longest tunnel in length of 4,850 m. The tunnel will be excavated from a head tank side and it makes the tunnel excavation works during snow season possible.

In order to construct a economical and functional project in harmony with environment some interesting technology such as an inflatable rubber weir, a buried underground penstock, and omission of spillway is adopted.

4 - 4

 Construction on New Technology

 Construction on New Technology

 Example 1 - Kurotani Project

1.2 Topography and Geology of the Project Area

The Kurotani River having total length of $25 \sim 30$ km originates from mountainous area at elevation of 1,400 ~ 1,800 m and runs from south to north. The project is located in the area 6 ~ 16 km upstream from the confluence of the Kurotani River and the Ina River. The project area is in topographic maturity and its valley is narrow and steep.

The bed rock of the project area consists of Permian slate interpolated

by granite and gabbro. Dikes consists of rhyolite, porphyrite, diabase, and liparite are also distributed in small area. The slate is black and hard, being developed by block-form joints. The granite which is hard is distributed in the downstream area of the waterway. The granite is deeply weathered at low elevation in the downstream area of the waterway.

1.3 Construction Schedule and Plan

Bergan troubergian in einig teat

The construction works begun in May 1991 and the project is expected to be commissioned in May 1994. The construction period is very limited because of heavy snowfall from December to April. The construction work will be stopped during the snow season except the TBM tunnel excavation work.

Efforts not to disturb natural condition by the construction work were made. A cable crane and incline facilities were adopted as substitutions for construction roads. The newly constructed roads are a road for No. 3 Intake Dam and a road for penstocks.

Section 1 : Adoption on New Technology Example 1 - Kurotani Project

and the state of the local state of the state of

1.4 Inflatable Rubber Weir

In order to keep the river bed in natural condition as much as possible, a 6 m high inflatable rubber weir will be constructed on the main river. Compared with a steel gate having similar functions, in inflatable weir has the following features:

Safe and sure automatic deflation and automatic erection through adoption of a multiplex mechanism

- Easy maintenance due to less trouble because of a simple operating mechanism and no necessity for painting
- Excellent weather resistance and durability against impact of boulders
- Shortening of construction period is possible because of light weight which makes delivery and installation easy.
- Prevention of water level rise upstream of dam, as no backwater caused by the dam and sedimentation

Other important features include: The symptotic set of the show

A settling basin and a desilting gate can be omitted, because sediment flowing into the pond can be removed naturally by deflating the weir.

Manpower, connected with the maintenance and operation such as sand flushing, can be saved.

- .6

and a second		. It south a	Section 1 : Adoption on New Technology
	lander of hereiter		Example 1 - Kurotani Project
		· · · · · · · · · · · · · · · · · · ·	

1.5 Burled Underground Penstock

penstock.

A penstock of 2.2 m in diameter will be buried underground 1 m below the surface. The underground penstock has the following advantages compared with a surface penstock:

na na shine na shekara ta ka ga shine na shekara ta ka ga kasa na ana shine na shekara ta

- Supporting structures such as saddles for penstock are not necessary because the penstock will be supported and restrained by the surrounding ground and backfilld earth. Anchor block concrete can be reduced as the horizontal forces on anchor blocks are alleviated.
 - There is less susceptibility to effects of natural phenomena such as air temperature and snowfall.
 - There is safety against external impacts from avalanches, rockfall, etc.

Scenery can be maintained through greening after burying the

Consequently, by burying penstocks at sites of severe natural environment such as cold and heavy snowfall areas, there will be even more merits gained from the point of view of long-term maintenance.

It is unavoidable that the shell thickness of a buried penstock will be slightly greater compared with a surface penstock, considering the earth pressure of the surrounding backfield earth besides the internal pressure. However, a reduction in overall construction costs can be expected, because supporting structures are not necessary.

AP12 - 211

4 - 7

da en el construir en protoco de la construir. En protoco de la construir en protoco de la construir en el construir en protoco de la construir en el construi Section 1 : Adoption on New Technology Example 1 - Kurotani Project

1.6 Omission of Spillway

(1) Outline

Most of the medium- and small-scale hydraulic power plants are generally planned as small run-of-river types, and are not usually economical. However, in most cases, it can be made economical by ingenuity and new technology because the total construction cost is not so high. One of the means of reducing construction expenses is an economical design that omits the spillway that leads the spilled water from the head tank to the river and adds a discharge valve tapped from penstock just upstream side of inlet valve instead.

The omission of the spillway is made by two methods: that is, one is by using civil engineering facility and the other is by the deflector discharge of the Pelton turbine. In Japan, several power plants that were developed by these methods are operating now.

These power plants usually have a small discharge, under 4 m^3/s , to generate electricity and only one main machinery. In the case of a deflector discharge, only the Pelton turbine is allowed to be used. As the Kurotani Power Plant has a relatively large discharge of 12 m^3/s and two Francis turbine units, many problems have to be examined to use a discharge valve instead of the spillway.

The omission of the spillway in the Kurotani Power Plant was made possible by research including the improvement of the valves, making the penstock discharge valve system applicable for discharge above 4 m^3/s .

erable for the

AP12 - 212

and a second state of the state of the second state of the state of the second state of the second state of the

Section 1 : Adoption on New Technology Example 1 - Kurotani Project

> Fig. 1.1 shows a conceptional drawing of an ordinary power plant and the Kurotani Power Plant where the spillway was omitted by adding the penstocks discharge valve.

> In an ordinary power plant, at load rejection by failure of transmission line and/or generating equipment, the level of the water in the head tank rises and spills, and the spilled water is discharged into the river through a spillway tapped from the tank. The spillway is usually provided parallel to the penstock and most of them are expensive. The system applied this time detects the rise of water level in head tank caused by load rejection and discharges water in an amount proportional to spilled water to the downstream bypassing through a discharge valve.



Fig. 1.1 Omission of Spillway

4 - 9

Section 1 : Adoption on New Technology Example 1 - Kurotani Project

The penstock discharge valve system is activated at the time of the load rejection and discharges water not to spill from head tank. For this purpose, the investigation and research, such as the evaluation of the reliability, the control system linked with the hydraulic turbine, the backup method in the case of mulfunctioning, were conducted and the application to actual plant was realized.

and the second second

(2) Selection of discharge valve

Five kinds of valves, that is, a cone valve (H.B.V.), a hollow jet valve (H.J.V.), a jet flow valve (J.F.V.), a needle valve (N.V.), and a pressure-regulator-type valve (R.T.V.) were selected, examined, and evaluated for the penstock discharge valve.

u na kana sa karaka na sa kana da kara sa sa ka

The examinations were performed for 12 items, such as structural design, operation and control performance, flow characteristics, energy-absorbing effect, etc.

As the result of the overall evaluation of those valves, the cone valve (H.B.V.) with a small operating force, a large energy absorbing effect of the valve itself, simple structure, and least maintenance, was adopted. It has to be noted that the hollow jet valve (H.J.V.) has advantages that has self-opening characteristics when water pressure is applied to its body and that it has high operational reliability owing to it's operation mechanism capable of using pressure oil system of hydraulic turbine as stand-by.

The following photograph shows how it is installed.

o esta terra do un filosoria de tasio do terrotadalo. Arresta esta rasionado estre a charactería

Section 1 : Adoption on New Technology Example 1 - Kurotani Project



1.7 Selection of Turbine Type and Unit Discharge

To select the type of hydraulic turbine for the Kurotani Power Plant, the following three cases were examined for economic efficiency.

(a) 6 + 6 m³/s vertical shaft Francis turbine
(b) 8 + 4 m³/s vertical shaft Francis turbine
(c) 9 + 3 m³/s vertical shaft Francis turbine

The vertical shaft Pelton turbine was also examined as an alternative, although evidence was given that it is not economical to use because of its higher machinery cost and a larger housing space requited for installing spiral case with not less than four nozzles.

The annual run off and it's period, which was calculated from the run off-duration curve, for the power generation scheme are roughly as follows. (The river flow required for downstream and not to be used

AP12 - 215

ng a daga kana sa kara sa	an an Andrea An Andrea	Section 1 : Adoption on New Technology Example 1 - Kurotani Project
<u>م من الم الم الم الم الم بن من الم بن الم الم الم الم الم الم الم الم الم الم</u>		

for power generation is subtracted. May to November: $0.5 \text{ m}^3/\text{s} / 100 \text{ km}^3$, December to April: $0.25 \text{ m}^3/\text{s} / 100 \text{ km}^3$)

-1. j.		- 1	1999. AN 19			
12	m³/s	or	more	usable	80	days/year
8	m³/s	or	more	usable	90	days/year
6	m ³ /s	or	more	usable	110	days/year
4	m³/s	or	more	usable	160	days/year
3	m³/s	or	more	usable	210	days/year
2	m^3/s	or	more	usable	300	days/year
1	m ³ /s	or	more	usable	365	days/year

For the medium and small scale run-of-river plants without a regulating capacity, the annual energy production shall be maximized especially considering minimum operation limit of turbine in dry season.

Therefore, the hydraulic turbine, which can be operable at around 1 m^3/s flow (25 - 30% Q_{max}), was selected for this plan.

The energy production was calculated based on the efficiencies of the hydraulic turbine and generator in the attached data.

In conclusion, the adoption of the b) plan, hydraulic turbine, is most economical, as a result of comparing specific data, energy production and rough construction cost per kWh for three cases.

n in the second seco

"什么,这时,我们还是你的问题,你是我们就是你这些人的是你的人都能能能能能。"

an is a share with a state state.

the dispersive fetting to prove set in the second second second second second second second second second secon Standards to the structure of second secon

4 - 12



Project Feature of Kurotani Project

Characteristics

River

Agano river - Kurotani river

- Ohyuzawa river

 Koyuzawa river Average Runoff

7.08 m³

- Kurotani river

Catchment area

52.8 km²

23.7 6 <u>6.5</u>

- Koyuzawa river - Ohyuzawa river Total.

678.0 m

465.50 1

194.30 12.00 m³/

83.0 km

Maximum Discharg nstalled Capacity Tail Water Level Effective Head Intake Level

Annual Energy Production

72 GM 19,600 kH

Main Equipment

k - Type Turbine

13,500 kW (1st unit), 6,900 kW (2nd unit) Vertical Francis - Power

Generator

- Type Synchronized Generator - Capacity 13,800 kVA (1st unit), 7,000 kVA (2nd unit)

Ma

n Structures	
Dam	
- Kurotani Intake Weir	
Type	Inflatable Rubber Weir
D intension	II.6 m high x 50.3 m long
- Ohvuzawa Intake Weir	
Type	Concrete Gravity
Dimension	12.0 m high x 56.0 m long
- Koyuzawa Intake Weir	
Type	Concrete Gravity
Dimension	11.0 m high x 32.0 m long
Watanuau	the second s
rraici way	
= 1ylve	non-pressure mimer
- Width	2.2 - 3.3 m
- Height	2.1 ~ 3.3 m
- Length	8,162.43 m
Penstock	
- Type	burried underground
- Inner diameter	2.2 - 0.78 m
- Length	453.83 m
Powerhouse	
- Type	semi-underground
- Width	12.2 ш
- Length	28-9 ш
- Height	24.8 m

14














Section 2 : Adoption of New Technology Example 2 - Tadami Project

2.1 Outline of the Project

Tadami Dam is a facility for power generation located 3 km downstream of Tagokura Dam built earlier by Electric Power Development Co., Ltd. (EPDC) on the Tadami River of the Agano River System. At Tadami Hydroelectric Power Station electric power of a maximum output of 65 MW is generated using a maximum power discharge of 375 m^3/s , taking advantage of the effective head of 19.8 m made available by a regulating pond having an effective storage capacity of 2 hm³ created by this dam and a tailrace canal 2.2 km in length.

At power station sites of low head located of the middle or downstream stretches of rivers such as the Tadami site, the widths of the rivers are broad and alluvial deposits exist in many cases. Excavation and fill volumes will tend to be large using conventional construction methods that core bases are based directly on foundation bedrock, while care of the river would be of enormous scale making dam construction by such methods difficult for practical purposes. Consequently, to construct dams directly on alluvial deposits and to carry out foundation treatment rationally assume extremely great importance.

The river width at the dam site is approximately 180 m, and is more than 450 m when the terrace portions at the right and left banks are included. Therefore, Tadami Dam was laid out to have a main dam portion from the left bank to the present river channel (crest length 354 m), and next to it a spillway and a power intake structure (total width 74 m), while further on the right-bank side there is a side dam (crest length 154.5 m), the total length of the river structures including the spillway being 582.5 m. The main dam is a central impervious core rockfill dam constructed directly on alluvial deposits approximately 20 m in thickness.

The side dam (height 24.0 m) at the right-bank side adjacent to the spillway and power intake structure is also a central impervious core

4 - 20 AP12 - 224

nette de la companya	Section 2 : Adoption of New Technology
en en la sector de l	Example 2 - Tadami Project

rockfill dam. This side dam was based directly on the bedrock as the alluvial deposits were thin at the right-bank side.

The embankment volume of the main dam and the side dam together was approximately $450,000 \text{ m}^3$.

The new technology for foundation treatment of alluvial deposit and for low head utilization was developed in this project.

2.2 Foundation Treatment for Alluvial Deposit

The alluvial deposits at the Tadami site are comparatively wellcompacted with the void ratio approximately 25 percent, the deformation modulus being about 1,700 kgf/cm² according to plate bearing tests. The maximum particle size of the sand and gravel is roughly about 60 cm. Coefficients of permeability tend to become successively higher going from the right-bank side to the left-bank side, with values of the orders of 10^{-3} cm/s and 10^{-2} cm/s indicated at the right and left-bank sides, respectively. Whereas the alluvial deposits at this site contain few boulders so that excavation is easy, there are many parts where coefficients of permeability are low for sand-gravel deposits so that improvement by grouting methods is difficult and the diaphragm cut off wall method is more advantageous economically compared with grouting methods.

The diaphragm cut off wall at Tadami Dam is of a construction for cutting off water acting integrally with the impervious soil core, and therefore, the location of the diaphragm wall was arranged underneath the impervious core to form a continuous cut off wall which would be based directly on the bedrock existing at a depth of approximately 20 m. Thicknesses of diaphragm cut off walls normally range between 60 and 100 cm, and 80 cm was selected in this case giving consideration to the maximum particle size of the alluvial deposits, scale of the dam,

Section 2 : Adoption of New Technology Example 2 - Tadami Project

and performances of construction equipment. Bentonite concrete which shows properties close to the deformability of the surrounding alluvial deposits was adopted as the material for the diaphragm wall.

The connection of the diaphragm wall and the impervious soil core was where the hydraulic gradient would be a maximum, so that blanket grouting using wet milled cement (WMC) grout was performed along the entire width of the impervious core aiming to suppress seepage flow velocity.

(1) Bentonite Concrete Diaphragm Cut Off Wall

Bentonite concrete is a material with its deformability increased taking advantage of the water-retentive properties of bentonite. A deformability approximately the same as the alluvial-deposit foundation is exhibited, while since the water cut off property is good, bentonite concrete is extremely logical as a diaphragm was material making structural design of the dam easy. EPDC has actively worked to develop this concrete. Mix designs of bentonite concrete are for unit cement contents in a range of 75 to 200 kg/m³ with about 10 to 30 kg/m³ of bentonite added to concrete, and water-cement ratios from 1.20 to 3.50, appropriate proportions required to be selected depending on the use and construction method.

The mix proportions of bentonite concrete were selected giving consideration to approaching the deformability of the surrounding alluvial deposits while securing water cut off property, stability of quality, and workability. A standard mix design of bentonite concrete is given in table below.

> ka ang kapangkang dan pang dan pang dan pang dan pang dan Mari di Kapangka (di Sang Kapang dan pang dan pang dan Mari 2000 dan pang kapang dan pang dan pang dan pang dan

a negaciye saki ya shah gaunginn ngadarra

AP12 - 226

Section 2 : Adoption of New Technology Example 2 - Tadami Project

Water-Cement ratio W/C (2)		223
Sand percentage s/a (%)			47
	Bentonite	В	25
	Cement	С	125
Unit weight (kg/m ³)	Water	W	279
	Fine aggregate	S	792
	Coarse aggregate	G	928

Standard Mix Design Of Bentonite Concrete

The structural study of the diaphragm wall was made by a linear finite element method giving consideration to the embankment and water impoundment processes. As a result, the amounts of settlement of the diaphragm wall and the river deposits at completion of embankment were 2.1 cm and 2.5 cm, respectively, the difference in the variation being 0.4 cm. It was decided that the examination of stresses in the diaphragm wall would be done by element safety factor, with 2.0 to be secured as the element safety factor at this site throughout embankment and impounding, and during earthquake. As a result of analysis, it was found that the maximum stress occurring inside the diaphragm wall was in the vicinity of the embedded part of the wall, and the element safety factor at this time was 2.3. By adopting a bentonite concrete diaphragm wall, the difference in settlement amounts between diaphragm wall and alluvial deposits was practically eliminated, while stress-wise, large concentrations of stresses did not occur, and a rational design was made possible.

Regarding the structure of the connection between diaphragm wall and impervious soil core, model experiments were conducted in

4 - 23

Section 2 : Adoption of New Technology Example 2 - Tadami Project

view of the extreme importance of this part from the standpoint of water cut off, and the safety was confirmed. Also, in-situ tests were performed before actual construction of the bentonite concrete diaphragm cut off wall, and confirmations were made of constructibility, deformability, watertightness, and response properties at time of earthquake.

Confirmation of the water cut off properties of the diaphragm was done by permeability tests by the packer method utilizing test holes of ϕ 66 mm made in the wall. As a result of the tests the coefficient of permeability was found to be an average of 4.4 x 10^{-7} cm/s. The control criterion for coefficient of permeability of the wall is 1.0 x 10^{-6} cm/s or under, so that the permeability test results all satisfied the criterion, and it was ascertained that ample watertightness had been secured.

(2) Wet Milled Cement (WMC) Blanket Grouting

Ordinary cement which has been conventionally used for grouting bedrock is a material which excels in the aspects of handling, strength, durability, costs, etc., but there are often limits occurring with respect to practicle size in grouting of alluvial deposits. EPDC focused on the fact that cement grout is used in the form of a slurry and carried out research on the WMC grouting method aiming for increased efficiency of pulverization by switching the milling process of cement from the conventional dry system to a wet system. This grouting method is featured by the fact that injection can be done changing the quality of the grout micropulverizing cement effectively, and moreover, to any desired particle size with simple facilities incorporating a wet milling process in the conventional process of injecting cement grout.

The wet micromilling apparatus (hereinafter referred to as "micromill") is a device consisting of a vessel in which steel

AP12 - 228

in the second second second second second		Section 2 : Adoption of New Technology
		Example 2 - Tadami Project

beads are filled with the beads rotated at high speed and cement particles passing through the voids in the beads pulverized by forces such as friction, compression, and shear.

The alluvial deposits at the Tadami site are generally fine-

particled and difficult to improve by grouting, but it was judged that by manufacturing and injecting WMC of the finest size, it would be possible for representative sand-gravel layers, needless to say, and even silty-sand layers having minute voids existing at parts to be improved.

Results Of Studies On Groutability Ratios

Sample	Partic] of dep (m	le size posits m)		Groutabil	ity ratios	
No			Ordinar	y cement	W	MC
	D15	D10	D15/G85 (≥15)	D10/G95 (≥8)	D15/G85 (≥15)	D10/G95 (≥8)
1	8.0	4.3	229	86	1,778	614
2	0.45	0.3	34	6	267	40
3	1.2	0.18	1.4	4	111	26
4	0.07	0.06	2	1	16	9
Note: Ordin	hary cemen WMC	nt G95 G95	= 0.05 mm, = 0.007mm,	G85 = 0.(G85 = 0.()35 mm)045 mm	

The target permeability was made 5 Lu since the grouting was to be blanket grouting; the range of injection was along the entire bottom surface of the impervious soil core with the depth of improvement to be 5 m. The injection pattern was that of two rows at 1.5 m spacings on both upstream and downstream sides of the diaphragm wall with grout hole intervals in the direction of the dam axis 2.5 m.

Section 2 : Adoption of New Technology Example 2 - Tadami Project

At the difficult-to-improve right-bank side, since adequate improvement effects were not obtained with primary injection, secondary injection and additional grout hole injection were performed. As a result, the probability of non-exceedence at 5 Lu became 88 percent to attain the target.

At the left-bank side of comparatively high coefficient of permeability, the improvement target was more or less reached with primary injections. As a result of permeability tests after a slight amount of additional grouting, the probability of nonexceedence at 5 Lu became 93 percent.

The relationships of amount of grout injected and improvement effect according to the right and left-bank side are summarized in table below.

Relationships of Amount of Grout Injected and Improvement Effect According to the Right and Left-bank Sides

		, et tal i de <u>en en el de pre</u>
Location	Left bank side	Right bank side
Coefficients of perme-ability before injection (cm/s)	1.7×10^{-2}	2.3 x 10 ⁻³
Coefficients of perme-ability after injection (cm/s)	2.3 x 10 ⁻⁵	2.2×10^{-5}
Probability of non-exceedence at 5 Lu (%)	93	88
Amounts of grout per valve (()	623	456
Amounts of cement per length (kg/m)	346	204

en en en en general en de la seu de la segunda de la segun

4 - 26

and a characteristic construction of the state of the second second second second second second second second s National second second

2.3 Bulb Turbine

(1) Introduction

The bulb turbine generating unit is the optimum unit for electric power generators at low head sites under large flow conditions. Owing to the cylindrical and linear arrangement of the casing and draft tube which comprise the water passage, the bulb turbine has the following advantages in comparison with the vertical shaft Kaplan turbine:

- Higher efficiency due to less head loss
- Smaller machine size due to higher unit speed

Requires less excavation than elbow type draft tube and volute type casing

The EPPC's Tadami Project is typical under those circumstances and is applied advanced technology.

In order to pursue the features of low head and large capacity machines, careful feasibility studies were made between the Kaplan type unit and the bulb type unit in terms of the efficiency, size of the power house building, required excavations, maintainability and so on and finally the bulb type was selected making points for its less construction cost and more energy production.

4 - 27

 the state of the s	n faar seele	Section 2 : Adopt	ion of New Technology
 a a cara a c		Exar	nple 2 - Tadami Project

The power station is partially underground as shown in Fig. 2.1.



Fig. 2.1 Sectional View of the Tadami Powerhouse

A 1,700 kW S-type tubular unit is installed side by side with the 65 MW bulb unit so that, at any time, the released water 8 m^3/s , to protect natural condition of the river, can be discharged bypassing the bulb unit.

and the second secon

and a second on a state of a state of the transformer and the

AP12 - 232

Section 2 : Adoption of New Technology Example 2 - Tadami Project

(2) Features and Construction

Table 2.1 lists the specifications of bulb turbine and S-type tubular turbine.

Table 2.1 Specifications of Turbine and Generator Units

Type Bulb Turbine	Bulb Turbine	S-type Tubular Turbine
No. of units	1	1
Capacity (M/W)	65.8	1.75
Head (m)	20.7	24.2
Speed (rev/min)	100	600
Specific speed (m-kW)	614	468
Submergence (horizontal) center of rotating parts (m)	-8.5	-3.45

Type Generator	Bulb Turbine	S-type Tubular Turbine
Capacity (MVA)	67.2	1.7
Voltage (kV)	11	б.б
Frequency (Hz)	50	50
No. of poles	60	10
Speed (rev/min)	100	600
Power factor	0.95	0.98

4 - 29 AP12 - 233

an a	Section 2 : Adoption of New Technology Example 2 - Tadami Project

Feat	ures of the Tadami bulb unit are described below.
1 Cuc	area of the Idaami barb and are accounted that
	Burney and Wishelph Opho
α τ <u>ι</u> 11 του του του του (α) στ	Kunner and Wicker Galen and Arts a six programmer
	A five-blade runner was used, in view of the father high
	head of 20.7 m, and a high nickel content 13-chromium
	stainless steel casting was used to assure high fatigue
	strength in water and good weldability.
	en e
	Twenty wicket gates, made of 13 chromium stainless steel
and the second sec	casting, were conically arranged and supported by
	cylindrical stem bearings.
(b)	Bulb Supporting System
. · · ·	This system has six stay vanes, two horizontal supports and
	a bulb support, which support the various loads; hydraulic
	thrust bulb weight, buoyancy, generator driving torque.
	generator thermal load seismic force. fluctuating
	budroulic force and sessonal thermal load. The above loads
	and all operied to the surrounding congrete by the stay
. · · · ·	are all carried to the suffounding concrete by the stay
	vanes and the support.
1	
. ·	

AP12 - 234

Beneral to the second se

Section 2 : Adoption of New Technology Example 2 - Tadami Project



Therefore, their reliability is very important. The fishtail shape six stay vanes are hollow. These stay vanes are spaced at equal pitch around the bulb body to reduce the share load on the surrounding concrete.

The large top and bottom stay vanes are hollow for maintenance access and to accommodate generator leads and piping. A bulb support is at the bottom of the generator and two horizontal supports are on each side of the generator. The stiffness of these supports, with longer pipes and fixed ends, is selected so that the bending stress caused by forced displacement cannot increase. These longer pipe supports do not need a large concrete pier and spherical bushings at each end. Therefore,

Section 2 : Adoption of New Technology Example 2 - Tadami Project

maintenance is easier and less concrete work is required, and hydraulic head loss at the large concrete pier is reduced. The two horizontal supports must each be preloaded using pre-set hydraulic rams, so that at any time, the support can maintain the minimum required compressive load.

The stay vanes and supporting structures are designed to be rigid enough to withstand the various loads, to assure smooth operation without excessive deformation, to withstand frictional force at each bearing and vibration, and to be safe enough to withstand low and high cyclic loads.

(c) Bearing System

Three guide bearings are provided in view of the machine's large size and capacity and these bearings are forcibly lubricated by a gravity head from an upper oil tank. The Thrust bearing is close to the stay vanes so that it can be supported rigidly. The thrust load is thereby transmitted directly from the stay vanes to the concrete foundation.

For the thrust bearing, a Hitachi pivot-spring type thrust bearing is used. This bearing has both the advantages of good oil film formation and good load balancing through the pivot spring operation. This bearing structure minimizes thermal distortion through the use of double-layer thrust bearing pads.

na i priš

AP12 - 236

Section 2 : Adoption of New Technology Example 2 - Tadami Project

(d) Cooling Method for Generator

The bulb generator must be designed to have adequate ventilation for cooling in the closed and limited diameter of the bulb casing. Also, the design of the ventilation channels must be simple so that the generator can be easily maintained. For the Tadami bulb generator and efficient cooling effect was achieved by improving the construction of the stator frame. A non-pressurized cooling method was adopted.

(3) Special Model Tests

(a)

Hydraulic Performance Model

The water passage and the stay ring were optimized to have a accelerated at their outlet. The runner blades were developed using F.E.M. flow analyses.

A flat, high efficiency, over the entire output range was achieved, as shown in Fig. 2.3.





4 - 33

Section 2 : Adoption of New Technology Example 2 - Tadami Project

(b) Cavitation characteristics

The relationship between the critical cavitation coefficient and the plant cavitation coefficient is shown in Fig. 2.7, where the cavitation margin at the maximum turbine output of 65.8 MW is approximately 25 percent. Runner vanes were developed, which assured a no-bubble condition over the entire operating range.

Scale Model of the Stay Ring

To assure reliability in construction before manufacturing the prototype machine, a 1/8 scale model was built, comprised the stay vanes, the surrounding concrete, a bulb support, two horizontal supports, and the rotating parts of the turbine and generator. Model tests were tested int he laboratory using a 1,200 ton capacity testing machine and a 20 ton vibration testing stand.

(4) Manufacture and Installation

(a) Stay Ring

The stay ring was divided into 12 pieces for easier transportation. The pieces were connected at the site using coupling bolts and seal welding. This coupling method is considered a good way to reduce the large amount of deformation caused by welding heat.

(b)

(c)

Shop Assembly of the Bulb Turbine

Shop assembly was performed, including the turbine rotating such parts as runner, shaft, etc. All clearances, gate opening, deformation of the shaft and major components,

4 - 34

the east of the second

	and the first	Section 2 : Adoption of New Technology
an a	n de la companya de En esta de la companya	Example 2 - Tadami Project

load acting on the turbine bearing, operation of the runner blades, etc., were tested and compared with the design values.

Shop Assembly of the Bulb Generator

The generator was fully assembled and rotating tests were performed in the shop. Guaranteed performance was confirmed at a satisfactory value. All clearances, deformation, stress and temperature rise of major components were measured and compared with the design values.

(d)

(c)

Site Installation

Most of the construction of the Tadami powerstation has been completed. Installation of the turbine embedded parts (stay ring, hatch cover, draft tube liner, etc.) have already been finished. To get a highly reliable stay ring, which is the most important part of the bulb generating unit, an adjustable spider bracing was used during installation to maintain the accuracy of the machined face. A deformation of 0.3-0.8 mm per 10.2 m diameter was less than the allowable deformation 1.5 mm. The runner, generator rotor and other main part were installed successfully.

AP12 - 239

Section 2 : Adoption of New Technology Example 2 - Tadami Project

IAIN STRUCTRUES	Main Dam	Sub Dam
Dam		
Туре	Rockfill with center impervious core	Rockfill with center impervious core
Height	29.0 m	19.0 m
Crest Length	354.0 m	154.5 m
Crest Width	10.0 m	10.0 m
Volume	310,000 m ³	90,000 m ³
Slope Gradient		
Upstream Downstream	1 : 2.8 1 : 2.2	1 : 2.8 1 : 2.2
Spillway		
Туре	Controlled	
Dimension	Width : 14.0 m	
Discharge Capacity	6,000 m ³ /s	
Number of Gate	Roller Gate x 3 Width : 14.0 m Height : 17.0 m	
Outlet Works		
Туре	Controlled	
Dimension	Conduit pipe	
and grade and the second s	φ1,100 - φ600 Length : 21.5 m	an an stàitean stàitean stàitean stàite
Discharge Capacity	2.5 m ³ /s	
Power Intake		
Туре	Reinforced concrete	
Dimension	Height : 24.0 m Width : 20.5 m	
Power House		· · ·
Туре	Semi-Underground	
Dimension	Width : 20.5 m Height : 43.0 m Length : 74.0 m	
Tailrace		
Туре	Open	
Dimension	Width : 45.0 m - 87.2 m Length : 2,200.0 m	

Project Feature of Tadami Project

4 - 36

.

Section 2 : Adoption of New Technology Example 2 - Tadami Project

Main Dam	Sub Dam
Main Turbine	Sub Turbine
	· · ·
Bulb turbine	S-type tubular turbine
65,800 kW	1,750 kW
1	1
Three phase AC synchronous generator, horizontal shaft	Three phase AC synchronous generator, horizontal shaft
67,200 kVA	1,750 kVA
1	1
	Main Dam Main Turbine Bulb turbine 65,800 kW 1 Three phase AC synchronous generator, horizontal shaft 67,200 kVA 1



AP12 - 242





AP12 - 244

.

Example 1 - A-Project

3.1 Outline of the Project

This project is a small scale run-of-river hydroelectric power project, comprises a 4,200 m pressurized headrace tunnel and a 8,100 kW powerhouse, and generates 39 GWh annually. A L-shaped profile tunnel layout was adopted to prevent a long penstock and distruction of environment.

The project intends to use a tunnel boring machine (TBM) in the construction work of a tunnel. An adoption of a L-shaped profile tunnel makes omission of a head tank and a spillway possible.

3.2 TMB Method

 $d(t) = \frac{1}{2} \left(t - t \right) \left(t - t \right)$

The TBM methods are adopted for the project construction sites for the following reasons:

All All All All All

(1) The progress of the overall construction work in each scheme depends almost entirely on the progress of the tunnel work. By adopting a TBM, the rate of the tunnel work can be stepped up, thus securing an early start to the commercial operation of the power stations while at the same time providing the economic advantage of generating incomes through the production of electric power that much earlier.

(2) The tunnel length is 4,200 m. Tunnels of such a length can be excavated by the TBM method at lower costs than by the conventional method.

2. A start of the start of t

AP12 - 245

4 - 41

and any device concerning with the second product of the second second second second second second second second

Section 3 : Adoption of New Technology in Foreign Countries Example 1 - A-Project

n en son ang sina kala. Na kanang sina kala

and the All

- (3) The geology of the tunnel at each construction site is estimated to consist of a homogeneous granitic rock in the deeper layer, whereas the surface layer is weathered. In this case the TBM method is suitable.
- (4) All the tunnels can be excavated starting from the power station side. It is easy to transport construction machinery to any of the power stations through the well-maintained roads of access to the said powerhouses provided that parts of these access roads are improved. In the powerhouse area exists flat land providing a suitable assembly yard for a TBM.
- (5) The TBM method is a method desirable from the viewpoint of environmental aspect because its unidirectional work does not require any intermediate work adits, construction roads and disposal areas. It can be executed without destroying the forest above the tunnel section.

3.3 Construction Work of Shafts by Raise Borer

- (1) A vertical shaft is intended to be excavated with a raise borer. The use of the raise borer makes it possible to execute the construction work of a shaft safely and in a short period of time.
- (2) A raise borer is generally composed of the main body (drill unit, control unit, valve unit, power unit, switch unit) and tools (drill rod, pilot bit, reaming bit, etc.), and in a broader sense comprises also water and air supply equipment.
 - (3) The excavation of a shaft will be executed after completion of the excavation of horizontal tunnel by installing the main body aboveground and executing pilot drilling downward from the top

Section 3 : Adoption of New Technology in Foreign Countries Example 1 - A-Project

using a pilot bit with a small diameter of 250 to 300 mm, until the pilot bit reaches the horizontal tunnel where a switch-over to a reaming bit takes place to start reaming upward from the bottom.

The rate of excavation by a raise borer depends on the characteristics of the bedrock in question. The Project at hand has been planned with the following rates of excavation in mind based on the records of similar works:

Pilot drilling	10 m/day
Reaming	8 m/day

(4)

These standards are provisional and therefore must be reviewed after conducting a detailed geological investigation at the definite design phase.

Section 3 : Adoption of New Technology in Foreign Countries Example 1 - A-Project

Project Feature of A-Project

a services

Items	Unit	Sempam
Planning Dimensions		· ·
1. Catchment Area	km ²	78.0
Main (Inter basin)	km ²	78.0
2. Annual Mean Inflow	10 ⁶ m3 (m ³ /s-day)	82.2 (951.3)
3. Maximum Discharge	m ³ /s	4.5
4. Firm Discharge	m ³ /s	1.2
5. Intake Water Level	E.L. m	440.5
6. Turbine Center	E.L. m	216.0
7. Gross Head	m	224.5
8. Effective Head	n la la martina de la composición de la	217.5
9. Installed Capacity	kW	a - 41 a - 41 8,100
10. Dependable Capacity	kW	2,200
11. Annual energy	10 ³ kWh	39,270
Facilities	•	
1. Diversion Dam Type Dimensions Concrete Volume	Hm x Lm m ³	Concrete 7.50 x 51.50 7,630
2. Waterway Type Vertical Shaft Horizontal Penstock	P. or Non-P L x D L x D L x D L x D	Pressure 125.5 x 1.75 4,200 x 2.80 200 x 1.15 - 0.85
Tailrace 3. Powerhouse Type Turbine	LxD	T. Culvert 71 Surface V.Pelton, 4N
Concrete	m x m m ³	1,790

4 - 44





AP12 - 250



AP12 - 251



Section 4 : Adoption of New Technology in Foreign Countries Example 2 - B-Project

4.1 Outline of the Project

This project is a small scale run-of-river hydroelectric power project to supply energy in isolated remort area. The project consists of an intake dam 8.6 m in height, a 342 m pressurized headrace tunnel, two penstocks in 337 m and 290 m in length and a 6,000 kW powerhouse, and generates 40 GWh annually.

Because a headrace tunnel was very short, a settling basin is designed to have a function of a head tank, and a head tank and a spillway could be eliminated. The fiber reinforced plastic (FRP) pipes are used as penstocks and some parts of penstocks are buried underground.

4.2 Omission of Head Tank or Surge Tank

Generally speaking, a surge tank is installed on a pressurized headrace when the headrace is long and very large water hammering can occur, in order to absorb the surge effect and protect the tunnel

In the case of this project, the length of headrace channel is 417.89 m, and the length of penstock is 311.788 m, and the total length of 731.678 m is a relatively short headrace channel. The surge tank may be omitted when the water channel is short. In addition, as Pelton turbines are used in this case, the magnitude of water hammering is small.

A Pelton turbine has the needle which controls the spouting water (jet steam) that impact the runner, and the deflector to control the direction of the water jet that impacts the runner, and the outstanding feature of this type of turbine is that it can control or shut off the force of water that acts on the runner without changing the water flow that enters the powerhouse. That is, the rate of flow entering the powerhouse can be adjusted by the needle, and the water that acts on

4 - 49

Section 4 : Adoption of New Technology in Foreign Countries Example 2 - B-Project

the runner can be adjusted or shut-off by the deflector. Therefore, when the turbine-generator has to be stopped urgently due to mechanical or electrical fault on the powerhouse equipment electrical fault on the transmission line, the power generation unit can be shut down without abruptly changing the rate of inflow to the powerhouse. This is an advantage because the rise of water pressure due to shutting off of water flow can be suppressed to a low value.

Generally speaking, the needle is operated from the full open position to the full close position in 30 to 60 seconds, and the deflector can be fully closed from full open position within 1 to 4 seconds.

As discussed above, there is no serious problem concerning the pressure rise in pressure tunnel and penstock because the Pelton turbine is adopted. Therefore, it has been decided for this Project not to install a surge tank at the end of the headrace tunnel in order to reduce the total construction cost.

4.3 Adoption of FRP Pipe

It was decided to mainly use the FRP pipe, which is being remarked recently as a new material replacing the conventional steel pipe, with the objective of reducing the construction cost and construction period. However, steel pipes will be used for the sections which are buried into concrete and for branches and curved sections.

The FRP pipe has the following features what the statistic details and

and manufactured, and a second solution in a week of the transmission

(1) FRP pipes having design pressure of up to 250 m can be

tarra se servici part detal del se se control e control de la control de la servicio de la control de la contro Per se control de la control

. The constraint of the constraint of the set of the s

Example 2 - B-Project

(2) The standard of FRP pipe Association is applied to the fiber reinforced plastic pipes, and structurally stable products can be obtained.

(3) In comparison to general grade steel pipes, the total cost is low, and the workability is superior as FRP pipes are light weighted. They have many advantages, i.e., good performance in connecting to pipes of other types, capability to stand outside pressure at low cost, superior erosion resistance, superior hydraulic characteristics, and the lack of need of painting.

(4) At present, there are many examples of applications in construction work. EPDC has selected FRP pipes for the penstock (2.4 m in diameter, 338.14 m long, with maximum static water pressure of 177.0 m) for Okinawa Sea Water Pumped Storage Power Plant (30 MW) which is under construction.

4.4 Continuous Foundation for Penstock

The methods of supporting FRP penstock can be broadly divided into the saddle support type foundation and the continuous foundation. In the former case, the pipe is supported at both ends, at intermediate 2 points, 3 points, 4 points, etc.

With the continuous support method, the bending force in the direction of the pipe axis and the shear become zero, and the stress generated are only the bending force in the circumferential direction, tensile strength caused by internal pressure, and the stress in the direction of pipe axis. As the total stress is reduced, the pipe was thickness can be reduced.

In this design, the curved section is fixed by anchor blocks, and other straight sections are supported by continuous concrete foundation. The

4 - 51

Example 2 - B-Project

FRP pipe used has 6.0 m unit length, and the joint is an inserting type T-joint. Therefore, the load is distributed to each pipe unit, and the load does not transmit continuously as in the case of steel pipe. This makes it possible to save the volume of anchor block concrete. In addition, as the pedestal type saddle support is eliminated to choose the continuous foundation, the pedestal form having complicated shape is not required, and the workability is improved. In particular, in the lower section of the penstock, where the slope is gentle (15° to 30°) and it is covered by talus which is ten plus several meters thick, the surface ground will be excavated for a depth of 3 to 4 meters to expose the stable natural ground, and continuous concrete foundation will be constructed (the bearing force of the foundation ground is estimated at approximately 18 t/m^2), thereby distributing the load of penstock.

This continuous concrete floor foundation are provided with expansion joints at locations of the joints of FRP pipes, so that even when a foundation of a unit pipe moves, the stress concentration will not be created in the pipe except for the pipe joint owing to this independent foundation blocks.

المحدث والعادية والمركب ومناجب والمعتوي والمعرور والمعرور

4.5 Adoption of Buried Type Penstock

The downstream section of the penstock will be placed on a gentle slope having a longitudinal gradient of 15° to 30°. According to boring surveys, this area is covered with talus cones which are ten plus several meters deep, and it is difficult to place anchor blocks on the bed rock. In addition, chasms created by surface water during rainy season cross the route of the penstock. Therefore, if the penstock is placed in an open cut channel with slope treatment, the rain chasms will be regenerated in a heavy rain, to erode the slope and bury the penstock with debris. For this reason, it has been decided to bury the

 A second sec second sec

4 - 52

a substrate the second seco
NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT

Section 4 : Adoption of New Technology in Foreign Countries Example 2 - B-Project

penstock in this section. At the same time, drain channels will be provided on both sides of penstock to prevent ingress of surface water.

The burial of the penstock has the effect of preventing extension/contraction of FRP pipes due to temperature change of this region, and protecting the penstock from impact of fallen rock or gun bullet. Also, the forest fire in the vicinity will be prevented, and help people travel for hunting and fishing.

^AP12 - 257

4 - 53

NEW TECHNOLOGY FOR SMALL SCALE HYDROELECTRIC POWER DEVELOPMENT

Section 4 : Adoption of New Technology in Foreign Countries Example 2 - B-Project

Project Feature of B-Project

and a state of the

Items	Unit	Sempam
Planning Dimensions		n na ku tekke di sakasi matati
1. Catchment Area		,
2. Annual Mean Inflow	10 ⁶ m ³ (m ³ /s-day)	307.9 (3,564)
3. Firm Discharge	m ³ /s	1.11
4. Intake Water Level	E.L. m	489.0
5. Turbine Center	E.L. m	306.7
6. Gross Head	m	161.5
7. Effective Head	m	158.0
8. Installed Capacity	k₩	6,000
9. Dependable Capacity	kW	1,400
10. Annual energy	10 ³ kWh	40,299
Facilities		
1. Diversion Dam Type Dimensions	Hm x Lm	Concrete 8.6 x 77.0
2. Waterway Type Headrace Penstock	L x D L x D	Pressure 342.3x2.0 336.8x0.9~0.5 290.1x2.0~1.1
3. Powerhouse Type Turbine		Surface V.Pelton, 4N 1,000kWx2 2,000kWx2

4 - 54



AP12 - 259









AP12 - 263

