




- 62 -








PLAN AT EL. 107.50






























12. CONSTRUCTION SCHEDULE AND CONSTRUCTION COST

12.1 Construction Schedule

The construction period required for this Amplification Project is approximately 4 years for Stage I (for Unit-5, commissioned in 2002), and approximately 2 years for Stage II (for Unit-6, commissioned in 2006).

The construction schedule is presented in Fig. 12-1

12.2 Construction Cost

It was considered that designs, construction methods, materials, and products of the technical levels which can be expected at the present time will be applied to the construction cost. Estimation was made considering the geological and topographical conditions of the project site, construction scale, etc. The time of estimation was taken as October 1992. (The foreign exchange rate was considered as US\$1 = 5.8Lempira.)

The construction cost will be US\$110,077,000. Local and foreign currency requirements in terms of U.S. dollars are as follows:

69

Local currency: US\$17,692,000 Foreign currency: US\$92,385,000

Figure 12-1 Construction Schedule

	1	199) 8				19	99				2	0 0	0				2	0 0	1				2	00	2				2	200) 3				2	0 0	4	فالأهمام طليطية	1		20	0 5				in the second	2	0 () 6		مرجر بم الي مرجز بي
I I I I I I I I I I I I I I I I I I I	FMAN	111	A S	O N	t d	FM	A M J	JA	so	N D J	F M	AM	11	AS	0 N	DJ	FM	AM	1 1	A S	0 N	DJ	FM	A M	1 1	AS	0 N	DI	FM				S O N	DJ	FM				0 N · I	D] F	MA	MJ	JA	s o	N D	JF	M	A M	3]	Α	s	л N с
Temporary Works		ß					~~~~~										1 1							<u> </u>											*****								<u>+</u>									
																						-	-		_																									İ		
Work Adit										_																								+																		
Work adit (to EL. 85.5)																		_										_						:						-												-
Work adit (to EL. 93.5)										++																																										
Work adit (to EL. 106, 3)					51										: :							+					-						<u> </u>							+			$\frac{1}{1}$				$\frac{1}{1}$	1				\pm
Vertical work adit							+ + -								+ +					: :											++															+	+					\pm
(to EL, 180, 0)																																																				
						++									_																															+						+
Durana Tampal			+++		-											+												_												+												++
Pressure Tunnel		::				86680						+ +													+																<u>i i</u>		<u> </u> 	+ +						+		+
Excavation								83												<u>i</u> i		+							<u> </u>		+++++++++++++++++++++++++++++++++++++++	+ +		+													<u> </u>					
Penstock liner			<u> </u>										882								-					: :						<u>; ;</u>	<u> i i </u>	<u>-</u>							<u> </u>					+		+				+
			+				+++									_																		-								+ +		+ +	+					+		$\frac{1}{1}$
Powerhouse		$\frac{1}{1}$	$\frac{1}{7}$: :				+		:						1						<u>; ;</u>														++-		+	1 1					$\frac{1}{1}$
Arch excavation			+ +-	<u>i i i</u> i i i			<u>i i</u>		<u>; ;</u>			+ +										_										+ +		+		<u> </u>	<u> </u>									<u> </u>		-	<u>; ;</u> ; ;			
Arch concrete					- 183							<u> </u>			<u> i i i i i i i i i </u>			_			<u> </u>	+						_			<u> </u>												+++++++++++++++++++++++++++++++++++++++									
Excavation		+++++++++++++++++++++++++++++++++++++++				1 1							<u></u>				_													<u>.</u>								<u> </u>					++									
Barrel & casing concrete					-						2	8			R																								183				++	<u> </u>			+ + +		<u> </u>	<u>;</u> ;		
Pier & slab concrete			<u>.</u>						<u> </u>		<u>.</u>										- <u></u>								<u>.</u>				<u> </u>							_	<u> </u>										<u> </u>	
			<u> </u>		-																			<u> </u>																												
																					<u> </u>	_										<u> </u>					<u> </u>	<u> </u>								+						
Excavation									國 —————	<u> </u>	<u> </u>	<u>. </u>			<u> </u>																				<u>.</u>																<u> </u>	
Concrete			<u> </u>							<u> </u>																									<u>.</u>							_										
							<u> </u>				<u> </u>	<u> </u>									•																							<u>.</u>				-				
																						-		<u> </u>																				<u> </u>	<u> </u>							
Excavation																																																				<u> </u>
Concrete							1 231																							<u> </u>																						
																																																<u>.</u>	<u> </u>		<u> </u>	
Service Shaft																																																				
Excavation																																																				
Concrete																																												; ;								
Gate								1 23																																												
· · · · · · · · · · · · · · · · · · ·																																																		1		
Electro-mechanical Equipment				Í			: :																Ī																													
Crane																																																				
Draft tube					T																:						; ;																									
Turbine & Generator Unit 5					+ ;													K III																																:		
Turbine & Generator Unit 6					-																						;			Ī										國												
Test Unit 5					+											+					G																	:														
Test Unit 6		+		+++	+										<u>;</u> ;	+	++							$\frac{1}{1}$	+	11	Ť			Ť				1	11								1 1		. E					-		·····

(

- 70 -

13. IMPACTS ON ENVIRONMENT

A new power plant amplification project is now studied and this chapter describes study results of impacts of the amplification project on environment in the reservoir and downstream area.

This project is an amplification project and the main cause to change the present state of environment is increased discharge for power generation. Such being the case, emphasis is placed on the above point in discussion of impacts on environment and their countermeasures.

13.1 Impacts of Power Plant Amplification on Environment

(1) Flow-duration Change in Downstream

(a) Water Level Fluctuation Range

Non uniform flow calculation was made concerning the dam discharge rate and water level rise rate in the downstream.

The dam discharge increases by approximately 100 m^3/sec as a result of the extension and the calculation shows that the water level rises by about 0.4 to 0.6 m in each cross section except particular points.

The water level fluctuation range over an overall length of the water system is estimated at about 1 plus or minus alpha meter, including the present fluctuation and fluctuation due to the plant amplification. Impacts on nearby residents can be eased by making them known to every resident without exception. However, in the rainy reason or a flood, the downstream water level rises higher and even the above rise may affect banana and other farms near Santa Rita and downstream.

71 -

If the plant is operated after the expansion to reach the peak output within three hours in the morning in accordance with the existing operation rules, the water level rise rate will be (About 1 m)/3 hrs = About 33 cm/hr. The Japanese standards may be a guide to the limit of the discharge change which does not cause any river disasters nor any accident resulting in injury, death and damage downstream. The judgment standard in "Dam Operation Rules" stipulated by the Ministry of Construction provides that safety can be secured if the fluctuation in 30 minutes is 50 cm or less and that about 30 cm/30 minutes is the standard. Even if compared with the above standard, the water level rise rate indicated may give no problem.

(2) Water Quality

Judging from the existing vertical distribution of water quality of the reservoir, quality of discharge water may remain unchanged even if the discharge rate increases. In the rapid stream part extending over several km downstream right below the dam, dissolved oxygen may increase and sulfide concentration may decrease but some impact may be given to aquatic life before a big branch joins the stream.

(3) Items During Construction Work

According to the field investigation, private houses are hardly seen in the dam site and its vicinity and existence of scarce animals and plants is not reported. Existing roads to the dam site are kept in good condition for transportation of construction materials and power generation equipment. Impact on the vicinity of work may not cause a serious problem except that due care must be paid to proper processing of excavated earth and sand by construction work.

- 72 -

13.2 Environmental Protection Measures

(1) Items after Plant Amplification

The following items are considered as environmental protection measures against the above.

- Residents downstream from the dam live in full recognition of the present water level variation by discharge for generation. We think they will show some understanding of the water level rise by the plant amplification and all possible measures will be implemented to make the changes of the present situation known to every resident.
 - It is seen that a small boat is used to get across the river as the current traffic means. Other river-crossing means are arranged depending on the request of residents having boats.
 - Gravel collection as industry and fishing as food hunting are seen in small scale in the downstream areas. Compensation for them is considered as possibility.

It is proposed to install discharge warning means to secure safety of downstream residents. As one of the means, the discharge alarm equipment used in Japan is considered. Details are shown in "8. Remote Transmission System".

(2) Items During Construction Work

The following items are considered as environmental protection measures.

Excavated earth and sand produced by construction work, switchyard work, etc. are estimated at about $40,000 - 50,000 \text{ m}^3$. Spoil banks are prepared to process the above earth and sand. Attention is paid in this work not to impair the nearby scenery and to prevent outflow of earth and sand from spoil banks.

- 73 -

14.1 Economic Evaluation

(1) Method of Economic Evaluation

"Alternative facility approach method" is adopted in the Project. A thermal power generation facility is assumed to be an alternative project, since the Project is designed to be a peak load power generation plant. Thus, a gas turbine power generation facility which has an output capacity equivalent to the Project is assumed to be its alternative project.

Construction cost, operation and maintenance cost, etc. are to be calculated as the cost, while these costs for the alternative project are taken as the benefit of the Project, and economic evaluation is to be made, by calculating Net Present Value (B-C), Benefit/Cost Ratio (B/C) and Economic Internal Rate of Return (EIRR).

(2) Economic Cost of the Project

The project costs were appropriated in consideration of the project's characteristics that an increase of energy production cannot be expected from the expansion of power generating facilities. Namely, they are:

- construction cost of the power plant's expansion

- construction cost of a base-load, coal-fired power plant to be required with the expansion
- operation and maintenance cost of the above power stations (including fuel cost)

(3) Economic Benefit of the Project

"Alternative facility approach" method is adopted in the Project and a gas turbine power generation plant with an installed capacity equivalent to the Project is assumed to be the benefit.

- 74 -

(4) Economic Evaluation of the Project

As a result of evaluation, it has been revealed that the Project is feasible with any index. (See Table 14-1)

 Net Present Value (B-C):
 US\$15,076 x 10³

 Benefit/Cost Ratio (B/C):
 1.12

Economic Internal Rate of Return (EIRR): 162

(5) Sensitivity Analysis

As sensitivity analysis for the Project, effects are calculated for the following cases:

- when discount rate is changed to be 8%, 10%, and 12%

when construction cost is increased by 5 to 20%

The results show that the Project is economically feasbile in all cases.

14.2 Financial Evaluation

(1) Method of Financial Evaluation

It is not appropriate to apply usual method of financial evaluation for the Project, because an increase of energy production cannot be expected from installation of additional generators. Therefore, in place of a usual financial evaluation, a study is to be made as to how much of internal reserve will enable the realization of the Project, in other words, how much of incremental income from electric power sale will make the Project viable financially.

75

(2) Financial Cost and Benefit of the Project

Financial costs of the Project are the initial investment at market prices, renovation cost, and operation and maintenance cost, and taxes are added.

Financial benefit of the Project is to be the incremental income of selling electric power by ENEE as a whole, and the amount of incremental income is estimated using an incremental unit price of electricity which is made available by price increase and power demand forecast by ENEE (low case). The average unit price of US\$ 0.088/kWh is used as the unit electricity price.

(3) Financial Evaluation of the Project

Financial Internal Rate of Return (FIRR) has been calculated based on the incremental income from the sale of electric power resulting from price increase.

Rate of Increase	32	47	57	10%
FIRR	6.3%	9.67	12.4%	14.9%

From this table, it is concluded that some 5% of price increase is necessary to make the Project viable financially, or to obtain an FIRR which exceeds the expected borrowing rate of interest in terms of domestic fund (12%). (See Table 14-2)

76 -

Table 14-1 Economic Evaluation

ŀ	· ·	T		C 0 S	T				BENI	FIT		<u>5 doll</u>
No.	Year	EL C/	JON		LOAD TH	ERMAL.			GAS TURBI			B -
				INVEST			TOTAL (C)	INVEST	0 & M		TOTAL (B)	
-4	1998	6.880				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	6,880		1	1.000	0	-6,
-3	1999	29, 364			1		29,364	ł.			0 0	-29
-2	2000		1	11 002								5
-1		15,092		11,826		1	26,918	35,320		·	35, 320	8.
	2001	11.708		7,884		A	19,592	15,137		5 400	15,137	-4.
1	2002	0			899	2,731	4,301	1	2,301.		7,923	3,
2	2003	0			899	2,731	4, 301		2, 301		7,923	3.
3	2004	18, 113		11,826	899	2,731	34,241	35,320	2,301		43,243	9,
4	2005	11, 708	672	7,884	899	2,731	23,893	15,137	2,301	5,622	23,060	-
5	2006		1,109		1,798	5,462	8,368		4,602	11,244	15,846	7.
6	2007		1,109		1, 798	5,462	8,368		4,602		15,845	7,
7	2008		1,109	· ·	1,798	5,462	8,368		4,602	11,244	15,846	1.
8	2009		1, 109		1, 798	5,462	8,368		4,602	11, 244	15,846	- 7.
9	2010		1, 109		1, 798	5,462	8,368		4,602	11, 244	15,846	. i.
-			1,109									
10	2011				1,798	5,462	8,368		4,602		15,846	1,
11	2012		1,109		1,798	5,462	8,368		4,602		15,846	7,
12	2013	Ì	1,109		1,798	5,462	8,368		4,602		15,846	1,
13	2014		1,109		1,798	5,462	8,368		4,602		15,846	1,
14	2015		1,109		1,798	5,462	8,368	35, 320	4,602		51,166	42,
15	2016		1,109		1,798	5,462	8,368	15, 137	4,602	11,244	30,983	22,
16	2017		1,109		1,798	5,462	8,368		4,602	11,244	15,846	1,
17	2018		1,109		1,798	5,462	8,368		4,602		15,846	1,
18	2019		1,109		1,798	5,462	8,368	35, 320	4,602	11,244	51, 166	42,
19	2020		1,109		1,798	5, 462	8,368	15,137	4, 502		30,983	22,
20	2021		1, 109		1,798	5,462		10,107	4,602	11,244	15,846	7,
21	2022				1, 798							
		1 100	1,109			5.462	8,368		4,602		15,846	7.
22	2023	1,106			1,798	5,462	9,475		4,602		15,846	6,
23	2024	11, 497		· · · · · ·	1, 798	5,462	31,692		4,602	11,244	15,846	-15,
24	2025	11, 517	1,109	11,825	1,798	5,462	27, 770		4,602		15,846	-11.
25	2026	11, 517	1,109	7,884	1,798	5,462	19,886		4,602	11,244	15,846	-4.
26	2027	0	1, 109		1,798	5,462	8,368		4,602	11,244	15,846	1,
27	2028		1,109		1,798	5,462	8,368	1.1	4,602	11,244	15,846	1,
28	2029	17, 276		11,826	1,798	5,462	37, 470		4,602		15,846	-21,
29	2030	11, 517		7,884	1, 798	5,462	27,770	35, 320	4,602	11,244	51, 166	23,
30	2031	11, 011	1,109	1,004	1,798	5,462	8,368	15,137	4,602	11,244	30, 983	22,
								10,101				
31	2032		1,109		1,798	5,462	8,368		4,602	11,244	15,846	7,
32	2033		1,109		1,798	5,462	8,368		4,602	11,244	15,846	1.
33	2034		1,109		1;798	5,462	8,368	35, 320	4,602		51,166	42,
34	2035		1,109	А.	1,798	5,462	8,368	15,137	4,602		30,983	22,
35	2036		1,109		1,798	5,462	8,368		4,602	11.244	15,846	7.
36	2037		1,109		1,798	5,462	8,368		4,602	11 244	15,846	. 7.
37	2038		1,109		1,798				4,602		15,846	1.
38	2039	1 A.	1, 109		1,798	5,462	8,368		4,602	11,244	15,846	7,
39	2040		1,109		1,798	5,462	8, 368		4,602	11, 244	15, 846	1,
			1,109			5,462	8,368		4,602	11, 244	15,846	1,
40	2041	. 1			1,798							
41	2042		1,109		1,1798	5,462	8,368		4,602	11,244	15,846	1, 1
42	2043		1,109		1,798	5,462	8,368		4,602	11,244	. 15,846	1,1
43	2044		1.109		1,798	5,462	8,368		4,602	11,244	15,846	7.4
44	2045		1,109		1, 798	5,462	8,368	35,320	4,602	11,244	51,166	42, "
45	2046		1,109		1, 798	5,462	8,368	15,137	4,602	11,244	30,983	22, (
46	2047		1,109		1, 798	5 462	8,368		4,602	11,244	15,846	7, 1
47	2048		1, 109		1,798	5,462	8, 368		4,602	11 244	15,846	7,
								35, 320	4,602	11, 244	51,166	
48	2049		1,109		1,798	5,462	8,368					42,
49	2050		1,109		1,798	5,462	8,368	15, 137	4,602	11,244	30,983	22,
50	2051		1,109		1,798	5,462	8,368	-80,731	4,602		-64,885	-73,
		157,297	53, 684	78,840	86, 282	262, 187	638, 290	322,930	220,883	539 771 :	1,083,534	445,
TOT	IAL i=12%]		00,004	10,010	oo, non 3	000, 101	122, 564	000,000	,	0.00,101	137,640	15, 0

B/C IRR 1.12

77 --

Table 14-2

Financial Evaluation

					(Unit:	<u>1000US\$)</u>
No	Year	and the second	COST O&M	Wotal	BENEFIT	B - C
	1998	Invest 8,613	Uam	<u>Total</u> 8,613		-8,613
-4	1999	37,630		37,630		-37,630
			. 1		l I	
-2	2000	20,060		20,060		~20,060
-1	2001	15,893	0 000	15,893	14 010	-15,893
1	2002	: 0	2,002	2,002	14,013	12,011
2	2003	0	2,002	2,002	14,778	12,776
3	2004	24,519	2,002	26,520	15,583	-10,937
4	2005	15,893	2,002	17,894	16,439	-1,455
5	2006		2,495	2,495	17,341	14,846
6	2007		2,495	2,495	18,295	15,800
7	2008		2,495	2,495	19,301	16,800
8	2009		2,495	2,495	20,362	17,86
-9	2010	1	2,495	2,495	21,482	18,981
10	2011		2,495	2,495	21,482	18,98'
11	2012		2,495	2,495	21,482	18,98'
12	2013	2 4 1	2,495	2,495	21,482	18,987
13	2014		2,495	2,495	21,482	18,981
14	2015		2,495	2,495	21,482	18,98
15	2016		2,495	2,495	21,482	18,98
16	2017		2,495	2,495	21,482	18,98
17	2018		2,495	2,495	21,482	18,98
18	2019		2,495	2,495	21,482	18,98
19	2020		2,495	2,495	21,482	18,98
20	2021		2,495	2,495	21,482	18,98
21	2022		2,495	2,495	21,482	18,98'
22	2023	1,504	2,495	3,999	21,482	17,48
23	2024	15,631	2,495	18,126	21,482	3,35
24	2025	15,659	2,495	18,153	21,482	3,329
25	2026	15,659	2,495	18,153	21,482	3,329
26	2027	0	2,495	2,495	21,482	18,98
27	2028	0	2,495	2,495	21,482	18,98
28	2029	23,488	2,495	25,983	21,482	-4,50
29	2030	15,659	2,495	18,153	21,482	3,32
	2031	10,000				
30			2,495	2,495	21,482	18,98
31	2032		2,495	2,495	21,482	18,98
32	2033		2,495	2,495	21,482	18,98
33	2034		2,495	2,495	21,482	18,98
34	2035	1	2,495	2,495	21,482	18,98
35	2036		2,495	2,495	21,482	18,98
36	2037		2,495	2,495	21,482	18,98′
37]	2038		2,495	2,495	21,482	18,98'
38	2039		2,495	2,495	21,482	18,98
39	2040		2,495	2,495	21,482	18,98
40	2041		2,495	2,495	21,482	18,98
41	2042		2,495	2,495	21,482	18,98
42	2043		2,495	2,495	21,482	18,98
43	2043	[2,495	2,495	21,482	18,98
		l				
44	2045		2,495	2,495	21,482	18,98
45	2046		2,495	2,495	21,482	18,98
46	2047		2,495	2,495	21,482	18,98
47	2048		2,495	2,495	21,482	18,98
48	2049		2,495	2,495	21,482	18,98
49	2050		2,495	2,495	21,482	18,98
50	2051		2,495	2,495	$\frac{21,482}{1,038,361}$	18,98
00 1		210,207	122,772	332,979		705,38

- 78 -

.

15. FURTHER INVESTIGATIONS

This project will be implemented after 2002; however, preparation works for construction shall be started in 1996, assuming that it takes approximately 2.5 years for detail design etc. prior to start of construction works and approximately 3.5 years for construction.

Meteorological, hydrological and geological investigations are stated as items of future works.

(1) Meteorology and Hydrology

It is recommended that telemetering system be attached to meteorological and hydrological gauging stations and that statistical analysis and arrangement of observed data be continued as before.

(2) Geology

Amplified powerhouse is to be constructed next to the existing powerhouse, so additional boring is not necessary.

Test boring will be necessary to confirm geological characteristics of each structure to every detail.

Geological investigation records shall be kept in custody not to be scattered and lost because they are important data for the future construction work.

Water leakage around the dam body shall be watched and observed from now on.

