8.4.3 Project Cost

1) General

The cost estimate is based on the result of the preliminary engineering study. The cost estimates of the construction works are prepared referring to the results of cost estimates (i.e. unit prices) in studies related to recent similar projects.

2) Construction Cost Estimate

Table 8.4.2 shows the summary of the preliminary construction cost estimated for each alternative route (A, B1 and B2) at the initial stage (4 lanes/2 directions) in term of financial cost at 1988 prices.

			(Uni	it: Million Rp.)
	Cost Item	Route A	Route B1	Route B2
1.	Earth Work	541,584	236,789	198,681
2.	Pavement	89,030	82,250	80,830
3.	Bridges	53,009	50,537	73,841
4.	Grade Separation	47,371	48,538	45,284
5.	Drainage	6,070	8,818	8,921
6.	Related Construction	4,084	4,980	4,996
7.	Miscellaneous	21,647	20,849	20,102
8.	Interchange & Parking Area	53,844	52,244	52,244
9.	Road for Construction	33,864	4,980	4,980
	Total Construction Cost:	850,503	509,976	489,879
10.	Overhead	127,575	76,496	73,482
11.	Tax (VAT)	97,808	58,647	56,336
12.	Engineering Fee	68,465	41,053	39,435
13.	Contingency	156,982	94,129	90,419
	Sub-Total of 1-13:	1,301,333	780,302	749,552
14.	Land Acquisition	80,000	70,000	60,000
and the	Grand Total	1,381,333	850,302	809,552

 Table 8.4.2
 Construction Cost Estimate

Note: All costing at 1988 prices.

For cost estimate purposes the following assumptions are made:

- a) It is assumed that major construction works will be contracted to general contractor by international open tender.
- b) The unit prices of each construction item are based on the economic conditions prevailing in November 1988.
- c) A price escalation factor during the construction period is not assumed.
- d) The exchange rates used is:Indonesia Rp. 1,716 = US Dollar 1.00
- e) Overhead is assumed to be 15% of total construction cost.
- Tax (the value added tax) is assumed to be 10% of total construction cost and overhead.
- h) Contingency is assumed to be 15% of total construction cost, overhead and engineering fee.
- i) Land acquisition cost is assumed based on the preliminary information from BINA MARGA and JASA MARGA. Furthermore, compensation costs are not yet fully studied and will be finalized after the completion of the 1/5,000 topographic map (currently at drawing stage) which is required in order to count the actual number of housing/buildings that will require compensation. The total amount of housing/buildings involved in compensation is deemed to be considerable and cannot be clearly estimated without a good larger scale map.
- 3) Economic Construction Costs

The economic costs for economic analysis is obtained from financial costs (shown in Table 8.4.2) by applying a conversion factor of 0.85 to the financial costs for the purpose of reducing the portion of transfer items such as taxes and duties. The conversion factor of 0.85 is based on study results related to recent similar projects.

As for the land acquisition cost, no adjustment is made. The economic costs for each alternative route are summarized in Table 8.4.3.

·		(Unit:	Million Rp.)
Particular	Route A	Route B1	Route B2
Direct Construction Cost	722,927	433,480	416,398
Overhead/Profit, Engineering Fee, Contingency, Land Acquisition, etc.	380,069	249,927	232,836
Grand Total	1,102,996	683,407	649,234

 Table 8.4.3 Economic Construction Cost Estimate

To compare the construction costs of the alternatives, Route B2 is the lowest. Route B1 costs about 5% and Route A about 70% higher than Route B2 in terms of both financial and economic costs as summarized in Table 8.4.4.

Table 8.4.4 Comparison of Construction Cost by Index Factor

(Route B2 = 100)

Construction Cost	Route A	Route B1	Route B2
Financial Cost	171	105	100
Economic Cost	170	105	100

4) Operation and Maintenance Costs

The operation and maintenance (O&M) costs for the Project are estimated based on the actual cost data of JASA MARGA.

The O&M cost data for years 1986, 1987 and 1988 (Jan. - June) of the existing tollways in service in Indonesia, related to the estimated total length of the tollways at each of the years, have been used as the basis for estimating O&M cost for the project tollway. Thus, the operation and maintenance costs per kilometer for each year of the existing tollways can be obtained. Considering the growth ratio of the consumer price index in DKI Jakarta during 1986 - 1988 (1986 = 100, 1987 = 108 and 1988 = 118), the costs are then converted to the 1988 price.

As a result, the average operating/maintenance costs of these three years was estimated to be 164.5 million Rp. per kilometer/annum. By applying this cost per kilometer to the proposed length of each alternative route, the annual operation/maintenance cost for each alternative route is obtained for a tollway with 2 lanes.

Furthermore, assuming that the variable cost portion out of total costs will be increased in proportion to the number of lanes, the cost in the case of 4 lanes and 6 lanes are assumed as follows (unit: Million Rp./year):

		2 lanes	<u>4 lanes</u>	<u>6 lanes</u>
Route A	:	24,960	29,702	38,189
Route B1	•	23,018	27,392	35,218
Route B2	:	22,689	27,000	34,714

The economic operation and maintenance costs are obtained by applying a conversion factor of 0.85 to the above financial costs.

8.5 Preliminary Economic and Financial Comparison

8.5.1 Economic Comparison of Alternative Routes

1) Economic Benefit

The economic benefits which would be realized from implementation of the project are defined as the saving in travel costs when comparing the "With" and "Without" Project conditions. Travel costs comprise vehicle operating cost and time cost.

a) Vehicle Operating Costs

For preliminary economic analysis of the Project, recent similar studies related to the tollway project are examined. Mainly for the reason of being up-to-date, the study result of "Consulting Engineering Service of Jakarta Outer Ring Road Project, Phase I Report, October 1988" was reviewed. Based on the above study result, the vehicle operating costs by type of vehicle and by travel speed is assumed.

b) Vehicle Time Cost

Based on the study result of the above report (Jakarta Outer Ring Road Project), the vehicle time costs are also presumed. On the other hand, time costs of trucks and pick-ups which convey cargo are deemed to be somewhat debatable, partially from the viewpoint that time cost of drivers and assistants of truck are included in the factor of vehicle operating cost, and the time cost of cargo is often difficult to be quantified.

Therefore, the time cost of trucks and pick-ups are not taken into consideration for the sake of conservative analysis in the preliminary study stage. The time costs are assumed to be varied for future years with conservative estimates in future real growth rates in income. From 1988 to 1995 the vehicle time costs are increased at 4% per annum. From 1995 to 2005 and from 2005 to 2015 the costs are increased at 3% and 2.5% per annum, respectively. As a result, the time costs by vehicle type are presumed as shown in Table 8.5.1.

Table 8.5.1 Preliminary Time Cost by Vehicle Type

			(unit: Rp	/Vehicle/hou
Veh. Type	1988	1995	2005	2015
Sedan	6,910	9,093	12,220	15,643
Pick-up		· • •		-
Truck			. _	· -
Bus	16,264	21,402	28,763	36,819

Preliminary Economic Cost Benefit Analysis 2)

The benefit of vehicle operating costs is estimated as a difference of vehicle operating costs between "With" and "Without" Project conditions.

Table 8.5.2 shows a summary of the economic benefits in travel costs for each planning year of 1995, 2005 and 2015.

Table 8.5.2 Economic Benefit in Travel Costs for Each Alternative Route

			(Unit: Mi	llion Rp./Year)
A	Iternative Route	1995	2005	2015
A	 (1) V.O.C. (2) Time Cost (Total) 	99,866 86,774 186,640	191,791 292,684 484,475	336,330 571,688 908,018
В1	 (1) V.O.C. (2) Time Cost (Total) 	90,591 76,188 166,779	186,323 276,934 463,257	316,529 528,803 845,332
B2	(1) V.O.C. (2) Time Cost (Total)	83,510 68,871 152,381	168,047 249,627 417,719	284,298 475,017 759,316

Note: V.O.C.: Vehicle Operating Cost

In case of "Without" Project, costs such as road maintenance costs on the road network would occur. When such costs are taken into consideration, the net benefit would be increased. However, such costs are excluded for cost-benefit analysis for the sake of conservative analysis.

The following assumptions for analysis are made:

Project Life	:	30 years after the completion of the construction works of the initial construction stage
Analysis Period	:	1992 to the end of the project life (1992 - 2027)
Prices	:	1988 prices
Residual Value	:	None

Following the conventional discounted cash flow method, such efficiency measures as the economic internal rate of return (EIRR), the net present value (NPV) and the benefit cost ratio (B/C) are calculated and the results are presented in Table 8.5.3.

Table 8.5.3 Economic Comparison of Alternative Routes

Efficiency Measures	Route A	Route B1	Route B2
Economic Internal Rate of Return (EIRR)	22.8%	28.6%	27.9%
Net Present Value (NPV) at Discount Rate of 15% (Million Rp.)	723,663	912,651	796,253
Benefit Cost Ratio (B/C) at Discount Rate of 15%	1.89	2.69	2.55

In terms of the above economic comparison, Route B1 showed the highest efficiency to the project investment out of the alternative Routes.

1) Toll Rates and Revenue

In the analysis of the traffic demand projection, the toll model was derived from the study result of existing toliway tariff which was prepared for the traffic assignment. The toll rates for the revenue estimation of financial analysis in the preliminary study stage are based on the said toll rate model.

The toll rates (at 1988 price) adopted are assumed to increase at 7 percent a year escalation rate and revised every three years. The revenue amounts estimated for each alternative route are shown in Table 8.5.4.

Table 8.5.4 Estimated Tollway Revenue for Alternative Route

(Unit: Million Rp./Year)

Alternative Route	1995	2005	2015
Α	118,291	350,476	941,175
Bl	115,674	339,375	912,581
B2	104,639	302,370	813,941

2) Financial Comparison of Alternative Routes

٠

By arrangement of the revenues and costs, the financial cash flows of alternative routes of A, B1 and B2 are prepared.

The revenues in the intermediate years are interpolated and those beyond 2015 are extrapolated over the analysis period.

Following the conventional discounted cash flow method, the efficiency measures are calculated and the results are shown in Table 8.5.5.

Efficiency Measures	Route A	Route B1	Route B2
Financial Internal Rate of Return (FIRR)	17.3%	21.6%	20.9%
Net Present Value (NPV) at Discount Rate of 15% (Million Rp.)	289,963	604,849	500,050
Benefit Cost Ratio (B/C) at Discount Rate of 15%	1.29	1.92	1,79

Table 8.5.5 Financial Comparison of Alternative Routes

Route B1 again showed the highest efficiency to the project investment out of the alternative Routes.

8.6 Selection of Optimal Route

This Chapter has discussed pros and cons of the alternative routes and has compared such elements as physical, socio-economic, environmental, engineering and economic/ financial features.

A summary of the result of the above comparative analysis is given as shown in Table 8.6.1.

	Comparative Elements	Route A	Route B1	Route B2
a)	Environmental and Socio- economic Impacts	Fair	Good	Fair
b)	Economic Efficiency	Poor	Good	Fair
c)	Financial Efficiency	Poor	Good	Fair

Table 8.6.1 Overall Comparison of Alternative Routes

Finally alternative Route B1 is recommended as the optimal route for Cikampek-Cirebon Tollway Project and the route to be utilized in the subsequent preliminary design work. CHAPTER 9. TOLLWAY OPERATION AND MAINTENANCE PLANNING

CHAPTER 9. TOLLWAY OPERATION AND MAINTENANCE PLANNING

9.1 Tollway Operation

9.1.1 Tollway Operator

It is government policy at present to utilize the private sector for tollway construction and operation. A selected investor(s) is authorized to operate a tollway within a contracted concessionary period, and thereafter he has to transfer the tollway property to the government.

The government intends to apply this policy to the Cikampek-Cirebon Tollway as is the case for N-S Link and Tangerang-Merak Tollway.

The Cikampek-Cirebon Tollway is planned to connect directly with the Jakarta-Cikampek Tollway and the Cikampek-Padalarang Tollway, and these tollways will be operated by different operators.

P.T. Jasa Marga, a public tollway corporation, is to participate in all tollway investment and operation. This is an essential requirement for tollway operation as well as for design and construction to preserve the public good of the road, and to secure and maintain a standard level of traffic services and safety to the public users.

9.1.2 Toll Collection System

1) Tariff System

A distance proportional tariff is proposed for the following reasons:

- A toll per unit distance travelled is seen to be fair by users
- It is suitable for a wide fluctuation of travel distances
- Control of access into both ordinary roads and tollway can be effected, if necessary
- The directly connecting Jakarta Cikampek Tollway is operated by distance proportional tariff.

2) Toll Collection and Management System

A magnetic card system is proposed for the project tollway. Users stop at on-ramps and off-ramps, a transit card is handed on entry and a toll is paid on exit.

In order to clearly identify the jurisdiction of toll revenue of different tollway operators, it is proposed to build throughway barrier gates at the east terminus of Jakarta - Cikampek Tollway and the west terminus of Cikampek - Cirebon Tollway.

A barrier gate will also be required at the east terminus of the project tollway when it is extended further east and operated by a different operator.

The on-line system, which connects all the toll booths with their toll offices and the respective regional operation offices and integrates all data at the head office, can be most desirable.

Since the construction of an on-line network is costly as is the maintenance of the computer system, it is proposed that the card issuing and cash transaction data be stored on floppy disks by a smaller capacity computer at the toll booths and that the data be compiled at the toll office.

The compiled data stored on floppy disk is delivered everyday from each toll office to the computer center in Head Office. The final compiled data can then be sent to the respective regional offices.

9.1.3 Operational Organization

Assuming that the project tollway is operated by a private investor separately from Jasa Marga, the operational organization must be self-sufficient.

However, since it is required that high standards of service and safety should be maintained, Jasa Marga should be authorized to dictate the technical standards and to supervise the operator to ensure that these standards are being maintained.

The organization will consist of three different levels, namely Head Office, Regional Operating Office and Toll Office as shown in Fig. 9.1.1.

The Head Office will comprise the Board of Directors and four departments with the sections shown in Fig. 9.1.2. The office is best located in Jakarta to ensure smooth and easy access to government agencies, financial institutions and business opportunities.

Organization of the regional Operation Office is proposed as shown in Fig. 9.1.3 and this should be located every 50-80 kilometers of the tollway to enable a patrol/emergency car to reach any location in not more than 30 minutes. Longitudinal staged construction is proposed for the project tollway, that is, the initial construction package between Cikampek and Dawuan and the second stage construction package between Dawuan and Cirebon. Hence Subang and Dawuan offices are proposed where good access to the administrative and development centers are assured.

A toll office is planned to be built at every interchange to administer toll ticket issuing and toll collecting activities.







Fig. 9.1.2 Organization of Head Office





9.2 Tollway Maintenance

9.2.1 General

"Tollway Maintenance" is defined as the function of preserving, repairing, and restoring a toliway and keeping it in condition for safe, convenient, and economical use. "Maintenance" includes both physical maintenance activities, such as patching, filling joints, mowing, and so forth, and traffic service activities including remarking and removing litter. It does not include major rehabilitation or reconstruction activities, such as widening the roadbed, or extensive resurfacing projects.

Tollway maintenance programs are designed to offset the effects of weather, vandalism, organic growth, and traffic wear and damage, as well as deterioration due to the effects of ageing, material failures, and design and construction faults. ASHTO Maintenance Manual (1) includes a table that clearly distinguishes between the four general classes of roadway maintenance and construction activities:

- 1) Maintenance
 - a. Traffic services
 - b. Physical maintenance
- 2) Construction
 - a. Betterment
 - b. Construction and reconstruction

9.2.2 Maintenance Management

Routine and periodic inspections should be programmed for the maintenance activities of the regional operation office.

Since the data and information collected by the inspection should be properly assessed for maintenance works, an inspection manual is required to determine measures to be taken.

Maintenance budgets are based on the estimated costs to accomplish specific work programs to stated levels of service and performance standards. Maintenance

management includes control procedures that are applied to ensure that the work accomplished by field personnel is in line with the objectives of the program and the budgeted funds available.

The basic purpose of a maintenance management system is to record information about maintenance activities performed and resources expended.

Typical features of a maintenance management system include:

- 1) Development of an annual work program
 - a. Defining work activities
 - b. Establishing work quantity planning values
 - c. Establishing maintenance performance standards
 - d. Conducting a road inventory and inspection
 - e. Estimating the size of the work program
- 2) Budgeting and allocating resources
- 3) Work authorization and control
- 4) Scheduling
- 5) Performance evaluation
- 6) Fiscal control

9.2.3 Machinery and Devices

Maintenance machinery will be divided into installed devices, patrol vehicles, vehicle weight scales, axle load scales and miscellaneous devices for tollway maintenance works and traffic accidents. Table 9.2.1 shows the number of major vehicles per operation office of the Japan Highway Public Corporation in 1988. The vehicles concerned with snow, ice and tunnel are omitted.

The maintenance length for each operation office is around 50-80 km. Assuming this as the case a minimum of two operation offices are required in this project. The operation offices are recommended to be established at Subang and Dawuan Interchanges.

	Control	Control		-			Tyn	a nf	Mai	ntor	ance	v	eh i	CIA					ويطوعها ويلد طوخطون	-	
Bureau	Office	Length	Pa	trol	& M	ainte	1,7 Pi		eani	ng		Ť		beci	al W	ork		True	ck		lotal
		(Km)	A	B	1 C	D	E	F,	G	Ĩ	П,	1	<u>J</u>	18,		<u>M</u>	<u> N</u>	0	<u> P</u>	0	Number
		57.9	.4 1	4	1	0		0	· .]	1	. U	;	1. U	1	1	. 1		יט מי	U D 1 5		32
י. זיצט~1		40.4	2	4	2	Ŭ.	1 i	0			Ű	í I	1	i	1	1		ŏ.	οĭ	17	22
	4	54.0	3	ż	4	1	Ĩ	Ō	Ī		, Q		Ō	1	1	0		0 0	0 1	7	23
	5	49.3	3	2	4		2	0	1	() (<u></u>			0	+		$\frac{1}{1}$ $\frac{1}{12}$	5	18
	lotal	1 251.1 511 9	15	- 15	<u>16</u>				4		4					1		1.7	$\frac{1}{1}$ $\frac{12}{5}$	40	23
		65.2	2	4	2	o i	2	ŏ				İ	Ĩ	Ő	1	i		Ô	0 4	5	24
	i i	49.5	2	1	3	1	2	1	(1) (ļ	0	0	1	0		0 (05	4	20
TY0-11	4	48.8	2	3	3	0		0	1)	1	0		0			04	6	25
	ר ה	1 Z9.6	2	2 9	Z A	1	Z 9	1	ւ Ո) U 1		1	0 0) ()) 1	י ני 1		0 1	02	45	24
	1 7	58.7	2	ź	3	Ö.	2		i õ	;) Î		Ó	ŏ	i d	i ĭ		Ŏ	Ő Ž	4	16
	8	70.2	2	2	3	1	2	1	0		0		1	. 1	1	0		0 (0 4	6	25
	Fotal	426.8	$\frac{17}{5}$	<u> 19</u>	<u>23</u>	4	16]		1			;		<u> </u>		2 ($\frac{1}{29}$	38	- 174
		40.4	2	J 4	2	1	3	0			1		1	1	. 1 1	0		0	19	6	32
TYO-J11	ไ วั	58.2	2	4	ž	Ô	3	Ĭ	õ) Ó		ŏ	Ō	i õ	Ō		Ō	õ ĝ	5	26
	1	39.4	2	2	2	0	1	0	1		0]	6	0	1	1		0 (04	4	
	5	54.5	2	2	3	1	2	1	() () <u>1</u>		1	0		1 U 1 A		11 U N N	U 4 N 10	4	61 27
	rotal	$\frac{40.9}{113.6}$	$1\frac{2}{2}$	- 17	15	<u>j</u> -	14	12	2			it.	-2		4	Ť	1-	0	$\frac{10}{140}$	30	151
	T	42.3	2	1	4	0	3	0	1	() (1	1	1	0		0 (01	7	22
	2	60.4	2	2	3	6	4	0					0	U C	9 ()) (3 U 1 0		U U 1 /	83 05	8	23
		4Z.1 68.2	2	ו. מ	រ 5	. U	22	1	ւ 1) () (1	1	1	, u 1	, o		1 (02	5	45
	5	43.4	1	3	ĭ	ŏ	4	Ō	1) (j	Ō	Ō	Ô	i Ö		i (ō ā	5	26
	6	48.9	1	1	4	0	2	1	0) () (0	0	0	0		1 (0 4	4	18
NAGOYA		52.3	2	3	4	. 8		0			i 2) 6		1	2		F U 1 0		U U 0 (13 - 14 10 - 14		30
		40.0 58.6	3	2	2	1		1		; ;) (3 I	0	1	, 0	0		0 1			31
	10	22.2	2	ារី	ž	Ô	ĺî	- Ô	Ŏ	i i	i č	j	õ	Ō	i Ō	Ō		Ō (0 4	3	13
	11	86.0	2	2	3	0	3	1	0		0		1	0		0			04	5	23
	12	19.1	1	- <u>-)</u>	<u>- 2</u> - 26	- 10	1	<u>ប</u> ភ					<u>1</u> 5	- <u>1</u> 6	10			<u>u</u> 5 ($\frac{3}{1}$ 55	61	$\frac{11}{293}$
		1304.1	- 4	1	6	- 0	- 2	<u> </u>		i	i t	ίt	Ť	ΞĬ	Ž	Ö	Ť	Ď	<u> </u>	7	29
	2	48.9	2	0	4	1	1	0	1		0		0	0	0 (1 (6	19
aar	3	66.2	2	1	4	0	2	0	0		เป		1	1	ι U ι 0	U U		9 I A (J D N K	.5	20
USAKA	4 5	175.5	. 3	3	- J - 1	1	1	0	1 U			i i	1	Ŭ		i Ö		0 0	DI	4	16
	6	27.3	2	ì	2	Ō	i	Ő	1		. Ő) į	î	1	Ō	1		0 0	0 2	2	15
	7	25.1	1	1	2	0	1	1	0) (0	1	0			0 (2	10
	8 B	31.0	10	<u> </u>		- 1	12	<u> </u>	<u> </u> 			<u>'</u>	<u> </u>	0	2	U 3		<u>u (</u> 1 ($\frac{J}{22}$	$\frac{3}{33}$	145
	ινιαι	1 396.3	10		29		16	<u></u>				·						Å`	<u> </u>	100	
				T	уре	of Ve	hic	les				М	ai.	jor	work	s					
		Note:	Å	Com	nuni	catio	n c	ar		Pa	rol,	: 11	less	sage	rel	ay					
			Մ Ռ	Pati	r01 nton	car	~~ 12	~		- Fa - Lou	TUL,	1 in	nst n s	nd and		nvie	ion	of	ronair	aro	35
			L N	Mai	nten	ance	car car	(R)		Ine	inect	tin	א טי הוו	and -	SUPE	rvis	ion	of	repair	are	as as
			r F	Sor	inkl	er	GUI	(0)		Roa	id cl	lea	nir	ng	0070		1011	01 1	or or a rest	~	
			F	Road	d s₩	eeper	(A))		Roa	id cl	lea	nir	ng							
			G	Roa	d sw	eeper	(B)		Roa	id c]	lea	nir	ng							
			11	Jet	Cle	aner	-			Cle	eanin	Ig	of	exp	oans i	on j	oin	ts ai	nd dra	in p	ipes
		•	I	Oth	er C	leane	r			Cle	eanin	Ig									
		· ·	J	Bear	n li	fter				Ma	inter	nan	ce	of	ligh	iting	ap	parat	tus	• .	
		1	K	Lif	t .					Roa	ud si	gn	IS a	and	Culv	ert		ntena	ance,	10SP	ection
			ե	Mul	t1-p	urpos	e ti	ruck		MON	nng	01	gi	rass	MOW	ring	UI .	sras:	s and	htay	1118
			Mi Mi	111S(T		aneou:	s \			5p6	eciai	i₩ vr+	OCK ati	15 ion							
		i	nt Di	11/10 Trouv	ск (- 6-7-	11Kfit zadiu	/ ጠነ			i Li לימים	nsha Usha	n t rt	a.u ati	ion							
			D D	Tru	un (l ek C	acuiu Iaree	π7 }			Tre	nspo	n t Srt	ati	ion							
		ļ	9	Sig	n pl	ate ca	ar			Tra	ffic	e r	egu	ilat	ion	at w	ork	area	as and	acc	idents

 Table 9.2.1 Example for Stationing of Maintenance Vehicles in Japan

As there will be a difference in conditions compared to Japan, for example, advanced information devices such as variable message signs and monitors, or a high ratio of old vehicles unfit for long distance and high speed travel, patrolling should be increased. The appropriate stationing of vehicles and personnel should be considered in order to quickly relay messages, provide effective service to drivers and quick removal of traffic obstructions.

The types and number of vehicles to be provided at each control office are recommended as shown on Table 9.2.2.

	Subang	Dawuan	
Communication car	3	3	
Patrol car	4	4	
Maintenance car	4	4	
Sprinkler	0	1	
Road sweeper	1	1	
Jet cleaner	0	11	
Beam lifter	1	0	
Lift	1	0	
Truck (medium)	2	2	
Sign plate car	5	5	
Water tank truck (for plants)	1	1	

Table 9.2.2 Required Maintenance Vehicles

9.3 Traffic Control and Information System

9.3.1 General

Traffic control and information service is vital in monitoring safe and smooth traffic flow regardless of weather or traffic conditions including the following key activities:

- Traffic regulation (volume, speed, weight);
- Information collection and dissemination;
- Accidents and congestion monitoring; and
- Facility security

Control, largely exercised by traffic police, includes monitoring of speed and driving behavior to ensure a safe operating environment.

Traffic information facilities are expected to require sophisticated treatment in future particularly as volume on key demand sectors approach saturation capacity. Closed-circuit television, radio broadcasts, variable-message boards and loop-type traffic detectors will, in all likelihood, be desirable in future.

The installation of roadside emergency telephones at approximately two kilometer intervals will serve as a valuable aid in enhancing para-medical services and removing disabled vehicles.

9.3.2 Staged Installation of Control Devices

Traffic control and information devices are generally categorized as shown in Fig. 9.3.1.

The basic traffic control devices should be provided in the initial investment stage. In order to economize the initial cost the advanced devices should be installed depending on the traffic volume and needs raised through the tollway operation.

In the initial stage, however, patrol activities should be enhanced to substitute for the advanced traffic control devices and assure the collection and dissemination of traffic information as well as other tollway environmental factors.



Fig. 9.3.1 Traffic Control and Information Devices

CHAPTER 10. PRELIMINARY DESIGN WORK

CHAPTER 10. PRELIMINARY DESIGN WORK

10.1 General

Based on the determined design standard as described in paragraph 7.4, the preliminary design is carried out for the selected optimal route which is described in paragraph 8.7.

10.2 Alignment Design

10.2.1 Basic Data

1) Aerial Photographic Survey and Topographic Maps

As described in the Interim Report, an aerial photographic survey including ground control survey was completed in October 1988.

Based on the aerial photography, plotting works at a scale of 1:5,000 for topographic mapping was conducted by PT. AEROKARTO INDONESIA under supervision of the survey team.

The work was completed in July 1989 and the area covers 840 km^2 with 282 models and 117 sheets.

The products of the topographical mapping are as follows:

- Aerial photograph (2,100 km², 1:20,000),
- Uncontrolled mosaic sheets $(2,100 \text{ km}^2, 1:25000)$,
- Topographic map (840 km^2 , 1:5,000) and
- Data and survey results of aerial photography, ground survey and cartography.

2) Soils and Materials Survey

A soils and materials survey was carried out along the length of the proposed tollway in the period from October to December 1988 to provide information and data for earthwork, pavement, structural work and other items for the tollway.

Machine boring, Dutch cone penetration tests, test pits, laboratory tests etc. were carried out by P.T. WIRA NUSANTARA and a summary of the results was included in the Interim Report.

10.2.2 Route Locations

1) General

The proposed tollway is approximately 142 km in length starting from the end point of the Jakarta-Cikampek Tollway and connecting with national road route 013 ten (10) km east of Cirebon city. A total of seven (7) interchanges is planned in the initial stage of construction and eleven (11) at the final stage. Two service areas are considered for tollway users in the Subang area and south of the Cirebon area. Taking into consideration proper amount of construction volume and economical distribution of earth works, tentative construction sections and packages are set up as follows:

Package A: Cikamp	oek I.C Suba	ng I.C.	L = 37.5 km	
Section 1	STA. 92.5	- STA. 109.5	L = 17.0 km	
Section 2	STA. 109.5	- STA. 130.0	L = 20.5 km	
Package B: Subang	I.C Dawuan	I.C.	L = 52.0 km	
Section 3	STA. 130.0	- STA. 149.5	L = 19.5 km	
Section 4	STA. 149.5	- STA. 162.0	L = 12.5 km	
Section 5	STA. 162.0	- STA. 182.0	L = 20.0 km	
Package C: Dawuan I.C East Cirebon L = 52.8 km				
Section 6	STA. 182.0	- STA. 194.0	L = 12.0 km	
Section 7	STA. 194.0	- STA. 208.0	L = 14.0 km	
Section 8	STA. 208.0	- STA. 222.0	L = 14.0 km	
Section 9	STA. 222.0	- STA. 234.8	L = 12.8 km	



2) Route Description

a) Package A (Cikampek I.C. - Subang I.C.)

In accordance with the regional structural plan of West Java Province, Cikampek is a development center in Purwasuka region and a connection point with the existing provincial road between Cikampek and Bandung. Large and medium industries are planned to be located along this provincial road in Cikampek and Jatiluhur areas. Jatiluhur area has high potential for tourism development.

The proposed alignment of the tollway passes through gently-sloping areas with the incline of less than 8 percent and plantation areas and paddy fields from Cikampek to the northern areas of Subang.

Subang is one of the sub-development centers of the Purwasuka region which has high potential for plantations, fishery and small home industry development. The alignment is selected to avoid physical and social constraints such as sparsely located villages, rivers, schools, mosques, etc.

Cikampek Interchange was designed according to the planning concept prepared in the Jakarta-Cikampek Project. The existing toll gate becomes unnecessary after completion of the throughway toll barrier.

A trumpet type interchange with single structure is designated for Subang and Kalijati Interchanges. The ramp terminals for both interchanges are located on the south side of the proposed tollway connecting provincial road (076) and Kabupaten road (07) respectively due to future traffic movements.

b) Package B (Subang I.C. - Dawuan I.C.)

The alignment runs through flat and partly gently-sloping areas near Sungai Cipanas when the land is used for paddy fields, forest and plantation.

Although there are no significant towns and obstructions for alignment selection, the route was plotted with such constraints as scattered villages, rivers, local roads and narrow gauge railway tracks.

10 - 4

Haur Selatan and deferred Cikedung interchanges are planned to be connected with the Kabupaten road (6) and the provincial road (074) respectively by trumpet pattern. Around the end of the area in this package, the route crosses Cimanuk river the largest meandering river in this project area, then connected with Dawuan city which is the most highly expected development sub center in Cirebon influenced areas and connection point with the existing national road (023) between Cirebon and Bandung.

Additionally, the tollway in this section is expected to give an impact for regional development by the reason that no existing parallel road with the tollway is found in this area.

c) Package C (Dawuan I.C. - East Cirebon I.C.)

The route in this section runs through well irrigated paddy field and is located along the north side of the national road (023) from Kadipaten to Palimanan. And the alignment passes through flat areas avoiding the built up areas developed for residential and industrial proposes. In Plumbon area, the route swings east south, crosses over the national road (024) and proceeds to the provincial road (067) providing under pass. Then the alignment swings east through the gently-sloping areas near situ Patok Lake and goes through the terminal point of the project.

This region is intended to develop in balance with the growth of Jakarta and is to function as a transport junction of Jakarta, Bandung and Central Java. In addition, the region is expected to grow up as a center of industrial, commercial and agricultural development.

10.2.3 Geometric Design Standard

1) General

The geometric design standard for the tollway was established through meetings held at the time of the Interim Report and at the commencement of Phase II Study.

2) Design Speed

Since the terrain is flat except for part of the route near Cikampek and Cirebon areas in the project corridor, a design speed of 120 km and 100 km is used for tollway carriageways in flat and rolling areas respectively.

The following design speeds are applied to the various types of roads related to this project:

-	Tollway carriageway	120 - 100 km/hr
-	Interchange loops	40 km/hr
-	National highway	80 km/hr
-	Provincial road	80 km/hr
-	Kabupaten road	60 km/hr

3) Lane Width

No modification or change is made to the current government standard of 3.60 m.

4) Shoulder

The government standard of 3.00 m and 1.50 m are adopted for outer shoulder and inner shoulder respectively.

5) Median

A minimum width of 5.00 m is considered sufficient allowance for the construction of piers of flyover bridges and drainage structures.

6) Crossfall of Carriageway

For quick drainage of surface rain water, a crossfall of 2.0% for flexible pavement and 2.5% for rigid pavement is adopted for both the tollway carriageway and interchange ramps.

7) Others

Based on the design speed adopted, other design criteria and elements such as sight distance, horizontal curvature, vertical alignment, super elevation, etc. are determined by following government standards.

10.2.4 Alignment Design

1) General

As part of the Trans Java Tollway, the alignment design was based on the following basic planning concepts:

- to accommodate traffic safely under high speed operation,
- to prepare a comfortable driving environment for tollway users,
- to maintain a combination of horizontal and vertical alignment and
- to provide economical distribution of earth excavation and embankment works.

2) Horizontal Alignment

From a technical and socio-economic point of view as detailed in the Interim Report, the selected route was defined on the topographical maps (1:5,000 scale) developed and confirmed by supplemental field survey.

The following major factors are considered in setting up the horizontal alignment.

- to provide horizontal alignment with gentle curvature reflecting the flat terrain conditions,
- to shift the alignment to the most suitable distance to the built up areas and development centers in the proposed interchange areas,
- to arrange right angle crossings as much as possible at river sites,
- to avoid as much as possible public facilities, factories and buildings and
- to avoid parks, playgrounds, golf courses and cemeteries.
- 3) Vertical Alignment

The vertical alignment is attained considering the following constraints:

- to maintain local activities and communications by provision of box culverts or over passes based on comparative study of both alternatives,
- to keep a minimum embankment height of 2.0 m above existing ground in paddy fields for pipe culverts.
- to provide necessary vertical clearance for roads, rivers and narrow gauge railway tracks, and
- to provide over passes for existing roads over the tollway for grade separation, in principle, to maintain flexibility for future development at the road crossing. This is in consideration of economy and ease to adapt to any future social and regional changes in the area.

10.3.1 General

The location and type of interchanges are decided on the basis of future traffic movements and socio-economic conditions in the project area as listed in Table 10.3.1.

Interchange			Road to be
Initial Stage	Future Stage	Туре	connected
Cikampek		Single Trumpet	Province road Route 080
Subang	Kalijati	Single Trumpet	Province road Route 075
Cikedung	Haur Selatan	Single Trumpet	Kabupaten road Route 015
Dawuan		Single Trumpet	National road Route 023
Palimanan	Sumberjaya	Single Trumpet	Province road Route 025
Cirebon	West Cirebon	Single Trumpet (+ grade separation intersection)	Province road Route 067
East Cirebon		(Single Trumpet)	National road Route 023

Table 10.3.1 Interchange List

Note: () shows future plan

In the case of the closed tollway system the trumpet type is suitable for interchanges. As shown below, trumpet type can be A type or B type depending on which direction forecast traffic volume predominates.







B Type

The accident rate on tollways is overwhelmingly high for interchange sections, so it is not proper to apply the alignment standard of throughway to interchange sections. In addition to the geometric design criteria proposed in 10.2.3 we would propose criteria for interchange sections in accordance with the criteria of Japan Highway Public Corporation as follows:

Description		Design Speed of Throughway		
		120	100	80
Horizontal-curve Radius (more than m.)	standard special	2,000 1,500	1,500 1,000	1,100 700
Minimum Vertical-curve Radius Convex Type (more than m.)	standard special	45,000 23,000	25,000 15,000	12,000 6,000
Minimum Vertical-curve Radius Dent Type (more than m.)	standard special	16,000 12,000	12,000 8,000	8,000 4,000
Gradient (%)	standard special	2 2	2 2	3 4

Table 10.3.2 Geometric Design Criteria for Interchange Section

10.3.3 Major Points for Design of Interchanges

1) Cikampek Interchange

Cikampek interchange has been partially constructed by Jakarta-Cikampek project, which has already been opened. The partial construction includes the ramp-way 1210 and the toll plaza and office. The remaining facilities will have to be completed as the starting point for this project.

However, the longitudinal alignment for this interchange has been decided under conditions which are not applicable to the above standard. Namely it is designed such that the traffic from the Cirebon direction which will flow into provincial road Route 079 through a loop type off-ramp shall approach the ramp along a tollway section of grade 2.7% (more than the 2.0% standard).

The future Cirebon bound carriageway is at present temporarily operated as a twolane two-way tollway, therefore, longitudinal modification will be possible at the time of the forthcoming additional construction for the Cikampek bound carriageway.

As modification of the present Cirebon bound carriageway will be difficult due to the longitudinal slope of throughway around this area, two grade separations of the adjacent railway and provincial road create vertical control points, the longitudinal grade of the Cikampek bound carriageway as it approaches the loop type off ramp should be modified so as to eliminate the dangerous situation of traffic flow exiting from carriageway via the ramp.

However, if such a longitudinal separation is adopted, a retaining wall of height 4 meters and length 200 meters must be provided within the planned narrow median.

This is beyond the scope of this project. Furthermore, the estimated traffic volume on this ramp is small, therefore the design criteria of interchanges will not be applied for the Cikampek interchange in this study. It shall be reviewed at the time of the detailed design stage.

2) Subang Interchange

Subang interchange is connected with the provincial road Route 076 about 4 Km from Subang city center. The interchange will serve the connections between the tollway and Subang-Bandung to the south and Pamanukan to the north.

In addition to the necessary facilities for the interchange, operation and maintenance offices should be built at this interchange. Two offices will be required for the operation and maintenance of the Cikampek-Cirebon tollway which has a length of approximately 142 Km.

The tollway shall be roughly divided into equal maintenance and operation sections with each office located midway on the section which it shall be

10 - 11

responsible for. The office staff may therefore reach any location for operation or maintenance purposes in the shortest time. Thus the offices should be built at suitable sites near STA. 130 and STA. 200.

Subang city is the second largest city in the project area, and labor and material may be easily obtained there. The location of the interchange is STA 129 + 400 and the tollway operation and maintenance range is 37 Km to the west and 30 Km to the cast up to Cikedung interchange, which is well balanced.

3) Dawuan Interchange

Dawuan interchange is connected with the national road Route 023 by the right bank of Cimanuk river and will serve Kadipaten and the route towards Bandung.

Kadipaten is expected to show the greatest development of the towns within the sphere of influence of Cirebon, and will be a sub-center of Cirebon city.

The distance between this interchange and the national road Route 023 has to be as long as 4 Km because the location where this tollway crosses Cimanuk river is restricted by the meandering river and the land use conditions, and because of the balance of the alignment.

An operation and maintenance office as mentioned in paragraph 2), will be constructed at this interchange. The range allotted to this office will be up to 23 Km to the west and 53 Km to the east.

Although there is an imbalance between the east and west sections the office location is determined taking into consideration the early partial opening between Cikampek and Dawuan inerchange.

4) Cirebon Interchange

Cirebon interchange is connected with provincial road Route 067 and serves the city center of Cirebon to the north and Kuningan town to the south.
To avoid construction of a long embankment section and the problem of insufficient embankment material, the excavation type is adopted for Cirebon interchange.

In consideration of the increase of traffic volume related to the establishment of the interchange, the provincial road is recommended to be widened to 4 lanes for 3.1 Km between the interchange and Cirebon bypass.

Initially, the crossing with the provincial road should be an at-grade intersection, however, considering the fact that a grade separation will be necessary in the future, the site area should be secured in advance.

5) East Cirebon Interchange

This interchange is to be connected with the national road Route 013 at the eastern suburbs of Cirebon. This connection point is the terminus point of the project. The interchange will serve Cirebon as well as routes towards Central Java and East Java.

The ramp way of the East Cirebon interchange should not be completed until the extension of the tollway to the east is completed, thus partial construction as in the Cikampek interchange will be adequate. The off-ramp will have two lanes used for both entering and exiting traffic. The access road from the toll gate to the national road crosses the railway, however there are only 12 shuttle trains/day, therefore, for the estimated traffic, at-grade intersection will be adequate to begin with. Grade separation will be considered in the future according to the number of trains using the railway and traffic volume on the access road.

10.4 Service Area and Parking Area

10.4.1 General

In such restricted areas as the roadside of an expressway, facilities meeting the physiological needs of the drivers and facilities providing refueling, water supply and maintenance services for vehicles are required to ensure safe and comfortable journeys and for quick and economical transportation. As the lengths of the existing tollways in Indonesia are short, these facilities are not installed yet. For the future extension plans of the tollway, a standard for the installation of these facilities is being planned by Jasa Marga, however, for this preliminary design, the standards of the Japan Highway Public Corporation will be used.

10.4.2 Intervals of Service and Parking Areas

Service areas are facilities which provide sufficient services to meet the needs of drivers and vehicles. Facilities for personal use include parks, public lavatories, restaurants, stores, and mosques. Facilities for vehicles include parking lot, gas stations and service stations.

Parking areas should be installed to meet the physiological needs of the drivers as the minimum required facilities to remove fatigue and tension of the driver: parking lot, public lavatories, and stands.

The standard intervals for locating service and parking areas according to the Japan Highway Public Corporation are as follows:

Intervals for each area:	15 - 25 Km
Intervals for service areas:	50 - 100 Km

Service areas require large facilities, thus increasing the construction and maintenance costs and the demand for such facilities is greatly influenced by the amount of traffic volume, landscape, objective of traffic, habits and the country's state of affairs.

Considering these facts, the location of a service area was decided upon near STA. 111 + 500, which is a suitable site if the maximum 100 Km interval is used.

(The above interval standards may be observed even if a service area is not set up along the present Jakarta-Cikampek tollway.) (The distance from Jakarta interchange is 92 Km.)

Another service area should be constructed near STA. 227 if the tollway is extended further east of Cirebon. Parking areas should be set up based on the above interval standards, and the locations are shown in Fig. 10.4.1.

10.4.3 Scale and Required Facilities

The scale of facilities will depend on the designed traffic volume forecast for the next 10 years after opening the tollway, and the past facilities utilization records, although it should be noted that the facilities utilization rates for new roads are difficult to estimate because they vary depending on the nature of the route, objective of traffic, habits, religion, season, and day of the week. The size of the parking lot should be decided according to the estimation of the daily traffic volume and the percentage of large vehicles.

The standard size of parking lot to meet with the traffic volume will accommodate 65 passenger cars and 35 large-sized cars. Further expansion of the parking lot and facilities will be conducted in stages according to the extent of use.



10.5 Throughway Toll Barrier

10.5.1 General

The Indonesian authority intends to implement and operate the project tollway separately from other connecting tollways, thus, accounts should be settled separately for each different project section which will be managed by a different agency. This project concerns the tollway which makes up part of the road network system in Java Island. A throughway toll barrier should be set up at both ends of the project.

10.5.2 Location

The throughway toll barrier is a facility for stopping traffic, thus it is of a contradictory nature to roads that are meant for the smooth flow of traffic. Therefore, the following points should be considered for the installation location and design:

- 1) It should not endanger traffic safety.
- 2) It should be easily seen from a distance.
- In order to avoid traffic congestion an adequate number of lanes should be provided for peak times.
- 4) The toll gate area should be in a flat and straight area.
- 5) Traffic control and toll service should be carried out efficiently and expediently.
- 6) Electricity supply should be available nearby.

The location of the throughway toll barrier was decided at STA. 104 + 500 between Cikampek and Kalijati interchange taken into account the above mentioned points. If the tollway is extended further east of Cirebon, another barrier should be installed between the other end of Cirebon and East Cirebon interchange.

10.5.3 Scale and Required Facilities

Considering the points mentioned below, the number of lanes at the throughway toll barrier was decided upon as 11 at the initial stage, and should be increased to 16 in the future.

- Design hour volume (DHV) of the barrier section, which is applied for the initial stage, was derived from the estimated traffic volume in 2008, that is 10 years after the opening of tollway operation.
- 2) As a result the design hour volume (DHV) of the barrier section resulted in 3000 vehicles/hour.
- 3) The average service time will be 6 seconds at the entrance and 14 seconds at the exit.
- 4) The service standard was measured by the average number of waiting vehicles, which was assumed to be one vehicle for this calculation.

Required facilities in the throughway toll barrier are as follows:

- 1) Toll Facility (Toll Plaza, Toll Gate, Equipment)
- 2) Offices
- 3) Police Box and Watch Box
- 4) Power Supply Facility
- 5) Water Supply Facility (Water Tank, Water Tower, Pump House)
- 6) Lighting Facility
- 7) Landscaping

10.6 Structural Design

10.6.1 General

Based on the design concept of economy, ease of construction, construction period and aesthetics, preliminary structural designs for bridges, culverts and retaining walls were conducted to establish standardization of structural types.

The loading specifications of Bina Marga used for the design of structures are as follows:

- Loading Specifications for Highway Bridges, No. 12/1970, by Bina Marga
- General Explanation and Interim Guide for using Loading Specifications for Highway Bridges, No. 12/1970, 1974, by Bina Marga
- Explanation and Supplementary Specifications of Loading Standards for Highway Bridges No. 12/1970, February 1977, by Bina Marga.
- Revision to the Loading Specifications 1980, Bina Marga Draft.

Other design criteria such as materials and basic strengths, and allowable stresses were discussed in the Interim Report.

10.6.2 Standardization of Bridges

A comprehensive study was made to establish standards of structure types for throughway bridges and over bridges.

The span length of bridges was determined by relating span length and bridge type construction requirements with environmental and aesthetic requirements. The substructures of throughway and over bridges are of reinforced concrete piers of aesthetic appearance.

The foundation type is determined by subsoil conditions and economic criteria.

The structures are as follows:

-	Superstructure	:	PC hollow slab
			RC hollow slab
			PC continuous box girder
			•
-	Substructure	:	Column type
			Wall type
-	Foundation	:	Precast PC Pile
			Precast RC Pile
			Steel Pipe Pile









10.7 Hydrology and Drainage

10.7.1 General

In order to determine formation level of tollway gradients and location and size of tollway crossing structures, results of the hydraulic study as discussed in the Interim Report were used.

In this preliminary design, based on examination of the developed topographic maps (1:5,000 scale) and site investigation, the following major check points were studied:

- Bridge location
- River or channel width for bridge design
- Clearance between bridge and high water level of rivers

10.7.2 Rivers

The main rivers in the project areas listed below originate in the southern mountainous areas and flow down to the Java Sea.

Over crossing structures of rivers were designed to keep a clearance of at least 180 cm and 120 cm for 50 and 100 year storms respectively.

ſ	N	Otation	T and with	Catchment Area	Discharge	Flood Level
	Name	Station	Length	(km ²)	(m ³ /sec.)	(m)
·						
	Cilamaya	STA. 102	47	151	136	2.5
	Cibodas	STA. 120	24	73	103	3.5
	Ciasem	STA, 120	37	167	176	4.5
	Cilamatan	STA. 139	35	164	179	2.5
	Cipanas	STA. 161	29	75	93	1.5
	Cimanuku	STA. 181	294	2436	644	3.5
	Cikeruh	STA. 190	27	131	170	3.0
1	Ciwaringin	STA. 199	26	60	80	4.0
į	Ũ					

Table 10.7.1 River Characteristics

In the knowledge that the proposed alignment runs through upland areas of technical irrigation and semi technical irrigation areas with many irrigation canal crossings along the proposed tollway, careful attention was paid to maintain the existing conditions of irrigation canals.

10.7.4 Waterways

The existing waterways based on Indonesian Standards were classified on analysis of topographical data and field investigations as follows:

- Drainage: Rivers (major, minor and local)
- Irrigation: Canals

The classification identifies where bridges, box culverts or pipe-culverts are used.

10.7.5 Roadway and Roadside Drainage

In the course of the study the basic policy for roadway and roadside drainage was considered:

- To avoid discharging the road surface water into irrigation canals,

- To maintain the existing water usage in local areas and
- To design median run-off by median channels of earth, mortared rubble and U-ditches following the conditions of horizontal and vertical alignment.

10.8 Pavement Design

10.8.1 General

Based on the comments arising at the progress report meeting in August 1989, the preliminary design has been reviewed and finalized as follows:

10.8.2 Pavement Design

In the progress reporting period a comparative study was made of the following elements of rigid and flexible pavement:

	Rigid	Flexible
Service life time	Longer	Shorter
Construction works	Fair	Easier
Maintenance works	Difficult	Easier
Construction period	Longer	Shorter
Sensitivity to overloaded vehicles	Smaller	Bigger
Comfortable riding	Fair	Better
Material	Cement	Asphalt
	(National Production)	(Imported material)

In addition to the above evaluation a cost comparative study was conducted to select the pavement type.

10.8.3 Cost Comparative Study

1) Initial Construction Cost

Cost estimates of pavement works were prepared with reference to unit prices obtained from recent similar projects.

Tables 10.8.1 and 10.8.2 detail the construction cost of rigid and flexible pavement respectively.

Description	Unit	Quantity	Unit Price (Rp.)	Total (Rp.)
Subgrade preparation	m ²	100	150	15,000
Cement treated sub-base	m ³	10	40,000	400,000
(t = 10 cm)				
Portland cement concrete slab	m ³	27	115,000	3,105,000
(t = 27 cm)				
Total	m^2	100	· · · · · · · · · · · · · · · · · · ·	3,520,000
Unit Price	Rp./m ²			35,200

Table 10.8.1 Construction Cost Estimate of Rigid Pavement

Table 10.8.2 Construction Cost Estimate of Flexible Pavement - Initial Stage

Description	Unit	Quantity	Unit Price (Rp.)	Total (Rp.)
Subgrade preparation	m ²	100	150	15,000
Aggregate subbase (t = 27 cm)	m ³	27	25,000	695,000
Asphalt treated base (t = 15 cm)	ton	35.25	41,000	1,445,250
Binder course (t = 6 cm)	ton	14.10	47,000	662,900
Surface course ($t = 4 \text{ cm}$)	ton	9.40	55,000	517,000
Prime coat	kg	175	400	70,000
Tack coat	kg	120	400	48,000
Total	m ²	100		3,432,950
Unit Price	Rp./m ²			34,330

2) Maintenance Cost

Maintenance costs were estimated based on "Evaluasi Biaya & Perwujudan Perkerasan Flexible vs Rigid pada Proyek Warung Buneit - Lingkar DKI - Juli, 1987".

Maintenance works are as follows:

for Rigid Pavement

- Patching
- Crack sealing

- Joint sealing
- Joint repair
- Retexturing

for Flexible Pavement

- Patching
- Surface dressing
- Overlay

And the above works are carried out periodically during 20 years.

The total maintenance costs are shown in Table 10.8.3.

Table 10.8.3 Total Maintenance Costs

			(Rp./cm ²)
·		Flexible 1	Pavement
	Rigid Pavement	Overlay in 5 years	Overlay in 10 years
Cost	4,390	26,520	17,840
Present Cost*	680	6,178	3,475

Note: Present value is estimated using 15% discount rate.

3) Cost Comparison

The cost comparison of flexible pavement and rigid pavement over a 20 year life span is shown in Table 10.8.4.

Table 10.8.4 Cost Comparison

	T			Flexible	Pavement	
1	Rigid Pa	avement	Overlay once 5 years		Overlay once 10 years	
	Cost (Rp./m ²)	PV (Rp./m ²)	Cost (Rp./m ²)	PV (Rp./m ²)	Cost (Rp./m ²)	PV (Rp./m ²)
Initial Cost	35,200	35,200	34,330	34,330	34,330	34,330
Maintenance Cost	4,390	680	26,520	6,178	17,840	3,475
Total Cost	39,590 (100%)	35,880 (100%)	60,850 (154%)	40,508 (113%)	52,170 (132%)	37,805 (105%)

Note: PV means the present value of 15% discount rate.

10.8.4 Difference in Vehicle Operating Cost

A rough surface causes relatively high vehicle running cost compared to a smooth pavement.

For the estimation of vehicle operating costs on roads in different surface conditions, the method from "An improved Data Base for Estimating Vehicle Operating Cost in Developing Countries" - TRRL Supplementary Report 223US, by H. Hide - was adopted.

The two cost elements of vehicle maintenance and tyre consumption were considered to be affected by the roughness of road pavement.

- 1) Parts Consumption for Vehicle Maintenance
 - R = Roughness (mm/km)

PC = Parts cost per 1,000 km

VP = Cost of an equivalent new vehicle

K = Age of the vehicle in cumulative kilometers run

- Passenger Car

$$\frac{PC}{VP} = (-2.03 + 0.0018 \text{ R}) \times K \times 10^{-11}$$

• Truck

$$\frac{PC}{VP} = (0.48 + 0.00037 \text{ R}) \times K \times 10^{-11}$$

Bus

$$\frac{PC}{VP} = (0.67 + 0.0006 \text{ R}) \times \text{K}^{1/2} \times 10^{-9}$$

2) Tyre Consumption

Tc = Number of Tyres consumed per 1,000 kilometers

L = Total weight of the vehicle (ton)

Medium and heavy vehicles

$$\frac{\text{TC}}{\text{L}} = (83 + 0.0112 \text{ R}) \times 10^{-7}$$

The roughness of flexible pavement was assumed to be 2500 mm/km and that of rigid pavement to be 10% higher, i.e. 2750 mm/km.

Accordingly, the difference between parts and tyre consumptions on flexible and rigid surface roads are calculated as follows:

- M	laintenance	parts	consumption:
-----	-------------	-------	--------------

Maintenance parts consumption:	Cost on rigid pavement/ Cost on flexible pavement	
Passenger car	1.18	
Pick-up	1.07	
Bus	1.07	
Truck	1.07	
Tyre Consumption:		
Passenger car	1.23	
Pick-up	1.23	
Bus	1.03	
Truck	1.03	

Applying the above ratios to the corresponding equations of vehicle operating cost elements, an increase in cost for using the rough surface (rigid pavement) road was derived per vehicle-km.

Total vehicle-kilometers on the project tollway was estimated already in the traffic assignment phase, and on which basis a total increment of operating cost was derived for each planning year of 1995, 2005 and 2015.

Values in intermediate years were interpolated and the incremental cost stream was prepared over 20 years from 1998, when the tollway was assumed to open to traffic. to 2017.

Based on this cost stream a present value of the increased cost in vehicle operation, when using the rigid pavement road, was calculated using a discount rate of 15%. The total surface area is estimated in the engineering study to be about 2,361,000 m², so that the accumulated present value of vehicle operating cost increases resulted in Rp. $13,010/m^2$.

10.8.5 **Determination of Surface Pavement**

Combining the previously estimated costs for pavement construction and maintenance, and incremental costs for vehicle operation, the difference between rigid and flexible pavement appeared as shown in Table 10.8.5.

Table 10.8.5Comparison between Rigid and Flexible Pavement
by Present Value over 20 Years Period

 $(Rp./m^2)$

	Rigid	Flexible Pavement		
	Pavement	Overlay (5 yrs)	Overlay (10 yrs)	
Pavement/Maintenance	35,880	40,508	37,805	
Benefit from VOC [•] Comparison between Rigid and Flexible Pavement	**	13,010	13,010	

* VOC: Vehicle Operating Costs

As obviously shown in Table 10.8.5, the rigid pavement incurs relatively higher costs from the combined aspects of pavement cost and benefit.

Even from the tollway operator point of view the following can be said, that is:

- The difference of the totaled pavement and maintenance costs is not significant, namely, the flexible pavement is $5 \sim 13\%$ higher than the rigid pavement in terms of present value comparison.
- In terms of construction and maintenance works, there may not be enough experience in the construction of rigid pavement to ensure the required strength and stability. Repairs and retexturing works to rigid pavement are considerable tasks where the need could arise to close one direction of the carriageway.

From a road user point of view, in addition to the above, flexible pavement is more comfortable due to smooth surface dressing and lack of construction joints.

In overall view of the above considerations it is recommended to use flexible pavement for the proposed tollway.

10.9 Tollway Facilities

10.9.1 General

The following tollway facilities are considered for the proposed tollway:

- Road lighting
- Traffic signals
- Traffic signs
- Toll gates and islands
- Other road facilities
- Traffic control facilities

10.9.2 Road Lighting

The highway lighting facilities were designed in accordance with "Toll Road & Bridge Design Manual" May 1985 Bina Marga and PT. Jasa Marga, and supplemented by CIE (Commission International De L'Eclairage), SPLN (Standard Perum Listrik Negara) and PUIL (Peraturan Umum Instalasi Listrik Indonesia).

Road lighting is designed at the interchange areas including ramps, terminals, access roads, parking and service areas.

10.9.3 Traffic Signals

Traffic signals provide for the orderly movement of traffic at grade intersections to reduce the likelihood of collisions.

10.9.4 Traffic Signs

Three kinds of signs are designed, namely, regulatory signs, warning signs and guide signs to assist traffic safety and for the convenience of users.

1) Regulatory and Warning Signs

Regulatory signs and warning signs are directly in accordance with the Government's regulations or traffic laws.

2) Guide Signs

Guide signs convey to drivers information such as destinations and distances, service facilities and route confirmation.

10.9.5 Toll Gates and Islands

The number of booths provided is for the year 2005 and additional booths may be provided later. Refuge islands of standard type provide a foundation for toll booths and protection from approaching vehicles.

10.9.6 Road Markings

Road markings provide traffic safety by lane identification, carriageway edge markings and instructions on the correct lane to use in association with traffic signs and signals.

10.9.7 Guard Rails

The major purpose of a guardrail is to protect uncontrolled vehicles from running off the highway and to protect facilities such as bridge piers from damage by such vehicles.

Guard rails are planned to be installed at the following locations:

- High embankment sections (H > 4.0 m)
- Bridge and box culvert approaches
- Box culvert wing walls and bridge piers
- Guide signs

10.9.8 Traffic Control Facilities

The design of traffic control facilities will be in accordance with the basic policy on tollway maintenance, administration and operation.

10.10.1 General

According to the Japanese standard process of environmental study, environmental factors to be either assessed or measured are established after field work in which the following conditions are shown to be present relating to the respective environmental factors. They are:

1)	Air Pollution:	If housing is present along the planned road.
2)	Water Pollution:	If sewage from service areas and parking areas flows
		construction work is great.
	· · ·	
3)	Noise:	Same as for Air Pollution.
4)	Vibration:	If land subsidence in poor ground areas will cause a
		great impact on the housing around that area.
5)	Land Subsidence:	Same as for Vibration.
6)	Topography/Geology:	If the field study reveals the area to have valuable
		scientific objects or precious natural products.
7)	Vegetation:	Same as for Topography/Geology.
8)	Animals:	Same as for Topography/Geology.
9)	Scenery:	If the project area is designated as a special area by the
		Natural Park Laws, or if it is noted for its natural
		scenery, or if it is designated as a recreational area for
	·	the preservation of the natural environment.

Apart from the environmental factors mentioned above, the following factors will have to be considered: living environment of the inhabitants; separation of the community; regional sewage disposal; securing water resources for the downstream area; groundwater obstruction; dust and siltation during construction work; roads for construction use; borrow pits and spoil banks. Based on the field study results careful selection of the project route made it possible to minimize the impact on the environment.

10.10.2 Results of Field Study of the Project Area

A field study of the project area was conducted with the Indonesian counterpart, and the study revealed that the area did not fall under any of the following categories:

- 1) Areas containing objects of historical, archaeological, religious, artistic or scientific value or precious natural products
- 2) Areas containing useful or scarce animals or vegetation that need to be preserved
- 3) Areas with poor ground where the tollway may incur negative impacts on the existing housing area
- 4) Areas that may have an impact on the natural scenery

10.10.3 Study Results

In order to minimize negative impacts on the environment, criteria for the selection of the project route and miligation measures against negative impact are established as follows:

- 1) Public institution areas should be avoided.
- 2) Cemetery areas should be avoided.
- 3) Irrigation channels should be crossed over at their existing location.
- An embankment road should be applied to rice field areas to allow crossing of small irrigation channels. (minimum 2 meters high for embankment)

- 5) Green preservation areas should be avoided.
- 6) Community separation should be minimized.
- 7) The construction work should be carried out as far as possible away from schools, mosques and hospitals.
- 8) A detour distance, when unifying the existing road by a grade separation, should be made as short as possible.

Even after the above considerations are taken into the regional and route selection studies, the following four problems may still remain unsolved. A detailed field study based on Indonesian environmental standards should be conducted at the detailed design stage.

- 1) Water pollution due to sewage from STA. 112 Kalijati Service Area.
- Alteration of the groundwater level caused by large scale excavation work in the rubber plantation area around STA. 162 Kerta Jati and its effects on the downstream rubber plantations.
- 3) Air pollution and noise in the densely built up areas around Cirebon City.
- 4) Effects of earth, sand and dust caused by the construction on the residential areas and cultivated land.

CHAPTER 11. FORECAST TRAFFIC VOLUME AND STAGED CONSTRUCTION

CHAPTER 11. FORECAST TRAFFIC VOLUME AND STAGED CONSTRUCTION

11.1 Traffic Volume on the Project Tollway

11.1.1 Tariff System

A toll per user kilometer which is assumed to decline as the user travels longer distances, and which is based on the present actual toll levy system was adopted as shown in Fig. 11.1.1.



Tollway Distance

Fig. 11.1.1 Conceptual Tariff System

A regression equation was calibrated using interchange intervals (Km) and corresponding toll rates, and the results as shown below:

a)	Jagorawi	:	y = 142.35771 x X ^{0.831811}
b)	Jakarta-Cikampek	:	$y = 286.61176 \ge X^{0.695307}$
c)	Jakarta-Tangerang	:	y = 89.728416 x X ^{0.996328}

Equation b) was assumed to apply for Cikampek-Cirebon and also Cikampek-Padalarang Tollways: and equation c) also for the Jakarta-Merak Tollway. Conditions of the road links were determined by referring to the latest road inventory data and the data derived from the Study Team's travel speed survey and reconnaissance survey.

Road links incorporated into the network were classified into 7 categories and the Q-V (quantity and velocity) relationships were determined as shown in Table 11.1.1.

Table 11.1.1 Q-V Conditions of Network Links



				· · · · · · · · · · · · · · · · · · ·		
	Road Type	V1	V2	V3	Q1	Q2
1)	Tollway 4-lane	100	60	30	48.000	57.600
2)	Tollway 2-lane	80	40	30	14.000	16.800
3)	4-lane Arterial	70	40	15	44.000	52.800
4)	2-lane 2 way (Wider lane width)	70	40	15	11,000	13.200
5)	2-lane 2 way (About 6.5 m width)	60	30	15	9.000	10.800
6)	2-lane 2 way (5.5, 6.0 m width in flat area)	60	30	15	8.000	9.600
7)	2-lane 2 way (5.5, 6.0 m width in rolling area)	40	25	15	6.000	7.200

Q-V Curve

11.1.3 Assigned Traffic Volumes

The future road traffic volume has been estimated by assigning the future OD traffic (Matrix) to the future road network. The method used for this project traffic assignment is shown in Fig. 11.1.2.

A minimum travel time was adopted as a criterion when selecting possible alternative routes or an optimal one for a particular OD pair traffic.

The future OD matrix is divided into 5 steps of 20% OD Matrix and the assigned traffic volume was estimated separately for "via toll" and "via alternative route".

Link conditions (i.e. link speed) of the road network after the first 20% OD traffic is assigned to the network, and under the altered new conditions the second 20% of the OD traffic is assigned to the network based on minimum time travel routings under each scenario.

A travel time difference between "via tollways" and "via non-tollways" is computed for particular origin-destination traffic under the minimum route search process. Travel distance on the tollway is simultaneously calculated at the route search simulation stage. The distance is used to find the toll to be paid for respective tollways.

Derived travel time difference and the corresponding toll for using tollways are the basis used to calculate a rate of traffic diversion to the tollways. The diversion model applied to the project study has been estimated previously in Section 6.2 and the tariff system was assumed as discussed in Section 11.1.1 above.

The network scenario is composed of the network development in the planning years 1995, 2005 and 2015, which have been previously discussed in Section 5) of 6.3.2; future road network; and "with" and "without" Cikampek-Cirebon Tollway options.



Fig. 11.1.2 Flow Chart for Estimating Future Assigned Traffic Volumes

Numeric results of the assignment scenarios present the projected future traffic volumes on the Cikampek-Cirebon Tollway and imply effects of the project tollway that are to be quantified for testing the economic feasibility of the project.

The traffic volume on the project tollway was based on the OD matrices that were estimated previously by the present pattern method and the gravity method. The OD matrices used for future tollway traffic were those made by the present pattern method for years 1995 and 2005, and those by the gravity method for years 2005 and 2015.

The commencement of the project tollway operation is assumed in 1998, so that the tollway traffic is estimated by interpolating the traffic volumes in 1995 and 2005, which result from the present pattern OD matrices.

The traffic is assumed to grow according to the present pattern projection basis until the project tollway is completed for the entire stretch between Cikampek and Cirebon, since a longitudinal staged construction is considered for the project.

The traffic volume estimated on the gravity model basis is assumed to apply for years after the Cikampek-Cirebon link is completed, because a direct tollway linkage between Jakarta-Cikampek and Cikampek-Cirebon will induce regional development and attract large numbers of traffic resulting in the alteration of the traffic distribution pattern in the influenced region.

The forecast traffic volume is presented in Fig. 11.1.3, where the 1995 volumes are based on the present pattern method and the 2005 and 2015 volumes are based on the gravity model method.



Future Traffic Demand on Cikampek-Cirebon Tollway with All Interchanges Fig. 11.1.3

11.2 Characteristics of Assigned Traffic in the Study Area

11.2.1 User Traffic

The number of project tollway users on average was estimated at 10,422, 38,352 and 74,728 vehicles in 1995, 2005 and 2015 respectively as shown in Table 11.2.1. The higher increase in traffic volume between 1995 and 2005 was brought about by the factor of reduced travel time through the tollway, which was incorporated into the gravity model applied to estimating 2005 and 2015 traffic demand.

The average trip length of the tollway traffic was 75.1 Km, 87.2 Km and 89.2 Km for years 1995, 2005 and 2015 respectively. As tollway traffic increases travel distance becomes longer. The average travel distance covers about $54\% \sim 64\%$ of the total length, i.e. 140 Km of Cikampek and Cirebon.

		Year				
	Tollway Traffic	1995	2005	2015		
(1)	No. of Tollway Users (Veh./day)	10,422	38,352	74,728		
(2)	Total VehKm on Tollway (x1000)	783	3,344	6,665		
(3)	Average Trip Length of Users (Km/Veh.)	75.1	87.2	89.2		
(4)	Average Cross Sectional Traffic (Veh./day) on Tollway with Toll Charge Condition	5,611	24,198	48,160		
(5)	Average Cross Sectional Traffic (Veh./day) on Tollway with Toll Free Condition	17,200	41,000	59,700		
(6)	Average % of Diverted Traffic (%) to Tollway	33	59	81		

Table 11.2.1 Characteristics of Project Tollway Users

11.2.2 Diversion of Traffic to Tollway

The percentage of the diverted traffic to the tollway among potential users, estimated under toll free condition, was 35%, 62% and 85% in 1995, 2005 and 2015 respectively.

The higher diversion ratio in 2015 results from a lack of road density in the study area compared to Fig. 11.2.1 the screen line traffic with road capacity. This means improvement of the network is needed to meet future traffic demand in the study area.

The situation of traffic congestion in the study area is presented in Fig. 11.2.2. According to this congestion map, the alternative routes between Cikampek and Cirebon are saturated with traffic in most cases before the year 2005.

The existing 2-lane national roads between Indramayu and Cikampek; Cikampek and Bekasi are required to be widened before 2005, even if the project tollway is to be constructed as proposed.

If the project tollway is not constructed the traffic on the above roads will exceed the road capacity in the year 1995. Therefore, not only the road widening scheme but also new road construction is urgently required to ease the anticipated traffic congestion in the study area and not to impede the development of region.


11 - 9



11.2.3 Number of Traffic Lanes and Staged Construction

The relationship between the traffic demand and the tollway capacity is shown diagrammatically in Fig. 11.2.3. The tollway capacity was estimated by the Highway Capacity Manual and the resulting road capacity is presented in Section 7.5.

The traffic volume on the tollway almost reaches the capacity of a 2-lane/2-way road in the assumed opening year of 1998. Therefore, the initial stage construction of the tollway should be a 4-lane tollway.

The second stage construction to widen the tollway from 4-lane to 6-lane should be completed before the year 2010 for the Cikampek-Dawuan section and before the year 2015 for the Dawuan-Cirebon section.



TRAFFIC VOLUME

(X 1000 Veh/day)

11 - 12

CHAPTER 12. CONSTRUCTION AND IMPLEMENTATION PLANNING

CHAPTER 12. CONSTRUCTION PLAN AND IMPLEMENTATION PLANNING

12.1 General

In order to establish a construction and implementation plan, efficient identification of construction material resources is of major importance. It is also important to determine details for funding arrangements, procurement of materials/equipment/labor, cost control, etc. The final construction plan and schedule, and breakdown into sections should take into consideration government implementation policy and schedules.

12.2 Construction Sections and Work Volume

Due to the magnitude of the project, the following construction sections are proposed:

- Section 1: STA. 92+500 - 109+500 L = 17.0 Km (Cikampek I.C. - Kalijati S.A.)
- Section 2: STA. 109+500 - 130+000 L = 20.5 Km (Kalijati S.A. - Subang I.C.)
- Section 3:
 STA. 130+000 149+500 L = 19.5 Km
 (Subang I.C. Haur Selatan I.C.)
- Section 4: STA. 149+500 - 162+000 L = 12.5 Km (Haur Selatan I.C. - Cikedung I.C.)
- Section 5: STA. 162+000 - 182+000 L = 20.0 Km (Cikedung I.C. - Dawuan I.C.)

Section 6:
 STA. 182+000 - 194+000 L = 12.0 Km
 (Dawuan I.C. - Sumbrjaya I.C.)

Section 7:
 STA. 194+000 - 208+000 L = 14.0 Km
 (Sumbrjaya I.C. - Palimanan I.C.)

Section 8: STA. 208+000 - 222+000 L = 14.0 Km (Palimanan I.C. - Cirebon I.C.)

- Section 9:

STA. 222+000 - 234+800 L = 12.8 Km (Cirebon I.C. - East Cirebon I.C.)

Since the construction plan is divided into nine (9) sections, the method of haulage, excavation and filling has been considered using a mass curve. Accessibility to each construction area was also considered and quantities for each section were estimated as shown in Table 12.2.1.

Table 12.2.2 shows the quantities of remaining works for the ultimate stage (6-lanes).

Table 12.2.1	Quantity (Initial Outer 4-Lanes)

			PACKAGE A			PAG	AGE B				PACKAGE C			
1701		fre	on Cikasingk	to Supris	Castless 2	from Suba	ng to Davia	<u>n</u>	Casting	from Da	thing to tas	t Circlion	·····	Talal
1164	USTI	Section 1	1 Section 2	Sub Total	SECTION 3	<u>Section 4</u>	Section 5	Sub Tolal	1 26C 11011 0	I Section (1 STA. 208.0	1 SECTION 5	Lefot du?	10(4)
		STA. 02.9	514.130.0	300 10141	STA. 149.5	STA. 162.0	1 \$14.182.0	Jailo Iotai	STA. 194.0	ST4.208.0	STA.222.0	STA.234-8		1
Earth vorks			1	1			1							
Clearing and grubbing	a2	1,292,000	1,610,000	2,932,000	1.287.000	800.000	1,200,000	3.287.000	720.000	\$10.000	910,000	870,000	3,340,000	9.559.000
Common excavation (E-L)	<u>\$3</u>	2,191,000	3.178.000	5.669.000	1,411,000	791.000	1.253.000	3.161.000	22.000	58.000	59,000	1.201.000	1.450.000	3 000 000
Borrow excavation (E-L)	П.5.	1 900 000	161,000	101.000	20,000	720.000	23	200.000	1 200 000	1 221 000	1 131 000	1 166 000	1 950 000	33 227 000
Rautage & (7km)	R.3.	270 000	675 000	035,000	68.000	203.000	1.832.000	2.103.000	1.000.000	11.231.000	0	1.080.000	1.080.000	4.128.000
Bautage B (13Km)	n 3	0	1.620.000	1,620,000	0	0	0	0	1,739,000	Ó	1.432.000	68.000	3.239.000	4,859.000
Haulage C (20km)	n 3	0	0	0	0	Q	0	Ó	0	1.509.000	Q	0	1,509.000	1,509.000
Sodding solid	n 2	166.000	198,600	361.000	191,000	123.000	196.000	510,000	118.000	137,000	137,000	124.000	516.000	1,390,000
Sodding Strip	<u>#2</u>	723.000	910.000	1,663,000	613.000	333.000	511.000	1.572,000	326.000	378,000	447.000	441.000	1.592.000	4.827.000
2 Flexible Pavedent		211 000	272 000	697 000	361 000	232 000	370 000	003 000	222.000	250 000	259,000	231 000	975 000	2 625 000
Agreeale Subase (1=27cm	<u></u>	114.000	135,000	249.000	131.000	81.000	131,000	349.000	81.000	94.000	91.000	85.000	351.000	952.000
Asphalt treated base(15cm	ton	01 900	121.400	223.300	117.500	75.400	120.300	313,200	72.500	81,200	81.300	76.200	317.200	853,700
Binter course (1=6c#)	юл	39,900	47,500	87.400	46,000	29,500	47.100	122,600	28,400	32,900	33.000	29.800	124,100	331.100
Surface course (t=4cm)	ton	28,500	31,500	58.000	30,500	19,600	31,300	81,400	18,800	21,900	21,900	19,800	82,400	221,800
Prise coal	ka.	549.500	652,750	1,202.250	631.750	406.000	647,500	1,685,250	390,250	453,250	453,250	409.500	1.706,250	4,593,750
Tack coal	hg	340.800	405.600	746.400	392,400	252,000	902.000	1.046.400	242.400	280,800	282.000	251,400	326.000	2,852,400
3 Ruidage	ÞΖ	108.000	128,000	230.000	121.000	00.000	121.000		11.000	03.000	03.000	01.000	333.000	
Short soon bridges	Ξž	1.730	1.530	3,270	0	0	2,140	2,149	2.140	3.000	5,660	5,510	16.370	21.780
Nediua span bridges	a2	10.710	16.070	26,780	11.480	6.890	5.360	23.730	3,830	6,120	3,060	6.890	19.900	70.410
Long span bridges	m 2	0	5.200	5.200	0	0	5.200	5.200	0	0	0	0	. 0	10,490
4 Grade separation structure														
Medium span bridges	=2	4.750	9,880	9,630	3.00	2.990	3,250	9,950	2,340	4,200	8,000	9,030	18.120	38,300
Der Bridges (Pedectrian)	22	200		980	390	500	780	1 760	300	590	590	390	1.960	4,700
Roan Bridges Credestriany	a2	õ	i č	0	0	880	0	880	880	880	Ö	880	2,640	3.520
5 Urainage			İ											
V-ditch & Catchbasin	ka	17.0	20.5	33	19.5	12.5	20.0	52	12.0	11.0	14.0	12.8	53	142
Concrete pipe e 100	ē	950	1,500	2,450	240	910	440	1,620	1.260	870	1,620	780	4,530	8,600
Culvert A (3 x 3)	ñ	490	1,190	1,680	890	1.020	50	1,960	<u></u>	400	210	120	1,430	1 270
G Salated Construction	.	<u> </u>	210	210		<u>.</u>	30		ļ			1	<u></u> 002	1.210
Road relocation	Ka	1.3	0.9	2.2	0.2	0.3	0.0	0.5	0.4	0.9	1.2	0.5	3.0	5.7
Road improvement (access)	Kel .	0.0	0.0	0.0	0.0	1.3	0.0	1.3	0.0	7.0	0.0	3.5	10.5	11.8
Road improvement (const.)	Ka	3.5	3.0	6.5	0.0	0.0	2.0	2.0	3.0	0.0	2.0	0.0	5.0	13.5
Nev construction (access)	Ka	0.0	0.0	0.0	0.0	0.0	2.0	2.0	0-0	0.0	0.0	0.5	0.5	2.5
7 discellaneous		4 000		10.500	1 1/2	2 000	4 400	12 400	2 500	5 700	7 200	5 900	22 200	45 100
Gange Ve Peol POU Claire	- <u>P</u>	4,800	20 5	10,000	1,109	3,000	20 0	12,400	12 0	3,100	16.0	12 8	22,200	142 3
Marking	-7	14,000	17.000	31.000	16,000	10,000	17.000	43.000	10,000	12.000	12.009	11,000	45,000	119.000
Signs and Signal	ka	17.0	20.5	38	19.5	12.5	29.0	52	12.0	14.0	11.0	12.8	53	142.3
8 Interchange(exclud bridge)	cach	1	1	2	Ö	1		2	0	1	0		2	6
9 Through ay Toll Barrier	each		0	[]	0	<u> </u>	ļ	<u>0</u>	<u> </u>	<u></u>	[ļ	ļ	i
0 Parking Area	each	<u>Q</u> .	ļQ	<u>Q</u>		<u>, </u>	ļ	8	2	<u>0</u>	2	×	4	12
I Service Area	each	0	I I	I		0	<u> </u>	U 0	<u> </u>	<u>L</u>	<u>I</u>	<u> </u>	1	<u>ال</u>

				-										
			ALCOULCE 1		·	010	RICE B				PACKAGE C			
			PACKAGE A	to Cubang		from Suba	na Ju Dacija	n		fron Da	man to Eas	i Cirebón		1
1704	NH11	Section 1	Section 2	to squarts_	Section 3	Section 4	Section 5	<u></u>	Section G	Section 7	Section 8	Section 9		Total
1101	M 111	CTA 02 5	1 STA 169 5	Sub Tolat	\$11,130.0	STA. 149.5	STA. 162.0	Sub Total	STA.182.0	STA. 194.0	ST4.208.0	STA.222.0	Sub Total	
		sti. 109.5	STA. 130.0	300 10141	STA. 149.5	STA 162.0	STA. 182.0		STA. 191.0	STA.208.0	\$14.222.0	STA 234.8		
1 Farth works			1 augusterse			1								
Clearing and grubbing	2	Ö	0	Q	0	Q	Q	0	0	Q	Q	<u>Q</u> .		
Common excavation (E-L)	#3	Ó	0	0	0	0	0	<u>.</u>	<u></u>	<u>Q</u>	ļ			
Borrov excavation (E-L)	∎3	0	0	0	Q	0		0						
Embankment (Ikm T-C) soil	B 3	0	0	0	ļQ.	<u></u>			<u>y</u> .	[······································	······	
Haulage A (7Km)	<u>n3</u>	<u> </u>	QQ	<u>9</u>	Q.	ļ			·				ň	ň
Haulage B (13Ka)	#3	<u></u>	0	ÿ	<u>0</u> .						ň	ŏ	Ō	ŏ
Haulage C (20Km)	<u>#3</u>					·	·····	ň	ŏ	ň	ŏ	Ó	Ò	Ő
5000108 50110	1.04])×]%)Ö	ŏ	Ŏ	ŏ	Ŏ	0	0	0
2 Clauible Patemont	<u> #2</u>			f		├─── [─]	[×	_	×		r			
Subgrade Prenaration	-2	153,000	182,000	335.000	176.000	113.000	182,000	471,000	107,000	126,000	126,000	114,000	473,000	1,279,000
Jagregate Subhase (1=27cm	3	48,000	57.000	105.000	55,000	35,000	57,000	117.000	33,000	40,000	40,000	36,000	149,000	101.000
Ashalt treated hase (15c	ton	45,300	53,900	99,200	52,100	33,400	51.000	139,500	31,600	37,300	37,400	33,800	140,100	318,800
Binder course (t=6c=)	lon	17.200	20,500	37,700	19,800	12,700	20,500	53,000	12,000		14,200	12,800		143,900
Surface course (1=4cm)	ton	11,400	13,500	24,900	13,100	8,400	3,600	35,100	1,900	9,400	320 500		977 7-0	2 228 250
Prize coat	1.8	267,750	318,500	586,250	308,000	197,750	318.500	824,230	102 200	121 200	121 200	10 100	156 000	1,231,800
Tack coat	18	147,600	175,200	322,800	1/0,400	10 000	20,000	100,000	17 001	5 000	21.000	19,000	78,000	210,000
Seal coat	=2	25,000	30.000	55.000	29.000	10.000	30.000	11,000		21.000	21.000		101000	
3 Bridges								0	0	0	0	0	0	0
Short span bridges	-4				ľ Š	l ă	ů.	Ğ	Ö	Ö	Û	0	Q	Q
Long Suga bridger		·····	ľ.	ľ · · · · · · č	ň	ŏ	ŏ	0	0	0	0	0	0	0
4 Grade separation structure	24		1							l	[
Medium span bridges	2	0	0	Q	Ó	0	0	0	0	0	0	<u>.</u>	0	
1/C bridges	B 2	0	0	Ó	0	0	0	0	0	0	0			
Over-Bridges (Pedestrian)	1 2	0	0	0	0	0	0		<u>v</u>	<u> </u>				······
Roup Bridges	2	0	0	0	0	0	- 0	0	<u>ب</u>	ų <u> </u>	ļ		<u>_</u>	······································
5 Draimage							10.0	51.2	1	13.7	13.7	12.4	51.4	139.0
U-uitch E Catchbasin	Ύē	10.6	13.8	30.3		14:3				6	Ó	0	0	0
Culver 1/2 v 2				IX	<u>۲</u>		ă	ŏ	ŏ	Ŏ	Ŏ	0	Ó	Ō
Culvest B (5 x 5)		,	l ő	ť Š	ŏ	ŏ	ŏ	Ŏ	Ó	0	0	0	0	0
6 Related Construction	-	¥.	1		ľ									
Road relocation	K.	0.0	0,0	0.0	0.0	0.0	0.0	0.0	0.0	<u>] 0.0</u>	<u>0.0</u>	<u></u>	<u>v.</u> 0	
Road improvement (access)	Ka	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	<u></u>	0.0
Road improvement (const.)	Ke	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	U.0	0.0			
New construction (access)	Ka.	0.0	0.0	0.0	0.0	<u> </u>	0.0	0.0	<u> </u>		- v.v	····	<u>v.v</u>	<u> </u>
7 Niscel Janeous		17 000	00 000		10 000	12 000	20.020	51,000	12 000	14.000	14.000	12,000	52,000	140.000
Card Kall (double)		11.000	20,000	1	19,000	6.0	0.0	0	0.0	0.0	0.0	0.0	Ó	Q.
PERCE, ME POSL, XUV STAKE		8 000	10.000	18 000	10,000	6,000	10.000	26,000	6,000	7.000	7.000	6,000	26,000	70,000
Signs and Signal	ke.	0.0	0.0	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	0.0	0.0	0.0	_ 0	0.0	0.0	0.0	0.0	0	0
8 Interchange(exclud bridge)	each	0	1 1	<u>1</u>	1	0	0	1		0]]	0		
9 Through ay Toll Barrier	cacli	Ő	Ó	Ó	İ Ó	0	0	0	0.	ļ <u>0</u>	[Q			
10 Parking Area	each	Û	0	0	0	0		<u>0</u> .	[ğ.	ļ	<u>§</u>			
11 Service Area	each	0	1 0	1 0	1 0	0	0	0	<u> </u>	10	<u> </u>		··	L

Table 12.2.2 Quantity (Remaining Works for 6-Lanes)

12.3 Construction Roads

Construction roads can comprise any of the following:

1) Existing Road

The locations where existing roads can be used as a construction road are shown in Fig. 12.3.2 but these may require relocation or pavement repair and improvement such as widening and/or raising.

2) New Construction Road

At several places as shown in Fig. 2.2.2, new construction roads will be required for access between arterial road and the working area.

3) Use of the Project Road

Half the project road width can be used as a construction road reversed when the first half is completed. (Refer to Fig. 12.3.1)



Fig. 12.3.1 Scheme of Project Road Used as Construction Road



12 - 6

12.4 Construction Method

As in similar road construction projects in Indonesia in the past, mechanical plant and equipment will be utilized in this project as follows:

1) Earthworks

Table	12.4.1	Earthwork	Equipment

	Main Works		Equipment							
Main Wo	orks	Max, Haul 100m	Max. Haul 500m	Max. Haul 2000m						
Clearing and gi	rubbing		• Bulldozer							
Excavation			• Bulldozer •Tractor drawn scrape	• Motor scraper						
Loading		• Bulldozer	• Bulldozer •Cr • Excavator • D	awler type loader ump truck						
Embankment	Scatter		• Bulldozer							
	Levelling		• Motor grader							
Compaction		• Tamping roller • Pneumatic type	Vibratory re- roller Steel roller	oller						
Finishing		• Bulldozer	• Motor grade	• Motor grader						

2) Pavement Work

Concrete Pavement	Asphalt Pavement
Truck mixer	• Dump truck
Concrete spreader	Asphalt finisher
 Concrete finisher 	Steel roller
Concrete plant	Pneumatic tyre roller
	Asphalt mixing plant

3) Bridge Work

Ma	ain Work		Equipment	
	Excavation	• Bulldozer	• Excavator	Dump truck
Sub structure	Foundation	Diesel pile hammerPile driver	• Truck mixer	• Truck crane
	Structure	• Crane	• Truck mixer	• Crawler crane
Super	Making beam	• Trailer	•	
structure	Erection	• Erection girder		

Table 12.4.3 Bridge Construction Equipment

12.5 Construction Schedule

1) Construction Period

In Indonesia, although the basic working hour is generally no more than 7 hours, on construction sites the average working hour ranges from 7 to 10 hours.

Based on rainfall data obtained from stations along the project corridor, the number of suitable working days in a month was estimated for earth works and pavement works etc. as shown in Tables 12.5.1 and 12.5.2.

	Month														
Place	1	2	3	4	5	6	7	8	9	10	11	12			
Cikampek	15	14	12	10	.7	4	3	2	2	7	11	11			
Cikalong	17	15	13	8	8	5	3	2	3	6	10	14			
Pasir Bungir	19	17	16	12	10	6	5	3	4	7	12	14			
Subang	19	19	20	16	13	6	5	4	4	10	16	19			
Udjung Jaya	17	15	16	11	8	4	3	2	3	6	12	17			
Sumedang	18	15	18	16	12	5	6	4	2	8	14	18			
Sumurwatu	18	15	15	12	8	4	4	2	3	5	11	16			
Kertasumaya	1ē	13	14	9	7	4	4	- 3	2	4	8	13			
Kadipaten	18	17	18	14	9	5	4	2	2	6	13	18			
Wiahar	18	16	17	13	8	4	4	2	2	6	12	17			
Majalengka	19	17	18	12	9	4	3	2	1	5	10	16			
Average	18	16	16	12	9	5	4	3	3	6	12	16			

Table 12.5.1 Number of Rainy Days in the Project Area (1965-1976)

Table 12.5.2 Number of Working Days in a Month

Item	Dry Season 5-10 (6 Months)	Rainy Season 11-4 (6 Months)
Average number of rainy day in a month	5 days	15 days
Working efficiency on a rainy day	65%	35%
Number of holidays in a month	5 days	5 days
Number of actual working days in a month	23.3 days	15.3 days
Working efficiency in a month	78%	51%

2) Construction Schedule

Taking into consideration various factors, the maximum possible construction period for each section of this project is estimated to be 3 and 4 years. The scale of each work items and construction difficulties etc. were studied and schedules for individual package were prepared as shown in Figs. 12.5.1 to 12.5.2.

Hom	r							-`						Not	111														
i tocm	6	2	4	6	8	10	1	21	4	16	18	2	0 2	2.7	24	26	28	8 3	0 3	2	34	36 3	38	40	42	4	q q	34	8
	f	Ť	ŕ	Ť	Ť	Ť		Ē	Ť	Ť	Ť		1		Т	T			Ē	T	1	Ť	Т	Т					—
1 Preperation			-						1-	1				-	F	1	-			-	-	-	T	_	_				
2 Earth works		<u> </u>													-													,'	
3 Pavement			<u> </u>											5.88					7862									·	
4 Bridges	-	-		-				-	<u> </u>																		<u></u>		
5 Grade senaration	-	-	-		+	_		ļ	_	+	-	29					-							500					
structure		1	1		Ì	1	_		Ē			_				1							Ì	1					
6 brainage	$\left \right $	╀	╞														Ī								+			 . i	
7 Related	-		-	-		-			\vdash	-		_			-	+				-	-		╞	-	-				╞
8 Niscel laneous			1		1	_			Ľ	-					L	Ŧ				<u> </u>	1	185	-						
9 Finishing	╞	╞		+				}	-		-				<u> </u>	\pm				_							1967		
		Γ		Γ				· ·															1					í	L

Fig. 12.5.1 Construction Schedule - Section 1 to 5 (Package A and B)

ltem	Month																			
	þ	2	4	6	8 1	0	12	14	1	61	82	02	22	42	62	83	03	23	4 3	6
													-		L	<u> </u>				
1 Preparation			{			ļ	_	_				<u> </u>				ļ	ļ			
	Ļ_	.	ļ	 		ļ	 	-				ļ				ļ	ļ	<u> </u>		
2 Earth works	┝								-							 	 			
D. D				┝╍		Ŀ	<u> </u>												<u> </u>	
3 Pavement			÷																1	i
4 Bridges								{ 5090	5							[[]	
1 0.10000	L	1		· ·		1		+	~~~											
5 Grade separation		1				-			200											
structure									1							l				
6 Drainage		<u> </u>		-			+										{	L		
	ļ	<u> </u>	ļ	L		ļ	L	1								ļ	ļ	L		
7 Related	 				L		Ļ									Ŀ	ļ	L		
construction	<u> </u>		<u> </u>													l				
8 Niscellaneous															(57 SM-		ļ	Ke g	{	
9 Finishing																			10000	
																			<u>.</u>	

Fig. 12.5.2 Construction Schedule - Section 6 to 9 (Package C)

12.6 Implementation Plan

The schedule of project implementation is shown in Table 12.6.1 with reference to similar project in Indonesia.

Year	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998
Feasibility Study								:		
Loan Processing for Detailed Design			5							
Procurement for Detailed Design									 	
Detailed Design										
Land Acquisition and Compensation					A,B	С				
Construction										
Package C										

 Table 12.6.1 Implementation Schedule

CHAPTER 13. ESTIMATED PROJECT COST

CHAPTER 13. ESTIMATED PROJECT COST

13.1 Estimation of Construction Costs

The construction work is divided into 9 sections and 3 packages according to the construction plan and the work schedule. The quantity of each work item of construction per section is estimated and the construction cost is calculated according to the unit cost based on similar past projects.

Tables 13.1.1 to 13.1.6 show the direct construction cost for the initial stage and remaining works for the ultimate stage per package.

د می از این این این این این این این این این این				
ITEN	UNIT	QUANTITY	UNIT COST	AMOUNT
	1		(Rp.)	(1000Rp.)
1 Earth works				1 010 000
Clearing and grubbing	<u>m2</u>	2,932,000	550	1,612,600
Common excavation (E-L)	<u>už</u>	5,669,000	3,500	19,841,500
Borrow excavation (E-L)	<u>m3</u>	164,000	3,800	623,200
Embankment (1km T-C) soil	<u>m3</u>	5.094.000	2,500	12,735,000
Haulage A (7Km)	<u>n3</u>	945,000	3,500	3,307,500
Haulage B (13Km)		1,620,000	6,500	10,530,000
Haulage C (20Km)	<u>m3</u>		10,000	
Sodding Solid	m2	364,000		182,000
<u>Sodding</u> Strip	<u>m2</u>	<u>1,663,000</u>	350	582,050
<u>Sub-total</u>		<u></u>		49,413,850
2 Flexible Pavement				100 050
Subgrade Preparation	<u>m2</u>	687,000	150	103,050
Aggregate Subbase	<u>m3</u>	249,000	25,000	6,225,000
Asphalt treated base	ton	223,300	41,000	9,155,300
Binder course (t=6cm)	ton	87,400	47,000	4,107,800
Surface course (t=4cm)	ton	58,000	55,000	3,190,000
Prime coat	Kg	1,202,000	400	480,800
Tackcoat	Kg	746,400	400	298,560
Seal coat	m2	236.000	1,200	283,200
Sub-total				23,843,710
3 Bridges				
Short span bridges	m2	3,270	715,000	2,338,050
Medium span bridges	m2	26,780	770,000	20,620,600
Long span bridges	m2	5,200	1,240.000	<u>6,448,000</u>
Sub-total				29,406,650
4 Grade separation structure				
Medjum span bridges	m2	9,630	770,000	7,415,100
1/C bridges	m2	1,540	770,000	1,185,800
Over-Bridges (Pedestrian)	m2	980	957,650	938,497
Ramp Bridges	m2	0	770,000	0
Sub-total				9,539,397
5 Drainage				
U-ditch & Catchbasin	kт	37.5	68,800,000	2,580,000
Concrete pipe o 100	h	2,450	227,104	556,405
Culvert A (3 x 3)		1.680	1,200,000	2,016,000
Culvert B (5×5)		270	2,600,000	702.000
Sub-total				5,854,405
6 Related Construction				
Road relocation	Km	2.2	498,000.000	1,095,600
Road improvement (access)	Km	0.0	415,000.000	0
Road improvement (coust.)	Km	6.5	332,000.000	2,158,000
New construction (access)	Km	0.0	498,000,000	
Sub-total			10010001000	3,253,600
7 Niccellaneous				~,2001000
(uard gail (cingte)		10 500	67.415	707.858
Gance Vie Doct POU Ctake	<u>н</u> 	27 5	30,000,000	1,125,000
rence, All rost, NUK Stake	<u>NII</u>	31 000	20,000,000 2 500	77 500
Flat Kills		27 6	12 800 000	000 080
STRUS ANU STRUATS	<u>K(II</u>	51.0	12,000,000	2 300 328
SUD-total	each		3 500 000 000	7 000 000
o milerchange (exclud of luge)	each		5 700 000 000	5 700 000
9 InFoughway Toll Barrier	eacn	i	1 020 000 000	01001000
IU PARKING AFEA	each	<u>v</u>	4 200 000 000	1 200 000
11 Service Area	each	I	4,200,000,000	16 000 000
SUD-total	and the state of the state of the state of the state of the state of the state of the state of the state of the	·		140 602 000
Direct Construction Cost		· · · · · · · · · · · · · · · · · · ·		140,002,000

Table 13.1.1 Direct Construction Cost of Package-A (Outer 4-Lanes)

13 - 2

ITEM	דואון	QUANTITY	UNIT COST	AMOUNT
ELUI		mychilit I f	(Rp.)	(1000Rp.)
1 Earth works				
Clearing and grubbing	m2	3,287,000	550	1,807,850
Common excavation (E-L)	m3	3,461,000	3,500	12,113,500
Borrow excavation (E-L)	m3	269,000	3,800	1,022,200
Embankment (1km T-C) soil	<u>, m3</u>	3,383,000	2,500	8,457,500
Haulage A (7Km)	wy	7,103,000	3,500	1,360,500
Haulage B (13Km)	ш3	<u> </u>	6,500	<u>V</u>
Haulage C (20Km)	<u> </u>	510 000	10,000	255 000
Sodding Solid	<u>m2</u>	1 572 000	000 950	200,000
Sub-total	<u></u>	1,0(2,000		31.566.750
2 Flexible Pavement	· ····			04 1000 10V
Subgrade Preparation	m2	963.000	150	144.450
Aggregate Subbase	<u>т3</u>	349.000	25,000	8,725.000
Asphalt treated base	ton	313,200	41,000	12,841,200
Binder course (t=6cm)	ton	122,600	47,000	5,762,200
Surface course (t=4cm)	ton	81.400	55,000	4,477,000
Prime coat	. Kg	1,685,000	400	674,000
Tackcoat	Kg	1,046,000	400	418,400
Seal coat	<u>m2</u>	331,000	1.200	397,200
<u>Sub-total</u>				33,439,450
3 Bridges	······ <u>·</u> ·····			1 500 100
Short span bridges	<u>m2</u>	2,140	715,000	1,530,100
Medium span bridges	<u>m2</u>	23,730	710,000	18,272,100
Long span bridges	<u>m2</u>	5,200	1,240,000	0,448,000
Sub-total				20,200,200
4 Grade separation structure	بري	0.050	770 000	7 661 500
neurum span of luges	 ምን	0,300	770 000	Ω
Dver-Bridges (Pedectrian)	ຢີ ສາວ	1 760	957_650	1.685.464
Ramp Rridges	m2		770_000	677.600
Sub-total	1114	000		10.024.564
5 Drainage		*** **********************************		
V-ditch & Catchbasin	ka	52.0	68,800,000	3,577,600
Concrete pipe o 100	Ш	1,620	227,104	367,908
Culvert A (3x3)	Ш	1,960	1,200,000	2,352,000
Culvert B (5 x 5)	Ш	200	2,600.000	520.000
Sub-total			·····	6,817,508
6 Related Construction		·····	400 000 000	640 AAA
Road relocation	Km	0.5	498,000,000	249,000
Koad improvement (access)	Km	<u>1.3</u>	415,000,000	539,500
Koad Improvement (const.)	<u>K</u> m	<u></u>	332,000,000	000 000
New construction (access)	<u> </u>	2.0	498,000,000	<u>3 776 200</u>
Z Minocillanocuo				4,440,000
r mscertaneous	net in the second second second second second second second second second second second second second second s	12 /00	67 AIS	825 QAR
Rence Vm Doct DOU State	ill Vm	14,400 52 A	30 000 000	1.560.000
Marking	ოე 	13 000	2 500	107.500
Signe and Signale		52 A	12,800,000	665.600
Sub-total	<u></u>	02.1V	1010001000	3,169,046
8 Interchange(exclud bridge)	each	2	3,500,000,000	7,000.000
9 Throughway Toll Barrier	each	້	5,700,000.000	0
10 Parking Area	each	8	1,030,000.000	8,240,000
11 Service Area	each	0	4.200.000.000	0
Sub-total				15,240,000
Direct Construction Cost				128,956,000

Table 13.1.2 Direct Construction Cost of Package-B (Outer 4-Lanes)

ITEM	TINIT	QUANTITY	UNIT COST	AMOUNT
T I LAT			(Rp.)	(1000Rp.)
1 Earth works				
Clearing and grubbing	<u>m2</u>	3,340,000	550	1,837,000
<u>Common excavation (E-L)</u>	m3	1,460,000	3,500	5,110,000
Borrow excavation (E-L)	<u>m3</u>	3,536,000	3,800	13,430,000
Embankment (Ikm T-C) soll	<u>m3</u>	4,800,000	2,000	2 790 000
Haulage A ((Km)	<u></u> 2	2 220 000	3100 8 500	21 052 500
Haulage B (13Km)	<u></u>	3,239,000	10,000	15 090.000
Raulage L (20Km)	<u>رس</u> س	516 000	500	258,000
Sodding Solid	<u>m2</u>	1 592 000	350	557,200
Sub-total	(62	11002,000	000	73.247.500
2 Flexible Pavement	· · · · · · · · · · · · ·	······	· · · · ·	
Subgrade Preparation	m2	975,000	150	146,250
Aggregate Subhase	m3	354,000	25,000	8,850,000
Asphalt treated base	ton	317,200	41,000	13,005,200
Binder course (t=6cm)	ton	124,100	47,000	5,832,700
Surface course (t=4cm)	ton	82,400	55,000	4,532,000
Prime coat	Kg	1,706,000	400	682,400
Tackcoat	Kg	1,060,000	400	424,000
Seal coat	_m2	336,000	1,200	403.200
Sub-total				33,875,750
3 Bridges	·····			
Short span bridges	<u></u> 2	16,370	715,000	11,704,550
Medium span bridges	<u>m2</u>	19,900	770,000	15,323,000
Long span bridges	<u>m2</u>	0	1,240,000	<u> </u>
Sub-total			<u> </u>	21,021,030
4 Grade separation structure		10 200	770 000	14 414 400
Medium span bridges	<u>mz</u>	18,120	770 000	19,414,400
I/C DETOges	/⊪∠ 	1 060	057 650	1 876 994
Over-Bridges (redestrial)		2 640	770 000	2,032,800
Substatal	[1]2	2,010	110,000	18.324.194
5 Drainage				10,021,101
U-ditch & Catchbasin	kn	53	68,800,000	3,646,400
Concrete pipe o 100	m	4.530	227.104	1,028,781
Culvert A (3 x 3)		1,430	1,200,000	1,716,000
Culvert B (5 x 5)	剧	800	2,600,000	2,080.000
Sub-total				8,471,181
6 Related Construction				
Road relocation	Km	3.0	498,000,000	1,494,000
Road improvement (access)	Кт	10.5	415,000,000	4,357,500
Road improvement (const.)	Km	5.0	332,000,000	1,660,000
<u>New construction (access)</u>	Km	0.5	498,000,000	249,000
Sub-total				7,760,500
7 Miscellaneous				
Guard Rail (single)	n	22,200	67,415	1,496,613
Fence, Km Post, ROW Stake	<u>Kn</u>	53.0	30,000,000	1,590,000
Marking	m2	45,000	2,500	112,500
Signs and Signals	Kfi	53.0	12,800,000	2 277 512
SUP-TOTAL	anal		3 500 000 000	7 000 000
O Interchange exclud of loge	each	<u>2</u>	5 700 000 000	1,000,000
o mioughway full Dallier	pach		1,030,000,000	4 120 000
10 Falking Area	each		4,200,000,000	
Sub-total	CACI	<u>0</u>	1120010001000	11,120,000
Direct Construction Cost	and the second second second second second second second second second second second second second second second			183,704.000
	and the second second second second second second second second second second second second second second second			

Table 13.1.3 Direct Construction Cost of Package-C (Outer 4-Lanes)

Table 13.1.4 Direct Construction Cost of Package-A (Remaining Works for 6-Lanes)

.

ITEM	UNIT	QUANTITY	UNIT COST (Rp.)	AMOUNT (1000Rp.)
1 Earth works				
<u>Clearing and grubbing</u>	<u>m2</u>	<u>0</u>	550	Q
Common excavation (E-L)	<u>m3</u>	<u>0</u>	3,500	<u> </u>
Borrow excavation (E-L)	<u>m3</u>	<u></u>	3,800	<u>0</u>
Embankment (1km T-C) soil	<u>m3</u>	<u>Q</u>	2,500	<u> </u>
Haulage A (7Km)	<u>m3</u>	<u>0</u>	3,500	<u>0</u>
Haulage B (13Km)	<u>m3</u>	0	6,500	
Haulage C (20Km)	<u>m3</u>	<u> 0</u>	10,000	<u>0</u>
Sodding Solid	<u>m2</u>	<u> </u>	500	<u>0</u>
<u>Sodding</u> Strip	<u>m2</u>	0	350	0
<u>Sub-total</u>				0
2 Flexible Pavement				EA OFA
Subgrade Preparation	<u>m2</u>	335,000	150	50,250
Aggregate Subbase	<u>m3</u>	105,000	25,000	2,625,000
Asphalt treated base	ton	99,200	41,000	4,067,200
Binder course (t=6cm)	ton	37,700	47,000	1,771,900
Surface course (t=4cm)	ton	24,900	55,000	1,369,500
Prime coat	Kg	586,250	400	234,500
Tackcoat	Kg	322,800	400	129,120
<u>Seal coat</u>	<u>m2</u>	55,000	1,200	66,000
Sub-total				10,313,470
<u>3 Bridges</u>				
Short span bridges	<u>m2</u>		715,000	
Medium span bridges	<u></u>		770,000	<u>0</u>
Long span bridges	<u>m2</u>	0	1,240,000	0
<u>Sub-total</u>	·····			0
4 Grade separation structure				
Medium span bridges	<u>m2</u>	0	770,000	
I/C bridges	<u>m2</u>	0	770,000	<u>0</u>
Over-Bridges (Pedestrian)	<u>m2</u>	0	957,650	0
Ramp Bridges	<u>m2</u>	0	770,000	
<u>Sub-total</u>				0
5 Drainage				
U-ditch & Catchbasin	KI	36.4	68,800,000	2,504,320
Concrete pipe o 100	n	0	227,104	0
Culvert A (3 x 3)	<u>n</u>	0	1,200,000	0
<u>Culvert B (5 x 5)</u>	11	0	2,600,000	0
<u>Sub-total</u>				2,504,320
6 Related Construction				
Road relocation	Km	0.0	498,000,000	0
Road improvement (access)	Km	0.0	415,000,000	<u>0</u>
Road improvement (const.)	Km	0.0	332,000,000	<u>0</u>
<u>New construction (access)</u>	Km	0.0	498,000,000	<u> </u>
Sub-total				0
7 Miscel laneous				
Guard Karl (double)	<u>M</u>	37,000	95,000	3,515,000
rence, Km Post, KUW Stake	Km	0.0	30,000,000	U
Marking	<u>n2</u>	18,000	2,500	45,000
Signs and Signals	KM	0.0	12.800,000	0
<u>Sub-total</u>				3,560,000
8 Interchange(exclud bridge)	each	<u> </u>	3,500,000,000	3,500,000
9 Throughway Toll Barrier	each	0	5,700,000,000	0
10 Parking Area	each	0	1,030,000,000	0
11 Service Area	each	0	4,200,000,000	0
				0 700 000
<u>Sub-total</u>				3,500,000

Table 13.1.5	Direct Construction Cost of Package-B (Remaining Works for 6-Lanes)

		QUANTITI	(Rn.)	(1000Rp.)
Farth works				~~~ \
Clearing and grubbing	m2	0	550	0
Common excavation (E-L)	mЗ	0	3,500	0
Borrow excavation (E-L)	mЗ	0	3,800	0
Embankment (1km T-C) soil	mЗ	0	2,500	0
Haulage A (7Km)	m3	0	3,500	Q
Haulage B (13Km)	mЗ	0	6,500	0
Haulage C (20Km)	m3	0	10,000	0
Sodding Solid	#2	0	500	0
Sodding Strip	m2	0	350	0
Sub-total		-		0
Flexible Pavement				
Subgrade Preparation	₩2	471,000	150	70,650
Aggregate Subbase	mЗ	147,000	25,000	3,675,000
Asphalt treated hase	ton	139.500	41,000	5,719,500
Binder course (t=8cm)	ton	53,000	47,000	2,491,000
Surface course (t=4cm)	ton	35.100	55,000	1,930,500
Prime coat	Kջ	824,250	400	329,700
Tackcoat	Kø	456.000	400	182,400
Seal coat	a m2	77.000	1.200	92,400
Sub-total				14,491,150
Bridges			······································	
Chart onen bridgee	m9	0	715,000	Ő
Modium open bridges		<u>×</u>	770,000	Ő
Long enan bridges	1112 m9		1.240.000	Ő
Cub-total	1024			<u>0</u>
Crade congration structure		<u> </u>		
Modium open bridger	н Э	·····	770,000	Ω
I/C bridgeo			770 000	ň
Quan-Paideaa (Padaataian)		······	957 850	Ϋ́
Deep Deidges (reues in rail)	<u>IIIZ</u> ຫາງ	·····	770 000	v
Ramp Driuges	. IIIZ		110,000	Ŏ
Sug-total				V
Uralitate & Catabhagin				3 522 560
U-often & Catenbasin	КЛ		00,000,000	3,022,000
Concrete pipe o IUU		V	221,104	
Culvert A (3 x 3)	<u> </u>	V	1,200,000	
<u>Curvert B (5 x 5)</u>	m	U	2,000,000	2 522 500
Sub-total				3,322,000
Related Construction	. W	~	400 000 000	
Road relocation	Ka	<u> </u>	498,000,000	
koad improvement (access)	<u>K</u> M	<u>v</u>	410,000,000	
Koad Improvement (const.)	<u>Km</u>	Ň	332,000,000	
<u>New construction (access)</u>	Km	<u> </u>	498.000.000	
Sub-total				0
Miscellaneous	·····		07 000	
Guard Rail (double)	<u>n</u>	51,000	95,000	4,845,000
Fence, Km Post, ROW Stake	Km	0.0	30,000,000	Q
Marking	m2	26,000	2,500	65,000
Signs and Signals	km	0.0	12,800,000	0
Sub-total				4,910,000
Interchange(exclud bridge)	each	. 1	3,500,000,000	3,500,000
Throughway Toll Barrier	each	Ó	5.700.000.000	
Parking Area	each		1.030.000.000	Õ
Service Area	each	Ň	4,200,000,000	Ň
JUITICO AICA	Cacil	<u> </u>	1120010001000	<u></u>
Sub-total				3.500.000

Table 13.1.6 Direct Construction Cost of Package-C (Remaining Works 6-Lanes)

.

.

.

	•			
ITEM	UNIT	QUANTITY	UNIT COST	AMOUNT
			(Rp.)	(1000Rp.)
1 Earth works				<u>م</u>
Clearing and grubbing	<u>m2</u>	<u>V</u>	2 500	V
Common excavation (E-L)			3,000	V
BOFFOW excavation (E-L)	611 	······	2 500	
	ւ		3.500	
Haulage R (13Km)	n3		6,500	0
Haulage C (20km)	m3		10,000	Ŏ
Solding Solid	<u>m2</u>		500	0
Sodding Strip	m2	Ó	350	0
Sub-total				0
2 Flexible Pavement				
Subgrade Preparation	m2	473,000	150	70,950
Aggregate Subbase	<u>m3</u>	149,000	25,000	3,725,000
Asphalt treated base	ton	140,100	41,000	5,744,100
Binder course (t=6cm)	ton	53,200	47,000	2,500,400
Surface course (t=4cm)	ton	35,200	55,000	1,935,000
Prime coat	<u>Kg</u>	821,100	400	192 400
	<u>K8</u>	400,000	1 200	03 600
Seal coat	niz.	10,000	1+200	14 583 550
2 Bridges				1110001000
Short span bridges	m2		715.000	0
Medium soan bridges	m2	Õ	770,000	0
Long span bridges	m2	Ö	1.240.000	0
Sub-total				0
4 Grade separation structure				
Medium span bridges	m2	0	770,000	0
I/C bridges	<u>m2</u>	0	770,000	0
Over-Bridges (Pedestrian)	<u>m2</u>		957,650	<u> </u>
<u>Ramp Bridges</u>	m2	0	770,000	· U
Sub-total				<u>U</u>
5 Urainage		E1 A	000 000 00	2 526 220
U-OITCH & LATCHDASIN			227 104	
		······································	1 200 000	
$\frac{\text{Curvert } A (5 \times 5)}{\text{Curvert } B (5 \times 5)}$			2,600,000	Ň
Sub-total	14	V_	2,000,000	3,536,320
6 Related Construction				
Road relocation	Km	0	498,000,000	0
Road improvement (access)	Km	0	415,000,000	0
Road improvement (const.)	Кт	0	332,000,000	0
<u>New construction (access)</u>	Km	0	498,000,000	0_
Sub-total				0
7 Miscellaneous				
Guard Rail (double)	<u>n</u> i	52,000	95,000	4,940,000
Fence, Km Post, ROW Stake		0.0	30,000,000	U
Marking	<u>m2</u>	26,000	2,500	65,000
Signs and Signals	<u> </u>	0.0	12,800,000	U 5.005.000
SUD-total		· · · · · ·	2 500 000 000	2 000 000
o Interchange(excluo prioge)	eacn		5,500,000,000	5 700 000
5 HICOUSHWAY 1011 BALTIEL	eaco	<u>1</u>	1 030 000 000	
IV LALATING ALGA	each			4.200.000
Sub-total	Cauli	<u>-</u>	1120010001000	16,900,000
Direct Construction Cost				40,025,000

13.2 Land Acquisition and Compensation Costs

Land acquisition and compensation costs are estimated according to the unit cost shown in Tables 13.2.1 and 13.2.2 which were investigated by Indonesian counterpart.

Category	Unit Cost (Rp./m ²)
Housing Area	4,000
Paddy Field	2,000
Vegetable Garden	1,500
Plantation	1,500
Forest	500

Table 13.2.1 Unit Costs of Land Acquisition

 Table 13.2.2 Unit Costs of Compensation for Property

Category	Unit Cost (Rp./m ²)
Semi-Permanent Housing	84,500
Paddy	300
Rubber	12,000
Teak	24,000
Miscellaneous Tree	1,000
Others	200

13.3 Project Costs

Tables 13.2.3 and 13.2.4 show a summary of the project cost per package including indirect cost, maintenance vehicles and furniture purchasing cost, land acquisition cost and compensation cost.

Table	13.3.1	Project	Cost	(Initial	4-Lar	ies)
1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		r			111-1	A 1

(1000 Rp.)

	ITEM		Initial	Lanes		
		PACKAGE A	PACKAGE B	PACKAGE C	TOTAL	
	1 Earth works					
	Clearing and grubbing	1,612,600	1,807,850	1,837,000	5,257,450	
	Common excavation (E-L)	19.841.500	12.113.500	5.110.000	37,065,000	
	Rorroy excavation (E-L)	623.200	1,022,200	13.436.800	15.082.200	
	Emboolmont (1km T-C) soil	12 735 000	8 457 500	12,125,000	33,317,500	
		2 207 500	7 200 500	9 700 000	14 440 000	
	Haulage A C (Km)	3,307,300	11001000	31 001 000	14,440,000	
	Haulage B (13Km)	10,530,000		21,003,000	31,000,000	
	Haulage C (20Km)	U	V.	15,090,000	12,030,000	
	Sodding Solid	182,000	255,000	258,000	695,000	
	Sodding Strip	582,050	550.200	557,200	1,689,450	
	Sub-total	49,413,850	31,566,750	73.247.500	154,228,100	
	2 Flexible Pavement					
	Subgrade Prenaration	103.050	144.450	146.250	393.750	
	Aggregate Subbace	6 225 000	8 725 000	8 850 000	23 800 000	
	Aggregate Junuase	0,220,000	10,120,000	12 005 200	25,000,000	
	Aspnalt treated base	9,100,500	12,041,200	13,003,200	33,001,100	
	Binder course (t=6cm)	4,107,800	5,762,200	5,832,700	15, (02, (00	
	Surface course (t=4cm)	3,190,000	4,477,000	4,532,000	12,199,000	
	Prime coat	480,800	674,000	682,400	1,837,200	
	Tackcoat	298.560	418.400	424.000	1.140.960	
	Seal coat	283 200	397.200	403.200	1.083.600	
	Sub-total	23 812 710	33, 430 450	33,875,750	91,158,910	
	2 Pridaon	4010101110	0011001100	0010101100	0111001010	
	J DI TURES	0.000.000	1 500 100	11 204 650	15 579 700	
	Short span prioges	2,338,030	1,030,100	14,704,550	1919121100	
	Medium span bridges	20,620,600	18,2/2,100	15,323,000	54,215,700	
	Long span bridges	6.448,000	6,448,000	0	12,896.000	
	Sub-total	29,406,650	26,250,200	27,027,550	82,684,400	
	4 Grade separation structure					
	Medium span bridges	7.415.100	7,661,500	14.414.400	29.491.000	
	1/C bridge	1 195 900	0		1 185 800	
	1/C ULIUSES	1,100,000	1 COE ACA	1 070 004	A 500 055	
	Uver-bridges (redestrian)	930,491	1,000,404	1,010,004	4,000,000	
	Kamp Bridges	UV	677,600	2.032.800	Z, 110, 400	
	Sub-total	9,539,397	10,024,564	18,324,194	37,888,155	
	5 Drainage					
	U-ditch & Catchbasin	2,580,000	3,577,600	3,646,400	9,804,000	
	Concrete pipe o 100	556,405	367.908	1,028,781	1,953,094	
	Culvert A (3 x 3)	2.016.000	2.352.000	1.716.000	6.084.000	
	Culvert $B \left(5 \times 5 \right)$	702.000	520,000	2.080.000	3.302.000	
	Substatal	5 854 405	6 817 508	8 471 181	21,143,094	
	6 Palated Construction	0,001,100	0,011,500	013111101	21,110,001	
	Dead as least ton	1 005 000	240 000	1 404 000	1 020 600	
	KOAO FELOCATION	1,095,600	249,000	1,494,000	Z,030,000	
	Koad Improvement (access)	0	539,500	4,357,500	4,891,000	
	Road improvement (const.)	2,158,000	664,000	1,660,000	4,482,000	
	New construction (access)	0	996,000	249.000	1.245.000	
1	Sub-total	3,253,600	2,448,500	7,760,500	13,462,600	
	7 Miscellaneous					
	Guard Rail (cingle)	707 858	825 016	1.496.613	3.040.417	
	Fonce Vm Doct DOLL Ctalia	1 125 000	555,010 560 000	1 500 000	4 275 AAA	
	Manual Ann FUSE, NUM STAKE	1,120,000	107 500	110 500	212101000	
	TIAT KINS	11,500	107,300	112,000	231,000	
	Signs and Signals	480,000	665,600	6/8,400	1.824.000	
	Sub-total	2.390,358	3,169,046	<u>3,877,513</u>	9,436,917	
	8 Interchange(exclud bridge)	-7,000,000	7,000,000	7,000,000	21,000,000	
	9 Throughway Toll Barrier	5,700,000	0	0	5,700,000	
	10 Parking Area	0	8.240.000	4,120,000	12.360.000	
	11 Service Area	4 200 000			4.200.000	
	Sub-total		15 240 000	11 120 000	000 03C FA	
	Dineal Canal method Card		101 050 000	102 704 000	452 202 000	
	UITECT CONSTRUCTION COST	140.602.000	128,950,000	183,704,000	403.202.000	
	Contingency 15%	21,090,000	19,343,000	27,556,000	67,989,000	
	Overhead & Profit 10%	16,169,000	14,830,000	21,126,000	52,125,000	
	Engineering fee 7%	12,450,000	11,419,000	16,267,000	40,136,000	
	Vehicle & Furpiture	1.042.000	1.042.000	1.042.000	3,126,000	
	Ταγ 109	10 125 000	17 550 000	24 970 000	61 664 000	
	Land Acquisition 9 Compared	17 204 000	25 002 000	16 700 000	60 227 000	
	Lanu Acquisition & Compensat	17.304.000	30,093,000	10,100,000	00,201,000	
	Project Lost	221,852,000	228.242.000	291,440,000	141.039.000	

					(1000 Kp.)
. [ITEM	·	Remaining Work	s for 6-Lanes	
		PACKAGE A	PACKAGE B	<u>PACKAGE C</u>	TOTAL
	1 Earth works				
	Clearing and grubbing	0	0	0	0
	Common excavation (E-1)	0	0	0	0
	Rorroy excavation (F-1)	0	ñ	0	0
1	Embanizment (1km T.C) coil	ň	Ň	Ő	Ó
			ň	ň	Ň
1	Haulage A (IKm)			V.	
	Haulage B (13Km)	<u>V</u>		<u>v</u> .	0
	Haulage C (20Km)	<u> </u>		<u> </u>	
	Sodding Solid	<u> </u>	<u> </u>	<u> </u>	,, V
	Sodding Strip	··· ()	0	<u> </u>	<u> </u>
	Sub-total	0	0	0	0
	2 Flexible Pavement				
	Subgrade Preparation	50,250	70,650	70,950	191,850
	Aggregate Subbase	2,625,000	3,675,000	3,725,000	10,025,000
	Asphalt treated base	4,067,200	5,719,500	5,744,100	15,530,800
	Rinder course (t=6cm)	1.771.900	2.491.000	2,500,400	6,763,300
	Surface course (t=Acm)	1.369.500	1.930.500	1,936,000	5.236.000
1	Prime coat	234.500	329 700	331.100	895.300
	Tackcoat	120.120	182 400	182,400	493,920
. 1	Coal coat	66 000	02,700 02 A00	003 600	252 000
	Scal COat	10 212 470	10 001 150	14 582 550	30,388,170
]		10,010,410	11,101,100	11,000,000	001000110
j.	3 BLIDES	······		~	~
Ĩ	Short span bridges	<u> </u>	<u> </u>	<u>v</u>	
	Medium span bridges	<u></u> 0	0	0	<u> </u>
	Long span bridges	0	0	0	0
	Sub-total	0	0	0	0
	4 Grade separation structure				
	Medium span bridges	0	0	0	0
	1/C bridges	0	Ō	0	0
	Over-Bridges (Pedestrian)	Ň	ň	0	0
	Poen Bridges (reucstrian)	ň	ñ	Ö	Ň
	Kamp bridges		0	0	Ŏ
	Sub-total	V	U		· · · · · · · · · · · · · · · · · · ·
	5 Drainage	0 504 990	0 500 500	2 526 220	0 562 140
	U-ditch & Catchbasin	2,504,320	3,522,500	3,030,320	9,000,140
	Concrete pipe o 100	<u>9</u>	<u> </u>		
	Culvert A (3x3)			Q	
	Culvert B (5 x 5)	0	0	0	<u> </u>
	Sub-total	2,504,320	3.522.500	3.536,320	9,563,140
	6 Related Construction			· ·	
	Road relocation	0	0	.0	0
	Road improvement (access)	0	0	0	0
1	Road improvement (const.)	ñ	ñ	0	0
1	New construction (access)	ñ	ñ	Ň	0
j	Cub-total			<u> </u>	ñ
: 1	2 Miccallanacua			V	
	Cuand Dail	2 515 000	A 845 000	1 040 000	13 300 000
		3,313,000	410431000	212401000	1010001000
	Fence, Km Post, RUV Stake	0		U	175 000
	Marking	45,000	65,000	65,000	t.13,000
	Signs and Signals	0	0	0	0
	Sub-total	3,560,000	4,910,000	5,005,000	13,475,000
	8 Interchange(exclud bridge)	3,500,000	3,500,000	7,000,000	14,000,000
	9 Throughway Toll Barrier	0	0	5,700.000	5,700,000
	10 Parking Area	0	0	0	0
	11 Service Area	0	0	4.200.000	4,200,000
	Sub-total	3.500.000	3,500,000	16,900,000	23,900,000
	Direct Construction Cost	19 878 000	26 424 000	40.025.000	86.326.000
1	Captingano:: 156	2 102 100	20.729.000	6 001 000	12 050 000
	Contingency 154	2,302,000	2 020 000	0,004,000	a 020 000
	Uvernead & Profit 10%	2,286,000	3,039,000	4.003.000	3, 320,000
- 1	Engineering fee 7%	1,760,000	2,340,000	3,544.000	7,644,000
	Vehicle & Furniture	0	0		0
	Tax 10%	2,691,000	3,577.000	5,418,000	11,685,000
1	Land Acquisition & Compensation	0	0	0	0
	Project Cost	29,597,000	39,344,000	59,594,000	128,533,000

Table 13.3.2 Project Cost (Remaining Works for 6-Lancs)

13.4 Operation and Maintenance Costs

The operation and maintenance costs for the proposed tollway are estimated based on information from Jasa Marga about the operation and maintenance costs of several existing tollways in service with 4-lanes. Based on data of the total operation and maintenance costs and the total service length of the tollways, the average operation and maintenance costs per kilometer for a tollway with 4 lanes is estimated to be about 111 Million Rp. per annum. The operation and maintenance costs of a tollway with 6 lanes is assumed to be 1.1 times those with 4 lanes (about 121 Million Rp. per annum).

Table 13.4.1 Estimation of Operation and Maintenance Costs

(1) Case	of Jagora	vi			
	O/M Cost (Rp.Mil.)	Length (Km)	O/M Cost per Km	factor of Overhead	O/M Cost O/M Cost per Km per Km (Rp.Mil.)(Rp.Mil.)
					4 Lanes 6 Lanes
Op. Maint. Total	3,113.6 911.7 4,025.3	47,6	85.0	1.2	102.0 112.0
				~ ~	
(2) Case of Jakarta-Merak					
	O/M Cost (Rp.Mil.)	Length (Km)	O/M Cost per Km	factor of Overhead	O/M Cost O/M Cost per Km per Km (Rp.Mil.)(Rp.Mil.)
					4 Lanes 6 Lanes
Op. Maint. Total	2,658.6 808.0 3,466.6	26.8	129.0	1.2	154.8 170.0
(3) Case of Surabaya-Gempol					
	O/M Cost (Rp.Mil.)	Length (Km)	0/M Cost per Km	factor of Overhead	O/M Cost O/M Cost per Km per Km (Rp.Mil.)(Rp.Mil.)
					4 Lanes 6 Lanes
Op. Maint.	2,614.4 748.3				
Total	3,362.7	43.6	77.0	1.2	92.4 102.0
(Average	of Above !	Follways))		
	O/M Cost (Rp.Mil.)	Length (Km)	0/M Cost per Km	factor of Overhead	O/M Cost O/M Cost per Km per Km (Rp.Mil.)(Rp.Mil.)
					4 Lanes 6 Lanes
Op. Maint.	8,386.6 2,468.0				
Total	10,854.6	118.0	92.0	1.2	110.4 121.0

Note:

Data source of operation and maintenance costs of above tollways is from Jasa Marga.

CHAPTER 14. ECONOMIC PROJECT ANALYSIS

CHAPTER 14. ECONOMIC PROJECT ANALYSIS

14.1 General

The main aim of the economic analysis is to show the effect of the Cikampek-Cirebon Tollway on the nation's economic well-being and to estimate the expected economic rate of return on the resources invested. The evaluation is an assessment of the economic viability of the proposed Cikampek-Cirebon Tollway.

The evaluation of quantified economic costs and benefits follows the conventional discounted cash flow methodology in determining the net present value, internal rate of return and benefit cost ratio.

Aside from these efficiency measures, positive effects of the tollway on industrial development are examined and likely development types in the proposed interchange areas are discussed in the last section of this chapter.

14.2 Project Cost

14.2.1 Construction and Land Acquisition Costs

The initial investment cost for construction and land acquisition costs of the proposed tollway were estimated at a total of 747,539.0 million rupiah in constant 1989 prices. Of this total, 658,234 million rupiah is the construction and supervision cost, 69,237.0 million rupiah is the land acquisition and compensation cost and the remaining 20,068.0 million rupiah is the final engineering costs. The implementation schedule followed in the analyses (see Table 12.6.1) indicates that final engineering activities will continue from late 1991 through 1993, with land acquisition starting in 1993. Construction is scheduled over four years from 1994 to 1997.

As with the financial costs, the economic costs are estimated in constant 1989 prices. The economic costs were estimated by adjusting and eliminating all transfer payments such as taxes and duties as summarized in Table 14.2.1. The economic costs in constant 1989 prices are properly phased according to the construction schedule as shown in Table 14.2.2.

14 - 1

			· · · · · · · · · · · · · · · · · · ·	(mil	lion Rp. at 19	989 prices)
Package	Cost	Land Acquisition & Compensation	Engineer Detailed Eng. Design	ing Services Construc- tion Supervision	Construc- tion	Total
A:	Initial 4-lane Financial Economic	17,364.0 17,364.0	6,225.0 5,185.4	6,225.0 5,185.4	198,038.0 156,772.9	227,852.0 184,507.7
	Remainings for 6-lane Financial Economic	0 0	880.0 733.0	880.0 733.1	27,837.0 22,241.4	29,597.0 23,707.5
B:	Initial 4-lane Financial Economic	35,093.0 35,093.0	5,709.5 4,756.0	5,709.5 4,756.0	181,730.0 144,025.2	228,242.0 188,630.2
	Remainings for 6-lane Financial Economic	0 0	1,170.0 974.6	1,170.0 974.6	37,004.0 29,637.5	39,344.0 31,586.7
C:	Initial 4-lane Financial Economic	16,780.0 16,780.0	8,133.5 6,775.2	8,133.5 6,775.2	258,398.0 205,008.6	291,445.0 235,339.0
	Remainings for 6-lane Financial Economic	0 0	1,772.0 1,476.0	1,772.0 1,476.0	56,050.0 44,153.1	59,594.0 47,105.1
Total	Initial 4-lane Financial Economic	69,237.0 69,237.0	20,068.0 16,716.6	20,068.0 16,716.6	638,166.0 505,806.7	747,539.0 608,476.9
	Remainings for 6-lane Financial Economic	0 0	3,822.0 3,183.6	3,822.0 3,183.7	120,891.0 96,032.0	128,535.0 102,399.3
Grand Total	Financial Economic	69,237.0 69,237.0	23,890.0 19,900.2	23,890.0 19,900.3	759,057.0 601,838.7	876,074.0 710,876.2

Table 14.2.1 Economic and Financial Project Costs
TOTAL (A+B+C)	OPERATION/ MAINTENANCE	CONSTRUCTION COSTS	LAND ACQ. & COMPENSATION	ENGINEERING SERVICES	AR	YI
.0	.0	.0	.0	.0	1989	1
.0	.0	.0	.0	.0	1990	2
3,343.0	.0	.0	.0	3,343.0	1991	3
6,687.0	.0	.0	.0	6,687.0	1992	4
59,144.0	.0	.0	52,457.0	6,687.0	1993	5
80,917.0	.0	60,160.0	16,780.0	3,977.0	1994	6
156,440.0	.0	151,742.0	.0	4,698.0	1995	7
176,940.0	.0	172,242.0	.0	4,698.0	1996	8
125,006.0	.0	121,663.0	.0	3,343.0	1997	9
14,186.0	14,186.0	.0	.0	.0	1998	10
14,186.0	14,186.0	.0	.0	.0	1999	11
14,186.0	14,186.0	.0	.0	.0	2000	12
14,186.0	14,186.0	.0	.0	.0	2001	13
14,186.0	14,186.0	.0	.0	.0	2002	14
14,186.0	14,186.0	.0	.0	.0	2003	15
14,186.0	14,186.0	.0	.0	.0	2004	16
14,186.0	14,186.0	.0	.0	.0	2005	17
14,186.0	14,186.0	.0	.0	.0	2006	18
14,186.0	14,186.0	.0	.0	.0	2007	19
41,834.0	14,186.0	25,940.0	.0	1,708.0	2008	20
41,834.0	14,186.0	25,940.0	.0	1,708.0	2009	21
15,099.0	15,099.0	.0	.0	.0	2010	22
15,099.0	15,099.0	.0	.0	.0	2011	23
15,099.0	15,099.0	.0	.0	.0	2012	24
38,651.0	15,099.0	22,076.0	.0	1,476.0	2013	25
38,651.0	15,099.0	22,076.0	.0	1,476.0	2014	26
15,464.0	15,464.0	.0	.0	.0	2015	27
15,464.0	15,464.0	.0	.0	.0	2016	28
15,464.0	15,464.0	.0	.0	.0	2017	29
15,464.0	15,464.0	.0	.0	.0	2018	30
15,464.0	15,464.0	.0	.0	.0	2019	31
15,464.0	15,464.0	.0	.0	.0	2020	32
15,464.0	15,464.0	.0	.0	.0	2021	33
15,464.0	15,464.0	.0	.0	.0	2022	34
1,080,316.0	369,439.0	601,839.0	69,237.0	39,801.0	AL	TO

Table 14.2.2 Economic Project Cost Flows

14.2.2 Operation and Maintenance Costs

Operation and maintenance costs were estimated at 111 million rupiah per kilometer or 15,762 million rupiah per year for the initial 4-lane tollway operation between Cikampek and Cirebon. At the ultimate stage of 6-lane tollway operation these are estimated to be 121 million rupiah per kilometer or 17,182 million rupiah per year. The financial operation and maintenance costs were adjusted to economic costs by eliminating transfer payments such as taxes. The project's economic operation and maintenance costs and capital costs for each analysis year are shown in Table 14.2.1.

14.3 Vehicle Operating Costs

14.3.1 General

A major part of the estimated economic benefits which would be realized from the implementation of the project are quantified in terms of savings in the vehicle operating costs which would result from improved traffic movement on the road network in the study area. The estimation of the vehicle operating costs is based on the method accepted by Jasa Marga in previous similar studies. All cost components and variables were up-dated according to the latest information collected in this study.

14.3.2 Representative Vehicles

Since a major factor in vehicle operating costs is the cost and type of vehicles under consideration, it is necessary to establish representative vehicles for the vehicle categories of the traffic assignment. The vehicle categories of the traffic assignment are passenger car, pick-up bus and truck, which respectively consist of sedan, jeep and mini bus, pick-ups, medium and large buses, and small and large trucks. The representative vehicles for each category are discussed below and their specifications are shown in Table AP 14.3.1. Appendix to Chapter 14.

1) Passenger Car and Pick-up

The sales data of sedans in Indonesia from 1985 to 1987 were collected and reviewed in order to establish a representative sedan. Honda consistently had the largest market share in sedan cars during the above period and the Jakarta Post recently noted that again Honda had the largest market share in 1988. The top selling Honda sedan car in 1986 and 1987 was the Honda Civic. Therefore, from the above make and model, the Honda Civic Grand was selected as the representative passenger car.

In Jakarta, many minibuses, such as Mitsubishi Colt or Toyota Kijang, are commonly used as sedan substitutes. After reviewing the sales data, the Toyota Kijang Minibus was selected as the representative minibus and the Toyota Kijang Pick-up was selected as the representative pick-up.

2) Bus

The representative medium and large buses used for public transportation services were also selected according to the sales data. The Mercedes Benz 0508 I was selected for the representative medium bus and the Mercedes Benz OH 306S was selected for the large bus.

3) Truck

The Mitsubishi Colt FE 104 and Mitsubishi Fuso FM 516 H were selected for the representative small and large trucks respectively.

14.3.3 Unit Prices and Operating Cost Components

The financial and economic unit prices of the major operating cost components were up-dated with 1989 prices collected in this study. The tax structures and duties utilized in estimating the economic unit prices were also updated according to recent changes in luxury taxes. The financial and economic unit prices are discussed below and are shown in Table 14.3.1.

Table 14.3.1 Unit Prices of Vehicle Operating Cost Components

(Constant 1989 Prices)

		UNIT: RP.
PRICE OF VEHICLES	FINANCIAL PRICE	ECONOMIC PRICE
Sedan : Honda Civic Grand 1500 Minibus : Toyota Kijang Minibus Pick-Up : Toyota Kijang Pick-Up Medium Bus : Benz 508I Large Bus : Benz OH 306S Small Truck : Mitsubishi Colt FE 104 Large Truck : Mitsubishi Fuso Fm 516H Depreciable value of veh	48,000,000 19,000,000 12,000,000 73,350,000 128,700,000 23,518,000 55,165,000 ticle = 90% of	21,600,000 14,707,000 9,240,000 56,480,000 99,099,000 18,109,000 42,477,000 price
PRICE OF ONE SET OF TIRE/TUBE	FINANCIAL PRICE	ECONOMIC PRICE
Minbus/Pickup: 550×13 Sedan : 185×14 Medium Bus : 750×16 Large Bus : 900×20 Small Truck : 750×15 Large Truck : 900×20	47,500 93,750 124,750 254,000 108,750 254,000	38,285 75,563 100,549 204,724 87,653 204,724
FUEL AND ENGINE OIL PRICE (PER LITER)	FINANCIAL PRICE	ECONOMIC PRICE
Gasoline Diesel oil Engine oil for passenger car Engine oil for van and gasoline truck Engine oil for bus and diesel truck	385 200 2,075 1,975 2,200	360 192 1,886 1,795 2,000
WAGES (PER HOUR)	FINANCIAL PRICE	ECONOMIC PRICE
Mechanic Bus driver Truck driver Bus conductor Truck assistant	997 1,336 1,336 516 605	997 1,336 1,336 516 605

1) Vehicles

The current 1989 market prices for vehicles were obtained through interview surveys with the major dealers in Jakarta. In Indonesia, a 100% import duly on the CIF (cost, insurance and freight) value of CKD (complete knocked down) parts is imposed on sedans but does not apply, however, to commercial vehicles. After adjusting for other transfer payments such as the PPN tax and value added tax (VAT), the tax ratios on the total sales price of vehicles were estimated at 55% and 23% for sedans and commercial vehicles respectively (Appendix to Chapter 14, Table AP 14.3.2).

2) Tires

The market prices of tires for the various vehicle types were updated to 1989 prices (Table 14.3.1) and a total tax ratio was assumed at 19.4% of the actual market sales prices for determining the economic unit prices.

3) Fuels and Engine Oils

Bahan Bakar Minyak, or BBM, refers to the eight fuel products which are produced, processed and marketed in Indonesia by Pertamina. The Government of Indonesia sets the prices of these products, and if sales do not generate enough revenue to cover costs (including crude, refining, storage, transport and marketing), the Government pays Pertamina to cover the difference, thereby creating a domestic fuel subsidy.

<u>The Petroleum Report</u>, Indonesia, September 1988, published by the Embassy of the United States of America, Jakarta, reported that the domestic fuel subsidy was temporarily eliminated in fiscal year 1986/1987 as a result of the combined effect of lower procurement prices for crude oil and the marginally lower retail prices. For fiscal year 1987/1988, however, there was a domestic fuel subsidy totalling 401.2 billion rupiah.

For fiscal year 1988/1989, the original budget estimated a domestic fuel subsidy totalling 266.5 billion rupiah on a total domestic consumption of 26.67 billion liters of BBM. This is equivalent to a 10 rupiah per liter subsidy, assuming that the subsidy is evenly distributed among the eight fuel types of BBM. Therefore,

after adjusting for a 10% value added tax, the economic price of gasoline and diesel was increased by 10 ruplah per liter to account for the subsidy.

4) Wages

The 1985 to 1987 wage rates of drivers, conductors and maintenance labor was obtained from the Central Statistics Bureau. The average growth rate of the wages in the above period was used to estimate the wages in 1989. The wage, or earned income, of taxi drivers was estimated from an interview survey with a major taxi company. The wage levels, however, are still generally low and most are not subject to any income tax, or if at all, at around one to two percent of their total income. Under these circumstances, the economic values are considered to be equal to their market wage rates.

5) Interest Costs

A discount rate of 12% per annum was used. The interest costs in relation to speed were calculated from the annual running distance.

6) Insurance Costs

The average insurance premiums from the previous study and other studies were reviewed and incorporated into this report as follows:

Passenger Car & Pick-up	:	3.5% of vehicle Price
Bus	:	4.0% of vehicle Price
Truck	:	6.0% of vehicle Price

The average insured vehicle rate was assumed at 50%, and insurance costs were equated in consideration of the annual running distance by speed.

7) Wage Costs of Crew and Overhead Costs

The average crew size by type of vehicle was obtained from field interview results, and their wage costs were derived from their traveling hours equated by average running speed. The overhead costs of commercial vehicles were assumed at 10% of the total of other cost items.

8) Cost Equations of Vehicle Operation Costs

The various operating cost elements discussed above were individually expressed in terms of a vehicle's average running speed, in order that costs at different speeds on a level tangent road could be derived. The equations with a speed variable used in this study are based on those applied in previous similar studies in Indonesia. The equations for vehicle operating costs are shown in Appendix to Chapter 14, Table AP 14.3.3.

14.3.4 Vehicle Operating Costs by Vehicle Type

Based on the cost components and the equations of vehicle operating costs described above, vehicle operating costs by speed, by vehicle type in financial and economic prices were computed. Table 14.3.2 presents the road vehicle operating costs in both financial and economic prices.

The above vehicle operating costs were calculated for the seven representative vehicle types described earlier. The costs were then combined into the four vehicle categories of the traffic assignment based upon the vehicle composition rate shown below in Table 14.3.3.

Table 14.3.2 1989 Vehicle Operating Costs

Speed (KPH)	CAR	MINI BUS	PICK UP	MEDIUM BUS	LARGE BUS	SMALL TRUCK	LARGE TRUCK
5	1,928	817	544	1,502	2,301	936	1,673
10	1,151	501	342	987	1,562	574	1,049
15	877	388	267	811	1,307	444	824
20	728	323	225	724	1,175	377	705
25	634	284	198	671	1,102	333	627
30	568	252	176	640	1,054	301	573
35	518	229	160	618	1,023	279	535
40	481	213	149	605	1,007	265	506
45	449	199	138	598	1,000	253	. 485
50	427	190	132	597	999	244	471
55	408	1,81	127	597	1,004	238	461
60	391	175	123	603	1,014	237	458
65	380	171	121	. 611	1,032	233	457
70 -	369	169	121	. 62,3	1,052	237	459
75	362	169	122	635	1,077	239	465
80	359	169	123	649	1,103	243	476
85	358	173	129	666	1,133	249	488
90	358	175	133	684	1,165	260	503
95	358	179	137	702	1,205	266	523
100	361	187	144	723	1,244	278	545

Financial Vehicle Operating Costs (Rp./Km

Economic Vehicle Operating Costs (Rp./Km.

Speed (KPH)	CAR	MINI BUS	PICK UP	MEDIUM BUS	LARGE BUS	SMALL TRUCK	LARGE TRUCK
 5	906	641	431	1,288	1,925	840	1,451
10	554	396	274	833	1,291	509	902
15	426	309	217	678	1,073	391	703
20	356	259	182	600	959	329	597
25	311	226	158	552	893	289	528
30	277	202	144	521	848	262	481
35	254	184	130	503	822	240	447
40	236	171	121	492	805	228	420
45	221	159	113	482	798	215	400
50	210	151	107	480	794	208	388
55	201	144	103	481	796	202	380
60	195	141	100	483	805	199	374
65	191	137	99	488	817	199	374
70	187	135	99	498	834	199	377
75	186	137	101	. 508	854	201	382
80	186	137	103	518	876	206	391
85	187	139	106	532	901	212	403
90	192	146	112	549	928	219	418
95	196	150	117	563	959	230	435
100	201	154	122	581	996	239	454

Vehicle Category	Vehicle Type	Composition Rate (%)
Passenger Car	Sedan	46
· ·	Minibus (Private)	54
Pick-up	Pick-up	100
Bus	Medium Bus	19
- 	Large Bus	81
Truck	Small Truck	40
	Large Truck	60

Table 14.3.3 Vehicle Composition Rate

Source: Based on Traffic Survey by Study Team in 1988 at Location No. 12

As a result, the weighted averages of the vehicle operating costs by speed, by vehicle category in financial and economic prices were obtained as shown in Table 14.3.4. The results were then applied directly to the vehicle kilometers in different speed groups of tollway users in both network cases of "with" and "without" project tollway.

	ہ سے جب بین سند سند جب سے سے جب جب جب جب ہے ہے			
Speed (KPH)	Pass. Car	Bus	Pick- Up	Truck
دین دیر جن دیر کی سے سے بلے سے بید دی س		na an chu tha tre tre tha tha tha tha tha tha tha tha t		
5	1,328	2,149	544	1,378
10	800	1,453	342	859
15	613	1,213	267	672
20	509	1,089	225	574
25	445	1.020	198	509
30	397	975	176	464
35	362	946	160	433
40	336	931	149	410
45	314	924	138	392
50	299	923	132	380
55	285	927	127	372
60	274	936	123	370
65	267	952	121	367
70	261	970	121	370
75	258	993	122	375
80	256	1.017	123	383
85	258	1.044	129	392
90	250	1.074	133	406
20 Q5	255	1 109	137	420
100	267	1,145	144	438

Table 14.3.4 1989 Composite Vehicle Operating Costs

Financial Vehicle Operating Costs (Rp./Km.)

Economic Vehicle Operating Costs (Rp./Km.)

Speed (KPH)	Pass. Car	Bus	Pick- Up	Truck
5	763	1,804	431	1,207
10	469	1,204	274	745
15	363	998	217	578
20	304	891	182	490
25	265	828	158	432
30	237	786	144	393
35	216	761	130	364
40	201	746	121	343
45	188	738	113	326
50	178	734	107	316
55	170	736	103	309
60	166	744	100	304
65	162	754	99	304
70	159	770	99	306
75	160	788	101	310
80	160	808	103	317
85	161	831	106	327
90	167	856	112	338
95	171	884	117	353
100	176	917	122	368

14 - 12

14.4 Vehicle Time Cost

14.4.1 General

The vehicle time costs estimated here were directly applied to the vehicle hours of the potential tollway users derived from the "with" (with the project) and "without" (without the project) traffic assignment in order to estimate the vehicle time costs which would be saved with the implementation of the Tollway.

The vehicle time cost estimation involves various factors and aspects that are still controversial among specialists. Methodologies in practice have been developed for evaluating the economic viability of road projects and economical travel distances.

The method applied for this study is based on the tollway diversion equations derived from the traffic survey conducted by the Study Team in 1988.

The tollway diversion model explains the percentage tollway traffic among the potential users against the factor of the toll divided by travel time difference compared "via project tollway" with "via alternative existing road" as conceptually illustrated in the diagram below.



The diversion curve above implies that those which evaluate a saved travel time to be more than λ_1 rupiah per unit time (λ : toll/time difference) correspond to P₁%, whilst those which evaluate it to be more than λ_2 decrease to P₂%.

Therefore, the diversion curve resembles a cumulative distribution curve of time values.

14.4.2 Time Values by Vehicle Type

Tollway diversion equations were estimated in Chapter 6, section 6.2.2. The diversion equation differentiated by time value (λ) shows the probability density distribution.

Based on the obtained probability distribution function a median value of toll/time difference (λ : time value), that is a value corresponding to a diversion rate of 50%, is calculated following the equation below:

$$P = \frac{K}{1 + \alpha(T/S)^{\beta}} = 50(\%)$$

Therefore,

$$\lambda = T = S \left\{ \frac{1}{\alpha} \left(\frac{k}{P} - 1 \right) \right\}^{1/\beta}$$

where, P: Diversion Rate (%)

- T: Toll per travel time difference (Rp./min.) between "via tollway" and "via alternative route"
- S: Shift factor (for adjusting income level in different years)
- α,β,Κ: Parameters of the diversion equation model(See Section 6.2.2)

Applying the above method to the previously estimated tollway diversion equations, time values for each vehicle time were estimated below:

Passenger car	;	$\lambda = S \cdot (1/\alpha)^{1/\beta} = 1.0 \times (1/2.77992 \times 10^{-5})^{1/2.080629}$
(Median Value:	P = 50%)	≠ 155 Rp./min. = 9,300 Rp./hr.
Pick-up	:	$\lambda = S(1.25/\alpha)^{1/\beta} = 1.0 \text{ x} (1.25/2.20822 \text{ x} 10^{-4})^{1/1.803121}$
(Median Value:	P = 40%)	≑ 121 Rp./min. = 7,260 Rp./hr.
Truck	:	$\lambda = S \cdot (1.67/\alpha)^{1/\beta} = 1.0 \times (1.67/2.07866 \times 10^{-5})^{1/2.276770}$
(Median Value:	P = 30%)	≠ 143 Rp./min. = 8,580 Rp./hr.

A tollway diversion model for buses was not satisfactorily estimated from the traffic data collected through the survey in 1988. Therefore, an income approach to estimate non-car owners was employed and the average occupancy per bus was used to derive the bus time cost.

Consequently, the vehicle time costs were estimated as shown in Table 14.4.1.

9,300
7,260
8,580
17,100

Table 14.4.1 Vehicle Time Cost

Note: * Including mini buses for private use

14.5 Economic Benefits

14.5.1 General

The quantified economic benefits which would be realized from implementation of the project are defined as the saving in travel costs when comparing the "with" and "without" project conditions. The toll revenue created by the project is regarded as a transfer payment, and is therefore excluded from the benefits, because the toll is paid by the toll road users in return for the expected savings in travel costs and/or increase in safety and comfort of travel.

Other economic benefits would also be realized from the implementation of the project which have not been quantified. The project would create additional short-term employment in the construction of the tollway and this would have a multiplier effect in the project area. Long-term jobs would also be created through the staff requirements for operation and maintenance. The tollway could also be expected to have a positive effect on industrial development. Increased efficiency in the transportation of goods should benefit both producers and consumers. In addition, the tollway would have a favorable influence on tourism development, by providing faster and more comfortable travel services. These and other benefits have not been quantified for the economic analysis; therefore, the estimated project benefits can be considered to be on the conservative side.

14.5.2 Economic Benefits in Travel Costs

As mentioned above, the quantified economic benefits in travel costs are defined as the savings in economic travel costs when comparing the "with" and "without" project situations. Travel costs are divided into vehicle operating cost and time cost.

The "with" project situation is the "with" project traffic assignment in vehiclekilometers and vehicle-hours of tollway users on their routes between origin and destination, including the proposed Cikampek-Cirebon Tollway. The "without" project condition is the traffic assignment of the above tollway users on their routes "without" the proposed tollway. The total daily economic vehicle operating costs, in both the "with" and "without" conditions, were calculated by taking the daily vehicle-kilometers of the traffic assignment computed under Q-V conditions of road links and multiplying them by the respective vehicle operating costs by speed. These daily costs were then converted to total annual costs by multiplying by 365. The economic benefit in operating costs was then taken as the savings in operating costs when comparing the total "with" and "without" project vehicle operating costs.

A similar method was followed in estimating the economic benefits of tollway users in time costs where the total vehicle-hours were applied directly to the time costs per hour in the "with" and "without" project conditions.

After converting from total daily time costs to yearly time costs the costs were netted out to arrive at the savings in time costs. These savings in vehicle operating costs and time costs are summarized for the planning years as described in Table 14.5.1.

			(1	Unit: Rp. Million/Year)
·	Economic Benefits	of Savings In:		
Year	Vehicle Operating Costs	Time Costs	Total Benefits	Remarks
1995	3,680	59,145	62,825	Present Pattern Model
2005	(50,227) 208,738	(176,270) 430,861	(226,497) 639,599	(Present Pattern Model) Gravity Model
2015	(250,787) 553,589	(585,367) 1,080,224	(836,154) 1,633,813	(Present Pattern Model) Gravity Model

Table 14.5.1 Estimated Economic User Benefits of Project Tollway

14.6 Economic Cost-Benefit Analysis and Project Returns

14.6.1 Basic Assumptions and Methodology

The analysis follows the conventional discounted cash flow methodology in determining the net present value (NPV), the economic internal rate of return (EIRR), and the benefit cost ratio (B/C). These efficiency measures will establish the economic viability of the tollway and indicate the sensitivity of the project's economic viability to changes in project costs and benefits.

The economic costs in the "without" project condition have conservatively been defined as the travel costs that are expected in absence of the Tollway. Additional "without" project costs could be allocated as a result of higher maintenance and repair costs on the alternative routes of project tollway users, which would occur "without" the project due to higher traffic volumes. Since these additional "without" project costs would directly increase the incremental project benefit, the practical exclusion of these costs adds another conservative element into the analysis of the project's viability.

Apart from the elements previously discussed, the basic assumptions for the economic project cost-benefit analysis are described below:

Base Year	:	1989
Project Life	:	25 years after the completion of the full length between
		Cikampek and Cirebon
Prices	:	Constant 1989 prices
Residual Value	:	None

14.6.2 Economic Cost-Benefit Analysis

The economic project costs were previously discussed in Section 14.2. The economic benefits from savings in vehicle operating costs and time costs for the planning years were discussed previously in Section 14.5 and these were presented in Table 14.5.1. The benefits in the intermediate years were interpolated based on the projected vehicle kilometers and those beyond the year 2015 were held constant.

The total economic project cost and benefit streams are presented in Table 14.6.1. The cash flow or incremental project benefit stream is the basis for the internal rate of return calculations. The project costs and benefits streams at their net present values are the basis for the benefit-cost ratio calculations.

Following the conventional discounted cash flow methodology, the efficiency measures were calculated and the results are as follows:

Internal rate of return (EIRR) = 32.28% Net present value at 15% (NPV) = 818,896 Million Rp. at 1989 constant price Benefit Cost ratio at 15% (B/C) = 4.29

_	PROJECT COSTS			BENEFITS	
- YEAR	CAPITAL COSTS	O/M COSTS	TOTAL COSTS	TOTAL SAVINGS	PROJECT BENEFIT
1989	0	0	0	0	(
199 0	0	0	0	0	
1991	3,343	0	3,343	0	-3,34
1992	6,687	0	6,687	0	-6,68
1993	59,144	0	59,144	. 0	-59,144
1994	80,917	0	80,917	0	-80,91
1995	156,440	0	156,440	0	- 156, 44
1996	176,940	0	176,940	. 0	-176,94
1997	125,006	0	125,006	0	-125,000
1998	0	14,186	14,186	111,927	97,74
1999	0	14,186	14,186	187,309	173,123
2000	0	14,186	14,186	262,690	248,504
2001	0	14,186	14,186	338,072	323,886
2002	0	14,186	14,186	413,454	399,268
2003	0	14,186	14,186	488,836	474,650
2004	0	14,186	14,186	564,217	550,03
2005	0	14,186	14,186	639,599	625,413
2006	0	14,186	14,186	739,020	724,834
2007	0	14,186	14,186	838,442	824,250
2008	27,648	14,186	14,186	937,863	923,677
2009	27,648	14,186	14,186	1,037,285	1,023,09
2010	0	15,099	15,099	1,136,706	1,121,607
2011	0	15,099	15,099	1,236,127	1,221,028
2012	0	15,099	15,099	1,335,549	1,320,450
2013	23,552	15,099	15,099	1,434,970	1,419,87
2014	23,552	15,099	15,099	1,534,392	1,519,293
2015	0	15,464	15,464	1,633,813	1,618,349
2016	0	15,464	15,464	1,633,813	1,618,349
2017	0	15,464	15,464	1,633,813	1,618,349
2018	0	15,464	15,464	1,633,813	1,618,349
2019	0	15,464	15,464	1,633,813	1,618,349
2020	0	15,464	15,464	1,633,813	1,618,349
2021	0	15,464	15,464	1,633,813	1,618,349
2022	0	15,464	15,464	1,633,813	1,618,349
 10TAI	710 877		077 016	26 306 067	25 320 064

Table 14.6.1 Economic Project Cost and Benefit Streams

ECONOMIC IRR= 32.28%

NET PRESENT VALUE Disc. at 15%= 818,896

B/C RATIO 4.29

1) Sensitivity to Traffic Demand

A lower traffic demand forecast can be used to ensure the economic feasibility of the project tollway. The demand forecast derived from the OD matrix by the present pattern model shows quite slow growth of the tollway traffic, because the model does not incorporate into its formula the factor of reduced time of travel via the proposed tollway.

In order to avoid over stating the economic benefit, tollway traffic volume estimated with the present pattern method was used to examine how the IRR and other evaluation parameters would differ from those calculated previously as a base case.

The total benefit from savings in vehicle travel costs are compared in Table 14.5.1, section 14.5.2.

The analysis result is presented in Table 14.6.2 and it shows that evaluation parameters still maintain a high level of project feasibility, that is, EIRR equals 22.77%, Net Present Value is 262,026 million Rupiah at 1989 constant price and Benefit-Cost ratio is 2.05.

INCREMENTAL PROJECT BENEFIT	BENEFITS TOTAL SAVINGS	PROJECT COSTS			-
		TOTAL COSTS	O/M Costs	CAPITAL	YEAR
C	0	0	0	0	1989
0	0	0	0	• 0	1990
-3,343	0	3,343	0	3,343	1991
-6,687	0	6,687	0	6,687	1992
-59,144	0	59,144	0	59,144	1993
-80,917	0	80,917	0	80,917	1994
-156,440	0	156,440	0	156,440	1995
-176,940	- O	176,940	C	176,940	1996
-125,006	0	125,006	0	125,006	1997
97,741	111,927	14,186	14,186	0	1998
114,108	128,294	14,186	14,186	0	1999
130,475	144,661	14,186	14,186	0	2000
146,842	161,028	14,186	14,186	0	2001
163,209	177,395	14,186	14,186	. 0	2002
179,577	193,763	14,186	14,186	0	2003
195,944	210,130	14,186	14,186	0	2004
212,311	226,497	14,186	14,186	0	2005
273,277	287,463	14,186	14,186	0	2006
334,242	348,428	14,186	14,186	· • • 0	2007
395,208	409,394	14,186	14,186	27,648	2008
456,174	470,360	14,186	14,186	27,648	2009
516,227	531,326	15,099	15,099	0	2010
577,192	592,291	15,099	15,099	0	2011
638,158	653,257	15,099	15,099	0	2012
699,124	714,223	15,099	15,099	23,552	2013
760,089	775,188	15,099	15,099	23,552	2014
820,690	836,154	15,464	15,464	0	2015
820,690	836,154	15,464	15,464	0	2016
820,690	836,154	15,464	15,464	0	2017
820,690	836,154	15,464	15,464	0	2018
820,690	836,154	15,464	15,464	0	2019
820,690	836,154	15,464	15,464	Q	2020
820,690	836,154	15,464	15,464	0	2021
820,690	836, 154	15,464	15,464	0	2022
11,846,941	12,824,857	977,916	369,439	710,877	TOTAL

Table 14.6.2Economic Project Cost and Benefit Streams by
Present Pattern Model for 1995, 2005 and 2015

ECONOMIC IRR 22.77%

NET PRESENT VALUE Disc. at 15% 262,026

B/C RATIO 2.05

2) Sensitivity to Alteration of Benefit and Cost

Assuming that the benefit and cost stream might alter $\pm 10\%$, $\pm 20\%$ and $\pm 30\%$, the effect on the economic evaluation parameters was analyzed and the result is summarized in Table 14.6.3.

Cost\Benefit	Base	-10%	-20%	-30%
Base	32.28	30.69	29.01	27.20
+10%	30.89	29.39	27.77	26.02
+20%	29.69	28.24	26.67	24.97
+30%	28.62	27.21	25.69	24.03

Table 14.6.3 EIRR by Altered Benefit and Cost

Even the most severe case of -30% benefit and +30% cost still maintains a high internal rate of return of 24.03%.

According to the above analysis it appears that a percentage increase in the cost has less effect on IRR than a reduction of benefit by the same percentage of negative value.