

2.3.11 Future Destinations (LPA) of Waste Haulage Trucks by Origin (Rayon)

It is planned that a new LPA in Benowo will open in 1996. Commencement of waste receiving will differ by origin (Rayon) of waste, and by closure schedule of the existing LPA in Keputih and Lakarsantri.

It is assumed that all waste generated in Center, North and South Rayons will be hauled to the new LPA in Benowo in 1996 and thereafter. Waste of West Rayon will be hauled to the new LPA in Benowo in 1997. In 1998 and thereafter, all waste in Surabaya including East Rayon will be hauled to the new LPA in Benowo. Table 3.2-5 shows the destinations (LPA) to be used by origin and by year.

Table 3.2-5 Future Destinations (LPA) of Waste Haulage by Waste Origin (Rayon)

| Year | Waste Hauled from Center | Waste Hauled from North | Waste Hauled from East | Waste Hauled from South | Waste Hauled from West |
|------|--------------------------|-------------------------|------------------------|-------------------------|------------------------|
| 1993 | Keputih | Keputih | Keputih | Lakarsantri | Lakarsantri |
| 1994 | Keputih | Keputih | Keputih | Lakarsantri | Lakarsantri |
| 1995 | Keputih | Keputih | Keputih | Lakarsantri | Lakarsantri |
| 1996 | Benowo | Benowo | Keputih | Benowo | Lakarsantri |
| 1997 | Benowo | Benowo | Keputih | Benowo | Benowo |
| 1998 | Benowo | Benowo | Benowo | Benowo | Benowo |
| 1999 | Benowo | Benowo | Benowo | Benowo | Benowo |

2.3.12 Target Average Waste Amount to be Hauled per Truck per Day

1) Method of Estimation

Target average waste amount to be hauled per truck per day (expressed as A below) is estimated through the following calculation:

$$A = b \times c$$

where, b: Target average waste amount to be hauled per trip per truck

c: Target average number of trip to be made per truck per day

2) Target Average Waste Amount per Trip per Truck

Target average waste amounts per trip per trucks are estimated as follows:

a. Arm-roll truck with 8 m³ container: 2.376 ton/trip/truck

Calculation: 8 m³ x 90 % x 0.33 ton/m³ = 2.376 ton/trip/truck

Assumptions used:

- Average utilization of container capacity: 90 % of the container
- Average waste density in the container: 0.33 ton/m³

(The average waste density 0.33 ton/m³ is used based on the JICA Study Team' waste survey conducted in both rainy and dry seasons.)

b. Arm-roll truck with 14 m³ container: 4.158 ton/trip/truck

Calculation: 14 m³ x 90 % x 0.33 ton/m³ = 4.158 ton/trip/truck

Assumptions used:

- Average utilization of container capacity: 90 % of the container
- Average waste density in the container: 0.33 ton/m³

3) Haulage Distance between LPA and Waste Origins (Rayon) and Travel Time

a. Haulage Distance

The haulage distance between waste origins and LPA (Keputih, Lakarsantri and Benowo) are estimated as shown in the table below based upon the truck trip survey conducted by JICA Study Team.

Table 3.2-6 Haulage Distance to LPA from Waste Origin (Rayon)

| Destination LPA | Waste Hauled from Center | Waste Hauled from North | Waste Hauled from East | Waste Hauled from South | Waste Hauled from West |
|-----------------|--------------------------|-------------------------|------------------------|-------------------------|------------------------|
| Keputih | 11 km | 16 km | 3 km | Not Hauled | Not Hauled |
| Lakarsantri | 17 km | Not Hauled | Not Hauled | 12 km | 2 km |
| Benowo | 23 km | 21 km | 28 km | 24 km | 17 km |

b. Haulage Time

Time taken for one way waste haulage trip from waste origins to LPA (Keputih, Lakarsantri and Benowo) is estimated as shown in the table below based upon the truck trip survey conducted by JICA Study Team.

Table 3.2-7 One Way Haulage Trip Time from Waste Origins to LPA

Unit: Minutes per one way trip

| Destination LPA | Waste Hauled from Center | Waste Hauled from North | Waste Hauled from East | Waste Hauled from South | Waste Hauled from West |
|-----------------|--------------------------|-------------------------|------------------------|-------------------------|------------------------|
| Keputih | 18 min. | 33 min. | 10 min. | Not Hauled | Not Hauled |
| Lakarsantri | 35 min. | Not Hauled | Not Hauled | 30 min. | 10 min. |
| Benowo | 45 min. | 45 min. | 65 min. | 50 min. | 35 min. |

4) Target Trip Number

Trip number per truck per day differ by origin and destination of trip. Target average trip numbers as shown in the table below are used as basis for estimation of average waste amounts to be hauled per arm-roll truck per day, which in turn are used for estimation of number of arm-roll trucks needed for waste haulage.

Table 3.2-8 Target Average Round Trip Numbers per Truck per Day

Unit: Round trips/truck/day

| Origin of Trips | Destination LPA | | |
|-----------------|-----------------|-----------------|--------------------|
| | Keputih LPA | Lakarsantri LPA | Planned Benowo LPA |
| 1. Center | 7.8 | N.A. | 3.8 |
| 2. North | 4.9 | N.A. | 3.8 |
| 3. East | 11.4 | N.A. | 2.8 |
| 4. South | N.A. | 5.3 | 3.5 |
| 5. West | N.A. | 11.4 | 4.7 |

Note: N.A. stands for not applicable; waste generated in the areas marked with N.A. are not hauled to the destination indicated.

The above-shown average round trip numbers are estimated based on 1) the trip study conducted by the Study Team, 2) assumption that net working time is 400 minutes per worker per day, and 3) assumption that loading of containers and waste dumping take 15 minutes on average per trip.

Consideration on the Future Traffic Congestion

Some people may be worried that number of trips may decrease in the future because the future traffic congestion would get worse due to increasing number of cars in Surabaya. However, it is considered possible to maintain the target trip numbers at the target level in view of the following:

- a. It is possible for waste haulage trucks to avoid traffic congestion by leaving the garage early in the morning. At present, KMS' trucks leave between 7:30 and 8:30 am. It is advised that KMS trucks should leave the garage before 7:30 am.
- b. KMS has a plan to construct new roads during the SUDP period, which could alleviate traffic congestion.

5) Target Average Waste Amount to be Hauled per Truck per Day

Based on the two kinds of information shown in the previous two sections (waste amount per trip, and trip number), target average waste amounts to be hauled per truck per day are estimated as shown in the table below:

Table 3.2-9 Target Daily Average Waste Amount to be Hauled per Truck (Arm-Roll Truck with 8 m³ Container)

Unit: ton per truck per day

| Origin of Trips | Destination LPA | | |
|-----------------|-----------------|-----------------|--------------------|
| | Keputih LPA | Lakarsantri LPA | Planned Benowo LPA |
| 1. Center | 18.5 | N.A. | 9.0 |
| 2. North | 11.6 | N.A. | 9.0 |
| 3. East | 27.1 | N.A. | 6.7 |
| 4. South | N.A. | 12.6 | 8.3 |
| 5. West | N.A. | 27.1 | 11.2 |

Table 3.2-10 Target Daily Average Waste Amount to be Hauled per Truck (Arm-Roll Truck with 14 m³ Container)

Unit: ton per truck per day

| Origin of Trips | Destination LPA | | |
|-----------------|-----------------|-----------------|--------------------|
| | Keputih LPA | Lakarsantri LPA | Planned Benowo LPA |
| 1. Center | 32.4 | N.A. | 15.8 |
| 2. North | 20.4 | N.A. | 15.8 |
| 3. East | 47.4 | N.A. | 11.6 |
| 4. South | N.A. | 22.0 | 14.6 |
| 5. West | N.A. | 47.4 | 19.5 |

2.3.13 Waste to be Hauled by Type of Trucks

1) Use of Contractors for Haulage with Small Containers and Compactor Trucks

At present, KMS applies two major waste haulage systems, i.e., 1) haulage system with large containers and arm-roll trucks, and 2) haulage system with small containers and REL compactor trucks. It is planned that KMS will continue to apply these two major systems in the future.

However, KMS will concentrate on the haulage system with large containers and arm-roll trucks in the future, and will not purchase compactor trucks and small containers.

KMS will use contractors for the waste haulage with compactors and small containers because it is expected that contractors will be very cost-effective in the application of this haulage system.

In addition, it can be expected that the use of contractors for this haulage system will cause the haulage service coverage to increase as the contractors would wish to purchase more equipment (small containers and trucks) to increase waste haulage amounts if the remuneration to the contractors is based on the amount of waste hauled.

2) Open Dump Trucks

KMS will use 5 trucks; one for each Rayon for haulage of the following special waste irregularly collected:

- 1) Bulky waste
- 2) Construction debris such as stones, sand and concrete
- 3) Trees cut
- 4) Waste collected from rivers and drainage by citizens

Future waste amounts to be hauled by KMS and its contractors, and by type of trucks are shown in the table below:

Table 3.2-11 Future Amount of Waste to be Hauled by Type of Trucks

Unit : ton/day on rainy season base

| Year | Waste Amount to be Hauled under KMS' Responsi- bility | To be Hauled by K M S' Own Trucks | | | | To be Hauled by Contractors | | | |
|------|---|-----------------------------------|--------------------------|------------------------|---------------------|-----------------------------|--------------------------|------------------------|-----------------------------------|
| | | Arm- Roll Trucks | Com- pactor Trucks | Open Dump Trucks | KMS Total | Arm- Roll Trucks | Com- pactor Trucks | Open Dump Trucks | Con- tractors' Total |
| | (1) | [2] | (3) | (4) | (5)=(2)+ (3)+(4) | [6] | [7] | [8] | (9)=[6]+ [7]+[8]= (1) - [5] |
| 1992 | 989 | 539 | 121 | 31 | 691 | 0 | 0 | 298 | 298 |
| 1993 | 1,027 | 617 | 60 | 14 | 691 | 217 | 69 | 50 | 336 |
| 1994 | 1,070 | 658 | 30 | 5 | 691 | 246 | 108 | 25 | 379 |
| 1995 | 1,117 | 691 | 0 | 5 | 691 | 266 | 148 | 12 | 426 |
| 1996 | 1,167 | 691 | 0 | 5 | 691 | 312 | 158 | 6 | 476 |
| 1997 | 1,222 | 691 | 0 | 5 | 691 | 362 | 169 | 0 | 531 |
| 1998 | 1,282 | 691 | 0 | 5 | 691 | 410 | 181 | 0 | 591 |
| 1999 | 1,350 | 691 | 0 | 5 | 691 | 464 | 195 | 0 | 659 |

Note: Waste to be hauled by contractors' compactor trucks (column 7) will increase by a 20 % of annual incremental waste (column 1) in 1996 and thereafter.

2.3.14 Waste Haulage Amount by Rayon (Districts)

1) Differential Waste Increases by Rayon

Surabaya has 5 Rayon, i.e., Center, North, East, South and West. Table 3.2-12 shows projection of the future waste amounts to be hauled under KMS' responsibility. The future waste amounts are projected based upon the projection of future population. It is projected that waste amount in the Center will be rather constant, while the waste amounts in the East, South and West will increase rapidly.

Table 3.2-12 Projection of Future Waste Haulage Amount by Rayon

Unit: ton/day on rainy season base

| Year | Center | North | East | South | West | Total |
|------|----------------|----------------|----------------|----------------|----------------|-----------------|
| 1992 | 207 (20.9%) | 174 (17.6%) | 298 (30.1%) | 235 (23.8%) | 75 (7.6%) | 989 (100%) |
| 1993 | 208 (20.2%) | 180 (17.5%) | 310 (30.2%) | 245 (23.9%) | 84 (8.2%) | 1,027 (100%) |
| 1994 | 209 (19.5%) | 186 (17.4%) | 324 (30.3%) | 257 (24.0%) | 94 (8.8%) | 1,070 (100%) |
| 1995 | 210 (18.8%) | 193 (17.3%) | 340 (30.4%) | 269 (24.1%) | 105 (9.4%) | 1,117 (100%) |
| 1996 | 212 (18.2%) | 201 (17.2%) | 356 (30.5%) | 282 (24.2%) | 116 (9.9%) | 1,167 (100%) |
| 1997 | 215 (17.6%) | 209 (17.1%) | 374 (30.6%) | 298 (24.4%) | 126 (10.3%) | 1,222 (100%) |
| 1998 | 215 (16.8%) | 218 (17.0%) | 394 (30.7%) | 315 (24.6%) | 140 (10.9%) | 1,282 (100%) |
| 1999 | 219 (16.2%) | 228 (16.9%) | 415 (30.8%) | 335 (24.8%) | 153 (11.3%) | 1,350 (100%) |

2) Waste Haulage by KMS and Contractors

It is planned that KMS' trucks will concentrate on the waste haulage in the Center, North and East Rayon, while KMS will use contractors for hauling waste from West Rayon at first, and then gradually increase waste haulage activity in South and East Rayon.

Respective amounts to be hauled by KMS' trucks and contractors are shown in the following two tables that were produced as a result of decomposition of the above table.

Table 3.2-13 Projection of Future Waste by Rayon to be Hauled by KMS' Trucks

Unit: ton/day on rainy season base

| Year | Center | North | East | South | West | Total |
|------|--------|-------|------|-------|------|-------|
| 1992 | 133 | 99 | 286 | 110 | 63 | 691 |
| 1993 | 177 | 149 | 263 | 101 | 1 | 691 |
| 1994 | 178 | 158 | 275 | 79 | 1 | 691 |
| 1995 | 178 | 164 | 289 | 59 | 1 | 691 |
| 1996 | 180 | 171 | 302 | 37 | 1 | 691 |
| 1997 | 183 | 178 | 318 | 11 | 1 | 691 |
| 1998 | 183 | 185 | 321 | 1 | 1 | 691 |
| 1999 | 186 | 194 | 309 | 1 | 1 | 691 |

Table 3.2-14 Projection of Future Waste by Kecamatan to be Hauled by KMS' Contractors

Unit: ton/day on rainy season base

| Year | Center | North | East | South | West | Total |
|------|--------|-------|------|-------|------|-------|
| 1992 | 74 | 75 | 12 | 125 | 12 | 298 |
| 1993 | 31 | 27 | 47 | 144 | 83 | 336 |
| 1994 | 31 | 28 | 49 | 178 | 93 | 379 |
| 1995 | 32 | 29 | 51 | 210 | 104 | 426 |
| 1996 | 32 | 30 | 54 | 245 | 115 | 476 |
| 1997 | 32 | 31 | 56 | 287 | 125 | 531 |
| 1998 | 32 | 33 | 73 | 314 | 139 | 591 |
| 1999 | 33 | 34 | 106 | 334 | 152 | 659 |

2.3.15 Planned Waste Amount to be Hauled by KMS' New Trucks by Waste Origin and by Type of Trucks

The following tables show planned waste haulage waste amounts to be hauled by KMS' new trucks by area by types of trucks.

**Table 3.2-15 Planned Waste Amount to be Hauled
by KMS' Existing Trucks and New Trucks**

Unit: ton/day on rainy season base

| Year | Total (1) | Waste to be Hauled by Existing Trucks (2) | Waste to be Hauled by New Trucks (3)= (1) - (2) |
|------|--------------|--|--|
| 1992 | 691 | 691 | 0 |
| 1993 | 691 | 316 | 375 |
| 1994 | 691 | 122 | 569 |
| 1995 | 691 | 21 | 670 |
| 1996 | 691 | 0 | 691 |
| 1997 | 691 | 0 | 691 |
| 1998 | 691 | 0 | 691 |
| 1999 | 691 | 0 | 691 |

**Table 3.2-16 Planned Waste Amount to be Hauled by KMS' New Arm-Roll
Trucks (for 8 m³ Containers) by Waste Origin**

Unit: ton/day on rainy season base

| Year | Total (1)= (2)+(3)+(4) +(5)+(6) | Center (2) | North (3) | East (4) | South (5) | West (6) |
|------|--|---------------|--------------|-------------|--------------|-------------|
| 1992 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993 | 72 | 19 | 16 | 27 | 10 | 0 |
| 1994 | 86 | 22 | 19 | 35 | 10 | 0 |
| 1995 | 186 | 48 | 44 | 78 | 16 | 0 |
| 1996 | 199 | 52 | 49 | 88 | 10 | 0 |
| 1997 | 192 | 51 | 50 | 88 | 3 | 0 |
| 1998 | 185 | 49 | 49 | 87 | 0 | 0 |
| 1999 | 178 | 48 | 50 | 80 | 0 | 0 |

Table 3.2-17 Planned Waste Amount to be Hauled by KMS' New Arm-Roll Trucks (for 14 m³ Containers) by Waste Origin

Unit: ton/day on rainy season base

| Year | Total (1)= (2)+(3)+(4) +(5)+(6) | Center (2) | North (3) | East (4) | South (5) | West (6) |
|------|--|---------------|--------------|-------------|--------------|-------------|
| 1992 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993 | 303 | 78 | 65 | 116 | 44 | 0 |
| 1994 | 480 | 124 | 110 | 191 | 55 | 0 |
| 1995 | 480 | 124 | 114 | 202 | 40 | 0 |
| 1996 | 488 | 127 | 121 | 214 | 26 | 0 |
| 1997 | 494 | 131 | 127 | 229 | 7 | 0 |
| 1998 | 501 | 133 | 134 | 234 | 0 | 0 |
| 1999 | 508 | 137 | 143 | 228 | 0 | 0 |

Table 3.2-18 Planned Waste Amount to be Hauled by KMS' New Dump Trucks by Waste Origin

Unit: ton/day on rainy season base

| Year | Total (1)= (2)+(3)+(4) +(5)+(6) | Center (2) | North (3) | East (4) | South (5) | West (6) |
|------|--|---------------|--------------|-------------|--------------|-------------|
| 1992 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1994 | 3 | 1 | 1 | 1 | 0 | 0 |
| 1995 | 4 | 1 | 1 | 1 | 1 | 0 |
| 1996 | 4 | 1 | 1 | 1 | 1 | 0 |
| 1997 | 5 | 1 | 1 | 1 | 1 | 1 |
| 1998 | 5 | 1 | 1 | 1 | 1 | 1 |
| 1999 | 5 | 1 | 1 | 1 | 1 | 1 |

2.3.16 Truck Requirement by Rayon and by Type

Number (not the number of additional purchase units) of trucks to be used for waste haulage by origin (Rayon) are estimated as shown in the tables below based on the planned waste haulage amounts by waste origin and type of trucks, and the target waste haulage amounts per truck per day.

If the number of trucks calculated have decimals, the decimals are rounded up.
 (Example: 1.23 units of truck is rounded up to 2 units of truck.)

Table 3.2-19 Number of New Arm-Roll Trucks Serving for 8 m³ Containers to be Used

Unit: Number of trucks

| Year | Total (1)= (2)+(3)+(4) +(5)+(6) | Center (2) | North (3) | East (4) | South (5) | West (6) |
|------|--|---------------|--------------|-------------|--------------|-------------|
| 1992 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993 | 6 | 2 | 2 | 1 | 1 | 0 |
| 1994 | 7 | 2 | 2 | 2 | 1 | 0 |
| 1995 | 11 | 3 | 4 | 3 | 1 | 0 |
| 1996 | 17 | 6 | 6 | 4 | 1 | 0 |
| 1997 | 17 | 6 | 6 | 4 | 1 | 0 |
| 1998 | 26 | 6 | 6 | 14 | 0 | 0 |
| 1999 | 25 | 6 | 6 | 13 | 0 | 0 |

Table 3.2-20 Number of New Arm-Roll Trucks Serving for 14 m³ Container to be Used

Unit: Number of trucks

| Year | Total (1)= (2)+(3)+(4) +(5)+(6) | Center (2) | North (3) | East (4) | South (5) | West (6) |
|------|--|---------------|--------------|-------------|--------------|-------------|
| 1992 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993 | 12 | 3 | 4 | 3 | 2 | 0 |
| 1994 | 18 | 4 | 6 | 5 | 3 | 0 |
| 1995 | 17 | 4 | 6 | 5 | 2 | 0 |
| 1996 | 24 | 9 | 8 | 5 | 2 | 0 |
| 1997 | 24 | 9 | 9 | 5 | 1 | 0 |
| 1998 | 39 | 9 | 9 | 21 | 0 | 0 |
| 1999 | 39 | 9 | 10 | 20 | 0 | 0 |

Table 3.2-21 Number of New Dump Trucks to be Used

Unit: Number of trucks

| Year | Total (1)= (2)+(3)+(4) +(5)+(6) | Center (2) | North (3) | East (4) | South (5) | West (6) |
|------|--|---------------|--------------|-------------|--------------|-------------|
| 1992 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1994 | 3 | 1 | 1 | 1 | 0 | 0 |
| 1995 | 4 | 1 | 1 | 1 | 1 | 0 |
| 1996 | 4 | 1 | 1 | 1 | 1 | 0 |
| 1997 | 5 | 1 | 1 | 1 | 1 | 1 |
| 1998 | 5 | 1 | 1 | 1 | 1 | 1 |
| 1999 | 5 | 1 | 1 | 1 | 1 | 1 |

Table 3.2-22 Number of New Trucks to be Used by Type

(This table is prepared based on the previous 3 tables.)

| Year | Arm-Roll Trucks for 8 m ³ Containers (1) | Arm-Roll Trucks for 14 m ³ Containers (2) | Dump Trucks (3) | Total (1)+(2)+(3)= (4) |
|------|--|---|--------------------|------------------------------|
| 1992 | 0 | 0 | 0 | 0 |
| 1993 | 6 | 12 | 0 | 18 |
| 1994 | 7 | 18 | 3 | 28 |
| 1995 | 11 | 17 | 4 | 32 |
| 1996 | 17 | 24 | 4 | 45 |
| 1997 | 17 | 24 | 5 | 46 |
| 1998 | 26 | 39 | 5 | 70 |
| 1999 | 25 | 39 | 5 | 69 |

Table 3.2-23 Remaining Number of the Existing Trucks

| Year | Arm-Roll Trucks | | | | REL Compactor Trucks | | | Open Trucks (8) | Total (4)+(7) +(8)= (9) |
|------|--|--|--|--------------------------------------|-------------------------------------|---------------------------------------|------------------------------|--------------------|----------------------------------|
| | for 6 m ³ Container (1) | for 10 m ³ Containers (2) | for 12 m ³ Containers (3) | Sub-Total (1)+(2)+ (3)= (4) | 7 GVW (6 m ³) (5) | 14 GVW (10 m ³) (6) | Sub-Total (5)+(6)= (7) | | |
| 1992 | 26 | 13 | 4 | 43 | 5 | 10 | 15 | 6 | 64 |
| 1993 | 12 | 5 | 4 | 21 | 5 | 10 | 15 | 6 | 42 |
| 1994 | 12 | 0 | 0 | 12 | 3 | 5 | 8 | 2 | 22 |
| 1995 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| 1996 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 1 |
| 1997 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1998 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1999 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

Fig. 3.2-5 compares the number of the existing trucks and new trucks. Number of new trucks will exceeds the number of the existing trucks in 1994. Most of the existing trucks will abandoned by 1995.




Fig. 3.2-5 Number of the Existing and New Trucks in Comparison

2.3.17 Container Requirement by Rayon and Type

Numbers (not the numbers of purchase units) of containers to be used by each Rayon are estimated as shown in the tables below based on the planned waste haulage amounts by waste origin and type of trucks.

If the calculated number of containers have decimals, the decimals are rounded up. (Example: 14.34 units of containers is rounded up to 15 units of containers.)

Table 3.2-24 Number of New Containers to be Used

| Year | 8 m ³ Containers | 14 m ³ Containers |
|------|-----------------------------|------------------------------|
| 1993 | 33 (2) | 77 (4) |
| 1994 | 39 (2) | 122 (6) |
| 1995 | 83 (4) | 122 (6) |
| 1996 | 89 (5) | 124 (6) |
| 1997 | 86 (5) | 125 (7) |
| 1998 | 82 (4) | 128 (7) |
| 1999 | 79 (4) | 130 (7) |

Note: Figures in parenthesis () indicate number of spare containers, which are included in the numbers without parenthesis.

2.3.18 Feasibility Study of a Large Transfer Station for Waste Haulage to the Planned Disposal Site (LPA) in Benowo

1) Background

The planned future LPA in Benowo is located further than the existing LPA in Keputih or Lakarsantri. The JICA Study Team has made a comparative study of the haulage costs with or without a large transfer station in order to know whether or not a transfer station is necessary.

2) Conclusions

As a result of the comparative study it is concluded that :

- a. Under the existing haulage system of Surabaya where there are many Depo and LPS, a large transfer station is not necessary if a final disposal site (LPA) is located within 40 km from collection areas.
- b. The above conclusion means that construction of any large transfer stations is not feasible, and therefore not advisable if a LPA is located in Surabaya.
- c. A transfer station might be necessary if a LPA is constructed outside Surabaya such as Sidoarjo.
- d. The KMS's existing haulage system with Depo and LPS is efficient as Depo and LPS serve as mini-transfer stations.

3) Cost Comparison

The haulage distances between the collection areas and Benowo LPA ranges 17 km - 30 km. As shown in the table and figure below, cost ratio between with and without a transfer station differ by the haulage distance.

If the haulage distance is 20 km, the haulage cost with a transfer station is 37 % higher than the haulage cost without a transfer station. If the haulage distance is 30 km, the haulage cost with a transfer station is still 11 % higher than the haulage cost without a transfer station. The haulage costs become identical if the haulage distance is 40 km.

Table 3.2-25 Comparison of Haulage Cost With and Without a Transfer Station

Unit: Rupiah per ton

| Distance between LPA and Collection Areas | Haulage Cost Without a Transfer Station (1) | Haulage Cost With a Transfer Station (2) |
|---|--|---|
| 10 km | 8,285 [100] | 16,462 [199] |
| 20 km | 12,759 [100] | 17,430 [137] |
| 30 km | 16,313 [100] | 18,148 [111] |
| 40 km | 18,641 [100] | 18,639 [100] |




Fig. 3.2-6 Comparison of Haulage Cost With and Without a Transfer Station

4) Major Assumption Used

The above conclusions were drawn based upon the assumptions and cost estimation as shown below :

a. Transfer Station Assumed

- a) Type: Compaction type (same as designed for Jakarta)
- b) Capacity: 1,000 ton/day
- c) Location: 5 km from central part of Surabaya
- d) Operation: 2 working shifts
- e) Investment: Rp 14,704 million

| | |
|---------------------------|--------------------------|
| 1. Main Facility: | Rp 9,293 million |
| 2. Waste Water Treatment: | Rp 1093 million |
| 3. Building: | Rp 2,457 million |
| 4. Building Facility: | Rp 682 million |
| 5. Civil work: | Rp 1,179 million |
| Total: | Rp 14,704 million |

b. Waste Haulage from Collection Areas to a Transfer Station

- a) Type and Capacity of Trucks: Arm-roll trucks with 10 m³ containers

c. Haulage Cost from a Transfer Station to LPA

- a) Type and capacity of Trucks: 40 m³ trailer
- b) Waste haulage amount: 20 ton per trailer per trip
- c) Working shifts: 2 working shifts
- d) Purchase cost of trailer: Rp 300 million per unit

d. Details of Unit Costs of Haulage with a Transfer Station

The following table shows details of haulage costs with a transfer station.

Table 3.2-26 Details of Unit Haulage Cost with a Transfer Station

Unit cost: Rupiah per Ton of waste

| Distance between LPA and Collection Areas | Unit Cost of Haulage from Collection Areas to Transfer Station (1) | Unit Cost of Transfer Station (Depreciation, Operation & maintenance) (2) | Unit Cost of Haulage from Transfer Station to LPA (3) | Total Unit Cost (1)+(2)+(3)= (4) |
|---|---|--|--|--|
| 10 km | 5,674 | 9,731 | 1,057 | 16,462 |
| 20 km | 5,674 | 9,731 | 2,025 | 17,430 |
| 30 km | 5,674 | 9,731 | 2,743 | 18,148 |
| 40 km | 5,674 | 9,731 | 3,234 | 18,639 |

More details on the assumptions and costs are shown in Volume 4 Supporting Report Part 1 Section 1.3.

2.4 Placement of Containers in Depo and LPS

2.4.1 Container Placement Plan

Table 3.2-29 shows a container placement plan with number and size (either 14 m³ or 8 m³) of containers to be placed in each of the existing Depo and LPS. This plan was prepared based on the field survey of all the existing Depo and LPS conducted with respect to the following conditions:

1. Present amount of waste hauled from each Depo and LPS
2. Space of and access to Depo and LPS to determine physical possibility to place either 14 m³ or 8 m³ containers
3. Existing status (Some Depo and LPS are not used at present.)

Space and access requirement are shown in the table below:

Table 3.2-27 Space Requirement for Placement of Containers

| | Conditions for Placement of 14 m ³ Containers | Conditions for Placement of 8 m ³ Containers |
|-----------------------------|--|---|
| 1. Length of Depo/LPS | 13 m minimum | 11 m minimum |
| 2. Width of Depo/LPS | 3 m minimum | 2.5 m minimum |
| 3. Width of Entrance | 4 m minimum | 4 m minimum |
| 4. Turning Space for Trucks | 10 m radius minimum for turning | 9 m radius minimum for turning |

Number of Depo and LPS to be placed with either 14 m³ or 8 m³ containers are as shown below:

Table 3.2-28 Number of the Existing Depo and LPS to be Placed with Containers

| | Depo & LPS to be Placed with 14 m ³ Containers | Depo & LPS to be Placed with 8 m ³ Containers | Number of Depo & LPS that Need either Expansion or Relocation |
|----------------|---|--|---|
| 1. Depo | 42 | 11 | 0 |
| 2. LPS | 40 | 61 | 6 |
| 3. Total (1+2) | 82 | 72 | 6 |

In principle, 14 m³ containers will be placed in Depo/LPS that have adequate space. As can be seen from the table above, it is possible to place 14 m³ containers in 82 Depo/LPS, while 72 Depo/LPS have to be provided with 8 m³ containers.

It should be noted that it is necessary to construct new Depo and LPS in the near future (as planned in Part 3 of this report), and also more number of containers will have to be provided as amounts of waste increase in the future.

2.4.2 Expansion of Depo and LPS

As can be seen in Table 3.2-28, there are 8 Depo/LPS as listed below where it is not possible to place either 14 m³ or 8 m³ containers. Those Depo/LPS need expansion or relocation.

1) Depo/LPS that Require either Expansion or Relocation

1. LPS Pasar Kapasan (Kel. Sidodadi, Kec. Simokerto)
2. LPS Pasar Turi (Kel. Bubutan, Kec. Bubutan)
3. LPS Pasar Tambak Rejo (Kel. Rangkah, Kec. Tambaksari)
4. LPS Pasar Bangun Rejo (Kel. Dupak, Kec. Krembangan)
5. LPS Krembangan (Kel. Krembangan Selatan, Kec. Krembangan)
6. LPS Bak Larangan (Kel. Sukolilo, Kec. Kenjeran)

2) Depo/LPS of Which Entrance Needs to be Enlarged

7. LPS Pasar Kembang (2.7 m) (Kel. Wonorejo, Kec. Tegalsari)
8. LPS Pasar Kapasan (Kel. Sukolilo, Kec. Kenjeran)

Abbreviations:

- Kel.: Kelurahan
Kec.: Kecamatan

Table 3.2-29 Container Placement Plan (1)

| No | Sub District | Kecamatan | Kelurahan | Name of Depo/LPS | Status | Hauled by | Type of Truck Currently Used | No. of the existing Containers | Estimated Waste Amount | 14 m3 Containers to be placed | 8 m3 Containers to be placed |
|----|------------------|------------|-----------------------|----------------------|--------------|------------|------------------------------|--------------------------------|------------------------|-------------------------------|------------------------------|
| 1 | Central Surabaya | Bubutan | Alun Alun Contong | Sulung | Used | KMS | 10 m3 container | 1 | 3.0 t | 1 | [2] |
| 2 | Central Surabaya | Bubutan | Bubutan | Penghela | Used | KMS | 10 m3 container | 4 | 11.9 t | 3 | N.P. |
| 3 | Central Surabaya | Bubutan | Bubutan | Depo Pimjadi | Used | KMS | 10 m3 container | 4 | 10.8 t | 3 | N.P. |
| 4 | Central Surabaya | Bubutan | Bubutan | Pasar Turi | Used | KMS | Dump truck | - | 15.5 t | N.P. | N.P. |
| 5 | Central Surabaya | Bubutan | Jepara | Babahan/Dupak | Used | KMS | 10 m3 container | 2 | 5.9 t | 2 | [3] |
| 6 | Central Surabaya | Bubutan | Tembok Dukuh | Pasar Tembok | Used | KMS | 10 m3 container | 2 | 6.0 t | 2 | N.P. |
| 7 | Central Surabaya | Bubutan | Tembok Dukuh | Depo Demak | Used | KMS | 12 m3 container | 4 | 14.3 t | 4 | N.P. |
| 8 | Central Surabaya | Genteng | Embong Kaliasin | Depo Kayoon | Used | KMS | 12 m3 container | 5 | 17.8 t | 5 | N.P. |
| 9 | Central Surabaya | Genteng | Genteng | Depo Simpang Dukuh | Used | KMS | 6 m3 container | 5 | 8.9 t | N.P. | 4 |
| 10 | Central Surabaya | Genteng | Kapasari | Pecindilan | Used | KMS | 10 m3 container | 6 | 14.9 t | 4 | N.P. |
| 11 | Central Surabaya | Genteng | Peneleh | Makan Peneleh | Used | KMS | 6 m3 container | 4 | 7.1 t | 2 | [3] |
| 12 | Central Surabaya | Simokerto | Kapasari | Gembong Gas | Used | KMS | 6 m3 container | 4 | 7.1 t | 2 | [3] |
| 13 | Central Surabaya | Simokerto | Sidodadi | Pasar Kapasan | Used | Contractor | Dump truck | - | 8.9 t | N.P. | N.P. |
| 14 | Central Surabaya | Simokerto | Simokerto | Simolawang | Used | Contractor | Dump truck | - | 11.0 t | N.P. | [5] |
| 15 | Central Surabaya | Simokerto | Simolawang | Pegirian | Used | KMS | 6 m3 container | 4 | 7.9 t | N.P. | 4 |
| 16 | Central Surabaya | Simokerto | Tambakrejo | Depo Tambakrejo | Used | KMS | 10 m3 container | 4 | 14.9 t | 4 | N.P. |
| 17 | Central Surabaya | Tegalsari | Dr. Sutomo | Pandegiling | Used | KMS | 10 m3 container | 4 | 15.0 t | 4 | N.P. |
| 18 | Central Surabaya | Tegalsari | Dr. Sutomo | Pasar Kupang | Used | KMS | 6 m3 container | 1 | 1.8 t | N.P. | 1 |
| 19 | Central Surabaya | Tegalsari | Dr. Sutomo | Taman Ketampon | Used | KMS | 6 m3 container | 3 | 5.4 t | 2 | [3] |
| 20 | Central Surabaya | Tegalsari | Kedungdoro | Kedung Anyar Wetan | Used | Contractor | Dump truck | - | 11.0 t | 3 | [5] |
| 21 | Central Surabaya | Tegalsari | Kepuran | Depo Kepuran | Used | KMS | Dump truck | - | 18.0 t | 4 | N.P. |
| 22 | Central Surabaya | Tegalsari | Kepuran | Depo Diroyo | Used | Contractor | Dump truck | - | 12.8 t | 3 | N.P. |
| 23 | Central Surabaya | Tegalsari | Tegalsari | Kedungsari | Used | KMS | 6 m3 container | 4 | 9.4 t | 3 | [4] |
| 24 | Central Surabaya | Tegalsari | Wonorejo | Pasar Kembang | Used | Contractor | Dump truck | - | 3.6 t | N.P. | 2 |
| 25 | North Surabaya | Kenjeran | Bulak | Depo Tambak Deres | Used | KMS | 6 m3 container | 1 | 1.8 t | [1] | 1 |
| 26 | North Surabaya | Kenjeran | Bulak Banteng | Depo Bulak Banteng | Will be used | - | - | - | - | P | P |
| 27 | North Surabaya | Kenjeran | Kenjeran | Kenjeran | Used | KMS | 6 m3 container | 1 | 1.8 t | [1] | 1 |
| 28 | North Surabaya | Kenjeran | Kenjeran | Depo Wiramo | Used | KMS | 6 m3 container | 1 | 0.9 t | [1] | 1 |
| 29 | North Surabaya | Kenjeran | Sidotopo Wetan | Depo Sidotopo Wetan | Used | KMS | 6 m3 container | 3 | 2.8 t | 1 | [2] |
| 30 | North Surabaya | Kenjeran | Sukolilo | Bak Larangan | Used | Contractor | Dump truck | - | 2.0 t | N.P. | N.P. |
| 31 | North Surabaya | Kenjeran | Tanah Kali Kedingding | Depo Kali Kedingding | Used | KMS | 6 m3 container | 2 | 3.0 t | 1 | [2] |
| 32 | North Surabaya | Krembangan | Dupak | Pasar Bangun Rejo | Used | Contractor | Dump truck | - | 3.0 t | N.P. | N.P. |
| 33 | North Surabaya | Krembangan | Dupak | Depo Dupak Bandarejo | Used | KMS | 6 m3 container | 4 | 7.2 t | N.P. | 4 |
| 34 | North Surabaya | Krembangan | Krembangan Selatan | Krembangan Barat | Used | KMS | 10 m3 container | 4 | 11.0 t | 3 | [5] |
| 35 | North Surabaya | Krembangan | Krembangan Selatan | Krembangan | Used | KMS | 6 m3 container | 1 | 0.6 t | N.P. | 1 |
| 36 | North Surabaya | Krembangan | Moro Krembangan | Depo Gresik | Used | KMS | 12 m3 container | 4 | 14.0 t | 4 | N.P. |

Table 3.2-29 Container Placement Plan (2)

| No | Sub District | Kecamatan | Kelurahan | Name of Depo/LPS | Status | Responsible Body | Type of Truck | No. of the existing Containers | Estimated Waste Amount | 14 m ³ Containers to be placed | 8 m ³ Containers to be placed |
|----|----------------|-----------------|-----------------|---------------------|--------------|--------------------|-----------------------------|--------------------------------|------------------------|---|--|
| 37 | North Surabaya | Krebangan | Perak Barat | Depo Tanjung Sadari | Used | Counterpart | Dump truck | - | 9.7 t | 3 | 5 |
| 38 | North Surabaya | Pabean Cantikan | Bongkaran | Depo Bunguran | Used | KMS | 6 m ³ container | 5 | 8.9 t | 3 | 4 |
| 39 | North Surabaya | Pabean Cantikan | Bongkaran | Pengampon | Used | KMS | 6 m ³ container | 4 | 7.1 t | 2 | 3 |
| 40 | North Surabaya | Pabean Cantikan | Krebangan Utara | Babaan | Used | Contractor | Dump truck | - | 9.2 t | 3 | N.P. |
| 41 | North Surabaya | Pabean Cantikan | Krebangan Utara | Pesapan Pompa | Used | Counterpart | Dump truck | - | 4.8 t | 2 | 2 |
| 42 | North Surabaya | Pabean Cantikan | Nyaplungan | Gambir | Used | Contractor | Dump truck | - | 7.5 t | N.P. | 4 |
| 43 | North Surabaya | Pabean Cantikan | Nyaplungan | Dukuh Gili | Used | KMS | 10 m ³ container | 2 | 3.0 t | 1 | 2 |
| 44 | North Surabaya | Pabean Cantikan | Perak Timur | Indrapura PLN | Used | Contractor | Dump truck | - | 1.0 t | 1 | 1 |
| 45 | North Surabaya | Pabean Cantikan | Perak Timur | Kalimas Barat | Used | KMS | 10 m ³ container | 3 | 5.9 t | 2 | 3 |
| 46 | North Surabaya | Pabean Cantikan | Perak Utara | Depo Kalimas Baru | Used | Sea Port Authority | Dump truck | - | 2.6 t | 1 | 2 |
| 47 | North Surabaya | Pabean Cantikan | Perak Utara | Teluk Kumai | Used | Sea Port Authority | 6m ³ container | 3 | 5.4 t | 2 | 3 |
| 48 | North Surabaya | Pabean Cantikan | Perak Utara | Kalianget | Used | Sea Port Authority | Dump truck | - | 1.0 t | N.P. | 1 |
| 49 | North Surabaya | Pabean Cantikan | Perak Utara | Depo Tanjung Priok | Used | Sea Port Authority | Dump truck | - | 7.0 t | 2 | 3 |
| 50 | North Surabaya | Pabean Cantikan | Perak Utara | Teluk Nibung | Used | KMS | 6 m ³ container | 1 | 1.8 t | 1 | 1 |
| 51 | North Surabaya | Pabean Cantikan | Perak Utara | Janurut Selatan | Used | KMS | 6 m ³ container | 2 | 3.6 t | 1 | 2 |
| 52 | North Surabaya | Pabean Cantikan | Perak Utara | Nilam | Used | KMS | 6 m ³ container | 1 | 1.8 t | 1 | 1 |
| 53 | North Surabaya | Pabean Cantikan | Perak Utara | Mirah | Used | KMS | 6 m ³ container | 1 | 1.8 t | 1 | 1 |
| 54 | North Surabaya | Pabean Cantikan | Perak Utara | Jakarta Lloyd | Used | KMS | 6 m ³ container | 1 | 1.8 t | 1 | 1 |
| 55 | North Surabaya | Semampir | Ampel | Pasar Pegrian | Used | KMS | 10 m ³ container | 4 | 9.6 t | 3 | 4 |
| 56 | North Surabaya | Semampir | Ampel | Nyaplungan | Used | KMS | 10 m ³ container | 2 | 5.0 t | 2 | 3 |
| 57 | North Surabaya | Semampir | Sidotopo | Kunti | Used | Contractor | Dump truck | - | 10.0 t | 3 | N.P. |
| 58 | North Surabaya | Semampir | Wonokusumo | Depo Wonosari Tegal | Used | Contractor | Dump truck | - | 13.8 t | 4 | N.P. |
| 59 | West Surabaya | Benowo | Benowo | Benowo | Will be used | | | | | P | P |
| 60 | West Surabaya | Lakarsantri | Lidah Kulon | Wisma Lidah Kulon | Used | KMS | 6 m ³ container | 1 | 0.8 t | 1 | 1 |
| 61 | West Surabaya | Lakarsantri | Lontar | Depo Candi Lontar | Used | KMS | 6 m ³ container | 1 | 1.8 t | 1 | 1 |
| 62 | West Surabaya | Tandes | Asenrowo | Pasar Asenrowo | Used | Contractor | Dump truck | - | 0.6 t | 1 | 1 |
| 63 | West Surabaya | Tandes | Balongsari | Depo Balongsari | Used | KMS | 6 m ³ container | 2 | 4.8 t | 2 | 3 |
| 64 | West Surabaya | Tandes | Buntaran | Buntaran | Will be used | | | | | P | P |
| 65 | West Surabaya | Tandes | Karang Poh | Depo Karang Poh | Used | KMS | 6 m ³ container | 2 | 2.8 t | 1 | 2 |
| 66 | West Surabaya | Tandes | Manukan Kulon | Depo Manukan Kulon | Used | KMS | 6 m ³ container | 4 | 8.8 t | 3 | 4 |
| 67 | West Surabaya | Tandes | Manukan Kulon | Manukan Telaga | Used | KMS | 6 m ³ container | 1 | 3.4 t | N.P. | 2 |
| 68 | West Surabaya | Tandes | Manukan Wetan | Manukan Wetan | Used | KMS | 6 m ³ container | 1 | 2.4 t | 1 | 1 |
| 69 | West Surabaya | Tandes | Putat Gede | Depo Kupang Indah | Used | KMS | 6 m ³ container | 3 | 5.8 t | 2 | 3 |
| 70 | West Surabaya | Tandes | Simomulyo | Depo Simomulyo | Used | Contractor | Dump truck | - | 11.0 t | 3 | 5 |
| 71 | West Surabaya | Tandes | Simomulyo | Depo Simohilir | Used | KMS | 6 m ³ container | 2 | 3.4 t | 1 | 2 |
| 72 | West Surabaya | Tandes | Sonokwijenan | Depo Sonokwijenan | Used | KMS | 6 m ³ container | 2 | 3.0 t | 1 | 2 |

Table 3.2-29 Container Placement Plan (3)

| No | Sub District | Kecamatan | Kelurahan | Name of Depo/LPS | Status | Responsible Body | Type of Truck | No. of the existing Containers | Estimated Waste Amount | 14 m3 Containers to be placed | 8 m3 Containers to be placed |
|-----|----------------|---------------|----------------|----------------------------|--------------|------------------|-----------------|--------------------------------|------------------------|-------------------------------|------------------------------|
| 73 | West Surabaya | Tandes | Sukomanunggal | Sukomanunggal | Used | KMS | 6 m3 container | 1 | 0.6 t | [1] | 1 |
| 74 | West Surabaya | Tandes | Tandes Kidul | Darmo Indah | Stop | | | - | - | P | P |
| 75 | West Surabaya | Tandes | Tandes Lor | Sentong | Stop | | | - | - | P | P |
| 76 | West Surabaya | Tandes | Tuban | Depo Tuban | Used | KMS | 10 m3 container | 1 | 3.2 t | 1 | [2] |
| 77 | South Surabaya | Karang Pilang | Babatan | Depo Babatan | Used | KMS | 6 m3 compactor | [3] | 0.5 t | [1] | 1 |
| 78 | South Surabaya | Karang Pilang | Balas Klumprik | Balas Klumprik | Stopped | - | - | - | - | - | - |
| 79 | South Surabaya | Karang Pilang | Dukuh Kupang | Dukuh Kupang Barat (Sel) | Used | KMS | 6 m3 container | 1 | 1.8 t | [1] | 1 |
| 80 | South Surabaya | Karang Pilang | Dukuh Kupang | Dukuh Kupang Barat (Utara) | Used | KMS | 10 m3 compactor | 1 | 1.8 t | [1] | 1 |
| 81 | South Surabaya | Karang Pilang | Gunungsari | Yani Golf | Used | KMS | 6 m3 container | 1 | 1.0 t | [1] | 1 |
| 82 | South Surabaya | Karang Pilang | Jajar Tunggal | Jajar Tunggal | Used | KMS | 6 m3 container | 1 | 1.8 t | [1] | 1 |
| 83 | South Surabaya | Karang Pilang | Karang Pilang | Karang Pilang | Used | KMS | 6 m3 container | 1 | 1.7 t | [1] | 1 |
| 84 | South Surabaya | Karang Pilang | Kebraon | Kemliten | Used | KMS | 6 m3 container | 1 | 1.7 t | [1] | 1 |
| 85 | South Surabaya | Karang Pilang | Kebraon | Kebraon | Used | KMS | 6 m3 container | 2 | 4.0 t | 1 | [2] |
| 86 | South Surabaya | Karang Pilang | Kedurus | Kedurus | Used | KMS | 6 m3 container | 2 | 3.6 t | 1 | [2] |
| 87 | South Surabaya | Karang Pilang | Waru Gunung | Waru Gunung | Used | KMS | 6 m3 container | 1 | 1.5 t | [1] | 1 |
| 88 | South Surabaya | Karang Pilang | Wiyung | Wiyung | Used | KMS | 6 m3 container | 1 | 1.6 t | [1] | 1 |
| 89 | South Surabaya | Karang Pilang | Wiyung | Depo Gunung Sari Indah | Used | KMS | 6 m3 container | 1 | 1.7 t | [1] | 1 |
| 90 | South Surabaya | Sawahan | Banyu Urip | Pasar Simo | Used | Contractor | Dump truck | - | 5.4 t | 2 | [3] |
| 91 | South Surabaya | Sawahan | Banyu Urip | Simo Karang | Used | KMS | 6 m3 container | 2 | 1.8 t | [1] | 1 |
| 92 | South Surabaya | Sawahan | Pakis | Bintang Diponggo | Used | KMS | 12 m3 container | 2 | 5.0 t | 2 | [3] |
| 93 | South Surabaya | Sawahan | Pakis | Depo Dukuh Kupang Timur | Used | KMS | 12 m3 container | 3 | 7.5 t | 2 | [4] |
| 94 | South Surabaya | Sawahan | Pakis | Depo Kembang Kuning | Used | Contractor | Dump truck | - | 33.0 t | 8 | N.P. |
| 95 | South Surabaya | Sawahan | Petemon | Depo Bukit Barisan | Used | Contractor | Dump truck | - | 16.7 t | 4 | N.P. |
| 96 | South Surabaya | Sawahan | Putat Jaya | Pasar Kupang Gunung | Used | Contractor | Dump truck | - | 1.2 t | [1] | 1 |
| 97 | South Surabaya | Sawahan | Sawahan | Widodaren | Used | KMS | 6 m3 container | 2 | 2.4 t | [1] | 1 |
| 98 | South Surabaya | Sawahan | Sawahan | Merapi | Used | KMS | 6 m3 container | 2 | 1.6 t | N.P. | 1 |
| 99 | South Surabaya | Wonocolo | Bendul Merisi | Depo Bendul Merisi | Used | KMS | 6 m3 container | 3 | 4.1 t | 1 | [2] |
| 100 | South Surabaya | Wonocolo | Gayangan | Gayangan Pring | Used | KMS | 6 m3 container | 1 | 1.5 t | N.P. | 1 |
| 101 | South Surabaya | Wonocolo | Gayangan | Depo Gayungsari | Used | KMS | 6 m3 container | 2 | 3.6 t | 1 | [2] |
| 102 | South Surabaya | Wonocolo | Gayangan | Gayungsari Pasar | Will be used | | | - | - | N.P. | P |
| 103 | South Surabaya | Wonocolo | Jambangan | Kebon Agung | Used | Contractor | Dump truck | - | 2.2 t | [1] | 1 |
| 104 | South Surabaya | Wonocolo | Jemur Wonosari | Jemur Wonosari | Used | KMS | 6 m3 container | 3 | 5.4 t | 2 | [3] |
| 105 | South Surabaya | Wonocolo | Jemur Wonosari | Jemur Ngawan | Used | KMS | 6 m3 container | 1 | 1.8 t | [1] | 1 |
| 106 | South Surabaya | Wonocolo | Karah | Depo Karah | Will be used | | | - | - | P | P |
| 107 | South Surabaya | Wonocolo | Ketintang | Ketintang LPN | Used | Contractor | Dump truck | - | 1.8 t | N.P. | 1 |
| 108 | South Surabaya | Wonocolo | Ketintang | Ketintang Sekolah | Will be used | | | - | - | N.P. | P |

Table 3.2-29 Container Placement Plan (4)

| No | Sub District | Kecamatan | Keurahan | Name of Depo/LPS | Status | Responsible Body | Type of Truck | No. of the existing Containers | Estimated Waste Amount | 14 m ³ Containers to be placed | 8 m ³ Containers to be placed |
|-----|----------------|-----------|---------------|----------------------------|---------|------------------|-----------------|--------------------------------|------------------------|---|--|
| 109 | South Surabaya | Wonocolo | Keitang | Ketintang Baru | Used | Contractor | Dump truck | - | 1.4 t | N.P. | 1 |
| 110 | South Surabaya | Wonocolo | Menanggal | Perum. BBD Ahmad Yani | Used | KMS | 6 m3 compactor | 1 | 0.3 t | [1] | 1 |
| 111 | South Surabaya | Wonocolo | Menanggal | Depo Menanggal | Used | KMS | 6 m3 container | 2 | 2.5 t | 1 | [2] |
| 112 | South Surabaya | Wonocolo | Pagesangan | Depo Pagesangan | Used | Contractor | Dump truck | - | 2.7 t | 1 | [2] |
| 113 | South Surabaya | Wonocolo | Pagesangan | Kebonsari | Used | Contractor | Dump truck | - | 1.8 t | N.P. | 1 |
| 114 | South Surabaya | Wonocolo | Siwalan Kerto | Siwalan Kerto | Used | KMS | 6 m3 container | 1 | 1.6 t | [1] | 1 |
| 115 | South Surabaya | Wonokromo | Darmo | Opak | Used | KMS | 6 m3 container | 1 | 0.4 t | N.P. | N.P. |
| 116 | South Surabaya | Wonokromo | Jagir | Bendul Merisi | Used | Contractor | Dump truck | - | 12.1 t | 3 | [5] |
| 117 | South Surabaya | Wonokromo | Jagir | Pasar Wonokromo | Used | Contractor | Dump truck | - | 16.2 t | 4 | N.P. |
| 118 | South Surabaya | Wonokromo | Ngagel | Ngagel | Used | Contractor | Dump truck | - | 3.6 t | 1 | [2] |
| 119 | South Surabaya | Wonokromo | Ngagel Rejo | Depo Bratang Lapangan | Used | KMS | 6 m3 container | 4 | 5.4 t | 2 | [3] |
| 120 | South Surabaya | Wonokromo | Ngagel Rejo | Depo Ngagel Dadi III | Used | KMS | 6 m3 container | 4 | 4.3 t | [2] | 2 |
| 121 | South Surabaya | Wonokromo | Ngagel Rejo | Pasar Krukah | Used | KMS | 6 m3 container | 1 | 1.5 t | [1] | 1 |
| 122 | South Surabaya | Wonokromo | Sawunggaling | Wonoboyo | Used | KMS | 6 m3 container | 2 | 1.8 t | [1] | 1 |
| 123 | South Surabaya | Wonokromo | Sawunggaling | Pasar Wonokitri | Used | Contractor | Dump truck | - | 0.4 t | [1] | 1 |
| 124 | South Surabaya | Wonokromo | Sawunggaling | Pasar Wonokitri | Used | KMS | 6 m3 container | 3 | 6.0 t | 2 | [3] |
| 125 | South Surabaya | Wonokromo | Sawunggaling | Joyoboyo | Used | KMS | 6 m3 container | 1 | 1.5 t | [1] | 1 |
| 126 | South Surabaya | Wonokromo | Wonokromo | Depo Kintamani | Used | KMS | 6 m3 container | 5 | 11.2 t | 3 | [5] |
| 127 | South Surabaya | Wonokromo | Wonokromo | Jejis | Used | KMS | 6 m3 container | 1 | 2.2 t | [1] | 1 |
| 128 | East Surabaya | Gubeng | Airlangga | Srikana | Used | KMS | 12 m3 container | 3 | 14.0 t | 4 | [6] |
| 129 | East Surabaya | Gubeng | Barata Jaya | Bratang Binangun | Used | KMS | 10 m3 container | 3 | 9.0 t | 3 | [4] |
| 130 | East Surabaya | Gubeng | Baratajaya | Baratajaya | Used | KMS | 10 m3 container | 1 | 4.5 t | [2] | 2 |
| 131 | East Surabaya | Gubeng | Gubeng | Depo Kangean | Used | KMS | 10 m3 container | 3 | 12.6 t | 3 | N.P. |
| 132 | East Surabaya | Gubeng | Kertajaya | Pasar Pucang Anom | Used | Contractor | Dump truck | - | 2.0 t | [1] | 1 |
| 133 | East Surabaya | Gubeng | Mojo | Mojoarun | Used | KMS | 10 m3 container | 1 | 9.0 t | 3 | [4] |
| 134 | East Surabaya | Gubeng | Mojo | Depo Kaliwaron | Used | KMS | 6 m3 container | 2 | 3.8 t | 1 | [2] |
| 135 | East Surabaya | Gubeng | Mojo | Mojo | Used | KMS | 6 m3 container | 2 | 3.5 t | 1 | [2] |
| 136 | East Surabaya | Gubeng | Pucang Sewu | Depo Kalibokor | Used | KMS | 6 m3 container | 4 | 8.1 t | 2 | [4] |
| 137 | East Surabaya | Rungkut | Kali Rungkut | Raya Rungkut | Used | KMS | 6 m3 container | 2 | 3.0 t | 1 | [2] |
| 138 | East Surabaya | Rungkut | Kali Rungkut | Rungkut Harapan | Used | KMS | 6 m3 container | 1 | 1.2 t | [1] | 1 |
| 139 | East Surabaya | Rungkut | Kali Rungkut | Depo Rungkut Alang Alang | Used | Contractor | Dump truck | 1 | 8.1 t | 2 | [4] |
| 140 | East Surabaya | Rungkut | Kali Rungkut | Raya Kali Rungkut | Stopped | - | - | - | - | P | P |
| 141 | East Surabaya | Rungkut | Kedung Baruk | Kedung Asem | Stopped | - | - | - | - | P | P |
| 142 | East Surabaya | Rungkut | Kandang Sari | Raya Kandang Sari Industry | Used | KMS | 6 m3 container | 2 | 2.8 t | [1] | 1 |
| 143 | East Surabaya | Rungkut | Kandang Sari | Depo Kandang Sari Block C | Used | KMS | 6 m3 container | 1 | 1.7 t | [1] | 1 |
| 144 | East Surabaya | Rungkut | Kandang Sari | Prapen | Used | KMS | 6 m3 container | 1 | 0.8 t | [1] | 1 |

Table 3.2-29 Container Placement Plan (5)

| No | Sub District | Kecamatan | Kelurahan | Name of Depo/LPS | Status | Responsible Body | Type of Truck | No. of the existing Containers | Estimated Waste Amount | 14 m3 Containers to be placed | 8 m3 Containers to be placed |
|-----|---------------|-------------|-------------------|----------------------------|--------------|------------------|------------------|--------------------------------|------------------------|-------------------------------|------------------------------|
| 145 | East Surabaya | Rungkut | Kandangari | Kandangari Telkom | Used | KMS | 6 m3 container | 2 | 2.2 t | [1] | 1 |
| 146 | East Surabaya | Rungkut | Kutisari | Kutisari Indah | Used | KMS | 6 m3 container | 3 | 4.6 t | [2] | 2 |
| 147 | East Surabaya | Rungkut | Panjarangan Sari | Panjarangan Sari | Used | KMS | 6 m3 container | 1 | 1.2 t | [1] | 1 |
| 148 | East Surabaya | Rungkut | Rungkut Kidul | Depo Rungkut Kidul | Used | KMS | 6 m3 container | 5 | 9.6 t | 3 | [4] |
| 149 | East Surabaya | Rungkut | Rungkut Menanggal | Depo Rungkut Menanggal | Used | KMS | 6 m3 container | 2 | 3.6 t | 1 | [2] |
| 150 | East Surabaya | Rungkut | Rungkut Menanggal | Rungkut Barata | Stopped | - | - | - | - | P | P |
| 151 | East Surabaya | Rungkut | Tenggilis Mejoyo | Tenggilis Tengah | Will be used | - | - | - | - | P | P |
| 152 | East Surabaya | Rungkut | Tenggilis Mejoyo | Depo Tenggilis Mejoyo | Used | KMS | 6 m3 container | 2 | 3.2 t | 1 | [2] |
| 153 | East Surabaya | Tambak Sari | Ploso | Depo Karang Gayam | Used | KMS | 6 m3 container | 3 | 6.0 t | 2 | [3] |
| 154 | East Surabaya | Tambak Sari | Rangkah | Pasar Tambak Rejo | Used | Contractor | Dump Truck | - | 3.6 t | N.P. | N.P. |
| 155 | East Surabaya | Tambak Sari | Rangkah | Sarangan Tuwowo | Used | KMS | 6 m3 container | [3] | 0.8 t | N.P. | 1 |
| 156 | East Surabaya | Tambak Sari | Tambak Sari | Depo Bogen | Used | KMS | 6 m3 container | 4 | 6.6 t | 2 | [3] |
| 157 | East Surabaya | Sukolilo | Dukuh Sutorejo | Sutorejo I | Used | Contractor | Dump truck | - | 0.6 t | [1] | 1 |
| 158 | East Surabaya | Sukolilo | Dukuh Sutorejo | Sutorejo II | Used | Contractor | Dump truck | - | 0.6 t | [1] | 1 |
| 159 | East Surabaya | Sukolilo | Kalisari | Mulyosari | Used | KMS | 12 m3 Container | 1 | 4.3 t | [2] | 2 |
| 160 | East Surabaya | Sukolilo | Manyar Sabrangan | Manyar Kertoadi | Used | KMS | 10 m3 container | 2 | 5.9 t | 2 | [3] |
| 161 | East Surabaya | Sukolilo | Manyar Sabrangan | Depo Manyar | Used | KMS | 10 m3 containers | 4 | 16.0 t | 4 | N.P. |
| 162 | East Surabaya | Sukolilo | Menur Pumpungan | Sarangan Arif Rahman Hakim | Stopped | - | - | - | - | P | P |
| 163 | East Surabaya | Sukolilo | Menur Pumpungan | Arif Rahman Hakim | Used | KMS | 10 m3 container | 2 | 7.0 t | 2 | [3] |
| 164 | East Surabaya | Sukolilo | Mulyorejo | Depo Wisma Permai | Used | KMS | 6 m3 container | 1 | 1.5 t | [1] | 1 |
| 165 | East Surabaya | Sukolilo | Semolowaru | Semolowaru Elok | Used | KMS | 6 m3 container | 2 | 1.7 t | [1] | 1 |
| 166 | East Surabaya | Sukolilo | Semolowaru | Depo Semolowaru | Used | KMS | 6 m3 container | 2 | 3.6 t | 1 | [2] |
| 167 | East Surabaya | Tambak Sari | Gading | Puro Agung Wetan | Used | KMS | 10 m3 container | 3 | 10.0 t | 3 | [4] |
| 168 | East Surabaya | Tambak Sari | Pacar Keling | Tambangboyo | Used | KMS | 6 m3 container | 2 | 3.7 t | 1 | [2] |
| 169 | East Surabaya | Tambak Sari | Pacar Keling | Depo Pacar Keling | Used | KMS | 6 m3 container | 3 | 4.4 t | [2] | 2 |
| 170 | East Surabaya | Tambak Sari | Pacar Keling | Pasar Gubeng Masjid | Used | KMS | 6 m3 container | 1 | 1.4 t | [1] | 1 |
| 171 | East Surabaya | Tambak Sari | Pacar Keling | Pacar keling | Used | KMS | 10 m3 container | 1 | 4.0 t | 1 | [2] |
| 172 | East Surabaya | Tambak Sari | Pacar Keling | Petojo | Used | KMS | 6 m3 container | 1 | 1.9 t | [1] | 1 |
| 173 | East Surabaya | Tambak Sari | Pacar Keling | Gubeng Masjid | Used | KMS | 6 m3 container | 1 | 1.9 t | [1] | 1 |
| 174 | East Surabaya | Tambak Sari | Pacar Kembang | Sarangan Pacar kembang | Used | KMS | Dump truck | - | 0.3 t | [1] | 1 |
| 175 | East Surabaya | Tambak Sari | Ploso | Ploso Baru | Stopped | - | - | - | - | P | P |

Note : 1. Figures in parenthesis [] indicate numbers of optional containers that can be possibly be placed, but not advisable mainly because waste amount is not large enough, or not cost-effective.

2. "N.P." means not possible or difficult to place containers because the spaced or access to Depo/LPS is inadequate.

3. "P" means possible to place containers. But the marked Depo/LPS are not used currently.

2.5 Procurement Plan and Manpower Requirement

2.5.1 Annual Procurement Plan

Annual procurement schedule during the period 1992/93 - 1998/99 are shown in the following three (3) tables.

It is planned that all equipment needed will be procured in the preceding years. (Eg. Trucks to be used in 1995/96 will be procured in 1994/95.)

The life time (duration) of trucks and equipment is assumed as follows:

- 1) Trucks: 7 years
- 2) Containers: 5 years

Table 3.2-30 Trucks Procurement Schedule During SUDP Period 1992/3-1998/99

| Year | 8 m ³ Container Truck (1) | 14 m ³ Container Truck (2) | Open Dump Truck (3) | Compactor Trucks (4) | Total (5) |
|---------|---|--|---------------------------|----------------------------|--------------|
| 1992/93 | 0 | 0 | 0 | 0 | 0 |
| 1993/94 | 7 | 18 | 3 | 0 | 28 |
| 1994/95 | 4 | 0 | 1 | 0 | 5 |
| 1995/96 | 6 | 6 | 0 | 0 | 12 |
| 1996/97 | 0 | 0 | 1 | 0 | 1 |
| 1997/98 | 9 | 15 | 0 | 0 | 24 |
| 1998/99 | 0 | 0 | 0 | 0 | 0 |
| Total | 26 | 39 | 5 | 0 | 70 |

Table 3.2-31 Containers Procurement Schedule During SUDP Period 1992/3-1998/99

| Year | 8 m ³ Container (1) | 14 m ³ Container (2) | Total (1) + (2) = (3) |
|--------------|--------------------------------------|---------------------------------------|-----------------------------|
| 1992/93 | 0 | 0 | 0 |
| 1993/94 | 39 | 122 | 161 |
| 1994/95 | 44 | 0 | 44 |
| 1995/96 | 6 | 2 | 8 |
| 1996/97 | 0 | 1 | 1 |
| 1997/98 | 0 | 3 | 3 |
| 1998/99 | 0 | 2 | 2 |
| Total | 89 | 130 | 219 |

Table 3.2-32 Handcarts Procurement Schedule During SUDP Period 1992/3-1998/99

| Year | 1.0 m ³ Handcart (1) | 1.5 m ³ Handcart (2) | Total (1) + (2) = (3) |
|--------------|---------------------------------------|---------------------------------------|-----------------------------|
| 1992/93 | 0 | 0 | 0 |
| 1993/94 | 85 | 31 | 116 |
| 1994/95 | 85 | 31 | 116 |
| 1995/96 | 86 | 32 | 118 |
| 1996/97 | 0 | 0 | 0 |
| 1997/98 | 0 | 0 | 0 |
| 1998/99 | 0 | 0 | 0 |
| Total | 256 | 94 | 350 |

2.5.2 Manpower Requirement

At present, there are 146 truck crew (drivers and assistant) in 1992. It is expected that the number of crew will decrease gradually in the future as the existing containers and trucks are replaced with larger containers and trucks.

It is planned that the future size of crew will be constant at 92 in 1995 and thereafter as shown in the table below.

Some of the personnel to be made redundant will retire after reaching the retirement age or will be transferred to other sections in the Cleansing Department.

Like the present system, a truck (serving for either 8 m³ or 14 m³ containers) will be operated by:

- one (1) driver, and
- one (1) assistant

However, it is considered possible for a driver to operate arm-roll trucks without any assistants. As a matter of fact, arm-roll trucks are operated by one man in Japan and other countries. Therefore, it is advised that KMS will use a driver only for a truck towards the end of the SUDP period.

All dump trucks will be operated by one driver per unit. Assistants will be provided from Rayon offices depending on need of each occasion.

Table 3.2-33 Number of Drivers and Assistants Needed (Summary)

| Year | New Trucks | | Existing Trucks | | Spare Crew | | Total | | |
|---------|---------------|-----------------------|-----------------|-----------------------|---------------|-----------------------|-------------------------------------|--|---------------------------|
| | Driver (1) | Assis- tant (2) | Driver (3) | Assis- tant (4) | Driver (5) | Assis- tant (6) | Driver (1)+(3) + (5) = (7) | Assis- tant (2)+(4) +(6) = (8) | Total (7)+(8) = (9) |
| 1992/93 | 0 | 0 | 64 | 68 | 5 | 9 | 69 | 77 | 148 |
| 1993/94 | 21 | 18 | 38 | 46 | 4 | 5 | 63 | 69 | 132 |
| 1994/95 | 29 | 25 | 21 | 25 | 8 | 8 | 58 | 58 | 116 |
| 1995/96 | 33 | 28 | 3 | 2 | 14 | 13 | 50 | 43 | 93 |
| 1996/97 | 46 | 41 | 0 | 0 | 3 | 2 | 49 | 43 | 92 |
| 1997/98 | 46 | 41 | 0 | 0 | 3 | 2 | 49 | 43 | 92 |
| 1998/99 | 70 | 18 | 0 | 0 | 4 | 0 | 74 | 18 | 92 |

Table 3.2-34 Number of Drivers and Assistants Needed for New Trucks

| Year | Arm-Roll Trucks Serving for 8 m ³ Containers | | Arm-Roll Trucks Serving for 8 m ³ Containers | | Open Dump Trucks | | Total | | |
|---------|---|---------------|---|---------------|------------------|---------------|---------------------------|------------------------------|---------------------|
| | Driver (1) | Assistant (2) | Driver (3) | Assistant (4) | Driver (5) | Assistant (6) | Driver (1)+(3)+ (5) = (7) | Assistant (2)+(4) +(6) = (8) | Total (7)+(8) = (9) |
| 1992/93 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1993/94 | 6 | 6 | 12 | 12 | 3 | 0 | 21 | 18 | 39 |
| 1994/95 | 7 | 7 | 18 | 18 | 4 | 0 | 29 | 25 | 54 |
| 1995/96 | 11 | 11 | 17 | 17 | 5 | 0 | 33 | 28 | 61 |
| 1996/97 | 17 | 17 | 24 | 24 | 5 | 0 | 46 | 41 | 87 |
| 1997/98 | 17 | 17 | 24 | 24 | 5 | 0 | 46 | 41 | 87 |
| 1998/99 | 26 | 0 | 39 | 18 | 5 | 0 | 70 | 18 | 88 |

Table 3.2-35 Number of Drivers and Assistants Needed for the Existing Trucks

| Year | Trucks for 6 m ³ Container | | Trucks for 10 m ³ Container | | Trucks for 12 m ³ Container | | REL Trucks for 0.6m ³ Container | | REL Trucks for 1.0m ³ Container | | Open Dump Trucks | | Total | | |
|---------|---------------------------------------|----|--|----|--|---|--|---|--|----|------------------|---|-------|----|-------|
| | D | A | D | A | D | A | D | A | D | A | D | A | D | A | Total |
| 1992/93 | 26 | 26 | 13 | 13 | 4 | 4 | 5 | 5 | 10 | 20 | 6 | 0 | 64 | 68 | 112 |
| 1993/94 | 12 | 12 | 5 | 5 | 4 | 4 | 5 | 5 | 10 | 20 | 2 | 0 | 38 | 46 | 84 |
| 1994/95 | 12 | 12 | 0 | 0 | 0 | 0 | 3 | 3 | 5 | 10 | 1 | 0 | 21 | 25 | 46 |
| 1995/96 | 2 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 2 | 5 |
| 1996/97 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1997/98 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1998/99 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

D: Driver

A: Assistant

2.6 Investment, Operation and Maintenance Costs

2.6.1 Investment

Yearly investment schedules of trucks, containers, and handcarts are shown in the table below. Total investment amount is estimated to be Rp 6,644.4 million in 1992 price including the 10 % government tax (PPN).

Table 3.2-36 Yearly Investment Schedule

Unit: Million Rupiah in 1992 price

| Year | Trucks | | | | Containers | | | Handcarts | | | Grand Total (4)+(7)+ (10)= (11) |
|-------------|--|---|------------------------------|---|---|--|--|---|--|--|--|
| | 8 m ³ Con- tainer Truck (1) | 14 m ³ Con- tainer Truck (2) | Open Dump Truck (3) | Total Truck (1)+(2) +(3)= (4) | 8 m ³ Con- tainer (5) | 14 m ³ Con- tainer (6) | Total con- tainer (5)+(6) =(7) | 1 m ³ Hand- -cart (8) | 1.5 m ³ Hand- -cart (9) | Total Hand- cart (8)+(9) =(10) | |
| 1992/ 93 | (0) | (0) | (0) | (0) | (0) | (0) | (0) | (0) | (0) | (0) | (0) |
| 1993/ 94 | 354.2 (7) | 1,535.4 (18) | 152.1 (3) | 2,041.7 (28) | 234.0 (39) | 976.0 (122) | 1,210.0 (161) | 40.8 (85) | 17.1 (31) | 57.9 (116) | 3,309.6 |
| 1994/ 95 | 202.4 (4) | 0.0 (0) | 50.7 (1) | 253.1 (5) | 264.0 (44) | 0.0 (0) | 264.0 (44) | 40.8 (85) | 17.0 (31) | 57.8 (116) | 3574.9 |
| 1995/ 96 | 303.6 (6) | 511.8 (6) | 0.0 (0) | 1,068.5 (12) | 36.0 (6) | 16.0 (2) | 52 (8) | 41.3 (86) | 17.6 (32) | 58.9 (118) | 1,179.4 |
| 1996/ 97 | 0.0 (0) | 0.0 (0) | 50.7 (1) | 50.7 (1) | 0.0 (0) | 8.0 (1) | 8.0 (1) | 0 | 0 | 0 | 58.7 |
| 1997/ 98 | 455.4 (9) | 1,279.5 (15) | 0.0 (0) | 1,734.9 (24) | 0.0 (0) | 24.0 (3) | 24.0 (3) | 0 | 0 | 0 | 1,758.9 |
| 1998/ 99 | 0.0 (0) | 0.0 (0) | 0.0 (0) | 0.0 (0) | 0.0 (0) | 16 (2) | 16 (2) | 0 | 0 | 0 | 16 |
| Total | 1,315.6 (26) | 3,326.7 (39) | 253.5 (5) | 4,895.8 (70) | 534.0 (89) | 1,040.0 (130) | 1,574.0 (219) | 122.9 256 | 51.7 (94) | 174.6 (350) | 6,644.4 |

Note:

- 1) Figures in parenthesis show number of units to be procured.
- 2) The above costs include the government tax (PPN - 10 %).

2.6.2 Operation and Maintenance Costs

Operation and maintenance costs of new trucks and containers to be procured are estimated to be Rp 5,276 million in total during the period 1992/93 - 1998/99 in 1992 price. The details of the costs are shown in the tables below. There will be no costs incurred for operation and maintenance of handcarts because they will be given to local communities.

Table 3.2-37 Operation and Maintenance Costs of Trucks and Containers

Unit: Rupiah in 1992 price

| Year | 7 GVW Arm-Roll Trucks & 8 m ³ Containers (1) | 14 GVW Arm-Roll Trucks & 14 m ³ Containers (2) | Dump Trucks (3) | Total (1)+ (2)+ (3) = (4) |
|---------|--|--|--------------------|---------------------------------|
| 1992/93 | 0 | 0 | 0 | 0 |
| 1993/94 | 116,490,000 | 295,836,000 | 39,384,000 | 451,710,000 |
| 1994/95 | 135,905,000 | 443,754,000 | 52,512,000 | 632,171,000 |
| 1995/96 | 213,565,000 | 419,101,000 | 52,512,000 | 685,178,000 |
| 1996/97 | 330,055,000 | 591,672,000 | 65,640,000 | 987,367,000 |
| 1997/98 | 330,055,000 | 591,672,000 | 65,640,000 | 987,367,000 |
| 1998/99 | 504,790,000 | 961,467,000 | 65,640,000 | 1,531,897,000 |
| Total | 1,630,860,000 | 3,303,502,000 | 341,328,000 | 5,275,690,000 |

Note: The above costs are calculated based upon the unit operation/maintenance costs per truck system as shown in the table below, and number of units used as shown in Table 3.2-22.

Unit operation and maintenance costs are estimated below. A unit cost covers one arm-roll truck and 6 containers (either 8 m³ or 14 m³) served by an arm-roll truck.

Table 3.2-38 Unit Annual Operation and Maintenance Costs

Unit: Rupiah in 1992 price

| | A 7 GVW Arm-Roll Truck & 6 units of 8 m ³ Containers | A 14 GVW Arm-Roll Truck & 6 units of 14 m ³ Containers | A Dump Truck |
|--|---|---|-----------------|
| 1. Fuel | 5,900,000 | 6,500,000 | 2,000,000 |
| 2. Salary for Driver & Assistant | 4,260,000 | 4,260,000 | 2,760,000 |
| 3. Tax and Insurance | 2,030,000 | 2,030,000 | 2,030,000 |
| 4. Maintenance (12.5 % of truck purchase Cost) | 6,325,000 | 10,663,000 | 6,338,000 |
| 5. Sub-total (1+2+3+4) | 18,515,000 | 23,453,000 | 13,128,000 |
| 6. Maintenance cost of 6 containers (2.5 % of purchase cost) | 900,000 | 1,200,000 | 0 |
| 7. Total (5 + 6) | 19,415,000 | 24,653,000 | 13,128,000 |

Chapter 3 F/S Component 2: Construction of Sanitary Landfill Site in Benowo

3.1 Key Factors of Design

3.1.1 Site Locations and Conditions

KMS decided that KMS's future landfill should be sited Kelurahan Benowo, the western part of Surabaya City. This decision was made by the competent officials of KMS including Mayor of the city on November 28, 1992. The whole site designated has an area of about 150 ha, of which the westernmost part was designated to be the first phase construction site of the sanitary landfill for which the Study Team has carried out the Feasibility Study. The site is found to be possible to convert to a solid waste landfill site based on the consideration of its characteristics if some appropriate countermeasures are applied.

1) Location and Access

The planned landfill in Kecamatan Benowo is about 10 to 15 km to the west of the central part of the city as shown in Fig. 3.3-1. The following five (5) subdistricts locate partly or wholly in the planned site (150 ha).

- Kelurahan Sumberejo
- Kelurahan Pakal
- Kelurahan Benowo
- Kelurahan Romo Kalisari
- Kelurahan Tambak Osowilangon

The planned site is situated in a catchment area of River Lamong, five (5) km away from the estuary of the river. The site extends along the river channel.

Access road to the planned site is AMD road and through Jl. Benowo it leads to all the other city area as shown in Fig. 3.3-2. AMD road does not have any connection to the neighboring Kabupaten Gresik, therefore the access from the other parts of the city is limited only through Jl. Benowo to AMD road. AMD road has a railway crossing which is not installed any protection device, then all the vehicles go over the rail directly at present.




FIG. 3.3-1

LOCATION OF PLANNED LANDFILL SITE

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY




FIG. 3.3-2

ACCESS OF PLANNED LANDFILL SITE

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

2) Topography

The planning site is located on an alluvium plane belongs to River Lamong's catchment area. The altitude ranges from 2 to 3 meter above sea level in the area about 5 km away from seashore. This means the site is originally flat and furthermore most area here is used as the salt farm so the ground surface is kept precisely horizontal to facilitate the salt production by using solar heating.

Reflecting the dominant land use, the surface of the site is classified simply into 3 major types, namely Salty water drying bed, River, channel and pond, and Footpath and bank.

The altitude is so low that the coastal plane belongs to tidal compartment. River Lamong and its many tributaries distributed around the site show consequently alternate flow direction corresponding to the tidal wave, and this nature enables the utilization of salty water for salt production here.

3) Geology

Surface soil consists of soft silty clay which classified as alluvium deposit. The depth of this soft clay was confirmed by the boring test at around 10 m at the site. Below this soft clay, there distribute stiff clay and silt layer with the thickness of about 15 m which has already been consolidated and dense fine sand/silt.

The clay is generally used for water proof lining material for the footpath and the partition of salt farms here. Then it is considered that the surface soil has enough impermeability under the small head not more than 1 meter. According to the result of laboratory test, the coefficient of permeability distributes in the range from 0.8 to 5×10^{-5} cm/s. The surface soil causes many cracks when dried up, however, it is considered to be impermeable if it is kept in wet condition.

The whole layer of alluvium deposit with a depth of about 10 m still has a possibility of consolidation. According to the result of laboratory test, the pre-compression stress is measured to be from 3 to 4 t/m². This means the subsoil stays in normal consolidation status.

4) Existing Land Use

Most part of coastal plane is occupied by salt farm around the planning landfill site, and remaining part such as canal, dredged pond are used for fishery or fish breeding. Bigger sized canal or tributary of River Lamong are used for water transportation of salt or salt production materials.

Small villages are located in the marginal area of coastal plane or along the river in isolated position each other. The nearest residences with about 20 houses are located on AMD road, 300 m away from the proposed connection point between AMD road and the access road of the landfill site. There are four villages that are located on the downstream of tributaries that flow through the planning landfill site. The nearest village from the whole candidate landfill site for future expansion is located about 1 km below along the stream. In these villages no piped waster is available, so people use river water for laundry and bathing. Drinking water is supplied by PDAM tank lorry and stored in a communal reservoir installed in each village.

Amid the salt farm, there is no permanent residence, however, some temporary huts for seasonal laborers of salt farm are scattered with a distribution one in several hectare. These huts are only used during the dry season when the salt production is executed, therefore there are no inhabitants during the rainy season in the planning landfill site.

3.1.2 Design Concept

To design a landfill site, the technical guideline issued by Directorate of Environmental Sanitation, CIPTA KARYA, was referred to. The guideline explains several negative impacts that may be caused by landfill operation, and at the same time suggests mitigation measures against each impact. First of all, the design of planned landfill site in Benowo followed the recommendations of this guideline as long as the guideline shows circumstances similar to the planned site. Besides this guideline, the following factors were taken into consideration:

- a. Environmental protection
- b. Construction cost and operation
- c. Future land use

These items are investigated respectively below.

1) Environmental Protection

Surrounding water body is mostly used for salt production or fishery. On the contrary, ground water is not utilized in the neighboring villages located along the lower reaches of the tributaries flowing through the planned site due to salinity of the groundwater. Then the fundamental subject in environmental protection is water quality of the surface water.

Considering the circumstances of the site, the water in the site should be controlled to prevent the pollution of the surrounding water body in the manner shown below :

- a. Enclose the leachate within the site
- b. Reduce the leachate by recirculation and evaporation
- c. Lower the porewater pressure by underdrain
- d. Collect the rainwater that has not touched the garbage separately from the leachate and discharge

Garbage pile generates inflammable gases during decomposition process, which is caused by microorganism and ensures the volume reduction. The gases sometimes cause spontaneous fire on the surface of the garbage layer. It is not only dangerous but a choking and in some cases harmful smoke would intrude into the adjacent area. Therefore the ventilation facility is planned to be introduced to the landfill site. The facility consists of vertical gas vents and horizontal underdrain network. Both of them have the two functions, namely leachate drain by the infiltrated part and ventilation by the other vacant part. The facility is expected to obtain the following effects of ventilation.

- a. Facilitate the aerobic decomposition by supplying air into the garbage layer
- b. Shorten the necessary time for stabilizing the layer that results in the subsidence of the surface.
- c. Disperse the inflammable gases safely

Another major protection subject is prevention of overflow of garbage out of site as is commonly observed in the existing landfill sites. For this purpose, the landfill operation is planned to be conducted within enclosure dike higher than the waste pile. Garbage surface is also covered with some stable material periodically and finally covered with soil with sufficient thickness.

2) Construction Cost and Operation

Major part of construction cost usually consists of soil works such as enclosure dyke and drainage, and leachate treatment facility. As for soil works, there are few choices in the selection of construction method because the site has a very soft ground surface that is not suitable to sustain any complicated or heavy structures on it. Therefore the major interest in the selection of an economic method would be how to treat leachate water.

a. Application of the Least Cost Systems

The sanitary landfill facilities consist of various sub-systems. The Study Team has given a priority to the selection of the most cost-effective systems of the least cost that fulfill required functions as explained below.

(1) Use of Steel Sheet Pile for Reinforcement of Foundation of Dike

The total construction cost turned out to be costlier than initially thought because that the site is covered with soft clay, and it is necessary to reinforce the foundation of dike by driving either steel sheet pile or steel pipes into the clay soil to the depth of 10 m. As a matter of fact, the cost of the reinforcement of the soft clay foundation shares 40 % of the total construction cost of the planned LPA.

As a result of the cost comparison, the use of steel sheet pile is recommended and adopted for the plan because the other method (use of steel pipes) is more than 60 % costlier than the former as shown below:

| | <u>Unit Price</u> | <u>Cost Index</u> |
|-----------------------|-------------------|-------------------|
| (1) Steel sheet pile: | Rp 1,600/ton | (100) |
| (2) Steel pipe: | Rp 2,600/ton | (163) |

(2) Leachate Treatment

There are the following two methods for leachate treatment: 1) leachate recirculation system, and 2) mechanical treatment. The JICA Study recommend the former because the latter is more than 12 times costlier than the former as shown below:

| | <u>Cost</u> | <u>Index</u> |
|-----------------------------------|------------------|--------------|
| 1) Leachate Recirculation System: | Rp 754 million* | (100) |
| 2) Mechanical Treatment: | Rp 9,600 million | (1,273) |

* Details of the costs of the leachate recirculation system are as follows:

| | |
|-----------------------------------|---|
| - Construction of retention pond: | Rp 186 million |
| - Recirculation pump: | Rp 108 million |
| - Land acquisition | Rp 460 million (Rp 23,000m ² x 20,000 m ²) |
| - Total: | Rp 754 million |

b. Unit Cost Comparison between the Planned Sanitary Landfill and the Existing Incinerator

The unit waste incineration cost of the existing incinerator, Rp 85,600/ton is more than 7 times higher than the unit disposal cost (about Rp 12,000/ton max.) of the planned sanitary landfill in Benowo.

In view of operation, the leachate confining method requires less intensive maintenance than the mechanical treatment plant. The main point of operation is only to control the water level of the retention pond by using the pump and recirculation facilities during rainy season when the monthly precipitation exceeds the monthly evaporation. Therefore this treatment method can be thought a better way to save an operation cost and manpower.

3) Future Land Use

The planned site is involved in a comprehensive development plan called "Rencana Detail Tata Ruang Kota Tambak Osowilangon". The land around the site will be green area according to the development plan. The site and the neighboring area for future expansion is bounded by two high tension electricity line in the west side and also bounded by planned toll road Surabaya Gresik in the north side. The south side is connected with planned residential area or golf course.

The future land use of the planned landfill site is not definitely decided yet. If the land would be used is decided as green area, it is possible to change the site with less care after completion of landfill operation. According to the experience of Japan, in about 15 years after the end of landfill operation, it can be converted into various types of land use with some mitigation measures for the site and the building. If the type of land use has less requirements like park, green belt and golf course, it can be converted

sooner than 15 years. Some examples of land use conversion from final disposal site are presented in Appendix 6 of this report.

4) Stage Plan

The most desirable plan for acquiring the landfill site is to get both Benowo (150 ha) and the New East (120 ha). The critical time when the existing landfill site is exhausted is forecast to be the year 1996. It is necessary to prepare the new landfill site before the critical time at the latest. This means KMS should have the additional capacity of landfill by the end of 1995 with the minimum capacity that meets the demand expected in the next year.

This requirement of time correspondence seems to be difficult, but it is not necessary to construct all the facilities before the beginning of landfill operation. The construction should be continued even after the commencement of the landfill operation according to the annual landfill amount expected in the successive years. Time schedule for the execution of the project is outlined in Table 3.3-1.

Table 3.3-1 Project Stage of Benowo Landfill Site

| Activity | 1993 | 1994 | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 |
|---|-------|-------|------|-------|------|------|------|------|------|------|------|------|-------|
| Land Acquisition | ————— | | | | | | | | | | | | |
| Construction (Including Detail Design) | | ————— | | | — | — | — | — | — | — | — | — | |
| Landfill | | | | ————— | | | | | | | | | |
| Closing | | | | | | | | | | | | | ————— |

Note : Broken lines mean the work for installation of underdrain and gas vent. The installation is supposed to be done during dry seasons.

The planned landfill site for the Feasibility Study is expected to expand to northeastern direction along the high tension lines up to Surabaya-Gresik Toll Road. In the course of expansion, it is assumed that the land for another landfill site will be acquired in an area adjacent to area (45 ha) of the Feasibility Study, and the site will be expanded in a step by step manner. Based on this assumption, a lay-out of facility is prepared so as to avoid duplicated construction of common facilities such as on-site access road, retention pond and enclosure dike those which are required for each stage of construction.

Another point to be considered is that the northern boundary contacts the high tension line and Surabaya-Gresik Toll Road both of which should be protected against the displacement of ground surface. To satisfy this requirement, it is desirable to keep the landfill point away from the said high tension lines and the toll road as far as possible. As for the high tension line, it is not allowed to build facilities such as dike within 50 m from the center of high tension lines. Considering these requirements, the retention ponds for each step of landfill sites will be constructed along the northern boundary next to high tension line and Surabaya-Gresik Toll Road.

Thus the final lay-out of the whole area of 150 ha is placed as shown in Fig. 3.3-3. Consequently the first step of the first landfill site (45 ha) has been designed according to the lay-out plan.




FIG. 3.3-3

PLAN FOR FUTURE EXPANSION

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

3.2 Structure and Function of Facility

3.2.1 Composition of Facility

Facilities for the planned new landfill site consist of the following components. A layout plan for the facilities is shown in Fig. 3.3-4.

Table 3.3-2 Major Component of Landfill Site

| Type | Definition |
|------------------------------|--|
| 1. Access Road | a. Connect the planned site with AMD road b. Constructed as an essential component of the landfill site |
| 2. Leachate Control Facility | a. Consists of collection facility, reservoir and recirculation facility b. Collection facility has the function to collect the rain water through the garbage pile. |
| 3. Rainwater Drainage | a. Consists of collection facility, retention pond and discharge facility b. Collection facility has the function to collect the rain water in principle c. Discharge facility has the function to overflow the excessive rainwater during heavy rain that ensure enough dilution effect on leachate concentration |
| 4. Enclosure Dike | a. Made of soil in principle b. Limit the range of dumping area c. Placed along the boundary of the site |
| 5. Divider Dike | a. Made of aged garbage in principle b. Limit the range of dumping area c. Placed on the boundary of the partition for the demarcation of annual operation |
| 6. Landfill Area | a. The place where waste is placed b. Installed with on-site road, under drain for leachate and gas vent according to the progress of the landfill operation c. Divide the total area of 37 ha into 3 zones Zone 1 12 ha (south) Zone 2 13 ha (center) Zone 3 12 ha (north) |
| 7. Gas Vent | a. Made of porous material to facilitate the penetration of gaseous substances and recirculation water b. Installed vertically through the garbage layer and cover soil c. Connected with the under drain at each level |
| 8. Administrative Facility | a. Consists of building and other miscellaneous facilities b. Contain the function for occupation of the necessary operation staff c. Limit the landfill activity within the site |




FIG 3.3-4

LAYOUT PLAN OF FACILITY

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

3.2.2 Access Road

It is planned that an access road will be provided along the existing main footpath that is now used for bicycle transportation of salt product and production materials. The planned access road will provide the shortest access to the existing public road.

The bearing capacity of the access road is planned to be 10 ton of axle load according to the regulation of DPU (Ministry of Public Works) : Decree of Minister No. 378, 1987. The pavement specification will be decided so as to satisfy the above regulation and referring to the standard enacted by DPU : Decree of Minister No.378, 1987. The design width of the access road is 30 m considering the mitigation of influence caused by garbage haulage vehicles to the neighboring area. The road side space of 8 m in width will serve as a buffer zone.

On-site road which is constructed along the boundary of the site in direct connection with the access road will be subject to the similar standard as applied to the access road.

As for the crossing point with the high tension line of PLN, it is necessary to adapt a special protection measures in accordance with the regulation on the electricity supply. The requirement of protection work is specified by PLN. A protection work for the access road as planned accordingly is included in this plan.

The similar item related to AMD road can be pointed out, namely the railway crossing improvement. It will be also necessary to be solved by Dinas PU before the construction of landfill site starts.

3.2.3 Leachate Control Facility

Leachate water should be taken out from waste layers as soon as possible and reserved in a retention pond. Then it is aerated and returned to waste layers again. The function of the leachate control system is classified into two parts; one is collection and the other is aeration and recirculation.


Leachate is collected by the network of under drain placed on the bottom of the dumping area first. The network is also installed in an appropriate level according to the progress of landfill operation, considering the subsidence of the site that would be caused by the load of filled garbage and soil. The bottom network leads to the retention

pond and the upper networks are connected with the lower networks through vertical conduit of gas vent. The structure of the collection system is shown in Fig. 3.3-5.

Leachate will be recirculated with an electric pump from the retention pond to the top of the enclosure dike. Pumped up water is delivered to the recharging point by the combination of small reservoir tank and connection hose. Recharge point is selected out of gas vent distributed on the surface of dumping area according to the stage of landfill operation. Therefore the delivery facility should have a convenient structure so as to make it easy to move the facility from one recharge point to another. The concept of recirculation system is illustrated in Fig. 3.3-6. The recirculation enables to keep the retention pond empty for 8 months, and to keep the water level lower than the bottom of under drain outlet during the remaining 4 months from January to April. Therefore outflow of leachate scarcely happens even in rainy season. Most organic matters contained in leachate will be returned to the garbage pile and finally fixed there through the process of recirculation. Then the amount of pollutant in the retention pond can be reduced steadily, however, there remains a risk that the leachate or its sediment exposed in the air may emit an offensive odor created through anaerobic decomposition of organic matters. But it is not certain if the influence of the odor reaches a critical level that affects the neighboring area. In general, it is difficult to design a mitigation measure without identifying the magnitude and frequency of the risk in advance. So countermeasures against offensive odor are not included in the current plan. It is however advisable that some measures be taken when details of the offensive odor are known.


The surface soil is so soft and contractible, the elevation of the under drain faces the risk to lose its function because of subsidence of the surface soil layer. In order to prevent the leachate discharge function being affected by the subsidence, the structure of the under drain network is designed as follows:

- a. Place several rows of bamboo piles vertically just below the bottom under drain in order to support the drain against the surface soil subsidence.
- b. Construct an upheaved under drain as the bottom network with a height of 1.5 m in order to secure the horizontal conduit for both leachate and air even if the subsidence occurs.



Cross Section of Leachate Drain

1st Stage Main Drain
(Branch Drain)
B - B



2nd Stage Main Drain
(Branch Drain)
A - A




FIG 3.3-5

LEACHATE COLLECTION SYSTEM




FIG. 3.3-6

LEACHATE RECIRCULATION SYSTEM

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

3.2.4 Rainwater Discharge

Rainwater should be discharged to the neighboring water body directly as far as it can be separated from leachate in principle. It is also permissible to discharge rainwater including leachate during heavy rain if only the water does not flow directly into the neighboring salt farm or fish pond.

The critical intensity of rainfall is set at 80 mm/h that may happen once in ten years based on the statistics of rainfall in Surabaya. The critical rainfall will generate about 5 m³/s of water flow from the site assuming the run-off rate would be 40%. Compared with the average of leachate volume in peak month of 0.03 m³/s, the rainwater flow is forecast to be more than 100 times bigger. This means that even if the leachate is mixed into the storm water effluent, the negative influence of leachate will be mitigated enough to be neglected. Furthermore, the rainwater during flood forms a constant and rapid flow toward the sea diluting the effluent coming from the landfill site with a huge amount of water coming out of the other part of catchment area of the River Lamong.

To achieve the above mentioned requirements, an appropriate discharge point of rainwater should be selected. Based on the survey result of land use and topography, the River Sememi seems to be the best because it flows directly to the River Lamong without passing through any salt farm or fish pond. To discharge rainwater through the River Sememi, it is necessary to install a conduit across some neighboring salt farms. The length and the size of the conduit is estimated at about 300 m and 5 m² respectively. The rainwater discharge system is illustrated in Fig. 3.3-7.

In addition to this system, some supplementary diversion work will be required to keep the existing flow of the surrounding water body. It will be done just outside the landfill site. Costs of the supplementary diversion works are included in the current estimate of the site construction.

It is planned that rainwater will be utilized for the administrative facilities. The utilization system consists of collection ditch, underground reservoir, delivery equipment and consumer equipment.




FIG. 3.3-7

RAINWATER DRAINAGE

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

3.2.5 Dike

Landfill area is planned to place within an enclosed area by dikes which are classified into two types by their location, namely :

- a. Enclosure dike
- b. Divider dike

Dikes should be constructed before the landfill operation starts in order to prepare the landfill area for the first year operation. Then the construction is carried out three times according to the stage plan, and finally the whole layer reaches 10 m in height.

The section of dike is planned to be a trapezoid with the following basic dimensions :

- a. Width of the top : minimum 3 m
- b. Gradient of exterior slope : 1:2.0
- c. Gradient of interior slope : 1:1.2

Material of dike is selected so as to secure its stability at low costs. From this view point, a possibility to acquire the aged garbage buried in Lakarsantri landfill site or Keputih is worth studying.

According to the result of geological survey, the surface soil is used as the basis of the dike does not have enough capacity to bear the load, therefore, some reinforcement should be adopted prior to the the construction. Based on the analysis of stability against slide corruption, it is planned to install a row of metal pile with a length of 15 m below the enclosure dike in order to reinforce the soil foundation. The structure of dike is illustrated in Fig. 3.3.8.




FIG. 3.3-8

STRUCTURE OF DIKE

3.2.6 Gas Ventilation

Gas ventilation facility has three function :

- a. Supply air into the garbage layer to facilitate aerobic decomposition
- b. Discharge gaseous substance generated in the garbage layer
- c. Discharge rainwater collected by a horizontal underdrain network through the bottom drain network

To perform these functions, the vertical gas vent will be installed besides horizontal underdrain network. The gas vent is mainly composed of the porous material such as crushed stone, however, PVC tube is also applied to the bottom layer of underdrain network in order to increase the air supply amid the garbage layer.

Considering the convenience of installation, it should be placed just before the start of the landfill operation. Consequently the structure of gas vent requires the stability to keep its form during landfill operation by heavy equipment around it. Then the crushed stone is contained in a conical bamboo basket without top and bottom, and placed at an intersection of the horizontal underdrain network. The top diameter of the taper shape of bamboo basket is smaller than the bottom, and the shape of bamboo basket facilitates the penetration of recirculated leachate into the garbage layer. The outline of the structure is shown in Fig. 3.3-9.

As for gas utilization it is not taken into consideration because 1) the planned site is rather far from the nearest residents that could be the consumer of methane gas, and 2) the waste layer is as deep as 9 m at final level. Normally, recovery of methane gas is feasible in case the depth of waste layer is more than 10 m. Then an example of applied usage of recovered methane gas is presented in case it was found feasible in Appendix 7.




FIG. 3.3-9



STUCTURE OF GAS VENT

3.2.7 Administrative Facility


The proposed components of administrative facilities are summarized in Table 3.3-3, and its layout is shown in Fig. 3.3-10. To keep an orderly landfill operation, it is necessary to assign a resident administrative staff at the site.

Table 3.3-3 List of Administrative Facility

| Function | Remarks |
|----------------------|---|
| Office | a. Include the space for the chief and his seven staffs with an area of about 80 m ² b. Locker and rest room for 11 heavy equipment operators and office staffs with an area of about 40 m ² c. Kitchen 20 m ² d. Storage 20 m ² e. Toilet and bath 60 m ² |
| Workshop and Garage | a. Include the following vehicles - 4 Bulldozers - 1 Excavator - 2 Dump trucks b. Install a set of equipment for daily maintenance of heavy equipment which consists of : - Hot water spray washer - Tuning tools - Checking pit - Storage |
| Weighing Booth | a. Install a unit of weigh bridge with a maximum capacity of 30 ton b. Automatic recording system installed in a booth located on the access road |
| Water Supply | a. Utilization of rainwater by using collection ditch, underground reservoir and delivery equipment b. Access road is planned to be the rainwater collection surface and the attached ditches on both sides are connected with underground reservoir c. Water will be used for office, workshop and truck washing pond. d. Delivery is done by electric pump. For workshop's use, the water is supplied through a solar heating apparatus. |
| Vehicle Washing Pool | a. Wash the lower part of vehicle and tyre in a shallow pool b. Fresh rainwater will be used. c. Placed on the way out before the weighing booth |
| Parking Lot | a. Space for vehicles of employers and visitors b. Placed at the entrance of the site |
| Miscellaneous | a. Gate and fence b. Lighting c. Signboard |



Detail A



Detail B

FIG. 3.3-10

LAYOUT OF ADMINISTRATIVE FACILITY

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

3.3 Proposed Operation and Maintenance

3.3.1 Design of Landfill Operation

1) Stage Plan

It is planned that the landfill operation period will be 9 years based on the simulation for the allocation of landfill demand. The whole operation period is divided into three stages in accordance with the height of garbage layer as shown below :

- Stage 1 : 1996 - 1998 (height up to 3 m)
- Stage 2 : 1999 - 2001 (height up to 7 m)
- Stage 3 : 2002 - 2004 (height up to 9 m)

The landfill area is also divided into 3 zones which correspond to the annual operation in each stage. Therefore, the operation is executed in each zone for a year and transferred to the next zone year by year as shown below.

| Stage \ Zone | 1 | | | 2 | | | 3 | | |
|--------------|------|------|------|------|------|------|------|------|------|
| | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 |
| Zone 1 | █ | | | █ | | | █ | | |
| Zone 2 | | █ | | | █ | | | █ | |
| Zone 3 | | | █ | | | █ | | | █ |

Fig. 3.3-11 Stage Plan for Landfill Operation by Partition

2) Design of Working Face

To maintain a sanitary condition, it is necessary to minimize area of working face where the garbage is unloaded every day. The average specification of working face is calculated for one week operation as follows :

- Duration of unloading : 7 days
- size of working face : 50 to 70 m
- Daily amount of garbage : 900 t/d
- Height of layer : 1.8 to 2.0 m (x 2 layers)
- Size of cell (1 lot of a series of : 4,200 m²
operation for 7 days)

Each cell is covered with aged garbage or soil in order to prevent the generation of offensive odor and waste scattering. Covering is planned to be carried out once a week just after finishing the shaping of a layer for a cell. The thickness of cover layer is planned to be 10 to 20 cm for every intermediate cover.

3) Operation Cycle

Landfill operation in a cycle is executed according to the repeated cycle which is composed of the process to complete a cell of garbage. The standard process is explained sequentially as follows:

1st Layer

- Unloading garbage/shaping the cell ----- 7 days
- Surface covering ----- 1 or 2 days
- Gas vent installation ----- within 1 week or less

2nd Layer

- Unloading garbage/shaping the cell ----- 7 days
- Surface Covering ----- 1 or 2 days
- Gas vent installation ----- within 1 week or less
- Underdrain installation ----- within 1 week or less

The cycle will be applied to each zone of landfill. The operation in a zone will be completed when the operation crew has covered the whole zone. Then the crew moves to the next zone.

4) **Additional Construction and Material Demand**

Gas vent and underdrain should be constructed for each cell in stage by stage manner because these facilities are placed among the waste layer. This part of construction cost is estimated separately from the initial construction cost. Table 3.3-4 presents a tentative bill of quantity for the operation stage.

Table 3.3-4 Bill of Quantity for Operation Stage

| Items | | Unit | Quantity | | | | |
|----------------|----------------|-------|----------|--------|--------|--------|--------|
| | | | 1996 | 1997 | 1998 | 1999 | 2000 |
| Leachate Drain | Cobble filling | m3 | | | 7,700 | 7,910 | 6,630 |
| | PVC pipe | m | | | 5,680 | 5,720 | 5,360 |
| Gas Vent | Bamboo cage | piece | 55 | 63 | 105 | 118 | 113 |
| Covering | Soil Transport | m3 | 66,000 | 66,000 | 66,000 | 66,000 | 66,000 |
| | Thickness | (m) | (0.4) | (0.4) | (0.4) | (0.4) | (0.4) |

| Items | | Unit | Quantity | | | | |
|----------------|----------------|-------|----------|---------|---------|---------|---------|
| | | | 2001 | 2002 | 2003 | 2004 | Total |
| Leachate Drain | Cobble filling | m3 | | | | | 22,240 |
| | PVC pipe | m | | | | | 16,760 |
| Gas Vent | Bamboo cage | piece | 105 | 118 | 113 | 50 | 840 |
| Covering | Soil Transport | m3 | 66,000 | 120,000 | 120,000 | 120,000 | 756,000 |
| | Thickness | (m) | (0.4) | (1.0) | (1.0) | (1.0) | |

3.3.2 Organization

It is recommended that the landfill site is operated by the full-time staff. The proposed organization for landfill site is shown in Fig. 3.3-12.




Fig. 3.3-12 Proposed Administrative Organization

Among this organization, the operation division is thought to be a branch of the existing haulage section (Seksi Angkutan), however, it is desirable to execute the landfill operation under the instruction of technical staff in order to satisfy technical requirements of sanitary landfill.

However, it may be suitable for KMS to entrust the landfill operation to a private contractor because the landfill operation requires frequent installation of drain and gas vent for each landfill stage. Installation work has usually been entrusted to private

contractors in many cities in Japan and other countries. And the place of installation work is located very closely to that of landfill operation.

Therefore, the whole landfill operation as well as construction may be done by one contractor efficiently. The use of a private contractor for landfill operation is worth investigation when KMS has acquired a certain experience in sanitary landfill operation.

3.3.3 Heavy Equipment

Landfill operation is planned to be executed with heavy equipment listed in Table 3.3-5.

Table 3.3-5 List of Heavy Equipment

| Type | Quantity | Duty |
|------------|----------|--|
| Bulldozer | 4 | Construct on-site road Place and compact garbage Form the cell Soil cover |
| Excavator | 1 | Finish the cell Maintain ditch, road and pond |
| Dump truck | 2 | Transport cover soil from the internal deposit to the working cell. |

Note : Dump trucks are expected to work for 2 days a week.

3.4 Construction Schedule

Construction schedule is shown in relation to the operation stage in Fig. 3.3-13 and 3.3-14. Initial stage of construction will take about 2 years excluding design work since 1995 to 1996. The whole construction will last for 9 years up to 2003 according to the progress of the landfill operation.

| Work Design | | 1994 | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 | |
|--------------|--------------|------------------------|--------|------|------|------|------|------|------|------|------|------|------|--|
| Design | Construction | Access Road | 0.1 | 2 | 3 | | | | | | | | | |
| | | Retention Pond | | A | B | | | | | | | | | |
| | | Enclosure Dike | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | | |
| | | Divider Dike | | 1 | 2 | 3 | 4 | 5 | | 6 | 7 | | | |
| | | Rainwater Drain | | 1 | 2 | 3 | | | | | | | | |
| | | Leachate Ditch | | 1 | 2 | 3 | | | | | | | | |
| | | Leachate Drain | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | | |
| | | Gas Ventilation | | 1 | 2 | 3 | | | | | | | | |
| | | Recirculation facility | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | | |
| | | Adm. Building | | | | | | | | | | | | |
| | | Onsite Road | | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | | |
| | | Operation | Zone-1 | | | | | | | | | | | |
| Zone-2 | | | | | | | | | | | | | | |
| Zone-3 | | | | | | | | | | | | | | |
| Covering | | | | | | | | | | | | | | |
| Closing Work | | | | | | | | | | | | | | |

FIG. 3.3-13

TIME SCHEDULE OF CONSTRUCTION

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY




FIG. 3.3-14

PLAN FOR CONSTRUCTION STAGE

THE STUDY ON THE SOLID WASTE MANAGEMENT IMPROVEMENT FOR SURABAYA CITY

3.5 Project Cost and Finance

3.5.1 Investment Cost

Investment costs except vehicle or heavy equipment procurement are summarized in Table 3.3-6. The total amount of direct cost is estimated at about Rp 23,283,000 and adding tax of 10%, the total investment cost is estimated at Rp 25,610,000.

3.5.2 Operational and Maintenance Cost

The operation and maintenance costs are classified into two (2) types; 1) costs of operation and maintenance of heavy equipment including salary of employees, and 2) costs for application of cover material.

Table 3.3-6 Investment Cost for Construction
(Total Cost)

| Works | Type | Subitem | Unit | Quantity | Unit Price | Amount (10 ³ Rp) | Remarks |
|------------------------|------------------------------|------------------|-------|----------|------------|-----------------------------|---------------------|
| Ground work | Flattening | | m2 | 445,000 | 670 | 298,150 | |
| Foundation | Steel Sheet Pile | | t | 4,785 | 1,650,000 | 7,895,250 | |
| | Installation | | m | 99,680 | 10,000 | 996,800 | |
| Subtotal | | | | | | 8,892,050 | |
| Main Structure | Banking | Clay | m3 | 364,740 | 14,000 | 5,106,360 | with material |
| | Banking | Aged Waste | m3 | 47,420 | 12,780 | 606,028 | with transport cost |
| | Slope Forming | | m2 | 88,520 | 13,550 | 1,199,446 | |
| | Lining | t=200mm | m2 | 4,180 | 15,680 | 65,542 | |
| Subtotal | | | | | | 6,977,376 | |
| Retention Pond | Excavation | | m3 | 15,650 | 5,600 | 87,640 | |
| | Soil Haulage | | m3 | 15,650 | 470 | 7,356 | |
| | Banking | | m3 | 2,040 | 14,000 | 28,560 | |
| | Slope Forming | | m2 | 4,580 | 13,550 | 62,059 | |
| Subtotal | | | | | | 185,615 | |
| Leachate Recirculation | Pump | 22kw | Unit | 2 | 54,000,000 | 108,000 | |
| Underdrain | PVC Tube | ø300 | m | 24,540 | 38,500 | 944,790 | |
| | | ø150 | m | 24,300 | 15,000 | 364,500 | |
| | Crushed Stone | | m3 | 44,860 | 16,520 | 741,087 | |
| | Bamboo | | m | 103,920 | 605 | 62,872 | |
| | Bamboo Panel | | m2 | 47,949 | 1,500 | 71,924 | |
| Subtotal | | | | | | 2,185,172 | |
| Gas Vent | | ø500 x ø1000 | Piece | 1,008 | 17,000 | 17,136 | |
| Rainwater Drain | a block | 900 x 1,350 | m | 690 | 326,000 | 224,940 | |
| | b block | 1,600 x 1,800 | m | 160 | 466,000 | 74,560 | |
| | c block | 2,700 x 2,000 | m | 180 | 818,000 | 147,240 | |
| | d block | 2,300 x 1,500 | m | 970 | 458,000 | 444,260 | |
| | e block | 4,000 x 1,150 | m | 220 | 579,000 | 127,380 | |
| | Box Culvert | | L.S. | 1 | | 63,569 | |
| | Side Ditch | R=25(semicircle) | m | 2,360 | 4,205 | 9,923 | |
| | Weir | H=300 | L.S. | 1 | | 10 | |
| Subtotal | | | | | | 1,091,882 | |
| Access Road | A Type | | m | 510 | 1,084,000 | 552,840 | |
| | B Type | | m | 1,340 | 510,000 | 683,400 | |
| Subtotal | | | | | | 1,236,240 | |
| Maintenance Road | C Type | W=2m | m | 1,950 | 15,000 | 29,250 | |
| | D Type | W=5m | m | 885 | 97,000 | 85,845 | |
| Subtotal | | | | | | 115,095 | |
| On-site Road | | W=7m | m | 1,355 | 57,000 | 77,235 | |
| Adm. Building | Building | | L.S. | 1 | | 379,450 | |
| | Power Receiving | | L.S. | 1 | | 207,100 | |
| Subtotal | | | | | | 586,550 | |
| Workshop | | | L.S. | 1 | | 283,175 | |
| Weighing Facility | Truck Scale | | L.S. | 1 | | 168,663 | |
| | Weigh Booth | | L.S. | 1 | | 8,560 | |
| Subtotal | | | | | | 177,223 | |
| Small Water Supply | Tank, Pump Small Purifyer | 10m x 6m x 3.5m | L.S. | 1 | | 64,199 | |
| Vehicle Washing Pool | | 5m x 10m x 0.5m | L.S. | 1 | | 12,351 | |
| Parking Lot | | | L.S. | 1 | | 22,750 | |
| Total | | | | | | 22,330,198 | |
| Auxiliary Works | | | L.S. | 1 | | 953,628 | x5% |
| Direct Cost Total | | | | | | 23,283,826 | |

The first type of cost is shown in Table 3.3-7.

Table 3.3-7 Cost of Operation & Maintenance of Heavy Equipment

| Item | Calculation (Rp. 1,000/y) | Cost (Rp. million/y) |
|--------------------------|--|-------------------------|
| a. Insurance | Rp. 1,430,000 (purchase cost of equipment) x 2% | 29 |
| b. Equipment Maintenance | Rp. 1,430,000 (purchase cost of equipment) x 12.5% | 179 |
| c. Fuel | Bulldozer 20l/h x 8h/d x 365d x Rp. 450 x 4 units | 105 |
| | Excavator 20l/h x 5h/d x 365d x Rp. 450 | 16 |
| | Dump Truck 4l/h x 5h/d x 2 d/w x 52w x Rp. 450 x 2 units | 2 |
| d. Salary | 14 person x Rp. 100,000 x 12 m | 17 |
| e. Electricity | 90 kwh/d x 365 x 0.153 + 6.9 x 12 | 5 |
| Total | | 353 |

Note: Purchasing cost of heavy equipment

| | | |
|-----------|---|---|
| Bulldozer | @ | Rp. 300 million x 4 = Rp. 1,200 million |
| Excavator | @ | Rp. 230 million x 1 = Rp. 230 million |
| Total | | Rp. 1,430 million |

The second type of cost is shown in the following table.

Table 3.3-8 Cost of Application of Cover Material (1996-2004)

| Items | Calculation (Rp./y) | Cost (Rp million/y) |
|----------------|--|------------------------|
| Cover Material | @ 5,000 Rp/m ³ x 66,000 m ³ (1996-2001) | 330 |
| | @ 5,000 Rp/m ³ x 120,000 m ³ (2002-2004) | 600 |

Overall operation and maintenance costs are shown in the following table.

Table 3.3-9 Overall Maintenance and Operational Cost

| Maintenance & Operational Cost for | | Cost (Rp million/y) | Planning Disposal Amount (1,000 t/y) | Unit Cost (Rp/t) |
|---------------------------------------|-----------|------------------------|--|---------------------|
| O & M Cost related to Heavy Equipment | | 353 | 329 | 1,073 |
| Cost of Application of Cover Material | 1996-2001 | 330 | 329 | 1,000 |
| | 2002-2004 | 600 | 329 | 1,820 |
| Total (cash expense) | 1996-2001 | 683 | 329 | 2,073 |
| | 2002-2004 | 953 | 329 | 2,893 |

Operation and Maintenance Cost is estimated at about Rp 683 million/year for the first six (6) years and Rp 953 million/year for the last three (3) years. This cost corresponds to a unit cost of about Rp 2,100/t and Rp 2,900/t according to the respective operation stage. These unit costs are higher than present unit cost by 25% and 75% respectively.

3.5.3 Investment Schedule

Investment will concentrate in the initial stage of the project to construct the landfill site and procure heavy equipment for landfill operation.

Total investment amount is estimated at about Rp 25.6 billion including value added tax as shown in Table 3.3-10.

Table 3.3-10 Investment Schedule

Without value added tax (unit : Rp million)

| | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | Total |
|------------------------------|--------|-------|------|-------|------|-------|------|------|------|------|--------|
| Initial | 16,668 | 3,356 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 20,024 |
| Additional Construction Cost | 0 | 1 | 1 | 1,278 | 909 | 1,012 | 2 | 2 | 2 | 52 | 3,259 |
| Total | 16,668 | 3,357 | 1 | 1,278 | 909 | 1,012 | 2 | 2 | 2 | 52 | 23,283 |

Including value added tax (unit : Rp million)

| | 1995 | 1996 | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | Total |
|------------------------------|--------|-------|------|-------|-------|-------|------|------|------|------|--------|
| Initial | 18,335 | 3,692 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 22,027 |
| Additional Construction Cost | 0 | 1 | 1 | 1,405 | 1,000 | 1,113 | 2 | 2 | 2 | 57 | 3,583 |
| Total | 18,335 | 3,693 | 1 | 1,405 | 1,000 | 1,113 | 2 | 2 | 2 | 57 | 25,610 |

Note : Value Added Tax (VAT) is 10% of the original price without the tax.

Unit investment cost per ton of waste disposed is estimated to be approximately Rp 9,000/ton assuming that total disposal amount would be about 3 million ton during the period from 1995 to 2004.

3.6 Environmental Impact Assessment (EIA)

3.6.1 Procedure of EIA

An environmental impact assessment (EIA) has been carried out according to the Indonesian laws and regulations listed below. The EIA also followed the Indonesian standards with respect to water and air quality and by-laws concerning river management and solid waste management.

- a. Laws No.4/1982 concerning the Principle Determination of Environmental Management.
- b. Governmental Regulations No.29/1986 concerning Environmental Assessment
- c. Decree of Minister of Population and Environment No.KEP-49/MENKLH/6/1987 and Decree of East Java Governor No.183/1988 concerning Important Impact Determination Guidelines and its attachments.
- d. Decree of Minister of Population and Environment No.JEP-50/MENKLH/6/1987, Decree of East Java Governor No.184/1988 concerning Environmental Assessment Preparation Guidelines, and Attachment to the Decision of East Java Governor No.185/1988
- e. Decree of Public Works Minister No.531/KPTS/1989 concerning AMDAL Selection Guidelines of Public Works Projects.
- f. Decree of Public Works Minister No.506/KPTS/1991 Replace Decree No.557/KPTS/1989 concerning AMDAL Management Guidelines of Public Works Projects.
- g. Decree of Public Works Minister No.779/KPTS/1989 concerning AMDAL Technical Guidelines of Public Works Projects - Solid Waste Project

It is understood that an EIA with respect to the construction of a new disposal site is required by the Decree e. listed above. An EIA was then conducted according to the procedure stipulated in the Decree c. above.


Cipta Karya and East Java Provincial Government agreed that an EIA and its appraisal should be conducted in the following manner:

1. AMDAL Commission on this project should consist of the Central AMDAL Commission of Cipta Karya and Local AMDAL Commission of East Java Provincial Government.
2. The Decree g. is used as a technical guideline for the EIA.
3. The procedure of EIA follows the Decree d.

To begin with EIA, the Study Team prepared a terms of reference (KA ANDAL), and submitted it under the name of the mayor of Surabaya City, project proponent, to the Local AMDAL Commission of East Java Province. The KA ANDAL was accepted by the Governor of the East Java Provincial Government in January 1993.

3.6.2 Environmental Impact Analysis (ANDAL) Conducted

ANDAL was conducted with a process shown below:



1) Impact Identification

Impacts of the project were identified by the following four (4) project phases:

1. Acquisition of site
2. Construction
3. Landfill operation
4. Post operation phase

2) Data Collection

Primary data on the following aspects were collected through a field survey conducted for two (2) months from October 1992.

1. Topography of the areas in and around the project site (General topography, River catchment area, Elevation)
2. Geology (Strata, Soil mechanics and physical characteristics)
3. Land utilization (area and distribution by land use)
4. Quality of air (NH₃, H₂S)
5. Quality of surface and ground water (Temperature, pH, Cl⁻, DO, SS, COD, BOD, T-N, SO₄²⁻, CN⁻, Heavy metals, Coliform and other toxic substances)
6. Wild lives (Flora and Fauna)
7. Health Conditions
9. Socio-economic conditions

3) Impact Forecasting and Suggestion of Mitigation Measures

Impacts of the project were forecasted qualitatively in terms of comparison of the conditions that would arise with and without implementation of the project. Mitigation measures were suggested against any significant impacts forecasted.

4) Impact Assessment

Impacts of the project were assessed in terms of the following aspects according to the Decrees b) and c) listed in Section 3.6.1.

1. Number of people affected,
2. Affected Area,
3. Duration of impact,
4. Intensity of impact,
5. Other components affected,
6. Cumulative characteristics of the impacts, and
7. Possible re-occurrence of the impact

3.6.3 Impact Identification

The project can be divided into three phases: land acquisition phase, construction phase, operation phase and post operation phase. Environmental impacts are described for both positive and negative aspects in four phases as follows:

a. Land Acquisition Phase

Negative environmental impacts by this phase are:

- Decreases of land value
- Loss of job in fishery and salt arming

b. Construction Phase

A positive environmental impact by the construction works is :

- Increasing employment opportunities of labor

Negative environmental impacts by the construction works are as follows :

- Increases in traffic volume caused by transportation of construction materials and equipment
- Generation of noise, vibration and air pollution caused by heavy equipment and vehicles
- Generation of turbid water

c. Operation Phase

The main objective of the sanitary landfill is to upgrade the sanitary standard of solid waste disposal. This is positive environmental impact.

It is expected that the landfill operation would cause some negative environmental impacts as follows:

- Generation of leachate from garbage
- Generation of odor from the disposal site and vehicle
- Garbage scattering by wind, birds and mammal

- Generation of noise and air pollution by heavy equipment and vehicle
- Increases in traffic volume by haulage vehicles

d. Post Operation Phase

A positive environmental impact after operation is expected by converting the disposal area to other purposes. For example, it is possible to create some open - air facilities such as park, garden, sport facilities and so on. But, some mitigation measures will be necessary for a certain period even after the completion of closing works.

3.6.4 Forecasted Significant Environmental Impact and Possible Mitigation Measures

1) Air Quality and Noise

a. Dust and Noise

The site preparation and waste haulage to the site will cause an impact in the form of:

- 1) dust raising by construction and haulage vehicles, 2) Noise of the above vehicles.

To mitigate the negative impacts, the following measures can be applied:

1. Spray water on the access road close to the neighboring community
2. Cover the freight of vehicles with canvas or plastic sheet
3. No activities at night

b. Offensive Odor and Gasses

Gasses will be generated at landfill site through waste decomposition process. As a result, offensive odor will be generated through landfill operation and also waste haulage and landfill operation. Offensive odor may directly affect neighbors. Gasses, mainly composed of methane may cause spontaneous fire or lead to generation of other harmful gasses such as formaldehyde. To mitigate the negative impacts, the following measures can be applied:

1. Cover the freight of haulage vehicles with canvas or plastic sheet.
2. Provide a green belt as a buffer zone around the landfill site.
3. Cover the waste layer with soil as soon as possible.
4. Diffuse gasses safely through ventilation network.

2) Surface Water and Ground Water Quality

The significant negative impact to surface water and ground water quality is pollution due to leachate. The major components of leachate is COD, N and P which are about 30,000 mg/l, 20 mg/l and 60 mg/l respectively.

To mitigate the negative impact, leachate recirculation will accelerate waste decomposition process: COD of leachate supplies the energy source and N&P as nutrient for microorganism. The other alternative is the natural treatment of leachate using soil process, ARIFANI & SARWOKO (1992) found out the reduction of COD, N and P by about 90% can be made possible by flowing the leachate to the land with soil texture of sand:silt:clay = 45%:35%:20%. Irrespective of whatever technology used, the leachate treatment gives the positive impact.

3) Flora and Fauna

The flora and fauna that may be affected by LPA operation are:

1. The impact will be interlocked with pollution of water surface by leachate, especially in the wet season because the leachate control is very difficult.
2. Disease carrying vector such as insects and rats will increase because of the solid waste disposal.

Measures for mitigation of impact on the aquatic flora and fauna are same as those for mitigation of leachate.

To reduce insects and rats population, it is effective to cover solid waste with soil as soon as possible after the waste dumping.

4) Socio-Economic Condition

Land acquisition activity may raise restless opinion in local community. Especially if the cost of compensation is too low or if the land acquisition negotiation is not smooth, the project will make the community restless because the perception of the people on LPA is "the environmentally poor land".

The general method to solve that problem is to give the reasonable compensation to the loss of their land and other property.

The procedure of land acquisition and compensation, by government is stipulated in Kep. Men. Dagri No.2/1985: If the area of land is less than 5 ha, Camat and lurah take the responsibility, if the area is more than 5 ha, the Nine - Persons - Committee (Panitia Sembilan) takes responsibility. The stipulated steps of land acquisition are :

- a. Coordination meeting among responsible agencies.
- b. After the meeting, announcement of the land acquisition is released by Walikota (Mayor).
- c. Preconditioning meeting with affected community should be held. The agencies are responsible to arrange meetings with affected community. The agencies should explain community about the project, and people can ask some questions.
- d. "9 - Persons - Committee" calculate some items of land acquisition. There are a specification of costs according to land status, building type, land use, etc. After estimation of costs, they will arrange meetings with the community again.

The other related stipulations are as follows:

- a. The community may propose the compensation costs.
- b. The Government will not give the compensation to the people who live in the government land.
- c. If negotiations with the land owners are not agreeable, then the problem of compensation can be brought to the court.
- d. The compensation costs are paid by the Government.
- e. That procedure may last for one year.

Based on the experience in the Surabaya city, the compensation by means of "money" is the successful factor of the land acquisition.

In construction phase, use of external man power will frustrate the local people who have no chance to get job from the project. To prevent that, the project must use the local man power. Use of external man power should be allowed in specific conditions only.

5) Amenity

In operation phase, the negative impact that need specific mitigation are the aesthetic disturbance that may be caused through

1. used old trucks to bring the solid waste and
2. dispersion of paper and other waste by wind to the settlements nearby the site.

The mitigation of these problem is described in section 1) Air Quality and Noise.

The community may full in a restless condition because people have perception that impact of landfill activities will create security problems. Therefore the sanitary landfill authority must manage the activities, and give guarantee to community that the landfill activities is not disturbing aesthetic environment

3.6.5 Evaluation

A detailed assessment of the project impacts was carried out. As a result, an ANDAL report was prepared. It was then submitted to the Local Commission of AMDAL, Jawa Timur. The approval letter of ANDAL report was already issued by the Local Commission as shown in Appendix 5.

Based on the Approval Letter, this project was identified environmentally sound in terms of both natural and social conditions, if only the executing agency of the project pays attention to the following issues:

1. The negative impact on Social-Culture to be caused by the operation of new disposal site.
2. Pay attention on the aesthetic environment after development of new disposal site.

3. Handle leachate and construct the leachate retention ponds and to control its limited state.
4. Handle air pollution problems such as dust, smell, etc.
5. Establish green linkage area by planting trees around the disposal site area.
6. The traffic disturbing or congestion that may be caused by the waste trucks.

Chapter 4. F/S Component 3: Construction and Rehabilitation of Depo/LPS & Improvement of Asemrowo Workshop

4.1 Background, Purpose and Outline of the Project

4.1.1 Construction of New Depo and LPS

At present, KMS has 58 Depo and 102 LPS in Surabaya which serve as small transfer stations. (A Depo has a small administrative office stationed with an officer, while LPS does not have such office.)

The existing Depo and LPS is not sufficient in number at present. In principle, a Kelurahan should be provided with either a Depo or LPS. In view of the future increases in population and waste amount, it is considered necessary to construct new Depo and LPS.

It is planned 24 Depo and 12 LPS will be constructed during the 4 years period 1994/95 - 1997/98. Total construction cost is estimated to be Rp 1,157 million approximately in 1992 price.

The priority is given to Kelurahan with higher population density in the selection of the Kelurahan where new Depo or LPS are constructed, as well as in the determination of order of construction.

4.1.2 Rehabilitation of the Existing Depo and LPS

Some of the existing Depo and LPS need rehabilitation with respect to the following facilities:

1. Wall
2. Office building
3. Drainage
4. Gate
5. Floor
6. Water pipes and Electricity equipment
7. Enlargement of entrance
8. Expansion of area

In addition, tree planting around Depo and LPS is advisable as it is effective to make them look nicer. KMS should identify suitable kinds of trees.

It is planned that 30 Depo and 34 LPS will be rehabilitated during the planned 4 years period 1994/95 - 1997/98.. In addition, it is planned that tree will be planned for 90 % of Depo and LPS during the period. Total cost of the rehabilitation is estimated to be Rp 184 million.

4.1.3 Improvements of Asemrowo Workshop

In order to improve the vehicle maintenance capacity of Asemrowo Workshop, the following construction and procurement is planned.

1. Remodeling of the Workshop
2. Procurement of tool and equipment for maintenance and repair

Total cost needed for the above improvements is estimated to be Rp 267 million approximately in 1992 price. These improvements will be implemented in 1994/95.

4.2 Project Description

4.2.1 Construction of New Depo and LPS

1) Construction Program

It is planned that 24 new Depo and 12 LPS will be constructed during the 4 years period from 1994/95 - 1997/98. In each year, 6 Depo and 3 LPS will be constructed. Table 3.4-2 shows names of Kelurahan where Depo or LPS should be constructed. Locations of new Depo and LPS are shown in Fig. 3.4-1.

Land Acquisition

The land ownership status is shown also in Table 3.4-2. Of the 24 Depo and 12 LPS, it is identified that KMS should purchase land for construction of nine (9) Depo as shown in the table below. Land for other Depo and LPS is either owned by KMS or can possibly be made available for KMS free of charge.

Table 3.4-1 Land Acquisition for Construction of New Depo and LPS

| Land Status | Depo | LPS |
|---|------|-----|
| 1. Number of Depo & LPS to be constructed | 24 | 12 |
| 2. Number of Depo & LPS of which land is owned by KMS | 10 | 1 |
| 3. Number of Depo & LPS of which land belongs to other persons or organizations, but can possibly be made available for KMS' use free of charge | 5 | 11 |
| 4. Number of Depo & LPS of which land must be purchased (1 - 2 - 3) | 9 | 0 |

Table 3.4-2 Depo and LPS Construction Program

| No | Construction Year | Kecamatan | Kelurahan | Area (ha) | Population ##### | Population Density (per ha) | Depo | LPS | Land Status | Necessity of Land Purchase |
|----|-------------------|--------------|--------------------|-----------|------------------|-----------------------------|------|-----|---------------|----------------------------|
| 1 | 1994/1995 | Bubutan | Jepra | 45 | 28,400 | 632 | 1 | | TNI AD | - |
| 2 | | Bubutan | Gundih | 50 | 28,900 | 577 | | 1 | PIKA | - |
| 3 | | Semampir | Sidotopo | 65 | 31,700 | 488 | | 1 | KMS | - |
| 4 | | Simokerto | Sidotadi | 35 | 16,000 | 427 | | 1 | Market/KMS | - |
| 5 | | Kremlangan | Kemayoran | 48 | 19,000 | 396 | 1 | | Private | √ |
| 6 | | Sawahan | Kupang Krajan | 69 | 25,400 | 368 | 1 | | Private | √ |
| 7 | | Semampir | Pegirian | 78 | 26,700 | 342 | 1 | | Cemetery | - |
| 8 | | Sawahan | Petemon | 174 | 42,000 | 241 | 1 | | Private | √ |
| 9 | | Sawahan | Pusat Jaya | 207 | 42,400 | 205 | 1 | | Cemetery | - |
| 10 | 1995/1996 | Kremlangan | Dupak | 66 | 27,000 | 412 | | 1 | Market/KMS | - |
| 11 | | Genteng | Peneteleh | 53 | 19,000 | 302 | | 1 | Brantas Hilir | - |
| 12 | | Tambaksari | Rangkah | 67 | 19,600 | 292 | | 1 | Market/KMS | - |
| 13 | | Sukolilo | Nginden Jangkungan | 104 | 12,700 | 122 | 1 | | KMS | - |
| 14 | | Lakarsantri | Jeruk | 37 | 4,400 | 119 | 1 | | KMS | - |
| 15 | | Suko | Tanjung Sari | 108 | 12,400 | 115 | 1 | | Real Estate | - |
| 16 | | Gunung Anyar | Rungkut Tengah | 119 | 13,700 | 115 | 1 | | Real Estate | - |
| 17 | | Sukolilo | Klampis Ngasem | 150 | 16,400 | 109 | 1 | | KMS | - |
| 18 | | Wonocolo | Sidosermo | 114 | 8,900 | 78 | 1 | | KMS | - |
| 19 | 1996/1997 | Kremlangan | Kremlangan Selatan | 86 | 18,400 | 214 | | 1 | Market/KMS | - |
| 20 | | Bubutan | Bubutan | 81 | 15,300 | 189 | | 1 | Market/KMS | - |
| 21 | | Kremlangan | Moro Kremlangan | 277 | 36,900 | 133 | | 1 | Binamarga | - |
| 22 | | Benowo | Tambakdono | 29 | 1,879 | 65 | 1 | | Private | √ |
| 23 | | Tandes | Gedang Asin | 11 | 1,716 | 65 | 1 | | Private | √ |
| 24 | | Dukuh Pakis | Dukuh Pakis | 143 | 8,696 | 61 | 1 | | TVRI | √ |
| 25 | | Tandes | Banjar Sugihan | 130 | 7,935 | 61 | 1 | | KMS | - |
| 26 | | Tandes | Karang Poh | 51 | 2,866 | 56 | 1 | | Private | √ |
| 27 | | Tambaksari | Gading | 1,115 | 59,243 | 53 | 1 | | Private | √ |
| 28 | 1997/1998 | Genteng | Kevabang | 121 | 11,000 | 91 | | 1 | KMS | - |
| 29 | | Kenjeran | Sukolilo | 53 | 3,900 | 74 | | 1 | Market/KMS | - |
| 30 | | Mulyorejo | Kalijudan | 135 | 6,842 | 51 | | 1 | Uncertain | - |
| 31 | | Sukolilo | Gebang Putih | 118 | 5,582 | 47 | 1 | | Private | √ |
| 32 | | Kenjeran | Kenjeran | 53 | 2,163 | 41 | 1 | | KMS | - |
| 33 | | Sukolilo | Medokan Semampir | 180 | 6,800 | 38 | 1 | | KMS | - |
| 34 | | Kenjeran | Kedung Cowek | 89 | 3,339 | 38 | 1 | | KMS | - |
| 35 | | Rungkut | Penjaringan Sari | 189 | 6,900 | 37 | 1 | | KMS | - |
| 36 | | Lakarsantri | Sambi Kerep | 348 | 9,600 | 28 | 1 | | KMS | - |

Note: "√" shown in the most right column means that KMS should purchase land.