- Drought Relief Project, 9 out of 13 : 69%

The above rates include boreholes which yield less than 0.5 cu.m/hr, and it should be considered in the plan that groundwater development is becoming harder to harder as the time. The success rate for the Project, however, is to be taken at 70 percent considering the above results.

# 5-2-4 Site Selection

Site selection is one of the most important factors for the successful construction of boreholes. The methods of siting are mainly composed of geophysical prospecting such as GEP and E-M prospecting. However, it is also important to make a judgment based on local conditions such as vegetation, lithofacies and microtopography together with human experience in the area.

The DWD has geophysicists and hydrogeologists at its Headquater and in its Provincial Offices. The site selection will be executed by Japanese engineer with assistance from the siting team of DWD who are well versed in local conditions.

The siting methods are as follows;

- Analysis by Airphotos:

Using airphotos, preliminary siting by airphoto survey will be carried out in the geography concerned with hydrogeology, the pattern of distribution of lineaments and so forth.

- E-M Prospecting:

E-M prospecting will be carried out for the rough field survey for further prospecting by GEP prospecting.

- GEP Prospecting:

GEP prospecting will be conducted at the sites selected by E-M survey results. The some kinds of GEP prospecting methods will be applied for the judgment of thickness of weathered zone and/or detection of fissured zone which are able to form aquifers. Based on the results obtained from some kinds of prospecting such as Wenner's, Schlumberger's, dipole-dipole, etc., the most effective method for the area will be determined.

# 5-3 BASIC DESIGN OF FACILITIES

# 5-3-1 Design of Boreholes

The borehole should be deeper than 30 m and have a six meters grout sealing zone at the minimum so as to secure safe and stable water and to protect water quality from contamination caused by the infiltration of surface water.


The borehole diameter is to be 100 mm for the holes constructed by the Japanese side and 150 mm for the holes constructed by the Zimbabwean side.

The borehole types are designed as shown in Figure 5-3-1.

### 5-3-2 Design of Headworks

The type of headworks for each borehole is standardized in Zimbabwe, and the same design will be adopted by the Project. This type is almost similar to others prevailing in other African countries and can be judged as appropriate.

The design of the headworks is given in Figure 5-3-2.



- 70 -




Figure 5-3-2 Plan and Section of Head Works

- 71 -

### 5 - 4 Basic Plan of Equipment and Materials

The outline of the equipment and materials to be procured is shown in section 4-3-3. In this section, the quantity and specifications of the selected equipment are provided;

And, the origin of the equipment and materials is as follows.

- Third-country products : Steel casing and air-compressor in a case
- Zimbabwean products

Japanese products

- Handpump Others
- .

**Drilling Rigs** 

(1)

2 units

The technical specifications for the rig are as follows;

- a) Top-drive Rotary and DTH type, Hold back capacity : 6,000 kg, rated capacity : 200 m with 117 mm drill pipes,
  - Mudpump capacity : 600 l./min
- b) Standard accessories and tools,
- c) Truck-mounted model, engine output : 160 HP

### (2) Air-compressors, product f Japan or a third country 2 units

An air-compressor will be provided for each drilling rig.

a) Air-compressor, capacity: 19 cum./min. at 18.0 kg/cm<sup>2</sup>

### (3) Supporting Vehicles

The borehole construction works will be done by the teams for drilling (2), testing (1), construction of headworks (1), management (1) and geophysical prospecting (1), total 6 teams. The types and/or model, numbers and purpose of vehicles used by the above teams are shown in Table 5-4-1.

### TABLE 5-4-1 LIST OF SUPPORTING VEHICLES

| Type / Model   | No. | Specifications and Purpose  |
|----------------|-----|---|
| Tool Truck     | 2   | 4 	imes 4, with 3-ton crane, GVW : 15 ton   |
| Cargo Truck    | 2   | $4 \times 4$ , with 3-ton crane, GVW : 15 ton   |
| Recovery Truck | 1   | Pulling capacity : 20 ton   |
| Pick-up        | 4   | $4 \times 4$ , management, headworks construction, borehole test, transport for staff/goods |
| Station Wagon  | 2   | 4	imes 4, transport for staff, prospecting  |

# (4) Geophysical Instruments

a) E-M Instrument :

portable type with battery-source power, frequency, 0.5 - 6.0 kHz or equivalent

b) GEP Instrument :

prospecting depth, 100 m

(5) Borehole Logger

The logger is as follows:

| Items to be measured | : | resistivity, caliper and temperature |
|----------------------|---|--------------------------------------|
| Recording method     | : | automatic recorder                   |
| Depth to be measured | : | 100 m                                |

# (6) Radio-telephone System

The radio-telephone systems are provided for the communication between the job sites and camp/Provincial Office, Harare.

| Base stations (2 units)   |   | 100 W |
|---------------------------|---|-------|
| Mobile stations (6 units) | ; | 30 W  |

2 sets

2 units

2 lots

(7) Trailor-mounted Mobile Workshop

2 lots

- Trailor-mounted workshop for warehouse,  $2.4 \times 6.0 \times .20$  m
- Container with working table, etc.
- Equipment and tools for the above
- (8) Handpump

### (40) units

40 handpumps are included in the construction works by the Japanese side.

3 units

(9)

Submersible-motor Pump

| Submersible-motor pump : |   | 1.5 kw for 100 mm diameter |  |  |
|--------------------------|---|----------------------------|--|--|
| Diesel Generator         | • | 20 PS, 390 V               |  |  |
| Water Table Detector     | : | 100 m                      |  |  |

(10) Steel Casing (third country product)

### 1,080 Nos.

Steel casing for 360 boreholes, 3 numbers to each, to be constructed by the Zimbabwean side will be procured.

:

Casing

6.0 m length, 7 mm thickness, API 5A H40 or equivalent, plain ends

1 lot

### (11) Air-foam and Mud Agents

The following agents are provided.

| - | Air-foam |   | 1,000 kg   |
|---|----------|---|------------|
| - | CMC      | : | $260 \ kg$ |
| - | Rester   |   | 3,000 kg   |

(12) Spare Parts

1 lot

Spare parts for the above equipment are provided. The quantities of spare parts are for 2-years' operation, equivalent to an amount of 10 to 15 percent of the prices for equipment itself.

Spare parts for Phase-2 equipment are also provided. The list of items is attached in Annex-7.

- 75 -

## 5-5 Implementation Programme

# 5-5-1 Implementation Policy

Project execution under Japanese grant aid, the borehole construction will be executed by a Japanese Contractor under the supervision by the DWD and/or a Japanese Consultant.

Borehole construction by the Japanese Contractor is aiming to facilitate technical transfer for maintenance and operation of equipment, which are newly introduced to the Zimbabwean staff on the occasion of the Project, through on-thejob training. The major responsibilities of the Japanese Contractor are shown below.

The construction works will be done in UMP District with the following contents;

| District | No. of<br>Boreholes | No. of<br>Drilling | Drilling<br>Length (m) | Length of<br>Casing/Screen |
|----------|---------------------|--------------------|------------------------|----------------------------|
| UMP      | 40                  | 57                 | 3,190                  | 1,500/500                  |
| Hwedza   | -                   | -                  | •                      | - / -                      |
| Total    | 40                  | 57                 | 3,190                  | 1,500/500                  |

### TABLE 5-5-1 PLANNED CONSTRUCTION WORKS

Note: Drilling length is based on : 50 m for successful boreholes (40 Nos.) and 70 m for dry holes (17 Nos.)

The above work can be divided into following seven items. And, ( ) shows the name of responsible body.

# (1) Project Management:

- Coordination with related authorities, (DWD, Consultant)
- Schedule management and coordination, (Consultant, Contractor)
- Management of equipment, spare parts (Contractor)
- Construction report, arrangement of test data, (Contractor)

Other project management, (DWD, Consultant)

### (2) Construction Management:

- Control of schedule, staff and employees, (Contractor)
- Supply and storage of materials, (Contractor)
- O & M for base/site camps, (Contractor)

### (3) Site Selection:

- Pre-siting, (DWD, Consultant)
- Prospecting, arrangement of access road, (Contractor)
- Technical transfer on prospecting, (Contractor)
- Decision of site, (DWD, Consultant)

# (4) Drilling:

Preparation of construction materials, (Contractor)

- Drilling, logging, (Contractor)
- Casing installation, development, (Contractor)
- Water quality check for pH/Ec, (Contractor)
- Technical transfer on drilling, (Contractor)
- (5) Borehole Test (pumping test):

Borehole test, (DWD)

# (6) Construction of Headworks:

- Supply of handpumps, (Contractor)
- Supply of construction materials, (Contractor)
- Installation of handpumps, (DWD)
- Construction of headworks, (DWD)

# (7) Maintenance:

- Daily maintenance of equipment, (Contractor)
- Technical transfer on maintenance, (Contractor)
- Maintenance of the completed boreholes, (ZW side)

# 5 - 5 - 2 Remarkable Points on Construction

The borehole tests and the construction works for headworks of 40 boreholes to be drilled by the Japanese Contractor are to be executed by DWD, as no technical transfer is required. However, the costs on fuel, construction materials such as cement, gravel, wooden poles, etc., except form, are to be provided by the Contractor.

The remarkable point for the borehole construction works is siting. The siting work should be careful and detailed with enough flexibility in its schedule due to difficulty for development.

Finally, it is suggested that close attention should be paid to health control because the area is affected by Malaria.

# 5-5-3 Supervising Programme

This Project will be executed with the Japanese grant aid. In this case, a Japanese Consulting firm recommended by JICA will enter into contract with the DWD for the following consultant services based upon the Japanese grant aid system.

- a) Detailed Design and services on Tender
  - Preparation of detailed design and tender documents for the procurement of equipment and materials.

- Tendering on behalf of DWD and tender evaluation of the offered tenders.
- Witnessing and advising on the negotiations between DWD and the successful tenderer.
- Supervision of procurement of equipment and materials, transportation to Zimbabwe and construction works. Supervision of procurement will be done for factory inspection and of construction work for the period required for completion.
- Coordination, discussion and confirmation of selected sites with the Zimbabwean side and the Contractor.
- Other necessary consulting services.
- b) Supervision of the Construction Work

The Consultant will dispatch his resident engineer to Zimbabwe and carried out the following services during the construction period.

- Coordination and discussions with the concerned authorities of Zimbabwe.
- Discussions and confirmations on the selected site.
- Supervision of the technical transfer carried out by the Contractor.
- Control and management of the construction report, record submitted by the Contractor.

### 5-5-4 Procurement and Construction Programme

The Contractor/Supplier will conduct the following procurement of equipment and materials and the construction work required for the on-the-job training based upon the contract awarded by DWD.

There will be no difficulty in procurement of equipment and materials. The normal transportation route to Zimbabwe is to be to the Port of Durban by sea and to Harare by road through Beitbridge, even if the route will be entrusted to the Contractor:

- procurement of equipment and materials and their transportation to Harare, by the Supplier
- dispatch of staff to Zimbabwe for the construction work, by the Contractor
- execution of the construction work, by the Contractor
- on-the-job training through the construction work, the Contractor and/or the Supplier

The staff to be despatched to Zimbabwe are composed of the following engineers and/or experts.

- Contractor's representative in Zimbabwe,
- Two senior drilling engineers,
- Mechanical engineer,
- Hydrogeological engineer r geophycist.

### 5-5-5 Implementation Schedule

Based upon the construction quantities for 40 boreholes and conditions of the job sites and Japanese living conditions, the plan of the implementation schedule is formulated as follows;

### (1) Days Necessary for Drilling Works

| ' a) | for successful Boreholes,    | an an Anna an An |
|------|------------------------------|------------------|
|      | Moving in, preparation       | 1.0 day          |
|      | Drilling (Ave. depth 50 m)   | 3.5              |
|      | Logging, casing installation | 0.7              |
|      | Graveling, development       | 0.5              |
|      | Moving out, finishing up     | 0.3              |
| . :  | Total                        | 6.0              |

- 80 -

| b) | for Dry Holes,             |         |  |  |  |
|----|----------------------------|---------|--|--|--|
|    | Moving in, preparation     | 1.0 day |  |  |  |
|    | Drilling (Ave. depth 70 m) | 3.8     |  |  |  |
|    | Moving out, finishing up   | 0.3     |  |  |  |
| •  | Total                      | 5.1     |  |  |  |
|    |                            |         |  |  |  |

# (2) Days Necessary for Borehole Test

| Moving in, preparation   |       | 0.3 day |
|--------------------------|-------|---------|
| Borehole (pumping) test  | · 11. | 1.0     |
| Moving out, finishing up |       | <br>0.2 |
| Total                    |       | 1.5     |

# (3) Days Necessary for Headworks Construction

| Moving in, pump installation           | 0.5 day |
|--|---------|
| Placing of concrete                    | 1.0     |
| <u>Moving out, finishing up (test)</u> | 0.5     |
| Total                                  | 2.0     |

# (4) Working Day and Period

Working days in a year for the construction work are estimated as follows;

| •  | Work condition   | 8 hours per day (8:00 ~ 17:00)              |
|----|--|---|
| ÷. | $ \frac{1}{1 + 1} = \frac{1}{1 + 1} \left( \frac{1}{1 + 1} + \frac{1}{1 + 1} $ | 6 days per week                             |
|    |  | 14 national holidays per year               |
| -  | Climatic conditions  | 50 percent of progress rate in rainy season |
|    |  | (Dec. to Mar.)                              |

Under the above mentioned conditions, the total holidays and time loss during rainy season in a year are computed as follows;

| - | Weekly holidays         | :   | 52 weeks $	imes$ 1 day                             | - | 52 days        |
|---|-------------------------|-----|--|---|----------------|
| - | National holidays       | :   |  | = | 14 days        |
| - | Time loss in rainy seas | on: | $4 \text{ months} \times (30 - 66/12) \times 50\%$ | = | <u>49 days</u> |
|   | ·                       |     | Total  |   | 115 days       |

Thus the annual working days are estimated at 250 days (365 - 115)

| The time required for drilling :   |   |            |
|--|---|------------|
| Mobilization and preparation works   | = | 0.4 month  |
| Drilling for successful borehole   | = | 5.8        |
| (40 Nos. $	imes$ 6.0 days/(250/year) $	imes$ 12 $\div$ 2 units)                              |   |            |
| Drilling for dry boreholes   | Ħ | 2.1        |
| $(17 \text{ Nos.} \times 5.1 \text{ days}/(250/\text{year}) \times 12 \div 2 \text{ units})$ |   |            |
| Total  |   | 7.9 months |

And, necessary periods for Borehole test and Headworks construction of 40 boreholes are 2.9 and 3.8 months, respectively, these periods are shorter than the ones for drilling.

Period required for Site Selection is subject to the schedule for prospecting works, and is estimated at 1.0 month for pre-siting and about 4.0 months for prospecting works for both E-M and GEP survey.

# (2) Implementation Schedule

In the case of the Implementation schedule of the Project with Japanese grant aid, the Project schedule shall be divided into two stages due to the restriction of the single fiscal year system of the Government of Japan. The components of each stage are as follows;

| - First Stage  | : | Procurement of equipment and materials. |
|----------------|---|---|
| - Second Stage | : | Siting of the boreholes,                |
|                |   | Borehole construction for 40 boreholes, |
|                |   |   |

On-the-job training for siting, drilling and operation and maintenance of the equipment.

The schedule for the first stage will take about four (4) months from the signing of E/N, after the Consultant agreement, detailed Design and Tendering, to the Supplier Contract. The Supplier will commence his duties specified in the contract documents, after the contract becomes in effective. It will take another six (6) months for the procurement and manufacturing of the equipment and materials, and about 2.5 months for ocean and inland transportation. The equipment will arrive in Harare and will follow the formalities such as registration and/or insurance contract(s) required in Zimbabwe, and afterwards the equipment and materials to be used for the construction will be transported to the job site.

The schedule for the second stage will also take four (4) months from the signing of second-stage E/N to the contractor's contract through the consultant's contract, detailed design and tendering. E/N will be exchanged in the following fiscal year from E/N for the first stage. The construction works will start 6 months after the E/N and it will take about nine months to compete borehole construction including preparation, pre-siting works, geophysical prospecting, drilling, headworks construction and finishing up of the equipment and handing over of the completed facilities and used equipment and materials.

The above implementation schedule is shown in Figure 5-5-1.

FIGURE 5-5-1 IMPLEMENTATION SCHEDULE FOR THE PROJECT

| 1 2 3 4 5 6 7 8 9 10 11 12   Stage-1: (Detailed Design and<br>Detailed Design and<br>Tendering (Detailed Design) (Inspection of<br>Equipment) (Inspection of<br>Equipment)   Precurement of<br>Equipment and<br>Material (About 4 Months) (Svaluation and Contract Award) (Inspection of<br>Equipment)   Precurement of<br>Equipment and<br>Material (About 9 Months) (Precurement of Materials) (Inspection of<br>Equipment)   Sage 2: (Detailed Design and<br>Construction Works (About 9 Months) (Precurement of<br>Betailed Design and<br>Construction Works (Inhard Transport)   Construction Works (by ZW side) (Sting) (Drilling)   (by ZW side) (by ZW side) (Interview)   |      |                     |        |                |                     |                 | Number of Months | [ Months   |               |           |            |                   |            |           |
|--|------|---------------------|--------|----------------|---------------------|-----------------|------------------|------------|---------------|-----------|------------|-------------------|------------|-----------|
| etailed Design and<br>etailed Design and<br>endering<br>etailed Design and<br>etailed Design and<br>modering<br>(About 4 Months)<br>courrement of<br>(About 9 Months)<br>(About 9 Months)<br>(About 9 Months)<br>(About 9 Months)<br>(About 9 Months)<br>(About 4 Months)<br>(About 4 Months)<br>(About 4 Months)<br>(About 4 Months)<br>(About 4 Months)<br>(About 9 Months)<br>(Abou   |      |                     | prof.  |                | 4                   | or<br>          | 9                | 2          | 8             | 6         | 10         | 11                | 12         | <b>.</b>  |
| etailed Design and<br>etailed Design and<br>endering<br>modering<br>(About 4 Months)<br>(Procurement of<br>quipment and<br>quipment and<br>deterial<br>(About 9 Months)<br>(About 4 Months)<br>(Detailed Design)<br>(Detailed Design)<br>(Detailed Design)<br>(Detailed Design)<br>(Detailed Design)<br>(Detailed Design)<br>(Detailed Design)<br>(About 4 Months)<br>(About 4 Months)<br>(About 4 Months)<br>(About 4 Months)<br>(About 9 Morths)<br>(About 9 Morths)<br>(About 9 Morths)<br>(About 9 Morths)<br>(Detailed Design)<br>(Detailed Design)<br>(By ZW side)<br>(By ZW side)<br>(About 9 Morths)<br>(About 9 Morths)<br>(Detailed Design)<br>(Detailed Design)<br>(By ZW side)<br>(By ZW side)<br>(About 9 Morths)<br>(About 9 M | Stag | e-1:                |        |                |                     |                 |                  |            |               |           |            |                   |            |           |
| etailed Design and<br>andering (Tendering)<br>(About 4 Months) (Evaluation and Contract Award)<br>(About 4 Months) (Recurement of Materials)<br>courement of<br>quipment and<br>aterial (About 9 Months) (Crendering)<br>etailed Design and<br>(About 9 Months) (Bvaluation and Contract Award)<br>(About 4 Months) (Bvaluation and Contract Award)<br>(About 4 Months) (Bvaluation and Contract Award)<br>(About 9 Months) (Bvaluation and Contract Award)<br>(About 9 Months) (Bvaluation and Contract Award)<br>(About 9 Months) (About 9 Months) (About 9 Months)  |      |                     |        | (Discussion    | esign)<br>s with DW | ···· 6          |                  |            |               |           |            |                   |            |           |
| etarled Design and<br>indering (About 4 Months) (Evaluation and Contract Award)<br>(About 4 Months) (Procurement of Materials)<br>courrement of<br>quipment and<br>quipment and<br>(Procurement of Materials)<br>(Procurement of Equipment<br>(Procurement of Materials)<br>(About 9 Months) (Prevaluation and Contract Award)<br>etailed Design and<br>etailed Design and<br>(About 4 Months) (Evaluation and Contract Award)<br>etailed Design and<br>(About 4 Months) (Evaluation and Contract Award)<br>(About 4 Months) (Siting)<br>(by ZW side) (by ZW side)<br>(by ZW side) (by ZW side) (by ZW side)   |      |                     |        |                | E                   | endering)       |                  | •••••      |               |           |            |                   | • •        |           |
| (About 4 Months) (Procurement of Materials)   courrement of<br>quipment and<br>aterial (Procurement of Materials)   (courrement of<br>quipment and<br>aterial (Procurement of Materials)   (About 9 Months) (Detailed Design)   (About 9 Months) (Evaluation and Contract Award)   (About 4 Months) (Siting)   (by ZW side) (by ZW side)   (by ZW side) (by ZW side)   | -    | Detailed Design and |        |                | (B)                 | valuation a     | and Contra       | ict Award) |               | •••••     | ( <b>1</b> | :<br>             |            | V         |
| courrement of<br>quipment and<br>aterial (Procurement of Materials)   courrement of<br>quipment and<br>aterial (Procurement of Equipment<br>(About 9 Months)   (Detailed Design and<br>etailed Design and<br>etailed Design and<br>(About 4 Months) (Evaluation and Contract Award)   (Bvaluation and Contract Award) (Siting)   (Bvaluation and Contract Award) (Siting)   (by ZW side) (by ZW side)   (by ZW side) (Siting)  |      | 9111 DD115 T        | (Abou  | it 4 Months)   |                     |                 |                  |            |               |           | Equ        | pector of ipment) |            | ł         |
| quipment and<br>aterial (Procurement of Equipm<br>(About 9 Months) (Procurement of Equipm<br>(Sea T   (About 9 Months) (Detailed Design)   (About 9 Months) (Tendering)   etailed Design and<br>endering (Detailed Design)   (About 4 Months) (Evaluation and Contract Award)   (About 4 Months) (Siting)   (by ZW side) (by ZW side)   (by ZW side) (by ZW side)   (by ZW side) (About 9 Months)  |      | Drocurement of      |        | :<br>Procureme | nt of Mater         | ials)           |                  |            |               |           |            |                   | <br>       |           |
| aterial (About 9 Months) (Chetailed Design) etailed Design and (Discussions with DWD) (Tendering) (Cheparation) (Evaluation and Contract Award) (About 4 Months) (Evaluation and Contract Award) (About 4 Months) (Siting) (Siting) (by ZW side) (bout 9 Morths) (About  |      | Equipment and       |        |                |                     |                 |                  | (Procure)  | ment of E     | quipment  | ~          |                   |            |           |
| (About 9 Months) (About 9 Months)   etailed Design and (Detailed Design)   etailed Design and (Discussions with DWD)   etailed Design and (Tendering)   (About 4 Months) (Evaluation and Contract Award)   onstruction Works (by ZW side)   (by ZW side) (by ZW side)   (by ZW side) (by ZW side)  |      | Material            |        |                |                     |                 |                  |            |               | (Sea Tran | sport)     |                   | . i        |           |
| etailed Design and<br>etailed Design and<br>etailed Design and<br>indering<br>indering<br>indering<br>(About 4 Months)<br>(Preparation)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(About 9 Months)  |      |                     | (About | t 9 Months)    |                     |                 |                  |            |               |           | (Inland 1  | [ransport)        |            |           |
| esign and<br>(About 4 Months)<br>(About 4 Months)<br>(Bvaluation and Contract Award)<br>(Bvaluation and Contract Award)<br>(Bvaluation and Contract Award)<br>(Bvaluation and Contract Award)<br>(Bvaluation and Contract Award)<br>(About 4 Months)<br>(by ZW side)<br>(by ZW side)<br>(About 9 Months)   | Stag | e-2 :               |        | (Detailed D    | sign)               |                 |                  |            |               |           |            |                   |            |           |
| esign and<br>(About 4 Months)<br>(About 4 Months)<br>(Evaluation and Contract Award)<br>(Preparation)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)  |      |                     |        | (Discussion)   | s with DWI          | ີດ <sup>:</sup> |                  |            |               |           |            |                   |            |           |
| on Works (About 4 Months) (About 4 Months) (Siting) (Siting) (Siting) (by ZW side) (by ZW side) (by ZW side) (by ZW side) (About 9 Morths)   |      | Detailed Design and |        |                | (T,                 | sndering)       |                  |            |               |           |            |                   |            |           |
| (About 4 Months)<br>(Preparation)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)  | .'   | Tendering           |        | ••••           | (B)                 | /aluation a     | nd Contra        | ct Award)  | ener<br>State |           |            |                   |            |           |
| (Preparation)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)  |      |                     | (About | t 4 Months)    |                     |                 |                  |            |               |           |            |                   |            |           |
| (by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(by ZW side)   |      |                     |        | (Prenaration)  |                     |                 |                  |            |               |           |            |                   |            | un genete |
| (by ZW side)<br>(by ZW side)<br>(by ZW side)<br>(About 9 Morths)   |      |                     |        |                |                     |                 | :<br>Siting      |            |               |           |            |                   |            |           |
| (by ZW side)<br>(by ZW side)<br>(About 9 Morths)   |      | Construction Works  |        | ••••           |                     |                 |                  |            |               |           | (Drilling) |                   |            |           |
|  |      |                     |        |                | -                   | -               |                  |            |               |           |            |                   |            |           |
|  |      |                     |        | (by ZW SIGE)   |                     |                 |                  |            |               |           |            | 3                 |            |           |
|  |      |                     |        | (by ZW side)   | · · ·               | <br>            |                  |            | U             |           | (Headwo    | irks)             |            |           |
|  |      |                     | (Abou  | t 9 Morths)    |                     | 1.              |                  |            |               |           | (Inspecti  | :<br>ion, hand-c  | ;<br>over) |           |
|  |      |                     | · ·    |                |                     |                 |                  |            |               |           |            |                   |            | 7         |

- 84 -

# 5 - 6 Rough Cost Estimate of the Project

### (1) Undertakings by both Governments

In the case of implementation of the Project with Japanese grant aid, the undertakings of the Governments of Japan and Zimbabwe are as follows;

a) Undertakings of the Government of Japan

Procurement, transport and handing-over of the equipment and materials described in the basic plan of equipment and materials, section 5-3-3.

Construction of Borehole Facilities, aiming at technical transfer through on-the-job training by the construction work equivalent to 40 successful boreholes.

On-the-job training to Zimbabwean staff.

Handing-over of the equipment and remaining materials after completion of the construction work.

b) Undertakings of the Government of Zimbabwe

- To confirm the proposed borehole sites and execute the pre-siting together with the users.
- To secure the necessary number of Zimbabwean personnel for Project implementation and to bear all expenses.
- To secure the necessary number of Zimbabwean staff to be rendered on-the-job training and to bear all expenses.

- To execute the construction works such as borehole test, headworks, pump installation, other than those to be executed by the Japanese Contractor.

To procure all the equipment and materials necessary for the Project implementation and bear all expenses other than those to be borne by Japanese grant aid.

To provide the workshop facilities to the Japanese Contractor when required.

- To acquire land for Base camp, site camp etc., and rights-of-way for the Project works.
- To ensure tax exemption and customs clearance at port in Zimbabwe to facilitate the import of equipment and materials and the local equipment and materials for the Project implementation.
- To ensure the exemption from taxes and duties on all personal goods, equipment and effects which are to be brought into Zimbabwe by Japanese personnel related to the Project.
- To ensure the safety of Japanese personnel related to the Project.
- To accord Japanese personnel related to the Project such facilities as may be necessary for their entry and/or reentry into Zimbabwe and stay therein for the Project.
- To bear the bank commissions based upon the banking arrangements.
- To maintain the completed facilities.
- To operate and maintain the equipment supplied under the Project.

### (2) Rough Cost of the Project

The Project implementation costs for Zimbabwean side's works are roughly estimated as follows;

a) Conditions of cost Estimation

| 1) | Date of Estimate | : | October 1993       |
|----|------------------|---|--------------------|
| 2) | Exchange Rate    |   | 1  US = 6.439  Z\$ |
| 3) | Project Period   | : | 2 Stages           |

b) Estimated Costs

Costs for the Construction of 360 Boreholes;

| - | Siting           | • | $360 \times Z$ \$1,000  | = 360,000   |
|---|------------------|---|-------------------------|-------------|
|   | Successful Holes |   | $360 \times Z$25,000$   | = 9,000,000 |
| - | Dry Holes        | • | $154 \times Z$ \$10,000 | = 1,540,000 |
|   | Sub-total        |   |                         | 10,900,000  |

| - | 10% Contingency    | : | 1,090,000     |  |
|---|--------------------|---|---------------|--|
| - | 15% Price Increase | : | 1,800,000     |  |
|   | Total              |   | Z\$13,790,000 |  |

Note: Success rate is estimated at 70% for the overall Project

### Maintenance Costs:

The cost paid by the DDF for the 325 Boreholes and Deep Wells in 1992 was Z\$116,300 (Z\$358 per borehole). The additional costs for the Project is proportionally calculated as follows, however all maintenance costs for Boreholes and Deep Wells are to be paid by the users before completion of this Project, except supervising and/or monitoring costs which will be continuously responsible of the DDF.

 $400 \text{ boreholes} \times Z$  = \$143,200

# CHAPTER 6. PROJECT EVALUATION AND CONCLUSION

### 6 - 1 Project Evaluation

The Project is a part of the "Integrated Rural Water Supply and Sanitation (IRWSSP)" which is on going in UMP and Hwedza districts in Mashonaland East Province in Zimbabwe. It has a target for completion in fiscal 1996. The Project shares procurement of the Equipment and Materials necessary for the construction of 400 boreholes and the Construction Work for 40 boreholes ensuring the On-the-Job Training for the Zimbabwean Counterparts in the IRWSSP which covers the construction work for a total of 432 boreholes and 267 wells.

The direct benefits of the Project is composed of the following factors;

- To achieve the project target, to provide villagers with 30 lit./day/person of safe water through the construction of one (1) borehole for every two hundred and fifty (250) persons.
- (2) To suppress diseases owing in unsafe drinking water, and
- (3) To utilize the labour force which is otherwise utilized in fetching water for other activities.

The population benefiting from the construction of 400 boreholes of this Project is estimated below, with the an estimate of 250 persons per borehole. This population is equivalent to 64 percent of the area's population, according to the 1992 census.

|          | P: Population, | Present Condition, | Benefited Po | pulation by the Projec |
|----------|----------------|--------------------|--------------|------------------------|
| District | 1992           | P: rate            | B/H No.      | P: rate                |
| UMP      | 86,302         | 15,500 (18%)       | 280          | 70,000 (99%)           |
| Hwedza   | 69,981         | 32,000 (46%)       | 120          | 30,000 (89%)           |
| Total    | 156,283        | 47,500 (30%)       | 400          | 100,000 (94%)          |

Note: Present conditions: persons currently served by safe water and the rate.

Furthermore, many more people will be benefited by further borehole construction after the Project, which will be carried out by the DWD's Staff having learnt the technical knowledge through the on-the-job training using equipment supplied for this Project as in Phase-1 and 2 Projects.

For past experience, it is justifiable to believe that the completed boreholes will be properly maintained. The maintenance costs for the completed boreholes are estimated at Z\$143,200, which is scheduled to be transferred to the users in the near future. This new system, maintained by the users, is a familiar system to other African countries. This new scheduled will be carried out successfully due to the eager efforts of the Government of Zimbabwe.

## 6-2 Conclusions and Recommendations

## (1) Conclusions

The conclusions reached as a result of the field survey in Zimbabwe, the discussions with DWD and the basic design study in Japan are as follows.

From the following conclusions and the facts described in the previous section 6-1, it is considered that grant aid assistance for the Project is justifiable from both objective and political points of view.

- a) Construction of 400 boreholes by the Project is a key part of the overall project for the Integrated Rural Water and Sanitation (IRWSSP) being executed in Zimbabwe. IRWSSP is an on-going National Project. The IRWSSPs for five (5) districts have been completed and are on-going in twenty seven (27) districts. After the completion of IRWSSP, Zimbabwe can reach the target described in the Master Plan Report which has the aim of constructing one borehole for every 250 persons in rural areas.
- b) The population directly benefiting from by the construction of the Project's 400 boreholes is estimated to be 100,000 people, equivalent to 64 percent of the population in the Project Area. Furthermore, after

this Project, the DWD will continue the IRWSSP using the equipment supplied under this Project through its lifetime. In this way many more people will be benefited.

- c) The improvement of rural water supply facilities is the basis of improvement of the lives of the rural people, so the inhabitants can experience a healthy life and improved economic conditions by utilizing the labour force for other activities.
- d) The Project has already been started by the Government of Zimbabwe, however there are another 370 remaining boreholes which will require two sets of equipment to achieve the Project by the target year of 1996.
- e) The external assistance for IRWSSP is composed of NORAD, Dutch, KFW, etc. at the moment, and the EC and Great Britain will join in the near future.
- f) It has been confirmed by the study team that the equipment supplied under the past Projects is properly and satisfactorily maintained by the DWD.

### (2) Recommendations

The following can be recommended to the Government of Zimbabwe as a result of the basic design study for the Project.

- a) The Project Area will achieve its target by the completion of this Project. However, further efforts in this sector will be continuously required along with monitoring of the users how they utilize the completed boreholes.
- b) To ensure the budget to be used for the equipment supplied under the Project for further execution of the IRWSSP in other districts.

c) The maintenance of the completed boreholes is the responsibility of the DDF at the moment. However, in the near future this maintenance system will be transferred to the users including the payment for the pump-minders and spare parts. To assure this planning, it would be required to make periodic inspections by the Government and to consider assistance if it is deemed necessary.

•

- 91 -

Appendix - 1:

| In Charge  | Name  | Office/Firm                                 |
|--|---|---|
| Team Leader  | Hiroshi NISHIDA   | Grant Aid Division,<br>Economic Cooperation |
| an<br>Marina ang sang sang sang sang sang sang san | and a second second<br>Second second | Bureau, Ministry of Foreign<br>Affairs      |
| Chief of the Consultant                            | Yoshio MATSUMURA  | Sanyu Consultants Inc.                      |
| Hydrogeology                                       | Izumi KATO  | Sanyu Consultants Inc.                      |
| Equipment Planning                                 | Shin-ichi ARAI  | Sanyu Consultants Inc.                      |

# MEMBER LIST OF THE STUDY TEAM

.

۸-1

## Appendix - 2:

## LIST OF OFFICIALS CONTACTED BY THE TEAM

Embassy of Japan,

Mr. Haruo OKAMOTO, Minister Mr. Takumi OHASHI, Counselor

J. O. C. V. Office,

Takeshi INADA, Director Hosui SASAKI, Coordinator

Ministry of Finance, Economic Planning and Development (MFEPD): Mr. O. M. MATSHALAGA, Under Secretary

Domestic and International Finance

Ministry Land, Agriculture and Water Development (MLAWD): Mr. K. LANDING, Director for Department of Water Development, (DWD)

Mr. V. CHOGA, Deputy Director, Operations, (DWD) Mr. G. NHUNHAMA, Chief Hydrogeologist, (DWD) Mr. S. SUNGURO, Hydrogeologist, (DWD) MRS. O. ZIMBA, Hydrogeologist, (DWD)

Provincial Water Engineer's Office (DWD):

Mr. CHATORA, Provincial Water Engineer, Mr. F. JASPERS, Ares Engineer for Mashonaland Mr. J. RASHIRAYI, Drilling Superintendent Mr. D. MUSHANDU, Executive Officer, Administration

Mashonaland East Provincial Administrator's Office: Mr. J. MURWISI, Deputy Provincial Administrator Mr. MEDA, Provincial Administrative Officer

# Mr. D. GRONINGEN, Provincial Water and Sanitation Coordination Advisor

Mr. D. CHINYOWA, Provincial Officer of DDF (District Development Fund)

Miss. JARAWAZA, Deputy Provincial Officer of DDF Mr. B. MACHE, Principal Agricultural Extension Officer of AGRITEX

Provincial Medical Director's Office, Ministry of Health: Mr. MANGWADU, Provincial Environmental Health Officer

Zvataida (UMP) District Administrator's Office:

Mr. C. GATSI, District Administrator

Mr. J. MAKUNDE, Administrative Officer

Mr. N. NYAMAZANA, Supervisor of Water Division of DDF

Mr. ZINYAMA, Field Officer of DDF

Mr. E. GUZHA, Principal Environmental Health Officer for UMP Water and Agriculture Project

Hwedza District Administrator's Office:

Mr. C. NDARUWA, District Administrator Mr. A. T. NGORIMA, Water Officer of DDF Appendix - 3 :

# MINUTES OF DISCUSSIONS BASIC DESIGN STUDY FOR IMPROVEMENT OF RURAL WATER SUPPLIES IN MASHONALAND EAST PROVINCE IN THE REPUBLIC OF ZIMBABWE

ราว การการการให้ 19 ก็ไม้ได้การการสารสู้การสู่สารที่สารที่สุดสู่สารสู่สารความ เกิดการการที่สี่สี่สุดสุดสู่มนุษณ

At the request of the Government of the Republic of Zimbabwe, the Government of Japan have agreed to conduct Basic Design investigations of the Project for the Improvement of Rural Water Supplies in the Mashonaland East Province (hereinafter referred to as "the Project"), and the latter has entrusted the study to the Japan International Cooperation Agency (JICA).

JICA sent a study team known as the Basic Design Study Team headed by Mr. Hiroshi NISHIDA, from the Japanese Ministry of Foreign Affairs, to the Republic of Zimbabwe during the period from the 24th August, 1993 to the 23rd September, 1993.

The Basic Design Study Team held discussions with the relevant officials of the Government of the Republic of Zimbabwe and conducted a field survey in the study area.

As a result of the discussions and field survey, both parties have confirmed the main items described in the attached sheets. The Team will proceed to prepare the Basic Design Study report.

Harare, 1st September, 1993.

西田寛


Mr. Hiroshi NISHIDA. Leader, Basic Design Study Team, JICA

Mr.K. LANDING.

Mr.K. LANDING, Director of Department of Water Development, (MLAWD)

Ministry of Finance





### ATTACHMENT

#### 1. Objective

The objective of the Project is to provide the necessary  $equ_{ip}$ , ment, materials and services in order to accelerate the rural water supply programme in certain parts of the Mashonaland East Province in the Republic of Zimbabwe.

### 2. Project Area

The Project Area is composed of the following Communal Lands (C.L.) in the Mashonaland East Province.

- 1) Uzumba C.L. (Zvataida District)
- 2) Maramba C.L. (Zvataida District)
- 3) Pfungwe C.L. (Zvataida District)
- 4) Hwedza C.L. (Hwedza District)

### 3. Executing Agency

The executing agency is the Department of Water Development (DWD) in the Ministry of Lands, Agriculture and Water Development of the Government of Zimbabwe.

### 4. Items requested by the Government of Zimbabwe

After discussions with the Basic Design Study Team, the following items were requested by the Government of Zimbabwe:

- (1) Provision of Equipment and Materials for borehole construction.
- (2) Provision of services for the implementation of the project

Provisional details of the items required are listed in ANNEX-L

The final components of the Project will be determined by the Basic Design Study Team, after further studies and consultation with officials of the Departmnet of Water Development.

## 5. Japanese Grant Aid System

- (1) The Government of Zimbabwe has understood the Japanese Grant
- Aid System as explained by the Basic Design Study Team.
  - (2) The Government of Zimbabwe will take the necessary measures, described in ANNEX-II for the smooth implementation of the Project, on condition that the Grant Aid Assistance by the Government of Japan is extended to the Project.

### 6. Schedule of the Study

- The Consultant will continue field survey work in Zimbabwe until September 23, 1993.
- (2) Based on the Minutes of Discussions and technical examination of the study results, JICA will complete the final report and send it to the Government of Zimbabwe by February, 1994.

### ANNEX-I.

The following items have been requested by the Government  $_{\rm Of}$  Zimbabwe.

# Procurement of Equipment and Materials

| (1)  | truck-mounted top-head-drive rotary drilling rig;  | 2    | units |
|------|--|------|-------|
| (2)  | standard accessories and tools for the above;      | 2    | lots  |
| (3)  | high-pressure air-compressor;                      | 2    | units |
| (4)  | cargo truck with 4-ton crane (4x4);                | 4    | units |
| (5)  | break-down recovery truck                          | . 1  | unit  |
| (6)  | pick-up truck (4x4);                               | 4    | units |
| (7)  | station wagon (4x4);                               | 2    | units |
| (8)  | geophysical equipment;                             | 2    | lots  |
| (9)  | borehole test equipment;                           | 2    | lots  |
| (10) | radio-telephone system;                            | 2    | lots  |
| (11) | drilling supporting equipment;                     | 2    | lots  |
| (12) | trailer-mounted mobile workshop with necessary     | 2    | lots  |
|      | equipment and tools;                               |      |       |
| (13) | hand pumps;  | 400  | units |
| (14) | submersible-motor pump with diesel generator;      | 3    | units |
| (15) | spare parts for the above equipment                | 2    | lots  |
|      | good enough for 3 years operation;                 |      |       |
| (16) | plastic casing and screen pipes for 100 B/H        | 1    | lot   |
|      | and steel casing for 300 B/H;                      |      |       |
| (17) | drilling agent;                                    | 1    | lot   |
| (18) | spare parts for the equipment procured under       | 1    | lot   |
|      | the Japanese Grant Aid for the Rural Water         |      | 4     |
|      | Supplies Project (Phase 2)                         |      |       |
|      |  |      |       |
| 2.   | Services necessary for the construction of 40 bore | oles | 3     |
|      |  |      |       |

2. Services necessary for the construction of 40 boreholes in the Project Area, including on-the-job training of Zimbabwean staff for siting, drilling and maintenance of drilling equipment. ANNEX-II.

S

s

S

S

S

Ś

S

Necessary measures to be taken by the Government of Zimbabwe in the event that Japanese Grant Aid is extended to the Project.

- 1. To provide data and information necessary for the Project.
- 2. To secure land for the sites of the Project.
- 3. To clear the sites prior to commencement of the construction.
- 4. To bear commissions to the Japanese foreign exchange bank to execute the banking Services based upon the Banking Arrangement.
- 5. To ensure prompt unloading and customs clearance at port(s) of disembarkation in Zimbabwe and facilitate internal transportation therein of the products purchased under the Grant.
- 6. To exempt Japanese nationals from customs duties, internal taxes and other fiscal levies which may be imposed in Zimbabwe with respect to the supply of the products and services under the Verified Contract(s).
- 7. To accord Japanese nationals whose services may be required in connection with the supply of the products and the services under the Verified Contract(s), such facilities as may be necessary for their entry into Zimbabwe and stay therein for the performance of their work.
- 8. To assign the necessary staff for operation and maintenance of the equipment purchased under the Grant.
- 9. To maintain and use properly and effectively the equipment and materials purchased and facilities constructed under the Grant.

10. To bear all the expenses other than those to be borne by the Grant Aid, necessary for construction of the facilities as well as for the transportation and the installation of the equipment in the Project area.

# Appendix - 4:

## FIELD SURVEY ITINERARY

| Da         | ite         | Day  | Activities   |
|------------|-------------|------|--|
| Aug.       | 24          | Tue. | Arrived in Harare. Courtesy call on Embassy of Japan, Ministry of<br>Finance and Department of Water Development of (DWD) in the<br>Ministry of Lands, Agriculture and Water Development (MLAWD) |
| на 14<br>- | 25          | Wed. | Discussion on Inception Report with DWD  |
|            | 26          | Thu. | Reconnaissance survey guided by DWD Officers for UMP   |
|            | 27          | Fri. | Reconnaissance survey guided by DWD Officers for Hwedza  |
|            | 28          | Sat. | Data arrangement and preparation works for further study   |
| 2.87       | 29          | Sun. | Inner meeting  |
|            | <b>30</b> ) | Mon. | Field survey for Hwedza  |
| at Made    | 31          | Tue. | Discussion on Minutes  |
| Sep.       | 1           | Wed. | Exchanged the Minutes of Discussion  |
|            | 2           | Thu. | Leader left Harare for Tokyo<br>Meeting with DWD Head Office   |
|            | 3           | Fri. | Field survey for Pfungwe C.L.  |
|            | 4           | Sat. | Office work  |
|            | 5           | Sun. | Inner meeting  |
|            | <b>6</b> :  | Mon. | Field survey for UMP<br>Meeting with DDF District Office and Data collection for UMP   |
|            | 7           | Tue. | en e   |
|            | 8           | Wed. | Field survey for UMP<br>Meeting with DDF District Office and Data collection for Hwedza  |
|            | 9           | Thu. | Field survey for UMP<br>Meeting with DDF District Office and Data collection for Hwedza  |
|            | 10          | Fri. | Meeting with DWD Head Office<br>Data collection for the Province   |

| Date    | Day  | Activities  |
|---------|------|---|
| Sep. 11 | Sat. | Inspection for Boreholes constructed under Phase-1 Project in<br>Chilimanzi C.L. in Midlands Province |
| 12      | Sun. | Returned to Harare  |
| 13      | Mon. | Meeting with Provincial Office of DDF<br>Field survey for Hwedza                                      |
| 14      | Tue. | Meeting with DWD Head Office<br>Field survey for Hwedza   |
| 15      | Wed. | Inspection of Drilling Rig under Phase-2 Project in Gokuwe District in<br>Midlands Province           |
| 16      | Thu. | Meeting with Provincial Agritex Office and Provincial Medical Director<br>Office                      |
| 17      | Fri. | Meeting with District Administrator Office in Hwedza and office work                                  |
| 18      | Sat. | Office work   |
| 19      | Sun. | Inner meeting   |
| 20      | Mon. | Meeting with DWD Head Office and supplemental Field Survey  |
| 21      | Tue. | - do -  |
| 22      | Wed. | - do -  |
| 23      | Thu. | Courtesy call on Embassy/DWD. Left Harare to Tokyo  |

A-11

• • •

# Appendix - 5 (5 - 1):

| No.      | Location/Name       | Grid Refer           | ence       | Type of      |
|----------|---------------------|----------------------|------------|--------------|
| 190.     | Location/Ivame      | S. Latit. E. Longit. | Grid Ref.  | Water Source |
| Pf-1     | near KAFURA Sch.    | 16-51-36, 32-15-37   | VS 220 359 | Pvt. Well    |
| Pf - 2   | NYANZOU Sch.        | 16-46-57, 32-18-16   | 259 446    | B/H          |
| Pf-3     | NYANZOU Clinic      | 16-46-50, 32-18-56   | 269 447    | Deep Well    |
| Pf-4     | KAFURA Sch.         | 16-51-16, 32-15-39   | 212 366    | B/H          |
| Pf-5     | KAFURA Clinic       | 16-46-57, 32-18-16   | 207 378    | B/H          |
| Pf-6     | MAGUDA Sch.         | 16-55-59, 32-09-33   | 100 277    | B/H          |
| Pf - 7   | near DINDI Mission  | 16-52-32, 32-06-09   | 045 342    | B/H          |
| Pf-8     | near SOWA Sch.      | 17-00-10, 32-06-15   | 046 200    | B/H          |
| Ma - 1   | near BORERA Missi.  | 17-01-37, 31-59-19   | US 924 174 | B/H          |
| Ma - 2   | BORERA Mission      | 17-01-26, 31-58-46   | 914 177    | Shallow Well |
| Ma - 3   | BORERA Sec.Sch.     | 17-01-19, 31-58-12   | 907 179    | B/H          |
| Ma - 4   | GOYU Township       | 17-00-46,3 2-01-30   | 968 189    | В/Н          |
| Ma - 5   | GOYU Sch.           | 17-00-40, 32-01-53   | 967 191    | B/H          |
| Ma - 6   | SAPARANYAMBUYA Sch. | 17-07-28, 32-02-05   | 972 065    | B/H          |
| Ma - 7   | MUTAWATAWA B.C.     | 17-06-57, 31-58-41   | 913 075    | B/H          |
| Uz - 1   | KATIYO B.C.         | 17-13-05, 31-50-36   | UR 770 961 | Deep Well    |
| Uz - 2   | MASANHI Sec.Sch.    | 17-24-20, 31-58-50   | UR 917 755 | B/H          |
| Uz - 3   | MUGABE Sec.Sch.     | 17-22-53, 31-56-50   | UR 822 783 | B/H          |
| Uz - 4   | MANYIKA B.C.        | 17-21-28, 31-54-27   | UR 840 807 | B/H          |
| Uz - 5   | UZUMBA High Sch.    | 17-21-50, 31-53-42   | UR 827 799 | B/H          |
| Uz - 6   | MATSENGE Sch.       | 17-19-58, 31-51-56   | UR 788 834 | B/H          |
| Uz - 7   | DDF Office          | 16-46-57, 32-18-16   | UR 755 907 | Deep Well    |
| Uz - 8   | MORIS Sch.          | 17-19-43, 31-48-40   | UR 736 838 | B/H          |
| Uz - 9   | NAKIWA B.C.         | 17-22-24, 31-48-04   | UR 727 789 | Deep Well    |
| Uz - 10  | MAGUNJE Sch.        | 17-24-05, 31-47-27   | UR 718 757 | B/H          |
| Uz - 11  | CHITIMBE Sch.       | 17-26-42, 31-47-04   | UR 713 710 | B/H          |
| Uz - 12  | NYAGANDE Sch.       | 17-09-24, 31-51-06   | US 777 029 | B/H          |
| Uz - 12' | near NYAGANDE Sch   |                      |            | Deep Well    |
| Uz - 13  | NYAGANDE Campsite   | 17-09-23, 31-50-48   | US 772 029 | B/H          |
| Uz - 14  | CHIKUHWA Sch.       | 17-12-33, 31-50-57   | UR 776 970 | Deep Well    |
| Uz - 15  | Village             | 17-12-03, 31-50-04   | UR 761 980 | Deep Well    |
| Úz - 16  | near DDF Office     | 17-16-06, 31-49-45   | UR 755 905 | Deep Well    |

## LIST OF BOREHOLES AND WELLS INSPECTED (1/2)

|        | T (* 757           | Grid Reffe           | rence      | Type of      |
|--------|--------------------|----------------------|------------|--------------|
| No.    | Location/Name      | S. Latit. E. Longit. | Grid Ref.  | Water Source |
| H - 1  | CHIGWEDERE Sch.    | 18-41-4, 31-34-23    | UQ 495 336 | В/Н          |
| H - 2  | near CHIGWEDERE    | 18-38-48, 31-35-42   | 519 386    | B/H          |
| H-3 ·  | GARABA Store       | 18-43-22, 31-32-01   | 454 293    | B/H          |
| H - 4  | RAMBANAPASI Sch.   | 18-44-03, 31-32-57   | 471 280    | B/H          |
| H-5    | MUREMBA Dam        | 18-37-57, 31-35-46   | 519 393    | B/H          |
| H - 6  | MARATA Sch.        | 18-38-39, 31-36-57   | 540 381    | B/H          |
| H-7    | MKUNDWA Sch.       | 18-38-39, 31-36-57   | 568 362    | B/H          |
| H-8    | NHEKAIRO B.C       | 18-39-26, 31-41-36   | 622 366    | B/H          |
| H - 9  | MATSINE Sch.       | 18-39-57, 31-44-05   | 666 359    | B/H          |
| H - 10 | MAKWARIMBA         | 18-41-04, 31-45-15   | 338 686    | B/H          |
| H-11   | DENDENYORE         | 18-41-31, 31-41-56   | 330 628    | B/H          |
| H - 12 | ST.MARFS Mission   | 18-43-30, 31-40-41   | 606 292    | B/H          |
| H - 13 | ST.AUGUSTINE Sch   | 18-47-21, 31-39-38   | 447 220    | B/H          |
| H - 14 | MUKWANA Sch.       | 18-49-08, 31-43-06   | 649 187    | B/H          |
| H - 15 | CHIGONDO B.C.      | 17-06-57, 31-58-41   | 646 140    | B/H          |
| H - 16 | MAGUNI Sch         | 18-54-03, 31-41-36   | 623 098    | B/H          |
| H - 17 | ST.JOSEPH Sch.     | 18-56-21, 31-43-28   | 056 657    | B/H          |
| H - 18 | ST.PETER's Sch.    | 18-41-33, 31-46-11   | 702 329    | B/H          |
| H - 19 | ZVIDENDE Dip       | 18-42-57, 31-47-26   | 725 303    | B/H          |
| H - 20 | GOTO near St.Annes | 18-44-03, 31-49-21   | 759 283    | Deep Well    |
| H - 21 | MORIS Bridge       | 18-44-14, 31-50-00   | 377 280    | River        |
| H - 22 | CHISASIKE B.C.     | 18-46-28, 31-49-18   | 758 239    | B/H          |
| H - 23 | St.STEPHEN's Sch.  | 18-46-10, 31-51-50   | 802 249    | B/H          |
| H - 24 | St.BARNABAS Sch.   | 18-49-01, 31-49-28   | 761 191    | B/H          |
| H - 25 | Village            | 18-49-44, 31-49-47   | 766 178    | B/H          |
| H - 26 | St.JOHN's Sch.     | 18-51-34. 31-49-26   | 762 144    | B/H          |
| H - 27 | St.MATHIAS Sch.    | 18-50-21, 31-47-32   | 728 148    | B/H          |
| H - 28 | MUKUMBA B.C.       | 18-52-31, 31-49-06   | 756 127    | B/H          |
| H - 29 | CHIHAVE B.C.       | 18-54-25, 31-51-25   | 797 095    | B/H          |
| H - 30 | Village            | 18-55-48, 31-52-39   | 818 066    | B/H          |

### LIST OF BOREHOLES AND WELLS INSPECTED (2/2)

Note: Latitude and longitude are taken from G.P.S. and plot them on the map. Then, Grid Ref. is read from the map.

Appendix - 5 (5 - 2):

| No.      | Type of Source | T (°C) | pH  | Ec  | Coliforms       | M-organisms | Remarks  |
|----------|----------------|--------|-----|-----|-----------------|-------------|--|
| Pf-1     | Shallow Well   | 24.0   | 7.5 | 310 | many            | many        | Pvt. Well  |
| Pf-2     | B/H            | 26.2   | 7.6 | 740 | 0               | 2           |  |
| Pf-3     | Deep Well      | 26.6   | 8.5 | 610 | 2               | many        | Pump damaged   |
| Pf-4     | B/H            | -      | -   | -   | - E             |             | and the second   |
| Pf-5     | B/H            | 26.7   | 7.1 | 980 | 1 - <b>1</b>    | . 0         | n<br>Martin Angela   |
| Pf-6     | B/H            | 26.5   | 7.3 | ok  | 0.1             | 0           | $  x   = \frac{1}{2} \left( -\frac{1}{2} \left( \frac{1}{2} - \frac{1}{2} \right) \right)$ |
| Pf-7     | B/H            | 26.6   | 7.5 | •   | 0               | 0           | Salty  |
| Pf 8     | B/H            | 25.7   | 7.6 | ok  | 0               | 7           |  |
| Ma - 1   | В/Н            | 27.1   | 7.7 | 900 | 0               | 0           |  |
| Ma - 2   | Shallow Well   | 21.8   | 7.9 | 460 | 3               | 24          |  |
| Ma - 3   | B/H            | 26.2   | 7.4 | ok  | 0               | 0           |  |
| Ma - 4   | B/H            | 26.3   | 7.5 | ok  | 0               | 0           |  |
| Ma - 5   | B/H            | 25.9   | 7.6 | ok  | - 4             | 21          |  |
| Ma - 6   | B/H            | 26.7   | 7.4 | ok  | 0               | 0           |  |
| Ma - 7   | B/H            | 26.4   | 7.4 | 250 | 0               | 2           | na an an Anna Anna Anna Anna Anna Anna   |
| Uz- 1    | Deep Well      | 24.8   | 7.6 | 310 | 0               | 0           |  |
| Uz - 2   | B/H            | 24.2   | 7.5 | 320 | 6               | 10          |  |
| Uz- 3    | B/H            | 23.9   | 7.7 | 600 | 0               | 0           |  |
| Uz - 4   | B/H            | 24.7   | 7.6 | 330 | 0               | 0           |  |
| Uz-5     | B/H            | 23.0   | 77  | 510 | • 0             | 0           | an geologie – Et   |
| Uz- 6    | B/H            | 24.1   | 7.6 | 320 | 0               | E 0         |  |
| Uz- 7    | Deep Well      | 25.2   | 8.3 | 280 | 6               |             |  |
| Uz- 8    | B/H            | 25.0   | 7.2 | 170 | . 0             | 0           |  |
| Uz- 9    | Deep Well      | 23.7   | 8.1 | 240 | 5 · · · · 5 · · | 60          |  |
| Uz - 10  | B/H            | 23.9   | 7.5 | 290 | 0               | 0           |  |
| Uz - 11  | B/H            | 23.7   | 7.7 | 250 | 0               | 0           |  |
| Uz - 12  | B/H            | 25.8   | 7.5 | 310 | 0               | 0           |  |
| Uz - 12' | Deep Well      | 26.5   | 7.5 | 460 | 12              | 10          |  |
| Uz-13    | B/H            | 26.5   | 7.5 | 360 | 0               | 0           |  |
| Uz - 14  | Shallow Well   | 23.0   | 9.0 | 410 | 8               | 11          |  |
| Uz - 15  | Shallow Well   | 25.2   | 7.7 | 300 | 5               | 6           |  |
| Uz - 16  | Shallow Well   | 22.0   | 7.4 | 105 | 17              | many        |  |

## **RESULT OF SIMPLIFIED WATER QUALITY TEST (1/2)**

۸-14

| No.    | Type of Source | T (℃) | pH  | Ec           | Coliforms         | M-organisms | Remarks      |
|--------|----------------|-------|-----|--------------|-------------------|-------------|--------------|
| H - 1  | B/H            | 24.4  | 7.8 | 590          | 1                 | 2           |              |
| H - 2  | B/H            | 21.5  | 7.4 | 90           | 1                 | 23          |              |
| H - 3  | B/H            | 24.2  | 7.4 | 160          | 10                | · 0         |              |
| H-4    | B/H            | -     | -   | . <b>-</b> , | -                 | -           | Pump damaged |
| H-5    | B/H            | 23.8  | 7.6 | 110          | 0                 | 0           |              |
| H-6    | B/H            | 24.4  | 8.2 | 90           | 0                 | 0           |              |
| H-7    | B/H            | 24.3  | 6.7 | 79           | · 5 ·             | 0           |              |
| H - 8  | B/H            | 23.1  | 7.0 | 69           | 0                 | 0           |              |
| H-9    | B/H            | 22.5  | 7.5 | 65           | 8                 | 7           |              |
| H-10   | B/H            | 25.4  | 6.3 | 60           | 5                 | 5           | 1            |
| H-11   | B/H            | -     | 7.1 | 240          | · · · 0 · ·       | 0           |              |
| H-12   | B/H            | 23.1  | 6.8 | 86           | · · 0 ·           | 0           |              |
| H-13   | B/H            | –     | -   | -            | -                 |             | Pump damaged |
| H - 14 | B/H            | 23.4  | 7.5 | 84           | · · · · · · 0 · · | 0           |              |
| H-15   | B/H            | 23.5  | 6.7 | 100          | 2                 | 10          | W/ e. pump   |
| H-16   | B/H            | 22.8  | 7.6 | 150          | 0                 | 4           |              |
| H-17   | B/H            | 23.5  | 7.5 | 280          | 0                 | 0           |              |
| H-18   | B/H            | 23.2  | 8.2 | 112          | 0                 | 0           |              |
| H - 19 | B/H            | 24.5  | 7.2 | 74           | 0                 | 0           |              |
| H - 20 | Deep Well      | 25.0  | 7.6 | 170          | 1.<br>            | 12          | W/m.pump     |
| H - 21 | River          | 19.2  | 8.1 | 65           | many              | many        |              |
| H - 22 | B/H            | 23.5  | 7.2 | 170          | 0                 |             | · · ·        |
| H - 23 | B/H            | 24.2  | 7.5 | 290          | many              | 19          | · · ·        |
| H - 24 | B/H            |       |     | -            | -                 | -           | Pump damaged |
| H - 25 | B/H            | 25.1  | 8.1 | 270          | 1 . <b>1</b> .    | 9           |              |
| H - 26 | B/H            | 24.4  | 7.8 | 210          | . 0               | 0           |              |
| H - 27 | B/H            | 25.0  | 7.4 | 280          | 0                 | 0           |              |
| H - 28 | B/H            | 25.7  | 7.4 | 400          | 0                 | 6           |              |
| H - 29 | B/H            | 25.9  | 7.7 | 370          | 0                 | 2           |              |
| H - 30 | B/H            | 26.1  | 7.9 | 410          | 1                 | 4           |              |

### **RESULT OF SIMPLIFIED WATER QUALITY TEST (2/2)**

Note: W/e. pump: with engine pump, m. pump: motor pump

ok in EC means no extraordinary findings by taste, while is done during machine trouble.

### Appendix - 6: DATA OF ZIMBABWE (1) GDP, GNP and Domestic Product

#### TABLE 7.1: REAL GROSS DOMESTIC AND NATIONAL PRODUCT PER CAPITA AT MARKET PRICES' Z\$ million

(at market prices)

|        |                   | Current prices                                    |                              | Consta                       | int prices <sup>3</sup>      | Constant       | prices34                 |
|--------|-------------------|---|------------------------------|------------------------------|------------------------------|----------------|--------------------------|
|        |                   | Net investment                                    |                              |                              |                              | Per c          | apita                    |
|        | Gross<br>domestic | income paid<br>to other<br>countries <sup>2</sup> | Gross<br>national<br>product | Gross<br>domestic<br>product | Gross<br>national<br>product | Gross domestic | Gross nationa<br>product |
| Period | product           | countries-  | product                      | product                      |                              | product        | ploque                   |
| 1975   | 1 998             | 45  | 1 953                        | 3 266                        | 3 159                        | 520            | 503                      |
| 976    | 2 166             | - 58  | 2 108                        | 3 230                        | 3 123                        | 498            | 481                      |
| 977    | 2 198             | 48  | 2 150                        | 3 064                        | 2 984                        | 457            | 445                      |
| 978    | 2 359             | - 42  | 2 317                        | 2 998                        | 2 937                        | 433            | 424                      |
| 979    | 2 822             | 53  | 2,769                        | 3 1 1 2                      | 3 055                        | 436            | 428                      |
| 980    | 3 4 4 1           | - 47  | 3 394                        | 3 441                        | 3 394                        | 468            | 461                      |
| 981    | 4 433             | - 115   | 4 3 18                       | 3 872                        | 3 756                        | 509            | 494                      |
| 982    | 5 197             | 194   | 5 003                        | 3 974                        | 3 778                        | 522            | 496                      |
| 983    | 6 306             | - 248   | 6 058                        | 4 037                        | 3 824                        | 522            | 495                      |
| 984    | 6 404             | - 195   | 6 209                        | 3 960                        | 3812                         | 498            | 479                      |
| 985    | 7 297             | - 284   | 7 013                        | 4 235                        | 4 049                        | 518            | 496                      |
| 986    | 8 376             | 384   | 7 992                        | 4 347                        | 4 106                        | 517            | 488                      |
| 987    | 9 273             | — 355   | 8 9 1 8                      | 4 302                        | 4 108                        | 498            | 475                      |
| 988    | 10 925            | - 478   | 10 447                       | 4 696                        | 4 473                        | 529            | 504                      |

1. Source: Central Statistical Office.

2. Gross domestic product less net investment income paid to other countries equals gross national product.

3. At 1980 prices.

4. Z\$.

#### TABLE 7.2: DOMESTIC PRODUCT AT FACTOR COST BY INDUSTRY' Z\$ million

(at current prices)

| Period | Agricul-<br>ture and<br>Forestry | Mining<br>and<br>quarrying | Manufac-<br>turing | Electricity<br>and<br>water | Construc-<br>tion | Finance<br>and<br>insurance | Real<br>estate | Distribu-<br>tion,<br>hotels and<br>restaurants | Transport<br>and<br>communi-<br>cation | Public<br>administra-<br>tion and<br>defence | Education<br>services | Other<br>services <sup>2</sup> | Totel |
|--------|----------------------------------|----------------------------|--------------------|-----------------------------|-------------------|-----------------------------|----------------|---|--|--|-----------------------|--------------------------------|-------|
| 1975   | 323                              | 131                        | 447                | 50                          | 94                | 86                          | 44             | 258   | 145                                    | 130  | 65                    | 129                            | 1 902 |
| 1976   | 350                              | 152                        | 480                | 57                          | 88                | 92                          | 47             | 262   | 159                                    | 163  | 73                    | 141                            | 2 06  |
| 1977   | 334                              | 149                        | 460                | 56                          | 84                | 102                         | 47             | 242   | 186                                    | 204  | 76                    | 149                            | 2 05  |
| 1978   | 289                              | 156                        | 515                | 62                          | 67                | 105                         | 45             | 356   | 178                                    | 239  | 66                    | 157                            | 2 25  |
| 1979   | 321                              | 226                        | 625                | 71                          | 92                | 123                         | 44             | 425   | 188                                    | 270  | - 88                  | 167                            | 2 65  |
| 1980   | 451                              | 285                        | 802                | 70                          | 91                | 159                         | 43             | 451   | 211                                    | 291  | 169                   | 201                            | 3 22  |
| 1981   | 640                              | 252                        | 1 016              | 78                          | 138               | 185                         | 55             | 603   | 306                                    | 309  | 215                   | 252                            | 4 04  |
| 982    | 669                              | 217                        | 1 121              | 73                          | 190               | 228                         | 55             | 741   | 365                                    | 367  | 309                   | 322                            | 4 65  |
| 1983   | 544                              | 393                        | 1 441              | 195                         | 258               | 275                         | 59             | 783   | 403                                    | . 398  | 343                   | 340                            | 5 43  |
| 1984   | 748                              | 320                        | 1 475              | 142                         | 205               | 282                         | 60             | 742   | 434                                    | 444  | 416                   | 381                            | 5,64  |
| 1985   | 1316                             | 335                        | 1 488              | 144                         | 154               | 343                         | 68             | 777   | 431                                    | 476  | 520                   | 453                            | 6 50  |
| 1986   | 1 202                            | 446                        | 1 832              | 229                         | 168               | 366                         | 75             | 971   | 582                                    | 518  | 610                   | 432                            | 7 43  |
| 1987   | 1 061                            | 686                        | 2 0 4 3            | 276                         | 225               | 476                         | - 94           | 1 001   | 669                                    | 614  | 676                   | 439                            | 8 25  |
| 1988   | 1 263                            | 824                        | 2 346              | 268                         | 256               | 530                         | 100            | 1 078   | 760                                    | 810  | 822                   | 545                            | 9 64  |
| 1989   | 1 390                            | 1 001                      | 2 932              | 367                         | 253               | 633                         | 105            | 1 273   | 856                                    | 895  | 925                   | 642                            | 11 27 |
| 1990   | 1 686                            | 1 071                      | 3 4 36             | 434                         | 289               | 740                         | 111            | 1 499   | 978                                    | 977  | 1 069                 | 739                            | 13 02 |
|        | 1                                | 1                          | 1                  | 1                           | ł                 | 1                           | 1              | 1   | 1                                      | I  | 1                     | 1                              | 1     |

1. Source: Central Statistical Office

2. Includes health, private domestic service and allowance for imputed banking service charges.

S 45

# (2) External Financing Requirements

(Source: A. Framework for Economic Reform (1991-95))

|                                     | Tal      | ole 5. EX | TERNAL FIN | ANCING REG  | UIREMENTS |                    | ·<br>·  |
|-------------------------------------|----------|-----------|------------|-------------|-----------|--------------------|---------|
|                                     | 100      |           |            | lions US\$) |           |                    | · .     |
|                                     |          |           |            | •           | -         |                    |         |
|                                     | 1991     | 1992      | 1993       | 1994        | 1995      | 1991-95            | •<br>•  |
| REQUIREMENTS:                       |          |           |            |             |           |                    |         |
| Imports (GNFS)                      | 2097     | 2274      | 2429       | 2600        | 2779      | 12179              | '       |
| Factor Payments                     | 307      | . 341     | 376        | 410         | 441       | 1875               | · · · · |
| (Interest)                          | 167      | 191       | 217        | 241         | 262       | 1078               |         |
| Amortization                        | 235      | 259       | 242        | 265         | 313       | . 1314             | • • • • |
| Change in Reserves                  | 136      | 114       | 123        | 108         | 114       | 595                | · • ·   |
| Total                               | ∙ 2775 ⊂ | 2987      | 3170       | 3383        | 3647      | 15963              | •       |
|                                     | 1        |           | •          | • •         |           | 8 - 1 <sup>2</sup> | Х       |
| SOURCES:                            |          |           | · • •      |             |           |                    |         |
| Exports (GNFS)                      | 2028     | 2207      | 2409       | 2640        | 2900      | 12184              | •       |
| Factor receipts                     | 48 .     | 60        | 69         | 79          | 88        | 344                | •       |
| "Current Transfers                  | -20      | 25        | -31        | -35         | -37       | - 148              |         |
| Foreign investment                  | 19       | 26        | 28         | 32          | 33        | 138                | •       |
| Total Primary Sources               | 2076     | 2267      | 2475       | 2717        | 2984      | 12518              | ۰.,     |
| TOTAL FINANCING REQUIRED            | 700      | 720       | 696        | 666         | 663       | 3444               |         |
|                                     | •        | · · · ·   | •          |             | _         | .'                 |         |
| Disbursment on Existing Commitments | 360      | 380       | 167        | 79          | 77        | 1063               |         |
| IBRD                                | 2.9      | 31        | 35         | 36          | 36        | 168                |         |
| Other Multilateral                  | 95       | 86        | 66         | 40          | 39        | 326                |         |
| Bilateral                           | 83       | 90        | 66         | 2           | 2         | 244                |         |
| Commercial Banks (incl. IFC)        | 152      | 173       | Ο.         | Ū           | 0         | 325                |         |
|                                     |          |           |            |             | •         |                    |         |
| ADDITIONAL FINANCING REQUIRED       | 340      | 340       | 528        | . 587       | 586       | 2382               |         |
|                                     |          |           | -          |             |           |                    | · .:    |

۸-17

(3) Budget Allocation for Water Sector

PRU REMENT PREPARATION SCHEDULE

|                                       |             |                    |                            | SCHEM FACTORY TON SCHEVELS  | ULC.                                 | -    | •              | . •         |          | • •     |                               |                |              | :         |
|---------------------------------------|-------------|--------------------|----------------------------|---|--------------------------------------|------|----------------|-------------|----------|---------|-------------------------------|----------------|--------------|-----------|
| MINISTRESORGANIZATION Processment     | Procuranian | Contract<br>Amount | Contract<br>Amount         | Contractor  |                                      |      |                | 5 sburse    | ancost 1 |         | Disbursenient Fortcast (USSn) |                | <b>.</b>     | Prepara   |
|                                       |             | (Estimate USS)     | (Actual USS)               |   | Comments                             | Мiy  | in (           | Juf A       | Aug S    | Sep Q   | NoV L                         | Oct New Dec 94 |              | Ship Date |
| DDF Heavy Truck Spares                | ΠC          | 450,000.00         |                            | 891,124.90 OTC Ossenhandels, Germany                              | Awaiting delivery of goods           | 0.1  |                |             |          |         |                               |                | 30/          | 30/11/93  |
| 2 MLAWD geophys equipt                | ICB         | 1,500,000.00       |                            | 444,071.56 Atlas Copco, Sweden                                    | Awaiting delivery of goods           |      |                | 0.1         | · · ·    | 0.2     | 0,1                           | :              | 30/          | 30/07/93  |
| 3 MLAWD Computers                     | LCB         | 150,000.00         | _                          | 161,763.68 Infolech, Zimbabwe                                     | Awaiting delivery of goods           |      |                | نې چې<br>ب  | 0.2      |         |                               |                | 31/          | 31/07/93  |
| 4 RWA Submersible Pumps               | LCB         | 250,000.00         |                            | 160,228.00 BV Kim, Holland  | Goods delivered                      | Good | Goods received |             |          |         |                               |                |              |           |
| 5 DDF Light Net-up Spares             | LCB         | 400,000.00         |                            | 97,160.00 Kjaer & Kjaer, Denmark                                  | Awaiting delivery of goods           |      |                | 1 - 5 I<br> | 0.1      |         |                               |                | 31/          | 31/08/93  |
| 6 DDF/MLAWD Raw Materials             | ICB         | 3,000,000.00       | 1                          | .784.715.00 Kjacr & Kjacr/EB Exports                              | Part contract delive <del>re</del> d | 0.2  |                | <u></u>     |          | 0.2     |                               |                | 31/          | 31/08/93  |
| 7 DDF Water Bowsers (                 | rca         | 100,000.00         | 171,866.78                 | 171,866.78 OTC Aussenhandels, Germany Awaiting delivery of goods  | Awaiting delivery of goods           |      |                | <br> <br>   |          |         | 0.2                           | <br> <br>      | ğ            | 30/11/03  |
| 8 DDF Compressor Spares               | LCB         | 150,000.00         |                            | 253,388.00 Atlas Copco Geotechnical                               | Application for LC with Reserve Bank |      |                | <br>        |          | 5.0     |                               |                | 34.00        | 30/00/03  |
| 9 DDF/MWD Pumps + Engine              | ICB         | 4,500,000,00       | -                          | .966,132.00 • Awarded, awaiting contract signing                  | zning                                |      |                |             | 0.2      |         | 0.2                           |                | 30/          | 30/00/05  |
| .10 DDF/MWD String + Drill Supervisio | LCB         | 2,000,000.00       | 2                          | .000,000.00 * Awarded, DWD preparing cor                          | contracts                            |      |                |             |          | 0.2     |                               |                | 1.5 28/      | 28/07/04  |
| 11 DDF/MWD Pumps+Eng Spares           | rcB         | 500,000.00         | 1                          | .391,234.00 Technology Supply Co                                  | Awaiting delivery of goods           | 0.1  |                |             | 1.2      | 13      |                               |                |              | 31/03/94  |
| 12 DDF/MWD Drilling tender            | ICD         | 8,000,000.00       | *                          | ,000,000.00 * With World Bank for review                          |                                      |      |                | <br>        |          |         | 0.8                           | <br>           | 7.1 31/03/04 | 10/10     |
| 13 DDF New Tractors (farming)         | ICB         | 3,000,000,000      | 2,694,845.13               | 694,845.13 * With World Bank for review                           |                                      |      |                |             |          | 0.3 2   | 2.4 0.3                       |                | SE<br>E      | 10/01/1E  |
| 14 DDF Tractor Spares                 | ICB         | 2,500,000.00       | 2,457,800.00               | 457,800.00 Lots 1,2,3 awaiting delivery, lot 4 with Tentler Board | 4 with Tender Board                  |      | 0.3            | 8.1         | 0.3      |         |                               |                | 34           | 31/07/93  |
| 15 MLAWD Ford Trador Spares           | ГCB         | 500,000.00         | 23,872.00 Duly's           | Duly's Contraction  | With MIC for import licence          |      | -              |             | 0        | 0.02    |                               |                | 30/C         | 30/00/03  |
| 16 MLAWD Spares for Percussion Rig    | ICB         | 250,000.00         | 351,804,70 Leegold, UK     |   | Awaiting delivery of goods           |      |                | 0.1         | 0.2      |         |                               |                | 312          | 10/10/18  |
| 17 MLAWD Diesel Testing Equipment     | - ICB       | 50,000.00          | 224,402.14                 | 224,402.14 Lucas Assembly, UK                                     | Awaiting delivery of goods           |      |                |             | 0.2      |         |                               |                | 31/0         | 31/07/93  |
| 18 MLAWD Spares for Drill Equipmen    | LCD         | 500,000.00         | 413,161.00                 | 413,161.00 Atlas Copco, Sweden                                    | Awaiting delivery of georis          |      |                |             | 0.2      | 0.1     |                               |                | 31/0         | 31/0/16   |
| 19 MLAWD Large Drill Rigs Sports      | ICB         | 1,500,000,00       | 2.627.067.68 Mitsui, Japan |   | Awaiting delivery of goods           |      |                | 0.3         |          | 2 (0)   | 0.3                           |                | 31/1         | 31/10/97  |
| 20 MLAWD Small Drill Rigs Sporce      | LCB         | 300,000.00         | 313,510.30                 | Sweden  | Awaiting delivery of goods           |      | <br>           | 5           | 0.10     | 10      |                               | <br>           | 31/0         | 31/07/93  |
| 21 []DF/MVD Drill Consumables         | ICB         | 2,000,000.00       | 1,401,200,00               | λ.  | Awaiting delivery of goods           | 1    |                |             | 0.2      | 1.2 0.2 | 2                             |                | 30/01        | 1 6/6/01  |
| TOTAL                                 |             | 31,600,000,000     | 27,829,346.87              |   |                                      | 0,40 | 0.30           | 2.50 4.30   | 5        |         | 1                             | 0,0            | 8 90         |           |
|                                       |             | -                  |                            |   | <b>₽</b>                             |      | 1              |             |          |         |                               |                | 1            |           |

= ₽ Λ-18 EMERGENCY DROUGHT RECOVERY AND HILFIGATION PROJECT

DATE: 20/08/93

.

Estimated value

# Appendix - 7 :

List of Spare Parts for Phase-2 Equipment

| Ite   | em Description  | •   | Q'ty               |
|-------|---|---|--------------------|
| No.   |   |   | Q CJ               |
|       | INJECTION PUMP, MODEL "   |   | <u> </u>           |
| 1)    | Hydraulic motor,  | AND I   | 1 pc.              |
|       | nydraurie motor,  |   | r po.              |
| 2)    | VALVE BOX ASSEMBLY,   |   |                    |
| 2)    |   | E2702_029   | 2 000              |
|       | Rubber,   | E2702-023   |                    |
|       | Liner,  | E2705-049<br>A2841-034  |                    |
|       | Piston rod,   | 1   | 1. Contract (1997) |
|       | Seat ball valve,  | E2916-011   |                    |
|       | Piston body,  | E0337-018   |                    |
| · · · | Nut<br>Distor nubbor  | E2160-214   |                    |
|       | Piston rubber,  | E2161-004   |                    |
|       | Spring, SC2-016-04,   | SC201604  | 8                  |
|       | V-packing, H18,   | RKV0018   |                    |
| :     | Steel ball,   | BBB0254   | 8                  |
| 3)    | GEARING ASSEMBLY,   |   |                    |
|       | Oil seal, SB 70x90x12   | SEA07003  | 4 pcs.             |
|       | Oil seal, SB 85x110x13,   | SEA08502  | 4                  |
|       | Oil seal, SB 120x150x14,  | SEA12001  | 4                  |
| -     | HIGH TORQUE LOW SPEED HY  |   |                    |
|       | Oil motor, GR-H-350-567-  | -10-D-JA-J  | 2 pcs.             |
|       | 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - | and and a second se<br>Second second | a at               |
| 4)    | AIR WATER SWIVEL ASSEMBL  | ¥,  | :                  |
|       | Grand packing,  | D1150-355   | 6 pcs.             |
|       | Grand packing,  | D1150-356   | 3                  |
|       | Grand packing,  | D1150-427   | 3                  |
|       | Grand packing,  | E1150-428   | 3                  |
|       |   | D2528-386   | 16                 |
|       | Sleeve,   | D2958-572   | 3                  |
|       | O-ring, G130  | RRG0130   | 6                  |
|       | O-ring, G85   | RRG0085   | 3                  |
|       | Oil seal, SB. 95. 115. 13,  |   | 3                  |
|       |   |   |                    |

| Ite | m Description            | · · ·  | Q'ty   |
|-----|--------------------------|--|--|
| No. |                          |  |  |
| 14) | OPERATION ASSEMBLY,      |  |  |
| /   | Relief valve,            | BAB1005  | 2 pcs.   |
|     | Manual valve,            | BAC0021  | 2  |
|     | Multi valve,             | BAD0011  | $\mathbf{z}^{\mathbf{z}}$ , where $\mathbf{z}^{\mathbf{z}}$ , $\mathbf{z}^{$ |
|     | Multi valve,             | BAD0040  | 2  |
|     | Needle valve,            | BAZ2002  | 2  |
|     |                          |  | and the state of the second second   |
| 15) | LEVER ASSEMBLY, ENGINE   | GOVERNOR,  |  |
|     | Control cable, (V700-33) |  | 1 pc.  |
|     | Clevis with pin (CLE32)  | and the second | 4 sets   |
|     |                          |  |  |
| 16) | GENERATOR ASSEMBLY, MODI | EL "PWD280SBL  | • A state of the second se   |
|     | Hand fuel pump for ISU   |  | 2 pcs.   |
| :   | (complete),              |  | The second second second second  |
|     | Injector pump for ISUZI  | J engine   | <b>1</b> pc.   |
|     | (complete),              |  |  |
|     | Injectors for ISUZU en   | gine   | 16 pcs.  |
|     | (complete)               |  |  |
|     | · · · ·                  |  |  |
| 17) | ENGINE MODEL "PD6"       |  | n an tha an the state of the second  |
|     | Fan                      | 21060-96002  | 1 pc.  |
|     | Pulley,                  | 21051-96061  | ${\mathbb F}_1^{(n)}$  |
|     | Oil seals,               | 12278-96006  | 6  |
|     | Water pump ass'y         | 21010-96004  | $d^{2}\mathbf{\hat{2}}_{ij}$ and $d^{2}$ is the set of the set of $\mathbf{\hat{2}}_{ij}$  |
|     | Manual pump feed fuel,   | 16640-96000  | 2  |
|     | Fuel injection pump,     | 16640-96064  | en <mark>i</mark> Alexandra de Alexandre de Caracteria de C  |
|     | Injector nozzles,        | 16600-96001  | . <b>12</b>  |
|     | Oil filter element,      | 15274-99227  | 36   |
|     | Fuel filter element,     | 16444-99028  | 36   |
|     | Oil filter element,      | 15274-99025  | <b>36</b>  |
|     | Gasket cylinder,         | 11044-96007  | 3  |
|     | Gasket cylinder,         | 32001-90326  | <b>3</b>   |
|     | Gasket cylinder,         | 11121-97500  | 3  |
|     |                          |  |  |
|     | ·                        | unto presentario 🖡   | and the second products of the   |
|     |                          |  |  |
|     |                          |  |  |
|     |                          | • •  |  |
|     |                          | ۸-20   |  |
|     |                          |  |  |
|     |                          |  |  |

|                  | Description                            | Q   | 'ty  |
|------------------|--|-----|------|
| <u>No.</u><br>5) | DRILL HEAD DAMER ASSEMBLY,             |     |      |
|                  | Drill head saver sub, 3-1/2"           | 2   | pes. |
|                  | IF box to 3-1/2" IF pin                |     | •    |
| 3)               | THREE WING BITS HEAD METAL INSERTS,    |     |      |
|                  | 10-5/8" wing bit with $3-1/1$ " IF box | : 5 | pes. |
|                  | 8-5/8" wing bit with $3-1/1$ " IF box  | 6   |      |
| 7)               | ROLLER BITS,                           |     |      |
|                  | 10-5/8" soft formation roller bit      | 6   | pes. |
|                  | Extra soft formation roller bit        | 6   |      |
| 8)               | DOWN THE HOLE HAMMER,                  |     |      |
|                  | DTH hammer, (To suit 6" bit),          | 4   | sets |
|                  | 6" DTH hammer bits                     | 6   | pes. |
| 9)               | LUBRICATOR ASSEMBLY,                   |     |      |
|                  | Pump, KSP 502L,                        | 2   | pes. |
| C )              | HIGH PRESSURE AIR HOSE,                |     |      |
|                  | Hose (70K x 50 mm) Length              | 100 | m    |
|                  | High pressure hose fittings complete   | 6   | sets |
|                  | Nipple, E2196-385                      | 4   | pes. |
|                  | 50 mm quick release valve,             | 6   |      |
| -                | LIGHTING ASSEMBLY,                     |     |      |
|                  | Lamp, DAA0001, (HSS-MA-3)              | 12  | pes. |
| 2)               | DRUM ASSEMBLY MODEL "MA-3",            |     |      |
|                  | Gear 1,                                | 1   | pc   |
|                  | Gear 2,                                | 1   |      |
|                  | Motor, 3 PH, 200V,                     | 1   |      |
| 3)               | OIL COOLER ASSEMBLY,                   |     |      |
|                  | Fan and motor,                         | 1   | set  |
|                  |  |     |      |

۸-21

-

