

PROJECT SUMMARY (Basic Study)

ASE IDN/S 502/85

Compiled Mar.1988

Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS						
1.COUNTRY	Indonesia	1.SITE OR AREA	The upstream basin of River Negara in South Kalimantan (6,500 sq.km for mapping)			1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued				
2.NAME OF STUDY	Topographic Mapping Project for Upper Stream Area of Negara Basin, South Kalimantan	2.PROJECT COST	(US\$1,000)	Total Cost	Local Cost	Foreign Cost	(Description) The Negara River basin has large development potentials such as water resource development in the upstream and agricultural development in the midstream and downstream. The maps will be basic to such development planning.				
3.SECTOR	Social Infrastructures/Survey & Mapping	3.CONTENTES OF MAJOR PROJECT(S)	1)								
4.REFERENCE NO.			2)								
5.TYPE OF STUDY	Basic Study	Preparation of national base maps (scale: 1/50,000 9 plates)									
6.COUNTERPART AGENCY	Directorate of Planning and Programming, Directorate General of Water Resource Development, Ministry of Public Works										
7.OBJECTIVES OF STUDY	To prepare the 1:50,000 topographic maps covering an area of 6,500 sq.km in upper stream of Negara river basin										
8.DATE OF S/W	Feb.1983										
9.CONSULTANT(S)	International Engineering Consultants Association										
10.STUDY TEAM	No.of Members 23 Period Feb.1983-Jan.1986(30 months)	4.CONDITIONS AND DEVELOPMENT IMPACTS	The prepared maps are indispensable to water resource development planning in the basin area. The maps will be useful to a feasibility study on agricultural development scheduled soon to begin in the downstream area.			2.MAJOR REASONS FOR PRESENT STATUS					
	<table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <th>Total M/M</th> <th>Japan</th> <th>Field</th> </tr> <tr> <td style="text-align: center;">29.00</td> <td style="text-align: center;">10.50</td> <td style="text-align: center;">18.50</td> </tr> </table>	Total M/M				Japan		Field	29.00	10.50	18.50
Total M/M	Japan	Field									
29.00	10.50	18.50									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY											
12.EXPENDITURE		5.TECHNICAL TRANSFER									
	<table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td>Total</td> <td style="text-align: right;">336,955 (¥'000)</td> </tr> <tr> <td>Contracted</td> <td style="text-align: right;">169,795</td> </tr> </table>	Total	336,955 (¥'000)	Contracted	169,795	1) Participation of the counterparts in the JICA training program 2) Employment of local consultants 3) GJT for the counterparts on aerophotography	3.PRINCIPAL SOURCE OF INFORMATION				
Total	336,955 (¥'000)										
Contracted	169,795										
						①					

和名 カリマンタン州ネガラ河上流域地図作成事業

(M/P,M/P+(F/S),Basic Study,Other)

PROJECT SUMMARY (Basic Study)

ASE IDN/A 502/85

Compiled Mar.1991
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS							
1.COUNTRY	Indonesia	1.SITE OR AREA	Kalimantan Island, downstream area of the Negara River Basin in South Kalimantan		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued						
2.NAME OF STUDY	Mosaic Photomap Project of the Downstream Area of the Negara River Basin in South Kalimantan	2.PROJECT COST	Total Cost	Local Cost	(Description) A master plan study on Negara River basin overall irrigation development was undertaken by JICA during 1987-1989.							
3.SECTOR	Agriculture/General	(US\$1,000)	1) 2)									
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)			2.MAJOR REASONS FOR PRESENT STATUS This study started for the purpose of establishing agricultural development plan, however, Indonesian Government was reluctant to hand over topographical maps abroad. Therefore this study concluded as photo map project.							
5.TYPE OF STUDY	Basic Study	Following works were done as basic data for establishing Agricultural Development Plan in downstream area of the Negara River Basin. 1.Taking air photos of those area 6.300 sq.m (1/20,000) 2.Mosaic photomap of Amuntai area (about 1,200 sq.km (1/10,000))										
6.COUNTERPART AGENCY	Directorate General of Water Resources Development, Ministry of Public Works	4.CONDITIONS AND DEVELOPMENT IMPACTS			3.PRINCIPAL SOURCE OF INFORMATION ①							
7.OBJECTIVES OF STUDY	Preparation of master plan for agricultural development	Negara River, the tributary of Barito River where development works have been done on the small scale, remains undeveloped. Indonesian Government recognizes that establishing agricultural development plan is indispensable to facilities development of those areas. This study is basic data for it.										
8.DATE OF S/W	Apr.1983	5.technical transfer			Transfer of technology in aerial photogrammetric mapping							
9.consultant(S)												
10.STUDY TEAM	No.of Members 21 Period Jul.1983-Jul.1986(33 months)											
	<table style="width: 100%; border: none;"> <tr> <td style="text-align: left;">Total M/M</td> <td style="text-align: left;">Japan</td> <td style="text-align: left;">Field</td> </tr> <tr> <td style="text-align: right;">72.87</td> <td style="text-align: right;">14.76</td> <td style="text-align: right;">58.11</td> </tr> </table>	Total M/M	Japan	Field	72.87	14.76	58.11					
Total M/M	Japan	Field										
72.87	14.76	58.11										
11.associated and/or subcontracted study												
12.EXPENDITURE												
	Total	376,764 (¥'000)										
	Contracted	373,813										

和名 南カリマンタン州ネガラ河下流域写真図作成調査

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/S 118/86

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																				
1.COUNTRY	Indonesia	1.SITE OR AREA	The entire country			1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued																		
2.NAME OF STUDY	Long Term Planning for Development of Telecommunications System	2.PROJECT COST						Total Cost	Local Cost	Foreign Cost															
3.SECTOR	Communications & Broadcasting/General		(US\$1,000)	1) 346,283	314,623	(Description) Based on the recommendations of the study, the master plan study was undertaken by the JICA team on the long-term and medium-term plan for telecommunications network in Jabotabek area of Jakarta during 1988 - 1989. OECF approved in 1991 a loan for the priority project, namely, the junction cable network expansion project in Jabotabek area. Sep. 1991 OECF loan agreement signed (3,556 million yen) Based on the master plan study, a JICA study on the 6th five-year plan for telecommunication development was undertaken in 1992.																			
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)	2) 31,660	(1) Formulation of development goals up to the year 2004 (the ending year of the 7th national development plan) and identification of development strategies (2) Formulation of the basic plan on the scale of development (3) Financial and economic evaluation of the plan and project formation																					
5.TYPE OF STUDY	M/P	4.CONDITIONS AND DEVELOPMENT IMPACTS	The proposed plan and projects will support the national economic and social development of the country by improving telecommunication services and the profitability of the telecommunication operations.																						
6.COUNTERPART AGENCY	POSTEL, PERUMTEL	7.OBJECTIVES OF STUDY						Development of the telecommunication network and services up to the year 2004.																	
8.DATE OF S/W	Nov.1985	9.CONSULTANT(S)									Nippon Telecommunication Consulting Co., Ltd. Yachiyo Engineering Co., Ltd.														
10.STUDY TEAM		11.ASSOCIATED AND/OR SUBCONTRACTED STUDY												No.of Members 17 Period Jan.1986-Feb.1987(14 months) <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td></td> <td style="text-align: center;">38.27</td> <td style="text-align: center;">49.04</td> </tr> </table>			Total M/M	Japan	Field		38.27	49.04			
Total M/M	Japan	Field																							
	38.27	49.04																							
12.EXPENDITURE		5.TECHNICAL TRANSFER															(1) 2 counterparts were invited to Japan for the training on long-term telecommunication development planning (2) On the job training (PERUMTEL counterparts)								
		6.MAJOR REASONS FOR PRESENT STATUS																		(1) High priority (2) Effectiveness					
		3.PRINCIPAL SOURCE OF INFORMATION	①④																						

和名 電気通信システム長期開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 212A/86

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS				
1.COUNTRY	Indonesia	1.SITE OR AREA	Semarang and its environs, Java Province		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued			
2.NAME OF STUDY	Development Plan of the Port of Semarang (Phase-2)	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost	(Description) Followed by F/S			
3.SECTOR	Transportation/Port	(US\$1,000)	1) 76,775	28,782	47,993				
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)							
5.TYPE OF STUDY	M/P+ (F/S)	The target year of this master plan for the following plans is 2005. 1. Land use plan 1) For Cargo Movement International Terminal: 57.2 ha, Domestic Public Wharf: 64.8 ha, Distribution Area: 55.4 ha 2) For Industrial Activities Littoral Industry: 73.2 ha, Manufacturing Industry: 169.1 ha 3) For Business and Government Area Government Area:26.6 ha, Business Area: 13.6 ha 4) Others Railway road area: 13.6 ha 2. Plan for improvement of facilities Item Size General cargo berth 3,000 m Container berth 280 m Berth for iron & steel and scrap 400 m Widening and deepening of west channel New center and east channel							
6.COUNTERPART AGENCY	Directorate General of Sea Communication	4.CONDITIONS AND DEVELOPMENT IMPACTS							
7.OBJECTIVES OF STUDY	F/S on the long-term and short-term development plan of Semarang Port	Semarang Port will be developed as a development center in the middle Java province, and industrial and economic development of the area will be promoted.							
8.DATE OF S/W	Dec.1984								
9.CONSULTANT(S)	Overseas Coastal Area Development Institute of Ja								
10.STUDY TEAM	No.of Members 9 Period May.1985-Aug.1986(16 months) <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">61.15</td> <td style="text-align: center;">35.60</td> <td style="text-align: center;">25.55</td> </tr> </table>						Total M/M	Japan	Field
Total M/M	Japan	Field							
61.15	35.60	25.55							
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Investigation for natural conditions 12,918,000 Yen	5.TECHNICAL TRANSFER							
12.EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: right;">176,495 (¥000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: right;">172,629</td> </tr> </table>	Total	176,495 (¥000)	Contracted	172,629	Counterparts training was carried out on port planning and construction		3.PRINCIPAL SOURCE OF INFORMATION	
Total	176,495 (¥000)								
Contracted	172,629								
				①					

和名 スマラン港整備計画 (フェーズII)

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 212B/86

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT			
1.COUNTRY	Indonesia	1.SITE OR AREA		Semarang, and its environs, Java Province		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing		
2.NAME OF STUDY	Development Plan of the Port of Semarang (Phase-2)	2.PROJECT COST		Total Cost	Local Cost			Foreign Cost	
3.SECTOR	Transportation/Port			(US\$1,000)	94,938	(Description) The project is under implementation with OECF loans. Mar.1987 OECF E/S loan agreement (545 million yen) 1987 Part of the western breakwater (part of the Phase I project) was destroyed by high waves. Dec.1987 OECF loan agreement for emergency fortification of the western breakwater (726 million yen) Nov.1989 E/S of the Phase II completed. Sep.1991 OECF loan agreement Package 1, Phase II (7,530 million yen, excluding handling equipment) Sep.1992 OECF loan agreement Package 2, Phase II (3,590 million yen) Oct.1993 Package 1 (Phase II) construction to be started To be completed in Dec. 1995 Sep.1994 Package 2 (Phase II) construction to be started To be completed in Feb. 1996			
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)							
5.TYPE OF STUDY	(M/P)+F/S	Urgent Development Plan toward 1990. (1) Required Berths - wharf for foreign trade -10m wharf: 345m -7.5m wharf: 100m - Passenger terminal: 150m (multi-purpose) - coal wharf: 150m - Fertilizer wharf: 150m - Wharf for steel materials: 100m (2) total required area; 199 ha (including new reclaimed land area 120ha) * the above cost is as of May 1991. A yen credit of about 8.9 billion yen (=US\$6.4 million) has been granted by OECF.							
6.COUNTERPART AGENCY	Directorate General of Sea Communication								
7.OBJECTIVES OF STUDY	F/S on the long-term and short-term development plan of Semarang Port								
8.DATE OF S/W	Dec.1984	Imp. Period:		Mar.1988-Oct.1990				2.MAJOR REASONS FOR PRESENT STATUS	
9.CONSULTANT(S)	Overseas Coastal Area Development Institute of Ja	4.FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes	EIRR1) 28.10 EIRR2) EIRR3)	FIRR1) 3.80 FIRR2) FIRR3)				
10.STUDY TEAM	No. of Members 9 Period May.1985-Aug.1986 (16 months)	Conditions and Development Impacts: Conditions: 1) the project life is for 30 years from 1985 to 2014. 2) future cost includes port management and operation cost for phase I project. Development Impacts: 1) Reduction in Transportation Cost: a) Saving Vessel's Waiting cost b) Saving Transshipment cost from Offshore Anchorage c) Saving Landhaul Cost from the Neighbouring Provinces 2) Saving Energy Cost by Changing from Petroleum to Coal 3) Development of regional economy of hinterland.							
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Investigation for natural conditions 12,918,000 Yen	5. TECHNICAL TRANSFER						3.PRINCIPAL SOURCE OF INFORMATION	
12.EXPENDITURE	Total 176,495 (¥'000) Contracted 172,629	Counterpart training: Counterpart training on the methods of F/S, and visits to similar ports was conducted for three counterparts.							

和名スマラン港整備計画 (フェーズII)

{F/S,(M/P)+F/S,D/D}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 213A/86

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS						
1.COUNTRY	Indonesia	1.SITE OR AREA	Yogyakarta, Surakarta		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued					
2.NAME OF STUDY	Airport Development Project in Central Java and Jogjakarta	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost	(Description) Followed by F/S					
3.SECTOR	Transportation/Air Transportation & Airport	(US\$1,000)	1) 92,000	3,600							
4.REFERENCE NO.		(US\$1=200Yen)	2) 47,000	1,300							
5.TYPE OF STUDY	M/P+ (F/S)	3.CONTENTES OF MAJOR PROJECT(S)									
6.COUNTERPART AGENCY	Directorate General of Air Communication	Refer to F/S Form									
7.OBJECTIVES OF STUDY	Airport facilities	4.CONDITIONS AND DEVELOPMENT IMPACTS									
8.DATE OF S/W	Feb.1985	Impacts: Trunk line network which connects several regions will be developed by improving Yogyakarta and Surakarta airports as one of transportation facilities improvement plan in Central Java region especially in the Southern area, where transport network requires improvement.									
9.CONSULTANT(S)	Pacific Consultants International	5.technical transfer									
10.STUDY TEAM	No.of Members 11 Period Aug.1985-Nov.1986(16 months)										
	<table style="margin-left: auto; margin-right: auto;"> <tr> <td>Total M/M</td> <td>Japan</td> <td>Field</td> </tr> <tr> <td style="text-align: center;">77.12</td> <td style="text-align: center;">41.42</td> <td style="text-align: center;">35.70</td> </tr> </table>	Total M/M	Japan	Field	77.12		41.42	35.70			
Total M/M	Japan	Field									
77.12	41.42	35.70									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY											
12.EXPENDITURE											
	<table style="margin-left: auto; margin-right: auto;"> <tr> <td>Total</td> <td>233,054 (¥'000)</td> </tr> <tr> <td>Contracted</td> <td>221,324</td> </tr> </table>	Total	233,054 (¥'000)	Contracted	221,324	(1) Demand forecast technique, seminar on using computer (2) Training on execution method of air passenger flow survey (3) Overseas training of airport planning					
Total	233,054 (¥'000)										
Contracted	221,324										
					2.MAJOR REASONS FOR PRESENT STATUS						
					3.PRINCIPAL SOURCE OF INFORMATION						
					①						

和名 中部ジャワ・ジョグジャカルタ空港整備計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 213B/86

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT													
1.COUNTRY	Indonesia	1.SITE OR AREA		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;"></td> <td style="width: 25%; text-align: center;">Total Cost</td> <td style="width: 25%; text-align: center;">Local Cost</td> <td style="width: 25%; text-align: center;">Foreign Cost</td> </tr> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">92,000</td> <td style="text-align: center;">3,600</td> <td></td> </tr> <tr> <td style="text-align: center;">(US\$1=200Yen)</td> <td style="text-align: center;">47,000</td> <td style="text-align: center;">1,300</td> <td></td> </tr> </table>			Total Cost	Local Cost	Foreign Cost	(US\$1,000)	92,000	3,600		(US\$1=200Yen)	47,000	1,300		1.PRESENT STATUS <input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input checked="" type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing	
	Total Cost	Local Cost	Foreign Cost																
(US\$1,000)	92,000	3,600																	
(US\$1=200Yen)	47,000	1,300																	
2.NAME OF STUDY	Airport Development Project in Central Java and Jogjakarta	1) Yogyakarta, 2) Surakarta																	
3.SECTOR	Transportation/Air Transportation & Airport	2.PROJECT COST		(Description) Suspended after the completion of F/S, and future prospects uncertain.															
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)																	
5.TYPE OF STUDY	(M/P)+F/S	Runway 1) Yogyakarta 2) Surakarta 2,500m X 45m 390 X 45m(Extension) (New construction) Apron 41,000sq.m 20,000sq.m Passenger Terminal 12,000sq.m 7,700sq.m Air Navigation(ILS CAT-1),Supply Management facilities Systems																	
6.COUNTERPART AGENCY	Directorate General of Air communication	4.FEASIBILITY AND ITS ASSUMPTIONS																	
7.OBJECTIVES OF STUDY	Airport facilities	Feasibility: EIRR1) 13.90 FIRR1) Yes/No EIRR2) 14.00 FIRR2) EIRR3) FIRR3)																	
8.DATE OF S/W	Feb.1985	Imp. Period: .1991-.1994 .1990-.1993																	
9.CONSULTANT(S)	Pacific Consultants International	Conditions and Development Impacts: IRR calculation: Future traffic volume was forecast for the target year 2000 and 2010. Project life is estimated for 15 years after commencement of the construction up to 2010. Impact: Trunk line network which connects several regions will be developed by improving Yogyakarta and Surakarta airports as one of transportation facilities improvement plan in Central Java region especially in the southern area, where transport network requires improvement.																	
10.STUDY TEAM	No.of Members 11 Period Aug.1985-Nov.1986(16 months) <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%; text-align: center;">Total M/M</td> <td style="width: 30%; text-align: center;">Japan</td> <td style="width: 40%; text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">77.12</td> <td style="text-align: center;">41.42</td> <td style="text-align: center;">35.70</td> </tr> </table>	Total M/M	Japan			Field	77.12	41.42	35.70	2.MAJOR REASONS FOR PRESENT STATUS									
Total M/M	Japan	Field																	
77.12	41.42	35.70																	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER		3.PRINCIPAL SOURCE OF INFORMATION															
12.EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;"></td> <td style="width: 50%; text-align: right;">233,054 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Total</td> <td></td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: right;">221,324</td> </tr> </table>		233,054 (¥'000)	Total		Contracted	221,324	(1) Demand forecast technique, seminar on using computer (2) Training on execution method of air passenger flow survey (3) Overseas training on airport planning (4) Employment of local Consultants for soil/topo survey work		①									
	233,054 (¥'000)																		
Total																			
Contracted	221,324																		

和名 中部ジャワ・ジョグジャカルタ空港整備計画

{F/S,(M/P)+F/S,D/D}

PROJECT SUMMARY (F/S)

ASE IDN/S 331/86

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																					
1.COUNTRY	Indonesia	1.SITE OR AREA				1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing																				
2.NAME OF STUDY		Surabaya and Banjarmasin																									
Surabaya-Banjarmasin Submarine Cable Project		2.PROJECT COST				(Description) Jan.1987 OECF loan agreement (7,946 million yen) Detailed design undertaken by KDD. Dec.1989 Construction contract signed May 1990 Construction started Feb.1992 Construction completed																					
		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;"></td> <td style="width: 10%;"></td> <td style="width: 10%; text-align: center;">Total Cost</td> <td style="width: 10%; text-align: center;">Local Cost</td> <td style="width: 10%; text-align: center;">Foreign Cost</td> </tr> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">1)</td> <td style="text-align: center;">57,000</td> <td style="text-align: center;">2,000</td> <td style="text-align: center;">55,000</td> </tr> <tr> <td style="text-align: center;">(US\$1=125Yen)</td> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">3)</td> <td></td> <td></td> <td></td> </tr> </table>								Total Cost	Local Cost	Foreign Cost	(US\$1,000)	1)	57,000	2,000	55,000	(US\$1=125Yen)	2)					3)			
		Total Cost	Local Cost	Foreign Cost																							
(US\$1,000)	1)	57,000	2,000	55,000																							
(US\$1=125Yen)	2)																										
	3)																										
3.SECTOR		3.CONTENTS OF MAJOR PROJECT(S)																									
Communications & Broadcasting/Telecommunication		(1) Optical Fiber Submarine Cable System(280M bit/s) Optical fiber submarine cable(390 km), submersible repeaters, Terminal equipment, power supply equipment (2) Digital Microwave Radio System (3) Power Supply Equipment Engine generator for large capacity, three diesel engine generators (4) Buildings and Site Land <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;"></td> <td style="width: 10%; text-align: center;">[Station Buid.]</td> <td style="width: 10%; text-align: center;">[Site Land]</td> <td style="width: 10%; text-align: center;">[Access Road]</td> </tr> <tr> <td>Bumi Anyar</td> <td style="text-align: center;">104sq.m</td> <td style="text-align: center;">1,200sq.m</td> <td style="text-align: center;">not necessary</td> </tr> <tr> <td>Murbulanqan</td> <td style="text-align: center;">15sq.m</td> <td style="text-align: center;">300sq.m</td> <td style="text-align: center;">Ground leveling for about 50m is necessary.</td> </tr> <tr> <td>Takisung</td> <td style="text-align: center;">104sq.m</td> <td style="text-align: center;">1200sq.m</td> <td style="text-align: center;">not necessary</td> </tr> </table> (5) Ocean Earthing (6) Stacking							[Station Buid.]	[Site Land]	[Access Road]	Bumi Anyar	104sq.m	1,200sq.m	not necessary	Murbulanqan	15sq.m	300sq.m	Ground leveling for about 50m is necessary.	Takisung	104sq.m	1200sq.m	not necessary				
	[Station Buid.]	[Site Land]	[Access Road]																								
Bumi Anyar	104sq.m	1,200sq.m	not necessary																								
Murbulanqan	15sq.m	300sq.m	Ground leveling for about 50m is necessary.																								
Takisung	104sq.m	1200sq.m	not necessary																								
4.REFERENCE NO.																											
5.TYPE OF STUDY		F/S																									
6.COUNTERPART AGENCY																											
POSTEL, PERUMTEL																											
7.OBJECTIVES OF STUDY																											
To examine technical and economical/financial Feasibilities of Surabaya-Banjarmasin submarine cable project																											
8.DATE OF S/W		Imp. Period: Apr.1984-Dec.1996																									
Feb.1985																											
9.CONSULTANT(S)		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: EIRR1) 18.90 FIRR1) 17.10 EIRR2) FIRR2) EIRR3) FIRR3)																							
Nippon Telecommunication Consulting Co., Ltd. Kokusai Denshin Denwa Co, Ltd. Sanyo Hydrographic Survey Co., Ltd.		Yes																									
		Conditions and Development Impacts: Conditions: IRR calculated based on: (1) 3,960 ch(280 Mbps) Submarine cable system (2) System life time; 25 years																									
10.STUDY TEAM		Development Impacts: (1) Improvement in toll traffic between Kalimantan and Jawa Island. (2) Expansion of ground transmission system. (3) Introduction of new technology. (4) Improvement and expansion of telecommunication system.																									
No.of Members 30																											
Period Dec.1985-Aug.1986(9 months)																											
Total M/M		Japan																									
48.42		21.13																									
		Field																									
		27.29																									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER																									
		(1) Trainee acceptance; 2 counterparts studied marine cable system (2) On the job training (PERUMTEL counterparts)																									
12.EXPENDITURE		3.PRINCIPAL SOURCE OF INFORMATION																									
Total 247,184 (¥'000)		①④																									
Contracted 236,165																											

和名 スラバヤ-バンジャルマシン海底ケーブル建設計画

{F/S,(M/P)+F/S,D/D}

PROJECT SUMMARY (M/P)

ASE IDN/S 119/87

Compiled Mar.1990

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS	
1.COUNTRY	Indonesia	1.SITE OR AREA	Jakarta metropolitan area		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
2.NAME OF STUDY	Arterial Road System Development Study in Jakarta Metropolitan Area	2.PROJECT COST	Total Cost Local Cost Foreign Cost		(Description) Japanese Government mission visited Indonesia in 1988 and agreed to carry out a feasibility study. The JICA contact mission was to be sent in Feb.1989, but the formal request from the Indonesian Government had been held up awaiting the adjustment between the Ministry of Public Works and the municipal government of Jakarta City and the clearance on the project's relationship with the on-going mass transit system development. The Indonesian Government requested JICA for the feasibility study in 1992, and the F/S on the East-West corridor and the North-South corridor began in March, 1993.	
3.SECTOR	Transportation/Road	(US\$1,000)				
4.REFERENCE NO.		US\$1=1,648Rp.				
5.TYPE OF STUDY	M/P	1)				
6.COUNTERPART AGENCY	Ministry of Public Works	2)				
7.OBJECTIVES OF STUDY	Arterial Road System Development Study in Jakarta Metropolitan Area.	3.CONTENTS OF MAJOR PROJECT(S)				
8.DATE OF S/W	Jun.1984	7 types of arterial road development programs were recommended from the viewpoint of future urban formulation and transportation development strategies.				
9.CONSULTANT(S)	Pacific Consultants International	1) Medium/Mass Transportation Corridor Development Program 6 routes (595,560 million) 2) Major Arterial Street Development Program: 7 routes (240,957 million) 3) Arterial Street Development Program in the Newly Urbanized Area 22 routes (18,424 million) 4) Present Traffic Problem Oriented Program: 12 routes (354,454 million) 5) East-West Connection Improvement Program: 2 routes (38,363 million) 6) North-South Axis Strengthening Program: 2 routes (40,685 million) 7) Freeway Development Program: 5 routes (1,665,089 million)				
10.STUDY TEAM	No.of Members 15 Period Nov.1984-Sep.1987 (35 months)	Total Cost: 3,253.5 billion Rupiah Note: Investment costs are in 1987 price.				
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Person Trip Survey	4.CONDITIONS AND DEVELOPMENT IMPACTS				
12.EXPENDITURE		Development Impacts: 1) The east-west corridor including medium/mass transit would establish the desirable urban structure. 2) Increasing transportation capacity of the north-south axis, which is congested with excessive traffic demand, would increase transportation efficiency. 3) Giving higher accessibility between C.B.D. and activity centers would enhance center development. 4) Proper arrangement of arterial streets/collector streets/local streets would form desirable urban units.				
Total	798,675 (¥'000)	5. TECHNICAL TRANSFER			2.MAJOR REASONS FOR PRESENT STATUS	
Contracted	791,363	(1) JICA's training for counterpart staff on urban traffic planning; (2) Ministry of Public Works employed most of the graduate students who worked for the survey			3.PRINCIPAL SOURCE OF INFORMATION	
					①	

和名 ジャカルタ首都圏幹線道路網整備計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/S 121/87

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																					
1.COUNTRY	Indonesia	1.SITE OR AREA	Whole country of Indonesia		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued																				
2.NAME OF STUDY Future Demand of the Inter-Island Traffic		2.PROJECT COST			(Description) Based on the findings of the study, the Directorate General of Air Communication (DGAC) requested to the Japanese Government a M/P study on the rehabilitation of major airports and the study was completed in 1991. Other related requests were as follows. - DGAC requested a master plan study on national telecommunication system development. - DGAC requested OECF for the study on Ujung Pandang Airport Development. - BBTP and IPTN (an Indonesian airplane manufacturer) are considering to request a study on feeder air routes. - DGAC requested OECF for the study on Surabaya Airport Development.																					
3.SECTOR Transportation/Air Transportation & Airport		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 15%; text-align: center;">Foreign Cost</td> </tr> <tr> <td>(US\$1,000)</td> <td>1)</td> <td style="text-align: center;">800</td> <td></td> <td></td> </tr> <tr> <td></td> <td>2)</td> <td></td> <td></td> <td></td> </tr> </table>							Total Cost	Local Cost	Foreign Cost	(US\$1,000)	1)	800				2)								
		Total Cost	Local Cost	Foreign Cost																						
(US\$1,000)	1)	800																								
	2)																									
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)																								
5.TYPE OF STUDY M/P		<p>Indonesia was divided into 7 regions (primary zones) in order to forecast inter-regional traffic demand. The main objective is to derive and present the future development project and the direction for introduction of appropriate aircraft types. To this end, a methodology was used that the primary zones were subdivided into 181 zones to make a detailed demand forecast.</p> <p>According to this detailed demand forecast, realistic new-air routes were extracted and incorporated with the existing air network to forecast the future air passenger traffic. At the same time, the study incorporated the study of airport facilities, air navigational system, telecommunication system as well as fundamental specifications into the analysis of demand forecast of appropriate aircraft (seat number, operational cost, airports to be used and routes distance) were carried out and fed back to the future air traffic demand forecast, taking into account the characteristics of the air routes.</p>																								
6.COUNTERPART AGENCY Assessment and Application of Technology (BBTP)		4.CONDITIONS AND DEVELOPMENT IMPACTS																								
7.OBJECTIVES OF STUDY Air Transport		<p>10 routes for 1994 and 10 for 2004 as the realistic new trunk routes and 13 routes for 1994 and 19 routes for 2004 as the realistic new feeder routes were selected by extracting the O-D data for passengers and cargo of major airports, local airports, trunk routes and feeder routes.</p> <p>It is the first time for Indonesia to conduct such a soft-ware study as this kind, and the Study was appreciated to be attributable to the development plan for an aeronautical system as a whole.</p> <p>Since this kind of study is essential prior to plan to develop an airport, the Study would have a great impact on the other transport system than the air.</p> <p>It is assumed that more soft-ware projects of this kind will be generated in future.</p>																								
8.DATE OF S/W Jun.1986		10.STUDY TEAM																								
9.CONSULTANT(S) Nihon Koel Co., Ltd. Central Consultant, Inc.		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;">No.of Members</td> <td style="width: 15%;">11</td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td>Period</td> <td>Dec.1986-Mar.1988 (16 months)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>Total M/M</td> <td>61.14</td> <td>Japan</td> <td>14.10</td> <td>Field</td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td>47.04</td> </tr> </table>					No.of Members	11				Period	Dec.1986-Mar.1988 (16 months)				Total M/M	61.14	Japan	14.10	Field					47.04
No.of Members	11																									
Period	Dec.1986-Mar.1988 (16 months)																									
Total M/M	61.14	Japan	14.10	Field																						
				47.04																						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5.TECHNICAL TRANSFER																								
12.EXPENDITURE		3.PRINCIPAL SOURCE OF INFORMATION																								
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;">Total</td> <td style="width: 15%;">218,319 (¥'000)</td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td>Contracted</td> <td>171,077</td> <td></td> <td></td> <td></td> </tr> </table>		Total	218,319 (¥'000)				Contracted	171,077				Counterparts of BBTP, IPTN as well as DGCA were positively asked to join in the study work in conjunction with the process of the work. It was also noted that the trainees														
Total	218,319 (¥'000)																									
Contracted	171,077																									
		2.MAJOR REASONS FOR PRESENT STATUS																								
		It has been a common practice for any developed country in the world to plan an aeronautical development under a basic plan in view of soft-ware study before carrying out development of an airport. It is assumed that there become a tendency also in Indonesia to carry out a development project under such a concept.																								

和名 島嶼間交通需要予測

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/S 120/87

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																	
1.COUNTRY	Indonesia	1.SITE OR AREA	Two Kabupatens of Serang and Pandeglang and the Krakatau Islands of Kab.Lampung Selatan		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued																
2.NAME OF STUDY	Regional Development Project in the Western Part of Java	2.PROJECT COST	<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">(US\$1,000)</th> <th style="text-align: center;">Total Cost</th> <th style="text-align: center;">Local Cost</th> <th colspan="2" style="text-align: center;">Foreign Cost</th> </tr> </thead> <tbody> <tr> <td>1)</td> <td style="text-align: center;">7,000</td> <td style="text-align: center;">6,150</td> <td colspan="2" style="text-align: center;">850</td> </tr> <tr> <td>2)</td> <td style="text-align: center;">133,700</td> <td style="text-align: center;">96,600</td> <td colspan="2" style="text-align: center;">37,100</td> </tr> </tbody> </table>			(US\$1,000)	Total Cost	Local Cost	Foreign Cost		1)	7,000	6,150	850		2)	133,700	96,600	37,100		(Description) The Directorate General of Tourism(DGT) is examining the possibility of obtaining OECF financing and/or private sector investments. Actually, small-scale tourism development projects are carried out by private investors. (FY 1992 Overseas Survey) Waiting for the answer.	
(US\$1,000)	Total Cost	Local Cost	Foreign Cost																			
1)	7,000	6,150	850																			
2)	133,700	96,600	37,100																			
3.SECTOR	Tourism/General	3.CONTENTES OF MAJOR PROJECT(S)																				
4.REFERENCE NO.		Following six(6) projects were proposed as promising tourism projects for the period through 2010. (1) Old Banten Site (Priority project) - Main facilities: Restoration of the old moats, Museum, Bird sanctuary, Heritage garden, etc. - Construction cost: Rp. 11.5 billion (2) Beach Resort(priority project) - Main facilities: Marina, International standard hotels & condominiums, Golf ground, etc. - Development cost: Rp.219 billion (total) (Stage 1: Rp.115 billion/ Stage 2: Rp.104 billion) (3) Tropical Marine Park - Main facilities: Aquarium, Dolphin show pool, Maritime museum, etc. (4) Ujung Kulon and Krakatan Islands - Main facilities: Guest house, Jetties, Observation towers, Camping grounds, Sea garden, etc. (5) Country park - Main facilities: Camping site, Sports fields, Gymnasium, Model farm, etc. (6) Kur Park - Main facilities: Hotel & Restaurant, Swimming pool, Open air theater, etc.																				
5.TYPE OF STUDY	M/P																					
6.COUNTERPART AGENCY	Development of Tourism, Post and Tele-communication, Directorate General of Tourism																					
7.OBJECTIVES OF STUDY	Formulation of a Master Plan of tourism projects to promote regional development																					
8.DATE OF S/W	Feb.1986	4.CONDITIONS AND DEVELOPMENT IMPACTS			2.MAJOR REASONS FOR PRESENT STATUS																	
9.CONULTANT(S)	Nihon Koei Co., Ltd. Mitsubishi Research Institute	Development Impacts: (1) Foreign exchange earning, (2) Recreational benefits for people, (3) Improvement of living standard of the people. Old Banten Site -Foreign exchange earning: Rp.5.4 million (in the operation year of 1994) Rp.8 million (in the target year of 2010) -Job opportunity: About 1 million men-days (construction period) 273 persons (operation period) -Multiplier effects: Rp.20 billion (investment inducing effects) Rp.76.1 billion (income generating effects) Beach Resort -Foreign exchange earning: US\$9.2 million (1995) US\$68.4 million (2010) -Job opportunity: 7 million men-days (construction period) 2,443 persons (operation period) -Multiplier effects: Rp.374.6 billion (investment inducing effects) Rp.6,923.0 billion (income generating effects)																				
10.STUDY TEAM		5. TECHNICAL TRANSFER			3.PRINCIPAL SOURCE OF INFORMATION																	
No.of Members 12 Period Jul.1986-Feb.1988 (20 months) <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Total M/M</th> <th style="text-align: center;">Japan</th> <th style="text-align: center;">Field</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">89.94</td> <td style="text-align: center;">39.66</td> <td style="text-align: center;">50.28</td> </tr> </tbody> </table>							Total M/M	Japan	Field	89.94	39.66	50.28										
Total M/M	Japan	Field																				
89.94	39.66	50.28																				
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		(1) On the job training for local counterparts (2) Training in Japan for 4 principal counterparts (3) Conduct of tourism resources survey by entrusting it to the local consu			①																	
12.EXPENDITURE																						
<table style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td style="text-align: right;">Total</td> <td style="text-align: right;">273,586 (¥'000)</td> </tr> <tr> <td style="text-align: right;">Contracted</td> <td style="text-align: right;">265,285</td> </tr> </tbody> </table>		Total	273,586 (¥'000)	Contracted	265,285																	
Total	273,586 (¥'000)																					
Contracted	265,285																					

和名 ジャワ西部地域開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/A 103/87

Compiled Mar.1991
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																
1.COUNTRY	Indonesia	1.SITE OR AREA			1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued															
2.NAME OF STUDY		Soybean ----- East Java Potato ----- West Java			(Description) Improvement of the farm for foundation seed potatoes was completed with the FY1992 grant aid of Japan. The Ministry of Agriculture has been keen to implement the soybean seed project by Japanese assistance. A JICA expert has been examining the necessary steps toward implementation.																
Multiplication and Distribution of Improved Soybean Seed and Seed Potato		2.PROJECT COST																			
3.SECTOR		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">(US\$1,000)</td> <td></td> <td style="text-align: center;">Total Cost</td> <td style="text-align: center;">Local Cost</td> <td style="text-align: center;">Foreign Cost</td> </tr> <tr> <td></td> <td style="text-align: center;">1)</td> <td style="text-align: center;">4,730</td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td style="text-align: center;">11,486</td> <td></td> <td></td> </tr> </table>					(US\$1,000)		Total Cost	Local Cost	Foreign Cost		1)	4,730				2)	11,486		
(US\$1,000)		Total Cost	Local Cost	Foreign Cost																	
	1)	4,730																			
	2)	11,486																			
Agriculture/General		3.CONTENT'S OF MAJOR PROJECT(S)																			
4.REFERENCE NO.		To reinforce followings in order to produce seeds for soybeans and potatoes 1.Fostering seed producing farmers 2.Improving seed processing and storage facilities 3.Promoting seed distribution 4.Strengthening administration system for seed multiplication and distribution 1) Field for foundation seed/registered seed 2) Seed inspection 3) Training activities (Note) Cost 1) is for soybeans and Cost 2 for potatoes																			
5.TYPE OF STUDY																					
M/P																					
6.COUNTERPART AGENCY																					
Crop production Bureau, Ministry of Agriculture		4.CONDITIONS AND DEVELOPMENT IMPACTS																			
7.OBJECTIVES OF STUDY		Conditions: 1.Pertinent organization and disposition of personnel 2.Financial assistance(Raise operating fund) 3.Administrative Coordination(Research & Administration) 4.Securing necessary land Development Impacts: 1.Increase of agricultural production and resultant increase of farmers' income by the introduction of better seeds and their stable supply (ordinary farmers and seed producing farmers) 2.Contribute to the self-sufficiency of food																			
Multiplication and distribution of improved Soybean Seed and Seed Potato																					
8.DATE OF S/W																					
Mar.1987																					
9.CONSULTANT(S)																					
Overseas Merchandise Inspection Co., Ltd.																					
10.STUDY TEAM																					
No.of Members 6 Period Jul.1987-Sep.1987(3 months)																					
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">24.24</td> <td style="text-align: center;">8.49</td> <td style="text-align: center;">15.75</td> </tr> </table>		Total M/M	Japan	Field	24.24	8.49	15.75														
Total M/M	Japan	Field																			
24.24	8.49	15.75																			
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		2.MAJOR REASONS FOR PRESENT STATUS																			
		As the result of this study, the project for potatoes started ahead soybeans. After its completion the project for modernization of soybean seed production is to start.																			
12.EXPENDITURE		3.PRINCIPAL SOURCE OF INFORMATION																			
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: center;">73,445 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td></td> </tr> </table>		Total	73,445 (¥'000)	Contracted		①															
Total	73,445 (¥'000)																				
Contracted																					

和名 主要食用作物生産振興計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (F/S)

ASE IDN/S 332/87

Compiled Mar.1990

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																					
1.COUNTRY	Indonesia	1.SITE OR AREA		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 15%; text-align: center;">Foreign Cost</td> </tr> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">46,900</td> <td style="text-align: center;">12,100</td> <td style="text-align: center;">34,800</td> </tr> </table>			Total Cost	Local Cost	Foreign Cost	(US\$1,000)	46,900	12,100	34,800	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;">1.PRESENT STATUS</td> <td style="width: 15%;"><input checked="" type="checkbox"/> Completed or in Progress</td> <td style="width: 15%;"><input type="checkbox"/> Promoting</td> </tr> <tr> <td></td> <td><input type="checkbox"/> Completed</td> <td><input type="checkbox"/> Delayed or Suspended</td> </tr> <tr> <td></td> <td><input type="checkbox"/> Implementing</td> <td><input type="checkbox"/> Discontinued or Cancelled</td> </tr> <tr> <td></td> <td><input checked="" type="checkbox"/> Processing</td> <td></td> </tr> </table>		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress	<input type="checkbox"/> Promoting		<input type="checkbox"/> Completed	<input type="checkbox"/> Delayed or Suspended		<input type="checkbox"/> Implementing	<input type="checkbox"/> Discontinued or Cancelled		<input checked="" type="checkbox"/> Processing	
	Total Cost	Local Cost	Foreign Cost																								
(US\$1,000)	46,900	12,100	34,800																								
1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress	<input type="checkbox"/> Promoting																									
	<input type="checkbox"/> Completed	<input type="checkbox"/> Delayed or Suspended																									
	<input type="checkbox"/> Implementing	<input type="checkbox"/> Discontinued or Cancelled																									
	<input checked="" type="checkbox"/> Processing																										
2.NAME OF STUDY Solid Waste Management System Improvement Project in the City of Jakarta		2.PROJECT COST (US\$1,000)																									
3.SECTOR Public Utilities/Urban Sanitation		3.CONTENTES OF MAJOR PROJECT(S)				(Description) OECF agreed to the E/S Loan IP-366 (L/A in Dec. 1990 for 270 million yen). However, the site for the solid waste transfer station was reassigned for housing development. As of Dec. 1990, the city authorities of Jakarta is still looking for an alternative site for the station, delaying the start of E/S. The Engineering Services on the Jakarta Solid Waste Management System Improvement Project was started by the consultant who was employed by the Indonesian Government under the OECF Loan from December 1991. The site for the solid waster transfer station is designated in Kelurahan Sunter, North Jakarta. The site is approximately 70m width and 900m length. The solid waste final disposal site is designated in Zone 2 of the Bekasi disposal site in Bander Gebang, Bekasi. The Ministry of Public Works has asked through BAPPENAS to obtain an OECF loan for the project implementation in the 1992/93 fiscal year.																					
4.REFERENCE NO.		5.TYPE OF STUDY																									
5.TYPE OF STUDY		F/S																									
6.COUNTERPART AGENCY Ministry of Public Works, Jakarta Municipality, Department of Human Settlements		6.COUNTERPART AGENCY																									
7.OBJECTIVES OF STUDY Master plan for improvement of solid waster management system, and feasibility study for the first priority project		7.OBJECTIVES OF STUDY																									
8.DATE OF S/W		Sep.1984		Imp. Period: Apr.1990-Mar.1992																							
9.CONSULTANT(S) Yachiyo Engineering Co., Ltd. EX Cor.		4.FEASIBILITY AND ITS ASSUMPTIONS		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;">Feasibility:</td> <td style="width: 15%; text-align: center;">EIRR1)</td> <td style="width: 15%; text-align: center;">6.30</td> <td style="width: 15%; text-align: center;">FIRR1)</td> </tr> <tr> <td style="text-align: center;">Yes</td> <td style="text-align: center;">EIRR2)</td> <td></td> <td style="text-align: center;">FIRR2)</td> </tr> <tr> <td></td> <td style="text-align: center;">EIRR3)</td> <td></td> <td style="text-align: center;">FIRR3)</td> </tr> </table>		Feasibility:	EIRR1)	6.30	FIRR1)	Yes	EIRR2)		FIRR2)		EIRR3)		FIRR3)										
Feasibility:	EIRR1)	6.30	FIRR1)																								
Yes	EIRR2)		FIRR2)																								
	EIRR3)		FIRR3)																								
10.STUDY TEAM		10.STUDY TEAM				2.MAJOR REASONS FOR PRESENT STATUS Although the procedures for E/S loan for fiscal year 1988 was prepared, the application was not made due to the financial situation of Indonesia. The E/S for the Project was financed under OECF Loan in fiscal year of 1990/91. E/S, LA OECF Loan IP-366 in December 1990. 271 million yen.																					
No.of Members 13 Period Dec.1985-Nov.1987 (24 months)		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%; text-align: center;">Japan</td> <td style="width: 15%; text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">36.90</td> <td style="text-align: center;">61.03</td> </tr> <tr> <td style="text-align: center;">97.93</td> <td></td> <td></td> </tr> </table>			Japan			Field	Total M/M	36.90	61.03	97.93															
	Japan	Field																									
Total M/M	36.90	61.03																									
97.93																											
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY Topographic survey analysis for specimen arrangement of equipment for collection and equipment		11.ASSOCIATED AND/OR SUBCONTRACTED STUDY																									
12.EXPENDITURE		12.EXPENDITURE				3.PRINCIPAL SOURCE OF INFORMATION ①																					
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%; text-align: center;">286,706 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Total</td> <td></td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">279,747</td> </tr> </table>			286,706 (¥'000)	Total				Contracted	279,747	(1) Training on waste disposal technology in Japan for four counterparts; (2) Lessons were given on large drying furnace for waste quality analysis and method for waste quality analysis																	
	286,706 (¥'000)																										
Total																											
Contracted	279,747																										

和名 ジャカルタ市都市廃棄物整備計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

Compiled Mar.1990

Revised Mar.1992

ASE IDN/S 333/87

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA		Jakarta and Padang, Medan and Banda Aceh		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY	Trans-Sumatera Terrestrial Digital Transmission System	2.PROJECT COST		Total Cost	Local Cost		
3.SECTOR	Communications & Broadcasting/Telecommunication			(US\$1,000) 1) 61,000	100	60,900	
4.REFERENCE NO.				(US\$1=125Yen) 2)			
5.TYPE OF STUDY	F/S			3)			
6.COUNTERPART AGENCY	POSTEL, PT. TELKOM	3.CONTENTS OF MAJOR PROJECT(S)		Contents Scale Digitalization of Switching system 2,690 L.U.(1994) Digitalization of Transmission system same above			
7.OBJECTIVES OF STUDY	To verify technical and economic feasibility for trans-Sumatra Terrestrial Digital Transmission System and links major cities in Sumatra Island and Jakarta						
8.DATE OF S/W	Nov.1986	Imp. Period: .1989-.1991		4.FEASIBILITY AND ITS ASSUMPTIONS Feasibility: Yes EIRR1) 23.00 FIRR1) 25.00 EIRR2) FIRR2) EIRR3) FIRR3)			
9.CONSULTANT(S)	Nippon Telecommunication Consulting Co., Ltd. Yachiyo Engineering Co., Ltd. Nippon Sogo Architects and Engineers						
10.STUDY TEAM	No. of Members 13 Period Jan.1987-Mar.1988 (14 months)			Conditions and Development Impacts: -Assumption of IRR computation is to put practical use of existing route, JKT-MDN (1994) and MDN-BNA -Development impacts: By the digitalization of telecommunication network for Sumatra island, corresponding to possible all new services.			
	Total M/M Japan Field 39.39 17.16						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER		2.MAJOR REASONS FOR PRESENT STATUS (1) Effectiveness (2) High priority			
12.EXPENDITURE	Total 145,950 (¥'000) Contracted 140,023						
				3.PRINCIPAL SOURCE OF INFORMATION ①			

和名 スマトラ縦断幹線伝送路整備計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P)

ASE IDN/S 123/88

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS	
1.COUNTRY	Indonesia	1.SITE OR AREA	The entire sea around Indonesia and major ports		1.PRESENT STATUS	<input type="checkbox"/> In Progress or In Use <input checked="" type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
2.NAME OF STUDY	Maritime Safety Plan Concerning Search and Rescue	2.PROJECT COST			Total Cost	
3.SECTOR	Transportation/Marine Transportation & Ships		(US\$1,000)	1) 643,500	2)	(Description) The Government of Indonesia is preparing to apply to either the OECF yen credit or to the Japanese grant aid program.
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)				
5.TYPE OF STUDY	M/P	- Procurement of search and rescue vessels and establishment of telecommunication between the vessels and coastal stations - Establishment of a training center - Improvement of port traffic control systems (Jakarta and Surabaya)				
6.COUNTERPART AGENCY	Directorate General of Sea Communications, Ministry of Communications	4.CONDITIONS AND DEVELOPMENT IMPACTS				
7.OBJECTIVES OF STUDY	Development of the maritime safety and search and rescue system	With the introduction of search and rescue boats, the improvement of communication and manpower training, the project will increase the country's capability of coping with maritime accidents. The better port traffic control will considerably reduce the occurrence of maritime accidents.				
8.DATE OF S/W	Feb.1987	10.STUDY TEAM				
9.CONSULTANT(S)		No.of Members 11 Period Oct.1987-Dec.1988 (17 months)				
		Total M/M	Japan	Field		
		67.60	36.90	30.70		
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5.TECHNICAL TRANSFER			2.MAJOR REASONS FOR PRESENT STATUS	
12.EXPENDITURE					3.PRINCIPAL SOURCE OF INFORMATION	
		Total	210,629 (¥'000)		①	
		Contracted	197,260			

和名 海難搜索救助並びに海難予防体制整備計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/S 122/88

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																
1.COUNTRY	Indonesia	1.SITE OR AREA	Ujung Pandang City and its adjacent area, South Sulawesi		1.PRESENT STATUS	<input type="checkbox"/> In Progress or In Use <input checked="" type="checkbox"/> Delayed <input type="checkbox"/> Discontinued															
2.NAME OF STUDY		2.PROJECT COST			(Description) Road rehabilitation in Ujung Pandang City area was included in the project list for the loan of OECF in 1991. Indonesian Government ranks the project low in priority.																
Ujung Pandang Area Highway Development Study		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 15%; text-align: center;">Foreign Cost</td> </tr> <tr> <td>(US\$1,000)</td> <td style="text-align: center;">1)</td> <td style="text-align: center;">144,194</td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> </table>							Total Cost	Local Cost	Foreign Cost	(US\$1,000)	1)	144,194				2)			
		Total Cost	Local Cost	Foreign Cost																	
(US\$1,000)	1)	144,194																			
	2)																				
3.SECTOR		3.CONTENTES OF MAJOR PROJECT(S)																			
Transportation/Urban Transportation		The study proposed a master plan for traffic control in Ujung Pandang City and the development of radial roads.																			
4.REFERENCE NO.		1. Short-term Plan (total cost Rp19,261 million) Road Widening (15,850m); Intersection Imprv.(19 locations); Road Rehab.(14 routes); Pedestrian Facilities Imprv.(29 routes); Bus Facilities Imprv.(196 locations); Becak Transport Imprv.(2 routes); and Traffic Regulation Imprv.(4 locations)																			
5.TYPE OF STUDY		2. Long-term Plan 1st Stage (up to 1994) (total cost Rp58,395 million) Inner Ring Road Constr.(9.95km); Jl. Gowa Jaya Widening (27km); Jl. Gowa Raya Widening (6.55km); Jl. Toll Road Widening (11.5km); and Industrial Access Road Constr. (3.25km) (Total 58.25km)																			
6.COUNTERPART AGENCY		3. Long-term Plan. 2ndt Stage (up to 2009) (total cost Rp171,944 million) Inner Ring Road Constr.(9.95km); Middle Ring Road Constr.(12.95km); Outer Ring Road Constr.(17.1km); Central Radial Road Constr.(8.75km); South Radial Road Constr. (5.71km); Jl. Gowa Jaya Widening (27km); Jl. Gowa Raya Widening (6.55km); and Jl. Toll Road Widening (11.5km) (Total 99.48km)																			
7.OBJECTIVES OF STUDY		4.CONDITIONS AND DEVELOPMENT IMPACTS																			
Road network development		The residential areas have been sprawling toward the outlying areas of the city, but the development of necessary infrastructure has been inadequate relative to the rapid increase of the population. The proposed project will contribute effectively to the development of residential areas. The project will also provide the functional linkages between the port, the industrial estate and the airport, thereby contributing the growth of the Ujung Pandang area.																			
8.DATE OF S/W		5. TECHNICAL TRANSFER																			
Jun.1987		On-the-job training for the counterparts on the computerized method of traffic demand projection.																			
9.CONSULTANT(S)		6.MAJOR REASONS FOR PRESENT STATUS																			
Central Consultant, Inc. Chodal Co., Ltd.		Indonesian Government ranked low with this project.																			
10.STUDY TEAM		7.PRINCIPAL SOURCE OF INFORMATION																			
No.of Members 9 Period Nov.1987-Mar.1989(16 months)		①																			
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">50.39</td> <td style="text-align: center;">8.24</td> <td style="text-align: center;">42.15</td> <td></td> <td></td> </tr> </table>							Total M/M	Japan	Field			50.39	8.24	42.15							
Total M/M	Japan	Field																			
50.39	8.24	42.15																			
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY																					
12.EXPENDITURE																					
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td style="text-align: center;">Total</td> <td style="text-align: center;">167,217 (¥'000)</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">160,498</td> <td></td> <td></td> <td></td> </tr> </table>							Total	167,217 (¥'000)				Contracted	160,498								
Total	167,217 (¥'000)																				
Contracted	160,498																				

和名 ウジュンパンダン都市圏道路網整備計画

(M/P,M/P+(F/S),Basic Study,Other)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 214A/88

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS														
1.COUNTRY	Indonesia	1.SITE OR AREA	Bandung (study area of 1,771 sq.km)		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued													
2.NAME OF STUDY	Flood Control Plan of the Upper Citarum Basin	2.PROJECT COST			<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">1)</td> <td style="text-align: center;">Total Cost</td> <td style="text-align: center;">Local Cost</td> <td style="text-align: center;">Foreign Cost</td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td style="text-align: center;">72,868</td> <td style="text-align: center;">18,161</td> <td style="text-align: center;">54,707</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">(US\$1=1,655Rp.)</td> <td></td> <td></td> </tr> </table>		(US\$1,000)	1)	Total Cost	Local Cost	Foreign Cost		2)	72,868	18,161	54,707			(US\$1=1,655Rp.)
(US\$1,000)	1)	Total Cost	Local Cost	Foreign Cost															
	2)	72,868	18,161	54,707															
		(US\$1=1,655Rp.)																	
3.SECTOR	Social Infrastructures/River & Erosion Control	3.CONTENTES OF MAJOR PROJECT(S)			(Description) A feasibility study was subsequently conducted on the urgent projects.														
4.REFERENCE NO.		1. Outline of the Plan: River improvement by dredging/excavation was proposed for the Citarum River system, from Curug Jompong Fall (downstream end) to the upstream end of the maximum flood area in 1986, including the Cisanqkuy, Citarik and Cikeruh rivers. The river improvement, with design flood of 20 years return period, is expected to reduce the flood damage within the flood area of 7,249 ha. Land use regulation and flood forecasting/warning system for the remaining flood area were proposed. 2. Short Term Program(1992-1995) (Rp. 101.7 billion) An urgent project including the river improvements of Citarum River from Curug Jompong to Sapan(center of flood area) and Cisanqkuy River with the design flood of 5 years return period, land use regulation and flood forecasting / warning system was proposed. 3. Long Term Program(1996-2005), (Rp.150 Billion) River improvement of the all rivers, with the design flood of 20 years return period, from Curug Jompong to upstream end of the flood area was proposed. * The budgets mentioned above are based on the 1987 price level.																	
5.TYPE OF STUDY	M/P+ (F/S)																		
6.COUNTERPART AGENCY	Directorate of Rivers (DOR), Directorate General of Water Resource Development (DGWRD)																		
7.OBJECTIVES OF STUDY	Formulation of a master plan through 2005 and identification and evaluation of urgent flood control projects																		
8.DATE OF S/W	Dec.1986																		
9.CONSULTANT(S)	Pacific Consultants International																		
10.STUDY TEAM	No.of Members 11 Period May.1987-Dec.1988(20 months)																		
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">57.44</td> <td style="text-align: center;">17.13</td> <td style="text-align: center;">40.31</td> </tr> </table>							Total M/M	Japan	Field	57.44	17.13	40.31							
Total M/M	Japan						Field												
57.44	17.13	40.31																	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Geological survey Installation of hydrological meters																		
12.EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: right;">203,741 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: right;">187,711</td> </tr> </table>	Total	203,741 (¥'000)	Contracted	187,711														
Total	203,741 (¥'000)																		
Contracted	187,711																		
		4.CONDITIONS AND DEVELOPMENT IMPACTS			2.MAJOR REASONS FOR PRESENT STATUS														
		Conditions for Economic Evaluation: 1. Benefit is flood damage reduction by lowering flood water level and expressed by the difference in flood damage between without and with the river improvement. 2. Tangible benefits include the flood damage reduction in house, factory, commercial building, paddy field, fish pond, public facility, etc. 3. Base costs are expressed under the socio-economic conditions prevailed in 1987. 4. Annual O/M cost is assumed to be 0.5% of the construction cost for 50 years after completion of the project works.																	
		5. TECHNICAL TRANSFER			3.PRINCIPAL SOURCE OF INFORMATION														
		Effects of the Project: By the river improvement, the maximum flood area of 7,249 ha (by 1.5 year flood) is expected to be reduced to 900 ha by 20 year flood. The results of economic evaluation are as follows: EIRR: 11.6% B/C : 1.18 NPV : Rp.13.1 billion																	
		1) Participation of 3 counterparts in the JICA training program 2) OJT and a seminar			①														

和名 チタルム川上流域洪水防御計画

(M/P,M/P+(F/S),Basic Study,Other)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 214B/88

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT					
1.COUNTRY	Indonesia	1.SITE OR AREA		Bandung (study area of 1,771 sq.km)		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input checked="" type="checkbox"/> Processing				
2.NAME OF STUDY	Flood Control Plan of the Upper Citarum Basin	2.PROJECT COST		Total Cost	Local Cost			Foreign Cost			
3.SECTOR	Social Infrastructures/River & Erosion Control			1) (US\$1,000)	2) 90,321	45,923	44,399				
4.REFERENCE NO.		3.CONTENT(S) OF MAJOR PROJECT(S)		(Description) Dec.1990 OECF loan agreement signed (21.5 billion yen) Part of the loan to be used for Flood Control of the Upper Citarum Basin Jul.1991 - Sep. 1992 D/D undertaken Nov.1992 I/P for construction prepared. 1994 Construction to be started							
5.TYPE OF STUDY	(M/P)+F/S	The F/S proposed an urgent flood control project including, -River improvement of the Citarum and Cisanquy rivers from Curuq Jampong to Sapan in order to reduce the flood damage in the area from Dayeuh Kolot to Sapan where properties concentrate. - Flood forecasting/ warning system for the remaining flood risk area. The major project works, according to the detailed design results made in September 1992, are as follows: 1) River Improvement Works(Citarum River 30.6km, Cisanquy River 6.9km) - Dredging/excavation : 6,030,000 cu.m - Bank protection : 7.9 km - Bridge : 11 places - Inspection/maintenance road : 71 km - Land acquisition : 169 ha - Compensation : 634 houses 2)Telemetering System Works - Six telemetering station at the existing water level gauging stations. - One master station - Monitoring equipment in the existing station. * Above budgets are based on the 1992 price level.									
6.COUNTERPART AGENCY	Directorate of Rivers (DOR), Directorate General of Water Resource Development (DGWRD)	Imp. Period: .1990-.1995						4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	
7.OBJECTIVES OF STUDY	Formulation of a master plan through 2005 and identification and evaluation of urgent flood control projects	EIRR1) 14.10 FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)						Conditions and Development Impacts: Conditions for Economic Evaluation: 1. Benefit is flood damage reduction by lowering flood water level and expressed by the difference in flood damage between without and with the river improvement. 2. Tangible benefits include the flood damage reduction in house, factory, commercial building, paddy field, fish pond, public facility, etc. 3. Base costs are expressed under the socio-economic conditions prevailed in Nov 1991. 4. Annual O/M cost is assumed to be 0.5% of the construction cost for 50 years after completion of the project works. Effects of the Project: By the river improvement, the maximum flood area of 7,249 ha (by 1.5 year flood) is expected to be reduced to 3,160 ha by 5 year flood. The results of economic evaluation are as follows: EIRR: 15.3%, B/C : 1.96, NPV : Rp.121.5 billion Average annual flood damage reduction is estimated to be Rp.42.9 billion.			
8.DATE OF S/W	Dec.1986	10.STUDY TEAM						2.MAJOR REASONS FOR PRESENT STATUS			
9.CONSULTANT(S)	Pacific Consultants International	No.of Members 11 Period May.1987-Dec.1988 (20 months)									
		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;">Total M/M</td> <td style="width: 30%;">Japan</td> <td style="width: 30%;">Field</td> </tr> <tr> <td style="text-align: center;">57.44</td> <td style="text-align: center;">17.13</td> <td style="text-align: center;">40.31</td> </tr> </table>						Total M/M	Japan	Field	57.44
Total M/M	Japan	Field									
57.44	17.13	40.31									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Geological survey Installation of hydrological meters	11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		3.PRINCIPAL SOURCE OF INFORMATION							
12.EXPENDITURE	Total 203,741 (¥'000) Contracted 187,711	5.technical transfer		①④							
		1) Participation of 3 counterparts in the JICA training program 2) OJT and a seminar									

和名 チタルム川上流域洪水防御計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/S 335/88

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA	Southeastern slope (550 sq.km) of Mt.Galunqqng, Kabupaten Tasikmalaya, West Java Province			1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY Disaster Prevention Project in the Southeastern Slope of Mt.Galungung		2.PROJECT COST (US\$1,000)		Total Cost 66,205	Local Cost 30,591		
3.SECTOR Social Infrastructures/River & Erosion Control		3.CONTENTIS OF MAJOR PROJECT(S)				(Description) DGWRD is considering the possible application for OECF financing. (Related Information) In order to maintain the spare capacity of the sand pockets, the Indonesian Government is excavating the accumulated sediment in the sand pocket and transporting these as aggregate construction materials to Jakarta by Indonesia State Railways (PJKA) (as privatization project). However, in order to not sufficient the capacity of railway transportation, JICA dispatched the short term experts for the technical transfer of the implementation planning of such capacity in August 1991. According to the report of JICA Short Term Experts, PURUMKA is considering the actual plan of the implementing transport capacity.	
4.REFERENCE NO.		1) Maintenance of sand pockets (as expansion of the height of wall for existing 12km long sand pocket)					
5.TYPE OF STUDY		2) Stabilization of river channels within the sand pockets (to construct for 12km expansion of the existing dike)					
6.COUNTERPART AGENCY Directorate General of Water Resource Development		3) Construction of 34 Sabo dams in the southern slope 4) Drainage works for the crater lake (to construct new 2m 700m long tunnel) 5) Establishment of the early warning and evacuation system					
7.OBJECTIVES OF STUDY							
8.DATE OF S/W		Mar.1987		Imp. Period:			
9.CONSULTANT(S) Yachiyo Engineering Co., Ltd.		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes		EIRR1) 10.90 FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)	
10.STUDY TEAM		Conditions and Development Impacts: The project will reduce the damages caused by volcanic debris and floods, and contribute to the improvement of land use and living environment for the local inhabitants, creation of employment, and regional economic growth.					
No.of Members 12 Period Jun.1987-Nov.1988 (18 months)						2.MAJOR REASONS FOR PRESENT STATUS	
Total M/M Japan Field 76.28 34.32 41.96							
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY						3.PRINCIPAL SOURCE OF INFORMATION	
Topographic survey (vertical and cross 115km); boring(1-200m; survey of riverbed materials (20 samples)		5.technical transfer				①	
12.EXPENDITURE		OJT on river and erosion control					
Total 238,944 (¥'000)							
Contracted							

和名 ガルンゲン火山防災計画

{F/S,(M/P)+F/S,D/D}

PROJECT SUMMARY (F/S)

ASE IDN/S 337/88

Compiled Mar.1990

Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																									
1.COUNTRY	Indonesia	1.SITE OR AREA		Three beaches of the southern coast of Bali Island		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input checked="" type="checkbox"/> Processing <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled																								
2.NAME OF STUDY		2.PROJECT COST						Total Cost	Local Cost	Foreign Cost																					
Urgent Bali Beach Conservation Project		(US\$1,000)		1) 44,655	10,586	34,089	(Description) Dec.1990 OECF loan agreement signed (E/S, 279 million yen) Nov.1991-Dec.1992 D/D undertaken, and tender documents prepared The total cost of the project is estimated to be 8,585 million yen (US\$59.2 million). The construction is expected to start in 1993 and to be completed in 1996.																								
3.SECTOR		3.CONTENT(S) OF MAJOR PROJECT(S)																													
Social Infrastructures/River & Erosion Control		- Major beach projects are as follows:																													
4.REFERENCE NO.		<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th style="text-align: center;">Kuta</th> <th style="text-align: center;">Nusa Dua</th> <th style="text-align: center;">Sanur 1</th> <th style="text-align: center;">Sanur 2</th> </tr> </thead> <tbody> <tr> <td>Beach Reinforcement length (km)</td> <td style="text-align: center;">2.7</td> <td style="text-align: center;">2.35</td> <td style="text-align: center;">0.7</td> <td style="text-align: center;">4</td> </tr> <tr> <td>width (average, m)</td> <td style="text-align: center;">50</td> <td style="text-align: center;">50</td> <td style="text-align: center;">30</td> <td style="text-align: center;">30</td> </tr> <tr> <td>amount (sq.m)</td> <td style="text-align: center;">783,000</td> <td style="text-align: center;">229,000</td> <td style="text-align: center;">96,000</td> <td style="text-align: center;">352,000</td> </tr> <tr> <td>groins</td> <td colspan="2" style="text-align: center;">4(T-shaped) Extension of 1(straight) existin groin</td> <td style="text-align: center;">3</td> <td style="text-align: center;">4</td> </tr> </tbody> </table>						Kuta	Nusa Dua	Sanur 1	Sanur 2	Beach Reinforcement length (km)	2.7	2.35	0.7	4	width (average, m)	50	50	30	30	amount (sq.m)	783,000	229,000	96,000	352,000	groins	4(T-shaped) Extension of 1(straight) existin groin		3	4
	Kuta	Nusa Dua	Sanur 1	Sanur 2																											
Beach Reinforcement length (km)	2.7	2.35	0.7	4																											
width (average, m)	50	50	30	30																											
amount (sq.m)	783,000	229,000	96,000	352,000																											
groins	4(T-shaped) Extension of 1(straight) existin groin		3	4																											
5.TYPE OF STUDY		- Tanah Lot Conservation using concrete blocks around the island.																													
6.COUNTERPART AGENCY		Imp. Period: Jan.1990-Dec.1994 <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 15%;">4.FEASIBILITY AND ITS ASSUMPTIONS</th> <th style="width: 15%;">Feasibility:</th> <th style="width: 15%;">EIRR1)</th> <th style="width: 15%;">29.50</th> <th style="width: 15%;">FIRR1)</th> </tr> </thead> <tbody> <tr> <td></td> <td style="text-align: center;">Yes</td> <td>EIRR2)</td> <td></td> <td>FIRR2)</td> </tr> <tr> <td></td> <td></td> <td>EIRR3)</td> <td></td> <td>FIRR3)</td> </tr> </tbody> </table>				4.FEASIBILITY AND ITS ASSUMPTIONS	Feasibility:	EIRR1)	29.50	FIRR1)		Yes	EIRR2)		FIRR2)			EIRR3)		FIRR3)											
4.FEASIBILITY AND ITS ASSUMPTIONS	Feasibility:	EIRR1)	29.50	FIRR1)																											
	Yes	EIRR2)		FIRR2)																											
		EIRR3)		FIRR3)																											
7.OBJECTIVES OF STUDY		Conditions and Development Impacts: Conditions: 1) Project life of 20 years; 2) Early implementation of the project; 3) Establishment of coastal authority; 4) Prohibition of coral material dredging; 5) Preservation of natural environment and traditional, cultural assets under the construction																													
8.DATE OF S/W		EIRR by each beach are as follows: <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th style="text-align: center;">EIRR(%)</th> <th style="text-align: center;">B/C(discount rate:12%)</th> </tr> </thead> <tbody> <tr> <td>Kuta</td> <td style="text-align: center;">21.0</td> <td style="text-align: center;">1.70</td> </tr> <tr> <td>Nusa Dua</td> <td style="text-align: center;">43.2</td> <td style="text-align: center;">4.43</td> </tr> <tr> <td>Sanur</td> <td style="text-align: center;">33.4</td> <td style="text-align: center;">3.09</td> </tr> <tr> <td>Whole Project</td> <td style="text-align: center;">29.5</td> <td style="text-align: center;">2.57</td> </tr> </tbody> </table>					EIRR(%)	B/C(discount rate:12%)	Kuta	21.0	1.70	Nusa Dua	43.2	4.43	Sanur	33.4	3.09	Whole Project	29.5	2.57											
	EIRR(%)	B/C(discount rate:12%)																													
Kuta	21.0	1.70																													
Nusa Dua	43.2	4.43																													
Sanur	33.4	3.09																													
Whole Project	29.5	2.57																													
9.CONSULTANT(S)		Impacts: The project will contribute to the increase of tourists from abroad and thereby increase foreign exchange earnings.																													
INA Civic Engineering Consultants Co., Ltd.		10.STUDY TEAM No.of Members 13 Period Jan.1988-Mar.1989 (15 months)																													
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 15%;">Total M/M</th> <th style="width: 15%;">Japan</th> <th style="width: 15%;">Field</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">54.88</td> <td style="text-align: center;">23.29</td> <td style="text-align: center;">31.59</td> </tr> </tbody> </table>				Total M/M	Japan	Field	54.88	23.29	31.59																				
Total M/M	Japan	Field																													
54.88	23.29	31.59																													
maritime survey; depth survey; shoreline survey; survey of sea and river sand as materials for beach reinforcement		5. TECHNICAL TRANSFER Seminars on beach conservation (at Bali and Bandung in Nov. 1988)																													
12.EXPENDITURE		3.PRINCIPAL SOURCE OF INFORMATION ①																													
Total 218,930 (¥'000)																															
Contracted 205,864																															

和名 バリ海岸緊急保全計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/S 334/88

Compiled Mar.1990

Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT					
1.COUNTRY	Indonesia	1.SITE OR AREA	Ocean Area between Kalimantan and Sulawesi in regard to the Submarine Cable Construction Project			1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled				
2.NAME OF STUDY		2.PROJECT COST		Total Cost	Local Cost	(Description) The Government of Indonesia is planning to apply of OECF financing in the future.					
Kalimantan-Sulawesi Submarine Cable System		(US\$1,000)		1) 92,000							
				2)							
				3)							
3.SECTOR		3.CONTENTES OF MAJOR PROJECT(S)									
Communications & Broadcasting/Telecommunication		-The Phase 1 study of the Kalimantan-Sulawesi Submarine Cable Project was done from August to November 1987 by JICA Study Team. The final report was submitted to the Indonesian Government on June 1988. -The Phase 2 study of the Kalimantan-Sulawesi Submarine Cable Project was aimed at confirming the availability of planned route by the ocean survey and at surveying both landing sites (Takisung, Kalimantan and Bonto Marannu, Sulawesi) precisely.									
4.REFERENCE NO.		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 20.08 EIRR2) EIRR3)	FIRR1) 18.14 FIRR2) FIRR3)					
5.TYPE OF STUDY	F/S	7.OBJECTIVES OF STUDY		Conditions and Development Impacts:		2.MAJOR REASONS FOR PRESENT STATUS					
6.COUNTERPART AGENCY	Directorate General of Posts and Telecommunication (POSTEL) Perum, Telekomunikasi Headquarters (PERUMTEL)	Execution of Ocean Survey (Phase 2) based on S/W and study Results of Phase 1 of this project		Conditions of IRR Calculation: Adoption of cable route between Banjarmasin (Kalimantan) and Ujung pandang (Sulawesi) as the Kalimantan-Sulawesi Submarine Cable System Development Impacts: It is expected to promote digitalization for transmission paths and switching facilities on the Indonesia whole networks							
8.DATE OF S/W	Mar.1987	8.DATE OF S/W		Imp. Period: 1989-1993							
9.CONSULTANT(S)	Nippon Telecommunication Consulting Co., Ltd. Sanyo Hydrographic Survey Co., Ltd.	10.STUDY TEAM		5.TECHNICAL TRANSFER		3.PRINCIPAL SOURCE OF INFORMATION					
No. of Members 21 Period Aug.1987-Oct.1988 (15 months)		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;">Total M/M</td> <td style="width: 30%;">Japan</td> <td style="width: 30%;">Field</td> </tr> <tr> <td style="text-align: center;">64.20</td> <td style="text-align: center;">42.60</td> <td style="text-align: center;">21.60</td> </tr> </table>		Total M/M	Japan			Field	64.20	42.60	21.60
Total M/M	Japan	Field									
64.20	42.60	21.60									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		12.EXPENDITURE				①					
		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;">Total</td> <td style="width: 30%;">286,857 (¥'000)</td> </tr> <tr> <td>Contracted</td> <td>278,840</td> </tr> </table>		Total	286,857 (¥'000)			Contracted	278,840		
Total	286,857 (¥'000)										
Contracted	278,840										

和名 カリマンタンスラウェシ海底ケーブル建設計画 (フェーズI及びII)

{F/S,(M/P)+F/S,D/D}

PROJECT SUMMARY (F/S)

ASE IDN/S 336/88

Compiled Mar.1990
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA				1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input checked="" type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing
2.NAME OF STUDY	Implementaion of Intra-City Digital Microwave Subscriber System	Jakarta City					
3.SECTOR	Communications & Broadcasting/Telecommunication	2.PROJECT COST				(Description) After the completion of the study, the cable expansion project financed by World Bank made rapid progress for implementation, while developers of building/estates began to install necessary telephone facilities by themselves. In this situation, request of yen loan for this project is currently reviewed by Indonesian Government. Consequently, the Government decided not to apply the project for an OECF loan. In areas where the cable installatio is difficult or impossible, the microwave subscriber system is effective. The project may be revivedby delimiting suitable areas.	
4.REFERENCE NO.							
5.TYPE OF STUDY	F/S						
6.COUNTERPART AGENCY	Directorate General of Post and Telecommunications						
7.OBJECTIVES OF STUDY							
8.DATE OF S/W	Nov.1987						
9.CONSULTANT(S)	NTT International Corporation						
10.STUDY TEAM	No.of Members 7 Period Mar.1988-Jan.1989(11 months)						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY							
12.EXPENDITURE							
	Total 121,796 (¥'000)						
	Contracted 116,438						
		3.CONTENTES OF MAJOR PROJECT(S)					
		1) To meet the rapidly increasing demand in Jakarta, digital microwave subscriber systems are proposed to be introduced for large/important subscribers.					
		2) Contents of Project - Subject areas: 18 areas in Jakarta - Subject subscribers: approx. 200 subscribers - Subject lines: approx. 15,000 lines.					
		3) Establishment of a new maintenance system.					
		4.FEASIBILITY AND ITS ASSUMPTIONS					
		Feasibility: Yes					
		EIRR1) 36.90 FIRR1) 24.90					
		EIRR2) FIRR2)					
		EIRR3) FIRR3)					
		5.TECHNICAL TRANSFER					
		OJT on digital microwave transmission and demand projection					
		2.MAJOR REASONS FOR PRESENT STATUS					
		Influenced by the progress of other projects and the change of other circumstances, requet of yen loan is delayed. Under the latest circumstances, review of applicable area to this project is necessary.					
		3.PRINCIPAL SOURCE OF INFORMATION					
		①					

和名 都市加入者マイクロ波網整備計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/A 310/88

Compiled Mar.1990
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT		
1.COUNTRY	Indonesia	1.SITE OR AREA		Total Cost Local Cost Foreign Cost 43,000 18,600 23,900		1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing	<input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY	Batang Kumu Irrigation Project in Riau Province	2.PROJECT COST (US\$1,000)						
3.SECTOR	Agriculture/General	3.CONTENTS OF MAJOR PROJECT(S)		(Description) The Indonesian Government has applied to Japanese Government for the OECF's loan for the Detailed Design and the construction.				
4.REFERENCE NO.		Wet season paddy: 7,300 ha Dry season paddy: 3,100 ha Upland crops in dry season: 2,700 ha The following facilities will be constructed to attain the foregoing target. Head work: W=50m, H=5.5m Flood gate: 14m x 3 nos Head reach: 2.6 km Main canal: 25.6 km Secondary canal: 50.1 km Secondary drainage canal: 56.5 km Tertiary canal: 486 km Tertiary drain: 102 km, Farm road:146 km						
5.TYPE OF STUDY	F/S	4.FEASIBILITY AND ITS ASSUMPTIONS						Feasibility: Yes EIRR1) 12.70 FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)
6.COUNTERPART AGENCY	Directorate General of Water Resources Development, Ministry of Public Works	Conditions and Development Impacts: It is expected that the project will stabilize the regional economy in the project area including transmigration area settled since 1981, by introducing irrigation facilities and will also support the transmigration program and regional development in the province. In addition, the project will contribute to the increase of self-sufficiency of rice in the province.						
7.OBJECTIVES OF STUDY	F/S	8.DATE OF S/W		Imp. Period: .1992-.1996		2.MAJOR REASONS FOR PRESENT STATUS		
8.DATE OF S/W	Nov.1984	9.CONSULTANT(S)		Japan Irrigation and Reclamation Consultants Co,				
9.CONSULTANT(S)	Japan Irrigation and Reclamation Consultants Co,	10.STUDY TEAM		3.PRINCIPAL SOURCE OF INFORMATION				
10.STUDY TEAM	No.of Members 18 Period Jun.1985-Mar.1986(14 months) May.1988-Jan.1989 <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">56.00</td> <td style="text-align: center;">22.00</td> <td style="text-align: center;">34.00</td> </tr> </table>	Total M/M	Japan					Field
Total M/M	Japan	Field						
56.00	22.00	34.00						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Topographic Survey Geological Survey	5.technical transfer		①				
12.EXPENDITURE	<table style="width: 100%; border: none;"> <tr> <td style="text-align: right;">Total</td> <td style="text-align: right;">212,093 (¥'000)</td> </tr> <tr> <td style="text-align: right;">Contracted</td> <td style="text-align: right;">171,000</td> </tr> </table>	Total	212,093 (¥'000)					Contracted
Total	212,093 (¥'000)							
Contracted	171,000							

和名 バタンクム農業開発計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P)

ASE IDN/S 125/89

Compiled Mar.1991
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS							
1.COUNTRY	Indonesia	1.SITE OR AREA	Four provinces of northern Sumatra (Aceh, North Sumatra, West Sumatra and Riau)		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued						
2.NAME OF STUDY	Integrated Regional Development Plan for the Northern Part of Sumatra	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost	(Description) Indonesian government's enthusiasm about this study is clearly indicated by its request to extend the identification of priority projects by seven months so that the study's outcome can be fully utilized to formulate Repelita V (the Fifth 5-Year Development Plan). They have particularly appreciated the Integrated Development Programs since shortcomings of the conventional sectoral approach have become widely recognized in Indonesia. The Ministries of Public Works and Home Affairs, BAPPENAS and the provincial governments will cooperate to implement the programs and other projects. Three IDEPs (of total eleven) made it into the 1991/1992 Bluebook (government shopping list for the donors). BAPPENAS has already started to contact such donors as ADB, Islamic Development Bank, USAID and Italy in an effort to promote some of the projects identified in the study. As of December 1992, some projects in the Tapanuli IDEP are awaiting approval by the Islamic Development Bank. The study results have also been extensively used by the Government as a model regional plan in an effort to establish a system of spetial plan for the country. The plan was particularly instrumental in preparing the Provincial Spetial Structural Plan for each of the 27 provinces and drafting the Spetial Planning Act enacted in 1992.						
3.SECTOR	Development Plan/Integrated Regional Development Plan	(US\$1,000)	1) 3,069,000		2)							
4.REFERENCE NO.		3.CONTENT'S OF MAJOR PROJECT(S)										
5.TYPE OF STUDY	M/P	Considering the largeness of the region and limited financial resources, the team chose to focus on some selected areas. Eleven such priority areas are identified from among 24 subregions through a potential evaluation and strategic considerations. A multisector program is then formulated for each of the 11 priority areas and termed the Integrated Development Program (IDEP). Many other sectoral projects which do not make up an IDEP but is needed from the regional standpoint are also identified and outlined. In total: 11 IDEPs On average, Each covers 10,000 sq.Km and one million population, Consists of 30 to 40 sectoral projects. 430 Sectoral Projects (291 IDEP components)										
6.COUNTERPART AGENCY	Directorate General of Human Settlements, Ministry of Public Works	4.CONDITIONS AND DEVELOPMENT IMPACTS										
7.OBJECTIVES OF STUDY	Long-term planning (1989-2008) and preparatory study of priority projects	(1) The macroeconomic framework for plan: GDP growth rate (non-oil/gas) is 5.7% (88-93), 6.5% (93-98); population growth will remain higher than the national average; the total investment required is US \$77 billion, 65% of which will be financed by private sources. (2) As a result, per capita GDP will grow faster than the national average while east-west disparities will reduce in the region. The five objects will be attained. 1) Center for food production 2) Promotion of exports and tourism 3) Center for manufacturing 4) Reception of immigrants 5) Integrated regional economy										
8.DATE OF S/W	Jan.1988	10.STUDY TEAM										
9.CONSULTANT(S)	International Development Center of Japan Nihon Koel Co., Ltd.	No.of Members 18 Period Mar.1988-Mar.1990 (25 months)										
		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">130.73</td> <td style="text-align: center;">9.90</td> <td style="text-align: center;">120.83</td> </tr> </table>			Total M/M		Japan	Field	130.73	9.90	120.83	
Total M/M	Japan	Field										
130.73	9.90	120.83										
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Complication of land use maps	5. TECHNICAL TRANSFER										
12.EXPENDITURE		(1) Five workshops held to discuss each report. (2) Study tour for 6 officials. (3) A lecture for counterparts on how to carry out planning practice.										
Total	428,345 (¥'000)	3.PRINCIPAL SOURCE OF INFORMATION										
Contracted	427,744	①										
		2.MAJOR REASONS FOR PRESENT STATUS										
		(1) Enthusiasm among Indonesian officials (2) Timely proposal of the IDEP approach as a prospective countermeasure to the sectoral approach (3) Team's effort to facilitate policy dialogue										

和名 北部スマトラ地域総合開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/S 124/89

Compiled Mar.1991

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																
1.COUNTRY	Indonesia	1.SITE OR AREA	JABOTABEK Area			1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued														
2.NAME OF STUDY	Long-Term and Medium-Term Plan for Telecommunications Network in Jabotabek Area	2.PROJECT COST						<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">1)</td> <td style="text-align: center;">Total Cost</td> <td style="text-align: center;">Local Cost</td> <td style="text-align: center;">Foreign Cost</td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td style="text-align: center;">29,900</td> <td style="text-align: center;">145</td> <td style="text-align: center;">28,450</td> </tr> <tr> <td colspan="6"> (US\$=130Yen)=2,000Rp </td> </tr> </table>			(US\$1,000)	1)	Total Cost	Local Cost	Foreign Cost		2)	29,900	145	28,450	(US\$=130Yen)=2,000Rp
(US\$1,000)	1)	Total Cost	Local Cost	Foreign Cost																	
	2)	29,900	145	28,450																	
(US\$=130Yen)=2,000Rp																					
3.SECTOR	Communications & Broadcasting/Telecommunication	3.CONTENTES OF MAJOR PROJECT(S)	Long-Term Plan The study selected the expansion of junction network for the expanded Jakarta multi-exchange area as the priority project to be implemented from the beginning of Repeleta V. Components of the priority project: -Junction Section (17sections including 2 sections for suburbs) -Optical Fibre Cable Transmission System : 15 sections (127.4km) -Radio Transmission System : 2 sections (19km BEK-CL; 14km TAN-CKP) The target planning year for the sub-systems: Muldex.....1994 Optical fibre...1999 Radio.....1994 Power.....1999			(Description) - Sept. 1991 OECF Loan Agreement of "The Junction Network for Expanded Jakarta Multi-Exchange Area" - Consulting Service Contract was concluded on Feb. 13, 1992. Tendes evaluation and negotiation has been carried out from Nov.1992 to Mar.1993.															
4.REFERENCE NO.		4.CONDITIONS AND DEVELOPMENT IMPACTS						2.MAJOR REASONS FOR PRESENT STATUS (1) Effectiveness achieved by th fulfillment of the project (2) High priority													
5.TYPE OF STUDY	M/P	Conditions: (1)Transmission systems use optical fibre cables or digiral radio. (2)Existing Meralic Cables should be taken away after the deqitization of switching equipment. Development Impacts: (1) Promotion of Industrial Growth Direct investments from abroad, particularly those from Japan and NIES, are at present booming in Indonesia, and substantial portion of the investments is directed to the Jabotabek area. Development of telecommunication in this area will serve for acceleration of such industrialization trend, which is a major objective of REPELITA V. (2) Promotion of Regional Development Development of telecommunications along with that of transport sector can be an effective step to promote the government's regional development policies. In the Jabotabek area, development of the area along an east-west axis is encouraged. Intensive development of telecommunications and transport systems, with Tangerang and Bekasi as its key cities, will greatly contribute to the promotion of regional development in this area.																			
6.COUNTERPART AGENCY	Postal, Perumtel									5.technical transfer	3.PRINCIPAL SOURCE OF INFORMATION ①										
7.OBJECTIVES OF STUDY	The Long-term and medium-term plan for telecommunications network in JABOTABEK Area.	8.DATE OF S/W	Feb.1988																		
9.CONSULTANT(S)	Nippon Telecommunication Consulting Co., Ltd.	10.STUDY TEAM	<table style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="3">No.of Members 9</td> </tr> <tr> <td colspan="3">Period Jul.1988-Jul.1989(12 months)</td> </tr> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">57.71</td> <td style="text-align: center;">23.74</td> <td style="text-align: center;">33.97</td> </tr> </table>			No.of Members 9			Period Jul.1988-Jul.1989(12 months)			Total M/M	Japan	Field	57.71	23.74	33.97				
No.of Members 9																					
Period Jul.1988-Jul.1989(12 months)																					
Total M/M	Japan	Field																			
57.71	23.74	33.97																			
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	None	12.EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: center;">161,105 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">159,088</td> </tr> </table>			Total	161,105 (¥'000)	Contracted	159,088												
Total	161,105 (¥'000)																				
Contracted	159,088																				

和名 ジャカルタ首都圏電気通信網整備計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/A 104/89

Compiled Mar.1991
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS	
1.COUNTRY	Indonesia	1.SITE OR AREA	Negara River Basin, South Kalimantan Province (Study Area 12,683 sq.km)		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
2.NAME OF STUDY	Negara River Basin Overall Irrigation Development Plan	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost	(Description) Technical Assistance for the Negara Pilot project will be requested to Japanese Government
3.SECTOR	Agriculture/General	(US\$1,000)	1) 215,000			
4.REFERENCE NO.			2)			
5.TYPE OF STUDY	M/P	3.CONTENTES OF MAJOR PROJECT(S)				
6.COUNTERPART AGENCY	Directorate General of Water Resources Development, Ministry of Public Works	The following four package projects which are composed of 76 schemes are formulated for the period from Repelita V to Repelita X, ie. 30 years for 1989/90-2018/19 period.				
7.OBJECTIVES OF STUDY	Formulation of the development strategy in Negara River Basin, South Kalimantan	Project	Irrigation Scheme	Drainage Scheme	Polder Scheme	
8.DATE OF S/W	Jul.1987	1	3	1	0	
9.CONSULTANT(S)	Nihon Koei Co., Ltd.	5	18	0	1	
10.STUDY TEAM	No. of Members 10 Period Mar.1988-Jul.1989 (13 months)	15	8	4	1	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Cost of equipment for water level measurement	9	9	0	1	
12.EXPENDITURE	Total 212,021 (¥'000) Contracted 172,248	30	38	5	3	
		4.CONDITIONS AND DEVELOPMENT IMPACTS Conditions: In order to implement all the 76 proposed schemes until 2018, it is necessary to increase public investment with an annual growth rate of 10% for water resources development in the Study Area. Major development impacts: The completion of the proposed four package projects would raise the annual paddy production to 880,000 tons, which would be more than the projected demand for paddy (815,600 tons) in 2018 in the Study Area. In addition, the completion of the four package projects would bring the following effects: - Increase of population growth from the projected 0.65% p.a. to 1.18% p.a. - 70% increase of gross income of typical farmers - Contribution to foreign exchange savings of about US\$74 million and export earnings of US\$39 million (1988 constant prices).				
		5. TECHNICAL TRANSFER Technology transfer to the counterparts in the course of the study.			2.MAJOR REASONS FOR PRESENT STATUS	
					3.PRINCIPAL SOURCE OF INFORMATION	
					①	

和名 ネガラ河下流域かんがい開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P)

ASE IDN/A 105/89

Compiled Mar.1991

Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS		III. PRESENT STATUS OF STUDY RESULTS														
1.COUNTRY	Indonesia	1.SITE OR AREA	Java Barat, Java Timur, Lampung and Sulawesi Selatan Provinces		1.PRESENT STATUS	<input type="checkbox"/> In Progress or In Use <input checked="" type="checkbox"/> Delayed <input type="checkbox"/> Discontinued												
2.NAME OF STUDY	Improvement of Rice Post Harvest and Marketing in Farmer Groups	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost	(Description) No information is available.												
3.SECTOR	Agriculture/Agricultural Processing	(US\$1,000)	1) 210,000		210,000													
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)	Pilot Plans Pilot Area Telaqasari Baqor Mattiro Bulu Trimurjo 1.Location Cadas (desa) Kertajaya Selorejo Marannu Purwodadi 2.Paddy field 119 109 105 157 (ha) 3.Nos. of Farm 172 363 87 254 Family 4.Cropping Intesity Wet season 100% 90% 100% 100% Dry season 100% 80% 70% 100%															
5.TYPE OF STUDY	M/P	4.CONDITIONS AND DEVELOPMENT IMPACTS					Conditions: 1.Financial Support by the Government 2.Intensive Investment in Farm Roads and Drainage Canals Development Impacts: After the implementation of the pilot plan, harvesting and processing losses will be reduced considerably through improvement of post harvest activities. Harvesting cost will also be reduced in significantly by the introduction of improved harvesting system i.e. reaping by organized laborers under cash payment system and effective threshing works by pedal and power threshers through farmer groups' custom service.											
6.COUNTERPART AGENCY	Directorate General of Food Crops Agriculture,Ministry of Agriculture (DGFA)	5.technical transfer	Technology transfer to counterparts in the course of the study.															
7.OBJECTIVES OF STUDY	Formulation of the Pilot Plan of Rice-Post Harvest and Marketing in Farmer Group	12.EXPENDITURE					<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;">Total</td> <td style="width: 15%;">85,077 (¥'000)</td> </tr> <tr> <td>Contracted</td> <td>80,374</td> </tr> </table>				Total	85,077 (¥'000)	Contracted	80,374				
Total	85,077 (¥'000)																	
Contracted	80,374																	
8.DATE OF S/W	Jun.1988	11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	None															
9.CONSULTANT(S)	Nihon Koei Co., Ltd.	10.STUDY TEAM					<table style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="3">No.of Members 6</td> </tr> <tr> <td colspan="3">Period Nov.1988-Oct.1989(12 months)</td> </tr> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">29.05</td> <td style="text-align: center;">11.09</td> <td style="text-align: center;">17.96</td> </tr> </table>				No.of Members 6			Period Nov.1988-Oct.1989(12 months)			Total M/M	Japan
No.of Members 6																		
Period Nov.1988-Oct.1989(12 months)																		
Total M/M	Japan	Field																
29.05	11.09	17.96																
		2.MAJOR REASONS FOR PRESENT STATUS																
		3.PRINCIPAL SOURCE OF INFORMATION					①											

和名 收穫後処理及び流通改善計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 215A/89

Compiled Mar.1991
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS						
1.COUNTRY	Indonesia	1.SITE OR AREA	Within ex-airport project site: 133 hectare Outside ex-airport project site: 4 sites 19 hectare		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued					
2.NAME OF STUDY	Kemayoran Urban Housing Development Project	2.PROJECT COST	Total Cost	Local Cost	(Description) Followed by F/S.						
3.SECTOR	Social Infrastructures/Urban Planning & Land Development	(US\$1,000)	1) 120,137	2) 120,137							
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)	(1)Development Plan within ex-airport area (a) for low income group (b) for general use (totald to 14,500 units) (c) for urban amenities and infrastructure arrangement (2) Housing renewal plan in neighborhood area of ex-airport (3) Development of methodology of urban renewal The M/P assumes that the hosuing development be implementedwih the available local funds and that the accruing benefits of the development (including the income of land sales) favorably stimulate housing improvent efforts in the neighboring areas.								
5.TYPE OF STUDY	M/P+ (F/S)	4.CONDITIONS AND DEVELOPMENT IMPACTS									
6.COUNTERPART AGENCY	Directorate General of Human Settlements Ministry of Public Works	1. Promotion of Jakarta City to the direction of east 2. To assure to stickness to urban development plan caused by increase of supply of housing 3. Effective use of land within Jakarta City 4. Contribution to prevention of disasters of urban area 5. Promotion of inhabitants' participation at urban development 6. Dissemination of method of urban renewal	2.MAJOR REASONS FOR PRESENT STATUS								
7.OBJECTIVES OF STUDY	Conduct of Feasibility Study on Urban Housing and Urban Renewal										
8.DATE OF S/W	Apr.1988	10.STUDY TEAM	3.PRINCIPAL SOURCE OF INFORMATION ①								
9.CONSULTANT(S)	Yachiyo Engineering Co., Ltd. JCP Co., Ltd.	No. of Members 12 Period Jul.1988-Mar.1990 (20 months)									
		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33%;">Total M/M</td> <td style="width: 33%;">Japan</td> <td style="width: 33%;">Field</td> </tr> <tr> <td style="text-align: center;">74.18</td> <td style="text-align: center;">9.52</td> <td style="text-align: center;">64.66</td> </tr> </table>	Total M/M	Japan	Field	74.18	9.52	64.66	5. TECHNICAL TRANSFER 1. Development of methodology of urban renewal, and urban housing renewal. 2. Seminar was held in Jakarta on the implementation of urban renewal project, with the attendance of about 100 people.		
Total M/M	Japan	Field									
74.18	9.52	64.66									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	(1) Detailed Survey of existing physical 7 socio-economic conditions. (2) Four editions of slides synchronized with sound.	12.EXPENDITURE									
		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33%;">Total</td> <td style="width: 33%;">267,007 (¥'000)</td> <td></td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">246,728</td> <td></td> </tr> </table>	Total	267,007 (¥'000)		Contracted	246,728				
Total	267,007 (¥'000)										
Contracted	246,728										

和名 クマヨラン地区都市・住宅再開発計画

(M/P,M/P+(F/S),Basic Study,Other)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 215B/89

Compiled Mar.1991
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA				1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing
2.NAME OF STUDY	Kemayoran Urban Housing Development Project	Within ex-airport project site: 133 hectare Outside ex-airport project site: 4 site 19 hectare					
3.SECTOR	Social Infrastructures/Urban Planning & Land Development	2.PROJECT COST		Total Cost	Local Cost	(Description) 1. Part of the development/redevelopment of the ex-airport site commenced in 1989 by local funds. Housing development on 133 ha will be implemented by Perumnas (Indonesian Housing Cooperation). 2. Sites A and B located in the ex-airport site will be implemented in accordance with the results of this study. 3. Indonesian side is now considering the implementation of Sites C, D, E and F. In particular, Site F is feasible if the recommended renewal method is applied.	
4.REFERENCE NO.		(US\$1,000)	1) 3,889	3,889	Foreign Cost		
5.TYPE OF STUDY	(M/P)+F/S	3.CONTENT(S) OF MAJOR PROJECT(S)					
6.COUNTERPART AGENCY	Directorate General of Human Settlements Ministry of Public Works	Housing renewal on total 3.5 ha. of Case Study Sites D located in the vicinity of the ex-airport including 635 houses for low income group.					
7.OBJECTIVES OF STUDY	Conduct of Feasibility Study on Urban Housing and Urban Renewal	8.DATE OF S/W		Imp. Period:		2.MAJOR REASONS FOR PRESENT STATUS	
8.DATE OF S/W	Apr.1988			.1989-.1990	.1995-.1999		
9.CONSULTANT(S)	Yachiyo Engineering Co., Ltd. JCP Co., Ltd.	4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 19.00 EIRR2) EIRR3)		
10.STUDY TEAM	No.of Members 12 Period Jul.1988-Mar.1990 (20 months)	Conditions and Development Impacts: 1. 120 ha. housing development: Increase in housing stock at the center of the city. Reinforcement of urban functions of Jakarta city. 2. Renewal of surrounding: Safeguarding ex-airport development, increase in housing stock, enhancing urban functions by intensive land use, contributing to the prevention of urban disaster. 3. Enlightenment of community participation by demonstrating actual sample of urban renewal. 4. Application of developed renewal methodology to other urban areas and other cities.		FIRR1) 23.90 FIRR2) FIRR3)			
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	(1) Detailed Survey of existing physical & socio-economic conditions. (2) Four editions of slides synchronized with sound.	5. TECHNICAL TRANSFER				3.PRINCIPAL SOURCE OF INFORMATION	
12.EXPENDITURE	Total 267,007 (¥'000) Contracted 246,728	1. Development of methodology of urban renewal, and urban housing renewal. 2. Seminar was held in Jakarta on the implementation of urban renewal project, with the attendance of about 100 people. 3. Acceptance of trainees: 2 trainees					

和名 クマヨラン地区都市・住宅再開発計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 216A/89

Compiled Mar.1991

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS															
1.COUNTRY	Indonesia	1.SITE OR AREA	Throughout Indonesia		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued														
2.NAME OF STUDY	Integrated Radio and Television Servicing System Project	2.PROJECT COST			<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">1)</td> <td style="text-align: center;">Total Cost</td> <td style="text-align: center;">Local Cost</td> <td style="text-align: center;">Foreign Cost</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">155,071</td> <td style="text-align: center;">26,108</td> <td style="text-align: center;">128,963</td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> </table>		(US\$1,000)	1)	Total Cost	Local Cost	Foreign Cost			155,071	26,108	128,963		2)		
(US\$1,000)	1)	Total Cost	Local Cost	Foreign Cost																
		155,071	26,108	128,963																
	2)																			
3.SECTOR	Communications & Broadcasting/Broadcasting	3.CONTENTS OF MAJOR PROJECT(S)	US\$1=Rp.1,771=142.8yen The following projects will be suggested by the year of 1999. (1) Rehabilitation of 8 High Radio Stations (2) Rehabilitation of 5 TV transmitting stations (3) Establishment of a Maintenance System (7 maintenance bases) (4) Improvement of Engineering Communication Network (48 radio stations, 100 TV stations) (5) Introduction of TV Up-Links (2 TV stations) (6) Improvement of Programme Transmission Lines (48 radio stations) (7) Additional Construction of MW facilities at SW-Only stations (10 stations) (8) Rehabilitation of studios at Regional Radio Stations (22 stations) (9) Improvement of RN-I Network (10 stations) (10) Improvement of TVN-I Network (50 stations)																	
4.REFERENCE NO.		4.CONDITIONS AND DEVELOPMENT IMPACTS	Conditions: Indonesia's national broadcasting services are confronted by many difficult problems to be solved. In order that the broadcasting may carry out the mission assigned to it, it is most essential for the broadcasting organizations to deliver services of richer content and higher quality in such a way that they can be enjoyed fully by the people throughout the country. And at the same time, the broadcasting organizations should continue to be the kind of entities that deserve high trust and support of the people.																	
5.TYPE OF STUDY	M/P+(F/S)	10.STUDY TEAM	Development Impacts: (1) Restoration and maintenance of broadcasting functions, and an increase of broadcasting service by establishment of maintenance system. (2) Qualitative and quantitative improvement of broadcasting network. (3) Enrichment of broadcast programme. (4) With achievement of efficient management and financial stability, Indonesia's broadcasting can be expected to take another great leap toward its ultimate goals set for the year 2000 and beyond.																	
6.COUNTERPART AGENCY	RTF, Ministry of Information	11.ASSOCIATED AND/OR SUBCONTRACTED STUDY																		
7.OBJECTIVES OF STUDY	Reviewing of the existing long-term plan covering Repelita V and Repelita VI formulated by JICA in 1984	12.EXPENDITURE	5.TECHNICAL TRANSFER Technical and Management transfer are done in the following items. (1) Measurement of Field Strength; (2) Organization and Management of broadcasting stations; (3) Programme Transmission by Satellite etc.																	
8.DATE OF S/W	Nov.1988	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">44.53</td> <td style="text-align: center;">14.31</td> <td style="text-align: center;">30.22</td> </tr> </table>		Total M/M	Japan	Field	44.53	14.31	30.22	2.MAJOR REASONS FOR PRESENT STATUS 1. High priority: High priority has been given to the role of broadcasting to achieve the target of the National Development Plan. 2. Continuity: To continue the improvement of broadcasting in connection with previous loan projects relating to broadcasting in 1970s.										
Total M/M	Japan			Field																
44.53	14.31	30.22																		
9.CONSULTANT(S)	Integrated Technology Inc. Yachlyo Engineering Co., Ltd.	3.PRINCIPAL SOURCE OF INFORMATION ①④																		

和名 ラジオ・テレビ放送総合開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 216B/89

Compiled Mar.1991

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT		
1.COUNTRY	Indonesia	1.SITE OR AREA	Throughout Indonesia			1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing	
2.NAME OF STUDY	Integrated Radio and Television Servicing System Project	2.PROJECT COST						Total Cost
3.SECTOR	Communications & Broadcasting/Broadcasting		(US\$1,000)	1) 60,721	2) 4,402	3) 56,319	(Description) Dec. 1990 OECF L/A signed for the first phase (Rehabilitation of Radio and Television Network I, 7,478 million yen) Jan. 1992 Construction started (to be completed in May 1995) Contents of the Phase I OECF loan: 1) Replacement/rehabilitation of equipment at 10 radio transmitting stations 2) Replacement of studio equipment at 10 radio transmitting stations 3) Replacement of studio equipment at 3 TV transmitting stations 4) Construction of 3 new maintenance centers The Phase II project (of the same title) is being prepared to apply for FY1993/94 OECF Yen Credit.	
4.REFERENCE NO.		3.CONTENT(S) OF MAJOR PROJECT(S)	(1) Rehabilitation of 8 High Radio Stations (2) Rehabilitation of 5 TV transmitting stations (3) Establishment of a Maintenance System (Maintenance Center) (4) Improvement of Radio Programme Transmission Line, Engineering Communication Network and Introduction of TV Up-Links (5) Additional Construction of MW Facilities at SW-only stations (5 stations) (6) Rehabilitation of studios at Regional Radio Stations (4 stations)					
5.TYPE OF STUDY	(M/P)+F/S	4.FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes	EIRR1) 11.70	FIRR1)	FIRR2)		
6.COUNTERPART AGENCY	RTF, Ministry of Information	Conditions and Development Impacts: Conditions: It is estimated that about 84 million people are bestowed benefit directly by this improvement plan. The investment cost of whole projects to achieve the plan totals 107.5 billion Rp, and as the total number of households is about 3,919 Rp., the cost per household is about 2,743 Rp. It seems that this amount is not so large to enjoy good quality broadcasting. Broadcasting service can obtain income only after the total system is established. Distribution of income for partial improvement of the system is difficult. Evaluation is only for EIRR but not for FIRR. Development Impacts: (1) Recovery of the deteriorated functions of broadcasting. (2) Arrangement of the structure to maintain the system. (3) Expanding a stable medium-wave broadcasting network. (4) Achieve wholesome management and operation in broadcasting that focuses on audience servicing.						
7.OBJECTIVES OF STUDY	Feasibility Study Covering Repelita V					Imp. Period: 1992-1994		
8.DATE OF S/W	Nov.1988	10.STUDY TEAM No.of Members 18 Period Apr.1989-Mar.1990(12 months)				2.MAJOR REASONS FOR PRESENT STATUS 1. High priority: High priority has been given to the role of broadcasting to achieve the target of the National Development Plan. 2. Continuity: To continue the improvement of broadcasting with precedence of OECF finance in connection with previous projects in 1970s.		
9.CONSULTANT(S)	Integrated Technology Inc. Yachiyo Engineering Co., Ltd.	Total M/M Japan Field 44.53 14.31 30.22						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER				3.PRINCIPAL SOURCE OF INFORMATION ①④		
12.EXPENDITURE		Technical and Management transfer are done in the following items. (1) Measurement of Field Strength, (2) Organization and Management, (3) Programme Transmission by Satellite etc. And Personal Training in Japan was done in November, 1989 to transfer the analysis technique of Study Result. (2persons)						
		Total		154,474 (¥'000)				
		Contracted		142,842				

和名 ラジオ・テレビ放送総合開発計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/S 338/89

Compiled Mar.1991
Revised Mar.1992

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT			
1.COUNTRY	Indonesia	1.SITE OR AREA		Route area between Cikampek-Cirebon and surrounding area		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input checked="" type="checkbox"/> Processing <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled		
2.NAME OF STUDY		2.PROJECT COST							
Cikampek-Cirebon Tollway Project				Total Cost	Local Cost	Foreign Cost	(Description) The Indonesian government requested in Feb. 1991 OECF E/S financing, but did not obtain the approval. The government received financing from IBRD and the study started in Aug.1992. The construction will be by BOT.		
3.SECTOR				510,000	299,000	211,000			
Transportation/Road									
4.REFERENCE NO.				3.CONTENTS OF MAJOR PROJECT(S)					
5.TYPE OF STUDY		F/S		The tollway has planned as a 4-lane divided highway covering the whole length. Between Cikampek and Cirebon and widened to a 6-lane at inner lanes at the final stage. The construction is to be divided into nine(9) sections taking into consideration operation for hauling, excavation and filling, accessibility to each section, and proper work volume.					
6.COUNTERPART AGENCY		Bina Marga Jisa Marga		Package A: Cikampek interchange(I.C.)- Subang I.C. L=36.9km (Section 1-2) Package B: Subang I.C. - Dawuan I.C. L=53.5km (Section 3-5) Package C: Dawuan I.C. - East Cirebon L=53.9km (Section 6-9)					
7.OBJECTIVES OF STUDY		To determine feasibility of constructing tollway		Construction cost (x 1,000US\$) 1) Initial 4 lanes 435,000 2) Additional 2 lanes 75,000 Total 510,000					
8.DATE OF S/W		Mar.1988		Imp. Period: 1991-1997					
9.CONSULTANT(S)		Pacific Consultants International Yachiyo Engineering Co., Ltd. Pasco International Inc.		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes EIRR1) 32.28 FIRR1) 23.80 EIRR2) FIRR2) EIRR3) FIRR3)			
10.STUDY TEAM		No.of Members 19 Period Sep.1988-Mar.1990 (1 months)		Conditions and Development Impacts: Conditions: 1. Expressway standard with full access control as a part of the Trans-Java Tollway network. 2. Viable alternative to existing national roads for through traffic from Central and East Java to Jakarta and westwards. 3. Location of interchanges are to be in selected areas where 1) the population is estimated to be more than 50,000 within the sphere of influence of the interchange, and 2) minimal traffic requirement for the interchange demand to approximate to 3,000 vehicles per day(basic standard employed in Japan). Development Impact: 1) Relieving existing roads for local traffic use and providing easy accessibility to regional development centers. 2) Increasing benefits to road users. 3) Increasing the incentive development impact for the area surrounding interchanges. (i.e. Cikampek, Subang, Cirebon and etc.) In particular, Cirebon is a coastal city with a high potential for development.				2.MAJOR REASONS FOR PRESENT STATUS	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		Topographic mapping work		5.TECHNICAL TRANSFER				3.PRINCIPAL SOURCE OF INFORMATION	
12.EXPENDITURE		Total 395,190 (¥'000) Contracted 383,604		The traffic survey and engineering site survey were performed with Indonesian counterparts. A staff of Bina Marga visited Japan for participation in a training program in July 1989.				①	

和名 チカンベック・チレボン有料高速道路建設計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/A 311/89

Compiled Mar.1991
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA		Benakat Area in South Sumatra Province		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing
2.NAME OF STUDY	Industrial Plantation Forest Development Plan in South Sumatra Area	2.PROJECT COST		Total Cost	Local Cost		
3.SECTOR	Forestry/Forestry & Forest Conservation			1) 32,742	12,454	20,288	
4.REFERENCE NO.				2) US\$1=1,780Rp.			
5.TYPE OF STUDY	F/S			3)			
6.COUNTERPART AGENCY	Ministry of Forestry	3.CONTENTS OF MAJOR PROJECT(S)				(Description) The counterpart agency has been implementing the project.	
7.OBJECTIVES OF STUDY	This feasibility study is prepared to clarify the financial and economic feasibility of this plan in order to contribute to the promotion of industrial plantation development and the improvement of the planning capability.	Study Area : Approximately 50,000 ha Operation site : Approximately 43,000 ha Planting site : Approximately 27,000 ha Planting species : A.mangium and other 2 species (Short rotation : 8 years), P.canescens and other 2 species (Long rotation : 20 years, 35 years) Nurseries and offices : 3 places, 9.5ha Forest road : Approximately 560 km in length					
8.DATE OF S/W	Mar.1988	Imp. Period:		EIRR1) 14.31	FIRR1) 9.45	2.MAJOR REASONS FOR PRESENT STATUS According to the Fifth 5 year Development Plan (Repelita 1989/90-1993/94), the enlargement of re-afforestation and the increase of timber production have been proposed in the forestry sector. 4.4 million ha of industrial plantations are planned during 15 years.	
9.CONSULTANT(S)	Japan Forest Technical Association	4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR2) EIRR3)		
10.STUDY TEAM	No.of Members 9 Period Nov.1988-Mar.1990 (17 months)	Conditions and Development Impacts: Precondition : Planting will be completed in 8 years with mechanical afforestation method based on the results of Project-type technical cooperation in this area. (considering the rotation of planting trees, security of labour force and need of early forestation in grasslands) Development Impacts: To contribute to developing the Industrial Plantation Project in Indonesia; To develop local forestry and forest product industry; To conserve soils; To stabilize agricultural products; and To increase local inhabitants' income.				3.PRINCIPAL SOURCE OF INFORMATION ①	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Preparation of topographic maps and cartographic works on thematic maps	5.technical transfer					
12.EXPENDITURE	Total 200,913 (¥'000) Contracted 195,973	1.To accept four trainees 2.On the job training					

和名 産業造林計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P)

ASE IDN/S 126/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																
1.COUNTRY	Indonesia	1.SITE OR AREA	Selected 10 Airports 2.PROJECT COST <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 15%; text-align: center;">Foreign Cost</td> </tr> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">1)</td> <td style="text-align: center;">70,000</td> <td style="text-align: center;">27,700</td> <td style="text-align: center;">42,300</td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> </table>				Total Cost	Local Cost	Foreign Cost	(US\$1,000)	1)	70,000	27,700	42,300		2)				1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
		Total Cost			Local Cost	Foreign Cost															
(US\$1,000)	1)	70,000	27,700	42,300																	
	2)																				
2.NAME OF STUDY Airport Maintenance and Rehabilitation		3.CONTENTES OF MAJOR PROJECT(S) Project of maintenance and rehabilitation in 10 airports. 1.Gunung Sitoli: Overlay of runway, taxiway, apron, installation of air conditioning, provision of mower and tractor; 2.Palembang: Overlay of runway, finishing of PAX Bldg., provision of handy mower; 3.Semarang: Expansion of PAX Bldg., provision of mower, tractor, handy mower and sweeper; 4.Pontianak: Extension of runway and PAX Bldg., taxiway overlay, installation of air conditioning, provision of handy mower and sweeper. 5. Sampit: Overlay of runway, installation of air conditioning, provision of mower, tractor, handy mower and dump truck; 6.Ambon: Overlay of runway, taxiway and apron, installation of air conditioning, provision of mower, tractor and handy mower; 7. Ternate: Expansion of PAX Bldg. runway extension, installation of security equipment and air conditioning provision of mower and handy mower; 8.Mataram: Overlay of apron, installation of security equipment and air conditioning, expansion of runway and apron provision of sweeper; 9.Bima: Extension of runway, provision of dyke, overlay of taxiway and apron, installation of security equipment and air conditioning, provision of mower, tractor and handy mower; 10. Merauke: Overlay of runway, overlay of taxiway and apron, expansion of apron and FAX Bldg., installation of provision of mower, handy mower, sweeper and dump truck.			(Description) DGAC will request for an OECF loan.																
3.SECTOR Transportation/Air Transportation & Airport							4.CONDITIONS AND DEVELOPMENT IMPACTS Implementation of maintenance and rehabilitation for 10 selected airports will contribute to the following effects: 1. Gunung Sitoli: Safe aircraft operation, improvement of service level promotion of tourism development. 2. Palembang Sitoli: Safe air transportation 3. Semarang: Ditto, removal of factors restraining air traffic demand 4. Pontianak: Ditto, removal of factors restraining air traffic demand 5. Sampit: Ditto 6. Ambon: Ditto 7. Ternate: Ditto, promotion of unrestricted air transport, contribute to reduce regional disparity. 8. Mataram: Ditto, Ditto, Tourism development. 9. Bima: Ditto 10. Merauke: Ditto, Contribute to regional economy			2.MAJOR REASONS FOR PRESENT STATUS As one of the basic policies of the Government of Indonesia, effective utilization of existing facilities and improvement on maintenance work are considered important.											
4.REFERENCE NO.		5. TECHNICAL TRANSFER 1. Invitation of Trainee Mr. Iman Soelvan (DGAC) 1990 October 2. Seminar in Indonesia 1991 February			3.PRINCIPAL SOURCE OF INFORMATION ①																
5.TYPE OF STUDY M/P							10.STUDY TEAM No.of Members 11 Period Jan.1990-Mar.1991(15 months) <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">31.00</td> <td style="text-align: center;">33.00</td> <td></td> <td></td> </tr> </table>							Total M/M	Japan	Field				31.00	33.00
Total M/M	Japan	Field																			
	31.00	33.00																			
6.COUNTERPART AGENCY Directorate General of Air Communications (DGAC)		12.EXPENDITURE <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td style="text-align: center;">Total</td> <td style="text-align: center;">270,849 (Y'000)</td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">249,000</td> <td></td> <td></td> <td></td> </tr> </table>							Total	270,849 (Y'000)				Contracted	249,000						
Total	270,849 (Y'000)																				
Contracted	249,000																				
7.OBJECTIVES OF STUDY Preparation of master plan for maintenance and rehabilitation for 10 airports selected from 20 etc.		8.DATE OF S/W Oct.1989																			
8.DATE OF S/W Oct.1989						9.CONSULTANT(S) Pacific Consultants International															
9.CONSULTANT(S) Pacific Consultants International																					
10.STUDY TEAM No.of Members 11 Period Jan.1990-Mar.1991(15 months) Total M/M Japan Field 31.00 33.00																					
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY -Topographic Survey -Soil Investigation -Building Survey																					
12.EXPENDITURE Total 270,849 (Y'000) Contracted 249,000																					

和名 地方空港整備計画

(M/P,M/P+(F/S),Basic Study,Other)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 219A/90

Compiled Mar.1992

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS			
1.COUNTRY	Indonesia	1.SITE OR AREA	DKI Jakarta 650 sq.km			1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued	
2.NAME OF STUDY	Urban Drainage and Wastewater Disposal Project in the City of Jakarta	2.PROJECT COST						(US\$1,000)
3.SECTOR	Public Utilities/Sewerage	3.CONTENTES OF MAJOR PROJECT(S)	1)	72,000			(Description) A feasibility study on urban drainage and wastewater disposal for the priority areas was conducted after the completion of the master plan study.	
4.REFERENCE NO.			2)	980,000				
5.TYPE OF STUDY	M/P+(F/S)	1) Urban Drainage: Canal Improvement: L=76.1km New Channel Construction: L=11.4km Pump Station Installation: 2 stations 8.7 cub.m/s capacity 2) Wastewater Disposal: The Study Area is divided into three areas based on the areal population density as follows: Area A: Simple On-site Treatment System Development Area B: High level On-site Treatment System Development Area C: Sewerage Development The capacity of sewerage treatment system in 2010 is 1252000 cub.m/d and total proposed sewer length is 2223km.						
6.COUNTERPART AGENCY	CIPITA KARYA DKI JAKARTA	4.CONDITIONS AND DEVELOPMENT IMPACTS						
7.OBJECTIVES OF STUDY	Prepare a master plan up to 2010 on urban drainage and wastewater disposal in the city of Jakarta							
8.DATE OF S/W	Dec.1988	1) Urban Drainage: The proposed drainage development plan is formulated in conformity with the other on-going urban drainage project. 2) Wastewater Disposal: The existing population of DKI Jakarta is 9 millions. Areas of high population density with more than 500 persons/ha. are located in the central part of DKI Jakarta with no sewerage system. It causes to aggravate the river water quality and the environmental conditions of continuity in the city of Jakarta. Hence, the sewerage development as the most efficient measures is proposed to mitigate it.						
9.CONSULTANT(S)	Pacific Consultants International Nihon Koel Co., Ltd.	5. TECHNICAL TRANSFER						
10.STUDY TEAM	No.of Members 13 Period Sep.1989-Feb.1991(17 months) <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td></td> <td style="text-align: center;">25.92</td> <td style="text-align: center;">82.77</td> </tr> </table>							Total M/M
Total M/M	Japan	Field						
	25.92	82.77						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	- Topographic Survey - Water Quality Analysis - Installation of Automatic Water Level	3.PRINCIPAL SOURCE OF INFORMATION						
12.EXPENDITURE	<table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: center;">380,130 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">360,592</td> </tr> </table>						Total	380,130 (¥'000)
Total	380,130 (¥'000)							
Contracted	360,592							
		- Counterparts training in Japan was conducted. - Technical knowledge was transferred by the internal discussion with JICA Study Team members.			①			
		2.MAJOR REASONS FOR PRESENT STATUS						

和名 ジャカルタ市都市排水・下水道整備計画

(M/P,M/P+(F/S),Basic Study,Other)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 219B/90

Compiled Mar.1992

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA		Urban Drainage: 38 sq.km Wastewater Disposal: 43 sq.km		1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY		2.PROJECT COST		Total Cost	Local Cost		
Urban Drainage and Wastewater Disposal Project in the City of Jakarta		(US\$1,000)		1) 27,700	2) 240,700		
3.SECTOR		3.CONTENTIS OF MAJOR PROJECT(S)				(Description) 1) Urban Drainage The proposed project will be implemented by the Government of Indonesia as supplementary to the existing on-going project. 2) Wastewater Disposal The proposed project will be implemented in two phases because it requires a large cost of US\$ 240.7 million at 1990 price and the long construction period of eight years. The first phase will be completed in 1996. The second phase will be implemented subsequently to complete in 2000. The necessary arrangements for the implementation of the first phase project from 1992 with OECF loan are now being undertaken by the Government of Indonesia. Detailed design of North Central Jakarta Sewerage Area will be undertaken from Oct.1993. The construction of part of the treatment plant at Pluit Pond will be completed within 45 months after the completion of the detailed design. The detailed design study and the implementation will be financed by OECF yen credit. Oct. 1992 OECF loan agreement signed (2,121 million yen)	
Public Utilities/Sewerage		1) Urban Drainage: Channel Improvement: L=27.4km Revetment works: L=46km Bridge improvement: 15 places					
4.REFERENCE NO.		2) Wastewater Disposal: Sewer lines					
5.TYPE OF STUDY		-Conveyance sewer: dia.1900 - 2900mm L=10.34km					
6.COUNTERPART AGENCY		-Collection sewer: dia.150 - 1500mm L=538km					
CIPTA KARYA DKI JAKARTA		: Booster pump station /place 63 cub.m/min.					
7.OBJECTIVES OF STUDY		: Treatment plant: Aerated lagoon system (Pluit Pond) Q=530000 cub.m/d					
Conduct a feasibility for the priority areas selected in the master plan		Imp. Period: 1992-2000					
8.DATE OF S/W		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: EIRR1) 20.00 FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)			
Dec.1988		Yes					
9.CONSULTANT(S)		Conditions and Development Impacts:					
Pacific Consultants International Nihon Koei Co., Ltd.		1) Urban Drainage : The economic efficiency of the proposed project is estimated as follows. NPV : US\$ 11.3 million B/C : 2.15 EIRR : 20.0%					
10.STUDY TEAM		2) Wastewater Disposal :					
No.of Members 13		The total pollution load reduction by sewerage development in the Project Area is estimated at 49659kg/d as BOD, which represents a reduction efficiency of 84% with impact to the total pollutin load discharge of 59145kg/d in the year 2000. The sewerage development is further expected to contribute the pollution load reduction of 21210kg/d from 24960kg/d to 3750kg/d as BOD in the JSSP Area in the year 2000.					
Period Sep.1989-Feb.1991(17 months)							
Total M/M		Japan		Field			
		25.92		82.77			
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5.TECHNICAL TRANSFER					
- Topographic Survey - Water Quality Analysis - Existing Sanitary Condition along Rivers		Technical knowledge was transferred to the Indonesian side by Seminar and internal discussion with JICA Study Team members.					
12.EXPENDITURE				3.PRINCIPAL SOURCE OF INFORMATION			
Total		380,130 (¥'000)		①④			
Contracted		360,592					

和名 ジャカルタ市都市排水・下水道整備計画

{F/S,(M/P)+F/S,D/D}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 217A/90

Compiled Mar.1992
Revised

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDY RESULTS																
1.COUNTRY	Indonesia	1.SITE OR AREA	JABOTABEK area 2.PROJECT COST <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;"></td> <td style="width: 10%; text-align: center;">(US\$1,000)</td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 10%; text-align: center;">Foreign Cost</td> </tr> <tr> <td>1)</td> <td></td> <td style="text-align: right;">37,082</td> <td style="text-align: right;">17,888</td> <td style="text-align: right;">19,193</td> </tr> <tr> <td>2)</td> <td></td> <td style="text-align: right;">254,904</td> <td style="text-align: right;">95,906</td> <td style="text-align: right;">158,995</td> </tr> </table> US\$1=1,758Rp				(US\$1,000)	Total Cost	Local Cost	Foreign Cost	1)		37,082	17,888	19,193	2)		254,904	95,906	158,995	1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
	(US\$1,000)	Total Cost				Local Cost	Foreign Cost															
1)		37,082	17,888	19,193																		
2)		254,904	95,906	158,995																		
2.NAME OF STUDY	Integrated Transportation System Improvement by Railway and Feeder Service in Jabotabek Area	3.CONTENTES OF MAJOR PROJECT(S)	(Description) The reinforcement plan of the railway side (JABOTABEK railway plan) on which this master plan is based has been steadily being materialized, since the establishment of the master plan in 1981, through F/S, D/D, and construction execution. Considering the long-term development of the JABOTABEK area, it is necessary to establish an integrated transportation system based on individual improvement plans in the urban railway and road sectors. In this regard, the following recommendations were made toward the organic harmony of the railway and road plans. (1) Select an optimum pattern taking into consideration the reinforcement plans of the railway and roads. (2) Propose a master plan for reinforcement that should be done by the railway side based on the above optimum pattern. (3) Based on (2), projects to be urgently implemented were selected. 4.CONDITIONS AND DEVELOPMENT IMPACTS M/P: Increase the railway share up to 15% and alleviate train congestion by increasing train frequency through reinforcing the JABOTABEK railway and also by improving feeder service. It is possible to confirm the adequacy of the integrated transportation system as a whole which aims at organic coordination of the railway and roads toward 2005. Drastic service improvement can also be expected by promoting the railway reinforcement plan. Furthermore, increase in passenger traffic can be expected by improving the access of the railway and roads through upgrading feeder services and reinforcing station plazas, transfer facilities, etc.																			
3.SECTOR	Transportation/Railway																					
4.REFERENCE NO.																						
5.TYPE OF STUDY	M/P+(F/S)																					
6.COUNTERPART AGENCY	PHBD, Indonesia																					
7.OBJECTIVES OF STUDY	M/P for JABOTABEK area up to 2005																					
8.DATE OF S/W	Feb.1988																					
9.CONSULTANT(S)	Japan Railway Technical Service Pacific Consultants International																					
10.STUDY TEAM	No.of Members 15 Period Nov.1988-Aug.1990 (21 months) <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%; text-align: center;">Total M/M</td> <td style="width: 30%; text-align: center;">Japan</td> <td style="width: 40%; text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">109.20</td> <td style="text-align: center;">51.30</td> <td style="text-align: center;">57.90</td> </tr> </table>	Total M/M					Japan	Field	109.20	51.30	57.90											
Total M/M	Japan	Field																				
109.20	51.30	57.90																				
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	None																					
12.EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;"></td> <td style="width: 30%; text-align: center;">Total</td> <td style="width: 40%; text-align: right;">342,883 (Y'000)</td> </tr> <tr> <td></td> <td style="text-align: center;">Contracted</td> <td style="text-align: right;">335,000</td> </tr> </table>		Total	342,883 (Y'000)		Contracted	335,000	5.technical transfer	2.MAJOR REASONS FOR PRESENT STATUS 1. Size of project effect 2. Recognition, by the Indonesian side, of the importance of railway reinforcement 3. Much assistance from the Japanese side (Funds, technical cooperation, services)													
	Total	342,883 (Y'000)																				
	Contracted	335,000																				
		1)Preparation, explanation, and discussion of the Working Paper 2)Two counterparts received JICA training, and also participated in the overall discussions.	3.PRINCIPAL SOURCE OF INFORMATION	①																		

和名 ジャボタバック圏統合輸送システム改良計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 217B/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT		
1.COUNTRY	Indonesia	1.SITE OR AREA		JABOTABEK Area		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing	
2.NAME OF STUDY	Integrated Transportation System Improvement by Railway and Feeder Service in Jabotabek Area	2.PROJECT COST		Total Cost	Local Cost			Foreign Cost
3.SECTOR	Transportation/Railway			(US\$1,000)	1)	37,082	17,888	19,193
4.REFERENCE NO.				US\$1=1758Rp	2)	254,904	95,906	158,995
5.TYPE OF STUDY	(M/P)+F/S	3.CONTENTS OF MAJOR PROJECT(S)				(Description)		
6.COUNTERPART AGENCY	PHBD, Indonesia	F/S deals with the following urgent projects. (1) Improvement of feeder services and facilities of the three stations. (Pasar Senen, Jatinegara, Kemayoran) - Separate pedestrians and motor vehicles on roads near station. - Expand roads leading to stations; Establish signals and overpasses. - Set up bus bays in station plazas. An improvement plan was drawn up for the three most important stations selected from 63 stations. (2) Station facilities improvement - station building, platform, overbridge, platform shed Station facilities to be improved are closely related to feeder services, therefore it is effective to make the improvements of station facilities simultaneously with the improvements in feeder services. (3) Grade separation of the Eastern Line - track elevation, flyover system						
7.OBJECTIVES OF STUDY	F/S for urgent project based on the M/P up to 2005	8.DATE OF S/W		Feb.1988		The station building improvement, station plaza reinforcement, etc. are going to be implemented jointly with some projections included in the JABOTABEK Project (such as track elevation, double tracking, and electrification of the Central Line), and the construction is under way. As for the platform improvement of thb, Jng, and Pse station, the construction will start one by one by using OECF funds authorized for fiscal 1991. It is necessary to continue studies hereafter concerning the handling of the track elevation of the East Line, since this projection is not included in the sealed-down plan. Furthermore, adjustment with a recommendation of introducing a LRT to the East Line voiced in connection with another project.		
9.CONSULTANT(S)	Japan Railway Technical Service Pacific Consultants International	Imp. Period:		.1993-.2005 .1997-.2002				
10.STUDY TEAM	No.of Members 15 Period Nov.1988-Aug.1990 (21 months)	4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes		EIRR1) 34.78 FIRR1) 6.33 EIRR2) 15.22 FIRR2) EIRR3) FIRR3)		
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	None	Conditions and Development Impacts:		Preconditions:		2.MAJOR REASONS FOR PRESENT STATUS		
12.EXPENDITURE	Total 342,883 (¥'000) Contracted 335,000	1.Project life: 20 years after completion of the project. 2.Standard time for value estimation: april 1989 3. Exchange rate: 1US\$=1,758 Rp (1) Develop the passenger convenience and increase the passenger traffic through improving feeder services and facilities of the three stations. (2) Enable to increase the train frequency on the East Line and to deal with the increasing traffic on level crossings. (3) Time saving for travel and freight transportation, time savings at major railway crossings. (4) The land of the existing Kota is also expected to be utilized after the completion of the new station. Note: F/S 1) Sufficient economic feasibility is shown for the improvement of the three stations; 2) With respect to the project of Grade Separation of the Eastern Line, only economic analysis was carried out, because financial analysis is not so meaningful due to the characteristics of the project.						
		5. TECHNICAL TRANSFER		1) Preparation, explanation, and discussion of the Working Paper. 2) Two counterparts received JICA training, and also participated in the overall discussions.		3. PRINCIPAL SOURCE OF INFORMATION		
						①④		

和名 ジャボタバック圏統合輸送システム改良計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P+F/S)

Compiled Mar.1992

Revised Mar.1993

ASE IDN/S 218A/90

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																					
1.COUNTRY	Indonesia	1.SITE OR AREA	Surabaya and its surrounding area (GERBANGKERTOSUSILA) and Jombang		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued																				
2.NAME OF STUDY Long-Term and Medium-Term Plan for Telecommunications Network in Surabaya and Surrounding Areas		2.PROJECT COST			(Description) Followed by F/S.																					
3.SECTOR Communications & Broadcasting/Telecommunication		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;"></td> <td style="width: 10%;"></td> <td style="width: 10%; text-align: center;">Total Cost</td> <td style="width: 10%; text-align: center;">Local Cost</td> <td style="width: 10%; text-align: center;">Foreign Cost</td> </tr> <tr> <td>(US\$1,000)</td> <td></td> <td style="text-align: center;">1) 854,000</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">2)</td> <td></td> <td></td> </tr> <tr> <td>US\$1 = Rp1,850 = 148Yen</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>							Total Cost	Local Cost	Foreign Cost	(US\$1,000)		1) 854,000					2)			US\$1 = Rp1,850 = 148Yen				
		Total Cost	Local Cost	Foreign Cost																						
(US\$1,000)		1) 854,000																								
		2)																								
US\$1 = Rp1,850 = 148Yen																										
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)																								
5.TYPE OF STUDY M/P+(F/S)		Long-term plan (2004) : - Surabaya Multi-Exchange Area 1) Expansion of Surabaya multi-exchange area 2) Provision of Telephone Exchange capacity up to 408000 line unit (Telephone Density: 8.0/100) 3) Establishment of Route Diversity Configuration for Junction Network - Surrounding Area 1) Improvement of Telephone Density in Kabupaten capitals up to 8.0/100 inhabitants 2) Provision of Automatic Telephone Service to all villages (DESA).																								
6.COUNTERPART AGENCY Directorate General, Posts and Telecommunications		4.CONDITIONS AND DEVELOPMENT IMPACTS			2.MAJOR REASONS FOR PRESENT STATUS To fulfill the target at the end of Repelita V (1994).																					
7.OBJECTIVES OF STUDY The long-term and medium-term plan for telecommunications network in Surabaya and surrounding areas		Telephone supply strategy applied in this Study is based on the supply difference between Jakarta and Surabaya. The supply difference as of the end of Repelita V in telephone density will be kept up to the year 2004 to stop a magnification of the difference. The implementation of the proposed master plan is anticipated to give a variety of impacts on socioeconomy of the study area, especially on the following aspects: - Regional Development - Urban and Industrial areas - Rural areas																								
8.DATE OF S/W Jun.1988		10.STUDY TEAM			3.PRINCIPAL SOURCE OF INFORMATION ①																					
9.CONSULTANT(S) Nippon Telecommunication Consulting Co., Ltd.																										
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY None.		5.TECHNICAL TRANSFER																								
12.EXPENDITURE		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;"></td> <td style="width: 10%;"></td> <td style="width: 10%; text-align: center;">Total</td> <td style="width: 10%; text-align: center;">Japan</td> <td style="width: 10%; text-align: center;">Field</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">1) 202,367 (¥'000)</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">2)</td> <td></td> <td></td> </tr> <tr> <td>Contracted</td> <td></td> <td style="text-align: center;">3) 185,234</td> <td></td> <td></td> </tr> </table>					Total	Japan	Field			1) 202,367 (¥'000)					2)			Contracted		3) 185,234				
		Total	Japan	Field																						
		1) 202,367 (¥'000)																								
		2)																								
Contracted		3) 185,234																								
		1) OJT was conducted for the counterparts during the field survey. 2) Technology transfer was conducted through local consultants employed. 3) Training was conducted in Japan accepting counterparts as trainees of Colombo																								

和名 スラバヤ都市圏電気通信網整備計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/S 218B/90

Compiled Mar.1992

Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA				1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input checked="" type="checkbox"/> Processing
2.NAME OF STUDY	Long-Term and Medium-Term Plan for Telecommunications Network in Surabaya and Surrounding Areas	Surabaya and its surrounding area (GERBANGKERTOSUSILA) and Jombang					
3.SECTOR	Communications & Broadcasting/Telecommunication	2.PROJECT COST		Total Cost	Local Cost	Foreign Cost	
4.REFERENCE NO.		(US\$1,000)	1) 27,560	3,440	24,120	(Description) A part of proposed project (some sections of junction network in Surabaya multi-exchange area and some sections of trunk network) is scheduled to be implemented in order to achieve the targets at the end of Repelita V (1994). Oct. 1992 OECF loan agreement signed (2,941 million yen) A consulting contract between P.T. TELKOM (EX-PERUMTEL) and NTC in association with PT. WIDYA DUTA INFORMINDO (LOCAL CONSULTANT) was signed in Mar. 1993. Implementation Schedule 1) Tender (Invitation-Negotiation): beginning of 1994 2) Contract and start of implementation: Mid.1994 3) Completion of construction: Mid. 1995 The request of the assistance by Government of Japan is being prepared to implement the remaining portion of the project.	
5.TYPE OF STUDY	(M/P)+F/S	US\$1 = Rp1,850 = 148yen		2) 1)	3) 2)		
6.COUNTERPART AGENCY	Directorate General Posts and Telecommunications	3.CONTENTS OF MAJOR PROJECT(S)				2.MAJOR REASONS FOR PRESENT STATUS Urgent implementation is required to achieve the targets of the end of Repelita V (1994).	
7.OBJECTIVES OF STUDY	The long-term and medium-term plan for telecommunications network in Surabaya and surrounding areas	1. Expansion of Junction Network in Surabaya Multi-exchange Area 1) Fiber-optic transmission system : 13 new sections, expansion of 13 existing sections. (140 Mbit/s) 2) Microwave system upgraded : 1 hop (87 bit/s to 34 Mbit/s system) 2. Improvement of Trunk Network 1) Installation of new microwave link : 1.5 Ghz 8 Mbit/s system; 5 hops. 2 GHz 34 Mbit/s system; 4 hops 2) Microwave system upgrading : 4 hops (8 Mbit/s to 34 Mbit/s system) 3. Improvement of Rural Area Network 9 base stations, 64 radio subscriber terminals, 1,700 subscribers.					
8.DATE OF S/W	Jun.1988	Imp. Period: 1992-1994				3.PRINCIPAL SOURCE OF INFORMATION ①④	
9.CONSULTANT(S)	Nippon Telecommunication Consulting Co., Ltd.	4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 14.85 EIRR2) EIRR3)		
10.STUDY TEAM	No.of Members 7 Period Sep.1988-Dec.1990 (13 months)	Conditions and Development Impacts: 1. The project proposed in this study is formulated based on the completion of on-going projects on the basis of the scope of work "TELECOM III". 2. The project should be implemented coordinated with telephone exchange digitalization program in the objective area. 3. The implementation of proposed project is anticipated to give a variety of impacts on socioeconomy of the objective area, especially following aspects: - Regional development - Urban and industrial areas - Rural areas.				3.PRINCIPAL SOURCE OF INFORMATION ①④	
	Total M/M Japan Field 60.53 20.34 40.18						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	None.	5. TECHNICAL TRANSFER				3.PRINCIPAL SOURCE OF INFORMATION ①④	
12.EXPENDITURE	Total 202,367 (¥'000) Contracted 185,234	1) OJT was conducted for the counterparts during the field survey. 2) Technology transfer was conducted through local consultants employed. 3) Training was conducted in Japan accepting 2 counterpart as trainees during home study period of the Study Team. 4) Contents of DR/R was presented by counterparts trained in					

和名 スラバヤ都市圏電気通信網整備計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P+F/S)

ASE IDN/A 201A/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS				
1.COUNTRY	Indonesia	1.SITE OR AREA	Kabupaten Asahan in North Sumatra Province			1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued		
2.NAME OF STUDY	Master Plan Study on Lower Asahan River Basin Development	2.PROJECT COST						Total Cost	Local Cost
3.SECTOR	Agriculture/General		(US\$1,000)	1) 1,285,000	2)	(Description) Based on the result of this study, the feasibility study of the Silan-Bunut rehabilitation irrigation project was conducted.			
4.REFERENCE NO.		3.CONTENTES OF MAJOR PROJECT(S)							
5.TYPE OF STUDY	M/P+(F/S)	Among study area of 6,000 km ² , the following ten projects are formulated: (i) Silau-Bunut rehabilitation irrigation project (14,300ha) (ii) Padang Mahondang irrigation extension project (6,200ha) (iii) Kanopan left bank drainage improvement project (4,300ha) (iv) Small-scale irrigation package project (7,200ha) (v) Aek Natas irrigation project (4,200ha) (vi) Aek Naetek irrigation project (3,500ha) (vii) Kualuh right bank irrigation project (2,400ha) (viii) Tambun Tulang swamp development project (5,800ha) (ix) Simpang Empat swamp development project (2,800ha) (x) Leldong-Asahan swamp development project (45,600ha)							
6.COUNTERPART AGENCY	Directorate General of Water Resources Development, Ministry of Public Works	4.CONDITIONS AND DEVELOPMENT IMPACTS							
7.OBJECTIVES OF STUDY	Formulation of agricultural development master plan in line with the flood control projects	Optimum utilization of development potential of land and water resources in the area of the lower Asahan river basin having 6,000km ² in Kabupaten Asahan was undertaken. Jen irrigation/survey development project were formulated. The target year of the basin development study is set to be the year of 2005. The final target of the projects aim to provide 10% of rice demand in the year of 2005 in North Sumatra province. Priority sequence of 10 projects was determined based on three indicators such as economic feasibility, investment cost/ha and number of beneficiaries. As a result, the Silan-Bunut rehabilitation irrigation project and the Padang Mahondang irrigation extension project were ranked 1st and 2nd priority, respectively. The expected increase of rice production is about 1.2 million tons on 10% of the provincial target of paddy production.							
8.DATE OF S/W	Jul.1984	2.MAJOR REASONS FOR PRESENT STATUS							
9.CONSULTANT(S)	Nihon Koei Co., Ltd. Nikken Consultants., Inc. Yachiyo Engineering Co., Ltd.	3.PRINCIPAL SOURCE OF INFORMATION							
10.STUDY TEAM	No.of Members 9 Period Jun.1989-Jun.1990(13 months)	①							
	<table style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 0 10px;">Total M/M</td> <td style="padding: 0 10px;">Japan</td> <td style="padding: 0 10px;">Field</td> </tr> <tr> <td style="text-align: center;">56.19</td> <td style="text-align: center;">20.63</td> <td style="text-align: center;">35.56</td> </tr> </table>							Total M/M	Japan
Total M/M	Japan	Field							
56.19	20.63	35.56							
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER							
12.EXPENDITURE		Technical transfer to counterparts in the course of the field survey and study.							
	<table style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 0 10px;">Total</td> <td style="padding: 0 10px;">255,621 (¥'000)</td> </tr> <tr> <td style="padding: 0 10px;">Contracted</td> <td style="padding: 0 10px;">171,668</td> </tr> </table>	Total	255,621 (¥'000)	Contracted	171,668				
Total	255,621 (¥'000)								
Contracted	171,668								

和名 アサハン河下流域開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

ASE IDN/A 201B/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																										
1.COUNTRY	Indonesia	1.SITE OR AREA				1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled																									
2.NAME OF STUDY	Master Plan Study on Lower Asahan River Basin Development	Silau-Bunut Area in Kabupaten Asahan, North Sumatra Province																														
3.SECTOR	Agriculture/General	2.PROJECT COST				(Description) Detailed design of the project is under consideration by the Indonesian Government for the OECF loan.																										
4.REFERENCE NO.		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;"></td> <td style="width: 10%; text-align: center;">1)</td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 15%; text-align: center;">Foreign Cost</td> </tr> <tr> <td style="text-align: center;">(US\$1,000)</td> <td></td> <td style="text-align: center;">8,900</td> <td style="text-align: center;">4,300</td> <td style="text-align: center;">5,600</td> </tr> <tr> <td colspan="2">US\$1.00=1,770Rupiah</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">3)</td> <td></td> <td></td> <td></td> </tr> </table>							1)	Total Cost	Local Cost	Foreign Cost	(US\$1,000)		8,900	4,300	5,600	US\$1.00=1,770Rupiah						2)					3)			
	1)	Total Cost	Local Cost	Foreign Cost																												
(US\$1,000)		8,900	4,300	5,600																												
US\$1.00=1,770Rupiah																																
	2)																															
	3)																															
5.TYPE OF STUDY	(M/P)+F/S	3.CONTENTS OF MAJOR PROJECT(S)																														
6.COUNTERPART AGENCY	Directorate General of Water Resources Development (DGWRD), Ministry of Public Works	1. Construction of an inter-basin water transfer canal from the Silau to the Bunun 2. Construction of an integrated diversion weir on the Silau 3. Rehabilitation of 3 existing weirs on the Silau 4. 60km rehabilitation and 110km construction of irrigation canal 5. Rehabilitation/New construction of drainage canal of 180km 6. Construction of farm road network (about 350km) 7. Construction of on-farm facilities (about 9,500ha) 8. Construction of flood protection dike (34km)																														
7.OBJECTIVES OF STUDY	In-depth study on top priority project selected in the Master Plan Study	4.FEASIBILITY AND ITS ASSUMPTIONS																														
8.DATE OF S/W	Jul.1984	Imp. Period: <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 20%;"></td> <td style="width: 10%; text-align: center;">Feasibility:</td> <td style="width: 15%; text-align: center;">EIRR1)</td> <td style="width: 15%; text-align: center;">13.20</td> <td style="width: 15%; text-align: center;">FIRR1)</td> </tr> <tr> <td></td> <td style="text-align: center;">Yes</td> <td style="text-align: center;">EIRR2)</td> <td></td> <td style="text-align: center;">FIRR2)</td> </tr> <tr> <td></td> <td></td> <td style="text-align: center;">EIRR3)</td> <td></td> <td style="text-align: center;">FIRR3)</td> </tr> </table>					Feasibility:	EIRR1)	13.20	FIRR1)		Yes	EIRR2)		FIRR2)			EIRR3)		FIRR3)												
	Feasibility:	EIRR1)	13.20	FIRR1)																												
	Yes	EIRR2)		FIRR2)																												
		EIRR3)		FIRR3)																												
9.CONSULTANT(S)	Nihon Koei Co., Ltd. Nikken Consultants., Inc. Yachiyo Engineering Co., Ltd.	Conditions and Development Impacts:																														
10.STUDY TEAM	No.of Members 9 Period Jun.1989-Jun.1990 (13 months)	Conditions: Irrigation benefit is the difference of primary project from crops between future with project and without project conditions.																														
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	1. Geological/soil mechanical survey 2. Topographic survey	Development Impacts: -Increase of job opportunity and rice production (about 109,300 tons) -Increase in farmer's income -Improvement of marketing -EIRR = 13.2%																														
12.EXPENDITURE	Total 255,621 (¥'000) Contracted 171,668	5. TECHNICAL TRANSFER																														
		Technical transfer to counterparts in the course of the field survey and study. Seminar about the results of the project study at the end of the field survey period.																														
		2.MAJOR REASONS FOR PRESENT STATUS																														
		3.PRINCIPAL SOURCE OF INFORMATION																														
		①																														

和名 アサハン河下流域開発計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/S 339/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																									
1.COUNTRY	Indonesia	1.SITE OR AREA		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="4">West Java Province, Java Island, Indonesia</td> </tr> <tr> <td colspan="2">2.PROJECT COST</td> <td>Total Cost</td> <td>Local Cost</td> <td>Foreign Cost</td> </tr> <tr> <td>(US\$1,000)</td> <td>1)</td> <td>337,380</td> <td>132,140</td> <td>205,240</td> </tr> <tr> <td>US\$1=Rp.1,750=145yen</td> <td>2)</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>3)</td> <td></td> <td></td> <td></td> </tr> </table>		West Java Province, Java Island, Indonesia				2.PROJECT COST		Total Cost	Local Cost	Foreign Cost	(US\$1,000)	1)	337,380	132,140	205,240	US\$1=Rp.1,750=145yen	2)					3)				1.PRESENT STATUS <input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled	
West Java Province, Java Island, Indonesia																															
2.PROJECT COST		Total Cost	Local Cost	Foreign Cost																											
(US\$1,000)	1)	337,380	132,140	205,240																											
US\$1=Rp.1,750=145yen	2)																														
	3)																														
2.NAME OF STUDY	Bogor-Bandung Road Project	3.CONTENTES OF MAJOR PROJECT(S)																													
3.SECTOR	Transportation/Road	1) Construction of new road that shall include the extension of the Jaqorawi Toll Road and link the main cities of West Java Province: Cibadak, Sukabumi, and Cianjur. The new road, length 100m, shall terminate at the new Cikampek-Padalaranq Toll Road. Project cost is US\$ 324 million. The new Bogor-Bandung Road is recommended to be constructed as a four lane access controlled road in its final form. However, by taking into account the expected growth of traffic demand and the balance between cost and benefit as major factors, the construction is recommended to be implemeted in three phases as follows: 1) Extension of the Jaqorawi tollroad until Sukabumi with a two lane access controlled road; 2) Extension of the same road until Citatah with a two lane access controlled road. The whole of the Boqor-Bandung Road is temporarily connected by the end of this phase with a two lane across controlled road; 3)Widening of the Boqor-Bandung Road to a four lane road at the section between Ciawi and Sukabumi. Widening of the rest, namely the section bewteen Sukabumi and Citatah, is recommended to be taken into account the traffic demand build up. 2) Widening of the existing 15km-long road connecting Puncak Pass with Jaqorawi Toll Road. Project cost: US\$ 13 million. The Program recommended consists of the spot improvement at several locations such as Taman Safari intersection and Cibulan Market; the improvement of road cross section such as paved hard shoulder, introduction of climbing lanes and clearly divided devises such as quard fences, safety mirrors, window central median strip, etc.		(Description) The Indonesian Government has shown a strong interest in this F/S as a countermeasure to the existing Puncak traffic congestion, and a spur to the lagging development in the neighboring Sukabumi region where the potential for tourism and industrial activities is high. But at present the Government identifies projects eligible for foreign aid as those of national high priority, and projects that will contribute to the stable and uniform development among the country's regions and ensure a balanced investment policy amongst them. Therefore, the tendency is that profitable projects should, as much as possible be executed applying the BOT method. However, in the case of road projects, even if the F/S counfirms a high EIRR, the profits will be disseminated in the development effects, etc., resulting in a low FIRR. Therefore, in order to encourage the application of BOT method, it is necessary to improve the FIRR by adopting favourable conditions for soft loan, taxation system, subsidies, etc., all combined. Concerning the road widening projects, the low project cost suggests that it be included in a regional road development package to be financed by Yen credit. F/S showed that even with soft loan FIRR is low and to promote BOT method many issues must be resolved before construction, indicating a long delay in implementation.																											
4.REFERENCE NO.		4.FEASIBILITY AND ITS ASSUMPTIONS				<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Feasibility:</td> <td>EIRR1)</td> <td>17.80</td> <td>FIRR1)</td> <td rowspan="3" style="text-align: center; vertical-align: middle;">8.80</td> </tr> <tr> <td>Yes</td> <td>EIRR2)</td> <td>27.00</td> <td>FIRR2)</td> </tr> <tr> <td></td> <td>EIRR3)</td> <td></td> <td>FIRR3)</td> </tr> </table>		Feasibility:	EIRR1)	17.80	FIRR1)	8.80	Yes	EIRR2)	27.00	FIRR2)		EIRR3)		FIRR3)											
Feasibility:	EIRR1)	17.80	FIRR1)			8.80																									
Yes	EIRR2)	27.00	FIRR2)																												
	EIRR3)		FIRR3)																												
5.TYPE OF STUDY	F/S	5. TECHNICAL TRANSFER				2.MAJOR REASONS FOR PRESENT STATUS																									
6.COUNTERPART AGENCY	Directorate General of Highways Ministry of Public Works	Conditions and Development Impacts: The traffic demand along the road linking two of West Java Pronince's major cities, Boqor and Bandung, is very high. However, the present road network is poor, and the mixture of slow traffic related to daily activities of roadside settlements with the long-distance traffic along the only road linking the new cities creates traffic congestions and slow travelling speeds. The potential of this project area, which is very close to Jakarta, are high in terms of tourism, agriculture and industry, but the development has so far been slow. Furthermore, the project is necessary to meet the increased demand in the flow of people and goods between the two cities and their surrounding areas. Conditions of EIRR: 1)Base Year: 1989, 2)Project Life: 2010-2040 30years after completion of the construction in the third phase, 3)Analysis Period: 1993-2040, 4)Prices: 1989 prices in economic terms, 5)Residual value: None Conditions of FIRR: 1)Toll rates: Passenqer cars 60Rp/km, Truck and bus 90Rp/km, 3% increase/year, 2)interest rate: 5%/year, 3)Repayment conditions Grace period:full construction period (5 years), Installment period: 25 years.				3.PRINCIPAL SOURCE OF INFORMATION																									
7.OBJECTIVES OF STUDY	Development of road network to serve the increasing traffic demand and regional development					①																									
8.DATE OF S/W	Nov.1988	Imp. Period: .1991-.2010																													
9.CONSULTANT(S)	Yachiyo Engineering Co., Ltd. Oriental Consultants Co., Ltd. Kokusai Kougyo Co., Ltd.																														
10.STUDY TEAM	No.of Members 18 Period Mar.1989-Nov.1990 (0 months) <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">65.50</td> <td style="text-align: center;">15.00</td> <td style="text-align: center;">50.50</td> </tr> </table>	Total M/M	Japan	Field	65.50	15.00	50.50																								
Total M/M	Japan	Field																													
65.50	15.00	50.50																													
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	- Traffic Survey - Geological Survey - Aerial Photographic Survey																														
12.EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tr> <td>Total</td> <td style="text-align: right;">295,047 (¥'000)</td> </tr> <tr> <td>Contracted</td> <td style="text-align: right;">278,120</td> </tr> </table>	Total	295,047 (¥'000)	Contracted	278,120	This Study was undertaken in close cooperation with the Indonesian Counterpart Team, and the relationship between high service level roads and regional development was the subject of examination and discussion at a seminar held in Jakarta at the close of the Study.																									
Total	295,047 (¥'000)																														
Contracted	278,120																														

和名 ボゴルーバンドン道路整備計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/S 340/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																											
1.COUNTRY	Indonesia	1.SITE OR AREA	South Kalimantan			1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing																										
2.NAME OF STUDY	Maintenance Dredging in the Access Channel of Banjarmasin Port	2.PROJECT COST						Total Cost	Local Cost	Foreign Cost																							
3.SECTOR	Transportation/Port		(US\$1,000)	1) 51,100	14,100	37,000	(Description) No action has been taken toward implementation.																										
4.REFERENCE NO.		3.CONTENTS OF MAJOR PROJECT(S)																															
5.TYPE OF STUDY	F/S	First-stage Plan aiming the year 1995 Comprehensive Plan aiming the year 2000 Siltation counter measures: Both sides of the access channel Length: 11km (7km First-stage) Effective planning and management of maintenance dredging Arrangement of navigational aids and procurement of pilot boat																															
6.COUNTERPART AGENCY	Directorate General of Sea Communication																																
7.OBJECTIVES OF STUDY	Development of siltation counter measures in the access channel and effective planning and management of maintenance dredging																																
8.DATE OF S/W	Nov.1987	Imp. Period: .1993-.2000																															
9.CONSULTANT(S)	Overseas Coastal Area Development Institute of Japan Nippon Tetrapod Co., Ltd.	4.FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes/No	EIRR1) 13.20 EIRR2) EIRR3)	FIRR1) 5.00 FIRR2) FIRR3)																												
10.STUDY TEAM	No.of Members 13 Period Mar.1988-Mar.1991 (37 months) <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">159.69</td> <td style="text-align: center;">84.45</td> <td style="text-align: center;">75.25</td> </tr> </table>	Total M/M	Japan	Field	159.69	84.45		75.25	Conditions and Development Impacts: (First-stage) <table style="width: 100%; border: none;"> <tr> <td></td> <td style="text-align: center;">Without Case</td> <td style="text-align: center;">With Case</td> </tr> <tr> <td>Channel Size :</td> <td style="text-align: center;">Depth/6m, Width/100m</td> <td style="text-align: center;">Depth/6m, Width/100m</td> </tr> <tr> <td>Annual Maintenance :</td> <td style="text-align: center;">5.1 million c.m</td> <td style="text-align: center;">3.5 million c.m</td> </tr> <tr> <td>Dredging Volume</td> <td></td> <td></td> </tr> <tr> <td>Unit Cost</td> <td></td> <td></td> </tr> <tr> <td>- Economic Price :</td> <td style="text-align: center;">1.9 US\$/c.m</td> <td style="text-align: center;">1.9 US\$/c.m</td> </tr> <tr> <td>- Nominal Price :</td> <td style="text-align: center;">0.7 US\$/c.m - 1.9 US\$/c.m (1996 - 2025)</td> <td style="text-align: center;">0.7 US\$/c.m - 1.9 US\$/c.m (1996 - 2025)</td> </tr> </table>					Without Case	With Case	Channel Size :	Depth/6m, Width/100m	Depth/6m, Width/100m	Annual Maintenance :	5.1 million c.m	3.5 million c.m	Dredging Volume			Unit Cost			- Economic Price :	1.9 US\$/c.m	1.9 US\$/c.m	- Nominal Price :	0.7 US\$/c.m - 1.9 US\$/c.m (1996 - 2025)	0.7 US\$/c.m - 1.9 US\$/c.m (1996 - 2025)
Total M/M	Japan	Field																															
159.69	84.45	75.25																															
	Without Case	With Case																															
Channel Size :	Depth/6m, Width/100m	Depth/6m, Width/100m																															
Annual Maintenance :	5.1 million c.m	3.5 million c.m																															
Dredging Volume																																	
Unit Cost																																	
- Economic Price :	1.9 US\$/c.m	1.9 US\$/c.m																															
- Nominal Price :	0.7 US\$/c.m - 1.9 US\$/c.m (1996 - 2025)	0.7 US\$/c.m - 1.9 US\$/c.m (1996 - 2025)																															
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Geodeta Berlian Center p.t.																																
12.EXPENDITURE	Total 855,401 (¥'000) Contracted	5. TECHNICAL TRANSFER																															
		1. Seminars in Indonesia; Large Scale Seminar(Once), Small Scale Seminar (Three times), Training for the Survey Equipment (Two times) 2. Counterpart Training in Japan: No. of counterparts : 2 persons, Period : 11/1989 - 12/1989																															
		3.PRINCIPAL SOURCE OF INFORMATION																															
		①																															
		2.MAJOR REASONS FOR PRESENT STATUS																															
		The project cost is too large. The privatization of the Port Authority and the Dredging Corporation is being considered.																															

和名 バンジャルマシンの港航路維持・浚渫計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (F/S)

ASE IDN/A 312/90

Compiled Mar.1992
Revised Mar.1993

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT		
1.COUNTRY	Indonesia	1.SITE OR AREA	14,800ha on the Selagan River in kec. Muko-Muko Utara, Kab. Bangkulu Utara, Bengkulu Province.			1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled	
2.NAME OF STUDY	Air Selagan Irrigation Project	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost			
3.SECTOR	Agriculture/General		(US\$1,000)	1) 37,325	2) 9,842	3) 27,483		
4.REFERENCE NO.		3.CONTENTS OF MAJOR PROJECT(S)	The Project is mainly for irrigation and drainage to the paddy field 4,200ha and Plantation area, 2,750ha for oil palm and corn in the existing and additional transmigration area and included the following contents. (1) Construction of weir, (2) Construction of irrigation and drainage facilities, (3) Construction of inspection roads and connecting roads, (4) Construction of tertiary networks, (5) Reclamation of new farm lands, (6) Construction of O & M facilities and, (7) Construction of small-scale hydro-power station.				(Description) Directorate General of Water Resources Development, Ministry of Public Works, is making preparations to apply for an OECF Loan on detailed design and construction.	
5.TYPE OF STUDY	F/S	4.FEASIBILITY AND ITS ASSUMPTIONS						Feasibility: Yes
6.COUNTERPART AGENCY	Directorate of Irrigation II, Directorate General of Water-Resources Development, Ministry of Public Works.	7.OBJECTIVES OF STUDY	Conditions and Development Impacts: The Project is not only for irrigation and drainage for paddy cultivation and oil palm and corn plantation in the transmigration area, but also for small scale hydro-power generation, flood protection work, domestic water supply, etc. Therefore, it is especially necessary to pay the attention to the followings. (1) It is expected that additional transmigration is implemented on schedule. (2) Coordination among authorities concerned and among related projects around the site. It is strongly expected that the Project is urgently implemented for the emergent transmigrants from Kedung Onbo in the Central Java especially. To promote agricultural development in the study area situated in the agricultural region (northern part of the Province) contemplated by the Provincial Government is not only to contribute the economic stabilization of the transmigrants and local people in the study area, but also to imply the realization of a strong impact of the agricultural development to the region in the neighborhood.				2.MAJOR REASONS FOR PRESENT STATUS To realize an economic stability of the farmers in the Area to encourage the transmigration scheme and to keep self-sufficiency of rice in national level.	
8.DATE OF S/W	Feb.1989	8.DATE OF S/W						Imp. Period: 1991-1996
9.CONSULTANT(S)	Japan Irrigation and Reclamation Consultants Co, Nihon Koei Co., Ltd.	10.STUDY TEAM	5. TECHNICAL TRANSFER Provision of transfer of technology to Indonesian counterpart personnel in the course of the Study.				3.PRINCIPAL SOURCE OF INFORMATION ①	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Survey, Geological Investigation, Soil Mechanical Tests, Installation of Hydroclimatological Observation Equipments and Environmental Assessment Study	No. of Members 10 Period Aug.1989-Nov.1990(15 months) <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">40.91</td> <td style="text-align: center;">16.94</td> <td style="text-align: center;">23.97</td> </tr> </table>						Total M/M
Total M/M	Japan	Field						
40.91	16.94	23.97						
12.EXPENDITURE								
	Total	148,867 (¥'000)						
	Contracted	143,474						

和名 アイルスラガン灌漑開発計画

(F/S,(M/P)+F/S,D/D)

PROJECT SUMMARY (M/P+F/S)

Compiled Mar.1993

Revised

ASE IDN/S 220A/91

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS									
1.COUNTRY	Indonesia	1.SITE OR AREA	Integrated river basins between Belawan and Padang rivers of approx. 5,800km ²		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued								
2.NAME OF STUDY	Belawan-Padang Integrated River Basin Development	2.PROJECT COST	Total Cost Local Cost Foreign Cost (US\$1,000) 1) 390,390 cost in Sept. 1991 2)		(Description)									
3.SECTOR	Social Infrastructures/River & Erosion Control	3.CONTENTS OF MAJOR PROJECT(S)												
4.REFERENCE NO.		Master Plan (1995-2010): Total implementation costs of 761.26 bil.Rp 1. Flood Control Plan (1) Belawan River River improvement (21.9km) (2) Deli-Perhut River system: a)Deli river improvement (37.4km); b)Medan Floodway (3.8km); c)Namobatanq Dam; d)Perhut river improvement (28.0km); e)Lausimeme Dam (3) Serdang River River improvement (25.4km) (4) Ular River Karal Dam (5) Belutu River River improvement (32.7km) (6) Padang River River improvement (29.5km) 2. Water Utilization Plan (1) Lausimeme Dam Reservoir capacity 33.40 MCM (2) Namobatanq Dam Reservoir Capacity 14.60 MCM (3) Belumai Sluice Way * Both dams are to serve two functions of flood control and water supply to the Medan Area.												
5.TYPE OF STUDY	M/P+ (F/S)	4.CONDITIONS AND DEVELOPMENT IMPACTS												
6.COUNTERPART AGENCY	Directorate of Planning & Programming, Directorate General of Water Resources Development, Ministry of Public Works	Assumptions: - The flood control project scale was set at a 100-year return period for the Deli-Perhut River System and a 50-year period for the other rivers. River improvement was proposed for the areas which are flooded in a 100-year period. - Based on the projected population for 2010 in the study area and the standards for Repelita V set by the General Directorate of Human Settlements, the water demands (cu.m./day) were estimated as follows: <table style="margin-left: 20px; border: none;"> <tr> <td style="text-align: right;">Population(,000)</td> <td style="text-align: right;">Water Demand(cu.m./day)</td> </tr> <tr> <td style="text-align: right;">Medan 2,679</td> <td style="text-align: right;">597,723</td> </tr> <tr> <td style="text-align: right;">Tebing Tinggi 173</td> <td style="text-align: right;">38,639</td> </tr> <tr> <td style="text-align: right;">Other eight river basins 2,753</td> <td style="text-align: right;">127,440</td> </tr> </table> - The implementation schedule was identified, by taking into consideration 1)urgent needs to reduce flood damages and to meet the growing demands for water in urban areas, 2)high economic efficiency achievable by the proposed projects, and 3)strengthening and facilitation of the on-going flood control projects. Impacts: Reduction of flood damages and the water supply to Medan and other urban areas. The EIRR for the Master Plan was calculated to be 13.55% (13.90% for the flood control plan and 10.70% for the water utilization plan).					Population(,000)	Water Demand(cu.m./day)	Medan 2,679	597,723	Tebing Tinggi 173	38,639	Other eight river basins 2,753	127,440
Population(,000)	Water Demand(cu.m./day)													
Medan 2,679	597,723													
Tebing Tinggi 173	38,639													
Other eight river basins 2,753	127,440													
7.OBJECTIVES OF STUDY	1)To formulate a Master Plan of integrated river basin development of the integrated river basins from Belawan to Padang, focusing on flood control and water utilization; and 2)To conduct a Feasibility Study on urgent projects based on													
8.DATE OF S/W	Nov.1989													
9.CONSULTANT(S)	CTI Engineering Co., Ltd. Pasco International Inc.													
10.STUDY TEAM	No.of Members 17 Period Mar.1990-Mar.1992(24 months) <table style="margin-left: 20px; border: none;"> <tr> <td style="text-align: right;">Total M/M</td> <td style="text-align: right;">Japan</td> <td style="text-align: right;">Field</td> </tr> <tr> <td style="text-align: right;">93.63</td> <td style="text-align: right;">37.30</td> <td style="text-align: right;">56.33</td> </tr> </table>	Total M/M	Japan	Field	93.63	37.30	56.33	2.MAJOR REASONS FOR PRESENT STATUS						
Total M/M	Japan	Field												
93.63	37.30	56.33												
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Construction of Hydrological Stations; Bed Material and Suspended Load Survey; Water Quality Survey; Geological and Soil Mechanics Investigation; and Environmental	3.PRINCIPAL SOURCE OF INFORMATION												
12.EXPENDITURE	<table style="margin-left: 20px; border: none;"> <tr> <td style="text-align: right;">Total</td> <td style="text-align: right;">531,233 (¥'000)</td> </tr> <tr> <td style="text-align: right;">Contracted</td> <td style="text-align: right;">507,837</td> </tr> </table>	Total	531,233 (¥'000)	Contracted	507,837	5.TECHNICAL TRANSFER								
Total	531,233 (¥'000)													
Contracted	507,837													

和名 ブラワン-パダン統合河川流域開発計画

{M/P,M/P+(F/S),Basic Study,Other}

PROJECT SUMMARY (M/P+F/S)

Compiled Mar.1993
Revised

ASE IDN/S 220B/91

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Indonesia	1.SITE OR AREA	Integrated river basins between Belawan and Padang rivers of approx. 5,800km ²			1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Completed <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input checked="" type="checkbox"/> Promoting <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY	Belawan-Padang Integrated River Basin Development	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost		
3.SECTOR	Social Infrastructures/River & Erosion Control	(US\$1,000)	1) 136,791	71,383	65,408	(Description) A part of the proposed project, the Deli river improvement has been undertaken by the Local Government with financial assistance from ADB. The remaining components of Percut river improvement, Medan Floodway and the dam are to be included in the 1993 OECF loan application.	
4.REFERENCE NO.		Cost in Sept.1991	2) 28,721	11,540	17,181		
5.TYPE OF STUDY	(M/P)+F/S	3)					
6.COUNTERPART AGENCY	Directorate of Planning & Programming, Directorate General of Water Resources Development, Ministry of Public Works	3.CONTENTES OF MAJOR PROJECT(S)					
7.OBJECTIVES OF STUDY	1)To formulate a Master Plan of integrated river basin development of the integrated river basins from Belawan to Padang, focusing on flood control and water utilization; and 2)To conduct a Feasibility Study on urgent projects based on	Proposed Projects: 1) Deli-Perkut River Flood Control and Water Supply Project (1) Deli River Improvement 37.4km Design Discharge 460cu.m/s (2) Percut River Improvement 28.0km Design Discharge 300cu.m/s (3) Medan Floodway 3.8km Design Discharge 120cu.m/s (4) Lausimeme Dam Rockfill type (Height 74.5m; Cap.34 million cu.m) 2) Padang River Improvement Project River Improvement 29.5km Design Discharge 630cu.m/s					
8.DATE OF S/W	Nov.1989	Imp. Period:		.1995-.2000	.1995-.2002		
9.CONSULTANT(S)	CTI Engineering Co., Ltd. Pasco International Inc.	4.FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes	EIRR1) 17.90 EIRR2) 9.90 EIRR3) 11.86	FIRR1) FIRR2) FIRR3)		
10.STUDY TEAM	No.of Members 17 Period Mar.1990-Mar.1992 (24 months)	Conditions and Development Impacts:					
Total M/M	Japan	Assumptions: - The flood control project scale was set at a 30-year for the Deli-Perkut River System and a 10-year period for the Padang River. - The target year of water supply development is the year 2000, and the project will supply enough water during a dry year of a 10-year return period. Impacts: 1) Flood damage in Medan and its vicinities will be mitigated for floods of less than a 30-year return period. In the year 2000, the total municipal water demand of Medan City and a part of irrigation water can be met by the proposed project. 2) Flood control capacity of Padang River will be upgraded from a 2-year to a 10-year return period, and Tebing Tinggi City will also be relieved from flood damage. Of the EIRRs shown above, 1)is for Deli-Perkut River Flood Control, 2)for Deli-Perkut River Water Supply Project (14.35% for the two combined), and 3)for Padang River Improvement Project.					
93.63	37.30						
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER					
Construction of Hydrological Stations; Bed Material and Suspended Load Survey; Water Quality Survey; and Geological and Soil Mechanics Investigation.							
12.EXPENDITURE		3.PRINCIPAL SOURCE OF INFORMATION					
Total	531,233 (¥'000)	①					
Contracted	507,837						

和名 ブラワン-パダン統合河川流域開発計画

(F/S,(M/P)+F/S,D/D)