

表5.3.2 灌漑用水量 (通常土壌地1,000haあたり用水量) (1/2)

(Unit: m3/s)

| Month | 10 Days | Kharif | | | | | Rabi | | | | | Total | |
|-------|---------|-----------------|----------------|----------------|-----------------|--------------------|-----------------|-----------------|--------------------|-----------------|------------------|-------|------------------|
| | | Cotton 100ha | Pulses 50ha | Maize 200ha | Fodder 100ha | Sugarcane 100ha | Fruits 50 ha | Wheat 450 ha | Oil Seeds 100ha | Pulses 100ha | Fodder 100 ha | | Oilseeds 50ha |
| Jan. | 1 | | | | | 0.022 | 0.012 | 0.152 | 0.033 | 0.033 | 0.011 | | 0.264 |
| | 2 | | | | | 0.024 | 0.012 | 0.168 | 0.036 | 0.037 | 0.007 | | 0.283 |
| | 3 | | | | | 0.017 | 0.009 | 0.142 | 0.031 | 0.031 | 0.000 | | 0.231 |
| Feb. | 1 | | | | | 0.027 | 0.015 | 0.211 | 0.047 | 0.000 | 0.008 | 0.008 | 0.363 |
| | 2 | | | | | 0.017 | 0.011 | 0.169 | 0.038 | 0.000 | 0.006 | 0.006 | 0.287 |
| | 3 | | | | | 0.017 | 0.012 | 0.169 | 0.039 | 0.000 | 0.013 | 0.014 | 0.303 |
| Mar. | 1 | | | | | 0.028 | 0.020 | 0.242 | 0.056 | 0.000 | 0.018 | 0.019 | 0.444 |
| | 2 | | | | | 0.017 | 0.015 | 0.155 | 0.033 | 0.038 | 0.009 | 0.011 | 0.279 |
| | 3 | | | | | 0.018 | 0.015 | 0.098 | 0.020 | 0.025 | 0.016 | 0.018 | 0.211 |
| Apr. | 1 | | | | | 0.043 | 0.030 | 0.129 | 0.026 | 0.033 | 0.041 | 0.043 | 0.344 |
| | 2 | | | | | 0.045 | 0.031 | 0.055 | 0.008 | 0.015 | 0.000 | 0.048 | 0.251 |
| | 3 | | | | | 0.040 | 0.035 | 0.024 | 0.000 | 0.005 | 0.000 | 0.052 | 0.228 |
| May | 1 | 0.005 | | | | 0.087 | 0.045 | 0.000 | | | 0.064 | 0.057 | 0.259 |
| | 2 | 0.012 | | | | 0.094 | 0.044 | 0.000 | | | 0.045 | 0.038 | 0.233 |
| | 3 | 0.023 | | | 0.007 | 0.107 | 0.046 | 0.000 | | | 0.029 | 0.022 | 0.234 |
| Jun. | 1 | 0.039 | 0.006 | 0.023 | 0.030 | 0.125 | 0.051 | | | | | 0.008 | 0.293 |
| | 2 | 0.047 | 0.007 | 0.028 | 0.047 | 0.128 | 0.048 | | | | | | 0.304 |
| | 3 | 0.066 | 0.012 | 0.047 | 0.070 | 0.137 | 0.048 | | | | | | 0.380 |
| Jul. | 1 | 0.048 | 0.008 | 0.032 | 0.068 | 0.111 | 0.035 | | | | | | 0.302 |
| | 2 | 0.061 | 0.014 | 0.060 | 0.087 | 0.113 | 0.034 | | | | | | 0.369 |
| | 3 | 0.072 | 0.020 | 0.088 | 0.085 | 0.112 | 0.031 | | | | | | 0.408 |
| Aug. | 1 | 0.073 | 0.019 | 0.083 | 0.071 | 0.098 | 0.026 | | | | | | 0.370 |
| | 2 | 0.094 | 0.031 | 0.134 | 0.063 | 0.109 | 0.031 | | | | | | 0.463 |
| | 3 | 0.101 | 0.038 | 0.162 | 0.045 | 0.109 | 0.031 | | | | | | 0.486 |
| Sep. | 1 | 0.092 | 0.040 | 0.165 | 0.027 | 0.096 | 0.029 | 0.000 | 0.000 | 0.000 | 0.000 | 0.000 | 0.449 |
| | 2 | 0.099 | 0.046 | 0.188 | 0.018 | 0.102 | 0.032 | 0.012 | 0.012 | 0.019 | 0.019 | 0.019 | 0.529 |
| | 3 | 0.103 | 0.050 | 0.195 | 0.007 | 0.107 | 0.034 | 0.023 | 0.023 | 0.040 | 0.040 | 0.040 | 0.583 |
| Oct. | 1 | 0.078 | 0.038 | 0.125 | 0.000 | 0.083 | 0.027 | 0.070 | 0.029 | 0.049 | 0.049 | 0.049 | 0.527 |
| | 2 | 0.071 | 0.030 | 0.092 | 0.000 | 0.079 | 0.025 | 0.075 | 0.030 | 0.031 | 0.057 | 0.057 | 0.490 |
| | 3 | 0.065 | 0.022 | 0.063 | 0.000 | 0.074 | 0.025 | 0.086 | 0.033 | 0.034 | 0.066 | 0.066 | 0.468 |
| Nov. | 1 | 0.037 | 0.012 | 0.030 | | 0.050 | 0.018 | 0.120 | 0.019 | 0.021 | 0.045 | 0.045 | 0.353 |
| | 2 | 0.027 | 0.007 | 0.009 | | 0.047 | 0.017 | 0.143 | 0.021 | 0.023 | 0.045 | 0.045 | 0.339 |
| | 3 | 0.020 | 0.003 | | | 0.046 | 0.018 | 0.186 | 0.027 | 0.030 | 0.046 | 0.046 | 0.375 |
| Dec. | 1 | 0.005 | | | | 0.024 | 0.010 | 0.082 | 0.018 | 0.019 | 0.025 | 0.025 | 0.183 |
| | 2 | 0.000 | | | | 0.021 | 0.009 | 0.094 | 0.020 | 0.022 | 0.019 | 0.019 | 0.185 |
| | 3 | | | | | 0.016 | 0.007 | 0.093 | 0.020 | 0.021 | 0.010 | 0.010 | 0.167 |

Irrigation efficiency of 58% is applied.

表5.3.2 灌漑用水量 (砂質土壌地1,000haあたり用水量) (2/2)

(Unit : m³/s)

| Month | 10 Days | Kharif | | | | | Rabi | | | | | Total | |
|-------|---------|-----------------|----------------|----------------|-----------------|--------------------|-----------------|-----------------|--------------------|-----------------|------------------|-------|------------------|
| | | Cotton 100ha | Pulses 50ha | Maize 200ha | Fodder 100ha | Sugarcane 100ha | Fruits 50 ha | Wheat 450 ha | Oil Seeds 100ha | Pluses 100ha | Fodder 100 ha | | Oilseeds 50ha |
| Jan. | 1 | | | | | 0.043 | 0.023 | 0.295 | 0.063 | 0.064 | 0.022 | | 0.510 |
| | 2 | | | | | 0.046 | 0.024 | 0.324 | 0.070 | 0.071 | 0.013 | | 0.548 |
| | 3 | | | | | 0.033 | 0.018 | 0.275 | 0.060 | 0.061 | 0.000 | | 0.446 |
| Feb. | 1 | | | | | 0.052 | 0.029 | 0.408 | 0.090 | 0.091 | 0.000 | 0.016 | 0.702 |
| | 2 | | | | | 0.032 | 0.020 | 0.328 | 0.074 | 0.075 | 0.000 | 0.012 | 0.554 |
| | 3 | | | | | 0.033 | 0.023 | 0.326 | 0.075 | 0.078 | 0.000 | 0.026 | 0.586 |
| Mar. | 1 | | | | | 0.053 | 0.039 | 0.468 | 0.109 | 0.119 | 0.000 | 0.035 | 0.859 |
| | 2 | | | | | 0.033 | 0.029 | 0.300 | 0.064 | 0.074 | 0.000 | 0.021 | 0.539 |
| | 3 | | | | | 0.036 | 0.030 | 0.189 | 0.039 | 0.049 | 0.000 | 0.031 | 0.408 |
| Apr. | 1 | | | | | 0.083 | 0.059 | 0.249 | 0.050 | 0.064 | 0.000 | 0.078 | 0.665 |
| | 2 | | | | | 0.087 | 0.060 | 0.107 | 0.016 | 0.029 | 0.000 | 0.091 | 0.485 |
| | 3 | | | | | 0.116 | 0.067 | 0.047 | 0.001 | 0.009 | 0.000 | 0.102 | 0.441 |
| May | 1 | 0.010 | | | | 0.168 | 0.087 | 0.000 | | | | 0.124 | 0.500 |
| | 2 | 0.023 | | | | 0.181 | 0.086 | 0.000 | | | | 0.087 | 0.451 |
| | 3 | 0.044 | | | 0.013 | 0.208 | 0.090 | 0.000 | | | | 0.055 | 0.453 |
| Jun. | 1 | 0.075 | 0.011 | 0.044 | 0.058 | 0.242 | 0.098 | | | | | 0.024 | 0.566 |
| | 2 | 0.091 | 0.013 | 0.054 | 0.091 | 0.247 | 0.092 | | | | | | 0.588 |
| | 3 | 0.128 | 0.023 | 0.090 | 0.136 | 0.265 | 0.093 | | | | | | 0.735 |
| Jul. | 1 | 0.092 | 0.015 | 0.062 | 0.132 | 0.215 | 0.068 | | | | | | 0.584 |
| | 2 | 0.119 | 0.027 | 0.116 | 0.168 | 0.219 | 0.066 | | | | | | 0.714 |
| | 3 | 0.139 | 0.038 | 0.169 | 0.165 | 0.216 | 0.060 | | | | | | 0.788 |
| Aug. | 1 | 0.141 | 0.036 | 0.161 | 0.138 | 0.189 | 0.050 | | | | | | 0.715 |
| | 2 | 0.182 | 0.061 | 0.260 | 0.122 | 0.210 | 0.060 | | | | | | 0.896 |
| | 3 | 0.195 | 0.074 | 0.314 | 0.088 | 0.210 | 0.060 | | | | | | 0.940 |
| Sep. | 1 | 0.178 | 0.077 | 0.319 | 0.053 | 0.186 | 0.055 | 0.000 | 0.000 | 0.000 | 0.000 | | 0.869 |
| | 2 | 0.191 | 0.090 | 0.364 | 0.035 | 0.198 | 0.061 | 0.024 | 0.024 | 0.037 | 0.037 | | 1.023 |
| | 3 | 0.199 | 0.097 | 0.377 | 0.014 | 0.207 | 0.066 | 0.044 | 0.044 | 0.078 | 0.078 | | 1.127 |
| Oct. | 1 | 0.150 | 0.073 | 0.242 | 0.000 | 0.160 | 0.052 | 0.136 | 0.055 | 0.055 | 0.094 | | 1.018 |
| | 2 | 0.137 | 0.057 | 0.178 | 0.000 | 0.153 | 0.049 | 0.145 | 0.058 | 0.059 | 0.110 | | 0.947 |
| | 3 | 0.125 | 0.043 | 0.122 | 0.000 | 0.143 | 0.048 | 0.166 | 0.064 | 0.066 | 0.127 | | 0.904 |
| Nov. | 1 | 0.072 | 0.023 | 0.058 | 0.098 | 0.098 | 0.035 | 0.231 | 0.038 | 0.041 | 0.087 | | 0.682 |
| | 2 | 0.052 | 0.013 | 0.018 | 0.090 | 0.090 | 0.034 | 0.276 | 0.041 | 0.045 | 0.087 | | 0.656 |
| | 3 | 0.038 | 0.006 | | 0.088 | 0.088 | 0.035 | 0.359 | 0.053 | 0.057 | 0.089 | | 0.725 |
| Dec. | 1 | 0.009 | | | 0.046 | 0.046 | 0.019 | 0.159 | 0.035 | 0.037 | 0.048 | | 0.353 |
| | 2 | 0.000 | | | 0.041 | 0.041 | 0.018 | 0.182 | 0.039 | 0.042 | 0.036 | | 0.358 |
| | 3 | | | | 0.030 | 0.030 | 0.014 | 0.181 | 0.038 | 0.040 | 0.019 | | 0.323 |

Irrigation efficiency of 30% is applied.

表5.3.3 灌溉用水量總括表

| Month | 10 Days | Ordinary Land | Sandy Land | Total | |
|-------|---------|---------------|------------|-----------------------|---------|
| | | | | (m ³ /sec) | (MCM) |
| | 1 | 28,639 | 3,547 | 32,186 | 27.81 |
| Jan. | 2 | 30,771 | 3,811 | 34,582 | 29.88 |
| | 3 | 25,089 | 3,108 | 28,197 | 26.80 |
| | 1 | 39,468 | 4,888 | 44,356 | 38.32 |
| Feb. | 2 | 31,139 | 3,857 | 34,995 | 30.24 |
| | 3 | 32,939 | 4,080 | 37,018 | 25.59 |
| | 1 | 48,286 | 5,981 | 54,266 | 46.89 |
| Mar. | 2 | 30,262 | 3,748 | 34,010 | 29.38 |
| | 3 | 22,924 | 2,839 | 25,764 | 24.49 |
| | 1 | 37,376 | 4,629 | 42,006 | 36.29 |
| Apr. | 2 | 27,230 | 3,373 | 30,603 | 26.44 |
| | 3 | 24,805 | 3,072 | 27,877 | 24.09 |
| | 1 | 28,095 | 3,480 | 31,575 | 27.28 |
| May | 2 | 25,347 | 3,139 | 28,487 | 24.61 |
| | 3 | 25,429 | 3,150 | 28,578 | 27.16 |
| | 1 | 31,819 | 3,941 | 35,761 | 30.90 |
| Jun. | 2 | 33,023 | 4,090 | 37,114 | 32.07 |
| | 3 | 41,278 | 5,113 | 46,391 | 40.08 |
| | 1 | 32,795 | 4,062 | 36,857 | 31.84 |
| Jul. | 2 | 40,114 | 4,968 | 45,083 | 38.95 |
| | 3 | 44,299 | 5,487 | 49,786 | 47.32 |
| | 1 | 40,182 | 4,977 | 45,159 | 39.02 |
| Aug. | 2 | 50,327 | 6,233 | 56,561 | 48.87 |
| | 3 | 52,841 | 6,545 | 59,386 | 56.44 |
| | 1 | 48,809 | 6,045 | 54,855 | 47.39 |
| Sep. | 2 | 57,460 | 7,117 | 64,577 | 55.79 |
| | 3 | 63,328 | 7,844 | 71,171 | 61.49 |
| | 1 | 57,224 | 7,088 | 64,312 | 55.57 |
| Oct. | 2 | 53,205 | 6,590 | 59,795 | 51.66 |
| | 3 | 50,817 | 6,294 | 57,111 | 54.28 |
| | 1 | 38,300 | 4,744 | 43,044 | 37.19 |
| Nov. | 2 | 36,864 | 4,566 | 41,429 | 35.80 |
| | 3 | 40,729 | 5,045 | 45,774 | 39.55 |
| | 1 | 19,844 | 2,458 | 22,302 | 19.27 |
| Dec. | 2 | 20,139 | 2,494 | 22,633 | 19.55 |
| | 3 | 18,147 | 2,248 | 20,395 | 19.38 |
| | | | | | 1,307.7 |

表5.3.5 計画排水横断構造物の計画規模

| No of Cross Drainage | Name of Crossed River | Q1 (Discharge at upper measured point) | Q2 (Discharge at CRB Canal) | L1 (Dist. between points of Q1 and CRB) | L2 (Dist. between points of Q1 and Lift canal) | Catchment Area (km ²) | Pattern of Run-off for Plain area * | q (Discharge from Plain Area (cfs)) | Q ² (=Q ² -q) | a (=1/LxLx(Q ² /(Q1))) | Q (=Q1exp(-aL ²)) | Proposed Discharge (cfs) | Proposed Design Discharge (cms) |
|----------------------|-----------------------|--|-----------------------------|---|--|-----------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|-----------------------------------|-------------------------------|--------------------------|---------------------------------|
| 1 | Paniaia River | - | 12,500 | - | - | 64.5 | B | 1,685 | 10,815 | 0.000 | 10,815 | 10,800 | 306 |
| 2 | Hauz Khud | 52,000 | 23,000 | 23.2 | 11.0 | 109.3 | B | 2,856 | 25,144 | 0.031 | 36,975 | 37,000 | 1,048 |
| 3 | Takwara N. | 54,600 | 21,600 | 68.5 | 47.6 | 147.0 | B | 3,841 | 17,759 | 0.016 | 25,494 | 25,500 | 722 |
| 4 | Gomal diversion | 5,000 | 5,000 | - | - | 57.6 | B | 1,505 | 5,000 | 0.000 | 5,000 | 5,000 | 142 |
| 5 | Gomal N. | 21,000 | 18,500 | 23.0 | 10.7 | 97.3 | - | - | 18,500 | 0.006 | 19,691 | 19,700 | 558 |
| 6 | Lumi North (1) | 7,000 | 7,000 | - | - | 77.5 | - | - | 7,000 | 0.000 | 7,000 | 7,000 | 198 |
| 7 | Lumi North (2) | 2,500 | 2,500 | - | - | 29.8 | - | - | 2,500 | 0.000 | 2,500 | 2,500 | 71 |
| 8 | Lumi North (3) | 5,500 | 5,500 | - | - | 82.4 | - | - | 5,500 | 0.000 | 5,500 | 5,500 | 156 |
| 9 | Lumi South (1) | 32,200 | 32,200 | - | - | 117.2 | - | - | 32,200 | 0.000 | 32,200 | 32,200 | 912 |
| 10 | Lumi South (2) | 24,900 | 12,200 | 16.0 | 6.0 | 59.6 | - | - | 12,200 | 0.045 | 19,008 | 19,000 | 538 |
| 11 | Too N. | 17,800 | 17,800 | - | - | 21.9 | B | 572 | 17,228 | 0.000 | 17,228 | 17,200 | 487 |
| 12 | Daraban Zam | 35,800 | 35,800 | - | - | 49.7 | B | 1,299 | 34,501 | 0.000 | 34,501 | 34,500 | 977 |
| 13 | Chaudiwan Zam | 60,200 | 41,200 | 11.6 | 7.9 | 99.3 | B | 2,594 | 38,606 | 0.040 | 43,889 | 43,900 | 1,243 |
| 14 | Khad Waraki | 4,850 | 4,850 | - | - | 29.8 | A | 1,957 | 2,893 | 0.000 | 2,893 | 2,900 | 82 |
| 15 | Kaura Khad | 8,820 | 8,820 | - | - | 19.9 | A | 1,307 | 7,513 | 0.000 | 7,513 | 7,500 | 212 |
| 16 | Velheri N. | 8,520 | 5,960 | 34.0 | 23.6 | 64.6 | A | 1,200 | 4,760 | 0.017 | 5,704 | 5,700 | 161 |
| 17 | Gajistan N. | 13,220 | 15,000 | - | - | 69.5 | A | 4,565 | 10,435 | 0.000 | 10,435 | 10,400 | 295 |
| 18 | Sherana N. | 14,460 | 14,460 | - | - | 34.8 | A | 2,286 | 14,460 | 0.000 | 14,460 | 14,500 | 411 |
| 19 | Ramak diversion | 8,000 | 2,540 | 19.2 | 14.6 | 24.8 | A | 1,629 | 911 | 0.113 | 1,540 | 1,500 | 42 |
| 20 | Ramak N. | 24,000 | 19,000 | 20.4 | 13.8 | 59.5 | A | 3,908 | 15,092 | 0.023 | 17,473 | 17,500 | 496 |

* : Specific discharge of plain area of pattern A, B are applied at 1.86 m³/s/km² and 0.74 m³/s/km², respectively.

表5.6.1 チャシュマ右岸開発公社の組織構成

(事業実施ステージ)

| C.R.B.D.A. MAIN OFFICE | |
|---|-----------------|
| Item | Number of Staff |
| I. Board Members | 4 |
| Chairman (Grade 21/22) | 1 |
| Members (Grade 20/21) | |
| 1. Irrigation | 1 |
| 2. Agriculture | 1 |
| 3. Socio-Economic Development | 1 |
| Advisor | (2) |
| II. Technical Staff (Grade 17-19) | 71 |
| 1. Irrigation | |
| 1-1 Superintending engineer | 1 |
| 1-2 Superintending engineer | 1 |
| 1-3 Senior engineer | 6 |
| 2. Agriculture | |
| 2-1 Director, extension | 1 |
| 2-2 Director, adaptive research and seed develop | 1 |
| 2-3 Director, marketing and credit | 1 |
| 2-4 AD, land develop. and water manage. | 1 |
| 2-5 AD, Extension | 1 |
| 2-6 AD, Seed | 1 |
| 2-7 AD, adaptive research | 1 |
| 2-8 AD, marketing | 1 |
| 2-9 AD, agricultural credit | 1 |
| 2-10 Extension advisor | 25 |
| 2-11 Seed expert | 6 |
| 2-12 Agronomist | 3 |
| 2-13 Insecticide expert | 1 |
| 2-14 Fertilizer expert | 1 |
| 2-15 Soil expert | 1 |
| 3. Socio-Economic Development | |
| 3-1 Director, Infrastructure | 1 |
| 3-2 Land acquisition collector | 1 |
| 3-3 Senior engineer | 2 |
| 3-4 Junior engineer | 4 |
| 4. Finance | |
| 4-1 G.M. finance | 1 |
| 4-2 Director finance | 1 |
| 4-3 Director, audit | 1 |
| 4-4 Accounts officer | 2 |
| 4-5 Auditor | 4 |
| III. Supporting Staff (Grade 1-16) (Secretary, assistant, typist, drivers, etc.) | 165 |
| Total | 240 |

(維持・管理ステージ)

| C.R.B.D.A. MAIN OFFICE | |
|---|-----------------|
| Item | Number of Staff |
| I. Board Members | 4 |
| Chairman (Grade 21/22) | 1 |
| Members (Grade 20/21) | |
| 1. Irrigation | 1 |
| 2. Agriculture | 1 |
| 3. Socio-Economic Development | 1 |
| Advisor | (2) |
| II. Technical Staff (Grade 17-19) | 67 |
| 1. Irrigation | |
| 1-1 Superintending engineer | 1 |
| 1-2 Senior engineer | 3 |
| 2. Agriculture | |
| 2-1 Director, extension | 1 |
| 2-2 Director, adaptive research and seed develop | 1 |
| 2-3 Director, marketing and credit | 1 |
| 2-4 AD, land develop. and water manage. | 1 |
| 2-5 AD, Extension | 1 |
| 2-6 AD, Seed | 1 |
| 2-7 AD, adaptive research | 1 |
| 2-8 AD, marketing | 1 |
| 2-9 AD, agricultural credit | 1 |
| 2-10 Extension advisor | 25 |
| 2-11 Seed expert | 6 |
| 2-12 Agronomist | 3 |
| 2-13 Insecticide expert | 1 |
| 2-14 Fertilizer expert | 1 |
| 2-15 Soil expert | 1 |
| 3. Socio-Economic Development | |
| 3-1 Director, Infrastructure | 1 |
| 3-2 Land acquisition collector | 1 |
| 3-3 Senior engineer | 2 |
| 3-4 Junior engineer | 4 |
| 4. Finance | |
| 4-1 G.M. finance | 1 |
| 4-1 Director finance | 1 |
| 4-2 Director, audit | 1 |
| 4-3 Accounts officer | 2 |
| 4-4 Auditor | 4 |
| III. Supporting Staff (Grade 1-16) (Secretary, assistant, typist, drivers, etc.) | 139 |
| Total | 210 |

→
After completion
of construction
work, the organi-
zation will be
sifted.

INTAKE OPERATION OFFICE

| Item | Number of Staff |
|------------------------------|-----------------|
| Officer in charge (Grade 18) | (1/3) |
| Gauge reader | 3 |
| Total | 3 |

PUMP OPERATION OFFICE

| Item | Number of Staff |
|-------------------------------|-----------------|
| Officer in charge (Grade 18) | (1) |
| Technical Staff (Grade 17) | |
| Mechanical engineer | 3 |
| Electrical engineer | 2 |
| Supporting Staff (Grade 1-16) | |
| Technical assistant | 6 |
| Others | 15 |
| Total | 26 |

FEEDER CANAL O&M OFFICE (F-1-2)

| Item | Number of Staff |
|-------------------------------|-----------------|
| Officer in charge (Grade 18) | (1/3) |
| Supporting Staff (Grade 1-16) | |
| Technical assistant | 2 |
| Driver | 2 |
| Others | 4 |
| Total | 8 |

MAIN CANAL O&M OFFICE (M-1-6)

| Item | Number of Staff |
|-------------------------------|-----------------|
| Officer in charge (Grade 18) | (1/6) |
| Technical staff (Grade 17) | 1/2 |
| Supporting Staff (Grade 1-16) | |
| Technical assistant | 2 |
| Driver | 3/2 |
| Others | 6 |
| Total | 10 |

DISTRIBUTARY O&M OFFICE (D-1-25)

| Item | Number of Staff |
|-------------------------------|-----------------|
| Extension advisor | (1) |
| Supporting Staff (Grade 1-16) | |
| Technical assistant | 2 |
| Driver | 1 |
| Others | 2 |
| Total | 5 |

表6.1.2 幹線水路水理設計諸元

| Section No. | Design Discharge (m ³ /s) | Roughness Coefficient | Slope (1 :) | Area (m ²) | Wetted Perimeter (m) | Water Depth (m) | Base Width (m) | Velocity (m/s) | Freeboard (m) |
|-------------|--------------------------------------|-----------------------|--------------|------------------------|----------------------|-----------------|----------------|----------------|---------------|
| 1 | 72 | 0.016 | 14,000 | 70.57 | 26.21 | 3.94 | 12.00 | 1.02 | 1.21 |
| 2 | 53 | 0.016 | 14,000 | 55.76 | 23.23 | 3.53 | 10.50 | 0.95 | 1.22 |
| 3 | 30 | 0.016 | 9,000 | 30.94 | 17.37 | 2.60 | 8.00 | 0.97 | 1.20 |
| 4 | 20 | 0.016 | 7,000 | 20.78 | 14.22 | 2.14 | 6.50 | 0.96 | 1.06 |
| 5 | 10 | 0.016 | 4,000 | 10.04 | 9.87 | 1.49 | 4.50 | 1.00 | 0.91 |

Note : Canal Side Slope 1 : 1.5

表6.1.3 分岐幹線掛かり灌漑面積及び取水量

| Disty No. | Name of Disty | G.C.A. (ha) | C.C.A. | | Total (ha) | Discharge (m ³ /s) |
|-----------|----------------|-------------|-----------------|-------------|------------|-------------------------------|
| | | | Good & Mod (ha) | Margi. (ha) | | |
| D-1 | SAKHI MARDAN | 1,930 | 0 | 1,700 | 1,700 | 1.72 |
| D-2 | UMAR KHAN | 2,770 | 400 | 2,030 | 2,430 | 2.27 |
| D-3 | YARIK (1) | 2,740 | 1,350 | 1,040 | 2,390 | 1.76 |
| D-4 | YARIK (2) | 1,480 | 1,260 | 0 | 1,260 | 0.66 |
| D-5 | RODI KHEL | 10,470 | 9,280 | 0 | 9,280 | 4.87 |
| D-6 | REHMAN DHERI | 11,470 | 10,150 | 0 | 10,150 | 5.33 |
| D-7 | BUDH | 2,720 | 2,410 | 0 | 2,410 | 1.26 |
| D-8 | KOT ISA KHAN | 8,090 | 7,060 | 0 | 7,060 | 3.70 |
| D-9 | POTAH | 13,430 | 11,400 | 0 | 11,400 | 5.98 |
| D-10 | SHAHID | 3,130 | 2,380 | 0 | 2,380 | 1.25 |
| D-11 | SIKANDAR | 3,120 | 2,660 | 0 | 2,660 | 1.40 |
| D-12 | MADDI | 15,510 | 13,620 | 0 | 13,620 | 7.15 |
| D-13 | KOT ZAFAR | 7,500 | 6,240 | 0 | 6,240 | 3.27 |
| D-14 | SWAN | 4,470 | 3,630 | 0 | 3,630 | 1.90 |
| D-15 | GANDI ASHIQ | 2,300 | 1,860 | 0 | 1,860 | 0.98 |
| D-16 | MOCHI WAL | 6,900 | 5,910 | 0 | 5,910 | 3.10 |
| D-17 | GARAH ISA KHAN | 11,000 | 9,150 | 0 | 9,150 | 4.80 |
| D-18 | ALI GARAH | 3,010 | 2,560 | 0 | 2,560 | 1.34 |
| D-19 | BABRAN | 3,060 | 2,560 | 0 | 2,560 | 1.34 |
| D-20 | GAJISTAN | 2,800 | 2,440 | 0 | 2,440 | 1.28 |
| D-21 | KAURI HOT | 4,110 | 3,650 | 0 | 3,650 | 1.92 |
| D-22 | SHAH GHARBI | 3,760 | 2,750 | 500 | 3,250 | 1.95 |
| D-23 | SHERANNA | 1,440 | 1,180 | 0 | 1,180 | 0.62 |
| D-24 | CHIRRI BHUHAR | 3,370 | 2,700 | 250 | 2,950 | 1.67 |
| D-25 | JHANGI | 4,020 | 2,040 | 1,440 | 3,480 | 2.53 |

(Note) C.C.A.(1) : Good & Moderate irrigable land (Ordinary Land)

C.C.A.(2) : Marginal irrigable land (Sandy Land)

表6.1.5 調整池の容量及び規模

| Distributary | Capacity | | | Size (m)*(m) |
|--------------|--------------|-------------------|---------------|-----------------|
| | Dead (m3) | Effective (m3) | Total (m3) | |
| D- 1 | 23,600 | 148,600 | 172,200 | 230*230 |
| D- 2 | 33,100 | 206,800 | 239,900 | 270*270 |
| D- 3 | 25,800 | 162,200 | 188,000 | 240*240 |
| D- 4 | 9,400 | 61,000 | 70,400 | 150*150 |
| D- 5 | 71,200 | 439,000 | 510,200 | 390*390 |
| D- 6 | 75,000 | 462,200 | 537,200 | 400*400 |
| D- 7 | 17,500 | 111,200 | 128,700 | 200*200 |
| D- 8 | 53,500 | 331,700 | 385,200 | 340*340 |
| D- 9 | 87,000 | 535,600 | 622,600 | 430*430 |
| D-10 | 17,500 | 111,200 | 128,700 | 200*200 |
| D-11 | 19,500 | 123,100 | 142,600 | 210*210 |
| D-12 | 104,500 | 641,800 | 746,300 | 470*470 |
| D-13 | 47,200 | 293,000 | 340,200 | 320*320 |
| D-14 | 28,100 | 176,500 | 204,600 | 250*250 |
| D-15 | 14,000 | 89,300 | 103,300 | 180*180 |
| D-16 | 44,200 | 274,600 | 318,800 | 310*310 |
| D-17 | 67,400 | 416,300 | 483,700 | 380*380 |
| D-18 | 19,500 | 123,100 | 142,600 | 210*210 |
| D-19 | 19,500 | 123,100 | 142,600 | 210*210 |
| D-20 | 17,500 | 111,200 | 128,700 | 200*200 |
| D-21 | 28,100 | 176,500 | 204,600 | 250*250 |
| D-22 | 28,100 | 176,500 | 204,600 | 250*250 |
| D-23 | 9,400 | 61,000 | 70,400 | 150*150 |
| D-24 | 23,600 | 148,600 | 172,200 | 230*230 |
| D-25 | 35,700 | 222,800 | 258,500 | 280*280 |

(*)Size : Length of Top Bank
Side Slope : 1:1.5

表 7.1.1 フェーズ別事業費

| Project Cost Component | Project Total | | | Phase I | | | Phase II | | |
|---|---------------------|--------------------|---------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|
| | Foreign Currency | Local Currency | Total Cost | Foreign Currency | Local Currency | Total Cost | Foreign Currency | Local Currency | Total Cost |
| | (1,000 Rs.) | (1,000 Rs.) | (1,000 Rs.) | | | | | | |
| I. Direct Construction Cost | | | | | | | | | |
| a) Land Acquisition, Compensation & Preliminary (3200ha) (t:Camp. 1,000ha and 72 houses II: 2,200ha and 58 houses) | 35,604.8 | 226,407.2 | 262,012.0 | 35,604.8 | 119,407.2 | 155,012.0 | 0.0 | 107,000.0 | 107,000.0 |
| b) Feeder Canal (58.6km) | 1,479,685.8 | 808,072.7 | 2,287,758.4 | 1,479,685.8 | 808,072.7 | 2,287,758.4 | 0.0 | 0.0 | 0.0 |
| c) Pump Station (1 station) (t: Major part of Pump equipment and Delivery Pipe) | 1,193,602.8 | 395,015.2 | 1,588,618.0 | 679,383.4 | 282,032.4 | 961,415.8 | 514,219.3 | 112,982.8 | 627,202.1 |
| d) Main Canal (113.3km) (t: Sta.0-Sta.32+800 II: Further to the End) | 1,084,801.2 | 1,044,497.6 | 2,129,298.8 | 471,888.5 | 454,356.4 | 926,245.0 | 612,912.7 | 590,141.1 | 1,203,053.8 |
| e) Distributory Canals (442.6km) (t: D-1 to D-6 II: D-7 to D-25) | 413,238.5 | 402,778.4 | 816,016.8 | 97,111.0 | 94,652.9 | 191,764.0 | 316,127.4 | 308,125.4 | 624,252.9 |
| f) Regulation Pond (25 nos) (Same as above) | 330,307.0 | 265,176.4 | 595,483.5 | 77,622.2 | 62,316.5 | 139,938.6 | 252,684.9 | 202,860.0 | 455,544.9 |
| h) Drainage Canals (579.5km) (Same as above) | 1,247,968.5 | 273,147.7 | 1,521,116.2 | 293,272.6 | 64,189.7 | 357,462.3 | 954,695.9 | 208,958.0 | 1,163,653.9 |
| i) Commercial Roads (32.5km) (Same as above) | 11,014.5 | 7,045.6 | 18,060.1 | 2,588.4 | 1,655.7 | 4,244.1 | 8,426.1 | 5,389.9 | 13,816.0 |
| j) On-farm Development Cost (32.5km) (Same as above) | 346,915.6 | 292,202.0 | 639,117.6 | 81,525.2 | 68,667.5 | 150,192.6 | 265,390.4 | 223,534.5 | 488,925.0 |
| k) Sump Well & Domestic Water Supply (L.S.) (Same as above) | 10,915.6 | 9,244.5 | 20,160.2 | 2,565.2 | 2,172.5 | 4,737.6 | 8,350.5 | 7,072.1 | 15,422.5 |
| l) Other and Miscellaneous Works (L.S.) (Same as above) | 97,104.0 | 145,656.0 | 242,760.0 | 38,841.6 | 58,262.4 | 97,104.0 | 58,262.4 | 87,393.6 | 145,656.0 |
| Sub-total of Direct Construction Cost | 6,251,153.3 | 3,869,243.3 | 10,120,401.6 | 3,260,088.7 | 2,015,785.8 | 5,275,874.5 | 2,991,069.6 | 1,853,457.5 | 4,844,527.1 |
| II. Indirect Construction Cost | | | | | | | | | |
| a) Consultancy Service Cost(10% to D.Cost) | 625,115.8 | 386,924.3 | 1,012,040.2 | 326,008.9 | 201,578.6 | 527,587.5 | 299,107.0 | 185,345.7 | 484,452.7 |
| b) Implementation Cost(6% of D. Cost) | 375,069.5 | 232,154.6 | 607,224.1 | 195,605.3 | 120,947.2 | 316,552.5 | 179,464.2 | 111,207.4 | 290,671.6 |
| Sub-total | 1,000,185.3 | 619,078.9 | 1,619,264.3 | 521,614.2 | 322,525.7 | 844,139.9 | 478,571.1 | 296,553.2 | 775,124.3 |
| III. Physical Contingency (10%) | 625,115.8 | 386,924.3 | 1,012,040.2 | 326,008.9 | 201,578.6 | 527,587.5 | 299,107.0 | 185,345.7 | 484,452.7 |
| Total Base Construction Cost | 7,876,459.4 | 4,875,246.6 | 12,751,706.0 | 4,107,711.7 | 2,539,890.2 | 6,647,601.9 | 3,768,747.7 | 2,335,356.4 | 6,104,104.1 |
| IV. Price Contingency*1 | 2,281,201.8 | 1,779,755.1 | 4,060,956.9 | 1,148,159.6 | 905,819.8 | 2,053,979.4 | 1,133,042.2 | 873,935.3 | 2,006,977.5 |
| V. Interest and Service Charge | 218,907.1 | 134,183.2 | 353,090.3 | 87,652.2 | 52,704.1 | 140,356.3 | 131,254.9 | 81,479.2 | 212,734.1 |
| GRAND TOTAL COST | 10,376,568.4 | 6,789,184.9 | 17,165,753.3 | 5,343,523.5 | 3,498,414.1 | 8,841,937.6 | 5,033,044.8 | 3,290,770.9 | 8,323,815.7 |

Note: *1: with annual escalation of 4.5% for F.C. and 5.5 % for L.C.

表7.1.2 年度別事業費

Unit: 1,000 Rs.

| | | Annual Disbursement Schedule | | | | | | | | | | | | | | | |
|----------------------------------|---------------------|--|--------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|
| | | 1st(1996) | | 2nd(1997) | | 3rd(1998) | | 4th(1999) | | 5th(2000) | | 6th(2001) | | 7th(2002) | | | |
| Project Cost Component | Total Cost | FC | LC | FC | LC | FC | LC | FC | LC | FC | LC | FC | LC | FC | LC | FC | LC |
| I. Direct Cost | | | | | | | | | | | | | | | | | |
| a) Land Acquisition | 262,012.0 | 35605 | 20582 | 0 | 41165 | 0 | 41165 | 0 | 41165 | 0 | 41165 | 0 | 41165 | 0 | 41165 | 0 | 0 |
| b) Feeder Canal | 2,287,758.4 | 0 | 0 | 246614 | 134679 | 493229 | 269358 | 493229 | 269358 | 246614 | 134679 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Pump Station | 1,588,618.0 | 0 | 0 | 67938 | 28203 | 135877 | 56406 | 271753 | 112813 | 306659 | 107206 | 411375 | 90386 | 188755 | 181743 | 393060 | 378456 |
| d) Main Canal | 2,129,298.8 | 1,084,801.2 | 1,044,497.6 | 0 | 0 | 0 | 0 | 38844 | 37861 | 144220 | 140570 | 124798 | 121639 | 298682 | 287585 | 204304 | 196714 |
| e) Distributory Canals | 816,016.8 | 413,238.5 | 402,778.4 | 0 | 0 | 0 | 0 | 31049 | 24927 | 115277 | 92547 | 99753 | 80083 | 386454 | 84585 | 479636 | 104980 |
| f) Regulation Pond | 595,483.5 | 330,307.0 | 265,176.4 | 0 | 0 | 0 | 0 | 647 | 414 | 2979 | 1906 | 4018 | 2570 | 20381 | 17167 | 93841 | 79041 |
| g) Drainage Canals | 1,521,116.2 | 1,247,968.5 | 273,147.7 | 0 | 0 | 0 | 0 | 1026 | 869 | 3810 | 3226 | 3297 | 2792 | 1026 | 869 | 3810 | 3226 |
| i) Farm Roads | 18,060.1 | 11,014.5 | 7,045.6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) On-farm Development | 639,117.6 | 346,915.6 | 292,202.0 | 0 | 0 | 0 | 0 | 20381 | 17167 | 93841 | 79041 | 126537 | 106581 | 20381 | 17167 | 93841 | 79041 |
| k) Sump Well | 20,160.2 | 10,915.6 | 9,244.5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Miscellaneous | 242,760.0 | 97,104.0 | 145,656.0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Sub-total | 10,120,401.6 | 6,251,158.3 | 3,869,243.3 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 | 10,120,401.6 |
| II. Indirect Cost | | | | | | | | | | | | | | | | | |
| a) Consultancy Service | 1,012,040.2 | 625,115.8 | 386,924.3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Implementation | 607,224.1 | 375,069.5 | 232,154.6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Sub-total | 1,619,264.3 | 1,000,185.3 | 619,078.9 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 | 1,619,264.3 |
| III. Physical Contingency | | | | | | | | | | | | | | | | | |
| Base Cost | 12,751,706.0 | 7,876,459.4 | 4,875,246.6 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 | 12,751,706.0 |
| IV. Price Contingency | 4,069,956.9 | 2,431,201.8 | 1,779,755.1 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 | 4,069,956.9 |
| V. Service Charge | 353,090.3 | 218,907.1 | 134,183.2 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 | 353,090.3 |
| TOTAL COST | 17,165,753.3 | 10,376,568.4 | 6,789,184.9 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 | 17,165,753.3 |
| VI. Annual O&M | 229,721.6 | 0.0 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 | 229,721.6 |
| TOTAL | 17,395,474.9 | 10,376,568.4 | 7,018,906.5 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 | 17,395,474.9 |
| | | FC : Foreign Currency, LC : Local Currency | | 115,600.0 | | 0 | | 6,800 | | 38,100 | | 80,300 | | 115,600 | | 115,600 | |
| | | Development Area (ha) | | 115,600.0 | | 0 | | 0 | | 18,140 | | 27,210 | | 80,210 | | 80,210 | |
| | | Area Under Irrigation (ha) | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | | 0 | |

表 8.1.1 作物生產純增便益 (經濟價格)

| Items | CCA 115,600 ha | Without Project | | | With Project | | | Incremental | |
|----------------------------|-------------------|--------------------------|---|--------------------|--------------------------|---|--------------------|--------------------------|------------------------------|
| | | Cropping Area (ha) | Net Production Value Per ha (Rs./ha) | Total (Rs.'000) | Cropping Area (ha) | Net Production Value Per ha (Rs./ha) | Total (Rs.'000) | Cropping Area (ha) | N.P. Value (Rs.'000) * |
| Kharif Season Crops | | | | | | | | | |
| Sorghum | | 2,440 | 2,260 | 5,520 | | | | -2,440 | -5,520 |
| Millet | | 2,390 | 3,080 | 7,365 | | | | -2,390 | -7,365 |
| Maize | | 20 | 660 | 13 | 23,100 | 9,991 | 230,792 | 23,080 | 230,779 |
| Pluses | | 10 | 2,460 | 25 | 5,800 | 13,040 | 75,632 | 5,790 | 75,607 |
| Cotton | | 60 | 15,030 | 902 | 11,500 | 20,181 | 232,082 | 11,440 | 231,180 |
| Fodder | | 10 | 640 | 6 | 11,500 | 5,662 | 65,113 | 11,490 | 65,107 |
| Guara | | 210 | 4,270 | 896 | | | | -210 | -896 |
| Vegetables (Eggplant) | | 30 | 3,240 | 97 | 3,000 | 21,050 | 63,150 | 2,970 | 63,053 |
| Sub-total | | 5,170 | | 14,824 | 54,900 | | 666,769 | 49,730 | 651,944 |
| Rabi Season Crops | | | | | | | | | |
| Wheat | | 8,500 | 5,380 | 45,694 | 52,000 | 19,967 | 1,038,284 | 43,500 | 992,590 |
| Pulses (Gram) | | 4,280 | 4,300 | 18,422 | 11,500 | 13,638 | 156,837 | 7,220 | 138,415 |
| Oilseeds (Rape/Mustard) | | 2,400 | 2,970 | 7,121 | 11,500 | 13,009 | 149,604 | 9,100 | 142,482 |
| Sugarcane | | 30 | 8,720 | 262 | 11,500 | 16,237 | 186,726 | 11,470 | 186,464 |
| Fodder (Berseem) | | 60 | 960 | 58 | 11,500 | 8,428 | 96,922 | 11,440 | 96,864 |
| Fruit (Mango) | | 15 | 3,670 | 55 | 3,000 | 15,947 | 47,841 | -2,985 | 47,786 |
| Vegetables | | 15 | 6,910 | 104 | 3,000 | 38,075 | 114,225 | 2,985 | 114,121 |
| Sub-total | | 15,300 | | 71,715 | 104,000 | | 1,790,438 | 88,700 | 1,718,723 |
| Spring Season Crops | | | | | | | | | |
| Maize | | | | | 5,800 | 11,181 | 64,850 | 5,800 | 64,850 |
| Oilseeds | | | | | 5,800 | 12,166 | 70,563 | 5,800 | 70,563 |
| Sub-total | | | | | 11,600 | | 135,413 | 11,600 | 135,413 |
| Kharif Season Crops | | 5,170 | | 14,824 | 54,900 | | 666,769 | 49,730 | 651,944 |
| Rabi Season Crops | | 15,300 | | 71,715 | 104,000 | | 1,790,438 | 88,700 | 1,718,723 |
| Spring Season Crops | | | | | 11,600 | | 135,413 | 11,600 | 135,413 |
| Total | | 20,470 | | 86,540 | 170,500 | | 2,592,619 | 150,030 | 2,506,080 |
| | | | | | | | | (Rs./ha) | 21,679 |

Note : *) N.P. : Net Production

表 8.1.2 經濟事業費、年間維持管理費、更新費之年別發生費用

| Project Cost Component | Financial Cost (Rs.'000) | Construction Conversion Factor | Economic Cost (Rs.'000) | Annual Economic Cost Disbursement (Rs.'000) | | | | | | | | Total | | |
|---------------------------------------|--------------------------|--------------------------------|-------------------------|---|-----------|-------------|-------------|-------------|-------------|-------------|--------------|-----------|--------------|--|
| | | | | 1st | 2nd | 3rd | 4th | 5th | 6th | 7th | 8th | | | |
| I. Direct Cost | | | | | | | | | | | | | | |
| a) Land Acquisition | 262,012.0 | 53.6 | 140,438.4 | 30,116.4 | 22,064.4 | 22,064.4 | 22,064.4 | 22,064.4 | 22,064.4 | 22,064.4 | 22,064.4 | 0.0 | 140,438.4 | |
| b) Feeder Canal | 2,287,758.4 | 92.8 | 2,123,039.8 | 0.0 | 353,840.0 | 707,679.9 | 707,679.9 | 353,840.0 | 0.0 | 0.0 | 0.0 | 0.0 | 2,123,039.8 | |
| c) Pump Station | 1,588,618.0 | 95.7 | 1,520,307.4 | 0.0 | 92,007.5 | 184,015.0 | 368,030.0 | 396,069.0 | 480,185.9 | 0.0 | 0.0 | 0.0 | 1,520,307.4 | |
| d) Main Canal | 2,129,298.8 | 90.5 | 1,927,015.4 | 0.0 | 0.0 | 0.0 | 335,300.7 | 698,221.9 | 530,571.6 | 222,779.1 | 188,108.3 | 362,921.2 | 1,927,015.4 | |
| e) Distributory Canals | 816,016.8 | 90.4 | 737,679.2 | 0.0 | 0.0 | 0.0 | 69,341.8 | 257,450.0 | 165,089.5 | 139,396.7 | 546,653.9 | 0.0 | 737,679.2 | |
| f) Regulation Pond | 595,483.5 | 91.8 | 546,653.9 | 0.0 | 0.0 | 0.0 | 51,385.5 | 190,782.2 | 454,081.6 | 6,093.4 | 5,111.8 | 0.0 | 546,653.9 | |
| h) Drainage Canals | 1,521,116.2 | 96.4 | 1,466,356.0 | 0.0 | 0.0 | 0.0 | 0.0 | 454,081.6 | 0.0 | 0.0 | 0.0 | 0.0 | 1,466,356.0 | |
| i) Farm Roads | 18,060.1 | 92.5 | 16,705.6 | 0.0 | 0.0 | 0.0 | 981.5 | 4,518.9 | 6,093.4 | 5,111.8 | 0.0 | 0.0 | 16,705.6 | |
| j) On-farm | 639,117.6 | 90.9 | 580,957.9 | 0.0 | 0.0 | 0.0 | 34,131.3 | 157,149.1 | 211,904.4 | 177,773.1 | 580,957.9 | 0.0 | 580,957.9 | |
| k) Sump Well | 20,160.2 | 90.7 | 18,285.3 | 0.0 | 0.0 | 0.0 | 1,718.8 | 6,381.6 | 5,522.2 | 4,662.7 | 18,285.3 | 0.0 | 18,285.3 | |
| l) Miscellaneous | 242,760.0 | 88.5 | 214,842.6 | 30,691.8 | 30,691.8 | 30,691.8 | 30,691.8 | 30,691.8 | 30,691.8 | 30,691.8 | 30,691.8 | 30,691.8 | 214,842.6 | |
| | 10,120,401.6 | | 9,292,281.5 | 60,808.2 | 498,603.7 | 944,451.1 | 1,621,325.7 | 2,571,250.5 | 2,238,471.8 | 1,357,370.5 | 2,296,281.5 | 0.0 | 9,292,281.5 | |
| II. Indirect Cost | | | | | | | | | | | | | | |
| a) Consultancy Service | 1,012,040.2 | 92.6 | 937,149.2 | 197,294.6 | 123,309.1 | 147,970.9 | 246,618.2 | 98,647.3 | 75,985.5 | 49,323.6 | 937,149.2 | 0.0 | 937,149.2 | |
| b) Implementation | 607,224.1 | 92.5 | 561,682.3 | 245,551.0 | 52,688.5 | 52,688.5 | 52,688.5 | 52,688.5 | 52,688.5 | 52,688.8 | 561,682.3 | 0.0 | 561,682.3 | |
| Sub-total | 1,619,264.3 | | 1,498,831.5 | 442,845.6 | 175,997.6 | 200,659.4 | 299,306.7 | 151,335.8 | 128,674.0 | 102,012.4 | 1,498,831.5 | 0.0 | 1,498,831.5 | |
| III. Physical Contingency | 1,012,040.2 | 92.5 | 936,137.2 | 8,405.2 | 51,178.4 | 95,341.1 | 163,418.0 | 258,165.1 | 223,901.5 | 135,727.9 | 936,137.2 | 0.0 | 936,137.2 | |
| Base Cost | 12,751,706.0 | | 11,727,250.2 | 512,059.0 | 725,779.7 | 1,240,451.6 | 2,084,050.4 | 2,980,751.4 | 2,589,047.3 | 1,595,110.8 | 11,727,250.2 | 0.0 | 11,727,250.2 | |
| IV. O & M Cost (Full Year) | 317,080.0 | 84.1 | 266,664.3 | 0.0 | 0.0 | 0.0 | 0.0 | 27,929.6 | 41,806.1 | 123,460.5 | 266,664.3 | 0.0 | 266,664.3 | |
| V. Replacement Cost | | | | | | | | | | | | | | |
| a) Pump/Equipment | 1,080,000.0 | 96.5 | 1,042,200.0 | 0.0 | 312,660.0 | 312,660.0 | 416,880.0 | 0.0 | 0.0 | 0.0 | 1,042,200.0 | 0.0 | 1,042,200.0 | |
| b) Pump/Equipment | 105,500.0 | 86.6 | 91,365.0 | 12,297.2 | 12,297.2 | 36,978.2 | 14,895.2 | 14,895.2 | 0.0 | 0.0 | 91,365.0 | 0.0 | 91,365.0 | |
| c) Others | 4,655.0 | 96.1 | 4,473.5 | 602.1 | 602.1 | 1,810.6 | 729.3 | 729.4 | 0.0 | 0.0 | 4,473.5 | 0.0 | 4,473.5 | |

表 8.1.3 経済費用、便益フローと経済内部収益

(Unit: Rs.000)

| No. of Year | Cost | | | | Production Developed (ha) | Built-up Ratio | Crop Production Benefit (INCPV-) | | | | Total | Benefit | | | | | Total |
|-------------|--------------|---------|-------------|-----------|---------------------------|----------------|----------------------------------|---------|-----------|---------|-----------|------------------|----------------------|-----------------------|-------------------------------|-------------|-----------|
| | Construction | O&M | Replacement | Total | | | Area(A) | Area(B) | Area(C) | Area(D) | | Road Development | Water Right Transfer | Domestic Water Supply | Reduction/ Seasonal Migration | Environment | |
| | | | | | | | | | | | | | | | | | |
| 1 | 512,059 | 0 | 0 | 512,059 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 2 | 725,780 | 0 | 0 | 725,780 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 3 | 1,240,452 | 0 | 0 | 1,240,452 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 4 | 2,084,050 | 0 | 0 | 2,084,050 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 5 | 2,980,751 | 27,930 | 0 | 3,008,681 | 18,140 (A) | 0.50 | 196,629 | 0 | 0 | 0 | 196,629 | 18,582 | 2,059 | 3,544 | 821 | 3,648 | 725,283 |
| 6 | 2,589,047 | 41,806 | 0 | 2,630,853 | 9,070 (B) | 0.65 | 255,617 | 98,314 | 0 | 0 | 353,931 | 32,149 | 3,705 | 6,132 | 1,420 | 6,311 | 403,648 |
| 7 | 1,995,111 | 123,461 | 0 | 2,118,572 | 53,000 (C) | 0.75 | 304,943 | 127,809 | 374,494 | 0 | 699,246 | 89,197 | 10,440 | 17,013 | 3,940 | 17,509 | 1,135,345 |
| 8 | 0 | 266,664 | 0 | 266,664 | 35,390 (D) | 0.85 | 334,269 | 147,471 | 746,842 | 393,610 | 1,612,192 | 144,200 | 16,878 | 27,504 | 6,370 | 28,306 | 1,835,450 |
| 9 | 0 | 266,664 | 0 | 266,664 | 0 | 0.90 | 333,931 | 167,134 | 861,740 | 498,693 | 1,881,498 | 168,288 | 19,698 | 32,098 | 7,434 | 33,024 | 2,142,050 |
| 10 | 0 | 266,664 | 0 | 266,664 | 0 | 0.95 | 373,594 | 176,966 | 976,639 | 575,415 | 2,107,614 | 188,065 | 27,013 | 35,871 | 8,908 | 36,916 | 2,393,737 |
| 11 | 0 | 266,664 | 0 | 266,664 | 0 | 1.00 | 393,257 | 186,797 | 1,034,088 | 652,157 | 2,266,229 | 202,704 | 23,726 | 38,563 | 8,554 | 39,799 | 2,580,116 |
| 12 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,091,538 | 690,498 | 2,371,922 | 212,153 | 24,832 | 40,465 | 9,372 | 41,644 | 2,700,388 |
| 13 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 728,859 | 2,467,732 | 220,723 | 25,835 | 42,100 | 9,750 | 43,326 | 2,809,466 |
| 14 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 15 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 16 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 17 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 18 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 19 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 20 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 21 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 22 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 23 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 24 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 25 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 26 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 27 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 28 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 29 | 0 | 266,664 | 12,899 | 279,563 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 30 | 0 | 266,664 | 325,559 | 592,223 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 31 | 0 | 266,664 | 351,449 | 618,113 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 32 | 0 | 266,664 | 432,505 | 699,169 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 33 | 0 | 266,664 | 15,625 | 282,289 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 34 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 35 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 36 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 37 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 38 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 39 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 40 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 41 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 42 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 43 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 44 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 45 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 46 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 47 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 48 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 49 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |
| 50 | 0 | 266,664 | 0 | 266,664 | 0 | | 393,257 | 186,629 | 1,148,987 | 727,220 | 2,506,093 | 224,154 | 26,237 | 42,754 | 9,902 | 44,000 | 2,853,140 |

| No. Year | Crop Production | Balance With | | | | All Item |
|----------|-----------------|--------------------|------------------------|-------------------------|---------------------------------|------------|
| | | + Road Development | + Water Right Transfer | + Domestic Water Supply | + Reduction/ Seasonal Migration | |
| 1 | -512,059 | -512,059 | -512,059 | -512,059 | -512,059 | -512,059 |
| 2 | -725,780 | -725,780 | -725,780 | -725,780 | -725,780 | -725,780 |
| 3 | -1,240,452 | -1,240,452 | -1,240,452 | -1,240,452 | -1,240,452 | -1,240,452 |
| 4 | -2,084,050 | -2,084,050 | -2,084,050 | -2,084,050 | -2,084,050 | -2,084,050 |
| 5 | -2,812,052 | -2,793,470 | -2,791,411 | -2,787,867 | -2,787,046 | -2,783,398 |
| 6 | -2,276,922 | -2,244,773 | -2,241,068 | -2,234,936 | -2,233,516 | -2,237,205 |
| 7 | -711,326 | -632,129 | -621,659 | -606,676 | -600,736 | -583,227 |
| 8 | 1,345,528 | 1,497,328 | 1,506,606 | 1,514,110 | 1,540,480 | 1,565,786 |
| 9 | 1,614,834 | 1,783,122 | 1,802,820 | 1,834,918 | 1,842,352 | 1,875,386 |
| 10 | 1,835,950 | 1,024,015 | 2,046,028 | 2,081,899 | 2,090,207 | 2,127,123 |
| 11 | 1,999,615 | 2,202,319 | 2,226,043 | 2,261,708 | 2,273,662 | 2,313,452 |
| 12 | 2,105,238 | 2,317,411 | 2,342,243 | 2,382,700 | 2,392,080 | 2,433,728 |
| 13 | 2,231,068 | 2,471,791 | 2,447,616 | 2,489,726 | 2,499,476 | 2,542,802 |
| 14 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 15 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 16 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 17 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 18 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 19 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 20 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 21 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 22 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 23 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 24 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 25 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 26 | 2,239,429 | 2,463,583 | 2,489,820 | 2,532,574 | 2,542,476 | 2,586,476 |
| 27 | 2,239,429 | 2,463,583 | 2,489,820 | | | |

付図




图3.1.1 土壤图




图3.1.2 土地分級图





图3.1.3 現況土地利用图



Source : D.I. Khan Meteorological Station, 30 years average from 1961 to 1990

図 3.3.1 調査対象地域の気象








図 3.3.2 調査対象地域の現況作付体系



(a) Marketing Flow of Wheat

- (1) 58% and 64% of wheat production are marketed from farms in Study Area and CRBC area, respectively.
- (2) 65% and 94% of wheat marketed are through Beopari in Study Area and CRBC area, respectively.
- (3) Procurement is conducted through PASSCO by the Food Department in D.I. Khan.



(b) Marketing Flow of Oil seeds (Sunflower)

図 3.3.3 小麦と油料作物の流通経路





図 3.3.4 D.I. カーン県における農産物の流れ



• 上記の各No. は、CRBC の排水横断構造物位置




図3.4.1 現況河川システム
F - 11




图 3.4.2 現況排水系統圖




図3.5.1 D.I. カーンにおける主要道路網




図3.5.2 パキスタン国における送電線グリッド




図3.5.3 調査対象地域の詳細送電線網






图5.3.4 灌溉用水系統圖



MTW System Type




DTW System Type

Exemplified Table
between length A and B

| A | B |
|---------|-------|
| 2,000 m | 870 m |
| 2,100 | 830 |
| 2,200 | 790 |
| 2,300 | 760 |
| 2,400 | 730 |
| 2,500 | 700 |
| 2,600 | 670 |
| 2,700 | 640 |
| 2,800 | 620 |
| 2,900 | 600 |
| 3,000 | 580 |

Vary the dimension of A and B as shown right table, in accordance with interval between distributary and flood carrier channel

図5.3.5 圃場整備標準図



Note: 1. Extension Advisors should be located in the field at the rate of one Advisor for each District. 10 Advisors should be recruited each year and given specialized training with foreign exposure. They will be the key functionaries and coordinators between the farmers and authority. They will help the farmers in demand based irrigation system, lay out of water courses, preparation of check bands and extension work.
 2. The construction staff should be gradually reduced as the canal goes to completion. Operational staff should simultaneously be increased for future operation.
 3. However, a joint project with Punjab, the gravity canal may continue to remain with WAPDA. However, its Distribution System may be taken over by the Authority.
 4. During construction stage the design and construction supervision should be done by the consultants. The Authority will provide top supervision only.

図5.6.2 チャシユマ右岸開発公社組織図




図6.1.1 チャシユマ貯水池の水位変化




図6.1.2 導水路標準断面

DIMENSION (Unit: mm)

| | SECTION OF CANAL | | | | |
|----|------------------|--------|-------|-------|-------|
| | 1 | 2 | 3 | 4 | 5 |
| B | 12,000 | 10,500 | 8,000 | 6,500 | 4,500 |
| D | 3,940 | 3,530 | 2,800 | 2,140 | 1,490 |
| Fb | 1,200 | 1,200 | 1,200 | 1,050 | 900 |

B : BED WIDTH
D : WATER DEPTH
Fb : FREE BOARD





図6.1.3 幹線水路標準断面



REMARKS
 DW : DIVERSION WEIR
 DS : DRAINAGE SIPHON
 SP : SUPER PASSAGE
 OD : OPEN DRAIN
 * : SUPPLEMENTAL DRAINAGE

INDEX 1-305/107

35% OF FULL FLOOD DISCHARGE
 FULL FLOOD DISCHARGE
 NO. OF CHANNEL

图 6.1.4 洪水路計画图





图7.3.1 各維持・管理事務所位置図



When sudden alternative happen, FDA request to change discharge

図7.3.2 灌漑用水供給スケジュールの決定手順

添付資料

調査関係者リスト

| Name | Position |
|---------------------------------|---|
| A. Advisory Committee | |
| Mr. Osamu Tuji | Chairman of Advisory Committee (MAFF) |
| Mr. Akira Hashimoto | Member, Irrigation and Drainage (MAFF) |
| Mr. Yoshizou Ichino | Member, Facilities and Structure (MAFF) |
| Mr. Akihiko Azumi | Member, Agriculture (MAFF) |
| Mr. Youichi Yamauchi | Member (MAFF) |
| Mr. Izumi Ohba | Member (MAFF) |
| Mr. Osamu Hotta | Member (Ministry of Foreign Affairs) |
| Mr. Yukio Okuda | Member (OECD) |
| B. Study Team | |
| Mr. Tadashi Otori | Team Leader |
| Mr. Chikaichi Takahashi | Co-Leader/Irrigation & Drainage Institution |
| Mr. Abdur Rahim Mahsud | Institution |
| Dr. Shuichi Matsushima | Meteorology & Hydrology |
| Mr. Akira Koto | Land Use/Farm Road |
| Mr. Makoto Suga | Geology/Land Conservation |
| Mr. Fumihiko Nagao | Soil/Agriculture |
| Mr. Manabu Fujikawa | Marketing |
| Mr. Yuichi Fukasaka | Agro-Economy/Project Evaluation |
| Mr. Keiji Tateyama | Environment |
| Mr. Motoo Taki | Facility Plan/Topo-survey |
| Mr. Akihiro Abe | Mechanical Plan/Design |
| Mr. Koichi Yamamoto | Design/Cost Estimate |
| C. Counterpart Personnel | |
| Mr. Akhtar Ali Ismaili | Overall Supervision, Irrigation Department, NWFP |
| Mr. Parvez Khan | Irrigation/Drainage, Project Irrigation Circle D.I.Khan, NWFP |
| Mr. Zaman Khan | Irrigation/Drainage, P&I Division, WAPDA, Peshawar |
| Mr. Shaifullah Khan | Irrigation/Hydrology, Project Irrigation Div. D.I.Khan, NWFP |
| Dr. Gul Hassan | Meteorology/Agriculture, ARI, D.I.Khan |
| Dr. Ahmad Bakhsh | Land Use, ARI, D.I.Khan |
| Mr. Naem Qasuria | Farm Road, Rural Development, D.I.Khan |
| Mr. Mehboob Alam | Geology/Land Conservation, P&I Division, WAPDA, Lahore |
| Dr. Nasir Ud Din | Agriculture, ARI, D.I.Khan |
| Mr. Inayat Ullah | Marketing, Agricultural Extension, D.I.Khan |
| Mr. Wahid Ud Din | Project Economy, P&I Division, WAPDA, Lahore |
| Dr. M.Bashir Khan | Environment, Environmental Protection Agency, Peshawar |
| Mr. Ghulam Abbas Virk | Design/Cost Estimate, P&I Division, WAPDA, Lahore |
| Mr. Shah Hussain Shah | Agro-Economy, ARI, D.I.Khan |
| Mr. Amir Reza | Facility design, P&I Division, WAPDA, Lahore |
| Mr. Syed Ahmed | Facility design, P&I Division, WAPDA, Lahore |
| Mr. Shafiq Ur Rehman | Mechanical design, HEPO, WAPDA, Lahore |

MAFF: Ministry of Agriculture, Forestry and Fisheries

ARI: Agricultural Research Institute


SCOPE OF WORK
FOR
THE FEASIBILITY STUDY
ON
CHASHMA RIGHT BANK 1ST LIFT IRRIGATION PROJECT

AGREED UPON BETWEEN
THE GOVERNMENT OF NORTH WEST FRONTIER PROVINCE,
THE ISLAMIC REPUBLIC OF PAKISTAN
AND
JAPAN INTERNATIONAL COOPERATION AGENCY


PESHAWAR, 11TH NOVEMBER, 1992



Mr. Inamullah Khan
Additional Secretary II
Planning and Development Department,
The Government of
North West Frontier Province



Mr. Sumio Oishi
Leader,
Preparatory Study Team,
Japan International
Cooperation Agency.



Mr. Faqir Ahmad Paracha
Secretary,
Irrigation and Public Health Department,
The Government of
North West Frontier Province

I. INTRODUCTION

In response to the request of the Government of the Islamic Republic of Pakistan (hereinafter referred to as 'GOP'), the Government of Japan (hereinafter referred to as 'GOJ') has decided to undertake the Feasibility Study on Chashma Right Bank 1st Lift Irrigation Project (hereinafter referred to as 'the Study'), in accordance with the relevant laws and regulations in force in Japan.

Accordingly, the Japan International Cooperation Agency (hereinafter referred to as 'JICA'), the official agency responsible for the implementation of the technical cooperation programmes of GOJ will undertake the Study, in close cooperation with the authorities concerned of the Islamic Republic of Pakistan (hereinafter referred to as 'Pakistan').

And as for the organizations concerned of Pakistan, the Irrigation & Public Health Engineering Department, the Government of North West Frontier Province (hereinafter referred to as 'IPIED'), will act as the counterpart agency to the Japanese study team as well as coordinating body in relation with other governmental and non-governmental organizations concerned for smooth implementation of the Study.

The present document sets forth the Scope of Work with regard to the Study.

II. OBJECTIVES OF THE STUDY

The objectives of the Study are:

1. To conduct the feasibility study on agricultural development for the Chashma Right Bank 1st Lift Irrigation Project (hereinafter referred to as 'the Project').
2. To carry out technology transfer to the Pakistani counterpart personnel through on-job training in the course of the Study.

III. STUDY AREA

The Study covers the Chashma Right Bank 1st Lift Irrigation Project area, which is approximately 110,000ha (see attached map).

IV. SCOPE OF THE STUDY

The Study will consist of two (2) phases and will cover the following:

R

V

1. Phase I

1-1 To collect and review existing data and information and to carry out field survey and investigation in the study area:

- natural condition
 - a. meteorology
 - b. hydrology
 - c. geology
 - d. soil
 - e. topography
 - f. others
- agriculture
 - a. land use and tenure
 - b. cropping pattern and yield
 - c. agronomy and institution
 - d. others
- agricultural infrastructure
 - a. irrigation and drainage facilities
 - b. farm roads
 - c. others
- socio-economic situation
 - a. population
 - b. household and farmers
 - c. regional socio-economy and household economy
 - d. social and farmers organizations
 - e. historical right/costums regarding irrigational water usage
 - f. others
- other information related to the Project
 - a. administrative organizations related to the Project
 - b. environmental impacts
 - c. others

1-2 To carry out household survey

1-3 To review other projects related to the Project

1-4 To review topographic map covering the study area, which has already been made in Pakistan (scale: 4 inch = 1 mile).

2. Phase II

2-1 Based on the results of the Phase I study, Phase II study covers the following items:

pk

✓ 30

- additional field survey, data collection and analysis including:
 - a. hydrology and meteorology
 - b. geology and soil classification
 - c. land use and tenure
 - d. cropping pattern and yield
 - e. irrigation and drainage
 - f. hill torrent study for cross drainage, erosion and flood damages
 - g. regional socio-economy and farm household economy
 - h. social and farmers organizations
 - i. environment
 - j. others
- 2-2 To formulate an irrigation and agricultural development programme for the Project
- 2-3 Preliminary design of the major structures of the Project
- 2-4 Preparation of the implementation schedule
- 2-5 Preparation of the operation and maintenance plan for major structures
- 2-6 Preparation of the environmental preservation plan
- 2-7 Estimate of the project costs and benefits
- 2-8 Recommendation

V. STUDY SCHEDULE

The study will be carried out in accordance with the attached tentative schedule.

VI. REPORTS

JICA shall prepare and submit following reports in English to GOP.

- (1) Inception Report
Twenty (20) copies at the commencement of the Study.
- (2) Progress Report (1)
Twenty (20) copies at the end of the Phase I Study in Pakistan.
- (3) Interim Report
Twenty (20) copies at the end of the Phase I study.

fl

[Handwritten signature]

- (4) Progress Report (2)
Twenty (20) copies at the end of the Phase II Study in Pakistan.
- (5) Draft Final Report
Twenty (20) copies at the end of the Phase II study.
GOP provides JICA with its comments on the Draft Final Report within one (1) month after receipt of the Draft Final Report.
- (6) Final Report
Fifty (50) copies within two (2) months after receiving GOP's comments on the Draft Final Report.

VI. UNDERTAKING OF THE GOVERNMENT OF PAKISTAN

1. To facilitate smooth conduct of the study, GOP shall take necessary measures:
 - 1-1 to secure the safety of the Japanese study team.
 - 1-2 to permit the members of the Japanese study team to enter, leave and sojourn in Pakistan for the duration of their assignment therein, and exempt them from foreign registration requirements and consular fees.
 - 1-3 to exempt the members of the Japanese study team from taxes, duties, fees and any other charges on equipment, machinery and other materials brought into of Pakistan for the conduct of the study.
 - 1-4 to exempt the members of the Japanese study team from income tax and charges of any kind imposed on or in connection with any emoluments or allowances paid to the members of the Japanese study team for their services in connection with the implementation of the Study.
 - 1-5 to provide necessary facilities to the Japanese study team for the remittance as well as utilization of the funds introduced into Pakistan from Japan in connection with the implementation of the Study.
 - 1-6 to secure permission for entry into private properties and other areas for the conduct of the Study as and when necessity arises.
 - 1-7 to secure permission for the Japanese study team to take all data and documents related to the Study including photographs and maps, also including aerial photographs necessary for the Study (excluding restricted areas), out of Pakistan to Japan, on case to case bases.
 - 1-8 to provide medical services as needed. Its expense will be chargeable on the members of the Japanese study team.
2. GOP shall bear claims, if any arises, against the members of the Japanese study team, resulting from, occurring in the course of, or otherwise connected with the discharge of their duties in the implementation of the Study, except when such claims arise from gross negligence or wilful misconduct on the part of the members of the Japanese study team.

3. IPIED shall, at own expense, provide the Japanese study team with the followings, in cooperation with the other authorities concerned:
 - 1) available data and information related to the Study,
 - 2) counterpart personnel,
 - 3) suitable office with necessary furniture in Peshawar and project sites,
 - 4) credentials or identification cards, and
 - 5) necessary number of vehicles with drivers.

IV. UNDERTAKING OF JICA

For the conduct of the Study, JICA shall take the following measures:

1. To dispatch study teams, at its own expense, to Pakistan, and
2. To conduct technology transfer to the Pakistani counterpart personnel in the course of the Study.

V. CONSULTATION

JICA and IPIED will consult each other in respect of any matter that may arise from or in connection with the Study.

q

4
✓

30

TENTATIVE SCHEDULE

| Month | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | |
|----------|-----------|---|---|---|---|---|-------------|---|---|----|-----------|----|----|----|----|----|----|----|----|----|----|-------------|-----------|----|----|----------|----|--|
| Item | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Phase I | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Phase II | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Reports | △ IC/R | | | | | | △ P/R(1) | | | | △ IT/R | | | | | | | | | | | △ P/R(2) | △ DF/R | | | △ F/R | | |

(Remarks) IC/R : Inception Report P/R(1) : Progress Report (1)
 IT/R : Interim Report P/R(2) : Progress Report (2)
 DF/R : Draft Final Report F/R : Final Report


— : Work in Pakistan
 - - - : Home Office Work in Japan
 ⊙ : Comments on DF/R by Pakistan side

Handwritten mark

Handwritten mark

Handwritten mark

AREA OF
THE FEASIBILITY STUDY ON
CHASHMA RIGHT BANK
1ST LIFT IRRIGATION
PROJECT



MINUTES OF MEETING
ON
SCOPE OF WORK
FOR
THE FEASIBILITY STUDY
ON
CHASHMA RIGHT BANK 1ST LIFT IRRIGATION PROJECT


The preparatory study team (hereinafter referred to as 'the Team') organized by the Japan International Cooperation Agency (hereinafter referred to as 'JICA'), and headed by Mr. Sumio Oishi, visited the Islamic Republic of Pakistan from October 26 to November 13, 1992 for the purpose of discussing and confirming the Scope of Work for the Feasibility Study on the Chashma Right Bank 1st Lift Irrigation Project (hereinafter referred to as 'the Study').

The team had a series of discussions with the officials concerned of the Irrigation and Public Health Engineering Department, the Government of North West Frontier Province (hereinafter referred to as 'IPHED') on the Scope of Work for the Study. The list of participants in a series of meetings is attached in the Annex.


The following are the main issues discussed and agreed by IPHED and the Team.

1. IPHED and the Team both agreed on the issues mentioned in the Scope of Work.
2. IPHED shall provide the Japanese study team a set of topographic map (scale, 4 inch = 1 mile, contour, 5 feet) which covers the whole Study area before the commencement of the Study, and also will provide the one in scale, 1:5,000, contour, 0.25 metre, until 1(one) year after the commencement of the Study.
3. The Team has decided to conduct the Study according to the confirmation given by IPHED that there are sufficient amount of water and electricity available regarding the implementation of the Chashma Right Bank 1st Lift Irrigation Project.
4. IPHED shall provide the Japanese study team with offices which are equipped with electricity, city water, and telephones in Peshawar and the Study area.
5. IPHED requested that local consultants be associated with the Study to the extent possible. The Team noted this request, but observed that this would be determined by the Japanese study team.


6. IPHED requested that the following equipments necessary for the Study be procured by JICA and be donated to IPHED after the termination of the Study. The Team promised to convey its request to the Government of Japan.
- vehicles
 - computers
 - copymachines
 - faxmachines
 - survey equipments
7. IPHED requested the counterpart training in Japan. The Team promised to convey its request to the Government of Japan.
8. The Government of North West Frontier Province noted that items mentioned in the Scope of Work, sub-paragraph 1-2 to 1-5, and 1-7 of paragraph Ⅷ, would require clearance by the Federal Government.



Mr. Inamullah Khan
Additional Secretary II,
Planning and Development Department
The Government of
North West Frontier Province



Mr. Sumio Oishi
Leader,
Preparatory Study Team,
Japan International
Cooperation Agency






Mr. Faqir Ahmad Paracha
Secretary,
Irrigation and Public Health Engineering Department,
The Government of
North West Frontier Province

LIST OF PARTICIPANTS

ANNEX

PAKISTAN SIDE

| | | |
|-----------------------------|--|---|
| 1. Mr. Mohammad Saleem Khan | Secretary | Planning and Development Department, The Government of NWFP |
| 2. Mr. Inamullah Khan | Additional Secretary II | Planning and Development Department, The Government of NWFP |
| 3. Mr. Faqir Ahmad Paracha | Secretary | Irrigation and Public Health Engineering Department, The Government of NWFP |
| 4. Mr. Muhammad Munir | Chief Engineer (P&I) | WAPDA, Lahore |
| 5. Mr. M. Ishhaq Shinwari | Project Director (P&I) North | WAPDA, Lahore |
| 6. Mr. Nawab Khan Masood | Chief Engineer Water Sector Investment Planning | Planning and Development Department, The Government of NWFP |
| 7. Mr. Akhtar Ali Ismaili | Chief Engineer (Development) | Irrigation and Public Health Engineering Department, The Government of NWFP |
| 8. Mr. Jan Sardar Gul | General Manager | WAPDA, North |
| 9. Mr. Muhammad Zaman Khan | Director (P&I) | WAPDA, Peshawar |
| 10. Mr. Habibullah Khan | Project Director, D. I. Khan | Irrigation and Public Health Engineering Department, The Government of NWFP |
| 11. Mr. Abdul Wasai | Director | WAPDA, Peshawar |
| 12. Dr. Abdul Waheed | Chief Planning Officer | Food, Agriculture and Cooperative Department, The Government of NWFP |
| 13. Mr. Mohammad Yousef | Director, Water Management | Agriculture Department, The Government of NWFP |
| 14. Mr. Attaullah Khan | Director, Planning | Agriculture Extension Department, The Government of NWFP |
| 15. Mr. Amjad Shahid Afridi | Chief (Water & Power)  | Planning and Development Department, The Government of NWFP |

- | | | |
|---------------------------|--|--|
| 16. Mr. Ahmad Samad | Project through Secretary of Agriculture | Agriculture Extension Department. The Government of NWFP |
| 17. Mr. Muhammad Zulfiqar | Planning Officer | Agriculture Extension Department. The Government of NWFP |
| 18. Mr. Khan Said | Director. Technical | Area Electricity Board. WAPDA, Peshawar |


THE TEAM

- | | |
|---------------------------|----------------------|
| 1. Mr. Sumio Oishi | Leader |
| 2. Mr. Takannbu Kobayashi | Irrigation Engineer |
| 3. Mr. Akihiko Azumi | Agronomist |
| 4. Dr. Katsumi Chida | Environmental Expert |
| 5. Mr. Akira Shimizu | Coordinator |


H

[Signature]


V




PLAN
SCALE B




SECTION C-C
SCALE B




SECTION E-E
SCALE B




SECTION B-B
SCALE B



SECTION D-D
SCALE B




SECTION OF HEAD RACE DRAGGING
SCALE A






SECTION A-A
SCALE B

(*) MAX.P.L. : MAXIMUM POND LEVEL
N.P.L. : NORMAL POND LEVEL



ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF NORTH WEST FRONTIER PROVINCE
CHASHMA RIGHT BANK 1ST LIFT IRRIGATION PROJECT
INTAKE STRUCTURE WITH CROSSING OF DIKE
OF CHASHMA BARRAGE
JAPAN INTERNATIONAL COOPERATION AGENCY D.W. NO.



ISLAMIC REPUBLIC OF PAKISTAN
GOVERNMENT OF NORTH WEST FRONTIER PROVINCE
CHASHMA RIGHT BANK 1ST LIFT IRRIGATION PROJECT


PUMP STATION (1/3)

JAPAN INTERNATIONAL COOPERATION AGENCY D.W. NO.

TP-01(BP OF MAIN CANAL
X = 3020 135.000
Y = 876 631.111


DELIVERY PIPELINE
3 SERIES OF STEEL PIPES
L = 684 M
(#3200 IN DIAMETER)

DELIVERY PIPELINE
3 SERIES OF STEEL PIPES
L = 684 M
(#3200 IN DIAMETER)




PLAN OF PUMP HOUSE

S·I·300




FLOW SHEET OF AUXILIARY EQUIPMENTS




PLAN OF SUBSTATION

S·I·200

| |
|--|
| ISLAMIC REPUBLIC OF PAKISTAN GOVERNMENT OF NORTH WEST FRONTIER PROVINCE |
| CHASHMA RIGHT BANK 1ST LIFT IRRIGATION PROJECT |
| PUMP STATION (2/3) |
| JAPAN INTERNATIONAL COOPERATION AGENCY D.W. NO. |




C - C S = 1 : 300




D - D S = 1 : 300


ISLAMIC REPUBLIC OF PAKISTAN
 GOVERNMENT OF NORTH WEST FRONTIER PROVINCE
 CHASHMA RIGHT BANK 1ST LIFT IRRIGATION PROJECT
 PUMP STATION (3/3)
 JAPAN INTERNATIONAL COOPERATION AGENCY | D.W. NO.




TYPICAL SECTION FULL CUT WITH FLOOD PROTECTION DIKE
SCALE A




LINING DETAILS
SCALE C



TYPICAL SECTION CUT & FILL WITH FLOOD PROTECTION DIKE
SCALE A



DETAIL-A
SCALE B (BERM DRAIN)



TYPICAL SECTION CUT & FILL OR FULL CUT WITHOUT FLOOD PROTECTION DIKE
SCALE A

DIMENSION TABLE

| No. OF SECTION | STATION No. OF BP - EP | DISCHARGE (m ³ /s) | BOTTOM WIDTH B (m) | CANAL HEIGHT H (m) | WATER DEPTH h (m) | FREE BOARD F.B. (m) | W (m) |
|----------------|----------------------------|-------------------------------|--------------------|--------------------|-------------------|---------------------|-------|
| 1 | 0+000 - 32+800 (32.80km) | 72 | 12.0 | 5.15 | 3.94 | 1.21 | 27.45 |
| 2 | 32+800 - 58+550 (23.75km) | 53 | 10.5 | 4.75 | 3.53 | 1.22 | 24.75 |
| 3 | 58+550 - 75+000 (16.45km) | 30 | 8.0 | 3.80 | 2.60 | 1.20 | 19.40 |
| 4 | 75+000 - 94+300 (19.30km) | 20 | 6.5 | 3.20 | 2.14 | 1.06 | 16.10 |
| 5 | 94+300 - 113+250 (18.95km) | 10 | 4.5 | 2.40 | 1.49 | 0.91 | 11.70 |

