

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: PART 2, FEASIBILITY STUDY

c) Hatta quay will be exclusively used for container terminal and the on-going plan should be basically followed by the Study.

64. The capacity of the new container terminal to be completed in 1997 is estimated at 145,000 TEU(116,000 Box)/Year and will be saturated in 1999 - 2002. The saturation will come from the shortage of container yard area as well as handling equipment. Thus, an additional container yard including CFS area should be provided outside the Port as an inland depot prior to the saturation, because there is no available space near the container terminal or at any place inside the Port.

65. The site next to the existing ship yard at Kel Tallo north of the Port is proposed for the location of the inland container terminal. Equipment for handling containers is also proposed for procurement together with the development of additional access channels and terminal facilities. Development of access roads are further proposed to keep smooth connection with the regular and toll roads around the inland terminal.

66. Cost estimation is carried out based on the preliminary design of the major facilities and the implementation program. Total construction cost including infrastructure, superstructure, and equipment of both the port and inland terminals amounts to 190,112 million Rp.

5.1.3 Short-Term Development Plan

67. On the basis of the Master Plan and cargo forecast for the years 2003 and 2010, the following facilities and equipment will be required for accepting container ships and handling containers.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: PART 2, FEASIBILITY STUDY

| | Master Plan (M/P) | Short-Term Development Plan |
|------------------------------------|--|--|
| 1.New Hatta Quay | -Power supply : 1 set -Terminal building : 600 m ² -Yard fence : 270 m -Information and control system | -same as M/P -same as M/P -same as M/P -same as M/P |
| 2.Inland Container Terminal | -Yard reclamation : 15.5 ha -CFS sheds : 15,750 m ² -Open yard storage : 6.6 ha -Office building : 1 bld. -Work shop : 1 bld. -Utilities : 1 set | -: 8.5 ha -: 9,000 m ² -: 2.7 ha -same as M/P -same as M/P -: 1 set |
| 3.Access Entrance | -Road embankment and pavement -Gate -Bridge(Box culvert) -Utilities | -same as M/P -same as M/P -same as M/P |
| 4.Connecting Toll Road | -Road embankment and pavement -Fence and utilities | -part of M/P -same as M/P |
| 5.Access Channel | -Navigation aids -Dredging and disposal :685,000m ³ | -same as M/P -:438,000 m ³ |
| 6.Equipment and Information System | -Quay gantry crane : 3 units -Rubber tired gantry crane : 14 units -Forklift(7 ton) : 14 units -(3.5 ton) : 12 units -Reachstacker(45ton) : 6 units -Tractor head : 54 units -Chassis :108 units -Generator(150KVA) : 2 units -(400KVA) : 2 units -Computer & software : 11 units | -: 3 units -: 9 units -: 7 units -: 9 units -: 2 units -:27 units -:54 units -: 1 units -: 2 units -:10 units |

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: PART 2, FEASIBILITY STUDY

68. Preparation for project implementation, such as basic /detail design will continue until the end of 1997. Following this period, the beginning of the construction works and installation of the container handling equipment will begin as required till 2003.

69. Project cost is estimated based on the basic design of the major facilities and handling equipment. Total construction cost including infrastructure, superstructure, and equipment of both the port and inland terminals amounts to 129,125 million Rp.(Foreign portion: 106,412 million Rp., Local portion: 22,713 million Rp.) including physical contingency and engineering fee.

70. Environmental impact assessment(EIA) was carried out for the two works as follows:

- a)Dredging and dumping in access channel of Uj. Pandang Port
- b)Construction of inland container terminal for Uj. Pandang Port

According to the assessment, both portions are expected to cause impacts to some environmental components around the project site to some extent. Therefore careful countermeasure to avoid significant impacts should be employed for the project implementation and operation.

71. Evaluation of the short-term development plan for the container terminal at Uj. Pandang Port was executed by the internal rate of return(IRR) through cost/benefit analysis. Economic benefit is mainly accrued from the saving in ships' port staying cost and interest of cargo cost, etc. Calculated IRR for the container terminal including the inland terminal is 15.6 % under a 30 year project life. This figure exceeds the national and international bench-mark and the project can be considered to be economically feasible.

72. In order to confirm the viability of the project, Financial Internal Rate of Return(FIRR) is calculated for the proposed project together with related alternative schemes. If the project is executed through low-interest fund, not only this project but also the total project including the on-going project will become financially feasible. Even if the equipment in the terminal is financed and operated by a private company, it will be difficult for the company to refund the capital cost under the current market interest rate. Accordingly, the project should be executed by low-interest rate source, and operated and managed, together with the on-going project as one body, by the public sector.

5.2 RECOMMENDATIONS

73. In order to compensate for the shortage of container yard space including CFS area, an additional inland terminal should be developed outside the Port to coordinate operation with the port terminal. In view of the limited CFS area inside the Port, it is recommended that an additional CFS be installed in the inland terminal in 1997 when the container terminal is inaugurated.

74. The Team suggests that the on-going terminal plan partially implemented should be modified to some extent taking into consideration the linkage between the new inland terminal and the on-going plan. The planned construction works related to the proposed modification should be soon postponed and then implemented based on the short-term development plan which is to be proposed in Part 2.

75. The on-going project excludes the procurement of handling equipment for containers, but it is clear that the container cargo loaded/unloaded in 1997 when the terminal is completed will not be able to be handled without installation of container gantry cranes, judging from the efficiency of ship gears for container handling. Therefore it is recommended that two gantry cranes with other related equipment be provided upon completion of the proposed container terminal.

76. To raise efficiency in terminal operation and service, it is preferable to introduce computerization when the gantry cranes are installed in the terminal. Further, the computer systems should be expanded to the inland terminal to operate the container terminal including the inland terminal as one body when it is used as a container yard other than CFS area.

77. Since Sulawesi has no railway facilities, road is the major arterial transport facility. In line with the progress of the container terminal, Uj. Pandang port, highways under planning to connect the Port and Uj. Pandang city with its hinterland should be developed without delay.

78. The inland terminal should be smoothly connected to the toll road in each directions. According to the original development plan of the toll road, it is unlikely that the connecting road from the terminal will easily join the proposed toll road southward because of the steep slope of the planned toll road. Therefore it is suggested that

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: PART 2, FEASIBILITY STUDY

coordination should be made to connect both roads with other for smooth joining between port and road sides.

79. In line with increase of international container ship calls, it is suggested that a new berth allocation system like 'window system' instead of 'first come, first served' system, be studied to keep container ship sailing on schedule.

80. It is suggested that the establishment of a new sub division should be examined to operate the specialized container terminal including the inland terminal, in order to raise efficiency and high quality service in terminal operation.


81. To obtain more safety of navigation around the port water area, special navigation traffic rules should be examined with the development of the new entrance channel and tanker docking facilities of PERTAMINA.

82. When dredging the access channel is carried out, a dredging fleet consisted of grab dredger along with barges with bottom doors should be selected instead of cutter suction dredger or drug suction dredger. Further, reclamation works should be started after revetments are completed.

83. The container terminal at Uj. Pandang port will be still in the cradle stage in 2003 and it is expected that the project should be executed by low-interest rate source, and operated and managed, together with the on-going project as one body, by the public sector (PELABINDO IV).

Part 3

Feasibility Study of Container Cargo Handling Facilities of Gedebage Dry Port and Connecting Railway



Route Map Between Tg.Priok and Gedebage

SERIBU
Morioo.
National ARCHIPELAGO
Park
★ Seaside Resort
(THOUSAND ISLANDS)




Photo. taken: April. 1994

Container Yard of Container Terminal I (CTI), Port of Tanjung Priok, Jakarta



Pasoso Terminal and Tanjung Priok Station, Jakarta

Note:
All Photographs
are taken by
JICA Study Team

Photo. taken: May. 1994




Photo taken: April, 1994

Gedebage Dry Port, Bandung, West Java





Photo taken: April, 1994

Kiaracondong, Bandung



Land space expected for arrival and departure tracks at Gedebage



Land space expected for tracks at Pasoso container terminal



The bridge on the doubling track section between Gedebage and Kiaracandong

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY

Table of Contents

| | | |
|--|--|-------------|
| Part 3: Feasibility Study of Gedebage Dry Port and the Connecting Railway | | Page |
| 1. | Transportation Plan | -----160 |
| 1.1 | Container Cargo Demand Forecast at Gedebage Dry Port | -----160 |
| 1.2 | Freight Volume at Container Station and Train Operation | -----161 |
| 1.3 | Selection of Container Transportation Route and Purpose of Dry Port | -----164 |
| 2. | Construction Plan | -----167 |
| 2.1 | Layout of Required Facilities at Each Station | -----167 |
| 2.2 | Doubling of Track Plan | -----175 |
| 2.3 | Necessary Rolling Stock and Car Depot Improvement | -----178 |
| 2.4 | Environmental Impact Study | -----180 |
| 3. | Operation and Management Plan | -----183 |
| 3.1 | Basic Idea | -----183 |
| 3.2 | Daily Revenue and Expenses | -----184 |
| 4. | Investment Cost Estimate and Construction Schedule | -----187 |
| 4.1 | Necessary Investment Amount | -----187 |
| 4.2 | Construction Schedule | -----187 |
| 5. | Economic Analysis and Financial Analysis | -----190 |
| 5.1 | Economic Analysis | -----190 |
| 5.2 | Financial Analysis | -----191 |
| 6. | Conclusions and Recommendations | -----194 |
| 6.1 | Conclusions | -----194 |
| 6.2 | Recommendations | -----195 |
| Appendix 1 The Present Situation of Gedebage Dry Port and Connecting Railway | | |

List of Tables

Part 3

| | | |
|----------|---|-----|
| Table 47 | Container Cargo Demand Forecast in the Hinterland of Gedebage | 160 |
| Table 48 | Container Cargo Demand Forecast at Gedebage Dry Port | 160 |
| Table 49 | Container Cargo Demand Forecast for Full and Empty Container | 160 |
| Table 50 | Container Cargo Demand Forecast for 20' and 40' Container | 161 |
| Table 51 | Freight Volume Processed at Container Stations | 162 |
| Table 52 | Transportation Demand and Required Number of Trains Between Tanjung Priok and Gedebage | 163 |
| Table 53 | Handling Capacity at Container Stations (at Peak Time) | 174 |
| Table 54 | No. of Trains by Year (Includes Sent-on Locos) | 176 |
| Table 55 | Required Number of Locomotives | 179 |
| Table 56 | Required Number of Wagons | 179 |
| Table 57 | Container and Handling Charge Between Gdb and Tg. Priok | 185 |
| Table 58 | Expense Per Container Train | 186 |
| Table 59 | Required Investment Amount | 188 |
| Table 60 | Required Completion Times for Facilities | 189 |
| Table 61 | Results of Sensitivity Analyses | 191 |
| Table 62 | Results of Sensitivity Analysis | 193 |

List of Figure

Part 3

| | | |
|-----------|--|-----|
| Figure 32 | Main Improvements for Container Transportation | 166 |
| Figure 33 | Track Layout at Gedebage | 170 |
| Figure 34 | Layout of Facilities at Kac | 171 |
| Figure 35 | Network Around Tg. Priok (Pasoso) | 172 |
| Figure 36 | The Change of Track Layout at Each Step | 173 |
| Figure 37 | Layout of Double Track | 177 |
| Figure 38 | Profile of Embankment (A) | 177 |

Preface

The team selected Gedebage Dry Port and its connecting railway for a feasibility study (F/S) from among four existing routes contained in the Master Plan (M/P), and reported on the first half of the construction (till 1999) in the F/S as the Urgent Implementation Plan (Vol. 2 : Chapter 8).

The F/S report (Vol.4) includes not only the improvement until 2003, but additional improvements executed during the project's life span, which are necessary for both the economic and financial analysis.

The study going on with the above is proceeded based on the following issues.

- i) The object of F/S is Gedebage Dry Port and the relevant facilities.
- ii) As the premises, the necessary doubling of track and automatic signalization between Ckp and Pdl is completed by another project.
- iii) F/S includes urgent implementation plan and objectives only additional number of handling containers and the additional investment from 1995, based on the container traffic demand.
- iv) F/S studies whether the present transportation route can be responsible for the forecasted demand at Gedebage in 2003 year and for the set up of TCT-III expected by 2000 year or not.
- v) Major facilities to be improved are as follows. **(Fig. 19)**
 - a) New additional Container terminal at Gdb.
The study of the way of using concerning Gdb. and Kac.
 - b) Improvement of Tpk and Pasoso corresponding to the above and the Tg. Priok port improvement action plan.
 - c) Improvement of car depot, if necessary.
 - d) Doubling track between Gdb and Kac and the automatic signalization between them.

The present situation of the subject is described in **Appendix 1.**

1. TRANSPORTATION PLAN

1.1 CONTAINER CARGO DEMAND FORECAST AT GEDEBAGE DRY PORT

1. Container cargo exported from Gdb consists of light industry products such as textiles.

Therefore, the economic growth rate is forecasted for the hinterland as 75% of that of the West Jawa industrial zone.

Based on the above growth rate, all container cargo demand originating from the hinterland is forecasted by summing up each product in the future classified by textile, other light industry products and agricultural products. (Table 47)

Table 47 Container Cargo Demand Forecast in the Hinterland of Gedebage

| | (TEU) | | | | |
|-----------------|--------|--------|---------|---------|---------|
| Year | 1993 | 1994 | 1998 | 2003 | 2010 |
| Container cargo | 77,000 | 80,000 | 102,000 | 139,000 | 214,000 |

2. About 10% of the above demand ignores the railway due to high cube type containers or client requests.

Therefore, potential demand for railway is calculated as 90% of total demand forecast as follows.

Table 48 Container Cargo Demand Forecast at Gedebage Dry Port

| | (TEU) | | | | |
|-----------------|--------|--------|--------|---------|---------|
| Year | 1993 | 1994 | 1998 | 2003 | 2010 |
| Container cargo | 70,000 | 72,000 | 92,000 | 124,000 | 190,000 |

3. The present annual ratio for full and empty container is adopted as follows.

Table 49 Container Cargo Demand Forecast for Full and Empty Container

| | (TEU) | | | | |
|----------------|--------|--------|--------|--------|--------|
| Year | 1993 | 1994 | 1998 | 2003 | 2010 |
| Exported full | 32,000 | 34,000 | 42,000 | 57,000 | 88,000 |
| Exported empty | 3,000 | 2,000 | 4,000 | 5,000 | 7,000 |
| Imported full | 10,000 | 10,000 | 15,000 | 20,000 | 30,000 |
| Imported empty | 25,000 | 26,000 | 31,000 | 42,000 | 65,000 |

4. The handling volume ratio between 20' and 40' containers is 44:56 in terms TEUs. The ratio of 40' containers has been increasing, so a fifty: fifty ratio is adopted for the future as follows.

Table 50 Container Cargo Demand Forecast for 20' and 40' Container

| | (TEU) | | | | |
|---------|--------|--------|--------|--------|---------|
| Year | 1993 | 1994 | 1998 | 2003 | 2010 |
| 20 feet | 27,100 | 31,500 | 37,900 | 47,000 | 63,000 |
| 40 feet | 33,800 | 40,500 | 54,100 | 77,000 | 127,000 |

1.2 FREIGHT VOLUME AT CONTAINER STATION AND TRAIN OPERATION

(1) The maximum processing capacity of the Gdb container yard is estimated only at five trains at peak time (87,000 TEUs / year), due to the small platform space even after urgent implementation.

Concerning handling at other stations, unloading of empty containers at Gdb is shifted to Kac St in 1998, as a result of the completion of the Urgent Implementation Plan in 1997.

5. This will result in the handling volume at Gdb decreasing remarkably from 92,000 TEUs to 61,000 TEUs. However volume will exceed 87,000 TEUs again in 2004, and it will be necessary to move all unloading work to Kac St.

Based on the above, the annual handling volume at each station is as shown in Table 51.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

Table 51 Freight Volume Processed at Container Stations (unit :TEU)

| Year | Gedebage | Kiaracondong | Pasoso | Remarks |
|------|----------|--------------|---------|-------------|
| 1993 | 60,918 | | 60,918 | Result |
| 1994 | 72,000 | | 72,000 | Forecast |
| 1995 | 77,000 | | 77,000 | hereinafter |
| 1996 | 82,000 | | 82,000 | the same |
| 1997 | 87,000 | | 87,000 | |
| 1998 | 61,000 | 31,000 | 92,000 | * |
| 1999 | 65,000 | 33,000 | 98,000 | |
| 2000 | 69,500 | 35,500 | 105,000 | |
| 2001 | 73,000 | 37,500 | 111,000 | |
| 2002 | 78,000 | 40,000 | 118,000 | |
| 2003 | 82,000 | 42,000 | 124,000 | |
| 2004 | 88,000 | 45,000 | 133,000 | |
| | 66,500 | 66,500 | 133,000 | ** |
| 2010 | 95,000 | 95,000 | 190,000 | |

* Unloading of arriving empty containers only at Kac St.

** Unloading of all arriving containers at Kac St.

(2) The capacity of a container train is 34 TEUs, and requires an auxiliary locomotive between Gdb and Pwk.

The operational pattern of container trains is planned in accordance with weekly deviation classified by Sundays and Mondays, other weekdays, and annual peak time. The change in annual transportation demand and the necessary supply of trains is as shown in Table 52.

**Table 52 Transportation Demand and Required Number of Trains
between Tanjung Priok and Gedebage**

| Year | Transportation demand TEU | Number of trains | | | Train operation plan | | | | Train operation rate |
|------|----------------------------------|------------------|-------|-------------|----------------------|---------------------------|--|-------------------------------------|----------------------|
| | | /year | B/365 | Round-trips | Operation pattern | Number of trains /year | Average number of train one round trip/day | Transportation capacity TEU/year | B/P% |
| | | | /day | /day | /day | | | | |
| A | B | C | D | E | F | G | H | I | |
| 1990 | 23,065 | 678 | 1.9 | 1.0 | | | | | |
| 1991 | 35,836 | 1,054 | 2.9 | 1.5 | | | | | |
| 1992 | 52,008 | 1,530 | 4.2 | 2.1 | | | | | |
| 1993 | 60,918 | 1,792 | 4.9 | 2.5 | 2- 3- 4 | 2,102 | 2.9 | 71,469 | 85.3 |
| 1994 | 72,000 | 2,118 | 5.8 | 2.9 | 3- 4- 5 | 2,832 | 3.9 | 96,288 | 74.8 |
| 1995 | 77,000 | 2,265 | 6.2 | 3.1 | | | | | 80.0 |
| 1996 | 82,000 | 2,412 | 6.6 | 3.4 | | | | | 85.2 |
| 1997 | 87,000 | 2,559 | 7.0 | 3.5 | | | | | 90.4 |
| 1998 | 92,000 | 2,706 | 7.4 | 3.7 | 4- 5- 6 | 3,562 | 4.9 | 121,108 | 76.0 |
| 1999 | 98,000 | 2,882 | 7.9 | 4.0 | | | | | 80.9 |
| 2000 | 105,000 | 3,088 | 8.4 | 4.2 | | | | | 86.7 |
| 2001 | 111,000 | 3,265 | 8.9 | 4.5 | 5- 6- 7 | 4,292 | 5.9 | 145,928 | 76.1 |
| 2002 | 118,000 | 3,471 | 9.5 | 4.8 | | | | | 80.9 |
| 2003 | 124,000 | 3,647 | 10.0 | 5.0 | | | | | 85.0 |
| 2004 | 133,000 | 3,912 | 10.7 | 5.4 | 6- 7- 8 | 5,022 | 6.9 | 170,748 | 77.9 |
| 2005 | 143,000 | 4,206 | 11.5 | 5.8 | | | | | 83.8 |
| 2006 | 152,000 | 4,471 | 12.2 | 6.1 | | | | | 89.0 |
| 2007 | 162,000 | 4,765 | 13.1 | 6.6 | 7- 8- 9 | 5,752 | 7.9 | 195,568 | 82.8 |
| 2008 | 171,000 | 5,029 | 13.7 | 6.9 | | | | | 87.4 |
| 2009 | 181,000 | 5,324 | 14.6 | 7.3 | 8- 9-10 | 6,482 | 8.9 | 220,388 | 82.1 |
| 2010 | 190,000 | 5,588 | 15.3 | 7.7 | | | | | 86.2 |

Note : 1. Transportation demand is based on 1990 - 1993 traffic results.

2. The transportation capacity of a train is 34TEUs.

3. Operation pattern : Sundays and Mondays - other weekday - peak days.

1.3 SELECTION OF CONTAINER TRANSPORTATION ROUTE AND PURPOSE OF DRY PORT

(1) The selection of transportation route (Fig. 32)

6. There exists the request for changing the present container transportation route which is due to the inability of the Jatinegara (Jng) - Bekasi (Bks) section to handle increases in transportation demand.

As for countermeasures, the team must consider doubling the double track or constructing new Bekasi line, whose construction schedule is pending.

Both duplicated investment at the same time is wasteful.

The existing transportation route will have no problems in the near future based on the traffic demand for 2003 (6 - 7 trains one way), as long as there are not large increases in commuter. This is because that freight and passenger traffic utilizes the section at different time zone each other.

7. Since the new Bekasi Line will pass through highly populated area, and be constructed as an elevated structure, utilizing available land from the removal of sidings on the south side of the Pasoso St. so land acquisition is not necessary.

This will permit the installation of a new branch line at Pasoso St.

Shifting the container and intercity routes will not only alleviate transportation capacity between Jak, Mri and Bks, but also cut in half the 32 km distance between Pasoso and Bekasi. This will improve the chances of profitability for the New Bekasi Line and result in the disappearance of a train crossing in front of Tpk station square.

Early construction of the new line is therefore warranted.

(2) Purpose of dry ports

8. In the Urgent Implementation plan, Kac St. handles only the unloading of empty containers.

This is an effective countermeasure, because it requires only small scale initial investment, in spite of the increase in handling costs owing to empty chassis being sent to Kac St.

However, an increase of eight round-trips or more demands the installation of arrival and departure track at Gdb St. and the installation of a gantry crane and sub-main track together with heavy pavement for the container yard, at Kac St. In this case the

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

potential handling capacity is estimated at ten round trips (see details in Vol.4 Section 2.2).

Based on the above, the following argument would arise; improvements at Gdb St. should be restricted to the Urgent Implementation plan stage and Gdb and Kac should be in charge of both loading and unloading to deal with Pasoso and TCT III individually.

9. On the other hand, Gdb St. can only handle a maximum of five trains (one way) at peak time (four trains on average), because the present container yard space at Gdb St. can be enlarged only a little bit more, and three stacks have already occurred below the crane at a maximum of four trains operation stage.

Furthermore, for Kac St. to handle these remained five trains (one way) at peak time, it must install three storage sidings and one lead track, which will require land acquisition on the Gdb St. side and expensive earth works for a hill full of houses. In addition, tractive locomotives must be exchanged, which will disturb the grade crossing on the Bd side and increase the closing time of the gate. (Fig. 2 -1(2))

In conclusion, PERUMKA will continue the separate loading and unloading system on and after 2004.




Fig. 32 Main Improvements for Container Transportation

2. CONSTRUCTION PLAN

1. The Urgent Implementation Plan is for the first half of the period that the F/S covers and is to resolve existing bottlenecks.

Improvements in the second half of the period are executed step by step in accordance with annual traffic demand increases.

2.1 Layout of Required Facilities at Each Station

2. The premises for track layout are as follows.

a. Whenever TCT III is set up by 2000 and has a traffic demand corresponding to the year 2003, Tg. Priok Port will become a mother port, after being used as a feeder port for a while.

b. The establishment of TCT III will result in an increase in the number of trains, so Kac St. will handle unloading only and Gdb will handle loading only in the future.

c. The transportation route is kept as it is for a while, in spite of the above, and shunting work is conducted by a shunting locomotive at Tpk St. and as well by a shunting locomotive at Gdb and Pasoso stations.

Bandung Depot is used for daily inspection and fuelling.

d. Transportation facilities between Ckp and Bd will be improved by another project. The influence of the installation of a new dry port along the transportation route is taken into consideration in this F/S.

(1) Gedebage St. (Fig. 33, Fig. 36)

a. Four arrival and departure tracks are added on the Kac side, and the existing arrival and departure track (3#) is converted to the track to turn back tractive locos and to provide passage for wagon formations. The lead track L1 is extended for easy shunting.

The installation of arrival and departure tracks is executed at the same time as doubling track.

An additional office is built in accordance with increased demand.

b. Eight trains are operated and the max. storage for wagon formations is six during 2004~2006.

The maximum number of trains that can be handled is estimated at ten round trips (nine on average), considering both container yard space and the storage capacity of the

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

track layout.

(2) Kiaracondong St. (Fig. 34, Fig. 36)

3. To accept all imported containers, the following work is to be executed by 2003.

a. One arrival and departure track is added to accommodate more trains in 2004.

Accordingly, one gantry crane that can span two tracks is installed.

b. The existing fence securing the bonded area is moved 4 m further out from the container yard.

c. Storage and delivery at the container yard has to be conducted smoothly.

The layout of the container yard is planned to accommodate the daily arrival of ten trains a day, taking into consideration of container volume, delivery storage, and the working areas for the vehicles and handling machines.

d. Heavily paved surfaces are used when handling all imported containers.

4. The approach problem for the grade crossing will be alleviated by adopting the following countermeasures.

a. A system that separates entering and exiting independently will be used, and a waiting place for quick shunting of trailers is established.

b. As stated in Urgent Implementation Plan (Vol. 2 Item 8.1.4.1), the existing dead head handling side track (9#) is converted to a sub-main track with through type.

This can eliminate wasteful shunting of container wagons that disturb traffic flow near the grade crossing.

(3) Tg. Priok Port (Fig. 35)

The purpose of the container transfer yard at TCT III is the loading and unloading with top lifters as well as at Pasoso. Destination classification is all conducted at the port's marshalling yard.

The max. number of wagon formations that can be stored in the F/S is six, because eight trains (single direction) at peak time will be operated during 2004 - 2006. (Refer to Table 53).

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

a. TCT III transfer yard

5. A loading and unloading track (1#), a storage track (2#), a locomotive run-round track (3#) and a lead track (L1#) are installed in TCT III, respectively.

The track layout is sufficient for a shunting loco. to shunt at the entrance of the loading and unloading track, which will permit the loco. to avoid traffic congestion on the street. The track space denoted by the dotted line is secured in case either there is an increase in the number of trains or a new container yard between Ckp and Bd is realized in the future.

6. Concerning TCT III transfer yard construction, the cost allocation is expected as follows.

i) Land acquisition

The Port Authorities will secure all the necessary land, including land for the approach track for the extension to TCT III.

ii) Construction

* PERUMKA will bear the cost for track extension work, including the new grade crossing.

* The Port Authorities will bear the construction costs of the TCT III platform and its relevant facilities.

iii) Operation

Additional shunting and depreciation costs are to be recouped via user tariffs or fares.

b. Pasoso (Fig. 35)




A storage track and a locomotive run-round track are installed taking the New Bekasi Line into consideration.

This storage track will convert to an arrival and departure track after the New Bekasi Line is laid. This situation will bring no use of the storage tracks at Tpk St., because the operation between Tpk and Pasoso changes unnecessary.

c. Train storage capacity

Storage tracks capable of handling a max. of six wagon formations for eight train operations during 2004 - 2006, as well as seven wagon formations for ten train operation during 2009 - 2010, are sufficient as below.

| | |
|---------|--------------------|
| Pasoso | 6 wagon formations |
| TCT III | 2 ditto |



(Section A-A)

Fig. 33 Track Layout at Cedebage




Fig. 34 Layout of Facilities at Kac




Fig. 35 Network around Tg. Priok (Pasoso)




Fig. 36 The change of track layout at each step

Table 53 Handling Capacity at Container Stations (at peak time)

| Item | Present | Urgent Impl. Plan | | 2004 ~2006 | 2007 ~2010 | After 2011 |
|---------------------------|------------|---|--|--|--|--|
| | | 1997 | 1998~2003 | | | |
| Round-trip | 4 | 5 | 6 - 7 | 8 | 9 - 10 | |
| Gdb | A | 4 | 7 | 7 | 10 | 10 |
| | FH | Max. storage of 4 (1 formation stays on main track) | <ul style="list-style-type: none"> Increase of storage track. staying : 4 | <ul style="list-style-type: none"> Separate unloading of arriving empty containers. (1998) staying : 5 | <ul style="list-style-type: none"> Increase no. of arrival and departure track. Separate unloading of arriving full containers. (2004) staying : 6 | staying : 7 |
| Kac | FH | | | <ul style="list-style-type: none"> Convert a siding to a arrival and departure track. Start unloading of arriving empty containers. (1998) staying : 1 | <ul style="list-style-type: none"> Increase No. of arrival and departure track. Install a Gantry crane. Start unloading arriving all containers. (2004) staying : 2 | staying : 2 |
| New C.T | A | | | | | 2 |
| Tpk & Pasoso | A | 7 | 7 | 7 | 11 | 11 |
| | FH | staying 4 | staying : 4 | staying : 5 | <ul style="list-style-type: none"> Increase no. of arrival and departure track at Pasoso. (2004) TCT III open staying : 6 | staying : 7 |
| synthetic judgment | 4 | 5 | 7 | 10 | 10 | |
| facilities capacity /year | 71,500TEUs | 87,000TEUs | 145,900TEUs | 220,400TEUs | 220,400TEUs | <ul style="list-style-type: none"> New Bekasi Line opens. TCT III improved |

Notes : 1. A ; Possible no. of train round-trips.
 2. FH ; Improved facilities and max staying.
 3. Transportation ability ; 34TEUs/train.

(4) Relationship between facility capacity and transportation capacity.

7. The relationship between the necessary annual supply of trains (based on the demand forecast) and investment in facilities is summarized based on the above items. The results of it are as shown in Table 53, where the max. number of wagon formations to be stored is calculated by interpolating the existing train diagram in order to justify the above-mentioned plan.

2.2 Doubling of Track plan

(1) It is about 5.2 km from Kac to Gdb on the double track section. (Fig. 37)
Track alignment between both stations is on an embankment (L = 3.9 km H = 0.5~1.5 m) and is situated in a paddy field zone and forms a straight line.
There are hardly any houses, except near Kac. St along the line.
As for structures, there are seven bridges with a span of 3 m or more, and two level crossings whose width and traffic volume are also small.
The main road (near mile marker 164 km 325 m) crosses the line and is a fly over, so new track can pass through the north side of the span.

8. Doubled track is extended from the existing lead track at Gdb, but executed on the north side parallel with existing track on the intermediate section.
Land acquisition is not necessary because the land has already been secured.
Private houses (about 230) are crowded on the north side near Kac St. and will prevent the doubling of track.
However, the used land is owned by PERUMKA, and is leased to the inhabitants.
Therefore, it is necessary to compensate for the relocation of private houses.
As for embankment soil material, borrow material is used and there is no need to take special measures to strengthen subgrade because of the embankment's low height. (Fig. 38)

Main road (JL.SOEKARNO-HATTA) is flied over with the width B = 12.15 m to make double track possible by using the north of existing line.

(2) Generally speaking, there are two ways to increase track capacity on a single track section: doubling of track or automatic signalling.
The team gives priority to automatic signalling in the Urgent Implementation Program for the following reasons.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

- a. The lower cost estimates for automatic signalling (12 billion RP) compared with doubling of track(19 Billion RP).
- b. The necessary execution period for automatic signalling is shorter.
- c. The timeliness of automatic signalling, which needs foreign currency for investment.
- d. Modernization

However, PERUMKA prefers doubling of track for various reasons.
 Therefore, both plans are kept in the F/S in parallel hereafter.

(3) The team considers the completion time of the doubling of track as follows.

- a. In the case of automatic signalling preceding
 According to Table 54, the number of trains using the Kac-Gdb section already exceeds the track capacity of 81, automatic signalling in 1997 will make possible to drive 117 trains for both directions. On the other hand, even increases in container trains only will come relatively close to reaching this new upper limit in track capacity by 2009.

Table 54 No. of trains by year (includes sent-on locos)

| | at present | 2003 | 2009 | Remarks |
|----------------|------------|----------|-----------|---------|
| Container | 20 (5*4) | 28 (7*4) | 40 (10*4) | * |
| others | 69 | 69 | 69 | |
| Total | 89 | 97 | 109 | ** |
| Track capacity | 81 | 117 | 117 | |

* () shows sent-on loco again

** Includes irregular train runs

Accordingly, even if the increasing rate of passenger trains is unknown, it is necessary to complete the doubling of track by 2008 at the latest.

- b. In the case of doubling of track preceding
 Track capacity in the case of the doubling of track having an existing mechanical blocking system will be 200 trains both ways even if the one-block one-intersection system is used.




Fig. 37 Layout of Double Track




Fig. 38 Profile of Embankment (A)

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

The team can say that additional automatic signalling is not needed during the project life as long as the argument is limited to the intermediate section.

However, an increase in container trains requires arrival and departure track at Gdb St. and the installation of mechanical interlocking apparatus. This results in the complex situation of there being two mechanical signal cabins at Gdb St, and adversely affects safety.

So electronic interlocking should be completed at the same time when arrival and departure tracks are installed (completed in 2003).

9. Doubling of track will be completed in 1998 on the basis of construction schedule to be implemented from now.

Therefore, the situation where track capacity is exceeded will continue one year longer than automatic signalling preceding.

2.3 Necessary Rolling Stock and Car Depot Improvement

(1) Necessary rolling stock

The required number of trains per day (one way) in the peak period estimated by the rolling stock operation plan up to 2010 are as follows. (Refer to Table-52).

| | | | |
|------------|----------|-----------|-------------------------|
| At present | (1994) : | 5 trains | (Present train diagram) |
| | 1998 : | 6 trains | |
| | 2001 : | 7 trains | |
| | 2004 : | 8 trains | |
| | 2007 : | 9 trains | |
| | 2009 : | 10 trains | |

10. After considering the mean daily locomotive running distance, the number of required rolling stock is estimated (including auxiliary locomotives between Gab and Pwk).

In addition, spare rolling stock for inspection, repair requirements and standby are estimated as 15% of the total operating rolling stock.

Required locos are shown in Table 55.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

Table 55 Required Number of Locomotives

| | At present | | | | | | Total |
|---|------------|------|------|------|------|------|-------|
| | (1994) | 1998 | 2001 | 2004 | 2007 | 2009 | |
| No. of running trains per day in peak period | 5 | 6 | 7 | 8 | 9 | 10 | - |
| Necessary no. running loco. in peak period | 7 | 8 | 9 | 10 | 11 | 13 | - |
| Auxiliary loco. | 4 | 4 | 5 | 6 | 7 | 7 | - |
| Subtotal | 11 | 12 | 14 | 16 | 18 | 20 | - |
| Numbers of Loco. to be increased | - | 1 | 1 | 2 | 1 | 2 | 7 |
| For spares | - | 1 | - | - | - | - | 1 |
| New loco. to be purchased | - | (2) | (1) | 2 | 1 | 2 | 8 |

Note : () for Urgent Implementation Plan.

11. The above table shows that eight new locomotives (including 3 locos) for the Urgent Implementation Plan are to be purchased by 2009. The number of required wagons is shown in Table 56. At present, there are 190 wagons.

Table 56 Required Number of Wagons

| | At present | | | | | | Total |
|---|------------|------|------|------|------|------|-------|
| | (1994) | 1998 | 2001 | 2004 | 2007 | 2009 | |
| No. of running trains per day in peak period | 5 | 6 | 7 | 8 | 9 | 10 | - |
| Required numbers (units) | 7 | 8 | 9 | 10 | 11 | 13 | - |
| (numbers) | 119 | 136 | 153 | 170 | 187 | 221 | - |
| Necessary no. of wagons (including spare wagons) | | | | 196 | 215 | 254 | |
| Total numbers to be purchased (including spare wagons) | | | | 17 | 17 | 34 | 68 |

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

The above table shows that the required number of wagons is 68.
As for the type of wagons, PKPKW type is recommendable.

(2) Bandung Car Depot

All locomotives used for container trains belong to the Bandung Car Depot.
The depot is in charge of 48 locomotives at present : 34 tractive locos and 14 shunting locos.
Maintenance facilities were improved in 1992, so the capacity for intermediate inspections and repairs is more than 90% capable.
There is no problem for an increase of eight locos as shown in Table 55.

2.4 Environmental Impact Study

(1) An environmental assessment of the railway is conducted at three places : Gedebage including the doubled track section, Kiaradong, and the approach to TCT III. The evaluation of those three places is below the standard levels in the ANDAL STUDY.

The team has only to submit the study results for each place to the AMDAL Committee.

(2) The team conducted the required site survey in accordance with Indonesian environmental regulations. The survey is composed of three parts : physical-chemical, biological and social environment. The method of the environmental assessment is as follows. Based on the above-mentioned site survey existing data, and Indonesian environmental regulations, the team makes an examination, whenever an extraordinary value is found, check the range, and the draw up necessary countermeasures if the value can be attributed to construction or the completion of construction at a site.

(3) The results and countermeasures are as follows.

Impact level A : Heavy impact is supposed C : Uncertain

B : A little impact is supposed D : Impact is negligible

a. Gedebage Dry Port and Doubled track area

i) During construction

Physical-chemical environment

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

| Items | Influence on environment | Level | countermeasure |
|---------------|---|-------|---------------------------|
| Air | Increase of dust caused by construction | D | Check method of execution |
| Water quality | Water pollution caused by bridge work | D | Check method of execution |

Biological environment

| | | | |
|----------------------|--|---|---------------------------|
| Aquatic living thing | Water pollution. Increase plankton. | D | Check method of execution |
|----------------------|--|---|---------------------------|

ii) After construction

Physical-chemical environment

| | | | |
|-----------|---------------------------------|---|--|
| Noise | Arrival and departure of trains | D | Low level, no need for countermeasures |
| Vibration | Ditto | D | Ditto |

b. Kiaracandong

i) Prior to construction

Social environment

| Items | Influence on environment | Level | Countermeasure |
|------------------------|---|-------|---|
| Removal of inhabitants | Land compensation for doubling of track | B | Environmental countermeasure for surrounding area |

ii) During construction

Construction is executed in the container yard, so the influence on the environment is negligible.

iii) After construction

Social environment

| | | | |
|---------|--|---|-------------------------------------|
| Traffic | Traffic congestion near the grade crossing | B | Check entrance and exit at the yard |
|---------|--|---|-------------------------------------|

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

c. Approach to TCT III

i) Prior to construction

Social environment

| | | | |
|------------------------|--|---|--|
| Removal of inhabitants | Land acquisition for approaching track | B | Environmental countermeasures for surrounding area |
|------------------------|--|---|--|

ii) After construction

Physical-chemical environment

| | | | |
|-----------|-----------------|---|--------------------------------|
| Noise | Sent for trains | C | Decrease of Rail joint. |
| Vibration | ditto | C | Wide side path along the track |

Details of the survey result are contained in Appendix 3-1(Vol.4).

3. OPERATION AND MANAGEMENT PLAN

3.1 Basic Idea

(1) The team makes an examination from the viewpoint that Gdb and Kac are a single unified dry port and that the handling facilities at Gdb are located partially at Kac.

(2) The sub-office is placed at the container depot, and handles only unloading and delivers containers to customers.

(3) Accordingly, regular telecommunications devices (such as telephones and facsimiles) are sufficient if only equipped.

(4) The main office gives operational orders about container handling to the sub-office using a facsimile, etc.

The sub-office then submits a finished report on the handling to the main office via facsimile, after finishing a series of the procedures.

(5) For the above activities, the cooperation of the same forwarders is necessary at both stations.

(6) Facilities, equipment, and work allocation are as follows as well as Gedebage Dry Port.

The trailer head and chassis for the movement of containers to CFS are owned by PERUMKA.

Those for delivery to customers are owned by the forwarders.

| (Machine) | (Owner) | (Operation) | (Maintenance) |
|--------------|---------|-----------------|-----------------|
| Gantry crane | PERUMKA | private company | Private company |
| Top lifter | PERUMKA | PERUMKA | PERUMKA |
| Forklift | PERUMKA | PERUMKA | PERUMKA |

3.2 Daily Revenue and Expenses

(1) Daily railway revenue from containers consists of tariff and handling charge at Gdb St.

Table-57 shows the tariff and handling charge at the dry ports.

(2) Daily expenses consist of variable costs concerning trains, their fixed costs and container handling costs at Gdb St. The cost estimate is based on the operation cost table per train submitted by PERUMKA referring to hearing on sites and other submitted data, and is arranged as a daily expense table per round trip train (Table 58).

The handling charge paid by customers is shared with the contractor of the gantry crane handling payment according to the following rule.

| | | | |
|--------------------------|------------|---|---------|
| | Contractor | : | PERUMKA |
| Until 2000 TEU/month | 45 | : | 55 |
| More than 2000 TEU/month | 40 | : | 60 |

The above revenue of PERUMKA should be paved for the handling work under the direct management of PERUMKA, but the work cost is already appropriated in the item named stations and yards of Table 58.

Table 57 Container and Handling Charge between Gdb and Tg. Priok

(Rp.) 11. Nov. 1994

(Lift off/on : include tax 10%)

| Item | Gedebage and Pasoso | | | | | | Gedebage and UTPK Tg. Priok | | | | | | | |
|----------------------|---------------------|---------|---------|---------|---------|---------|-----------------------------|---------|---------------|-------------|---------|---------------|---------|---------|
| | 20feet | | | 40feet | | | 20feet | | | 40feet | | | | |
| | Loaded | | Empty | Loaded | | Empty | UTPK-I + II | | Oermaga - 207 | UTPK-I + II | | Oermaga - 207 | | |
| | Full | Stuffed | | Full | Stuffed | | Full | Stuffed | Full | Stuffed | Full | Stuffed | | |
| Lift off | 17,500 | 9,700 | 0 | 25,700 | 15,000 | 0 | 17,500 | 9,700 | 17,500 | 9,700 | 25,700 | 15,000 | 25,700 | 15,000 |
| Lift on | 17,500 | 17,500 | 9,700 | 25,700 | 25,700 | 15,000 | 17,500 | 17,500 | 17,500 | 17,500 | 25,700 | 25,700 | 25,700 | 25,700 |
| Stacking | 4,000 | 4,000 | 1,750 | 7,750 | 7,750 | 3,500 | 4,000 | 4,000 | 4,000 | 4,000 | 7,750 | 7,750 | 7,750 | 7,750 |
| Stuffing | 0 | 27,500 | 0 | 0 | 41,050 | 0 | 0 | 27,500 | 0 | 27,500 | 0 | 41,050 | 0 | 41,050 |
| Revenue at Gdb | 39,000 | 58,700 | 11,450 | 59,150 | 89,500 | 18,500 | 39,000 | 58,700 | 49,000 | 58,700 | 59,150 | 89,500 | 59,150 | 89,500 |
| Tariff | 124,000 | 124,000 | 80,650 | 223,599 | 223,500 | 145,750 | 124,000 | 124,000 | 124,000 | 124,000 | 223,500 | 223,500 | 223,500 | 223,500 |
| Security | 8,000 | 8,000 | 0 | 8,000 | 8,000 | 0 | 8,000 | 8,000 | 8,000 | 8,000 | 8,000 | 8,000 | 8,000 | 8,000 |
| Total | 182,000 | 132,000 | 80,650 | 281,500 | 231,500 | 145,750 | 132,000 | 132,000 | 132,000 | 132,000 | 231,500 | 231,500 | 231,500 | 231,500 |
| Lift off | 21,000 | 21,000 | 10,500 | 31,500 | 31,500 | 16,000 | 21,000 | 21,000 | 21,000 | 21,000 | 31,500 | 31,500 | 31,500 | 31,500 |
| Lift on | 21,000 | 21,000 | 10,500 | 31,500 | 31,500 | 16,000 | 21,000 | 21,000 | 21,000 | 21,000 | 31,500 | 31,500 | 31,500 | 31,500 |
| Stacking | 5,000 | 5,000 | 2,500 | 10,000 | 10,000 | 5,000 | 5,000 | 5,000 | 5,000 | 5,000 | 10,000 | 10,000 | 10,000 | 10,000 |
| Revenue at Pasoso | 47,000 | 47,000 | 23,500 | 73,000 | 73,000 | 37,000 | 47,000 | 47,000 | 47,000 | 47,000 | 73,000 | 73,000 | 73,000 | 73,000 |
| Truck forwardly | 0 | 0 | 0 | 0 | 0 | 0 | 32,500 | 32,500 | 0 | 0 | 52,500 | 52,500 | 0 | 0 |
| Railway forwardly | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 32,500 | 32,500 | 0 | 0 | 52,500 | 52,500 |
| Lift off/on | 0 | 0 | 0 | 0 | 0 | 0 | 21,000 | 21,000 | 21,000 | 21,000 | 31,500 | 31,500 | 31,500 | 31,500 |
| Imp. and Exp. issue | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Revenue at Tg. Priok | 0 | 0 | 0 | 0 | 0 | 0 | 53,500 | 53,500 | 21,000 | 21,000 | 84,000 | 84,000 | 31,500 | 31,500 |
| Port authorities | 47,000 | 47,000 | 23,500 | 73,000 | 73,000 | 37,000 | 100,500 | 100,500 | 68,000 | 68,000 | 157,000 | 157,000 | 104,500 | 104,500 |
| PERUKA | 171,000 | 190,700 | 92,100 | 290,650 | 321,000 | 164,250 | 171,000 | 190,700 | 203,500 | 223,200 | 290,650 | 321,000 | 343,150 | 373,500 |
| Tariff all in | 218,000 | 237,700 | 115,600 | 363,650 | 394,000 | 201,250 | 271,500 | 291,200 | 271,500 | 291,200 | 447,650 | 478,000 | 447,650 | 478,000 |

Table 58 Expense per Container Train

(Unit : Rp.)

| Items of expenditure | | From Gdb to Pasoso per train A | From Psoso to Gdb per train B | One-round trip per train A + B = C | Notes |
|---------------------------------------|-----------|---|--|---|--|
| Variable expenses | | | | | |
| Maintenance of Loc. | | 757,356 | 757,356 | 1,514,712 | Gdb-Pwk;2 CC201 Pwk-Tpk;1 CC201 |
| Maintenance of wagon | | 483,312 | 483,312 | 966,624 | 17wagon/train |
| Station and yard | | 104,831 | 104,831 | 209,662 | |
| Maintenance track | | 171,451 | 130,507 | 301,958 | |
| Rehabilitation for derailment | | 5,191 | 5,191 | 10,382 | |
| Subtotal | A | 1,522,141 | 1,481,197 | 3,003,338 | |
| Personnel expenses | B | 77,568 | 78,821 | 156,389 | Driver, co-driver, conductor, army |
| Fuel | C | 420,117 | 327,967 | 748,084 | |
| Total Variable expenses A + B + C = D | | 2,019,826 | 1,887,985 | 3,907,811 | |
| Fixed expenses | E | 1,114,829 | 1,067,626 | 2,182,455 | Not include compensation and interest |
| Total expenses | D + E = F | 3,134,655 | 2,955,621 | 6,090,266 | |

Notes : 1. Locomotive between Gdb and Pwk means 2 CC 201
" " Pwk and Tpk means 1 CC 201

2. PERUMKA crew between Gdb and Pwk consists of 2 drivers, 2 co-drivers, 1 conductor.
" " between Pwk and Tpk consists of 1 driver, 1 co-driver, 1 conductor.

3. Security between Gdb and Tpk consists of 2 Army soldiers (non PERUMKA personnel)

4. Include, personnel expenses and non-personnel expenses.

4. INVESTMENT COST ESTIMATE AND CONSTRUCTION SCHEDULE

4.1 Necessary Investment Amount

The premises of the cost estimate and investment unit cost of the F/S is the same as the Urgent Implementation Program (Vol.2, Chapter 8).

The investment amount till 2003 which is the term of the F/S and that of the project life term are shown in Table 59.

(1) In the case of Automatic signalling preceding

The necessary total construction cost of the project life term is 120.4 billion Rp (73.7 billion Rp as foreign currency).

Meanwhile, that of the term of the F/S, i.e., till 2003, is 62.5 billion Rp (43.1 billion Rp as foreign currency).

(2) In the case of Doubling of track preceding

The necessary total construction cost of the project life term is 119.5 billion Rp (72.5 billion Rp as foreign currency).

Meanwhile, that of the term of the F/S, i.e., till 2003, is 83.3 billion Rp (55.7 billion Rp as foreign currency).

Accordingly, the construction cost till 2003 is cheaper in the case of Automatic signalling preceding than Doubling of track preceding.

4.2 Construction Schedule

The necessary completion time of each construction item, based on Chapter one to three, is as shown in Table 60.

Furthermore, the team considers the case of a 10% decrease in transportation as sensitivity analysis in both economic and financial analysis, owing to the construction of an expressway expected to finish in 1997.

This means a two-year delay in the forecasts in and after 1998 in Table 52, so completion time may be delayed by two years in Table 60.

Table 59 Required Investment Amount

(1) In the Case of Automatic Signalling Preceding

Unit : Billion Rp

| Investment Stage | Until 2003 | | | Later than 2003 | | | Grand Total | | |
|--|-------------|-----------|-------------|-----------------|-------------|-------------|--------------|-------------|-------------|
| | Total | F/C | D/C | Total | F/C | D/C | Total | F/C | D/C |
| Construction Items | | | | | | | | | |
| a. Doubling of Track | | | | | | | | | |
| Compensation | 0 | 0 | 0 | 5.3 | 0 | 5.3 | 5.3 | 0 | 5.3 |
| Civil works and buildings | 0 | 0 | 0 | 7.4 | 5.7 | 1.7 | 7.4 | 5.7 | 1.7 |
| Track | 0 | 0 | 0 | 4.9 | 4.3 | 0.6 | 4.9 | 4.3 | 0.6 |
| b. Yard improvement | | | | | | | | | |
| Land acquisition and compensation | 4.3 | 0 | 4.3 | 0 | 0 | 0 | 4.3 | 0 | 4.3 |
| Civil works and buildings | 8.7 | 5.4 | 3.3 | 0 | 0 | 0 | 8.7 | 5.4 | 3.3 |
| Tracks | 17.7 | 15.1 | 2.6 | 0 | 0 | 0 | 17.7 | 15.1 | 2.6 |
| c. Signalling and Telecommunication | | | | | | | | | |
| Automatic signalling including electronic interlocking apparatus | 11.3 | 10 | 1.3 | 0 | 0 | 0 | 11.3 | 10 | 1.3 |
| Yard Facilities | 4.8 | 4.3 | 0.5 | 2 | 1.7 | 0.3 | 6.8 | 6 | 0.8 |
| d. Machines | | | | | | | | | |
| Rolling stock | 9.8 | 4.9 | 4.9 | 25.8 | 8.1 | 17.7 | 35.6 | 13 | 22.6 |
| Handling machines | 0.3 | 0.3 | 0 | 7.2 | 7.2 | 0 | 7.5 | 7.5 | 0 |
| e. Management | 5.6 | 4 | 1.6 | 5.3 | 2.7 | 2.6 | 10.9 | 6.7 | 4.2 |
| Grand Total | 62.5 | 44 | 18.5 | 57.9 | 29.7 | 28.2 | 120.4 | 73.7 | 46.7 |

(2) In the Case of Doubling of Track Preceding

| Investment Stage | Until 2003 | | | Later than 2003 | | | Grand Total | | |
|--|-------------|-------------|-------------|-----------------|-------------|-------------|-------------|-------------|-----------|
| | Total | F/C | D/C | Total | F/C | D/C | Total | F/C | D/C |
| Construction Items | | | | | | | | | |
| a. Doubling of Track | | | | | | | | | |
| Compensation | 5.3 | 0 | 5.3 | 0 | 0 | 0 | 5.3 | 0 | 5.3 |
| Civil works and buildings | 7.4 | 5.7 | 1.7 | 0 | 0 | 0 | 7.4 | 5.7 | 1.7 |
| Tracks | 4.9 | 4.3 | 0.6 | 0 | 0 | 0 | 4.9 | 4.3 | 0.6 |
| b. Yard Improvement | | | | | | | | | |
| Land acquisition and compensation | 4.3 | 0 | 4.3 | 0 | 0 | 0 | 4.3 | 0 | 4.3 |
| Civil works and buildings | 8.7 | 5.4 | 3.3 | 0 | 0 | 0 | 8.7 | 5.4 | 3.3 |
| Tracks | 17.7 | 15.1 | 2.6 | 0 | 0 | 0 | 17.7 | 15.1 | 2.6 |
| c. Signalling and Telecommunication | | | | | | | | | |
| Mechanical equipment required by doubling of track | 1 | 0.6 | 0.4 | 0 | 0 | 0 | 1 | 0.6 | 0.4 |
| Automatic signalling including electronic interlocking apparatus | 16.3 | 14.3 | 2 | 0 | 0 | 0 | 16.3 | 14.3 | 2 |
| d. Machines | | | | | | | | | |
| Rolling stock | 9.8 | 4.9 | 4.9 | 25.8 | 8.1 | 17.7 | 35.6 | 13 | 22.6 |
| Handling machines | 0.3 | 0.3 | 0 | 7.2 | 7.2 | 0 | 7.5 | 7.5 | 0 |
| e. Management | 7.6 | 5.1 | 2.5 | 3.2 | 1.5 | 1.7 | 10.8 | 6.6 | 4.2 |
| Grand Total | 83.3 | 55.7 | 27.6 | 36.2 | 16.8 | 19.4 | 120 | 72.5 | 47 |

*Notes : The items in c and d are different from the other items in that they can be made accurate relatively so physical contingencies were not considered.

*F/C shows foreign currency.

*D/C shows domestic currency.

Table 60 Required Completion Times for Facilities

| Stage | Present | Urgent | F/S | M/P | Reference |
|------------------------|---------|--|--|--|---|
| Operation round trip | 4 | 5 | 8 | 9 ~ 10 | |
| Gedebage | | 2 storage tracks Pavement 2920 m ² 1996 | 4 sub-main tracks 2003 Electronic interlocking 2003 | | () ← . → () When doubling of track preceding as first alternative |
| Kiaracondong | | 1 sub-main tracking 1997 Electronic interlocking 1997 | Increase of a sub-main track 2003 Pavement 23350m ² CFS 700m ² 2003 Electronic interlocking 2003 | | |
| Tanjung Priok & Pasoso | | | 2 storage tracks 2003 | | Sub-main tracking (1) will be necessary for Bekasi New Line after 2010. |
| New C.T | | | Platform 7200 m ² 2003 | | Additional storage tracks (2) will be necessary for TCT III after 2010. |
| Doubling of track | | (1998) ← | 3935 m | 2008 | |
| Rolling stock | | Loco : 2 1997 | Loco : 2 2004 Wagon : 17 2004 | Loco : 1 2007 Wagon : 17 2007 | Loco : 2 2009 Wagon : 34 2009 |
| Operational year | 1997 | ←2003 | ←2006 | ←2010 | |

5. ECONOMIC ANALYSIS AND FINANCIAL ANALYSIS

5.1 Economic Analysis

(1) Premises

To carry out an economic analysis, the WITH / WITHOUT project cases are taken up using the demand forecast in Table 50.

- a. WITH case : Investment is executed based on the F/S
WITHOUT case : Investment is not executed based on the F/S, and transportation volume more than 71,500 TEUs moves to highway.
- b. The project life is thirty years (1995 to 2024).
- c. The economic analysis is executed on the following two cases.
 - i) When automatic signalling precedes.
 - ii) When doubling of track precedes.
- d. Sensitive analysis is conducted for the above cases for a 10% decrease in transportation volume and a 10% increase in investment.
- e. Economic analysis is done under the assumption that the project costs concerning automatic signalling and doubling of track will be allocated in proportion to the ratio of container trains versus the number of other trains at present (20 / 69). (See Table 54).

(2) Results of analysis

The EIRR is calculated on the basis of the premises mentioned above, and is summarized in Table 61. The lowest EIRR is 17.2%.

Note, that calculations are only based on countable measures, so we can expect more indirect merit.

According to the analysis, the EIRR in the case of doubling of track preceding is the highest. It is said that the opportunity cost of capital in Indonesia is 10 to 15%. All the cases are economically feasible for executing the project.

Table 61 Results of Sensitivity Analyses EIRR (%)

| Case | CASE-1 | CASE-2 |
|-----------|--------|--------|
| Base Case | 29.66 | 32.33 |
| Case A | 23.18 | 24.91 |
| Case B | 22.56 | 24.21 |
| Case C | 17.22 | 18.36 |

Case A : Increase in construction cost by 10%

Case B : Decrease in forecasted benefits by 10%

Case C : Increase in construction cost by 10% and decrease in benefits by 10%

CASE-1 : When automatic signalling precedes

CASE-2 : When doubling of track precedes

5.2 Financial Analysis

(1) Premises

a. The financial analysis is carried out from the stand point of PERUMKA being the executing entity of the project.

All investment costs for the dry ports and connecting railway are to be borne by PERUMKA initially.

b. The project life is thirty years (1995 to 2024).

c. As for the dry ports and connecting railway, the financial analysis is to be made only for the portion under the control of PERUMKA.

d. The financial analysis will only cover increases in container freight transportation revenues brought about by the execution of the project.

In this case, the project cost concerning automatic signalling and doubling of track should be allocated in proportion to the ratio of the number of container trains versus other trains at present (20 : 69). (See Table 54).

e. The financial analysis is executed for the following two cases.

i) When automatic signalling precedes.

ii) When doubling of track precedes.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

f. Sensitivity analysis is conducted for the above cases and for both a 10% decrease in transportation volume and a 10% increase in investment.

Beside the team tries to confine construction to the Urgent Implementation Plan stage.

(2) Results of analysis

The FIRR is calculated on the basis of the cash flow gained from the premises mentioned above, and is summarized in **Table 62**.

According to this, the FIRR in the case when automatic signalling precedes, and investment is up till the Urgent Implementation Plan stage, is highest.

Although the FIRR of this project is not high, taking the present interest rate in Indonesia into account (e.g., the interest for a public corporation's borrowing from the Indonesian state bank is 13.5% p.a., the interest of the Indonesian private bank for a corporate or individual finance is 17%-22% p.a.), all the cases may become financially feasible for the executing entity of the project (PERUMKA), as long as PERUMKA can obtain soft loans, such as government to government borrowing for the foreign currency portion and government grants for the local currency portion.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

Table 62 Results of Sensitivity Analysis

| | F I R R (%) | | | |
|--------|---------------|------------------------|-------------------------|------------|
| | a) Base Case | b) Revenue 10% down | c) Investment 10% up | d) b) + c) |
| Case A | | | | |
| Case 1 | 5.1 | 3.9 | 4.0 | 3.0 |
| Case 2 | 5.4 | 4.2 | 4.3 | 3.2 |
| Case B | | | | |
| Case 1 | 10.9 | 9.6 | 9.7 | 8.5 |
| Case 2 | 10.8 | 9.5 | 9.7 | 8.4 |

Case A : Short-term Development Plan stage

Case B : Urgent Implementation Plan stage

Case 1 : When automatic signalling precedes.

Case 2 : When doubling of track precedes.

6. CONCLUSIONS AND RECOMMENDATIONS

6.1 Conclusions

(1) The decreases in container transportation after a raise in fares in resolving the existing facilities bottleneck, so the execution of the Urgent Implementation Plan has some leeway.

The team can say that the growing seeped in demand hereafter depends on the recovery of textile industry and new investment in other growth industries.

(2) The Urgent Implementation Plan was a facilities investment plan for a traffic demand forecast until 1999.

However, this F/S shows the plan is applicable even for demand until 2003.

The reason for this is that the former is based on another report assuming high economic growth and the latter is framed on the present economic situation.

(3) As a result of the economic analysis, it can be said that the opportunity cost of capital in Indonesia is 10 to 15%, which means the EIRR is feasible from the view point of the national economy.

(4) The result of the financial analysis proves the project is feasible in all cases corresponding to demand until 2010.

As the profitability of the basis plan (Case I), when doubling of track is carried out first is a little better than when automatic signalling is executed first, but the difference is so negligible that the investment order between them is irrelevant.

The team tried a sensitivity analysis when there is a 10% decrease in traffic demand, and found that the FIRR index is greater than the expected financed interest rate in any cases.

(5) Base on Table-61, successive investment for the existing dry ports later than 2003, makes the feasibility inferior but profitable.

Investment later than 2003 should be reviewed, by examining the demand in Bd District at the beginning of the 21 st century. The team can then select suitable places needing only low investment cost, such as the following:

- i) Eager sponsors (local government or private sector) are wanting investment.
- ii) Huge investment is not needed (such as doubling track)

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

- iii) No need for land acquisition
- iv) Utilization of existing facilities (tracks and signals)
- v) Auxiliary locomotives are not needed.

Pwk seems to be satisfied with the above conditions as long as the demand exists.

6.2 Recommendations

(1) Urgent implementation plan which is the front half of F/S, should be carried out as soon as possible, because both the storage capacity for container wagons at Gdb and track capacity between Gdb and Kac are in shortage even now. Concerning the rear half of F/S additional execution will be examined again at the head of 2000, whether it is necessary or not, by considering demand forecast at that time, because violent economic deviation is anticipated in near future.

Further more,

(2) Normalization of train operation and bringing up of forwarders

On the 2 nd site survey, some customers were doubtful of the railway, since its arrival time is inaccurate.

High economic development required accurate and quick service, as well as cost effectiveness, not only for the railway but for all means of transportation

In Japan, regular conventional freight trains were slow and unpunctual, which resulted in their falling into disuse.

Unpunctual trains will lose the trust of customers and they will go elsewhere.

Locomotive break down occupies near half of the cause of the delay.

The above is already known and Bd Depot has been also improved. The study and carrying out of the cause and checking system on spare parts supply, personnel training etc., under the decision that the break down should be exclude, is desirable.

However, it would be sure that the almost delay of arrival time caused by railway operation is less than 30 minutes.

The complaint by customers on the big delay seems to be caused in the shortage of equipment such as trailer head and chassis owned by forwarder.

The foster of resourceful forwarders is also desirable as one of the resolutions on the subject.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, SUMMARY: Part 3, FEASIBILITY STUDY

(3) Improvement of delivery capability

Due to transportation costs rising by 15%, the volume of containers handled in July of last year decreased by about 15% as well, and container stocks in container terminals greatly decreased.

It was said that the excessive container stocks were caused by customers accepting their goods, but waiting theory teaches us that the more likely causes is in shortage of distributive capability.

Therefore, it is necessary for forwarder to have sufficient distributive capability (trailer truck head, chassis, and working force) when transportation demand for containers revives. Otherwise, even if the storage capacity of the tracks is enough, it will reproduce huge excess of container stock once again.

(4) Co-operation between railway construction and urban planning

In relation with the above improvement, the New Transportation Line will be constructed, new urban railway has a large influence on urban development and urban structure, so it is necessary to coordinate railway construction planning with urban planning.

If a new line is constructed without such coordination, buildings would be built on the predetermined line before the start of the construction project, or land prices would rise remarkably. This would then force a reexamination of land utilization and the public facilities related to it.

The team therefore recommends holding discussions with relevant government and private organizations concerning these problems, and drawing up countermeasures such as simultaneous execution with urban development and land use regulations.

By the way, Bekasi new line is not only effective for commuter service between Jng and Bks, but it has various merits, so we expect the promotion for the earlier construction.

(5) Promotion of submergence countermeasure at Gdb District

The submergence problem is not only for Gdb St, but for all Gdb District.

The arrangement of relevant drainage facilities should be executed by the public works. The team expects the negotiation for the early execution between relevant governmental organizations.

APPENDIX 1

The Present Situation of Gedebage Dry Port and Connecting Railway

Appendix 1 The Present Situation of Gedebage Dry Port and Connecting Railway

(1) Gedebage Dry Port

a. Activity

Gedebage dry port is located in the suburbs of Bandung city with the population of 1.8 million people. It is 187 Km apart from South East of Tg. Priok Port. (App. Fig. 1 - 1) The transportation has started in 1987 for the sake of alleviation of highway transport and the annual increase has been remarkable as follows.

| year | annual transportation volume | daily actual no. of running trains |
|------|---------------------------------|---------------------------------------|
| 1987 | 2,595 TEUS | one train / single way |
| 1988 | 8,887 TEUS | ditto |
| 1990 | 23,065 TEUS | two train / single way |
| 1993 | 60,918 TEUS | three train / single way |

The contents are as follows, where empty containers are imported and goods to be exported are stuffed to them.

| | full | empty | |
|--------|------|-------|----------------------------------|
| import | 30% | 70% | : industrial materials, machines |
| export | 92% | 8% | : Textile goods, tea, shoes |

The main destination for export is japan.

Container size and the used ratio are as follows on Box substitute. (Result in 1993)

| | |
|--------------------|-----|
| 20 ft (8 * 8 * 20) | 61% |
| 40 ft (8 * 8 * 40) | 39% |

Average transportation weight of a full container is as follows.

| | 20 ft | 40 ft |
|--------|----------|-----------|
| export | 8 - 14 t | 18 - 24 t |
| import | 10 t | 22 - 30 t |

The share of Railway transportation in Bandung district occuppies about 80% in

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
 DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
 Vol.1, Part 3, APPENDIX 1

Bandung district, but it deserves of only 6% of containers handling volume in Tg. Priok Port.

b. Facilities at Gedebage dry port

i) general remarks

The track layout of Gedebage St. is shown as App. Fig. 1 - 2.

The outline of the facilities is as follows.

ii) Infrastructure

- * land area 3.5 ha (after spreading)
2.6 ha (at present)
- loading and unloading space for transtainer 3000 m², container yard 1.5 ha and 6000 m² under construction
- * loading and unloading side track 1 * 240 m
- * passing tracks 2 * 240 m
- * CFS for export and import 2 buildings
- * warehouse 20 m * 15 m * 5 m
- * wagon checking tracks 2
- * private siding track to oil terminal 1
(stopped the use at present)

iii) Equipment

- * Transtainer for 42 t 1
- * Toploader for 35 t 1
- * Forklift for 10 t 1
- * ditto for 2.5 t 4
- * ditto for 3.5 t 1
- * Hand pallet for 2.5 t 2
- * Head truck 2
- * Chassis 4

iv) Rolling stock

PERUMKA prepares 190 marine container wagons including spare ones as follows, for this route operation.

Two axle bogies with four wheels : PPCW 150 wagons

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, Part 3, APPENDIX 1

l = 13 m (1 * 40 ft or 2 * 20 ft use)

Three axle bogies with six wheels : PKPKW 40 wagons

l = 17.6 m (more than 30 t use)

Total : 190 wagons

Besides, one shunting locomotive is dispatched at Gdb all day long.

c. Management

This dry port is not one of the regular stations, but independent organization under PERUMKA Semarang Branch. It is the only real dry port in Indonesia, and arranges all functions necessary for a dry port.

The following bloc units are established in it for the export procedure.

The shipping procedure by customers can finish here.

Chief of dry port is the representative of all organization in this terminal as follows.

| | | | |
|---------|----|---|-----|
| PERUMKA | 25 | Others | 148 |
| | | * Port authority | 48 |
| | | Customs | 32 |
| | | * Quarantine | 3 |
| | | * BNI bank | 2 |
| | | Praghan Indonesia (Handling company) | 60 |
| | | Export inspector | 3 |
| | | * sign is in the PERUMKA office | |

Valid time for the reception for business document

7:30 - 14:00

Valid time for the carrying in containers

8:00 - 22:00

d. Outline of Kiaracandong

Kac St. is next to Gdb St. on Bandung direction, the track layout is shown as App.Fig.1-2. All the container trains for Gdb St.can stop here on the way where a dead end siding possible to unloading is located in the land space with about 2.6 ha parallel to the station.

THE STUDY ON THE MASTER PLAN OF CONTAINER CARGO HANDLING PORTS,
DRY PORTS AND CONNECTING RAILWAYS IN THE REPUBLIC OF INDONESIA
Vol.1, Part 3, APPENDIX 1

(2) Tanjung Priok St. and the belonging station.

The network around Tpk St. is shown as App. Fig. 1 - 3.

The Pasoso St. is located next to TCT Berth, the industrial railway track branched from Tpk St. reaches PERTAMINA oil base, where Pasoso St. is located intermediary one km apart from Tpk St.

a. Pasoso St.

The industrial railway track branched from Tpk St. where track is owned by PERUMKA and the other facilities are owned by the Port Authorities.

Seven of PERUMKA staff are working here for contact business with the port.

The track layout is shown as App. Fig. 1 - 4.

We can find three side tracks including locomotive run-around siding, PERTAMINA route which is in no use, is utilized as a lead track, and signals and safety facilities are not installed.

The length of present elevated platform was 300 m where two top-lifters were operating by Port side operators, it has finished extension works for securing 600 m after completion.

After that, two container wagon formations become possible to be handled at the same time, though the shunting is complicated a little.

The width is 49 m enough to handle containers with top lifters.

There is a warehouse (107 m * 40 m) seemed to be CFS on the platform but it seems to be little used.

b. Tanjung Priok

Tpk St. is a terminal, and the track layout is shown as App. Fig. 1 - 3.

There are two double track routes, one is for Jakarta kota, another is for Jatinegara. The former is not used now.

It is not enough used in spite of being a big station.

Sepur Labuhan route connects pasoso St. with Tpk St. Accordingly, a train going for Pasoso has to receive double switch back shunting at Tpk.

c. Operation

- i) Imported containers are carried to Pasoso by a yard truck one hour later after unloading from a ship. Exported ones are carried into marshalling yard in TCT, one or two hours before shipping at latest.
- ii) Shunting is conducted by a shunting locomotive, and the wagon formations waiting for departure are stored at Tpk St. or Pasoso St.
- iii) Arrival trains are admitted even on the locomotive run-around track used for shunting, owing to excess empty wagons.
- iv) The tractive locomotives successively arriving at Tpk St. from Gdb St. at midnight start from Tpk St, soon after exchanging wagon formation, at the same midnight. Therefore the staying time of the locomotives is not so long.

(3) Facilities of connecting railway

This route consists of both double track section and single track section; the former is Jabtabek Eastern Line (Tpk-Jng) that is one of the urban railways in Java island and the Northern Trunk Line (Jng-Ckp); the latter is Southern Trunk Line (Ckp-Gdb) Which has partial double track section (Pdl-Kac).

The track layout of the every station on this route is shown in App. Fig. 1 - 5.


In the Southern Trunk Line, the section between Cikampek and Padalarang (approximately 75km) is the single track line, with sharp-curved alignment (minimum $R=150m$) and steep gradient ($i=7.6-16.6/1000$) on the mountainous terrain, the effective length of main track is 300m in the Northern Trunk Line, but in the Southern Trunk Lines limited to 239m owing to the difficulty of extension.

The blocking system on this route is one block between every two adjacent stations, and every station is equipped with mechanical signal and interlocking.

The locomotive and coach depot is located in Bandung and Jatinegara, and the locomotives for container trains belong to Bandung depot.




App. Fig. 1-1 General Route Map between Pasoso and Gedeage




Kiaracandong

Gedebage


App. Fig. 1-2 Track Layout at present



App. Fig. 1-3 Network around Tg.Priok St. Map



App. Fig. 1-4 Track Layout at Pasoso



App. Fig. 1-5 Track Layout Between Pasoso and Gedebage

JICA