Table 4.7.1 Approximate Quantities of Major Items

Descriptions	Unit	Quantities
Cutting	cu. m	184,600
Filling	cu. m	75,700
Concrete	cu. m	14,500
Reinforcement Bar	tons	1,300
Gabions	cu. m	9,200
Stone Masonry	sq. m	6,900
Graveled Surface	sq. m	42,900
Penetration Macadam Surface	sq. m	9,800
Concrete Surface for Causeways	sq. m	10,200
Drainage Ditches	m	12,400

4.8 Maintenance Work

4.8.1 General

The scope of work to be carried out by HMG covers the maintenance with some improvements of existing roads, except the stretches under construction. The main work will be composed of:

- Removal of landslide deposits on the road.
- Removal of debris flow deposits on the causeways after being hand over.
- Removal of sediment materials in the drainage ditches and culverts.
- Regular maintenance of on- and off-road work.
- Repair of slope protection.
- Other maintenance works, as needed.

4.8.2 Scope of Maintenance Work and Work Quantities

Required road maintenance work will mostly be to remove earth and rock deposited on the road by landslides and at the causeways after being handed over. Also, the rehabilitation and repair of the road is to include reconstruction of worn structures, replacement of expansion joints on bridges and slope stabilization work. All of this is classified in terms of both manpower and mechanized maintenance work, discussed as follows:

A. Removal of Earth and Rock by Landslides

This work will consist of removing, loading, hauling and dumping of earth and rocks deposited on the road by landslides. This is expected to occur mostly between Kamara bridge and Sindhuli Bazar due to the existing conditions of topography. Required work volume is estimated based on currently available data as follows.

 $37.0 \text{ km times } 700 \text{ m}^3/\text{km/year} = 25,900 \text{ m}^3/\text{year}, \text{ say } 26,000 \text{ m}^3/\text{year}$

B. Removal of Sediment Materials at Causeways

This work will require the excavation, dozing, loading, hauling and dumping of the sediment materials at 17 causeway locations. The required work volume is estimated at 17,000 m³/year with the condition that the sediment volume is 250 m³/place and is to be carried out four times per year at each of the 17 causeways as shown below:

250 m³/place x 17 places x 4 times/year = $17,000 \text{ m}^3$ /year

C. Removal of Sediment Materials in the Drainage Ditches and Culverts

It is difficult to estimate the required work volume (quantitatively) for the drainage ditches and culverts; however, the amount and type of equipment to be provided to meet the needs for maintaining the 37.0 km of road length should be adequate to remove all sediment materials in the drainage ditches and culverts.

D. Regular Maintenance of On- & Off-Road Work

This work comprises: 1) replacement and compaction of gravel, 2) surface grading and 3) maintenance of road structures. The work to be performed is gathering and screening of gravel, hauling and dumping of gravel along the road's surface, spreading and compaction.

As noted above, it is difficult to estimate the required work volume quantitatively; however, the equipment to be provided to meet the needs for maintaining the 37.0 km of road length should be adequate to perform the required repair/rehabilitation work.

4.8.3 Selection of Maintenance Equipment

The required maintenance equipment is classified in accordance with the stipulated maintenance work mentioned above and is listed as follows:

- Earthmoving Equipment.
- Concrete Production Equipment.
- Lifting Equipment.
- Roadway Equipment.

Many kinds of equipment and tools are necessary for the repair shops which are planned to be located at Bardibas and Sindhuli Bazar. Procurement of spare parts are planned for two years of operation.

Maintenance equipment was selected taking into consideration the following factors:

- To meet all of the different types of required maintenance work for Section I.
- To repair the equipment by the trained DOR maintenance staff.
- A readily available supply of spare parts and tools.

A. Earthmoving Equipment

Bulldozer : For removal of earth and rock deposited on the

road by means of one bulldozer with 14-ton

capacity. This is to be allocated to Bardibas.

Backhoes : For removal of earth and rock deposited on the road as well as sediment at 17 causeways and

drainage ditches along the road using a backhoe with a 0.6 m³ of bucket capacity that is allocated

to Bardibas.

Wheel Type Loader

For removing earth, clay, rock and other materials on the road and sediment at 17 causeways by two wheel type loaders with 1.4 m³ bucket capacity. They will be allocated to Bardibas.

Crawler Type Loader:

For removing earth and rock deposited on the road by means of one crawler loader with a 1.5 m³ bucket capacity. It will be allocated to Bardibas.

Dump Trucks

For hauling deposited and sedimented materials using Three dump trucks, each with an 8-ton capacity. They will be allocated to Bardibas.

Vibratory Rollers

For compaction of surfacing materials by a vibratory roller with a 4-ton capacity. This will be allocated to Bardibas.

B. Concrete Production Equipment

Concrete Mixers

For production of concrete at the work site for reconstruction of structures by means of a portable type concrete mixer (0.3 m³ capacity). They will be allocated to Bardibas.

C. Lifting Equipment

Truck Crane

For handling heavy cargo and materials by means of a truck crane having a 5.0-ton lifting capacity that will be allocated to Bardibas.

D. Roadway Equipment

Motor Grader

For grading work along 37.0 km of road by means of a motor grader having a 2.8 m blade width. This will be allocated to Bardibas.

Plate Compactors

For compaction work along 37.0 km of road by

means of Three 80 kg vibratory plate compactors.

These will be allocated to Bardibas.

E. Repair Shop Equipment and Tools

Power Supply

To generate and supply electric power for the

repair shop, a diesel engine generator with 50/60 kVA generating capacity will be procured

for the maintenance/repair shop at Bardibas.

Equipment and Tools:

To repair the maintenance equipment by means of

standard type of equipment and tools for the repair

shop at Bardibas.

F. Spare Parts

Spare parts (mainly fast-moving ones) are to be procured for two years of operations.

4.8.4 Required Maintenance and Repair Shop Equipment to be Supplied by GOJ

The types of maintenance and repair shop equipment to be supplied by GOJ are summarized below in Table 4.8.1 and Table 4.8.2, respectively.

Table 4.8.1 List of Maintenance Equipment at Bardibas for Section I

Equipment	Capacity	Total
Bulldozer	14.0 t	1
Backhoe	0.6 m ³	1
Wheel Loaders	1.4 m ³	2
Crawler Loader	1.5 m ³	1
Dump Trucks	1 0.8	3
Vibratory Roller	4.0 t	. 1
Truck Crane	5.0 t	1
Motor Grader	2.8 m	1
Plate Compactors	80 kg	3
Diesel Generator	50/60 kVA	1
4-Wheel Jeep	2/5 Passenger 350/150 kg	1
Pickup Trucks	1 t	2
Repair Shop Equipment & Tools	- .	1 lot
Spare Parts		1 lot

Table 4.8.2 List of Equipment & Tools for DOR Repair Shop at Bardibas

Equipment/Tools	Bardibas
Gas Welding Set	1
Arc Welding Set	1
Gear Puller	.1
Drilling Machine	1
Electric Grinder	1
Portable Air Compressor	1
Vices	2
Chain Block	1
Hydraulic Jack	: . 1
Compression Gauge	1
Revolution Indicator	1
Thickness Gauge	1
Hydraulic Meter	1
Current Meter	1
Voltage Meter	. 1
Tool Sets for Vehicle Repair	2
Tool Sets for Repair or Construction Equipment	2
Tool Set for Tire Repair	1
Battery Charger	

4.9 Implementation Program

4.9.1 Construction Principles

The following construction principles will apply:

- The construction work is to be undertaken by a Japanese contractor.
- The implementation program shall be divided into a detailed design stage and a construction stage with an adequate interval in between for the land/house acquisition tendering and other matters.
- Upon being constructed and after handing over the maintenance responsibility for the bridges, approach roads, and causeways will be transferred to DOR.

- HMG shall maintain the road and related facilities using the equipment supplied by GOJ.

4.9.2 Special Considerations for the Construction Plan

For the construction of the nine bridges including their approach roads and the 17 causeways, the following shall be taken into consideration:

- Since the Project site is located far from Kathmandu, there will be a lack of adequate facilities such as electric power, water supply, telecommunications and lodgings.
- The bridge construction sites are divided in about 27-km segments, with PC girder fabrication yards being required for each bridge site.
- The contractor's central concrete mixing plant and rock crushing plant must be adequate for the required concrete volume.

Taking the above into account, the construction plan will be made under following working conditions:

- To construct the base camp composed of the concrete mixing plant, rock crushing plant, workshop, contractor's office/lodgings, laboratory and consultant's office/lodgings near the center of the Project site.
- To construct the girder fabrication yards and contractor's field offices for the bridges.
- To prepare a sufficient communication systems connecting the sites and Kathmandu, the sites and Japan (by satellite) and from site to site.





Figure 4.9.1 Location of Work Facilities

4.9.3 Bridge Construction Methods


The erection of the bridge PC girders will require the use of proven methods and experts, as discussed in the following sub-sections.

A. Erection

Considering the site conditions, and from an economical viewpoint, two erection methods have been selected for the bridges in Section I. These are the erection girder method and truck crane method as shown in Figures 4.9.2 and 4.9.3, respectively. It is planned that the truck crane method will be applied for Ratu Bridge while the erection girder method will be applied for the other bridges.



Figures 4.9.2 Erection Girder Method






Figure 4.9.3 Truck Crane Method

B. Necessity of Experts

Production and erection of PC girders require well trained experts. Since the bridge sites are located quite a distance from Kathmandu with few experts available in Nepal, they will have to be dispatched from Japan at the required time for the purpose of operating special equipment and performing related work for erecting the girders.

4.9.4 Special Considerations for Project Implementation

The following considerations have been taken into account for formulating the implementation of the Project.

- As floods often take place from June to September, work in the river is dangerous. This will require that all work be limited to land-based operations for safety purposes during the flood season. Therefore, the commencement of the Project should be before October so as to use the full dry season profitably.
- Land acquisition for the permanent work items should be carried out by HMG prior to the commencement of the Project. In this regard, the detailed design including the centerline survey should be completed about six months before the commencement of the construction work.
- As construction of the approach roads will undoubtedly interfere with the existing traffic, where possible the construction of these roads should be carried out in the dry season since most of the vehicles can then safety utilize the riverbeds as detours.

4.9.5 Consulting Services for the Detailed Design and Construction Supervision

Immediately after the Exchange of Notes (E/N), the contract for Engineering Consulting Services should be signed. These Services will cover the design, cost estimate, tender/contract documents, tendering, and construction supervision. The required Japanese staff and their responsibilities concerning the Services is outlined as follows:

A. Team Leader

Responsible for all aspects of the Consulting Services.

B. Road Engineer

Responsible for the detailed design of the roads, and the supervision of road construction.

C. Superstructure Engineer

Responsible for the detailed design of the superstructure, and the supervision of its construction.

D. Substructure Engineer

Responsible for the detailed design of the substructure, and the supervision of the substructure construction.

E. River Structure Engineer

Responsible for the detailed design of the causeways during the detailed design stage.

F. Construction Planner/Cost Estimator

Responsible for the preparation of the detailed implementation schedule and Project cost estimate during the detailed design stage.

G. Contract Specialist

Responsible for the preparation of tender, contract and related documents during the detailed design stage.

H. Survey Engineer

Responsible for the topographic and other survey work.

I. Resident Engineer

To reside in Nepal and will supervise the construction work.

J. Materials Engineer

Responsible for the control/advice of specified material quality and strength for the road and structures during construction.

4.9.6 Procurement Plan for Materials and Equipment

The plan for procuring construction materials and construction equipment is presented below.

A. Construction Materials

(1) Normal Portland Cement

Normal Portland cement is manufactured in Nepal, but there is not always enough capacity. Therefore, some part of the normal Portland cement will probably have to be imported from other countries.

(2) High-early Strength Cement

Since high-early strength cement is not manufactured in Nepal, it should be imported from Japan or other countries.

(3) Reinforcement Bars

Indian-made reinforcement bars are sold in the local market, but the maximum size available is only 25 mm. As a result, rebar exceeding 25 mm ϕ will not be used.

(4) Timber and Plywood

Timber and plywood having a water-proof treatment for use in making concrete forms are available in the local market.

(5) Concrete Hume Pipe

Concrete hume pipe is available in Janakpur.

(6) Crushed Stone, Sand, Ready Mixed Concrete and Asphalt mixture

As crushed stone and sand for use in producing such items as ready-mix concrete, asphalt mixture and base course materials, etc. are

not available in the local market, they will have to be produced by the Contractor.

(7) Fill Materials for Road Construction

Materials used as fill when constructing the approach roads will be obtained from nearby borrow areas approved by the Consultant.

(8) Petrol, Oil, Lubricants and Asphalt

The prices of petrol, oil, lubricants and asphalt are regulated by the Government and their prices are fairly consistent in Nepal. Suppliers can transport these items to the sites if the demand is large enough.

(9) Galvanized Steel Wire

Galvanized steel wire for gabions is available in the local market.

(10) Special Construction Materials

PC cable, PC anchors, concrete admixtures, bridge expansion joints and similar items will be imported from Japan.

B. Construction Equipment

Most of the construction equipment available in Nepal is old and it is difficult to obtain spare parts quickly in the case of breakdown. Some items of equipment can probably be rented from the larger construction companies when it is not in use, but there is no assurance that it will always be available. Therefore, it was decided that all needed construction equipment should be brought in from Japan by the Contractor

4.9.7 Implementation Schedule

The implementation schedule for the detailed engineering design and construction of the nine bridges, the approach roads and 17 causeways is depicted below in Figure 4.9.4.




Figure 4.9.4 Tentative Implementation Schedule

The total implementation period is broadly divided into three stages as described below.

A. Contract with the Consultant and the Detailed Design

After signing the contract with the selected a Japanese firm, the detailed design will be carried out by the Consultant including the preparation of the tender/contract documents, drawings and cost estimate. The direct contract system currently in use by DOR will be applied to obtain the Consultant.

B. Prequalification, Tendering and Contract with the Contractor

After discussion with and approval by JICA pertaining to evaluation of the items for the prequalification (P/Q) of tenderers for the construction work, the P/Q activities will be carried out in Japan by the Consultant on behalf of HMG to select the qualified tenderers.

In the tendering operation, the principle of general competitive bidding will be applied to select a Japanese contractor for the construction work. Evaluation of the tenders and selection of the contractor will be performed in Japan by representatives of HMG and the Consultant in the presence of JICA officials. Negotiations with the selected contractor and signing of the contract will be also be done in Japan. The direct contract system currently in use by DOR will be applied to obtain the Contractor.

Parallel to the signing of the contract, HMG will conclude a banking arrangement with an authorized foreign exchange bank in Japan to open accounts for the purpose of receiving the funds granted by GOJ, and making payments to the Japanese consultant and contractor. This banking arrangement will serve as the basis for HMG to issue the Authorization to Pay (A/P) that is indispensable for use by the Japanese consultant as well as for use by the Japanese contractor who will have to obtain export licences for equipment and materials.

Such banking arrangement will also be used to receive payments as stipulated in the contract terms and should be concluded within one month after the signing of the E/N. It is noted that the Japanese consultant and contractor will able to carry out their contract responsibilities only after receiving the verified contract and A/P.

The next step is a verification to be conducted by GOJ. Verification means to examine whether the contents of contracts conform to the provisions of the E/N, which is requisite for the contract to be effective.

C. Construction Work

The construction work will basically consist of the approach roads, causeways, foundations and substructures for the bridges, production and erection of PC girders, bridge surfacing work, river protection and ancillary work. The construction is estimated to take about 19 months to complete.

4.9.8 Scope of Work

The work to be executed by the Japanese side and Nepal side is summarized below, together with the required undertakings by HMG.

A. Scope of Work to be Executed by the Japanese Side

- (1) Consulting services for the design, prequalification, tendering and construction supervision services.
- (2) Construction of nine bridges; namely, the Bhozate Bridge, Karkare Bridge, Gangate Bridge, Ratu Bridge, Sindhuse Bridge, Kamara Bridge, Phittang Bridge, Buka Bridge and Gadeuli Bridge.
- (3) Construction of the approach roads for the above nine bridges.
- (4) Construction of 17 causeways.
- (5) Provision of equipment for maintenance of the road from Bardibas to Sindhuli Bazar and tools for the Bardibas repair shop that will be needed to keep such equipment in operation.

B. Scope of Work to be Executed by DOR

- (1) To perform maintenance of the road, drainage ditches and bridges from Bardibas to Sindhuli Bazar using equipment provided by Japanese Grant Aid.
- (2) To perform improvement of selected segments of the road.
- (3) To staff and operate the repair shop.

C. Undertaking by HMG and DOR

- (1) Provision of necessary land for construction of the bridges, approach roads and causeways.
- (2) Demolition and/or removal of any impediments within the above mentioned land.
- (3) Organizing and financing the maintenance activities that will be needed for Section I.

- (4) Arranging for exemption of tax for all imported construction equipment and materials provided by the Japanese Grand Aid.
- (5) Exemption of income tax for expatriates.

The expenditures to be borne by HMG in connection with the implementation of the Project is estimated as shown below:

		(Unit: Mil. NRs.)
1)	Land Acquisition and House Compensation Cost	10.9
2)	DOR Administration Cost	1.9
3)	Maintenance Cost	13.4
	Total	26.2

CHAPTER 5 SUMMARY OF MAIN POINTS AND CONCLUSION FOR THE PROJECT (SECTION I)

CHAPTER 5 SUMMARY OF MAIN POINTS AND CONCLUSION FOR THE PROJECT (SECTION I)

5.1 Summary of Main Points of the Project (Section I)

Sindhuli District, having a population of about 130,000, has only one road connecting it to the East-West Highway. The road has been constructed by DOR using equipment provided in 1982 by the Japanese Grant Aid Program; however its service level is extremely low because of a lack of bridges and paved surface.

The lack of bridges and the problem of natural disasters such as landslides cause road blockages which isolate the District during the rainy season thus placing serious hardships on the villagers.

The Project (Section I) consists of the construction of nine bridges with approach roads and 17 causeways in order to make the existing road/traffic conditions safe, especially during the rainy season. This will ensure an adequate transportation line for hauling subsistence commodities and agricultural produce between the East - West Highway and Sindhuli Bazar

Such improvements will not only provide safety for the villagers in Sindhuli District and Ramechhap District, they will also allow the linkage of farms around the Districts and market centres thereby intensifying regional economic gains.

DOR can carry out the maintenance of the Project after its completion because of its strengthened maintenance capability that is included as a part of the Project and due to a lesser requirement for maintaining concrete bridges as compared to steel bridges.

The objectives of the Sindhuli Road Project are consistent with the objectives of the road transport development called for in the Eighth Plan. Also the effects of the Project (Section I) mentioned above fully agree with the policies of the Eighth Plan such as consolidation of regional integration.

The main environmental impact will be that of land acquisition and demolition of some (not many) houses.

The construction period of about 19 month's is considered to be reasonable.


5.2 Conclusion


Based on the findings of the Basic Design Report included herein, the Project (Section I) should be implemented under the Japanese Grant Aid Program with the starting date to begin at the earliest possible time.


In order to ensure the smooth progress of the Project (Section I), it is recommended DOR undertake the following:


- To establish an efficient organization for implementing the Project.
- To obtain the required land and pay an adequate amount of compensation to the residents and land owners that will be affected by the Project.
- To limit the use of borrow areas (for fill, sand and boulders) near the bridges so that scoring of the riverbed will be avoided.
- To carry out the maintenance and improvement operations planned for Section I.
- To carry out the site inspection immediately after rain and remove any deposits at the causeways.


APPENDIX A THE DRAWINGS

















DESIGN CONDITION

TOTAL BRIDGE LENGTH	L+50.00m
SPAN	5-25.004
WIDTH	W= 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	1=10/(25+L)
SEISMIC COEFFICIENT	Kn=0.18
ANGLE OF SKEW	ao. 0o. 0o.
RADIUS OF CURVATURE	R- 60
LONGITUDINAL SLOPE	1=-7.000%~8.000%

SUPERSTRUCTURE


[TEM	CLASS	UNIT	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE	<u> </u>					
GIRDER	g ck = 350	W _a	18.23	54.69	109.38	
CAST IN PLACE	##/c=	W,		7.90	15.80	
CONCRETE	##/##1 # Ch = 240	w,		71.76	472.92	
FORM						
GIRDER		W,	113.90	341.69	683.38	
CAST IN PLACE		m²		451.63	903.26	
PRESTRESSING	CABLE					
GIRDER	12T12.4	ksf	872.60	2617.80	5236.00	
CROSS BEAM	12# 5	kgf		70.60	141.20	
REINFORCEME	NT BAR					
	≠13 .	KEF	1466.67	8300 00	16600.00	
	∌ 18~•25	kgf	1800.00	16300.00	32600 00	
SHOE	FIX.WOV	n		6	12	
EXPANSION .	JOINT	m			22.50	
DRAIN		n		2	4	
PAVEMENT		m²		186.80	373.60	
ERECTION		tf	45.58	136.73	273.45	


SUBSTRUCTURE

ITEM	CLASS	UNIT	A - 1	P - 1	A - 2	REMARKS
EXCAVATION	REGULARCLAY	m²		570.0		
	MEDIUM SOUND ROCK	m³	264.9		332.6	
CONCRETE	gck=240kg/cm²	H13	91.3	130.7	91.3	
FORM	REGULAR	m²	134.2	32.6	134.2	
	CURVE	m²		70.7		
REINFORCEMENT BAR	ø13	ksf		400.0		
	φ16~φ25	kgf	1800.0	17800.0	1800.0	

ITEM	CLASS	UNIT	RIGHT BANK	LEFT BANK	TOTAL	REMARKS
EXCAVATION		m³		182.0	182 0	
EMBANKMENT		mª .		135.7	135.7	1
FOUNDATION	· · · · · · · · · · · · · · · · · · ·	m		29.0	29.0	STONE MASONRY
		m				STONE PITCHING
STONE MASONRY		ភេះ		125.8	125.8	
STONE PITCHING		m _s				
MAT GABIONS		tu ₂		306.0	306.0	
7			1	 		

Figure 4.6.2 General Plan of Karkare Bridge





DESIGN CONDITION

TOTAL BRIDGE LENGTH	L+30 0Dm
SPAN	\$-30.00m
WIDIH	4- 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	1-10/(25+L)
SEISWIC COEFFICIENY	Kh+0.18
ANGLE OF SKEW	60, 00, 00,
RADIUS OF CURVATURE	R= 62
LONGITUDINAL SLOPE	1-6.000%

SUPERSTRUCTURE


	·					
ITEM	CLASS	TINU	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE						
GIRDER	ock=350	m³	24.88	74.65	74.65	
CAST IN PLACE	pck-300	W _a		10.61	10.61	
CONCRETE	a C & • 240	W ₂		86.18	86.18	
FORM						
GIRDER		m _s	:58.04	474.13	474.13	
CAST. IN PLACE		ω _{\$}	. ——-	541.76	541.76	
PRESTRESSING	CABLE				4.7	
GIRDER	12112.4	Kgf	1309.67	3929.00	3929.00	
CROSS BEAM	120 5	kgf		70.60	70.60	
REINFORCEMEN	NT BAR					
	Ø13	kgf	2000.00	11000.00	11000.00	
	#16~#25	kgf	2466.67	20400.00	20400.00	
SHOE	FIX.MOV	n	· ·	6	6	
EXPANSION .	TAIOL	m			15.00	
DRAIN		n		2	2	
PAVEMENT		m*		224.30	224.30	
ERECTION		tf	62.21	186.63	186.63	


SUBSTRUCTURE

I TEM	CLASS	UNIT	A - 1	A ~ 2	REMARKS
EXCAVATION	REGULARCLAY	Πτ	 .		
	MEDIUM SOUND ROCK	m	250.8	161.8	
CONCRETÉ	ock-240<8/cm	III.	99.6	134.7	
FORM	REGULAR	nt*	189.9	289.0	
	CURVE	m²			1.1
REINFORCEMENT BAR	φ13	ksf	200.0	300.0	
	φ16~¢25	kgf	11700.0	16500.0	


1 TEM	CLASS	UNIT	RIGHT BANK	LEFT BANK	TOTAL	REMARKS
EXCAVATION		m³			1848.1	
EMBANKMENT		tu _a			1947.0	
FOUNDATION		П	47.0	79.0	126.0	STONE MASONRY
		m,		<u> </u>		STONE PITCHING
STONE MASONRY	.,	u ₁			834.8	
STONE PITCHING		m	<u> </u>			
MAT GABIONS		m			567.0	
		1				

Figure 4.6.3 General Plan of Gangate Bridge





CROSS SECTION S-1:50



DESIGN CONDITION

TOTAL BRIDGE LENGTH	L-180 00m
SPAN	5-30.00m
WIDTH	#+ 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	(=10/(25+L)
SEISMIC COEFFICIENT	Kh+0-18
ANGLE OF SKEW	80, 00, 00,
RADIUS OF CURVATURE	R- 60
LONGITUDINAL SLOPE	I = - 0 . 300%

SUPERSTRUCTURE


1 TEM	CLASS	UNIT	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE	1					
GIRDER	3 CK + 350	W,	24.88	74.65	671.85	
CAST IN PLACE		m ^a		10.61	95.49	
CONCRETE	0CK 240	m³		86.18	775.62	
FORM	·					
GIRDER		W ₅	158.04	474.13	4267.17	
CAST IN PLACE	1	m²		541.76	4875.84	
PRESTRESSING	CABLE				· · · · · · · · · · · · · · · · · · ·	
GIRDER	12T12.4	kgf	1309.67	3929.00	35361.00	
CROSS BEAM	126 5	kef		70.60	635.40	
REINFORCEME	NT BAR			:		
	613	kgf	2000.00	11000.00	99000.00	
	#16~#25	kgf	2466.67	20400.00	183600.00	
SHOE	FIX.WOY	n		6	54	
	JOINT	m			75.00	
DRAIN		n		2	18	
PAVEMENT		W ₂		224.30	2018.70	
ERECTION		tf	62.21	186.63	1679.63	


SUBSTRUCTURE

1 TEM	CLASS	UNIT	A - 1	Ρ ~ 1	P - 2	P - 3	P - 4	P - 5 ·	P - 6	P - 7	P - 8	A ~ 2	REMARKS
EXCAVATION	REGULARCLAY	m³		756.1	1161.6	861.2	1097.1	807.6	508.5	659.1	- 508.1	662.5	
A Company	MEDIUM SOUND ROCK	m³	530.4						i ——				
CONCRETE	ock=240kg/cm	m³	145.6	162.5	162.5	162.5	157.4	157.4	128.4	157.4	133.4	285.5	
	REGULAR	rir	247.9	121.7	121.7	121.7	118.2	118.2	103.7	118.2	107.2	493.6	
	CURVE	m²		53.4	53.4	53.4	50.3	50.3	37.7	50.3	40.8		
REINFORCEMENT BAR		ksf	300.0	400.0	400.0	400 · D	400.0	400 0	300.0	400.0	300.0	700.0	
	φ16~φ25	kgf	16500.0	19100.0	19100.0	19100.0	18400.0	18400.0	14900.0	18400.0	15600.0	33900.0	

EMARKS	RE	.	TOTAL	iĸ	EFT BAR	4	RIGHT BAN	UNIT	CLASS	ITEM
		. 9	56.	9	56	1		U ₂		XCAVATION
		$_{\perp}$				T		m²		MBANKMENT
E MASONRY	STONE	. 5	47.			₹	47.5	FT)		OUNDATION
E PITCHING	STONE	. 5	26.	5	26	Τ		m		
		. в	234.			3	234.8	m		TONE MASONRY
		.7	288	2	203	şΤ	85.	m		TONE PITCHING
		. 0	330	0	159	ग	171.0	m ^a		AT GABIONS
				T		T				
		. 0	330	0	159.	<u>)</u>	171.0	m³		AT GABIONS

Figure 4.6.4 General Plan of Ratu Bridge





DESIGN CONDITION

SPAN	TOTAL BRIDGE LENGTH	L-80 00m
LIVE LOAD A-TYPE LIVE LOAD ("251 IMPACT COEFFICIENT (1-10/(25-L)) SEISMIC COEFFICIENT KN-0 18 ANGLE OF SKEW 90'00'00'	SPAN	S-30 00m
IMPACT COEFFICIENT (1-10/(254L) SEISMIC COEFFICIENT Kh-Q 18 ANGLE OF SKEW QD' OD 00'	WIDTH.	w- 7 50m
SEISMIC COEFFICIENT KH-Q 18	LIVE LOAD	A-TYPE LIVE LOAD (25)
ANGLE OF SKEW DO' OD' DO'	IMPACT COEFFICIENT	1+10/(25+L)
	SEISMIC COEFFICIENT	KN+0 18
RADIUS OF CURVATURE R. to	ANGLE OF SKEW	80, 00, 80,
	RADIUS OF CURVATURE	R • co ∵
LONGITUDINAL SLOPE 1-3.000%	LONGITUDINAL SLOPE	1-3.000%

SUPERSTRUCTURE


ITEM	CLASS	UNIT	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE	}					
GIRDER	##/##* #CK+350	"m»	24.88	74.65	149.30	
CAST IN PLACE	sck-300	m³		10.61	21.22	
CONCRETE	0 ck = 240	m³		86.18	172.36	
FORM						
GIRDER		W ₃	158.04	474.13	948.26	
CAST IN PLACE		W _I		541.76	1083.52	
PRESTRESSING	CABLE					
GIRDER	12112.4	kgf	1909:67	3929.00	7858.00	····
CROSS BEAM	120 5	K8f		70.60	141.20	
RE INFORCEMEN	NT BAR					
	613	ksf	200.00	11000.00	22000.00	
	ø16~ø25	kgf	2456.67	20400.00	40800.00	
SHOE	FTX.MOV	. n		6	12	
EXPANSION J	OINT	m			22.50	
DRAIN		n		2	4	
PAVEMENT		· W ₂		224.30	448.60	
ERECTION		tf	52.21	186.63	373.25	


SUBSTRUCTURE

1TEM	CLASS	UNIT	A - 1	P - 1	A - 2	REMARKS
EXCAVATION	REGULARCLAY	mª .	516.0	508.1		
	MEDIUM SOUND ROCK	mª.			693.0	
CONCRETE	ock=240<8/cm	III ⁹	281.9	162.5	145.5	
FORM	REGULAR	LU ₃	498.0	121.7	247.1	
	CURVE	m²		-53.4		
REINFORCEMENT BAR	φ13.	kgf	700.0	400.0	300.0	
	φ16~φ25	kgf	33800.0	19100.0	16500.0	

ITEM	CLASS	UNIT	RIGHT BANK	LEFT BANK	TOTAL	REMARKS
EXCAVATION		m²	362.6	509.3	871.9	<u> </u>
EMBANKMENT		m,	96.2	244.9	341.1	
FOUNDATION		m				STONE MASONRY
		m	37.0	48.5	85.5	STONE PITCHING
STONE MASONRY		U.S				<u> </u>
STONE PITCHING		m²	146.5	192.0	338.5	
MAT GABIONS		mª	222.0	482.5	704.5	1

Figure 4.6.5 General Plan of Shindhuse Bridge





DESIGN CONDITION

TOTAL BRIDGE LENGTH	L-12D 00m
5PAN	S+30.00m
WIDTH	W- 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	1-10/(25+L)
SEISMIC COEFFICIENT	Kn+Q. 18
ANGLE OF SKEW	80, 00, 00,
RADIUS OF CURVATURE	R+ 40
LONGITUDINAL SLOPE	11.400%

SUPERSTRUCTURE


					1	
ITEM	CLASS	UNIT	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE	·					
GIRDER	##/cm	m ₃	49.66	148.97	446.91	
CAST IN PLACE	88/cm²	W ₃		20.41	61.23	
CONCRETE	0 Ck • 240	m³		118.41	355.23	
FORM						
GIRDER	T	m²	284.93	854.79	2564.36	
CAST IN PLACE		m²		720.22	2160.65	
PRESTRESSING	CABLE			:		
GIRDER	12112.4	kgf	2451.75	7355.30	22066.00	
CROSS BEAM	120 5	kgf.		117.70	352.98	
REINFORCEME	NT BAR	ii				
	413	kgf	4033.33	19900.00	59700.00	
	●18~●25	kgf	4900.00	32800.00	98400.00	
SHOE	FIX.WOV	n		6	18	
EXPANSION .	TAIOL	m			30.00	
DRAIN		n		2	6	
PAVEMENT		m².		299.30	897.75	1
ERECTION		tf	124.15	372.44	1117.32	


SUBSTRUCTURE

ITEM	CLASS	UNIT	A - 1	P - 1	P - 2	A - 2	REMARKS
EXCAVATION	REGULARCLAY	m³		478.5	525 1	480.0	
	MEDIUM SOUND ROCK	IT/P	350.0				
CONCRETE	ock=240kg/cm	ttr ^a	88.7	103.8	1166	210.4	
FORM	REGULAR	m².	146.1	28.9	31.4	400.7	
	CURVE	m²		47.1	55.0		
REINFORCEMENT BAR	φ13	kgf		300.0	300.0	500.0	
	φ16~φ25	kgf	2100.0	14300.0	15700.0	25000.0	

ITEM	CLASS	UNIT	RIGHT SANK	LEFT BANK	TOTAL	A REMARKS
EXCAVATION		mª	120.0		120 0	
EMBANKMENT		m²				
FOUNDATION		m		<u> </u>		STONE MASONRY
		m	20.0		20.0	STONE PITCHING
STONE MASONRY		n7				
STONE PITCHING		m²	127.3		127.3	
MAT GABIONS		III ²	233.0		233.0	

Figure 4.6.6 General Plan of Kamara Bridge





DESIGN CONDITION

TOTAL BRIDGE LENGTH	L+50.00m
SPAN	\$-25.00m
WIDTH	₩* 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	I-10/(25+L)
SEISMIC COEFFICIENT	Kh=0.18
ANGLE OF SKEW	50, 00, 00,
RADIUS OF CURVATURE	R= 45
LONGITUDINAL SLOPE	i =- 0 . 300%

SUPERSTRUCTURE

ITEM	CLASS	UNIT	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE	-					
GIRDER	sck - 350	m³	18 23	54.69	109.38	
CAST IN PLACE	#1/cm	m²		7.90	15.80	
CONCRETE	#1/ca"	m³		71.76	472.92	
FORM						
GIRDER		W ₃	113.90	341.69	683.38	
CAST IN PLACE		m²		451.63	903.26	
PRESTRESSING	CABLE					
GIRDER	12712.4	kgf	£72.60	2617.80	5236.00	
CROSS BEAM	124 5	kgf		70.60	141.20	
REINFORCEMEN	IT BAR				:	
	¢13	ksf	1465.67	8300.00	16600.00	
	#18~#25	kgf	1800.00	16300.00	32600.00	
SHOE	FIX.MOV	n		6	12	
EXPANSION J	OINT	6			22.50	
DRAIN		n		2	4	
PAVEMENT		m²		186.80	373.60	
ERECTION t		tf	45.58	136.73	273.45	


SUBSTRUCTURE


ITEM	CLASS	UNIT	A - 1	P - 1	A - 2	REMARKS
EXCAVATION	REGULARCLAY	ma		478.5	852.0	
	MEDIUM SOUND FROCK	ma	550.0		-	
CONCRETE	ock=240<8/cm	LU ₂	155.8	106.2	222.7	
FORM	REGULAR	m²	292.0	28.9	409.4	
	CURVE	π²		51.1		
REINFORCEMENT BAR	φ13	ksf	400.0	300.0	500.0	
	¢16~¢25	kgf	17900.0	14700.0	26400.0	

RIVER-PROTECTION

1 TEM	CLASS	TINU	RIGHT BANK	LEFT BANK	TOTAL	REMARKS
EXCAVATION		m³ ·	243.6	476.0	719.6	
EMBANKMENT		W ₂	61.9		61.9	
FOUNDATION		m				STONE MASONRY
		m	43.5	40.0	83.5	STONE PITCHING
STONE MASONRY		m²				
STONE PITCHING	····	m²	180.6	281.2	4 61 .8	
MAT GABIONS		m³		663.8	663.8	
		1	1			

Figure 4.6.7 General Plan of Phittang Bridge





DESIGN CONDITION

TOTAL BRIDGE LENGTH	L-50.00m
SPAN	S-25.00m
WIDTH	₩+ 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	1-10/(25·L)
SEISWIC COEFFICIENT	Kn-0 18
ANGLE OF SKEW	80, 00, 00,
RADIUS OF CURVATURE	R- to
LONGITUDINAL SLOPE	1=3.400%

SUPERSTRUCTURE

ITEM	CLASS	דנאט	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE						
GIRDER	dCK+350	m³	18.23	54.69	109.38	
CAST IN PLACE	25/cm2	m³		7.90	15.80	
CONCRETE	\$1/em	Шэ		71.76	472.92	
FORM	12					
GIRDER		m² ·	113.90	341.69	683.38	
CAST IN PLACE		M²		451.63	903.26	
PRESTRESSING	CABLE					
GIRDER	12112.4	kgf	872.60	2617.80	5236.00	
CROSS BEAM	120 5	kgf		70.60	141.20	
REINFORCEME	NT BAR					
	Ø13	kgf	1466.67	8300.00	16600.00	
	ø16~ø25	kgf	1800.00	16300.00	32600.00	
SHOE	FIX.MOV	0		6	12	
EXPANSION .		m			22.50	
DRAIN		n		2	4	
PAVEMENT		m²		186.80	373.60	
ERECTION		t.f	45.58	136.73	273.45	


SUBSTRUCTURE


1 TEM	CLASS	TINU	A - 1	P - 1	A - 2	REMARKS
EXCAVATION	REGULARCLAY	m³	276.0	570.0		
	MEDIUM SOUND ROCK	m³			375.0	
CONCRETE	ock=240<8/cm2		149.3	128.7	90.7	
FORM	REGULAR	m².	270.8	119.8	146.4	
. 0	CURVE	m²		35.3		
REINFORCEMENT BAR		kgf	300.0	300.0		
	φ16~φ25	kgf	17000.0	14500.0	2100.0	

RIVER-PROTECTION

						· ·
ITEM	CLASS	TINU	RIGHT BANK	LEFT BANK	TOTAL	REMARKS
EXCAVATION		m²	201.0	113.9	314.9	
EMBANKMENT				25.1	25.1	
FOUNDATION		- m	30.0	33.5	63.5	STONE MASONRY
POUNDATION						STONE PITCHING
STONE MASONRY		m²	117.4	243.4	360.8	
STONE PITCHING		m²				
MAT GABIONS		m³	382.5	201.0	583.5	<u> </u>
			l			L

Figure 4.6.8 General Plan of Buka Bridge





DESIGN CONDITION

TOTAL BRIDGE LENGTH	L=50.00m
SPAN	\$+25.00m
MIDIH	w- 7.50m
LIVE LOAD	A-TYPE LIVE LOAD (TL-25)
IMPACT COEFFICIENT	1-10/(25+L)
SEISNIC COEFFICIENT	<h-0.18< td=""></h-0.18<>
ANGLE OF SKEW	60, 00, 00,
RADIUS OF CURVATURE	R- Ø
LONGITUDINAL SLOPE	1=0.350%

SUPERSTRUCTURE

ITEM	CLASS	TINU	PER GIRDER	PER SPAN	PER BRIDGE	REMARKS
CONCRETE	J					
GIRDER	dek-350	m³	18.23	54.69	109.38	
CAST IN PLACE	##/cm	m³		7.90	15.80	
CONCRETE	# 1 2 40	m,		71.76.	472.92	
FORM						
GIRDER	Ì	W ₂	113.90	341.69	683.38	
CAST IN PLACE		m*		451.63	903.26	
PRESTRESSING	CABLE	1				
GIRDER	12112.4	kgf	872.60	2617.80	5236.00	
CROSS BEAM	120 5	ksf		70.60	141.20	
REINFORCEME	NT BAR			:		
	013	kgf	1466.67	8300.00	16600.00	
	#16~#25	k g f	1800.00	16300.00	32600.00	
SHOE	FIX.HOV	n		6	12	
EXPANSION .	JOINT	m			22.50	
DRAIN		n		2	4	
PAVEMENT		m².		186.80	373.60	
ERECTION		t.f	45.58	136.73	273.45	

SUBSTRUCTURE

ITEM	CLASS	UNIT	A - 1	P - 1	A - 2	REMARKS
EXCAVATION	REGULARCLAY		235.2	508.1		
	MEDIUM SOUND ROCK	F			562.5	
CONCRETE	ock-240kg/cm	F-3°	110.5	136.5	218.4	
FORM	REGULAR	ci*	192.6	127.8	374.9	
	CURVE	c:r		40.1		
REINFORCEMENT BAR	ø13	ksf	200.0	300.0	500 D	
	φ16~φ25	KEF	12000.0	15500.0	25800.0	

GARD-BANK-STRUCTURE

ITEM	CLASS	UNIT	RIGHT BANK	LEFT BANK	TOTAL	REMARKS
EXCAVATION			679.4	335.4	1014.B	
EMBANKMENT			23.7	148.2	171.9	
FOUNDATION		en en	39.5	39.0	78.5	STONE MASONRY
		ត				STONE PITCHING
STONE MASONRY		E.P	220 8	218.0	438.8	
STONE PITCHING	:	F-2				
MAT GABIONS	· · · · · · · · · · · · · · · · · · ·	ವ	237.0	234.0	471.0	
			1			

Figure 4.6.9 General Plan of Gadeuli Bridge

