

PROJECT SUMMARY (F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASO LKA/S 304/83

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Sri Lanka	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input checked="" type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY	Telecommunications Network Improvement Project in Greater Colombo	Colombo metropolitan area					
3. SECTOR	Communications & B/Telecommunication	2. PROJECT COST		Total Cost	Local Cost	Foreign Cost	
4. REFERENCE NO.		(US\$1,000)	1)	38,333	4,526	33,807	
5. TYPE OF STUDY	F/S	(US\$1=270Yen)	2)				
6. COUNTERPART AGENCY	Sri Lankan Telecommunications Department (SLTD)	3)	3. CONTENTS OF MAJOR PROJECT(S)				
7. OBJECTIVES OF STUDY	Feasibility study on "Telecommunications Network Improvement Project in Greater Colombo" as an integral part of the National Development Plan.	(1) Junction Network Junction cable installation: 109.1km (The above includes optical fiber cable installation for 11.7km.) PCM system establishment: 781 systems PCM repeaters: 1,411 pcs Manhole construction: 327 pcs Duct installation: Installation length 59.7 km, Pipe length 230km (2) Subscriber Network Primary cable installation: 147km Secondary cable installation: 950km Cross-connecting cabinet establishment: 187 locations Number of lead-in cable pairs to exchanges: 67,900 pairs Manhole construction: 450 pcs Duct installation: Installation length 96km, Pipe length 490km				(Description) May 1985 OECF loan agreement (10,359 million yen) (Ph-I) Mar. 1991 Construction completed Mar. 1991 OECF Loan Agreement (Ph-II) Dec. 1991 Consulting Service Agreement Jul. 1995 Scheduled to be completed (FY 1992 Overseas Survey) Jun. 1993 Detailed Design and start of construction Dec. 1994 Implementation scheduled to be completed (FY1993 Overseas Survey) Jan. 1995 Implementation scheduled to be completed. (FY1995 Domestic Survey) It is under implementation. Construction period is extended until Mar., 1996. (FY1995 Overseas Survey) Apr. 1996 Implementation scheduled to be completed.	
8. DATE OF SAV	1982/12	Imp. Period: 1985.8-1988.11					
9. CONSULTANT(S)	Nippon Telecommunication Consulting Co., Ltd.	4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 29.70		FIRR1) 15.20
10. STUDY TEAM	No. of Members 15 Period Jan. 1983-Nov. 1983 (11 months)	EIRR2)	EIRR3)	FIRR2)	FIRR3)		
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	None	Conditions and Development Impacts: [Assumptions] 1) The project life is set at 20 years after service-in. 2) The prices used in the financial analysis were converted to 'the border price' by multiplying by the standard conversion factor. As for this project, the border prices happen to be the same as the domestic market prices. 3) Economic benefits consist of consumer's surplus and the operating revenues calculated in the financial analysis. [Development Impacts] 1) Improvement of telecommunication service in the Metropolitan areas; 2) The greater ease of emergency access to medical institutions is conducive to protection and rescue of human lives; 3) Upgrading and diversification of government services including improvement of security; 4) Increased supply of information; 5) Activation of economic activities; 6) Creation of employment opportunity.					2. MAJOR REASONS FOR PRESENT STATUS
12. EXPENDITURE	Total 117,636 (¥'000) Contracted 109,525	5. TECHNICAL TRANSFER					
		1) Joint preparation of the report 2) On the job training (SLTD counterparts)					①, ②, ③

PROJECT SUMMARY (F/S)

Compiled Mar.1986

Revised Mar.1996

ASO LKA/S 303/83

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Sri Lanka	1. SITE OR AREA				1. PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input checked="" type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY	Colombo-Katunayake Expressway and New Port Access Road Project	Colombo metropolitan area					
3. SECTOR	Transportation/Road	2. PROJECT COST		Total Cost	Local Cost	(Description) The D/D of the port access road (1.5km) of Project B was undertaken as part of the OECF loan on the Colombo Port improvement (L/A in Oct.1987, 1,955 million yen). Mar.1990 OECF E/S loan agreement (520 million yen) on Colombo - Katunayake Express way Jun.1990 D/D started Dec.1992 D/D completed (FY1993 Overseas Survey) Land acquisition and resettlement are in progress. (FY1994 Domestic Survey) The environmental report regarding this Project has been officially announced by the Gov't of Sri Lanka on Mar.1994. (FY1995 Domestic Survey) At present, the new Government is checking and re-investigating the priorities of all existing projects. This project particularly faces on many problems such as environmental matters, resettlement of the inhabitants and so on. Additionally, the security circumstances go from bad to worse. (FY1995 Overseas Survey) This project is suspended due to strong public protest for land acquisition surveys.	
4. REFERENCE NO.		1)	51,080	19,790	31,290		
5. TYPE OF STUDY	F/S	2)	236,517	129,779	106,738		
6. COUNTERPART AGENCY	Greater Colombo Economic Commission (GCEC)	3)					
7. OBJECTIVES OF STUDY	Technical and economical feasibility study for the expressway connecting the international airport and the port of Colombo with a distance of 30km.	3. CONTENTS OF MAJOR PROJECT(S)					
8. DATE OF SA/	1982/9	The budget 1) is for F/S and 2) for D/D. [Project A] 1) Main Road 25.4km K-1: Dalugama IC - Ragama IC 7.1km; K-2: Ragama IC - Ekala IC 8.4km K-3: Ekala IC - Airport 9.9km 2) Alternatives and affiliated roads K-4: Wewelduwa - Kiribathgoda (Access Road to Biyagama) 1.7km K-5: Ekala IC - Negombo(A3) Road 3.1km; K-6: Dandugam - Airport 9.5km K-7: KIPZIC - Canada Sri Lanka Friendship Road 1.6km [Project B] 1) Main Road 5.7km P-1: Colombo Port - Prince of Wales Avenue 1.6km P-2: Prince of Wales Avenue - Peliyagoda 1.5km P-3: Peliyagoda - Dalugama (Along Kandy) 2.9km 2) Alternative and affiliated roads P-4: Peliyagoda - Dalugama (Along Kandy) 2.6km P-5: Peliyagoda - Wattala 1.0km					
9. CONSULTANT(S)	Japan Bridge and Structure Instituted, Inc.	4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 18.50 EIRR2) 19.04 EIRR3)		
10. STUDY TEAM	No. of Members 21 Period Dec.1982-Jan.1984 (13 months)	Conditions and Development Impacts: The IRR 1) is for F/S and 2) for D/D. [Conditions] Start of operation in 1990; the project life of 25 years; opportunity cost of capital at 12%. [Development Impacts] 1) Establishment of an efficient road network through the separation of passing traffics and large vehicles. 2) Productivity improvement in the GCEC area and Gampaha District as the result of transport connection. 3) Inducement of new industrial investments to Katunayake Investment Promotion Zone and elsewhere. 4) Expansion of the regional market due to the construction of new roads, particularly of the expressway. 5) Shortening of the commuting time within GCEC area and Gampaha District, and the resulting population diffusing effect.					
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	Topographic and geological survey	5. TECHNICAL TRANSFER				2. MAJOR REASONS FOR PRESENT STATUS	
12. EXPENDITURE	Total 203,467 (¥000) Contracted 193,010	1) Participation of 2 trainees in JICA training program 2) OJT				3. PRINCIPAL SOURCE OF INFORMATION	
						①, ②, ④	

PROJECT SUMMARY (M/P)

Compiled Mar.1988
Revised Mar.1996

ASO LKA/S 101/85

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS															
1.COUNTRY	Sri Lanka	1.SITE OR AREA	Whole country		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued														
2.NAME OF STUDY	Master Plan for the Domestic Telecommunication Network	2.PROJECT COST			Total Cost Local Cost Foreign Cost (US\$1,000) 1) 29,307 (US\$=26.00Rp) 2)		(Description) Mar.1991 OECF Loan Agreement (Phase II, 10,968 million yen) Dec.1991 Consulting Service Agreement Jul.1995 Implementation scheduled to be completed (FY 1993 Overseas Survey) No additional information. (FY1995 Domestic Survey) M/P and F/S are now repeatedly implemented again since Mar., 1995 in order to fit for the political and economical change of recent years. (FY1995 Overseas Survey) 1) Trunk Transmission Network Development Project was undertaken with ADB funding and is nearing completion by now. 2) Greater Colombo Area Telecommunication Project-2 was undertaken with OECF funding and it is scheduled to be completed in March, 1995. 3) SLTD Organization Improvement Project was undertaken with the World Bank funding in FY1993/94 and was successfully completed.													
3.SECTOR	Communications & B/Telecommunication	3.CONTENTIS OF MAJOR PROJECT(S)	To propose 100% of Digitalization of Trunk Network in the year 2000 and the network development for the following towns (1) Greater Colombo Area Telecommunications Improvement Project-2 (2) SLTD Organization Improvement project (3) Subscriber's line expansion project and Telecommunications network expansion project for rural towns/villages																	
4.REFERENCE NO.		4.CONDITIONS AND DEVELOPMENT IMPACTS			[Conditions] To realize 100% of demand fulfillment and 100% of digitalization in the year 2000 [Impacts] To decrease the difference in Quality between Urban area and Rural area.															
5.TYPE OF STUDY	M/P	10.STUDY TEAM						2.MAJOR REASONS FOR PRESENT STATUS (1) Effectiveness (2) High priority												
6.COUNTERPART AGENCY	Ministry of Posts and Telecommunications Development.	11.ASSOCIATED AND/OR SUBCONTRACTED STUDY								3.PRINCIPAL SOURCE OF INFORMATION ①, ②, ④										
7.OBJECTIVES OF STUDY	To study the Master Plan for telecommunications development in the year 2000.	12.EXPENDITURE										Total 136,112 (Y'000) Contracted 128,045								
8.DATE OF SAV	1984/8	5.TECHNICAL TRANSFER												1) Trainee acceptance: 3 counterparts invited Japan 2) On the job training (SLTD counterparts)						
9.CONSULTANT(S)	Nippon Telecommunication Consulting Co., Ltd.																			

PROJECT SUMMARY (F/S)

Compiled Mar. 1990
Revised Mar. 1996

ASO LKA/A 304/85

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Sri Lanka	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY	Rehabilitation of Tank Irrigation Project	Minipe scheme	6,800ha	Nagadeepa scheme	2,400ha		
3. SECTOR	Agriculture/Irrigation, Drainage & Reclamation	2. PROJECT COST		Total Cost	Local Cost	(Description) (FY 1992 Overseas Survey) The project has been implemented with the OECF loan and the Japanese grant aid. Jul. 1988 OECF L/A signed (1,850 mil. yen) The loan covers the rehabilitation of main canals (73.3km) and roads, branch canals (90km) and roads, etc. Construction scheduled to be completed in 1994. Apr. 1989 Grant Aid E/N signed (449 mil. yen) Minipe and Nagadeepa Rural Development Phase I: Improvement of roads and digging of wells Completed Jun. 1989 Grant Aid E/N signed (709 mil. yen) Phase II: Improvement of roads and digging of wells Completed (FY1993 Overseas Survey) Sep. 1995 Scheduled to be completed. (FY1994 Domestic Survey) No additional information. (FY1995 Domestic Survey) It is planned to extend the OECF financing period until Mar., 1998. And the period of the agreement with consultant is also extended until Dec., 1996. (FY1995 Overseas Survey) May 1995 Grant Aid E/N signed (2,200 mil. yen) for the construction of Mahaweli Bridge.	
4. REFERENCE NO.		(US\$1,000)	1)	16,830	9,370		
5. TYPE OF STUDY	F/S	US\$1=27.5Rs	2)				
6. COUNTERPART AGENCY	Ministry of Lands and Land Development		3)				
7. OBJECTIVES OF STUDY	To stabilize agricultural products and increase incomes and living standard	3. CONTENTS OF MAJOR PROJECT(S)					
8. DATE OF SAV	1984/6	1. Canal System		Minipe	Nagadeepa		
9. CONSULTANT(S)	Japan Engineering Consultants Co., Ltd. Kyowa Engineering Consultants Co., Ltd.	Main Canal		55.3km	11.6km		
10. STUDY TEAM	No. of Members 10 Period Jan. 1985-Mar. 1986 (15 months)	Branch Canal			6.3km		
		D Canal		70.3km	20.0km		
		F Canal		42.0km	42.9km		
		Heen Ganga Intake		7.4m(H) X 74m(L)			
		2. Road System					
		Rehabilitation of Road		18.8km	5.9km		
		Bridge			4 X 50m		
		Imp. Period:					
		4. FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes	EIRR1) 17.10	FIRR1)		
		Conditions and Development Impacts:		EIRR2)	FIRR2)		
		[Conditions]		EIRR3)	FIRR3)		
		Agricultural products and farmers' income are expected to go up by					
		(a) extending irrigation areas during the dry season.					
		(b) growth of yield per unit area					
		(c) agricultural diversification					
		[Development Impacts]					
		Stabilizing agricultural products and upgrading the income by					
		(a) rehabilitating the existing irrigations and the road system					
		(b) ensuring proper operation and maintenance of the system					
		5. TECHNICAL TRANSFER					
		1) OJT					
		2) Acceptance of Trainees (1 person)					
12. EXPENDITURE		Total		198,301 (¥'000)			
		Contracted		184,918			
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY		Topographic and Geological Survey					
2. MAJOR REASONS FOR PRESENT STATUS							
3. PRINCIPAL SOURCE OF INFORMATION		①, ②, ③, ④					

PROJECT SUMMARY (M/P)

Compiled Mar. 1990
Revised Mar. 1996

ASO LKA/A 101/87

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS	
1. COUNTRY	Sri Lanka	1. SITE OR AREA			1. PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
2. NAME OF STUDY	Integrated Rural Development Project for Gampaha District	Gampaha district (1,600sq.km, 1.4 million population)				(Description) In 1987, the Sri Lankan government selected the Model Project for Improvement of Agricultural Production which is one of the priority projects based on this master plan as the first priority project for implementation, and made request to the Japanese government for grant aid to materialize it. Basic design was completed in January 1989. For Phase I, E/N was signed in June 1989 (996 mil. yen) and the construction was completed in February 1991. For Phase II, E/N was signed in June, 1990 (1,075 mil. yen) and the construction was completed in October 1991. As of the present, formal request has been made by the Sri Lankan government for project technical cooperation for the project. (FY1991 Overseas Survey) No additional information (FY1992 Overseas Survey) A formal request for a project-type technical cooperation was made, and a pre-development study mission was dispatched in March 1993. A request for a Grant Aid was made in February 8 1993, for construction and renovation of bridges and improvement of link roads (A total cost of Rp. 370.4 mil.). (FY1993 Overseas Survey) Project-type technical cooperation has not yet commenced. (FY1994 Domestic Survey) The Basic design was completed in January 1994, E/N was signed in April 1994 (Grant Aid 1195 million Yen for Phase I) and E/N was signed in Sept. 1994 (Grant Aid 531 million Yen for Phase II). Phase I work is under implementation and phase II work is under tendering. At present Project-type technical cooperation is proceeding for the first part of the project for Improvement of Agricultural production. (FY1995 Domestic Survey) On Aug., 1995, the Sri Lankan Office submitted a request to Survey work to review a M/P project of 1987, about 10 years ago, to the Embassy of Japan. (FY1995 Overseas Survey) Phase II was commenced in 1994 and is about to complete now. 16 bridges have been constructed and a set of equipment has been provided for each local council and Western Province Road Development Authority.
3. SECTOR	Agriculture/(Agriculture in)General	2. PROJECT COST				
4. REFERENCE NO.		(US\$1,000) Total Cost Local Cost Foreign Cost 1) 22,046 512 21,534 2) 10,710				
5. TYPE OF STUDY	M/P	3. CONTENTS OF MAJOR PROJECT(S)				
6. COUNTERPART AGENCY	Rural Development Bureau, Ministry of Finance, Planning, Racial Problems and State Unification (former Ministry of Project Planning and Implementation)	5 long term and 20 short term objectives were set. 3 priority projects were selected from the short term projects for early development. Short term projects: 1. Development of Agricultural Production 2. Development of Agricultural Infrastructure 3. Development of Rural Industries 4. Development of Human Resources 5. Development of Social Infrastructure Priority projects: 1. Model Project for Improvement of Agricultural Production 2. Development of Human Resources 3. Development of Social Infrastructure The Cost 1) above pertains to the short-term plan, and the Cost 2) to the total of priority projects.				
7. OBJECTIVES OF STUDY	District-wide integrated rural development	4. CONDITIONS AND DEVELOPMENT IMPACTS				
8. DATE OF SAV	1986/4	Implementation of the priority projects is prerequisite for later implementation of all the short term projects which will nurture a conducive socio-economic and physical infrastructure to realize the latter. [Development Impacts] 1. Increased production (minor export crops, general upland crops, paddy) 2. Increased farmers income 3. Social benefit (Improved diet, increased employment opportunities, upgrading of education level, and improved health)				
9. CONSULTANT(S)	Chuo Kaihatsu International Corp. Sanyu Consultants Inc.	5. TECHNICAL TRANSFER				
10. STUDY TEAM	No. of Members 13 Period Jul. 1986-Mar. 1987 (9 months)	1) Training in Japan 2) One through the preparation of the study report 3) Instructions for equipment or materials donated upon the completion				
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	Topographic and Geological Survey	2. MAJOR REASONS FOR PRESENT STATUS				
12. EXPENDITURE	Total 168,183 (¥'000) Contracted 146,293	Project implementation is progressing smoothly. This is due to the fact that the understanding of affected residents was obtained during the master study phase, and that the project places emphasis on the rehabilitation of existing structures.				
		3. PRINCIPAL SOURCE OF INFORMATION				
		①, ②, ③				

和名 ガンパハ県農業総合開発計画

[M/P, Basic Study, Other]

PROJECT SUMMARY (M/P)

Compiled Mar. 1991

Revised Mar. 1996

ASO LKA/A 102/89

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS													
1. COUNTRY	Sri Lanka	1. SITE OR AREA	Kirinda Fishery Harbour Southeastern Coast Fishery population 1,408/ Fishing boats 128/Yearly haul 385t		I. PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued												
2. NAME OF STUDY	Sand Drift in the Southeastern Coast	2. PROJECT COST	<table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">(US\$1,000)</td> <td style="text-align: center;">Total Cost</td> <td style="text-align: center;">Local Cost</td> <td style="text-align: center;">Foreign Cost</td> </tr> <tr> <td style="text-align: center;">1)</td> <td style="text-align: center;">14,437</td> <td></td> <td style="text-align: center;">14,437</td> </tr> <tr> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> </table>		(US\$1,000)	Total Cost	Local Cost	Foreign Cost	1)	14,437		14,437	2)				(Description) According to this study results, grant aid was provided in 1991 to conduct the socio-economic survey and the fishery survey and to formulate the rehabilitation project. In January 1992, B/D was commenced. The content of the rehabilitation project is; Phase I: Extension of the main breakwater by 60m and construction of the sub-breakwater (80m) Phase II: Extension of the main breakwater by 120m and construction of the jetty (120m) and the sub-breakwater (140m) Phase III: Extension of the main breakwater by 20m, rehabilitation of the main breakwater (120m) and construction of sub-breakwater May 1992 E/N signed (2,158 mil. yen, 1992-95) Mar 1993 Phase I is about to be completed. Apr 1993- Phase II is commenced. Upon the completion of Phase III, the Kirinda Fisheries will be in full operation. (FY1991 Overseas Survey) The project is now in progress according to the masterplan. (FY1994 Domestic Survey) The implementation management work has been completed on 12th of Oct. 1994. (FY1995 Domestic Survey) It became a good and vivid fishery harbour, and it is planned to despatch short-term experts (2 for cold storage and one for coastal survey works) on Jan., 1995. (FY1995 Overseas Survey) No additional information.	
(US\$1,000)	Total Cost	Local Cost	Foreign Cost															
1)	14,437		14,437															
2)																		
3. SECTOR	Fisheries/Fisheries	3. CONTENTS OF MAJOR PROJECT(S)	<table style="width: 100%; border: none;"> <tr> <td style="width: 80%;">Extension of Main Breakwater</td> <td style="width: 20%; text-align: center;">200m</td> </tr> <tr> <td>Improvement of Existing Main Breakwater</td> <td style="text-align: center;">100m</td> </tr> <tr> <td>Construction of Sub-breakwater</td> <td style="text-align: center;">230m</td> </tr> <tr> <td>Construction of Jetty</td> <td style="text-align: center;">200m</td> </tr> </table>		Extension of Main Breakwater	200m	Improvement of Existing Main Breakwater	100m	Construction of Sub-breakwater	230m	Construction of Jetty	200m						
Extension of Main Breakwater	200m																	
Improvement of Existing Main Breakwater	100m																	
Construction of Sub-breakwater	230m																	
Construction of Jetty	200m																	
4. REFERENCE NO.		4. CONDITIONS AND DEVELOPMENT IMPACTS With conducting natural condition survey in the NE & SW monsoon season and clarifying numerical simulation for the sand drift, the following proposals were planned. (1) By constructing a Groyne at the Kirinda point, the sand drift of the SW monsoon season will be shifted onto an offshore course. (2) By extension of main breakwater, the coastal sand drift will be prevented and the tranquility within the harbour will be improved for mooring. (3) By establishing another new sub-breakwater in the north of the existing sub-breakwater, siltation will be prevented at harbour mouth.		2. MAJOR REASONS FOR PRESENT STATUS														
5. TYPE OF STUDY	M/P																	
6. COUNTERPART AGENCY	Ministry of Fisheries and Aquatic Resources Executing Agency: Ceylon Fishery Harbours Corporation	5. TECHNICAL TRANSFER 1) Training and study in Japan (2 persons) 2) Guidance about using survey materials and a new method of investigation in Sri Lanka. 3) OJT		3. PRINCIPAL SOURCE OF INFORMATION ①, ②, ③														
7. OBJECTIVES OF STUDY	Countermeasure for Siltation																	
8. DATE OF S/W	1987/10	10. STUDY TEAM No. of Members 6 Period Mar. 1988-Dec. 1989 (16.5 months) <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">29.73</td> <td style="text-align: center;">16.81</td> <td style="text-align: center;">12.92</td> </tr> </table>		Total M/M	Japan	Field	29.73	16.81	12.92	11. ASSOCIATED AND/OR SUBCONTRACTED STUDY Sounding, Topographical survey/Observation of Meteorology and Hydrographic Conditions/Hydraulic model test								
Total M/M	Japan			Field														
29.73	16.81	12.92																
9. CONSULTANT(S)	Nippon Tetrapod Co., Ltd.																	
12. EXPENDITURE	<table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: right;">224,515 (¥000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: right;">203,563</td> </tr> </table>	Total	224,515 (¥000)	Contracted	203,563													
Total	224,515 (¥000)																	
Contracted	203,563																	

和名 南東部沿岸漂砂調査

[M/P, Basic Study, Other]

PROJECT SUMMARY (M/P)

Compiled Mar.1993

Revised Mar.1996

ASO LKA/S 102/91

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS						
1. COUNTRY	Sri Lanka	1. SITE OR AREA	Port of Galle			1. PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued				
2. NAME OF STUDY	Development of the Port of Galle	2. PROJECT COST				(US\$1,000) Total Cost Local Cost Foreign Cost 1) 334,612 89,321 245,291 (US\$1=Rs41) 2)		(Description)			
3. SECTOR	Transportation/Port	3. CONTENTS OF MAJOR PROJECT(S)	Master Plan: (1) Southwest Breakwater : 1,500m (protection from SW Monsoon) (2) Container Terminal : 3 berths (-14m, 1,090m), container yard (2,200 slots) Cargo handling machinery (container cranes, transtainers, tractor trailers), other related facilities and buildings (3) General/Bulk Cargo : 2 berths (-14m x 270m, and -12m x 240m), storage sheds, handling machinery (unloaders, belt conveyors, forklifts) (4) Bunker Oil Berth : 1 Dolphin-type berth (-7.5m x 120m)			In this study, the urgent plan (breakwater 350m) was formulated. After the completion of this study, the implementation of that was requested from Sri Lankan Government. If the breakwaters are constructed, the SLPA says that a foreign shipping line will call at the Port of Galle. (FY1992 Overseas Survey) The Sri Lankan government is now under consideration to adopt the BOT schemes in order to implement this project and will select an implementing firm in June. At the same time, it is examining the possibility to apply for OECF Loan. (FY1994 Domestic Survey) No additional information. (FY1995 Domestic Survey) The firm to implement the development works is not selected as yet. However, the Governmental authorities concerned are continuously investigating the way to materialize this project, i.e. to accept project plans from foreign firms such as "new development of the Port of Galle". (FY1995 Overseas Survey) No additional information.					
4. REFERENCE NO.		4. CONDITIONS AND DEVELOPMENT IMPACTS				[Development impacts] 1) It will enable the direct access to foreign markets from the southern region (e.g., Galle, Matara and Hambantota), contributing to the restructuring and rational function arrangement of Sri Lanka Ports. 2) It will relieve the crowdedness of the Port of Colombo and meet future demands. 3) It will decrease the traffic load of the National Road A2 (from Colombo to Hambantota via Galle) and the coastal railroad, meeting the increase of traffic demands and motorization. 4) It will develop benefits to containers with the improvement of service standards and cost conditions for the shippers and consignees in the hinterland of Galle. 5) The functions of international shipping base of the port of Galle will promote the regional economy. 6) It will be conducive to the development of Kegalla export processing district in the Galle region. The port development will increase the number and production of factories in the Kegalla region. 7) It will build a development core in the southern region, activating the economy through industrialization. Especially the development of cement factories in behind the port and milling factories close to the port will proceed in the future. 8) The agriculture in the southern region will be favorably influenced from the cost reduction of inland transportation compared with the case of using the Port of Colombo. 9) The port construction and management along with regional industrial development will increase employments and income level in the region.					
5. TYPE OF STUDY	M/P	5. TECHNICAL TRANSFER						Through discussion with counterparts, technical transfer was conducted by transmitting the method of development planning, calmness analysis and so on.		2. MAJOR REASONS FOR PRESENT STATUS The project for development of the Southern district is given very important position as for one of the big political items of the State. And the development of the Port of Galle is considered as one of the main component.	
6. COUNTERPART AGENCY	Sri Lanka Ports Authority	7. OBJECTIVES OF STUDY									
8. DATE OF SAW	1990/4	11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	Total M/M Japan Field 68.72 39.65 29.07		3. PRINCIPAL SOURCE OF INFORMATION ①, ②						
9. CONSULTANT(S)	Overseas Coastal Area Development Institute Japan Port Consultants Co., Ltd.	12. EXPENDITURE					Total 232,251 (¥000) Contracted 226,013				
10. STUDY TEAM	No. of Members 10 Period Sep.1990-Nov.1991 (13 months)										

和名: ガール港整備計画

(M/P, Basic Study, Other)

PROJECT SUMMARY (F/S)

Compiled Mar.1994
Revised Mar.1996

ASO LKA/A 305/92

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Sri Lanka	1.SITE OR AREA	Left bank of the Walawe river 180km southeast Colombo			1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY	Walawe Irrigation Upgrading and Extension Project	2.PROJECT COST (US\$1,000)		Total Cost	Local Cost	Foreign Cost	(Description) Basic design is being carried out under grant aid. It consists of main rural roads of 31 km including a bridge across the Walawe river and a water purification plant in Suriyawewa. A request of technical assistance improvement of the existing area was submitted to official, and an appraisal mission was sent. (FY1993 Overseas Survey) An application has been made to OECF for financing & implementation of the Project which includes detailed designs, preparation of contract document and supervision of construction. (FY1994 Domestic Survey) Since January 1994, this project has been under implementation by grant aid. 1994.1.21: Grant Aid E/N 968 million yen (Stage I) 1994.7.28: Grant Aid E/N 1,018 million yen (Stage II) Major components: Construction of main rural roads of 31km including a bridge across the Walawe river and a water purification plant in Suriyawewa 1994.6: OECF loan agreement (E/S) 379 million yen Major components: Rehabilitation of irrigation facilities in the existing irrigation area (2,900ha), Rearrangement of irrigation/drainage water network in a part (1,040ha) of the rain water dependent area, execution of the farm land renovation, stabilization of irrigation water, Upgrading of land use efficiency. Detailed design which includes preparation of environmental monitoring plan, study and proposal of O&M system, and preparation of agricultural extension plan for the Walawe Left Bank Irrigation Upgrading and Extension project. Loan is to be used for consulting/service fees of the D/D etc. (FY1995 Domestic Survey) Apr., 1995 D/D commenced (up to Nov., 1996) Aug., 1995 A review report is submitted to MASL. (FY1995 Overseas Survey) June 1994 The project for improvement of rural infrastructure in Walawe Left Bank is started with the Grant Aid (Dec. 1995 scheduled to be completed) July 1997 Walawe Left Bank irrigation upgrading and extension project is scheduled to be started with the OECF loan and the own fund of GOSL (3,940ha). (June 2005 scheduled to be completed) July 1999 Walawe Left Bank irrigation upgrading and extension project is scheduled to be started (5,140ha). (June 2003 scheduled to be completed. Not financed yet.)
3.SECTOR	Agriculture/(Agriculture in)General		1)	66,045	41,273	24,773	
4.REFERENCE NO.			2)	12,841	7,841	5,000	
5.TYPE OF STUDY	F/S	3.CONTENTS OF MAJOR PROJECT(S)	3)	45,727	18,023	27,705	
6.COUNTERPART AGENCY	Mahaveli Authority of Sri Lanka	(1) Upgrading and rehabilitation of existing irrigation facilities in the MEA are of 2,900 ha, including a total of 190 km of the left bank main canal and subordinate canals and 2,200 related structures;	(2) Construction of irrigation and drainage facilities in the Edension and MEA areas of 6,380 ha including 25 km of the left bank rasis canal 313 km of subordinate irrigation canals, 47 tanks 254 km of drainage canals, about 1,000 structures, and 322 km of canal inspection roads; (3) Land reclamation for 5,240 ha of paddy and upland fields and construction of on-farm works for 6,380 ha; (4) Provision of information including preparation of 1,200 ha of land for 22 villages, 28 schools, 12 health & medical care facilities, 22 drinking water supply system, 140km of roads, 22 administration offices, 6 agro-extension facilities and a development center.				
7.OBJECTIVES OF STUDY	Increasing agricultural production, incomes of rural people, and employment opportunities in the Project and through grading and extension of irrigation facilities and provision of rural infrastructure						
8.DATE OF S/W	1990/11	Imp. Period:					
9.CONSULTANT(S)	Nippon Koei Co., Ltd. Naigai Engineering Co., Ltd.	4.FEASIBILITY AND ITS ASSUMPTIONS					
10.STUDY TEAM	No.of Members 8 Period Jun.1992-Nov.1992(18 months)	Feasibility: Yes/No	EIRR1) 17.30	FIRR1)			
	Total M/M Japan Field	Conditions and Development Impacts:	EIRR2) 14.20	FIRR2)			
	29.31 11.50 17.81	1) Based on the estimated benefits and costs	EIRR3) 13.60	FIRR3)			
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Natural Environment (Vegetation, Animals, Socio-economic Environment) Surveys.	2) Benefit reduction of 10%, cost rise of 10%	3) Benefit reduction of 10%, cost rise of 15%				
12.EXPENDITURE	Total 183,493 (¥000) Contracted 90,005	5.TECHNICAL TRANSFER					
		1) Survey/Investigation and planning method, and its evaluation.	2 MAJOR REASONS FOR PRESENT STATUS The southern area development plan is given top priority in the National Development Plan.				
		2) Training in Japan.					
		3) One through the preparation of the study report.	3.PRINCIPAL SOURCE OF INFORMATION ①, ②				

狀況 (要約表添付文書)

ASO LKA/A 305/92	(F/S)
Name of Walawe Irrigation Upgrading and Extension Project Study	
Country	Sri Lanka
Type of Study	F/S
Sector	Agriculture/(Agriculture in)General
Present Status: Implementing	
(Description)	
<p>Basic design is being carried out under grant aid. It consists of main rural roads of 31 km including a bridge across the Walawe river and a water purification plant in Suriyawewa. A request of technical assistance improvement of the existing area was submitted to official, and an appraisal mission was sent.</p> <p>(FY1993 Overseas Survey) An application has been made to OECF for financing & implementation of the Project which includes detailed designs, preparation of contract document and supervision of construction.</p> <p>(FY1994 Domestic Survey) Since January 1994, this project has been under implementation by grant aid. 1994.1.21:Grant Aid E/N 968 million yen (Stage I) 1994.7.28:Grant Aid E/N 1,018 million yen (Stage II) Major components: Construction of main rural roads of 31km including a bridge across the Walawe river and a water purification plant in Suriyawewa 1994.6:OECF loan agreement (E/S) 379 million yen Major components: Rehabilitation of irrigation facilities in the existing irrigation area (2,900ha), Rearrangement of irrigation/drainage water network in a part (1,040ha) of the rain water dependent area, execution of the farm land renovation, stabilization of irrigation water, Upgrading of land use efficiency. Detailed design which includes preparation of environmental monitoring plan, study and proposal of O&M system, and preparation of agricultural extension plan for the Walawe Left Bank Irrigation Upgrading and Extension project. Loan is to be used for consulting/service fees of the D/D etc.</p> <p>(FY1995 Domestic Survey) Apr., 1995 D/D commenced (up to Nov., 1996) Aug., 1995 A review report is submitted to MASL.</p> <p>(FY1995 Overseas Survey) June 1994 The project for improvement of rural infrastructure in Walawe Left Bank is started with the Grant Aid (Dec. 1995 scheduled to be completed) July 1997 Walawe Left Bank irrigation upgrading and extension project is scheduled to be started with the OECF Loan and the own fund of GOSL (3.940ha). (June 2006 scheduled to be completed) July 1999 Walawe Left Bank irrigation upgrading and extension project is scheduled to be started (5.340ha). (June 2003 scheduled to be completed. Not financed yet.)</p>	

PROJECT SUMMARY (M/P)

Compiled Sep.1995
Revised Mar.1996

ASO LKA/A 103/94

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS																																																					
1. COUNTRY	Sri Lanka	1. SITE OR AREA			1. PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued																																																				
2. NAME OF STUDY	Agricultural and Rural Development for Up-country Peasantry Rehabilitation Programme	Central Uva and Sabaragamuwa Provinces (Total area approx. 19,000 sq.km)			(Description) A part of the proposed project for District-1 is in process in order to be implemented as a grant aid project. (FY1995 Overseas Survey) The main report has been distributed among the relevant Ministries, Department and Institutions. Data and statistics have been used and an action has been taken to implement a proposed project. A request for grant aid has been submitted to the Japanese government.																																																					
3. SECTOR	Agriculture/(Agriculture in)General	2. PROJECT COST																																																								
4. REFERENCE NO.		<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">(US\$1,000)</th> <th style="text-align: center;">Total Cost</th> <th style="text-align: center;">Local Cost</th> <th style="text-align: center;">Foreign Cost</th> </tr> </thead> <tbody> <tr> <td>1)</td> <td style="text-align: right;">34,800</td> <td style="text-align: right;">14,300</td> <td style="text-align: right;">7,400</td> </tr> <tr> <td>2)</td> <td style="text-align: right;">18,200</td> <td style="text-align: right;">20,500</td> <td style="text-align: right;">10,800</td> </tr> </tbody> </table>			(US\$1,000)	Total Cost	Local Cost	Foreign Cost	1)	34,800	14,300	7,400	2)	18,200	20,500	10,800																																										
(US\$1,000)	Total Cost	Local Cost	Foreign Cost																																																							
1)	34,800	14,300	7,400																																																							
2)	18,200	20,500	10,800																																																							
5. TYPE OF STUDY	M/P	3. CONTENTS OF MAJOR PROJECT(S)																																																								
6. COUNTERPART AGENCY	Ministry of Inland Farming villages' Restriction	<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;"></th> <th style="text-align: center;">District-1</th> <th style="text-align: center;">District-2</th> </tr> </thead> <tbody> <tr> <td>Renovation of the irrigation facilities</td> <td style="text-align: center;">766ha</td> <td style="text-align: center;">214.2ha</td> </tr> <tr> <td>Renovation of the rural farm roads</td> <td style="text-align: center;">128.8km</td> <td style="text-align: center;">67.0km</td> </tr> <tr> <td>Renovation of the water supplying facilities for the farm villages</td> <td style="text-align: center;">915m</td> <td style="text-align: center;">2,822m</td> </tr> <tr> <td>Renovation of the various facilities</td> <td style="text-align: center;">9places</td> <td style="text-align: center;">14places</td> </tr> <tr> <td>Preservation of agricultural field</td> <td style="text-align: center;">100ha</td> <td style="text-align: center;">50ha</td> </tr> </tbody> </table>				District-1	District-2	Renovation of the irrigation facilities	766ha	214.2ha	Renovation of the rural farm roads	128.8km	67.0km	Renovation of the water supplying facilities for the farm villages	915m	2,822m	Renovation of the various facilities	9places	14places	Preservation of agricultural field	100ha	50ha																																				
	District-1	District-2																																																								
Renovation of the irrigation facilities	766ha	214.2ha																																																								
Renovation of the rural farm roads	128.8km	67.0km																																																								
Renovation of the water supplying facilities for the farm villages	915m	2,822m																																																								
Renovation of the various facilities	9places	14places																																																								
Preservation of agricultural field	100ha	50ha																																																								
7. OBJECTIVES OF STUDY	Formulation of a Master Plan of rural development, mainly consisted of the development of agricultural industry and farm villages, considering the maintenance of environment	4. CONDITIONS AND DEVELOPMENT IMPACTS																																																								
8. DATE OF SA/	1992/11	<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4">[Development Impacts]</th> </tr> <tr> <th colspan="4">Estimated number of beneficiaries</th> </tr> </thead> <tbody> <tr> <td colspan="4">1. Agricultural activities</td> </tr> <tr> <td style="padding-left: 20px;">Facilities of the market of farm village</td> <td style="text-align: right;">43,560</td> <td colspan="2"></td> </tr> <tr> <td style="padding-left: 20px;">Storage house for agricultural products</td> <td style="text-align: right;">69,578</td> <td colspan="2"></td> </tr> <tr> <td style="padding-left: 20px;">Storage house for materials</td> <td style="text-align: right;">35,214</td> <td colspan="2"></td> </tr> <tr> <td style="padding-left: 20px;">Agricultural training center</td> <td style="text-align: right;">28,500</td> <td colspan="2"></td> </tr> <tr> <td style="padding-left: 20px;">Inspection station for the seedings</td> <td style="text-align: right;">60,600</td> <td colspan="2"></td> </tr> <tr> <td colspan="4">2. Renovation of the irrigation system</td> </tr> <tr> <td></td> <td style="text-align: right;">4,630</td> <td colspan="2"></td> </tr> <tr> <td colspan="4">3. Infrastructure for farm villages</td> </tr> <tr> <td style="padding-left: 20px;">Water supply</td> <td style="text-align: right;">12,704</td> <td colspan="2"></td> </tr> <tr> <td style="padding-left: 20px;">Rural roads</td> <td style="text-align: right;">23,280</td> <td colspan="2"></td> </tr> </tbody> </table>			[Development Impacts]				Estimated number of beneficiaries				1. Agricultural activities				Facilities of the market of farm village	43,560			Storage house for agricultural products	69,578			Storage house for materials	35,214			Agricultural training center	28,500			Inspection station for the seedings	60,600			2. Renovation of the irrigation system					4,630			3. Infrastructure for farm villages				Water supply	12,704			Rural roads	23,280				
[Development Impacts]																																																										
Estimated number of beneficiaries																																																										
1. Agricultural activities																																																										
Facilities of the market of farm village	43,560																																																									
Storage house for agricultural products	69,578																																																									
Storage house for materials	35,214																																																									
Agricultural training center	28,500																																																									
Inspection station for the seedings	60,600																																																									
2. Renovation of the irrigation system																																																										
	4,630																																																									
3. Infrastructure for farm villages																																																										
Water supply	12,704																																																									
Rural roads	23,280																																																									
9. CONSULTANT(S)	Nippon Koei Co., Ltd.				2. MAJOR REASONS FOR PRESENT STATUS																																																					
10. STUDY TEAM	No. of Members 8 Period Feb.1993-Jul.1994 (18 months)																																																									
	<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Total M/M</th> <th style="text-align: center;">Japan</th> <th style="text-align: center;">Field</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">70.03</td> <td style="text-align: center;">44.53</td> <td style="text-align: center;">25.50</td> </tr> </tbody> </table>	Total M/M	Japan	Field	70.03	44.53	25.50																																																			
Total M/M	Japan	Field																																																								
70.03	44.53	25.50																																																								
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	Survey of Farmhouse, Soil Analysis, Topographic Survey																																																									
12. EXPENDITURE	Total 233,429 (¥000) Contracted	5. TECHNICAL TRANSFER			3. PRINCIPAL SOURCE OF INFORMATION																																																					
		1) Training in Japan 2) OJT 3) One through the preparation of the study results			①、②、日本エ管(株)スリランカ事務所																																																					

PROJECT SUMMARY (F/S)

Compiled Sep.1995

Revised Mar.1996

ASO I.KA/S 306/94

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT							
1.COUNTRY	Sri Lanka	1.SITE OR AREA				1.PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input checked="" type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input type="checkbox"/> Discontinued or Cancelled						
2.NAME OF STUDY	Kalu Ganga Water Supply Project for Greater Colombo	Greater Colombo Zone											
3.SECTOR	Public Utilities/Water Supply	2.PROJECT COST		Total Cost	Local Cost	(Description) As for the 1st stage of the project implementation, a grant aid cooperation was requested to the Government of Japan for water intake, water conducting pipeline and filtration plant. For the water supplying and distribution pipelines, Yen Credit have been requested to OECF. The authorized organization in charge of implementation is eagerly hoping to make a part of the project by means of grant aid since they face the financial difficulty. (FY1995 Overseas Survey) No additional information.							
4.REFERENCE NO.		(US\$1,000)	1) 2) 3)	14,305 10,258	10,797 7,148			3,508 3,110					
5.TYPE OF STUDY	F/S	3.CONTENTS OF MAJOR PROJECT(S)											
6.COUNTERPART AGENCY	National Water Supply and Sewage Corporation (NWSDB)	To establish water supply system from the Kalu Ganga as the water resources. (Main Facilities) Taking in facility : 191,000cu.m/d Water conducting pipe : 1,500mm dia., 7,670m in length Filtration plant : 182,000cu.m/d Clean water reservoir : 30,000cu.m Water supplying pipe : 1,650-200mm dia., 37,130m in length Water distribution pipeline : 700-90mm dia., 192,200m in length											
7.OBJECTIVES OF STUDY	To carry on a Feasibility Study on the water supply system of Kalu Ganga to find out an adequate scale in order to supply enough amount of water for greater Colombo Zone after 2000.	8.DATE OF SAW		1993/8									
9.CONSULTANT(S)	Nippon Jogesuido Sekkei Co., Ltd. Nippon Koei Co., Ltd.	4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes/No	EIRR1) EIRR2) EIRR3)	FIRR1) FIRR2) FIRR3)	10.00 12.30						
10.STUDY TEAM	No.of Members 10 Period Dec.1993-Dec.1994(13 months) <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">52.30</td> <td style="text-align: center;">23.10</td> <td style="text-align: center;">29.20</td> </tr> </table>	Total M/M	Japan	Field	52.30	23.10	29.20	Conditions and Development Impacts: [Development Impacts] By means of establishment of the water supply system from Kalu Ganga as the water resources, water will be supplied to the southern part, where do not have water supply as yet, and keep enough amount of water good for the total demand of water of the greater Colombo Zone even after 2000. This project will contribute to the improvement of the health and welfare of inhabitants and to the promotion of the local industries.				2.MAJOR REASONS FOR PRESENT STATUS	
Total M/M	Japan	Field											
52.30	23.10	29.20											
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY	Survey works for water quality, environment, Topography and geology	5.technical transfer		1) OJT 2) Training in Japan 3) One through the preparation of the study report.		The project has been included in the National Development Plan as a priority project.							
12.EXPENDITURE	Total 92,979 (¥'000) Contracted					3.PRINCIPAL SOURCE OF INFORMATION							
						①, ②							

和名 大コロンボ圏給水拡張計画調査

[F/S,D/D]

PROJECT SUMMARY (F/S)

Compiled Mar.1988

Revised Mar.1996

ASE THA/S 301/76

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Thailand	1.SITE OR AREA				1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input checked="" type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY Project of Strengthening and / or Replacement of Steel Bridges on the State Railway		Southern line 1,159 km 110 bridges Northern line 751 km 22 bridges Northeastern line 1,205 km 45 bridges		2.PROJECT COST			
3.SECTOR Transportation/Railway				Total Cost Local Cost Foreign Cost		(Description) The project has been under implementation by the government funds since 1979. Based on the recommendations of the study, 104 bridges have been strengthened so far. 17 of them were replaced by steel bridges. Furthermore, additional 37 bridges have been under various stages of implementation by the national budgets during 1987 and 1991. The remaining 25 are expected to be built after 1992. (FY1991 Overseas Survey) The strengthening works on the eastern line is not concluded yet, because the traffic density remains low. Construction of other parts will be finished in 1993. (FY1993 Overseas Survey) The project except bridges on eastern line is scheduled to be completed in 1996. SRT budgeted at 300 million bahts. To increase loading capacity, the old steel bridges needs strong thening. Otherwise, speed restriction has to be introduced. (FY1994 Domestic Survey) The strengthening works on the main lines was already finished. For the eastern line, the strengthening works have been performed by construction a new prestressed concrete bridge up to Khlong Sip Kao Station (KM.84) in order to upgrade the track standard to match with the new line construction Klong Sip Kao-Kaeng Khoi which will open in near future. Upgrading of the remaining Steel bridge on this line shall be subjected to the result of the Eastern Railway Corridor Study conducted by TDRI. Moreover, the strengthening of some remaining steel bridges on the branch lines have to be revised due to budget constraint and if it is necessary the works will be integrate in the track rehabilitation scheme. (FY1995 Domestic Survey) No additional information. (FY1995 Overseas Interview Survey) The reinforcement of 214-span-bridge was designed on DL-16 standard weight. Most all of the bridges has been reinforced or replaced already.	
4.REFERENCE NO.				1) 16,683 8,656 8,027			
5.TYPE OF STUDY		F/S		2) (US\$1,000)			
6.COUNTERPART AGENCY State Railway of Thailand				3) (US\$1=20Bahts)			
7.OBJECTIVES OF STUDY Investigation, from the aspects of design and work execution, of the existing 214 spans of steel bridges requiring strengthening and/or replacement		3.CONTENTIS OF MAJOR PROJECT(S) The number of steel bridge on the whole railway in Tailand become 1,397 (2,853 span) at the end of 1976. 169 of them (214 span) are recommended to need improvement by the study of VKRAS(England). After this study, government of Thailand proposed gov. of Japan to cooperate a now detailed study of strengthening and replacement of them. So the purpose of this study are following: 1) Evaluating strength of 214 span 2) Suggesting a standard design and method of improvement / strengthening / replacement. 3) Estimating a cost of this project. Proposals: Of the 214 spans: 197 spans are to be repaired and strengthened. 17 spans are to be replaced with the construction of new bridges					
8.DATE OF S/W		1975/10		Imp. Period: 1977. -1981.			
9.CONSULTANT(S) Japan Railway Technical Service		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes/No			
10.STUDY TEAM				EIRR1) HRR1) EIRR2) HRR2) EIRR3) HRR3)			
No.of Members 17 Period Jan.1976-Nov.1976(10 months)		Conditions and Development Impacts: 1)Improvement of bridges constituting greater danger to train operation will be given high priority. 2)Disturbance to train operation during the works will be minimized. 3)According to the current traffic density, the lines considered likely to generate more profit through improvement work will be given priority. 4)The work is scheduled to be accomplished in five years. 5)The work is planned in relation to the schedule for replacement of timber bridges. 6)Steel materials will be imported, but the processing of the members for repair and strengthening will be done by fabricators in Thailand. 7)The new bridges required for replacement will be imported from foreign countries. The cost estimation is based on prevailing rate during April 1976, with assumption of 10% per year as the rate of subsequent price escalation. It was considered beneficial for SRT to receive a few advisors for its technical and financial needs for the initial one or two years. *Above implementation period is 5 year [Development Impacts] The nation's railway capacity and it operation would be improved so much by implementation of this bridge project.					
Total M/M Japan Field 87.27 66.60 20.67							
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY None		5.TECHNICAL TRANSFER Investigations were conducted with the cooperation of counterparts. Methodology training for strengthening steel bridges in Japan (5 trainees).					
12.EXPENDITURE						2.MAJOR REASONS FOR PRESENT STATUS	
Total 106,843 (¥000)							
Contracted 108,230						3.PRINCIPAL SOURCE OF INFORMATION ①, ②, ③	

PROJECT SUMMARY (F/S)

Compiled Mar. 1990
Revised Mar. 1996

ASE THA/A 301/77

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY		West bank tract of the Greater Chao Phraya, center of Ayutthaya Province					
Irrigated Agricultural Development Project in the West Bank Tract of the Greater Chao Phraya		2. PROJECT COST		Total Cost	Local Cost	Foreign Cost	
		(US\$1,000)	1)	36,200	17,640	18,560	
		US\$1=20B in 1985		2)			
				3)			
3. SECTOR		3. CONTENTS OF MAJOR PROJECT(S)				(Description) 1979.6.14 OECF L/A signed (E/S, 150 million yen) 1979.6-1982.2 Detail design undertaken (Sanyu Consultants Inc.) 1982.7.16 9th OECF L/A signed (2.65 billion yen) Of which, construction equipment 2.02 billion yen consultation service 390 million yen contingency 240 million yen 1982.6 Construction started 1988.7 Yen loan expired. Construction continued by ALRO. (FY 1991 Overseas Survey) Construction completed in 1990 by the OECF loan. OECF Loan: - Circle embankment - Pump stations - Irrigation and drainage canals - On-farm development (tertiary irrigation and drainage canals and farm roads) - Rehabilitation and improvement of rural roads and bridges. (FY 1993 Overseas Survey) No additional information. (FY1994 Domestic Survey) No additional information after the completion of the project in 1990.	
Agriculture/(Agriculture in)General		Irrigation Area: 10,542 ha Circle Embankment : 114.5 km Pump station for irrigation and drainage : 3 station Main irrigation canal/secondary, tertiary canal : 36km/432km Main drainage canal/secondary, tertiary canal: 30km/494km Main street/farm road : 177km/404km Village water supply : 4 places					
4. REFERENCE NO.		* Above project costs are in 1985 prices.					
5. TYPE OF STUDY		F/S					
6. COUNTERPART AGENCY		Agricultural Land Reform Office, Ministry of Agriculture and Cooperative					
7. OBJECTIVES OF STUDY		To study the agricultural development of irrigation area in the west bank tract of the Greater Chao Phraya					
8. DATE OF SAV		/					
9. CONSULTANT(S)		Sanyu Consultants Inc.					
10. STUDY TEAM		Imp. Period: 1977.10-1983.9 4. FEASIBILITY AND ITS ASSUMPTIONS Feasibility: Yes EIRR1) 16.00 FIRR1) EIRR2) FIRR2) EIRR3) FIRR3) Conditions and Development Impacts: [Conditions] 1. Pilot farm of about 500ha to show intensive irrigated agriculture 2. Cultivation of double cropping of paddy (HYV) under the sufficient management of water 3. Dissemination of agricultural technology and establishment of training center 4. Establishment of farmers' organization such as maintenance management and agricultural cooperative 5. Implementation of village development plan including improvement of agricultural environment [Development Impacts] Advancement of land use, Increase of agricultural production, Increase of farmers' income, Reduction of flood damage, Rise in living standards					
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY							
12. EXPENDITURE		5. TECHNICAL TRANSFER					
Total		1) OJT					
Contracted		2) Training in Japan (6 trainees)					
		86,198 (¥'000)					
		80,831					
		3. PRINCIPAL SOURCE OF INFORMATION					
		①, ②, ④					
		2. MAJOR REASONS FOR PRESENT STATUS					
		A part of land for irrigation canal cannot be purchased due to rise in land price in and around Bangkok recently, and construction has not been completed.					

PROJECT SUMMARY (D/D)

Compiled Mar. 1990
Revised Mar. 1996

ASE THA/S 401/77

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA		Bangkok Metropolitan Area		1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY		2. PROJECT COST		Total Cost	Local Cost		
Bangkok Telephone Network Project : Junction Lines		(US\$1,000)		1)			
				2)			
				3)			
3. SECTOR		3. CONTENTS OF MAJOR PROJECT(S)				(Description) Jul. 1978 OECF loan agreement (1,464 million yen)	
Communications & B/Telecommunication		Contents		Scale			
4. REFERENCE NO.		Construction of Junction cable		250,000 Pair-km			
5. TYPE OF STUDY							
D/D							
6. COUNTERPART AGENCY							
Telephone Organization of Thailand (TOT)							
7. OBJECTIVES OF STUDY							
D/D of junction cable network and five local cable networks							
8. DATE OF S/W		Imp. Period:					
1977/2							
9. CONSULTANT(S)		4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes/No			
Nippon Telecommunication Consulting Co., Ltd.				EIRR1) FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)			
		Conditions and Development Impacts:					
		-To full of demand in site area -This project come under construction of junction network for 3rd M/P Package 1, Phase 1					
10. STUDY TEAM							
No. of Members 13							
Period May. 1977-Feb. 1978 (9 months)							
Total M/M		Japan		Field			
		29.73		70.77			
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY							
12. EXPENDITURE		5. TECHNICAL TRANSFER					
Total 260,588 (¥000)		Many counterparts engineers participated in preparation of D/D					
Contracted 251,129							
		2. MAJOR REASONS FOR PRESENT STATUS					
		Telephone demand in the metropolitan area is urgent.					
		3. PRINCIPAL SOURCE OF INFORMATION					
		①②					

和名 バンコク市内線路網実施設計

PROJECT SUMMARY (F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 305/78

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																																										
1. COUNTRY	Thailand	1. SITE OR AREA	Phetchabun - Chai Badan, Northern Region			1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Discontinued or Cancelled <input type="checkbox"/> Processing																																									
2. NAME OF STUDY	Phetchabun - Chai Badan Highway Project	2. PROJECT COST	Total Cost	Local Cost	Foreign Cost																																											
		(US\$1,000)	1) 16,600	9,400	7,200																																											
		(US\$1=20Bahts)	2)																																													
		3)																																														
3. SECTOR	Transportation/Road	3. CONTENTS OF MAJOR PROJECT(S)	Three Alternatives of route: I Improvement of local community II New land development III Improvement of transportation																																													
4. REFERENCE NO.																																																
5. TYPE OF STUDY	F/S	1. Optimal route (I+II)	Tha Maduk - Rang Yoi - Si Thep - Wichian Buri - Sap Bon - Nong Daeng - Pak Bot - Noen Sadso - Khok Charoen - Yang Lat - Tham Nam Bang - Nam Ron - Phetchabun																																													
6. COUNTERPART AGENCY	Department of Highway	2. Road length																																														
7. OBJECTIVES OF STUDY	Road Construction	1) Improvement	130.1 km (85%)	(FY1991 Overseas Survey) No additional information. (FY1992 Overseas Survey) 1,366 million yen was appropriated for this project from the OECF loan. The total cost for the project was 171.42 million bahts. The construction was started in June 1981 for the Yang Lat-Phetchabun route and was completed in September 1981 for Sithep-Wichian Buri route. The total length was 149.2 km. (FY1994 Domestic Survey) No information.																																												
		2) New construction	21.2 km (15%)																																													
		Total	151.3 km																																													
		3. Pavement type																																														
		1) SBST (asphalt)	94.2 km (62%)																																													
		2) Laterite	57.1 km (38%)																																													
		Total	151.3 km																																													
		4. Road width																																														
		1) Formation width	9.0 m																																													
		2) Pavement width	5.5 m																																													
8. DATE OF SAV	1978/2	Imp. Period:	1980.4-1982.12																																													
9. CONSULTANT(S)	Nippon Koei Co., Ltd. Katahira & Engineers International	4. FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes	EIRR1) 20.40 EIRR2) EIRR3)	FIRR1) FIRR2) FIRR3)																																											
10. STUDY TEAM	No. of Members 12 Period Mar. 1978-Mar. 1979 (9 months)	Conditions and Development Impacts: [Conditions] Traffic forecast 1) Passenger traffic forecasted by trip rates obtained from a home interview survey and projected population increase. 2) Freight traffic forecasted by transportation demand of agricultural products. [Development impacts] 1. Benefits (million baht)																																														
	Total M/M Japan Field	<table style="width: 100%; border-collapse: collapse;"> <tr> <td></td> <td style="text-align: center;">1983</td> <td style="text-align: center;">1989</td> <td style="text-align: center;">1997</td> <td colspan="2"></td> </tr> <tr> <td>1) Road users' cost saving</td> <td style="text-align: center;">47.8</td> <td style="text-align: center;">55.3</td> <td style="text-align: center;">62.4</td> <td colspan="2"></td> </tr> <tr> <td>2) Incremental net added value of agricultural products</td> <td style="text-align: center;">15.2</td> <td style="text-align: center;">51.0</td> <td style="text-align: center;">46.3</td> <td colspan="2"></td> </tr> <tr> <td>3. Saving transportation cost</td> <td colspan="5"></td> </tr> <tr> <td>4. Increase in farmers' income</td> <td colspan="5"></td> </tr> <tr> <td>5. Development of better transportation</td> <td colspan="5"></td> </tr> <tr> <td>6. Reduction of running cost</td> <td colspan="5"></td> </tr> </table>						1983	1989	1997			1) Road users' cost saving	47.8	55.3	62.4			2) Incremental net added value of agricultural products	15.2	51.0	46.3			3. Saving transportation cost						4. Increase in farmers' income						5. Development of better transportation						6. Reduction of running cost					
	1983	1989	1997																																													
1) Road users' cost saving	47.8	55.3	62.4																																													
2) Incremental net added value of agricultural products	15.2	51.0	46.3																																													
3. Saving transportation cost																																																
4. Increase in farmers' income																																																
5. Development of better transportation																																																
6. Reduction of running cost																																																
	44.33 26.33 18.00																																															
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY																																																
12. EXPENDITURE		5. TECHNICAL TRANSFER																																														
Total	108,742 (¥'000)	(1) OJB (2) JICA training (3) Joint reporting																																														
Contracted	101,688																																															
		2. MAJOR REASONS FOR PRESENT STATUS				3. PRINCIPAL SOURCE OF INFORMATION																																										
		(1) Big Development effects (2) Favorable financial status (3) High priority (4) Strong promotion by department of Highway																																														
		①, ②, ③, ④																																														

PROJECT SUMMARY (F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 303/78

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT							
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input checked="" type="checkbox"/> Discontinued or Cancelled						
2. NAME OF STUDY	Separate System of Metropolitan Water Supply in Bangkok	2. PROJECT COST (US\$1,000)	1) Total Cost 73,121	2) Local Cost	3) Foreign Cost	(Description) The project was completed by the OECF financing. Jun. 1979 OECF L/A signed (8,400 million yen) Sep. 1984 OECF L/A signed (10,710 million yen) Completed in 1989 Oct. 1985 OECF L/A signed (2,985 million yen) Completed in 1989 Nov. 1988 OECF L/A signed (4,380 million yen) To be completed in June 1993 Sep. 1991 OECF L/A signed (8,638 million yen) Scheduled to be completed in Aug. 1995 Jan. 1993 OECF L/A signed (16,969 million yen) Sep. 1993 OECF L/A signed (5,599 million yen) (FY1994 Domestic Survey) (FY1995 Domestic Survey) No additional information. The central system is carrying on for the implementation of this project. (FY1995 Overseas Survey) MWA has been implementing Bangkok Water Supply Project since 1980. The most parts of the project is through Central System. The project is financed by MWA for 25% of the total cost, OECF for 30-40%, and bond issuance for the rest. JICA studied Separate System, however OECF finance is for Central System.							
3. SECTOR	Public Utilities/Water Supply	3. CONTENTS OF MAJOR PROJECT(S)	1. Project: Separate System of Metropolitan Water Supply Project surrounding Bangkok 2. Area: The 9 Amphoes surrounding Bangkok city and the related housing and industrial project areas (168sq.km) 3. Target year: Completion set at 2000 (Start to work in 1982) 4. Water source: 8 Amphoes (excluding Nong Khaem) and Bang Chan from groundwater. The others from Central System. 5. Groundwater: 33 Deep Wells built in 9 areas.										
4. REFERENCE NO.		4. FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes/No	EIRR1) EIRR2) EIRR3)	FIRR1) FIRR2) FIRR3)								
5. TYPE OF STUDY	F/S	Conditions and Development Impacts: [Conditions] 1. Population density in served area: 1,500/sq.km (minimum) 2. Population in served area: 363,900 (in 2000) 3. House connection ratio: 75% (in 2000) 4. Daily max. demand: 77,800cu.m [Development impacts] 1. Supply of clean water 2. Rational system realized This plan was independent system; but will be advanced in connection with existing Central Water Supply System in Bangkok city.											
6. COUNTERPART AGENCY	Metropolitan Water Works Authority	8. DATE OF S/W	1977/1	Imp. Period: 1981. -2000.									
7. OBJECTIVES OF STUDY	Water Service plan	9. CONSULTANT(S)	Pacific Consultants International		2. MAJOR REASONS FOR PRESENT STATUS								
10. STUDY TEAM	No. of Members 14 Period May. 1977-Jul. 1978 (15 months) <table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total M/M</td> <td style="text-align: center;">Japan</td> <td style="text-align: center;">Field</td> </tr> <tr> <td style="text-align: center;">24.30</td> <td style="text-align: center;">7.20</td> <td style="text-align: center;">17.10</td> </tr> </table>	Total M/M	Japan	Field	24.30	7.20	17.10	11. ASSOCIATED AND/OR SUBCONTRACTED STUDY				3. PRINCIPAL SOURCE OF INFORMATION	①, ③, ④
Total M/M	Japan	Field											
24.30	7.20	17.10											
12. EXPENDITURE	<table style="width: 100%; border: none;"> <tr> <td style="text-align: center;">Total</td> <td style="text-align: center;">143,869 (¥'000)</td> </tr> <tr> <td style="text-align: center;">Contracted</td> <td style="text-align: center;">44,780</td> </tr> </table>	Total	143,869 (¥'000)	Contracted	44,780	12. TECHNICAL TRANSFER - Overseas training for counterpart staff - Inspection of water purification plant							
Total	143,869 (¥'000)												
Contracted	44,780												

PROJECT SUMMARY (F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 302/78

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT		
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input checked="" type="checkbox"/> Discontinued or Cancelled	
2. NAME OF STUDY	Pattaya Tourism Development	Pattaya, Ko lan Island						
3. SECTOR	Tourism/ (Tourism in) General	2. PROJECT COST		Total Cost	Local Cost	Foreign Cost		
4. REFERENCE NO.		(US\$1,000)	1)	368,000	193,000	175,000		
5. TYPE OF STUDY	F/S	(US\$1=20Bahts)	2)					
6. COUNTERPART AGENCY	Dept. of Tourism		3)					
7. OBJECTIVES OF STUDY	Establishment plan of infrastructure for tourism	3. CONTENTS OF MAJOR PROJECT(S)				(Description) The project is under construction with government funds. (FY1991 Overseas Survey) The Thai Government (National Economic and Social Development Board) applied for an OECF Loan in 1979 but was not accepted. A new local administrative office was established according to the new development plan and the new detailed design prepared by the Department of Town and Country Planning. The project has been revived in a new JICA study "Pattaya Tourism Development." (FY1994 Domestic Survey) No information.		
8. DATE OF SAV	1976/11	Imp. Period: 1977. -1996.						
9. CONSULTANT(S)	Pacific Consultants International Nippon Tetrapod Co., Ltd.	4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility:	EIRR1) 26.00			HRR1)
10. STUDY TEAM	No. of Members 12 Period Dec. 1976-Dec. 1977 (12 months)			No	EIRR2)			HRR2)
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY		Conditions and Development Impacts: Private investment has been made in tourism industry while public sector has not invested; therefore, inappropriate development continues and tourism resource has not been utilized. This project aims to utilize this resource and contribute to tourism development.				2. MAJOR REASONS FOR PRESENT STATUS		
12. EXPENDITURE	Total 335,524 (¥'000) Contracted 206,380	5. TECHNICAL TRANSFER				3. PRINCIPAL SOURCE OF INFORMATION		
		Overseas training for 6 trainees						
						①, ②		

和名 パタヤ地区基盤整備計画

PROJECT SUMMARY (M/P)

Compiled Mar. 1990
Revised Mar. 1996

ASETHA/A 101/79

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDY RESULTS																	
1. COUNTRY	Thailand	1. SITE OR AREA	Mid and down stream of Mae Klong River Basin : area 490,000ha			1. PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued																
2. NAME OF STUDY	Irrigated Agricultural Development in the Greater Mae Klong River	2. PROJECT COST	<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 10%;"></th> <th style="width: 10%;"></th> <th style="width: 10%;">Total Cost</th> <th style="width: 10%;">Local Cost</th> <th style="width: 10%;">Foreign Cost</th> </tr> </thead> <tbody> <tr> <td>(US\$1,000)</td> <td>1)</td> <td>441,300</td> <td>264,780</td> <td>176,520</td> </tr> <tr> <td></td> <td>2)</td> <td>285,300</td> <td>171,180</td> <td>114,120</td> </tr> </tbody> </table>						Total Cost	Local Cost	Foreign Cost	(US\$1,000)	1)	441,300	264,780	176,520		2)	285,300	171,180	114,120	(Description) A feasibility study was conducted in 1979 on Kamphaeng Saen irrigation and agricultural development, but the project was not implemented, partly owing to the change of government policy. (FY 1991 Overseas Survey) The Phase II Development Program is being undertaken and will be finished in 1994. A review study may be necessary in the near future. (FY 1994 Domestic Survey) This project targeted the land consolidation (about 2,000,000 rai) on the left bank of Greater Mae Klong river. The right bank area (700,000 rai) of the river had been implemented using IBRD loan as the Phase I. Following this, the project area was also decided to be implemented with IBRD loan. (FY1995 Domestic Survey) The construction works of the Phase-II, which are targeted the land consolidation for about 2,000,000 rai on the left bank of Greater Mae Klong River, has been commenced the implementation on 1990, and will be completed on 1995. Total budget of this construction is about 1.344 billion bahts from the World Bank Loan and the allocated budget by the government.	
		Total Cost	Local Cost	Foreign Cost																			
(US\$1,000)	1)	441,300	264,780	176,520																			
	2)	285,300	171,180	114,120																			
3. SECTOR	Agriculture/(Agriculture in)General	3. CONTENTS OF MAJOR PROJECT(S)	1. Short-term development plan 1) Improvement of field of 185,900ha 2) Repair of irrigation and drainage canals of 1,082km 2. Long-term development plan 1) Improvement of field of 174,200ha 2) Repair of irrigation and drainage canals of 56km 3) Construction of irrigation and drainage canals of 345 km * Cost 1) is for the short-term development plan and cost 2) is for the long-term development plan excluding the short-term development plan.																				
4. REFERENCE NO.		4. CONDITIONS AND DEVELOPMENT IMPACTS				2. MAJOR REASONS FOR PRESENT STATUS																	
5. TYPE OF STUDY	M/P																						
6. COUNTERPART AGENCY	Ministry of Agriculture and Cooperatives	1. The production of rice will be 1.7 times in 30 years (total amount 2,400,000t) 2. The production of Sugarcane will be 1.3 times in 30 years (total amount 1,400,000t) * Of 2,400,000t of rice production, 1,000,000t will be possible to be exported. 3. EIRR 26.5%				3. PRINCIPAL SOURCE OF INFORMATION ①, ②																	
7. OBJECTIVES OF STUDY	To formulate the on-farm improvement plan of Mae Klong area in order to increase the rice production and the efficiency of water usage.																						
8. DATE OF S/W	1977/7	5. TECHNICAL TRANSFER																					
9. CONSULTANT(S)	Sanyu Consultants Inc.																						
10. STUDY TEAM	No. of Members 20 Period Dec. 1977-Mar. 1980 (28 months) <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">Total M/M</th> <th style="width: 30%;">Japan</th> <th style="width: 30%;">Field</th> </tr> </thead> <tbody> <tr> <td>130.19</td> <td>45.83</td> <td>84.36</td> </tr> </tbody> </table>	Total M/M	Japan	Field	130.19	45.83	84.36																
Total M/M	Japan	Field																					
130.19	45.83	84.36																					
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	None																						
12. EXPENDITURE	<table style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td style="width: 10%;">Total</td> <td style="width: 10%;">346,684 (¥'000)</td> </tr> <tr> <td>Contracted</td> <td>242,550</td> </tr> </tbody> </table>	Total	346,684 (¥'000)	Contracted	242,550	OJT																	
Total	346,684 (¥'000)																						
Contracted	242,550																						

和名 メクロン川マスタープラン

(M/P, Basic Study, Other)

PROJECT SUMMARY (M/P)

Compiled Mar.1986
Revised Mar.1996

ASE THA/S 101/79

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDY RESULTS	
1.COUNTRY	Thailand	1.SITE OR AREA	Bangkok Metropolitan Area		1.PRESENT STATUS	<input checked="" type="checkbox"/> In Progress or In Use <input type="checkbox"/> Delayed <input type="checkbox"/> Discontinued
2.NAME OF STUDY	Bangkok Suburban Transportation Project	2.PROJECT COST	Total Cost	Local Cost	Foreign Cost	(Description) The project proposed by the study was not included in the Sixth National Development Plan. No progress was made in upgrading the railway service in downtown Bangkok. (FY 1991 Overseas Survey) The project was integrated in the Infrastructure Section of the Fourth National Economic and Social Development Plan. (FY1993 Overseas Survey) Because of the following two reasons, the project didn't continue. - Government gave the first priority to solve traffic problems in town. - The existing railway system in the suburban area could be used. SRT officials said that no new lines in Bangkok suburban were to be built. (FY1994 Domestic Survey) No information. (FY1995 Overseas Survey) This project was transferred from ETA to MRTA (Metropolitan Rapid Transit Agency) in 1992. Some part of the "Hopewell", proposed projects, such as Ban Su-Don Muang line, were implemented by a Hong Kong firm, Hopewell.
3.SECTOR	Transportation/Railway	(US\$1,000)	1) 834,400			
4.REFERENCE NO.		(US\$1=260Yen)	2)			
5.TYPE OF STUDY	M/P	3.CONTENT(S) OF MAJOR PROJECT(S)				
6.COUNTERPART AGENCY	Expressway and Rapid Transit Authority(ETA), Royal State Railway of Thailand(SRT)	Formulation of Master Plan for large scale transportation for Bangkok and its surrounding areas. Basic policy is to make the utmost use of existing railway system as the transportation means for people commuting to work. Main components are: Suburban lines(new construction) 6 lines(11 segments) total length 102.8km Improvement of existing lines (double track,new stations, signal and communication) total length 151 km Rolling stock(Year 2000) Suburban line 756 or 478 (depending on fare) Existing national railway 318				
7.OBJECTIVES OF STUDY	Transportation Plan	4.CONDITIONS AND DEVELOPMENT IMPACTS				
8.DATE OF SAW	1978/7	This project is expected to mitigate traffic congestion in inner city and suburban area in BANGKOK. Furthermore, utilization of existing rail line is also expected to contribute to improve financial condition of SRT, and to contribute to induce urban structure of Bangkok to appropriate direction with corridor development.				
9.CONSULTANT(S)	Pacific Consultants International	5. TECHNICAL TRANSFER				
10.STUDY TEAM	No.of Members 7 Period Oct.1978-Aug.1979(11 months)	Training in Japan				
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		12.EXPENDITURE			2.MAJOR REASONS FOR PRESENT STATUS	
		Total	90,378 (¥'000)	This project is an extension from downtown to suburban areas. Therefore, F/S is unlikely to be conducted unless progress is made on projects for the downtown area.		
		Contracted	85,377			3.PRINCIPAL SOURCE OF INFORMATION
					①, ②, ③	

PROJECT SUMMARY (F/S)

Compiled Mar.1986
Revised Mar.1996

ASE THA/S 306/79

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT		
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled	
2. NAME OF STUDY Nong Bua - Ban Lam Chi Bon Highway Project		Nakkon Sawan Prefecture, Chiyaphum Prefecture						
3. SECTOR Transportation/Road		2. PROJECT COST		Total Cost	Local Cost	Foreign Cost		
4. REFERENCE NO.		(US\$1,000)		30,600	17,300	13,300		
5. TYPE OF STUDY F/S		US\$1=20Bahts		1)	2)	3)		
6. COUNTERPART AGENCY Department of Road Ministry of communication		3. CONTENTS OF MAJOR PROJECT(S)				(Description) 1983 Sep. OECF loan agreement (5,770 million yen) 1984 Dec. D/D completed 1986 Feb. Construction commenced 1988 Aug. Construction completed * Contents of OECF Loan(The Productive Road Construction Project 3) 1. prefectural road construction in the northern and north-eastern Thailand.(165km) 2.rehabilitation works of 8 routes in the northern area.(293.9km) 3.consulting costs. (FY1991 Overseas Survey) No additional information. (FY1992 Overseas Survey) 2,517 million yen was appropriated for the project from the OECF loan. The total cost for the project was 348.70 million bahts. The total length was 162.2 km. (FY1994 Domestic Survey) No information.		
7. OBJECTIVES OF STUDY Provincial road improvement		Three alternatives of route: I Nong Bua-Wang Wat II Wang Wat-Tha Pong III Tha Pong-Lup Pho 1. Objective: The project aims at accelerating socio-economic development in rural areas and, at the same time, at providing an inter-provincial road, in an east-west direction, to supplement the existing highway network which are mainly of radial type connection with Bangkok. 2. Optimal route: Nong Bua-Nong Ngu Luam-Sap Bon-Wang Wat-Tha Pong-Nong Bua Rave-Lup Pho. 3. Road length 1) Improvement: 41.9km 2) Newconstruction: 112.8km total 154.7km 4. Road width 1) Formation width: 9.0-10.0m 2) Pavement width (SBST): 5.5-6.0m 5. Surface treatment 1) SBST: 105.0km (68%) 2) Soil aggregate surface: 49.7km (32%)						
8. DATE OF SAW 1978/7		Imp. Period: 1981.4-1983.12						
9. CONSULTANT(S) Nippon Koei Co., Ltd. Katahira & Engineers International		4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 21.70 EIRR2) EIRR3)			FIRR1) FIRR2) FIRR3)
10. STUDY TEAM No. of Members 11 Period Jun.1979-Feb.1980(8 months) Total M/M Japan Field 43.40 18.50 24.90		Conditions and Development Impacts: [Conditions] 1. The method of optimum route selection Evaluation of the alternatives was made mainly according to the following three factors: 1) Construction cost 2) Route length which reflects on the road users' costs 3) Availability of newly cultivatable land along the route which reflects the magnitude of agricultural benefits. 2. Uncultivated land available for future development: 286,000 rai 3. Estimation of passenger traffic was based on the projected population and the person trip rate model derived from the home interview survey. [Development impacts] 1. Benefits (million Baht) 1984 1990 1998 Road users' cost saving 113.6 130.7 161.6 Agricultural development benefit 1.2 58.8 55.4 2. Agricultural development 1) Increase of productivity (paddy) 2) Acceleration of rate of opening of new land 3) Increase of farm gate price						
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY Topographic Survey Traffic Survey		5. TECHNICAL TRANSFER				2. MAJOR REASONS FOR PRESENT STATUS		
12. EXPENDITURE		(1) O/T: Discussion about route selection. Traffic forecast and development benefits. (2) Trainee: 1 engineer				- large development impact - good linkage with other major road - high priority - effective administration		
Total 104,520 (¥'000) Contracted 103,547								3. PRINCIPAL SOURCE OF INFORMATION ①, ②, ③, ④

PROJECT SUMMARY (F/S)

Compiled Mar. 1990

Revised Mar. 1996

ASE THA/A 303/80

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																			
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input checked="" type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input type="checkbox"/> Discontinued or Cancelled																		
2. NAME OF STUDY Mae Wang-Kew Lom Irrigated Agriculture Development Project		Lampang City, Lampang Province, northern part of Thailand area 22,700 ha																							
3. SECTOR Agriculture/(Agriculture in)General		2. PROJECT COST				(Description)																			
4. REFERENCE NO.		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;"></td> <td style="width: 10%; text-align: center;">1)</td> <td style="width: 15%; text-align: center;">Total Cost</td> <td style="width: 15%; text-align: center;">Local Cost</td> <td style="width: 15%; text-align: center;">Foreign Cost</td> </tr> <tr> <td>(US\$1,000)</td> <td style="text-align: center;">34,880</td> <td style="text-align: center;">19,506</td> <td style="text-align: center;">15,374</td> <td></td> </tr> <tr> <td>US\$1=20B in 1979</td> <td style="text-align: center;">2)</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: center;">3)</td> <td></td> <td></td> <td></td> </tr> </table>							1)	Total Cost	Local Cost	Foreign Cost	(US\$1,000)	34,880	19,506	15,374		US\$1=20B in 1979	2)					3)	
	1)	Total Cost	Local Cost	Foreign Cost																					
(US\$1,000)	34,880	19,506	15,374																						
US\$1=20B in 1979	2)																								
	3)																								
5. TYPE OF STUDY F/S		3. CONTENTS OF MAJOR PROJECT(S)				<p>At the time of the JICA study, the Thai Government enacted the Law of Agricultural Infrastructure Improvement, and was vigorously promoting the improvement of agricultural infrastructure to expand the area of double cropping.</p> <p>However, the proposed project was not implemented, partly because it presupposed farmers' sharing of the development cost, which turned out to be much higher than expected, and partly because the external debts of the Thai Government increased.</p> <p>(FY 1991 Overseas Survey) No additional information.</p> <p>(FY 1993 Overseas Survey) E/S by OECF loan (L/A in 1982, July 16 of 430 million USD) was conducted in 1982, however due to changes in development policy of the government of Thailand and the suspension of construction of Kuu Khong Ma Dam which was supposed to be one of the water source for the project, the project was not implemented yet.</p> <p>(FY1994 Domestic Survey) The priority of the on-farm development which is major component of this project is low because of the change of government policy about agricultural development strategy.</p> <p>F/S of Kew Kohma dam was decided to start by a local consulting firm with the budget of 23 million Baht.</p> <p>(FY1995 Domestic Survey) On-farm development project has been suspended due to changes in policy. The F/S of Kiew Kor Mah Dam, as for a new water resources, will be commenced by a domestic consultant on Oct., 1995.</p>																			
6. COUNTERPART AGENCY RID (Royal Irrigation Department), Ministry of Agriculture and Cooperatives		Irrigation area : 22,700ha Main irrigation canal : 100.12 km Tributary irrigation canal : 79.65 km Main drainage canal : 240.77 km Field improvement : 15,400 ha * Above costs are in 1979 prices.																							
7. OBJECTIVES OF STUDY To make integrated agricultural development plan by the improvement of agricultural infrastructure based on the field renovation.		8. DATE OF SAV 1979/2				Imp. Period: 1980.10-1987.9																			
9. CONSULTANT(S) Sanyu Consultants Inc.		4. FEASIBILITY AND ITS ASSUMPTIONS Feasibility: Yes <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 15%;"></td> <td style="width: 10%; text-align: center;">EIRR1)</td> <td style="width: 15%; text-align: center;">27.10</td> <td style="width: 15%; text-align: center;">FIRR1)</td> </tr> <tr> <td></td> <td style="text-align: center;">EIRR2)</td> <td style="text-align: center;">25.30</td> <td style="text-align: center;">FIRR2)</td> </tr> <tr> <td></td> <td style="text-align: center;">EIRR3)</td> <td></td> <td style="text-align: center;">FIRR3)</td> </tr> </table>							EIRR1)	27.10	FIRR1)		EIRR2)	25.30	FIRR2)		EIRR3)		FIRR3)						
	EIRR1)	27.10	FIRR1)																						
	EIRR2)	25.30	FIRR2)																						
	EIRR3)		FIRR3)																						
10. STUDY TEAM No. of Members 10 Period Jul. 1979-Mar. 1980 (9 months)		Conditions and Development Impacts: Conditions: Considering the production of paddy crop is relatively high, promotion of production during dry season is planned by utilizing the water of Kiv Lom Dam. To do this field improvement should be implemented. Development Impacts: Large increase of benefit by double cropping through effective use of existing water resource is expected.				2. MAJOR REASONS FOR PRESENT STATUS There are no plans to revive the project because of the reasons noted above.																			
<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%;"></td> <td style="width: 10%; text-align: center;">Japan</td> <td style="width: 15%; text-align: center;">Field</td> </tr> <tr> <td>Total M/M</td> <td style="text-align: center;">47.04</td> <td style="text-align: center;">25.07</td> </tr> <tr> <td></td> <td style="text-align: center;">21.97</td> <td></td> </tr> </table>			Japan	Field	Total M/M			47.04	25.07		21.97		5. TECHNICAL TRANSFER Training of and technical transfer to staffs of RID in Thailand and Japan.												
	Japan	Field																							
Total M/M	47.04	25.07																							
	21.97																								
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY None		3. PRINCIPAL SOURCE OF INFORMATION ①, ②, ③, ④																							
12. EXPENDITURE																									
Total 115,644 (¥'000)																									
Contracted 107,095																									

PROJECT SUMMARY (F/S)

Compiled Mar.1986
Revised Mar.1996

ASE THA/S 307/80

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input checked="" type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY Bangkok Urban Truck Terminals Construction Project		Bangkok metropolitan area					
3. SECTOR Transportation/Land Transportation		2. PROJECT COST		Total Cost	Local Cost	(Description) Detailed design was partially undertaken by local consultants. In June, 1987 Ministry of Transport and Communication has approved the commencement of the construction. Private investment have been promoted for the construction of truck terminals. So far, contracts have been signed on two of the four sites. Due to rapid urbanization, some sites proposed for terminals have been already used for other purposes. JICA is conducting a restudy of Bangkok urban truck terminals since Dec. 1991, in which suggestions will be made to expedite the project implementation. (FY1991 Overseas Survey) Project scale was reduced from four terminals to three. (FY1994 Domestic Survey) No additional information. (FY1995 Overseas Survey) The Thai Government ratified to construct truck terminal by its own budget. After the ratification, this project moved into implementation according to the JICA's study. September 1995, D/D was completed but land acquisition was not finished yet.	
4. REFERENCE NO.				42,033			
5. TYPE OF STUDY		F/S					
6. COUNTERPART AGENCY Department of Land Transport		3. CONTENTS OF MAJOR PROJECT(S)					
7. OBJECTIVES OF STUDY Traffic plan		Description		Scale			
8. DATE OF S/W		1979/1		Imp. Period:			
9. CONSULTANT(S) Pacific Consultants International Nittsu Research Center Inc.		4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: No	EIRR1) 10.00 EIRR2) EIRR3)	FIRR1) FIRR2) FIRR3)	
10. STUDY TEAM		No. of Members		9			
Period		Aug. 1979-Mar. 1980 (8 months)					
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY		Total M/M		Japan		Field	
		32.60		22.90		9.70	
12. EXPENDITURE		Total		83,169 (¥'000)			
		Contracted		79,340		3. PRINCIPAL SOURCE OF INFORMATION	
						①, ②, ③	
		5. TECHNICAL TRANSFER		Technical advice on demand forecasting, traffic survey, and economic analysis.			
						2. MAJOR REASONS FOR PRESENT STATUS	

PROJECT SUMMARY (D/D)

Compiled Mar. 1990

Revised Mar. 1996

ASE THA/S 402/80

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY		Bangkok Metropolitan Area					
Bangkok Telephone Network Project: Local Cable Network		2. PROJECT COST		Total Cost	Local Cost	Foreign Cost	
		(US\$1,000)	1) 2) 3)				
3. SECTOR		3. CONTENTS OF MAJOR PROJECT(S)				(Description) 1987 Jul. OECF L/A completed for extending telecommunication network	
Communications & B/Telecommunication		1) Detailed design of local cable network for five exchanges (Fronchit, Chinwatana, Packrett, Ramintra, and Onutt-I) 2) Additional detailed designs for three exchanges (Kurontoi, Labrana and Ekachai)					
4. REFERENCE NO.							
5. TYPE OF STUDY	D/D						
6. COUNTERPART AGENCY							
Telephone Organization of Thailand							
7. OBJECTIVES OF STUDY							
Detailed designs for 8 telephone exchanges							
8. DATE OF SAV	1978/7	Imp. Period:					
9. CONSULTANT(S)		4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes/No	EIRR1) EIRR2) EIRR3)	FIRR1) FIRR2) FIRR3)	
Nippon Telecommunication Consulting Co., Ltd.				Yes/No			
		Conditions and Development Impacts: Detailed designs are based on the program in the 4th National Economic Development Plan. Five exchanges correspond to Package I of Phase 2 and three additional exchanges to Package II of Phase 1.					
10. STUDY TEAM						2. MAJOR REASONS FOR PRESENT STATUS	
No. of Members 12						Urgency of the problem	
Period Aug. 1978-Jun. 1979 (22 months)							
Oct. 1979-Aug. 1980							
Total M/M		Japan		Field			
107.79		49.63		59.16			
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY							
		5. TECHNICAL TRANSFER				3. PRINCIPAL SOURCE OF INFORMATION	
12. EXPENDITURE		OUT for counterparts				①, ④	
Total		278,789 (¥'000)					
Contracted		277,097					

和名 バンコック市内線路網実施設計

(F/S,D/D)

PROJECT SUMMARY (F/S)

Compiled Mar.1990
Revised Mar.1996

ASE THA/A 304/81

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Thailand	1.SITE OR AREA		Right bank of PaSak River, SaraBuri Province		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input checked="" type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY Kaeng Khoi-Ban Mo Pumping Irrigation Project		2.PROJECT COST (US\$1,000)		Total Cost 40,700	Local Cost 24,500		
3.SECTOR Agriculture/(Agriculture in)General		3.CONTENTS OF MAJOR PROJECT(S) The objective of the project is to encourage the agriculture in the project area through stable irrigation water supply to the entire beneficial area together with introduction of the dry season crop as much as possible. Proposed cropping plans are about 14,000ha in wet season and 2,800ha in dry season within limited water resources allocation. Major facility of the project is summarized as follows: - Main pumping station: 1,000mm x 560kw, Q=17.5cu.m/sec, H=16.5m, 7 units - Irrigation canal : 148km including lateral canals - Drainage canal : 22km - Demonstration farm : 260ha				(Description) The detailed design was undertaken by Sanyu Consultants Inc and Chuo Kaihatsu Corporation during the period from July 1984 to June 1985, with the E/S loan from OECF. However, the project implementation was delayed, because the adjustment of water rights (with beneficiaries of the waterway between Chainat and PaSak) was not settled. July 1982 OECF loan agreement signed (E/S, 190 million yen) (FY 1991 Overseas Survey) No additional information. (FY 1993 Overseas Survey) D/D by OECF Loan (L/A on 1982 July 16 of 190 million USD) was conducted during July 1984 to June 1985, however, due to the suspension of Nakhon Nayok Dam construction of PaSak River delayed the implementation of the project. The government of Thailand is planning to initiate construction of Nakhon Nayok Dam to solve serious water shortage in these days. Once the dam construction is initiated, the project proposed by JICA Study can be implemented. (FY1994 Domestic Survey) Dam project on the main stream of PaSak River has been started in 1994. Therefore, the basic conditions were settled for this project. RID intends to implement the project under OECF loan and is planned to be up-dated the last detailed design.	
4.REFERENCE NO.		5.TYPE OF STUDY		F/S			
6.COUNTERPART AGENCY RID (Royal Irrigation Department), Ministry of Agriculture and Cooperatives		4.FEASIBILITY AND ITS ASSUMPTIONS Feasibility: Yes EIRR1) 16.90 FIRR1) EIRR2) 14.30 FIRR2) EIRR3) FIRR3) Conditions and Development Impacts: {Conditions} - Available water resources of the project are quite limited due to runoff discharge fluctuation of the PaSaku river until construction of storage dam on the river. - Extension and education of the beneficial farmers are very important role for introduction of irrigated agricultural development. - Urgent resolution of the available water resources for the project - Detailed design of the project has been finished by the government of Thailand supported by OECF engineering service loan. {Impacts} - Planting of 100% in rainy season and 20% in dry season will be done by completion of irrigation facilities to increase agricultural profit. - Training related to improvement of terminal facilities, water management and culture technique will be done in demonstration farm. *EIRR calculated (14.3%) includes on-farm.				2.MAJOR REASONS FOR PRESENT STATUS	
7.OBJECTIVES OF STUDY Feasibility study on irrigated agricultural development project							
9.CONSULTANT(S) Sanyu Consultants Inc.		10.STUDY TEAM No.of Members 10 Period Jun.1981-Jan.1982(8 months)		Total M/M Japan Field 37.55 17.80 19.75		3.PRINCIPAL SOURCE OF INFORMATION ①, ②, ③, ④	
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5.TECHNICAL TRANSFER Transfer to staffs of RID in Thailand and Japan was done.		12.EXPENDITURE Total 96,370 (¥'000) Contracted 90,677			

和名 ケンコイ・バンモーポンプかんがい計画

[F/S,D/D]

PROJECT SUMMARY (M/P+F/S)

Compiled Mar.1990

Revised Mar.1996

ASE THA/A 201B/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																											
1.COUNTRY	Thailand	1.SITE OR AREA		2 places in each part of north, central, northeast, south, totaling 8 places. <M/P> In the districts of north, central, northeast, south, where four proposed		1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled																										
2.NAME OF STUDY	Agricultural Cooperative Promotion	2.PROJECT COST		M/P 1) 2) (US\$1,000)	Local Cost 45,508		Foreign Cost 6,478																										
				E/S 1) 2) (US\$1=23Bahts)		39,030																											
3.SECTOR	Agriculture/(Agriculture in)General	3.CONTENTS OF MAJOR PROJECT(S)				(Description) <M/P> A Feasibility study was subsequently undertaken. 1. Thai Government requested Japanese Government for cooperation on the establishment of model agricultural cooperatives based on the final master plan report of Feb.1981 2. An S/W mission was sent to Thailand on an F/S in July 1981. After the S/W was concluded and the study was conducted from July to Sept. 3. The final report of F/S was submitted in Mar.1982, and Japanese experts were assigned for one year and a half from Dec. 1982. The project-type technical cooperation (5 years) began in July 1984. <F/S> The proposals of the study was implemented with the Japanese technical cooperation and grant aid. 1. Thai Government requested Japanese Government for a project-type technical cooperation and grant aid in June 1983. 2. R/D for technical cooperation was concluded in July 1984, and the five-year project began. The project was completed in July 1989, but extended for two years for the follow-up cooperation 3. In 1985, the Agricultural Cooperative Training Center of Northeast Thailand was established by the Japanese grant (598 million yen) Investment Cost (thousand Baht) <table style="width: 100%; border-collapse: collapse;"> <tr> <td></td> <td style="text-align: center;">JICA</td> <td style="text-align: center;">RTG</td> <td style="text-align: center;">Total</td> </tr> <tr> <td>May -Nov.87</td> <td style="text-align: center;">3,711</td> <td style="text-align: center;">---</td> <td style="text-align: center;">3,711</td> </tr> <tr> <td>Jan.-Jun.87</td> <td style="text-align: center;">4,489</td> <td style="text-align: center;">175</td> <td style="text-align: center;">4,664</td> </tr> <tr> <td>FY 87, 88</td> <td style="text-align: center;">4,000</td> <td style="text-align: center;">233</td> <td style="text-align: center;">4,233</td> </tr> <tr> <td>FY 89</td> <td style="text-align: center;">4,000</td> <td style="text-align: center;">200</td> <td style="text-align: center;">4,200</td> </tr> <tr> <td>Total</td> <td style="text-align: center;">16,000</td> <td style="text-align: center;">608</td> <td style="text-align: center;">16,608</td> </tr> </table> Thai side appreciate the model project of the agricultural cooperative development.					JICA	RTG	Total	May -Nov.87	3,711	---	3,711	Jan.-Jun.87	4,489	175	4,664	FY 87, 88	4,000	233	4,233	FY 89	4,000	200	4,200	Total	16,000	608	16,608
	JICA	RTG	Total																														
May -Nov.87	3,711	---	3,711																														
Jan.-Jun.87	4,489	175	4,664																														
FY 87, 88	4,000	233	4,233																														
FY 89	4,000	200	4,200																														
Total	16,000	608	16,608																														
4.REFERENCE NO.		<M/P> We pointed realities and problems of organization, operations and management of agricultural cooperative of Thailand, and proposed basic idea for their improvement, based on case studies in each area. 1. Basic idea to strengthen the function of agricultural cooperative four strategic targets, strengthening of member's organization base, promotion of regional agriculture by conducting guidance of agriculture management, expansion of sales and purchase abiding by fair rule, realization of comprehensive agricultural financial system, are shown, and "total system" to facilitate all of them in a comprehensive way was proposed. 2. Establishment of Agricultural Cooperative <F/S> 1. Projects to nurture agricultural cooperative 2. Establishment of consultant units and traveling guidance 3. Strengthening of training by agricultural cooperative training centers 4. Improvement of facilities of agricultural cooperative 5. Comprehensive financial measures																															
5.TYPE OF STUDY	M/P+F/S																																
6.COUNTERPART AGENCY	Cooperatives Promotion Department MOAC																																
7.OBJECTIVES OF STUDY	To raise the agricultural production of cooperative member farms and to improve their socio-economic well-being.																																
8.DATE OF SAV	1981/7																																
9.CONSULTANT(S)	The Institute for the Development of Agricultural																																
						Imp. Period:		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes		EIRR1) FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)																					
10.STUDY TEAM	No.of Members 6 Period May.1980-Feb.1982(23 months)					Conditions and Development Impacts: <M/P>1.We proposed that establishment of model Agricultural Cooperative should be chosen taking into consideration the difference of regional character and basic condition of each area. 2.Development effect of promoting agricultural cooperative is expected by planning of agricultural cooperative promotion, guidance to implement the plan, and dissemination of the fruits of model agricultural cooperative to neighboring cooperatives. <F/S>[Conditions] 1.Establishment of promoting system in CPD. 2.Guidance of agricultural management and strengthening of sales activities. 3.Financial back up by the government 4.Cooperation with ACFT and CLT [Development Impacts] 1.Improvement of management by agricultural cooperatives 2.Increase of employment opportunities, Increase of income, Decreasing the difference of income.																											
	Total M/M Japan Field 37.21 27.36 9.85																																
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY																																	
12.EXPENDITURE	Total 127,935 (¥'000) Contracted 107,192	5.TECHNICAL TRANSFER		- Transfer of research method during the period of F/S. - Discussion and cooperative operation in writing a report accepting two trainees.						2.MAJOR REASONS FOR PRESENT STATUS																							
										3.PRINCIPAL SOURCE OF INFORMATION																							
										①, ②																							

PROJECT SUMMARY (M/P+F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 203B/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT			
1. COUNTRY	Thailand	1. SITE OR AREA				I. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input checked="" type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled		
2. NAME OF STUDY	Bangkok Solid Waste Management	City of Bangkok							
3. SECTOR	Public Utilities/Urban Sanitation	2. PROJECT COST				(Description) A Japanese expert was sent to BMA in 1983 - 1989, and the short-term measures proposed by the study were implemented during the period. The Phase II study was undertaken during FY1989 - FY1992 by the JICA team. Another Japanese expert was posted to BMA. (FY 1991 Overseas Survey) Most of the short-term improvement plan recommended in the original master plan was already been brought into practice, such as introduction of compact trucks, collection by boats, uniform supply for collection workers, etc. This study was revised in the phase II study completed in 1991. (FY1995 Domestic Survey) No additional information. (FY1995 Overseas Survey) Except the contribution of ten used trucks from Tokyo Municipality, BMA bought Japanese trucks. The major component of the long term plan is construction of incinerator, however, the plan was not realized because of the difficulty of acquisition of land. Regarding compost plant, a new plant is under construction in On Nut (1,000t/d) and will be completed in 1995. Composting plants in Ram Intra and Nong Kean were also constructed, the total capacity is 2,000t/d. They were financed by the central government for 60% and BMA for the rest.			
4. REFERENCE NO.		M/P 1) 17,248 Local Cost		8,667 Foreign Cost					
5. TYPE OF STUDY	M/P+F/S	2) (US\$1,000) 578,712		352,590					
6. COUNTERPART AGENCY	Public Cleansing Dept., BMA	3) (US\$1=26.25B) 2) 578,712		3) 352,590					
7. OBJECTIVES OF STUDY	To formulate M/P of improving waste disposal system and feasibility study of it.	3. CONTENTS OF MAJOR PROJECT(S)							
8. DATE OF S/W	1979/3	<M/P>The master plan to improve waste disposal system by the year of 2000 and 67 immediate action programmes. (1) The master plan includes construction and introduction of: 5 composting plants, 2 incineration plants, 3 final disposal sites, 1,190 collection vehicles, 88 road sweepers, 5 river cleaning boats, 110 barges, 25 dump trucks, 18 bulldozers (2) The immediate action programmes in which 3 levels of priority is shown include improvements in: 1) discharge and collection system 2) transport and transferring system 3) composting plants 4) final disposal system 5) administrative system 6) countermeasures to floods The total cost above pertains to the short-term improvement plan. <F/S> Construction of final disposal site 3 1,500t/d Construction of refuse incineration plant 2 1,500t/d X2 Construction of rapid type composting plant 2 800t/d							
9. CONSULTANT(S)	Tokyo Metropolis Environmental Service Corporation	Imp. Period: 1985. -2000.							
10. STUDY TEAM	No. of Members 55 Period Aug. 1979-Feb. 1980 (36 months) May. 1980-Sep. 1982 Total M/M Japan Field 278.08 124.54 153.54	4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes					
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	Geological Survey, Characteristic Analysis of the Solid Waste	EIRR1) FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)						2. MAJOR REASONS FOR PRESENT STATUS	
12. EXPENDITURE	Total 491,070 (¥'000) Contracted 447,098	5. TECHNICAL TRANSFER							
		(1) training to the local staff through OJT. (2) reception of trainees, 6 local staff (3) effective application of local consultants.				3. PRINCIPAL SOURCE OF INFORMATION			
						①, ②, ③			

和名 バンコク市都市廃棄物整備計画

[M/P+F/S]

PROJECT SUMMARY (M/P+F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 202B/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA	Bangkok City and Thonburi area located at the other side of Chao Phaya river. <M/P> Bangkok City <F/S>			1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY	Bangkok Sewerage System Project	2. PROJECT COST	M/P 1) 116,160 Local Cost	69,100 Foreign Cost	47,060	(Description) <M/P> A feasibility study was subsequently implemented and Japanese experts went to Thailand for technical assistance. (FY1993 Overseas Survey) DDS had reviewed the M/P since 1990 and formulated following 5 projects. - Si Praya : 92-93, BMA budget (284 mil. Baht) - Yannawa : 94-96, BMA (25%) and Central Government (75%) budget (4,700 mil. Baht) - Bangkok Waste Water Treatment Project Phase I: 94-96, BMA(25%) and Central Government (75%) budget (6,300 mil. Baht) - Rattanakosin Project (D/D): 91-92, Central Government budget (11 mil. Baht) - Nongkham - Pasicharoen - Ratburana: scheduled to be approved in FY 1994, BMA (25%) and Central Government (75%) budget (7,000 mil. Baht) <F/S> Bangkok Metropolitan Administration(BMA) undertook D/D on two sewage treatment plants (the capacity: 30,000 cu.m/day and 25,000 cu.m/day). In late 1990, BMA was preparing a request to Japanese assistance on another treatment plant with a capacity of 60,000 cu.m/day. (FY1991 Overseas Survey) The Department of Drainage and Sewerage has modified the study, by rearranging the Bangkok Sewerage Area into 6 areas. Detailed design is under implementation for each area and the implementation will begin before long. (FY1994 Domestic Survey) A part of the above project is under way. (FY1995 Domestic Survey) No additional information. (FY1995 Overseas Survey) Si Phraya plant completed in 1993 by BMA budget of 284 million Baht. Construction of collection system is being done between 1994 and 1996. Treatment process is Contact Stabilization Activated Sludge Process. Treatment capacity is 30,000m ³ /day. Rattanakosin plant; will be completed in 1995 by the central government budget of 883 million Baht. Treatment process is Two Stage Activated Sludge Process. Treatment capacity is 40,000m ³ /day. Din Daeng; will be completed in Dec. of 1996 by the central government budget for 75% and BMA for 25% (total 6.382 billion Baht).	
3. SECTOR	Public Utilities/Sewerage		2) 32,300	23,200			
4. REFERENCE NO.		3. CONTENTS OF MAJOR PROJECT(S)	<M/P> Bangkok City has some problems such as flooding in rainy season and water pollution of river in dry season. Several studies on those problems have been carried out. This study was to review the previous study reports and to make new master plan in order to obtain the practical plan. Scope of the study is limited for sewerage system planning. <F/S> Project area : 970 ha Intercepting sewer : d 3,000-2,400mm for L=7,100m Combined sewer : d 8,500-2,000mm for L=1,300m Intermediate Pumping Station: 3 stations, Q=13-24cu.m/min Plant : Q=135,000 cu.m/day Inf. BOD= 160 mg/l Eff. BOD= 60 mg/l (Modified aeration process: grit chamber, aeration tank, final sedimentation basin, basin, chlorination chamber, digester, etc.)				
5. TYPE OF STUDY	M/P+F/S	4. FEASIBILITY AND ITS ASSUMPTIONS	Feasibility: Yes	EIRR1) FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)		2. MAJOR REASONS FOR PRESENT STATUS	
6. COUNTERPART AGENCY	Department of Drainage and Sewerage, BMA	10. STUDY TEAM	Imp. Period: 1984. -1988. Conditions and Development Impacts: <M/P> Study area is 37,000 ha, same as previous CDM plan, which was divided into 10 sewerage districts. Separate systems have been fundamentally adopted for the system. In central area of the city, however, a combined system has been temporarily adopted. Treatment plant is located at the vacant lot of the Tobacco Public Corporation. Treatment method is modified aeration system. <F/S> In 1982, the celebration of the 200th anniversary of Bangkok as Capital of Thailand, sewerage project was focussed to cope with the water quality problem of canal in the city. Sewerage project and Water Disposal Plan were made as a pair. F/S was conducted for the area selected by the investment efficiency as recommended in M/P. Development impacts are expected with pollution prevention of canal and decrease of inundation problem, which area, however, can not be scaled quantitatively.				
7. OBJECTIVES OF STUDY	Planning on the countermeasure of pollution and flood. F/S on first phase program, as recommended in M/S.	11. ASSOCIATED AND/OR SUBCONTRACTED STUDY	Topographic survey				
8. DATE OF SAW	1979/3	12. EXPENDITURE	Total 397,120 (¥'000) Contracted 377,556				
9. CONSULTANT(S)	Nihon Suido Consultants Co., Ltd.	5. TECHNICAL TRANSFER	(1) Carried out training program for two persons (2) Employment of the local consultant for land survey (3) Equipment granted and instructed for water quality tests (4) Report writing				
			3. PRINCIPAL SOURCE OF INFORMATION				
			①, ②, ③				

和名 バンコック市下水道整備計画

状況 (要約表添付文書)

ASE THA/S 202B/82	(M/P+F/S)
Name of Bangkok Sewerage System Project Study	
Country	Thailand
Type of Study	M/P+F/S
Sector	Public Utilities/Sewerage
Present Status: Implementing	
(Description)	
<p><M/P> A feasibility study was subsequently implemented and Japanese experts went to Thailand for technical assistance.</p> <p>(FY1993 Overseas Survey) DDS had reviewed the M/P since 1990 and formulated following 5 projects. - Si Praya : 92-93, BMA budget (284 mil. Baht) - Yannawa : 94-96, BMA (25%) and Central Government (75%) budget (4,700 mil. Baht) - Bangkok Waste Water Treatment Project Phase I: 94-96, BMA(25%) and Central Government (75%) budget (6,300 mil. Baht) - Rattanakosin Project (D/D): 91-92, Central Government budget (11 mil. Baht) - Nongkham - Phasichroen - Ratburana: scheduled to be approved in FY 1994, BMA (25%) and Central Government (75%) budget (7,000 mil Baht)</p> <p><F/S> Bangkok Metropolitan Administration(BMA) undertook D/D on two sewage treatment plants (the capacity: 30,000 cu.m/day and 25,000 cu.m/day). In late 1990, BMA was preparing a request to Japanese assistance on another treatment plant with a capacity of 60,000 cu.m/day.</p> <p>(FY1991 Overseas Survey) The Department of Drainage and Sewerage has modified the study, by rearranging the Bangkok Sewerage Area into 6 areas. Detailed design is under implementation for each area and the implementation will begin before long.</p> <p>(FY1994 Domestic Survey) A part of the above project is under way.</p> <p>(FY1995 Domestic Survey) No additional information.</p> <p>(FY1995 Overseas Survey) Si Phraya plant completed in 1993 by BMA budget of 284 million Baht. Construction of collection system is being done between 1994 and 1996. Treatment process is Contact Stabilization Activated Sludge Process. Treatment capacity is 30,000m³/day. Rattanakosin plant; will be completed in 1995 by the central government budget of 883 million Baht. Treatment process is Two Stage Activated Sludge Process. Treatment capacity is 40,000m³/day. Din Daeng; will be completed in Dec. of 1996 by the central government budget for 75% and BMA for 25% (total 6.382 billion Baht). Treatment process is Taper Conventional Activated Sludge Process. Treatment capacity is 350,000m³/day. Yannawa; started in 1995 by the central government budget for 60% and BMA for 40% (total 4.552 billion Baht). Treatment process is Sequencing Batch Reactor Activated Sludge. Treatment capacity is 200,000m³/day. Nongkham-Phasichroen-Ratburana; will be finished by 2000 by the central government budget for 60% and BMA for 40% (total 7.094 billion Baht). Treatment capacity is 157,000m³/day (Nongkham-Phasichroen), 65,000m³/day (Ratburana).</p>	

PROJECT SUMMARY (F/S)

Compiled Mar.1990

Revised Mar.1996

ASE THA/A 306/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY Mae Kuang Irrigated Agriculture Development Project		Chieng Mai and Lampoon Provinces					
3. SECTOR Agriculture/(Agriculture in)General		2. PROJECT COST (US\$1,000)		Total Cost	Local Cost	Foreign Cost	
4. REFERENCE NO.		1)	204,400	126,600	77,800	(Description) The project is under implementation in three stages with the OECF loans. Detailed Design: Jul. 1982 OECF loan agreement signed for E/S (940 million yen), of which 190 million used for the project. D/D undertaken by Sanyu Consultants, Inc. First Stage Construction: Sep. 1984 OECF loan agreement signed (2,300 million yen) Left saddle dam constructed. Construction was under direct management of RID and supervised by Sanyu Consultants, Inc. Second Stage Construction: Oct. 1985 OECF loan agreement signed (9,197 million yen) Main and Right saddle dam constructed. Construction undertaken by a Chinese company, supervised by Nippon Koei Co., Inc. Third Stage Construction: Sep. 1987 OECF loan agreement signed (2,805 million yen) Main and tributary canals have been under construction by an Italian company with supervision by Sanyu Consultants. (FY1993 Overseas Survey) Construction work has completed. (FY1994 Domestic Survey) All the project components including the Phase-1 (left dam), Phase-2 (Rightdam and main dam) and Phase-3 (main canal) have been completed in 1993.	
5. TYPE OF STUDY		2)	223,600	138,700	84,900		
6. COUNTERPART AGENCY RID (Royal Irrigation Department), Ministry of Agriculture and Cooperatives		3)					
7. OBJECTIVES OF STUDY		3. CONTENTS OF MAJOR PROJECT(S)					
8. DATE OF SAV		1. The dimension of dam					
1980/12		length	Crest elevation	Embankment volume	Dam height	Dam	
9. CONSULTANT(S) Sanyu Consultants Inc. Taiyo Consultants Co., Ltd.		(m)	(m)	(MCM)	(m)		
10. STUDY TEAM		1) Left saddle dam	395.0	2.26	52.0		
No. of Members 14		2) Main dam	395.0	5.58	77.0		
Period Feb.1981-Feb.1982 (13 months)		3) Right saddle dam	395.0	1.44	41.0		
Total M/M		2. Main irrigation canal: 87.4km					
Japan		3. Lateral irrigation canal: 146.6km					
57.09		4. The capacity of hydropower generation					
Field		1) Optimum installed capacity: 3.7MW					
35.32		2) Annual energy: 16.3GWH					
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. New cropping patterns					
		Rice-Rice, Rice-Groundnut, Rice-Soybean, Rice-Sweet corn, Rice-Tobacco,					
		Rice-Garlic, Rice-Vegetables, Soybean-Tobacco, Soybean-Groundnut and Longan					
12. EXPENDITURE		4. FEASIBILITY AND ITS ASSUMPTIONS					
Total		Feasibility: Yes		EIRR1) 17.70	FIRR1)		
193,441 (¥'000)				EIRR2)	FIRR2)		
Contracted				EIRR3)	FIRR3)		
165,175		5. TECHNICAL TRANSFER					
		1. Acceptance of one trainee					
		2. Several seminars held in RID during the period of the survey					
		3. PRINCIPAL SOURCE OF INFORMATION					
		①, ②, ③					

PROJECT SUMMARY (F/S)

Compiled Mar.1990

Revised Mar.1996

ASE THA/A 307/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																																			
1.COUNTRY	Thailand	1.SITE OR AREA				1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled																																		
2.NAME OF STUDY Upper Pasak Medium Scale Irrigation Project		Upper Pasak river basin under PHETCHABUN Province (about 330km north from Bangkok)																																							
3.SECTOR Agriculture/(Agriculture in)General		2.PROJECT COST		Total Cost	Local Cost	Foreign Cost																																			
		(US\$1,000)		1) 195,000	107,000	88,000																																			
		US\$1=23B		2)																																					
				3)																																					
4.REFERENCE NO.		3.CONTENTS OF MAJOR PROJECT(S)				(Description) The Royal Irrigation Development has been implementing the project with its own funds based on the results of the JICA Study. (FY1991 Overseas Survey) D/D Period : 1986-1992 Consultant's country : Thai Source of finance : Thai Construction Period : 1988-1996 Country of main contractors: Thai (FY1993 Overseas Survey) F/S review and D/D were conducted by government budget (180 million Bhts) in 1988 and dam construction in Fai Khon Ken and Khulong Charian Rab project sites was initiated by government budget. In Fai Khon Ken the construction was initiated in 1990 and is to be completed in 1995 and total project cost is 500 million Bhts. In Khulong Charian Rab, the construction was initiated in 1993 and to be completed in 1996 and the total project cost is 146 million Bhts. (FY1994 Domestic Survey) The D/D and Construction Works which have been proposed has been implementing by the Gov't of Thailand on the basis of the Development Study conducted by JICA. (FY1995 Domestic Survey) No additional information.																																			
5.TYPE OF STUDY		Sub-Project																																							
6.COUNTERPART AGENCY		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33%;"></td> <td style="width: 16.5%;">Huai Sa Duang Yai</td> <td style="width: 16.5%;">Huai Khon Kaen</td> <td style="width: 16.5%;">Huai Yai K.Chaliang Lab</td> <td style="width: 16.5%;"></td> </tr> <tr> <td>1.Irrigation Area(ha)</td> <td>5,400</td> <td>5,100</td> <td>1,800</td> <td>1,200</td> </tr> <tr> <td>2.Dam 1)Type</td> <td>Earthfil</td> <td>Earthfil</td> <td>Earthfil</td> <td>Earthfil</td> </tr> <tr> <td>2)Height(m)</td> <td>38</td> <td>57</td> <td>38</td> <td>35.3</td> </tr> <tr> <td>3)Crest Length(m)</td> <td>467</td> <td>950</td> <td>816</td> <td>1,259</td> </tr> <tr> <td>3.Irrigation Canal(km)</td> <td>-</td> <td>105.2</td> <td>26.6</td> <td>21.2</td> </tr> <tr> <td>4.Drainage Canal</td> <td>-</td> <td>72.3</td> <td>36.7</td> <td>20.0</td> </tr> </table>						Huai Sa Duang Yai	Huai Khon Kaen	Huai Yai K.Chaliang Lab		1.Irrigation Area(ha)	5,400	5,100	1,800	1,200	2.Dam 1)Type	Earthfil	Earthfil	Earthfil	Earthfil	2)Height(m)	38	57	38	35.3	3)Crest Length(m)	467	950	816	1,259	3.Irrigation Canal(km)	-	105.2	26.6	21.2	4.Drainage Canal	-	72.3	36.7	20.0
	Huai Sa Duang Yai	Huai Khon Kaen	Huai Yai K.Chaliang Lab																																						
1.Irrigation Area(ha)	5,400	5,100	1,800	1,200																																					
2.Dam 1)Type	Earthfil	Earthfil	Earthfil	Earthfil																																					
2)Height(m)	38	57	38	35.3																																					
3)Crest Length(m)	467	950	816	1,259																																					
3.Irrigation Canal(km)	-	105.2	26.6	21.2																																					
4.Drainage Canal	-	72.3	36.7	20.0																																					
7.OBJECTIVES OF STUDY		* Below implementation period is 10 years.																																							
Feasibility Study -to identify the order of priority -to formulate an irrigated agricultural development project and identify the feasibility of the project																																									
8.DATE OF S/W		Imp. Period:																																							
1981/4																																									
9.CONSULTANT(S)		4.FEASIBILITY AND ITS ASSUMPTIONS		Feasibility:	EIRR1) 13.90	FIRR1)																																			
Nippon Koei Co., Ltd. Chuo Kaihatsu International Corp.		Yes		EIRR2)		FIRR2)																																			
				EIRR3)		FIRR3)																																			
10.STUDY TEAM		Conditions and Development Impacts:																																							
No.of Members 34		[Condition] Agricultural benefit is estimated as a difference of both benefits accrued under with and without conditions. In addition, irrigation water supply to lower basin and drinking water supply to the Lom Sak municipality are assessed as a direct benefit from the project.																																							
Period Aug.1981-Mar.1983 (20 months)		[Development Impacts] 1) Increase of agricultural production 2) Rasing of the living standard of the regional inhabitants 3) Supplemental water supply to urban area																																							
Total M/M																																									
Japan																																									
Field																																									
72.48																																									
21.06																																									
51.42																																									
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY		5.TECHNICAL TRANSFER																																							
None		To undertake on-the-job training of the government's officials in the course of the survey and study.																																							
12.EXPENDITURE		3.PRINCIPAL SOURCE OF INFORMATION																																							
Total		①, ②, ③																																							
188,810 (¥'000)																																									
Contracted																																									
175,942																																									

PROJECT SUMMARY (F/S)

Compiled Mar.1990
Revised Mar.1996

ASETHA/A 305/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT										
1. COUNTRY	Thailand	1. SITE OR AREA	Phetchaburi River Basin, area : 52,600 ha, population: 192,000			1. PRESENT STATUS	<input type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="radio"/> Completed <input type="radio"/> Partially Completed <input checked="" type="checkbox"/> Delayed or Suspended <input type="radio"/> Implementing <input type="radio"/> Processing <input type="checkbox"/> Discontinued or Cancelled									
2. NAME OF STUDY Phetchaburi-Kaeng Krachan Irrigated Agriculture Development Project		2. PROJECT COST		Total Cost	Local Cost	Foreign Cost	(Description) The proposed project has been suspended because of the change in Thai Government policy on farmland consolidation. (FY 1991 Overseas Survey) No additional information. (FY 1993 Overseas Survey) Due to the changes in development policy of the Thai Government and difficulty in financial arrangement, implementation of the project is suspended. There is no possibility of the project to be implemented. (FY1994 Domestic Survey) The project aims mainly at the development of on-farm facilities. Due to the policy by the Government that higher priority is to be given in water resources development, not to the on-farm development, implementation of the Project is not ready in near future. Up to the year 1994, there has been no positive action taken for the Project implementation. (FY1995 Domestic Survey) No additional information.									
				233,865	163,396	70,469										
				(US\$1,000)	US\$1=23B=230Yen	1) 2) 3)										
3. SECTOR Agriculture/(Agriculture in)General		3. CONTENTS OF MAJOR PROJECT(S)														
		Development of irrigation agriculture centering on improvement of irrigation canal for Phetchaburi irrigated area of 45,000ha and new development of 7,100ha, and terminal facilities.														
		The Project aims to increase agriculture production in the project area with improvement and for readjustment of irrigation and drainage system in proper combination with existing facilities, those are Fochi Head Works and the Irrigation System constructed in 1950, Kan-Kra (hang Reservoir constructed in 1966 and the sea dike.														
4. REFERENCE NO.		Irrigation System		Farm Land												
5. TYPE OF STUDY		new canal : 120 km		land consolidation : 52600 ha												
F/S		canal lining : 167 km		canal improvement : 128 km												
6. COUNTERPART AGENCY		8. DATE OF SAW														
RID (Royal Irrigation Department), Ministry of Agriculture and Cooperatives		/		Imp. Period: 1987. -1998.												
7. OBJECTIVES OF STUDY		Feasibility study for irrigation and drainage system improvement and promotion of land consolidation		4. FEASIBILITY AND ITS ASSUMPTIONS												
				Feasibility: Yes		<table style="width: 100%; border: none;"> <tr> <td style="border: none;">EIRR1)</td> <td style="border: none; text-align: center;">26.00</td> <td style="border: none;">FIRR1)</td> </tr> <tr> <td style="border: none;">EIRR2)</td> <td style="border: none;"></td> <td style="border: none;">FIRR2)</td> </tr> <tr> <td style="border: none;">EIRR3)</td> <td style="border: none;"></td> <td style="border: none;">FIRR3)</td> </tr> </table>		EIRR1)	26.00	FIRR1)	EIRR2)		FIRR2)	EIRR3)		FIRR3)
EIRR1)	26.00	FIRR1)														
EIRR2)		FIRR2)														
EIRR3)		FIRR3)														
10. STUDY TEAM		Conditions and Development Impacts:				2. MAJOR REASONS FOR PRESENT STATUS										
No. of Members 11		- The increase of paddy production by 98,000t annually														
Period Nov.1980-Mar.1982 (17 months)		- Introduction of improved seeds to 48,700ha paddy														
Total M/M		Japan		Field												
50.73		18.36		32.37												
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY		- Expansion of cultivation in dry season - Total agriculture production and I.R.R. are estimated as; <table style="width: 100%; border: none;"> <tr> <td style="border: none;">Total Project Cost</td> <td style="border: none;">: 22200 Million Yen (1us\$=230Yen)</td> </tr> <tr> <td style="border: none;">Increment of Production</td> <td style="border: none;">: 584 Million Bahts</td> </tr> <tr> <td style="border: none;">Total Production</td> <td style="border: none;">: paddy rice 240 mung bean 7</td> </tr> <tr> <td style="border: none;">(x 10³) ton</td> <td style="border: none;">: fluit 16 vegetable 48</td> </tr> <tr> <td style="border: none;">Estimated IRR</td> <td style="border: none;">: 24%</td> </tr> </table>						Total Project Cost	: 22200 Million Yen (1us\$=230Yen)	Increment of Production	: 584 Million Bahts	Total Production	: paddy rice 240 mung bean 7	(x 10 ³) ton	: fluit 16 vegetable 48	Estimated IRR
Total Project Cost	: 22200 Million Yen (1us\$=230Yen)															
Increment of Production	: 584 Million Bahts															
Total Production	: paddy rice 240 mung bean 7															
(x 10 ³) ton	: fluit 16 vegetable 48															
Estimated IRR	: 24%															
Teaching Test, Construction of Testing Agricultural Fields		5. TECHNICAL TRANSFER				3. PRINCIPAL SOURCE OF INFORMATION										
		Training to engineers														
12. EXPENDITURE																
Total		201,291 (¥000)				①, ②										
Contracted		167,094														

PROJECT SUMMARY (F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 309/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input checked="" type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY		East Coast Region (Changwats Rayong and Chon Buri)					
East Coast Water Resources Development Project		2. PROJECT COST		Total Cost	Local Cost	Foreign Cost	
		(US\$1,000)	1)	242,000	103,870	137,700	
		(US\$1=230Yen=23B)	2)				
			3)				
3. SECTOR		3. CONTENTS OF MAJOR PROJECT(S)				(Description) Jul. 1982 OECF loan agreement on the pipeline (6,570 million yen) Jul. 1982 OECF loan agreement on E/S of Nong Pla Lai Dam (320 million yen) Sep. 1982 D/D completed Jun. 1984 Construction completed Sep. 1988 OECF loan agreement on the dam (4,357 million yen) Sep. 1989 OECF loan agreement on construction of Mab Ta Phud - Sattahip Pipeline (1,750 million yen) Dec. 1990 Construction of the pipeline (Mab Ta Phud - Sattahip) is under implementation (FY 1991 Overseas Survey) The construction is under implementation from 1989 to 1993. (FY 1993 Overseas Survey) No additional information. (FY 1995 Domestic Survey) No additional information.	
Social Infrastructure/Water Resource Development		1. Nong Pla Lai Sub-project a. Reservoir and dam: Catchment Area 426 sq.m, Gross reservoir storage 200,700,000 sq.m; Dam type-Earth fill type with cut-off trench, Crest elevation EL. 49.0 m, Max. dam height 31.0 m, Crest length 4,000m b. Water transmission system: Supply to Mab Ta Pud: Design discharge 3.63 cu.m/s, Total length 27.6 km Supply to Sattahip from Mab TA Pud: Design discharge 1.09 cu.m/s, Total length 21.9 km Supply to Laem Chabang: Design discharge 1.01 cu.m/s, Total length 53.0 km c. Irrigation and drainage system Irrigation area 3,650 ha, Irrigation canal: Main length 46.2 km, Lateral length 20 km Drainage area: Inside the project area 21.3 sq.m, Outside the project area 14.9 sq.m; Drainage length 6.5 km 2. Ban Bung Sub-project Reservoir and dam: Catchment area 53 sq.m, Gross reservoir storage 21,900,000 cu.m; Dam type-Earth fill type with cut-off trench, Crest elevation EL. 86.3 m, Max. dam height 21.5 m, Crest length 2,800 m					
4. REFERENCE NO.							
5. TYPE OF STUDY		F/S					
6. COUNTERPART AGENCY		Royal Irrigation Department					
7. OBJECTIVES OF STUDY		Water Resources Development covering Rayong, Nong Pla Lai, Chon Buri Changwats					
8. DATE OF S/W		1980/12					
9. CONSULTANT(S)		Imp. Period: 1983.1-1986.11					
CTI Engineering Co., Ltd. Sanyu Consultants Inc. Nomura Research Institute		4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 10.50 FIRR1) 4.90 EIRR2) 8.20 FIRR2) 1.80 EIRR3) FIRR3)		
10. STUDY TEAM		Conditions and Development Impacts: [Conditions] The proposed industrial development project in the east coast region be progressed as originally scheduled. [Development Impacts] 1. Direct impacts a. Municipal and industrial water consumption; b. Production of paddy and groundnuts; and c. Flood control 2. Indirect impacts a. Promotion of industrial development (gas separation & petrochemical plant, soda ash plant, chemical fertilizer plant, sponge iron plant, industrial estate, deep sea port, etc.); b. Improvement of living standard and c. Land enhancement by flood control Notes: Above EIRRs and FIRR are for 1) Nong Pla Lai Sub-project and 2) Ban Bung Sub-project. The respective EIRRs of the sectors are: 1. Nong Pla Lai Sub-project: Industrial and municipal water-10.4%, Irrigation-12.1%, and Flood control-3.5%; 2. Ban Bung Sub-project: Industrial and municipal water-8.3%, and Flood control-2.9%.					
No. of Members 11 Period Feb. 1981-Mar. 1982 (13 months)							
Total M/M		Japan		Field			
61.79		26.54		35.25			
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY		5. TECHNICAL TRANSFER				2. MAJOR REASONS FOR PRESENT STATUS	
Geological survey		Acceptance of Trainees: for about three months, four trainees despatched from the Government of Thailand pursued the study and training mainly field survey of water supply systems. In the long view, it is considered profitable to the trainees.					
12. EXPENDITURE						3. PRINCIPAL SOURCE OF INFORMATION	
Total		165,176 (¥000)					
Contracted		149,826				①, ②, ④	

PROJECT SUMMARY (F/S)

Compiled Mar. 1986
Revised Mar. 1996

ASE THA/S 308/82

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT	
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2. NAME OF STUDY Rama VI Bridge Construction Project		Northern area of Bangkok					
		2. PROJECT COST		Total Cost	Local Cost	Foreign Cost	(Description) Sep. 1983 OECF (10th) E/S loan agreement (170 million yen) Aug. 1986 D/D on New Rama IV Bridge completed Sep. 1987 OECF (11th) loan agreement on the new bridge (5,599 million yen) Dec. 1988 FQ for construction completed Jun. 1989 Tender for construction closed Nov. 1989 Construction contract completed Jan. 1990 Notice to proceed received by the contractor Sep. 1992 Construction to be completed Up to now 70 percent of the work completed. Construction and construction supervision are in progress satisfactorily and smoothly. (FY 1992 Overseas Survey) The project is included in the 5th and 6th National Social and Economic Development Plan. (FY1994 Domestic Survey) The maintenance period ended in Sep. 1993 after the completion of this Project in Sep. 1992. The consulting work for this Project has been completed.
		(US\$1,000)	1) 34,000	19,100	14,900		
		(US\$1=230Yen)	2)				
			3)				
3. SECTOR Transportation/Road		3. CONTENTS OF MAJOR PROJECT(S)					
4. REFERENCE NO.		1) New Highway Bridge Main Bridge: total length 290m, width 29.1m (6 Lanes+pedestrian), 85m+120m+85m=290m long (3 spans) (Freyssinet cantilever erection method) Approach Bridge: width 21.3m (6 Lanes), total length 650m					
5. TYPE OF STUDY F/S		2) New Railway Bridge width 12.5m total length 71.9m (dual track) (3 span continuous prestressed concrete girder)					
6. COUNTERPART AGENCY Public Works Dept. (PWD), Ministry of Interior		3) New Roads width 9.4m - 5.7m, total length 3,900m					
7. OBJECTIVES OF STUDY Alleviation of traffic congestion in Bangkok, with the bridge serving to complete the middle ring road		4) Other structures Riverfront, side ditch, drainage network, pump station, utilities, electricity, water and telecom (Total 5,700m), parking spaces, park, landscaping, pedestrian bridges, signal, etc.					
8. DATE OF SAV 1981/3		Imp. Period: 1983.10-1986.3					
9. CONSULTANT(S) Chiyoda Engineering Consultants Co., Ltd. Japan Overseas Consultants Co., Ltd.		4. FEASIBILITY AND ITS ASSUMPTIONS		Feasibility: Yes	EIRR1) 20.30 FIRR1) EIRR2) FIRR2) EIRR3) FIRR3)		
10. STUDY TEAM No. of Members 12 Period Jun. 1981-Mar. 1982 (10 months)		Conditions and Development Impacts: [Conditions] 1) Traffic volume projections for 1985, 1990 and 2000 2) Standard running speed of cars at 50km/hour 3) Traffic volumes of passengers and goods are projected on the basis of the O/D survey. [Development impacts] 1) Alleviation of traffic congestions in Bangkok and its adjacent areas 2) Industrial and residential development of the area along the Middle Ring Road because of an expansion of the traffic capacity of the road					
Total M/M Japan Field 38.05 3.55 34.50							
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY Traffic survey, topographic survey and geological survey							
12. EXPENDITURE Total 124,023 (¥'000) Contracted 116,682		5. TECHNICAL TRANSFER 1) OJT 2) Participation of counterparts in the JICA program. 3) Employment of local consultants					
		2. MAJOR REASONS FOR PRESENT STATUS 1) Large impact: stimulation of the regional economy by the alleviation of congestion and the reduction of travel time 2) High priority: the completion of the Middle Ring Road ensures the balanced growth of the metropolitan area of Bangkok. 3) Administrative expertise: PWD has experiences in bridge construction (already constructed 5 bridges across Chao Phraya River)					
		3. PRINCIPAL SOURCE OF INFORMATION ①, ②, ③, ④					

和名 チャオピヤ河架橋計画 (ラマ六世橋建設計画)

{F/S,D/D}

PROJECT SUMMARY (D/D)

ASE THA/S 403/82

Compiled Mar.1988

Revised Mar.1996

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS			III. PRESENT STATUS OF STUDIED PROJECT	
1.COUNTRY	Thailand	1.SITE OR AREA			1.PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled
2.NAME OF STUDY Rama VI Bridge Rehabilitation Project		The Rama VI bridge and neighboring areas, northern Bangkok				
3.SECTOR Transportation/Railway		2.PROJECT COST			(Description) Short-term plan * Completed with domestic funds --- the purpose of the project was tentatively attained. * Repair work on bridge piers and shoe resetting were implemented and the restriction on train speed lifted. Long-term plan * Double-tracking has not yet started due to its relation with a new road bridge. However, it seems that the State Railway of Thailand has started to make budgetary arrangements to repair the Rama VI Bridge and double-track it, in order to implement the double-tracking after construction of the New Rama Bridge that is now under way. (FY1993 Overseas Survey) Double - Tracking is scheduled to start soon after the approval of budget. It will cost 44 million baht. Construction period will be from Feb.94 to Aug.95. (FY1994 Domestic Survey) The construction works of RAMA VI bridge for track doubling has been started in May 1994 and scheduled to complete in September 1995 with the amount of Baht 43,750,000. The work is progressed by 51% as of October 1994. The approach at Bangkok side was designed to use composite bridges similar to the existing track which is in parallel. The work progress is about 61% as of October 1994 and expect to be completed by June 1995 with the total cost of Baht 45,207,500. The approach at Thonburi side (the other side) is now under designed. (FY1995 Domestic Survey) No additional information. (FY1995 Overseas Survey) The double-tracking started in May, 1994, and completed in July, 1995. It costed 47 million baht and was financed by SRT.	
4.REFERENCE NO.		3.CONTENTS OF MAJOR PROJECT(S)				
5.TYPE OF STUDY		(1) Survey to confirm present status riverbed scouring; Geological survey; Vibration survey (2) Analysis of causes of deformation (3) Study on repair policies ; (4) Basic design (5) Study on construction methods (6) Approximate calculation of costs (7) Detailed design (8) Preparation of calculation sheets for work execution (9) Cost estimation (10) Preparation of specifications * cost 1) above is for bridge piers and cost 2) for shoe resetting ** Implementation periods below are 1) for 10 months and 2) for 3 months.				
6.COUNTERPART AGENCY State Railway of Thailand		Total Cost Local Cost Foreign Cost 1) 1,353 1,353 2) 142 3)				
7.OBJECTIVES OF STUDY D/D and cost estimation, etc., for preparing bidding documents on the rehabilitation of the Rama VI bridge, which was in danger of collapse		4.FEASIBILITY AND ITS ASSUMPTIONS				
8.DATE OF SAV 1981/3		Imp. Period: 1983.1				
9.CONSULTANT(S) Japan Railway Technical Service		Feasibility: EIRR1) FIRR1) Yes/No EIRR2) FIRR2) EIRR3) FIRR3)				
10.STUDY TEAM No. of Members 18 Period Jan.1982-Dec.1982 (11 months)		Conditions and Development Impacts: In the short term, the current restrictions on large rolling stock and train speed are to be continued. In the long term, such measures as the repairing of bridge piers and shoe resetting are to be implemented.				
11.ASSOCIATED AND/OR SUBCONTRACTED STUDY -Survey by divers -Vibration survey -Excavation survey on bridge piers		5. TECHNICAL TRANSFER				
12.EXPENDITURE		1) OJT and JICA training program for counterparts 2) Employment of local consultants				
Total 87,560 (¥'000) Contracted 81,093		2.MAJOR REASONS FOR PRESENT STATUS				
		3.PRINCIPAL SOURCE OF INFORMATION				
		①, ②, ③				

和名 ラマ6世橋梁修復計画

(F/S,D/D)

PROJECT SUMMARY (M/P+F/S)

Compiled Mar.1986

Revised Mar.1996

ASE THA/S 204B/83

I. OUTLINE OF STUDY		II. SUMMARY OF STUDY RESULTS				III. PRESENT STATUS OF STUDIED PROJECT																													
1. COUNTRY	Thailand	1. SITE OR AREA				1. PRESENT STATUS	<input checked="" type="checkbox"/> Completed or in Progress <input type="checkbox"/> Promoting <input checked="" type="checkbox"/> Completed <input type="checkbox"/> Partially Completed <input type="checkbox"/> Delayed or Suspended <input type="checkbox"/> Implementing <input type="checkbox"/> Processing <input type="checkbox"/> Discontinued or Cancelled																												
2. NAME OF STUDY Development Project of the Industrial Port on the Eastern Seaboard		Coastal Area, Layan Province																																	
3. SECTOR Transportation/Port		2. PROJECT COST				(Description) The project is under implementation with the OECF financing.																													
4. REFERENCE NO.		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;">M/P 1)</td> <td style="width: 15%;">883,220</td> <td style="width: 15%;">Local Cost</td> <td style="width: 15%;">570,800</td> <td style="width: 15%;">Foreign Cost</td> <td style="width: 10%;">56,560</td> </tr> <tr> <td>(US\$1,000)</td> <td>2)</td> <td>Cost</td> <td>Cost</td> <td></td> <td></td> </tr> <tr> <td>(US\$1=239.2Yen)</td> <td>F/S 1)</td> <td>1,808,940</td> <td>668,491</td> <td></td> <td>1,140,449</td> </tr> <tr> <td></td> <td>2)</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>3)</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>						M/P 1)	883,220	Local Cost	570,800	Foreign Cost	56,560	(US\$1,000)	2)	Cost	Cost			(US\$1=239.2Yen)	F/S 1)	1,808,940	668,491		1,140,449		2)						3)		
M/P 1)	883,220	Local Cost	570,800	Foreign Cost	56,560																														
(US\$1,000)	2)	Cost	Cost																																
(US\$1=239.2Yen)	F/S 1)	1,808,940	668,491		1,140,449																														
	2)																																		
	3)																																		
5. TYPE OF STUDY M/P+F/S		3. CONTENTS OF MAJOR PROJECT(S)				Sep.1983 OECF E/S loan (1,720 million yen) Sep.1984 OECF loan on Map Ta Phut Industrial Port (5,610 million yen) Oct.1985 OECF loan on Map Ta Phut Industrial Port (16,050 million yen) and Industrial Estate (3,207 million yen) Oct.1985 D/D on Map Ta Phut Port completed Jan.1986 D/D on Industrial Estate completed Dec.1987 Construction of the Industrial Estate commenced Nov.1988 OECF loan on Satahip-Map Ta Phut Railway (3,002 million yen) (FY1991 Overseas Survey) 1989 Construction of the Port commenced (-1992) 1990 Construction of the Industrial Estate First Stage completed 1991 Construction of the Industrial Estate Second Stage commenced Scheduled to be completed in 1992 (FY1994 Domestic Survey)(FY1995 Domestic Survey) No additional information. (FY1995 Overseas Survey) Four(4) million tons of cargo could be handled in Laem-Chabang Port in 1995.																													
6. COUNTERPART AGENCY Industrial Estate Authority of Thailand, Port Authority of Thailand		<M/P>Development of Layan Province, Composed of Industrial Base, Port, Residential Area. The target year of the M/P is 2000. 1) Industrial Development: Gas separation plant, Soda ash plant, Petrochemical complex, Fertilizer complex, Iron & steel complex, Supporting industries, Down stream industries, Other industries. 2) Port development: Amount of cargo handled 23 million tons annually, 45 berths, total length 5,750m. 3) Urban Plan: New town 575ha, Population 71,500 Number of household 17,340 4) Infrastructure: Road, Water supply, Sewerage, Waste treatment, Railway(branch of the Chachoengsao - Sattaship line, length 25km, annual traffic volume transported 3.7 million tons) Electricity(total demand 1,354MW) Telephone(number of lines 10,000) Telex/Telegram terminals and other services 44 <F/S>1) Industrial Development: petorochemical, fertilizer, soda ash, various supporting industries, industrial estate Area 410ha, Quay wall 820m 2) Port Development: Quay-wall 850m, wharf 280m, breakwater 3,000m total length of berths 1,750m amount of cargo handled 4 million tons annually 3) Urban Development: Area 131ha, population 18,300 Number of Household 4,360 4) Infrastructure: Road, Water Supply, Sewerage, Waste treatment, Railway(Extension 24km, annual traffic volume transported 2 million tons), Electricity(total demand 133.5MW), Telephone(number of lines 3,000) Telex/Telegram terminals and other services(23)																																	
7. OBJECTIVES OF STUDY Establishing the Master Plan for Maplaput Port as an Industrial Port and feasibility study of the priority projects.		Imp. Period: 1984.1-1987.12				2. MAJOR REASONS FOR PRESENT STATUS (1) To formulate the core of development (2) High priority in Thailand National Plan																													
8. DATE OF SAV 1982/5		4. FEASIBILITY AND ITS ASSUMPTIONS																																	
9. CONSULTANT(S) Overseas Coastal Area Development Institute		<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;">Feasibility:</td> <td style="width: 15%;">EIRR1)</td> <td style="width: 15%;">15.70</td> <td style="width: 15%;">EIRR2)</td> <td style="width: 15%;">19.80</td> </tr> <tr> <td>Yes</td> <td>EIRR3)</td> <td></td> <td>EIRR2)</td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>EIRR3)</td> <td></td> </tr> </table>				Feasibility:	EIRR1)	15.70	EIRR2)	19.80	Yes	EIRR3)		EIRR2)					EIRR3)																
Feasibility:	EIRR1)	15.70	EIRR2)	19.80																															
Yes	EIRR3)		EIRR2)																																
			EIRR3)																																
10. STUDY TEAM No. of Members 9 Period Jul.1982-Nov.1983(17 months)		Conditions and Development Impacts: <M/P>[Impacts]1)Promotion of the Heavy industry at Eastern Seaboard Development. 2)Establishment of industries utilizing natural gas resources. 3)Acceleration of the region's urban-industrial development. 4)Increase in the economic growth of the nation and employment. <F/S>[Conditions]for Cargo Forecast:1985 GDP=4,350 A Bahts 2000 2000 GDP=11,200 A Bahts [Conditions of Industrial Development] GNP Growth (1981 - 1986) 6.6%(per annum) Manufacturing sector growth 7.6% Export oriented Industry 15.0% [Conditions] The value added which will be generated by the productive activity of the planned factories will be counted as the total benefit of this project. The benefits are calculated as the difference between the With-project and the Without-project conditions. [Impacts]1)Acceleration of regional development(esp. Map Ta Phut area). 2)Development of coastal shipping and port-related industries.				3. PRINCIPAL SOURCE OF INFORMATION ①, ②, ③, ④																													
11. ASSOCIATED AND/OR SUBCONTRACTED STUDY None		5. TECHNICAL TRANSFER Giving lecture on methods for Planning Ports and Industrial Estates																																	
12. EXPENDITURE																																			
Total		412,019 (¥'000)																																	
Contracted		411,680																																	