

JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
REPUBLIC OF THE PHILIPPINES

DETAILED ENGINEERING DESIGN STUDY
ON
PAN-PHILIPPINE HIGHWAY IMPROVEMENT PROJECT
(MINDANAO SECTION)

FINAL REPORT
MAIN TEXT

MARCH 1997

JICA LIBRARY



J 1134986 (7)

KATAHIRA & ENGINEERS INTERNATIONAL
NIPPON ENGINEERING CONSULTANTS CO., LTD.

SSF

CR(5)

97-018(2/89)



1134986 (7)

JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)

DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
REPUBLIC OF THE PHILIPPINES

DETAILED ENGINEERING DESIGN STUDY

ON

**PAN-PHILIPPINE HIGHWAY IMPROVEMENT PROJECT
(MINDANAO SECTION)**

**FINAL REPORT
MAIN TEXT**

MARCH 1997

**KATAHIRA & ENGINEERS INTERNATIONAL
NIPPON ENGINEERING CONSULTANTS CO., LTD.**

PREFACE

In response to a request from the Government of the Republic of the Philippines, the Government of Japan decided to conduct a detailed engineering design study on *Pan-Philippine Highway Improvement Project (Mindanao Section)* and entrusted the study to the Japan International Cooperation Agency (JICA).

JICA sent to the Philippines a study team headed by Mr. Kunihiko Sawano of Katahira & Engineers International, and composed of members from Katahira & Engineers International and Nippon Engineering Consultants Co., Ltd., twice between September 1995 to January 1997.

The team held discussions with the officials concerned of the Government of the Philippines, and conducted field surveys at the study area. After the team returned to Japan, further studies were made and the present report was prepared.

I hope that this report will contribute to the promotion of the project and to the enhancement of friendly relations between our two countries.

I wish to express my sincere appreciation to the officials concerned of the Government of the Republic of the Philippines for their close cooperation extended to the team.

March 1997



Kimio Fujita
President

Japan International Cooperation Agency

March 1997

Mr. Kimio Fujita
President
Japan International Cooperation Agency
Tokyo, Japan

Dear Mr. Fujita,

Letter of Transmittal


We are pleased to submit to you the Final Report of the Detailed Engineering Design Study on Pan-Philippine Highway Improvement Project (Mindanao Section) in the Republic of the Philippines. The report contains the advice and suggestions of the authorities concerned of the Government of Japan and your Agency as well as the Department of Public Works and Highways and other authorities concerned of the Government of the Philippines.

This report presents the results of the detailed engineering design including the preparation of construction plan and tender documents, cost estimate and environmental impact assessment. The project aims to cope with the various problems that the road presently suffers from, and to make the road solid, reliable and comfortable.

In view of the urgency of improving the project road which is the only axis in the east Mindanao, and of the need for socio-economic development in Mindanao Island as a whole, we recommend that the Government of the Philippines implement this project as a top priority.

We wish to take this opportunity to express our sincere gratitude to your Agency and the Ministry of Foreign Affairs. We also wish to express our deep gratitude to the Department of Public Works and Highways and other authorities concerned of the Government of the Philippines for the close cooperation and assistance extended to us during our investigations and study.

Very truly yours,



Kunihiko Sawano
Team Leader,
Detailed Engineering Design Study
on Pan-Philippine Highway
Improvement Project (Mindanao Section)

...the ... of ...

...the ... of ...

...the ... of ...

...the ... of ...

...the ... of ...

...the ... of ...

...the ... of ...

...the ... of ...


TABLE OF CONTENTS

| | <u>PAGE</u> |
|------------------|---|
| PART I | INTRODUCTION |
| CHAPTER 1 | INTRODUCTION |
| 1.1 | Background of the Study 1-1 |
| 1.2 | Objective of the Study 1-2 |
| 1.3 | Study Road 1-2 |
| 1.4 | Scope of the Study 1-2 |
| 1.5 | Study Flow 1-2 |
| 1.6 | Organization of the Study 1-4 |
| 1.7 | Reports 1-5 |
| PART II | ENGINEERING SURVEY |
| CHAPTER 2 | EXISTING ROAD CONDITION SURVEY |
| 2.1 | Roadway and Drainage Survey 2-1 |
| 2.2 | Slope Survey 2-10 |
| 2.3 | Bridge Survey 2-11 |
| CHAPTER 3 | TRAFFIC SURVEY |
| 3.1 | Traffic Survey 3-1 |
| 3.2 | Estimated Future Traffic 3-1 |
| CHAPTER 4 | TOPOGRAPHIC SURVEY |
| 4.1 | Route Survey 4-1 |
| 4.2 | Topographic Survey at Bridge Sites, Slopes and Flood-prone Areas 4-3 |
| 4.3 | River Profile and Cross-section Survey 4-3 |
| 4.4 | Aerial Photographic Survey and Mapping 4-3 |
| CHAPTER 5 | SOILS/MATERIAL AND GEOTECHNICAL INVESTIGATION |
| 5.1 | Geotechnical Investigation for Pavement Rehabilitation Design 5-1 |
| 5.2 | Geotechnical Investigation for Slope Protection Design 5-2 |
| 5.3 | Geotechnical Investigation for Bridge Foundation Design 5-2 |
| 5.4 | Soils Investigation for Soft Ground Sections 5-3 |
| 5.5 | Soils Investigation for Sianib Section 5-3 |
| 5.6 | Soils Investigation for Liboganon River Bank Design 5-4 |
| 5.7 | Material Sources Investigation 5-4 |

| | | |
|------------------|--|------|
| CHAPTER 6 | HYDROLOGICAL INVESTIGATION AND ANALYSIS | |
| 6.1 | Procedure | 6-1 |
| 6.2 | Preparation Works and Field Survey | 6-2 |
| 6.3 | Data Collection | 6-2 |
| 6.4 | Rainfall Analysis | 6-5 |
| 6.5 | Run-off Analysis | 6-14 |
| 6.6 | Non-uniform Flow Analysis | 6-19 |
| 6.7 | Inundation Analysis | 6-22 |
| 6.8 | Scouring Around Pier | 6-25 |
| 6.9 | Summary of the Result of Analysis | 6-31 |
| 6.10 | Recommendation | 6-38 |


PART III DETAILED DESIGN

| | | |
|-------------------|---|-------|
| CHAPTER 7 | CONTRACT PACKAGING | |
| 7.1 | Contract Packaging | 7-1 |
| 7.2 | Naming of Contract Packages | 7-2 |
| CHAPTER 8 | ROADWAY REHABILITATION/IMPROVEMENT | |
| 8.1 | Design Policies | 8-1 |
| 8.2 | Geometric Design Standards | 8-1 |
| 8.3 | Pavement Design | 8-2 |
| 8.4 | Shoulder Design | 8-35 |
| 8.5 | Typical Roadway Cross-section | 8-36 |
| 8.6 | Monkayo Bypass Alignment Study | 8-44 |
| 8.7 | Embankment Slope Stability and Consolidation Settlement at Soft Ground Areas | 8-49 |
| CHAPTER 9 | ROADWAY DRAINAGE IMPROVEMENT | |
| 9.1 | Design of Culverts (RCPC/RCBC) | 9-1 |
| 9.2 | Side Ditches/Under Drain | 9-8 |
| CHAPTER 10 | BRIDGE REHABILITATION/IMPROVEMENT | |
| 10.1 | Present Condition of Bridges | 10-1 |
| 10.2 | Rehabilitation Criteria and Rehabilitation Method | 10-7 |
| 10.3 | Structural Design Criteria | 10-19 |
| 10.4 | Scope of Works for Bridges | 10-22 |
| CHAPTER 11 | SLOPE PROTECTION | |
| 11.1 | Design Criteria | 11-1 |
| 11.2 | Scope of Works for Slopes | 11-6 |
| CHAPTER 12 | COUNTERMEASURES AGAINST FLOOD | |
| 12.1 | Design Criteria | 12-1 |
| 12.2 | Scope of Work of Countermeasures | 12-5 |




LOCATION MAP

TYPICAL SITE CONDITION AND IMPROVEMENT WORKS




CONCRETE PAVEMENT IN VERY BAD CONDITION. TOTAL RECONSTRUCTION WITH CONCRETE PAVEMENT.



CONCRETE PAVEMENT IN BAD CONDITION WITH PARTIALLY BROKEN SLABS. REPLACEMENT OF BROKEN SLABS WITH CONCRETE PAVEMENT AND AC OVERLAY.



ANDANAN BRIDGE. SERIOUSLY DETERIORATED SUPERSTRUCTURE WITH DEEP LOCAL SCOURING AT PIERS. TOTAL RECONSTRUCTION.



BAYUGAN BRIDGE. SERIOUSLY DETERIORATED SUPERSTRUCTURE. REPLACEMENT OF SUPERSTRUCTURE.



EMBANKMENT SLOPE FAILURE. ONE LANE AFFECTED. SLOPE PROTECTION WITH SURFACE AND SUBSURFACE WATER CONTROL.



EMBANKMENT SLOPE FAILURE. SHOULDER AFFECTED. SLOPE PROTECTION.



BURIED PIPE CULVERT WITHOUT INLET FACILITY. REPLACEMENT WITH NEW PIPE CULVERT.



GRAVEL SECTION AT SOFT GROUND AREA. AC PAVEMENT AFTER PRE-LOADING.

PART IV COST ESTIMATES AND TENDER DOCUMENTS

CHAPTER 13 PREPARATION OF CONSTRUCTION PLAN

| | |
|---|-------|
| 13.1 Basic Principles | 13-1 |
| 13.2 Maintenance of Traffic | 13-1 |
| 13.3 Construction Method | 13-4 |
| 13.4 Construction Materials | 13-6 |
| 13.5 Construction Equipment/Plants | 13-10 |
| 13.6 Work Program and Construction Period | 13-11 |

CHAPTER 14 COST ESTIMATES

| | |
|--|-------|
| 14.1 Unit Cost Analysis | 14-1 |
| 14.2 Estimated Construction Cost | 14-9 |
| 14.3 Right-of-Way Acquisition and Compensation Cost | 14-10 |
| 14.4 Consulting Services Cost for Construction Supervision | 14-10 |
| 14.5 Project Cost | 14-10 |

CHAPTER 15 PREPARATION OF TENDER DOCUMENTS

| | |
|---------------------------------------|------|
| 15.1 Prequalification Documents | 15-1 |
| 15.2 Tender Documents | 15-1 |

PART V PREPARATION FOR PROJECT IMPLEMENTATION

CHAPTER 16 ENVIRONMENTAL IMPACT STATEMENT

| | |
|--|------|
| 16.1 ECC Along the Existing Alignment | 16-1 |
| 16.2 EIS Along New Alignment: Monkayo Bypass | 16-1 |

CHAPTER 17 PROJECT IMPLEMENTATION PROGRAM

| | |
|---|------|
| 17.1 Current Status on Preparation for Project Implementation | 17-1 |
| 17.2 Implementation Program | 17-1 |

CHAPTER 18 PROJECT EVALUATION AND RECOMMENDATIONS

| | |
|-------------------------------|------|
| 18.1 Project Evaluation | 18-1 |
| 18.2 Recommendations | 18-2 |

| <u>TABLES</u> | <u>PAGE</u> |
|----------------------|---|
| CHAPTER 2 | |
| 2.1-1 | Pavement Distress Survey Result 2-4 |
| 2.1-2 | Example of Accomplished Field Survey Format 2-6 |
| 2.1-3 | Example of Accomplished Field Format-1 2-7 |
| CHAPTER 3 | |
| 3.2-1(1/2) | Future Traffic Volume by Section 3-4 |
| (2/2) | Future Traffic Volume by Section 3-5 |
| CHAPTER 5 | |
| 5.3-1 | Geotechnical Investigation at Bridge Sites 5-3 |
| CHAPTER 6 | |
| 6.3-1 | Inventory of Rainfall Data 6-3 |
| 6.3-2 | Annual Maximum Daily Rainfall and Annual Rainfall 6-3 |
| 6.4-1 | Rainfall Intensity of Three PAGASA Climatological Station 6-6 |
| 6.4-2(1/4) | Rainfall Depth - Duration Curves 6-9 |
| (2/4) | Rainfall Depth - Duration Curves 6-10 |
| (3/4) | Rainfall Depth - Duration Curves 6-11 |
| (4/4) | Rainfall Depth - Duration Curves 6-12 |
| 6.4-3 | Equation of Rainfall Duration Curves 6-13 |
| 6.5-1 | Model Hyetograph by Method of Soil Conservation Services 6-16 |
| CHAPTER 7 | |
| 7.2-1 | Contract Package Name and Construction Limits 7-2 |
| CHAPTER 8 | |
| 8.2-1 | Geometric Design Standards Originally Adopted for Pan-Philippine Highway 8-1 |
| 8.2-2 | Geometric Design Standards for Pan-Philippine Highway (Mindanao Section) 8-3 |
| 8.3-1 | Initial Performance Period for the Project 8-5 |
| 8.3-2 | Design Requirements 8-7 |
| 8.3-3 | Recommended Bus and Truck Factors 8-6 |
| 8.3-4 | Bus and Truck Factor Based on Axle Load Survey 8-8 |
| 8.3-5 | Traffic Loading Class 8-8 |
| 8.3-6 | MR AND K-VALUE 8-11 |
| 8.3-7 | Required PCC Slab Thickness: PCC Reconstruction 8-20 |
| 8.3-8 | Required Structural Number: AC Reconstruction 8-20 |
| 8.3-9 | Required AC Overlay Thickness, Pavement Condition (Very Bad) 8-21 |

| | | |
|-------------|---|------|
| 8.3-10 | Required AC Overlay Thickness, Pavement Condition (Bad) | 8-22 |
| 8.3-11 | Required AC Overlay Thickness, Pavement Condition (Fair) | 8-23 |
| 8.3-12(1/2) | Summary of Selected Pavement Rehabilitation Method | 8-33 |
| 8.3-12(2/2) | Summary of Selected Pavement Rehabilitation Method | 8-34 |
| 8.7-1 | Bridge Approach Embankment Slope Stability | 8-50 |
| | and Consolidation Settlement | 8-52 |
| 8.7-2 | Estimated Consolidation Settlement | 8-52 |

CHAPTER 9

| | | |
|-------|--|-----|
| 9.1-1 | Summary of Proposed Works for Culverts | 9-6 |
| 9.1-2 | Summary of Culvert Improvement/Rehabilitation by Package.. | 9-7 |
| 9.2-1 | Summary of Scope of Work for Side Ditches and Under Drain | 9-9 |

CHAPTER 10

| | | |
|-------------|---|-------|
| 10.1-1(1/3) | Summary of Bridges | 10-3 |
| (2/3) | Summary of Bridges | 10-4 |
| (3/3) | Summary of Bridges | 10-5 |
| 10.2-1 | Bridge Rehabilitation Methods and Their Application Criteria | 10-11 |
| 10.3-1 | Acceleration Coefficient (A) For Total Reconstruction Bridges | 10-21 |
| 10.4-1 | Summary of Scope of Work for Bridges | 10-23 |
| 10.4-2(1/2) | Scope of Works for Each Bridge | 10-25 |
| 10.4-2(2/2) | Scope of Works for Each Bridge | 10-26 |
| 10.4-3 | Justification and Outline of New Structure of Total Reconstruction and New Bridges | 10-27 |

CHAPTER 11

| | | |
|-----------|--|-------|
| 11.1-1(1) | Generally Applicable Slope Protection Works to Each Type of Slope Failure | 11-2 |
| (2) | Generally Applicable Slope Protection Works to Each Type of Slope Failure | 11-3 |
| (3) | Generally Applicable Slope Protection Works to Each Type of Slope Failure | 11-4 |
| (4) | Generally Applicable Slope Protection Works to Each Type of Slope Failure | 11-5 |
| 11.2-1 | Summary of Scope of Work For Slope Protection | 11-6 |
| 11.2-2 | Causes of Embankment Slope Failure and Slope Protection Works | 11-8 |
| 11.2-3 | Scope of Work for Each Slope | 11-10 |

CHAPTER 12

| | | |
|-----------|---|------|
| 12.1-1 | Criteria for Assessment of Flood Severity | 12-1 |
| 12.1-2 | Countermeasures Along Road | 12-3 |
| 12.1-3 | Countermeasures Along River | 12-4 |
| 12.2-1 | Countermeasures Adopted | 12-5 |
| 12.2-2(1) | Countermeasures Against Flood of Each Flood Section | 12-8 |
| 12.2-2(2) | Countermeasures Against Flood of Each Flood Section | 12-9 |

CHAPTER 13

| | | |
|-------------|---|-------|
| 13.2-1 | Application of Method for Maintenance of Traffic | 13-2 |
| 13.3-1 | Major Works | 13-4 |
| 13.3-2 | Major Equipment Used for Work | 13-5 |
| 13.4-1(1/2) | Material Sources | 13-6 |
| 13.4-1(2/2) | Material Sources | 13-7 |
| 13.6-1 | Work Schedule for Reconstruction of Short Bridge (L < 30m) . | 13-12 |
| 13.6-2 | Work Schedule of Middle Bridge (L = 30~60m) | 13-12 |
| 13.6-3 | Work Schedule of Andanan Bridge (L = 180m) | 13-12 |
| 13.6-4 | Work Schedule For Construction of Monkayo Bypass No. 2 Bridge (L = 146m) | 13-13 |
| 13.6-5 | Work Schedule of New Gov. Miranda Bridge (L-650m) | 13-13 |
| 13.6-6 | Work Program of Contract Package 1 | 13-15 |
| 13.6-7 | Work Program of Contract Package 2 | 13-15 |
| 13.6-8 | Work Program of Contract Package 3 | 13-15 |
| 13.6-9 | Work Program of Contract Package 4 | 13-16 |
| 13.6-10 | Work Program of Contract Package 5 | 13-16 |
| 13.6-11 | Work Program of Contract Package 6 | 13-16 |
| 13.6-12 | Work Program of Contract Package 7 | 13-17 |
| 13.6-13 | Work Program of Contract Package 8 | 13-17 |
| 13.6-14 | Work Program of Contract Package 9 | 13-17 |
| 13.6-15 | Work Program of Contract Package 10 | 13-18 |
| 13.6-16 | Work Program of Contract Package 11 | 13-18 |
| 13.6-17 | Work Program of Contract Package 12 | 13-18 |
| 13.6-18 | Work Program of Contract Package 13 | 13-19 |
| 13.6-19 | Work Program of Contract Package 14 | 13-19 |
| 13.6-20 | Work Program of Contract Package 15 | 13-19 |
| 13.6-21 | Work Program of Contract Package 16 | 13-20 |
| 13.6-22 | Work Program of Contract Package 17 | 13-20 |
| 13.6-23 | Work Program of Contract Package 18 | 13-20 |
| 13.6-24 | Work Program of Contract Package 19 | 13-19 |

CHAPTER 14

| | | |
|--------|--|------|
| 14.1-1 | Cost Component For Selected Construction Items | 14-3 |
| 14.1-2 | Equipment Rental Rates (ACEL RATES As of November 1992) | 14-5 |
| 14.1-3 | Cost of Commercial Materials | 14-7 |
| 14.1-4 | Labor Rates | 14-8 |
| 14.2-1 | Summary of Construction Cost | 14-9 |

| | | |
|--------|---------------------------------|-------|
| 14.3-1 | ROW and Compensation Cost | 14-10 |
| 14.5-1 | Summary of Project Cost | 14-10 |

CHAPTER 16

| | | |
|--------|---|------|
| 16.2-1 | Probable Impacts and Proposed Mitigating Measures | 16-3 |
|--------|---|------|

CHAPTER 17

| | | |
|--------|---|------|
| 17.2-1 | Implementation Schedule and Annual Fund Requirement | 17-4 |
|--------|---|------|

| FIGURES | PAGE |
|------------------|---|
| CHAPTER 1 | |
| 1.5-1 | Study Flow Diagram 1-3 |
| 1.6-1 | Organization Chart 1-4 |
| CHAPTER 2 | |
| 2.1-1 | Legends Used for Sketching Pavement Distress 2-2 |
| 2.1-2 | Example of Accomplished Field Survey Format 2-3 |
| 2.1-3 | Legends Used for Accomplishing Field Format 2-5 |
| 2.1-4 | Example of Accomplished Field Survey Format-2 2-8 |
| 2.1-5 | Classification of Headwall Types 2-9 |
| 2.3-1(1) | An Example of Detailed Dimension Survey 2-12 |
| (2) | An Example of Detailed Dimension Survey 2-13 |
| 2.3-2 | An Example of Crack Survey 2-14 |
| CHAPTER 3 | |
| 3.1-1 | Traffic Survey Stations 3-2 |
| 3.1-2 | AADT (1994) and Average Travel Speed 3-3 |
| CHAPTER 5 | |
| 5.7-1 | Borrow Sources Investigated 5-6 |
| 5.7-2 | Base/Subbase Material Sources Investigated 5-7 |
| 5.7-3 | Concrete Aggregate Sources Investigated 5-8 |
| CHAPTER 6 | |
| 6.1-1 | Flow Chart of Hydrological Analysis 6-1 |
| 6.4-1 | Comparison of Calculated Result With PAGASA'S DATA 6-7 |
| 6.5-1 | Hydrograph at NIA WEIR IN SIMULAO RIVER 6-18 |
| 6.7-1 | Three Dimensional Chart in Simulao Inundation Area 6-26 |
| 6.7-2(1/2) | Inundation Area of Simulao River 6-27 |
| (2/2) | Inundation Area of Simulao River 6-28 |
| 6.8-1 | Relation Between Maximum Scoured Depth and Flow Water Depth 6-29 |
| 6.9-1 | Peak Discharge Volume of Legaspi River 6-33 |
| 6.9-2 | Arega River and Its Surroundings 6-37 |
| 6.9-3 | Liboganon River Bank Elevation 6-39 |
| CHAPTER 8 | |
| 8.3-1 | Traffic Loading Class 8-9 |
| 8.3-2 | Traffic Loading Class and Contract Packages 8-10 |
| 8.3-3 | Initial Construction Cost 8-15 |

| | | |
|----------|--|------|
| 8.3-4(1) | Total Discounted Cost | 8-16 |
| (2) | Total Discounted Cost | 8-17 |
| (3) | Total Discounted Cost | 8-18 |
| 8.3-5 | Proposed Payment Structure: Package 5 | 8-28 |
| 8.5-1 | Typical Roadway Cross-Section: ACO Type-1 | 8-37 |
| 8.5-2 | Typical Roadway Cross-Section: ACO Type-2 | 8-38 |
| 8.5-3 | Typical Roadway Cross-Section: PCC Type-1 | 8-39 |
| 8.5-4 | Typical Roadway Cross-Section: PCC Type-2 | 8-40 |
| 8.5-5 | Typical Roadway Cross-Section: PCC Type-5 | 8-41 |
| 8.5-6 | Typical Roadway Cross-Section: PCC Type-6 | 8-42 |
| 8.5-7 | Typical Roadway Cross-Section: ACO Type-1 | 8-43 |
| 8.6-1 | Present Condition of Monkayo Town Area | 8-45 |
| 8.6-2 | Possible Corridors For Bypass Alignment | 8-47 |
| 8.6-3 | Alternative Alignments For Monkayo Bypass | 8-48 |
| 8.7-1 | Typical Cross-Section at Bridge Approaches | 8-51 |

CHAPTER 9

| | | |
|----------|--|------|
| 9.1-1 | Procedure of RCPC/RCBC Capacity Analysis | 9-2 |
| 9.1-2(1) | Discharge Capacity of Culvert: Pipe | 9-3 |
| (2) | Discharge Capacity of Culvert: Box | 9-4 |
| (3) | Discharge Capacity of Culvert: Box | 9-5 |
| 9.2-1(1) | Discharge Capacity of Side Ditches | 9-10 |
| (2) | Discharge Capacity of Side Ditches | 9-11 |
| (3) | Discharge Capacity of Side Ditches | 9-12 |

CHAPTER 10

| | | |
|-------------|--|-------|
| 10.1-1 | Location of Existing Bridges | 10-2 |
| 10.4-1 | Bridges To Be Rehabilitated/Improved Under This Project | 10-24 |
| 10.4-2 | Alternative Schemes For Andanan Bridges | 10-31 |
| 10.4-3 | Alternative Schemes For Monkayo Bypass 2 Bridge | 10-33 |
| 10.4-4(1/2) | Alternative Schemes For Gov.Miranda Bridges | 10-35 |
| 10.4-2(2/2) | Alternative Schemes For Gov.Miranda Bridges | 10-36 |

CHAPTER 11

| | | |
|--------|--|------|
| 11.2-1 | Slopes for Protection Works | 11-7 |
| 11.2-2 | Slope Protection Work at Km.1240+150 | 11-9 |

CHAPTER 12

| | | |
|-------------|--|-------|
| 12.2-1 | Flood Sections Needing Countermeasures | 12-6 |
| 12.2-2(1/2) | Simulao River Flood Area | 12-10 |
| 12.2-2(2/2) | Simulao River Flood Area | 12-11 |
| 12.2-3 | Countermeasures For Liboganon River | 12-12 |

CHAPTER 13

13.2-1 **Monkayo Bypass** 13-3
13.4-1 **Material Sources: Aggregate for Concrete** 13-8
13.4-2 **Material Sources: Subbase/Base Course** 13-9

CHAPTER 16

16.2-1 **Outline of Monkayo Bypass** 16-2

ABBREVIATIONS

| | |
|---------------|--|
| AADT | : Annual Average Daily Traffic |
| AASHTO | : American Association of State Highway and Transportation Officials |
| AC | : Asphalt Concrete |
| ACEL | : Associated Construction Equipment Lessors, Inc. |
| ADB | : Asian Development Bank |
| ADT | : Average Daily Traffic |
| ARMM | : Autonomous Region for Muslim Mindanao |
| AWP | : Annual Work Program |
| B/C | : Benefit/Cost |
| BOE | : Bureau of Equipment |
| BOM | : Bureau of Maintenance |
| CAR | : Cordillera Autonomous Region |
| CBR | : California Bearing Ratio |
| CEO | : City Engineering Office |
| DEO | : District Engineering Office |
| DENR | : Department of Environment and Natural Resources |
| DPWH | : Department of Public Works and Highways |
| ECA | : Environmentally Critical Area |
| ECC | : Environmental Compliance Certificate |
| ECP | : Environmentally Critical Project |
| EIA | : Environmental Impact Assessment |
| EIS | : Environmental Impact System |
| EMB | : Environmental Management Bureau |
| EMK | : Equivalent Maintenance Kilometer |
| EO | : Executive Order |
| ESAL | : Equivalent Single Axle Load |
| FWD | : Falling Weight Deflectometer |
| FYB | : First Year Benefit |
| GDP | : Gross Domestic Product |
| GNP | : Gross National Product |
| GOJ | : Government of Japan |
| GOP | : Government of the Philippines |
| GPDP | : Gross Provincial Domestic Product |
| GRDP | : Gross Regional Domestic Product |
| GVA | : Gross Value Added |
| HCM | : Highway Capacity Manual |
| IACEP | : Inter-Agency Committee on Environmental Protection |
| IBRD | : International Bank for Reconstruction and Development |
| IEE | : Initial Environmental Examination |
| IRI | : International Roughness Index |
| IRF | : Immediate Response Fund |
| IRR | : Internal Rate of Return |
| JICA | : Japan International Cooperation Agency |
| LOI | : Letter of Instruction |
| LTO | : Land Transportation Office |
| MBA | : Maintenance By Administration |
| MBC | : Maintenance By Contract |
| MTPDP | : Medium Term Philippine Development Plan |
| MTPIP | : Medium Term Public Investment Program |

| | |
|-----------------|--|
| NCR | : National Capital Region |
| NCSO | : National Census and Statistical Office |
| NDT | : Non-Destructive Test |
| NEDA | : National Economic and Development Authority |
| NEPC | : National Environmental Protection Council |
| NIA | : National Irrigation Administration |
| NPV | : Net Present Value |
| NRR | : Net Reproduction Rate |
| NSCB | : National Statistical Coordination Board |
| NSO | : National Statistics Office |
| NTCP | : National Traffic Count Program |
| OD | : Origin-Destination |
| OECF | : Overseas Economic Cooperation Fund |
| PAGASA | : Philippine Atmospheric, Geophysical and Astronomical Services Administration |
| PB | : Performance Budget |
| PCC | : Portland Cement Concrete |
| PCDG | : Prestressed Concrete Deck Girder |
| PD | : Philippine Description |
| P.D. | : Presidential Decree |
| PHIVOLCS | : Philippine Institute of Volcanology and Seismology |
| PHMMS | : Philippine Highway Maintenance Management System |
| PPP | : Philippine Population Projection |
| PSI | : Present Serviceability Index |
| PSR | : Present Serviceability Rating |
| RCBC | : Reinforced Concrete Box Culvert |
| RCDG | : Reinforced Concrete Deck Girder |
| RCPC | : Reinforced Concrete Pipe Culvert |
| RES | : Reinforced Equipment Service |
| ROW | : Right-of-Way |
| RRI | : Rehabilitation Requirement Index |
| RRR | : Rehabilitation Requirement Rating |
| SN | : Structural Number |
| SPT | : Standard Penetration Test |
| VOC | : Vehicle Operating Cost |

PART I

INTRODUCTION

CHAPTER 1 INTRODUCTION

1902

1903

1904

CHAPTER 1

INTRODUCTION

1.1 BACKGROUND OF THE STUDY

The Government of the Philippines, in the Medium-Term Philippine Development Plan, 1993-1998, puts emphasis on the infrastructure development to support the productive sector growth and reduce the regional disparities.

The Pan-Philippine Highway is the most important trunkline in the country's road network running through the four major islands of Luzon, Samar, Leyte and Mindanao with a total length of 2,100 km. The construction of the Highway, which was then a long-cherished desire of the country to attain the national targets such as regional development, industrial growth, preservation of peace and order, national unification, etc., was started in 1969 and completed in 1979.

Now, in 17 to 26 years after opening to traffic, the Pan-Philippine Highway suffers various problem such as progress of pavement deterioration, repeated slope failures in the mountainous areas, damage of bridges and so on.

To cope with the said problems, the Government of the Philippines conducted the following studies with technical assistance provided by JICA: Feasibility Study of Philippine Road Disaster Prevention Project (June 1984), Feasibility Study of Philippine Road Disaster Prevention Project, Stage II (July 1985), Feasibility Study of the Road Improvement Project on the Pan-Philippine Highway (September 1987), and Feasibility Study on Rehabilitation and Maintenance of Bridges along Arterial Roads (June 1989). These studies cover the Luzon, Samar and Leyte sections of the Pan-Philippine Highway and the rehabilitation projects formulated therein are now being implemented.

Mainly for the reason of peace and order problem, rehabilitation of Mindanao section of the Highway has been left behind although it is of urgent necessity to promote the development of Mindanao. In the restoration of peace and order situation, the Government of the Philippines has decided to start the rehabilitation of the Mindanao section of the Highway and conducted the Feasibility Study on Pan-Philippine Highway Rehabilitation Project (Mindanao Section) from March 1994 to May 1995 with technical assistance provided by JICA.

In view of the priority and urgency of the project, the Government of the Philippines further sought a technical assistance from the Government of Japan for the conduct of the **DETAILED ENGINEERING DESIGN STUDY ON PAN-PHILIPPINE HIGHWAY IMPROVEMENT PROJECT (MINDANAO SECTION)** (the Study).

In response to the request of the government of the Philippines, the Government of Japan decided to conduct the Study. JICA, the official agency responsible for the implementation of the technical cooperation programs of the Government of

Japan, organized a study team to be engaged in the Study. The JICA Study Team, in close collaboration with the DPWH Counterpart Team, commenced work in August 1995 and completed the Study in March 1997.

1.2 OBJECTIVE OF THE STUDY

The objective of the Study is to prepare the detailed engineering design and tender documents for the Pan-Philippine Highway Improvement Project (Mindanao Section).

1.3 STUDY ROAD

The Study Road is the Pan-Philippine Highway from Lipata Ferry Terminal (Km. 1,113+397) up to the end of the Davao City Diversion Road (Km. 1,515+949) with a length of 403.4 km.

1.4 SCOPE OF THE STUDY

In order to achieve the objective mentioned above, the Study covered the following items:

First Period of the Study

- Collection and Review of Relevant Studies
- Detailed Investigation on Existing Road Condition
- Topographic Survey and Mapping
- Geotechnical Investigation
- Hydrological Investigation
- Detailed Design (1) *

Second Period of the Study


- Detailed Design (2) *
- Preparation of Environmental Impact Statement for the Monkayo Bypass Construction Project
- Preparation of Construction Plan
- Project Cost Estimate
- Preparation of Implementation Program
- Preparation of Tender and Contract Documents

* Note: Detailed Design (1) covers 11 contract packages with higher priority out of 19 packages in total (see Chapter 6 as for contract packaging), while Detailed Design (2) covers the rest packages.

1.5 STUDY FLOW

The Study flow of the whole work is schematically shown in Figure 1.5-1.

FIGURE 1.5-1 STUDY FLOW DIAGRAM



1.6 ORGANIZATION OF THE STUDY

JICA organized a Study Team and DPWH organized a Counterpart Team and a Steering Committee. The Study was carried out jointly by the JICA Study Team and the DPWH Counterpart Team under the guidance of the DPWH Steering Committee. The organization chart is shown in Figure 1.6-1.




FIGURE 1.6-1 ORGANIZATION CHART

The JICA Study Team was composed of the following members:

- Team Leader/Highway Planner : KUNIHICO SAWANO
- Deputy Team Leader/Highway Engineer 1 : MITSUO HATAKEYAMA
- Highway Engineer 2 : KEIJI AOKI
- Bridge Engineer 1 : MOUSHUN YABIKU
- Bridge Engineer 2 : AL HILER
- Slope Protection Engineer : RICHARD PURSER
- Drainage Engineer : MITSUNORI MIZUISHI
- Geotechnical Engineer : SHIGERU KOBAYASHI
- Survey Engineer : SYUNICHI USAMI
- Hydrological/Hydraulic Engineer : SUSUMU HONDA
- Environmental Engineer : KAZUHIRO HASEGAWA
- Construction Engineer/Cost Estimator : MASARU IWAKI
- Specification Engineer : TERUMI MOCHIZUKI

The DPWH Counterpart Team was composed of the following members:

A. Key Staff:

- Team Leader : GERONIMO ALONZO
- Project Coordinator : JUANITO ALAMAR
- Highway Engineers : GENEROSO ALCONIS
CORAZON ARCETA
- Bridge Engineers : REMEGIO CALEZE
ANTONIO YAPTANGCO
- CAD Engineers : ARTURO FLORES
CASAN BUSRAN
ARIEL GAYO

- Slope Engineer : GENEROSO JOVES
- Drainage Engineers : FILOMENA VALES
FRANCIS ESCOBAR

B. Supporting Staff:

- Draftsmen : ROMEO NAUNGAYAN
ANTONIO VALENZUELA
ANTHONY CASTUERAS
DIOSDADO DIEGO
- Bookkeeper/Secretary : MA. LOURDES SANTOS
- Typist/Word Processor : JASMIN FIGUERAS
ESPERANZA AGUSTIN
- Xerox Machine Operator : RICARDO TING
- Utilityman : DANTE ZAMORA

The DPWH Steering Committee was composed of the following members:

- Chairman : TEODORO T. ENCARNACION
Undersecretary
- Member : MANUEL M. BONOAN
Assistant Secretary
- Member : BIENVENIDO LEUTERIO
Director, Bureau of Design
- Member : CLARITA BANDONILLO
Director, Bureau of Construction
- Member : DOMINADOR Y. SANTOS
Director, PMO-PJHL
- Member : JOSE P. GLORIA
Project Manager III, PMO-FS
- Member : JUAN D. LUALHATI
Director, Planning Service
- Member : ERNESTO SILVELA
Director, Region XI
- Member : CONRADO REPATO
Director, Region XIII
- Member : TAKAAKI KUSAKABE
JICA Adviser for Highway Engineering

1.7 REPORTS

The following reports were prepared during the Study:

- Inception Report (September, 1995)
- Interim Report (March, 1996)
- Implementation Program (August, 1996)
- Environmental Impact Statement
For Monkayo Bypass Construction (October, 1996)
- Draft Final Report (January, 1997)

The final report is organized with the following:

- Executive Summary
- Main Text
- Appendix
- Drawings
- Design Analysis Reports
- Pre-qualification Documents
- Tender and Contract Documents
- Cost Analysis Report
- Quantity Calculation Reports

PART II

ENGINEERING SURVEY

CHAPTER 2 EXISTING ROAD CONDITION SURVEY

CHAPTER 3 TRAFFIC SURVEY

CHAPTER 4 TOPOGRAPHIC SURVEY

**CHAPTER 5 SOILS/MATERIAL AND GEOTECHNICAL
INVESTIGATION**

**CHAPTER 6 HYDROLOGICAL INVESTIGATION
AND ANALYSIS**

SECTION

STATEMENT OF WORK

| | |
|--|----------|
| 1. PROJECT OBJECTIVES AND SCOPE | 1.000000 |
| 2. DELIVERABLES | 2.000000 |
| 3. PROJECT PHASES | 3.000000 |
| 4. RESOURCE REQUIREMENTS AND RISK MANAGEMENT | 4.000000 |
| 5. PROJECT COMMUNICATION AND REPORTING | 5.000000 |
| 6. PROJECT CLOSURE AND EVALUATION | 6.000000 |

CHAPTER 2

EXISTING ROAD CONDITION SURVEY

2.1 ROADWAY AND DRAINAGE SURVEY

2.1.1 Pavement Condition Survey

Pavement condition survey was undertaken for the entire stretch of the Study Road. Pavement distresses of the following were sketched on the field survey sheet for each slab:

Pavement Distress Surveyed

- Cracks (open cracks as well as sealed cracks)
- Cracks with faulting
- Potholes
- Scaling
- Depression
- Pop-out
- Patching

Other Information


- Pavement with overlay
- Section under construction
- Gravel section
- Location of kilometer post
- Bridge section

Figure 2.1-1 shows legends used for sketching and Figure 2.1-2 shows an example of accomplished field survey format.

The survey team walked all along the Study Road in order to sketch pavement distresses. Average speed of the survey of one survey team was about 10 km per day.

Data obtained were processed as shown in Table 2.1-1, using the following two indices:

- Crack ratio = crack length (m)/1,000 sq.m.
- Number of slabs with depressions and cracks with faulting.



LEGENDS :

1. Cracks ———
2. Potholes — Ph
3. Patching — Pa
4. Cracks with Faulting — Fc
5. Sealing — Sc
6. Depression — De
7. Pop out — Po
8. Overlay — OL
(Sketch area of pavement with overlay)
9. Under Construction — UC
10. Gravel — Gr
(Except Under Construction)
11. Other Information
 - Kilometer Post
 - Bridge

FIGURE 2.1.1 LEGENDS USED FOR SKETCHING PAVEMENT DISTRESS

FIGURE 2.1-2 EXAMPLE OF ACCOMPLISHED FIELD SURVEY FORMAT

Date : 10-15-95

Sheet No : 1/3

Km. 1266+000




TABLE 2.1-1 PAVEMENT DISTRESS SURVEY RESULT

| | | | | Cracks | | | | | | | | | |
|------|-------|------------|--------------|-----------------------|-------------------------|----------------------------|-----------|----------------------------|-----|-----|-----|-----|-----|
| | | Length (m) | Area (sq.m.) | Transverse Cracks (m) | Longitudinal Cracks (m) | Block/Alligator Cracks (m) | Total (m) | Crack Ratio (m/1000 sq.m.) | | | | | |
| Km. | | | | | | | | | 100 | 200 | 300 | 400 | 500 |
| 1246 | 1 | 71.4 | 478.4 | 3.4 | 49.5 | 0 | 52.9 | 110.5 | | | | | |
| | 2 | 72 | 482.4 | 6.7 | 9.0 | 0 | 15.7 | 32.5 | | | | | |
| | 3 | 72 | 482.4 | 0 | 18.0 | 0 | 18.0 | 37.3 | | | | | |
| | 4 | 72 | 482.4 | 3.4 | 27.0 | 0 | 30.4 | 62.9 | | | | | |
| | 5 | 72 | 482.4 | 0 | 22.5 | 0 | 22.5 | 46.6 | | | | | |
| | 6 | 72 | 482.4 | 6.7 | 13.5 | 0 | 20.2 | 41.9 | | | | | |
| | 7 | 72 | 482.4 | 30.2 | 0 | 44 | 73.9 | 153.2 | | | | | |
| | 8 | 72 | 482.4 | 33.5 | 94.5 | 0 | 128.0 | 265.3 | | | | | |
| | 9 | 72 | 482.4 | 0 | 215.0 | 0 | 215.0 | 447.8 | | | | | |
| | 10 | 72 | 482.4 | 13.4 | 63.0 | 35 | 112.4 | 233.0 | | | | | |
| | 11 | 72 | 482.4 | 23.5 | 103.5 | 88 | 215.0 | 445.6 | | | | | |
| | 12 | 72 | 482.4 | 16.8 | 117.0 | 0 | 133.8 | 277.3 | | | | | |
| | 13 | 72 | 482.4 | 20.1 | 72.0 | 0 | 92.1 | 190.9 | | | | | |
| | 14 | 22.5 | 150.7 | 20.1 | 45.0 | 0 | 65.1 | 432.0 | | | | | |
| | 15 | | | | | | | | | | | | |
| | 16 | | | | | | | | | | | | |
| | 17 | | | | | | | | | | | | |
| | Total | | 6,417.9 | 177.6 | 850.5 | 167.8 | 1195.8 | 189.3 | | | | | |
| 1247 | 1 | 72 | 482.4 | 30.2 | 148.5 | 31.5 | 210.2 | 435.6 | | | | | |
| | 2 | 72 | 482.4 | 7.7 | 94.5 | 27.0 | 198.6 | 411.6 | | | | | |
| | 3 | 72 | 482.4 | 6.7 | 103.5 | 0 | 110.2 | 228.4 | | | | | |
| | 4 | 72 | 482.4 | 20.1 | 36.0 | 0 | 56.1 | 116.3 | | | | | |
| | 5 | 72 | 482.4 | 0 | 0 | 0 | 0 | 0 | | | | | |
| | 6 | 72 | 482.4 | 13.4 | 13.5 | 0 | 26.9 | 55.8 | | | | | |
| | 7 | 72 | 482.4 | 0 | 0 | 0 | 0 | 0 | | | | | |
| | 8 | 72 | 482.4 | 0 | 0 | 0 | 0 | 0 | | | | | |
| | 9 | 72 | 482.4 | 0 | 36.0 | 26.8 | 62.8 | 130.2 | | | | | |
| | 10 | 72 | 482.4 | 36.9 | 121.5 | 60.3 | 218.7 | 453.3 | | | | | |
| | 11 | 72 | 482.4 | 20.1 | 40.5 | 0 | 60.6 | 125.6 | | | | | |
| | 12 | 72 | 482.4 | 23.5 | 81.0 | 9.0 | 113.5 | 235.2 | | | | | |
| | 13 | 72 | 482.4 | 16.8 | 108.0 | 23.5 | 148.2 | 307.2 | | | | | |
| | 14 | 53.7 | 359.8 | 23.5 | 72.0 | 0 | 95.5 | 265.3 | | | | | |
| | 15 | | | | | | | | | | | | |
| | 16 | | | | | | | | | | | | |
| | 17 | | | | | | | | | | | | |
| | Total | | 6,631.0 | 268.0 | 855.0 | 178.1 | 1301.1 | 196.2 | | | | | |

2.1.2 Shoulder and Side Ditch Survey

Shoulder and side ditch survey was undertaken along the entire stretch of the Study Road. Following were surveyed for each 100-m section:

Shoulder

- Existing shoulder material
- Present condition
- Proposed shoulder improvement

Side Ditch

- Cross-section type of road (to judge need of side ditch)
- Side ditch material
- Dimension of side ditch
- Present condition of side ditch
- Water flow direction
- Present condition of side ditch
- Proposed side ditch improvement

Legends used for accomplishing field survey format are shown in Figure 2.1-3 and an example of the accomplished field survey format is shown in Table 2.1-2.




FIGURE 2.1-3 LEGENDS USED FOR ACCOMPLISHING FIELD FORMAT

TABLE 2.1-2 EXAMPLE OF ACCOMPLISHED FIELD SURVEY FORMAT

PACKAGE: 5

1241 km.

Date: 10/13/95

No. 2/14

| | | | | | | | | | | | | | | | | | | | | |
|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|----------|
| Proposed | Shoulder | | | | | | | | | | | | | | | | | | | |
| | Side Ditch | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 |

North Bound

| | | | | | | | | | | | | | | | | | | | | |
|------------|------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Shoulder | Condition | A | B | B | B | B | B | B | B | B | B | B | B | B | B | B | B | B | B | B |
| | Material | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G |
| Side Ditch | Condition | | | | | | | | | | | | | | | | | | | |
| | c | | | | | | | | | | | | | | | | | | | |
| | b | | | | | | | | | | | | | | | | | | | |
| | a | | | | | | | | | | | | | | | | | | | |
| | Mat'l/Type | | | | | | | | | | | | | | | | | | | |
| | Flow | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | |
|---------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| CROSS SECTION | 100 | 200 | 300 | 400 | 500 | 600 | 700 | 800 | 900 |
| | C | C | C | C | C | C | C | C | C |

South Bound

| | | | | | | | | | | | | | | | | | | | | |
|------------|------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Side Ditch | Flow | | | | | | | | | | | | | | | | | | | |
| | Mat'l/Type | | | | | | | | | | | | | | | | | | | |
| | a | | | | | | | | | | | | | | | | | | | |
| | b | | | | | | | | | | | | | | | | | | | |
| | c | | | | | | | | | | | | | | | | | | | |
| | Condition | | | | | | | | | | | | | | | | | | | |
| Shoulder | Material | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G | G |
| | Condition | A | B | B | B | B | C | B | B | B | B | B | B | B | B | B | B | B | B | B |

| | | | | | | | | | |
|----------|------------|----------|----------|----------|----------|----------|----------|----------|----------|
| Proposed | Side Ditch | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 | DS(C)-61 |
| | Shoulder | | | | | | | | |

2.1.3 Pipe/Box Culvert Survey

All pipe/box culverts were surveyed their present conditions and possible improvement measures for each of the following portions:

- Inlet facility
- Culvert itself
- Outlet facility
- Upstream
- Downstream
- Others such as nearby embankment, etc.

Two field survey formats were prepared as shown in Table 2.1-3 and Figure 2.1-4. Figure 2.1-5 shows classification of headwall types.

During the field survey, maintenance engineers and foremen of District/City Engineering Offices accompanied with the JICA Study Team to assist in locating the pipe/box culverts as well as to provide information on conditions during heavy rain.

TABLE 2.1-3 EXAMPLE OF ACCOMPLISHED FIELD SURVEY FORMAT-1

PACKAGE: 5 PAGE: 5-1

| LOCATION (STATION) | CULVERT SIZE | CONDITION/RECOMMENDATION | | | | | |
|--------------------|--------------|---|-----------|----------|------------|--------------|----------|
| | | 1 INLET | 2 CULVERT | 3 OUTLET | 4 UPSTREAM | 5 DOWNSTREAM | 6 OTHERS |
| 1240+950 | Ø = 0.60m | 1. No headwall, clogged with debris (100%) / catch basin, cleaning 2. /Change to Ø = 1.20m 3. No headwall/Headwall Type B 4. Clogged 5. /Vertical Ditch 6. - | | | | | |
| 1241+000 | Ø = 1.20m | 1. No headwall, clogged with debris (30%) / Headwall Type A, Cleaning 2. No damage 3. Riprap headwall 4. - 5. /Vertical ditch, Concrete foundation 6. - | | | | | |
| 1241+050 | Ø = 0.90m | 1. Riprap headwall damaged, Clogged with debris (50%) / Catch basin, Cleaning 2. Damaged Culvert (2.0m) (Outlet) / Change to Ø = 1.20m 3. No headwall/Headwall Type B 4. - 5. /Vertical ditch with foundation 6. - | | | | | |
| 1241+200 | Ø = 1.20m | 1. No headwall, Clogged with debris (60%) / Catch basin, cleaning 2. Damaged culvert (2.0m) (Outlet) / Replacement of culvert (Outlet) 3. No headwall/Headwall Type A 4. - 5. /Vertical ditch 6. /Embankment protection (S.B.) | | | | | |

FIGURE 2.1-4 EXAMPLE OF ACCOMPLISHED FIELD SURVEY FORMAT-2


DATE: _____
 NO.: 5-1

PACKAGE: 5


| STATION | CULVERT SIZE | PLAN AND CROSS-SECTION | |
|------------|------------------|------------------------|--|
| 1240 + 950 | Pipe ø 0.60 | | |
| 1241 + 000 | P-pipe ø 1.20 | | |

FIGURE 2.1-5 CLASSIFICATION OF HEADWALL TYPES


HW (C) - A




HW (C) - B



HW (C) - C



HW (C) - D



2.2 SLOPE SURVEY

The field survey team revisited all damaged slope sections reported in the feasibility study and made supplementary observations and additional measurements. Of the original 76 selected slope sites, 6 sites were undergoing rehabilitation at the time of the site inspections and another 9 sites had been completely restored. an additional 26 extra slope sites were noted with various forms of damage. Three of these had completed restoration works. Those slopes which had been completed, or were undergoing restoration at the time of site inspection were as follows:

| <u>Slope Number</u> | <u>Location</u> | <u>Type of Disaster</u> | <u>Status</u> |
|---------------------|-----------------|-------------------------|---------------|
| 1-04 | Km 1116+200 | C-F | Completed |
| 2-07 | Km 1173+430 | E-F | " |
| 2-08 | Km 1177+000 | Debris | " |
| 2-09 | Km 1177+200 | Debris | " |
| 5-01 | Km 1378+500 | E-F | " |
| 5-07 | Km 1401+850 | E-F | " |
| 5-19 | Km 1445+700 | E-F | " |
| E-26 | Km 1449+700 | E-F | " |
| E-27 | Km 1449+950 | E-F | " |
| ----- | | | |
| 1-03 | Km 1115+800 | E-F | On-going |
| 1-07 | Km 1135+150 | E-F | " |
| 5-02 | Km 1378+800 | E-F | " |
| 5-05 | Km 1395+800 | E-F | " |
| 5-13 | Km 1430+950 | E-F | " |
| E-25 | Km 1449+400 | E-F | " |
| ----- | | | |

The underlying causes of the damage was reappraised and the geology was checked. The size of each area of damage was remeasured to check on any changes since the feasibility study site inspections. All previously identified sites were re-photographed and the extra sites were comprehensively measured as well as photographed.

2.3 BRIDGE SURVEY

All bridges along the Study Road were re-visited to re-check and update bridge conditions as well as to obtain additional data required for the detailed design. Field survey formats accomplished during the feasibility study were updated, if there are any changes in condition occurring in the interim period between the feasibility study and the detailed design.

Additional data gathering were concentrated mainly on the following:

- Detailed dimension survey of Structural Members
- Crack survey of RC/PC beams

Detailed Dimension Survey of Structural Members

Detailed dimension survey of structural members was undertaken for bridges to be rehabilitated or reconstructed. An example of survey result is shown in Figure 2.3-1.

Crack Survey of RC/PC Beams

Crack survey of RC/PC beams was undertaken for critical bridges. Cracks were classified as follows:

| | |
|------------------------------|-------------------|
| Hairline (or thin) crack (T) | : Less than 0.2mm |
| Medium crack (M) | : 0.2 to 0.6mm |
| Large crack (L) | : More than 0.6mm |

An example of field measurement of cracks is shown in Figure 2.3-2.

Photographs of the bridge portions where damaged or deteriorated were taken.

All bridges were re-assessed their structural soundness based on the data obtained in the field.




FIGURE 2.3-1(I) AN EXAMPLE OF DETAILED DIMENSION SURVEY




FIGURE 2.3-1(2) AN EXAMPLE OF DETAILED DIMENSION SURVEY

Assumed dimensions

FIELD SKETCH CRACK SURVEY

PAN PHILIPPINE HIGHWAY - MINOANAO
 BRIDGE INVENTORY SHEET NO. 13
 STATION: 1390+262



BRIDGE NO. : 5-02
 BRIDGE NAME : GARAJAN
 INVENTORY DATE : 12-18

BEAM DIM. C = 212




FIGURE 2.3-2 AN EXAMPLE OF CRACK SURVEY

CHAPTER 3

TRAFFIC SURVEY

3.1 TRAFFIC SURVEY

No traffic survey was undertaken, as the extensive traffic survey was undertaken during the feasibility study of which results were utilized under this Study.

The traffic surveys undertaken during the feasibility study were as follows:

- Traffic count survey at 24 stations
- Travel speed survey along the Study Road
- Axle load survey at 4 stations
- Commodity OD survey at 4 stations

Traffic survey stations and AADT (1994) are shown in Figure 3.1-1 and 2, respectively.

3.2 ESTIMATED FUTURE TRAFFIC

Future traffic estimated by the feasibility study was utilized under this Study. Estimated future traffic is shown in Table 3.2-1.




FIGURE 3.1-1 TRAFFIC SURVEY STATIONS

SOURCE: F/S Report




FIGURE 3.1-2 AADT (1994) AND AVERAGE TRAVEL SPEED

SOURCE: F/S Report

TABLE 3.2-1 (1/2) FUTURE TRAFFIC VOLUME BY SECTION

| Section | Year | Vehicles with 4 or more wheels | | | | | Others | | Total |
|---------|------|--------------------------------|---------|-----|-------|-----------|----------|---------|--------|
| | | Car | Jeepney | Bus | Truck | Sub-Total | Tricycle | M'cycle | |
| 1 | 1994 | 251 | 115 | 41 | 238 | 645 | 449 | 199 | 1,293 |
| | 2000 | 383 | 179 | 67 | 364 | 993 | 663 | 308 | 1,964 |
| | 2010 | 686 | 323 | 119 | 739 | 1,867 | 1,192 | 538 | 3,597 |
| | 2020 | 1,098 | 514 | 186 | 1,271 | 3,069 | 1,933 | 864 | 5,866 |
| 2 | 1994 | 372 | 595 | 61 | 596 | 1,624 | 16 | 134 | 1,774 |
| | 2000 | 571 | 898 | 103 | 922 | 2,494 | 24 | 218 | 2,736 |
| | 2010 | 1,024 | 1,617 | 177 | 1,863 | 4,681 | 44 | 371 | 5,096 |
| | 2020 | 1,635 | 2,601 | 282 | 3,239 | 7,757 | 70 | 588 | 8,415 |
| 3 | 1994 | 236 | 241 | 68 | 153 | 698 | 5 | 82 | 785 |
| | 2000 | 383 | 384 | 120 | 222 | 1,109 | 8 | 144 | 1,261 |
| | 2010 | 674 | 687 | 201 | 443 | 2,005 | 15 | 235 | 2,255 |
| | 2020 | 1,061 | 1,092 | 318 | 720 | 3,191 | 23 | 368 | 3,582 |
| 4 | 1994 | 200 | 194 | 61 | 186 | 641 | 7 | 49 | 697 |
| | 2000 | 339 | 320 | 113 | 274 | 1,046 | 9 | 95 | 1,150 |
| | 2010 | 588 | 569 | 183 | 533 | 1,873 | 21 | 147 | 2,041 |
| | 2020 | 914 | 899 | 290 | 863 | 2,966 | 30 | 229 | 3,225 |
| 5 | 1994 | 252 | 312 | 73 | 206 | 843 | 4 | 91 | 938 |
| | 2000 | 428 | 508 | 140 | 304 | 1,380 | 8 | 168 | 1,556 |
| | 2010 | 739 | 904 | 219 | 586 | 2,448 | 12 | 270 | 2,730 |
| | 2020 | 1,154 | 1,448 | 351 | 942 | 3,895 | 20 | 420 | 4,335 |
| 6 | 1994 | 612 | 673 | 70 | 440 | 1,795 | 73 | 238 | 2,106 |
| | 2000 | 985 | 1,067 | 137 | 649 | 2,838 | 110 | 396 | 3,344 |
| | 2010 | 1,753 | 1,907 | 210 | 1,252 | 5,122 | 199 | 676 | 5,997 |
| | 2020 | 2,801 | 3,085 | 339 | 2,047 | 8,272 | 327 | 1,067 | 9,666 |
| 7 | 1994 | 771 | 636 | 74 | 475 | 1,956 | 40 | 186 | 2,182 |
| | 2000 | 1,237 | 1,024 | 145 | 692 | 3,098 | 63 | 331 | 3,492 |
| | 2010 | 2,216 | 1,836 | 222 | 1,315 | 5,589 | 116 | 551 | 6,256 |
| | 2020 | 3,568 | 2,986 | 359 | 2,117 | 9,030 | 190 | 858 | 10,078 |
| 8 | 1994 | 712 | 782 | 164 | 462 | 2,120 | 39 | 250 | 2,409 |
| | 2000 | 1,157 | 1,258 | 308 | 667 | 3,390 | 61 | 435 | 3,886 |
| | 2010 | 2,076 | 2,295 | 492 | 1,252 | 6,115 | 115 | 744 | 6,974 |
| | 2020 | 3,350 | 3,763 | 801 | 2,005 | 9,919 | 191 | 1,180 | 11,290 |
| 9 | 1994 | 547 | 495 | 189 | 491 | 1,722 | 134 | 195 | 2,051 |
| | 2000 | 905 | 817 | 349 | 696 | 2,767 | 211 | 348 | 3,326 |
| | 2010 | 1,598 | 1,460 | 567 | 1,296 | 4,921 | 412 | 581 | 5,914 |
| | 2020 | 2,558 | 2,373 | 931 | 2,058 | 7,920 | 701 | 914 | 9,535 |
| 10 | 1994 | 459 | 225 | 184 | 343 | 1,211 | 6 | 156 | 1,373 |
| | 2000 | 770 | 394 | 343 | 491 | 1,998 | 9 | 287 | 2,294 |
| | 2010 | 1,342 | 668 | 553 | 931 | 3,494 | 18 | 465 | 3,977 |
| | 2020 | 2,143 | 1,053 | 907 | 1,486 | 5,589 | 31 | 726 | 6,346 |
| 11 | 1994 | 554 | 293 | 175 | 421 | 1,443 | 33 | 291 | 1,767 |
| | 2000 | 924 | 501 | 327 | 594 | 2,346 | 53 | 507 | 2,906 |
| | 2010 | 1,640 | 881 | 525 | 1,094 | 4,140 | 102 | 882 | 5,124 |
| | 2020 | 2,651 | 1,416 | 857 | 1,724 | 6,648 | 175 | 1,427 | 8,250 |
| 12 | 1994 | 386 | 264 | 115 | 295 | 1,060 | 72 | 794 | 1,926 |
| | 2000 | 658 | 456 | 215 | 422 | 1,751 | 113 | 1,306 | 3,170 |
| | 2010 | 1,131 | 797 | 345 | 794 | 3,067 | 225 | 2,447 | 5,739 |
| | 2020 | 1,794 | 1,283 | 561 | 1,267 | 4,905 | 385 | 4,090 | 9,380 |

SOURCE: Feasibility Study Report

TABLE 3.2-1 (2/2) FUTURE TRAFFIC VOLUME BY SECTION

| Section | Year | Vehicles with 4 or more wheels | | | | | Others | | Total |
|---------|------|--------------------------------|---------|-------|-------|-----------|----------|---------|--------|
| | | Car | Jeepney | Bus | Truck | Sub-Total | Tricycle | M'cycle | |
| 13 | 1994 | 334 | 101 | 119 | 191 | 745 | 8 | 178 | 931 |
| | 2000 | 572 | 191 | 219 | 278 | 1,260 | 13 | 322 | 1,595 |
| | 2010 | 981 | 303 | 357 | 530 | 2,171 | 25 | 531 | 2,727 |
| | 2020 | 1,547 | 462 | 580 | 860 | 3,449 | 43 | 837 | 4,329 |
| 14 | 1994 | 371 | 151 | 120 | 252 | 894 | 20 | 549 | 1,463 |
| | 2000 | 632 | 273 | 218 | 368 | 1,491 | 34 | 911 | 2,436 |
| | 2010 | 1,090 | 455 | 360 | 684 | 2,589 | 60 | 1,652 | 4,301 |
| | 2020 | 1,724 | 707 | 586 | 1,110 | 4,127 | 100 | 2,697 | 6,924 |
| 15 | 1994 | 405 | 113 | 153 | 355 | 1,026 | 202 | 633 | 1,861 |
| | 2000 | 679 | 208 | 274 | 516 | 1,677 | 315 | 1,041 | 3,033 |
| | 2010 | 1,190 | 339 | 459 | 924 | 2,912 | 588 | 1,889 | 5,389 |
| | 2020 | 1,888 | 516 | 748 | 1,478 | 4,630 | 964 | 3,059 | 8,653 |
| 16 | 1994 | 489 | 126 | 183 | 358 | 1,156 | 11 | 450 | 1,617 |
| | 2000 | 809 | 227 | 323 | 527 | 1,886 | 22 | 753 | 2,661 |
| | 2010 | 1,434 | 377 | 549 | 934 | 3,294 | 33 | 1,349 | 4,676 |
| | 2020 | 2,292 | 583 | 891 | 1,508 | 5,274 | 55 | 2,170 | 7,499 |
| 17 | 1994 | 649 | 157 | 305 | 500 | 1,611 | 80 | 511 | 2,202 |
| | 2000 | 1,061 | 274 | 529 | 733 | 2,597 | 128 | 847 | 3,572 |
| | 2010 | 1,900 | 467 | 910 | 1,284 | 4,561 | 232 | 1,523 | 6,316 |
| | 2020 | 3,055 | 733 | 1,474 | 2,047 | 7,309 | 370 | 2,457 | 10,136 |
| 18 | 1994 | 855 | 157 | 318 | 673 | 2,003 | 20 | 605 | 2,628 |
| | 2000 | 1,380 | 271 | 542 | 990 | 3,183 | 36 | 989 | 4,208 |
| | 2010 | 2,500 | 466 | 944 | 1,713 | 5,623 | 60 | 1,797 | 7,480 |
| | 2020 | 4,030 | 743 | 1,528 | 2,704 | 9,005 | 96 | 2,899 | 12,000 |
| 19 | 1994 | 1,029 | 332 | 488 | 1,137 | 2,986 | 1,050 | 1,110 | 5,146 |
| | 2000 | 1,644 | 548 | 811 | 1,674 | 4,677 | 1,640 | 1,777 | 8,094 |
| | 2010 | 3,005 | 980 | 1,442 | 2,862 | 8,289 | 3,020 | 3,255 | 14,564 |
| | 2020 | 4,854 | 1,568 | 2,326 | 4,458 | 13,206 | 4,827 | 5,242 | 23,275 |
| 20 | 1994 | 2,368 | 515 | 905 | 1,526 | 5,314 | 153 | 947 | 6,414 |
| | 2000 | 3,739 | 833 | 1,469 | 2,281 | 8,322 | 243 | 1,522 | 10,087 |
| | 2010 | 6,901 | 1,516 | 2,658 | 3,971 | 15,046 | 450 | 2,791 | 18,287 |
| | 2020 | 11,134 | 2,431 | 4,289 | 6,214 | 24,068 | 719 | 4,507 | 29,294 |
| 21 | 1994 | 2,807 | 957 | 1,043 | 2,122 | 6,929 | 1,016 | 1,596 | 9,541 |
| | 2000 | 4,425 | 1,527 | 1,675 | 3,215 | 10,842 | 1,603 | 2,538 | 14,983 |
| | 2010 | 8,205 | 2,805 | 3,060 | 5,666 | 19,736 | 2,973 | 4,689 | 27,398 |
| | 2020 | 13,238 | 4,513 | 4,947 | 8,901 | 31,599 | 4,770 | 7,566 | 43,935 |
| 22 | 1994 | 3,284 | 1,733 | 940 | 2,110 | 8,067 | 147 | 651 | 8,865 |
| | 2000 | 5,188 | 2,759 | 1,502 | 3,208 | 12,657 | 236 | 1,045 | 13,938 |
| | 2010 | 9,639 | 5,117 | 2,768 | 5,680 | 23,204 | 433 | 1,922 | 25,559 |
| | 2020 | 15,581 | 8,263 | 4,479 | 8,931 | 37,254 | 694 | 3,113 | 41,061 |
| 23 | 1994 | 2,666 | 2,237 | 442 | 1,568 | 6,913 | 15 | 858 | 7,786 |
| | 2000 | 4,217 | 3,558 | 706 | 2,388 | 10,869 | 28 | 1,368 | 12,265 |
| | 2010 | 7,841 | 6,628 | 1,302 | 4,228 | 19,999 | 45 | 2,537 | 22,581 |
| | 2020 | 12,675 | 10,725 | 2,107 | 6,641 | 32,148 | 73 | 4,114 | 36,335 |
| 24 | 1994 | 2,475 | 0 | 291 | 2,146 | 4,912 | 265 | 806 | 5,983 |
| | 2000 | 3,923 | 0 | 460 | 3,310 | 7,693 | 424 | 1,281 | 9,398 |
| | 2010 | 7,309 | 0 | 860 | 5,917 | 14,086 | 790 | 2,387 | 17,263 |
| | 2020 | 11,827 | 0 | 1,391 | 9,339 | 22,557 | 1,279 | 3,870 | 27,706 |

SOURCE: Feasibility Study Report

CHAPTER 4

TOPOGRAPHIC SURVEY

Following four kinds of topographic survey were undertaken:

- Route survey along the whole stretch of the Study Road
- Topographic survey at bridge sites, slopes and flood-prone areas
- River profile and cross-section survey
- Aerial photographic survey and mapping

4.1 ROUTE SURVEY

The route survey was undertaken for the entire stretch of the Study Road (or about 403 km) and for the proposed alignment of the Monkayo Bypass (about 2.5km) in accordance with the following procedure:

- GPS Survey
- Traverse Survey
- Establishment of Temporary Bench Marks (TBMs)
- Centerline Survey
- Centerline Stake-out Survey
- Profile Survey
- Cross-Section Survey
- Topographic Survey
- Preparation of Topographic Maps, Profiles and Cross-Sections

All data obtained in the field surveys were stored in the diskettes and mapping/drafting works were done by using computer softwares.

1) GPS Survey

GPS stations were established at about 10 km. interval, which were used as the control points for the traverse survey. An average of six satellites were observed. In order to check accuracy of the survey as well as to tie to National GPS Stations, five GPS stations established under the Philippine Geodetic Network were also measured. A total of 50 GPS stations were measured.

2) Traverse Survey

The traverse points were established at an interval of 200 to 1,000 meters. The traverse route was tied to GPS stations established under this project.

3) Establishment of TBMs

TBMs were established at about 500m interval and tied to the National Bench Marks.

4) Centerline Survey

The centerline survey was undertaken in order to determine the existing centerline alignment. Coordinates along the longitudinal joint of PCC pavement were measured. Curve elements were determined by using computer software developed by the JICA Study Team.

Problems encountered were as follows:

- The existing centerline at a curved section was not always follow a certain radius of curvature. Errors or deviations from the designed centerline were oftenly observed. This may be due to construction error and/or errors during PCC slab reconstruction.
- Thus, it was impossible to determine radius which exactly follows the existing centerline which is the alignment along the existing longitudinal joint of PCC pavement.
- Therefore, the Study Team selected radius which was least error to the existing centerline. Thus, the centerline alignment established by the Study Team was the nearest alignment to the existing alignment and there are minor deviation from the existing centerline.

5) Centerline Stake-out Survey

Centerline stake-out was undertaken at the interval of 20 meters and at points of beginning and end of each curve.

6) Profile Survey

Elevation of centerline stakes established at 20m interval and other points of inclination was measured. Levelling was tied to TBM and closed.

7) Cross-Section Survey

Cross-section survey was undertaken at 20m interval and other points of topographical changes. Distance covered by the survey was as follows:

| | |
|---------------------|---------------------------------------|
| Flat terrain | : 30m either side from the centerline |
| Rolling terrain | : 50m either side from the centerline |
| Mountainous terrain | : 60m either side from the centerline |

8) Topographic Survey

All structures such as houses, buildings, electric posts, side ditches, cross-drainage facilities, existing Km posts, and all other man-made facilities as well as topographic changes such as small vallies, creeks, etc. were measured. The topographic survey was so undertaken that the contour interval of 1m was attained.

9) Preparation of Topographic Maps, Profiles and Cross-Sections

Following maps/drawings were prepared:

Topographic Map

Scale : 1/1,000

Contour interval : 1m

Profile

Scale : H = 1/1,000

V = 1/100

Cross-Section

Scale : 1/100

4.2 TOPOGRAPHIC SURVEY AT BRIDGE SITES, SLOPES AND FLOOD-PRONE AREAS

Topographic survey for the following sections:

- 10 slopes which remarkably failed
scale : 1/500 with contour interval of 1 meter.
- 71 bridge sites proposed to be rehabilitated/
improved/reconstructed
scale : 1/200 for short bridges and 1/500 for long bridges
with contour interval of 1 meter
- 2 flood-prone sections
scale : 1/1,000 with contour interval of 1 meter

4.3 RIVER PROFILE AND CROSS-SECTION SURVEY

River profile and cross-section survey was undertaken for 39 rivers which require detailed hydraulic analysis and/or dredging/rechanneling.

Scale : Profile H = 1/1,000

V = 1/100

Cross-Section 1/100

4.4 AERIAL PHOTOGRAPHIC SURVEY AND MAPPING

For the purposes of detailed hydraulic analysis, route selection of a proposed bypass road, and dike planning, etc., aerial photographic survey and mapping was undertaken for the following three flood-prone areas:

- Simulao River Flood Area

Area covered = 10km x 3km = 30 sq.km

Scale : 1/5,000 with contour interval of 1 meter

- **Monkayo Bypass Construction Site**

Area covered = 2.5km x 2.5km = 6.25 sq.km

Scale : 1/2,000 with contour interval of 1 meter

- **Liboganon River Flood Area**

Area covered = 16km x 4km = 64 sq.km

Scale : 1/5,000 with contour interval of 1 meter

CHAPTER 5

SOILS/MATERIAL AND GEOTECHNICAL INVESTIGATION

The following investigations were undertaken:

- Geotechnical investigation for pavement rehabilitation design
- Geotechnical investigation for slope protection design
- Geotechnical investigation for bridge foundation design
- Soils investigation for soft ground sections
- Soils investigation for Sianib Section
- Soils investigation for Liboganon River bank design
- Material sources investigation

5.1 GEOTECHNICAL INVESTIGATION FOR PAVEMENT REHABILITATION DESIGN

Following investigations were undertaken:

- Concrete pavement coring
- Test pitting
- Auger boring

1) Concrete Pavement Coring

In order to examine PCC slab thickness and concrete strength, coring of PCC slabs was undertaken basically at 1 km interval for 214 km sections where pavement rehabilitation was proposed. A total of 197 concrete specimen were sampled and subjected to compressive strength test after measurement of thickness.

2) Test Pitting

In order to examine soil layer composition under PCC slab and characteristics of each soil layer including bearing capacity, test pitting to a depth of 1.5 meters was undertaken basically at 0.5 km interval for 214 km sections proposed for pavement rehabilitation. Test pitting was also undertaken for Monkayo Bypass section. A total of 414 test pittings were undertaken. Two soil samples per test pit were basically obtained. In-situ density tests were undertaken during test pitting. Soil samples obtained were subjected to the following laboratory tests:

- Soil classification
- Natural moisture content
- Sieve analysis
- Atterberg limits
- Moisture-density relation
- CBR

3) Auger Boring

In order to examine soil layer composition under PCC slab and characteristics of each soil layer, auger borings to a depth of 1.5 meters were undertaken basically at 0.5 meters were undertaken basically at 0.5 km interval for 214 km sections proposed for pavement rehabilitation. Auger borings were also undertaken for Monkayo Bypass section.

A total of 434 auger borings were conducted and basically two samples per auger boring were collected. Soil samples were subjected to the following laboratory tests:

- Soil classification
- Natural moisture content
- Sieve analysis
- Atterberg limits

5.2 GEOTECHNICAL INVESTIGATION FOR SLOPE PROTECTION DESIGN

One boring test per slope was undertaken at two embankment slopes which have already slid. Location of two slopes is as follows:

- Km 1282 + 500
- Km 1283 + 400

Total drilling length was 20.9 meters.

5.3 GEOTECHNICAL INVESTIGATION FOR BRIDGE FOUNDATION DESIGN

Geotechnical investigation was undertaken at 19 bridge sites and 42 borings with a total drilling length of 1,235.8 meters were conducted (see Table 5.3-1).

TABLE 5.3-1 GEOTECHNICAL INVESTIGATION AT BRIDGE SITES

| Bridge Name | Km | No. of Bore Holes | Drilling Length (m) |
|--------------------------|----------|-------------------|---------------------|
| 1. New Camalig | 1180+157 | 3 | 29.0 |
| 2. Guinoyoran | 1197+535 | 1 | 37.0 |
| 3. Sanghan | 1217+339 | 2 | 78.8 |
| 4. Ampayon | 1232+785 | 1 | 55.4 |
| 5. Andanan | 1266+097 | 4 | 87.3 |
| 6. Taglatawan | 1269+766 | 2 | 42.6 |
| 7. Lagcogangan | 1320+472 | 1 | 50.5 |
| 8. Tagbayagan | 1323+317 | 1 | 42.5 |
| 9. Wasian | 1330+888 | 2 | 95.6 |
| 10. Gabanan | 1390+242 | 3 | 36.3 |
| 11. Tina | 1397+365 | 2 | 34.7 |
| 12. Banlag | 1398+108 | 2 | 32.5 |
| 13. Nabunturan | 1424+698 | 2 | 64.7 |
| 14. Liboganon | 1465+285 | 1 | 57.4 |
| 15. Ilang | 1494+420 | 1 | 37.0 |
| 16. Monkayo Bypass No. 1 | | 2 | 46.7 |
| 17. Monkayo Bypass No. 2 | | 4 | 55.3 |
| 18. Monkayo Bypass No. 3 | | 2 | 26.7 |
| 19. New Gov. Miranda | | 6 | 330.8 |
| Total | | 42 | 1,240.8 |

5.4 SOILS INVESTIGATION FOR SOFT GROUND SECTIONS

Soils investigation for soft ground sections was undertaken at six locations as follows:

- Km 1303+900
- Km 1322+800
- Km 1333+350
- Km 1333+500
- Km 1346+100
- Km 1357+300

One boring test per location was undertaken and total drilling length was 92.7 meters.

5.5 SOILS INVESTIGATION FOR SIANIB SECTION

Sianib Section (about Km 1280 - Km 1283) has been suffering very fast pavement deterioration and slope failures. At about Km 1281+600, PCC pavement constructed in 1994 during the Feasibility Study Stage, had already severe cracks with faulting in 1995. In order to examine soil layers and their characteristics, three borings were undertaken with the total drilling length of 31.4 meters.

5.6 SOILS INVESTIGATION FOR LIBOGANON RIVER BANK DESIGN

For the purposes of examining soil conditions and analysis of the river bank stability, two borings were undertaken with a total length of 51.9 meters.

5.7 MATERIAL SOURCES INVESTIGATION

Prior to selection of material sources to be investigated, all possible material sources were identified based on DPWH material sources maps, information from contractors, etc., and visited to assess accessibility to each sources and to estimate approximate volume of materials. Number of material sources identified and visited were as follows:

| | |
|--------------------------------|------|
| Borrow Sources | : 30 |
| Base/Subbase Sources | : 34 |
| Aggregate Sources for Concrete | : 25 |

To be noted is that aggregate sources for concrete in Agusan del Sur are scarce and aggregates for concrete are expected to be hauled for a long distance in the Province.

Material sources to be investigated were selected from above possible material sources and following investigations were conducted:

1) Borrow Sources

A total of 19 sources were investigated (see Figure 5.7-1). One test pitting per source was undertaken. Two samples per test pit were collected and the following field/laboratory tests were conducted for each sample:

- In-situ density
- Soil classification
- Natural moisture content
- Sieve analysis
- Atterberg limits
- Moisture-density relation
- CBR

2) Base/Subbase Sources

A total 19 sources were investigated (see Figure 5.7-2). Two test pittings per source or 38 test pittings were undertaken. Two samples per test pit or a total of 76 samples were collected and subjected to the following laboratory tests:

- Sieve analysis
- Atterberg limits
- Moisture - density relation
- CBR
- Los Angeles abrasion (base material only)

3) Concrete Aggregate Sources

A total of 19 sources were investigated (see Figure 5.7-3). Two test pittings per source or 38 test pittings were undertaken. Two samples per test pit or a total of 76 samples were collected and the following laboratory tests were conducted:

- Sieve analysis
- Los Angeles abrasion
- Specific gravity
- Absorption
- Soundness
- Flakiness index




FIGURE 5.7-1 BORROW SOURCES INVESTIGATED




FIGURE 5.7-2 BASE/SUBBASE MATERIAL SOURCES INVESTIGATED




FIGURE 5.7-3 CONCRETE AGGREGATE SOURCES INVESTIGATED