

ANNEX E

Project Works, Cost Estimate, and Implementation Plan

**THE STUDY
ON
THE LINING OF DISTRIBUTARIES AND MINORS
IN
PUNJAB
IN
THE ISLAMIC REPUBLIC OF PAKISTAN
VOLUME II
ANNEX E PROJECT WORKS, COST ESTIMATES
AND IMPLEMENTATION PLAN**

Table of Contents

E.1 Project Works	E- 1
E.1.1 Structure Planning	E- 1
E.1.2 Construction Volume for Earthwork and Concrete Works	E- 2
E.1.2 Construction Procedure and Methods.....	E- 2
E.2 Cost Estimate	E- 2
E.2.1 Basic Condition and Assumption for the Cost Estimates	E- 2
E.2.2 Estimate of the Project Cost.....	E- 2
E.2.3 Breakdown of the Project Cost.....	E- 4
E.2.4 Unit Cost Analysis	E- 5
E.2.5 Annual Disbursement Schedule.....	E- 5
E.2.6 Replacement Cost and O&M Cost	E- 5
E.3 Project Implementation Plan.....	E- 6
E.3.1 General	E- 6
E.3.2 Implementation of Construction Work	E- 6
E.3.3 Construction Mode and Method	E- 7
E.3.4 Construction Schedule	E- 7

LIST OF TABLES

Table E - 1	Summary of Proposed Structures	ET - 1
Table E - 2	Proposed Structures for LJC Area	ET - 2
Table E - 3	Proposed Structures for LCC Area	ET - 3
Table E - 4	Proposed Structures for CBDC Area	ET - 4
Table E - 5	Project Work Volume Summary	ET - 5
Table E - 6	Project Work Volume for LJC Area	ET - 6
Table E - 7	Project Work Volume for LCC Area	ET - 7
Table E - 8	Project Work Volume for CBDC Area	ET - 8
Table E - 9	Financial Cost for Lining of Distributaries and Minors	ET - 9
Table E - 10	Financial Cost for Each Distrubutary Systems	ET - 10
Table E - 11	Direct Construction Cost for Lining on Pindi Distrubutary Systems	ET - 11
Table E - 12	Direct Construction Cost for Lining on Hujjan Distrubutary Systems	ET - 12
Table E - 13	Direct Construction Cost for Lining on Kirana Distrubutary Systems	ET - 13
Table E - 14	Direct Construction Cost for Lining on Sarangwala Distrubutary Systems	ET - 14
Table E - 15	Direct Construction Cost for Lining on Nasrana Distrubutary Systems	ET - 15
Table E - 16	Direct Construction Cost for Lining on Gojra Distrubutary Systems	ET - 16
Table E - 17	Direct Construction Cost for Lining on Mungi Distrubutary Systems	ET - 17
Table E - 18	Direct Construction Cost for Lining on Janiwala/Hamza Distrubutary Systems	ET - 18
Table E - 19	Direct Construction Cost for Lining on Pirmahal Distrubutary Systems	ET - 19
Table E - 20	Direct Construction Cost for Lining on Killianwala Distrubutary Systems	ET - 20
Table E - 21	Direct Construction Cost for Lining on Thamman Distrubutary Systems	ET - 21
Table E - 22	Direct Construction Cost for Lining on Chinna Distrubutary Systems	ET - 22
Table E - 23	Price List of Labour and Construction Material	ET - 23
Table E - 24	Operation Cost of Construction Equipment	ET - 24
Table E - 25	Unit Cost Comparison for Lining Work	ET - 25

Table E - 26	Disbursement Schedule for the Project	EF - 26
--------------	---	---------

LIST OF FIGURES

Figure E - 1	Proposed Organization of Project Implementation	EF - 1
Figure E - 2	Implementation Schedule	EF - 2

ATTACHMENTS

Attachment	Detailed List of Structures (Results of Inventory survey and the Basic Design
------------	---

Annex E Project Works, Cost Estimates and Implementation Plan

E.1 Project Works

E.1.1 Structure Planning

Proposed structure planning are shown in Table E-1~4. Detailed data are compiled into the attachment for the inventory survey and the basic design of the structures.

- Each distributary canal system is proposed to be transferred to the relevant farmer's organization and discharge measurement and control is necessary at outlet from main and branch canals. For the purpose, installation of diversion gates are proposed to the distributaries lacking them such as Mungi, Janiwala, Pirmahal, Killianwala, Thamman and China and automatic discharge reader and recorder are also proposed to be installed to all distributaries. Meter Flume is to be removed at construction.

- As required function of outlet, proportional extraction of water and silt independently from downstream water level is necessary for the project. Adjustable Proportional Module (APM) Outlet which has been applied at most of cases at present situation has been claimed its weak silt extraction function and Open Flume Outlet is exposed and vulnerable. Adjustable Orifice Semi-Module (AOSM) is thus proposed in general for the project since AOSM, applied for Command Water Management Project, showed good performance for proportional extraction of water and silt¹. Proposed numbers of outlets by types are shown below.

Type of Outlet	Lower Jhelum	Lower Chenab	CBDC	Project Total
AOSM	225	487	125	837
Open Flume Type	75	62	16	153
Pipe Outlet	10	19	19	48
Total	310	568	160	1,038

- Use of existing bridges with repair if necessary and replacement of Footpath Bridge by VR (Village Road) Bridge as well as new installation of VR Bridge if required among where bank damage by cattle was observed are proposed to improve rural transportation and minimize cattle passage over channel. As the

¹ Reference to SWABI SCARP Working Paper 37

results of the structure planning, total numbers of bridges tolerant for vehicle passage increase to be 442 (every 1.31 km) from 229 (every 2.53 km excluding the bridges fatally damaged).

- For the purpose of canal bank protection, 267 Buffalo Wallow (Cattle Ghat) are proposed nearby each bridges at watercourse head. Washing Steps, Drop and Spillway will be replaced disregarding the present condition. Canal Crossings (Aqueducts and pipe crossings), pipe culvert and railway bridges will be used as they are.

E.1.2 Construction Volume for Earthwork and Concrete Works

Construction volumes for each kind of works are decided by basic design based on the results of canal route survey executed within the Phase II field work period. Each work volumes are shown in Table B-5~8. The canal route survey was conducted through 541.27 km (Total length of the canals selected at Interim Stage is 583.42 km and out of which 553.23 km was estimated total length to be surveyed) consisting baseline survey, cross section survey and structure inventory survey and designed total length came to be 539.51 km. Total acreage of land compensation is estimated to be 138 ha and 2.7 m width outside ROW in average. Average work volume per linear meter estimated based on canal sections surveyed and designed are; 4.15 m³ excavation, 8.69 m³ embankment and 0.5 m³ concrete. The work volumes show wide fluctuation according to surface condition within ROW and thus more detailed survey is recommended to be executed at the time of Detailed Design. Designed canal profiles are shown in the Drawings (Vol. IV).

E.1.3 Construction Procedure and Methods

(1) Construction Method

Specifications of earthwork and dimension of improved canal cross section are proposed as shown in Figure B-6. Stripping thickness of 0.2 m is proposed respectively for outside and inside of canal prism. Bank cutting thickness within canal prism of 1.0 m or 2.0 m and over-embankment exceeding designed lining surface is proposed by 0.5 m or 1.0 m respectively for the cases that water depth is shallower than or equal to/deeper than 3.5 feet. Compaction is to be done up to designed lining height and earthen freeboard is formed by spoil banking. Width and minimum embankment from field level for operation and maintenance road are 4.0 m and 0.3 m(1 foot) respectively. Bank width

for filling section are proposed to be 1.0 m ($Q < 50$ cusec), 1.5 m ($50 < Q < 150$ cusec), 2.0 m ($150 < Q < 300$ cusec) and 2.5 m ($Q > 300$ cusec). Half width are respectively proposed for cutting section.

Earthworks is planned to start by stripping at the canal bottom and bank cut by combination of bulldozer and backhoe after completion of temporary diversion work by every 300 to 500 m according to site condition. Haulage of earth material is not considered for the diversion work. Succeedingly, embankment work including over-embankment portion which will be cut after compaction. Borrow of earth material is planned within ROW and areas where vitally salt affected and abandoned and average hauling distance is estimated to be 500 m. Embankment work is executed with emphasis on water content control by water bowser, bulldozer and roller. Cutting and trimming of lining surface is done by backhoe and by manual work.

Lining work is started with preparation of lining base layer by mortar, followed by spreading low-water-content-concrete with steel slip form and vibrator and finished with manual surfacing. Curing with supplying enough humidity (preferably kept under water or spraying water continuously) is strongly recommended to avoid surface crack.

E.2 Cost Estimates

E.2.1 Basic Conditions and Assumptions for the Cost Estimates

Foreign currency portion corresponding to services and material imported and local currency portion corresponding to domestic services and material are separately estimated for each cost items for the purpose of project evaluation and planning of loan arrangement. The project cost comprises investment cost, replacement cost and O&M cost. Institutional reform cost is included within the investment cost. Cost estimates are based on current price at the time of May, 1996 for material, manpower and machinery refereed from price index and statistics of import. Exchange rate of Rs. 34 to US\$ 1.0 is applied for cost estimate at the same time.

E.2.2 Estimates of the Project Cost

Project cost is thus estimated to be Rs. 3,120 million out of which the foreign currency portion turns to be Rs. 1,674 million and 54% and the local currency portion be

Rs. 1,446 million and 46%. The project cost, unit cost and work volume of each work items are shown in Table E-9. Distributary-wise project cost are shown in the Table E-10 ~ 22.

E.2.3 Breakdown of the Project Cost

Investment cost consists of 1) Compensation Cost, 2) Direct Construction Cost, 3) Administration and Consultant Cost, 4) Institutional Reform Cost, 5) Physical Contingency and 6) Price Contingency. Compensation cost of about Rs. 3.0 million includes land compensation cost for construction work outside of the Right of way and replacement cost of the facilities which would be damaged by the construction work. Direct construction cost of about Rs. 1,985 million includes gate installation, earthwork, lining, work, related facilities and miscellaneous works. Miscellaneous works are estimated to be 3% of total cost of the other items in the direct construction cost for temporary outlets, discharge measurement facilities, admixture of concrete and other uncounted items above while construction period. Administration and consultant cost comprises remuneration for expatriate consultants and local stuffs and office maintenance cost including procurement cost of equipments required in the project office. The administration and consultant cost is estimated to be Rs. 284 million and 14.3% of the direct construction cost. Institutional reform cost of about Rs. 76 million and 3.8% of the direct construction cost includes remuneration of expatriate consultant and stuffs (Rs. 64 million), procurement and operation cost of vehicle (Rs. 8 million), office maintenance cost including procurement cost of equipments (Rs. 3 million) and activities and transmission cost (Rs. 1 million) and described in detail in chapter 5.4. Physical contingency is estimated to be 10 % of the direct construction cost. Price contingency is estimated to be about 20% based on price escalation of 3% per year in both foreign and local currency for 4 year net construction period by the year of 2004.

Periodical repair of concrete lining portion as well as related facilities of the distributaries and minors to keep sustainable lined canal prism. The replacement cost is estimated to be 20% of the direct construction cost for every 20 years, namely Rs. 19.85 million and 1% of devaluation of canal is predicted and the replacement cost per 20 years comes to be Rs. 397 million.

E.2.4 Unit Cost Analyses

Unit cost for manpower and material as of May 1996 are surveyed and summarized in the Table E-23. Operation cost of construction machinery are summarized in the Table E-24. Unit cost of each kind of works are listed and compared with the similar project in Table E-25. The unit costs are thus justified applicable for cost estimates of the Project.

E.2.5 Annual Disbursement Schedule

Table E-26 shows annual disbursement schedule in accordance with the proposed project implementation schedule.

E.2.6 Replacement Cost and O&M Cost

Periodical repair of concrete lining portion as well as related facilities of the distributaries and minors to keep sustainable lined canal prism. The replacement cost is estimated to be 20% of the direct construction cost for every 20 years, namely Rs. 19.85 million and 1% of devaluation of canal is predicted and the replacement cost per 20 years comes to be Rs. 397 million. O&M cost is divided into facility maintenance cost and personnel cost. Consideration of safety factor, facility maintenance cost is estimated as high as the same item being spent for unlined channel of about Rs. 17.80 million per year for desilting work and remedies against weeding, erosion and devastation of canal prism. Personnel cost is estimated to be drastically reduced down to Rs. 5.03 million. Annual replacement cost and O&M cost are summarized in the following table.

Annual replacement cost and O&M cost (Unit: Rs. 1,000)				
Item of Cost	LJC	LCC	CBDC	Total
(1) Direct Cost	677,290	1,078,770	229,440	1,985,500
(2) Annual replacement cost and O&M cost				
1) Replacement*1	6,773	10,788	2,294	19,850
2) O&M Cost				
a) Maintenance	5,990	9,602	2,210	17,802
b) Personnel	1,323	2,845	860	5,028
Total	14,087	21,901	5,356	41,344
(3) Annual replacement cost and O&M cost / Direct Cost (%)				
	2.1	2.0	2.3	2.1

E.3 Project Implementation Plan

E.3.1 General

In accordance with the institutional reforms of the water sectors, the Provincial Irrigation Departments (PIDs) will be transformed into Provincial Irrigation and Drainage Authorities (PIDAs). Below the PIDAs, financially self-accounting Area Water Boards (AWBs) will be created. Below the AWB level, farmers will be encouraged to form Water Users Formations at the distributary and minor level on a pilot concept basis. In the current critical time, establishment of implementation program not only for construction work, but also operation and maintenance program - with institutional reforms - is of paramount importance. In this regard, it is strongly recommended to organize an executing agency as shown in Fig. E-1, for executing construction work and for promoting the farmers participation as well.

E.3.2 Implementation of Construction Work

The executive agency for the Project would be PIDA, which would be responsible for the planning, design, bidding and supervision of the project work, and keep close coordination with the three irrigation systems of LJC, LCC and CBDC offices on the project approval, finance and project implementation. The Project would be implemented under the organization of PIDA, which would be reorganized from PID, and would be of great importance in the coordination of activities among the respective departments concerned.

Prior to the commencement of the project work, the Project Director would be appointed under the Managing Director of PIDA. Three Deputy Directors would be nominated as co-managers to assist the Project Director to cover the responsibilities of respective departments of Technical/Civil Engineering, WUA & FO/Agriculture and Legislation.

Under the Technical Department, aiming at the smooth implementation, Planning, Engineering & Construction Section, Right-of-Way and Coordination Section, and Financial Section would be organized. Planning, Engineering & Construction Section would have the work for planning and monitoring of construction work, design and support of construction work and supervision of contract work. Right-of-Way and Coordination Section would deal with land acquisition, education and training to farmers,

management of claim during the construction. Financial Department would be in charge of disbursement and accounting.

E.3.3 Construction Mode and Method

The open international competitive bidding would be conducted with financial assistance from international institution. The procedure of pre-qualification and bidding for the contract work have not been authorized. According to the draft procedure, the Awarding Committee would be chaired by the Managing Director of PIDA. Every matter would be dealt with by the departments concerned under the proposed organization and approved by the committee, through administrative arrangement of Planning, Engineering & Construction Section.

E.3.4 Construction Schedule

Upon approval of the project, the detailed design as well as bidding documents, specifications and other documents/drawings necessary for the approval and implementation of the project work should be commenced and at the same time the selection of consultants would be carried out. The consultants would be selected first by the technical proposal. After approval of the selection, the contract conditions would be concluded. The pre-qualification documents would be revised by the consultants upon the commencement of consulting services and advertised after approval. The contract work would be bidden upon the approval of detailed design and construction drawings and started in the construction. The arrangement of all right-of-way should be accomplished before the construction with every efforts. These pre-construction activities are estimated to take about two years. Overall construction schedule is shown in Fig. E-2.

TABLES

Table E-3 Proposed Structures for LCC Area

No.	Name of Distribury	Name of Minor	Outlet(Nos.)			Drop Type A nos	Bridges(Nos)												Step Total nos	Aqui-duct	Water Course Cross	Pipe Culvert	Escape	Gates	Buffalo Wallow	total
			Type of Outlet				Type of Bridge						Type of Bridge													
			AOSM	Flume	Pipe		All	A	B	C	All	A	B	C	All	A	B	C								
1	SARANG WALA	2	57	43	6	8	26	0	0	0	0	0	2	24	10	1	13	10	1	17	111					
2	NASRANA		133	117	8	10	38	0	0	0	0	4	33	9	1	23	1	1	1	25	212					
3	NASRANA		3	3	3	0	7	0	0	0	0	2	2	2	5	0	0	0	0	0	10					
4	NASRANA		5	2	3	0	1	0	0	0	0	1	4	2	1	1	0	0	0	8	8					
5	NASRANA		6	1	5	0	3	0	0	0	0	7	3	1	2	0	0	0	0	1	10					
6	NASRANA		8	5	3	1	8	0	0	0	0	7	2	1	4	1	0	0	0	5	22					
7	NASRANA		12	8	4	0	8	0	0	0	0	7	2	1	4	1	0	0	0	4	26					
8	NASRANA		172	136	26	10	12	71	0	0	0	5	63	17	6	40	3	1	3	0	35	296				
	Sub-total		36	32	4	2	8	0	0	0	0	3	5	1	4	0	0	0	0	7	53					
9	GOJRA		4	1	3	1	2	0	0	0	0	1	1	1	1	0	0	0	0	3	10					
10	GOJRA		40	33	7	0	3	10	0	0	0	4	6	1	1	4	0	0	0	10	63					
	Sub-total		77	77	0	0	15	0	0	0	0	3	12	11	1	4	0	0	0	11	106					
11	MUNGI		9	6	2	1	6	0	0	0	0	1	5	1	1	0	0	0	0	1	18					
12	MUNGI		86	83	2	1	21	0	0	0	0	3	17	12	1	4	0	0	1	0	124					
	Sub-total		22	18	4	2	5	0	0	0	0	5	3	1	1	0	0	0	0	2	31					
13	JANTWALA/RAMZA		10	8	2	0	3	0	0	0	0	3	1	2	0	0	0	0	0	2	17					
14	JANTWALA		32	26	6	0	3	8	0	0	0	0	8	4	1	3	0	0	0	1	48					
	Sub-total		55	50	5	1	29	0	0	0	0	1	3	25	15	10	0	0	0	2	135					
15	PIR MAHAL		5	3	2	0	2	0	0	0	0	2	2	2	0	0	0	0	0	0	7					
16	PIR MAHAL		12	9	3	1	7	0	0	0	0	1	5	1	1	3	1	0	0	0	20					
17	PIR MAHAL		24	23	1	0	9	0	0	0	0	4	5	5	0	0	0	0	0	0	38					
18	PIR MAHAL		4	4	0	0	3	0	0	0	0	3	1	2	0	0	0	0	0	1	8					
19	PIR MAHAL		100	89	11	0	50	0	0	0	0	8	40	24	1	15	1	0	0	2	188					
	Sub-total		70	68	2	0	17	0	0	0	0	3	13	10	0	0	0	0	0	3	106					
20	KILJANWALA		11	9	2	0	4	0	0	0	0	4	1	3	0	0	0	0	0	0	22					
22	KILJANWALA		81	77	4	0	21	0	0	0	0	3	17	11	0	6	0	0	0	0	128					
	Sub-total		568	487	62	19	207	0	0	0	0	28	0	3	25	79	11	85	4	12	958					

Note: A: New or Replaced, B: Retained and C: Repaired

Table E-4 Proposed Structures for CBDC Area

No.	Name of Distributry	Name of Minor	Outlet(Nos)			Drop		Bridge(Nos)												Step Total nos	Aquiduct	Water Course/Cross	Pipe Culvert	Escape Gates	Cates	Buffalo	Wallow	total				
			Type of Outlet		Type A	Type of Bridge			VR			RW			B	B	A	A	A										A			
			AOSM	Fiume	Pipe	All	A	B	C	All	A	B	C	B																A	A	A
			A	A	A	All	A	B	C	All	A	B	C	B																A	A	A
1	Thaman	2	54	41	3	10	1	1	1	20	12	8	1	10	2							2	11	102								
2	Thaman	Saharan	18	10	4	4		0	9	9				9										3	30							
		sub-total	72	51	7	14	1	1	0	0	0	1	0	0	1	29	21	0	8	1	10	2	0	0	2	14	132					
3	China		63	56	4	3	1	0	20	17	3			3	1									2	16	106						
4	China	Kala	25	18	5	2		0	6	6				6										4	35							
		sub-total	88	74	9	5	1	0	26	23	0	3	0	3	1	0	0	0	0	0	0	0	0	2	20	141						
		Grand Total	160	125	16	19	2	57	0	0	0	0	1	55	44	0	11	1	13	3	0	0	0	4	34	273						

Note: A: New or Replaced, B: Retained and C: Repaired

Table E-5 Project Work Volume Summary

No.	Name of Distributary	Length Lined (km)	Design Discharge (m ³ /s)	Command Area (ha)	Construction Work Volume										Remarks
					Earthwork in Prism		Earthwork for Diversion			Lining Work		Haulage			
					Excavation (m ³)	Embankment (m ³)	Trimming (m ²)	Excavation (m ³)	Embankment (m ³)	Borrow&Haul (m ³)	Concrete (m ³)	Plaster (m ²)	Joints (Linear M.)		
1	Pindi	6.86	0.00	6.86	2,285	17,830.8	33,447.8	22,920.0	5,405.3	18,286.4	28,510.1	1,746.3	22,920.0	7,812.6	13,938.5
2	Hujan	80.13	1.95	78.18	25,236	276,813.9	560,866.4	416,803.3	157,713.2	381,506.9	507,846.2	31,755.9	416,803.3	143,002.0	136,959.1
3	Kirana	107.13	10.64	96.49	36,324	471,143.3	983,768.3	800,068.3	372,383.4	614,634.1	754,875.7	60,968.8	800,068.3	270,667.3	121,568.9
	LCC Total	194.12	12.59	181.53	63,844	265,788.0	1,578,082.4	1,229,791.5	535,501.9	1,014,439.4	1,291,232.0	94,471.0	1,229,791.5	421,481.9	272,466.5
4	Sarangwala	25.04	0.30	24.74	6,627	72,199.5	162,495.1	138,954.5	44,151.3	176,203.2	222,347.5	10,588.0	138,954.5	47,306.7	23,436.7
5	Nasrana	81.42	5.65	75.77	34,677	364,533.1	763,555.3	545,287.5	533,637.8	276,423.9	141,808.3	41,580.2	545,287.5	61,170.2	303,211.4
6	Cojra	17.77	2.25	15.52	7,540	48,274.9	99,830.1	82,510.1	36,175.8	61,583.4	76,982.8	6,287.6	82,510.1	29,339.6	16,669.9
7	Mungi	41.29	3.98	37.31	19,161	160,320.2	346,437.0	259,539.6	114,944.9	311,992.6	383,164.4	19,774.2	259,539.6	79,125.8	76,134.7
8	Jauwala/Hanza	18.58	0.00	18.58	6,513	48,315.8	95,381.2	69,849.2	27,789.7	56,288.0	75,563.7	5,321.8	69,849.2	35,332.3	2,639.1
9	Pir Mahal	82.13	0.00	82.13	18,242	306,817.6	638,323.2	461,798.8	328,315.9	445,610.3	448,800.0	35,194.9	461,798.8	155,346.4	100,125.8
10	Kilianwala	52.71	15.73	36.98	21,019	217,627.4	454,506.5	328,683.0	140,293.7	589,830.0	686,415.4	25,043.9	328,683.0	110,804.6	192,600.9
	LCC Total	318.95	27.91	291.03	110,779	1,315,088.5	2,550,548.2	1,886,622.6	1,225,509.1	1,917,921.4	2,035,082.1	163,790.5	1,886,622.6	518,455.6	214,818.5
11	Thamman	37.09	3.22	33.87	9,816	144,321.8	312,375.0	223,425.1	156,107.5	173,015.8	184,961.5	17,023.6	223,425.1	82,392.4	209,499.6
12	China	33.27	0.19	33.08	16,390	112,374.4	235,088.4	191,668.2	129,290.0	141,480.5	134,964.5	14,605.3	191,668.2	63,910.7	179,379.7
	CBDC Total	20.36	2.61	66.95	26,206	256,696.2	587,463.4	415,093.3	285,337.4	314,496.3	319,926.0	31,628.9	415,093.3	146,303.0	388,879.2
	Project Total	583.45	41.91	539.51	203,829.72	2,240,577.7	4,685,094.2	3,541,507.4	2,046,148.4	3,246,367.0	3,646,240.1	269,890.4	3,541,507.4	1,086,230.5	1,376,164.3

Table E-6 Project Work Volume for LJC Area

No.	Name of Distributary	Name of Minor	Length (km)	Lined (km)	Design Discharge (m ³ /s)	Command Area (ha)	Earthwork in Phases				Construction Work Volume				Land Compensation (m ²)	Remarks		
							Excavation (m ³)	Embankment (m ³)	Trimming (m ²)	Excavation (m ³)	Embankment (m ³)	Borrow/Haul (m ³)	Concrete (m ³)	Lining Plaster (m ²)			Joints (Linear M.)	
1	Pach		6.86	0.00	6.86	2.285	2,874.3	17,830.8	33,447.8	22,920.0	5,405.3	18,298.4	28,510.1	1,746.3	22,920.0	7,812.6	13,938.5	
2	Hujan	Arian	33.98	1.95	32.03	11,329	26,364.2	156,927.9	339,214.8	268,479.3	119,183.7	256,539.4	319,662.7	20,455.8	268,479.3	92,213.4	124,844.7	
3	Hujan	Kor Moman	5.43	0.00	5.43	1,392	2,164.4	14,088.6	25,594.0	16,671.9	6,989.0	3,992.4	8,528.9	1,271.1	16,671.9	5,572.5	0.0	
4	Hujan	Kor Raja	6.78	0.00	6.78	2,668	2,932.7	17,633.2	33,772.1	25,368.7	9,906.6	11,720.9	17,933.2	1,932.2	25,368.7	8,630.8	1,704.9	
5	Hujan	Bulcha	2.81	0.00	2.81	866	1,116.0	7,254.0	13,196.7	7,026.7	1,420.5	4,227.9	8,750.2	535.2	7,026.7	2,632.3	0.0	
6	Hujan	Sahawal	6.34	0.00	6.34	1,974	2,534.0	16,471.0	29,964.6	21,195.8	3,305.9	24,347.7	34,535.4	1,614.9	21,195.8	7,383.0	0.0	
7	Hujan	M. Wala	5.76	0.00	5.76	1,575	2,304.3	14,981.2	27,254.3	17,707.6	4,255.5	21,084.1	29,101.6	1,348.3	17,707.6	6,033.7	10,409.5	
8	Hujan	Jaspal	5.87	0.00	5.87	1,311	2,344.0	15,236.0	27,717.8	16,182.1	4,658.0	16,064.3	23,888.0	1,232.3	16,182.1	5,751.0	0.0	
9	Hujan	sub-total	4.84	0.00	4.84	1,470	1,935.2	12,578.8	22,883.7	14,976.7	3,020.8	9,379.1	16,663.2	1,141.1	14,976.7	4,972.0	0.0	
10	Hujan	sub-total	8.32	0.00	8.32	2,651	3,574.1	21,663.2	41,268.4	29,194.6	4,973.3	34,131.1	48,763.0	2,225.0	29,194.6	9,813.3	0.0	
11	Kirana	Saruli	62.95	9.52	53.43	25,236	67,569.8	356,181.7	771,609.7	640,171.1	318,546.2	474,616.7	571,498.6	48,783.0	640,171.1	215,961.5	121,568.9	
12	Kirana	Hadida	1.59	0.00	1.59	606	634.0	4,121.0	7,497.1	4,064.1	1,126.8	2,632.4	4,881.6	310.3	4,064.1	1,391.2	0.0	
13	Kirana	Malwana	4.11	1.12	2.99	1,639	1,644.4	10,688.6	19,445.0	12,277.9	3,174.4	6,246.4	11,828.5	935.8	12,277.9	4,266.8	0.0	
14	Kirana	Wasuana	10.16	0.00	10.16	3,548	4,571.4	26,254.8	50,158.2	40,932.4	11,020.6	38,151.1	51,033.9	3,118.5	40,932.4	14,095.0	0.0	
15	Kirana	Tandallian	6.89	0.00	6.89	1,731	2,802.4	18,215.6	33,138.4	19,771.4	8,665.0	12,299.7	18,557.5	1,507.6	19,771.4	6,798.0	0.0	
16	Kirana	Rodhan	3.96	0.00	3.96	1,304	1,584.8	10,301.2	18,740.3	12,336.1	14,554.6	13,569.7	7,454.3	939.0	12,336.1	4,182.6	0.0	
17	Kirana	Hunde	6.04	0.00	6.04	2,374	2,647.5	15,691.0	29,167.7	22,319.6	3,036.2	27,626.1	37,466.6	1,701.3	22,319.6	7,591.8	0.0	
18	Kirana	Killa	4.92	0.00	4.92	1,778	1,967.2	12,786.8	23,262.1	15,932.5	5,063.2	10,637.8	16,049.5	1,213.9	15,932.5	5,399.9	0.0	
19	Kirana	Dhabian	4.10	0.00	4.10	822	1,637.2	10,641.8	19,359.9	12,087.0	3,358.2	8,537.8	13,897.7	920.8	12,087.0	4,043.4	0.0	
20	Kirana	sub-total	2.41	0.00	2.41	822	963.2	6,260.8	11,389.8	20,176.2	3,238.3	30,316.8	22,207.5	1,538.6	20,176.2	6,037.2	0.0	
			107.13	10.64	96.49	36,324	86,021.9	471,143.3	983,768.3	800,068.3	372,383.4	614,634.1	754,875.7	60,968.8	800,068.3	270,667.3	121,568.9	
			194.12	12.59	181.53	63,844	134,165.6	765,788.0	1,578,082.4	1,239,791.5	535,501.9	1,014,439.4	1,291,232.0	94,471.0	1,239,791.5	421,481.9	272,466.5	

Total length for LJC is 194.18 km.

Table E-7 Project Work Volume for LCC Area

No.	Name of Distributory	Name of Minor	Length Lined (km)		Design Discharge (m ³ /s)	Command Area (ha)	Earthwork in Prism				Construction Work Volume				Remarks		
			Total (km)	for Lining (km)			Excavation (m ³)	Embankment (m ³)	Trimming (m ²)	Excavation (m ³)	Embankment (m ³)	Haulage Borrow & Haul (m ³)	Concrete (m ³)	Lining Work Plaster (m ²)	Joints (Linear M.)	Land Compensation (m ²)	
1	Sarangwala		25.04	0.30	24.74	2.46	13,853.8	72,199.5	162,895.1	138,954.5	44,151.3	176,203.2	222,347.5	10,588.0	138,954.5	47,506.7	23,436.7
2	Nasrana		54.64	0.00	54.64	8.87	52,893.3	299,696.9	644,443.3	472,776.2	493,214.3	256,473.6	108,010.7	36,036.8	472,776.2	32,838.6	299,684.3
3	Nasrana	Saduana	2.76	1.10	1.66	0.14	1,102.4	7,163.6	13,035.9	3,696.3	2,020.8	387.4	4,236.8	281.9	3,696.3	2,517.2	
4	Nasrana	Khillana	4.43	0.00	4.43	0.30	1,771.6	11,515.4	20,949.2	13,483.4	7,613.6	4,298.4	6,116.6	1,026.6	13,483.4	4,417.7	
5	Nasrana	Narwala	5.82	2.47	3.35	0.48	1,584.8	10,301.2	18,740.3	14,500.9	5,107.1	5,745.8	9,077.7	1,088.6	14,500.9	5,674.9	
6	Nasrana	Sabana	3.66	0.40	3.26	0.23	1,465.2	9,510.8	17,302.3	6,097.7	3,18.8	3,18.8	2,012.7	729.4	9,567.5	3,463.1	
7	Nasrana	Nalohri	4.60	0.82	3.78	0.44	1,850.0	12,025.0	21,876.3	13,927.2	7,046.4	3,744.3	6,549.2	1,061.2	13,927.2	5,673.9	
8	Nasrana	Domra	5.51	0.86	4.65	0.61	2,402.8	14,318.2	27,203.1	17,536.0	12,535.8	5,455.5	5,804.6	1,335.7	17,536.0	6,564.9	3,527.1
		Sub-total	81.42	5.65	75.77	8.87	63,068.1	364,533.1	763,555.5	545,287.5	533,637.8	276,423.9	141,808.3	41,580.2	545,287.5	61,170.2	303,211.4
9	Goyra		15.06	2.10	12.96	1.95	7,632.4	41,252.3	87,074.4	75,326.4	31,401.8	89,028.0	73,448.2	5,739.6	75,326.4	26,798.2	16,669.9
10	Goyra	Zozra	2.71	0.15	2.56	0.23	1,040.4	7,022.6	12,775.7	7,185.6	4,774.0	2,555.4	3,534.5	548.0	7,185.6	2,561.3	
		Sub-total	17.77	2.25	15.52	1.95	8,712.8	48,274.9	99,850.1	82,510.1	36,175.8	61,583.4	76,982.8	6,287.6	82,510.1	29,359.6	16,669.9
11	Mungi		36.97	3.98	32.99	5.03	24,435.9	149,202.6	326,211.5	247,325.2	113,181.5	305,794.4	369,611.8	18,841.7	247,325.2	74,314.0	76,134.7
12	Mungi		4.32	0.00	4.32	0.36	1,710.4	11,117.6	20,225.5	12,214.4	1,763.5	6,208.2	13,552.7	932.5	12,214.4	4,811.8	
		Sub-total	41.29	3.98	37.31	5.39	26,146.3	160,320.2	346,437.0	259,539.6	114,944.9	311,992.6	383,164.4	19,774.2	259,539.6	79,125.8	76,134.7
13	Jarwal/Hamra		10.96	0.00	10.96	1.59	5,157.1	28,503.8	57,798.6	42,676.8	17,436.4	38,980.3	50,758.7	3,252.3	42,676.8	25,999.6	2,639.1
14	Jarwal	Amarwala	7.62	0.00	7.62	0.51	3,240.0	19,812.0	37,582.6	27,172.3	10,353.3	17,387.7	24,803.0	2,069.6	27,172.3	9,332.6	
		Sub-total	18.58	0.00	18.58	1.59	8,403.1	48,315.8	95,381.2	69,849.2	27,789.7	56,288.0	75,561.7	5,321.8	69,849.2	35,332.3	2,639.1
15	Pr Mahal		47.57	0.00	47.57	5.24	34,433.7	216,766.6	438,533.2	327,746.7	279,542.2	341,696.2	303,922.6	24,978.2	327,746.7	108,393.0	99,626.3
16	Pr Mahal	Thera	4.85	0.00	4.85	0.23	1,940.4	12,612.6	22,945.2	12,584.5	2,679.1	8,464.4	16,118.0	959.9	12,584.5	4,212.9	
17	Pr Mahal	Magneya	9.89	0.00	9.89	0.45	4,942.5	25,701.0	54,367.5	40,913.2	13,666.4	31,454.1	46,454.3	3,119.2	40,913.2	14,622.7	
18	Pr Mahal	Juncwala	16.08	0.00	16.08	1.18	7,535.6	41,930.2	84,633.7	71,081.0	31,643.5	45,466.9	56,526.8	5,416.1	71,081.0	24,936.2	499.5
19	Pr Mahal	Jandwala	3.74	0.00	3.74	0.18	1,508.8	9,807.2	17,841.6	9,473.5	784.8	18,528.7	25,778.3	721.6	9,473.5	3,181.7	
		Sub-total	82.13	0.00	82.13	5.24	50,361.0	306,817.6	638,323.2	461,798.8	328,313.9	445,610.3	448,800.0	35,194.9	461,798.8	155,346.4	100,125.8
20	Killuanwala		46.05	15.73	30.32	6.96	32,552.5	200,303.6	422,980.5	308,346.7	123,774.6	583,345.6	682,257.9	23,339.9	308,346.7	103,238.8	192,600.9
21	Killuanwala	Minor #3	6.66	0.00	6.66	0.39	2,665.2	16,519.1	31,516.0	22,336.3	16,519.1	6,484.4	4,157.5	1,703.9	22,336.3	7,545.8	
		Sub-total	52.71	15.73	36.98	6.96	35,217.7	217,622.7	454,506.5	328,683.0	140,293.7	589,830.0	686,415.4	25,043.9	328,683.0	110,804.6	192,600.9
		Total	318.94	27.91	291.03	32.46	205,764.7	1,218,088.5	2,560,548.3	1,886,622.6	1,225,309.1	1,917,931.4	2,035,082.1	143,790.5	1,886,622.6	518,445.6	714,818.5

Total length for LCC is 290.07 km.

Table E-8 Project Work Volume for CBDC Area

No.	Name of Distributory	Name of Minor	Length Lined (km)		Design Discharge (m ³ /s)	Command Area (ha)	Earthwork in Prism				Construction Work Volume				Land Compensation (m ²)	Remarks			
			Total (km)	For Lining (km)			Excavation (m ³)	Embankment (m ³)	Trimming (m ²)	Excavation (m ³)	Embankment (m ³)	Borrow & Haul (m ³)	Lining Work						
													Concrete (m ³)	Plaster (m ²)			Joints (Linear M.)		
1	Thamman		29.85	3.22	26.63	8.29	6,599	23,836.9	125,552.4	275,166.1	196,545.3	138,853.6	162,585.5	173,345.6	14,975.0	196,545.3	72,328.7	183,665.5	
2	Thamman sub-total	Saharan	7.24	0.00	7.24	0.82	3,217	3,283.4	18,769.4	37,208.9	26,879.8	17,253.9	10,430.3	11,615.9	2,048.6	26,879.8	10,063.6	23,834.1	
3	China		37.09	3.22	33.87	8.29	9,816	27,122.3	144,321.8	312,375.0	223,425.1	156,107.5	173,015.8	184,961.5	17,023.6	223,425.1	82,392.4	209,499.6	
4	China sub-total	Kale Minor	25.46	0.19	25.27	4.33	12,664	15,097.1	92,060.6	193,646.1	156,512.1	103,220.2	124,843.8	123,209.0	11,928.2	156,512.1	52,122.0	139,590.5	
			7.81	0.00	7.81	0.96	3,726	3,707.9	20,313.8	41,442.3	35,156.1	26,009.8	16,636.7	11,755.5	2,677.1	35,156.1	11,788.6	39,789.2	
			33.27	0.19	33.08	4.33	16,390	18,805.0	112,374.4	235,088.4	191,668.2	129,270.0	141,480.5	134,964.5	14,605.3	191,668.2	63,910.7	179,379.7	
			70.36	3.41	66.95	12.62	26,206	45,927.3	256,696.2	547,463.4	415,093.3	285,337.4	314,466.3	319,926.0	31,628.9	415,093.3	146,303.3	388,879.3	

Total length for CBDC is 67.34 km.

**Table E-9 Financial Cost for
Lining of Distributaries and Minors**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.					2,421.9	0.0	2,421.9
1.2 Compensation for Hand Pump etc		L.S.					980.0	0.0	980.0
		Sub-total					3,401.9	0.0	3,401.9
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	12	10,701.0	3,600.0	7,101.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	385857.7	8,681.8	6,713.9	1,967.9
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	2240572.7	86,262.0	60,495.5	25,766.6
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	4686094.3	271,324.9	210,405.6	60,919.2
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	3646240.2	199,084.7	155,329.8	43,754.9
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	3541507.6	32,227.7	0.0	32,227.7
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	2046148.5	78,776.7	55,246.0	23,530.7
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	3246867.1	167,213.7	133,121.6	34,092.1
		Sub-total					834,889.7	614,598.5	220,291.2
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	3541507.6	183,450.1	43,560.5	139,889.6
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	269890.5	808,645.9	289,403.6	519,242.3
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2,100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	1086230.6	27,155.8	21,724.6	5,431.2
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					1,019,251.8	354,688.7	664,563.0
(New/Replace Installation)									
Outlet		nos	26000	7800	18200	1038	26,988.0	8,096.4	18,891.6
VR Bridge		nos	40000	12000	28000	200	8,000.0	2,400.0	5,600.0
Drop		nos	60000	18000	42000	51	3,060.0	918.0	2,142.0
Washing Step		nos	60000	18000	42000	84	5,040.0	1,512.0	3,528.0
Buffalo Wallow		nos	70000	21000	49000	267	18,690.0	5,607.0	13,083.0
Spillway		nos	70000	21000	49000	1	70.0	21.0	49.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	37	296.0	88.8	207.2
VR Bridge		nos	4000	1200	2800	169	676.0	202.8	473.2
		Sub-total					62,820.0	18,846.0	43,974.0
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					57,830.0	29,752.0	28,078.0
Direct Cost							1,985,495.5	1,021,485.2	964,010.2
III Administration and Consulting Cost							284,236.3	206,672.0	77,564.3
IV Institutional Reform Cost							76,118.2	34,544.0	41,574.2
V Physical Contingency (10% of item I, II, III and IV)							234,925.2	126,270.1	108,655.1
Base Construction Cost							2,584,177.0	1,388,971.3	1,195,205.7
							372.9	200.4	172.5
Price Escaration							535,760.1	285,222.1	250,538.0
Total Project Cost							3,119,937.1	1,674,193.4	1,445,743.7
US\$, per ha							450.2	241.6	208.6

Table E-10 Financial Cost for Each Distributory Systems

No.	Name of Distributory	Length			Design Discharge (m ³ /s)	Command Area (ha)	Construction Cost (Rs. in Million)															Remarks
		Total (km)	Lined (km)	for Lining (km)			Compen-sation	Gate	Earth-work	Lining	Structure	Other	Direct Cost	Admi & Instnu-tion	Physical Conti.	Base Cost	Price Conti.	Total Cost				
		3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21		
1	Pindi	6.86	0.00	6.86	0.54	2.285	0.05	0.00	5.54	6.61	0.56	0.38	13.09	1.88	0.50	1.55	17.08	0.00	17.08			
2	Hujan	80.13	1.95	78.18	6.46	25.236	0.56	0.00	100.37	120.31	12.14	6.98	239.81	34.34	9.19	28.39	312.30	0.00	312.30			
3	Kirana	107.13	10.64	96.49	12.86	50.765	0.33	0.00	169.59	230.88	11.55	12.36	424.38	60.30	16.30	50.13	551.45	0.00	551.45			
	LJC Total	194.12	12.59	181.53	19.86	78.286	0.94	0.00	275.50	357.81	24.25	19.73	677.29	96.52	26.00	80.08	880.83	0.00	880.83			
4	Sarangwala	25.04	0.30	24.74	2.46	6.627	0.14	0.00	36.37	40.10	3.74	2.41	82.62	11.95	3.16	9.79	107.65	0.00	107.65			
5	Nasrana	81.42	5.65	75.77	8.87	34.677	0.72	0.00	105.73	154.36	8.58	8.06	276.73	38.71	10.68	32.68	359.52	0.00	359.52			
6	Gojra	17.77	2.25	15.52	1.95	7.540	0.07	0.00	17.16	23.85	2.01	1.29	44.30	6.27	1.70	5.23	57.58	0.00	57.58			
7	Mungi	41.29	3.98	37.31	5.39	19.161	0.18	1.78	70.01	74.67	3.66	4.50	154.62	22.45	5.90	18.32	201.48	0.00	201.48			
8	Janiwala/Hamza	18.58	0.00	18.58	1.59	6.513	0.03	0.89	16.11	20.45	1.46	1.17	40.08	5.72	1.54	4.74	52.11	0.00	52.11			
9	Pir Mahal	82.13	0.00	82.13	5.24	18.242	0.22	1.78	113.07	133.26	5.68	7.61	261.40	37.61	10.01	30.92	340.16	0.00	340.16			
10	Killianwala	52.71	15.73	36.98	6.96	27.798	0.37	2.68	110.94	94.83	4.18	6.38	219.01	32.53	8.31	26.02	286.24	0.00	286.24			
	LCC Total	318.94	27.91	291.03	32.46	120.558	1.73	7.14	469.38	541.51	29.32	31.42	1,078.77	155.24	41.30	127.70	1,404.74	0.00	1,404.74			
11	Tharman	37.09	3.22	33.87	8.29	25.877	0.39	1.78	50.70	64.64	4.39	3.65	125.16	17.81	4.81	14.82	162.98	0.00	162.98			
12	China	33.27	0.19	33.08	4.33	16.390	0.34	1.78	39.31	55.29	4.86	3.04	104.28	14.66	4.02	12.33	135.63	0.00	135.63			
	CBDC Total	70.36	3.41	66.95	12.62	42.267	0.72	3.57	90.01	119.93	9.25	6.68	229.44	32.48	8.82	27.15	298.61	0.00	298.61			
	Project Total	583.42	43.91	539.51	64.94	241,111.13	3.40	10.70	834.89	1,019.25	62.82	57.83	1,985.50	284.24	76.12	234.93	2,584.18	0.00	2,584.18			

**Table E-11 Direct Construction Cost for
Lining on Pindi Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	1.39	24.5	0.0	24.5
1.2 Compensation for Hand Pump etc		L.S.					30.0	0.0	30.0
Sub-total							54.5	0.0	54.5
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	0	0.0	0.0	0.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	2874.3	64.7	50.0	14.7
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	17830.8	686.5	481.4	205.1
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	33447.8	1,936.6	1,501.8	434.8
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	28510.1	1,556.7	1,214.5	342.1
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	22920	208.6	0.0	208.6
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	5405.3	208.1	145.9	62.2
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	18298.4	942.4	750.2	192.1
Sub-total							5,538.8	4,093.9	1,444.9
3. Lining Work									
3.1 Mortar Pluster	1" mortar	m2	51.8	12.3	39.5	22920	1,187.3	281.9	905.3
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	1746.3	5,232.3	1,872.6	3,359.7
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	7812.6	195.3	156.3	39.1
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
Sub-total							6,614.8	2,310.7	4,304.1
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	10	260.0	78.0	182.0
VR Bridge		nos	40000	12000	28000	1	40.0	12.0	28.0
Drop		nos	60000	18000	42000	3	180.0	54.0	126.0
Washing Step		nos	60000	18000	42000		0.0	0.0	0.0
Buffalo Wallow		nos	70000	21000	49000	1	70.0	21.0	49.0
Spillway		nos	70000	21000	49000		0.0	0.0	0.0
(Repair Work)	10% of New								
DR Bridge		nos	8000	2400	5600		0.0	0.0	0.0
VR Bridge		nos	4000	1200	2800	2	8.0	2.4	5.6
Sub-total							558.0	167.4	390.6
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					381.3	197.2	184.2
Direct Cost							13,093.0	6,769.2	6,323.8
III Administration and Consulting Cost							1,878.4	1,369.6	508.8
IV Institutional Reform Cost							501.6	228.9	272.7
V Physical Contingency (10% of item I, II, III and IV)							1,552.7	836.8	716.0
Base Construction Cost							17,080.2	9,204.5	7,875.7

**Table E-12 Direct Construction Cost for
Lining on Hujjan Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	13.7	241.1	0.0	241.1
1.2 Compensation for Hand Pump etc		L.S.					320.0	0.0	320.0
Sub-total							561.1	0.0	561.1
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	0	0.0	0.0	0.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	45269.4	1,018.6	787.7	230.9
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	276813.9	10,657.3	7,474.0	3,183.4
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	560366.4	32,474.2	25,182.9	7,291.3
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	507846.2	27,728.4	21,634.2	6,094.2
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	416803.3	3,792.9	0.0	3,792.9
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	157713.2	6,072.0	4,258.3	1,813.7
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	381506.9	19,647.6	15,641.8	4,005.8
Sub-total							100,372.4	74,191.2	26,181.2
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	416803.3	21,590.4	5,126.7	16,463.7
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1923.9	31755.9	95,147.0	34,051.9	61,095.2
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	143002	3,575.1	2,860.0	715.0
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
Sub-total							120,312.5	42,038.6	78,273.9
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	126	3,276.0	982.8	2,293.2
VR Bridge		nos	40000	12000	28000	46	1,840.0	552.0	1,288.0
Drop		nos	60000	18000	42000	11	660.0	198.0	462.0
Washing Step		nos	60000	18000	42000	38	2,280.0	684.0	1,596.0
Buffalo Wallow		nos	70000	21000	49000	56	3,920.0	1,176.0	2,744.0
Spillway		nos	70000	21000	49000		0.0	0.0	0.0
(Repair Work)	10% of New								
DR Bridge		nos	8000	2400	5600	5	40.0	12.0	28.0
VR Bridge		nos	4000	1200	2800	32	128.0	38.4	89.6
Sub-total							12,144.0	3,643.2	8,500.8
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					6,934.9	3,596.2	3,388.7
Direct Cost							239,813.7	123,469.1	116,344.6
III Administration and Consulting Cost							34,342.0	24,980.9	9,361.1
IV Institutional Reform Cost							9,192.9	4,175.4	5,017.5
V Physical Contingency (10% of item I, II, III and IV)							28,391.0	15,262.5	13,128.4
Base Construction Cost							312,300.7	167,888.0	144,412.8

**Table E-13 Direct Construction Cost for
Lining on Kirana Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	12.16	214.0	0.0	214.0
1.2 Compensation for Hand Pump etc		L.S.					115.0	0.0	115.0
		Sub-total					329.0	0.0	329.0
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	0	0.0	0.0	0.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	86021.9	1,935.5	1,496.8	438.7
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	471143.3	18,139.0	12,720.9	5,418.1
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	983768.3	56,960.2	44,171.2	12,789.0
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	754875.7	41,216.2	32,157.7	9,058.5
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	800068.3	7,280.6	0.0	7,280.6
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	372383.4	14,336.8	10,054.4	4,282.4
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	614634.1	31,653.7	25,200.0	6,453.7
		Sub-total					169,586.5	124,304.1	45,282.3
3. Lining Work									
3.1 Mortar Pluster	1" mortar	m2	51.8	12.3	39.5	800068.3	41,443.5	9,840.8	31,602.7
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	60968.8	182,674.7	65,376.8	117,297.9
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	270667.3	6,766.7	5,413.3	1,353.3
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					230,884.9	80,631.0	150,253.9
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	174	4,524.0	1,357.2	3,166.8
VR Bridge		nos	40000	12000	28000	30	1,200.0	360.0	840.0
Drop		nos	60000	18000	42000	12	720.0	216.0	504.0
Washing Step		nos	60000	18000	42000	21	1,260.0	378.0	882.0
Buffalo Wallow		nos	70000	21000	49000	52	3,640.0	1,092.0	2,548.0
Spillway		nos	70000	21000	49000		0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	6	48.0	14.4	33.6
VR Bridge		nos	4000	1200	2800	39	156.0	46.8	109.2
		Sub-total					11,548.0	3,461.4	8,083.6
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					12,360.6	6,252.0	6,108.6
Direct Cost							424,380.0	214,651.5	209,728.4
III Administration and Consulting Cost							60,304.1	43,429.4	16,874.8
IV Institutional Reform Cost							16,303.8	7,259.0	9,044.8
V Physical Contingency (10% of item I, II, III and IV)							50,131.7	26,534.0	23,597.7
Base Construction Cost							551,448.6	291,873.9	259,574.7

**Table E-14 Direct Construction Cost for
Lining on Sarangwala Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	2.34	41.2	0.0	41.2
1.2 Compensation for Hand Pump etc		L.S.					95.0	0.0	95.0
		Sub-total					136.2	0.0	136.2
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	0	0.0	0.0	0.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	13853.8	311.7	241.1	70.7
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	72199.5	2,779.7	1,949.4	830.3
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	162495.1	9,408.5	7,296.0	2,112.4
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	222347.5	12,140.2	9,472.0	2,668.2
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	138954.5	1,264.5	0.0	1,264.5
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	44151.3	1,699.8	1,192.1	507.7
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	176203.2	9,074.5	7,224.3	1,850.1
		Sub-total					36,367.1	27,133.8	9,233.3
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	138954.5	7,197.8	1,709.1	5,488.7
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1923.9	10588	31,723.8	11,353.5	20,370.3
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	47306.7	1,182.7	946.1	236.5
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					40,104.3	14,008.8	26,095.5
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	57	1,482.0	444.6	1,037.4
VR Bridge		nos	40000	12000	28000	10	400.0	120.0	280.0
Drop		nos	60000	18000	42000		0.0	0.0	0.0
Washing Step		nos	60000	18000	42000	10	600.0	180.0	420.0
Buffalo Wallow		nos	70000	21000	49000	17	1,190.0	357.0	833.0
Spillway		nos	70000	21000	49000		0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	2	16.0	4.8	11.2
VR Bridge		nos	4000	1200	2800	13	52.0	15.6	36.4
		Sub-total					3,740.0	1,122.0	2,618.0
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					2,406.3	1,267.9	1,138.4
		Direct Cost					82,617.7	43,532.6	39,085.2
III Administration and Consulting Cost							11,952.5	8,807.7	3,144.8
IV Institutional Reform Cost							3,157.8	1,472.2	1,685.6
V Physical Contingency (10% of item I, II, III and IV)							9,786.4	5,381.2	4,405.2
Base Construction Cost							107,650.6	59,193.7	48,456.9

**Table E-15 Direct Construction Cost for
Lining on Nasrana Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	30.32	533.6	0.0	533.6
1.2 Compensation for Hand Pump etc		L.S.					190.0	0.0	190.0
		Sub-total					723.6	0.0	723.6
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	0	0.0	0.0	0.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	63068.1	1,419.0	1,097.4	321.6
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	364533.1	14,034.5	9,842.4	4,192.1
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	763555.3	44,209.9	34,283.6	9,926.2
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	141808.3	7,742.7	6,041.0	1,701.7
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	545287.5	4,962.1	0.0	4,962.1
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	533637.8	20,545.1	14,408.2	6,136.8
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	276423.9	14,235.8	11,333.4	2,902.5
		Sub-total					105,730.1	75,908.7	29,821.5
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	545287.5	28,245.9	6,707.0	21,538.9
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	41580.2	124,582.6	44,586.4	79,996.1
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	61170.2	1,529.3	1,223.4	305.9
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					154,357.7	52,516.9	101,840.9
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	172	4,472.0	1,341.6	3,130.4
VR Bridge		nos	40000	12000	28000	17	680.0	204.0	476.0
Drop		nos	60000	18000	42000	12	720.0	216.0	504.0
Washing Step		nos	60000	18000	42000	1	60.0	18.0	42.0
Buffalo Wallow		nos	70000	21000	49000	35	2,450.0	735.0	1,715.0
Spillway		nos	70000	21000	49000		0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	5	40.0	12.0	28.0
VR Bridge		nos	4000	1200	2800	40	160.0	48.0	112.0
		Sub-total					8,582.0	2,574.6	6,007.4
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					8,060.1	3,930.0	4,130.1
		Direct Cost					276,730.0	134,930.2	141,799.8
III Administration and Consulting Cost							38,709.0	27,299.7	11,409.2
IV Institutional Reform Cost							10,678.3	4,563.0	6,115.3
V Physical Contingency (10% of item I, II, III and IV)							32,684.1	16,679.3	16,004.8
Base Construction Cost							359,524.9	183,472.2	176,052.7

**Table E-16 Direct Construction Cost for
Lining on Gojra Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	1.67	29.4	0.0	29.4
1.2 Compensation for Hand Pump etc		L.S.					40.0	0.0	40.0
Sub-total							69.4	0.0	69.4
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	0	0.0	0.0	0.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	8712.8	196.0	151.6	44.4
2.2 Excavation for Canal Prism	by machine & manual	m3	38.5	27.0	11.5	48274.9	1,858.6	1,303.4	555.2
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	99850.1	5,781.3	4,483.3	1,298.1
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	76982.8	4,203.3	3,279.5	923.8
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	82510.1	750.8	0.0	750.8
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	36175.8	1,392.8	976.7	416.0
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	61583.4	3,171.5	2,524.9	646.6
Sub-total							17,158.3	12,567.8	4,590.5
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	82510.1	4,274.0	1,014.9	3,259.1
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1923.9	6287.6	18,838.9	6,742.2	12,096.7
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	29359.6	734.0	587.2	146.8
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
Sub-total							23,846.9	8,344.3	15,502.7
4. Structure									
(New/Replace Installation)									
Outlet		nos	26000	7800	18200	40	1,040.0	312.0	728.0
VR Bridge		nos	40000	12000	28000	1	40.0	12.0	28.0
Drop		nos	60000	18000	42000	3	180.0	54.0	126.0
Washing Step		nos	60000	18000	42000	0	0.0	0.0	0.0
Buffalo Wallow		nos	70000	21000	49000	10	700.0	210.0	490.0
Spillway		nos	70000	21000	49000	0	0.0	0.0	0.0
(Repair Work)									
DR Bridge	10% of New	nos	8000	2400	5600	4	32.0	9.6	22.4
VR Bridge		nos	4000	1200	2800	4	16.0	4.8	11.2
Sub-total							2,008.0	602.4	1,405.6
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					1,290.4	645.4	645.0
Direct Cost							44,303.6	22,159.9	22,143.7
III Administration and Consulting Cost							6,265.2	4,483.5	1,781.7
IV Institutional Reform Cost							1,704.4	749.4	955.0
V Physical Contingency (10% of item I, II, III and IV)							5,234.3	2,739.3	2,495.0
Base Construction Cost							57,576.8	30,132.1	27,444.7

**Table E-17 Direct Construction Cost for
Lining on Mungi Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	7.61	133.9	0.0	133.9
1.2 Compensation for Hand Pump etc		L.S.					50.0	0.0	50.0
		Sub-total					183.9	0.0	183.9
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	2	1,784.0	600.0	1,184.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	26146.3	588.3	454.9	133.3
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	160320.2	6,172.3	4,328.6	1,843.7
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	346437	20,058.7	15,555.0	4,503.7
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	383164.5	20,920.8	16,322.8	4,598.0
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	259539.6	2,361.8	0.0	2,361.8
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	114944.9	4,425.4	3,103.5	1,321.9
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	311992.6	16,067.6	12,791.7	3,275.9
		Sub-total					70,006.6	52,101.7	17,904.9
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	259539.6	13,444.2	3,192.3	10,251.8
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1923.9	19774.2	59,247.5	21,203.9	38,043.6
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	79125.8	1,978.1	1,582.5	395.6
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					74,669.8	25,978.7	48,691.0
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	86	2,236.0	670.8	1,565.2
VR Bridge		nos	40000	12000	28000	12	480.0	144.0	336.0
Drop		nos	60000	18000	42000	1	60.0	18.0	42.0
Washing Step		nos	60000	18000	42000	0	0.0	0.0	0.0
Buffalo Wallow		nos	70000	21000	49000	12	840.0	252.0	588.0
Spillway		nos	70000	21000	49000	0	0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	3	24.0	7.2	16.8
VR Bridge		nos	4000	1200	2800	4	16.0	4.8	11.2
		Sub-total					3,656.0	1,096.8	2,559.2
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					4,503.5	2,393.3	2,110.2
Direct Cost							154,619.9	82,170.5	72,449.3
III Administration and Consulting Cost							22,454.4	16,625.2	5,829.3
IV Institutional Reform Cost							5,903.3	2,778.8	3,124.5
V Physical Contingency (10% of item I, II, III and IV)							18,316.1	10,157.4	8,158.7
Base Construction Cost							201,477.6	111,731.9	89,745.7

**Table E-18 Direct Construction Cost for
Lining on Janiwala/Hamza Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	0.26	4.6	0.0	4.6
1.2 Compensation for Hand Pump etc		L.S.					25.0	0.0	25.0
Sub-total							29.6	0.0	29.6
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	592,000	300,000	592,000	1	892.0	300.0	592.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	8405.1	189.1	146.2	42.9
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	48315.8	1,860.2	1,304.5	555.6
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	95381.2	5,522.6	4,282.6	1,240.0
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	75563.7	4,125.8	3,219.0	906.8
2.5 Trimming & Surface Finishing	Mannual	m2	9.1	0.0	9.1	69849.2	635.6	0.0	635.6
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	27789.7	1,069.9	750.3	319.6
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	56288.0	2,898.8	2,307.8	591.0
Sub-total							16,112.9	11,864.3	4,248.6
3. Lining Work									
3.1 Mortar Pluster	1" mortar	m2	51.8	12.3	39.5	69849.2	3,618.2	859.1	2,759.0
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1923.9	5321.8	15,945.2	5,706.6	10,238.6
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	35332.3	883.3	706.6	176.7
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
Sub-total							20,446.7	7,272.4	13,174.3
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	32	832.0	249.6	582.4
VR Bridge		nos	40000	12000	28000	4	160.0	48.0	112.0
Drop		nos	60000	18000	42000	3	180.0	54.0	126.0
Washing Step		nos	60000	18000	42000	0	0.0	0.0	0.0
Buffalo Wallow		nos	70000	21000	49000	4	280.0	84.0	196.0
Spillway		nos	70000	21000	49000	0	0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	0	0.0	0.0	0.0
VR Bridge		nos	4000	1200	2800	3	12.0	3.6	8.4
Sub-total							1,464.0	439.2	1,024.8
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					1,167.5	596.3	571.2
Direct Cost							40,083.0	20,472.1	19,610.9
III Administration and Consulting Cost							5,719.9	4,142.0	1,577.9
IV Institutional Reform Cost							1,538.1	692.3	845.7
V Physical Contingency (10% of item I, II,III andIV)							4,737.1	2,530.6	2,206.4
Base Construction Cost							52,107.6	27,837.1	24,270.5

Table E-19 Direct Construction Cost for Lining on Pirmahal Distributary System

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	10.01	176.2	0.0	176.2
1.2 Compensation for Hand Pump etc		L.S.					45.0	0.0	45.0
Sub-total							221.2	0.0	221.2
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	2	1,784.0	600.0	1,184.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	50361	1,133.1	876.3	256.8
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	306817.6	11,812.5	8,284.1	3,528.4
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	638323.2	36,958.9	28,660.7	8,298.2
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	448800.0	24,504.5	19,118.9	5,355.6
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	461798.8	4,202.4	0.0	4,202.4
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	328315.9	12,640.2	8,864.5	3,775.6
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	445610.3	22,948.9	18,270.0	4,678.9
Sub-total							113,067.3	83,198.2	29,869.1
3. Lining Work									
3.1 Mortar Pluster	1" mortar	m2	51.8	12.3	39.5	461798.8	23,921.2	5,680.1	18,241.1
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	35194.9	105,451.0	37,739.5	67,711.5
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	155346.4	3,883.7	3,106.9	776.7
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
Sub-total							133,255.8	46,526.5	86,729.3
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	100	2,600.0	780.0	1,820.0
VR Bridge		nos	40000	12000	28000	24	960.0	288.0	672.0
Drop		nos	60000	18000	42000	3	180.0	54.0	126.0
Washing Step		nos	60000	18000	42000	0	0.0	0.0	0.0
Buffalo Wallow		nos	70000	21000	49000	25	1,750.0	525.0	1,225.0
Spillway		nos	70000	21000	49000	1	70.0	21.0	49.0
(Repair Work)	10% of New								
DR Bridge		nos	8000	2400	5600	8	64.0	19.2	44.8
VR Bridge		nos	4000	1200	2800	15	60.0	18.0	42.0
Sub-total							5,684.0	1,705.2	3,978.8
5. Miscellaneous Items	3% of Item I-4 above	L.S.					7,613.7	3,960.9	3,652.8
Direct Cost							261,404.9	135,990.9	125,414.0
III Administration and Consulting Cost							37,605.2	27,514.4	10,090.8
IV Institutional Reform Cost							10,007.5	4,598.9	5,408.6
V Physical Contingency (10% of item I, II, III and IV)							30,923.9	16,810.4	14,113.5
Base Construction Cost							340,162.6	184,914.5	155,248.1

**Table E-20 Direct Construction Cost for
Lining on Killianwala Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	19.26	339.0	0.0	339.0
1.2 Compensation for Hand Pump etc		L.S.					30.0	0.0	30.0
		Sub-total					369.0	0.0	369.0
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	3	2,676.0	900.0	1,776.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	35217.7	792.4	612.8	179.6
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	217627.4	8,378.7	5,875.9	2,502.7
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	454506.5	26,315.9	20,407.3	5,908.6
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	686415.4	37,478.3	29,241.3	8,237.0
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	328683	2,991.0	0.0	2,991.0
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	140293.7	5,401.3	3,787.9	1,613.4
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	589830.0	30,376.2	24,183.0	6,193.2
		Sub-total					110,941.4	83,495.5	27,445.9
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	328683	17,025.8	4,042.8	12,983.0
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	25043.9	75,036.5	26,854.6	48,182.0
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	110804.6	2,770.1	2,216.1	554.0
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					94,832.4	33,113.5	61,719.0
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	81	2,106.0	631.8	1,474.2
VR Bridge		nos	40000	12000	28000	11	440.0	132.0	308.0
Drop		nos	60000	18000	42000	1	60.0	18.0	42.0
Washing Step		nos	60000	18000	42000	1	60.0	18.0	42.0
Buffalo Wallow		nos	70000	21000	49000	21	1,470.0	441.0	1,029.0
Spillway		nos	70000	21000	49000	0	0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	3	24.0	7.2	16.8
VR Bridge		nos	4000	1200	2800	6	24.0	7.2	16.8
		Sub-total					4,184.0	1,255.2	2,928.8
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					6,379.0	3,562.9	2,816.1
Direct Cost							219,012.9	122,327.1	96,685.7
III Administration and Consulting Cost							32,529.2	24,749.8	7,779.3
IV Institutional Reform Cost							8,306.5	4,136.8	4,169.7
V Physical Contingency (10% of item I, II, III and IV)							26,021.8	15,121.4	10,900.4
Base Construction Cost							286,239.3	166,335.1	119,904.1

**Table E-21 Direct Construction Cost for
Lining on Thamman Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	20.95	368.7	0.0	368.7
1.2 Compensation for Hand Pump etc		L.S.					20.0	0.0	20.0
		Sub-total					388.7	0.0	388.7
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	2	1,784.0	600.0	1,184.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	27122.3	610.3	471.9	138.3
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	144321.8	5,556.4	3,896.7	1,659.7
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	312375	18,086.5	14,025.6	4,060.9
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	184961.5	10,098.9	7,879.4	2,219.5
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	223425.1	2,033.2	0.0	2,033.2
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	156107.5	6,010.1	4,214.9	1,795.2
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	173015.8	8,910.3	7,093.6	1,816.7
		Sub-total					50,695.4	37,110.2	13,585.2
3. Lining Work									
3.1 Mortar Pluster	1" mortar	m2	51.8	12.3	39.5	223425.1	11,573.4	2,748.1	8,825.3
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1923.9	17023.6	51,006.1	18,254.4	32,751.7
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	82392.4	2,059.8	1,647.8	412.0
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
		Sub-total					64,639.3	22,650.4	41,989.0
4. Structure (New/Replace Installation)									
Outlet		nos	26000	7800	18200	72	1,872.0	561.6	1,310.4
VR Bridge		nos	40000	12000	28000	21	840.0	252.0	588.0
Drop		nos	60000	18000	42000	1	60.0	18.0	42.0
Washing Step		nos	60000	18000	42000	10	600.0	180.0	420.0
Buffalo Wallow		nos	70000	21000	49000	14	980.0	294.0	686.0
Spillway		nos	70000	21000	49000	0	0.0	0.0	0.0
(Repair Work) 10% of New									
DR Bridge		nos	8000	2400	5600	1	8.0	2.4	5.6
VR Bridge		nos	4000	1200	2800	8	32.0	9.6	22.4
		Sub-total					4,392.0	1,317.6	3,074.4
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					3,645.3	1,850.3	1,795.0
		Direct Cost					125,156.1	63,528.6	61,627.5
III Administration and Consulting Cost							17,812.0	12,853.4	4,958.6
IV Institutional Reform Cost							4,806.1	2,148.4	2,657.8
V Physical Contingency (10% of item I, II, III and IV)							14,816.3	7,853.0	6,963.3
Base Construction Cost							162,979.2	86,383.4	76,595.8

**Table E-22 Direct Construction Cost for
Lining on Chinna Distributary System**

Work Item	Specification	Unit	Unit Cost(Rs.)			Work Volume	Cost(1,000Rs.)		
			Total	F	L		Total	F	L
I Compensation									
1.1 Compensation for Land, House etc		L.S.	16000		16000	17.94	315.7	0.0	315.7
1.2 Compensation for Hand Pump etc		L.S.					20.0	0.0	20.0
	Sub-total						335.7	0.0	335.7
II Direct Construction Cost									
1. Gate and Installation	at Disty's Head	nos	892,000	300,000	592,000	2	1,784.0	600.0	1,184.0
2. Earthwork									
2.1 Stripping (0.2 m)	by machine	m3	22.5	17.4	5.1	18805	423.1	327.2	95.9
2.2 Excavation for Canal Prism	by machine&manual	m3	38.5	27.0	11.5	112374.4	4,326.4	3,034.1	1,292.3
2.3 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13	235088.4	13,611.6	10,555.5	3,056.1
2.4 Borrow & Haulage	Excavation and haul within 500 m	m3	54.6	42.6	12	134964.5	7,369.1	5,749.5	1,619.6
2.5 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1	191668.2	1,744.2	0.0	1,744.2
2.6 Excavation for Diversion Work	by machine	m3	38.5	27.0	11.5	129230	4,975.4	3,489.2	1,486.1
2.7 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	141480.5	7,286.2	5,800.7	1,485.5
	Sub-total						39,312.9	28,629.0	10,683.9
3. Lining Work									
3.1 Mortar Plaster	1" mortar	m2	51.8	12.3	39.5	191668.2	9,928.4	2,357.5	7,570.9
3.2 Concrete insitu	3" thick	m3	2,996.2	1,072.3	1,923.9	14605.3	43,760.4	15,661.3	28,099.1
3.3 Precast Panel	2" thick	m3	3,300.0	1,200.0	2100		0.0	0.0	0.0
3.4 Joint	Rubber/Bitumen	m	25.0	20.0	5	63910.7	1,597.8	1,278.2	319.6
3.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40		0.0	0.0	0.0
	Sub-total						55,286.6	19,297.0	35,989.6
4. Structure									
(New/Replace Installation)									
Outlet		nos	26000	7800	18200	88	2,288.0	686.4	1,601.6
VR Bridge		nos	40000	12000	28000	23	920.0	276.0	644.0
Drop		nos	60000	18000	42000	1	60.0	18.0	42.0
Washing Step		nos	60000	18000	42000	3	180.0	54.0	126.0
Buffalo Wallow		nos	70000	21000	49000	20	1,400.0	420.0	980.0
Spillway		nos	70000	21000	49000	0	0.0	0.0	0.0
(Repair Work)									
DR Bridge	10% of New	nos	8000	2400	5600	0	0.0	0.0	0.0
VR Bridge		nos	4000	1200	2800	3	12.0	3.6	8.4
	Sub-total						4,860.0	1,458.0	3,402.0
5. Miscellaneous Items	3% of Item 1-4 above	L.S.					3,037.3	1,499.5	1,537.8
	Direct Cost						104,280.8	51,483.5	52,797.3
III Administration and Consulting Cost							14,664.5	10,416.4	4,248.1
IV Institutional Reform Cost							4,018.0	1,741.0	2,277.0
V Physical Contingency (10% of item I, II, III and IV)							12,329.9	6,364.1	5,965.8
Base Construction Cost							135,628.9	70,005.0	65,623.8

TABLE E-23 Price List of Labour and Construction Material

No.	Item	Unit	Cost(Rs.)			Remarks
			Total	Foreign	Local	
A. Labour						
1	Forman	man-day	250.0	0.0	250.0	
2	Assist. forman/Semi-skilled	man-day	200.0	0.0	200.0	
3	Heavy equi. ope	man-day	200.0	0.0	200.0	
4	Assist. heavy equi. ope	man-day	180.0	0.0	180.0	
5	Dump truck driver	man-day	180.0	0.0	180.0	
6	Assist. dump driver	man-day	150.0	0.0	150.0	
7	Common driver	man-day	150.0	0.0	150.0	
8	Carpenter/Mason	man-day	200.0	0.0	200.0	
9	Bar bender(cut and bind)	ton	900.0	0.0	900.0	
10	Common labour(unskilled)	man-day	110.0	0.0	110.0	
B. Construction Materials						
1 Aggregates, rock and soil						
a)	Sand(normal)	m3	110.0	0.0	110.0	from Chenab River
b)	Sand(coarse)	m3	200.0	0.0	200.0	from Chenab River
c)	Coarse Aggregate/Gravel	m3	300.0	60.0	240.0	Faisalabad(Rp 200/Salgodha, Rp 420/Lahore) Rock quarry at Salgodha
d)	Rock, Riprap	m3	425.0	85.0	340.0	Rock quarry at Salgodha, cost at Lahore
e)	Fine Clay	kg/m3	40.0	0.0	40.0	
2 Lumber						
a)	Plywood ,5mm	m2	100.0	0.0	100.0	
b)	Timber (Plank,1"*12")	m	130.0	0.0	130.0	
c)	Timber(Scaffolding,4")	m	90.0	0.0	90.0	
3	<u>Rainforced iron bar</u>	ton	20000.0	6000.0	14000.0	
4	<u>Portland cement</u>	ton	3700.0	1110.0	2590.0	
5 Fuel and Oil Product						
a)	Gasoline	lit	16.5	5.0	11.6	
b)	Diesel	lit	7.5	2.3	5.3	
c)	Engine oil	lit	95.0	28.5	66.5	
d)	Bitumen 80/100	kg	6.0	1.8	4.2	
6 RC Pipe & Flume						
a)	Dia. 6"	m	125.0	25.0	100.0	
b)	Dia. 12"	m	310.0	62.0	248.0	
7 Steel						
a)	Steel Plate/products	ton	25000.0	5000.0	20000.0	
b)	Hand Rail	ton	22000.0	4400.0	17600.0	
8 Other						
a)	Brick	1,000pc	1500.0	0.0	1500.0	commonly available
b)	Ceramic Tile	1,000pc	11500.0	0.0	11500.0	National Ceramic Co.
c)	PVC Sheet (0.08-0.12mm)	m2	18.0	18.0	0.0	imported from Korea
d)	Polyethylene sheet(same)	m2	14.0	4.2	9.8	Local Product
e)	EDPM Rubber Sheet(1mm)	m2	300.0	300.0	0.0	Japanese Market Price
f)	FPA Sheet(0.8mm)	m2	170.0	170.0	0.0	Estimated price at PC-1 of FESS Project
g)	Geo-Textile(1mm)	m2	30.0	0.0	30.0	
h)	Tree Plant	1,000nos	5000.0	0.0	5000.0	
i)	Water Stop(Lining Joint)	m	20.0	20.0	0.0	Rubber Belt(150mm width x 1mm thick)

Table E-24 Operation Cost of Construction Equipment

No.	Equipment	Specifications		Operation Cost			Remarks
		Spec.	PS	FC (Rs./hr)	LC (Rs./hr)	Total (Rs./hr)	
A Earth Moving & Excavation							
1.	Bulldozer ,D6	11t	160	851	90	941	
2.	Bulldozer ,D7	17 t	220	1,064	130	1,194	
3.	Bulldozer ,D8 with Ripper	21 t	290	1,918	179	2,097	
4.	Tractor shovel	1.2m3	100	660	127	787	*2
5.	Excavator	0.6m3	140	1,106	94	1,200	*1
6.	Excavator	1.2m3	210	2,092	130	2,222	*3
7.	Dredger of 1.2m3 bucket	21 t	230	2,092	130	2,222	*3
8.	Tractor Trailer	5 t	60	162	35	197	*2
9.	Wheel loader	2.2m3	160	1,060	109	1,169	*1
10.	Dump truck	11 t	210	766	151	916	*1
11.	Dump truck	20 t	290	1,467	206	1,674	
B. Compaction							
12.	Tyre roller	11-17t	100	336	70	406	*1
13.	Tyre roller	21-31t	150	586	87	673	*3
14.	Tamping roller (C. dozer)	17t	150	1,241	121	1,362	
15.	Tamping roller (C. dozer)	21t	230	1,943	205	2,148	
16.	Vibration roller	3t	25	393	50	443	
17.	Vibration roller	15t	160	1,576	126	1,703	
18.	Sheep-Foot Roller	11-17t	100	464	99	563	*3
19.	Pneumatic Vibrater	-	-	52	6	58	*2
20.	Tractor Water Bowser,4m3	5 t	60	174	35	209	*2
21.	Water tank rolly, 10m3	11 t	210	696	87	783	*1
22.	Motor Grader of 3.7m brade	17 t	150	1,241	121	1,362	*1
C. Other Equipment							
23.	Normal Truck	10t	160	348	52	400	*2
24.	Normal Truck	2 t	100	232	35	267	*2
25.	Jeep,4-wheel drive	2 t	120	319	46	365	*2
26.	Truck w/ 2t crane	10 t	160	406	52	458	*2
27.	Tractor w/ 1t crane	5t	60	209	35	244	*2
28.	Compressor	11m3	110	432	101	534	
29.	Compressor	17m3	190	636	150	787	
30.	Concrete mixer,1bag	0.16m3	-	383	35	418	*2
31.	Concrete mixer ,3bag	0.5m3	-	696	58	754	*2
32.	Truck Mixer(4m3)	11t	210	696	87	783	*3
33.	Batching Plant,0.6m3	41kw	-	1,297	44	1,341	
34.	Generator	10kVA	-	174	58	232	*2
35.	Generator	35kVA	-	371	87	458	*2
36.	Crusher Plant,dia=600mm	45kw	-	539	44	583	
37.	Secondary Crusher	0.5m3	-	128	17	145	*2
38.	Fuel Bowser, 10m3	11t	210	696	87	783	*1
39.	Low-bed Trailer	35t	320	1,392	174	1,566	*3
40.	Bitumen Sprayer,Truck Mountec	11 t	210	696	87	783	*3
D. Boring, Blasting & Piling							
41.	Boring Machine	3.7KW	-	94	36	130	
42.	Augar Machine	45kw	-	539	44	583	
43.	Pile Driver	-	210	696	87	783	
44.	Pneumatic Jack Hammer	2" bit	-	220	23	244	
45.	Rock Drill	-	-	220	23	244	

Note: 1. Blank Remarks means estimated cost according to international price
 2. *1: Price Listed from Punjab Gov't 3. *2: Price quoted or checked from Local Market
 3. *3: estimated from Local Market Price of Equivalent or similar item

Table E-25 Unit Cost Comparison for Lining Work

Work Item	Specification	Unit	Unit Price (Rs.)			Referred Total Unit Price*1		Remarks (Our Interim)	Labour Portion	
			Total	F	L	Chashma	FESS			IMP
1. Earthwork										
1.1 Excavation for Canal Prism	by machine & manual	m3	38.5	27.0	11.5	42.0	110(1.1-3)	15.2	25.0	8.6
1.2 Embankment and Compaction of Bank	by machine, normal	m3	57.9	44.9	13.0	52.4	A	21.5	65.0	8.0
1.3 Borrow & Haul	within 75 m	m3	54.6	42.6	12.0	0.6	A	1.8	-	2.9
1.4 Trimming & Surface Finishing	Manual	m2	9.1	0.0	9.1		9.2	7.9	7.0	8.8
1.5 Excavation for Diversion Work	by machine and Manual	m3	38.5	27.0	11.5	-	-	14.5	25.0	10.3
1.6 Embankment for Diversion Work	by machine	m3	51.5	41.0	10.5	-	-	14.5	25.0	1.5
2. Lining Work										
2.1 Mortar Plaster	1:6 mix, 1" mortar	m2	51.8	12.3	39.5	65.0	44.9	36.0	35.0	20.1
2.2 Concrete insitu	1:2:4 mix, 3" thick w/Stop Form	m3	2,996.2	1,072.3	1,923.9	2,500.0	1,870.0	2,000.0	3,100.0	428.3
2.3 Precast Panel	1:2:4 mix, 2" thick	m3	3,300.0	1,200.0	2,100.0	2,500.0	1,870.0	-	-	400.0
2.4 Joint	Rubber Joint	m	25.0	20.0	5.0	-	-	-	-	4.0
2.5 Geomembrane with geotextile	1 mm	m2	340.0	300.0	40.0	-	220.0	-	410.0	10.0

Note: *1: adjusted at 1996 May Chashma: JICA Study for Chashma Lift Irrigation Project in NWFP, 1994
IMP: Irrigation Management Project (ADB), 1996 or Punjab Water Conservation Project, 1994 FESS: Fordowah

Table E-26 Disbursement Schedule for the Project

Work Item	Total Cost (1,000Rs.)		Disbursement Schedule												
	Total	Foreign	Local	1999		2000		2001		2002		2003		2004	
				F	L	F	L	F	L	F	L	F	L	F	L
I Compensation	3,401.9	0.0	3,401.9			134		1134		1134				1000	
II Direct Construction Cost															
1. Gate and Installation	10,704	3,600	7,104			300	592	600	1184	1500	2960	1200	2368		
2. Earthwork	834,890	614,598	220,291			11132	3903	123075	44709	145001	51448	167695	60116	167695	60116
3. Lining Work	1,019,252	354,689	664,563			6387	11815	75374	141098	80532	151148	96198	180251	96198	180251
4. Structure	62,820	18,846	43,974			466	1088	4263	9947	4072	9501	5023	11719	5023	11719
5. Miscellaneous Items	57,830	29,752	28,078			549	522	6099	5908	6933	6452	8103	7634	8067	7563
Direct Cost Total	1,985,495	1,021,485	964,010	0	0	18834	17921	209411	202845	238038	221508	278219	262088	276983	259649
III Administration and Consulting Cost	284,236	206,672	77,564	62002	23269	31001	11635	31001	11635	31001	11635	31001	11635	20667	7756
IV Institutional Reform Cost	76,118	34,544	41,574	1727	2079	5182	6236	6909	8315	10363	12472	10363	12472		
V Physical Contingency	234,925	126,270	108,655	6373	2535	5502	3593	24732	22399	27940	24675	31958	28719	29765	26741
Base Construction Cost	2,584,177	1,388,971	1,195,206	70102	27883	60518	39518	272052	246322	307343	271424	351541	315914	327415	294146
VI Price Escalation	535,760	285,222	250,538	6500	2585	7596	4960	43331	39233	59641	52670	80810	72620	87345	78469
Total Project Cost	3,119,937	1,674,193	1,445,744	76602	30468	68114	44478	315383	285554	366983	324094	432352	388534	414760	372615

FIGURES

Fig. 6.1-1 Proposed Organization of Project Implementation




Fig. 6.2.3-1 IMPLEMENTATION SCHEDULE

ACTIVITIES	1997		1998		1999		2000		2001		2002		2003		2004						
	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	
I. PREPARATORY WORKS																					
(1) Loan Procedure																					
Preparation of PC- I Form																					
Approval of PDWP																					
Approval of CBWP																					
Financial Institution Appraisal																					
Loan Agreement																					
(2) Selection of Consultant																					
II. PRE-CONSTRUCTION WORKS																					
(1) Survey and Design Work including Review of Existing Development Plan																					
(2) Preparation of Bid Documents																					
(3) Prequalification of Contractors																					
(4) Bidding/Contracting																					
III. LAND ACQUISITION																					
IV. CONSTRUCTION WORKS																					
(1) LJC																					
Pindi																					
Hujjan																					
Kirana																					
(2) LCC																					
Sarangwala																					
Nasrana																					
Gojra																					
Mungi																					
Janiwala/Hamza																					
Pirmahal																					
Kilianwala																					
(3) CBDC																					
Thamman																					
China																					
V. ADMINISTRATION																					
V. ENGINEERING SERVICES																					