
Chapter 9

Evaluation of the Master Plan



9 Evaluation of the Master Plan

9.1 The Municipal Solid Waste Management Master Plan

9.1.1 Frameworks of the Master Plan

9.1.1.1 Review of the Planning Frameworks

The framework of the SWM Master Plan proposed in the Interim Report was heavily relying on the participation of private sectors in refuse collection, especially in the UA's and SUPA's where the majority of residents were expected to pay RCC. However, the conclusion of the financial analysis of the Master Plan was unfeasible without the financial supports of both Areas A and B^{2a}, as shown in Annex 16.

DCC started the expansion of refuse collection area to 25 wards from 5 wards by increasing the number of concessionaires in August 1996; this was like a trial run of the proposal in the Master Plan. However, the increase in the waste collection amount achieved by expansion plan was found to be only 6 tonnes per day, equivalent to 0.3 % of the total waste generation and 4 % to the total refuse collection amount.

This result definitely proves that experimental expansion of the private refuse collection has failed. This was anticipated from the results of the financial study of the SWM Master Plan presented in the Interim Report. The main cause of failure was that the majority of residents refused to pay RCCs. The achieved RCC collection rate did not reach even the rate expected in the Interim Master Plan.

This forced the basic framework of the SWM Master Plan to shift from a concessionaire oriented model to a more DCC oriented one. There has been a possibility of adopting a more DCC oriented plan since July 1997 due to the rapid increase in revenue from Tax by the new DCC. Therefore, the change of the basic framework was decided jointly by the DCC and the Study Team in March 1997.

9.1.1.2 Goals and Targets

a. Goals

The principal goal of the SWM Master Plan is to establish a proper management system for SW by the target year 2005 in Dar es Salaam City, this being the centre of the country's economic and industrial activities and where approximately 8% of the national population lives.

Through the establishment of a proper SWM system, the Plan aims at:

- preservation of the environment and public health, and sustainable development of the city; and
- promotion and growth of the Tanzanian economy through gaining foreign investment.

Accordingly, the goals of the Master Plan are as follows.

- 1. Establishment of a self-sustainable SWM system.
- Provision of collection services in the urban area (UA), semi-urban planned development area (SUPA) and semi-urban unplanned development area (SUUA).
- 3. Establishment of a reliable collection system under which regular services can be provided.
- 4. Construction of sanitary disposal sites which employ sufficient measures for protection of the environment and human health.
- 5. Development and promotion of a community based recycling system (on-site).
- Establishment of efficient street sweeping and drain cleansing system through public co-operation.
- 7. Establishment of a Beneficiary-Pay-Principle (BPP) under which customers pay refuse collection charges (RCCs) and refuse tipping fees.
- 8. Establishment of proper legislation and regulations through modification and revision of the existing ones.
- 9. Establishment of a control, monitoring and auditing committee which will consist of SWM experts and will be organised by PMO.
- 10. Establishment of proper roles expected of organisations involved in SWM.
- 11. Strengthening of the management and administration system.
- 12. Development and promotion of public participation and education programmes.
- 13. Development of SWM human resources.
- Securing funds for capital investment in equipment and facilities necessary for the realisation of the goals, especially during the time of take off.

b. Target Year

The master plan shall cover the period between 1997 and 2006. Upon consideration of the limited resources of DCC for SWM, the goal of the master plan shall be achieved in a stepwise manner. The period of the plan is divided into the following three stages.

Table 9-1: Target Year

Category of Plan	Target Year
Master Plan	1997 - 2010
Phase 1: Preparation for Implementing of F/S Projects	1997 - 1999
Phase 2: Implementation of F/S Projects	2000 - 2002
Phase 3: Implementation of M/P Projects	2003 - 2005



Targets c.

In order to achieve the principle goal of the master plan, the targets for the establishment of the major technical system components for each phase are proposed and tabulated in Table 9-2.

Table 9-2: Targets for Establishment of Major Technical System Components

Phase		Phase I	Phase II	Phase III
Components	1996	(1997 - 1999)	(2000 - 2002)	(2003 - 2005)
1. Refuse Collection Rate				
UA	90 %	-	100%	
SUPA	. 12 %	30%	50%	
SUUA	0%	4%	30%	
RA	0 %	0%	0%	
Length Covered by Street Sweeping Service	34 km	50 km	100 km	
Intermediate Treatment and Recycling	No treatment facilities other than pilot on-site compost and an incinerator for medical waste	Promotion of organised recycling	Promotion of organised recycling	Promotion of segregation at generation for recycling
Rate of Recycling	 			40.00
From Generation Source	. 6.5%		1	l '
Total Recycling	7.3 %	7.3 %	8.8 %	10.8 %
Final Disposal Landfill Sites	 Vingunguti	Vingunguti	Kunduchi	Kunduchi:
Sanitary Landfill Level	Open Dumping	Level 1 ¹	Level 2 ²	Level 2 Ilala & Temeke: Level 3 ³

9.1.1.3 Future Waste Stream


The main factors that will affect the changes in the waste stream in DSM are:

- · changes in waste generation amount.
- · changes in waste collection system.
- · changes in the recycling system.

The waste stream model below illustrates the flow of waste in DSM and shall also be used as the basis for forecasting future waste flows.

¹ Level 1: controlled tipping method.

Level 2: sanitary landfill without a liner for leachate.
 Level 3: sanitary landfill with a liner for the prevention of leachate percolation into the ground.



A: Waste Generation

The waste generation amount is as forecast in section 4.2.1.

B: Waste Collection for Final Disposal

After discharge, waste may be collected by official and unofficial collectors (mainly independent handcart operators and some private illegal contractors). The former transport the collected waste to the final disposal site while the latter usually illegally dump the waste they have collected.

The planned waste collection ratio in the master plan relates to official collectors only. Hence, the waste collection for final disposal amount will increase according to the planned waste collection ratio in the master plan.

 $B_0 = A_0$ x expected waste collection rate

C: Illegal Dumping by Unauthorised Collectors

The amount of waste illegally dumped after collection refers to the waste illegally dumped by unofficial collectors. This will decrease as the waste collection amount increases and a policy will also be implemented to eliminate this practice. This will result in the rate of illegally dumped waste after collection to the total waste generation amount decreasing from 7.3% in 1996 to 3.0% in 2002 and 0% in 2005.

 $C_n = A_n x$ expected illegal dumping by unauthorised collectors

D: Collection

The waste collection amount is the total amount of waste collected for final disposal including the illegally dumped waste from clandestine operators.

$$D_0 = B_0 + C_0$$

E: Recycling from Discharge

The amount of waste recycled is calculated assuming that the ratio of the recycling amount to the total waste generation amount in 1996 will be maintained until 2005.

$$E_n = A_n \times E_{1996} / A_{1996}$$





F: Discharge

The waste discharge amount is the sum of the waste collected and the amount which is recycled.

$$F_n = D_n + E_n$$

G: Recycling from Generation Sources

The amount of waste generated that is recycled is calculated assuming that the rate of the recycling amount to the total waste generation amount will increase to 8 % in 2002 and to 10 % in 2005 with the promotion of recycling activities.

$$G_n = A_n$$
 x expected recycling rate

H: Self Disposal and Illegal Dumping from Generation Sources

The amount of waste generated and illegally dumped or self disposed is calculated assuming that the ratio of the illegal dumping or self disposal amount to the total amount of illegally dumped and self-disposed waste in 1996 will be maintained until 2005.

$$H_n = (A_n - D_n - E_n) \times H_{1996} / (A_{1996} - D_{1996} - E_{1996})$$

I: Recycling at Final Disposal

The amount of waste recycled at the final disposal site is calculated assuming that the ratio of the recycling amount from final disposal to the total generation amount will be maintained until 2005.

$$I_n = A_n \times I_{1996} / A_{1996}$$

J: Final Disposal

The final disposal amount is the amount of waste which is finally disposed of after being transported to the final disposal sites and is equal to the difference of the waste collection for final disposal amount and the final disposal recycling amount.

$$\mathbf{J_n} = \mathbf{B_n} - \mathbf{J_n}$$

K: Recycling from Illegal Dumping

The amount of illegally dumped waste recycled is calculated assuming that the ratio of the recycling amount from illegal dumping to the total generation amount will be maintained until 2005.

$$K_n = A_n \times K_{1996} / A_{1996}$$

L: Final Illegal Dumping Waste Amount

The final amount of illegally dumped waste is calculated by summing the illegally dumped waste amounts from generation and collection and then subtracting the amount of illegally dumped waste recycled.

$$L_n = (C_n + H_n) \cdot K_n$$

These formulae are used to forecast the waste stream for DSM in 2002 and 2005 as shown in the following figures.




Figure 9-1: Waste Stream for DSM in 2002




Figure 9-2: Waste Stream for DSM in 2005







9.1.1.4 Frameworks of the Master Plan

The Master Plan is formulated based on the following concept.

a. Technical System

- The proposed refuse collection system is categorised into i. Curb side collection by tipper trucks without primary collection and ii. Point collection by skip trucks without primary collection depending on accessibility of the refuse collection vehicles.
- DCC will promote recycling activities (which will not need financial aid by DCC) such as on-site composting at generation but shall not construct/operate any collective intermediate and/or recycling facilities. The construction/operation of those facilities shall be by the private sector if they are any interests.
- For street sweeping system, manual work shall be applied as much as possible.
- Wastes collected from each 3 districts shall be disposed of at its own disposal site by a sanitary landfill operation.

b. Institutional System

- A Waste Management Authority (WMA) shall be newly established under DCC and be responsible for the SWM in DSM city including cesspit emptying service.
- Refuse collection service shall be provided either by the contractors selected through the contract out system or by the WMA of DCC directly.
- A Supervision and Monitoring Committee shall be established in order to monitor and control the cleansing services of DCC and the private contractors.
- The main financial source for the cleansing services shall be a special fund allocated from the city taxes and the RCC (refuse collection charge). As for the RCC a joint billing system with water/sewerage of newly established DAWASA (Dar es Salaam Water and Sewerage Authority) or RCC (Refuse Collection Charge) for commercial waste collection, RCC should be collected when business licenses are applied for or renewed or for special services such as door to door collection services in the high income households shall be applied.

9.1.1.5 Strategy

The strategies to be adopted in the three planning stages are summarised below.

Phase 1 (1997 - 1999): Preparation for Implementing F/S Projects

Technical Aspects

Upon consideration of the very limited refuse collection fleet of DCC at present, for the time being DCC shall provide and expand refuse collection services involving the private sector as much as possible. Refuse collection areas shall be divided into Area for Private Operation: urban area (UA), Area for Either Private or DCC Operation: semi-urban planned developed area (SUPA) and Area for DCC Operation: semi-urban unplanned developed area (SUUA) and rural area (RA). Area (A) shall be serviced by the private contractors and Area

1

- (B) by DCC. The priority of the service expansion is the order of UA, SUPA, SUUA and RA in accordance with the degree of urbanisation.
- A reliable collection service with fixed collection frequencies and schedule shall be established.
- In order to implement the first priority projects (F/S projects), the required funds shall be secured and a detailed design of the projects shall be conducted. Then, facilities shall be constructed and vehicles and equipment procured.
- Site selection work shall be conducted to identify appropriate disposal sites for the Temeke (south) and Ilala (west) Districts.

Institutional Aspects

- Development of clear policies and guidelines for the provision of private refuse collection by contracting out services.
- Establishment of a more autonomous and independent solid waste management organisation (i.e., the Waste Management Authority) which will integrate functions dispersed in the three departments (Health, Works and Planning) and be fully responsible for the provision of solid waste services (including cesspit emptying services) for the city in order to enable independent competency on administration, operation and accounting.
- Allocation of a revolving fund to the Waste Management Authority, under the authority of the head of the organisation, to be used for procurement of fuel, spare parts, and all other supplies and parts which require prompt payment.
- Enhancement of the city's tax collection capability and allocation of a special fund for cleansing services (SWM) from DCC's tax revenues.
- Although the fund shall be a main financial source for cleansing services, a joint billing system for RCC with water/sewerage charges of the newly established DAWASA (Dar es Salaam Water and Sewerage Authority) shall be examined in order to establish a "Beneficiary-Pay-Principle" in the future. If the joint billing is not feasible due to certain impediments, DCC shall collect RCC (Refuse Collection Charge) for commercial waste collection when business licenses are applied for and for special services such as door to door collection services to the high income households.
- Improvement of legislation dealing with solid waste management: formulation of a Sanitary Code.
- Organisation of a human resources development project in order to train the professionals involved with solid waste management
- Establishment of an independent body (the Supervision and Monitoring Committee) to monitor and control the cleansing services of DCC and the private contractors.

Phase 2 (2000 - 2002): Implementation of F/S Projects

Technical Aspects

- Operation of facilities constructed and vehicles and equipment procured in Phase
 1.
- Using the newly procured skip trucks and containers, DCC shall expand its refuse collection service up to 30 % to the SUUA where the collection services coverage target is only 4 % in Phase 1.
- Conduct a feasibility study for the projects (such as construction of disposal sites
 for Temeke and Ilala Districts) proposed in the M/P, other than the first priority
 projects, and to secure funds for implementation. When the funds are secured, the
 detailed designs of the projects are to be carried out.

Institutional Aspects

- Further enhancement of the city's tax collection capability for a financially selfsustainable SWM as well as review of RCC and tipping fee of the disposal site according to the cost incurred to establish a "Beneficiary-Pay-Principle".
- Strengthening of the Supervision and Monitoring Committee for the cleansing services, with emphasis on participation of the private sector.
- Strengthening the management and administration system conceived and implemented in phase 1.

Phase 3 (2003 - 2005): Implementation of M/P Projects

Technical Aspects

- The refuse collection services shall be expanded to 70 % for SUPAs and 50 % for SUUAs respectively.
- The M/P projects, such as construction of disposal sites for Temeke and Ilala Districts, shall be implemented.
- In order to pursue efficiency, the option of whether the operation of the northern Kinondoni District disposal site will be entrusted to the private sector shall be examined.

Institutional Aspects

- Further enhancement of the city's tax collection capability and review of RCC
 and tipping fees of the disposal site according to the cost incurred. With these
 improvements a sustainable SWM in DSM city will be established. In concrete
 terms, DCC will be able to construct facilities and procure equipment required
 for a sound SWM.
- Development of a nation-wide plan for waste minimisation and recycling.

9.1.2 The Municipal SWM Master Plan

a. Outline of the SWM Master Plan

Table 9-3 shows the outline of the Master Plan.

Table 9-3: Outline of the SWM M/P

	dance con district più con trace	Anna de la constanta de la con		THE RESERVE THE PARTY OF THE PARTY.
Phase Components	Present (1996)	Phase I (1997 - 1999)	Phase II (2000 - 2002)	Phase [[] (2003 - 2005)
1. Refuse Collection & Transportation				
Population in DSM	2,261,000	2,859,000	3,736,000	5,066,000
Population in the study area Waste generation amount	2,030,000 1,772	2,455,000 2,144	3,066,000 2,678	3,966,000 3,464
(t/d)	1,772	2,144	2,070	2,404
Collection rate of all waste	8%	17 %	37 %	57 %
Collection rate of	5%	15 %	33 %	52 %
household waste Waste collection amount	143	362	1,001	1.060
(t'd)	143	302	1,001	1,960
Nos, of households served	23,604	85,640	235,298	479,609
Served population	101,500	368,250	1,011,780	2,062,320
Non served population Collection system	1,928,500 Point & curb side	2,086,750 Point & curb side	2,054,220 UA:	1,903,680 UA:
Contention by stein	collection	collection	Curb side collection	Curb side collection
			SUPA:	SUPA:
		1	Curb side collection and Point collection	Curb side collection and Point collection
			SUUA:	SUUA:
			Curb side collection	Curb side collection
			and Point collection	and Point collection RA:
				Point collection
Major type of vehicles	Tipper	Tipper	UA:	UA:
	Skip truck Tractor trailer	Skip truck Tractor trailer	6 ton tipper truck SUPA:	4 ton compactor truck SUPA:
	Tracion charter	1136104 (131)61	6 ton tipper truck and	6 ton tipper truck and
			8 ton skip trucks	8 ton skip trucks
	1		SUUA: 6 tons tipper truck	SUUA:
			and 8 tons skip trucks	6 ton tipper truck and 8 ton skip trucks
			,	RA:
Transportation system	Direct haulage	Direct haulage	Direct haulage	8 ton skip trucks Direct haulage
Executing organisations	Directinuage	Direct naurage	Direct nadiage	Direct (13thage
DCC	Cleansing unit,	Cleansing unit,	WMA	WMA
Private contractors	Health dept 5 concessionaires	Health dept NA	NA .	NA
Required main equipment	5 concessionaires	1474	11/1	NA.
6 ton tipper trucks	14	NA	50	66
8 ton skip trucks 4 ton compactor truck		NA NA	67	95 10
8 m ³ skip with lids	ő	NA NA	134	190
8 m³ open skip	8	NA	536	760
No. of workers DCC	40 (Aug.1996)	NA.	317 152	455 132
Contractors	127 (Aug.1996)	NA NA	165	323
Unit cost	1			
DCC (USD, ton)	24.85 (1994)	NA	21.44 (excluding tipping	17.33 (excluding tipping
			(ce)	fee)
Private contractors	13.14 (1994)	NA	-	·
(USD, ton)	(including dumping fee)			
2. Street Sweeping				
Method of sweeping	Manual	Manual	Manual	Manual
Length of sealed regional	60.7	60.7	100	100
road in DSM (km) Length of served road	32.8	50	190	100
(km)				
Operator Nos. of u celears	Contractors	Contractors	Contractors	Contractors
Nos. of workers Private contractor	72	110	220	220
DCC	3	5	5	5
Contractors	69	105	215	215
Unit cost DCC (USD,'ton)	Not available		This cost is included	This cost is included
, ,			in the collection cost.	in the collection cost.
Contractor (USD, ton)	Not available	Manual	Manualment	
Main equipment	Manual	Manual	Manual work with	Manual work with





Phase	Present	Phase 1	Phase II	Phase III
Components	(1996)	(1997 - 1999)	(2000 - 2002) litter boxes	(2003 - 2005) litter boxes
3. Intermediate treatment	Community based pilot composting facilities	No requirement other than on-site & community based	On-site composting	On-site composting
I D P	•Simple incinerator for infectious waste	ones		<u> </u>
4. Recycling Recycling rate from generation	. 6.5 %	6.5 %	8.0 %	10.0 %
Överall recycling rate Recycling system	7.3 % No organised recycling	• DCC needs to organised present recycling system	Private sector centred system DCC encourage to organise recycling activities	Private sector centred system DCC promotes the separate discharge of wastes for recycling
S. Final Disposal Method of operation Final disposal site	Open dumping Vingunguti	Level I Vingunguli	Level 2 Kunduchi	Level 2 or 3 Level 2 for Kunduchi Level 3 for Ilala & Temeke
Transportation distance (km)	8.7	8.7	18	13 (average)
Operation by Nos, of workers Tipping fee (Tsh/ton)	DCC 11 800	DCC - 11 800	WMA 34 3,600	WMA 85 6,100
Tipping fee (Tsh/ton) Unit cost (USD/ton) Main equipment	N.A Bulldozer I	N.A Bulidozer I	5.37 Bulldozer: 3 Excavator: 1 Tipper truck: 3	9,22 Bulidozer: 6 Excavator: 3 Tipper truck: 6
6. Maintenance & Repair Preventive Maintenance	Mwananyamala	Mwananyamala	Pickup: 1 Nyerere workshop	Pickup: 3 Nyerere workshop
Major repair	depot Mwananyamala	depot Mwananyamala	Private workshop	Private workshop
Operation by	depot E & M sec, Works	depot E & M sec, Works	WMA	WMA
Nos. of workers	Dept., DCC	Dept., DCC	65	98
7. Public Organisations Responsible on SWM Competent authorities Operation by Nos. of staff	Health Dept., DCC Cleansing Sec.	Health Dept., DCC Cleansing Sec. 10	WMA WMA	WMA WMA 50
8. Financial Matters Unit SWM Cost (Tsh'ion) Revenue Source	Tax RCC collected by concessionaires	Tax RCC cellected by concessionaires	Tax RCC collected by joint billing with water or Special RCC collected by DCC	Tax RCC collected by joint billing with water or Special RCC collected by DCC
Breakdown of Revenue Tax (M. Tsh) RCC (M. Tsh) Total Revenue	296 not available not available	548	1,165 1,426 2,591	1,868 2,684 4,552
(M. Tsh) Total revenue per capita	not available	223	845	1,148
(Tsh) Total revenue per beneficiary (Tsh)	not available	1,488	2,561	2,207
SWM budget per capita (Tsh) DCC Budget (M. Tsh.)	160 5,910	223 10,963	350 23,291	471 37,368
Tax Revenue (M. Tsh) Subsidy (M. Tsh) Tax Forecast Scenario	2,540 3,370 not available	7,062 3,901 Moderate	18,775 4,516 Moderate	32,140 5,228 Moderate
Share of SWM budget Collection Rate of RCC Tariff Level for RCC (Tsh/month/household)	5 % 15 % 150 or 900	5 % 15 % 150 or 900	5 % 20 % 1,250	5 % 20 % 1,250
9. Role of Private Org. SWM services privatised	Parts of refuse collection Street sweeping	Parts of refuse collection Street sweeping	Parts of refuse collection Street sweeping	Parts of refuse collection Street sweeping
Type of contract 10. Legislation	Concession contract There are basic legislation but lack of enforcement	Concession contract Consolidation of scattered legislation on SWM into a Sanitary Code	Enforcement of the Sanitary Code	Lump sum contract Establishment of a law for waste minimisation and recycling
11. Public Cooperation	There are very little public education	Informing of proposed	Conduct of active public education and	Promotion of waste minimisation and

Phase Components	Present (1996)	Phase I (1997 - 1999)	Phase II (2000 - 2002)	Phase III (2003 - 2005)
	programmes and co- operation	institutional, administrative and legislative changes on SWM	cooperation campaigns	recycling campaigns
12. Medical SWM	• No clear classification of medical solid waste, • No discharger's responsibility, Lack of laws, codes & enforcement	Establishment of clear classification for medical SW and code of practice, Infectious wastes shall be properly treated at generation	Enforcement of strict segregation, separate collection, transportation and disposal system for infectious waste, Examination of thermal treatment of infectious waste with hazardous industrial SW	Establishment of thermal treatment of infectious waste with hazardous waste
13. Industrial SWM	No clear classification of industrial solid waste No discharger's responsibility, Lack of laws, codes & enforcement	Establishment of clear classification of industrial SW Examination of HISW generation amount and its disposal methods	Enforcement of proper disposal of hazardous industrial SW Examination of thermal treatment of infectious waste with hazardous industrial SW	Establishment of thermal treatment of infectious waste with hazardous waste



8

b. Location of SWM Facilities




Figure 9-3: Location Map of SWM Facilities





Figure 9-4: Master Plan of Waste Collection

Figure 9-5: Master Plan of The Waste Stream



Waste Stream in DSM in 1996









Figure 193 Marko Plance Wester Collection:


Expute 9.5 Master Plan of The Waste Sheam

	1.	Section 1	Intal Generation of the control of t	(i) 1.777 (ii) 1.777 (iii) 1.7
	And the second of the second o			11 - 1 12 - 1
٠.			to the state of th	
		·		


Waste Stream in DSM in 1996



Waste Stream in DSM in 2002



Waste Stream in DSM in 2005



9.2 Conceptual Design and Cost Estimation

This section estimates all costs required to implement the master plan. They are divided into the following items for cost estimation.

A. Direct Cost

- 1) Storage and discharge system
- 2) Primary collection system
- 3) Secondary collection and transportation system
- 4) Final disposal system
- 5) Street sweeping system

B. Indirect Cost

- 1) Maintenance shop
- 2) Motor pool
- 3) Administrative expenses of DCC

9.2.1 Design Conditions

a. The Period and Projects in the SWM Master Plan to be examined

The period and projects in the SWM Master Plan to be examined here are all projects which are planned to be implemented or operated from the year 2000 until 2005.

b. Key Design Data

• ASG of waste when it is transported by refuse vehicles without compaction:

 $390 \, \text{kg/m}^3$

ASG of waste when it is transported by refuse vehicles following compaction:

585 kg/m³

ASG of waste when it is compacted at a disposal site: 900 kg/m³

Average waste transportation distance:
 Operation efficiency of refuse vehicles:
 0.8

• Operation efficiency of refuse vehicles: 0.8

• Operation time of waste collection time: 7.5 hours/day 6 days/week

c. Economic Life

Skips: 7 years
Tipper trucks, skip trucks and heavy equipment: 7 years
Machinery: 15 years
Buildings and Civil works: 30 years

d. Remaining Economic Life of Existing Equipment

The economic life of most existing equipment which is being operated by DCC have expired. It is therefore assumed that the existing equipment would be operational until 2000.

e. Waste Collection Amount

Table 9-4 shows the waste collection amount per day based on 7 day collection per week.

Table 9-4: Waste Generation and Collection Amount per Day Based on 7
Collection Days per Week

Category of Waste	Description	unit	2000	2001	2002	2003	2004	2005
Household	Generation	t/d	1,838	1,979	2,140	2,323	2,530	2,769
	Collection	l t/d ∣	380	535	705	1,013	1,211	1,439
	Collection Rate	%	20.7%	27.0%	33.0%	43.6%	47.9%	52.0%
Commercial	Generation	t/d	69	83	98	115	134]	155
	Collection	Vd	49	66	88	115	134	1 5 5
	Collection Rate	%	70.0%	80.0%	90.0%	100.0%	100.0%	100.0%
Institution	Generation	t/d	13	14	15	17	. 18	20
	Collection	t/d	9	11	14	17	18	20
	Collection Rate	%	70.0%	80.0%	90.0%	100.0%	100.0%	100.0%
Market	Generation	t/d	78	92	108	125	145	168
	Collection	t/d	55	74	97	125	. 145	168
	Collection Rate	%	70.0%	80.0%	90.0%	100.0%	100.0%	100.0%
Street Sweeping	Generation	t/d	3	3	3	3	4	4
, -	Collection	t/d	3	3	3	3	4	4
	Collection Rate	%	100%	100%	100%	100%	100%	100%
Informal	Generation	t/d	299	305	314	324	335	348
	Collection	t/d ·	50	68	94	119	142	174
	Collection Rate	%	16.7%	22.3%	30.0%	36.7%	42.3%	50.0%
Total	Generation	t/d .	2,300	2,476	2,678	2,906	3,165	3,464
	Collection	t/d	545	757	1,001	1,392	1,653	1,960
	Collection Rate	%	23.7%	30.6%	37.4%	47.9%	52.2%	56.6%

f. SWM Costs Included in the Cost Estimation

All costs required to implement the SWM master plan are included in the cost estimation regardless of the type such as direct operation by DCC or contractors of DCC.

9.2.2 Storage and Discharge System

The SWM Master Plan proposed to use plastic sacks for tipper truck collection and skips for public use.

No cost is involved in storage and discharge of plastic sacks because plastic bags provided by shops to carry the shopping are proposed to be used.

Skips are used as communal containers. The number of containers required and the cost are estimated in section 9.2.4 (secondary collection and transportation). The required number of skip container is assumed to be 10 skip per truck.

9.2.3 Primary Collection System

The SWM Master Plan does not place an importance on the primary collection system because it can not be within the main stream in SWM. To improve the secondary collection and transportation system is far more important than the primary collection system in DSM where the present refuse collection rate is only 8.1 %.

To improvement of the the primary collection system is not taken into account in the SWM project costs which will be implemented by DCC. Its improvement should be conducted with financial resources from non-governmental organisations until 2005.







9.2.4 Secondary Collection and Transportation System

a. Conceptual Design of Secondary Collection and Transportation System

a.1 Required Transportation Distance to Landfill Sites

The transportation distances for wastes to the proposed landfill sites are determined or assumed as shown in Table 9-5 based on Figure 9-3.

Table 9-5: Summary of Transportation Distance to Landfill Sites

District	Area	2000-2	2002	2003-2005			
	Landfill Site		Distance	Landfill Site	Distance		
Kinondoni	SUPA	Kunduchi Landfill		Kunduchi Landfill	15 km		
	SUUA Kunduchi Landfill		1	Kunduchi Landfill	15 km		
	RA	Kunduchi Landfill	Average	Kunduchi Landfill	10 km		
Ilala	UA	Kunduchi Landfill	distance to	Ilala Landfill	13 km		
	SUPA	Kunduchi Landfill	Kunduchi	Ilala Landfill	10 km		
	SUUA	Kunduchi Landfill	Landfill Site is	Itala Landfill	10 km		
	RA	Kunduchi Landfill	18 km	Ilala Landfill	10 km		
Temeke	SUPA	Kunduchi Landfill	1	Temeke Landfill	10 km		
	SUUA	Kunduchi Landfill	1	Temeke Landfill	10 km		
	RA	Kunduchi Landfill	1	Temeke Landfill	10 km		

a.2 The Type of Refuse Collection Truck

The following three types of refuse collection trucks were determined to be appropriate for the use.

- 6 tonne tipper trucks for UA, SUPA, SUUA and RA
- 8 tonne skip container trucks for SUPA and SUUA
- 4 tonne compactor trucks for UA

Their proposed assignments are as follows.

Table 9-6: Assigment Plan of Refuse Collection Truck

Area		2000-2002		2003-
UA	100%:	6 ton tipper trucks	80-100 %: 20-0%:	4 ton compactor trucks 6 ton tipper trucks
SUPA	35-25%: 65-75%:	6 ton tipper trucks 8 ton skip container trucks	25%: 75%:	6 ton tipper trucks 8 ton skip container trucks
SUUA	10%: 90%:	6 ton tipper trucks 8 ton skip container trucks	10%: 90%:	6 ton tipper trucks 8 ton skip container trucks
RA		•	100%:	8 ton skip container trucks

a.3 Productivity Determination of Refuse Collection Vehicles

The productivities of the collection vehicles were calculated using the following equation.

$$Tr = \frac{60 \times t1 - t2 \times E}{D \div V + t3 + t4}$$

- Tr: Number of trips per day (trips)
- D: Travel distance per trip (km)
- V: Velocity of the vehicle (km/h)
- t1: Working hours per day (hours)
- t2: Time taken for daily service e.g. inspection and fuelling, etc. (min)
- t3: Time taken for loading waste (min)
- t4: Time taken for unloading waste (min)
- E: Work efficiency

$Qd = q \times d \times f \times Tr$

- q: Volume of a skip container or a tipping truck (m³)
- d: Density of waste when it is being transported (ton/m³)
- f: Work efficiency

Table 9-7: Productivity Determination

Description	unit Skip truck				Ti	ipper tru	ick	Compactor
Capacity in weight		8	8	8	6	6	6	4
Capacity in volume	m3	8	8	8	10	10	10	
Distance of one trip	km	36	30	20	17	36	30	26
Velocity of vehicle	km/n	40	40	40	40	40	40	40
Density of waste when transported	t/m3	0.39	0.39	0.39	0.39	0.39	0.39	0.585
tt:Working hour	h	7.5	7.5	7.5	7.5	7.5	7.5	7.5
t2:Daily service time	min	30	30	30	30	30	30	30
t3:Loading time per trip	min	5	5	5	110	110	110	64
t4:Unloading time	min	5	5	5	10	10	10	10
E: Working efficiency of transport		0.8	0.8	0.8	0.8	0.8	0.8	0.8
f: Work efficiency of transportation		0.8	0.8	0.8	0.8	0.8	0.8	0.8
Number of trips per day	times	5.25	6.11	8.40	2.30	1.93	2.04	2.97
Waste carried per day	t/d	13.10	15.25	20.97	7.18	6.02	6.35	11.13

b. Cost Estimation

b.1 Investment

b.1.1 Required Number of Equipment

Table 9-8 shows the required number of equipment which were calculated by their productivities and their distances per trip.

Table 9-8: Required Number of Equipment

Items	Unit	2000	2001	2002	2003	2004	2005
6 t tipper trucks	units	40	45	50	50	54	66
8 t tipper trucks	units	31	47	67	67	81	95
4 t compactor	units	0	0	0	7	9	10
8 m ³ container with lid	nos	0	94	134	134	162	190
8 m ³ container without lid	nos	0	376	536	536	648	760



1




Figure 9-7: Required Number of Trucks for Refuse Collection




Figure 9-8: Proposed Waste Collection Amount by The Type of Vehicles

b.1.2 Investment Schedule

Table 9-9 shows the procurement schedule which has taken their economic life into account.

Table 9-9: Procurement Schedule

ltems	unit	1999	2000	2001	2002	2003	2004	2005
6t tipper truck	units	40	5	5	0	4	12	3
8t skip truck	units	31	16	20	0	14	14	5
8 m ³ container with a lid	units	62	32	40	0	28	28	10
8 m ³ container without a lid	units	248	128	160	0	112	112	40
4 t compactor	units	0	0	0	7	2	1	0

Table 9-10 shows the investment schedule to procure equipment in accordance with the schedule.




Figure 9-7: Required Number of Trucks for Refuse Collection




Figure 9-8: Proposed Waste Collection Amount by The Type of Vehicles

b.1.2 Investment Schedule

Table 9-9 shows the procurement schedule which has taken their economic life into account.

Table 9-9: Procurement Schedule

Items	unit	1999	2000	2001	2002	2003	2004	2005
6t tipper truck	units	40	5	5	0	4	12	3
8t skip truck	units	31	16	20	0	14	14	5
8 m ³ container with a lid	units	62	32	40	0	28	28	10
8 m ³ container without a lid	units	248	128	160	0	112	112	40
4 t compactor	units	0	O	0	7	2	1	0

Table 9-10 shows the investment schedule to procure equipment in accordance with the schedule.

Table 9-10: Investment Schedule

Items	unit	unit	1999	2000	2001	2002	2003	2004	2005
		rate							l
6t tipper truck	th. USD	53.1	2,122	265	265	0	212	637	159
8t skip truck	th. USD	74.7	2,314	1,194	1,493	. 0	1,045	1,045	373
8 m3 container with lid	th. USD	. 6.0	369	190	238	0	167	167	60
8 m3 container without lid	th. USD	5.2	1,290	666	832	0	582	582	208
4 t compactor	th. USD	71.2	0	0	0	498	142	71	0
total in USD	th. USD		6,095	2,316	2,828	498	2,149	2,502	800
total in Tsh	M.Tsh	597.8	3,644	1,384	1,691	298	1,284	1,496	478

b.2 Operation Costs

The required manpower and materials for collection and transportation are shown in Table 9-11 and the required costs are summarised in Table 9-12.

Table 9-11: Required Quantities for Operation

Category	Description	unit	2000	2001	2002	2003	2004	2005
Labour	8t skip	persons	31	47	67	67	81	95
Driver	6t tipper	persons	40	45	50	50	54	66
	4t compactor	persons	0	0	0	7	9	10
	totai	persons	71	92	117	124	144	171
Labour	8t skip	persons	0	0	0	0	0	0
Collection worker	6t tipper	persons	200	225	250	250	270	330
	4t compactor	persons	0	0	0	21	27	30
	total	persons	200	225	250	271	297	360
Required Diesel	6t tipper	ľ/d	960	1,080	1,200	1,200	1,296	1,584
	8t skip	l/d	1,519	2,303	3,283	3,283	3,969	4,655
	4 t compactor	Ud .	0	0	0	210	270	300
	total		2,479	3,383	4,483	4,693	5,535	6,539

Table 9-12: Required Operation Cost Schedule

Item	unit	2000	2001	2002	2003	2004	2005
Labour, driver	M.Tsh/y	51	66	84	89	104	123
Labour, collection worker	M Tsh/y	96	108	120	- 130	143	173
Diesel	M Tsh/y	213	291	386	404	476	563
Lubricant	M.Tsh/y	21	- 29	39	40	48	56
Total	M.Tsh/y	382	494	629	664	770	915

b.3 Maintenance Costs

The maintenance cost includes prices of spare parts and costs incurred when repair works are commissioned to outside garages. The costs of preventive maintenance which will be provided by the central workshop are included as indirect expenses of the maintenance shop.

The maintenance costs for vehicles is estimated as 10 % of basic prices and for skip containers it is regarded as 3 % of basic prices. The estimated maintenance costs are summarised in Table 9-13.



Table 9-13: Required Maintenance Costs Schedule

									المقاندة ويوري ويوري
Item 1	Item 2	Item 3	unit	2000	2001	2002	2003	2004	2005
Vehicles	Basic Price	6t tipper	th. USD	2,432	2,736	3,040	3,040	3,283	4,013
		8t skip	th. USD	2,651	4,019	5,729	5,729	6,926	8,123
-		4 t compactor	th. USD	0]	0	0	566	728	809
	İ	Total	th. USO	5,083	6,755	8,769	9,335	10,937	12,944
	Repair Cost	10 % of Basic Price	th. USD	508	675	877	933	1,094	1,294
Skip	Basic Price	8 m3 with lid	th. USD	391	592	844	844	1,021	1,197
Container		8 m3 without fid	th. USD	1,438	2,181	3,109	3,109	3,758	4,408
•	*	Total	th. USD	1,829	2,773	3,953	3,953	4,779	5,605
	Repair Cost	3 % of Basic Price	th. USD	55	83	119	119	143	168
Total Repa	ir Cost in USD		th. USD	563	759	995	1,052	1,237	1,463
Total Repa	ir Cost in Tsh		M.Tsh/y	337	454	595	629	740	874

b.4 Summary of Cost Estimation

Table 9-14 shows the summary of required costs for secondary collection and transportation.

Table 9-14: Estimated Costs of Secondary Collection and Transportation

Description	unit	1999	2000	2001	2002	2003	2004	2005
1. Investment								
Equipment	M.Tsh	3,644	1,384	1,691	298	1,284	1,496	478
2. Operation								
Labour Cost	M.Tsh	0	147	174	204	219	246	296
Material and Fuel, etc.	M.Tsh	0	235	320	424	444	524	619
3. Maintenance	M.Tsh	0	337	454	595	629	740	874
Total	M.Tsh	3,644	2,103	2,639	1,521	2,577	3,005	2,267

9.2.5 Final Disposal System

a. Conceptual Design of Final Disposal System in the Master Plan

a.1 Final Disposal Programme

The remaining capacity of the existing Vingunguti disposal site is only for another 1 to 2 years as of July 1996 and it is causing serious environmental problems in its environs. Proper sanitary landfills are therefore, urgently required.

The final disposal system proposed in the Master Plan is summarised as follows.

Sites	Description	Before 2000	2000-2002	2003-2005
Vingunguti	Level: 1	Operation Receive all waste collected	• Closed	• Closed
Kunduchi	Level: 2 Capacity: 3.5 million m ³ Life year: 2000-2010	Construction	Operation Receive all wastes collected	Operation Receive waste collected in Kinondoni
llala	Level: 3 Capacity: 1.5 million m ³ Life year: 2003-2009	• Site selection	Construction	Operation Receive waste collected in Ilala
Temeke	Level: 4 Capacity: 1.5 miltion m ³ Life year: 2003-2010	• Site selection	Construction	Operation Receive waste collected in Temeke

- Until the end of 1999, the existing Vingunguti disposal site will be in use.
- At the beginning of the year 2000, the new disposal site to be constructed in Kunduchi New MECCO quarry will commence its operation. It will receive all wastes collected from DSM from 2000 until 2002.
- At the beginning of 2003, two disposal sites for Itala and Temeke districts will
 commence its operation and each site of the three will receive all wastes collected
 from its district.
- The proposed sanitary level of disposal sites are Level 2 for the Kunduchi landfill and Level 3 for the landfills to be constructed in Ilala and Temeke.
- The ratio of coverage soil volume to the waste volume will be 18 %.

a.2 Required Capacity of Disposal Sites

Based on the forecast for waste disposal amount, the volume of waste to be dumped at each disposal site was estimated as follows.

Table 9-15: Annual Estimate of Waste Amount at Disposal Sites (1)

		Collection	Amount	CONTRACTOR OF THE PARTY.	Waste Disposal Amount						
Site	Kunduchi	lla!a	Temeke	Total	Vingunguti	Kunduchi	Ilala	Temeke	Total		
υnit	t/y	t/y	Vy	t/y	t/y	t∕y	t/y	t/y	t/y		
1996	24,042	12,784	14,640	51,465	51,465	0	0	: 0	51,465		
1997	34,900	19,101	21,189	75,190	75,190] 0]	0	0	75,190		
1998	46,682	26,555	28,599	101,835	101,835	ol	0	0	101,835		
1999	59,629	35,495	37,006	132,130	132,130	[0]	0	0]	132,130		
2000	88,121	55,233	55,571	198,925	0	198,925	. 0	0]	198,925		
2001	119,756	79,559	76,990	276,305	0	276,305	0	0]	276,305		
2002	154,401	109,459	101,531	365,390	0	365,390	0	0	365,390		
2003	208,244	158,983	140,854	508,080	0	208,244	158,983	140,854	508,0 80		
2004	238,329	198,025	166,992	603,345	0	238,329	198,025	166,992	603,345		
2005	271,321	246,627	197,573	715,520	0	271,321	246,627	197,573	715,520		
2006	285,330	252,201	216,628	754,158	. 0	285,330	252,201	216,628	754,158		

Table 9-16: Annual Estimate of Waste Volume at Disposal Sites (2)

-		Collection	1 Amount	And the Control of Street, or working or party or work of	Waste Disposal Amount						
Site	Kunduchi	Ilala	Temeke	Total	Vingunguti	Kunduchi	llala	Temeke	Total		
unit	m3/y	m3/y	m3/y	m3/y	m3/y	m3/y	m3/y	m3/y	m3/y		
1996	26,713	14,204	16,266	57,183	57,183	O	0	0	57,183		
1997	38,778	21,223	23,543	- 83,544	83,544	0	. 0	0	83,544		
1998	51,868	29,505	31,776	113,150	113,150	0	0	0	113,150		
1999	66,255	39,438	41,118	146,811	146,811	- 0	0	0	146,811		
2000	97,912	61,370	61,746	221,028	0	221,028	. 0	0	221,028		
2001	133,063	88,399	85,544	307,006	0	307,006	0	0	307,006		
2002	171,556	121,621	112,812	405,989	0	405,989	0	. 0	405,989		
2003	231,382	176,647	156,501	564,533	0	231,382	176,647	156,504	564,533		
2004	264,810	220,027	185,546	670,383	0	264,810	220,027	185,546	670,383		
2005	301,467	274,029	219,525	795,022	0	301,467	274,029	219,525	795,022		
2006	317,033	280,223	240,698	837,954	0	317,033	280,223	240,693	837,954		







Table 9-17: Estimate of Waste Accumulated at Disposal Sites

Site	Vingunguti	Kunduchi	Ilala	Temeke
unit	m3/y	m3/y	m3/y	m3/y
1996	57,183	o	0	0
1997	140,728	ol	0	C
1998	253,878	ol	ol	0
1939	400,689	ol	0	0
2000	400,689	221,028	0	0
2001	400,689	528,033	ol	0
2002	400,689	934,022	ol	0
2003	400,689	1,165,404	176,647	156,504
2004	400,689	1,430,214	396,675	342,051
2005	400,689	1,731,681	670,704	561,576
2006	400,689	2,048,714	950,927	8)2,273

Table 9-18: Required Landfill Volume including Soil for Coverage

Site	Vingunguti	Kunduchi	ilala	Temeke
unit	m3/y	m3/y	m3/y	m3/y
1996	67,476	0	0	0
1997	166,059	0	0	0
1998	299,576	0]	oj.	0
1999	472,813	0	o	0
2000	472,813	260,813	0	0
2001	472,813	623,079	0	0
2002	472,813	1,102,146	O	0
2003	472,813	1,375,177	208,444	184,675
2004	472,813	1,687,652	468,076	403,620
2005	472,813	2,043,384	791,431	662,659
2006	472,813	2,417,483	1,122,094	946,683

The appropriate capacities of proposed disposal sites were therefore set up as shown in Table 9-19.

Table 9-19: Proposed Capacities of Disposal Sites

Site	Capacity (million m ³)	Reserve for Waste (million m ³)	Volume for Coverage Soil (million m³)	Life years (years)	Operation Period
Kunduchi	3.5	2.87	0.63	11	2000 - 2010
Ilala	1.5	1.23	0.27	7	2003 - 2009
Temeke	1.5	1.23	0.27	8	2003 - 2010

c. Investment

c.1 Landfill

The cost for operating the Kunduchi landfill adopted here is based on the cost estimated in the Main Report for the Feasibility Study.

The cost for the Ilala and Temeke landfill sites adopted here are based on the costs estimated as presented in Annex 16. The unit construction cost of the landfill site is 1,170 Tsh per cubic metre of landfill.

Table 9-20: Summary of Investment O & M Costs

unit: M.Tsh

**************************************							Trist tal toti
Site	1999	2000	2001	2002	2003	2004	2005
Kunduchi Landfill	831	0	. 0	430	0	580	0
llala	0	Ô	0	1,755	0	0	0
Temeke	0	0	0	1,755	0	0	0

c.2 Equipment

c.2.1 Determination of Productivity

The operating capacity of a bulldozer and tipper truck are calculated below.

Bulldozer, 210 Hp class

Bulldozers are used for pushing, spreading, levelling and compacting wastes at disposal sites. Its productivity is estimated below.

Probable cycle time (Cm)

Output

$$Qh = \frac{60 \times q \times f \times E}{Cm}$$

Qh: Output per hour (m³/h)
q: Output per push (m³/h)
f: Conversion factor of waste 1.0
E: Operation efficiency 0.5

Hence, Qh is 133.6 m³/h.

Qd =
$$133.6 \text{ m}^3/\text{h} \times 7 \text{ h/d} = 935 \text{ m}^3/\text{d}$$

= $935 \text{ m}^3/\text{d} \times 0.39 \text{ t/m}^3 = 365 \text{ t/d}$

Tipper truck, 8 tons

The main task of tipper trucks at disposal sites is to carry soil from outside to cover the waste. Its productivity is estimated below.







Probable cycle time (Cmt)

Carrying: 1 km @ 15 km/60 min = 4.0 min

Return trip: 1 km @ 20 km/60 min = 3.0 min

Loading: = 5.0 min

Dumping: = 1.0 min

= 13.0 min

Output -

$$Qh = \frac{60 \times C \times f \times Et}{Cmt}$$

Qh: Output per hour	(m³/h)
C: Output per trip	(m^3/h)
f: Conversion factor of waste	1.0
E: Operation efficiency	0.5

Hence, Qh is 40 tons per hour.

$$Qd = 40 t/h \times 7 h/d = 280 t/d$$

c.2.2 Required Number of Equipment

Based on the estimated productivity of the equipment, their required number were estimated as shown in Table 9-21.

Table 9-21: Required Number of Landfill Equipment

Disposal Site	Equipment	1999	2000	2001	2002	2003	2004	2005
Vingunguti	Bulldozer	2	0	0	0	0	0	0
Kinondoni	Bulldozer	0	2	2	3	2	2	2
	Tipper truck	0	3	3	3	2	2	2
	Excavator	0	1	1	1	1	1	1
	Pckup	0	1	1	1	1	1	1
ilala	Bulldozer	0	0	0	0	1	2	2
	Tipper truck	0	0	0	0	2	2	2
	Excavator	0	0	0	0	1	1	1
	Pckup	0	0	0	0	1	1	1
Temeke	Bulldozer	0	0	0	0	1	1	2
	Tipper truck	0	0	0	0	2	2	2
	Excavator	0	0	0	0	1	1	1
-	Pckup	0	0	0	0	. 1	1	1
Total	Bulldozer	2	2	2	3	4	5	- 6
	Tipper truck	0	3	3	3	6	6	6
	Excavator	0	1	1	1	3	3	3
	Pckup	0	1	1	1	3	3	3

c.2.3 Investment Schedule of Equipment

Table 9-22 shows the procurement schedule which has taken their economic life into account.

Table 9-22: Procurement Schedule of Landfill Equipment

Equipment	1999	2000	2001	2002	2003	2004	2005
Bulldozer	2	0	1	1	1	1	0
Tipper truck	3	0	0	3	0	0	0
Excavator	1	0	0	2	0	0	0
Pckup	1	0	0	2	0	0	0

Table 9-23 shows the investment schedule to procure equipment based on the above.

Table 9-23: Investment Schedule for Landfill Equipment

Site	1999	2000	2001	2002	2003	2004	2005
Kunduchi	600	0	150	0	0	0	0
ilala	0	0	0	196	150	0	0
Temeke	0	0	0	398	0	150	0

c.2.4 Iterim Investment

Sanitary landfill operation requires some construction works intermittently, for example extension of gas removal, leachate collection, provision of impermeable clay layer for slopes, etc. These costs are regarded as a part of operation costs since its characteristics are similar.

d. Operation and Maintenance Cost

The maintenance cost include spare parts prices and cost incurred from commissioning repairs to outside garages. The costs of preventive maintenance which will be provided by the central workshop are included as indirect costs of the maintenance shop.

The maintenance costs for vehicles are estimated as 10 % of basic prices.

Table 9-24 summarises the costs required related to the final disposal plan.

Table 9-24: O & M Schedule for Final Disposal

unit: M.Tsh

Site	Items	2000	2001	2002	2003	2004	2005
Kunduchi	Labour cost	20	20	21	19	19	19
	Material and fuel	64	70	92	62	64	67
	Spare parts & repair	60	60	75	54	54	54
Ilala	Labour cost	0	0	0	16	17	17
	Material and fuel	0	0	0	44	61	65
	Spare parts & repair	0	0	0	- 40	54	54
Temeke	Labour cost	0	0	0	16	16	17
	Material and fuel	0	0	0	42	45	61
	Spare parts & repair	0	0	0	40	40	54

e. Summary of Cost Estimation

Table 9-25 shows the summary of the costs required for final disposal.







Site	Items	1999	2000	2001	2002	2003	2004	2005
Kunduchi	Investment for facilities	831			430		580	
	Investment for equipment	600	o	150	0	0	. 0	0
	Operation for labours	0	20	20	21	19	19	19
	Operation for material and fuel	0	64	70	92	62	64	67
	Spare parts and repares	0	60	60	75	54	54	54
Ilala	Investment for facilities				1,755			
	Investment for equipment				196	150	0	0)
	Operation for labours				0	16	17	17
	Operation for material and fuel				0	44	61	65
	Spare parts and repares				0	40	54	54
Temeke	Investment for facilities	Ī			1,755	0	0	0
	Investment for equipment		1		398	0	150	0
	Operation for labours					16	16	17
	Operation for material and fuel	· '				42	45	61
	Spare parts and repares					40	40	54
Total		1,431	144	300	4,722	484	1,102	411

9.2.6 Street Sweeping System

- a. Description of Street Sweeping Plan
- The SWM Master Plan concerns only collecting litter from streets, excluding sand and grass cuttings which are currently being conducted by the Works Department in DCC and the Ministry of Works.
- Only asphalt paved streets are planned to be swept.
- The planned length to be swept is as follows:

Year	2000	2001	2002	2003	2004	2005
Length to be swept	67 km	83 km	100 km	100 km	100 km	100 km

• The frequency of street sweeping are set up below.

The method of street sweeping is manual sweeping. The required resources are:

Machinery	trucks
Labour	drivers
•	road sweepers
Material	broom
	handcart
	waste basket
	traffic safety devices
Fuel	petrol or diesel

b. Investment

Table 9-26 shows the required equipment and manpower for future street sweeping work.

Table 9-26: Required Equipment and Manpower

Items ·	unit	1999	2000	2001	2002	2003	2004	2005
4t truck	units	3	4	5	6	6	6	6
Driver	persons	3	4	5	6	6	6	6
No. of worker	persons	110	1 147	183	220	220	220	220

Table 9-27 shows the schedule of Procurement and Investment.

Table 9-27: Procurement and Investment Schedule

Item		1999	2000	2001	2002	2003	2004	2005
Procured	4t truck	1	1	1	0	0	0	. 0
Investment	M. Tsh	23	23	23	0	0	0	0

c. Operation Cost

Table 9-28 shows the operation cost schedule until 2005.

Table 9-28: Operation Cost Schedule

Calegory	Description	unit	2000	2001	2002	2003	2004	2005
Labour	Driver	M.Tsh	3	4	4	4	4	4
	Worker	M.Tsh	71	88	106	106	106	106
Fuel	Diesel, Petrol, Lubricant	M.Tsh	5	6	8	8	8	8
	Broom, handcart, safety devices etc.			25	30	30	30	30
Total		M.Tsh	99	123	148	148	148	148

d. Maintenance Cost

Maintenance costs include spare parts prices and cost incurred from commissioning repair works to outside garages. The costs of preventive maintenance which will be provided by the central workshop are included as indirect costs of the maintenance shop.

The maintenance costs for vehicles are estimated as 10 % of basic prices. The estimated maintenance costs are summarised in Table 9-29.

Table 9-29: Maintenance Cost Schedule

ſ	Item	unit	1999	2000	2001	2002	2003	2004	2005
	Repair	M.Tsh	-	9	12	14	14	14	14

9.2.7 Maintenance Shop

The Nyerere depot which is presently closed is planned to be used as a central workshop for SWM equipment. This workshop is planned provide preventive measures. Major repair works are planned to be done at private garages.

a. Investment

All improvement works of the Nyerere Workshop in the Master Plan are to be implemented in 1999.

a.1 Facilities

Total investment for facilities is 42 million Tsh as shown below.

	THE PARTY AND TH
Water Tank	5 M.Ths
Pavement	15 M.Ths
Drainage	. 10 M.Ths
Car cleaning pit	5 M.Ths
Sub-station	5 M.Ths
Furniture	3 M.Ths
Total	42 M.Ths

a.2 Machinery

Total investment for machnery is 297 million Tsh as shown below.

Description	Amount (USD)	Amount (M. Tsh)
Battery Shop	4,279	3
Inspection Pit	22,646	14
Welding Equipent	6,665	4
General Maintenance & Repair	78,850	47
Tire Shop	15,982	10
Other Equipment	287,189	172
Training Material	088,08	48
Total	496,490	297

b. Operation and Maintenance Costs

Table 9-30 shows the required manpower for operating the Nyerere Workshop.

Table 9-30: Manpower Schedule
Unit: persons

	-	,,,,,,,				
1999	2000	2001	2002	2003	2004	2005
1	1	1	1	. 1	1	· 1
	3	3	4	5	6	7
1	8	10	13	15	17	20
	27	34	43	49	57	66
	4	4	4	4	4	4
1	43	52	65	74	85	98
	1999	1999 2000 1 1 1 3 8 27 4	1999 2000 2001 1 1 1 3 3 3 8 10 27 34 4 4	1999 2000 2001 2002 1 1 1 1 1 3 3 4 8 10 13 27 34 43 4 4 4	1999 2000 2001 2002 2003 1 1 1 1 1 3 3 4 5 8 10 13 15 27 34 43 49 4 4 4 4	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1

Table 9-31 shows the operation and maintenance costs from 1999 to 2005.

Table 9-31: O & M Cost Schedule

Category	Description	unit	1999	2000	2001	2002	2003	2004	2005
	Manager	M.Tsh	4	4	4	4	4	4	4
	Mechanical Engineer	M.Tsh	0	4	4	5	6	7	8
	Mecanic	IM.Tsh	l o	6	7	9	11	12	14
	Assistant Mecanic	M.Tsh	l o	13	16	21	24	27	32
	Security Guard	M.Tsh	l ol	2	2	2	2	2	2
	Total	M.Tsh	4	28	33	40	46	52	60
Material	Power supply	M.Tsh		3	4	5	6	7	8
	Water supply	M.Tsh		3	. 4	5	6	7	8
	Others	M.Tsh	l	4	5	7	7	9	10
	Total	M.Tsh	0	11	14	17	19	22	25
Maintenai	nce	M.Tsh	0	15	18	22	26	29	34
Total		M.Tsh	342	54	64	80	91	104	119

9.2.8 Motor Pool

The Master Plan proposes for each district to have a motor pool for refuse collection vehicles so that the travel time can be shortened. The proposed locations of motor pools are as follows.

Kinondoni District: Mwananyamala depot

Ilala District: DRIMP depot

Temeke District: Temeke district office

The every site already has a fence and security guards. The present conditions of these facilities are satisfactory for the use as a motor pool, and therefore further investment is unnecessary. Only operation costs are therefore included.

Table 9-32: Operation Cost Schedule

บกit: M.Tsh

District	Site		2000	2001	2002	2003	2004	2005
Kinondoni	Mwananyamala	2 security guards	1	1	1	1	1	1
•		Miscellaneous	1	1	1	1	1	1
		sub-total	2	2	. 2	2	2	2
lala	DRIMP	2 security guards	1	1	1	1	1	1
		Miscellaneous	1	1	1	1	1	1
		sub-total	2	2	2	2	2	2
Temeke	Temeke District Office	2 security guards	1	1	1	1	1	1
		Miscellaneous	1	1	1	1	1	1
		sub-total	2	2	2	2	2	2
Total	Labour		3	3	3	3	3	3
	Miscellaneous		4	4	4	4	4	4
G-Total			7	7	7	7	7	7

9.2.9 Administrative Expenses

Table 9-33 shows the administrative costs.

Table 9-33: Administrative Costs

Items	1999	2000	2001	2002	2003	2004	2005
Inv. for facilities	29	0	Ō	0	0	0	0
Inv. for equipment	123	21	21	31	21	21	21
O&M for labor	38	48	58	67	77	86	96
O&M for material & fuel	0	8	10	11	13	15	16
Spare parts & repair	4	4	5	6	7	8	9
sub-total	194	81	93	115	117	130	142
Total	536	142	165	202	215	241	268

9.2.10 Project Cost Summary

a. Project Cost Schedule

Table 9-34 summarises the project cost schedule from 1999 to 2005 for implementing all the master plan projects.

Table 9-34: Project Costs Summary

						DE AVE DE LE	p. Ja.C M Market		PARTICIPATION NO.	M.Tsh
Category	Ca	legory	Description	1999	2000	2001	2002	2003	2004	
Direct	Collection	& Transport	Inv. for equipment	3,644	1,384	1,691	298	1,284	1,496	478 296
Cost	,		O&M cost for labor	0	147	174	204	219	246 524	
			O&M for material & fuel	0	235	320	424 595	444 629	740	
			Spare parts & repair	0	337	454 2,639		2,577	3,005	
	l		sub-total	3,644	2,103	2,039	430	2,371	580	0
	Final	Kunduchi	Inv. for facilities	831 600	0	150		ŏ		
	Disposal		Inv. for equipment O&M cost for labor	000	20	20	21	19	19	
			O&M for material & fuel	ŏ	64	7ŏ	92	62	64	67
			Spare parts & repair	ŏ	60	60	75	54	54	54
:		Ilala	Inv. for facilities	ő		Ô	1,755	0	0	0
	l) in the last	Inv. for equipment	Ŏ	ō	Ŏ	196	150	0	0 17
	l		O&M cost for labor	0	Ó	0	0	16	17	17
	İ		O&M for material & fuel	0	0	0	0	44	61	65
			Spare parts & repair	0	0	0	0	40	54	54
	ŀ	Temeke	Inv. for facilities	0	0	0	1,755	0	0	Ŏ
			Inv. for equipment	. 0	0	0	398	. 0	150 16	0 17
	1		O&M cost for labor	0	0	0	0	42	45	61
		1	O&M for material & fuel	ő	ů	Õ	0	40	40	54
	1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Spare parts & repair	1,431	144	300	4,722	484	1,102	411
	China Cour	sub-total	Inv. for facilities	1,431	0		0	0	0	0
	Street Sw	esbuið	liny, for equipment	23	23	23	ŏ			Ŏ
	İ		O&M cost for labor	0	73	91	110		110	110
			O&M for material & fuel	ŏ	25	31	38	38	38	38
			Spare parts & repair	0	9	12	14	14	14	14
			sub-total	23	132					162
	Total			5,093	2,378	3,097				2,840
Indirect	Maintenar	ice	Inv. for facilities	42	0	0	0	0	Ŏ	Ŏ
Cost	Workshop)	Inv. for equipment	297	0		.0	0 46	0 52	0 60
	İ		O&M cost for labor	4.	28 11	33 14	40 17	19	22	25
	1		O&M for material & fuel Spare parts & repair	ő	15	18	22	26	29	34
			Isub-total	342	54	64				119
•	Motor pod	J	O&M cost for labor	0	3		3	3	3	3
	MOIOI POL	,,	O & M for others	ĺŏ	4	4	3	4	4	4
l			Sub-total	Ιŏ	7	7	7	7	. 7	. 7
	Administration		Inv. for facilities	29	Õ	0	0	Ó	0	0
			Inv. for equipment	123	21	21	31	21	21	21
l			O&M cost for labor	38	48	58		77	86	96
	I		Q&M for material & fuel	Ō	8	10		13	15	16 9
I	I		Spare parts & repair	4	4	5	6 115		8 130	142
			sub-total	194	81 142	93 165	202	215	241	268
	Total			536		3,262		3,438	4,510	
Grand To	otal			5,634	2,520	3,202	0,007	3,430	4,010	3,100

b. Unit SWM Cost

Table 9-35 shows the unit SWM costs when all projects proposed in the Master Plan are implemented.

Table 9-35: Unit Solid Waste Management Cost

	Unit SWM Cost						
Type of Works	Present	Value	Including Interes	est of 11.6 %			
, "	Tsh/ton	USD/ton	Tsh/ton	USD/ton			
Collection and Transportation plus Street Sweeping	5,209	8.71	10,596	17.33			
Final Disposal	3,049	5.10	5,510	9.22			
Total	8,258	13.81	16,106	26.94			

The indirect costs composed of maintenance workshop, motor pools and administration expenses were distributed to the transportation plus street sweeping cost and the final disposal cost in accordance with their percentages of the total direct cost.

9.3 Financial Plan

9.3.1 Alternative Options for the Financial Source

a. Basic Concept for the Financial Plan

From the financial and economic evaluation of the Master Plan, it has been evident that the privatisation scheme under the concessionaire system proved to be a failure during the course of the study, concluding that the required financial sources should be partly generated from the municipal tax revenue and partly covered by the refuse collection charges through joint billing with DAWASA to all waste generators or direct special RCC to commercial, institutional and market waste generators. Based on this, the alternative options for the financial scheme for the Master Plan shall be discussed in the following manner so as to make the Master Plan financially feasible.

b. Alternative Options for the Financial Source

Previously in Progress Report 3, a number of alternative options for the financial scheme for the Master Plan were assessed. In the preliminary assessment, the following 8 options were discussed.

Table 9-36 Options for the Financial Scheme for the Master Plan

Option	Financial Source
Option a	Continuation of direct billing for all waste generators
Option b	Joint billing with TANESCO for all waste generators
Option c	Joint billing with DAWASA for all waste generators
Option d	Direct Billing of RCC for household wastes in relatively rich areas and a special fund based on the municipal tax for relatively poor areas
Option e	Direct Billing of RCC for only commercial, institutional and market wastes, and a special fund based on the municipal tax
Option f	Special fund based on the municipal tax
Option g	Special fund based on the municipal tax and joint billing with TANESCO for all waste generators
Option h	Special fund based on the municipal tax and joint billing with DAWASA for all waste generators

Case e and Case h were recommended by the Study Team and finally selected by DCC as final alternative scenarios of revenue sources for the Master Plan.

c. Parameters for Financial Evaluation

The following parameters for the financial evaluation of the Master Plan shall be employed as major variables of the financial plan.

c.1 Prices and Exchange Rate

All prices relevant to the financial evaluation will be converted to Tsh., and the rate will be set at 597.8 Tsh. to 1 USD, which is the mean rate among commercial banks as of the end of February 1997. The cost estimate for the Master Plan shall be also based on the price level as of the end of February 1997.

- .

c.2 Project Life

The Master Plan will start in 1999 upon delivery of the first consignment of vehicles procured and will end in 2005 when their economic life expires. Accordingly, the project life of the Master Plan to be used for the financial evaluation shall be 7 years (1999 to 2005).

c.3 Scrap Value

The vehicles procured after 1999 will have some residual value at the end of the project in the year 2005. The scrap value of these vehicles will be accordingly included as revenue in 2006.

c.4 Cut-off Rate

A cut-off rate, also known as an opportunity cost of capital, is fixed at 11.6 % per annum, which is equivalent to the real interest rate in the capital market of Tanzania.

9.3.2 Revenue Forecast

9.3.2.1 Tax Revenue Forecast

Apart from setting up a few parameters for the financial evaluation of the Master Plan, since all the alternative cases for the financial scheme require DCC's tax revenue sources on which the Master Plan is based, the revenue forecast of major municipal tax sources will be absolutely necessary.

The tax revenue for the Master Plan was forecasted through the following 3 steps: the first step was to accurately forecast DCC's potential tax revenue, the second was to fix the budget allocation of DCC's tax revenue for solid waste management, and the last step is to apply this fixed budget allocation for the overall SWM expenditure.

a. Methodology of Tax Revenue Forecast

The majority of DCC's tax sources include levies and taxes for development, property, petrol, services, hotels, businesses and markets etc. Revenue from these major tax sources shall be forecasted based on the following 3 factors.

- growth rate of the potential revenue
- maximum collection rate of the actual revenue to the potential revenue
- · growth rate of the actual revenue

b. Growth Rate of the Potential Revenue

.

Since the production level affects the amount of taxable resources, it could be safely argued that a growth rate of the potential revenue is roughly in proportion to the growth rate of the national Gross Domestic Product (GDP) of the country, unless the tax level remains unchanged. Accordingly, the growth rates of the potential revenue of all taxes and levies are fixed at 5.0% per annum, which is the target real growth rate of GDP of Tanzania.

ğ

c. Maximum Collection Rate of the Actual Revenue to the Potential Revenue

Although the potential revenue from each source will grow at any rate, the maximum collection rate will never be 100 %. This is due to the fact that the tax administration cannot economically accumulate all the potential revenue. However, the petrol levy is collected by Tanzania Revenue Authority and a fixed proportion of it, decided politically, is allocated to DCC. Considering these factors, the maximum collection rate of potential revenue are set as follows.

Table 9-37 Maximum Collection Rate of Potential Revenue

Revenue Potential
enses, 80 %
100%

d. Growth Potential of Actual Revenue

d.1 Development Levy

The Local Government Finance Management Act states that any person over the age of 18 years is required to pay the development levy. According to the estimate by DCC in 1996, while the potential revenue of the development levy stood at 2.88 billion Tsh., the real tax revenue was 55.6 million Tsh., which is only 19.3% of the potential value, indicating that there is a relatively higher potential for the further growth of the actual revenue of the development levy.

Therefore, the development levy is categorised as a relatively higher revenue potential, where the growth rate of the revenue from the development levy is estimated at 160 % in an optimistic scenario, 140 % in a moderate scenario, and 120 % in a pessimistic scenario. Table A - 1 and Figure A - 1 illustrate the estimated growth rate of the development levy from 1995 to 2006.

d.2 Property Tax

The owner of a property is charged based on the value of the real estate. According to the estimate by DCC in 1996, while the potential revenue of the property tax stood at 2.4 billion Tsh., the real tax revenue was 560.0 million Tsh., only 23.3% of the potential revenue, indicating that there is a relatively higher potential for further revenue increase as valuation of fixed assets is still going on.

Therefore, the property tax is categorised as a relatively high revenue potential, where the growth rate of the revenue from the property tax is estimated at 160 % (optimistic), 140 % (moderate), and 120 % (pessimistic). Table A - 2 and Figure A - 2 illustrate the estimated growth rate of the property tax from 1995 to 2006.

d.3 Petrol Levy

The petrol levy is collected by the Tanzania Revenue Authority (TRA) under the Ministry of Finance at a rate of 60 Tsh. per litre of petroleum products, and, out of this the DCC is supposed to receive a share of 5 Tsh. According to the estimate by the DCC in 1996, while the potential income from the petrol levy stood at 1.697 billion Tsh., for

the five years up to 1995, the central government only received 100.0 million Tsh., which is only 5.9% of the potential revenue, indicating that there is a higher potential for a further growth of the actual revenue of the petrol levy, if the central government commits itself to proper allocation of the petrol levy to DCC.

Therefore, the petrol levy can be considered as a potentially large revenue source, where the growth rate of the revenue from the petrol levy is estimated at 170 % (optimistic), 150 % (moderate), and 130 % (pessimistic). Table A - 3 and Figure A - 3 illustrate the estimated growth rate of the petrol levy from 1995 to 2006.

d.4 Service Levy

The service levy was a newly introduced levy which was formerly known as the "industrial cess". The levy is imposed on major transactions of goods and services at the rate of 0.75% of the turnover of these transactions. According to the estimate by DCC, while the revenue potential of the service levy in 1996 was 3,417million Tsh., the actual revenue of the levy was only 353.1 million Tsh, indicating that there is potential for further increase in actual revenue.

Therefore, the service levy has a high revenue potential, where the growth rate is estimated at 170 % (optimistic), 150 % (moderate), and 130 % (pessimistic). Table A - 4 and Figure A - 4 illustrate the estimated growth rate of the service levy from 1995 to 2006.

d.5 Hotel Levy

The hotel levy is imposed on owners of hotels and guest houses based on the number of rooms. It is estimated that the number of hotels and guest houses in DSM is approximately 3,000, and the current tariff for the hotel levy is 10% of the room charge. According to the estimate by DCC, while the revenue potential of the hotel levy in 1996 was 767 million Tsh., but the actual revenue of the levy was only 114 million Tsh., which is 14.8% of the potential, indicating it is highly probable that the revenue can be increased.

Therefore, there is a scope of improving revenue from the hotel levy, where the potential income is estimated at 160 % (optimistic), 140 % (moderate), and 120 % (pessimistic). Table A - 5 and Figure A - 5 illustrate the estimated growth rate of the hotel levy from 1995 to 2006.

d.6 Business Licenses and Market Ducs

DCC estimates that the actual revenues from business licenses and market dues are 33.3 % and 60.2 % of the potential values, respectively, implying that there is less potential in raising funds from business licenses and market dues.

Therefore, business licenses and market dues are considered to have a lower revenue potential, where the growth rate of the revenue from business licenses and market dues is estimated at 130 % (optimistic), 120 % (moderate), and 110 % (pessimistic). Table A - 6 and Figure A - 6 illustrate the estimate of the growth rate of business licenses from 1995 to 2006, and Table Λ - 7 and Figure A - 7 illustrate the estimated growth rate of market dues from 1995 to 2006.

d.7 Others

Although other taxes and levies include a wide range of revenue sources, there is a relatively lower probability for the further growth.

Therefore as with the business levies, these taxes and levies have a low potential for further development: the growth rates are estimated at 130 %(optimistic), 120 % (moderate), and 110 % (pessimistic). Table A - 8 and Figure A - 8 illustrate the estimated growth rate of other taxes and levies from 1995 to 2006.

d.8 Overall Forecast of DCC's Tax Revenue

Summing up DCC's rax revenue forecast, the following 3 scenarios of the total tax revenue are set up.

Table 9-38 Scenarios of DCC's Total Tax Revenue

unit: million Tsh. 2001 2002 2003 2004 2005 1999 2000 Revenue 17,250 18,112 16,279 11,771 14,639 6,779 9,103 Optimistic 15,062 8,462 10,281 12,538 Moderate 4,807 5,782 6,981 4,388 4,763 5,172 5,618 3,441 3,730 4,045 Pessimistic

The achievement rates by revenue source in the 3 revenue scenarios are tabulated in Table A - 9, Table A - 10 and Table A - 11, the growth rates by revenue source are tabulated in Table A - 12, Table A - 13 and Table A - 14. The achievement rate of the total tax revenue in the 3 revenue scenarios are illustrated in Figure A - 9 and the growth potential of the total tax revenue in the 3 revenue scenarios are illustrated in Figure A - 10.

As a result, Table A - 15, Table A - 16 and Table A - 17 indicate the overall estimate of DCC's tax revenue as well as the subsidy from the central government for the 3 scenarios; Figure A - 11 to Figure A - 16 illustrate the overall estimate of DCC's tax revenue and the supposed share of each revenue source.

e. Budget Allocation of DCC's Tax Revenue to the Solid Waste Management

Considering the recent trend in budget allocation of DCC's tax revenue to the solid waste management sector, the following 3 cases are set up; Tables 9-57, 9-58 and 9-59 give detailed accounts of the budget allocation forecast of DCC's Tax Revenue from 1997 to 2005. Also, the tables show the actual budget allocation for 1996, which is given as a fixed index.

Table 9-39 Estimated Budget Allocation of DCC's Tax Revenue to SWM

unit:% 2002 2003 2004 2005 1998 1999 2000 2001 1996 1997 Revenue 6.2 6.6 6.8 5.0 5.2 5.4 5.6 5.8 6.0 6.4 Optimistic 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5,0 5.0 5.0 Moderate 3.6 3.4 3.2 4.6 4.4 4.2 4.0 3.8 5.0 4.8 Pessimistic





c. Forecast of Budget Allocation Amount for SWM

On applying the budget allocation share to the forecasted tax revenue, the following 9 scenarios of budget allocation amount for SWM in the Master Plan were estimated, details of which are shown in Table A - 21.

Table 9-40 Scenarios of Budget Allocation Amount for SWM

	•						unit : mil	ion Tsh.
Tax Revenue	Budget Allocation	1999	2000	2001	2002	2003	2004	2005
	Rate to SWM							
	Optimistic	804	1160	1481	1729	1990	2287	2627
Optimistic	Moderate	717	1000	1235	1394	1555	1732	1932
'	Pessimistic	631	840	988	1060	1119	1178	1236
	Optimistic	614	804	1072	1444	1872	2198	2541
Moderate	Moderate	548	693	893	1165	1493	1665	1868
	Pessimistic	482	582	714	885	1053	1132	1196
	Optimistic	470	549	645	762	904	1081	1299
Pessimistic	Moderate	420	473	537	614	707	819	955
	Pessimistic	369	398	430	467	509	557	611

9.3.2.2 Forecast of Revenue from RCC

a. RCC collected through Joint Billing with Water Charge

The amount of RCC to be collected was forecast as follows.

a.1 Household waste

The second secon	
Target people	All households that receive refuse collection services
Amount of RCC	Tsh. 1,250 per household per month (according to the interview on willingness to pay)
Billing rate	30 %: (present provision rate of water supply (40%) x present billing rate of water supply charge (80%)
Collection cost rate of RCC	30%: 30% of RCC is paid to DAWASA for the collection cost

a.2 Wastes other than household waste

Target people	All dischargers of official, commercial and market waste that receive the service
Amount of RCC	Tsh. 20,000 per ton (approximately 1.33 times of Willingness to Pay of household waste)
Billing rate	70%: present provision rate of water supply of 80% x present billing rate of water supply charge of 90%
Collection cost rate of RCC	30%: 30% of RCC is paid to DAWASA for the collection cost.

a.3 Forecast of RCC collected through Joint Billing with Water Charge

unit: million Tsh

	2000	2001	2002	2003	2004	2005
RCC from Households	377	531	701	1,006	1,203	1,430
RCC from Others	410	552	725	937	1,085	1,254
Total	787	1,083	1,426	1,943	2,288	2,684

b. Special RCC collected by DCC

The amount of Special RCC to be collected was forecast as follows.

b.1 Business Waste (Commercial, Market and Institutional Wastes)

Target people	All dischargers of official, commercial and market waste that receive the service
Amount collected	Tsh. 20,000 per one ton (approximately 1.33 times of Willingness
7.44	to Pay of household waste)
Billing rate	80%

b.2 Household Waste

Concerning household waste, the special RCC is to be set up for the special refuse collection services, such as door to door collection, bulky waste collection, garden waste collection, etc., where collections costs are generally more expensive than for normal household waste.

b.3 Forecast of Special RCC ollected by DCC

						nillion Tsh
	2000	2001	2002	2003	2004	2005
RCC from Households	656	883	1,161	1,499	1,736	2,007

9.3.3 Case Studies for the Financial Plan

For the financial analysis several cases are set up regarding the following 3 aspects:

• Financial sources: Financial sources for the investment of the project cost

• Revenue source 1: RCC system

• Revenue source 2: Special Fund to be allocated from revenue from the city's

tax revenue

a. Financial Sources for the investment of the project cost

The following 3 cases were presented as financial sources.

Case	Description
Α	All of the project costs are covered by a loan.
	The investment in 1999 for the construction of the final disposal site and landfill equipment is granted by foreign aid.
	All investment in 1999 for the construction of the final disposal site, landfill equipment, refuse collection vehicles, machinery for the maintenance workshop, etc. are granted by foreign aid.

b. Refuse Collection Charge System

Following two cases were assumed for the refuse collection charge system.

Case 1	Joint billing with water supply and sewerage fee by DAWASA
Case 2	Special RCC collected by DCC

c. Special Fund to be allocated from the City's Tax Revenues

Following three cases were assumed for the total amount of special fund allocated from the city's tax revenues.

Case a	Most optimistic scenario of increase in city tax revenue and allocation ratio for solid waste management
Case b	Most likely scenario of increase in city tax revenue and allocation ratio for solid waste management
Case c	Most pessimistic scenario of increase in city tax revenue and allocation ratio for solid waste management

e. Revenue

The following three (3) cases out of the nine (9) SWM budget allocation scenarios are set up as further options in terms of the revenue forecast of the municipal tax for the Master Plan.

Table 9-41 Alternative Scenarios in terms of Revenue Forecast

unit: million Tsh.

Case	1999	2000	2001	2002	2003	2004	2005
a = Most Optimistic	804	1,160	1,481	1,729	1,990	2,287	2,627
b = Most Likely	548	693	893	1,165	1,493	1,665	1,868
c = Most Pessimistic	369	398	430	467	· 509	557	; 611

As a result, financial plans were formulated for a total of 18 cases (3 x 2 x 3) i.e. cost conditions (3 cases), billing system (2 cases), and revenue forecast (3 cases). Table A - 22 to Table A - 39 illustrate the method of financial planning for these 18 cases.

9.4 Examination on the Master Plan by Pilot Projects

a. Objectives of the Pilot Projects

Judging from previous experiences, numerous problems are bound to surface with the implementation of the projects proposed in the M/P. Pilot projects were carried out in the study to identify these problems and ways to be overcome these difficulties. The objectives of the pilot projects are summarised below.

- Examination of the applicability of technologies proposed in the master plan.
- Acquisition of basic data for the preliminary design of the feasibility study.
- Enhancement of public awareness and increase public participation in SWM.
- Demonstration of some improvement measures to authorities concerned and the public.

b. Implementation of Pilot Projects

The following four pilot projects were implemented.

Code:

- A. Enhancing of Public Awareness on SWM.
- B. Environmental Improvement of the Vingunguti Disposal Site.
- C. Improvement of the Refuse Collection System in Kariakoo.
- D. Improvement of the Refuse Collection System in Buguruni.

Pilot projects were planned in order to examine the applicability of the technologies and plans proposed in the Master Plan as countermeasures to problems identified in the first phase of the study.

Table 9-42: Contents of Pilot Projects

Current Problems	Proposals in the M/P	Contents of Pilot Projects	Code No.
Inappropriate technical system and	Improvement of refuse collection system	To examine the expedience of skip collection system in Kariakoo and Buguruni.	C, D
lack of resources	Sanitary Landfill	 Improvement of the environmental sanitary condition of the landfill site and its environs. Demonstration of environmental protection technologies such as gas removal, soil cover, etc. Demonstration and technical transfer of waste amount control system by using the computerised weighbridge system installed by JICA. 	В
	Improvement of street cleaning system	 Installation of 100 litter bins in Kariakoo ward and garbage collection from them. 	С
Lack of knowledge of dangers by refuse	Education on refuse	 Production of 20,000 refuse education textbooks. Trial lessons on refuse to primary school pupils. Seminar on refuse education to primary school teachers. Poster competition by primary school pupils. Educational cultural show on refuse. Educational film show on refuse. 	A
Lack of moral concern about refuse	To raise public awareness of refuse problems and to promote public cooperation	 "Beautify Your City" campaign was conducted. In order improve public spirit in DSM and make people feel responsible for maintaining the city clean, the catch phrase "Beautify Your City" for public the campaign was adopted. Most activities in the pilot projects were concentrated in February with February named as "Beautify Dar es Salaam Month". The contents of the pilot projects were publicised timely. Banners, posters, stickers, TV, newspaper, T shirts, etc. were used in order to advertise "Beautify Your City" and promote public cooperation. An open 10 km Taka Race from the City Hall to the National Stadium took place on 2nd March as the closing event of "Beautify Dar es Salaam Month" in order to raise public awareness on refuse. Every participant ran with stickers showing "Beautify Your City" on the front of his/her shirt. 	A

c. Findings from Pilot Projects

Through the implementation of the pilot projects the Team found out the following important issues for the modification of the M/P and the execution of the F/S for the first priority projects.

i. It is difficult to gain public co-operation for the prevention of littering if a sufficient refuse collection service is not provided. For example, the litter bins







installed in Kariakoo ward were used not only for litter but also for the discharge of residential and commercial wastes. Most of them became refuse collection points as a result. This shows that litter bins (which requires public co-operation for the prevention of littering) can not function according to their purpose without the provision of a sufficient refuse collection system. This also indicates that the skip collection system can work in Kariakoo ward, i.e. in the SUPA.

- ii. Public co-operation for primary refuse collection to a skip can be obtained if refuse collection services are sufficiently provided. For example in Buguruni ward, although skip containers were placed just beside the Uhuru road which is some distance from residential areas, it was observed that considerable amounts of household wastes were discharged into them. This proved that a considerable number of people would bring and discharge their wastes into skips to be installed along a trunk road even without primary collection services in the SUUA.
- iii. A major problem with any future campaign is the perception many residents have of the DCC. In the words of one participant: "DCC says a lot but does little". This is the main reason why many residents thought it was unfair to ask citizens to change their attitudes without a corresponding improvement in DCC's SWM performance. It is vital that the general public's perception of DCC is improved and this will primarily be achieved through improved SWM performance, not by education and awareness raising campaigns.
- iv. Programmes for public education require sufficient "attraction power" for the public so that the majority of public are willing to participate in them by their own will. Educational cinema shows and culture shows conducted as pilot projects gathered large audiences every time and it was shown that the cinema show in particular is a very cost effective measure for public education.

9.5 Evaluation of the Master Plan

9.5.1 Technical Evaluation

The technical system proposed in the Master plan is very simple as it will mainly constitute basic elements of collection, transportation, and final disposal. It will not include a major intermediate treatment system. This technical system would be suitable for DSM because it is consistent with the institutional requirements for the area, that are identified in Chapter 5, and also with the SWM objective for DSM, i.e. improvement of sanitary conditions.

Skip trucks were proposed as the main collection and transportation equipment. DSM has been using skip trucks (3) since 1988 until recently when they broke down. The tipper trucks which were also obtained in the same period are still in operation. The breakdown of the skip trucks is attributed to excessive use: the number of trips made by the skip trucks was 3 - 5 times more than the tipper trucks. DCC is adequately equipped with the technical skills required for the maintenance of skip trucks and the necessary spare parts are available in DSM. These trucks cost very little to operate and are quite convenient, and they are, therefore, most appropriate for DSM.

Tipper trucks were proposed for curb collection in some parts of Area A. The use of these trucks was decided because they are not technologically too advanced and will not require any sophisticated form of maintenance.

The Master Plan proposed the use of compactor trucks for collection in the city centre. The reasons why the use of compactor trucks in DSM between, 1991-1992, was terminated were unsuitability of the screw type compactor for the collection of waste with high density, and lack of technical assistance. However, the use of compaction trucks in the city centre would be very advantageous, particularly in consideration of the traffic conditions and the lighter density of wastes in this area, because they not only carry a lot of waste but also have a small body.

Leachate control is also considered essential in DSM, but because it usually requires expensive investment and O & M cost, a disposal system equipped only with primary leachate treatment system was proposed. This system will be investigated in detail to determine whether costs can be minimised with the use of simple technology.

No intermediate technology was proposed, except for on-site composting which does not require complicated techniques.

Since the proposed technical system is very simple, problems are not envisaged. However, there is a need to improve the capability of the maintenance workshop proposed in the Master Plan in anticipation of maintenance problems that would result from the rapid increase in the number of refuse collection vehicles.

9.5.2 Social Evaluation

Prior to the financial and economic evaluation, the master plan was evaluated in terms of the intangible social impacts it will incur, i.e., improvements in sanitary and public health conditions, prevention of flood, promotion of foreign investment and tourism, and increase in land value.

a. Improvements in Public Health and Sanitary Conditions

Poor collection or disposal practices encourage the breeding of insects, rodents, and pathogens that can cause and transmit diseases, particularly several of the diseases in the tropical cluster: schistosomiasis, trypanosomiasis, and Bancroftian filariasis. Since the master plan intends to mitigate the effect of such diseases by the elimination of waste heaps and the introduction of sanitary landfills with proper facilities, considerable improvements in public health conditions as well as conditions in nearby illegal dumping sites and in disposal sites can be anticipated.

The study by the World Bank suggests that 25 percent of soil transmitted diseases will be averted through feasible interventions such as covering of waste with soil at the dumpsite, fifteen to thirty centimetres deep, at the end of each day. Meanwhile, the Ministry of Health reported that 12.0 percent of the mortality rate in DSM is caused by some kind of soil transmitted diseases. The male mortality rate in DSM ranges from 19 per 1000 persons between the ages of 10-14 to 535 per 1000 persons between the ages of 75-79, and that the female mortality rate in DSM ranges from 16 per 1000 persons between the ages of 10-14 to 455 per 1000 persons between the ages of 75-79. Therefore, the calculated impact on the mortality rate ranges from 0.57 per 1000 persons between 10-14 to 16.17 per 1000 persons between 75-79.

b. Prevention of Flood

Inadequate collection and transport of wastes may also clog open drains, creating breeding grounds for malaria and dengue-transmitting mosquitoes, or causing floods in rainy seasons, which may increase human contact with pathogen-infected faeces contained in the waste. The master plan will significantly mitigate the dangers these situations may bring about through the regular road sweeping services it promotes.

c. Promotion of Investment and Tourism

In addition to the above-mentioned health effects, the proper collection, transport and disposal of wastes shall provide DSM with the favourable environment for the promotion of foreign investment and tourism. Since DSM, as the central gateway, is connected by major railroads and trunk roads to neighbouring countries, the improvement of its environment will enhance its image, and eventually contribute to attracting more investors and tourists to the area.

d. Increase in Land Value

Well-managed waste disposal services also improve the living environment which result in increased land values. A study on the correlation between the living environment and land value suggests that, with other factors held constant, housing values further from a landfill rise at an average rate of 6.2 % a mile within a two-mile radius of the landfill, presumably because the environmental and aesthetic problems associated with living near a landfill diminish as distance from it increases⁴. Thus, the master plan with proper sanitary landfilling measures should increases the land value around the present illegal dumping sites and the disposal site.

⁴ Beede, D.N. and Bloom, D.E. 1995, The Ecoonics of Municipal Solid Waste, The World Bank

9.5.3 Environmental Evaluation

Table 9-43 summarises the impacts which are predicted to occur with the implementation of the SWM Master plan.

Table 9-43: Summary of Environmental Evaluation of the SWM Master Plan

Project	Components	Positive Impacts	Negative Impacts
Increase in Waste Collec	tion Rate	Improvement in air quality Improvement in water quality Removal of offensive odour Improvement in aesthetic conditions Reduction of public nuisance	Ait pollution Noise pollution
Construction of new disposal sites in the outskirts of DSM	Closure of the Vingunguti dumping site	Improvement in air quality Improvement in water quality Removal of offensive odour Improvement in aesthetic conditions Reduction of public nuisance Reduction of traffic in access road	
	Operation of new disposal site		 Deterioration of sanitary conditions ⇒ Increase in morbidity & mortality • Worsening view • Air pollution • Water pollution • Noise pollution • Offensive odour
	Increase in Transport Distance		Air pollution Noise pollution Contribute to global warming

a. Impacts of Increase in Waste Collection Rate

The positive impacts are predicted to result from increase in waste collection rate, while the negative impacts are predicted to result from increase in refuse collection trucks. These are further discussed below.

a.1 Positive Impacts

Improvement in air quality

Methane (CH₄) and carbon dioxide (CO₂) are mainly emitted through the decomposition of organic solid wastes. This impact may not be recognised seriously because only a little gas is dispersed in a wide area. However, wherever it is emitted at generation sources or the landfill, the total pollutant load of emission gas will be the same. They would affect air quality anyway.

Improvement of water quality

Where waste collection services are absent, they are often disposed of at small open spaces or at rivers and drainage near generation points. Wastes disposed of at small open spaces will produce leachate consequently polluting surface and ground water. Wastes disposed of in rivers will pollute river water as well.

Removal of offensive odour







Removing wastes from the catchment area will remove the causes of offensive odour.

Improvement in aesthetic conditions

The removal of scattered wastes from the catchment area will improve aesthetic conditions, i.e., view, landscape.

a.2 Negative Impacts

Air pollution, noise pollution and traffic accidents would increase with the increased presence of refuse collection vehicles.

b. Construction of new disposal sites in the outskirts of DSM

This project consists of three diverse components, and because they will have different impacts, they are described separately as follows.

b.1 Closure of the Vingunguti Disposal Site

The improper landfill operation conducted at the Vingunguti disposal site has resulted in various negative environmental impacts. Therefore, its closure would be a positive environmental preservation measure as it would bring about: improvements in sanitary conditions, cleanliness, improvements in air quality, elimination of offensive odour and public nuisance.

b.2. Operation of New Disposal Site in the Outskirts of DSM

Basically, the same negative environmental impacts caused by the operation of the Vingunguti landfill site are also predicted to occur in the new disposal sites, but on a lesser scale because of the following reasons.

- The sanitary landfill level and operation of the new disposal sites will be much better than the existing disposal site.
- The new disposal sites will be located in areas suited to their functions.

b.3. Increase in Waste Transportation Distance

Increase in waste transportation distance and waste collection rate will increase the overall travel distance of refuse collection vehicles and consequently generate the following negative impacts:

Air pollution

Air quality would be affected by emissions, such as carbon dioxide, carbon monoxide (CO), oxides of nitrogen (NOx) and total suspended particulate (TSP) from vehicles.

Global warming

Carbon dioxide emitted by vehicles would contribute to global warming.

Traffic accidents

Operation of vehicles would cause traffic accidents, which would then generate casualties, traffic congestion, etc., as secondary impacts.

Consumption of fossil fuel

The vehicles will consume fuel which is a non-renewable resource.

c. Conclusion

The implementation of these projects will generate various significant positive impacts on the waste catchment area. These impacts will outnumber the negative impacts that will result from the increase in the use of refuse vehicles.

Conclusively, the three new disposal sites will generate less negative impacts than the existing Vingunguti disposal site due to the adoption of the following environmental preservation measures.

- Use of environmentally sound landfill structures and landfill operation system;
- The new disposal sites will be located in less populated areas.

9.5.4 Financial Evaluation

a. FIRRs

FIRR was calculated regarding the following the combined eighteen cases (3x2x3) of the three cases of project cost (A: all loan, B: grant provided only for disposal site, C: grant provided for disposal site, collection vehicles, workshops), two cases of billing (RCC) system (1: joint billing, 2. RCC only for special collection service), and the three scenarios of forecast regarding the special fund allocated from the city's tax revenue. The results of the calculations are tabulated below. Table A - 40 to Table A - 57 present the calculations for the relevant FIRRs, and Table A - 58 together with Figure A - 17 summarise the results of the FIRRs.

Table 9-44: FIRRs of Each Financial Case Study

Financial Plan	Financial Source	Revenue	Case	FIRRs
for Investment	<u> </u>	Forecast		(%)
	Tax and RCC collected by joint	Optimistic	A-1-a	1.52%
	billing with water supply charge	Most Probable	A-1-b	-5.38%
All loan		Pessimistic	A-1-c	-13.90%
	Tax and Special RCC collected by	Optimistic	A-2-a	-2.83%
-	DCC	MostProbable	A-2-b	-8.91%
		Pessimistic	A-2-c	-17.79%
Grant provided only	Tax and RCC collected in joint	Optimistic	B-1-a	4.88%
for the investment in	billing with water supply charge	MostProbable	B-1-b	-3.14%
1999 for construction		Pessimistic	B-1-c	-12.56%
of the disposal site	Tax and Special RCC collected by	Optimistic	B-2-a	-0.10%
and landfill equipment	DCC	Most Probable	B-2-b	-7.66%
		Pessimistic	В-2-с	-16.74%
-	Tax and RCC collected in joint	Optimistic	C-1-a	31.92%
	billing with water supply charge	MostProbable	C-1-b	8.34%
Grant provided for all		Pessimistic	C-1-c	-7.05%
investment in 1999	Tax and Special RCC collected by	Optimistic	C-2-a	17.01%
	DCC	Most Probable	C-2-b	0.57%
		Pessimistic	C-2-c	-12.76%







Following conclusion was drawn from the above FIRRs.

- In the case where there is a total loan scheme (Case A-1-a, A-1-b, A-1-c, A-2-a, A-2-b and A-2-c), FIRRs of all the financial cases was much lower than the opportunity cost of capital (cut-off rate) of Tanzania. Therefore, it is not financially feasible. It implies that supply of higher external financial sources such as foreign grant assistance for investment is essential.
- In the case where grant assistance covers investment cost for 1999 to construct the final disposal site and acquire landfill equipment (Case B-1-a, B-1-b, B-1-c, B-2-a, B-2-b and B-2-c), it is judged that all financial cases will be financially unrealistic because the FIRRs in all cases are under the cut-off rate. It implies that more financial resources, not only for the final disposal site but also for other investment costs, with a higher foreign grant equivalent is indispensable.
- In the case where all required investment for 1999 is granted (Case C-1-a, C-1-b, C-1-c, C-2-a, C-2-b and C-2-c), RCC is collected by DAWASA with water charge and tax forecast is most probable (Case C-1-b), the FIRR is 8.34 %. Although this value is slightly lower than the cut off rate of 11.6 %, the project implementation can be made financially feasible by DCC making additional efforts such as collect more taxes, increase RCC collection rate, etc.
- In the case where all required investment for 1999 is granted, special RCC is collected by DCC and tax forecast is most probable (Case C-2-b), the FIRR is 0.57 %. Although this value is lower than the cut off rate of 11.6 %, the required operation and maintenance cost can be at least covered by the revenue. In addition, further investment can be made by making additional efforts such as collect more taxes, increase RCC collection rate, etc.

9.5.5 Economic Evaluation

The economic evaluation has been carried out to determine economic impacts of the Master Plan on the national economy of Tanzania. Since the various factors distort the price level of the costs and benefits, financial costs and benefits will be converted as economic costs and benefits using relevant conversion factors. The locally-traded goods and services and unskilled labour force are over valued in the financial cost, thus, various taxes and subsidies, which are mere transfers of income, are excluded from the financial cost.

Table Λ - 59 presents the calculations of the conversion factors for investment, operation and maintenance, and indirect costs. The financial planning table, using these conversion factors, is shown in Table A - 60 together with the result of the economic internal rate of return (EIRR) shown in Table A - 61. The calculation indicates that the EIRR of the Master Plan is almost at the same level as the cut-off rate of 9.25%, suggesting that the Master Plan will contribute to the improvement of the economic development of Tanzania.

9.5.6 Overall Evaluation

The projects proposed in the Master Plan were evaluated in terms of their technical, social, environmental, financial and economic impacts.

The technical evaluation concluded that the simplicity of the proposed technical system is very appropriate for the present level in DSM. Although problems in vehicle and equipment maintenance are foreseen, they can be overcome by improvements in the proposed maintenance workshop.

The social evaluation concluded that the implementation of the proposed projects would generate various positive significantly intangible impacts such as improvements in public health and sanitary conditions, prevention of floods, promotion of foreign investment and tourism, increase in land value, etc.

The environmental evaluation concluded that the positive effects from the projects shall outnumber the negative impacts.

In the financial evaluation, FIRR (financial internal rate of return) for the 18 cases were calculated. As a result, if:

- All investment cost for 1999 is granted.
- The most probable scenario of increase of tax revenue is taken.
- RCC is collected by either DAWASA included in the water charges or the DCC directly.
- 1) In the case where RCC is collected by DAWASA with water charges, FIRR is 8.34 %. Although this value is slightly lower than the cut off rate of 11.6 %, the project implementation can be made financially feasible by DCC making additional efforts such as collect more taxes, increase RCC collection rate, etc.
- 2) In the case where special RCC is collected by DCC, FIRR is 0.57 %. Although this value is lower than the cut off rate of 11.6 %, the required operation and maintenance cost can be at least covered by the revenue. In addition, further investment can be made by making additional efforts such as collect more taxes, increase RCC collection rate, etc.

The economic evaluation is done based on the EIRR (economic internal rate of return) which is calculated from total economic cost (which is calculated by economic price obtained from the modification of the deviation in domestic market price) and total economic benefits. Therefore the evaluation takes into account that:

- · All project costs are covered by a loan without any grant component.
- RCC is collected by joint billing with DAWASA.
- There is a special fund to be allocated from city taxes revenue.

As a result, the EIRR is calculated at 9.25 %, which is almost equal to the cut-off rate of 11.6 %. Therefore, the implementation of the master plan will contribute to the national economy.

The overall evaluation concluded that the execution of the Master Plan would be essential to maintain the basic level of urban environment sanitation and public health and to enable sustainable urban development for DSM, at the same time it would be feasible technically, socially, environmentally, financially and economically.







9.6 Initial Environmental Examination

During the second period of work in Tanzania (March-August 1996 inclusive) the selection of appropriate disposal sites for DSM city was made using five criteria based on the existing proposal for future disposal site allocation within DSM city and social, environmental, technical and financial aspects. Only one site, Kunduchi New MECCO quarry, was assessed as being appropriate and it was examined for use as the new disposal site in the feasibility study to be conducted in the third phase of this Study.

This section deals with the IEE (Initial Environmental Examination) of the proposed disposal site. At present there are no formal environmental assessment guidelines in Tanzania. Instead, for major projects, it is required that an Environmental Impact statement be submitted to NEMC but no definition of "major" nor any criteria concerning the contents of this statement are given. Hence, JICA's Environmental Guidelines⁵ have been followed for the IEE and will be used in the EIA (Environmental Impact Assessment). Definitions of the terms used are given in the Guidelines and Fig 9-9 from the Guidelines is reproduced here to illustrate the procedure for environmental consideration.


The JICA Guidelines list 23 environmental items for evaluation under the headings: 'social environment', 'natural environment' and 'pollution'. In this case, a 24th item ('litter') was added under the 'pollution' heading. The guidelines state that "the scope should cover not only the project site for final disposal but also the entire area where it would create an impact directly or indirectly, including the routes of waste collection vehicles and where the effluent is discharged". In this case, the scope/IEE covered the proposed disposal site and the main access road (Bagamoyo Road) to the intersection with Sam Nujoma Road at Mwenge. Only this section of road was included as it will experience the most significant increase in traffic volume due to the passage of refuse vehicles.

The IEE consisted of the following steps:

- 1. The general screening and scoping assessments made by the Preparatory Study team were reviewed and scoping was then carried out for the Kunduchi New Mecco quarry site in order to identify the items requiring an Environmental Impact Assessment (EIA). The results of this assessment are shown in Table 9-45.
- 2. The contents of the EIA (i.e. required work) and possible environmental conservation/mitigation measures were then defined for each environmental item, using available data and in consultation with Tanzanian counterparts. The results of this examination are shown in Table 9-62.

These results show that serious environmental impact is expected for water pollution while some impact is expected for public health, hazards/risks, landscape/aesthetics, air pollution, soil contamination, noise and vibration, offensive odor and litter. The extent of the impact for economic activities, traffic and public facilities, waste, topography and geology, groundwater, hydrological situation and flora and fauna is unknown at this stage but should be clarified through the EIA which will be conducted during the third phase of this Study.

⁵ Environmental Guidelines for Infrastructure Projects No.VI Solid Waste Management, JICA, Sept 1992



telecommunication projects, etc.

When the environmental factors that may have serious impact are not identified, it is necessary to mention in the M.M. that such items would be clarified in the full scale study.

Figure 9-9: Procedure of Environmental Consideration of JICA

Froject Description Site Description

9.6.1 Scoping of Environmental Impacts

Table 9-45: Scoping of Environmental Impacts for Proposed Disposal Site at New MECCO Quarry

No	Environme	Description	Evaluat	Reason
· ·	ntal Item		ion	
	Destilant	Social Environment Resettlement due to land	D	No houses/residents in area for proposed site.
1	Resettleme nt	acquirement due to tand acquirement for project(s) (transfer of rights of land ownership/residence).	Ь	
2	Economic Activities	Loss of bases for economic activities (e.g. land) and effects on these activities.	С	Ministry of Works crushing plant operations and some individuals performing manual excavation works and associated activities in or near quarry will be affected; effect on recycling/scavenging activities unknown although scavengers at Vingunguti will be displaced.
3	Traffic and Public Facilities	Impacts on schools, hospitals, etc. and traffic conditions (e.g. increased traffic congestion/accidents).	С	Schools, hospitals and other public facilities in area may be affected; increased traffic congestion/accidents, especially on Bagamoyo Rd, near Mwenge, may occur.
4	Division of Community	Division of Community geographically due to project location, interruption of area traffic, etc.	D	No community in proposed area.
5	Cultural Property	Damage to or loss of value of churches, temples, archaeological remains or other cultural assets.	D	No cultural property in area around landfill site.
6	Water Rights/ Access Rights	Obstruction of fishing rights, water rights and rights of common access.	D	None; land is under control of Ministry of Energy and Minerals; no water/fishing rights affected.
7	Public Health	Deterioration of public health and sanitary conditions due to refuse generation and increase in pathogens/vermin.	В	Impact will be most significant near landfill site due to refuse disposal; deterioration in air and water quality will also affect public health.
8	Waste	Generation of construction wastes/debris.	С	Impact of construction wastes/debris should be considered although it is likely to be small.
9	Hazards/Ri sks	Increase in natural disasters (e.g. landslides) and man-made hazards (e.g. landfill gas explosions, refuse fires).	В	Possibility of natural disasters is unlikely to increase; impact of man-made hazards should be small if good landfill management practices followed.
10	Topograph y and Geology	Natural Environment Changes of valuable topography and geology due to excavation, construction and/or filling works.	C	Natural environment has already been seriously damaged by quarry operation - scale of construction excavation works should be small but further impact on natural environment should be assessed; some soil may be taken from other areas for impermeable liner and/or covering material for landfill - impact on these other areas should be considered although impact is likely to be small.
11	Seil Eresion	Topsoil erosion by rainfall after earthfilling and deforestation.	D	Topsoil has already been removed by quarry operation.
12	Groundwat er	Changes in groundwater level due to infiltration of leachate and run-off from disposal site.	С	Impact on groundwater level is likely to be small but should be considered.
13	Hydrologic al Situation	Changes in river discharge and riverbed condition due to inflow of run-off and landfill.	С	Impact on surface water sources in vicinity of landfill is likely to be small but should be considered.
14	Coastal Zone	Coastal erosion and changes in vegetation due to coastal reclamation and coastal changes.	D	Project will not impact on coastal zone.
15	Fauna and Flora	Obstruction of breeding and extinction of species due to changes in habitat conditions.	С	Flora has already been damaged by quarry operation; increase in vermin numbers may threaten flora and fauna.
16	Meteorolog y	Changes in temperature, rainfall, wind, etc. due to large scale land changes and building construction.	D ·	None; scale of landfill is too small to produce such changes.
17	Landscape/ Aesthetics	Changes in topography and vegetation due to earthworks; deterioration in environmental aesthetics.	В	Topography and vegetation has already been seriously damaged by quarry operation; further changes will occur in immediate vicinity of landfill site but impact is likely to be small.
		Pollution		
18	Air	Pollution caused by exhaust/toxic	В	Landfill gases (e.g. methane) will be generated;

No	Environme ntal Item	Description	Evaluat	Reason
	Pollution	gases, dust, smoke, fumes, etc. from refuse collection vehicles and the landfill site.		smoke/dust may be problematic especially during dry season; impact of fumes/exhaust gases from refuse collection and landfill vehicles should be small.
19	Water Pollution	Pollution caused by inflow of sand, silt, leachate and run-off from disposal site into rivers, groundwater and sea near river discharges.	A	Due primarily to leachate.
20	Soil Contaminat ion	Contamination of soil by leakage and diffusion of ash, leachate, etc.	В	Due primarily to leachate and hazardous/toxic substances in refuse.
21	Noise and Vibration	Noise and vibration generated by refuse collection vehicles and landfill site equipment.	В	Due to refuse collection vehicles and heavy landfill site equipment (e.g. bulldozers).
22	Land Subsidence	Deformation of land and land subsidence due to lowering of groundwater table.	D	Pumping of groundwater will be negligible; effect on land subsidence due to groundwater level changes caused by infiltration of leachate/run-off will be insignificant.
23	Offensive Odor	Generation of offensive odors from landfill site, associated treatment facilities and during waste transportation.	В	Odors due to landfill gases, refuse smell and leachate will be generated at landfill site.
2-1	Litter	Scattering of litter from landfill site and refuse collection vehicles.	В	Impact will be small, especially if appropriate counter- measures taken.

Note: Evaluation categories: A - serious impact expected; B - some impact expected; C - extent of impact unknown (examination needed; impacts may become clear as Study progresses); D - no impact expected; EIA not necessary

9.6.2 Summary of Relevant Factors for each EIA Item

Table 9-46: Explanation of Item 2

Item	2. Economic Activities	
Description	Loss of bases for economic activities (e.g. land) and effects on these activities	
Cauces of Impacts		

- 1. Acquisition of land for new disposal site.
- 2. Shifting of disposal site from Vingunguti to New MECCO Quarry in 2000.

Possible Environmental Impacts

- 1. Displacement of Ministry of Works Crusher Operation from quarry.
- 2. Loss of work for individuals who perform manual excavation works and associated activities (e.g. canteen for quarry workers) in or near quarry.
- 3. Shifting of disposal site will force changes in the present scavenging/recycling system conducted at Vingunguti disposal site.
- 4. Loss of work for individuals involved in scavenging/recycling activities (scavengers and middlemen) presently conducted at Vingunguti disposal site.
- 5. Social upheaval for individuals who choose to move to the new disposal site in order to begin or continue their scavenging/recycling activities.

Useful Factors for Evaluation

- 1. Status of Ministry of Works Crusher Operations.
- 2. Number of individuals involved in manual excavation works and associated activities and their income generating activities.
- 3. Number of permanent scavengers and middlemen at Vingunguti disposal site and details of their income generating activities.
- 4. Response of individuals involved in scavenging/recycling at Vingunguti to shifting of disposal site.

Possible Counter-Measures

- 1. Good communication and consultation with affected individuals/communities/Ministry of Works.
- 2. Possible compensation for those losing employment (monetary payment, alternative employment, etc.).
- 3. Assist adaptation of recycling system to changed circumstances.

Related Subjects for Study

- 1. Effect on scavenging/recycling system when the disposal site was shifted from Tabata to Vingunguti.
- 2. Future recycling plans.
- 3. Organisation of Scavengers in DSM.







7. Public Health

Item

Table 9-47: Explanation of Item 3

	Table of the Explanation of them of			
Item	3. Traffic and Public Facilities			
Description	Impact on schools, hospitals, etc. and traffic conditions (e.g. increased traffic congestion/ accidents)			
Causes of Impa				
	traffic in and around disposal site.			
2. Passage of re	fuse collection vehicles to and from disposal site.			
Possible Enviro	onmental Impacts			
1. Greater traffic	e congestion and risk of accidents due to increased traffic volume on access roads and around disposal			
site.				
2. Disturbance t	o public facilities along access roads due to increased traffic volume (noise, fumes, etc.).			
	for Evaluation			
	1. Road and traffic conditions near the disposal site and on main access road near Mwenge including assessment of			
accident danger	spots.			
	ublic facilities (e.g. schools, hospitals, army barracks) along main access roads and near disposal site.			
	3. Frequency distribution of refuse collection vehicles (weekly basis).			
	utes of refuse collection vehicles.			
Possible Count				
	of roads around the disposal site including possible modifications of the traffic system.			
	uling of refuse collection vehicles and routes to avoid peak hour traffic.			
3. Fix hours of	3. Fix hours of operation of landfill site to consider traffic conditions.			
4. Site entrance	4. Site entrance to landfill site to avoid queuing on main road.			
	5. Installation of traffic safety features, especially in accident danger spots.			
	6. Reduction in disturbance to public facilities by landscaping, screening, etc.			
	Related Subjects for Study			
	1. Present land use and traffic conditions.			
2. Future land u	2. Future land use and transportation plans including development of public facilities.			

Table 9-48: Explanation of Item 7

110112				
Description	Deterioration of public health and sanitary conditions due to refuse generation and increase in pathogens			
Causes of Impacts				
1. Increase in pathogens (microorganisms, insects, rodents, etc.) around disposal site.				
2. Emission of ga	ses, smoke, fumes, dust from the disposal site and refuse collection vehicles.			
3. Contamination	of groundwater and surface water sources around disposal site.			
4. Presence of he	alth hazards (e.g. syringes, broken glass, contaminated food) in refuse at disposal site.			
Possible Enviror				
1. Animals, birds	and insects at final disposal site could become vectors of disease, affecting public health.			
2. Increased incid	lence of respiratory diseases from gases, smoke, dust, fumes from the disposal site and refuse collection			
vehicles.				
Increased incid	lence of water-related diseases due to groundwater/surface water contamination.			
	to workers and scavengers if collection and disposal works are not conducted properly.			
Useful Factors for				
1. Recent history	of incidence of disease, especially epidemics, in vicinity of final disposal site.			
2. Water quality (groundwater, surface water sources) in immediate vicinity of disposal site.			
3. Air quality in i	mmediate vicinity of disposal site.			
4. Amount and na	sture of hazards in refuse disposed at final disposal site.			
Possible Counter				
1. Conduction of	appropriate surveys at regular intervals, to obtain base line and subsequent data for comparison (water and			
air quality, public	health, vermin, etc.) for area around disposal site.			
2. Installation of	monitoring, collection and treatment facilities/venting for leachate/landfill gases.			
3. Prevention of p	athogens by proper disposal site management including possible use of pesticides (for vermin) and control			
	s to minimise breeding of vectors of disease (e.g. mosquitoes).			
	4. Exclusion of hazardous/toxic waste from landfill.			
5. Public education on sanitation for local residents, refuse workers and scavengers to avoid infection.				
Related Subjects for Study				
1. Occurrence and frequency of vectors of disease in DSM, especially near landfill sites.				
2. Habitation and	2. Habitation and propagation of small mammals (e.g. rats) and insects (e.g. flies, mosquitoes).			
3. Occurrence and	d frequency of refuse-related, air-related and water-related diseases in DSM.			
	4. Meteorological data (e.g. precipitation, humidity, etc.)			
5. Topographical	5. Topographical and Geological Survey.			
6. Examination o	f corresponding data (water quality, public health, etc.) for Vingunguti and Tabata disposal sites.			

Table 9-49: Explanation of Item 8

Item	8. Waste	
Description	Generation of construction wastes/debris	
Causes of Impacts		
1. Generation of debris and construction waste due to construction of final disposal site.		
Possible Environmental Impacts		

1. Environmental degradation due to disposal of construction wastes/debris in inappropriate manner.

Useful Factors for Evaluation

- 1. Estimation of amount of construction wastes/debris according to scale of excavation/construction
- 2. Alternative uses for construction wastes/debris.

Possible Counter-Measures

- 1. Careful construction planning and management, including specification of standards/procedures for disposal of construction wastes/debris in project documents.
- 2. Temporary storage of construction wastes/debris during construction with subsequent transfer to new landfill.
- 3. Reuse of construction wastes/debris (e.g. earthfilling in low lying areas, erosion control).

Related Subjects for Study

Table 9-50: Explanation of Item 9

١	Item	9. Hazards/Risks
		Increase in natural disasters (e.g. landslides) and man-made hazards (e.g. landfill gas
	,	explosions, refuse fires)

Causes of Impacts

- 1. Changes in natural environment (topography, ground stability, etc.) due to construction, operation and after-care of disposal site.
- 2. Introduction of man-made hazards due to construction, operation and after-care of disposal site.

Possible Environmental Impacts

- 1. Increased occurrence of natural disasters in area around landfill.
- 2. Increased occurrence of man-made disasters (e.g. landfill gas explosions, refuse fires)

Useful Factors for Evaluation

- 1. Types and quantities of toxic/hazardous wastes in refuse normally disposed at Vingunguti disposal site.
- 2. Incidence of natural disasters in area around disposal site.
- 3. Prediction of amounts of landfill gas produced throughout lifetime (operation and after-care) of landfill site.
- 4. Incidence of fires at Vingunguti disposal site (annual basis) to identify high risk times of the year.

Possible Counter-Measures

- 1. Risk analysis of landfill site.
- 2. Containment, collection and venting of landfill gases.
- 3. Provision of fire safety measures, fire fighting equipment and appropriate training of refuse workers.
- 4. Preparation of safety procedures for landfill site.
- 5. Exclusion of toxic/hazardous waste from landfill.
- 6. Use of run-off for sprinkling.

Related Subjects for Study

- 1. Topographical and Geological Survey.
- 2. Meteorological data (e.g. precipitation, wind direction and speed, etc.).
- 3. Risks/hazards associated with sanitary landfill operation in tropical climates.







Table 9-51: Explanation of Item 10

Item	10. Topography and Geology
	Changes of valuable topography and geology due to excavation, construction and/or filling
	WOLKS

Causes of Impacts

1. Excavation of soil during construction works at landfill site.

2. Excavation of suitable soils for impermeable liner and/or covering material of landfill from other areas. Note: Natural environment of landfill site has already been seriously damaged by quarry operation. Additional excavation and construction work should not significantly impact further on topography/geology.

Possible Environmental Impacts

1. Damage to valuable topography and geology due to excavation works during construction and/or obtaining lining and/or covering material from other areas.

Useful Factors for Evaluation

1. Quantifying of construction exeavation works to be conducted.

2. Location and availability of soils suitable for use as impermeable liner and/or covering material for landfill.

Possible Counter-Measures

1. Careful construction planning and management with specification of standards/procedures to be followed for all excavation works in project documents.

2. Good excavation practice (e.g. minimising exposure of bare soils; timing of soil movements to suit season; careful storage of topsoils, etc.).

3. Placement, restoration and after-care programmes to appropriate standards.

Related Subjects for Study

1. Topographical and Geological Survey of landfill site and other areas.

2. Permeability of soils around disposal site.

Table 9-52: Explanation of Item 12

Item	12. Groundwater	
Description	Changes in groundwater level due to infiltration of leachate and run-off from disposal site	
Causes of Impacts		

1. Infiltration of leachate and run-off from disposal site into groundwater.

Possible Environmental Impacts

1. Changes in groundwater level due to changed infiltration flows.

2. Depression of groundwater level and land subsidence due to the extraction of groundwater in excavations below the water table.

Useful Factors for Evaluation

1. Effects of an impermeable liner in landfill on infiltration flows.

2. Permeability of soil around area of disposal site.

3. Groundwater conditions around and downstream of the site.

4. Water use around and downstream of the site, particularly in consideration of women.

Possible Counter-Measures

1. Collection and treatment of all leachate with control and monitoring of discharge.

2. Segregation and treatment of run-off from waste areas, with control and monitoring of discharge.

3. Possible use of impermeable liner for landfill.

4. Exclusion of hazardous/toxic waste from landfill.

5. Monitoring of groundwater around and downstream of the disposal site (including base line data).

Related Subjects for Study

1. Topographical and Geological Survey.

2. Precipitation and Hydrological Survey.

3. Examine relevant surveys concerning quarry's impact on groundwater.



Table 9-53: Explanation of Item 13

Item	13. Hydrological Situation		
Description	Change of river discharge and riverbed condition due to inflow of run-off a	nd landfill	
Cause of Impacts			

- 1. Inflow of drainage into rivers and lakes from disposal site.
- 2. Deposition of landfill into rivers and lakes from disposal site.

Possible Environmental Impacts

- 1. Change in regime of rivers and lakes by alteration of water bodies may damage ecosystems (plants, fish, animals, etc.).
- 2. Reduction in income to fishermen.

Useful Factors for Evaluation

- 1. Distribution of surface water bodies in area around landfill site.
- 2. Variation in surface water flows throughout the year.

Possible Counter-Measures

- 1. Segregation and treatment of run-off from waste areas, with control and monitoring of discharge.
- 2. Collection and treatment of all leachate with control and monitoring of discharge.
- 3. Monitoring of surface water bodies around and downstream of the disposal site.
- 4. Careful management of construction and landfill operations to prevent landfill entering surface water bodies.

Related Subjects for Study

- 1. Topographical and Geological Survey.
- 2. Precipitation and Hydrological Survey.
- 3. Water use from rivers and lakes around landfill site.
- 4. Aquatic life in rivers and lakes around landfill site.

Table 9-54: Explanation of Item 15

ı		
	Item	15. Flora and Fauna
	Description	Obstruction of breeding and extinction of species due to changes in habitat conditions

Causes of Impacts

- 1. Removal of vegetation and disturbance of animal and bird habitats for the construction/operation of landfill site.
- 2. Increase in pathogenic insects, animals and birds at disposal site.
- 3. Smoke, fumes and gases from landfill site and refuse collection vehicles.
- 4. Water pollution by leachate and run-off from disposal site.
- 5. Noise and vibration caused by the operation of construction equipment and refuse collection vehicles. Note: Flora and fauna has already been extensively damaged by quarry operation.

Possible Environmental Impacts

- 1. Reduction in population of valuable and precious species which may affect biodiversity (extinction possible).
- 2. Increased numbers of flies, birds and rats which may obstruct the breeding of other species.
- 3. Advese effects on flora and fauna around and downwind/downstream of site due to air/water pollution.

Useful Factors for Evaluation

- 1. Survey of flora and fauna in area around landfill site; in particular, assessing if there are species unique to the locality and/or endangered/rare species in the area.
- 2. Existence of national, bilateral and/or multilateral conventions on flora and fauna.

Possible Counter-Measures

- 1. Schedule construction work to avoid breeding and nesting season.
- 2. Good landfill practice and pollution control.
- 3. Conservation of major and/or sensitive flora and fauna features.
- 4. Briefing of site workers.
- 5. Control of seagulls and rats.

Related Subjects for Study

1. Ecosystem and food chain in area around landfill site.







Table 9-55: Explanation of Item 17

Michael Control of the Control of th	N VANDE AND AND THE THE THE THE THE THE THE THE THE THE			
ltem	17. Landscape/Aesthetics			
Description	Changes in topography and vegetation due to earthworks; deterioration in environmental aesthetics			
Causes of Impa				
	pography and vegetation for the construction of final disposal site.			
	pography during landfill operation and after-care.			
3. Visual appea	rance of landfill site and facilities.			
Note: Topograp	hy and vegetation has already been seriously damaged by quarry operation.			
Possible Envir	onmental Impacts			
1. Deterioration	in environmental aesthetics due to adverse visual impact of landfill site and facilities.			
2. Adverse effo	et on tourism in the area.			
3. Residents fee	lings may be aggravated if the landscape is related to their religious/cultural beliefs.			
Useful Factors	for Evaluation			
1. Consideratio	n of the role of the landscape in religion, culture, tourism, etc. in the area.			
	residents concerning the visual impact of the landfill site and facilities.			
3. Evaluation o	f the host country should be taken into consideration.			
4. Frequency of	tourists using main access road (Bagamoyo Road).			
Possible Count				
1. Careful design	n of disposal site and facilities including fencing, gates, siting of flares, plant and offices.			
2. Good communication and consultation with residents.				
	maximum height of landfill.			
4. Good landfil	practice (e.g. contouring and matching existing landscape, screening with bunds or vegetation)			
5. Restoration/rehabilitation plan for landfill.				
Related Subject	ets for Study			
1. Distribution	of tourist spots and historial sites.			
2. Local history	and folklore.			
3. Tourism dev	elopment plan.			

Table 9-56: Explanation of Item 18

Item	18. Air Pollution			
Description	Pollution caused by exhaust/toxic gases, dust, smoke, fumes, etc. from refuse collection vehicles and the landfill site.			
Causes of Imp	acts			
	f dust and landfill gases at disposal site.			
	smoke from occasional refuse fires at disposal site.			
3. Generation of equipment (e.g.	f dust, exhaust gases and fumes from construction vehicles, refuse collection vehicles buildozers).	and landfill site		
Possible Envir	onmental Impacts			
1. Increase in r	espiratory diseases due to dust, gases, smoke and fumes from the disposal site and ref	use collection vehicles		
and associated	equipment.			
	owth of plants due to toxic gases and dust falling on their leaves.			
3. Adverse effe	cts on nests of birds due to gases, dust, etc.			
~~~~	for Evaluation	•		
	ral data (e.g. wind direction and speed, air temperature distribution).			
	opulation density in surrounding area, especially downwind of the dominant winds.			
3. Proximity of	public facilities (e.g. hospitals) requiring clean air.			
	roads and traffic density (residents will be affected by dust and exhaust gases when la	nofill site access roads		
	have heavy traffic).	:		
<del></del>	rea around landfill.			
Possible Coun				
	of air pollution monitoring programme.	1		
	l practice (e.g. compaction, rapid cover, aprinking to prevent fires and dust).			
	, collection and venting of landfill gases.	• •		
	of fire prevention and fire fighting procedures.			
	ntain refuse collection vehicles on a regular basis.			
	vehicles, wheel wash and dust control.			
Related Subje	ets for Study	•		
2. Topographic	Quality Standards and/or Regulations.			
	Quality Standards and/or Regulations. al Survey.			
	Quality Standards and/or Regulations.			

# Table 9-57: Explanation of Item 19

******************	
Item	19. Water Pollution
Description	Pollution caused by inflow of sand, silt, leachate and run-off from disposal site into rivers
	and groundwater
The second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second secon	S. P. P. C. D. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. C. P. P. C. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. C. P. P. P. P. P. P. P. P. P. P. P. P. P.

#### **Causes of Impacts**

- 1. Inflow of sand and silt from construction of final disposal site.
- 2. Inflow of leachate and run-off into rivers and groundwater.
- 3. Leakage of hazardous substances during rainfall into rivers and groundwater.

#### Possible Environmental Impacts

- 1. Pollution of groundwater and rivers.
- 2. Obstruction to growth of aquatic life due to deterioration in water quality.
- 3. Occurrence of health problems due to using contaminated water.

#### **Useful Factors for Evaluation**

- 1. Permeability of soil around disposal site.
- 2. Groundwater and surface water conditions within the catchment area and downstream of the site.
- 3. Water use around and downstream of the site, particularly in consideration of women.

#### Possible Counter-Measures

- 1. Preparation of water pollution monitoring programme.
- 2. Timing of major earthworks to avoid wet season.
- 3. Collection and treatment of leachate with control and monitoring of discharge.
- 4. Segregation and treatment of run-off from waste areas with control and monitoring of discharge.
- 5. Possible use of impermeable liner for landfill.
- 6. Monitoring of groundwater and surface water quality around and downstream of the disposal site (including base line data).
- 7. Exclusion of toxic/hazardous waste from landfill.
- 8. Provision of another water supply for residents in immediate vicinity of site.

### Related Subjects for Study

- 1. Topographical and Geological Survey.
- 2. Precipitation and Hydrological Survey.

Use of impermeable liner for landfill.
 Collection and treatment of leachate.

Topographical and Geological Survey.

Related Subjects for Study

5. careful sorting of any refuse to be used for compost production.

### Table 9-58: Explanation of Item 20

Item	20, Soil Contamination				
Description	Contamination of soil by leakage and diffusion of ash, leachate, etc.				
Causes of Imp	acts				
1. Infiltration of	of leachate and run-off.				
2. Leakage of l	nazardous substances during rainfall into soil.				
3. Application	of refuse-derived compost, contaminated by heavy metals to farmlands.				
Possible Envir	ronmental Impacts				
1. Contaminati	1. Contamination of soil under and around disposal site.				
2. Subsequent contamination of groundwater and downstream water sources.					
3. Adverse effects on human health due to absorption by crops of contaminants in compost.					
Useful Factors for Evaluation					
1. Design policy for leachate collection, treatment and disposal.					
2. Amount and nature of hazardous/toxic waste to be disposed at final disposal site to assess magnitude of soil contamination risk.					
3. Investigation is needed if some refuse is to be composted and possible uses of compost.					
4. Water and land use around the disposal site.					
Possible Counter-Measures					
1. Preparation of soil pollution monitoring plan.					
2. Exclusion of toxic/hazardous waste from landfill.					



# Table 9-59: Explanation of Item 21

gram ammanani mana 4-4-4-4-4-4-4	大学的 1986年1983年1983年1983年1983年1983年1983年1983年1983					
Item						
Description	Description Noise and vibration generated by refuse collection vehicles and landfill site equipment					
Causes of Impa	cts					
1. Use of constru	otion equipment and vehicles for construction (e.g. bulldozers, dump trucks, etc.).					
2. Use of equipn	nent at disposal site (e.g. bulldozer) and refuse collection vehicles around disposal site and along the					
main access road	<del>, , , ,</del>					
Possible Enviro	nmental Impacts					
1. Residents, hos	pitals, schools and other public facilities along the access road would be affected by noise.					
2. Cracks in buil	dings on soft ground caused by vibrations.					
3. Disturbance to	farm animals and wildlife along the access road and around the disposal site.					
Useful Factors	for Evaluation					
1. Noise and vib	ration levels around disposal site and along access road.					
2. Distribution o	f residents and living conditions (especially housing).					
3. Distribution o	f public facilities such as schools, hospitals along access road.					
4. Ground condi	tions near landfill site and along access road.					
5. Distribution o	f livestock farming and wildlife habitats near landfill site and along access road.					
Possible Counte	r-Measures					
1. Installation of	buffer zone (e.g. planted area, trees) or other noise reduction methods (e.g. enclosures, screens,					
bunding) at disp	bunding) at disposal site and near sensitive locations.					
2. Correct use and maintenance of disposal site facilities, equipment and refuse collection vehicles.						
3. Careful consideration of construction and operation hours for landfill site.						
4. Careful consideration of operation hours and routes for refuse collection vehicles.						
	5. Use of low noise and vibration construction equipment.					
Related Subject	Related Subjects for Study					
1. Topographica	l and Geological Survey.					
2. Land use arou	2. Land use around the disposal site and along the access road.					

# Table 9-60: Explanation of Item 23

Item	23. Offensive Odour				
Description	Generation of offensive odours from landfill site, associated treatment facilities and during				
Description	transportation of refuse				
Compactions					
Causes of Impa	from refuse in disposal site in the case of open dumping without soil cover.				
1. Pumu smen	run-off from disposal sites, wash water from washing of refuse collection vehicles.				
3. Emission of I					
4. Defree coult	and fumes from refuse collection vehicles.				
Possible Enviro	onmental Impacts s could generate offensive odours, which depending upon wind direction and speed may affect				
	s could Scuetate outsisive odonts' which acheroms about with alternation and about was access				
inhabitants.	bout odour from residents and users of public facilities such as schools and hospitals around the final				
disposal site and	access roads.				
	roperty values in the vicinity of the disposal site and along access roads.				
Useful Factors					
1. Meleorologic	al data (e.g. wind direction and speed, air temperature distribution, precipitation).				
2. Distribution (	of residents, schools, hospitals and other public facilities around disposal site and along access road.				
3. Land use arou	and disposal site and along access road.				
4. Careful consideration of frequency of refuse collection to take into account waste composition, residents' living					
	conditions and climatic conditions.				
5. Location and nature of washing facilities for refuse collection vehicles.					
Possible Counter-Measures					
1. Frequent soil cover of refuse.					
2. Containment, collection and venting of landfill gases.					
3. Collection and treatment of leachate.					
4. Careful consideration of location of leachate treatment plant.					
Related Subjects for Study					
1. Topographical Survey.					
2. Past complain	2. Past complaints regarding offensive odours at Vingunguti and Tabata disposal sites.				

# Table 9-61: Explanation of Item 24

Item	24. Litter	:	
Description	Scattering of litter from landfill site and refuse collection vehicles		
Causes of Imp	acts	:	
1. Poor design	and operation of landfill site.		
2. Inadequate	overing of refuse during transportation.		
Possible Envi	ronmental Impacts		
	the environment and deterioration in aesthetics due to scattering of litter from	refuse trucks	
	ad and around disposal site.		
	s for Evaluation	: :	
	of refuse workers to use anti-litter devices.	•	
2. Composition	of refuse from different sources.	·	
Possible Cour			
1. Covering of	refuse collection vehicles during final transportation to disposal site.		
2. Rapid cover	of refuse at disposal site and use of portable fence to catch scattered litter.	:	
3. Briefing of a			
Related Subje	cts for Study	:	
1. Meteorologi	cal data (e.g. wind direction and speed, precipitation).		

# 9.6.3 Works Required for EfA

Table 9-62: Work Required for EIA and Environmental Conservation/Mitigation Measures

Environmental	Evalu- ation	Description of Work Required for EIA	Possible Environmental Conservation/Mitigation Measures
2. conomic Activities	C	<ul> <li>Assessment of status of Ministry of Works operations at site.</li> <li>Economic Survey of workers doing excavation works and associated activities at or near quarry.</li> <li>Economic Survey of permanent scavengers and middlemen at Vingunguti disposal site and other places (completed).</li> <li>Assessment of impact on recycling system of shifting the disposal site⁶.</li> </ul>	- good communication and consultation with affected individuals/communities/Ministry of Works.  - possible compensation for those losing employment.  - assist adaptation of recycling system to changed circumstances.
3. Traffic and Public Facilities	C	- Traffic Survey near disposal site and on access road near Mwenge Description and location of public facilities in area (part of Land Use Survey) Obtaining Land Use (for public facilities) and Road Development plans for area near site and along access road.	<ul> <li>improvement of roads around disposal site including possible modifications of traffic system.</li> <li>proper scheduling of refuse collection vehicles and routes to avoid peak hour traffic.</li> <li>site entrance to landfill to avoid queuing on main road.</li> <li>installation of traffic safety features, especially in accident danger spots.</li> <li>reduction in disturbance to public facilities by landscaping, screening, etc.</li> </ul>
7. Public Health	В	- Baseline Public Health Survey in area around disposal site Baseline Water Quality (groundwater, surface water sources) Survey in area around and downstream of disposal site Baseline Air Quality Survey in area around disposal site.	<ul> <li>taking measures to eradicate pathogens including use of pesticides (for vermin) and control of stagnant water (to minimise breeding of vectors).</li> <li>installation of monitoring, collection and treatment facilities/venting for leachate/landfill gases.</li> <li>exclusion of toxic/hazardous waste from landfill.</li> <li>public education on sanitation for local residents, refuse workers and scavengers to avoid infection.</li> </ul>
8. Waste	С	- Estimation of amount of construction wastes/debris according to scale of excavation/construction works Investigation of alternative uses for construction wastes/debris.	<ul> <li>careful construction planning and management, including specification of standards/procedures for disposal of construction wastes/debris in contract documents.</li> <li>temporary storage of construction wastes/debris during construction with subsequent transfer to new landfill.</li> <li>reuse of construction wastes/debris.</li> </ul>
9. Hazards/ Risks	В	- Risk Assessment of landfill site.	- exclusion of toxic/hazardous waste from landfill containment, collection and venting of landfill gases.

⁶ Decision on scavenger policy for new landfill required







⁷ Necessity for impermeable liner will be established on analysis of topographical and geological survey results.

Environmental Item	Evalu- ation	· Description of Work Required for EIA	Possible Environmental Conservation/Mitigation Measures				
			immediate vicinity of site.				
20. Soil Contamination	В	- Soil pollution forecast Topographical and Geological survey Water and land use in area.	<ul> <li>preparation of soil pollution monitoring plan.</li> <li>exclusion of toxic/hazardous waste from landfill.</li> <li>possible use of impermeable liner for landfill.</li> <li>collection and treatment of leachate.</li> <li>careful sorting of any refuse to be used for compost production.</li> </ul>				
21. Noise and Vibration	В	Noise and Vibration Survey near disposal site and along access road.     Land Use Survey (distribution of agriculture, housing, public facilities, tourist facilities, etc.) in area around disposal site and along access road.	<ul> <li>installation of buffer zone (e.g. planted area, trees) or other noise reduction methods (e.g. enclosures, screens, bunding) at disposal site and near sensitive locations.</li> <li>correct use and maintenance of disposal site facilities, equipment and refuse collection vehicles.</li> <li>careful consideration of construction and operational hours for landfill and operational hours and routes for refuse vehicles.</li> </ul>				
23. Offensive Odor	В	- Meteorological data (wind direction and speed, air temperature distribution, precipitation, evaporation).  - Land Use Survey (distribution of housing, public facilities, tourist facilities, etc.) in area around disposal site and along access road.	- frequent soil cover of refuse containment, collection and venting of landfill gases collection and treatment of leachate careful consideration of location of leachate treatment plant.				
24. Litter	В	- Consideration of appropriate anti-litter devices for refuse collection vehicles and disposal site.	- covering of refuse collection vehicles during final transportation to disposal site.  - rapid cover of refuse at disposal site and use of portable fences to catch litter.  - briefing of refuse workers.				

Note: Evaluation categories: A - serious impact expected; B - some impact expected; C - extent of impact unknown (examination needed; impacts may become clear as Study progresses); D - no impact expected; FIA not necessary.

Table 9-63: List of Works required for EIA

No.	Description of Work	Environmental Item
1	Topographical Survey	No. Reference 10, 12, 13, 17, 19, 20
2	Geological Survey	10, 12, 13, 19, 20
3	Hydrological Survey	12, 13, 19
4	Traffic Survey	3
5	Noise and Vibration Survey	21
6	Economic Survey (at disposal site)	2
7	Economic Survey (at Vingunguti)	2 (completed)
8	Baseline Public Health Survey	7
9	Baseline Water Quality Survey and Water Pollution Forecast	7, 19
10	Baseline Air Quality Survey and Air Pollution Forecast	7, 18
11	Baseline Soil Pollution Survey and Soil Pollution Forecast	20
12	Flora and Fauna Survey	15
13	Land Use Survey (distribution of agriculture, housing, public facilities, tourist facilities, etc.) for area near disposal site and along access road including estimation	3, 17, 18, 20, 21, 23
14	of population density	
14	Risk Assessment of Landfill Site	9
15	Meteorological data collection (precipitation, wind direction and speed, air temperature distribution, evaporation)	12, 13, 18, 19, 23
16	Obtaining Development plans for land use (agriculture, housing, public facilities, tourist facilities, etc.) and roads	3, 12, 13, 17, 18, 19
17	Water Use in area (groundwater and surface water)	12, 13, 19, 20
18	Estimation of amounts of construction wastes/debris that will be produced and investigation of alternative uses for construction waste	8
19	Research on location and availability of soils suitable for use as impermeable landfill liner.	10
20	Assessment of impact on recycling system of shifting disposal site	2
21	Assessment of status of Ministry of Works operations at site	2
22	Obtaining any existing national, bilateral and/or multilateral conventions on flora and fauna	15 :
23	Assessment of the role of the landscape in religion, culture, tourism, etc. in the area	17
24	Preparation of a pictorial model showing visual impact of the landfill site and facilities	17
25	Consideration of appropriate anti-litter devices for refuse collection vehicles and disposal site	24





# 9.7 Implementation Plan

The proposed implementation programme of the Master Plan is shown in Figure 9-10.

Figure 9-10: Implementation Programme of the Master Plan

Institutional System  Establishment of the Waste Management Authority Establishment of the Supervision and Monitoring Committee  Establishment of Special Fund for SWM  Establishment of Special Fund for SWM  Establishment of Special Fund for SWM  Change of Contract System  To formulate and to enforce the new Sanitary Code  To conduct promotional eampaign  Training  Waste Collection, Transport and Street Sweeping System  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the New Kunduchl Disposal Site  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Operationning  Development of the Disposal Sites In Itala and Temeke  Selection of Sites  Planning and Basic Design  Development of the Disposal Sites In Itala and Temeke  Selection of Sites  Planning and Basic Design  Development  Operationning  Development of the Newere  Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyerere  Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyerere  Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of Design and Tender Document  Operations and Procurement	rigare 5-10. Impr	1	1	· · · · · ·						
Establishment of the Waste Management Authority Establishment of the Supervision and Monitoring Committee Establishment of Special Fund for SWM Establishment of RCC system  Change of Contract System  To formulate and to enforce the new Sanitary Code To conduct premotional eampaign Training Waste Collection, Transport and Street Sweeping System Planning and Basic Design Detailed Design and Tender Document Operationning Development of the New Kunduchi Disposal Site Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning Development of the New Kunduchi Disposal Site Planning and Basic Design Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Development of the New Construction and Procurement Operationning Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Development of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Operationning Development of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Operationning Development of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Construction and Procurement		1997	1998	1999	2000	2001	2002	2003	2004	2005
Management Authority Establishment of the Supervision and Monitoring Committee Establishment of Special Fund for SWM Establishment of RCC system Change of Contract System To formulate and to enforce the new Sanitary Code To conduct promotional campaign Training Waste Collection, Transport and Street Sweeping System Planning and Basic Dosign Detailed Design and Tender Document Construction and Procurement Detailed Design and Tender Document Construction and Procurement Construction and Procurement Construction and Procurement Detailed Design and Tender Document Construction and Procurement Operationning Development of the Disposal Sites In Ilala and Temble Selection of Sites Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning Improvement of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Detailed Design and Tender Document Construction and Procurement Detailed Design and Tender Document Construction and Procurement	Institutional System									
Management Authority Establishment of the Supervision and Monitoring Committee Establishment of Special Fund for SWM  Establishment of RCC system  Change of Contract System  To formulate and to enforce the new Sanilary Code To conduct promotional campaign Training  Waste Collection, Transport and Street Sweeping System Planning and Basic Design  Detailed Design and Tender Decument  Operationning  Development of the New Kunduchl Islaposal Site Planning and Basic Design  Detailed Design and Tender Decument Construction and Procurement Construction and Procurement  Operationning  Development of the New Funduchl Islaposal Site Planning and Basic Design  Detailed Design and Tender Decument Construction and Procurement  Operationning  Development of the Disposal Sites In Italia and Tember Decument Construction and Procurement  Operationning  Development of the Disposal Sites In Italia and Tember Decument  Operationning  Development of the Nyeree Workshop Planning and Basic Design  Detailed Design and Tender Decument  Operationning  Improvement of the Nyeree Workshop Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyeree Workshop Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyeree Workshop Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyeree Workshop Planning and Basic Design  Detailed Design and Tender Document  Oconstruction and Procurement		183	Ansira o	CONTRACTOR ASSESSMENT		PAR-CO P	cian perce	-		geometric personal
and Monitoring Committee Establishment of Special Fund for SWM  Establishment of RCC system  Onange of Contract System  To formulate and to enforce the new Sanitary Code To conduct promotional campaign  Training  Waste Collection, Transport and Street Sweeping System  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the New Kunduchi Disposal Site  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Construction and Procurement  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyerre  Workshop  Planning and Basic Design  Detailed Design and Tender  Document  Operationning  Improvement of the Nyerre  Workshop  Planning and Basic Design  Detailed Design and Tender  Document  Oconstruction and Procurement	Management Authority						<u></u>	<b> </b>	<b></b> -	
Stablishment of Special Fund for SWM  Establishment of RCC system  Change of Contract System  To formulate and to enforce the new Sanitary Code  To conduct promotional campaign  Training  Waste Collection, Transport and Street Sweeping System  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Operationning  Development of the New Kunduchl Disposal Site  Planning and Basic Design  Development of the New Kunduchl Disposal Site  Planning and Basic Design  Development of the Disposal Sites Initial and Temeke  Selection of Sites  Planning and Basic Design  Development of the Disposal Sites Initial and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Operationning  Development of the Disposal Sites Initial and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Oconstruction and Procurement		į į	A CONTRACTOR OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF THE PARTY OF TH	105578 W.		METALENS.	-		******	Concest Bell
Change of Contract System  To formulate and to enforce the new Sanitary Code To conduct promotional campaign Training  Waste Collection, Transport and Street Sweeping System Planning and Basic Design  Detailed Design and Tender Document Construction and Procurement Planning and Basic Design  Development of the New Kunduchl Disposal Site Planning and Basic Design  Detailed Design and Tender Document Construction and Procurement  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design  Detailed Design and Tender Document Construction and Procurement  Operationning Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design  Detailed Design and Tender Document Construction and Procurement  Operationning  Improvement of the Nyerere Workshop Planning and Basic Design  Detailed Design and Tender Document Oconstruction and Procurement  Detailed Design and Tender Document Operationning  Improvement of the Nyerere Workshop Planning and Basic Design  Detailed Design and Tender Document Oconstruction and Procurement	<ul> <li>Establishment of Special Fund for</li> </ul>				224 1200	E-1145	norm (min	a 65720	pansir) F	
To formulate and to enforce the new Sanitary Code To conduct promotional campaign Training  Waste Collection, Transport and Street Sweeping System Planning and Basic Design Development of the New Kunduchl Disposal Site Planning and Basic Design Expansion of a anothing and Procurement Construction and Procurement Construction and Procurement Planning and Basic Design Expansion of a anothing and Expansion of a anothing special street anothing and Procurement Construction and Procurement Construction and Procurement Population of the Disposal Sites in Baland Temeke Selection of Sites Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Construction and Procurement Construction and Procurement Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Basic Design Planning and Procurement Construction and Procurement	· - · · · · · · · · · · · · · · · · · ·		ENTERE E	December 19	20 8459	(ES,200)		eq (cratan)		
new Sanitary Code  To conduct promotional campaign  Training  Waste Collection, Transport and Street Sweeping System  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the New Kunduchl Disposal Site  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites in Itala and Temeke  Selection of Sites  Planning and Basic Design  Development of the Disposal Sites in Itala and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites in Itala and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyerer Workshop  Planning and Basic Design  Detailed Design and Tender  Document  Operationning  Improvement of the Nyerer Workshop  Planning and Basic Design  Detailed Design and Tender  Document  Operationning  Improvement of the Nyerer Workshop  Planning and Basic Design  Detailed Design and Tender  Document  Operation and Procurement		232			005 p.ez-s		eve		EERS P	
Training  Waste Collection, Transport and Street Sweeping System  Planning and Basic Design  Detailed Design and Tender Decument  Operationning  Development of the New Kunduchl Disposal Site  Planning and Basic Design  Detailed Design and Tender Decument  Operationning  Development of the Disposal Sites In Itala and Temeke  Selection of Sites  Planning and Basic Design  Development of the Disposal Sites In Itala and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the New Funder Document  Operationning  Improvement of the Nyeree  Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Improvement of the Nyeree  Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operation and Procurement  Operation and Procurement  Operation and Procurement  Operation and Procurement	new Sanitary Code	72	STANDARD (S	<b>22</b>	123273		e (Georgianos)	26JA 27	134 ENECT	pyrodia
Waste Collection, Transport and Street Sweeping System  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the New Kunducht Disposal Site Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Operationning  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Operation and Procurement		Base.	80000	10053779 B		#400-2#	MESCESSE 404	es mais		
Street Sweeping System Planning and Basic Design Detailed Design and Tender Document Operationning Development of the New Kunduchl Disposal Site Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Detailed Design and Tender Document Operationning Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Detailed Design and Tender Document Operationning Development of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Operationning Development of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Operation and Procurement Operation and Procurement Operation and Procurement Operation and Procurement		E0000	• •	manes to		least seen				ATTAM PT
Detailed Design and Tender Document Construction and Procurement  Development of the New Kunduchl Disposal Site Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Document Construction and Procurement Detailed Design and Tender Document Construction and Procurement Detailed Design and Tender Document Construction and Procurement	Street Sweeping System									
Document Construction and Procurement Operationning  Development of the New Kunduchl Disposal Site Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning  Detailed Design and Tender Document Construction and Procurement Document Construction and Procurement Operationning  Improvement of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Construction and Procurement		<b>1888</b>								
Operationning  Development of the New Kunduchl Disposal Site Planning and Basic Design  Detailed Design and Tender Document Construction and Procurement  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Operationning  Detailed Design and Tender Document  Construction and Procurement  Operationning  Improvement of the Nyerere Workshop Planning and Basic Design  Detailed Design and Tender Document  Operationning  Operationning  Detailed Design and Tender Document  Operation of the Nyerere Workshop Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement	Document		11. 11. 11. 15 N	ļ						
Development of the New Kunduchl Disposal Site  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites In Itala and Temeke Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Operationning  Improvement of the Nyerere Workshop Planning and Basic Design  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Occument Construction and Procurement	Construction and Procurement	<u> </u>		14,14°40		- <u>-</u>				
Disposal Site  Planning and Basic Design  Detailed Design and Tender Document  Operationning  Development of the Disposal Sites In Itala and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Operationning  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Detailed Design and Tender Document  Operationning  Detailed Design and Tender Document  Construction and Procurement					econ de	(a) Cessa	624°157988 1	7.5822 <b>85.</b> 3		2000A *
Detailed Design and Tender Document Construction and Procurement Operationning  Development of the Disposal Sites in Itala and Temeke Selection of Sites Planning and Basic Design Detailed Design and Tender Document Construction and Procurement Operationning Improvement of the Nyerere Workshop Planning and Basic Design Detailed Design and Tender Document Operationning  Operation Basic Design Planning and Basic Design  Detailed Design and Tender Document Construction and Procurement  Construction and Procurement  Construction and Procurement	Disposal Site									
Detailed Design and Tender Document     Construction and Procurement     Operationning     Development of the Disposal Sites In Itala and Temeke     Selection of Sites     Planning and Basic Design     Detailed Design and Tender Document     Construction and Procurement     Operationning     Improvement of the Nyerere Workshop     Planning and Basic Design     Detailed Design and Tender Document     Operationning     Detailed Design and Tender Document     Operation of the Nyerere Workshop     Planning and Basic Design     Operation and Procurement     Construction and Procurement     Operation of the Nyerere Workshop     Postailed Design and Tender Document     Construction and Procurement		1200								
Operationning      Development of the Disposal Sites In Itala and Temeke     Selection of Sites      Planning and Basic Design      Detailed Design and Tender Document     Construction and Procurement      Operationning  Improvement of the Nyerere Workshop     Planning and Basic Design      Detailed Design and Tender Document     Construction and Procurement     Construction and Procurement     Construction and Procurement	Document									
Development of the Disposal Sites In Itala and Temeke  • Selection of Sites  • Planning and Basic Design  • Detailed Design and Tender Document  • Construction and Procurement  • Operationning  Improvement of the Nyerere Workshop  • Planning and Basic Design  • Detailed Design and Tender Document  • Construction and Procurement  • Construction and Procurement				MSDE CO						
In Ilala and Temeke  Selection of Sites  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement					escon 🛏	6000	90909			
Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement  Operationning  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement	In Itala and Temeke									
Detailed Design and Tender Document     Construction and Procurement     Operationning     Improvement of the Nyerere Workshop     Planning and Basic Design     Detailed Design and Tender Document     Construction and Procurement										
Document  Construction and Procurement  Operationning  Improvement of the Nyerere Workshop  Planning and Basic Design  Detailed Design and Tender Document  Construction and Procurement					AMAGAA.					
Operationning  Improvement of the Nyerere Workshop     Planning and Basic Design      Detailed Design and Tender Document     Construction and Procurement	Document					alestelle.				
Improvement of the Nyerere Workshop  • Planning and Basic Design  • Detailed Design and Tender Document  • Construction and Procurement	Construction and Procurement									
Workshop Planning and Basic Design Detailed Design and Tender Document Construction and Procurement	Operationning									202-6133
Planning and Basic Design      Detailed Design and Tender     Document      Construction and Procurement	Workshop				_,					
Document     Construction and Procurement	Planning and Basic Design	2016								
Construction and Procurement	Document		HINIDK.							
• Operationoing	Construction and Procurement									
- Abergraduerd	Operationning				DC487-8 \$550		2000 m			

Legend:

Implementation:

Functioning:

1

(Manual)