## MINISTRY OF CONSTRUCTION THE STATE OF ERITREA

3.1

## BASIC DESIGN STUDY REPORT

ON

## THE PROJECT FOR THE EQUIPMENT SUPPLY PROGRAM

FOR

## ROAD IMPROVEMENT

IN IN

## THE STATE OF ERITREA

JULY 1997

JAPAN INTERNATIONAL COOPERATION AGENCY CONSTRUCTION PROJECT CONSULTANTS, INC.

> and a second second

2 Contraction



No.



## MINISTRY OF CONSTRUCTION THE STATE OF ERITREA

## **BASIC DESIGN STUDY REPORT**

## ON

## THE PROJECT FOR THE EQUIPMENT SUPPLY PROGRAM

## FOR

## **ROAD IMPROVEMENT**

IN

## THE STATE OF ERITREA

## JULY 1997

## JAPAN INTERNATIONAL COOPERATION AGENCY CONSTRUCTION PROJECT CONSULTANTS, INC.

#### PREFACE

In response to a request from the Government of the State of Eritrea the Government of Japan decided to conduct a basic design study on the Project for the Equipment Supply Program for Road Improvement in the State of Eritrea and entrusted the study to the Japan International Cooperation Agency (JICA).

JICA sent to Eritrea a study team from April 8 to May 1, 1997.

The team held discussions with the officials concerned of the Government of Eritrea, and conducted a field study at the study area. After the team returned to Japan, further studies were made. Then, a mission was sent to Eritrea in order to discuss a draft basic design, and as this result, the present report was finalized.

I hope that this report will contribute to the promotion of the project and to the enhancement of friendly relations between our two countries.

I wish to express my sincere appreciation to the officials concerned of the Government of the State of Eritrea for their close cooperation extended to the teams.

July, 1997

Tinto

Kimio Fujita President Japan International Cooperation Agency

### Letter of Transmittal

We are pleased to submit to you the basic design study report on the Project for the Equipment Supply Program for Road Improvement in the State of Eritrea.


This study was conducted by Construction Project Consultants, Inc., under a contract to JICA, during the period from March 18, 1997 to August 8, 1997. In conducting the study, we have examined the feasibility and rationale of the project with due consideration to the present situation of Eritrea and formulated the most appropriate basic design for the project under Japan's grant aid scheme.

Finally, we hope that this report will contribute to further promotion of the project.

Very truly yours,

anzo hakanu

NAKAMURA Kenzo Project Manager Basic Design Study Team on the Project for the Equipment Supply Program for Road Improvement the State of Eritrea



Location Map

## The Project for the Equipment Supply Program for Road Improvement in the State of Eritrea

## Basic Design Study Report

## Table of Contents

Preface Letter of Transmittal Location Map


		Page
Chapter 1.	Background of the Project	1
Chapter 2.	Contents of the Project	3
2.1	Objectives of the Project	3
2.2	Basic Concept of the Project	3
	2.2.1 Mendefera - Barentu Road Rehabilitation Project	3
	2.2.2 Examination of the Contents of The Project	11
2.3	Basic Design	22
	2.3.1 Design Concept	22
1	2.3.2 Basic Design	24
Chapter 3.	Implementation Plan	28
3.1	Implementation Plan	28
: 1	3.1.1 Implementation Concept	28
· · · ·	3.1.2 Implementation Conditions	29
	3.1.3 Scope of Works	29
	3.1.4 Consultants Supervision	30
	3.1.5 Procurement Supervision	31
et i te	3.1.6 Implementation Schedule	32
	3.1.7 Obligation of Recipient Country	32
3.2	Project Cost Estimation	33
	3.2.1 Project Cost Estimation	33
	3.2.2 Management and Maintenance Plan	33
3.3	Operation and Maintenance Costs	34

		Page
Chapter 4.	Project Evaluation and Recommendation	37
4.1	Project Effect	37
4.2	Recommendation	39

## Appendices

- 1. Member List of the Survey Team
- 2. Survey Schedule
- 3. List of Party Concerned in Eritrea
- 4. Minutes of Discussions
- 5. Cost Estimation Borne by the Eritrean Side

# CHAPTER 1 BACKGROUND OF THE PROJECT



#### Chapter 1. Background of the Project

Since its independence in 1993 the Government of Eritrea has been exerting its maximum efforts for the recovery and firm establishment of the country. The Government implemented the Recovery and Rehabilitation Program in Eritrea (RRPE) in 1993, in which the recovery of production capacity and infrastructure are given the highest priority.

In spite of the fact that road transport shares 98% of the total transportation in the country for passenger and freight traffic, the condition of the road network is far below the required standards. Of a total 5,964 km of classified road network, only 8.4% are asphalt paved. Destruction and lack of appropriate maintenance during the war aggravated the situation, and the present condition is critical. The roads which are considered in comparatively fair condition now are only the Asmara - Massawa road and some limited sections of the most important trunk roads.

The Road Department, Ministry of Construction, has established the road program for the short, medium and long term in order of priority according to urgency. The short term program covers the most important trunk roads which need urgent rehabilitation to maintain traffic flow. On the other hand the medium and long term program covers the east-west and north-south trunk roads which are essential for the development of the national economy.

The targetted Mendefera-Barentu road forms a principal section of the east-west corridor (southern route) from the sea port Massawa to the Sudan border via Asmara, capital of Eritrea. The northern route, connecting Massawa, Asmara, Keren, Akrodat, then joins the Mendefera - Barentu road at Barentu. The rehabilitation project for the northern route is ongoing from Asmara up to 40 km beyond Keren, but the remaining 115 km up to Barentu is a completely deteriorated Macadam road, of which only 10-20 km/h is passable by 4WD. Regarding the southern route, the paved sections, i.e., Asmara - Mendefera section by DBST (Double Bituminous Surface Treatments) and from Mendefera the first 100 km of natural gravel are rather fair, but the remaining 100 km are not passable during rain. From Barentu to Tesseni (Sudan border) not only is the pavement in critical condition, passable only at 10-20 km/h by 4WD, but also retaining structure and several bridges are broken or have completely collapsed. Therefore, there is no reliable access to Sudan at present.

The Mendefera-Barentu road traverses the western lowlands which have high potentiality for agricultural development because of proper rainfall and moderate temperature, particularly for the cultivation of export oriented crops. The area is envisaged for the settlement of returned refugees from neighboring countries. To enable reliable access to Sudan for both passenger and freight, traffic and consequently to stimulate industries (textile, cement,

- 1 -

fishery, etc.) and also the transportation business, the rehabilitation of the targetted road together with the Massawa-Asmara road and the Barentu-Tessency road have been given the highest priority by the Government.


The project was implemented in 1994 financed by the Government's own fund on force account basis. Of a total of 200 km, approximately 100 km of base course has been completed to date. The Government has allocated considerable resources to this project, e.g. intensive labor from National Service, intending to complete the project by the year 2000. However, due to lack of appropriate construction equipment, progress has been seriously hindered.

Under these circumstances, the Government of Eritrea requested the following construction equipment from the Government of Japan to accelerate the progress and to complete the Mendefera-Barentu road project.

Motor grader (8 units), Bulldozer (7 units), Wheel loader (10 units), Road Roller (8 units), Dump Truck (10 units), Asphalt Distributor (4 units), Water Tanker (8 units), Fuel Tanker (8 units), Mobile Workshop (5 units), Pick-up truck (10 units) and Flat-bed Truck (2 units).

- 2

# CHAPTER 2 CONTENTS OF THE PROJECT



#### Chapter 2. Contents of the Project

#### 2.1 Objectives of the Project

The Mendefera - Barentu road forms a principal section of the east-west corridor (southern route) from sea port Massawa to the Sudan border via Asmara, capital of Eritrea. The road traverses the western lowlands which have high potentiality for agricultural development, particularly for the cultivation of export oriented crops. The area is envisaged for settlement of returned refugees from neighboring countries.

As reliable accessibility from the center to rural areas and also to neighboring countries is essential for the socio-economic recovery of the country, the Government of Eritrea has placed the highest priority on the rehabilitation of this road. The project was implemented in 1994 financed by the Government's own fund on force account basis. Of a total of 200 km, approximately 100 km of subbase course has been completed to date.

The Government has allocated considerable resources to this project, e.g. intensive labor from National Service, intending to complete the project by the year 2000. However, due to lack of appropriate construction equipment, progress is being hindered.

The objectives of the Project for the Equipment Supply Program for Road Improvement in the State of Eritrea (hereinafter referred to as "The Project") are to assist the Road Department of the Ministry of Construction to accelerate the on-going Mendefera - Barentu road rehabilitation project through the provision of construction machinery to increase its capacity of execution.

#### 2.2 Basic Concept of the Project

- 2.2.1 Mendefera Barentu Road Rehabilitation Project
- (1) Status of the Mendefera Barentu Road Rehabilitation Project

The project comprises three phases, i.e.:

Phase 1:	10 J I	CI 11	<b>D !</b>	Charles and	Other structures
	しっきもれれんそして	NUMBARA PA1170	* ארזממפ	I INVETT	I HEAT SITUCILITES
FRASE I	PAILIWORK.	SHUDDASE COULS	, DIMEN.	Cuivort.	

Phase 2: Base course, Double bitumen surface treatment (DBST), Shoulder, Ancillaries

Phase 3: Asphalt concrete (according to the future traffic increase)

Preparatory work was started in 1993. In the middle of 1994, after receiving an allocation of available equipment, earthwork was started. Of a total of 200 km,

some 100 km of subbase course has been completed to date. (Of which 40 km is categorized as "rehabilitation" and 60 km as "new construction or improvement".) The Government of Eritrea intends to complete Phase 1 for the remaining 100 km by the beginning of 1999, and Phase 2 for the total 200 km by the end of 2000.

Thus, the remaining works which will be covered by the equipment to be supplied under the Project are summarized as follows:

Phase 1 works:from May - lam to Barentu (100 km)Phase 2 works:from Mendefera to Barentu (200 km)

#### (2) Road Structure

As there is no detailed data regarding subgrade strength and traffic volume on the project road, the results of the feasibility study conducted in 1994 were referred to in this study as follows:

1) Cross Section

Carriageway width	3.5 m	2-lanes
Shoulder width	1.5 m	both sides

2) Pavement Structure

According to the feasibility study subgrade material with CBR > 30 is available along the entire section of the road. Traffic volume (AADT) is estimated at 60 with a growth rate of 4 - 5% per year. Under these conditions British standards for tropical area "Road Note" can be applied, thus the pavement structure will have the following characteristics:

Surface course	DBST	3 cm
Base course	Crushed stone	15 cm
Subgrade	Natural gravel	(CBR > 30)

Regarding surface course, asphalt concrete overlay may be constructed in future if the traffic volume on the road increases significantly.

#### Estimation of Work Volume

For the estimate of work volume, the feasibility study and achievement of work to date were referred to in this study. A comparison of the estimate by this study, the Road Department and the feasibility study is shown in Table 2.1.

Cross section used for the estimate of surface course and base course is shown in Fig. 2.1 and that for earthwork volume in Fig. 2.2. Assumptions adopted for the estimates are summarized as follows:

1) Clearing

For 100 km with clearing width and depth of 15 m and 20 cm, respectively.

- 2) Earthwork
  - Of a total of 100 km of the remaining section, 75 km to be cut/fill section and 25 km to be fill section.
  - Of a total of 975,000 m<sup>3</sup> of excavation, 780,000 m<sup>3</sup> (80%) to be general excavation and 195,000 m<sup>3</sup> (20%) to be rock excavation, for which excavation by ripdozer is possible.
  - Of a total of 950,000 m<sup>3</sup> of embankment, 600,000 m<sup>3</sup> by road cutting soil (180,000 m<sup>3</sup> with 1 km of hauling distance and 420,000 m<sup>3</sup> without hauling), and 350,000 m<sup>3</sup> by borrow with 2 km of hauling distance.
- 3) Subgrade preparation

For 200 km.

4) Subbase course

As the CBR of the subgrade material has a CBR > 30, and this material is available over the whole section, and the traffic volume is low at present, this layer may be omitted (Road Note).

- 5

5) Base course

For 200 km with a thickness of 15 cm.

(3)

6) DBST surface course

For 200 km with carriageway width and thickness of 7 m and 3 cm, respectively.

7) Bridges, box culverts and other structures and ancillaries

Estimate by Road Department

Detailed volume will be determined by the D/D, which is programmed for Mendefera - Barentu and Keren - Akrodat - Barentu - Tesseni (Sudan border) roads with finance assistance from IDA. It is probable that the estimate made by this study deviates from the results of D/D on the following points:

Volume of base course - In the case where the expected subgrade material below CBR 30 is available the thickness needs to be increased, thus the volume increases accordingly.


Regarding earthwork volume, after detailed survey it is more likely to increase.


In conclusion, regarding the equipment schedule to be proposed by this study, the equipment type is considered appropriate. Also, it is not likely that the equipment number will exceed the requirement which will be derived from the result of D/D.

Table 2.1 Estimation of Work Volume

2,062,560 1,355,919 677,959 (Base&Subbase) by FS (Cut&Fill) (TBST) 20,000 80,000 100,000 300,000 400 60,000 750,000 000'06 750,000 3,500 14,000 3,000 99,700 25,000 500,000 700,000 315,000 750,000 2,500,000 2,400,000 Scheduled 100 km by Road Department ł I Achievement 26,730 l ł I 122,488 175,000 9,200 8,500 ١ 1 I 450,000 543,636 568,000 100 km  $10.45\,\mathrm{m} \times 15\,\mathrm{cm} \times 200\,\mathrm{km}$  $1.261 \times 7.5 \text{m} \times 200 \text{km}$  $13m^3 \times 75km \times 80\%$  $13m^3 \times 75km \times 20\%$ Remarks  $10.9 \mathrm{m}^2 imes 100 \mathrm{km}$ by Road Dep.  $15m \times 100 km$ by Road Dep.  $14m^3 \times 25 km$ by Road Dep.  $7.0 \times 200 \mathrm{km}$  $8m^3 \times 75 km$ Estimation by the Basic Design Study 20cm 14,000 3,000 99,700 25,000 20,000 80,000 400 300,000 780,000 195,000 600,000 1,400,000300,000 1,890,000 3,500 313,500 1,500,000 350,000 1,090,000 Total t 1,500 25,000 20,000 80,000 400 ı 313,500 1,400,000L 300,000 1 1 ۱ I 1,890,000 I 1,090,000 Phase 2 200km 1 I 1 ł 1 3,000 98,200 780,000 195,000 600,000 350,000 ł ł Т 3,500 300,000 1,500,000 Phase 1 (00km Unit m<sup>2</sup> kg m<sup>3</sup> ш<sup>3</sup>  $m^2$ Unit n<sup>3</sup> n<sup>3</sup> m3 Ħ n n m³  $m^2$ a "a <del>х</del> 9 'n BB Retaining Wall (Masonry) - Filling from cutting - Filling from borrow - AC (Wearing layer) Subgrade Preparation Work Category Concrete Structure - AC (Base layer) Subbase Course -Plain concrete Surface Course Road Marking - General soil - Prime Coat Road Cutting - Boxculvert Ditch Lining **Road Filling** Base Course Traffic Sign - Tackcoat (Stripping) - Bridge Guardrail - DBST Clearing - Rock Filter ~ 14. Item <del>ن</del> ø 13. 4 vi φ 10. 12. ÷ નં en. Ш.

- 7 -





- 8 -

2

#### Construction Schedule

(5)

Available resources (funds and workforce) of the Road Department are one of the determinants for construction period, i.e. the period necessary for the completion of Phase 2 for all sections. Since the start of this road project in 1994 about Birr 93 million, including engineering costs were allocated for the project. This means that about Birr 31 million were disbursed annually in the last three years. On the other hand, the necessary funding required for the completion is estimated at about Birr 410 million of which savings due to this equipment supply program are estimated at about Birr 105-125 million. Thus, about Birr 285-305 million is required.

The Eritrean side intends to complete the project by the end of 2000(24 months after introduction of the equipment under the Project). According to its schedule, Birr 140-150 million is required annually, i.e., about 5 times the achievement of the last three years. The same applies to the workforce.

The Government confirms that resources will be allocated to this road project with the highest priority. However, considering the present situation of the road sector, where many projects are being implemented, it seems difficult to expect such an available workforce in the near future. This basic design study considers that assuming a workforce about 2.5 to 3 times the present workforce is reasonable.

On the other hand, from the view-point of work productivity during the last three years, the appropriate period can be derived as follows:

Period for completion of Phase 1 (remaining 100 km)

Of the 100 km of completed section only 60 km is considered as new construction or improvement. Thus the average progress during 36 months is estimated at 1.7 km/month. Provided the same productivity is maintained, it takes 60 months for the completion. On the other hand, through the introduction of new equipment under the Project it is possible to upgrade the productivity by 1.5 to 2 times the present level, i.e. Phase 1 can be completed in 36 months. Estimate by work item of Phase 1 is as follows:

- 9 -

			Achiever	nent		Estimated month	
Work item	Estimated Quantity	Q' ty	Months elapsed	Productivity per month	by Present Productivity	Increase of Productivity	by Increased Productivity
Clearing	1,500,000 m <sup>2</sup>	568,000 m²	18	31,556 m²/month	48 months	2.0	24 months
Cutting	975,000 m <sup>3</sup>	666,124 m <sup>3</sup>	36	18,503 m³/month	53 months	1.5	36 months
Filling (including borrow)	950,000 m <sup>3</sup>	450,000 m <sup>3</sup>	36	12,500 m³/month	76 months	2.1	36 months

Table 2.2 Construction Period Estimate

Period for Phase 2 (200 km)

Phase 2 can be started soon after the delivery of the equipment under the Project starting from the completed section of Phase 1. In other words it is necessary to start Phase 2 as soon as possible from the view-point of protecting completed sections of subgrade from deterioration and reducing maintenance costs. For this reason the same productivity as phase 1 is required, i.e. it is necessary to complete in 36 months in parallel with the Phase 1 work.

**Total Period** 

Considering the above mentioned 36 months for both Phase 1 and Phase 2 works a total period of 40 months is required as shown in Fig. 2.3.

Work Item	1st Year	2nd Ycar	3rd Year	4th Year
		Total period:	40 months	
Phase 1				
Clearing Earthwork/Cutting			(24 m)	- (36 m)
/Filling				(36 m)
Subgrade				(36 m)
Bridge & Structure			(24 m)	
Phasde 2				
Base Course		·		(36 m)
DBST Surface				(30 m)
Ancillaries				(12 m)

#### Fig. 2.3 Construction Schedule

- 10 -

### 2.2.2 Examination of the Content of the Project

(1) Examination of the Equipment Schedule

Through the discussion with the basic design study team the Eritrea side proposed a revised equipment schedule to the original request in respect of equipment type and number, because of the progress of work achieved since the above mentioned original request. Individual equipment requested by the revised schedule was examined by this study in view point of construction schedule, present performance of work and achievement to date.

Most of the equipment in the original request is categorized as for earthwork, although type and number is not necessarily balanced. Since then, several types of equipment for earthwork were procured under Government funding during the last three years. But the equipment available on site is below the requirement for completion of the remaining works of Phase 1. Moreover, there is no equipment available for Phase 2 works, such as stone crusher, asphalt distributor, chip spreader, etc.

The result of discussions and examination with the Eritrean side is summarized in Table 2.3.

#### (2) Equipment Schedule

1) Examination of the equipment required

The following steps were taken for determination of equipment type and number:

- Determine equipment type for every work category and calculate productivity of the equipment considering site conditions.
- Divide the estimated work volume by the above productivity and possible work days/hours during the work period to get gross equipment number required.
- Scheduling the equipment by work category with bar-chart.
- Derive the least required number of equipment.

The calculation is summarized in Table 2.4 to Table 2.5.

### 2) Equipment Schedule

The equipment number to be supplied under the Project was derived by deducting the existing number from the above mentioned least required number. The result is shown in Table 2.6.

			:										• .														·····				
Uses (U) and Reason of Selection (R)	· [	U: Spreading and grading of base course and stope		R: High power is necessary for works in rocky and	high altitude areas. Steel cabin for protection	from dust.	U: Earth, quarry and borrow pit excavation	R: Unified to 220-235 HP class below.	U: Earth, quarry and borrow pit excavation	R: High power is necessary for works in rocky and	high altitude areas. Steel cabin for protection	from dust.	U: Loading of excavated soil, blasted or crushed rock	R: 3.5m <sup>3</sup> bucket volume for speedy operation with	dump trucks of 9m <sup>3</sup> capacity.	U: Structural excavation	R: Wheel type for fast movement on site and 150 HP	for hard earth. Hydraulic breaker is cancelled due	to minor use of rock digging.	U: Soil stabilization with cement, lime or bitumen.	R: Deleted due to surcharge banking which is more	recommendable for an embankment of soft ground	than stabilization using agents.	U: Compaction of embanked soil, base material and	backfilled soil.	R: 10 ton class is suitable for wide compacting on	base course.		R: 9.5 ton is the most popular standard widely	manufactured.	
Nos.	ı	Ś							4				9			1						•		3				4		•	
ough Discussion		200-220HP	4.3m <sup>2</sup>	Steel cab.		•			220-235HP	Ripper	ROPS	· · ·	200-220HP	3.5m <sup>3</sup>	Steel cab.	150HP class	$0.7m^3$		:				-	10ton class	Front drum	with Water	Sprayer	9.5ton class	Front/Rear	drum with	Water Sprayer
Amended Request through Discussion		Motor Grader					- to be omitted -		Bulldozer				Wheel Loader			Wheel type Hyd. Excavator	Wheel type			- to be omitted -				Vibration roller				Vibration roller			
Nor	-2011	ν. ·					2		5				6			-				1				5				4	-		
E	E	200HP	•				320HP		220HP		· ·.		220HP			or 0.7m <sup>3</sup>				355HP				Ston	Front drum	with Water	Sprayer	10ton	Front/Rear	drum with	Water Sprayer
Domot Dofine Discussion	kequest betote Liscussion	Motor Grader					Bulldover	TAZODIMOT	Rulldozer			· · · · · · · · · · · · · · · · · · ·	Wheel Loader			Wheel type Hvd. Excavator	with Hvd. Breaker			Stabilizer	Wheel type			Vibration roller	-			Vibration roller			
	ltem	1.					,	i	4	់			4			5	1			e.	5							ø			

- 13 -

Nos. Uses (U) and Reason of Selection (R)	16 U: Transport of excavated earth, base material, blasted nock and chin for surface course.	R: 16m <sup>2</sup> lorry is considered inadequate for transport on	public roads in Eritrea and 9m <sup>3</sup> is the largest size	widely manufactured as on-road type.	6 U: Water pumping, transport and sprinking for earth	and rock material compaction.	R: Larger truck capacity is economical for long	distance hauling due to remote water resources.	1 U: Transport of fuel from Massawa to the site,	approx. 300 km.	R: Two days for a return trip and max. daily fuel	consumption 8,000 lit. on site.	2 U: Distribution of fuel from base camp to equipment	is a site straight and a site of the second site of	R: Two directions to job site from base camp and	max. daily consumption of 8,000 lit.	2 U: Boiled bitumen spreading for surface course.	R: Average daily use of heated bitumen by a surfacing	brigade is 12,000 lit. then 2 return trips from	asphalt boiler to the site a day on 30 km hauling.	1 U: Bitumen heating and storage for surface course.	R: Average daily use of boiled bitumen is 16,000 lit.	Short boiling time for 6,000 lit. bitumen is	required for loading to distributor.	2 U: Chip laying for surface course.	R: Halfway surfacing requires max. 4.0 m width	(3.5  m + 0.5  m  widening on curves)
Amended Request through Discussion N	Dump truck 9m <sup>3</sup> , 6x4				Water Tanker Truck 12000 lt				Fuel Tanker Truck 16000 lt				Fuel Tanker Truck 8000 lt		· · · · · · · · · · · · · · · · · · ·		Asphalt Distributor 6000 lt				Asphalt Boiler 6000 lt	with Storage Tank 16000 lt			Chip Spreader Self propelled	Spreading width 4m	
Request Before Discussion Nos.	truck 16m3 9				Water Tanker Truck 12000 lt 6				Fuel Tanker Truck 18000 lt 2			•	Fuel Tanker Truck 12000 lt 2				Asphalt Distributor 12000 It 2				Asphalt Boiler 6000 It 2	with Strong Tank 16000 lt	)		Chip Spreader Self propelled 2	Spreading width 4m	6m3
Item Reque	9. Dump truck		· · · ·		10. Water			· · ·	11. Fuel T				12. Fuel T				13. Asphal				14. Aspha	with S			15. Chip S	Spread	Honner

- 14 -

( ; ; ;	of Selection (K)	oment ong, motorgrader, and oldozer define the traik pe is necessary due to l ublic roads.	and light repair of ion from base camp. driver, two mechanics z capacity of 500 kg i or tools and spare part	ggregate for base and n capacity of 120 ton 0 ton/hr is ction of number of is is more suitable the 4 relocations of crush	to dump trucks. ng and 150 HP for essary for secondary r. uctural foundation and iddle size boulder. econdary cracking.	n/min. for crawler dril
	Uses (U) and Reason of Selection (K)	Transport of heavy equipment The largest size of 8m long, motorgrader, and heaviest weight of 38t bulldozer define the trailer's capacity, and low bed type is necessary due to low clearance of bridges on public roads.	Inspection of conditions and light repair of equipment on site. Two cars for each direction from base camp. Four seats required for a driver, two mechanics and a service man. Loading capacity of 500 kg is minimum requirement for tools and spare parts.	Production of crushed aggregate for base and surface course. Average daily production capacity of 120 ton is required. One set of 120 ton/hr is recommendable for reduction of number of quarrying equipment. Mobile crusher on wheels is more suitable than self-propelled type for 3-4 relocations of crushing	Loading of blasted rock to dump trucks. Loading of blasted rock to dump trucks. 1.0 m <sup>3</sup> bucket for loading and 150 HP for hydraulic breaker is necessary for secondary cracking of large boulder. Rock excavation for structural foundation and secondary cracking of middle size boulder. Jack hammer 3 set for secondary cracking.	Air compressor of 20 m/min. for crawler drill.
		R: T B T T T T T T T T T T T T T T T T T T	U: II R: 3 1 1			о ж
	Nos.	<b>-</b> -1	ব			-
		40ton 8m	4x4 Double cab	120t/h	150HP class 1.0m <sup>3</sup> Hyd. Breaker 7.5m <sup>3</sup> /min	5.0ton 5.0ton
	Amended Request through Discussion	Lowbed Trailer Tractor Bed length	Pickup Truck	Mobile Rock Crusher Mobile type screen: 40,25,19,10,5mm	Hydraulic Excavator Crawler type Air Compressor Jack Hammer x 3 sets	Crawler Drill with Air Compressor
	Nos.		4	8	0 0	
	: 	60ton	4x4 85HP	150HP 0-70mm 60t/h	150HP 22t 1.0m3 small size	30-84mm
	Request Before Discussion	Lowbed Trailer Tractor	Pickup Truck	Mobile Rock Crusher Self propelled crawler type Secondary crusher screen: 25, 19, 10,5mm with Generator and Belt conveyer	Hydraulic Excavator Crawler type Air Compressor Jack Hammer x 3 sets	Crawler Drill with Air Compressor
	ltem	19	17	<sup>1</sup> Si	20.	21.

- 15 -

Installation of pre-casted concrete slabs for drainage For site offices and accommodations at base camp Cancelled because the Road Department is able to Remarks: A weighted average of 8.0% of the total cost team. Hand tools, welders, repair tools for tires construction, at least 100 kVA power is required. dismantling, and loading and unloading of heavy 4 x 4 type truck with 6 ton loading capacity is Site garage is to be arranged by the construction of equipment above is considered sufficient structures, stone crushing plant assembling and Progress/quality control of the works and spare The capacity of 25 ton lifting at 3.0 m boom For the workshop and garages at base camp of Grease up and changing for equipment on site. equipment on rough surface site conditions. required for grease supply for a number of Uses (U) and Reason of Selection (R) for 1~2 years equipment operation. 30 kVA power is considered adequate. Replaced to service cars, item 17. Repair of equipment on site. goods and materials. radius is required. At base camp At base camp are included. parts filing. arrange. Ъ. ы К ä ä 5 ä ыä ы Ж ü ä Nos. 8% 2 Amended Request through Discussion 100KVA 30KVA 25ton 6ton - to be omitted 4X4 - to be omitted Lubrication Truck Repair Tool Sets for site camp Truck Crane for garage Spare parts Generator Generator 15% Nos. 3 ŝ 2 18KW 80KW 25ton 4x2 Request Before Discussion Garage facilities and tools Pre-fabrication garage Container for tools Material for garage Personal Computer Mobile Workshop Lubrication Truck for site camp Truck Crane with printer Spare parts for garage Generator Generator Item 25. 27. 22. 23. 24. 26. 28. 29.

- 16 -

.

# Table 2.4 Equipment Required by Work Item

Work Category		Equipment	Spec.	Quantity	Unit	Productivity /unit/h	Total hrs required unit-h	Total months		Numbe require
Dearing	Excavation	Bulldozer	28-30 t	300,000	m <sup>3</sup>	168.7	1,778	18	24	1
Journe	Loading	Wheel Loader	3.5 m <sup>3</sup>	60,000	m <sup>3</sup>	119.2	503	5	24	· · · _
	Transport	Dump Truck	14 t	12,000	m <sup>3</sup>	22.1	543	- 5	24	· _
and the second second	Disposing	Bulldozer	28 - 30 t	2,400	m <sup>3</sup>	168.7	14	0	24	
Cutting Soil	Excavation	Bulldozer	28 - 30 t	780,000	m <sup>3</sup>	168.7	4,624	46	36	1
	Loading	Wheel Loader	3.5m <sup>3</sup>	180,000	m <sup>3</sup>	119.2	1,510	15	36	1
	Transport	Dump Truck	14 t	180,000	m <sup>3</sup>	22.1	8,145	81	36	2
Rock	Ripping	Bulldozer	28 - 30 t	195,000	m <sup>3</sup>	53.9	3,618	36	36	1
Filling Borrow	Excavation	Bulldozer	28 - 30 t	350,000	m <sup>3</sup>	151.9	2,304	23	36	1
	Loading	Wheel Loader	3.5 m <sup>3</sup>	350,000	m <sup>3</sup>	107.3	3,262	: 33	36	. 1
	Transport	Dump Truck	14 t	350,000	m <sup>3</sup>	16.0	21,875	219	36	5
Fill	Spreading	Bulldozer	28 - 30 t	950,000	m <sup>3</sup>	104.4	9,100	5 91	36	2
· · · · ·	Compaction	Viv. Roller (F)	10 t	950,000	m <sup>3</sup>	176.4	5,385	54	36	2
	Watering	Water Tanker	12,000 0	76,000	kl	6.3	12,063	121	36	4
Subgrade	Grading	Motor Grader	4.3 m	2,180,000	m <sup>2</sup>	312.5	6,976	70	36	2
	Compaction	Vib. Roller (F)	10 t	2,180,000	m <sup>2</sup>	294.1	7,412	- 74	36	1
a katalan di Kasa	Watering	Water Tanker	12,000 0	52,320	m <sup>3</sup>	6.3	8,305	83	36	2
Ditch · Slope	Shaping	Motor Grader	4.3 m	760,000	. m <sup>2</sup>	384.6	1,976	20	36	1
Base Course	Spreading	Motor Grader	4.3 m	2,090,000	m <sup>2</sup>	312.5	6,688	67	36	2
	Compaction	Vib. Roller (F)	10 t	2,090,000	m <sup>2</sup>	243.9	8,569	86	36	2
and the second	Compaction	Vib. Roller (F/R)	9.5 t	2,090,000	m <sup>2</sup>	243.9	8,569	1	36	2
	Watering	Water Tanker	12,000 0	46,085	m <sup>2</sup>	6.3	7,315	73	36	2
	Loading	Wheel Loader	3.5 m <sup>3</sup>	313,500	m <sup>3</sup>	102.2	3,068		36	1
	Transport	Dump Truck	14 t	313,500	m <sup>3</sup>	10.1	31,040	<b>T</b>	+	8
DBST Surface 1st	Primecoat	Distributor	6,000 0	2,381	kl	1.2	1,985	· 20	30	1
	As Spraying	Distributor	6,000 l	1,610	kℓ	1.1	1,464		1	1
	Loading	Wheel Loader	3.5m <sup>3</sup>	28,000	m <sup>3</sup>	102.2	274	1		
	Transport	Dump Truck	14 t	28,000	m <sup>3</sup>	6.9	4,058	1	30	2
	Chipping	Chip Spreader	(1,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2,2	1,400,000	$m^2$	1,050.0	1,333		30	. • 1
	Compaction	Vib. Roller (F/R)	9,5 t	1,400,000	m <sup>2</sup>	480.0	2,917		30	1
2nd	As Spraying	Distributor	6,000 0	2,100	kl	1.2	1,750			
	Loading	Wheel Loader	3.5 m <sup>3</sup>	14,000	m <sup>3</sup>	102.2	137	1	30	
	Transport	Dump Truck	14 t	14,000	m <sup>3</sup>	6.9	2,029		30	2
an tha an an an air a' th	Chipping	Chip Spreader	0.5.4	1,400,000	m <sup>2</sup> m <sup>2</sup>	1,500.0			30	
	Compaction	Vib. Roller (F/R)	9.5 t	1,400,000	m kl	400.0	1 · · · · ·		30	
	As heating	As Boiler	6,000 Q /h 0.7 m <sup>3</sup>	6,091	m <sup>3</sup>	*·		12	24	· · · · · · · · · · · · · · · · · · ·
Culvert	Excavation	Wheel Excavator	$0.7 \text{ m}^3$	47,000		37.0	1,270	13	24	
Bridge	Rock Excava.	Air Compressor Truck Crane	7.5 m <sup>-</sup> /min 25 t		_	-	-	- 1	24	
Structure	Lifting Transport	Wheel Loader	$3.5 \text{ m}^3$						24	
Borrow	Excavation	Bulldozer	28 - 30 t	47,000	m <sup>3</sup>	151.9	309	3		
DOILOW	Loading	Wheel Loader	3.5 m'	47,000	m <sup>3</sup>	107.3	1		24	
	Transport	Dump Truck	14 t	47,000	m <sup>3</sup>	16.0			24	_
	Backfilling	Bulldozer	28 - 30 t	47,000	m <sup>3</sup>	87.6				1
	Compaction	Vib. Roller (F)	10 t	47,000	m <sup>3</sup>	176.4	1	1		
Concrete	Mixing	Mixing Truck	4.5 m <sup>3</sup>	20,500		3,4			_	
Production	Loading	Wheel Loader	3.5 m <sup>3</sup>	20,500	m <sup>3</sup>	112.4	182		1 .	-
	Transport a	Dump Truck	14 t	20,500	m <sup>3</sup>	22.1	928			
	Transport s	Dump Truck	14 t	20,500	1 0	22.1	928	9	24	<u> </u>
Quarry	Drilling	Crawler Drill	5 t	541,440	m <sup>3</sup>	76.9	7,041	70	40	
	Drilling	Air Compressor	20 m <sup>3</sup> /min	541,440	m <sup>3</sup>	74.1				
	Breaking	Hyd. Excavator	1.0 m <sup>3</sup>	451,200	m <sup>3</sup>	76.9			1	1
	Breaking	Hyd. Breaker		451,200		76.9		1	40	Į
	Ripping	Bulldozer	28 - 30 t	451,200	m <sup>3</sup>	53.9		8	40	
	Loading	Wheel Loader	3.5 m <sup>3</sup>	451,200	m <sup>3</sup>	85.1	5,302			
	Transport	Dump Truck	14 t	451,200		14.7			40	
Crushed Stone	Production	Rock Crusher	120 t/h	376,000	m <sup>3</sup>	1.08.0	3,481	35	40	
and a second	Loading	Wheel Loader	3.5 m <sup>3</sup>	376,000		102.2				
Transport	Material	Pick-up Truck	9 7 B++7°		- 1	- · · -	-		40	
	Fuel	Fuel Tanker	16,000 0	1 - 12 - <u>1</u>		1 10 14	1	·   . –	40	
1	Fuel	Fuel Tanker	8,000 0	1 <u>-</u>	<u> </u>			· · ·	40	
i de la companya de l		Lowbed Trailer	40 t	- 200 ° <u>-</u>					40	
	Equipment									
	Equipment Oil-Lubrica.					l di seri L	- 10 L L L L _	· -	40	
Panjoment	Oil-Lubrica.	Lub. Truck	<u>6t</u>	-						
Equipment Maintenance									40 40 40	)

- 17 -

1	16	ç	505		ñ ñ	8 A	55	2 2	8	6 2	<b>7</b> 7	F 8	889	8 8	<u>응</u> 음	8,	, <u>R</u>	888	2 2	2 2	1.1	. 2	· ·			1.1							
1	12		***	8	<b>a</b> a	<u>8</u> R	4 1	28	2 2	8 F	E E	2 2	8 8	8	88	<b>8</b> ,	3	888	2 2	* *	1 1	1, 57		74	\$ \$	2 2	\$ 2 \$	240	<b>ç</b> ç	<u>8</u> 9	29	98	\$ \$
	\$									-		· .	1	····;																			
	F																																:
	Ş												<u> </u>	:																			
	\$ \$				:			14. 					·[														·						~
	-			-						-				<u>.</u>				- <u> </u>				<u> </u>	-		-						<del>.</del>	╞	- 12
9 49	¥										• .	·									- <u>`</u>		-		1			с. С					
	Ŧ	1.0									1	· · · .			<u>.</u>															L	• •		
	Ŷ								·	L	 <u></u> .			• ••	** **		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~				• • •						- N		1	<b>*</b> -	- 10 -		
	8			<u>.</u>					~ -	2	<u> </u>	~ ~ ~			n		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~					- <u></u>			+			- •		+ -	- 0	~. •	
	5		· · ·	N -		40 N		N =	~ ~	- 14		~ ~ •			~ ~	-									┤═╴					+ -	- N -	"	~
	36			N -		-0 -0	2 63 4	~ 7	~ -	- 14	N N	N	•	-		-	2		 	1.1.1							- ~ ·			+ -	· N -		
	35	····		N -		<b>W</b> N		~ ~	~ -	~	~ ~	N - I			~ ~		2				1.	4.5				~ ~				* -		•	
	8			~ -		5 6	• • •	м -	~ -		N N	N = 1	•	-	N	-	7					• •		· :			- ~ ·			• -			~ •
	33			N **	*	5 0	+ e4 ==	2 1	N 1	- 11	N N				0 F	-	2		ļ			* 4 4 		- 1911 <del>- 1</del> 911								~	
	1 32			N *		50				- 2		N			~ - ~	_	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	· · · ·	<u> </u>				+-		┤╤╌			- •		+ -		~ ~	
9) -	00			N		50 60	• • •	- 2	~	- ~	<b>N</b> N	~ - •			ci -	-											- ~ ~			• -	- ~ ~	~ •	P+ .
- F	59		-4-	N ~		50 64	2 CI 4	N -	•	- ~	~ ~	N H I		,	N #	-	3			• •		s.,	1				- 41	- 10		* *	- N -	~	
	28	·				\$	4 14 4		~ .	5	04 N	0 - I			N ~		2								-		- • • •	. 0			· N +-	~ ~	
	27	·		N -		10 61		2		6		~ ~ •			4 5		~			:				191			- * ·	•			· ~ ~	2	
	58 			N -		10 CH	4 N 7	~ ~			N N N N	N F 4			N ₩	~~~~	N														- 01 -		
╍┼┼	5						4 60 4	~ ~	-	- ~	~ ~				~ ~	-	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	· 	0				+				~ ~	8 1		╞╾╴	- N -	N .	
	23 .			7 - 17		50 64	1 (1 4	~ ~	~	- 6	N N	N ~ .			64 -		ы		~ ~		· · · ·		-				- 11	- •		╡╤╶╴	• N 7+	~ .	
	<u>ڊ</u>			~ -		50 6		•• -	~ ~	~ ~	<b>54 67</b>	cv 10			~	-	~		61					-				- *		•	. ~ -	•	
	31			cu —		ю.	4 11 4	~ -	~		C1 64	N -	•		•	-	. •		~ ~				_		-		- ~ .		1	• -	- N -	~	
	20			N ►		K7 K	* * *	~ -		- ~		о <del>с</del>	•		<u>ce</u> ↔				- 11	* *				<u> </u>			- 4 -				- 0 -		
Yoer	1			N -		 	***	2 -	· • • •		0 0 0 0	~~~			~ ~		8												+ -		- ~ -	~	
540	1 18			N -			4 64 74	~ -		- ~					~ ~	-	e.										- ~			* -	- N -	~ ·	
	-	-		N -		50	4 N <del>4</del>	~ ~	~ ~	-	~ ~	~ ~			N **	••••••••••••••••••••••••••••••••••••••	1		- ~		•			-			- 14	1		- *	- 63	~ .	
	5.	-		м -		44 0	1 (1 4	~ ~		~		~ - •			N	-	N	•					-	-			~ ~ ~		1	+ -	- ~ ~	~ .	
	3	-		N -		50 64	4 64 4	~ ~		- ~	~ ~	~ - ~			N -	-	64		- 7					-	-			** *S			- 0 +	~ ·	
- <del> </del>	-			N -		83 6	4 0 4	~ ~	~ ~	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	N H	~ ~ ~			N **		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~					-	╇									~	
	+	-	<u> </u>	N		50 C	4 64 <b>4</b>	2 -		0	N N	N ~ 1			N		. 17 					-	+				- 14				- N -	~ .	 
	-	- · · ·	ļ			50 64	4 01 74	N -		- 0	~ ~	~ - 5							- 11	- +		-						1			- 0 -	2	
11		-		N		50 00	* **	~ ~		- ~	** **	N 1	•						- ~		· .	-	+-	•••							~ ~ ~	~	
	-	⊷ <u>,</u>		N		50 0	4 64 4	- 7		- 14	01 N	N - 1				÷.,			- N			_			-		- N		~ ~		- 64	~ 1	
		-		N -		50 64	4 14 4	N ~		- 2	***	<b>N</b>	·	•					- N	7		-	1		-		- 01						
1	_	-		- 1		10 0	4 14 <b>4</b>	2 - 2			0 0 0 0	8 - 8					-		- 0			-	-							-	- N	~ ~	
1 1	_1_			N -			- es -	en -			24 64	EN 1-											-		+		- 7				~ N ~	~ .	
	-	-		~ -		<b>5</b> 0 e	N 64 74		-	-			1						- 9						-		- 01	- 6		• •	- 01	~	<i></i> ,
	~	н .								T									- 6			·	T		-					• -	- ~ ~	~	~ •
_	•	-						·	_	ſ			ļ									-	_ _	-	-			••••		<b> </b>			
		28-30t 3.5m <sup>5</sup> 14t	26-301 26-301	ő	26-30t 3.5= <sup>5</sup>	ţ	29-301 101 120001	4, 3 <del>4</del>	ş			120001 3. 5a <sup>3</sup>		2 3		چ چ	1. Su <sup>3</sup> 141	9. St	0.72 7.5=%in		26-30t	141 28-301	1	3		20m/min 1. 0m <sup>3</sup> .	28-301		1201/h 3. 5=3	40mb1+ 160001	źż		
90 90 90		26-30t 3.5m5 14t	26-	7 F	- 5° 5	1	- 02 C	5	12		5 10 10 10	120	1000	- 2, 5m3	¥:	8.51 60001	i Si i	8.51	16 <sup>2</sup>	294 3.5	1.5	ž ž	친 물	1.5m <sup>2</sup>	1	8. °.	23-	5 T 2	1201/h 3. 5=3	- 19 19	1000	5	
			· ·	·			~			.	<u>_</u> 2	1		•	:	(R		2	5 5	-					-	ž -				×			Set
Į.		uch .	ter ter .oader	y ret	ter onder	ž,	zer Her (F	Brader Lar (F		Grader Wader	Ser G	Tankar Loader	ruck suter	Londer	ruck Preade	i Ler (F butor	Londer ruck	presde 11er (F	Erev	Crane	Zer	XIII I	Truck	Loader 'r wek	r Dril	apresi cavato	1	Loads	hushe. Loader	1	lanker Trait	n ct	Teol
Equipment		Bulidozer Wheel Lauder Dume Truck	Butidozer Butidozer Mhoel Loader	Dump Truc Buildozer	Bulidozer Wheel Loader	Dumo Truck	Vib. Rolfer (F) Mater Tarker	Mator Grader Vib Bollar(5)	Water Tanker	Notor Greder Notor Grader	Vib. Rolfer (F) Vib. Rolfer (F, R)	Neter Tanker Whoel Leader	<u>Diese Fruck</u> Dietributor	Distributor Wheel Londer	Dump Truck Chip Spreader	Vib. 8ol ler (F. R) Diatr ibutor	Mmeel Londer Dump Truck	Chip Spreader Vib. Roller (F. R)	As doller Wheel Excevator Air Gompressor	Truck Crane	Sulidazer Maai Londar	Dump Truck Buildezer	Vib.Roller(F) Mising Truck	Wheel Loader Duep Truck	Duep Truck Grawler Drifl	Air Compressor Hyd.Excevator	Hyd, Breaker Bul Joozer	Wheel Londer Dump truck	Rock Crusher	Pickrup Truck Fiel Tarker	ruel tanker Fuel Tanker - Lembed Trailer	Lub, Truck	Repair Tool Set
ش	- E		. <u>e</u> '		1		c							2					1		,			 	•						$r \in \mathcal{N}_{1}$		ance.
		Excevetion Loading Transport	<u>Proportion</u> Excevetion Londing	Transport Ripping	Excevation Loading	Transport	Spreading Compaction Matering	Brading Commercian	Hatering	Shapi ar Soread int	Compaction Compaction	Watering Loading	Framsport Pramount	As Spraying Loading	Transport Chipping	Gommention Am Spraying	Loeding Transport	Chisping Compaction	<u>Excevetion</u> Excevetion	Lifting	Ecowetion	Transport Backfililag	<u>Compaction</u> Mixing	Louéing Transport a	Transport Dr i 11 i mg	Breaking	Breeking Ripping	Losding Transport	Production . Londing	Xatorial Fiel	Fuel Esuipment	<u>Oil-Lubrica</u>	Na intenance
		13.	5 II 9					153	3 2	2	33	<b>#</b> ]		<b>د ۽</b>	ដ ច			53	នា ង ទ	- <b>1</b> - 4		122	8 7	46	ř ř	a a	ž ž	⊐ ⊧ 			រ៩ជំ	ö	ai i
fork itee		2.00 2	Cutting Soil		illing Borrow		5			Ditch-Siope Baae Course			Ĕ			. P4	÷ .,		Culvert Deructure	1. 14.	Borrow		\$						Crushed Stane	· .	i en l		Equipment
	- 1	learing of the	1.5		, E		1	aper Jüqe		i i			0857					. 1.	Culvert Ptructur			· ·	Concrete	10	Cuerry	12.1			÷.	Ι.	х. 6 В.		ă,

Table 2.5.1 Examination of Equipment Schedule

- 18 -

Tetal	1	- <u> </u>
	4	
	5	
	4	
	ş	
	Ŧ	
	¥	
	7	
	Ŧ.	NH NO - NN- N
	₽ 	
	<b>5</b> 5	0 55 6 9 4 <mark>2 4 - 9 9 - 9 1 - 1 1 - 1 1 - 1 1 1 - 1 1 1 1</mark>
		N F W K Y W F N N F N F T F F F N F F N F F N F F N F F N F
	-	
	33	NC= 7450-000-00-0 0
	35	N ** *********************************
	33	nr
•	3	****
۲	⊢⊦	N
	┝╼╄	NF# ###################################
5	┝-ŀ	NP
	F.	10 F # 10 4 10 # - N 00 - N
·	R	8
	2	524 545500000000000000000000000000000000
	N	B # F = 6 4 8 4 = 0 0 = 0 = 0 = 4 = = 0 = 0 = 1 = 0 = 0
••	2	10 0 F = 10 4 5 4 F 11 10 - 10 - 4 10 - 10 - 10 - 10 -
1	2	**************************************
÷	Ĩ	3
÷	8	
2nd Yeur	-	
24	-	f4
	Ē	Nor
	15 16	10 % h = 10 % # = 10 10 = 10 = 10 = 10 = 10 = 10 = 10
	1	Nav-8488-999-99-9-99-9-99-9-99
	10	<b>5 目 (* m l) 字 19 章 * N N N N N N P * P * N M M M M * M * N * N * N * N * N * N</b>
	12	
	11	
	10	Nee-0448-4 - 4 0+-01-0
	•	6 * * · · · · · · · · · · · · · · · · ·
	-	
J.	-	
ist Yaur		<u></u>
	\$	
	4	
	Ľ	
	~	
<u> </u>		
		1.3% 1.5% 1.5% 1.5% 1.5% 1.5% 1.5% 1.5% 1.5
	Spec	4.34 28-001 28-001 101 101 122001 122001 122001 122004 10002 12004 10002 12004 10002 12004 10002 12004 10002 12004 10002 10004 10002 10004 10002 10004 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 1000000
	Equipment	Meter Grander Dalladaar Mena Elacareter Mena Elacareter Mena Elacareter VII. Roller (7) Dans Frokker Meter Janker A. Blaterieter A. Blaterieter A. Blaterieter Mete Grunder Meter Grunde
	2	Metar Car Metar Car Massi Lac Messi Lac Messi Lac Messi Lac Metar Tach Metar Tach

able 2.5.2 Examination of Equipment Schedule

- 19 -

Item	Equipment	Main specification	Required equipment	Existing available number	Plan
1	Motor Grader	4.3 m	5		5
2	Bulldozer	28-301	9	5	4
3	Wheel Loader	3.5 m <sup>3</sup>	7	1	6
4	Hydraulic Excavator Wheel type	0.7 m <sup>3</sup>	1		1
5	Vibration Roller (Front drum)	10t	5	2	3
6	Vibration Roller (Front/Rear drum)	9.5t	4		4
. 7 .	Dump Truck	14t	26	10	16
8	Water Truck	12,000 ltr	8	2	6
9	Fuel Tanker Truck	16,000 ltr	1		1
10	Fuel Tanker Truck	8,000 ltr	2		2
11	Asphalt Distributor	6,000 ltr/hr	2		2
12	Asphalt Boiler	6,000 ltr	1		1
13	Chip Spreader (Self propelled)	width 4 m	2		2
14	Low bed Trailer Tractor	40 t	1		1
15	Pick up Truck	double cab.	4		4
16	Mobile Rock Crusher	120 t/h	1		1
17	Hydraulic Excavator Crawler type	1.0 m <sup>3</sup>	1		1
	Hyd. Breaker (attached to Hyd. Excavator)	1,200 kg	(1)		(1)
18	Air Compressor Tractor	7.5 m <sup>3</sup> /min	2		2
19	Crawler Drill	51	1		1
20	Air Compressor	20 m <sup>3</sup> /min	1		1
21	Repair Tool Set		· 1 · 2		1
22	Truck Crane	25 t	1	· · ·	1
23	Lubrication Truck	6 t	2		2
24	Generator for garage	100 KVA	1		1
25	Generator for site camp.	30 KVA	1		1
26	Spare parts		e interest		8%
······	Total	-	90	20	70

Table 2.6 Equipment Schedule

#### 2.2.3 Result of Examination

Through the above examinations the basic concept of the Project formulated is summarized to provide construction equipment necessary for the completion of the Mendefera - Barentu road project phase 1 and phase 2 by year 2002. The works comprise earthwork and structure/bridge work for approximately 100 km, and base course work and DBST surface course for approximately 200 km.

- 21 -

#### 2.3 Basic Design

#### 2.3.1 Design Concept

(1) Natural Condition

Climatic condition of the project area is semi-arid with altitude 1,000-2,000m above sea level. Annual average rainfall ranges 500 - 700 mm, and annual average temperature 20-30°c. Topography of the project site is steep mountainous or hilly. Geologically, rocky and conglomerate layers are observed. Therefore, high altitude, desert, severe and dangerous conditions shall be considered for the equipment specification.

(2) Capability of work execution and equipment maintenance of the Road Department

Through examination of the achievement of approximately 100 km from Mendefera to Mai-Lam, where difficult natural and transport conditions pertain, it can be said that the capability of the Road Department for the execution of civil work, equipment maintenance and management is adequate.

Implementation of road projects-except routine maintenance-is directly controlled by the Operation Division of the Road Department. A site office is established for each project. In the case of Mendefera - Barentu road project the existing Maidema office will be strengthened.

As for equipment maintenance, regular maintenance such as daily check, preventive maintenance, replacement of worn parts, and other minor repair work are carried out on site. For this purpose a mobile workshop is now attached to Mai-Lam camp (middle point of the project road.). In case the cause of defects can not be identified on site, mechanics will be despatched from the Road Department Mendefera Office to the site for investigation. If necessary, the equipment can be transported to the Central Workshop in Asmara for repair.

In general, it can be said that the equipment is well managed and maintained, so that all equipment including old types are in good condition or remain repairable.

- 22 -

(3)

(4)

#### Criteria for Selection of the Equipment

The equipment was selected as follows:

- Although the Eritrean side requested large sizes for all equipment, this is not always appropriate from the view-point of work efficiency on site. It is important that equipment combinations are balanced among themselves. Accordingly, a reasonable combination is one of the most important factors for the selection of model and number.
  - Although the Eritrean side requested a large size off-road type vehicle, this causes severe damage to the road structure. Accordingly, the largest size on-road type vehicle was selected.
  - As for spare parts, consumable parts and regular maintenance parts were given priority. Regarding other spare parts, an appropriate ratio to the cost of equipment was set out.

Criteria on Country of Origin of the Equipment

1) Equipment to be procured from Japan

Criteria on country of origin is as follows:

- Product Qualities
- Parts service system/organization
- Eligible third countries to be US, UK, Germany & Sweden
- 2) Equipment to be procured in Eritrea
  - Nothing due to lack of production and availability
- (5) Criteria for Procurement Schedule

Although the Eritrean side intends to complete Phase 2 for all 200km by year 2000, the basic design set out a 40 months construction period after delivery of the equipment. Based on this construction schedule all the equipment to be supplied under the Project will be operated soon after delivery.

- 23 -

Therefore, the equipment procurement schedule shall be completed in 12 months.

#### (6)Criteria for Hand-over

All the equipment to be procured under the Project will be imported at Massawa port, Place of hand-over for all equipment will be then transported to Asmara by road. Road Department in Asmara. Transport from Asmara to the construction site is the responsibility of the Eritrean Government.

Maximum draft of Massawa port is 8.5 - 8.7 m, therefore 20,000 - 25,000 ton class vessel is possible. However, the unloading facilities have insufficient capacity for unloading 30 ton class construction equipment such as bulldozer. Therefore, such equipment will be trans-shipped to a vessel equipped with derrick crane at Assab (Eritrea), Djibuti (Djibuti)or Jeddah (Saudi Arabia) ports.

#### 2.3.2 **Basic Design**

#### (1)**Design Policy**

The work units to be formed by the equipment under the Project will be as follows:

			1 - C - A - C		and the second second	5 St. 19
Work category		Number of units	Operator	Driver	Mechanic	Worker
Clearing work		1	1			20
Road Cutting	General excavation	1	2	2		20
	Rock excavation	1 .	1			20
Road Filling	Embankment	1	4	4		20
	Borrow excavation	2	2	5	a an th	10
Subgrade Preparation		2	3	2		50
Side ditch/slope shaping	· ·	1	1		the second	20
Base course		- 2	9	8		50
Surface course	1st layer	1	3	4		30
· · · · · · · ·	2nd layer	1	2	2		30
	Asphalt Boiler	1	1			20
Bridge, culvert & structu	ire	1	6			200
Cement concrete produc	tion (site camp)	1		1	at an	20
Stone quarry	· · · ·	1	7	6	4.10	10
Crushing plant		1	2			20
Transport service (site c	amp)	1		10	anna Chailte Mhail	20
Maintenance service (sit	e camp)	1	3		5	20
	Tota	l 19	. 47	44	5	580

24

Outline of the construction activities by the above mentioned work units will be as follows:

Earthwork will be continued up to Barentu (PK200) together with the existing unit. Regarding bridge, culvert and structure works, the work efficiency and safety will be upgraded significantly, such as excavation, lifting and placing of RC slab or stones for masonry work.

Base course work will be started from Mendefera (PK0) soon after the production of crushed stone, which will be produced by the stone crusher to be introduced under the Project.

Crushing plant will be established near quarries which will be developed along the route in parallel with work progress. Several possible locations for quarries are being examined by the Road Department. Of these, locations near PK50 and PK150 are considered appropriate from the view-point of hauling distance (approximately 25km).

Preparatory works such as clearing, construction of foundations and other related facilities will be started in accordance with the equipment supply schedule, which will enable the crusher to be set-up soon after its delivery.

(2) Equipment plan

Deployment schedule of the equipment to be supplied to the above mentioned work units are shown in table 2.7.

Table 2.8 shows a summary giving equipment name, major specification, required number and main purpose of use.

(3) Procurement plan

The eligible source country of the equipment is summarized in table 2.9.

Italian products will be eliminated from list of eligible countries because their parts service system is considered insufficient. The major construction equipment and vehicles should be procured from Japan from the view-point of quality and parts service system.

25 -

Eligible source countries for vibration rollers, air compressors and generators will be Japan, US, UK, Germany and Sweden from the view-point of product quality, parts service and price competitiveness, and those for asphalt boiler and chip spreader will be US, UK, Germany and Sweden from the view-point of availability.

- 26 -

Equipment	Main Spec.	Eligible source	Reason
Motor Grader	200-220HP	Japan	In view of quality and parts service
Bulldozer	220-235HP	Japan	In view of quality and parts service
Wheel Loader	200-220HP	Japan	In view of quality and parts service
Hyd. Excavator Wheel type	150HP class	Japan / third countries	Only one source in Japan, many sources in third countries
Vibration Roller	10t class	Japan / third countries	Good quality and price can be also expected in third countries.
Vibration Roller	9.5t class	Japan / third countries	Good quality and price can be also expected in third countries.
Dump Truck	9m <sup>3</sup> , 6x4	Japan	In view of quality and parts service
Water Tanker Truck	12,000 Ltr	Japan	In view of quality and parts service
Fuel Tanker Truck	16,000 Ltr	Japan	In view of quality and parts service
Fuel Tanker Truck	8,000 Ltr	Japan	In view of quality and parts service
Asphalt Distributor	6,000 Lir	Japan	In view of quality and parts service
Asphalt Boiler	6,000 Ltr/h	third countries	Difficult procurement in Japan
Chip Spreader	4m	third countries	Difficult procurement in Japan
Low Bed Trailer Tractor	4 Ot, 8m	Japan	In view of quality and parts service
Pick-up Truck	4x4, double cab	Japan	In view of quality and parts service
Mobile Rock Crusher	120 t/h	Japan	In view of quality and parts service
Hyd. Excavator Crawler type	150HP class	Japan	In view of quality and parts service
Air Compressor	7.5m <sup>3</sup> /min	Japan / third countries	Good quality and price can be also expected in third countries.
Crawler Drill	5t	Japan	In view of quality and parts service
Air Compressor	20m <sup>3</sup> /min	Japan	To be attached to crawler drill
Repair Tool Set	for repairs	Japan	In view of quality and parts service
Truck Crane	25t	Japan	In view of quality and parts service
Lubrication Truck	4 x 4	Japan	In view of quality and parts service
Generator	100kVA	Japan / third countries	Good quality and price can be also expected in third countries.
Generator	30kVA	Japan / third countries	Good quality and price can be also expected in third countries.

#### Table 2.7 Eligible Source Plan