

JAPAN INTERNATIONAL COOPERATION AGENCY

THIRD PROGRAM GENERAL AGREEMENT FOR TECHNICAL COOPERATION BETWEEN  
THE GOVERNMENT OF JAPAN AND THE GOVERNMENT OF INDONESIA

THE STUDY ON FLOOD CONTROL  
FOR AMBON AND PASARAH AREA

IN

THE REPUBLIC OF INDONESIA

FINAL REPORT

AND INTERPRETATION

JICA LIBRARY




J 1140903 (4)

NOVEMBER 1977

YAMAGUCHI ENGINEERING CO., LTD.



52  
114  
97.128



JAPAN INTERNATIONAL COOPERATION AGENCY

DIRECTORATE GENERAL OF WATER RESOURCES DEVELOPMENT  
MINISTRY OF PUBLIC WORKS, THE REPUBLIC OF INDONESIA

**THE STUDY ON FLOOD CONTROL  
FOR AMBON AND PASAHARI AREA**

IN

**THE REPUBLIC OF INDONESIA**

**FINAL REPORT  
MAIN REPORT**

NOVEMBER 1997

YACHIYO ENGINEERING CO., LTD.



|        |
|--------|
| SSS    |
| JR     |
| 97-143 |



1140903 (4)

**Exchange Rate**

**Master Plan and Conceptual Plan :**

**1US\$=¥115=Rp.2,300 (as of November 1, 1996)**

**Priority Project :**

**1US\$=¥120=Rp.2,928 (as of September 1, 1997)**

## PREFACE

In response to a request from the Government of the Republic of Indonesia, the Government of Japan decided to conduct a master plan study and feasibility study on flood control for Ambon and Pasahari Area and entrusted the study to the Japan International Cooperation Agency (JICA).


JICA sent to Indonesia a study team headed by Mr. Masatomo Watanabe, Yachiyo Engineering Co., Ltd., three times between October 1996 and November 1997.

The team held discussions with the officials concerned of the Government of Indonesia and conducted field surveys in the study area. After the team returned to Japan, further studies were made and the present report was prepared.

I hope that this report will contribute to the promotion of the project and to the enhancement of friendly relations between our two countries.

I wish to express my sincere appreciation to the officials concerned of the Government of the Republic of Indonesia for their close cooperation extended to the team.

November 1997



Kimio Fujita  
President

Japan International Cooperation Agency

November, 1997

Mr. Kimio Fujita  
President  
Japan International Cooperation Agency  
Tokyo, Japan

Dear Mr. Fujita,

**LETTER OF TRANSMITTAL**


We are pleased to submit to you the final report of the Study on Flood Control for Ambon and Pasahari Area in the Republic of Indonesia. The report contains plans of flood control and city water development projects, as well as the advice and suggestions of the authorities concerned of the Government of Japan and your Agency. Also included are comments made by the Directorate General of Water Resources Development, Ministry of Public Works, Republic of Indonesia, through technical discussions on the draft reports which were held in Jakarta and Ambon, Indonesia.

The report consists of the master plan and feasibility study for flood control and city water development in the central area of Ambon City, as well as the conceptual flood control plan for the Pasahari area. In the Ambon area, structural flood control measures such as river improvement, a diversion channel and small scale multi-purpose dams for the five (5) rivers, and non-structural flood control measures for the river basin management, were proposed targeting the year 2015 and 30-year return period design scale. In the planning, negative socio-economic impact (resettlement and land acquisition) and effects on the natural environment were minimized as much as possible. In addition city water development using small scale multi-purpose dams was planned, based on the future water demand, in conjunction with flood control project. In the Pasahari area, river dike systems with wide river width and low dikes targeting the year 2015 and 20-year return period design scale, were proposed as the most suitable flood control measures, based on the current and future conditions of socio-economy and land use.

In view of the urgent necessity for flood control measures and water resources development as well as river environment improvement in the central area of Ambon City, and of the need for the infrastructure development of Ambon as the capital of Maluku Province, we recommend that the Government of Indonesia implements the priority projects proposed in the report as a top priority.

We wish to take this opportunity to express our sincere gratitude to your Agency, the Ministry of Foreign Affairs and Ministry of Construction. We also wish to express our deep gratitude to the Directorate General of Water Resources Development, Ministry of Public Works, Republic of Indonesia for the close cooperation and assistance extended to us during our investigation and study.

Very truly yours,



Masatomo Watanabe  
Team Leader


The Study on Flood Control for Ambon and  
Pasahari Area in the Republic of Indonesia




**Study Area of Ambon (From the South-east, Martha Christina Tijahahu)**




**Study Area of Ambon (From the South-west)**



Ruhu River Mouth  
Much Sedimentation




Ruhu River  
Downstream View from  
the Left Side at 0k650




Ruhu River  
Downstream View from  
the Right Side at 1k400







Batu Merah River  
Upstream View from the  
River Mouth Bridge




Batu Merah River  
Upstream View from the  
Bridge at 0k250  
Closely Located Houses  
along the River




Batu Merah River  
Downstream View from  
1k450  
Inlet Site of Diversion



Tomu River  
Downstream View from  
the Bridge at 0k420  
Left Building is "PU"




Tomu River  
Downstream View from  
0k900  
Houses are closely  
located and the river is  
narrow and meandering.




Tomu River  
Upstream View from 1k900




Batu Gajah River Mouth  
Downstream View from 0k100



Batu Gajah River  
Downstream View from the  
Bridge at 0k750




Batu Gajah River  
Upstream View from the  
Bridge at 1k388



Batu Gantung River  
Upstream View from the River  
Mouth  
Some parts of Houses are  
located in the river.




Batu Gantung River  
Upstream View from the  
Bridge at 0k400  
The steep slope of Batu  
Gantung River basin is seen.




Batu Gantung River  
Downstream View from 1k150  
This section is the narrowest  
in Batu Gantung River.




Samal River  
View upstream from  
Irrigation Free Intake  
(Normal Flow)



Samal River  
View upstream from  
Irrigation Free Intake  
(Flood Flow)



Samal River  
Samal Road Bridge  
(Flood Flow)



Kobi River  
View upstream from  
New Free Intake  
(Under Construction)



Kobi River  
View downstream at  
Existing Free Intake  
(Gabion Protection)




Kobi River  
View upstream from  
Kobi Road Bridge  
(Flood Flow)






The Republic of Indonesia  
Location of Ambon Island and Seram Island

Study Area  
[ Ambon Central Area / Pasahari Area ]




Map of the Study Area (1/2)



Scale 1:1,000,000



Altitude is indicated with feet. [1 feet = 0.305m]







Map of the Study Area (2/2)

(ii)

## List of Study Reports

### SUMMARY

### MAIN REPORT

### SUPPORTING REPORT

#### *Master Plan and Feasibility Study for Ambon Area*

- Part-A Socio-economy and Land Use
- Part-B Topography and Geology
- Part-C Meteorology and Hydrology
- Part-D Flood Control Plan
- Part-E Water Utilization Plan
- Part-F Facility Design and Cost Estimate
- Part-G Environment
- Part-H Economic Evaluation
- Part-I Implementation Program
- Part-J Topographic Survey

#### *Conceptual Plan for Pasahari Area*

- Part-K Socio-economy and Land Use
- Part-L Topography and Geology
- Part-M Meteorology and Hydrology
- Part-N Flood Control Plan and Design
- Part-O Environment
- Part-P Economic Evaluation
- Part-Q Topographic Survey

### DATA BOOK

- DataBook-A Meteorological and Hydrological Data for Ambon Area
- DataBook-B Meteorological and Hydrological Data for Pasahari Area

## **SYNOPSIS**

### **The Study on Flood Control for Ambon and Pasahari Area in the Republic of Indonesia**

Study Period: October 1996 - November 1997

Recipient Agency: Directorate General of Water Resources Development, Ministry of Public Works

#### **1 BACKGROUND OF THE STUDY**

Ambon City, the capital of Maluku Province, is blessed with a good natural port and has been the social and economic center of the region ever since the days of colonial rule by the Netherlands. The population of Ambon City, which currently stands at 305,000 as of 1996, is forecast to rise to 420,000 by the end of 2015 with a population growth rate of 1.7 % based on the recent census. However, despite being such an important commercial center, the center of the city is flooded and damaged every year by the five main rivers. In addition, current water supply in the central Ambon area is not sufficient with a supply coverage of only 28 % and there will be a shortfall in supply of 9,500 m<sup>3</sup>/day by the year 2015 and 24,000 m<sup>3</sup>/day by the year 2030. Ambon needs to reinforce the infrastructure to support future growth in line with the central government policy to develop the eastern region of Indonesia.

Further more, at the strong request of the Indonesia side, it was decided to examine a conceptual flood control plan in the Pasahari area on the island of Seram next to Ambon. This area is one of the highest potential irrigation areas in Maluku Province but is also vulnerable to flood damage.

#### **2 OBJECTIVES OF THE STUDY**

The objectives of the study can be summarized into the following three points:

- 1) Formulation of a flood control master plan and city water development plan for the urban city area of Ambon
- 2) Implementation of a feasibility study into priority projects raised within the master plan that require particularly urgent attention
- 3) Preparation of a conceptual flood control plan for the Pasahari area on Seram Island

#### **3 FLOOD CONTROL FOR AMBON AREA**

##### **3-1 Outline of the Project**

##### **(1) Basic Policy**

Based on the basin characteristics and river conditions, the basic policy for flood control and city water development are set as follows:

- 1) Structural measures and non-structural measures for flood control and sediment control are planned with a planning scale of 30-year return period, targeting the year 2015.
- 2) Structural measures include river improvement works, dams, diversion channels and check dams. Non-structural flood control measures are measures other than structural flood control measures to mitigate flood disasters and include various methods for flood runoff suppression, for flood proofing and for facilitation of flood control activities.
- 3) Plans for water development for future domestic use through multi-purpose dams are proposed with a planning scale of 10-year return period. Target water supply coverage is set as 80 % by 2015 and 100 % by 2030.
- 4) Special attention is paid to possible negative social and environmental impacts to identify optimum projects.

## (2) Proposed Projects (Structural Flood Control Measures)

The proposed projects for flood control and water resources development in Ambon Area are shown in Table-1. All projects with the exception of Ruhu multi-purpose dam were selected as priority projects.

**Table-1 Proposed Projects in Ambon Area <sup>\*1</sup>**

| River                                  |                      | Ruhu                                  | Batu Merah           | Tomu                 | Batu Gajah             | Batu Gantung           |
|--|----------------------|---------------------------------------|----------------------|----------------------|------------------------|------------------------|
| Construction Cost                      | Rp.million           | 6,214                                 | 27,708               | 18,492               | 71,080                 | 47,179                 |
| Land Acq. & Comp. Cost                 | Rp.million           | 287                                   | 2,335                | 1,252                | 7,334                  | 6,026                  |
| Land Acquisition                       | Area                 | 615 m <sup>2</sup>                    | 4,250 m <sup>2</sup> | 1,781 m <sup>2</sup> | 192,958 m <sup>2</sup> | 149,291 m <sup>2</sup> |
| Resettlement                           | Household            | 5                                     | 33                   | 10                   | 69                     | 27                     |
| River Improvement Work                 | Type <sup>*2</sup>   | E, H, W                               | E, H, C, W           | E, H, C, W           | E, H, C, W             | E, H, C, W             |
|  | Length               | 1,600 m                               | 1,500 m              | 2,700 m              | 2,200 m                | 1,450 m                |
| Multi-purpose Dam                      | Type                 | Rock Fill                             | -                    | -                    | Rock Fill              | Rock Fill              |
|  | Height               | 44.7 m                                | -                    | -                    | 50.0 m                 | 36.6 m                 |
|  | N.D.D. <sup>*3</sup> | 16,000m <sup>3</sup> /d               | -                    | -                    | 8,000m <sup>3</sup> /d | 2,500m <sup>3</sup> /d |
| Diversion Channel                      | Type                 | -                                     | Tunnel               | -                    | -                      | -                      |
|  | Length               | -                                     | 900 m                | -                    | -                      | -                      |
| Check Dam                              | Type                 | Masonry                               | -                    | Masonry              | Masonry                | Masonry                |
|  | Height               | 3.8 m                                 | -                    | 4.9 m                | 6.1 m                  | 3.5 m                  |
| Land Reclamation<br>(as Disposal Site) | Cost                 | Construction Cost : Rp. 6,608 million |                      |                      |                        |                        |
|  | Ave.Depth            | 3.0 m                                 |                      |                      |                        |                        |
|  | Area                 | 6.56 ha                               |                      |                      |                        |                        |

\*1 Ruhu multi-purpose dam is not included in the Priority Projects but is included in the Master Plan.

\*2 E : Excavation, H : Flood Wall Heightening, C : Three-sided Concrete Channel, W : River Widening

\*3 N.D.D. : Newly Developed Discharge

## (3) Non-structural Flood Control Measures

The targets and methods of non-structural flood control measures are proposed as shown in Table-2.

**Table-2 Non-structural Flood Control Measures for Ambon Area**

| Objectives   | Methods  |
|--|--|
| Suppression of Flood Runoff                        | - Land Use Regulation<br>- Vegetation Improvement<br>- Off-site Storage<br>- Lowland Infiltration  |
| Improvement of Flood Proof Function                | - Land Use Regulation<br>- Flood Proof Facilities  |
| Facilitation of Flood Disaster Prevention Activity | - Management Organization<br>- Flood Forecast & Warning System<br>- Flood Risk Map<br>- Flood Fighting System<br>- River Management Zone<br>- Public Awareness<br>- Human Resource Development |

## (4) Project Cost

The project cost for the priority projects is estimated to be Rp. 302,049 million (equivalent to ¥ 12,379 million) using unit prices as of September 1997 (US\$ 1 = Rp.2,928 = ¥ 120). Of the total project cost, Rp. 23,732 million is the cost of land acquisition and compensation.

## 3-2 Implementation Program

The responsible agency for project implementation will be the Ambon Flood Control Project Office which will be newly established at the project site under DGWRD. The Indonesian government wish to implement this project using finance from an OECF loan (Overseas Economic Cooperation Fund). The overall implementation schedule is shown in Table-3.

**Table-3 Implementation Schedule**

| Fiscal Year           | (1)<br>1998/99 | (2)<br>1999/00 | (3)<br>2000/01 | (4)<br>2001/02 | (5)<br>2002/03 | (6)<br>2003/04 | (7)<br>2004/05 | (8)<br>2005/06 | (9)<br>2006/07 | (10)<br>2007/08 |
|-----------------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|----------------|-----------------|
| 1 Loan Procedure      | ■              |                |                |                |                |                |                |                |                |                 |
| 2 Procurement         | ■              | ■              | ■              | ■              |                |                |                |                |                |                 |
| a Consulting Services | ■              | ■              | ■              | ■              |                |                |                |                |                |                 |
| b Construction Work   |                |                | ■              | ■              | ■              |                |                |                |                |                 |
| 3 Consulting Services |                | ■              | ■              | ■              | ■              | ■              | ■              | ■              | ■              | ■               |
| a Survey & Design     |                | ■              | ■              | ■              |                |                |                |                |                |                 |
| b Tendering           |                |                | ■              | ■              | ■              |                |                |                |                |                 |
| c Const. Supervision  |                |                |                |                | ■              | ■              | ■              | ■              | ■              | ■               |
| 4 Construction        |                |                |                |                | ■              | ■              | ■              | ■              | ■              | ■               |
| 5 Land Acquisition    |                |                |                |                | ■              | ■              | ■              | ■              | ■              | ■               |

**3-3 Project Evaluation**

**(1) Environmental Impact Assessment**

Initial environmental examination was conducted and negative impacts were identified on 12 environmental elements. Of these twelve, resettlement, solid waste and groundwater were considered to be significant impacts when the proposed projects are implemented. On this basis, environmental impact assessment (EIA) for the priority projects was conducted and the impacts were carefully analyzed and conclusions were drawn as follows:

- 1) **Resettlement** : The projects will be planned and designed based on the policy of least negative impact as well as continuous care for the resettled households.
- 2) **Solid Waste** : Through land reclamation, existing landfills and construction material reuse, solid waste disposal will not be a significant problem during project construction.
- 3) **Groundwater** : Construction of the multi-purpose dams, the diversion tunnel and the three-sided concrete channel could cause negative impacts on groundwater. Facilities will be planned and designed taking into account measures such as leakage prevention, recharge of groundwater, alternative water resources and so on.

**(2) Economic Evaluation**

The entire project is assessed to be feasible, attaining an internal rate of return (IRR) of 16.4 % using a discount rate of 10 %. The projects for each river were also assessed to be feasible showing individual IRR of between 10.5 and 28.1 %.

**Table-4 Results of Economic Analysis for Priority Project**

| Case               | Economic Cost<br>(Rp. Million) | NPV at 10%<br>(Rp. Million) | B/C at 10% | IRR   | Remarks               |
|--------------------|--------------------------------|-----------------------------|------------|-------|-----------------------|
| Ruhu River         | 7,768                          | 26,154                      | 5.3        | 28.1% | 5-year return Period  |
| Batu Merah River   | 34,635                         | 98,256                      | 4.7        | 25.8% | 30-year return Period |
| Tomu River         | 23,115                         | 36,474                      | 3.0        | 19.9% |                       |
| Batu Gajah River   | 92,980                         | 37,262                      | 1.4        | 13.1% |                       |
| Batu Gantung River | 63,104                         | 3,619                       | 1.1        | 10.5% |                       |
| Entire Project     | 221,602                        | 168,756                     | 2.2        | 16.4% |                       |

**3-4 Recommendations**

- 1) Urgent implementation of the priority projects.
- 2) Implementation of the non-structural measures in line with the structural measures.
- 3) Careful and appropriate countermeasures to land acquisition and resettlement.
- 4) River environment management.
- 5) Formulation of water distribution plan by the local government.
- 6) Continuous effort to collect hydrometric data.

## 4 FLOOD CONTROL FOR PASAHARI AREA

### 4-1 Outline of the Project

Based on the social, economic and river conditions, the basic policy of flood control measures are set as follows:

- 1) Design scale of 20-year return period and target year of 2015.
- 2) Low cost river improvement works.
- 3) River dikes planned widely surrounding the current river course.
- 4) Multi-purpose dikes with road function.
- 5) Staged construction to be prioritized.

Based on these policies, conceptual flood control plans were proposed for Samal and Kobi rivers as shown in Table-5. The project cost is estimated to be as follows:

Samal River Project : Rp. 20,077 million    Kobi River Project : Rp. 22,190 million

**Table-5 Conceptual Flood Control Plan for Pasahari Area**

| River                  | Planned Gradient | Planned River Length (km) | Design Discharge (m <sup>3</sup> /sec) | Dike Height (m) | Planned River Width (m) | Land Acquisition Area (ha) |
|------------------------|------------------|---------------------------|--|-----------------|-------------------------|----------------------------|
| Samal River            | 1/200-1/5600     | 16.6                      | 1,550-2,450                            | 2.00            | 350-2,850               | 26.52                      |
| Tributary Musi River   | 1/220-1/270      | 5.5                       | 900                                    | 2.00            | 260-340                 | 15.98                      |
| Kobi River             | 1/180-1/4900     | 16.6                      | 1,900-2,650                            | 2.00-2.50       | 540-1,500               | 29.98                      |
| Tributary Tinupa River | 1/230-1/520      | 6.5                       | 750                                    | 2.00            | 220-410                 | 11.39                      |

### 4-2 Project Evaluation

#### (1) Initial Environmental Examination

Possible negative impacts were identified during project construction on 6 environmental elements as follows: 1) Resettlement, 2) Economic Activity, 3) Traffic and Living Activity, 4) Solid Waste, 5) Coastal Area and 6) Water Pollution. However, no negative impact is anticipated during operation stage following completion of construction.

#### (2) Economic Evaluation

Since an IRR of 16.0 % using a discount rate of 10 % will be achieved for the Samal River flood control project, it is judged to be economically feasible. However, economic feasibility of the Kobi River flood control project is marginal with an IRR of 8.2 %. It should be noted that flood control facilities in Kobi River could also be used as roads which would have additional impact on the local economy, although benefits are difficult to quantify due to lack of traffic data.

**Table-6 Results of Economic Analysis**


| Project             | Economic Cost (Rp. Million) | NPV at 10% (Rp. Million) | B/C at 10% | IRR    |
|---------------------|-----------------------------|--------------------------|------------|--------|
| Samal River Project | 17,065                      | 7,885                    | 1.88       | 16.0 % |
| Kobi River Project  | 18,862                      | -2,122                   | 0.79       | 8.2 %  |

### 4-3 Recommendations


- 1) Further stages of flood control planning in line with irrigation projects.
- 2) Continuous effort to collect hydrometric data.
- 3) Land use regulation for the wide river area.







Project Formation in Ambon Area




Legend

- : Dyke
- : River
- : High Ground
- : Road
- H : Dyke Height
- W : River Width

Project Formation in Pasahari Area

Scale 1:50,000

3000m



**THE STUDY ON FLOOD CONTROL FOR AMBON AND PASIHARI AREA  
IN THE REPUBLIC OF INDONESIA**

**FINAL REPORT  
(MAIN REPORT)**

**TABLE OF CONTENTS**

|                                 |       |
|---------------------------------|-------|
| Preface                         |       |
| Letter of Transmittal           |       |
| Map of the Study Area.....      | i     |
| List of Study Reports.....      | iii   |
| Synopsis.....                   | iv    |
| Table of Contents.....          | x     |
| List of Tables and Figures..... | xiv   |
| List of Abbreviations.....      | xxiii |

---

***INTRODUCTION    OUTLINE OF THE STUDY***

---

|   |                                      |         |
|---|--------------------------------------|---------|
| 1 | Background of the Study.....         | Intro-1 |
| 2 | Objectives of the Study.....         | Intro-2 |
| 3 | Study Areas.....                     | Intro-2 |
| 4 | Scope and Contents of the Study..... | Intro-2 |

---

***PART I    FLOOD CONTROL FOR AMBON AREA***

---

|                  |  |            |
|------------------|--|------------|
| <b>CHAPTER 1</b> | <b>GENERAL CONDITIONS OF THE STUDY AREA.....</b>           | <b>I-1</b> |
| 1.1              | Socio-economy.....   | I-1        |
| 1.1.1            | Current Social Conditions.....                             | I-1        |
| 1.1.2            | Current Economic Conditions.....                           | I-3        |
| 1.1.3            | Projection of Future Socio-economic Conditions.....        | I-4        |
| 1.2              | Physical Geography.....                                    | I-6        |
| 1.2.1            | Topography and Geology.....                                | I-6        |
| 1.2.2            | Land Use.....  | I-8        |
| 1.3              | Hydrology and Flood Damage.....                            | I-11       |
| 1.3.1            | Climate.....   | I-11       |
| 1.3.2            | River Systems and Hydrology.....                           | I-12       |
| 1.3.3            | Flood Damage and Flood Forecasting and Warning System..... | I-15       |
| 1.4              | Water Use and Demand.....                                  | I-18       |
| 1.4.1            | Current Water Use.....                                     | I-18       |
| 1.4.2            | Future Water Demand.....                                   | I-19       |
| 1.5              | Environment.....   | I-23       |
| 1.5.1            | Social Environment.....                                    | I-23       |
| 1.5.2            | Natural Environment.....                                   | I-25       |
| 1.5.3            | Environmental Pollution.....                               | I-26       |

|                  |   |             |
|------------------|---|-------------|
| <b>CHAPTER 2</b> | <b>FLOOD ANALYSIS</b>                                   | <b>1-28</b> |
| 2.1              | Rainfall Analysis                                       | 1-28        |
| 2.1.1            | Representative Rainfall Station and Basin Mean Rainfall | 1-28        |
| 2.1.2            | Rainfall Probability Analysis                           | 1-28        |
| 2.1.3            | Flood Rainfall  | 1-30        |
| 2.2              | Flood Runoff Analysis                                   | 1-31        |
| 2.2.1            | Design Rainfall   | 1-31        |
| 2.2.2            | Flood Runoff Modeling                                   | 1-33        |
| 2.2.3            | Flood Discharge   | 1-38        |
| 2.3              | Flood Damage Analysis                                   | 1-42        |
| 2.3.1            | Discharge Capacity of River Channels                    | 1-42        |
| 2.3.2            | Estimation of Flood Damage                              | 1-44        |
| 2.3.3            | Flood Discharge - Damage Curve                          | 1-49        |
| <b>CHAPTER 3</b> | <b>FLOOD CONTROL MASTER PLAN</b>                        | <b>1-52</b> |
| 3.1              | Basic Policy of Flood Control Plan                      | 1-52        |
| 3.1.1            | Principal Plan Conditions                               | 1-52        |
| 3.1.2            | Policy of Flood Control Measures                        | 1-53        |
| 3.2              | Structural Flood Control Measures                       | 1-54        |
| 3.2.1            | Study of Flood Control Measures                         | 1-54        |
| 3.2.2            | Alternative Flood Control Plans and Cost Estimate       | 1-78        |
| 3.2.3            | Identification of Optimum Plan                          | 1-85        |
| 3.3              | Non-structural Flood Control Measures                   | 1-96        |
| 3.3.1            | General Outline   | 1-96        |
| 3.3.2            | Suppression of Flood Runoff                             | 1-97        |
| 3.3.3            | Improvement of Flood Proof Function                     | 1-98        |
| 3.3.4            | Facilitation of Flood Disaster Prevention Activities    | 1-99        |
| 3.4              | Water Utilization Plan                                  | 1-105       |
| 3.4.1            | Planning Conditions                                     | 1-105       |
| 3.4.2            | City Water Development Plan                             | 1-108       |
| 3.4.3            | Small Scale Hydropower Generation                       | 1-112       |
| 3.4.4            | Multi-purpose Dam Plan and Cost Estimate                | 1-113       |
| 3.5              | River Environment Management                            | 1-116       |
| 3.5.1            | Necessity for River Environment Management              | 1-116       |
| 3.5.2            | River Environment Improvement Program                   | 1-116       |
| 3.6              | Implementation Schedule and Organization                | 1-118       |
| 3.6.1            | Implementation Schedule                                 | 1-118       |
| 3.6.2            | Implementation Organization                             | 1-118       |
| 3.7              | Project Evaluation                                      | 1-121       |
| 3.7.1            | Initial Environmental Examination                       | 1-121       |
| 3.7.2            | Economic Evaluation                                     | 1-124       |
| 3.7.3            | Financial Considerations                                | 1-127       |

|                  |  |       |
|------------------|--|-------|
| <b>CHAPTER 4</b> | <b>PRIORITY PROJECT</b> .....          | I-130 |
| 4.1              | Selection of Priority Project.....     | I-130 |
| 4.2              | Plan of Priority Project.....          | I-131 |
| 4.2.1            | General Conditions.....                | I-131 |
| 4.2.2            | Ruhu River Project.....                | I-132 |
| 4.2.3            | Batu Merah River Project.....          | I-139 |
| 4.2.4            | Tomu River Project.....                | I-146 |
| 4.2.5            | Batu Gajah River Project.....          | I-157 |
| 4.2.6            | Batu Gantung River Project.....        | I-169 |
| 4.3              | Facility Design and Cost Estimate..... | I-179 |
| 4.3.1            | Facility Design.....                   | I-179 |
| 4.3.2            | Construction Plan and Schedule.....    | I-188 |
| 4.3.3            | Cost Estimate.....                     | I-194 |
| 4.4              | Project Evaluation.....                | I-201 |
| 4.4.1            | Environmental Impact Assessment.....   | I-201 |
| 4.4.2            | Economic Evaluation.....               | I-206 |
| 4.5              | Implementation Program.....            | I-210 |
| 4.5.1            | Implementation Schedule.....           | I-210 |
| 4.5.2            | Finance and Disbursement Schedule..... | I-212 |
| <b>CHAPTER 5</b> | <b>RECOMMENDATIONS</b> .....           | I-213 |

---

**PART II**      *FLOOD CONTROL FOR PASAIHARI AREA*

---

|                  |   |       |
|------------------|---|-------|
| <b>CHAPTER 1</b> | <b>GENERAL CONDITIONS OF THE STUDY AREA</b> ..... | II-1  |
| 1.1              | Socio-economy.....                                | II-1  |
| 1.1.1            | Current Socio-economic Conditions.....            | II-1  |
| 1.1.2            | Future Socio-economic Conditions.....             | II-4  |
| 1.2              | Physical Geography.....                           | II-5  |
| 1.2.1            | Topography and Geology.....                       | II-5  |
| 1.2.2            | Land Use.....                                     | II-7  |
| 1.3              | Hydrology and Flood Damage.....                   | II-9  |
| 1.3.1            | Climate.....                                      | II-9  |
| 1.3.2            | River Systems and Hydrometric Stations.....       | II-10 |
| 1.3.3            | Flood Damage.....                                 | II-12 |
| 1.4              | Environment.....                                  | II-17 |
| 1.4.1            | Social Environment.....                           | II-17 |
| 1.4.2            | Natural Environment.....                          | II-18 |
| 1.4.3            | Environmental Pollution.....                      | II-18 |

|                  |  |              |
|------------------|--|--------------|
| <b>CHAPTER 2</b> | <b>FLOOD ANALYSIS</b> .....                              | <b>II-19</b> |
| 2.1              | Rainfall Analysis.....                                   | II-19        |
| 2.1.1            | Representative Rainfall Stations and Basin Rainfall..... | II-19        |
| 2.1.2            | Rainfall Probability Analysis.....                       | II-19        |
| 2.1.3            | Flood Rainfall.....                                      | II-20        |
| 2.2              | Flood Runoff Analysis.....                               | II-22        |
| 2.2.1            | Division of Catchment Areas.....                         | II-22        |
| 2.2.2            | Estimation of Peak Discharge by Rational Formula.....    | II-22        |
| 2.3              | Flood Damage Analysis.....                               | II-26        |
| 2.3.1            | Discharge Capacity of River Channels.....                | II-26        |
| 2.3.2            | Estimation of Flood Damage.....                          | II-28        |
| 2.3.3            | Flood Discharge - Damage Curve.....                      | II-32        |
| <b>CHAPTER 3</b> | <b>FLOOD CONTROL CONCEPTUAL PLAN</b> .....               | <b>II-34</b> |
| 3.1              | Basic Policy of Flood Control Plan.....                  | II-34        |
| 3.1.1            | Principal Planning Conditions.....                       | II-34        |
| 3.1.2            | Policy of Flood Control Measures.....                    | II-35        |
| 3.2              | Plan and Design of Flood Control Measures.....           | II-36        |
| 3.2.1            | Design Criteria.....                                     | II-36        |
| 3.2.2            | Alternative Flood Control Plans.....                     | II-37        |
| 3.3              | Selection of Optimum Plan.....                           | II-49        |
| 3.3.1            | Work Quantities.....                                     | II-49        |
| 3.3.2            | Cost Estimates.....                                      | II-50        |
| 3.3.3            | Optimum Flood Control Plan.....                          | II-50        |
| 3.4              | Implementation Schedule.....                             | II-51        |
| 3.5              | Project Evaluation.....                                  | II-52        |
| 3.5.1            | Initial Environmental Examination.....                   | II-52        |
| 3.5.2            | Economic Evaluation.....                                 | II-54        |
| <b>CHAPTER 4</b> | <b>RECOMMENDATIONS</b> .....                             | <b>II-57</b> |

---

## **APPENDICES**

---

|              |  |
|--------------|--|
| Appendix - A | List of JICA Advisory Committee Members          |
| Appendix - B | List of Steering Committee Members               |
| Appendix - C | List of Technical Committee Members              |
| Appendix - D | List of JICA Study Team Members and Counterparts |

# List of Tables and Figures

## List of Tables

| <b>INTRODUCTION</b> | <b>OUTLINE OF THE STUDY</b>  |         |
|---------------------|--|---------|
| Table-1             | Major Work Contents in Study Phases 1 and 2.....                           | Intro-4 |
| <hr/>               |  |         |
| <b>PART I</b>       | <b>FLOOD CONTROL FOR AMBON AREA</b>  |         |
| <hr/>               |  |         |
| <b>CHAPTER 1</b>    | <b>GENERAL CONDITIONS OF THE STUDY AREA</b>                                |         |
| Table-I.1.1         | Population Growth in Ambon City, 1961-1996.....                            | I-1     |
| Table-I.1.2         | Population, Area and Population Density (June 1996).....                   | I-2     |
| Table-I.1.3         | Breakdown of GDP, Ambon City (1994).....                                   | I-3     |
| Table-I.1.4         | Occupations of Inhabitants (1994).....                                     | I-4     |
| Table-I.1.5         | Population Projection in Ambon City.....                                   | I-4     |
| Table-I.1.6         | Population Projection in the Study Area.....                               | I-4     |
| Table-I.1.7         | Annual Growth Rate of Ambon City's per capita GDP.....                     | I-5     |
| Table-I.1.8         | Future GDP and per capita GDP of Ambon City<br>at 1996 prices.....         | I-5     |
| Table-I.1.9         | Geological Composition of Ambon Island.....                                | I-7     |
| Table-I.1.10        | Land Use Situation.....  | I-8     |
| Table-I.1.11        | Weather Conditions in Ambon Area<br>(Pattimura Ambon Station).....         | I-11    |
| Table-I.1.12        | Catchment Area and Length of Study Rivers.....                             | I-12    |
| Table-I.1.13        | Installed and Existing Observation Stations.....                           | I-14    |
| Table-I.1.14        | Flow Regime.....   | I-14    |
| Table-I.1.15        | Features of Past Flood Damage.....   | I-15    |
| Table-I.1.16        | Connection and Sales of Water by PDAM<br>in Ambon City (Average 1995)..... | I-18    |
| Table-I.1.17        | Summary of Future Water Demand (m <sup>3</sup> /day).....                  | I-19    |
| Table-I.1.18        | Future Water Demand Projection.....  | I-22    |
| <b>CHAPTER 2</b>    | <b>FLOOD ANALYSIS</b>  |         |
| Table-I.2.1         | Meteorological (Rainfall) Stations in Ambon.....                           | I-28    |
| Table-I.2.2         | Daily and Hourly Probable Rainfall [Pattimura Ambon].....                  | I-28    |
| Table-I.2.3         | Probable Rainfall Depth (Pattimura Ambon).....                             | I-29    |
| Table-I.2.4         | Flood Rainfall in Ambon [Pattimura Ambon].....                             | I-30    |
| Table-I.2.5         | Enlarging Ratio to Design Rainfall Depth.....                              | I-31    |
| Table-I.2.6         | Basin Modeling.....  | I-35    |
| Table-I.2.7         | $f_1, f$ and $R_s$ for Rivers in Japan.....                                | I-35    |
| Table-I.2.8         | Design Peak Discharge (Design Flood : 1990/06/06).....                     | I-38    |
| Table-I.2.9         | Peak Discharge.....  | I-39    |
| Table-I.2.10        | Summary Result of Discharge Capacity.....                                  | I-42    |
| Table-I.2.11        | Standard Asset Damage Rate in Japan.....                                   | I-45    |
| Table-I.2.12        | Value of General Assets.....   | I-45    |



|  |   |       |
|--|---|-------|
| Table-I.2.13                               | Estimation of Past Flood Damage.....  | I-46  |
| Table-I.2.14                               | Peak Discharge (m <sup>3</sup> /sec).....   | I-47  |
| Table-I.2.15                               | Estimation of Flood Damage with 30-year<br>and 100-year Return Period.....                  | I-47  |
| Table-I.2.16                               | Preliminary Estimation of Past Flood Discharges.....  | I-49  |
| Table-I.2.17                               | Estimation of Return Period and Discharge of Past Floods.....                               | I-49  |
| Table-I.2.18                               | Estimation Method.....  | I-50  |
| Table-I.2.19                               | Relationship between Flood Discharge and Damage Value.....                                  | I-50  |
| <b>CHAPTER 3 FLOOD CONTROL MASTER PLAN</b> |   |       |
| Table-I.3.1                                | Recommended Minimum Return Period of Design Flood.....                                      | I-53  |
| Table-I.3.2                                | Outline of River Improvement Works.....   | I-55  |
| Table-I.3.3                                | River Improvement Plan (Ruhu River).....  | I-57  |
| Table-I.3.4                                | River Improvement Plan (Batu Merah River).....  | I-59  |
| Table-I.3.5                                | River Improvement Plan (Tomu River).....  | I-61  |
| Table-I.3.6                                | River Improvement Plan (Batu Gajah River).....  | I-63  |
| Table-I.3.7                                | River Improvement Plan (Batu Gantung River).....  | I-65  |
| Table-I.3.8                                | Comparison of Candidate Dam Sites.....  | I-67  |
| Table-I.3.9                                | Design Flood Discharge Before/After Regulation by Dam.....                                  | I-69  |
| Table-I.3.10                               | Specifications of Dams and Reservoirs.....  | I-70  |
| Table-I.3.11                               | Specifications of Diversion Channels.....   | I-73  |
| Table-I.3.12                               | Annual Amount of Surface Erosion (Akitani).....   | I-75  |
| Table-I.3.13                               | Proposed Sediment Discharge.....  | I-76  |
| Table-I.3.14                               | Proposed Allowable Sediment Discharge.....  | I-76  |
| Table-I.3.15                               | Comparison between Sediment Discharge and<br>Allowable Sediment Discharge.....              | I-77  |
| Table-I.3.16                               | Outline of Check Dams.....  | I-77  |
| Table-I.3.17(1)                            | Alternatives of Flood Control Plan.....   | I-78  |
| Table-I.3.17(2)                            | Alternatives of Flood Control Plan.....   | I-79  |
| Table-I.3.18                               | Project Cost of Each Alternative Flood Control Plan.....                                    | I-85  |
| Table-I.3.19                               | Summary of Alternative Flood Control Plans.....   | I-86  |
| Table-I.3.20                               | Features of Flood Control Plan in the Study Area.....                                       | I-88  |
| Table-I.3.21                               | Optimum Flood Control Plan.....   | I-89  |
| Table-I.3.22                               | Non-structural Flood Control Measures for Ambon Area.....                                   | I-96  |
| Table-I.3.23                               | Work Units for Disaster Countermeasures of Ambon City.....                                  | I-104 |
| Table-I.3.24                               | Maintenance Discharge at Proposed Dam Sites.....  | I-106 |
| Table-I.3.25                               | Assumed Water Resources (Central Ambon Area).....   | I-108 |
| Table-I.3.26                               | Required Reservoir Volume for City Water Development.....                                   | I-109 |
| Table-I.3.27                               | City Water Development Plan - Ambon Central Area.....                                       | I-111 |
| Table-I.3.28                               | Basic Condition for Hydropower Generation Plan.....   | I-112 |
| Table-I.3.29                               | Approximate Cost of Hydropower Station [Batu Gajah Dam]... ..                               | I-112 |
| Table-I.3.30                               | Specification of Multi-purpose Dams and Reservoirs.....                                     | I-113 |
| Table-I.3.31                               | Project Cost of the Optimum Flood Control Plan<br>and the Plan with Multi-purpose Dams..... | I-115 |
| Table-I.3.32                               | Cost Estimation of Water Treatment Plant and Pipelines.....                                 | I-115 |
| Table-I.3.33                               | Implementation Schedule for the Master Plan.....  | I-119 |
| Table-I.3.34                               | Environmental Examination Matrix.....   | I-122 |
| Table-I.3.35                               | Calculation of Yearly Averages of Damage Alleviation.....                                   | I-124 |
| Table-I.3.36                               | Yearly Averages of Damage Alleviation of the Five Rivers.....                               | I-124 |

|              |   |       |
|--------------|---|-------|
| Table-I.3.37 | Economic Cost, NPV, B/C and IRR of Flood Control Facilities in Each of the Five Rivers..... | I-126 |
| Table-I.3.38 | Economic Cost, NPV, B/C and IRR of Options with Multi-purpose Dams.....                     | I-126 |
| Table-I.3.39 | Economic Cost, NPV, B/C and IRR of the Project as a Whole..                                 | I-127 |
| Table-I.3.40 | Maluku Province PU Budget (Plan), 1996/97 (million Rp) .....                                | I-128 |
| Table-I.3.41 | PU Budget (Plan) Allocated to Ambon City in 1996/97 (million Rp).....                       | I-128 |
| Table-I.3.42 | Ambon City PU Budget (Realization), 1995/96 (million Rp).....                               | I-129 |

#### CHAPTER4 PRIORITY PROJECT

|                 |  |       |
|-----------------|--|-------|
| Table-I.4.1     | Composition of Priority Projects .....                         | I-130 |
| Table-I.4.2     | List of Bridges in Ruhu River.....                             | I-136 |
| Table-I.4.3     | List of Drainage in Ruhu River.....                            | I-136 |
| Table-I.4.4     | Ruhu River Improvement Plan .....                              | I-137 |
| Table-I.4.5     | List of Bridges in Batu Merah River.....                       | I-143 |
| Table-I.4.6     | List of Drainage in Batu Merah River.....                      | I-143 |
| Table-I.4.7     | Batu Merah River Improvement Plan .....                        | I-144 |
| Table-I.4.8     | List of Bridges in Tomu River.....                             | I-149 |
| Table-I.4.9     | List of Drainage in Tomu River.....                            | I-150 |
| Table-I.4.10(1) | Tomu River Improvement Plan.....                               | I-151 |
| Table-I.4.10(2) | Tomu River Improvement Plan.....                               | I-152 |
| Table-I.4.11    | List of Bridges in Batu Gajah River.....                       | I-160 |
| Table-I.4.12    | List of Drainage in Batu Gajah River.....                      | I-161 |
| Table-I.4.13(1) | Batu Gajah River Improvement Plan .....                        | I-162 |
| Table-I.4.13(2) | Batu Gajah River Improvement Plan .....                        | I-163 |
| Table-I.4.14    | Flood Regulation Calculation Result (Batu Gajah Dam) .....     | I-166 |
| Table-I.4.15    | Specification of Batu Gajah Multi-purpose Dam.....             | I-168 |
| Table-I.4.16    | List of Bridges in Batu Gantung River.....                     | I-172 |
| Table-I.4.17    | List of Drainage in Batu Gantung River.....                    | I-173 |
| Table-I.4.18    | Batu Gantung River Improvement Plan.....                       | I-174 |
| Table-I.4.19    | Flood Regulation Calculation Result (Batu Gantung Dam) .....   | I-176 |
| Table-I.4.20    | Specification of Batu Gantung Multi-purpose Dam.....           | I-178 |
| Table-I.4.21    | Quantities of River Improvement.....                           | I-180 |
| Table-I.4.22    | Dimension of Diversion Tunnel .....                            | I-181 |
| Table-I.4.23    | Condition of Fixed Weir Design .....                           | I-181 |
| Table-I.4.24    | Construction Quantities of Diversion.....                      | I-181 |
| Table-I.4.25    | Design Condition of Dam.....                                   | I-183 |
| Table-I.4.26    | Design Flood Discharge .....                                   | I-183 |
| Table-I.4.27    | Major Structural Features.....                                 | I-186 |
| Table-I.4.28    | Dam Construction Quantities .....                              | I-187 |
| Table-I.4.29    | Specification of Check Dams.....                               | I-187 |
| Table-I.4.30    | Available Area for Land Reclamation .....                      | I-187 |
| Table-I.4.31    | Package Division.....  | I-188 |
| Table-I.4.32    | Construction Schedule for River Improvement Works.....         | I-189 |
| Table-I.4.33    | Access Roads.....  | I-190 |
| Table-I.4.34    | Length and Construction Period of River Diversion Tunnels..... | I-192 |
| Table-I.4.35    | Unit Cost of Main Construction Work.....                       | I-195 |
| Table-I.4.36    | Summary of the Project Cost.....                               | I-196 |

|                 |  |       |
|-----------------|--|-------|
| Table-I.4.37(1) | Construction Cost and Land Acquisition & Compensation Cost of Each River ..... | I-197 |
| Table-I.4.37(2) | Construction Cost and Land Acquisition & Compensation Cost of Each River ..... | I-198 |
| Table-I.4.38(1) | Construction Cost and Land Acquisition & Compensation Cost of Work Items ..... | I-199 |
| Table-I.4.38(2) | Construction Cost and Land Acquisition & Compensation Cost of Work Items ..... | I-200 |
| Table-I.4.39    | Project Components Subject to EIA Study .....                                  | I-201 |
| Table-I.4.40    | Environment Elements for EIA .....   | I-202 |
| Table-I.4.41    | Economic Cost, NPV, B/C and IRR of Each of the Five Rivers .....               | I-208 |
| Table-I.4.42    | Economic Cost, NPV and IRR of the Alternative Combinations .....               | I-208 |
| Table-I.4.43    | Sensitivity Analysis on Each of the Five Rivers .....                          | I-209 |
| Table-I.4.44    | Sensitivity Analysis on the Entire Project .....                               | I-209 |
| Table-I.4.45    | Implementation Schedule .....  | I-210 |
| Table-I.4.46    | Tender Packages for Civil Works .....  | I-211 |
| Table-I.4.47    | Annual Disbursement Schedule of the Project .....                              | I-212 |

---

**PART II FLOOD CONTROL FOR PASAHARI AREA**

---

**CHAPTER 1 GENERAL CONDITIONS OF THE STUDY AREA**

|               |   |       |
|---------------|---|-------|
| Table-II.1.1  | No. of Households and Population in the Study Area (December 1996) .....    | II-1  |
| Table-II.1.2  | Planted Area and Production of Major Food Crops (Fiscal Year 1995/96) ..... | II-2  |
| Table-II.1.3  | Transmigration Plan .....   | II-4  |
| Table-II.1.4  | Future Population in the Study Area .....                                   | II-4  |
| Table-II.1.5  | Anticipated Increase in Cropped Area and Yields .....                       | II-4  |
| Table-II.1.6  | Current Land Use in Flooded Area as of 1988 .....                           | II-7  |
| Table-II.1.7  | Weather Conditions in Pasahari Area (Kobisonta Station) .....               | II-9  |
| Table-II.1.8  | Study River Basins - Pasahari Area .....                                    | II-10 |
| Table-II.1.9  | Condition of Meteorological (Rainfall) Stations .....                       | II-11 |
| Table-II.1.10 | Condition of Hydrological Stations .....                                    | II-11 |
| Table-II.1.11 | List of Installed Observation Stations .....                                | II-11 |
| Table-II.1.12 | Features of Past Flood Damage .....   | II-12 |

**CHAPTER 2 FLOOD ANALYSIS**

|               |   |       |
|---------------|---|-------|
| Table-II.2.1  | Probable Daily Rainfall [Pasahari Area] .....               | II-19 |
| Table-II.2.2  | Rainfall Intensity [Kairatu] .....                          | II-21 |
| Table-II.2.3  | Flood Daily Rainfall in Pasahari .....                      | II-21 |
| Table-II.2.4  | Division of Samal and Kobi Catchment Areas .....            | II-22 |
| Table-II.2.5  | Proposed Values of Runoff Coefficient .....                 | II-24 |
| Table-II.2.6  | Time of Flood Concentration (Kraven's Formula) .....        | II-24 |
| Table-II.2.7  | Peak Flood and Specific Discharge by Rational Formula ..... | II-25 |
| Table-II.2.8  | Summary Result of Discharge Capacity .....                  | II-26 |
| Table-II.2.9  | Standard Asset Damage Rate in Japan .....                   | II-29 |
| Table-II.2.10 | Value of General Assets .....                               | II-29 |

|                  |  |       |
|------------------|--|-------|
| Table-II.2.11    | Paddy Rice Damage Rates.....   | II-29 |
| Table-II.2.12    | Estimation of Past Flood Damage.....                                     | II-30 |
| Table-II.2.13    | Estimation of Flood Damage with 100-year return period.....              | II-30 |
| Table-II.2.14    | Peak Discharge (m <sup>3</sup> /sec).....                                | II-30 |
| Table-II.2.15    | Estimation of Past Flood Discharges .....                                | II-32 |
| Table-II.2.16    | Estimation Method.....   | II-32 |
| Table-II.2.17    | Relationship between Flood Discharge and Damage Value .....              | II-33 |
| <br>             |  |       |
| <b>CHAPTER 3</b> | <b>FLOOD CONTROL CONCEPTUAL PLAN</b>                                     |       |
| Table-II.3.1     | Recommended Minimum Return Period of Design Flood.....                   | II-35 |
| Table-II.3.2     | Freeboard Relative to Design Flood Discharge .....                       | II-37 |
| Table-II.3.3     | Current and Planned River Conditions.....                                | II-37 |
| Table-II.3.4     | Alternative Flood Control Plans : Samal River System.....                | II-43 |
| Table-II.3.5     | Alternative Flood Control Plans : Kobi River System .....                | II-44 |
| Table-II.3.6     | Results of Uniform Flow Calculation : Samal River System .....           | II-45 |
| Table-II.3.7     | Results of Uniform Flow Calculation : Kobi River System.....             | II-46 |
| Table-II.3.8     | Work Quantities of Dikes.....  | II-49 |
| Table-II.3.9     | Project Costs.....   | II-50 |
| Table-II.3.10    | Implementation Schedule of Conceptual Flood Control Plan.....            | II-51 |
| Table-II.3.11    | Environmental Examination Matrix .....                                   | II-52 |
| Table-II.3.12    | Yearly Averages of Damage Alleviation at a 20 Year-Return<br>Period..... | II-54 |
| Table-II.3.13    | Economic Cost, NPV, B/C and IRR of Samal River.....                      | II-55 |
| Table-II.3.14    | Sensitivity Analysis - Samal River.....                                  | II-55 |
| Table-II.3.15    | Economic Cost, NPV, B/C and IRR of Kobi River.....                       | II-55 |
| Table-II.3.16    | Sensitivity Analysis - Kobi River .....                                  | II-56 |

## List of Figures

---

### **INTRODUCTION      OUTLINE OF THE STUDY**

---

|          |  |         |
|----------|--|---------|
| Figure-1 | Overall Location of the Study Areas..... | Intro-3 |
| Figure-2 | Study Flow Chart.....                    | Intro-5 |

---

### **PART I      FLOOD CONTROL FOR AMBON AREA**

---

|  |   |      |
|--|---|------|
| <b>CHAPTER 1      GENERAL CONDITIONS OF THE STUDY AREA</b> |   |      |
| Figure-I.1.1   | Population Growth in Ambon City .....   | I-1  |
| Figure-I.1.2   | Administrative Division of Central Ambon City .....                             | I-2  |
| Figure-I.1.3   | Growth of Regional GDP at 1983 constant prices .....                            | I-3  |
| Figure-I.1.4   | Population Projection in Ambon City and the Study Area.....                     | I-5  |
| Figure-I.1.5   | Schematic Topography and Geology of the River Basins<br>in the Study Area ..... | I-6  |
| Figure-I.1.6   | Geological Map of the Study Area .....  | I-7  |
| Figure-I.1.7   | Current Land Use.....   | I-9  |
| Figure-I.1.8   | Future Land Development.....  | I-10 |
| Figure-I.1.9   | Seasonal Fluctuation of Weather<br>at Pattimura Ambon Station .....             | I-11 |
| Figure-I.1.10  | Longitudinal Features of the Target Five Rivers .....                           | I-12 |
| Figure-I.1.11  | River Systems of the Target Rivers .....  | I-13 |
| Figure-I.1.12(1)   | Inundation Depth and Area .....   | I-16 |
| Figure-I.1.12(2)   | Inundation Depth and Area .....   | I-17 |
| Figure-I.1.13  | Future Water Demand Projection<br>(Study Area : Central City).....              | I-21 |
| <br><b>CHAPTER 2      FLOOD ANALYSIS</b>                   |   |      |
| Figure-I.2.1   | Plotting Positions of Daily and Hourly Probable Rainfall.....                   | I-29 |
| Figure-I.2.2   | Hyetograph of Main Flood Rainfall in Ambon .....                                | I-30 |
| Figure-I.2.3   | Actual Hyetograph of Selected Five Rainfalls .....                              | I-32 |
| Figure-I.2.4   | River Basin Division.....   | I-36 |
| Figure-I.2.5   | Basin Model.....  | I-37 |
| Figure-I.2.6   | Flood Hydrograph of Ruhu River (Return Period 30 year).....                     | I-40 |
| Figure-I.2.7   | Design Flood Hydrograph (1990/06/06 Flood Type).....                            | I-41 |
| Figure-I.2.8(1)  | Discharge Capacity .....  | I-42 |
| Figure-I.2.8(2)  | Discharge Capacity .....  | I-43 |
| Figure-I.2.9   | Assumption of Calculation of Flood Water Level .....                            | I-47 |
| Figure-I.2.10  | Estimated Flooded Depth and Area with 100-year Return Period .....              | I-48 |
| Figure-I.2.11  | Flood Discharge / Flood Scale - Damage Value Curve .....                        | I-51 |
| <br><b>CHAPTER 3      FLOOD CONTROL MASTER PLAN</b>        |   |      |
| Figure-I.3.1   | Longitudinal Section of Ruhu River.....   | I-56 |
| Figure-I.3.2   | Longitudinal Section of Batu Merah River.....                                   | I-58 |
| Figure-I.3.3   | Longitudinal Section of Tomu River.....   | I-60 |

|               |  |       |
|---------------|--|-------|
| Figure-I.3.4  | Longitudinal Section of Batu Gajah River.....  | I-62  |
| Figure-I.3.5  | Longitudinal Section of Batu Gantung River.....  | I-64  |
| Figure-I.3.6  | Locations of Candidate Dam Sites.....  | I-68  |
| Figure-I.3.7  | Water Height and Volume of Dam Reservoir.....  | I-71  |
| Figure-I.3.8  | Diversion Channel Plans.....   | I-72  |
| Figure-I.3.9  | Distribution of Flood Discharge (Ruhu River).....  | I-80  |
| Figure-I.3.10 | Distribution of Flood Discharge (Batu Merah River).....                                      | I-81  |
| Figure-I.3.11 | Distribution of Flood Discharge (Tomu River).....  | I-82  |
| Figure-I.3.12 | Distribution of Flood Discharge (Batu Gajah River).....                                      | I-83  |
| Figure-I.3.13 | Distribution of Flood Discharge (Batu Gantung River).....                                    | I-83  |
| Figure-I.3.14 | Optimum Flood Control Plan.....  | I-90  |
| Figure-I.3.15 | Optimum Flood Control Plan for Ruhu River.....   | I-91  |
| Figure-I.3.16 | Optimum Flood Control Plan for Batu Merah River.....   | I-92  |
| Figure-I.3.17 | Optimum Flood Control Plan for Tomu River.....   | I-93  |
| Figure-I.3.18 | Optimum Flood Control Plan for Batu Gajah River.....   | I-94  |
| Figure-I.3.19 | Optimum Flood Control Plan for Batu Gantung River.....                                       | I-95  |
| Figure-I.3.20 | Off-site Storage System for New Land Development.....  | I-97  |
| Figure-I.3.21 | Infiltration System in Lowland Areas.....  | I-98  |
| Figure-I.3.22 | Land Use Regulation along River Channel.....   | I-98  |
| Figure-I.3.23 | Flood Proof for Town Street.....   | I-99  |
| Figure-I.3.24 | Rainfall and Runoff Patterns.....  | I-100 |
| Figure-I.3.25 | Transfer System of Flood Information.....  | I-101 |
| Figure-I.3.26 | Flood Risk Map for Ambon Central Area.....   | I-102 |
| Figure-I.3.27 | National Level Organization for Natural Disaster<br>Countermeasures.....                     | I-103 |
| Figure-I.3.28 | Local Level Organization for Natural Disaster Countermeasures.....                           | I-103 |
| Figure-I.3.29 | River Management Zone.....   | I-105 |
| Figure-I.3.30 | Variation in Reservoir Volume with Daily Discharge (Dry Year).....                           | I-110 |
| Figure-I.3.31 | City Water Development Plan - Ambon Central Area.....  | I-111 |
| Figure-I.3.32 | Reservoir Storage Allocation.....  | I-114 |
| Figure-I.3.33 | Organization Structure of Ambon Flood Control Project Office<br>for Structural Measures..... | I-120 |
| Figure-I.3.34 | Organization of Special Committee for Non-structural Measures.....                           | I-120 |

#### CHAPTER 4 PRIORITY PROJECT

|               |   |       |
|---------------|---|-------|
| Figure-I.4.1  | Design Hyetograph : 1990/06/06 Flood.....                     | I-132 |
| Figure-I.4.2  | Planning Criteria of Ruhu River Flood Control Plan.....       | I-133 |
| Figure-I.4.3  | Ruhu River Basin.....   | I-134 |
| Figure-I.4.4  | Longitudinal Section of Ruhu River Improvement Plan.....      | I-138 |
| Figure-I.4.5  | Planning Criteria of Batu Merah River Flood Control Plan..... | I-140 |
| Figure-I.4.6  | Batu Merah River Basin.....                                   | I-141 |
| Figure-I.4.7  | Longitudinal Section of Batu Merah River Improvement Plan ... | I-145 |
| Figure-I.4.8  | Planning Criteria of Tomu River Flood Control Plan.....       | I-147 |
| Figure-I.4.9  | Tomu River Basin.....   | I-148 |
| Figure-I.4.10 | Longitudinal Section of Tomu River Improvement Plan.....      | I-153 |
| Figure-I.4.11 | Amenity Improvement Plan of Tomu River.....                   | I-155 |
| Figure-I.4.12 | Amenity Improvement Image of Tomu River.....                  | I-156 |
| Figure-I.4.13 | Planning Criteria of Batu Gajah River Flood Control Plan..... | I-158 |
| Figure-I.4.14 | Batu Gajah River Basin.....                                   | I-159 |

|               |   |       |
|---------------|---|-------|
| Figure-I.4.15 | Longitudinal Section of Batu Gajah River Improvement Plan .....         | I-164 |
| Figure-I.4.16 | Water Level and Reservoir Volume of Batu Gajah Dam .....                | I-166 |
| Figure-I.4.17 | Spillway H-Q Curve of Batu Gajah Dam .....                              | I-167 |
| Figure-I.4.18 | Flood Control Plan of Batu Gajah Dam .....                              | I-167 |
| Figure-I.4.19 | Flood Discharge Distribution of Batu Gajah River .....                  | I-167 |
| Figure-I.4.20 | Reservoir Volume Allocation for Batu Gajah Dam .....                    | I-168 |
| Figure-I.4.21 | Planning Criteria of Batu Gantung River Flood Control Plan .....        | I-170 |
| Figure-I.4.22 | Batu Gantung River Basin .....  | I-171 |
| Figure-I.4.23 | Longitudinal Section of Batu Gantung River Improvement Plan .....       | I-175 |
| Figure-I.4.24 | Water Level and Reservoir Volume of Batu Gantung Dam .....              | I-176 |
| Figure-I.4.25 | Spillway H-Q Curve of Batu Gantung Dam .....                            | I-177 |
| Figure-I.4.26 | Flood Control Plan of Batu Gantung Dam .....                            | I-177 |
| Figure-I.4.27 | Flood Discharge Distribution of Batu Gantung River .....                | I-177 |
| Figure-I.4.28 | Reservoir Volume Allocation for Batu Gantung Dam .....                  | I-178 |
| Figure-I.4.29 | Typical Cross Sections of River Improvement .....                       | I-179 |
| Figure-I.4.30 | Plan and Standard Cross Section of<br>Batu Merah Diversion Tunnel ..... | I-182 |
| Figure-I.4.31 | Batu Gajah Multi-purpose Dam .....                                      | I-184 |
| Figure-I.4.32 | Batu Gantung Multi-purpose Dam .....                                    | I-185 |
| Figure-I.4.33 | Location of Quarry Site and Access Roads .....                          | I-191 |
| Figure-I.4.34 | Construction Schedule .....   | I-193 |

---

**PART II FLOOD CONTROL FOR PASAHARI AREA**

---

**CHAPTER 1 GENERAL CONDITIONS OF THE STUDY AREA**

|                  |  |       |
|------------------|--|-------|
| Figure-II.1.1    | Irrigation Scheme in Pasahari Area .....                   | II-3  |
| Figure-II.1.2    | Schematic of Typical Flood Plain in Pasahari .....         | II-5  |
| Figure-II.1.3    | Geological Map of Pasahari Area .....                      | II-6  |
| Figure-II.1.4    | Land Use Situation in Pasahari Area in 1988 .....          | II-8  |
| Figure-II.1.5    | Seasonal Fluctuation of Weather in Kobisonta Station ..... | II-9  |
| Figure-II.1.6    | Longitudinal Profiles of Samal and Kobi Rivers .....       | II-10 |
| Figure-II.1.7    | Samal and Kobi River Systems .....                         | II-10 |
| Figure-II.1.8    | Location of Observation Stations .....                     | II-11 |
| Figure-II.1.9(1) | Inundation Area caused by 1988/01/27 Flood .....           | II-13 |
| Figure-II.1.9(2) | Inundation Area caused by 1992/04/03 Flood .....           | II-14 |
| Figure-II.1.9(3) | Inundation Area caused by 1996/02/19 Flood .....           | II-15 |
| Figure-II.1.9(4) | Inundation Area caused by Annual Flood .....               | II-16 |

**CHAPTER 2 FLOOD ANALYSIS**

|                  |   |       |
|------------------|---|-------|
| Figure-II.2.1    | Plotting Position of Probable Daily and Hourly Rainfall ..... | II-20 |
| Figure-II.2.2    | Division of Samal and Kobi Catchment Areas .....              | II-23 |
| Figure-II.2.3(1) | Discharge Capacity .....                                      | II-26 |
| Figure-II.2.3(2) | Discharge Capacity .....                                      | II-27 |
| Figure-II.2.4    | Estimated Flooded Area with 100-year Return Period .....      | II-31 |
| Figure-II.2.5    | Flood Discharge - Damage Value Curve .....                    | II-33 |
| Figure-II.2.6    | Flood Return Period - Damage Value Curve .....                | II-33 |

|                  |   |       |
|------------------|---|-------|
| <b>CHAPTER 3</b> | <b>FLOOD CONTROL CONCEPTUAL PLAN</b>  |       |
| Figure-II.3.1    | Schematic Cross Section of River.....   | II-36 |
| Figure-II.3.2    | Division of River Sections for River Improvement Plan.....  | II-38 |
| Figure-II.3.3    | Current Condition of Samal River<br>along the Planned River Course.....   | II-39 |
| Figure-II.3.4    | Current Condition of Musi River<br>along the Planned River Course.....  | II-40 |
| Figure-II.3.5    | Current Condition of Kobi River<br>along the Planned River Course.....  | II-41 |
| Figure-II.3.6    | Current Condition of Tinupa River<br>along the Planned River Course.....  | II-42 |
| Figure-II.3.7    | Standard Cross Section of Dike.....   | II-44 |
| Figure-II.3.8    | Alternatives of Flood Control Plan for Case-S1 and Case-K1<br>(Dike height = 2.0 m with exception of Kobi River<br>downstream = 2.5 m)..... | II-47 |
| Figure-II.3.9    | Alternatives of Flood Control Plan for Case-S2 and Case-K2<br>(Dike height = 2.5 m for all sections).....                                   | II-48 |



## List of Abbreviations

|                       |  |
|-----------------------|--|
| AMDAL                 | : Analisa Mengenai Dampak Lingkungan (Environment Impact Assessment)                                   |
| ANDAL                 | : Analisa Dampak Lingkungan (Environmental Impact Analysis)  |
| ABLN                  | : Administrasi Bantuan Luar Negeri (Foreign Aid Administration)  |
| BAPPENAS              | : Badan Perencanaan Pembangunan Nasional<br>(National Development Planning Board)                      |
| BAPPEDA               | : Badan Perencanaan Pembangunan Daerah<br>(Regional Development Planning Board)                        |
| BAPEDAL               | : Badan Pengendalian Dampak Lingkungan (Environmental Impact Agency)                                   |
| BMG                   | : Badan Meteorology dan Geofisika (Meteorology and Geophysical Agency)                                 |
| BPP                   | : Bina Program Pengairan (Directorate Of Planning and Programming)                                     |
| BPN                   | : Badan Pertanahan Nasional (National Land Agency)   |
| BUPATI                | : Kepala Daerah Tingkat II, Kepala Kabupaten (Head Of Regency)   |
| BPS                   | : Biro Pusat Statistik (Central Bureau For Statistics)   |
| CAMAT                 | : Kepala Kecamatan (Head Of Subdistrict)   |
| DATI I / DATI II      | : Daerah Tingkat I (Provincial Level) / Daerah Tingkat II (Municipal Level)                            |
| DPU (Dep. PU)         | : Departement Pekerjaan Umum (Ministry Of Public Works)  |
| DITJEN                | : Direktorat Jenderal (Directorate General)  |
| DITJEN<br>BINA MARGA  | : Direktorat Jenderal Bina Marga<br>(Directorate General Of Highways = DGHW)                           |
| DITJEN<br>CIPTA KARYA | : Direktorat Jenderal Cipta Karya<br>(Directorate General Of Human Settlements = DGHS)                 |
| DITJEN<br>PENGAIRAN   | : Direktorat Jenderal Pengairan<br>(Directorate General of Water Resources Development = DGWRD)        |
| DIRJEN                | : Direktur Jenderal (Director General)   |
| DPR                   | : Dewan Perwakilan Rakyat (House of Representatives = Parliament)                                      |
| DRM                   | : Daftar Rekanan Mampu (List Of Capable Contractors)   |
| EIRR                  | : (Economic Internal Rate Of Return)   |
| EKUIIN                | : Ekonomi, Keuangan dan Industri (Economy, Finance and Industry)                                       |
| GBHN                  | : Garis Besar Haluan Negara (National Policy Guidelines)   |
| GOI                   | : (Government Of Indonesia)  |
| GOJ                   | : (Government Of Japan)  |
| HAKI                  | : Himpunan Ahli Konstruksi Indonesia (Indonesian Contractors Association)                              |
| IAI                   | : Ikatan Arsitek Indonesia (Indonesia Architects Association)  |
| IWT                   | : Indonesia Wilayah Timur (Eastern Region of Indonesia)  |
| IKK                   | : Ibu Kota Kecamatan (Sub-District Capital)  |
| INKINDO               | : Ikatan Nasional Konsultan Indonesia (Indonesian Consultants Association)                             |
| INPRES                | : Instruksi Presiden (Presidential Instruction)  |
| IDT                   | : Inpres Desa Tertinggal<br>(Presidential Instruction for Underdeveloped Village)                      |
| IPEDA                 | : Iuran Pembangunan Daerah (Regional Development Tax)  |
| IUDP                  | : (Integrated Urban Infrastructure Development Programme = P3K1)                                       |
| JICA                  | : (Japan International Cooperation Agency)   |
| KA-ANDAL              | : Kerangka Acuan Analisa Dampak Lingkungan<br>(Terms of Reference for Environmental Impact Assessment) |
| KANWIL                | : Kantor Wilayah<br>(Regional Office of the Ministry at Provincial Level)                              |
| KAKANWIL              | : Kepala Kantor Wilayah (Head of the Regional Office)  |

|            |   |
|------------|---|
| KADIN      | : Kepala Dinas (Head of Provincial Office)  |
| KASUBDINAS | : Kepala Sub-Dinas (Head of Sub-Agency / Provincial Office)   |
| KASUBDIT   | : Kepala Sub-Direktorat (Head of Sub-Directorate)   |
| KDPU       | : Kepala Dinas Pekerjaan Umum<br>(Head of Provincial Public Works Office)                                     |
| KEPMEN     | : Keputusan Menteri (Ministerial Decree)  |
| KEPPRES    | : Keputusan Presiden (Presidential Decree)  |
| KK         | : Kepala Keluarga (Head of Family / Household)  |
| KODYA      | : Kotamadya (Municipality)  |
| KABUPATEN  | : District or Regency, Division of Province, same level as Municipality                                       |
| KECAMATAN  | : Sub-division of Kabupaten or Municipality   |
| KELURAHAN  | : Sub-division of Kecamatan, the same level as Village (Desa)   |
| LIPI       | : Lembaga Ilmu Pengetahuan Indonesia (Indonesian Institute of Science)  |
| LKMD       | : Lembaga Ketahanan Masyarakat Desa<br>(Village Community Residence Institution)                              |
| LSM        | : Lembaga Swadaya Masyarakat (Non Governmental Organization = NGO)  |
| LURAH      | : Kepala Desa / Kepala Kelurahan (Village Head)   |
| MCK        | : Mandi Cuci Kakus (Communal Unit for Bathing, Washing and Lavatory)  |
| MPR        | : Majelis Permusyawaratan Rakyat<br>(People Consultative Assembly = Congress)                                 |
| OECF       | : (The Overseas Economic Cooperation Fund)  |
| P2KT       | : Program Pembangunan Kota Terpadu (Integrated Urban Dev. Program)  |
| P3KT       | : Program Pembangunan Prasarana Kota Terpadu<br>(Integrated Urban Infrastructure Development Program = IUIDP) |
| PEMDA      | : Pemerintah Daerah ( Local / Regional Government )   |
| PDAM       | : Perusahaan Daerah Air Minum (Local Government Water Enterprise)   |
| PIL        | : Penyajian Informasi Lingkungan (Prelim. Environmental Information)  |
| PELITA     | : Pembangunan Lima Tahun (Five Year National Development)   |
| PERDA      | : Peraturan daerah ( Local Government Regulation )  |
| PIMPRO     | : Pemimpin Proyek (Project Manager)   |
| PPN        | : Pajak Pertambahan Nilai (Value Added Tax = VAT)   |
| PPSAPB     | : Proyek Pengelolaan Sumber Air & Pengendalian Banjir<br>(Water Resources Management & Flood Control Project) |
| PU         | : Pekerjaan Umum (Public Works)   |
| PUSDIKLAT  | : Pusat Pendidikan & Latihan (Education & Training Center)  |
| PUSLITBANG | : Pusat Penelitian & Pengembangan (Research & Development Center)   |
| RDTRK      | : Rencana Detail Tata Ruang Kota (Detailed Urban Plan)  |
| REPELITA   | : Rencana Pembangunan Lima Tahun (Five-Year National Dev. Plan)   |
| RKL        | : Rencana Pengelolaan Lingkungan (Environmental Management Plan)  |
| RPL        | : Rencana Pemantauan Lingkungan (Environmental Monitoring Plan)   |
| SEL        | : Studi Evaluasi Lingkungan (Environmental Evaluation Study)  |
| SUBBAG     | : Sub-Bagian (Sub-Division)   |
| SUBDIT     | : Sub-Direktorat (Sub-Directorate)  |
| WALIKOTA   | : Mayor of Municipality   |