#### 16.4 Throughway of Gwalior Bypass

#### 16.4.1 Review of Pre-F/S Alignment

#### 16.4.1.1 Detailed Field Investigation

The Study Team carried out the detailed field investigation along the Pre-F/S alignment between 4 and 8 November 1997 to review the Pre-F/S alignment and re-identify major controls for the establishment of survey corridor. A complete photo album was prepared by taking shots of all necessary objects in the fields. This was referred while the horizontal alignment was being prepared and finally verified.

#### 16.4.1.2 Three Major Controls Newly Identified

Three major controls were newly identified during the detailed field investigation as described below:

## 1) Waste Water Basin (STA. 2+100 - 2+500)

Waste water basin from distillery is located at STA. 1+500 with a size of 1 km wide and 1.5 km long. The Pre-F/S alignment crosses this area at the centre.

# 2) Independent Rocky Hill (Approximately STA. 4+500 – 7+000)

Independent Rocky Hill, where specified as Reserved Forest Area, exists at Approximately STA. 4+500 – 7+000. The height of the top flat area of the hill is approximately 30 m from the surrounding cultivated areas. The Pre-F/S alignment crosses this hill around 3 km in distance and the cut work will necessitate a considerable hard rock excavation.

# 3) Sojina Village and a Lake (STA. 13+200 - 14+000)

Sojina village is located at STA. 13+500 and a lake, 200 m wide and 300 m long exists approximately 500 m Southeast of the village. This lake is the only watering place of livestock in this area and also are some daily traffic between the village and the lake was observed. The Pre-F/S alignment will cut the access between the village and the lake, and it will damage the local community which should involve the access to the lake.

#### 16.4.1.3 Summary of Major Controls

Including the above mentioned new controls, the wide-area controls within approximate 1 km either side were summarised in Table 16-39. There are eight(8) villages, six(6) major roads including NH3 at the beginning and end point of the proposed bypass, two(2) railways, and four(4) watercourses including two(2) natural rivers. It shall be noted that there are 10 topographic controls, hills and valleys, in the project area.

Table 16-39 Major Controls

No.	STA	Side	Description
1	0	_	NH3
2	0.2	_	Railway (Narrow Gauge)
3	0.7	Right	Village(Niraoli)
4	1.5	Left	Village(Gajupura)
5	2.4	Left	Waste Water Pond
6	2.7	Left	Village(Jinaoh)
7	2.8	Left	Distillery
8	3.5	<del>-</del>	Major Village Road
9	5	Right	Rocky Hill (Reserved Forest Area)
10	7.7		Major Canal
11	8	Right	Village(Kulalth)
12	9.4	_	Major Village Road
13	10.3	<u> </u>	Natural River
14	12.8		Natural River
15	12.9	Right	
16	13.4	Left	Village(Sojina)
17	13.6	Left	Lake

No.	STA	Side	Description
18	15	Left	Village(Banjara ka pura)
19	15.2	_	Valley(Cultivation Area)
20	15.8		Major Village Road (Reserved Forest Area)
21	15.8-1	Left	Village Road (Reserved Forest Area)
22	17	Left	Valley (Reserved Forest Area)
23	19.7	Right	Valley(Reserved Forest Area)
24	20	Left	Hill(Reserved Forest Area)
25	20.5	Left	Valley(Reserved Forest Area)
26	21	Left	Valley (Reserved Forest Area)
27	22.5	Right	Valley(Reserved Forest Area)
28	23.1	Right	Hill(Reserved Forest Area)
29	23.4	Left	Hill(Reserved Forest Area)
30	24.2	Left	Lake(Raipur Kurd)
31	21.2	Right	Village(Raipur Kurd)
32	25.6		Major Canal
33	26.1	<u> </u>	Railway (Broad Gauge)
34	26.5		NH3

# 16.4.2 Alignment Designed

#### 16.4.2.1 Basic Data

The following basic data were obtained and/or prepared by the Study Team for the alignment design of Gwalior Bypass:

# 1) Topographic Map of Survey of India (Scale 1:50,000/250,000)

These maps were used to identify the name of villages and to obtain wide area information such as locations of major rivers, main roads and railways.

# Topographic Map prepared in the F/S

Topographic map prepared in the F/S was submitted to the Study Team at the end of February 1998. All controls were identified and work quantities were estimated based on this map.

## 3) Digital ASCII data of topographic survey

Digital ASCII data of topographic survey was also submitted from the entrusted local subcontractor. Digital Terrain Model (DTM) was established from the data in order to make the earthwork volume calculation.

#### 4) Satellite Photographs

Satellite photographs obtained from National Remote Sensing Agency (NRSA) were utilised for identification of the controls. As dense forest area are located from STA. 19+500, Satellite Photographs was useful in order to identify the possible route alternatives.

#### 5) Photographs

During the detailed site investigation by the Study Team, a complete photo album was prepared by taking shots of all necessary objects in the fields. This was referred while the horizontal alignment was being prepared and finally verified.

#### 16.4.2.2 Designed Alignment

## (1) Horizontal Alignment

Horizontal alignment was formulated applying radii of 600 – 3,000 m. Sixty-two (62) percent of the alignment is circular curves and spiral elements and the other forty-eight (38) percent is tangent elements. Spirals were attached between tangents and circular curves properly and superelevation was attained where required.

Figure 16-15 shows the relationship between the PWD alignment and JICA alignment. Figure 16-16 shows design element of the bypass.

Design Element	Length (m)	Ratio (%)
Tangent	10,095.5	38
Curve	11,831.7	44
Spiral (Clothoide)	4,720.0	18
	26.647.2	100


Table 16-40 Summary of Horizontal Alignment

## (2) Vertical Alignment

In the section of flat terrain area, especially, at the beginning and end section of the bypass, fill type structures were mainly applied. In the hilly section, cut and fill structures were applied to enable the minimisation of the earthwork volume. As the bypass is intended to operate as full control of access, all crossing with the main existing roads were designed as the grade separated intersections.

Maximum grade of 3.3 percent was applied for the vertical alignment and level grade was allowed where the height of filling is lower than 3 m, and the normal crossfall is applied.

# **ROUTE MAP OF GWALIOR BYPASS**



# PROPOSED BY JICA STUDY TEAM PROPOSED BY STATE PWD NH3 NATIONAL HIGHWAY OTHER ROAD RAILWAY RIVER, CANAL, DRAIN

JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)
THE FEASIBILITY STUDY ON NATIONAL HIGHWAY BYPASSES IN INDIA

OWO TITLE :

Figure 16-15 Route map of Gwalior Bypass






Figure 16-16 Horizontal Design Element of Gwalior Bypass

• 

Table 16-41 Summary of Vertical Alignment

Grade (%)	Length (m)	Ratio (%)
G = 0.0	3,050	11,5
0.0 < G <= 0.3	1,850	7.0
0.3 < G <=1.0	4,400	16.6
1.0 < G <= 2.0	13,197.182	49.8
2.0 < G <= 3.0	3,350	12.6
(Max. = 3.3)	(650)	(2.5)
Total	26,497.182	100.0

#### 16.4.3 Pavement Design

#### 16.4.3.1 Traffic Analysis and Determination of Design MSAL

As category of truck was not sub-divided in to LCV, HCV and MAV in the forecast, all volume was assumed as HCV, considering the current proportion (LCV: 10%, HCV: 87%, MAV: 3%) in to account, in order to estimate appropriate damage incurred by the vehicles. Table 16-42 shows the future traffic projection for commercial vehicles for Gwalior Bypass.

Table 16-42 Future Traffic Projection for Commercial Vehicles

Year 2002		Total (A)	Year 2012		Total (B)	Growth Rate(%/yr)
Bus	Truck		Bus	Truck	Ì	
124	3,983	4,107	220	8,000	8,220	7.19%

The design traffic volume recalculated as shown in Table 16-43.

Table 16-43 Design Traffic Volume

Year 2002		Total (A)	Design Traffic	Directional
Bus	Truck		(B:75% of A)	Traffic (C)
124	3,983	4,107	3,080	1,540

On the basis of the traffic projection and VDF, 6.69 for Gwalior, cumulative equivalent standard Axle Loads in Millions (MSAL) for Gwalior Bypass was calculated in following table.

Table 16-44 Million Equivalent Standard Axle Loads (MSAL)

Directional	Growth Rate(%/yr)	Design Life	VDF	MSAL
Traffic (C)				
1,540	18.23%	10	6.69	89

The design MSAL value is determined as 90 for the Feasibility Study.

#### 16.4.3.2 Composition of the Pavement

Taking into account that the design CBR value of subgrade was more than 30 percent, the total depth of the pavement is probably able to reduce to around 500 – 600 mm, based on Japanese experience.

However, the similar composition of the pavement is not clearly specified in IRC's guideline, the Study Team leaves the total depth of the pavement as 800 mm in the Feasibility Study. Further study to reduce the thickness of the pavement structure is strongly recommended in the detailed design phase. This will make a considerable cost-down of the construction.

Table 16-45 Pavement Composition in Gwalior Bypass

No.	Depth (mm)	Acc. Depth (mm)	Sign	Description
1	40	40	AC	Asphalt Concrete
2	160	200	DBM	Dense Bituminous
3	300	500	WMM	Wet Mix Macadam
4	300	800	GSB	Granular Sub-Base

#### 16.4.4 Drainage Design

#### 1) Longitudinal Drainage

Following longitudinal drainage was installed:

- 0 Kerb ditch at the fill section, higher than 3 m;
- 1 Berm ditch at the cut section, deeper than 7m;
- 2 Side ditch at the top of cut slope;
- 3 Side ditch at the bottom of cut slope; and
- 4 Side ditch along the service road;

Necessary locations to install the above drainage were identified based on the result of the alignment design.

# 2) Cross-sectional Drainage

Following cross-sectional drainage was installed:

- 0 Vertical drain at fill section where the height is more than 3 m;
- 1 Vertical drain at cut section where the height is more than 7 m; and
- 2 Transversal drain at superelevated section

Necessary locations to install above drainage were identified based on the result of the alignment design.

# 16.4.5 Utility Relocation

According to the concept and criteria, all utilities which have a potential to be affected by ROW were identified using the topographic map in a scale of 1:5,000.

High Tension Lines (HTL) is the biggest utilities when it is required the relocation. HTL will cross the proposed alignment at two places, STA. 1+800 and STA. 6+300.

# 16.4.6 Work Quantities

Overall work quantities derived from this preliminary design of throughway was summarised in Table 16-46.

Table 16-46 Quantities of Throughway Works

Item	Unit	Amount
Bypass Length	Km	26.497
Earthwork Section	Km	26.360(99.5%)
Structure Section	Km	0.137(0.5%)
Earthwork Balance		-1,335,328
Fill	M <sup>3</sup>	1,686,172
Cut	M³	350,844
Pavement		
AC	M³	20,138
DBM	M³	75,516
WMM	M <sup>3</sup>	151,033
GSB	M <sup>3</sup>	151,033
Service Road	Km	24.87
Slope Protection	M <sup>2</sup>	323,200
Drainage		
Kerb	M	19,600
Berm	M	800
Side Ditch	M	32,270
Vertical Drain	M	15,110
Transversal Drain	M	1,908
Utility Relocation		
HTL	M	200
Power Line	M	1,590
Telecom. Line	М	1,590
Well/Pump	М	10

# 16.5 Design of Intersection in Gwalior Bypass

#### **16.5.1** General

The Gwalior Bypass has two link points with the existing NH3 at the beginning point (BP) and end point (EP) of the throughway. These link points need to secure smooth and safe traffic flow for the road users as far as possible.

#### 16.5.2 Intersection at the Beginning Point

#### 16.5.2.1 Characteristics of Traffic Flow

#### Traffic Flow between NH3 (Agra side) and the Bypass

In the bypass section near BP, just after the diversion from NH3 to the bypass, the installation of tollgate was proposed. The tollgate section will require the length of 150 m as minimum including transition section to the throughway.

The design speed of section between the tollgate and BP does not need to the same design speed of the throughway because this section is regarded as a part of intersection, or the transition section between NH3 and the bypass. Consequently, the geometric design of the horizontal alignment does not require the adoption of a large curvature as required for the throughway.

#### Traffic Flow on NH3, between Agra side and Gwalior side

As the traffic flow from Gwalior side to Agra side will be crossed by the flow from the bypass to NH3 (Gwalior side), the careful study regarding the intersection layout is required.

The flow from Agra side to Gwalior side may utilise the existing NH3 as it is. However, this directional flow will receive the traffic flow which runs from the bypass to the NH3 (Gwalior side). Therefore, this traffic flow will require an appropriate merging section, which may necessitate an additional lane, to secure the smooth and safe traffic.

#### Traffic Flow between NH3 (Gwalior side) and the bypass

Based on the future traffic demand forecast, this directional traffic flow showed very small amount compared to other traffic flows. However, the traffic which tries to enter NH3 (Gwalior side) from the bypass is to at-grade cross two times on the bypass and on NH24. Intersection layout design shall be carried out carefully, taking into account this traffic movement, to minimise the adverse influence to the overall traffic management in this intersection.

#### 16.5.2.2 Selection of Intersection Type of BP

Four alternative layouts were prepared for the intersection design as illustrated below.




Figure 16-17 Intersection Type of Alternative 1




Figure 16-18 Intersection Type of Alternative 2




Figure 16-19 Intersection Type of Alternative 3




Figure 16-20 Intersection Type of Alternative 4

Table 16-47 Alternative of Intersection Type

	Merit	Demerit
Alternative 1	Less civil work will be required for the existing NH.	·Large additional land will be required.
Alternative 2	<ul> <li>Less additional land will be required.</li> <li>Less civil work will be required for the existing NH.</li> <li>Intersection angle between By pass and the</li> </ul>	Intersection between Bypass and the approach from NH is located on the curve
Alternative 3	Intersection angle between Bypass and the approach from NH is 90 degrees.  Intersection between the bypass and the approach from the NH is located on the tangent section of the bypass alignment.	• Additional land will be required for relocation of NH. • Alignment of NH will be worse than the present.
Alternative 4	•Less affection to NH during the construction. •Intersection angle between Bypass and the	<ul> <li>Alignment of bypass is worse than other alternatives.</li> <li>Additional land will be required for the bypass.</li> </ul>

## 16.5.2.3 Proposed Intersection type at BP of Gwalior Bypass

Based on the consideration described in the previous section, the Study Team recommends to apply the Alternative 2 as the proposed intersection layout for the project.

Figure 16-21 shows the recommended layout of the intersection at BP of Gwalior Bypass.




Figure 16-21 Layout of the Intersection at the Beginning Point of Gwalior
Bypass

#### 16.5.3 Intersection at the End Point

#### 16.5.3.1 Characteristics of Traffic Flow

Based on the future traffic demand forecast, the majority of traffic flow at this intersection will be given by the movement between the bypass and NH3 (Mumbai side), 25,400 pcu/day in 2012. The traffic movement on NH3 between Gwalior side and Mumbai side gave the second traffic volume. The third (the smallest) traffic is between the bypass and NH3 (Gwalior side). The Study Team gave the priority to the directional traffic flow between the bypass and NH3 (Mumbai side).

#### 16.5.3.2 Proposed Intersection type of EP

The alternative study of this intersection layout was quite similar to the study stated in Section 6.2.2 as the site situation is in mirror symmetry. Accordingly, the Alternative 2 type, similar to Figure 16-18, was judged as the most appropriate layout for the intersection at this location. The recommended layout of the intersection at EP of Gwalior Bypass is shown in Figure 16-22.




Figure 16-22 Layout of the Intersection at the End of Point of Gwalior Bypass

# 16.5.4 Work Quantities

#### 16.5.4.1 Work Quantities of BP Intersection

Work quantities of the proposed intersection at the BP of Gwalior Bypass is summarised in Table below.

ltem	Unit	Amount
2 Lane Approach Road	m	230
Earth filling	m3	39100
Pavement	m2	2990

Work quantities of toll barrier at BP is as follows:

Item	Unit	Amount
Toll barrier	Each	1
Earth filling	m3	880
Pavement	m2	440
Toll booth	Each	3

#### 16.5.4.2 Work Quantities of EP Intersection

Work quantities of the intersection at the EP is shown in the table below.

Item	Unit	Amount
2 Lane Approach Road	m	130
Earth filling	m3	2210
Pavement	m2	1690

Work quantities of toll barrier at EP is as follows:

Item	Unit	Amount
Toll barrier	Each	1
Earth filling	m3	880
Pavement	m2	440
Toll booth	Each	3

#### 16.6 Structure Design of Gwalior Bypass

#### 16.6.1 General

Methodology of structure planning and design was described in Chapter 15.11, "Design Standard and Criteria of Structures".

## 16.6.2 Crossing Facilities

#### 16.6.2.1 Roads

There is no highway or district road which cross the proposed bypass, and 12 village roads and 2 cart tracks were identified to cross the proposed bypass.

#### 16.6.2.2 Railways

Two railway lines cross the bypass at near the beginning point. The current feature is single track, narrow gauge. However, according to the discussion with state PWD and Ministry of Railway, it will be abandoned in near future.

The other one near the end point is single track, non-electrified meter gauge, and in future, it will be upgraded to double track, non-electrified broad gauge in the future.

#### 16.6.2.3 Water Channels

6 rivers and 3 canals were identified to cross the proposed bypass. Some of their hydrological feature were investigated and analysed.

#### 16.6.2.4 Summary of Crossing Facilities

Crossing facilities are summarised as shown in Table 16-48.

Table 16-48 Major Crossing Facilities in Gwalior Bypass (1/2)

No.	STA	Type and Class	Present Co	ondition	Remarks
1	0+190	Railway	Narrow Gauge Single Track Non-electrified		Scheme of Ministry of Railway was accepted by PWD Gwalior.
2	0+510	RD - VR	Width: 7.7m Height: 1.0m	(Non-paved)	
3	1+150	RD – VR			
4	2+510	RD - VR			
5	3+580	RD - VR	Width: 4.5~6.0m C.W.: 2.5m Height: 0.7m	(Paved)	Drainage is at one side.
6	4+400	RD - VR	Width: 3.5m Height: 0.6m	(Non-paved)	
7	4+735	WC - Minor Canal	Width: 10.5m Depth: 2.0m	from G.L.	Jigsauli Minor Design Discharge 10~12m³/sec
8	7+470	RD - CT	Width: 2.5m	(Non-paved)	
9	7+760	WC - Major Canal	Width: 12.4m Depth: 2.3m	from G.L.	TIGHARA CANAL Design Discharge 20m³/sec
10	7+925	RD – VR			*
11	8+170	RD - VR	Width: 6.4m C.W.: 2.9m Height: 1.0m	(Paved)	
12	8+190	WC - River	Width: 7.0m Depth: 5.0m		Kharai nala 3 <sup>rd</sup> order of River Water only in rainy season
13	9+370	WC - Minor Canal	Width: 5.3m Depth: 2.0m	from G.L.	Tighara east of Rai Ka Pura Village Design Discharge 20m³/sec (Presently abandoned)
14	9+370	RD - VR	Width: 7.0m Height: 2.0m	(Non-paved)	

Note: Present Condition RD:

Height is measured from existing ground level.

WC:

Width is distance between inside top of embankments.

G.L.:

**Existing Ground Level** 

Table 16-48 Major Crossing Facilities in Gwalior Bypass (2/2)

No.	STA	Type and Class	Present Condition	Remarks
15	10+340	WC - River	Width: 25.0m Depth: 5.0m from G.L.	Bandha Nala (Babukapura) Water only in rainy season
16	12+720	WC - River	Width: 14.0m Depth: 6.3m from G.L.	Rai ka Pura (Sojina)
17	15+150	RD - CT	(Not clear)	To Rai ka Pura
18	15+280	RD - VR	Width: 6.5m (Paved) C.W.: 2.5m Height: 1.0m	Connection of Tighara and Bithohi
19	18+230	RD - VR	Width: 4.5m (Paved) C.W.: 3.0m Height: 1.0m	To Deokhon
20	23+710	RD - VR		To Raipur Khuid
21	23+960	WC - River	Width: 12.0m Depth: 4.0m from G.L.	Raipur Khurd
22	24+120	RD - VR	(Non-paved)	
23	25+070	WC - River		
24	25+650	WC - River	Width: 13.3m Depth: 5.8m from G.L.	Raipur Tighara Nala *Village Road Bridge at vicinity
25	26+100	Railway	Broad Gauge Single Track Non-electrified	*Future Programme is confirmed by Ministry of Railway. (Broad Gauge, 2 Track, Non-electrified)

Note: Present Condition RD:

Height is measured from existing ground level.

WC:

Width is distance between inside top of embankments.

G.L.:

**Existing Ground Level** 

# 16.6.3 Design Condition (1), Hydrology

#### 16.6.3.1 General

Hydrological analysis was carried out for individual crossing facility of water channel identified.

Scope of work and applied formula of hydrological analysis were described in Chapter 15.11, "Design Standard and Criteria of Structure".

# 16.6.3.2 Summary of Hydrological Analysis

# (1) Maximum Design Discharge

## a) River

Table 16-49 Maximum Design Discharge of Rivers

No.		River		Rational formula				eken's rmula	Design Discharge	
of CF	SIA	River	A (hectare)	f	f p lc		Q (m³/sec)	Cd	Q (m³/sec)	Qd (m³/sec)
12	8+190	Kharai nala	1,200	0.93	0.52	9.12	148.2	6	1223.3	222.3
15	10+340	Bandha nafa	100	0.98	0.52	9.12	13.0	6	189.7	19.5
16	12+720	Rai ka Pura	2,200	0.85	0.52	9.12	248.3	6	1927.4	372.5
21	23+960	Raipur Khurd	100	0.98	0.52	9.12	13.0	6	189.7	19.5
23	25+070		-	-		-		-	-	•
24	25+650	Raipur Tighara nala	300	0.96	0.52	9.12	38.2	6	432.5	57.3

#### b) Canal

Table 16-50 Maximum Design Discharge of Canals

No.	STA	Name of Canal	Design Discharge (m³/sec)	Other Additional Information
7	4+735	Jigsauli Minor	10~12	
9	7+760	TIGHARA CANAL	20	Village Road Bridge at vicinity
13	9+370	Tighara east of Rai Ka Pura Village	20	Presently abandoned, and filled with rainy water

# (2) Design Highest Flood Level (DHFL) of Rivers

Table 16-51 Design Highest Flood Level

No.			M.O.D.	Application of Manning's Formula					
of CF	STA	River	Qd (m³/sec)	R (m)	S	n	V (m/sec)	A (m²)	OHFL. (m)
12	8+190	Kharai nala	222.3	2.7	1 / 182	0.045	3.2	70.8	6.5
15	10+340	Bandha nala	19.5	0.8	1 / 182	0.045	1.4	23.2	2.5
16	12+720	Rai ka Pura	372.5	1.8	1/62.5	0.035	5.3	90.5	5.0
21	23+960	Raipur Khurd	19.5	1.0	1/40	0.040	4.0	8.3	1.5
23	25+070		•	-	-	-	-	•	-
24	25+650	Raipur Tighara nala	57.3	1.3	1 / 164	0.040	2.4	13.7	2.5

Note: R:

hydraulic mean depth

S: bed slope

n:

rugosity co-efficient

V: velocity considered uniform throughout the cross-section

A:

available throughout area

OHFL: from deepest bed

# (3) Minimum Vertical Clearance

## a) River

Table 16-52 Minimum Vertical Clearance

No. of CF	STA	River	River Qd (m³/sec)		Minimum Vertical Clearance (mm)
12	8+190	Kharai nata	222.3	WCCBL	600
15	10+340	Bandha nala	19.5	WC-BR	600
16	12+720	Rai ka Pura	372.5	WC-BR	1,200
21	23+960	Raipur Khurd	19.5	WCCBM	600
23	25+070	-	-	WCCBM	600
24	25+650	Raipur Tighara nala	57.3	WC-BR	900

Note: No. of CF: Number of Crossing Facility

#### b) Canal

#### 0 Major Canal

Applied structure is bridge type structure, and minimum required clearance is defined with M.D.D. of each canal. However, in most case, vertical clearance was controlled by the village road along with canal.

#### 1 Minor Canal

Applicable structure is Culvert Box (WCCBS), and 600mm of vertical clearance was applied for flow obstruction caused by sediment in the future.

#### (4) Afflux

Afflux is required to consider for river at which the bridge structure was proposed.

Table 16-53 Afflux

		M.D.D. Orifice I							
No.	STA	River	Qd (m³/sec)	L (m)	W (m)	e	Co	႘ (m)	Obstructions
15	10+340	Bandha nala	19.5	25.0	25.0	0.00	1.000	0.000	No pier
16	12+720	Rai ka Pura	372.5	42.6	45.6	0.16	0.948	0.360	2 piers
24	25+650	Raipur Tighara nala	57.3	15.3	16.3	0.15	0.952	0.140	1 oler

Note: L: Sum of bridge spans

W: Unobstructed width of stream

e: Coefficient of Orifice Formula (Defined by L / W)

Co: Coefficient of Orifice Formula (Defined by L / W)

## (5) Maximum Depth of Scour

Maximum depth of scour is also required to consider for water channel at which the bridge structure was proposed.

Table 16-54 Maximum Depth of Scour

No.	STA	River	M.D.D. Qd (m³/sec)	E.L.W. (m)	D <sub>b</sub> (m²/sec)	K <sub>st</sub>	<b>ძ</b> <sub>sm</sub> (m)	M.D.S. (m)
15	10+340	Bandha nala	19.5	25.0	0.8	2.000	0.9	Abut; 1.1 Pier; 1.8
16	12+720	Rai ka Pura	372.5	21.5	17.3	2.000	7.1	Abut; 9.0 Pier; 14.2
24	25+650	Raipur Tighara nala	57.3	15.3	3.7	1.750	2.7	Abut; 3.4 Pier; 5.4

Note:

E.L.W.: Effective linear waterway which is the width of water surface caused by M.D.D.

O<sub>b</sub>: Discharge divided by E.L.W.

K<sub>sf</sub>: Silt factor of bed material

d<sub>sa</sub>: Mean depth of Scour

M.D.S: Maximum depth of scour

# (6) Application of Structures for Water Channel

With considering M.D.D. and other design condition, structure for individual water channel were applied.

#### a) River

Reported H.F.L. was applied for only the reference with DHFL. This is because it was the interviewed value from domestic residences, and not recorded value.

1) Facility No.12 (STA. 8+190, Location: Kharai nala)

Table 16-55 Hydrological Condition of Facility No.12

Item	Condition	
M.D.D. (m³/sec)	222.3	
Velocity of flow (m/sec)	3.2	
DHFL	6.5m above water bed level	
Reported H.F.L.	6.5m above water bed level	
Other information Water only in rainy season, and flow occupies 400m on each side and area gets		

Water is only in rainy season. River alignment is plainly depressed.

Considering above condition and also bypass alignment, culvert box is desirable as the applicable structure, and finishing level of bypass is required to be higher than the DHFL and reported H.F.L..

2) Facility No.15 (STA. 10+340, Location: Bandha Nala)

Table 16-56 Hydrological Condition of Facility No.15

Item	Condition	
M.D.D. (m³/sec)	19.5	
Velocity of flow (m/sec)	1.4	
DHFL	2.5m above water bed level	
Reported H.F.L.	6~7m above water bed level	
Other information	Water only in rainy season.	
	Soil of water bed is sand stone.	

Bridge type structure is applied, and reported H.F.L. is more than DHFL, so soffit level of superstructure is required higher than reported one, and also protection of embankment around abutment and approach road is required.

# 3) Facility No.16 (STA, 12+720, Location: Rai ka Pura)

Table 16-57 Hydrological Condition of Facility No.16

Item	Condition	
M.D.D. (m³/sec)	372.5	
Velocity of flow (m/sec)	6.7	
DHFL	5.0m above water bed level	
Reported H.F.L.	8~9m above water bed level	
Other information Soil of water bed is hard and compact sand sto		

Bridge type structure is applied. Reported H.F.L. is more than DHFL, so soffit level of superstructure is required higher than that DHFL, and also protection of embankment around abutment and approach road is required.

## 4) Facility No.21 (STA. 23+960, Location: Raipur Khurd)

Table 16-58 Hydrological Condition of Facility No.21

Item	Condition	
M.D.D. (m³/sec)	19.5	
Velocity of flow (m/sec)	5.2	
DHFL	2.5m above water bed level	
Reported H.F.L.	6m above water bed level	
Other information	Water only in rainy season	

It was found that bank of river is not well defined after site survey.

Culvert box is defined as the applicable structure.

This natural river is indicated on topographic map of s:1/5,000, and considering catchment area, M.D.D. will be small like previous facility No.22 or less. Culvert box is applied.

## 6) Facility No.24

(STA. 25+650, Location: Raipur Tighara Nala)

Table 16-59 Hydrological Condition

Item	Condition	
M.D.D. (m³/sec)	57.3	
Velocity of flow (m/sec)	2.4	
Estimated H.F.L.	2.5m above water bed level	
Reported H.F.L.	8.0m above water bed level	
Other information	Water only in rainy season	
	Over bridge of village road locates in vicinity.	

Bank of river is well defined, and weedy. Considering M.D.D., bridge type structure is applied.

## b) Canal

## 1) Major Canal

Major canal has the village road in parallel with it. With considering that local connection divided by bypass, bridge type structure is applied as described in Part 1, General.

# 2) Minor Canal

Culvert box type structure is applied with considering M.D.D. of each canal.

Applicable type of culvert box for water channel and number of internal cell is defined also with M.D.D..

#### Summary of Hydrological Condition for Structure Design (7)

Summary of hydrological condition of rivers is tabulated in Table 16-60.

Table 16-60 Summary of Hydrological Condition of Gwalior

No.	STA	River	AS.	M.D.D. (m³/sec)	DHFL (m)	M.V.C. (m)	Afflux (m)	M.D.S. (m)
12	8+190	Kharai nala	WCCBL	222.3	6.5	0.6	•	-
15	10+340	Bandha nala	WCBR	19.5	2.5	0.6	0.00	Abut: 1.1 Pier: 1.8
16	12+720	Rai ka Pura	WCBR	372.5	5.0	1.2	0.00	Abut: 9.0 Pier: 14.2
21	23+960	Raipur Khurd	WCCBM	19.5	1.5	0.6	•	-
23	25+070	-	WCCBM	-	-	•	•	-
24	25+650	Raipur Tighara nata	WCBR	57.3	2.5	0.9	0.14	Abut: 3.4 Pier: 5.4

Note: AS:

**Applied Structure** 

H.F.L.: Design Highest Flood Level

M.D.S.: Maximum Depth of Scour

M.D.D.: Maximum Design Discharge

M.V.C.: Minimum Vertical Clearance

## 16.6.4 Design Condition (2), Geology

## 16.6.4.1 Three Geological Groups in Gwalior Bypass

The general geological formations are alluvium, Gwalior shale, Gwalior sandstone. Soil is shallow and stony strata which varies from sandy loam on the escarpments to stiff clayey loam on the plateau. At the foot on the hill, soil is generally deeper due to the erosion or weathering of exposed rocky joints.

15 boring points were categorised in three (3) groups, and summarised in Table 16-61.

Table 16-61 Three Geological Groups in Gwalior Bypass

Group	ВН	Depth of Bearing Strata (Approx. m)	Soils
1	1~7	15	silty sand medium to fine sand clay of low plasticity(BH-2 & BH-3, only) sandy silt of low plasticity(BH-2 & BH-3, only)
II	8 ~ 11	5-10	gravely sand sandy gravel sandstone (BH-10 & BH-11, only)
11	12 ~ 15	10	fine grained clays of low to medium plasticity

## 16.6.4.2 Ground Water Level

Ground water level was measured when the bore holes were drilled. Throughout the bypass area, the ground water level was observed approximately 6 to 8 m deep. This is almost same elevation with we could observe at wells which locate at whole stretch of the proposed bypass except the rock hill.

# 16.6.5 Applied Structures

#### 16.6.5.1 General

Proposed locations of each structure was determined based on the site investigation and prepared topographic map of 1:5,000. There are some new crossing structures which planned their location to secure the current local traffic.

As the major structures, there are one railway over bridge and four bridges over rivers. Summary of applied structure for individual crossing facility is shown in the Table 16-62.

Table 16-62 Summary of Applied Structures (1/2)

No. of AS.	No. of CF.	STA	Applied Structure Type	Type and Class of Crossing Facility	Remarks
7.0-	1	0+190	(Level Intersection)	Railway	Railway will be abandoned soon.
1	2	0+510	RDCBM	RD - VR	<u> </u>
2	3	1+150	RDCBM	RD-VR	L = 33.4m
3	- <u>`</u> -	1+900	RDCBS	(New)	L = 33.4m
4	4	2+510	RDCBM	RD – VR	
5	5	3+580	RDCBL	RD - VR	L = 33.4m Drainage is settled at one side.
6	6	4+400	RDCBM	RD - VR	L = 33.4m
7	7	4+735	WCCBM (No. of Cell:3)	WC - Minor Canal	L = 33.4m
8	† <u> </u>	6+000	RDCBS	(New)	L = 33.4m
9	8	7+470	RDCBS	RD - CT	L = 33.4m

Note: CF.: Crossing Facility

AS.: Applied Structure

Code of Applied Structures are summarised and described in Part A: General.

Table 16-62 Summary of Applied Structures (2/2)

No. of AS.	No. of CF.	STA	Applied Structure	Type and Class of Crossing Facility	Remarks
10	9	7+760	WCBR (RC-Slab)	WC - Major Canal	Foundation: Abut: Pile
		7400	2 @ 9.0 = 18.0m	110 - Inojoi Canai	Pier: Pile
11	10	7+925	RDCBM	RD-VR	L= 33.4m
12	11	8+170	ROCBL	RD-VR	L = 33.4m
13	12	8+190	WCCBL (No. of Cell:6)	WC - River	L = 33.4m
14	13	9+370	WCCBM (No. of Cell:2)	WC - Minor Canal	L = 33.4m
15	14	9+370	RDCBL	RD - VR	L = 33.4m
16	15	10+340	WCBR (PC-Hollow) 1@25.0 = 25.0m	WC - River	Foundation: Abut: Pile
17		12+150	RDCBS	(New)	L = 33.4m
18	16	12+720	WCBR (RC-T beam) 14.0 + 19.0 + 14.0 = 47.0m	WC - River	Foundation: Abut: Pile
19		12+900	RDCBS	(New)	Pier: Well L = 33.4m
20	<u> </u>	13+600	RDCBS	(New)	L = 33.4m
21	17	15+150	RDCBM	RD-CT	L= 33.4m
-	•	13*100	NOODM	10-01	(Alignment of Crossing Facility will be replaced.)
22	18	15+280	RDCBL	RD - VR	L = 33.4m (Alignment of Crossing Facility will be replaced.)
23	19	18+230	RDCBM	RD - VR	L = 33.4m
24		22+450	RDCBS	(New)	L = 33.4m
25	20	23+710	RDCBM	RD - VR	L = 33.4m
26	21	23+960	WCCBM (No. of Cell:2)	WC - River	L = 33.4m
27	22	24+120	RDCBM	RD – VR	L = 33.4m
28	23	25+070	WCCBM (No. of Cell:2)	WC - River	L = 33.4m
29		25+120	RDCBS	(New)	L = 33.4m
30	24	25+650	WCBR (RC-Slab) 3 @ 10.0 = 30.0m	WC - River	Foundation: Abut: Well Pier: Well
31	25	26+100	ROB (Hollow Slab) 1 @ 17.0 = 17.0m	Railway	Foundation: Abut: Pile

Note: CF.: Crossing Facility

AS.: Applied Structure

Code of Applied Structures are summarised and described in Part A: General.

# 16.6.5.2 Railway Over Bridge (ROB) (STA. 26+100)

One railway over bridge was planned and designed near the bypass end point. Design conditions are summarised in Table 16-63, and site photograph is presented in Figure 16-23.

Table 16-63 Design Condition of Over bridge (STA. 26+100)

ltem		Condition	
Throughway Alignment	Vertical Alignment	i = 1,4% ~ -1.2%	
	Horizontal Alignment	R = 500	
	Cross Section	Type - Lof Bridge Section (L<100m)	
Crossing	Classification of Project	Railway (CF No.25)	
Facility	Present Condition	Broad Gauge, Single Track, Non-electrified	
	Future Programme	Broad Gauge, Double Track, Non-electrified	
	Lateral Clearance	9.445m (for Future Programme)	
	Vertical Clearance	5.030m	
	Other Information		
Geology	Depth of Bearing Strata	9.0m from G.L.	
	Type of Bearing Strata	Clay (N>20)	




Figure 16-23 General View of Crossing Point

Composition of applied ROB is summarised in Table 16-64.

Table 16-64 Applied Railway Over bridge (STA. 26+100)

Item	Conditions		
AS. No.	No. 31		
Superstructure	PC Hollow Slab	Total Length 17.0m,	1 @ 16.0m = 16.0m
Substructure	Abutment: Inversed T - type	Height of Abutment: Width of Footing:	12.0m 7.5m x 26.5m
Foundation	Abutment	1	lation yth: 10.0m neter 1.0m 3x 6 for each abutment

# 16.6.5.3 Bridge Over Major Canal (WCBR) (STA. 7+760)

Design condition is summarised in Table 16-65.

Table 16-65 Design Condition of Bridge (STA. 7+760)

	Item	Condition  i = -1.5% ~ 2.3%	
Throughway	Vertical Alignment		
Alignment	Horizontal Alignment	R = 1,000	
	Cross section of Throughway	Type - I of Bridge Section (L<100m)	
Crossing Facility	Classification of Project	WC - Major Canal (CF No.9) Tighara Canal	
·	M.D.D.	20.0 m³/sec	
	Other Information		
Geology	Depth of Bearing Strata	15.0m from G.L.	
	Type of Bearing Strata	Sand (N > 30)	
	Other Additional Information		

Considering local traffic, bridge type structure was applied.

Composition of applied bridge is summarised in following Table 16-66.

Table 16-66 Applied Bridge (STA. 7+760)

ltem			
AS No.	No.9		
Superstructure	RC-Slab (2 x simple span)	Total Length 19.0m, 2 @ 9.0m = 18.0m	
Substructure	Abutment: Inversed T - type	Height of Abutment: 8.5m Width of Footing: 5.0m x 26.5m	
	Pier: Wall type	Height of Pier: 7.0m Width of Footing: 5.0m x 5.0m	
Foundation	Abutment	Cast-in-Situ Pile Foundation Length: 11.0m Diameter 1.0m 3x 6 for each abutment	
	Pier	Cast-in-Situ Pile Foundation Length: 11.0m Diameter 1.0m 2x 3 for each abutment	

# 16.6.5.4 Bridge Over River (WCBR) (STA. 10+340)

Design condition is summarised in Table 16-67.

Table 16-67 Design Condition of Bridge (STA. 10+340)

ltem		Condition	
Throughway	Vertical Alignment	li = -3.0%	
Alignment	Horizontal Alignment	R = 2,000	
	Cross section of Throughway	Type – Lof Bridge Section (L<100m)	
Crossing	Classification of Project	WC - River (CF No.15), Bandha Nala	
Facility	M.D.D.	222.3 m³/sec	
	DHFL	2.5m from water bed	
	Linear Waterway	25.0m	
	Afflux	0mm	
	Vertical Clearance	600mm from DHFL + Afflux	
	Maximum Depth of Scour	Abutment: 1.1m Pier 1.8m from DHFL	
	Other Additional information		
Geology	Depth of Bearing Strata	BP side: 10.0m from G.L. EP side: 5.0m from G.L.	
	Type of Bearing Strata	BP side: Sandy Gravel EP side: Sand Stone (Rock)	
	Other Additional Information	Group II described in section 7.4 Design Condition (2), Geology	

Composition of applied bridge is summarised in following Table 16-68.

Table 16-68 Applied Bridge (STA. 10+340)

ltem		Composition	
AS No.	No.16		
Superstructure	PC-Hollow	Total Length 26.0m,	1 @ 25.0m = 24.0m
Substructure	Abutment: Inversed T - type	Height of Abutment: Width of Footing:	10.0m 7.0m x 26.5m
Foundation	Abutment	Cast-in-Situ Pile Foundation Length: 10.0m Diameter 1.0m 3 x 6 for each abutmen	

Protection of embankment in front of abutment is required to prepare the flow in spate in rainy season.

# 16.6.5.5 Bridge Over River (WCBR) (STA. 12+720)

Design condition is summarised in the following Table 16-69, and site photograph is shown in Figure 16-24.

Table 16-69 Design Condition of Bridge (STA. 12+720)

ltem		Condition	
Alignment	Vertical Alignment	i = -1.7%	
	Horizontal Alignment	R = 3,000	
	Cross section of Throughway	Type - I of Bridge Section	
Crossing	Classification of Project	WC - River (Facility No.16), Rai ka Pura (Sojina)	
Facility	M.D.D.	372.5 m³/sec	
	H.F.L.	5.0m from water bed	
	Linear Waterway	42.6m	
	Afflux	0.36m	
	Vertical Clearance	1,200mm from H.F.L.+Afflux	
	Maximum Depth of Scour	Abutment: 5.7m Pier: 9.0m from DHFL	
	Other Additional information	Water flow bed is hard and compact sand stone.	
Geology	Depth of Bearing Strata	10.0m from G.L. (Estimated)	
	Type of Bearing Strata	Sandy Gravel (Estimated)	
	Other Additional Information	Group II described in section 7.4 Design Condition (2), Geology	



Figure 16-24 General View of Crossing Point

Composition of applied over bridge is summarised in following Table 16-70.

Table 16-70 Applied Bridge (STA. 12+720)

	ltem	<u> </u>			
AS No.	No.18	<u>,</u>			
Superstructure	RC-T beam	Total Length 48	3.0m, 14.0+1	9.0+14.0 = 47	<u>'.0m</u>
Substructure	Abutment: Inversed T – type	A1 & A2 Height of Abuti Width of Footin		0.0m 8.0m x 26.5m	
	Pier: Wall type	P1 & P2 Height of Pier: Width of Footing		2.0m 6.0 x 6.0m	
Foundation	Abutment	Well Foundation	on .		
		A1:	Diameter:	6.0m	
			Depth	5.0m	x 3
		A2:	Diameter	6.0m	
			Depth	5.0m	<u>x 3</u>
	Pier	Well Foundation	on		
		P1:	Diameter:	6.0m	
			Depth:	5.0m	
			·	x 2 for 2	piers
		P2:	Diameter	6.0m	
			Depth:	5.0m	
ļ			•	x 2 for 2	piers

Protection of embankment in front of abutment is required to prepare the flow in spate in rainy season.

# 16.6.5.6 Bridge Over River (WCBR) (STA. 25+650)

Design condition is summarised in the following Table 16-71, and site photograph is shown in Figure 16-25.

Table 16-71 Design Condition of Bridge (STA. 25+650)

	Item	Condition
Alignment	Vertical Alignment	-0.5% ~ 1.4%
	Horizontal Alignment	R = ∞
	Cross section of Throughway	Type - I of Bridge Section
Crossing	Classification of Project	WC - River (Facility No.24), Raipur Tighara Nala
Facility	M.D.D.	57.3 m³/sec
	H.F.L.	2.5m from water bed
	Linear Waterway	15.3m
	Afflux	0.14m
	Vertical Clearance	1,200mm from H.F.L. + Afflux
	Maximum Depth of Scour	Abutment: 3.4m
		Pier: 5.4m from DHFL
	Other Additional information	Water flow bed is hard and compact sand stone.
Geology	Depth of Bearing Strata	10.0m from G.L. (estimated)
	Type of Bearing Strata	Sandy Gravel (estimated)
	Other Additional Information	Group III described in section 7.4 Design
		Condition (2), Geology



Figure 16-25 General View of Crossing Point

Composition of applied over bridge is summarised in following Table 16-72.

Table 16-72 Applied Bridge (STA. 25+650)

	Item			
AS No.	No.30			
Superstructure	RC- Slab (3 x simple span)	Total Length 31	i.0m, 3 @ 10.	0 = 30.0m
Substructure	Abutment: Inversed T - type	A1 & A2 Height of Abute Width of Footin	_	.0m .5m x 26.5m
	Pier: Wall type	P1 & P2 Height of Pier Width of Footing		:.0m i.0m x 6.0m
Foundation	Abutment	Cast-in-Situ Pi	Length: 10 Diameter 1	
	Pier	Well Foundati P1:	Diameter: Depth:	6.0m 8.5m x 2 for 2 piers 6.0m
		P2:	Diameter Depth:	8.5m x 2 for 2 piers

Protection of embankment in front of abutment is required to prepare the flow in spate in rainy season.

## 16.6.5.7 Culvert Box for Roads (RDCBL, RDCBM, and RDCBS)

At 23 crossing points, Culvert Box for road were applied. Summary is shown in Table 6-73

Table 16-73 Summary of Culvert Box for Road

Type of Culvert	No. of AS.	STA		Remarks	Type of Culvert	No. of AS.	STA	R	temarks
RDCBL	5	3+580	L=	33.4m	RDCBS	3	1+900	L=	33.4m
NOODE	12	8+170	L=	33.4m	'"""	8	6+000	L=	33.4m
	15	9+370	L=	33.4m	-	9	7+470	L=	33.4m
	22	15+280	L=	33.4m	1	17	12+150	L=	33.4m
	}	Length	L=	133.6m	1	19	12+900	L=	33.4m
RDCBM	1	0+510	<u>t</u> =	33.4m		20	13+600	L=	33.4m
	2	1+150	L=	33.4m	1	24	22+450	L=	33.4m
į	4	2+510	L=	33.4m		29	25+120	<u>l</u> =	33.4m
	6	4+400	L=	33.4m		Total Le	ength	L=	267.2m
	11	7+925	<u>t</u> =	33.4m					
	21	15+150	L=	33.4m					
	23	18+230	L=	33.4m					
	25	23+710	L=	33.4m	_				
	27	24+120	L =	33.4m	_				
	Total	Length	<u>L = </u>	300.6m					

# 16.6.5.8 Culvert Box for Water Channel (WCCBL, WCCBM, and WCCBS)

At 7 crossing points, Culvert Box for water channel were applied. Summary is shown in Table 16-74.

Type of culvert and number of cell was defined with M.D.D. of each canal.

Table 16-74 Summary of Culvert Box for Water Channel

Type of Culvert	No. of AS.	STA	No. of Cell	Length (m)	Remarks
WCCBL	13	8+190	3 x 2	L = 33.4m	*2 Culverts applied
WCCBM	7	4+735	3	L = 33.4m	
	14	9+370	2	L = 33.4m	
	26	23+960	2	L = 33.4m	
<u>.</u>	28	25+070	2	L = 33.4m	

## 16.6.6 Suggestion for Detail Design

There is a railway which crosses with the proposed bypass alignment near the beginning point.

Crossing plan in this study is assumed as at grade intersection, and this is because railway alignment is planned to be abandoned. This was discussed and confirmed by Ministry of Railway and State PWD Gwalior.

However, the target year of this abandon is still not definitive, and it is anticipated that it would be still operated when the bypass opens to public.

In detail design, the future programme of railway and crossing plan should be reviewed.

# Feasibility Study

Chapter 11	Socio-economic Conditions of the Study Area
	Supplemental Traffic Survey and Analysis
Chapter 13	Futura Teaties Draward Language

Chapter 13 Future Traffic Demand Forecast

Chapter 14 | Field Investigations Chapter 15 | Design Standards

Chapter 16 Design for the Feasibility Study

# Chapter 17 Construction Plan

Chapter 18	Foll	Collection	ı System

- Chapter 19 Operation and Maintenance System
- Chapter 20 Cost Estimates
- Chapter 21 Economic and Financial Analysis
- Chapter 22 Implementation Programme
- Chapter 23 Recommendations

# 17 Construction Programme

The Scope of Works provided for this Feasibility Study specifies the year of 2002 as the target year (short term) for the completion of the construction of high priority projects. In order to enable the construction start, it was understood that the following procedures should be carried out, beforehand.

- (1) Further detailed engineering design (assumed one year).
- (2) Process to obtain the project sanction.
- (3) Process to select the civil work contractor.
- (4) Land acquisition and compensation.

Judging from the above required procedures, the construction period for the proposed bypass was assumed as 3 years, from 1999 to 2002.

# 17.1 Major Project Features

## 17.1.1 Bareilly Bypass

The following were taken into account as the major project features:

- As the concrete structures, 13 bridges/viaducts and 29 culvert boxes were proposed. Amongst these structures, three bridges with 49 m long were proposed to cross over the Deonarain River at STA 7+900, SH 37 and railways at STA 9+090, and the Nakatia River at STA 14+270. Two interchange bridges were proposed with 30 m long at the crossing points of SH337 at STA 8+700, and SH 33 at STA 13+300, respectively;
- The required quantities for road embankment was estimated as approximately 2,700 ×10<sup>3</sup> m<sup>3</sup>. The maximum height of embankment will be approximately 10 m at STA 9+065 for the approach section to the ROB, and STA. 10+015 to install a middle size culvert box. According to the information given by the State PWD, the practical supply of fill material in the project area is carried out by "Side Borrow". Referring to this information, this Study also expected to supply the fill material by this "Side Borrow" method. When this method was applied for the whole stretch of the bypass with 90 m width at both side, side borrow excavation will require around 50 cm depth;
- Two interchanges of a Y-type with at-grade intersection were proposed to connect the bypass traffic to SH 37 at STA 8+700, and to SH 33 at STA 13+300; and,
- The proposed alignment will cross under the High Tension Line (HTL) at seven locations. As the actual height of the conductors of the HTL at the exact crossing point was not measured in the Study, it is recommended to measure the conductor's height at the crossing point, at the time of detailed engineering

design phase, to check whether the vertical clearance from the proposed level of bypass fulfil the required specification or not.

## 17.1.2 Gwalior Bypass

The followings were taken into account as the major project features:

- As the concrete structures, 5 bridges and 26 culvert boxes were proposed. The bridge over the river at STA 12+720 has the longest length of 47 m;
- It was understood the proposed ROB at STA 26+100 will be separated from the civil work contract for the bypass project to the jurisdiction of Ministry of Railways;
- The required quantities for road embankment was estimated as approximately 2,200 ×10<sup>3</sup> m<sup>3</sup>. By the excavation work at the cut section, around 330 ×10<sup>3</sup> m<sup>3</sup> will be generated. Therefore approximately 1,900 ×10<sup>3</sup> m<sup>3</sup> of fill material will be required supplied from the outside. As recommended by the State PWD, Gwalior, existing borrow pits are located in adjacent area of the project. The geotechnical survey conducted at the proposed borrow pits proved the appropriateness for the fill material. The hauling distance was assumed as 13 km in average;
- Although the project alignment was arranged to avoid the crossing of waste water basin at STA 2+400, the possibility of settlement of road embankment by the old deposit is suspected. The further study including the countermeasures of soft ground treatment may be required; and
- The old water supply canal and current water main, supplies water from Tighara Reservoir to Gwalior city, are crossing the proposed bypass at around STA 9+400.
   During the construction of structures to cross over these utilities, careful attention shall be taken, not to make any interruption of its function.

### 17.2 Workable Days at the Project Area

### 17.2.1 Bareilly Bypass

The number of workable days was estimated as shown in Table 17-1. The calculation of Non Workable days was based on the rainfall data of Revenue Department of Uttar Pradesh, 1995~1997. Non-Workable day was estimated by the following formula referred to the Manual of Earthwork for Road Construction, Japan Road Association.

Non-Workable day by Rainy day =  $(B \times 0.5 + C \times 1.0 + D \times 1.5) \times 0.5$ 

where, B: number of rainy day having 1 mm to 10 mm rainfall C: number of rainy day having 10 mm to 30 mm rainfall

D: number of rainy day having more than 30 mm rainfall

Table 17-1 Number of Workable Days at Bareilly Bypass Area

Item	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.	Total
A) Rainy day total	2	4	2	2	2	13	14	20	12	4	2	2	
B) Rainy day 1mm to 10mm	1	1	1	1	1	7	4	9	6	2	2	1	<u></u>
C) Rainy day 10mm to 30mm	0	2	1	1	1	5	4	6	3	2	0	1	
D) Rainy day above 30mm	1	1	0	0	0	1	6	5	3	0	0	0	<u> </u>
E) Holiday	5	4	4	4	5	4	4	5	4	5	4	4	
F) National Holiday	5	1	1	3	2	0	1	1	1	3	1	4	
G) Non-Workable day by Rainy day	1	2	1	1	1	5	8	9	5	2	1	1	
H) Total Non-Workable day	11	7	6	8	8	9	13	15	10	10	6	9	<u> </u>
I) Workable day	20	21	2S	22	23	21	18	16	20	21	24	22	253

Source: Revenue Department of Uttar Pradesh Government Rainfall Data of Baheri, 1995,1996

## 17.2.2 Gwalior Bypass

The number of workable days was estimated as shown in Table 17-2. The calculation of Non Workable days was based on the rainfall data of Climatological table of observation in India, 1931~1960, and rainfall data in monsoon season (June to October), 1995-1997.

Table 17-2 Number of Workable Days at Gwalior Bypass Area

Item	Jan.	Feb.	Mar.	Apr.	May	Jun.	Jul.	Aug.	Sep.	Oct	Nov.	Dec.	Total
A) Rainy day total	1.5	0.9	1	0.5	0.9	6	18	19	10	3	0.2	0.7	
B) Rainy day 1mm to 10mm	0	0.9	0	0.5	0.9	2	10	10	4	2	0	0	
C) Rainy day 10mm to 30mm	1.5	0	1	0	0	3	2	4	4	0	0.2	0.7	
D) Rainy day above 30mm	0	0	0	0	0	1	6	5	2	1	0	0	<u> </u>
E) Holiday	5	4	4	4	5	4	4	5	4	5	4	4	
F) National Holiday	5	1	1	3	2	0	1	1	1	3	1_1_	4	
G) Non-Workable day by Rainy day	1	0	1	0	0	3	8	8	5	1	0	0	
H) Total Non-Workable day	11	5	6	7	7	7	13	14	10	9	5	8	
I) Workable day	20	23	25	23	24	23	18	17	20	Z2	25	23	263

Source: Climatological table of observations in India (1931-1960), monsoon season (June to October), 1995~1997

### 17.3 Construction Schedule

### 17.3.1 Calculation of the Construction Period Required

The construction period was calculated based on the ability of the construction equipment by the following formula:

Construction Period (month) = Work Quantity

Construction Ability×Ratio of Workable Days×30 days

Construction ability was assumed on the basis of "Handbook on Road Construction Machinery".

### 17.3.2 Tentative Construction Schedule of Bypasses

As the both bypass projects have no particular structures which require high construction technology or time consuming construction period, the earthwork and the pavement work was judged as a critical-path to accomplish the project with in 3 years. Since the road length and work items/quantities were not differ much between both bypasses, the similar construction schedules were assumed. Tables 17-3 and 17-4 show the tentative construction schedule for Bareilly Bypass and gwalior bypass, respectively.

Table 17-3 Tentative Construction Schedule of Bareilly Bypass





Table 17-4 Tentative Construction Schedule of Gwalior Bypass



# Feasibility Study

Chapter 11	Socio-economic Conditions of the Study Area
Chapter 12	Supplemental Traffic Survey and Analysis

Chapter 13 Future Traffic Demand Forecast

Chapter 14 Field Investigations Chapter 15 Design Standards

Chapter 16 Design for the Feasibility Study

Chapter 17 Construction Plan

# Chapter 18 Toll Collection System

Cumples to Calerdania minimum commence and a com-	Chapter	19 (	peration and	l Maint	ениисе	System
---	---------	------	--------------	---------	--------	--------

Chapter 20 Cost Estimates

Chapter 21 Economic and Financial Analysis

Chapter 22 Implementation Programme

Chapter 23 Recommendations

### 18 Toll Collection System

The proposed Bareilly Bypass and Gwalior Bypass will provide major advantages in terms of improved communications, accessibility and environmental benefits. On the other hand, the scheme is intended to recover the invested project cost by means of toll collection. So it is necessary to make the Project as attractive as possible to the traffic in order to maximise the toll revenues.

The main factors, which attract the traffic to toll roads, are in reduction of travel time, distance travelled and operational costs (maintenance cost, fuel charge, etc). Because the road user is not always rational in the assessment of his travel costs, it is also essential to minimise delays on the bypass system including the passing time of interchanges and tollgates. Otherwise, potential users will be deterred from the toll roads. Thus, as the time savings are one of the main attractive features for a toll road, the toll plazas must be designed to accommodate the traffic flows on the bypass with the minimisation of delay and inconvenience to the user.

## 18.1 Comparison of Toll Collection System

There are two types of toll collecting system, the Open Toll System and the Closed Toll System.

## (1) Open Toll System

Open Toll System allows to use the toll road free of charge in some trip patterns. This system does not provide toll collecting facilities in every access points. The trip allowed for free of charge traffic is generally short distance, for partial passing of minor traffic flows.

Generally, vehicles can enter a toll road without stopping, and when they reach a tollgate on the throughway, they must stop to pay toll and receive a receipt. Toll collectors at tollgates identify the vehicle type and issue a receipt.

### (2) Closed Toll System

In case of a fully access-controlled road with toll levy, the JICA Study Team recommends the application of Closed Toll System as the most appropriate one. In this system, road users have to stop at least once at toll facilities and pay the toll.


In a typical case where the toll rates are distance dependent, vehicles have to stop at the tollgate, usually located in the interchange before entering the toll road, to receive a ticket, and then drive to the exit interchange. At the exit interchange, drivers hand over the ticket to the toll collector, pay a toll and receive a receipt. The toll collector at the entry interchange gives the ticket to the passing vehicles. Toll collectors at the exit interchange receive the ticket

and collect the prefixed toll often dependent on the distance travelled and vehicle type. After receiving payment, toll collectors give back the receipt and the change, if any, to drivers.

A general comparison of these systems is presented below.

Table 18-1 Comparison of Toll System

	Open Toll System	Closed Toll System
Access control	Not necessarily needed	Fully needed
Toll collection at all IC's	Not necessary	In principle
Rogue vehicle check	Difficult	Easy
Road closure	Not possible (difficult)	Possible (easy)






Figure 18-1 Open Toll System and Closed Toll System

### 18.2 Rogue Vehicle Check

To prohibit the entry of rogue vehicles is extremely important from the viewpoint of operation and maintenance of the tollway. There may be two reasons in this requirement.

The first reason is to avoid the damages of pavement or structures, especially bridges, by rogue vehicles having an overloaded freight. Although pavement or structures are designed for design loads inclusive of allowance by a safety factor, the

repetitive overloading will lead to deterioration of the strength of pavement and structures. As a result of repetitive overloading, the life of pavement and structures will be shorten. This will make the maintenance cost high.

The second reason is that rogue vehicles such as bicycles and auto-rikshaws disturb high-speed traffic flow. This will diminish the time saving benefit by using the bypass. They may cause traffic congestion and traffic accidents.

# (1) Rogue Vehicle Control under Open Toll System

It is difficult to check rogue vehicles under the Open Toll System because the highway is opened to ordinary roads connected and adjacent lands. Any type of vehicles can enter the toll road. To prevent the entry of rogue vehicles to the tollway, the special task force will be required to control the entry of vehicles at each access points.

# (2) Rogue Vehicle Control under Closed Toll System

It is easy to check rogue vehicles under the Closed Toll System as every user is captured somewhere at least once on the highway.

# 18.3 Proposed Toll Collection System

In this Study, the Closed Toll System was recommended as a toll collection system of Bareilly Bypass and Gwalior Bypass. This System was judged as more appropriate than the Open Toll System by the reasons mentioned above.

The Gwalior Bypass with the total length of 26.0 km has only two connecting points with the existing NH3, at the beginning (BP) and end points (EP) of the throughway. Therefore it is rather simple to allocate the toll collection system. The following Figure 18-2 illustrates the toll barrier location proposed for Gwalior Bypass. There are two toll barriers near the BP and EP on the throughway. Road users will stop at the toll barrier and pay a toll, just after his entry into the bypass section. It is not necessary to stop thereafter.




Figure 18-2 Toll Collection System proposed for Gwalior Bypass

On the other hand, Bareilly Bypass was designed to have two additional link points to the existing SH37 and SH33. Therefore, the bypass may form three sections; 1) Section 1 from NH24 to SH37, approximately 9.1 km, 2) Section 2 from SH37 to SH33,

approximately 4.5 km, and 3) Section 3 from SH33 to NH24, approximately 17.5 km. It is essential to establish the simple and efficient system for the both toll collection and road users.

In order to achieve this, the JICA Study Team proposed a toll collection system for Bareilly Bypass as shown in the Figure 18-3. Table 18-2 indicates the toll rates at each toll barrier/tollgate.




Figure 18-3 Toll Collection System proposed for Bareilly Bypass

Table 18-2	Charged Toll Rates at Toll Barrier/Γollgate at
	Bareilly Bypass

Direction	Toll gate	Toll Rate
Delhi → Lucknow	A	Rate for Section 1
	В	Rate for Section 2
	С	Rate for Section 3
	D	Rate for Section 2 & Section 3
Lucknow → Delhi	E	Rate for Section 3
	F	Rate for Section 2
	G	Rate for Section 2
	Н	Rate for Section 1

### 18.4 Location of Facilities related to Toll Collection

### 18.4.1 Location of Toll Barriers on the Bypass Throughway

The toll barriers on the throughway of the bypass is recommended to allocate near the beginning point and end point. The visible existence of toll barrier at near the entrance is expected to prohibit the entry of slower vehicles such as auto-rikshaws, bicycles, and carts into the bypass.

The layout of the toll barriers on the throughway may be arranged as shown in

Figure 18-4. A toll office in which toll collection system is controlled will be constructed nearby the toll barrier.




Figure 18-4 Typical Layout of Toll Barrier on Bypass Throughway

# 18.4.2 Location of Tollgate on the Ramp Way

As described in the previous section, 18.3, the installation of tollgates was recommended at the interchange for SH33 of Bareilly Bypass. The typical layout of the tollgates on the ramp way was illustrated in Figure 18-5. The location of tollgate will be selected on vacant land, away from villages and other settlements as far as possible.




Figure 18-5 Typical Layout of Tollgate on Ramp Way

## 18.4.3 Required Number of Lanes for the Toll Barrier/Tollgate

In this Study, the required number of lanes for toll barrier/tollgate were decided referring to the Interchange Design Standards of the Japan Highway Public Corporation (JH). JH provides Table 18-3 for selecting the number of tollgate lanes from the relevant elements of time for service (sec), average queue and Design Hourly Volume (DHV).

The Study Team employed the elements for the service time of 8.0 seconds and 3 vehicles for average queue. This condition is generally adopted for selecting the number of tollgate lanes in case of the manual toll collection. Number of toll lanes for the proposed toll barriers/tollgates are summarised in Table 18-4.

Table 18-3 Guide to determine Number of Lanes for Toll Barrier/Follgate

Time of Service	6.0	sec	8.0	sec	10.0	sec	14.0	sec	18.0	sec
Average Queue (No. of Vehicle)	1	3	1	3	1	3	1	3	1	3
Number of Lanes			D	esign F	lourly	Volum	e (DH)	7)		
1	300	450	230	340	180	270	130	190	100	150
2	850	1,040	640	780	510	620	360	440	280	350
3	1,420	1,630	1,070	1,230	850	980	610	700	480	550
4	2,000	2,230	1,500	1,670	1,200	1,340	860	960	670	740
5	2,590	2,830	1,940	2,210	1,550	1,700	1,110	1,210	860	940
6	3,180	3,430	2,380	2,570	1,910	2,060	1,360	1,470	1,060	1,140

Table 18-4 Proposed Number of Lanes for Toll Barrier/Tollgate

Bypass	Toll Barrier/ Tollgate	Direction	ADT	DHV	Estimated Number of Lanes	Proposed Number of Lanes
	A (BP)	entry	17,800	1,070	3	3
	B (SH33IC)	exit	13,100	790	3	3
	C (SH33IC)	entry	5,200	310	1	2
Bareilly	D (SH33IC)	pass	8,100	490	2	3
	E (EP)	entry	13,300	800	3	3
	F (SH33IC)	pass	8,100	490	2	3
	G (SH33IC)	entry	13,100	790	3	3
	H (BP)	exit	17,800	1,070	3	3
Gwalior	Barrier A	entry	9,000	540	2	3
	Barrier B	entry	9,000	540	2	3




Figure 18-6 Proposed Location of Tollgate in Bareilly Bypass

# 18.5 Toll Related Management Plan

### 18.5.1 Toll Rate

In this Feasibility Study, the following toll rates in 1997 price were assumed as the very basic condition of the study for future traffic demand forecast and economic/financial analysis.

Vehicle Type	Toll Rate (Rs./km) in 1997 price
Cars/Jeep/Van	1.00
Light Commercial Vehicle	1.75
Truck and Bus	3.50
Heavy Construction machinery	7.50
Two wheelers	0.50

Bicycles and pedestrians should be banned from the bypass. Slow speed traffic such as bullock cart or auto-rickshaw is also not permitted to enter, to avoid the reduction of traffic capacity. Otherwise, these transportation mode should be charged the same toll rates as cars.

Based on the above unit toll rates in 1997 price, the applied toll rate in 2002, when the proposed bypass is expected to open to the public, was estimated as shown in Table 18-5.

Table 18-5 Toll Rate at the Bypass Opening in 2002

Unit : Rs. (2002 price) Gwalior Bypass **Bareilly Bypass** Vehicle Type (L=26.5 km)(L=30.0 km)36 44 Car 64 76 Light Commercial Vehicle 128 153 Truck/Bus Two Wheelers 18 21

In case of the Bareilly Bypass, there are three sections as stated in Section 18.3. Therefore, the tolls for traffic using each section of the bypass would be as shown in the Table 18-6.

Table 18-6 Toll Rate of Bareilly Bypass at the Bypass Opening in 2002

Vehicle Type	Section 1 BP→ SH37	Section 2 SH37→ SH33	Section 3 SH33→ EP	Section 2 & 3 SH37→ EP	BP→ EP
Car	13	6	25	31	44
Light Commercial Vehicle	22	11	43	54	76
Truck/Bus	45	22	86	108	153
Two Wheelers	6	3	12	15	21

### 18.5.2 Methods of Toll Collection

As the most practical and simple method, the manual toll collection method with fixed toll rate at each toll barrier/tollgate was proposed for the project. Under the manual methods, payment will take place as the vehicle passes through the toll barrier/tollgate. As Gwalior Bypass only links to the existing road, NH3, at both ends, a toll collector will receive a fixed toll as listed in Table 18-5, give back the change, if any, and issue a receipt.

In case of Bareilly Bypass, the location layout of toll barriers/tollgates was established as shown in Figure 18-6. This arrangement enable to construct toll related facilities with the minimum cost, and to charge a toll to every vehicle who uses the bypass from NH24, SH37 and SH33. Furthermore, instead of additional tollgate arrangement to SH37 Interchange, it will be recommended from the viewpoint of administration of tollway bypass, by centralising toll related facilities including a operation & maintenance station to one location.

Although the vehicle who uses whole section of the bypass needs to stop two or three times for a toll payment, all toll barriers/tollgates will receive a fixed toll as shown in Table 18-6, by this arrangement. A fixed toll operation does not cause confusion to both drivers and toll collectors. Therefore it is strongly recommended to apply this method to avoid any mishandling of toll collection.

# 18.6 Justification of Installation of Tollgates at SH33 Interchange in Bareilly Bypass

By the basic concept of this Feasibility Study—the beneficiaries (driver) of the bypass ought to share the expenses for the bypass, toll barriers/tollgates were proposed to install in SH33 Interchange, to catch every bypass user from/to SH37 and SH33 Interchanges. However when the cost, related to toll collection from the user through interchanges, exceeds the revenue, it will be not recommendable to install toll barriers/tollgates at SH33 Interchange.

In this section, the feasibility of toll barriers/tollgates installation at SH 33 Interchange for the bypass users through interchanges was assessed. According to the future traffic demand forecast, the details of bypass traffic behaviour were estimated as shown in Tables 18-7 and 18-8. In the tables, toll barrier/tollgate name was presented in parentheses, where the bypass user through interchanges will pay the toll.

As illustrated in Figure 18-2, at least two toll barriers at the entry point to the bypass will be required for the through traffic user of whole bypass section. Therefore the toll revenue from Gate B to D, and Gate F to H, which is related to bypass user through interchanges, were counted for this assessment purpose. The subjected traffic was shadowed in the Tables 18-7 and 18-8.

Table 18-7 Traffic Flows from Interchange - to Interchange in 2002

(Total Vehicles/day)

	Year 2002	1	2	3	4	
No.	0000	NH 24 (Delhi side)	SH 37	SH 33	NH 24 (Lucknow side)	Total
1	NH24 (Delhi side)		973 (Gate A)	1,125 (Gate A, B)	1,159	3,257
2	SH 37	1,105 (Gate H)		1,924 (Gate B)	1,067 (Gate D)	4,096
3	SH 33	1,151 (Gate G, H)	1,846 (Gate G)		805 (Gate C)	3,802
4	NH24 (Lucknow side)	1,030	1,105 (Gate E, F)	841 (Gate E)		2,976
	Total	3,286	3,924	3,890	3,031	14,131

On	off Total of S	H37 (4096+3924)	On off Total of S	6H33 (3802+3890)
Car	2,588	32.3%	2,572	33.4%
Bus	1.023	12.8%	1,029	13.4%
Truck	2,592	32.3%	2,279	29.6%
2 Whis	1,817	22.7%	1,812	23.6%
Total	8,020	100.0%	7,692	100.0%

Table 18-8 Traffic Flows from Interchange - to Interchange in 2012

(Total Vehicles/day)

	Year 2011	2 1	2	3	4	
No.	Off	IC NH 24 (Delhi side)	SH 37	SH 33	NH 24 (Lucknow side)	Total
1	NH24 (Delhi side)		3,754 (Gate A)	2,804 (Gate A, B)	2,289	8,847
2	SH 37	4,107 (Gate H)		3,550 (Gate B)	1,855 (Gate D)	9,512
3	SH 33	2,841 (Gate G, H)	3,923 (Gate G)		2,517 (Gate C)	9,281
4	NH24 (Lucknow sid	2.050	1,913 (Gate E, F)	2,724 (Gate E)		6,687
	Total	8,998	9,590	9,078	6,661	34,327

On	off Total of S	H37 (9512+9590)	On off Total of S	SH33 (9281+9078)
Car	6,100	31.9%	5,944	32.4%
Bus	2,651	13.9%	2,300	12.5%
Truck	5,814	30.4%	5,910	32.2%
2 Whls	4,538	23.8%	4,205	22.9%
Total	19,103	100.0%	18,359	100.0%

Based on the toll rate, presented in Table 21-19, "Toll Rates of Bareilly Bypass at Current Prices of Each Year", Chapter 21, and traffic volume with vehicle type shown in Tables 18-7 and 18-8, toll revenue from the bypass user through interchanges by additional toll barriers/tollgates were estimated as shown in Tables 18-9 and 18-10.

Table 18-9 Interchange Related Toll Revenue from Additional Toll Facility in 2002

(×106 Rs./Year) 2 3 2002 Year NH 24 Total NH 24 Off IC SH 37 SH 33 No. (Lucknow side) On IC (Delhi side) 14.71 NH24 14.71 1 (from Gate B) (Delhi side) 23,19 9.98 8.33 41.50 2 SH 37 (from Gate D) (from Gate B) (from Gate H) 11.74 7.99 15.05 34.78 3 SH 33 (from Gate C) (from Gate H) (from Gate G) NH24 24.01 24.01 4 (from Gate F) (Lucknow side) 24.03 115.00 25.03 32.00 23.04 Total

Table 18-10 Interchange Related Toll Revenue from Additional Toll Facility in 2012

(x106 Rs./Year) 3 4 2 2012 Year NH 24 Total Off IC NH 24 SH 33 SH 37 No. (Lucknow side) (Delhi side) On IC 69.20 NH24 69.20 (from Gate B) (Delhi side) 74.26 68.99 27.57 170.82 2 SH 37 (from Gate D) (from Gate B) (from Gate H) 71.30 30.46 70.11 171.87 3 SH 33 (from Gate C) (from Gate H) (from Gate G) NH24 76.58 76.58 (from Gate F) (Lucknow side) 96.77 145.56 488.47 107.04 139.10 Total

The construction cost for the additional toll related facilities intended to collect the toll from the bypass user through interchanges were extracted from Table 20-18, "Construction Cost of Bareilly Bypass (3/3)", Chapter 20, as follows.

Table 18-11 Construction Cost of Additional Toll Related Facilities

Unit: Rs. in 1997 price Unit Ammount Sub item Qty. Item 266,065 Nos. Additional Toll Toll barrier(Gate H) 1 Toll barrier(Gate D, F) Nos. 2 532,131 Related Facilities 104,997 Toll gate(2booth) (Gate C) Nos. 1 279,826 Toll gate(3booth) (Gate B, G) Nos. 2 1,083,509 Sub operation office 1 Nos. 2,266,528 Total

Operation and Maintenance Cost required additionally was estimated as follows.

## **Operation Costs**

### (1) Personnel

As the scale (length) of Gwalior Bypass is very close to that of Bareilly Bypass, the difference of estimated personnel cost between two bypasses was counted. Referred to the estimated personnel costs in Chapter 20.4.2.1 and 20.4.3.1, the additional annual personnel costs was given as Rs. 5,270×10<sup>3</sup> in 1997 price.

(2) Toll machine maintenance and repair costs

The estimated additional annual toll machine maintenance and repair costs was Rs.  $189 \times 10^3$  in 1997 price.

(3) Utilities and other operation expenses

The estimated additional annual utilities and other operation expenses was  $Rs. 56 \times 10^3$  in 1997 price.

(4) Overhead cost for corporate management

The additional annual overhead cost for corporate management was estimated as 0.5% of interchange related toll revenue which was listed in Tables 18-9 and 18-10.

### Maintenance Costs

As for the additional maintenance costs, the lighting cost was counted out of three items listed in routine maintenance cost, i.e., Highway routine maintenance, Equipment maintenance and fuel, and Lighting. The additional maintenance cost was estimated as Rs.  $78 \times 10^3$  in 1997 price.

Therefore the additional costs related to the toll collection from the bypass user through interchanges will be summarised as follows.

- Construction cost : Rs. 2,267×10<sup>3</sup>

Construction was assumed to

take place in 2001

 Operation and Maintenance Costs excluding Overhead Rs. 5.593×10<sup>3</sup>

- Overhead charge : 0.5% of toll revenue related to the traffic through interchange

The justification of additional installation of toll barriers/tollgates at SH33 Interchange in Bareilly Bypass was conducted in financial basis considering 7%

annual inflation rate, and compared the net present value of Costs and Benefit (Toll Revenue) with the discount rate of 20%. Table 18-12 shows the assessment results.

Table 18-12 Financial Assessment Result for the Justification

Unit: Rs. x10<sup>3</sup>

	Benefit (B) Cost (C)				<del></del>			$t : Rs. \times 10^{3}$	
	Benefit (B)				1_	Pr	esent Valu	e	
Fiscal	Toll	Construction	Operation	<u> </u>	Total	Balance			
Year	Revenue	Cost	&c	Overhead	Cost		В	C	B-C
	Revenue	Cost	Maintence			İ			
1998							0	0	0
1999				l i		1	0	0	0
2000	1						0	0	0
2001		2,972			2,972	-2,972	0	1,433	-1,433
2002	115,000		7,844	575	8,419	106,581	46,216	3,383	42,833
2003	152,347		8,393	762	9,155	143,192	51,021	3,066	47,955
2004	189,694		8,981	948	9,929	179,765	52,940	2,771	50,169
2005	227,041		9,609	1,135	10,744	216,297	52,802	2,499	50,304
2006	264,388	<u> </u>	10,282		11,604	252,784	51,240	2,249	48,991
2007	301,735		11,002	1,509	12,511	289,224	48,732	2,021	46,711
2008	339,082	1	11,772	1,695	13,467	325,615	45,636	1,812	43,824
2009	376,429		12,596	1,882	14,478	361,951	42,219	1,624	40,595
2010	413,776	ŀ	13,477	2,069	15,546	398,230	38,673	1,453	37,220
2011	451,123		14,421	2,256	16,677	434,446	35,136	1,299	33,838
2012	488,470		15,430	2,442	17,872	470,598	31,704	1,160	30,544
2013	522,663		16,510	2,613	19,123	503,540	28,270	1,034	27,235
2014	559,249		17,666	2,796	20,462	538,787	25,207	922	24,285
2015	598,397	ì	18,903	2,992	21,895	576,502	22,476	822	21,654
2016	640,285		20,226	3,201	23,427	616,858	20,041	733	19,308
2017	685,104		21,642	3,426	25,068	660,036	17,870	654	17,216
2018	733,062		23,157	3,665	26,822	706,240	15,934	583	15,351
2019	784,376	j	24,778	3,922	28,700	755,676	14,208	520	13,688
2020	839,282		26,512	4,196	30,708	808,574	12,669	464	12,205
2021	898,032	!	28,368	4,490	32,858	865,174	11,296	413	10,883
2022	960,894		30,354	4,804	35,158	925,736	10,073	369	9,704
2023	1,028,157	' <sup>1</sup>	32,479	5,141	37,620	990,537	8,981	329	8,653
2024	1,100,128	8)	34,752	5,501	40,253	1,059,875	8,008	293	7,715
2025	1,177,137		37,185	5,886	43,071	1,134,066	7,141	261	<b>6,8</b> 80
2026	1,259,537	<b>'</b> [_	39,788	6,298	46,086	1,213,451	6,367	233	6,134
2027	1,347,704		42,573	6,739	49,312	1,298,392	5,677	208	5,470
2028	1,442,043	s	45,553				5,062	185	4,877
2029	1,542,986	; <b> </b>	48,742		56,457	1,486,529	4,514	165	4,349
2030	1,650,996	5	52,153				4,025		3,878
2031	1,766,569	<u> </u>	55,804		64,637		3,589	131	3,458
		,,					727,732	33,237	694,495

According to the above assessment, the present vale (1997 price) of benefit (toll revenue) shows Rs,  $727,732\times10^3$  and the present value of costs shows Rs.  $33,237\times10^3$ . The derived net present value (B-C) was Rs.  $+694,495\times10^3$  in 1997 price, and B/C shows quite high value of 21.9.

It will be concluded that to provide toll collection facilities for the bypass users through interchanges is worthwhile from the viewpoint of bypass operation.

# Feasibility Study

Chapter 11	Socio-economic Conditions of the Study Area
Chapter 12	Supplemental Traffic Survey and Analysis

Chapter 13 Future Traffic Demand Forecast

Chapter 14 Field Investigations Chapter 15 Design Standards

Chapter 16 Design for the Fensibility Study

Chapter 17 Construction Plan Chapter 18 Toll Collection System

# Chapter 19 Operation and Maintenance System

Cha	nter	20	Cost	$F_{st}$	ima	les
C. PEST	1.5	40				F 1/ -

Chapter 21 Economic and Financial Analysis
Chapter 22 Implementation Programme

Chapter 23 Recommendations



# 19 Operation and Maintenance System

### 19.1 General

Any kind of infrastructure, however sophisticatedly designed and built, would eventually deteriorate and lose its function, unless it were properly maintained and operated. A newly built highway, as well, requires deliberate attention and care in this regard. A National Highway bypass built as a toll road must also attain much higher levels of traffic smoothness, safety, and comfort so as to attract more users to it. Thus the concessionaire has to provide its own personnel, facilities, and equipment for operation and maintenance of the National Highway Bypass. O/M stations which accommodate this personnel and equipment should be located in the site of the highway. In the cases of the two Bypasses under the Study, it is recommended that one O/M station be built beside the highway and adjacent to one of the toll plazas.

# 19.2 Operation and Maintenance Programme

# 19.2.1 General Plan of an O/M Station

An O/M station in charge of highway maintenance and toll collection generally consists of buildings for management/administration offices and rooms for toll collection, facility control and communication machines, garages for maintenance vehicles, warehouses, parking spaces, etc. The standard spatial requirement for an O/M station whose responsibility covers the entire length of a single medium-sized (about 30 kms) toll highway bypass, though its configurations are diverse, would be assumed as below:

•	Building for offices	1,500 sq. m.
•	Building for machines	500 sq. m.
•	Building for garages	1,000 sq. m.
•	Warehouse	500 sq. m.
٠	Parking spaces	8,000 sq. m.

If a toll road has more than one toll plazas, a substation ,under the O/M station, in charge of toll collection only is needed for each additional toll plaza, which would require about one forth of the above area ,in aggregate, for buildings for offices and machines and parking lot.

# 19.2.2 Personnel for an O/M Station

Personnel to be staffed for operation and maintenance of a 24-hour open toll road includes such manpower as for management, administration, civil engineering maintenance/repair/reconstruction, equipment (mechanical, electric, architectural, communication, etc.) maintenance, toll collection, security and so on. Each category

generally consists of a combination of different personnel rankings such as managers, clerks, technical specialists, and labourers.

Table 19-1 Personnel Composition of an O/M Station

	Managers	Clerical/ Engineers	Tech. Specialists	Labourers
Management	0	0		
Administration		0		
Civil Eng. Maintenance	0	0	0	0
Equipment Maint.		0	0	0
Toll Collection	0	0		
Security		0	0	
Others				0

## 19.2.3 Equipment for an O/M Station

The equipment required for such a typical O/M station as mentioned above would be assumed as shown in Table 19-2.

### 19.3 Operation and Maintenance Activities

### 19.3.1 Toll Collection

A toll fixed for each of the four vehicle classes is paid by the user who stops at the toll gate and collected manually by the attendant in the corresponding booth, who then hands over the receipt and the change, if any. The toll plazas are operated 24 hours a day and attendants in charge are usually mobilised on a three-shift basis. Tolls collected at opening booths are periodically conveyed and kept in the O/M station/substation. Data on collected tolls and traffic should be systematically and incessantly computed and recorded.

Toll collection management to be undertaken by the O/M station includes routine checking of tolls and traffic data, safekeeping of collected tolls, periodic transfer to the bank account, bookkeeping, assignment of attendants to the booths, supply of materials to the toll plaza, maintenance of toll collection machines, and so on.

Responsibilities for such matters as policy and strategy formulation for and overall management of toll collection, accounting, and auditing will be generally taken by the headquarters of the concessionaire rather than the O/M station.

Table 19-2 Maintenance Equipment for an O/M Station

Item	Quantity
Sedans	3
Vans	4
Light Trucks	1
Heavy Trucks	2
Water Trucks	1
Lift Trucks	1
Sign Trucks	4
Tow Trucks	1
Sweepers	1
Portable Generators	4
Power Mowers	5
Chain Saws	1
Tampers	1
Miscellaneous Hand Tools	Lump sum

## 19.3.2 Road Maintenance

Road maintenance to be performed by an O/M station comprise two types of activities; one being routine maintenance, and the other periodic one. The former is supposed to be performed by personnel and equipment of the O/M station itself, while the latter by contractors on a respective tender basis. They include the followings.

## A. Routine maintenance

- (1) Road cleaning: pavement surface cleaning by sweepers and/or sprinklers with manual pick-up of large objects, manual cleaning of roadside facilities such as parking lots and arboriculture, machine/manual cleaning of guard rails, signs, delineators, drainage, expansion joints and lighting
- (2) Minor repairs of earthworks: repair of slope structure and drainage, removal of slid soils and rocks
- (3) Bridge repairs: repairs of expansion joints, shoes, railings, etc.
- (4) Repairs of traffic control devices: repairs of guard rails, repair and/or renewal of signs, repainting of pavement markings
- (5) Pavement repairs: pot-hole fitting, crack sealing, damaged portion patching, partial adjustment of longitudinal irregularity of vertical alignment
- (6) Vegetation control: weeding of slopes and medians, trimming of overgrown trees

- (7) Facility maintenance: maintenance/renewal of lighting, power system, communication, and equipment
- (8) Inspection: regular daily inspection by patrol cars of road conditions, less frequent but periodic on-foot visual inspection of structures, extra inspection of the road under unusual conditions for prevention of emergencies

### B. Periodic maintenance

- (1) Pavement overlay: pavement resurfacing or overlay in the interval depending upon the traffic volume and composition
- (2) Bridge repainting: repainting of steel bridges in the interval depending upon climatic and geographical conditions

# Feasibility Study

Chapter 11	Socio-economic Conditions of the Study Area
Chapter 12	. Supplemental Traffic Survey and Analysis

Chapter 13 Future Traffic Demand Forecast

Chapter 14 Field Investigations Chapter 15 Design Standards

Chapter 16 Design for the Feasibility Study

Chapter 17 Construction Plan Chapter 18 Toll Collection System

Chapter 19 Operation and Maintenance System

# Chapter 20 Cost Estimates

	Chapter 21	Economic and Financia	d Analysis
--	------------	-----------------------	------------

Chapter 22 Implementation Programme

Chapter 23 Recommendations



### 20 Cost Estimates

# 20.1 Unit Cost of Major Work Item

The construction cost of the proposed bypass were estimated on the basis of "MoST Standard Data Book For Analysis of Rates"

# 20.1.1 Unit cost analysis

In order to establish the unit cost for the Study the following three components of unit costs were analysed.

### (1) Labour Cost

Latest information of Labour Costs were obtained from PWD Bareilly, PWD Gwalior and local contractors in Gwalior. "Schedule of Rates of Govt. of Maharashtra", "Schedule of Rates For National Highways Wing, Bihar" and "Delhi Schedule of Rates" were also reviewed for the reference. Table 20-1 shows the summary of labour cost obtained from these sources.

# (2) Machinery and Equipment cost

In order to calculate the hire charge cost of Machinery and Equipment, formula in "Hand Book on Road Construction Machinery, MoST 1985" were adopted. Latest cost of Machinery and Equipment were enquired from manufacturer/importers in Delhi. Basic cost of machinery is summarised in Table 20-2 and applied formula of hire charge cost is shown in Table 20-3.

## (3) Material Cost

Latest information of Material Costs were obtained form PWD Bareilly, PWD Gwalior and local contractors in Gwalior. "Schedule of Rates In National Highway Zone P.W.D. Madhya Pradesh", "Schedule of Rates of Govt. of Maharashtra", "Schedule of Rates For National Highways Wing, Bihar" and "Delhi Schedule of Rates" were also revised for the reference. Table 20-4 shows the summary of material cost obtained form these sources.

# 20.2 Construction Cost Estimates

# 20.2.1 Condition of Construction Cost Estimates

#### 20.2.1.1 General

The construction cost estimates was carried out in accordance with the following basic assumption and conditions.

(1) The project cost was based on the prices in the month of March 1998 (FY 1997)

- (2) The exchange rate of currency was: US\$1.0=Rs. 39.15 (Average in February, 1998)
- (3) Ratio of local/foreign portion of major construction materials were discussed with and recommended by the Most as shown in Table 20-5.
- (4) Cost for preparatory work was assumed as Lump sum amount of 30 million Rupees.
- (5) Contractor's profit and overhead charges were assumed as follows:
  - 15% of Labour Cost
  - 10% of hire charge of Machinery and Equipment
  - 10% of Material Cost

Table 20-1 Labour Cost Data

Rs./day

, — ,———			,			Ks./day
Description	Bareilly	Gwalior		Maharashtra	Bihar	Delhi
	PWD	PWD	Contractor	Schedule	Schedule	Schedule
	TWD	FVVD	Contractor	of Rate	of Rate	of Rate
Diver						500 *
Mechanic	88	150~200	120	84.4		
Operator	50	150~200	150			
Supervisor	52	120	100		65	
Mate	52	120	70		42.9	
Carpenter 1	88	150	100	84.4	48.1	110
Mason I	88	125~150	110	84.4	54	110
Welder				78.4	59.2	100
Blacksmith	75	120	90	78.4	48.1	110
Bandhani	45	100	100			<b>7</b> 5
Carpenter II				78.4		90
Mason II				78.4	48.1	90
Driller				78.4		65
Blaster					67	65
Chiseller						<b>7</b> 5
Breaker						
Dresser	50	75	80			
Sprayer	45	75	80	78.4		70
Bhisti	50	- 80	70	76.4	<del></del>	71
Fitter				78.4		
Mazdoor	50	60	55	73.4	39.7	

<sup>\*</sup> MOST Standard Data Bood For Analysis of Rate



Table 20-4 Material Cost Data

* = G.// _ s = s./	Material	Unit	Bareilly		Gwalior		Maharashtra	Bihar	Delhi	MOST
			PWD	Carriage	Schedule of Rate	Contractor	Schedule of Rate	Schedule of Rate	Schedule of Rate and Contractor	Standard data book for analysis of rates
Steel	Mild steel		16,700	300		7/1/201	15,500		14,350	
	H.Y.S.D	tonne	16,700	300	15,000	15,700~16,500	16,000	14,000	14,500	
	Binding wire	tonne					26	22		
	Structure steel	tonne					20,000			
	Copper plate	tonne	<u> </u>						160,000	
	H.T. Strand	tonne							42,000	
	Nuts, bolts	kg							280	
Cement	Cement	tonne	3,000		3,000	2,260	2,600	2,700~3,200	2,525	
Bitumen	Packed	tonne	8,500	500	6,000		5,528	5,838		
	Bulk		8,000	500	6,000		4,768	5,044		
	Emulsion		11,650	350	9,000		7,100	The second of th	6,500~8,220	
	Premoulded joint filler 20 mm thick	m2							378	
Brick	Brick	1000 nos.	1,500				1,600			
Aggregate	75 mm broken stone	m3	210	150	70	1404		105	220	
Sand	63 mm broken stone	m3	220	150	80	140*	90	115	225	
Stone	45 mm broken stone	m3	230	150	95	160*	95		230	THE THEORY AND THE DESIGNATION OF
	45 mm crushed stone	m3	230	150	140	300*	210	140	230	
	26.5 mm crushed stone	m3	240	150	185	400*	240	150	240	
	22.4 mm crushed stone	m3	250	150	185	400*	290	160 270	265	
	13.2 mm crushed stone	m3	255		210			270	270	
!	11.2 mm crushed stone	m3	254 230	150 150	210	350* 350*	290	206	270	
	6.7 mm crushed stone	m3	230	150	120	300*	200	115	280	
	Crushed stone dust	m3			50	200*		38	gramma and a second control of the second co	man and the second of the second of the second of the second
	Coarse sand	m3			The second contract of	190*			315	
ł	Sand (screen)	m3	THE RESIDENCE OF THE PROPERTY			190*	80	I serve en la laboration a en la co	175	
8	Sand	m3	200	150	50	190*	60			The second section of the second section of the second section
	Moorum	m3			18	100*	18	45	190	
	Gravel	m3			45	130*				
	Boulder	m3	270	150				80		
	Bajri	m3							214	
	Bentonite	nı3	The state of the s	•					3,000	1,500
	Through and bond stone	nı3							115	
Wood	Sal ballies	<u> </u>							30	
products	Ply wood 25 mm							270		
Froducts	Ply wood 20 mm					-		235		
	Ply wood 12 mm							160		
ļ	Ply wood 6 mm							110		
Others	Sheathin pipe	m		<del></del>	··· <del>·</del>				60	
	Safety fuse wire	coil						and a company of the		200
	Neoprene nodules	kg		·   · · · · · · · · · · · · · · · · · ·					7	
	Special Gelatine 80%	kg kg							18	
1	Fibre board 20 mm thick	m2							325	
	Admixture	kg			-	<u>-</u>		- x · · · · · · · · · · · · · · · · · ·		75
* 25km log	d included		L	1	_!	<u> </u>				

<sup>\* 25</sup>km lead included

• . 

Table 20-2 Basic cost of Machinery

Machinery and Equipment	Basic cost (Rs.)
Road Roller 8 to 10 ton.	600,000
Vibratory Road Roller 8.5t	2,500,000
Hot Mix Plant 40-60tonne	28,000,000
Paver Finisher with sensor device 700 to 800t/hr.	7,500,000
Tipper/Dumper 5 to 6 Ton.	625,000
Tipper 10 Ton.	690,000
Bitumen Boiler Oil Fed 1500lts.	200,000
Bating Plant(30m³/hour)	5,170,000
Concrete Pump(27m³/hour)	3,000,000
Transit Mixer	1,400,000
Shovel 1.0m <sup>3</sup>	4,200,000

Table 20-3 Formula of Hire Charge Cost of Machinery and Equipment

		Item
Ownership charge	A)	Total investment at site of work
1	B)	Deduct salvage value 15% of A)
	Ć)	Total investment to be depreciated
	D)	Economic life in hours
	E)	Depreciation per hour
	F)	Strage charge per hour 1% of E)
	Ġ)	Total ownership charge E)+F)
	H)	Contractor's interest and insurance charge
	Ð	Total ownership charge for Contractor E)+F)+H)
Operational charge	'n	Repair charge per hour 150% of E)
Overhead charge	K)	5% of ownership and operatinal charge
Running charge	L)	Operater
	M)	Diesel
	N)	Mobil & Grease, others
	O)	Total running charge L)+M)+N)
Total Hire Charge		

Table 20-5 Ratio of Foreign Portion and Local Portion

	Local Portion %	Foreign Portion %
Steel	100	0
Cement	100	0
Bitumen	90	10
Diesel	60	40
Machinery	90	10

### 20.2.1.2 Conditions for Bareilly Bypass

## (1) Labour Cost

Latest information of Labour Costs was obtained from PWD Bareilly. "Schedule of Rates of Govt. of Maharashtra", "Schedule of Rates For National Highways Wing, Bihar" and "Delhi Schedule of Rates" were also reviewed for the reference. Table 20-6 shows the summary of labour cost obtained from these sources.

## (2) Machinery and Equipment cost

In order to calculate the hire charge cost of Machinery and Equipment, formula in "Handbook On Road Construction Machinery 1985, MoST" were adopted. Latest cost of Machinery and Equipment were enquired from manufacturer/importer in Delhi. Basic cost of Hire charges of Machinery and Equipment applied for the cost estimates are shown in Table 20-7. The procedures of calculation of hire charge are shown in "Breakdown of Cost Estimates".

### (3) Material Cost

Latest information of Material Costs was obtained form PWD Bareilly. "Schedule of Rates In National Highway Zone P.W.D. Madhya Pradesh", "Schedule of Rates of Govt. of Maharashtra", "Schedule of Rates For National Highways Wing, Bihar" and "Delhi Schedule of Rates" were also reviewed for the reference. Carriages of Sand, Aggregate and Gravel, etc. were applied 150 Rupee with the assumption of approximately 90km hauling distance from quarry site. Table 20-8 shows the summary of material cost obtained form these sources.

#### (4) Analysis of Rates

Analysis of Rates was calculated based on the updated data listed in Table 20-6 to Table 20-8. In order to calculate Analysis of Rates, "Standard Data Book For Analysis of Rates of MoST" was applied. Table 20-9 shows the summary of Analysis of Rates and the procedures of calculation are shown in "Breakdown of Cost Estimates.

### (5) Schedule of Rates

Schedule of Rates was calculated on the basis of Analysis of Rates. Table 20-10 shows the Schedule of Rates applied the cost estimates of the project. The procedures of calculation are shown in "Breakdown of Cost Estimates.

Table 20-6 Labour Cost Data for Bareilly Bypass

	T	Rat	e	Remarks	
Description	Unit -	Rs.	US\$	Kemarks	
Diver	Each	500	0	Labour1	
Mechanic	Each	90	0	Labour2	
Operator	Each	90	0	Labour3	
Supervisor	Each	90	0	Labour4	
Mate	Each	90	0	Labour5	
Carpenter	Each	90	0	Labour6	
Mason	Each	90	0	Labour7	
Welder	Each	80	0	Labour8	
Blacksmith	Each	80	0	Labour9	
Bandhani	Each	80	0	Labour10	
Carpenter2	Each	80	0	Labour11	
Mason2	Each	80	0	Labour 12	
Driller	Each	60	0	Labour13	
Blaster	Each	60	0	Labour14	
Chiseller	Each	60	0	Labour15	
Breaker	Each	60	0	Labour16	
Dresser	Each	60	0	Labour17	
Sprayer	Each	60	0	Labour18	
Bhisti	Each	60	0	Labour19	
Fitter	Each	60	0	Labour20	
Blacksmith2	Each	60	0	Labour21	
Mazdoor	Each	50	0	Labour22	

Table 20-7 Hire Charge Cost of Machinery and Equipment for Bareilly Bypass

	77	Department		Contr		Remarks
Item	Unit	Rs.	US\$	Rs.	US\$	Kemarks
Road roller 8 to 10 ton.	hour	185.9	1.2	212.4	1.1	Machinery1
F.E. loader (1m3)	hour	327.9	3.5	363.3		Machinery2
Vibratory road roller 8.5t	hour	559.4	2.3	669.9		Machinery3
Motor grader	hour	1.039.5	4.1	1,304.8		Machinery4
Motorised scraper	hour	1,097.1	4.5	1,318.2		Machinery5
Dozer	hour	966.1	4.2	1,156.3		Machinery6
Hot Mix Plant 40-60tonne	hour	3,967.7	11.5	5,073.3		Machinery7
Paver finisher 700ton/hr.	hour	1,168.7	4.0	1,478.3		Machinery8
Paver finisher with sensor device	hour	1,247.4	4.2	1,579.1		Machinery9
Crawler tractor	hour	138.7	0.9	158.6		Machinery10
Tipper/Dumper 5 to 6 Ton.	hour	157.4	1.0	185.0	1.0	Machinery11
Tipper 10 Ton.	hour	162.5	1.4	193.0	L	Machinery12
Bitumen boiler oil fed 1500lt.	hour	64.9	0.2	73.8	0.1	Machinery13
Concrete mixer	hour	61.6	0.6	63.7		Machinery14
Needle vibrator	hour	37.1	0.3	38.4		Machinery15
Pug mill	hour	43.6	0.3	48.0		Machinery16
Drilling equipment	hour	263.8	0.9	316.9	0.7	
Batching plant (30m3/hour)	hour	1,147.1	4.9	1,375.7		Machinery18
Transit mixer	hour	409.3	2.0	471.2		Machinery19
Concrete pump (27m3/hour)	hour	945.5	3.3	1,078.2	3.7	
Grab dredging crane	hour	489.6	1.8	613.4	1.8	
Shovel (1.0m3)	hour	862.6	5.1	1,048.4		Machinery 22
Truck mounted water tanker	hour	210.8	1.0	241.4	0.9	Machinery23

Table 20-8 Material Cost for Bareilly Bypass

	T	Basic c	Remark		
Material	Unit  -	Rs.	US\$	Kemark	
Mild steel	tonne	16,700.0	0.00	Material1	
H.Y.S.D	tonne	16,700.0	0.00	Material2	
Binding wire	kg	26.0	0.00	Material3	
Structure steel	tonne	20,000.0	0.00	Material4	
Copper plate	tonne	160,000.0		Material5	
H.T.Strand	tonne	42,000.0		Material6	
Nuts, bolts	kg	280.0		Material7	
Cement	tonne	2700.0		Material8	
Admixture	Lt.	75.0		Material9	
Bitumen	tonne	10,485.0	29.76		
Premoulded joint filler 20mm thick	m²	340.2		Material 11	
Diesel	Lt.	6.3	0.11	Material12	
Oil	Lt.	13.2	8.80	Material13	
Brick	nos.	1.5	0.00	Material 14	
Aggregate40mm	m³	230.0	0.00	Material15	
Aggregate20mm	m³	250.0	0.00		
Aggregate15mm	m³	250.0	0.00		
Aggregate10mm	m³	250.0	0.00	<del> </del>	
Aggregate5mm	m³	230.0	0.00		
Bajri	m³	214.0	0.00		
Crushed stone dust	m <sup>3</sup>	200.0	0,00	<del></del>	
Coarse sand	m <sup>3</sup>	200.0	0.00		
Sand	m³	200.0	0.00		
Moorum	m³	130.0	0.00		
Gravel	m <sup>3</sup>	130.0	0.00		
Boulder	m³	270.0	0.00		
Through and bond stone	m³	270.0	0.00		
Bentonite	m³	3,000.0		Material28	
Ply wood 25mm	m²	270.0		Material29	
Ply wood 6mm	m <sup>2</sup>	110.0		Material30	
Sal ballies	m	30.0		Material31	
Neoprene nodules	kg	200.0		Material32	
Safty fuse wire	coil	7.0		Material33	
Special gelatine 80%	kg	18.0		Material34	
Fiber board 20mm thick	m <sup>2</sup>	325.0		Material35	
Detonator	nos.	10.0		Material36	
Sheathing pipe	m	54.0		Material37	
Polyethene pipe 150mm	m	90.0		Material38	
Carriage of sand	m³	150.0		Material39	
Carriage of aggregate	m <sup>3</sup>	150.0		Material40	
Carriage of stone	m³	150.0		Material41	
Carriage of cement	tonne	300.0		) Material42	
Carriage of bitumen	tonne	350.0		) Material43	
Carriage of steel	tonne	300.0	0.00	) Material44	

Table 20-9 Analysis of Rates for Barcilly Bypass (1/2)

em	Unit	Rate Rs.	US\$	SLNo.	MOST Spec.	Analysis of rates
	На	11120	5.13	3	201	Analysis of rates1
leaning and grubbing	m3	31.1	0.16	3		Analysis of rates2
xcavation xcavation Hard Rock	m3	149.4	0.14	3	201	Analysis of rates3
	m3	31.1	0.16	3		Analysis of rates4
arth filling	m	250.5	0.53	0	0	Analysis of rates5
Median	m2	1.3	0.00	6		Analysis of rates6
Compaction of original ground	m3	12.9	0.05	7		Analysis of rates7
aying earth	m3	10.0	0.03	7	305.3 5	Analysis of rates8
Compaction Rolling Excavation for structure1 up to 3m	m3	57.5	0.00	1.1	304	Analysis of rates9
Excavation for structure 2 3m to 6m	m3	71.0	0.00	1.1	304	Analysis of rates 10
Exception for Structure2 photo 6rd	m3	92.0	0.00	1.1		Analysis of rates 11
Excavation for structure3 above 6m	m3	191.2	0.14	1.1		Analysis of rates 12
Excavation Hard Rock for structure	m	6235.4	16.30	2.6		Analysis of rates 13
Sinking of well(sand)	m	13130.9	32.59	2.6(b)		) Analysis of rates 14
Sinking of well(clay)	m3	479.1	0.00	2.7		) Analysis of rates 15
Sand filling in well	m3	41.8	0.00	8		4 Analysis of rates 16
Excavation in foundation trenches		522.3	0.00	1.3		5 Analysis of rates 17
Back filling behind abutment	m3 m3	17.1	0.00	1.2		4 Analysis of rates 18
Earth filling in foundation trench		480.2	0.06			2 Analysis of rates 19
Granular subbase service road	m3	631.2	0.45	3		1 Analysis of rates 20
Granular subbase Grading 1,CBR=30	m3		0.43	1		4 Analysis of rates21
Water bound macadam(base)	m3	677.3	0.27	2		6 Analysis of rates22
Wet mix macadam(base)	m3	765.1	6.72	- 6		4 Analysis of rates23
Bituminous macadam(binding course)	m3	2042.9		8		7 Analysis of rates24
Dense bituminous macadam	m3	2737.1	8.46			9 Analysis of rates25
Premix carpet 20mm thick	m2	79.0	0.53	11(ii)		2 Analysis of rates 26
Asphalt concrete	m3	2373.4	8.71	15		12 Analysis of rates27
Asphalt concrete bridge	m3	3977.4	11.99	4.6		5 Analysis of rates 28
Bitumen mastic	m3	28.7	0.28	4.7		
Tack coat	m2	9.9	0.03	5		B) Analysis of rates 29
Prime coal	m2	15.8	0.05	4		B) Analysis of rates30
Brick masonry	m3	1070.7	0.00			O Analysis of rates 31
Plain cement concrete M15	m3	1412.0	0.46			00 Analysis of rates32
Culvert (Reinforced cement concrete M25)	m3	2362.5	0.46			00 Analysis of rates 33
Well curb M35	m3	3079.1	1.23	2.5(1)	1200(N), 1500(N)&1700(	N) Analysis of rates 3
Well steining M35	m3	3074.4	1.23	2.5(1)	1200(N), 1500(N)&1700(	N) Analysis of fales
Bottom plug M25	m3	3160.6	1.28	2.5(1)	1200(N), 1500(N)&1700(	N) Analysis of fales x
Intermediate plug M25	m3	2394.1	1.08		1200(N), 1500(N)&1700(	NI Analysis of faless
Well cap M35	m3	2705.6	1.08	2.5(1)	1200(N), 1500(N)&1700(	N) Analysis of rates x
Cast in Situ Pile(D=1000mm)	m	3047.4	6.98		1100(N), 1600(N)&1700(	N) Analysis of ratess
Substructure Reiforced cement concrete M25	m3	2761.7	1.22			00 Analysis of rates4
RC Slab M25	m3	3172.7		4.1(ii)(a)		00 Analysis of rates4
RC_Slab M30	m3	3303.3	1.41	4.1(ii)(b)		00 Analysis of rates 4
RC_Tbeam M30	m3	3542.4	1.52			00 Analysis of rates4
PC_Hollow M40	m3	4499.7	1.52			(N) Analysis of rates4
RC_Railing	m	637.3	0.15			00 Analysis of rates4
Approach slab	L.S.	20467.6	2.43	4.12		200 Analysis of rates 4
HYSD(culvert)	tonne	20859.6	0.00			300 Analysis of rates4
HYSD(foundation)	tonne	20811.5	0.00	2.8		(N) Analysis of rates4
HYSD(substructure)	tonne	20811.5	0.00			(N) Analysis of rales4
	tonine	20954.5			3 1600	(N) Analysis of rates
HYSD(superstructure)	tonne	63895.7	21.2		1800	(N) Analysis of rates
PC_strand	tonne	38503.5			4 1200(N)&1900	(N) Analysis of rates
Cutting edge for well foundation	Each	14584.2			9 2000	(N) Analysis of rates
Etastomeric bearings		468.0			· L	(N) Analysis of rates
Providing galvanised mild steel plate	m_	814.8			<del>/ </del>	100 Analysis of rates
Providing and laying expansion joints	m	172.4		0 3.13(b		100 Analysis of rates
1 Description and fixing the heard	<u> </u>	176.5				100 Analysis of rates
Providing and fixing fibre board						
Providing joint filler					4	
	m m	3.8 1635.5	0.0	0 3.13(t	2	100 Analysis of rates 100 Analysis of rates

Table 20-9 Analysis of Rates for Bareilly Bypass (2/2)

	7	Rate Cu		SI.No.	MOST Spec.	Analysis of rates	
Item	Unit	Rs.	US\$	SI.1VQ.	• • • • • • • • • • • • • • • • • • • •	l	
Coarsed rubble masonary(foundation for culvert)	m3	1653.8	0.00	10		Analysis of rates61	
Precast Cement Concrete Kerb	m	120.7	0.24	1	1000/1700	Analysis of rates62	
Berm ditch	m	105.9	0.03	0		Analysis of rates63	
Side ditch	m	302.7	0.08	0	0	Analysis of rates64	
Veritical drain	m	97.8	0.13	0	0	Analysis of rates65	
Turfing slopes of new banks	m2	1.8	0.00	14	307	Analysis of rates66	
Planting plants and shrubs	m	14.0	0.00	22(i)		Analysis of rates67	
Roof setting of toll gate	Each	7244.7	0.00	O		Analysis of rates68	
Anchorage setting of toll gate	Each	27761.5	4.16	0	Japanese standard	Analysis of rates 69	

Table 20-10 Schedule of Rates for Bareilly Bypass

1	Rate		OTA .	Schedule of rates	
Unit	Rs.	US\$	SIA	Schedule of rates	
Each	2,215,110.4	209.7		Schedule of rates 1	
Each		160.8		Schedule of rates2	
Each		93.8		Schedule of rates3	
Each		90.5		Schedule of rates4	
Each	19,439,036.0			Schedule of rates5	
Each		3,293.2	STA 9+040	Schedule of rates6	
		10,096.2	STA 9+040	Schedule of rates7	
Each		749.6	STA13+610	Schedule of rates8	
Each		1,826.3	STA13+610	Schedule of rates9	
		6,053.4	STA13+610	Schedule of rates 10	
		334.4	STA22+900	Schedule of rates 11	
		1,400.8	STA22+900	Schedule of rates 12	
		5,571.6	STA22+900	Schedule of rates 13	
		749.6	STA 8+700	Schedule of rates 14	
				Schedule of rates 15	
				Schedule of rates 16	
				Schedule of rates 17	
				Schedule of rates 18	
				Schedule of rates 19	
				Schedule of rates 20	
				Schedule of rates 21	
				Schedule of rates 22	
				Schedule of rates 23	
				Schedule of rates 24	
				Schedule of rates 25	
				Schedule of rates 26	
				Schedule of rates 27	
				Schedule of rates 28	
				Schedule of rates 29	
				Schedule of rates30	
				Schedule of rates31	
				Schedule of rates32	
				Schedule of rates33	
<del></del>				Schedule of rates34	
				Schedule of rates3:	
				Schedule of rates36	
				Schedule of rates3	
				Schedule of rates3	
				Schedule of rates39	
				Schedule of rates40	
				Schedule of rates4	
				Schedule of rates4	
	Each Each Each Each Each Each	Unit Rs. Each 2,215,110.4 Each 1,711,724.4 Each 1,011,447.4 Each 1,011,447.4 Each 1,022,117.5 Each 19,439,036.0 Each 16,381,359.6 Each 1,964,842.4 Each 9,224,479.3 Each 2,642,084.4 Each 893,421.3 Each 2,642,084.4 Each 893,421.3 Each 7,486,934.3 Each 2,431,814.6 Each 1,964,842.4 Each 9,164,365.8 Each 2,797,501.0 Each 1,964,842.4 Each 9,164,365.8 Each 2,797,501.0 Each 1,964,842.4 Each 9,164,365.8 Each 2,797,501.0 Each 13,678,397.7 Each 11,302,482.5 Each 13,678,397.7 Each 11,302,482.5 Each 3,816,149.1 Each 13,737,725.9 Each 14,058,616.1 Each 3,303,100.4 Each 5,679,201.7 Each 1,167,873.7 Each 11,599,977.5 Each 11,684,035.4 Each 11,599,977.5 Each 11,599,677.5	Unit	Unit	

# 20.2.1.3 Conditions for Gwalior Bypass

## (1) Labour Cost

Latest information of Labour Costs was obtained from PWD Gwalior and local contractors in Gwalior. "Schedule of Rates of Govt. of Maharashtra", "Schedule of Rates For National Highways Wing, Bihar" and "Delhi Schedule of Rates" were also reviewed for the reference. Table 20-11 shows the summary of labour cost obtained from these sources.

# (2) Machinery and Equipment cost

In order to calculate the hire charge cost of Machinery and Equipment, formula in "Handbook On Road Construction Machinery, MoST 1985" were adopted. Latest cost of Machinery and Equipment were enquired from manufacturer/importer in Delhi. Basic cost of Hire charges of Machinery and Equipment applied for the cost estimates are shown in Table 20-12. The procedures of calculation of hire charge are shown in "Breakdown of Cost Estimates".

## (3) Material Cost

Latest information of Material Costs was obtained form PWD Gwalior and local contractors in Gwalior. "Schedule of Rates In National Highway Zone P.W.D. Madhya Pradesh", "Schedule of Rates of Govt. of Maharashtra", "Schedule of Rates For National Highways Wing, Bihar" and "Delhi Schedule of Rates" were also reviewed for the reference. Carriages of Sand, Aggregate and Gravel, etc. were applied 80 Rupee with the assumption of approximately 20 km hauling distance from quarry site. Table 20-13 shows the summary of material cost obtained from these sources.

## (4) Analysis of Rates

Analysis of Rates was calculated based on the updated data listed in Table 20-11 to Table 20-13. In order to calculate Analysis of Rates, "Standard Data Book For Analysis of Rates of MoST" was applied. Table 20-14 and shows summary of Analysis of Rates and the procedures of calculation are shown in "Breakdown of Cost Estimates".

## (5) Schedule of Rates

Schedule of Rates was calculated on the basis of Analysis of Rates. Table 20-15 shows the Schedule of Rates applied the cost estimates of the project. The procedures of calculation are shown in "Breakdown of Cost Estimates.

Table 20-11 Labour Cost Data for Gwalior Bypass

Danadation	Unit	Ra	Remarks	
Description	Olut	Rs.	US\$	Remarks
Diver	Each	500	0	Labourt
Mechanic	Each	150	0	Labour2
Operator	Each	150	0	Labour3
Supervisor	Each	120	0	Labour4
Mate	Each	120	0	Labour5
Carpenter	Each	120	0	Labour6
Mason	Each	120	0	Labour7
Welder	Each	100	0	Labour8
Blacksmith	Each	100	0	Labour9
Bandhani	Each	100	0	Labour10
Carpenter2	Each	100	0	Labour11
Mason2	Each	100	0	Labour12
Driller	Each	80	0	Labour13
Blaster	Each	80	0	Labour14
Chiseller	Each	80	0	Labour15
Breaker	Each	80	0	Labour16
Dresser	Each	80	0	Labour17
Sprayer	Each	80	0	Labour18
Bhisti	Each	80	0	Labour19
Fitter	Each	80	0	Labour20
Blacksmith2	Each	80	0	Labour21
Mazdoor	Each	60	0	Labour22

Table 20-12 Hire Charge Cost of Machinery and Equipment for Gwalior Bypass

Item	Unit	Department		Contractor		Remarks
i	Oinc	Rs.	US\$	Rs.	US\$	Remarks
Road roller 8 to 10 ton.	hour	200.9	1.3	227.4	1.2	Machinery 1
F.E. loader (1m3)	hour	355.8	3.8	391.2	3.8	Machinery2
Vibratory road roller 8.5t	hour	574.4	2.4	685.0	2.3	Machinery3
Motor grader	hour	1057.2	4.2	1322.5	5.1	Machinery4
Motorised scraper	hour	1116.6	4.6	1337.7	5.6	Machinery5
Dozer	hour	986.2	4.4	1176.4	4.9	Machinery6
Hot Mix Plant 40-60tonne	hour	3979.7	11.6	5085.3	51.1	Machinery7
Paver finisher 700ton/hr.	hour	1183.8	4.1	1493.4	5.6	Machinery8
Paver finisher with sensor device	hour	1262.4	4.3	1594.1	6.2	Machinery9
Crawler tractor	hour	152.0	0.9	171.9	0.8	Machinery10
Tipper/Dumper 5 to 6 Ton.	hour	171.6	1.1	199.2	1.0	Machinery11
Tipper 10 Ton.	hour	178.8	1.5	209.3	1.4	Machinery12
Bitumen boiler oil fed 1500lt.	hour	75.2	0.2	84.0	0.1	Machinery13
Concrete mixer	hour	74.8	0.7	76.8	0.6	Machinery14
Needle vibrator	hour	48.3	0.3	49.7	0.3	Machinery15
Pug mill	hour	54.8	0.3	59.2	0.3	Machinery16
Drilling equipment	hour	275.1	0.9	328.1	0.7	Machinery17
Batching plant(30m3/hour)	hour	1168.1	5.0	1396.7	6.1	Machinery18
Transit mixer	hour	425.4	2.1	487.3	1.9	Machinery19
Concrete pump(27m3/hour)	hour	959.9	3.4	1092.6	3.8	Machinery20
Grab dredging crane	hour	502.9	1.9	626.7	1.8	
Shovel (1.0m3)	hour	890.5	5.4	1076.2	5.6	Machinery22
Truck mounted water tanker	hour	224.0	1.1	254.5	0.9	Machinery23

Table 20-13 Material Cost for Gwalior Bypass

	77	Basic o		Remark
Material	Unit	Rs.	US\$	
Mild steel	tonne	15000.0		Material1
H.Y.S.D	tonne	15000.0		Material2
Binding wire	kg	26.0	0.00	Material3
Structure steel	tonne	20000.0		Material4
Copper plate	tonne	160000.0		Material5
H.T.Strand	tonne	42000.0		Material6
Nuts,bolts	kg	280.0		Material7
Cement	tonne	2700.0	0.00	
Admixture	Lt.	75.0	0.00	
Bitumen	tonne	8100.0		Material 10
Premoulded joint filler 20mm thick	m2	340.2		Material11
Diesel	Lt.	6.9		Material12
Oil	Lt.	15.5		Material13
Brick	nos.	1.6	0.00	
Aggregate40mm	m3	220.0	0.00	
Aggregate20mm	m3	320.0	0.00	
Aggregate15mm	m3	270.0	0.00	
Aggregate10mm	m3	270.0	0.00	
Aggregate5mm	m3	220.0		Material19
Bajri	m3	140.0		Material20
Crushed stone dust	m3	120.0		Material21
Coarse sand	m3	110.0		Material22
Sand	m3	110.0		Material23
Moorum	m3	20.0		Material24
Gravel	m3	50.0		) Material25
Boulder	m3	250.0		Material26
Through and bond stone	m3	250.0	0.00	
Bentonite :	m3	3000.0	0.0	
Ply wood 25mm	m2	270.0	0.0	
Ply wood 6mm	m2	110.0		0 Material30
Sal ballies	m	30.0		0 Material31
Neoprene nodules	kg	200.0	0.0	
Safty fuse wire	coil	7.0	0.0	
Special gelatine 80%	kg	18.0	L	0 Material34
Fiber board 20mm thick	m2	325.0		0 Material35
Detonator	nos.	10.0		0 Material36
Sheathing pipe	m	54.0		5 Material37
Polyethene pipe 150mm	m	90.0	<del> </del>	6 Material38
Carriage of sand	m3	80.0		Material39
Carriage of aggregate	m3	80.0	<del> </del>	Material40
Carriage of stone	m3:	110.0		Material41
Carriage of cement	tonne	300.0		00 Material42
Carriage of bitumen	tonne	350.0		00 Material43 00 Material44
Carriage of steel	tonne	300.0	0.0	o iviateriai4

Table 20-14 Analysis of Rates for Gwalior Bypass (1/2)

item	Ųnit	Rs. Rat	e US\$	St.No.	MOST Spec.	Analysis of rates
Cleaning and grubbing	Ha	1217.4	5.42	3	201	Analysis of rates1
Excavation	m3	41.2	0.21	3		Analysis of rates2
Excavation Hard Rock	m3	212.3	0.25	3	201	Analysis of rates3
Earth filling	m3	41.2	0 21	3	201	Analysis of rates4
Median	m	276.6	0.57	ō	0	Analysis of rates5
Compaction of original ground	m2	1.5	0.00	6		Analysis of rates6
Laying earth	m3	13.3	0.05	7	305.3.5	Analysis of rates?
Compaction Rolling	m3	10.5	0.03	7	305.3.5	Analysis of rates8
Excavation for structure1 up to 3m	m3	69.0	0.00	1.1	304	Analysis of rates9
Excavation for structure2 3m to 6m	m3	85.2	0.00	1.1	304	Analysis of rates 1
Excavation for structure3 above 6m	m3	110.4	0.00	1.1	304	Analysis of rates1
Excavation Hard Rock for structure	m3	215.8	0.14	1.1	304	Analysis of rates 1:
Sinking of well(sand)	m	6443.7	16.47	2.6	1200(N)	Analysis of rates1:
Sinking of well(clay)	m	13547.5	32.93	2.6(b)	1200(N)	Analysis of rates 1
Sand filling in well	m3	271.7	0.00	2.7	1207(N)	Analysis of rates 1
Excavation in foundation trenches	m3	50.6	0.00	8	304	Analysis of rates 1
Back filling behind abutment	m3	323.5	0.00	1.3	305	Analysis of rates 1
Earth filling in foundation trench	m3	20.9	0.00	1.2	304	Analysis of rates 1
Granular subbase service road	m3	268.4	0.06	1	40432	Analysis of rates 1
Granular subbase Grading I CBR=30	m3	525.0	0.46	3	401	Analysis of rates2
Water bound macadam(base)	m3	532.0	0.27	1	404	Analysis of rates2
Wet mix macadam(base)	m3	612.2	0.98	2	406	Analysis of rates2
Bituminous macadam(binding course)	m3	1640.3	5.93	6		Analysis of rates2
Dense bituminous macadam	m3	2366.2	7.39	8		Analysis of rates2
Premix carpet 20mm thick	m2	72.8	0.50	11(ii)		Analysis of rates2
Asphalt concrete	m3	2029.8	7.74	15	512	Analysis of rates2
Asphalt concrete bridge	m3	3483.2	10.57	4.6	22018512	Analysis of rates2
Bitumen mastic	m3	28.4	0.27	4.7	515	Analysis of rates2
Tack coat	m2	8.1	0.02	5		Analysis of rates2
Prime coat	m2	12.5	0.04	4		Analysis of rates3
Brick masonry	m3	1149.7	0.00	7		Analysis of rates3
Plain cement concrete M15	m3	1477.0	0.49	2	1000/1700	Analysis of rates3:
Culvert (Reinforced cement concrete M25)	m3	2330.2	0.49	. 4	1700	Analysis of rates3
Well ourb M35	m3	3069.9	1.28	2.5(i)	1200(N), 1500(N)&1700(N)	Analysis of rates3
Well steining M35	m3	3065.3	1.28		1200(N), 1500(N)&1700(N)	
Bottom plug M25	m3	3079.8	1.33	2.5(1)	1200(N), 1500(N)&1700(N)	Analysis of rates3
Intermediate plug M25	m3	2313.7	1.12	2.5(1)	1200(N), 1500(N)&1700(N)	Analysis of rates3
Well cap M35	m3	2650.4	1.12	2.5(I)	1200(N), 1500(N)&1700(N)	Analysis of rates3
Cast in Situ Pile(D=1000mm)	m	3098.7	3.35	2.11	1100(N), 1600(N)&1700(N)	Analysis of rates3
Substructure Reinforced cement concrete M25	m3	2705.4	1.27	3.3(b)	1500&1700	Analysis of rates4
RC Slab M25	m3	3111.0	1.46	4.1(ii)(a)	1500&1700	Analysis of rates4
RC Slab M30	m3	3243.6	1.46	4.1(ii)(b)	1500&1700	Analysis of rates4
RC Tbeam M30	m3	3478.7	1.57	4.1(ii)	1500&1700	Analysis of rates4
PC Hollow M40	m3	4563.9	1.57	4.2	1500(N)&1700(N)	Analysis of rates4
RC Railing	m	608.9	0.16	4.8	1500,1600,1700&2200	Analysis of rates4
Approach slab	L.S.	19203.7	2.53		1500,1600,17008.2200	Analysis of rates4
HYSD(culvert)	tonne	19209.5	0.00	6	1000/1600	Analysis of rates4
HYSD(foundation)	tonne	19193.0	0.00		1600(N)	Analysis of rates4
HYSD(substructure)	tonne	19193.0	0.00	3.5	1600(N)	Analysis of rates4
HYSD(superstructure)	lonne	19336.0	0.00	4.3		Analysis of rates5
PC strand	lonne	64275.5	20.88		1800(N)	Analysis of rates5
Cutting edge for well foundation	lonne	40091.5	0.00			Analysis of rates5
Etastomeric bearings	Each	14280.4	0.00	3.9	2000(N	Analysis of rates5
Providing galvanised mild steel plate	m	421.3	0.00			Analysis of rates5
Providing and laying expansion joints	m	816.4	0.00			Analysis of rates5
Providing and fixing fibre board	m	172.5	0.00		2100	Analysis of rates5
Providing joint filler	m	176.6	0.27		2100	Analysis of rates5
Providing and filling joint sealing compound	m	3.9	0.00			Analysis of rates5
Expansion joint	m	1590.7	0.27			Analysis of rates5
Laying apron(boulder)	m3	625.0	0.00			Analysis of rates6

Table 20-14 Analysis of Rates for Gwalior Bypass (2/2)

		Ra		SI.No.	MOST Spec.	Analysis of rates
tem	Unit	Rs.	US\$	01.110.	,	
(for a daylor for cultural)	m3	1634.4	0.00	10		Analysis of rates6
Coarsed rubble masonary(foundation for culvert)		133.5	0.26	1	1000/1700	Analysis of rates6
Precast Cement Concrete Kerb	m		0.04		0	Analysis of rates6
Berm ditch	m	110.8		<del> </del>		Analysis of rates6
Side ditch	m	327.0		<u> </u>		Analysis of rates6
	m	102 2	0.14	0		
Veritical drain	m2	2.0	0.00	14		Analysis of rates6
Turfing slopes of new banks	<del>                                     </del>	14.0		22(i)		Analysis of rates6
Planting plants and shrubs	m				Japanese standard	Analysis of rates6
Roof setting of toil gate	Each	7373.0		····	Japanese standard	Analysis of ratesf
Anchorage setting of toll gate	Each	27898.9	4.22	<u> </u>	Japanese standard	Managas a rocosa

Table 20-15 Schedule of Rates for Gwalior Bypass

		Ra		STA	Schedule of rates
eni	Unit	Rs.	US\$	OIA .	
1.1.1435	m3	34	0		Schedule of rates 1
xtra lead 13km	Each	2,126,262	229		Schedule of rales2
DCBL_cell 1	Each	1,643,422	176		Schedule of rates3
DC8M_cell 1	Each	971,603	102		Schedule of rates4
DCBS_cell 1	Each	4,354,941	453		Schedule of rates5
VCCBL_cell 3	Each	2,871,513	296	L	Schedule of rates6
VCCBM_cell 3	Each	2,019,817	208		Schedule of rates7
VCCBM_cell 2	Each	548,527	55		Schedule of rates8
VCCBS_cell 1	Each	3,155,410	1,022	STA26+100	Schedule of rates9
ROB_Superstructure	Each	7,903,212	1,863	STA26+100	Schedule of rates 10
ROB_Substructure	Each	1,115,525	612	STA26+100	Schedule of rates 11
ROB_Foundation	Each	7,220,070	2,214	STA10+340	Schedule of rates 12
WCBR1_Superstructure	Each	6,418,562	1,442	STA10+340	Schedule of rates 13
WC8R1_Substructure	Each	1,115,525	612	STA10+340	Schedule of rates 14
WCBR1_Foundation	Each	3,496,764	1,367	STA 12+720	Schedule of rates 15
WCBR2_Superstructure	Each	9,771,913	2,102	STA 12+720	Schedule of rates 16
WCBR2_Substructure	Each	6,894,745	2,130	STA 12+720	Schedule of rates 17
WCBR2_Foundation	Each	3,144,695	960	STA 7+760	Schedule of rates 18
WCBR3(Slab)_Superstructure	Each	5,300,177	1,344	STA 7+760	Schedule of rates 19
WCBR3(Slab)_Substructure	Each	1,227,077	898	STA 7+760	Schedule of rates 20
WCBR3(Slab)_Foundation		4,647,714	1,428	STA25+650	Schedule of rates 21
WCBR4(Slab)_Superstructure	Each	8,942,789	2,043	STA25+650	Schedule of rates 22
WCBR4(Slab)_Substructure	Each	5,518,239	3.008	STA25+650	Schedule of rates 23
WCBR4(Slab)_Foundation	Each	703,787	1,257		Schedule of rates24
Toll barrier(BP&EP)	Each		1,544		Schedule of rates25
Toll barrier(SH33IC)	Each	758,411 414,676	863	<del> </del>	Schedule of rates 28
Toll gate(2booth)	Each		2,578		Schedule of rates 27
Toli gate(3booth)	Each	1,039,405	7,411	<del> </del>	Schedule of rates 28
Main operation office	Each	9,802,542	1,520		Schedule of rates 29
Sub operation office	Each	904,543	1,020		Schedule of rates36
Removing telepone line	M	1,604	1	<del> </del>	Schedule of rates3
Removing power line	M	1,594	3,294		Schedule of rates3:
Service road	Km	1,632,915	0	<del>- </del>	Schedule of rates3
Road appurtenances	Km	109,168	_\ <u>v</u>	+	-
			<del> </del>		<del>-  </del>
				<del>-  </del>	
				<del> </del>	
			<del> </del> -		
		<u> </u>			
				<del>_  </del>	<del>-  </del> -
					<del>-  </del>
		1	_		

## 20.2.2 Estimated Construction Cost

Direct Construction Cost of Bareilly Bypass and Gwalior Bypass were estimated as shown in Tables 20-16 and 20-17, respectively. Details of the direct construction cost of both bypasses were presented in Tables 20-18 and 20-19, respectively.

Table 20-16 Direct Construction Cost of Bareilly Bypass

Item	Rs.	Local Portion Rs.	Foreign Portion US\$	Ratio
1 Preparatory work	30,000,000	30,000,000	0	2.8%
2 Earthwork	178,972,500	159,622,700	494,200	16.9%
3 Pavement	351,318,400	330,365,500	535,200	33.1%
4 Culvert	42,603,800	42,492,600	2,800	4.0%
5 Bridge/Viaduct	218,740,600	216,420,000	59,300	20.6%
6 Toll gate	68,484,900	64,548,100	100,600	6.5%
7 Service road	134,938,400	129,205,300	146,400	12.7%
8 Drainage	16,721,700	16,327,500	10,100	1.6%
9 Utility Diversion	13,099,300	12,886,000	5,400	1.2%
10 Road appurtenances	3,482,400	3,482,400	0	0.3%
11 Horticulture	1,766,900	1,736,900	800	0.2%
12 Environmental Mitigation Measures	500,000	500,000	0	0.0%
Total of direct cost	1,060,628,900	1,007,587,000	1,354,800	

Table 20-17 Direct Construction Cost of Gwalior Bypass

Item	Rs.	Local Portion Rs.	Foreign Portion US\$	Ratio
1 Preparatory work	30,000,000	30,000,000	0	3.8%
2 Earthwork	286,891,600	255,971,800	789,800	35.9%
3 Pavement	261,282,800	244,125,300	438,300	32.7%
4 Culvert	49,685,900	49,539,600	3,700	6.2%
5 Bridge/Viaduct	73,143,800	72,466,900	17,300	9.2%
6 Toll gate	26,910,200	25,500,400	36,000	3.4%
7 Service road	44,448,100	42,116,500	59,600	5.6%
8 Drainage	15,185,800	14,911,700	7,000	1.9%
9 Utility Diversion	6,751,700	6,596,100	4,000	0.8%
10 Road appurtenances	2,892,600	2,892,600	0	0.4%
11 Horticulture	1,613,300	1,589,200	600	0.2%
12 Environmental Mitigation Measures	500,000	500,000	0	0.1%
Total of direct cost	799,305,600	746,209,900	1,356,200	

Table 20-18 Construction Cost of Bareilly Bypass (1/3)

Itom	Sub item	Unit	Qty.	Rate		Amount	_ l	Kemark
				Rs.	OSS	Rs.	nss	
1 Preparatory work	Lab.Equipment,Accomodation And Vhicle, Etc.	SI				30,000,000		
SUB TOTAL(1)						30,000,000		A section of a second
2 Earthwork	Cleaning and grubbing	Ę.	247	1,162.49	3.76	951,782	676	Analysis of raices
	Excavation	Ê	0	32.70	0.12	<b>5</b> (		Amanysis of rates.
	Excavation Hard Rock	Ê.	0	150.59	0.11	0	0	Analysis of rates.
	Farth filling	Ê	2,691,780	32.70	0.12	88,027,801	320,668	
-	Median include kerb	ឥ	29,510	256.01	0.39	7,554,885	11,509	
	- The		2,691,780	13.37	0.04	35,987,482	97,750	Analysis of rates?
	Compaction Rolling	" E	2,691,780	10.31	0.02	27,765,421	63,391	Analysis of rates8
SUB TOTAL(2)				*		159,622,724	494,247	
3 Pavenent		^e	12.593	2.408.70	6.35	30,332,753	79,992	Analysis of rates26
	Dense bituminous macadam	Ê	42,285	2,865.03	6.46	121,148,003	272,992	Analysis of rates24
	Wet mix maradam(hase)	Ê	112.874	805.05	0.83	90,868,916	93,290	
	Granular subbase Grading 1 CBR=30	Ê	110,405	669.23	0.52	73,886,039	57,653	
	•	E H	817,584	10.11	0.02	8,268,107	18,241	
	Prime coat	a,	362,108	16.19	0.04	5,861,643	13,027	Analysis of rates30
STATOT BITS						330,365,462	535,196	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
300 101W(3)								
4 Culvert		Nos.	F-1	2,217,305.91	149.99	2,217,306	150	Schedule of rates1
	RDCBM cell 1	Nos.	17	1,713,407.81	115.02	29,127,933	1,955	
		Nos.	10	1,012,428.92	67.05	10,124,289	671	Schedule of rates?
	WCCBS cell 2	Nos.	-	1,023,064.97	64.71	1,023,065	99	Schedule of rates4
SUB TOTAL(4)						42,492,593	2,841	
5 Bridge/Viaduct (Superstructure)	RDBR1_Superstructure STA 9+040	Nos.	Ľ	12,694,857	3,269.86	12,694,857	3,270	3,270 Schedule of rates5
(Simpore and a C)								

Table 20-18 Construction Cost of Bareilly Bypass (2/3)

		-							****									-	وعدننو	-			Description of the last of the		-	-			-		
Remark		Schedule of rates8	Schedule of rates11	Schedule of rates14	Schedule of rates17	Schedule of rates20	Schedule of rates23	Schedule of rates26	Schedule of rates6	Schedule of rates9	Schedule of rates12	Schedule of rates15	Schedule of rates18	Schedule of rates21	Schedule of rates24	Schedule of rates27	Schedule of rates7	Schedule of rates10	Schedule of rates13	Schedule of rates16	Schedule of rates19	Schedule of rates 22	Schedule of rates25	Schedule of rates28				Schedule of rates29	Schedule of rates30	Schedule of rates31	Schedule of rates32
	US\$	199	291	199	661	1,322	1,322	3,945	2,380	1,299	066	1,299	1,299	1,834	1,750	5,487	3,257	1,952	1,797	2,068	2,068	4,043	5,083	10,539			59,276	8	99	E	31
Amount	Rs.	2,594,592	1,143,390	2,594,592	2,594,592	5,394,835	5,394,835	18,343,424	16,056,853	8,930,534	7,213,431	8,870,425	8,870,425	13,283,707	13,245,069	33,294,957	4,453,568	2,670,297	2,457,790	2,827,371	2,827,371	11,740,443	14,508,602	14,414,029			216,419,987	794,314	529,542	104,548	278,603
	SSO	660.54	291.00	660.54	660.54	1,321.50	1,321.50	657.57	2,380.04	1,298.96	06.686	1,299.32	1,299.32	1,834.46	1,749.50	914.48	3,256.58	1,952.47	1,797.02	2,067.54	2,067.54	4,043.41	5,082.53	1,756.56				33.06	33.06	11.47	15.62
Rate	Rs.	2,594,592	1,143,390	2,594,592	2,594,592	5,394,835	5,394,835	3,057,237	16.056.853	8.930,534	7,213,431	8,870,425	8,870,425	13,283,707	13,245,069	5,549,159	4,453,568	2,670,297	2,457,790	2,827,371	2,827,371	11,740,443	14,508,602	2,402,338				264,771.18	264,771.18	104,548.15	139,301.72
Otv.		1	-1	-	7	1	۲	9		-	·		7	-	F-4	9		1	7		1	1		9				3	7		7
Unit		Nos.	Nos.	Nos.	Nos	Nos.	Nos.	Nos.	Z	Nos	Sos	Zos.	Nos.	Nos	Nos.	Nos.	Nos.	Nos.	Nos.	Nos.	Nos.	Nos.	Nos.	Nos.		,		Nos.	Nos.	Nos.	Nos.
		STA13+610	STA22+900	STA 8+700	STA 13+300	STA 7+900	STA 14+270	ture	STA 9+040	STA13+610	STA22+900	STA 8+700	STA 13+300	STA 7+900	STA 14+270	re	STA 9+040	STA13+610	STA22+900	STA 8+700	STA 13+300	STA 7+900	STA 14+270		,					<del></del>	
Sub item		RDBR2 Superstructure	RDBR3 Superstructure	ICBR1 Superstructure	ICBR2 Superstructure	WCBR1 Superstructure	WCBR2 Superstructure	WCBR3(Slab)_Superstructure	DDBD1 Cubetmeeting	PDBR2 Substructure	RDBR3 Substructure	ICBR1 Substructure	ICBR2 Substructure	WCBR1 Substructure	WCBR2 Substructure	WCBR3(Slab)_Substructure	RDRR1 Foundation	RDBR2 Foundation	RDBR3 Foundation	CBR1 Foundation	ICBR2 Foundation	WCBR1 Foundation	WCBR2 Foundation	WCBR3(Slab) Foundation				Toll barrier(BP&EP)	Toll barrier(SH331C)	Toll gate(2booth)	Toll gate(3booth)
mot l	*****									(amynusanc)							(Foundation)	(ioning i)									SITR TOTAL(S)	6 Toll gate			

Table 20-18 Construction Cost of Bareilly Bypass (3/3)

Remark			189 Schedule of rates34	50 Schedule of rates38	79 Schedule of rates36	39 Schedule of rates37	50 Schedule of rates38				139 Schedule of rates43		5,670 Analysis of rates62	68 Analysis of rates63	1,919 Analysis of rates64	2,410 Analysis of rates65	267	4,317 Schedule of rates42	1,132 Schedule of rates41	0	5,449	O Schedule of rates44			0   Analysis of rates67	3	<del></del>	0		838
Amount.	)	6,282,292 11,335	6,291,615 11,289	7,407,691 13,450		12,037,806 23,439				1(	_		3,876,044 5,6	361,391	9,706,026 1,9	2,384,080 2,		5,448,680 4.2	1,437,344		12,886,024 5,	3,482,448					200,000	200,000		1,007,587,042 1,354,838
	USS	11,335.01	11,288.73	13,449.80	19,779.15	23,438.66	13 440 80	12,417.00 12,417.00	2,363.69	1,122.62	20 424 C	00:172/7	0.18	0.02	0.06	0.10		1.23	1.23	0.00	-	00.00		0.00	0.00		90.0			<del></del>
Rate	Rs.	6,282,292.11	6.291.615.22	7.407.691.17	10.893,660.74	12 037 805 84	7 4 07 601 17	7,407,091.17	10,441,173.14	1,039,558.08	0 100 000 07	4,130,000.77	123.05	106.29	303.50	98.92	•	1,552.33	1,562.33	6,000,000.00		109,167.65		1.80	900,000.00		500,000.00			
140	į Š	1		, t-	· -	·	٦ ٢	<b></b> 1 1	H 1	7		00.41	31,500	3,400	31,980	24 100		3.510.00	920.00	1.00		31.90		465,000	1.00		F-1			-
7:11	250	Nos	N		S Z	200	300	Nos:	Sos.	Nos.		ž	٤	8	E	£	=	E	Ε	S		ă		m2	L'S		LS		1	
	Sub item	Introduction ROSERD Times	Interchange_of weil_aimic	Interchange_brwer_Lane	Interchange 513512 Junio	Interchange_Stat/JC_Ztatie	Interchange_SH331C_Ilane	Interchange_SH33IC_2lane	Main operation office	Sub operation office		Service road	Descript Comont Concrete Kerb	por dish			Verincal orain	Daniel activities (190	Removing power and	Removing textpone mix		Road appurtenances		Turfing slopes of new banks	Planting plants and shrubs		Construction of check dams/retaining	walls/baffels etc.		<u>-</u> -
	Item										SUB TOTAL(6)	7 Service road	SUB 1OTAL(/)	8 Uramage			(5) h 4 sa (6) ta (6) h 5	SUB IOIAL(9)	9 Utility Diversion		SITE TOTAL(9)	10 Dead amunitonances	SUB TOTAL(10)	11 Most willting	יון זוסומרמונמים	SUB TOTAL(11)	12 Environmental Mitigation	Measures	SUB TOTAL(12)	TOTAL OF DIRECT COST

Table 20-19 Construction Cost of Gwalior Bypass (1/3)

	C. L. itam	1 Init	) Obv.	Rate		Amount	int.	Remark
n stant				Rs.	nS\$	Rs.	OSS	
1 Preparatory work	Lab.Equipment, Accomodation	<u> </u>				30,000,000.00		
	And Vhicle, Etc.	<u> </u>			-	30,000,000		
SUB IOIAL(1)	2 to 12 de 1 d	1	278	1,271,39	4.04	277,162	881	Analysis of rates1
2 Earthwork	na grupourg	in bad mas	165	43.33	0.16	7,188,470	26,296	Analysis of rates2
	Excavation Hand Book 3km			214.21	0.20	35,538,095	33,181	Analysis of rates3
			-	43.33	0.16	77,199,547	282,402	Analysis of rates4
		erd.		283.27	0.40	7,721,818	10,904	Analysis of rates5
	d 13km		-2	34.74	0.14	75,162,586	302,861	Schedule of rates1
				13.70	0.04	29,633,046	80,505	Analysis of rates?
	Compaction Rolling			10.75	0.02	23,251,037	52,748	52,748 Analysis of rates
SUB TOTAL(2)						255,971,762	789,778	
3 Pavement				7 000 54	E C7	22 505 503	63.104	Analysis of rates28
	Asphalt concrete	E -		7,023.51	70.0	CDC/CDC/22	בייניים	
	Dense bituminous macadam	"E	37,346	2,446.55	5.69	91,368,719	212,312	
	Wet mix macadam(base)	ੌਬ —	069'66	653.56	0.87	65,153,354	87,139	
	Granular subbase Grading 1, CBR=30		602'26	564.60	0.55	55,054,056	53,688	
		m <sub>2</sub>	722,090	8.25	0.02	5,954,925	12,970	Analysis of rates31
	Prime coat	B.	319,814	12.78	0.03	4,088,735	9,037	Analysis of rates32
SUB TOTAL(3)						244,125,291	438,250	
4 Culvert				00000	4000	0 517 694	12 Y	Cohodula of ratec
	RDCBL_cell 1	S Z		2,128,670.90	105.07	14 807 475	130	
	RDCBM_cell 1		7 7	1,043,269.43	72.27	9 77 8 805	732	
	RDCBS_cell 1	Nos.		#C:000:7/6	O. C. C. C.	2707077	647	
	WCCBL_cell 3	Nos.	2	4,359,706.39	17.676	C14/C1/0	ì	
	WCCBM_cell 3	Nos.		2,8/4,630.00	77177	007/4#/10	7	
	WCCBM_cell 2	Nos.		2,022,010.76	149.02	2,022,011	149	
	WCCBS_cell 1	Nos		549,104.43	39.24	1,647,313	118	Schedule of rates8
SUB TOTAL(4)	·					49,539,598	3,736	

Table 20-19 Construction Cost of Gwalior Bypass (2/3)

STA26+100 Nos. 1 2,125,8 STA10+340 Nos. 1 2,908,6  THE STA 12+720 Nos. 1 2,908,6  THE STA25+650 Nos. 1 2,908,6  STA10+340 Nos. 1 2,908,79,6  STA10+340 Nos. 1 2,909,79,709,709,709,709,709,709,709,709,		Cub itom		Unit	Ģ ĭv.	Rate	e.	Amount	nt.	Kemark
ROB Superstructure         STAZ6+100         Nos.         1         2.125,861         824.33         2.125,861         824.33         2.175,861         824.35         1.775,272         1.796,83         1.775,272         1.796,83         1.796,83         1.775,272         1.796,83         1.706,83         4.772,272         1.796,83         1.706,83         4.772,272         1.796,83         1.706,83         4.772,272         1.706,83         1.706,84         7.706,255         4.558,871         1.706,84         7.706,84         7.706,84         7.706,84         7.706,84         7.706,84         7.706,84         7.706,84         7.706,87         7.706,84         7.706,87	Item	מים זוכיזו			·	Rs.	SSO	Rs.	US\$	
WCBR_Superstructure         STA10+340         Nos.         1         4,712,522         1,795,78         4,712,522         1,796,78           WCBR_Subperstructure         STA10+320         Nos.         1         4,999,888         1,007         1,008         1,007         2,908,648         7,106         7,106         1,007         2,908,648         7,106	5 Bridge/Viaduct	, and a	-	y c	F	2,125,861	824.33	2,125,861	824	Schedule of rates9
VCBR2_Superstructure	(Superstructure)	INCBR1 Superstructure		Nos.	-	4,712,522	1,795.78	4,712,522		Schedule of rates12
WCBR3(Slab)_Superstructure STAZ5+650   Nos.   1 2,908,648   715.92   2,908,648   715.92   1,063.54   715.92   1,063.54   710.63		WCBR2 Superstructure		Nos.	-	4,959,888	1,007.82	4,959,888	1,008	Schedule of rates15
WCBR4(Slab)_Superstructure   STAZ6+100   Nos.   1   7,709,275   1,386.54   7,709,275   1,387   1,005		WCBR3(Slab) Superstructure	STA 7+760	Nos.	<b>-</b>	2,908,648	715.92	2,908,648	716	Schedule of rates is
ROB_Substructure		WCBR4(Slab)_Superstructure	STA25+650	Nos.	H	4,658,571	1,062.55	4,658,571	1,063	Schedule of rates21
ROB_Substructure				<u> </u>						
ture) ROB_Substructure STA26+100 Nos. 1 7,709,275 1,386,54 7,709,275 1,387 (9,030,906 Nos. 1 6,030,906 1,072.81 6,030,906 1,073 (9,030,906 Nos. 1 5,181,552 1,000.06 5,181,552 1,000 (9,045). Substructure STA 7+760 Nos. 1 8,740,459 1,520,36 8,740,459 1,520 1,000 (9,045). Substructure STA 7+760 Nos. 1 8,740,459 1,520,36 8,740,459 1,520 1,000 (9,045). Substructure STA 7+760 Nos. 1 1,121,846 440.82 1,121,846 441 (1,121,846 1,12				<u>,,</u>						
WCBR2_Substructure   STA10+340   Nos.   1   6,030,906   1,072.81   6,030,906   1,073		POR Substructure	STA26+100	Nos.	r-4	7,709,275	1,386.54	7,709,275	1,387	Schedule of rates10
WCBR2_Substructure   STA 12+720   Nos.   1   9,479,683   1,564.54   9,479,683   1,555   1,000	(agnacance)	WCBR1 Substructure	STA10+340	Nos.	H	906'080'9	1,072.81	906'060'9	1,073	Schedule of rates13
MCBR3(slab)_Substructure         STA 7+760         Nos.         1         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         5,181,552         1,000.06         1,520.36 <th< td=""><td></td><td>WCBR2 Substructure</td><td>STA 12+720</td><td>Nos.</td><td>H</td><td>9,479,683</td><td>1,564.54</td><td>6,479,683</td><td>1,565</td><td>Schedule of rates16</td></th<>		WCBR2 Substructure	STA 12+720	Nos.	H	9,479,683	1,564.54	6,479,683	1,565	Schedule of rates16
WCBR4(Slab)_Substructure   STA25+650   Nos.   1   8,740,459   1,520.36   8,740,459   1,520		WCBR3(Slab) Substructure	STA 7+760	Nos.		5,181,552	1,000.06	5,181,552	1,000	Schedule of rates19
ROB_Foundation   STA26+100   Nos.   1   1,121,846   440.82   1,121,846   441		WCBR4(Slab)_Substructure	STA25+650	Nos.	1	8,740,459	1,520.36	8,740,459	1,520	Schedule of rates22
ion) ROB_Foundation STA26+100 Nos. 1 1,121,846 440.82 1,121,846 441 440.82 1,121,846 441 440.82 1,121,846 441 440.82 1,121,846 441 440.82 1,121,846 441 440.82 1,121,846 441 440.82 1,121,846 441 440.82 1,121,846 441 441 441 441 441 441 441 441 441 4										
ion) ROB_Foundation STA26+100 Nos. 1 1,121,846 440.82 1,121,846 441 441 440.82 1,121,846 441 441 441 441 441 441 441 441 441 4				_						
ion) ROB_Foundation STA26+100 Nos. 1 1,121,846 440.82 1,121,846 441.84 440.82 1,121,846 441.84 441.84 440.82 1,121,846 441.84 44						,			***	F F. 10. A. 1. A.
VCBR1_Foundation         STA10+340         Nos.         1         1,121,846         440.82         1,121,846         441.82           WCBR2_Foundation         STA 12+720         Nos.         1         6,913,893         1,594.20         6,913,893         1,594           WCBR3(Slab)_Foundation         STA 7+760         Nos.         1         5,565,561         2,217.69         5,565,561         2,217           WCBR4(Slab)_Foundation         STA25+650         Nos.         1         5,565,561         2,217.69         5,565,561         2,218           FAL(5)         Toll barrier(BP&EP)         Nos.         2         723,628.25         980.72         1,447,256         1,961           Main operation office         Nos.         1         9,903,373.22         5,371.21         9,903,373         5,371           Interchance BP&EP Illane         Nos.         1         6,530,915.78         1,104.60         926,245         1,105           Interchance BP&EP Illane         Nos.         1         6,530,915.78         6,530,915.78         1,3539.28         6,530,916         13,539	(Foundation)	ROB_Foundation	STA26+100	Nos.	<b></b> -	1,121,846	440.82	1,121,840	T 4-4	Schedule of taiksta
VCBR2_Foundation         STA 12+720 Nos.         Nos.         1 6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,594.20 (6,913,893 (1,994.20 (6,994.20 (6,913,893 (1,994.20 (6,994.20	(	WCBR1 Foundation	STA10+340	Soz	-	1,121,846	440.82	1,121,846	<b>‡</b>	Schedule of rates 14
TAL(S)         WCBR3(Slab)_Foundation         STA 7+760 STA 7+760 Nos.         Nos.         1         1,236,342 646.56         646.56         1,236,342 646.56         647           WCBR4(Slab)_Foundation         STA25+650 Nos.         1         5,565,561         2,217.69         5,565,561         2,218           Foundation office         Nos.         2         723,628.25         980.72         1,447,256         1,961           Main operation office         Nos.         1         9,903,373         5,371.21         9,903,373         5,371           Sub operation office         Nos.         1         926,244.79         1,104.60         926,245         1,105           Interchance BP&EP 1 lane         Nos.         1         6,530,915.78         13,539.28         6,530,916         13,539		WCBR2 Foundation	STA 12+720	Nos.	1	6,913,893	1,594.20	6,913,893	1,594	Schedule of rates17
ral(s)         VCBR4(Slab)_Foundation         STA25+650         Nos.         1         5.565,561         2,217.69         5,565,561         2,218           ral(s)         Toll barrier(BP&EP)         Nos.         2         723,628.25         980.72         1,447,256         1,791           Main operation office         Nos.         1         9,903,373         5,371.21         9,903,373         5,371           Sub operation office         Nos.         1         926,244.79         1,104.60         926,245         1,105           Interchance BP&EP Ilane         Nos.         1         6,530,915.78         13,539.28         6,530,916         13,539		W/CRR3/Glab) Foundation	STA 7+760	Nos.		1,236,342	646.56	1,236,342	647	
ral(5)     Toll barrier(BP&EP)     Nos.     2     723,628.25     980.72     1,447,256     1,7291       Main operation office     Nos.     1     9,903,373.22     5,371.21     9,903,373     5,371       Sub operation office     Nos.     1     926,244.79     1,104.60     926,245     1,105       Interchance BP&EP llane     Nos.     1     6,530,915.78     13,539.28     6,530,916     13,539		WCBR4(Slab) Foundation	STA25+650	Nos.	1	5,565,561	2,217.69	5,565,561	2,218	
rAL(5)         Toll barrier(BP&EP)         Nos.         2         723,628.25         980.72         1,447,256         1,7291           Main operation office         Nos.         1         9,903,373.22         5,371.21         9,903,373         5,371           Sub operation office         Nos.         1         926,244.79         1,104.60         926,245         1,105           Interchance BP&EP Ilane         Nos.         1         6,530,915.78         13,539.28         6,530,916         13,539										
rAL(5)         Toll barrier(BP&EP)         Nos.         2         723,628.25         980,72         1,447,256         1,961           Main operation office         Nos.         1         9,903,373.22         5,371.21         9,903,373         5,371           Sub operation office         Nos.         1         926,244.79         1,104.60         926,245         1,105           Interchange BP&EP Ilane         Nos.         1         6,530,915.78         13,539.28         6,530,916         13,539				,					t	
Toll barrier(BP&EP)   Nos.   2 723,628.25   980.72   1,447,256   1,551     Main operation office   Nos.   1 926,244.79   1,104.60   926,245   1,105     Interchance BP&EP Ilane   Nos.   1 6,530,915.78   13,539,28   6,530,916   13,539	SUB TOTAL(5)							72,466,852	17,291	20-11- 20 -1-12-20
Main operation office         Nos.         1         9,903,373,22         5,371,21         9,903,373         5,371           Sub operation office         Nos.         1         926,244,79         1,104.60         926,245         1,104           Interchance BP&EP Ilane         Nos.         1         6,530,915,78         13,539,28         6,530,916         13,539	4 Toll cate	Toll barrier(BP&EP)		Nos.	ત	723,628.25	980.72	1,447,750	1,361	Senedule of rates 24
Nos. 1 926,244.79 1,104.60 926,245 1,105 Nos. 1 6,530,915.78 13,539.28 6,530,916 13,539	o rot gare	Main operation office		Nos.	<b>.</b>	9,903,373.22	5,371,21	9,903,373	5,371	
Nos. 1 6,530,915.78 13,539.28 6,530,916 13,539		Sub operation office		Nos.	7	926,244.79	1,104.60	926,245	1,105	
		Interchance BP&EP liane		Nos.	<b></b> 4	6,530,915.78	13,539.28	6,530,916	13,539	

Table 20-19 Construction Cost of Gwalior Bypass (3/3)

	S. H. Hom	Unit	Ott.	Rate		Amount	١.	Remark
ווהיוו			·	Rs.	nS\$	Rs.	US\$	
	Interchange_BP&EP_2lane	Nos.	F-1	6,692,580.33	14,035.71	6,692,580	14,036	Schedule of rates29
(7) 1 4 1.0 1. 61.5						25,500,371	36,012	
	Service road	km W	24.87	1,693,464.20	2,394.68	42,116,455 42,116,455	59,556 59,556	Schedule of rates34
8 Drainage	Precast Cement Concrete Kerb	Ħ	19,600	136.59	0.18	2,677,203		Analysis of rates64
	Berm ditch	E	800	111.17	0.03	88,937	1 024	Analysis of rates65
	Side ditch Veritical drain	EE	32,270 15,110	103.80	0.10	1,568,358		Analysis of rates67
SUB TOTAL(8)						14,911,733	6,999	
9 Utility Diversion	Removing power line	E	1,590.00	1,597.53	1.25	2,540,076	1,988	Schedule of rates33
	Removing telepone line	E ,	1,590.00	1,500,000,00	2.00	1,500,000	0 0	Schedure of raicost
STIR TOTAL(9)	Kemoving H.L.	ì	3			6,596,052	3,975	
10 Road appurtenances	Road appurtenances	Ř	26.50	109,167.65	0.00	2,892,615	0	Schedule of rates35
SUB TOTAL(10)						2,892,615		
	Turfing slopes of new banks	m2 .	361,800	2.07	0.00	749,155	919	Analysis of rates68 Analysis of rates69
CTTR TOTAL (11)	Planting plants and shrubs	 ਪੋ	٦	040,000.00	3	1,589,155	616	
ditioation	Construction of check dams/retaining	1.5	-	500,000.00	00.00	200,000	0	
	walls/baffels etc.			· · · · · · · · · · · · · · · · · · ·		200,000	0	
SUB TOTAL(12)								
TOTAL OF DIRECT COST						746,209,882	1,356,213	