5. PHYSICAL CONDITIONS OF STUDY AREA AND ENGINEERING SURVEY

5.1 Physical Conditions of Study Area

(1) Topography

The topography is favorable throughout the entire Project Site. Flat land is spread out in the Red River delta with elevations at less than 10 m. The open area is mainly utilized for rice cultivation.

(2) Geology

Geologically, the flat terrain in Red River delta area is of alluvium or diluvium formation of Holocene or Pleistocene Ages, composed of alluvial or diluvial soils of gravel, sand, loam, silt and clay.

(3) Climate

Annual average rainfall in Hanoi is about 1,700 mm of which 80 - 85 % falls in the rainy season. The annual average number of rainy days is 140. Annual average temperature in Hanoi is 23.6 °C with its minimum of 4 °C and maximum 39.4 °C; mean humidity is 82 %.

5.2 Topographic Survey

Topographic survey was conducted for three (3) alternative routes comprising:

- Centerline/profile survey;
- Plane table survey;
- Cross section survey; and
- River Cross section survey

Upon completion of the topographic survey, the following was produced for preliminary design:

- i) 28 sheet of topographic maps to a scale of 1/2,000 which show all the salient features such as buildings, roads, power lines, rice paddy or irrigation canal dykes, fish ponds;
- ii) Centerline profiles to the scale of 1/1,000 horizontal and 1/200 vertical along the centerline of SHTRR including Thanh Tri Bridge;

- iii) Cross sections for each 50 m intervals along the routes with the scales of 1/1,000 horizontal and 1/200 vertical;
- iv) Ground elevations at boring locations; and
- v) Topographic survey report.

5.3 Hydrological Survey

Hydrological survey was conducted to identify the hydrological conditions of the Red River:

- i) Soundings for nine (9) cross sections of the Red River;
- ii) Flow velocity measurement at three (3) alternative routes; (measured velocities varied between 0.8 m/sec near river-bed and 1.5 m/sec near water surface at selected route); and
- iii) Analysis of hydrological data for the Red River in Hanoi area.

The following findings are obtained as a result of hydrological survey:

- The maximum design flood water level of the Red River at Thanh Tri Bridge site is elevation 12.5 m;
- The deepest river-bed to be encountered at the bridge pier locations will be at elevation -3.80, therefore, the deepest water depth at the flood stage around bridge piers is expected to be 16.3 m;
- The estimated local scouring depth around bridge piers is approximately 6.0 m.

5.4 Soil Investigations

(1) Purpose of the Investigations

The purpose of the investigations is to obtain data for the preliminary design of bridges, embankment and pavement.

(2) Field Work and Laboratory Testing

The field work and laboratory testing were conducted by a local consulting firm. The JICA Study Team planned and supervised investigations. Machine boring with standard penetration tests was conducted at 19 locations. Thin-wall tube sampling were also carried out for soft soils. Test pit sampling were made at possible sources of embankment materials, pavement materials and concrete aggregates. The laboratory testings were carried out for the collected samples.

(3) Bearing Strata of Foundation Piles

Standard penetration tests were performed for the entire 50 m depth of each boring hole at intervals of one (1) meter. Summary of bearing strata (N-value more than 50) for piled foundations are shown in Table 5.1.

Table 5.1 Summary of the Bearing Strata for Piled Foundations (N≥50)

Boring No.	Ground Surface Elevation (m)	Depth of Bearing Strata
1	6.975	38.5 m
2	4.058	37.5 m
3	4.036	47.5 m
4	9.100	38.0 m
5	-4.270	46.5 m
6	7.325	40.0 m
7	5.562	37.0 m
8	5.835	40.0 m
9	5.794	41.3 m
10	9.015	43.0 m
11 11	8.410	41.0 m
12	-2.900	37.5 m
13	9.607	44.0 m
14	5.795	32.0 m
15	4.679	40.0 m
16	3.717	39.0 m
17	5.436	43.5 m
18	7.431	47.0 m
19	5.396	43.5 m

(4) Borrow Materials

Many sand supplying companies are located along the shore of the Red River, where the sand is pumped from the river-bed. Table 5.2 shows the sources of embankment materials for the construction.

Table 5.2 Borrow Material Sources

	Sources				
Section	Place	River	Material		
Thanh Tri Section	Linh Nam	Red River	River Sand		
	Bai Bac	Red River	River Sand		
Gia Lam Section	Phu Dong	Duong River	River Sand		

(5) Source of Coarse Aggregates

The sources of Coarse Aggregates are shown in Table 5.3.

Table 5.3 Sources of Coarse Aggregates

Materials	Place	Rock	Los Angeles Abrasion
Coarse Aggregates	Mieu Mon Quarry in Ha Tay Province	Limestone	33 %
Coarse Aggregates	Kien Khe Quarry in Ha Nam Province	Limestone	31 %

Mieu Mon quarry and Kien Khe quarry are located about 50 km and 60 km in single trip distance from Thanh Tri area respectively.

(6) General Descriptions of Subbase and Base Coarse Materials

Subbase course materials from the Red River will require processing for gradation control, considering the nature of deposit.

A number of aggregate producers are in operation in the NH No. 1 corridor. Above mentioned Mieu Mon and Kien Khe quarries are presently producing crushed rock. The existing capacity of each quarry is 200 ton/hour and practically no limit in the limestone deposit.

(7) CBR Test Results of Base Course Materials and Embankment Materials

As the base course material, limestone from Mieu Mon, Kien Khe and Xom Van quarries were selected, and as the embankment material, the Red River sand was chosen. The test results were as shown in Table 5.4.

Table 5.4 CBR Test Results of Base Course and Embankment Materials

Source	Soil Type	CBR (Soaked)
Kien Khe	Kien Khe Limestone	
Mieu Mon	Limestone	74-98
Xom Van	Limestone	74-96
Bai Bac	Sand	14-19.5
Phu Dong	Sand	13.5-21
Linh Nam	Sand	11.5-18

(8) Slope Stability and Settlement of Embankment Foundation

As a result of slope stability and settlement analysis it was concluded that:

- The slope of the embankment must be 1 vertical to 1.5 horizontal (1:1.5 slope) or flatter and adoption of 1:2 is recommended; and
- Sand drain with pre-loading will be required in the limited stretch of SHTRR where subsoil conditions are adverse (N≤5) and embankment height becomes higher (i.e. at bridge approaches and culvert locations).

6. DESIGN STANDARDS

6.1 Geometric Design Standards

In determining the geometrical design standards for the project, the standards of the MOT are esteemed as a base while Japanese and AASHTO standards are referred to when necessary.

(1) Design Speed

Design speed is the maximum safe speed that can be maintained over a specified section of road when conditions are so favorable that design features of road govern.

A design speed of 100 km/hr. is applied to the throughway of the SHTRR. In case of the frontage road, 40 km/hr. design speed is adopted considering good accessibility to adjoining properties and mixed traffic of motorized and motorized and non-motorized vehicles.

(2) Lane Width of Throughway

The lane width of 3.75 m is adopted based on TCVN 5729-1997.

(3) Recommended Geometric Design Standard

Table 6.1 presents the summary of major recommended criteria for geometric design of the throughway of SHTRR and Thanh Tri Bridge (hereinafter referred to as the "Project Highway") based upon the comparison and deliberation of Vietnamese standard, AASHTO and Japanese standard due to the lack of design standard for urban freeway in Vietnam. The geometric design criteria for frontage road is to comply with TCVN 4054-85.

6.2 Pavement Design Standard

Flexible pavement has been adopted in the preliminary pavement design. The thickness design of the pavement are based on the "AASHTO Guide for Design of Pavement Structures (1972 and 1986)".

Table 6.1 Design Criteria for Throughway

ltems	Unit	Vietnamese Standard TCVN 5729-97	AASHTO	Japanese Standard	Recommended Standard
Class of Road		Freeway Class 100	Urban Freeway	Urban Road 2-1	Urban Freeway
Terrain		Flat	Flat	Flat	Flat
Elements of Design					
Design Vehicle		TTSC '0	TTSC '''	TTSC '''	TTSC "
Minimum No. of Lanes		4	4	4	4
Design Speed	km/h	100	96 (60 mph)	100	100
Stopping Sight Distance	m	160	160 (525 ft)	160	: 160
Minimum Horizontal Curve	m	450	437 (1,432 ft)	460	450
Maximum Grade	%	5 (4) *3)	3	3	4
Minimum Vertical Curve Sag	m	3,000	3,650 (120 ft)	3,000	3,000
Minimum Vertical Curve Crest	m	6,000	5,800 (190 ft)	6,500	6,000
Vertical Clearance	m	4.5	4.27 (14 ft)	4.5	4.5
Crossfall	%	2.0	2.5	2.0	2.0
Maximum Superelevation	%	7	8	8	7
Cross Section Elements		: .			
Lane Width	m	3.75	3.66 (12 ft)	3.50	3.75
Raised Median (2)	m	1.50		1.75	2.00
Inner Shoulder	ın	1.00	1.22 (4 ft)	0.50	1.00
Outer Shoulder	m	3.00	3.05 (10 ft)	1.25	3.00

Note:

6.3 Bridge Design Standard

(1) Design Loading

Basically Vietnamese Bridge Design Code (Specifications 22 TCN 018-79) follows AASHTO specifications. Due to the reasons explained below, AASHTO load HS 20-44 x 125 % is adopted for design load. This load is in response to Vietnam's standard H30. With the present and projected heavy truck ratio in mind, this is an appropriate design load for the Project Bridges.

(2) Flood Clearance

Article 1.27 of Vietnam Bridge Design Code 22 TCN 018-79 was followed to determine the clearance for the design of bridges in case the river is not utilized for navigation.

^{*1)} TTSC abbreviates Truck Tractor - Semitrailer Combination.

^{*2)} The width of raised median is subject to securing the space for pier of crossing grade separation structure.

Bridge and approaches.

(3) Navigation Clearances

Confirmed that the navigational clearance for the bridge should be 10 meters above high water level (HWL) and this should be maintained over a width of 80 meters in addition the value of the HWL should be the predicted level of the river for a return period of 20 years.

(4) Road and Railway Clearances

The clearances for the design of bridges crossing over any classes of roads were determined in accordance with the Design Criteria of Highway TCVN-4054-85.

The clearances for the design of bridges crossing over 1 meter gauge railways are as follows:

Overall width :

B = 4.00 m

Overall height:

H = 5.30 m

7. FORMATION OF ALTERNATIVE PLANS

7.1 Study of Alternative Routes

(1) Project Site

The Southern section of Hanoi Third Road (SHTRR) is located in Thanh Tri and Gia Lam districts, crossing the Red River 6.5 km downstream of Chuong Duong Bridge and 3.5 km downstream of Pha Den (Hanoi) port.

The beginning point of the SHTRR is located at Phap Van on National Highway No. 1 and the ending point is at Sai Dong on National Highway No. 5.

(2) Alternative Routes

Three alternatives were selected for further comparison, namely Alternatives 1, 2b and 3 (Figure 7.1):

Alternative-1 : Shorter Bridge Length Scheme

Alternative-2b : Least-Affected Inhabitant Scheme

Alternative-3 : Least Land Acquisition Effort Scheme

(3) Description of Alternative Route

A route location of the SHTRR has already been proposed in the pre-feasibility study conducted by TEDI. Referring to TEDI's route and aerial photographs taken in 1993, the following three schemes were established in the Study (Figure 7.1).

Alternative-1: Shorter Bridge Length Scheme

Assuming the length of Thanh Tri Bridge is identical with the distance between dykes, the shortest crossing point of the Red River is selected at the north of TEDI's proposed route (1,860 m in length compared with 2,340 m of the TEDI's route). Also, the length of SHTRR will be the shortest among alternatives, namely approximately 700 m shorter than Alternative-3.

Alternative-2b: Least Affected Inhabitant Scheme

The SHTRR assumes to cross the Red River at the proposed point of the TEDI's route and passes undeveloped area with minimum number of affected inhabitants.



Alternative-3: Least Land Acquisition Effort Scheme

The SHTRR assumes to cross the Red River at the proposed point of the TEDI's route and make full use of existing road right-of-ways to minimize additional land acquisition effort.

(4) Traffic Capacity and Required Number of Lanes

To determine the magnitude of the construction effort, required number of traffic lanes was analysed based on future traffic characteristics.

(5) Further Studies

Further studies were conducted to provide the data for optimum route selection, concerning:

- Interchanges;
- Locations of New Highway No. 1 interchange and toll barrier gate; and
- Traffic maneuvering plan in Thanh Tri and Gia Lam area.

7.2 Study of Bridges and Other Structures

(1) General

Study was carried out for all alternative routes and broadly covered the following bridges and structures:

- River crossing bridges (Thanh Tri Bridge);
- Interchange structures;
- Flyovers; and
- Drainage structures and other bridges.

1) Thanh Tri Bridge

Than Tri Bridge consists of main bridge, dyke bridge and approach bridges.

2) Interchange Structures

The requirements for three interchanges have been identified, namely;

- At the intersection of the existing National Highway NH-1;
- At the intersection of the new National Highway NH-1; and
- At the intersection of the existing National Highway NH-5.

3) Flyovers

The alignment traverses a number of local roads and public footpaths and flyovers were planned to allow the public to traverse the highway in a safe manner.

4) Drainage Structures and other Bridges

The Site requires drainage structures which cross SHTRR, in particular, there are proposals for the location of a flood relief reservoir in Thanh Tri district. The Study Team envisaged that the proposed structures would be either a single or multi cell reinforced concrete box culverts or short span bridges.

(2) Initial Study of the Main Bridge of Thanh Tri Bridge

Through the initial study of a number of bridge types, the Study Team narrowed down the alternatives to the following short-listed bridge types for the main bridge:

- Alternative 1 : PC continuous Box Girder Bridge

- Alternative 2 : PC Extradosed Bridge

Alternative 3 : PC/Steel Cable Stayed Bridge

The above three alternatives were carried forward to the next step of detailed comparison to be made based on the results of comparative design as well as economic study if required.

(3) Study of Thanh Tri Bridge, Route Alternative 2b/3

From the alignment survey the total distance between dyke embankment is approximately 2.03 km with the normal water course situated closer to the mid-point of this distance. The width of the normal water course is approximately 633 meters.

The height of the dyke embankments are:

Hanoi side : 14.03 meters Gia Lam side : 13.30 meters

1) Main Bridge

Following bridge types are set out and initial design was made:

Bridge Type

Middle Span Length

- Continuous PC Box Girder Bridge

130 m and 150 m

- PC Extradosed Bridge

180 m

- PC/Steel Cable Stayed Bridge

260 m

2) Approach Bridges

The Study Team considered following three options:

- Extend the structural form of the main bridge;

- Use of simple supported or continuous precast post-tensioned concrete

beams with a span of 30 - 50 meters; and

Use of precast post-tensioned concrete beams with an in-situ deck

section over the pier to form a continuous deck.

3) Dyke Bridges

The alignment across the Hanoi dyke at a skew of approximately 50° and requires a bridge to span a distance of approximately 130 meters, along the line of the alignment. The Study Team has adopted a span over the dyke of 130 meters with side spans of 90 meters.

The Gia Lam dyke spans a distance of approximately 90 meters, along the line of the alignment, between existing ground levels. The span of the bridge over the dyke is 105 meters with side spans of 70 meters.

For both of these locations the Study Team considered that the bridge type should be a prestressed concrete box girder constructed using temporary formwork to support the deck during construction.

(4) Study of Thanh Tri Bridge, Route Alternative-1

From the alignment survey the total distance between dyke embankments is measured at approximately 1.96 km with the normal water course situated close to the Hanoi dyke. The width of the normal water course is approximately 510 meters.

The height of the dyke embankments are:

Hanoi side

14.45 meters

Gia Lam side

13.50 meters

1) Main Bridge

Refer to paragraph 7.2. (3). 1).

2) Approach Bridges

Refer to paragraph 7.2. (3). 2).

3) Dyke Bridges

The Hanoi dyke is situated close to the normal water course and so has been incorporated into the main river crossing.

The Gia Lam dyke spans a distance of approximately 65 meters, along the line of the proposed alignment, between existing ground levels. The span of the bridge over the dyke is 65 meters with side spans of 45 meters. For this span arrangement the Study Team proposed to form the deck from a continuous prestressed concrete box girder constructed using temporary formwork to support the deck during construction.

8. SELECTION OF THE OPTIMUM ALTERNATIVE ROUTE

8.1 Selection Approach

The main focus of evaluation at this step is to select an optimum route among three route alternatives, the study flow is shown in Figure 8.1.

8.2 Selection of the Optimum Route

(1) General

Formation of a consensus amongst the Government agencies concerned the development policies of the SHTRR, in particular, to fix an optimum route prior to the start of preliminary engineering design, is indispensable.

(2) Evaluation of Route Alternatives

For the purpose of comparison of each alternative, the following criteria were taken into account:

- Land Availability
- Impact on the Social Environment
- Construction Economy
- Road user Benefits
- River Morphology

The comprehensive comparison and evaluation of each alternative are summarized in Table 8.1.

(3) Conclusion

It was concluded that Route Alternative-3 is recommended for the optimum route assuming that the SHTRR on the existing road at Yen So in Thanh Tri district will be constructed providing frontage roads.

Comparison of bridge types of Thanh Tri main bridge (PC continuous box girder bridge vs PC cable stayed bridge) is necessary evaluating the entire Project schemes.




Figure 8.1 Study Flow for Selection of Optimum Route


Comparison of Route Alternatives Table 8.1

tems	All-1:Shorter Bridge Length Scheme	ALT-Zb:Least Affected Inhabitant Scheme	ALI-3:Least Land Acquisition Scheme
Major Indices	TA 3 1 1	12.05 Km	19.3 Km
עסמוני ריפוולים	I I.O NT	12,00 Mil	12.5 Mil
Thanh In Bridge Length	1,860 m	2,340 m	2,340 m
Construction Cost Indices	0.95	1.01	1,00
Land Acqueition & Compensation			
Acquired Land Area	68.3 ha	70.7 ha	61.7 ha
Affected Houses	315	225	422
Affected Inhabitants	1,400	1,000	1.900
Evaluation			
Social Environment			
Land Availability	It is necessary to acquire 3.6 ha inhabited lands along NH-1, NH-5 and both dyle roads, and a pottery factory and a warehouse at Nam Du Ha will be affected. However, no protected or environmentally sensitive area is found because the route passes onen spaces such as	It is necessary to acquire 3.0 ha inhabited lands along NH-1, NH-5, and a cement warehouse of Chinfon factory at Linh Nam will be affected. However, no protected or environmentally sensitive area is found because the route nesses once scares such as anond	It is necessary to acquire 9.6 ha inhabited lands along NH-1, NH-5 and 4 km long existing road at Yen So in Thanh Tri. However, since wide open space behind the existing road is available for relocation of affected inhabitants. 76 ha land acquiring riself has no difficults.
	O pond, arable land and undeveloped area.	O arable land and undeveloped area. The route will manage to pass beside the Hero's cemetery of Linh Nam commune just in case of required ROW of 50 m wide.	A cement warehouse of Chinfon factory at Linh Nam will be affected, but the route in the remaining section passes open spaces such as pond, arable land and
			undeveloped area.
impact on Social Environment	Since the route passes beside cemetery at Phap Van and Yen Duyen in Thanh Tri, some practical	Since the route passes beside cemetery at Phap Van and Yen Duyen in Thanh Tri, some practical	Since the route passes build-up area at Yen So and Pagoda at Xa Tran Phu in Thanh Tri, some practical
	△ countermeasures against community severance are	O countermeasures against community severance are	O countermeasures against community severance are
	deemed necessary. Several tombs are required to be	deemed necessary.	deemed necessary.
	230 of 315 affected houses and several tombs are	Do do ZZJ affected houses are deemed hecessary to be relocated elsewhere.	102 of 422 affected houses are deemed necessary to be relocated elsewhere.
	deemed necessary to be relocated elsewhere.		
Technical Feasibility			
Construction Economy	The length of route is the shortest, and Thanh Tri bridge becomes shorter as well. However the route	The route passes several water reservoirs and ponds where soft soil treatment is required 1.25 km farther	Although the route is the longest and has longer Thanh Tri bridge length than Al T-1 relative cost on
	passes many water reservoirs and ponds where soft soil	New NH-1 IC from ALT-3 and longer Thanh Tri bridge	comparison basis is the same level of ALT~2b because
	O INH-1 IC is located 1.25 km north from ALT-3 to increase relative cost on comparison basis.	△ basis. Construction cost is higher and higher maintenance	Oppores where soft soil treatment is required.
	Construction cost is lower but higher maintenance cost and longer construction period are expected.	cost and longer construction period are expected.	period are expected.
Road User's Benefits	The shorter scheme has advantages of considerable travel time and vehicle operating cost savings.	Sharper horizontal curve less 500m which has significant higher rate of traffic accident will be applied	The longer route has disadvantages of travel time and A vehicle operating cost for through-travelling users who
ä		to avoid violation of inhabited area.	will occupy half of total users in 2010.
River Morphology	Surveyed river cross sections imply slight presence of Δ inbalanced scouring force at river bed rather than $A_{\rm L}T$ -2b and 3.	Surveyed river cross sections ascertain balanced O scouring force at both sides of river bed.	Surveyed river cross sections ascertain balanced counting force at both sides of river bed.
Planning Consistency	The route should coordinate with the Hanoi Master Plan	The route should coordinate with the Hanoi Master Plan	This alternative has the same route as the city planning
	△ to find a way how to cross their Yen So regulating reservoirs planned in Thanh Tri area.	△ to find a way how to cross their Yen So regulating reservoirs planned in Thanh Tri area.	O road shown in the Hanoi Master Plan.
Comprehensive Evaluation		-	
	nus screme has advantages in the aspects of construction cost and road user's benefits. However, it	Into scheme is superior in the aspect of social environment, especially smaller number of affected	it apparently is bigger number of affected persons, but most of them are along existing road at Yen So, and
	is inferior in the aspects of stability of river morphology,	persons. However, it is inferior to horizontal alignment,	© they are easily set back in the same way as NH-5
	for relocation of inhabitants and tombs.	construction economy and planning consistency.	widefing. However, it has advantages of stability of fiver morphology, construction economy and planning
			consistency.

Notes:

O Fair or Superior

A Poor or Inferior



9. BRIDGE ALTERNATIVE STUDY AND SELECTION OF THE RECOMMENDED BRIDGE TYPE FOR THANH TRI BRIDGE

9.1 General

Alternative Study of Thanh Tri Bridge and selection of the optimum bridge type were carried out on the selected route of Alternative 3 (refer to 7.1 Study of Alternative Routes). The concept of various alternatives of Thanh Tri Bridge is shown in Figure 9.1.

9.2 Alternative Bridge Types of Main Bridge

(1) Alternative 1: PC Continuous Box Girder Bridge

1) Super Structure

The most economical center span length of 130 m was chosen and the span arrangement of 80 m + 4 @ 130 m + 80 m = 680 m adopted.

2) Piers

From the requirement of high degrees of rigidity (i.e. water depth, seismic coefficient and boat collision force) Hanoi bound and Gia Lam bound bridge deck supports (piers and foundations) were combined.

3) Foundation

Caissons and various design of foundation piling (i.e. steel pipe piles and cast-in-concrete piles) were compared and 2,000 mm diameter cast-in-situ concrete pipe piling was adopted.

(2) Alternative 2 : PC Extradosed Bridge

Increasing the span of Bridge Alternative 1 to a span of 180 m (i.e. economic span) will necessitate a concrete box girder of 10.5 m in depth at piers. This depth of construction may cause construction difficulties in Vietnam and the Study Team proposed to use a hybrid concrete box girder (known as 'extradose' in Japan). This bridge type incorporates low level cable stays to increase the effective girder section at the piers. The adopted span arrangement is 100 m + 3 @ 180 m + 100 m = 740 m, with concrete towers of 20.0 m above the deck.

Jyke Bridge Approach Bridge Approach Bridge (1) Main Bridge ALTERNATIVE 1: PC Continuous Box Girder Bridge Approach Bridge (1) Approach Bridge Dyke Bridge Approach Bridge (2)

Dyke Bridge Approach Bridge Approach Bridge (1) Main Bridge Approach Bridge (1) Approach Bridge Dyke Bridge Approach Bridge (2)

Approach Bridge (2) Dyke Bridge Approach Bridge Approach Bridge (1) Main Bridge Approach Bridge (1) Approach Bridge Dyke Bridge Approach Bridge (2)

Figure 9.1 Concept of Alternatives of Thanh Tri Bridge

ALTERNATIVE 2: PC Extradosed Bridge

ALTERNATIVE 3: PC Cable Stayed Bridge

(3) Alternative 3: PC Cable Stayed Bridge

1) Superstructure / Towers

The Study Team selected the most economical span arrangement of 130 m + 260 m + 130 m = 520 m. The height of tower is approximately 91 meters above sea level. the height of the towers are within the limits defined by the Vietnam Aviation Department.

2) Piers / Foundation

Refer to 9.2 (1) in above.

9.3 Determination of Bridge Types of Approach and Dyke Bridges

(1) Approach Bridges

The approach bridges have been grouped into the following types.

- Approach Bridge (1): the bridge between the main river bridge and the dyke bridge;
- Approach Bridge (2): the bridge between the dyke bridge and abutment.

1) Approach Bridge (1)

For the determination of the economical span arrangement, the comparison study was carried out and found that 50 m span continuous design is the most suitable. The shape of piers are similar to the main bridge, however Hanoi bound and Gia Lam bound are separated. Cast-in-situ concrete piling (D = 1,500 mm) has been adopted.

2) Approach Bridge (2)

The use of a precast beams, either simple supported or made continuous for the live load condition, with a span of 30 m was determined. The piers are with oblong shaped columns and other designs are similar to Approach Bridge (2).

3) Dyke Bridges

The span arrangement of dyke bridges are as follows:

Hanoi side : 75 m + 130 m + 75 m = 280 m; and

Gia Lam side : 50 m + 80 m + 50 m = 180 m.

However, further study is required based on the topographical survey results to be conducted in the detailed design. Piers/foundations are similar to Approach Bridge (1).

9.4 Screening of Alternative Bridge Types of Main Bridge

(1) Alternatives

The technical study and preliminary cost estimation were conducted on the following bridge alternatives.

Main Bridge; Alternative 1: 4 span PC Continuous Box Girder Bridge,

center spans = 130 m

Alternative 2: 3 span PC Extradosed Bridge,

center spans = 180 m

Alternative 3 : PC Cable Stayed Bridge, central span = 260 m

Adopted designs for approach bridge and dyke bridges are identical for all alternatives:

Approach Bridge (1); PC Simple or Continuous Box Girder Bridge, span 50 m

Approach Bridge (2); PC T-Beam Bridge, span 30 m

Dyke Bridge; Hanoi Side; 3 span PC Continuous Girder Bridge

span 75 m + 130 m + 75 m = 280 m

Gia Lam side; 3 span PC Continuous Girder Bridge

span 50 m + 80 m + 50 m = 180 m

(2) Elimination of Alternative 2

It is noted that Alternative 2: PC Extradosed Bridge has been eliminated from the available options in accordance with the decision of the Government's Steering Committee.

9.5 Evaluation of PC Box Girder Bridge and Cable Stayed Bridge Project Schemes based on Economic Study

The study of bridge types of Thanh Tri main bridge, PC continuous box girder bridge and PC cable stayed bridge, has been conducted based on full scale economic analysis. The study results are shown in Table 9.1.

Table 9.1 Summary of Economic Analysis

Unit of Cost: million Dong

	Description	Box Girder Main Bridge Scheme	Cable Stayed Main Bridge Scheme
(1)	Construction Cost of Highway and Interchanges 1)	1,390,860	1,390,860
(2)	Construction Cost of Thanh Tri Bridge 2)	2,660,900	3,251,600
(3)	Land Acquisition and Resettlement	129,654	129,654
(4)	Engineering and Supervision (7 %)	283,623	324,972
Tota	! Financial Cost	4,465,037	5,097,086
Tota	I Economic Cost	3,984,452	4,546,512
Ecor	nomic Internal Rate of Return	12.55 %	11.34 %
	efit Cost Ratio counted at 12 % per year)	1.06	0.93

Notes:

- 1) Packages 2 and 3
- 2) Package 1
- 3) All costs include 10 % of physical contingency

The result of the economic analysis revealed that: the Project with box girder main bridge design is judged to be feasible, showing 12.55 % of internal rate of return which is higher than the opportunity cost of capital in Vietnam.

9.6 Comparison of Short-Listed Bridge Types (PC Continuous Box Girder Bridge and PC Cable Stayed Bridge)

(1) Bridge Type Selection Method and Scoring System

Bridge type selection method followed Japanese government standard. The scoring (weighting) system is shown in Table 9.2.

 Table 9.2
 Scoring System in Comparison Component Evaluation

	Component of Evaluation	Scoring			
		Japanese Standard	Adopted Full Score		
1.	Construction Cost	40 – 50	50		
2.	Structural Characteristics	5 – 15	10		
3.	Constructability	5 – 15	15		
4.	Aesthetics	5 – 15	15		
5.	Maintenance	5 – 15	10		
	Total	_	100		

(2) Scoring Method

1) Construction Cost

Superior alternative: Give full score

Inferior alternative: full score - Construction Cost of Inferior Alternative

Construction Cost of Superior Alternative 1 x 50

2) Other Components

Good:

give full score

Fair:

50 % of full score

Poor:

put 0

(3) Evaluation Result

The summary of evaluation result of comparison component is shown in Table 9.3.

Table 9.3 Summary of Evaluation Result

		Gained Score				
Component of Evaluation		Alternative PC Continuous Girder Bridg	Box	Alternative 3 PC Cable Stayed Bridge		
1.	Construction Cost	US\$ 60 million	50	US\$ 102 million	15	
2.	Structural Characteristics	Good	10	Fair	5	
3.	Constructability	Good	15	Good	15	
4.	Aesthetics	Fair	8	Good	15	
5.	Maintenance	Good	10	Good	10	
	Total Score	93		60		
	Recommended Priority	1		2	100	

10. PRELIMINARY ENGINEERING DESIGN OF HIGHWAY

10.1 Design Policies

Basic design policies to be applied to the SHTRR were established after detailed study of surrounding conditions. Horizontal and vertical alignment designs were achieved by carrying out integral studies on geometric, structural, hydrological/drainage and geological aspects and by maintaining close contact and cooperation with the concerned people's committees and other authorities.

The outline of design policies and controls for the determination of horizontal and vertical alignment are described as follows:

- Safe and efficient movement of high volumes of traffic at the specified design speed (i.e., 100 km/hr) shall be attained by the provision of good roadway alignment;
- Where vertical and horizontal curves occur in combination or in close proximity to each other, consideration should be given to designing a flowing alignment by providing good coordination of these curves;
- Severance of local communities shall be avoided by the provision of flyovers and box culvert;
- Existing pump station, schools, monument, pagoda, church, cemetery and densely inhabited areas shall be avoided;
- Countermeasures shall be provided to maintain the functions of the existing roads, railways, waterways and irrigation channels which will be crossed by the SHTRR; and
- The embankment height shall be kept as low as possible to reduce foundation treatment effort as well as to shorten the construction period.

10.2 Traffic Capacity and Required Number of Lanes

(1) Methodology

The concept and methodology used for the highway capacity analysis were based on the "Highway Capacity Manual of Highway Research Board, U. S. A.". However, some adjustment was made to reflect local conditions based on the results of studies undertaken by the "Highway Research Board, Japan (Japanese Standard)", since much resemblance is found in type and size of vehicles and in operating conditions, in Vietnam and Japan.

(2) Summary of Traffic Capacity Analysis

Table 10.1 shows summary of traffic capacity analysis with brief notes in each calculation steps.

Table 10.1 Summary of Capacity Analysis

	*				
	Description	Symbol	Unit	Adopted	Remarks
Highway Type		-	-	-	Urban Expressway
Landuse/Terrain		-		Urban/Flat	See Note below
Design Speed			km/hr	100	
Lane Wid	lth	_	m	3.75	
Lateral	Outer		m	3.00	
Clearance	Inner	-	m	1.00	
Basic Cap	pacity	Св	PCU/hr/lane	2,200	Multilane highway
	Lane Width	γL	-	1.00	
	Lateral Clearance	γс		1.00	
Adjust- ment	Roadside Development	γι	-	1.00	
Factors	Large Vehicles	γг	-	1.00	Trucks and buses
	Driver Population	γD		1.00	
	Planning Level-2	γР	- · · · · · · · · · · · · · · · · · · ·	0.85	0.90 in urban region (Japanese Standard)
Possible (Capacity	CL	PCU/hr/lane	2,200	$CL = CB \bullet \gamma L \bullet \gamma C \bullet \gamma I \bullet \gamma T \bullet \gamma D$
Design C	apacity per Hour	: Co	PCU/hr/lane	1,870	CD = CL • YP
K-Factor		K	%	9	Highway Capacity Manual
D-Factor		D	%	55	Highway Capacity Manual
Design A	verage Annual Daily	DAADT	PCU/day/lane	18,900	Design AADT
Traffic V	olume				= CD • <u>5.000</u> K • D

(3) Conclusions

1) SHTRR

The number of lanes of the through traveled way is recommended to be a total of 4-lane for the both of Thanh Tri and Gia Lam sections of SHTRR (i.e., Total Capacity of 4-Lane Through Traveled Way = $18,900 \times 4 = 75,600 \text{ PCU/day}$). The capacity contains certain allowance compared with the maximum daily traffic volume in 2010 (73,200 PCU/day).

2) Thanh Tri Bridge

The number of lanes of the through traveled way is recommended to be basically a total of six (6) lanes (motorcycle lanes separated in initial stage) for Thanh Tri Bridge (i.e., Total Capacity of 6-Lane Bridge = $18,900 \times 6 = 113,400 \text{ PCU/day}$). The capacity has slight allowance even if compared with daily traffic volume in $2020 \times (111,700 \text{ PCU/day})$.

10.3 Cross Section Design

Elements of recommended typical cross sections of the SHTRR are noted below:

Number of through traveled way lanes : 4-lane
 Lane width : 3.75 m

- Widths of shoulders : 3.0 m for outer and 1.0 m for inner

- Median : 2.0 m raised median width

- Side slopes : 1 on 2

- Frontage road : 2-lane, 8 m total width

- Bicycle path width : 3.0 m - Sidewalk width : 3.0 m

Right-of-way widths of SHTRR are as follows:

- 50 m for the section of through traveled way with buffer zones;
- 60 m for the section of through traveled way with frontage road and border on one side; and
- 70 m for the section of through traveled way with frontage road and border on both sides.

The Project covers not only the construction of through traveled ways of SHTRR but also the new construction of frontage road and borders. These are provided on one side or both sides of the through traveled ways in the selected SHTRR stretches. Table 10.2 shows the summary of cross section design of SHTRR.

Table 10.2 Summary of Cross Section Design of SHTRR

Station	Location	North side Frontage Road and Border (m)	Through Travelled Way Width (m)	South side Frontage Road and Border (m)	Typical Cross Section
1+000	NH No.1				
		14	2 x 11.5	14	Type D
4 + 500	Local Road Crossing				
		14	2 x 11.5	-	Туре С
5 + 500	Local Road Crossing	·			
		14	2 x 11.5	14	Type D
6+000	Local Road Crossing				
		14	2 x 11.5	-	Туре С
7 + 100	End of Thanh Tri Bridge	e e			
	J. A	, i	2 x 15.0	14 to 1	Type A
10 + 200	End of Thanh Tri Bridge				
		14	2 x 11.5	<u>-</u>	Туре С
11 + 450	Local Road Crossing				
13 + 100	NH No.5	-	2 x 11.5	-	Type B

10.4 Interchanges

Figure 10.1 shows the location of interchanges on the SHTRR. Half cloverleaf type NH-1 IC was planned in the vicinity of Linh Dam lake to connect with National Highway No. 1.

Y-type interchange was planned at the NH-1 IC located 3 km east of existing NH-1 IC, which connects new NH-1 and SHTRR.

At the intersections of the SHTRR with the dyke roads it was proposed that half diamond interchanges be constructed to allow access to and from Thanh Tri Bridge.

Half cloverleaf type NH-5 IC was planned at the terminal point of the SHTRR to connect with National Highway No. 5.




Figure 10.1 Location of Interchanges on the SHTRR

10.5 Summary of Geometric Design

The recommended design speed, typical cross sections and number of lanes for each package are shown in Table 10.3 and Figure 10.2.

Table 10.3 Design Speed, Number of Lane and Typical Cross Sections

	Package	Length (km)	Design Speed	Number of Lanes	Typical Cross Section
Package 1:	Thanh Tri Bridge	3.1	100 km/hr.	6	Type A
Package 2:	Thanh Tri Section of SHTRR	6.1	100 km/hr.	4	Type C or D
Package 3:	Gia Lam Section of SHTRR	3.2	100 km/hr.	4	Type B or C

10.6 Pavement Design

(1) Design Conditions

"AASHTO Guide for Design of Pavement Structures (1972 and 1986)" was used to determine the thickness of the pavement layers. The design condition is presented as follows:

Pavement type

Flexible design

- Design life

10 years

- Serviceability loss

2.5


Subgrade strength

CBR = 6

(2) Adopted Design Thickness


Pavement Component	Thickness (cm)	
AC Surface	5	
AC Binder	5	
ATB	an en 1 à au 10 a con 13	
Stabilized Aggregate Base	15	
Subbase	35	
Total	70	






Motor Cycle Separation Scheme

Type B




Through Traveled Ways with Buffer Zone





Through Traveled Ways with Frontage Road and Buffer Zone





Through Traveled Ways with Frontage Road on Both Sides

Figure 10.2 Typical Cross Sections

11. PRELIMINARY ENGINEERING DESIGN OF BRIDGES

11.1 Bridge Categories

The preliminary engineering design for the bridge structures has been divided into the following bridge categories:

- River Crossing (Thanh Tri Bridge);
- Interchange Structure;
- Flyover; and
- Drainage.

11.2 Thanh Tri Bridge

Thanh Tri Bridge is basically a river crossing bridge and was separated into:

- Main bridge which crosses water course of the Red River;
- Dyke bridge; and
- Approach bridges provided for both main and dyke bridges.

A continuous prestressed concrete box girder scheme was adopted for the main bridge. The design features of proposed bridges are shown in Table 11.1.

Table 11.1 Design Features of Thanh Tri Bridge

Category	Bridge Type	Span Arrangement/
		Bridge Length (m)
Main Bridge	Continuous PC Box Girder	80+4@130+80 = 680
Approach Bridge (1) Thanh Tri Side Gia Lam Side	Continuous PC Box Girder Continuous PC Box Girder	Bridge Length = 620 Bridge Length = 780
Dyke Bridge Thanh Tri Side Gia Lam Side	Continuous PC Box Girder Continuous PC Box Girder	75+130+75 = 280 50+80+50 = 180
Approach Bridge (2) Thanh Tri Side Gia Lam Side	PC I or T-Girder	Bridge Length = 270 Bridge Length = 300

(1) Main Bridge

The span arrangement of the main bridge is 80+4x130+80, an overall length of 680 meters, which gives sufficient clearance for the navigational requirements. To ease construction the design separates the cross section to form two individual and unconnected box sections, one for each carriageway.

The pier type for the Main Bridge was determined considering following matters:

- Piers are constructed in the normal water course of the river and the maximum depth of stream water will be up to 13 m in rainy season;
- Superstructure consists of PC continuous box girder (80m+4x130m+80m). This is a large superstructure which will result in big reactions. It is required for piers to have high rigidity and for the dimension of footing to be large. Therefore, the type of piers will be a combined structure supporting both for Hanoi- and Gia Lam-bound carriageways;
- Due to 32.8 m bridge width, the piers will require crosshead to support the bearings;
- The construction of piers in the river will disturb the water flow and will cause eddies on the down stream side and consequentially scour action will occur. To minimize scour action, the pier columns will be elliptical in shape;
- Ship/barge collision is on the design force of 125 tonnes. The protection system will be considered in the detailed design.

According to the soil investigation of Thanh Tri bridge area, the bearing stratum for foundation (N-value>50) appears on the elevation from -33 m to -43 m. Pile lengths shall be approximately L=32-35 m for the Main Bridge. Cast-in-situ concrete pile $\phi 2000$ is selected as the most suitable foundation type.

(2) Approach Bridge (1)

Superstructure consists of PC continuous box girder (span 50 m). Comparing with Main Bridge the reactions are not as large so the scale of piers is not necessary to possess the high rigidity. Therefore, the substructure of Hanoi- and Gia Lam-bound carriageway shall be separated from the aesthetic viewpoint.

Piers near the normal water course of the Red River are submerged in the rainy season. The type of piers shall be elliptical in shape taking into consideration the main bridge pier type to allow compatibility from an aesthetic viewpoint.

Selection of foundation type was investigated as same procedure as main bridge, finally the cast-in-situ concrete pile \$\phi1500\$ was selected both for Approach Bridges (1) and (2).

(3) Dyke Bridges

The span arrangements of dyke bridges are as follows in the preliminary design stage.

Thanh Tri side 75 m + 130 m + 75 m = 280 m

Gia Lam side 50 m + 80 m + 50 m = 180 m

However, further study is required based on the survey results that will be conducted in the detailed design stage.

Pier types were determined referring to the results of the main bridge study. Cast-in-situ concrete pile, φ1500 was selected according to the same reason of approach bridges.

(4) Approach Bridge (2)

Superstructure consists of PC simple girder bridge (span = 30 m). The reactions from superstructure are further reduced than Approach Bridge (1). Similar piers to those of Approach Bridge (1) were adopted.

Referring to the results of slope and ground stability analysis, the critical height of embankment is more than 10 m; however, it seems that the high embankment is not practical in the urban area, so the critical embankment height is within 6 - 7 m at abutments. The reversed T-type abutment was adopted in the design.

11.3 Flyover and Waterway Bridges

The cross section of the main carriageway bridge is shown in Figure 11.1 and the Study Team adopted precast beams to allow for future widening if required. For the type of piers, abutment and foundation refer to Approach Bridge-2.




Figure 11.1 Typical Cross Section for Flyover and Waterway Bridges

11.4 Interchange Ramp Bridges

The horizontal curvature of the ramps (slip roads) requires a cross section to be able to resist both flexion and torsional moments. The optimum cross section will be either a steel or concrete box girder. However, the decision for the material choice will depend on the time of construction. A concrete solution would be the most economical, should the ramps be constructed at the same as SHTRR, where as a steel solution would result in less disruption if ramps be built in a later period. Concrete designs were adopted in the design.

12. CONSTRUCTION PLANNING

12.1 Construction Package and Scope

To consider a large scale construction, the entire construction is divided into 3 packages, they are:

Package 1: Thanh Tri Bridge;

Package 2: Thanh Tri Section of Southern Hanoi Third Ring Road; and

Package 3: Gia Lam Section of Southern Hanoi Third Ring Road.

(1) Package 1

Package 1 is the construction of 2 x 15 m effective width Thanh Tri bridge and comprises:

- Main bridge;
- Dyke bridge; and
- Approach bridges provided for both main and dyke bridges.

(2) Package 2

Main construction works in Package 2 is the construction of:

- Four lane throughways, frontage roads and border facilities;
- One partial cloverleaf type interchange to connect Southern Hanoi Ring Road (SHTRR) and National Highway No. 1 including flyover bridge;
- One Y-type interchange to connect SHTRR and New National Highway No. 1 including ramp bridges;
- One half-diamond type interchange to connect Thanh Tri bridge and dyke road; and
- Three prestressed concrete girder throughway bridges.

(3) Package 3

Main construction works in Package 3 is the construction of:

- Four lane throughways, frontage roads and border facilities;
- One partial cloverleaf type interchange to connect SHTRR and National Highway No. 5 including flyover bridge;

- One half-diamond type interchange to connect Thanh Tri bridge and dyke road;
- One barrier type toll plaza; and
- One prestressed concrete girder throughway bridges.

12.2 Hauling of Construction Materials

The construction involves the hauling of a large quantity of embankment, paving and concrete work materials. Basically the project area is provided with a sufficient road and inland water transport network. However, the pavement conditions of the existing local roads sometimes lack strength. Pavement strengthening/repair will be necessary but construction of new roads is unlikely.

In the roadway construction of Thanh Tri and Gia Lam sections, the construction should be executed in sequence in order to use the newly constructed road as a pilot so that it may be utilised in transportation of materials effectively. Existing dyke roads and local roads will be utilised systematically in order to expedite the construction work.

12.3 Source of Materials

(1) Borrow Materials for Embankment Construction

Table 5.2 in Section 5 shows the sources of embankment materials for the construction. The hauling distance (single trip) is generally less than 10 km at present however this distance may be increased in future due to the restriction of river sand exploitation since a large scale constructions such as NH No. 1 improvement will start shortly.

(2) Sources of Coarse Aggregates

The sources of Coarse Aggregates are shown in Table 5.3 in Section 5.

(3) Subbase and Base Coarse Materials

Subbase course materials from the existing rivers will require processing for gradation control, considering the nature of deposit.

A number of aggregate producers are in operation in the NH No. 1 corridor. Above mentioned Mieu Mon and Kien Khe quarries are presently producing crushed rock. The existing capacity of each quarry is 200 ton/hour and practically no limit in the limestone deposit.

(4) Asphaltic Concrete Mixtures

Producement of hot-mix asphaltic concrete is possible for the construction of asphalt treated base course and binder/surface course.

12.4 Construction Method of Thanh Tri Bridge

(1) Main Bridge

Cofferdams with steel sheet/pipe piling in the water will be required for the substructure construction. Cast-in-place concrete piling will be done using a reverse-circulation-drill method. The adoption of cantilever erection is required for the construction of continuous PC box girders.

(2) Dyke Bridges

Piers of bridges must be located away from the dykes to avoid weakening of dyke embankment and foundation in accordance with the Government's requirement. This condition will also be applied during the pier construction.

(3) Approach Bridges

In general, post-tension or pre-tension method is applicable for the fabrication of PC box girder/PC T or I-beams. However, the latter method requires a large investment cost for the development of the plant and is not advantageous unless scale of construction scale is large. Also the latter method entails the difficulty of hauling of girders or beams if the road network lacks sufficient carriageway width and pavement strength for the passage of large trailer trucks.

12.5 Construction Time Schedule

The construction time schedule for each construction package was prepared as shown in Figure 12.1.

Item														Mo													
	() :	2	4	6	8	0	12	14	16	18	20	0_2	22 2	24	26	28	30	32	34	36	38	40	42	44	46	48
Preparatory Work					•	Τ	T	Τ									1			1_			<u> </u>		<u> </u>	<u> </u>	1
Cofferdams and Str. Excavation			-																1	Ŀ					_		_
Cast-in-Place Conc. Piles			Π		_	-			+	4					-	+		+=		-			↓	\perp	<u> </u>		1
Substructure			1		T	_	-	+	+-				_				-						-	1_	<u> </u>	<u>L</u> .	<u> </u>
Superstructure					Т		-	-	+											1	+-	_					\perp
Bridge Furniture			1														<u> </u>	-		1				 		_	L
Bridge Lighting			1	Т	T		Т	Т	7												\perp	1					
Paving and Road Marking		1	1	1	1	1	1	\top	_	Т					Ι.						<u> </u>			1		1_	\perp
Demobilisation		 		1	1		1		7						T					Ţ.				Í			Ī

Package 1: Thanh Tri Bridge

Item	0	2		4	6	8	10	12	Мот 14		18	20 2	2 2	4 2	. 26 2	. 8 3	
Preparatory Work	Ť						1	<u> </u>		1 1			100	e i			
Earthwork			-														
Bridge Construction			-							_		+					ļ
Ditch and Culvert										+	-	†	<u> </u>	·			ــــــ
Pavement Construction								<u> </u>		-	1	 				<u> </u>	
Miscellaneous and						Į.	1				1						4
Demobilisation				<u> </u>	1			<u>l</u>		<u> </u>		<u> </u>	1		L	L	

Package 2: Thanh Tri Section of SHTRR

Item							_				Mo				2	24	26	28	30
	- 0	}	2	4	1	6	8_	j	0 1	2	14	10 .	18 2	20 2	2 2	24	26		, , , , , , , , , , , , , , , , , , ,
Preparatory Work	ŀ	-	T																
Earthwork											1					ļ	ļ		<u> </u>
Bridge Construction		:	· L	1						L							1		<u> </u>
Ditch and Culvert														<u> </u>		<u> </u>			<u> </u>
Pavement Construction						100			9.3					·			ļ		
Miscellaneous and Demobilisation														- A					

Package 3: Gia Lam Section of SHTRR

Figure 12.1 Construction Time Schedule

13. MANAGEMENT AND MAINTENANCE

13.1 Present Situation of Highway Maintenance Management

(1) Organization of Ministry of Transport

Organization chart of the Ministry of Transport (MOT) is shown in Figure 13.1. As seen in the figure, MOT has five bureaus:

- Vietnam Road Administration;
- Vietnam National Railway;
- Vietnam River Administration;
- Vietnam National Maritime; and
- Vietnam Highway Standing Committee.

(2) Vietnam Road Administration Bureau

Road administration exists within the jurisdiction of MOT. Under the Government Decree No. 07, the Vietnam Road Administration Bureau (VRAB) was formed on 30 January 1993 and commenced operation on 26 May 1993.

The VRAB has three levels of administrative groups as shown in the following and the management is divided into 12 sections/offices:

- Management;
- Transport Companies; and
- Road Management Units.


The comprehensive organization of the VRAB is shown in Figure 13.2 together with the number of employees for each group.

(3) Highway Maintenance Management


Regional Road Management Unit No. 2 (RRMU No. 2) is responsible for road management and maintenance of national highways in the northern part of Vietnam.

RRMU No. 2 is located in Hanoi and is mainly responsible for the maintenance of the National Highways Nos. 1, 2, 3, 4E, 5, 6, 15, 70, 183 and 279; a total of 1,476.5 km.

RRMU No. 2 is comprised of 10 Road Management Divisions and four autonomous enterprises. Road Management Divisions (RMD) are responsible for the routine maintenance of various lengths of national highway and receive an annual budget allocation from the MOT.



13 - 2



13 - 3

The Management Division for Bridge and Ferry on the Red River has been included in the above 10 Road Management Divisions.

The function of RRMU No. 2 is divided into seven departments and an engineering center as shown in Table 13.1.

Table 13.1 Organization of RRMU No. 2 Head Office

Function	Organization Units		Staff	No. of Units
	1. Traffic Management Dept.			
	2. Planning Economic Dept.			
RRMU No. 2	3. Financial Accounting Dept.			
Management	4. Science and Technology Dept.	•	70	R
Departments	5. Personnel and Labor Dept.		,,	U
	6. Administrative Dept.			
	7. Traffic Safety Dept.			
	8. RMU No. 2 Engineering Center	er		

The organizations of before-mentioned 10 Road Management Divisions (RMD) and four autonomous enterprises are shown in Table 13.2 together with numbers of staff for each organizational unit.

Only routine maintenance budget has been allocated to RMD and the other budgets for medium and large scale maintenance/repair has been allocated mostly to the Transport Construction and Repair Company. Allocated budget in 1994 and 1995 is shown in Table 13.3.

RMDs suffer from lack of maintenance equipment. In most cases, available equipment consists only one unit of grader, pick-up truck, and road roller.

Transport construction and repair company possesses the following vehicles and equipment for road maintenance and repair (Table 13.4).

Table 13.2 Organizations of 10 RMD and Four Repair/Production Units

Function	I	Organizational Units	Staff	Section	Team
	1.	Road Management Division (RMD)	241	4	7
		No. 222			
	2.	RMD No. 224	246	, 4	9
	3.	RMD No. 226	257	4	5
Road	4.	RMD No. 232	249	4	6
Management	5.	RMD No. 234	387	4	4
Division	6.	RMD No. 236	. 302	. 4	6
(RMD)	7.	RMD No. 238	137	4	5
	8.	RMD No. 240	131	4.	4
ļ	9.	RMD No. 242	300	4	5
1 .	10.	Management Division of Bridge and	180	4	4
		Ferry on the Red River			
	1.	Transport Construction and Repair	283	4	4
	j '	Company 230			
Repair	2.	Transport Mechanical Enterprise No. 2	122	3	3
Production	3.	Transport Material Support Engineering	213	3	3
Unit		Construction Company	÷		1
	4	Transport Material Production Company	457	5	4

Table 13.3 Allocated Budget for Maintenance and Repair

Category of	Allocated Budget (million Dong)							
Maintenance/Repair	1994	1995						
Routine Maintenance	12,886	16,136						
Medium Scale Repair	23,712	24,484						
Large Scale Repair	14,912	17,327						

Notes 1) Routine Maintenance:

Pavement potholes, drainage, signs, lane markings, weed

2) Medium Repair:

Pavement overlay (2 cm - 4 cm), 163 km/year

3) Large Scale Repair:

Pavement overlay (15 cm - 20 cm), 29 km/year

Table 13.4 Vehicles and Equipment Possessed by Transport Construction and Repair Company

Type of Equipment			- '	Numb	er of	Unit		
Concrete mixing plant		- / J			1			
Truck, 10 tons					10			
Steel wheel roller		100			. 1		-	٠.
Tire roller		1			1			
Macadam roller					. 3			
Passenger car					6			

13.2 Management and Maintenance Plan

(1) System of Highway Maintenance

In order to attain proper highway management and maintenance, all systems of highway maintenance have to be carried out orderly and in a proper manner, and established organization must be consistent with the requirement of work components and needed capacities. Figure 13.3 shows the general flow chart of the recommended overall highway maintenance works.

(2) Maintenance Operating System

Highway Maintenance covers various activities related to inspections, maintenance and repairs, which require quick response and are appropriate to keep the highway open to traffic.

The following matters must be specified to implement the above operations:


- Communications system (instruction, response, duty, decision and coordination) between headquarters of Maintenance Unit and Maintenance Division; and
- Extent of activities and responsibility of the Maintenance Unit and Maintenance Division.

The following should be considered to encourage the use of contractors to carry out highway maintenance activities:

- Maintenance activities based on a monthly and annual programme;
- Clarification of working criteria of maintenance and repairs;
- Formulation of contracts, supervision and acceptance system for highway maintenance work; and
- Provision of guidance to the contractors as to the significance of highway maintenance.

(3) Data Base and Management System

Data base and management system is indispensable for highway maintenance. One of the most important activities is to collect reliable data, in particular, to collect and keep as-built drawings and documents including design reports and specifications, construction record, and historical repair records.



13 - 7

(4) Activities and Tasks of Highway Maintenance

The activities and tasks of the highway maintenance are shown in Figure 13.4.

(5) Safety Measures during the Highway Maintenance

Highway maintenance will be conducted, in careful consideration of traffic regulations, traffic safety and circumstances along the highway.

Personnel in charge of traffic control will be assigned during the maintenance and repairs. They will ensure smooth and safe traffic flow and worker's safety.

(6) Traffic Control Measures

The date, time-frame, construction methods and proposed traffic control measures will be analyzed for the highway maintenance activities based on traffic volumes, number of traffic lanes and detours.

13.3 Recommended Maintenance and Management Body

It is recommended that new Expressway Management and Maintenance Unit as well as Operation and Maintenance Division will be set up in the organization of Vietnam Road Administration Bureau to attain efficient management and maintenance of SHTRR and future Hanoi Third Ring Road.

It is also recommended that the force account activities of the Expressway operation and maintenance will be kept at minimum level in scope and volume and the major part of the works should be done by contract basis. However, Expressway Maintenance Unit must undertake information collection & dissemination, and maintenance activities requiring a quick response.

13.4 Recommended Operation and Maintenance Equipment

(1) Required Vehicles and Equipment

The Division will be equipped with the following limited kinds of equipment for operation and maintenance works under such a system.

- Communication cars, patrol cars and maintenance vehicles for expressway patrol, inspection and supervision of maintenance works being carried out by the contractors;




Figure 13.4 Activities and Tasks of Highway Maintenance

- Trucks, dump trucks, small crane vehicles, small rollers and tampers, air compressors, breakers, asphalt cutters, etc. for routine maintenance and emergency repair works on occasions of accident and disaster;
- Water tankers, grass cutters, etc.; and
- Ambulance vehicles.

(2) Workshop and Depots

Workshop and depot will be located near Operation and Maintenance Division (OMD) building. However, they might be of small scale since major maintenance and repair work will be done by contractors under the supervision of OMD.

14. PROJECT COST ESTIMATES

14.1 General

The estimate of the project cost was based on the results of preliminary engineering design, quantity take-off of each work item, and the studies on construction planning and method as described in the preceding chapters.

The basic premises in estimating the project cost are as follows:

- All the construction work will be executed by constructor(s) to be selected by international competitive bidding;
- The unit cost of each cost component was determined based on the economic conditions prevailing in January 1998 (USD \$1.0 = 12,950 Dong);
- Engineering services cost is assumed to be 3 % of the construction cost;
- Supervisory services cost is assumed to be 4 % of construction cost; and
- Physical contingency is estimated to be 10 % of the total of construction cost, land acquisition and resettlement cost, engineering services cost and supervisory services cost.

The project cost was estimated in financial cost.

14.2 Construction Cost

(1) Unit Cost of Construction Works

The unit cost of construction works were studied based on the material cost, equipment cost, labor cost, overhead and profit for chief work items. The analyzed unit costs were compared with current bid prices and adjusted as required to obtain the most realistic prices.

(2) Estimated Construction Cost

The summary of estimated construction cost by each construction package is shown in Table 14.1.

Table 14.1 Summary of Estimated Construction Cost in 1998 Prices

Package No.	Construction Package	Foreign Exchange	Local Currency	Total
1	Thanh Tri Bridge	1,451,400	967,600	2,419,000
2	Thanh Tri Section of SHTRR	473,168	315,445	788,613
3	Gia Lam Section of SHTRR	285,483	190,322	475,805
	Total	2,210,051	1,473,367	3,683,418

Note: SHTRR denotes Southern Section of Hanoi Third Ring Road.

14.3 Land Acquisition and Resettlement Cost

Land acquisition and resettlement cost was estimated based on the area of required land acquisition estimated in the preliminary engineering design and the estimated building areas and number of resettled families in the field investigations.

The summary of estimated land acquisition and resettlement cost by each package is shown in Table 14.2.

Table 14.2 Summary of Estimated Land Acquisition and Resettlement Cost (Cost in Million Dong)

Package 1: Thanh Tri Bridge

I deliage II		
ompensation Items	Costs (mill.VND)	Notes
1) Land compensation	-	
4) Crops compensation	643	
7) Assistance for recovering	801	turkati, ja elikulu
	1,444	
costs	72	5% of the subtotal
	270	
Grand Total	1,786	
	1) Land compensation 4) Crops compensation 7) Assistance for recovering	Costs (mill.VND)

Package 2: Thanh Tri Section of SHTRR

	Tuckage 2, Indin 11:	Geetion or Ox	
Co	ompensation Items	Costs	Notes
		(mill.VND)	
Compensation	1) Land compensation	17,375	
	2) Houses compensation	34,065	Level II or III
	3) Other building compensation	7,859	
	4) Crops compensation	3,073	
	Subtotal	62,372	
Subsidy	5) Personal subsidy	2,160	
	6) Business or trade subsidy	198	
	7) Assistance for recovering	5,018	
	8) Assistance for moving	261	
	Subtotal	7,637	
Compensation as	nd subsidy total	70,009	
Infrastructure co	st for the resettlement sites	18,855	
Administration of	costs	3,500	5% of the compensation
			and subsidy costs
Allowance		10,263	
	Total	102,627	

Package 3: Gia Lam Section of SHTRR

	I ackage J. Gla Daili b		· · · · · · · · · · · · · · · · · · ·
Co	ompensation Items	Costs (mill.VND)	Notes
Compensation	1) Land compensation	3,515	
	2) Houses compensation	1,640	Level II or III
	3) Other building compensation	346	Graveyard included
	4) Crops compensation	1,660	
	Subtotal	7,161	
Subsidy	5) Personal subsidy	144	
	6) Business or trade subsidy	4	
	7) Assistance for recovering	2,975	
	8) Assistance for moving	20	
	Subtotal	3,143	
Compensation to	otal	10,304	
Infrastructure co	st for the resettlement sites	1,290	
Administration of	costs	515	5% of the compensation and
			subsidy costs
Allowance		1,345	10 % of the above
	Grand Total	13,454	

Note: SHTRR denotes Southern Section of Hanoi Third Ring Road.

14.4 Estimated Project Cost

The estimated Project cost in 1998 prices is shown in Table 14.3 together with the shares of foreign currency and local currency portions. The Project cost is expressed in terms of financial cost.

Table 14.3 Summary of Project Costs of Foreign Exchange and Local Currency in 1998 Prices

Package 1: Thanh Tri Bridge

Unit: Million Dong Local Total Foreign Description Exchange Currency 1,451,400 967,600 2,419,000 (1) Construction 1,786 (2) Land Acquisition and Resettlement 1,786 50,799 72,570 (3) Engineering Services (3%) 21,771 118,531 50,799 169,330 (4) Supervision Services (7%) 104,196 266,269 162,073 (5) Physical Contingency (10%) 2,928,955 1,782,803 1,146,152 Total

Package 2: Thanh Tri Section of SHTRR

Unit: Million Dong Total Foreign Local Description Exchange Currency 788,613 (1) Construction 473,168 315,445 0 102,627 102,627 (2) Land Acquisition and Resettlement 23,658 16,561 7,097 (3) Engineering Services (3%) 55,203 38,642 16,561 (4) Supervision Services (7%) (5) Physical Contingency (10%) 52,837 44,173 97,010 485,903 1,067,111 581,208 Total

Package 3: Gia Lam Section of SHTRR

Unit: Million Dong Foreign Local Total Description Exchange Currency 285,483 475,805 190,322 (1) Construction (2) Land Acquisition and Resettlement 13,454 13,454 0 14,274 (3) Engineering Services (3%) 9,992 4,282 23,314 9,992 33,306 (4) Supervision Services (7%) (5) Physical Contingency (10%) 31,879 21,805 53,684 590,523 350,668 239,855 Total

Note: SHTRR denotes Southern Section of Hanoi Third Ring Road

15. PROJECT IMPLEMENTATION PLAN

15.1 Execution of the Project

(1) Executing Agency

Project Management Unit Thang Long (PMU Thang Long), Ministry of Transport (MOT) is the Project executing agency and responsible for the execution of the following tasks:

- Pre-construction Works
 - Engineering Services (Review of Feasibility Study and Detailed Design);
 and
 - Land Acquisition and Resettlement.
- Construction Works and Construction Supervision

The necessary land acquisition and resettlement within proposed right-of-way will be undertaken prior to the start of the construction works. The organization chart of PMU Thang Long is shown in Figure 15.1.

(2) Procurement of Contractor(s)

Tender lot for the Project will be decided in consultation with the international financing agency. All times to be financed by the international financing agency shall be procured through international competitive bidding with pre-qualification in accordance with the guidelines of the international financing agency for procurement.

(3) Consulting Service for the Project

The selection and employment of the consultant for the consulting engineering (detailed design) and supervisory services shall be done in short-list method in accordance with the guidelines of the international financing agency.

(4) Budgetary Appropriation for the Project

Any portion of the Project not covered by the loan of the international financing agency are to be financed by the budget of the Government.




Figure 15.1 Organization Chart of PMU Thang Long

15.2 Project Implementation Time Schedule

(1) Construction Package

To consider a large scale construction, the entire construction is divided into 3 packages, they are:

- Package 1: Thanh Tri Bridge;

- Package 2: Thanh Tri Section of Southern Hanoi Third Ring Road; and

Package 3: Gia Lam Section of Southern Hanoi Third Ring Road.

(2) Construction Time Schedule

Construction time schedules were prepared based on the actual work quantities, site conditions and practical and economical construction methods. Taking into account the scale of the construction and the urgency of the Project, the maximum construction period were set:

Package 1 : 4 years; and

Package 2 and 3 : 2.5 years.

As shown in Figure 12.1 in Section 12, the completion of the construction in all packages will be set at the same time of 48th month to attain the optimum investment schedule.

(3) Project Implementation Time Schedule

Project implementation time schedule was tentatively drawn up as shown in Figure 15.2.

Description	1999	2000	2001	2062	2003
Detailed Design					
Package 1 Land Acquisition and Resettlement Construction		# #			
Packages 2 and 3 Land Acquisition and Resettlement Construction					

Figure 15.2 Project Implementation Time Schedule

15.3 Estimated Project Cost and Annual Fund Requirement

(1) Estimated Project Cost

The summary of project cost in 1998 prices is shown in Table 15.1. The project cost was expressed in term of financial cost by each construction package.

Table 15.1 Summary of Estimated Project Cost in 1998 Prices

Package No.	Construction Package	Project Cost (Million Dong)
1	Thanh Tri Bridge	2,928,955
2	Thanh Tri Section of SHTRR	1,067,111
3	Gia Lam Section of SHTRR	590,523
	Total	4,586,589

Note: SHTRR denotes Southern Section of Hanoi Third Ring Road.

(2) Estimated Annual Fund Requirement

A tentative disbursement schedule for the implementation of the Project was prepared as shown in Table 15.2.

Table 15.2 Estimated Annual Fund Requirement

 Implementation	Year	Financial Cost (million Dong)
1st year	1999	123,517
2nd year	2000	361,329
3rd year	2001	1,054,047
 4th year	2002	1,740,617
5th year	2003	1,307,079
 Total		4,586,589

Note: Costs are in 1998 prices and no price contingency is included.

16. ECONOMIC AND FINANCIAL ANALYSIS

16.1 Economic Analysis

(1) Economic Cost

The investment cost of the Project was estimated at 4,586,589 million Dong:

	Total	4,586,589 million Dong
d)	Land acquisition	129,654 million Dong
c)	Engineering and supervision	405,175 million Dong
b)	Thanh Tri Bridge	2,660,900 million Dong
a)	Highway and Interchange	1,390,860 million Dong

Economic cost can be calculated by removing various distorted factors such as import/export taxes, regulation of minimum wage of unskilled labor, monopoly of land, foreign exchange rate fixed by the government, etc. Table 16.1 shows the conversion result from market price to economic price.

Table 16.1 Conversion to Economic Cost from Financial Cost

Unit: Million Dong Investment **Foreign** Local Portion Overall Investment Items Costs Portion Tradable Non-tradable Skilled Unskilled Transfer Conversion Costs in In Market Goods Goods Labor Labor (Tax) Factor Economic Prices 1.004 1.004 0.996 0.985 0.300 Prices Hwy & Interchange 1,390,860 80 % 4% 4% 5 % 2 % 5 % 89 % 1,235,710 2,660,900 Thanh Tri Bridge 80 % 4 % 4 % 5% 2 % 5 % 89 % 2,364,077 Engin.Supervision 405,175 80 % 15% 5 % 90 % 365,042 Land Acquisition 129,654 0 % 100 % 129,135 100 % Total 4,586,589 4,093,964 Routine 27,520 0% 2 % 3% 0% 90 % 5 % 27 % 7,429 Maintenance Periodic Repair 4,587 0 % 5% 2% 80 % 3 % 5 % 29 % 1,329

Note: Routine maintenance cost is estimated at 0.6 % and Periodic maintenance cost at 0.1 % of the total investment cost.

Table 16.2 shows the construction period and cost allocation to 5 years.

Table 16.2 Yearly Allocation of Project Cost

Unit: Million Dong

Project Implementation	Implementation Year	Allocation Ratio	Financial Cost	Economic Cost
1st year	1999	3 %	123,517	110,251
2nd year	2000	8 %	361,329	322,520
3rd year	2001	23 %	1,054,047	940,837
4th year	2002	38 %	1,740,617	1,553,665
5th year	2003	28 %	1,307,079	1,166,691
Total		100 %	4,586,589	4,093,964

Note: Cost at 1998 Prices

(2) Benefit of the Project

Table 16.3 shows benefits by the realisation of the Project. In the city of Hanoi, average driving speed is less than 30 km/h at present. Main benefits by the construction of Thanh Tri bridge and SHTRR are; time cost saving of passenger and vehicles, and vehicle operating cost saving.

Table 16.3 Kinds of Benefit of the Project

- (1) Benefits of Driving Time Saving (or Time Cost Saving)
- (2) Benefits of Driving Cost Saving (or Vehicle Operating Cost Saving)
- (3) Benefits from Increase of Land Productivity
- (4) Other Benefits;
 - 1) Decrease of Traffic Accident
 - 2) Increase of comfortableness of traveling
 - 3) Decrease of spoiling loss of agricultural products
 - 4) Enhancement of Urban Development
 - 5) Strengthening the Function as the Capital City
 - 6) Decrease social cost by Improvement of Environments
 - 7) Enhancement of Social Development
 - 8) Integration of the Region

Time value Time value Passenger 4.7 Passenger car 1800h/y Working 2.8 62 % Trip 6,123,045dong 3,402dg/h 98.42dong/min. GRDP/year 6,671,890mil.dg GRDP/worker 1.0 Bus 1800h/y Working 29.3 51 % Trip 1,289,062 dg 1,289,062dong 178.36dong/min. 716dg/h No.of workers 5,175,772 Motorcycle 1800h/y Working 1.06 62 % Trip 3,70,053dong 22.25dong/min. 2,059dg/h No. of passenger Productivity Income structure Working hour

Figure 16.1 shows the method of measuring the value of saved time of passenger.

Figure 16.1 Transportation Time Value for Time Saving Benefit Calculation

Vehicle operation cost saving benefit is affected by many factors such as, vehicle type, running speed, road conditions, traffic conditions and others. Table 16.4 shows vehicle operating cost per vehicle-km. Seven vehicle types were classified into four types calculating from weighting average using composition ratio of vehicle types based upon the result of traffic count survey.

Table 16.4 Estimation of Economic Vehicle Operating Cost

Unit: Dong

	Passenger Car	Bus	Truck	M.Cycle
Items	Pas. Car Van	Mid-Bus L. Bus	M.Truck H.Truck	M.Cycle
Running Costs/vehicle-km	1,656.51 1,137.08	1,369.21 3,544.46	2,006.43 2,781.66	280.38
Vehicle Component	0.84 0.16	0.67 0.33	0.89 0.11	1.00
Weighted	1,391.47 181.93	917.37 1,169.67	1,785.72 305.98	280.38
Running Costs/vehicle-km	1,573	2,087	2,091	280
Fixed Costs/Vehicle-km	392.60 410.34	626.00 1,471.70	954.15 1,356.38	41.14
Vehicle Component	0.84 0.16	0.67 0.33	0.89 0.11	1.00
Weighted	329.78 65.65	419.42 485.66	849.20 149.20	41.14
Fixed Costs/Vehicle-km	395	905	998	41
Grand total	1,968	2,992	3,090	. 321

Note: Base speed of passenger car and van are 45 km/h, and others 40 km/h

Driving speed will decrease year by year as traffic increases in the Study Area. Vehicle operating cost will increase, as vehicle speed decreases. Table 16.5 shows the set speed of vehicle by year and by vehicles.

Table 16.5 shows road users benefit of vehicle operating cost from shorter distance. Driving distance on street by vehicle type was estimated based on origin and destination survey. Road user can save average 6.5 km by using project road. V.O.C saving from higher design standards was estimated by the deference of driving speed between project road and ordinary street for 12.3 km.

Table 16.5 V.O.C Saving by Distance Reduction and Driving Speed Increase

Saving by Distance Reduction

Unit :Dong/Vehicle

Vehicle	Driving Distant	ce	Drivin	g Distance (V.O.C S	aving	
Туре	by O.D (km)		Street	Project	Saving	1998	2020
Passenger Car	25.8	24 %	18.37	12.3	6.07	17,751	20,623
Bus	27.3	26 %	19.44	12.3	7.14	22,751	24,700
Truck	28.6	27 %	20.37	12.3	8.07	33,477	36,953
Motor Cycle	23.9	23 %	17.02	12.3	4.72	1,685	1,808
Average	26.4	100 %	18.80	12.3	6.50	-	

Saving by Driving Speed Increase

Unit :Dong/Vehicle

	Project Road	St	reet	V.O.C. Savings							
	2004-2020	1998	2020	1998	2020						
Passenger Car	23,764	35,953	41,771	12,189	18,007						
Bus	30,959	39,188	42,546	8,229	11,587						
Truck	37,220	51,045	56,346	13,825	19,127						
Motor Cycle	4,022	4,391	4,711	369	689						

(3) Result of Economic Analysis

The internal rate of return is the discounted rate in which discounted present value of benefits equals to the total discounted present value of costs. The higher the economic internal rate of return, the higher the priority of the Project. At the same time, if the internal rate of return turns out higher than the opportunity cost of capitals, that is 12 %, investment is proved to be feasible.

The result of economic study revealed the following indicators:

(a) Benefit cost ratio discounted at 12 % 1.12

(b) Net present value discounted at 12 % 329,000 million dong

(c) Economic internal rate of return 13.14 %

This project is judged feasible, showing 13.14 % of EIRR, higher than the opportunity cost of capital in Vietnam.

16.2 Financial Analysis

(1) Toll Fee and Road Users' Benefit

Users' benefit of the Project consists of three items as shown in Table 16.6: i) time cost saving of passenger, ii) vehicle operating cost saving from distance reduction, and iii) vehicle operation cost saving from higher design standards.

Table 16.6 Road Users' Benefit by One Trip in the Year 1998 and 2020

Unit: Dong/vehicle

Vehicle	Time Savir	ng Benefit	Vehicle	Operating	Total Road Users' Benefit					
Туре			Distance	Saving	Design D	ifference				
	1998	2020	1998	2020	1998	2020	1998	2020		
P. Car	2,579	4,387	17,751	20,623	12,189	18,007	32,519	43,017		
Bus	6,128	9,364	22,751	24,700	8,229	11,587	37,108	45,651		
Truck	0	0	33,477	36,953	13,825	19,127	47,302	56,080		
M.Cycle	588	946	1,685	1,808	369	689	2,642	3,443		

Level of toll fee must be less than users' benefit. Toll on the project road for 1998 was assumed to charge the same toll as Thang Long bridge since it is reasonable and realistic to charge of average toll of 45.2 % of users benefit.

Toll fee in future will increase as users' benefit increase in accordance with congestion increase in the city road. Therefore, following two cases of toll levels were used for estimation of revenue calculation as shown in Table 16.7.

Case 1: To keep the same toll/benefit ratio of present average 45.2 % (Thang Long bridge) till the year 2020

Case 2: To gradually increase toll/benefit ratio from 45.2 % in 1998 to 70 % in 2020

Table 16.7 Toll Fee Balanced with Road Users' Benefit and with Thang Long Bridge

Unit: Dong

Vehicle		1998		2020													
Туре	Users'	Toll/B.	Thang Long		Case 1	Case 2											
Passenger Car	Benefit	Ratio	Toll	Benefit	T/B. ratio	Toll	Benefit	T/B ratio	Toll								
Passenger Car	32,519 36.9 %		12,000	43,017	36.9 %	15,874	43,017	70 %	30,112								
Bus	37,108	57.9 %	21,480	45,651	57.9 %	26,426	45,651	70 %	31,956								
Truck	47,302	48.3 %	22,840	56,080	48.3 %	27,079	56,080	70 %	39,256								
Motor Cycle	2,642	37.8 %	1,000	3,443	37.8 %	1,308	3,443	70 %	2,410								
Average	29,893	45.2 %	14,330	37,048	45.2 %	17,670	37,048	70 %	25,934								

(2) Comparison between Toll Fee and Maintenance/Operation Cost

Table 16.8 is the result of comparison of routine/periodic maintenance cost of project road and operation cost for toll collection which is assumed at 20 % of toll revenue, with toll revenue from 2004 to 2028. Costs and revenue are compared by present value of 1998 price discounted by 15 %, average interest rate of market. Following revenue and cost ratio are obtained;

Case	Cost	Revenue	Reven	ue/Cost Ratio
Case 1	235 billion	779 billion	4	3.32
Case 2	290 billion	1,055 billion		3.64

Revenue of both case 1 and case 2 can cover the maintenance and operation cost, and gets more than 3 times revenue.

(3) Result of Financial Analysis

Viability of investment is proved by the comparison between toll revenue and expenditure using indicator of FIRR. The financial rate of return is the discount rate in which total discounted present value of toll revenue equals to the total discounted value of cost. If the FIRR turns out higher than the interest of market, investment is proved to be feasible.

The result of financial study revealed the following FIRRs:

		Case 1	Case 2
Government base	Soft loan 70 % and bank loan 30 %	2.83	5.64
Private base	Equity 30 % and bank loan 70 %	2.80	5.63

Table 16.8 Comparison between Maintenance/Operation Cost and Toll Revenue

		_																						-								-т	_
c 2	Present Worth	Revenue						71,329	68,354	65,626	63,134	60,872	58,832	57,009	53,134	49,769	46,858	44,355	42,219	40,414	38,911	37,684	36,710	35,961	32,332	29,072	26,142	23,510	21,145	19,020	17,109	15,392	1,054,896
Case 2	Presc	Cost						24,611	75,067	20,948	19,429	19,075	16,910	15,875	14,516	13,336	12,803	11 428	10,667	10,017	9,464	9,243	8,613	8,298	7,428	6,650	6,077	5,334	4,779	4,282	3,838	3,500	289,787
-	Worth	Revenue						63,622	59,805	56,311	53,116	50,197	47,534	45,109	41,180	37,751	34,757	32,142	29,856	27,860	26,117	24,598	23,276	22,123	19,456	17,110	15,048	13,235	11,640	10,238	9,005	7,921	779,006
Casc	Present Worth	Cost						23,070	20,957	19,085	17,426	16,940	14,650	13,495	12,125	10,932	10,382	8,986	8,195	7,506	6,905	6,625	5,927	5,530	4,853	4,258	3,858	3,279	2,878	2,526	2,217	2,006	234,609
Discount	Factor	15%	0.870	0.658	0.572	0.497	0.432	0.376	0.327	0.284	0.247	0.215	0.187	0.163	0.141	0.123	0.107	0.093	180.0	0.070	0.061	0.053	0.046	0.040	0.035	0.030	0.026	0.023	0.020	0.017	0.015	0.013	15.00%
	Toil	Revenue						189,737	209,097	230,863	255,412	283,199	314,766	350,767	375,964	404,974	438,483	477,318	522,477	575,166	636,842	709,268	794,579	895,123	925,508	600,726	079,686	1,023,536	1,058,654		=		16,018,343
2		Total						65,467	69,339	73,692	78,602	88,746	90,473	97,673	102,712	108,514	119,803	122,983	132,015	142,553	154,888	173,960	186,435	206,544	212,621	218,921	230,040	232,227	239,250	246,534	254,088	266,510	3,914,590
Case 2	Cost	Operation						37,947	41,819	46,173	51,082	56,640	62,953	70,153	75,193	80,995	87,697	95,464	104,495	115,033	127,368	141,854	158,916	179,025	185,102	191,402	197,934	204,707	211,731	219,014	226,568	234,403	3,203,669
		Maintenance Operation					*.	27,520	27,520	27,520	27,520	32,106	27,520	27.520	27,520	27,520	32,106	27,520	27,520	27,520	27,520	32,106	27,520	27,520	27,520	27,520	32,106	27,520	27,520	27,520	27,520	32,106	710,921
	Toll	Revenue						169,235	182,944	198,095	214,882	233,534	254,318	277,549	291,377	307,185	325,246	345,886	369,485	396,496	427,448	462,969	503,797	550,676	556,922	563,253	569,672	576,178	582,774	589,462	596,243	603,118	10,148,744
c 1		Total						61,367	64.108	67.139	70.496	78.813	78 383	83 029	85 795	88 957	97,155	769'96	101,417	106,819	113,009	124,700	128,279	137,655	138,904	140,170	146,041	142,755	144,074	145,412	146,768	152,730	2,740,670
Casc	Cost	Operation						33,847	36,589	39,619	42,976	46,707	50,864	55,510	58,275	61,437	65,049	69,177	73,897	79,299	85,490	92,594	100,759	110,135	111,384	112,651	113,934	115,236	116,555	117.892	119,249	120,624	2,029,749
		Maintenance	1					27.520	27,520	27.520	27.520	32,106	27.520	27,520	27,520	27 520	32,106	27,520	27.520	27,520	27,520	32,106	27,520	27,520	27,520	27,520	32,106	27,520	27,520	27,520	27,520	32,106	710,921
	Year	-	1998	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	
	T V			1 1"	, 4	·^	ی	7	œ	6	01	Ξ	12	13	7	15	91	17	œ	16	70	21	22	23	24	2.5	26	27	28	29	8	31	

As Table 16.9 shows FIRR should be higher than 4.61 % in the case operated by the Government. It should be higher than 8.5 % in the case operated by private company, which includes 10 % of interest, around 2 % of dividend and 3 % of profit.

Table 16.9 Average Interest Rates for Cases Implemented by Private Sector and Government

Unit: Million Dong

Sources	Component	Amount	Interest Rate	Amount	Av. Interest Rate
1) Implementation	ı by Governmen	f			
Soft Loan	70 %	3,210,612	2.3 %	73,844	
Bank Loan	30 %	1,375,977	10 %	137,598	
	100 %	4,586,589		211,442	4.61 %
2) Implementation	by Private Secto	or	(Dividend+Profit)		
Equity	30 %	1,375,977	(2 %+3 %)	68,799	
Bank Loan	70 %	3,210,612	10 %	321,061	
	100 %	4,586,589		389,860	8.50 %

Financial viability can be concluded as follows:

i) Project Implementation by the Government

Case 1: FIRR of 2.83 % is lower than the average interest rate of 4.61 % and judged to be financially not feasible.

Case 2: FIRR shows 5.64 % which is higher than the average interest rate of 4.61 % and the Project is judged to be financially feasible.

ii) Project Implementation by Private Sector

Case 1 and 2: Calculated FIRRs are 2.80 % and 5.63 % for Case 1 and Case 2 respectively. These FIRRs are far lower than the average interest rate of 8.50 % and judged to be financially not feasible.

17. ENVIRONMENTAL IMPACT STUDY

17.1 Scope and Objectives of the Study

(1) Initial Environmental Examination

Initial Environmental Examination (IEE) was carried out along the following three alternative routes (refer to Section 7.1 Study of Alternative Routes).

Alternative-1 : Shorter Bridge Length Scheme

Alternative-2b : Least Affected Inhabitant Scheme

Alternative-3 : Least Land Acquisition Effort Scheme

The objective of the IEE is to identify the significant environmental factors along the above three alternative routes.

(2) Environmental Impact Assessment

Environmental Impact Assessment was carried out along the selected SHTRR (i.e. including Thanh Tri Bridge) route. The environmental investigation area covered 200m wide strips (i.e. area 100 m from planned highway centerline on both sides) along the SHTRR.

The objectives of the EIA are to analyze and forecast the impacts of the significant environmental elements and to consider the mitigation measures for the possible serious adverse impacts.

17.2 Study Method

The IEE was carried out based on the available data/information obtained by data collection from the relevant agencies and field observations. An overall evaluation (environmental screening and scoping) of possible environmental impacts which will be caused by the project activities was carried out based on a checklist method.

Further, based on the results of the IEE, environmental survey results and other available information, the existing environmental conditions in the selected route and the adjacent area were identified and the expected significant environmental impacts in the construction phase and operation/maintenance phase were analyzed. Finally, based on the above mentioned analyses, countermeasures to mitigate the possible serious adverse impacts caused by the Project were considered. The countermeasure study included the overall cost estimation for the execution of environmental countermeasures.

17.3 Environmental Evaluation

Based on the results of the IEE and EIA analyses, the environmental evaluation in the construction and operation/maintenance phase was carried out for the selected route as shown in Table 17.1.

17.4 Mitigation Measures of Adverse Environmental Impact

Although the engineering design and construction methods will also consider the mitigation measures for expected environmental adverse impacts, the following measures should be taken:

(1) Construction Phase

- Control of water pollution for toxic waste and acid sulphate or alkaline effluents;
- Implementation of water quality monitoring for the construction works;
- Erosion and sediment control such as re-vegetation for land disturbance areas:
- Control of air pollution such as sealing of local access road surfaces;
- Implementation of air quality monitoring for the construction vehicles;
- Control of construction noise and vibration especially at concrete bathching plant;
- Management of procurement/dumping of construction materials such as bridge foundation piles;
- Maintenance of temporary construction works; and
- Instruction of the workers concerning the importance of the cultural properties.

(2) Operation/Maintenance Phase

- Erosion control such as re-vegetation of the river banks;
- Control of water pollution for accidental spills into the rivers;
- Implementation of air quality monitoring for the increased future traffic;
- Implementation of traffic noise monitoring; and
- Consideration of a noise barrier along Tran Phu primary school.

Table 17.1 Summary of Environmental Evaluation

No.	Environmental Item	Evaluation	Impacts and Reasons
Socia	l Environment		
1	Resettlement	▲ (C)	About 100 dwellings and about 12 hectares of agricultural lands will be demolished by the project.
2	Economic Activity	Δ (C) Ο (O)	Paddy fields and fish ponds will be lost in some portions by the project. However, regional economic activities will be vitalized by the project.
3	Traffic/Public Facilities	Δ (C)	The optimum route is designed to pass very close to some public facilities such as primary school.
	Community Severance		The optimum route is planned to avoid passing the densely inhabitant area.
5	Cultural Property		The optimum route is keep distance to important cultural property.
6	Rights of Common	-	There are no government regulations for fishery right.
7	Public Health Condition	-	Public health issues will not occurred by the project.
	Waste	Δ (C)	Waste management at construction phase should be considered.
	Hazards(Risk)		Risk of hazards will not increased by the project.
	al Environment		
10	Topography and Geology		As the project scale is not large, change of topography and geology will not occurred by the project.
11	Soil erosion	Δ (O)	Mitigation measures for topsoil erosion by rainfall after vegetation removal will be needed.
12	Groundwater	_	Change of the distribution of groundwater will not occurred.
13	Hydrological Situation		Change of the river discharge and riverbed condition will not occurred
- 14	Coastal Zone	-	The project site is not included in coastal zone.
15	Fauna and Flora	-	There is no endangered/rare species in the project site and the impacts on the existing ecosystem by the project will be very few.
- 16	Meteorology		Change of meteorological conditions will not occurred by the project
	Landscape	△ (C) ○ (O)	Although aesthetic deterioration may occurred due to the construction wastes and etc., the bridge's design is taking into account a harmony with local natural view.
Pollu	tion		
18	Air Pollution	△ (C) △ (O)	As the traffic volume will be increased slightly, air pollution caused by the project at construction and operation phase may slightly occurred. Mitigation measures should be considered.
19	Water Pollution	Δ (C)	Slight increase in water pollution by the project at construction phase mainly due to construction wastes. Mitigation measures should be
30	Soil Contomination		considered.
	Soil Contamination		As the construction methods will be considered the countermeasures for soil contamination, the impact will be very few.
21	Noise and Vibration	Δ (C)	As the optimum route is designed to pass close to houses and existing
* *** ***		Δ (0)	properties in some sites, the slight traffic noise and vibration impacts by the project should be considered.
22	Land Subsidence	_	As the construction methods will be considered the countermeasures
			for land subsidence, the impact will be very few.
23	Offensive Odor	-	There is very few factors generating offensive odor by the project.

Note: 1) Evaluation Categories

O: Slight favorable impact is expected.

△: Slight adverse impact is expected

♦: Significant favorable impact is expected.
♦: Significant adverse impact is expected.
♦: Slight
2) (C) = Construction Phase, (O) = Operation/Maintenance Phase

17.5 Proposed Monitoring Programme

Execution of the following monitoring programme is recommended:

Construction Phase

Category	Water Quality	Air Quality	Noise
Location	3 sites	5 sites	5 sites
Period	2 times/week for 5	1 day/month for 5	1 day/month for 5
	years	years	years
Sampling Items	pH, SS, COD, BOD,	TSPM, SO2, NOx,	Leq, L50
	DO, Ptotal, Al, Fe	HC, CO, Pb	

Operation/Maintenance Phase

Category	Water Quality	Air Quality	Noise
Location	3 sites	5 sites	5 sites
Period	2 times/month for 5 years	1 day/6 months for 5 years	1 day/6 months for 5 years
Sampling Items	PH, SS, COD, BOD,	TSPM, SO ₂ , NO _x ,	Leq, L50
	DO, Ptotal, Al, Fe	HC, CO, Pb	

18. RELOCATION PLAN

18.1 Action Measures by Steps

The implementation of land acquisition and resettlement mainly consists of the following 10 steps.

- 1) Establishment of Steering Committees for Implementation and Supervision
- 2) Socio-economic Survey
- 3) Valuation for Lost Assets
- 4) Cost Estimation for the Relocation Programmes
- 5) Preparation of Alternatives for Compensation and Relocation Site Selection
- 6) Negotiations about Compensation
- 7) Relocation Site Preparation with Re-creation of Social Environment
- 8) Land Transfer and Relocation
- 9) Monitoring of Execution
- 10) Coping with Environmental Consequences during Construction Works

The summary of these steps are described in the following together with the conceiving problems and recommendation of the Study Team.

(1) Establishment of Steering Committees for Implementation and Supervision

One of the most critical problem in the land acquisition and resettlement is the provision of compensation budget and seeking financial resources. The budget for relocation Programmes will be allocated by MOT through the evaluation by Hanoi People's Committee after submission of the amount of compensation costs evaluated by the steering committees.

(2) Socio-Economic Survey

The steering committees will be in charge of socio-economic survey to estimate the adequate and accurate population. The names of affected families are recorded immediately based on the results of survey to prevent to inflow of peoples ineligible for compensation.

(3) Evaluation for Lost Assets

The adequate evaluation for lost assets is significant task of steering committees to maintain the living environment of affected people. Consideration for partially lost assets is necessary because remained assets are sometimes economically unproductive.

(4) Cost Estimation for the Relocation Programmes

Compensation cost will be estimated by steering committees in accordance with the regulation of Hanoi People's Committee. Cost estimates must cover all aspects of relocation plan and Programmes, not only the land compensation costs but also resettlement costs and administrative costs, to avoid cost over-run and shortage of budget.

(5) Preparation of Alternatives for Compensation and Relocation Site Selection

The steering committees have a basic policy that the living environment has to be restored at least as same as original living standards. The resettlement sites are provided with infrastructures. Affected people have the right to live on the resettlement sites, however some may prefer to sell the right and move to somewhere by themselves.

(6) Negotiations

Expected major problems in this step are: miscommunication between steering committees and affected people; and poor participation in the resettlement process of the affected and host communities.

(7) Preparation of Relocation Site with Re-Creation of Social Environment

Restoration and improvement of the social environment is one of the most important policy for resettlement of the steering committees. Infrastructures and social services should be provided on the resettlement sites at least same levels of former dwelling. It should be considered that neighboring people or communities also enable to obtain the provided social services for their integration.

(8) Land Transfer and Relocation

The steering committees tend to relocate from the families who accept the compensation terms. However this fragmentary transfer may enhance risks for relocated people in the rehabilitation of living environment. Timely transfer co-ordinated with time tables of civil works should be carried out.

(9) Monitoring of Execution

It may occur that relocated people are neglected during the moving and rehabilitating their living environment. Then monitoring and communication by steering committees should be continued during implementation stage of relocation Programmes to avoid negligence toward the relocated people.

(10) Coping with Environmental Consequences during Construction Works

In the stage of execution of civil works, consequent troubles (noise, dust, vibration, cracks in the wall and etc.) and other unexpected troubles may occur. The steering committees have to take care of such situations, and submit and provide budgets for extra compensation beforehand.

18.2 Affected Sites and Relocation Policy

The alignment of SHTRR has been carefully designed to avoid relocations of resident and buildings. However some areas are unavoidable on the current design alignment, therefore the design has to be adjusted in detail design stage (Table 18.1 and Figure 18.1).

Unavoidable sites and properties should be compensated and relocated in accordance with the regulation of Hanoi People's Committee.

18.3 Land Acquisition and Resettlement Cost

The summary of estimated land acquisition and resettlement cost in the Project is shown in Table 18.2.

Table 18.2 Summary of Estimated Land Acquisition and Resettlement Cost

Compensation Items		Costs (Million VND)	Note
Compensation	1) Land compensation	20,890	
	2) Houses compensation	35,705	Level II or III
	3) Other building compensation	8,205	Graveyard included
	4) Crops compensation	5,376	
	Compensation total	70,176	
Subsidy	5) Personal subsidy	2,304	
	6) Business or trade subsidy	202	
	7) Assistance for recovering	8,794	
	8) Assistance for moving	281	
	Subsidy total	11,581	
Compensation and subsidy total		81,757	
Infrastructure cost for the resettlement sites		20,145	
Administration costs		4,087	5% of the
			compensation and subsidy costs
Allowance		11,878	
Grand Total		117,867	

Note: Refer to Table 14.2 in Section 14 for estimated cost by each package.

Table 18.1 Major Affected Sites and Properties on SHTRR

No.	Sites	Quantity	Note
1	· Housing sites (dense)	115 houses	along the NH1
2	Underground water exploitation companyTransport company	several buildings would be partially affected	along the NH1
3	· Office buildings · Housing sites (lined)	70 houses	along the Phap Van street
4	· Housing sites (scattered)	100 houses	along the Phap Van street
5	· Truck garage		along the Phap Van street
6	· Concrete factory		along the Phap Van street
7	· Treasury	2 storey building	along the Phap Van street
8	· Housing sites (dense)	60 houses	along the Phap Van street
9	· Housing sites (scattered)	55 houses	
10	· Housing sites (denser)	40 houses	a part of quarter
11	· Church	1 church	very close to the alignment
12	· Warehouses	3 small houses 2 larger houses	partially affected
13	· Housing sites (denser)	140 houses	a part of quarter
14	· Housing sites (dense)	20 houses	along the Mai Dong street
15	· Housing sites (scattered)	20 houses	close to Gia Lam dike
16	· Graveyard	3 graves	
17	· Housing sites (scattered)	10 houses	surrounded by rice paddy
18	· Housing sites (lined)	10 houses	along the NH5
19	· Beverage factory	2 workshops	partially affected





Figure 18.1 Major Affected Sites on SHTRR



19. CONCLUSION AND RECOMMENDATIONS

19.1 Necessity of the Project

The Project, which is to construct Thanh Tri Bridge and Southern Section of Hanoi Third Ring Road (SHTRR) is of great importance for the development of Hanoi capital region and is expected to play the following important roles:

- To improve and strengthen the road network in Hanoi capital region to cope with the future increase in vehicle traffic demand and rapid development in the region;
- To provide a by-pass road of national highway No. 1, since the existing roads in Hanoi central business district are seriously congested, especially in national highway No. 1 corridor; and
- To encourage increase in the traffic handling capacity of bridges crossing the Red River as a whole.

19.2 Future Traffic

The analysis of the socio-economic framework predicts that in the direct influence area of Hanoi city, the estimated total urbanized area in 2020 will become about 3.1 times that of 1997 and Gross Regional Product in 2000 is projected about 2.5 times that of 1990 at 1998 constant prices.

Under such a situation future traffic volume on Thanh Tri Bridge was forecast 73,100 PCU/day in 2010 and 111,700 PCU/day in 2020.

19.3 Conclusion in Technical Aspects

(1) Route

Three route alternatives were studied (Alternatives 1, 2b and 3). As a result of the comparison, it was concluded that Alternative-3 (least land acquisition effort scheme) is superior to other alternatives and selected as the optimum route.

(2) Type of Thanh Tri Main Bridge

Continuous PC box girder bridge scheme and PC cable stayed bridge scheme were examined in detail based on the comparative bridge design and economic analysis. PC

cable stayed bridge scheme was not selected as an optimum scheme because of higher cost compared with continuous PC box girder bridge scheme and economic analysis revealed that PC cable stayed bridge scheme is not economically feasible.

(3) Major Design Features

- 1) A 100 km/hr design speed will be applied as a urban expressway in flat terrain.
- 2) Lane width of the expressway (through traveled way) is 3.75 m with 3.0 m outer shoulder width and 1.0 m inner shoulder width.
- 3) Number of lanes of through traveled way in each construction package segment is shown in the following table.

Package No.	Section	Number of Lane
1	Thanh Tri Bridge	6
2	Thanh Tri Section of SHTRR	4
3	Gia Lam Section of SHTRR	4

- 4) Five interchanges, NH-1 IC (half cloverleaf), New NH-1 IC (Y-type), two dyke road IC (half diamond) and NH-5 IC (half cloverleaf) will be provided.
- 5) A barrier type toll gate will be provided in Package-3 section.
- 6) Flexible pavement was designed with a view to lower initial investment cost, better adoptability in embankment section and more comfortable riding condition than rigid pavement.

19.4 Project Cost

The Project cost is 4,465,037 million Dong in January 1998 prices as shown below:

Unit: Million Dong

Package No.	Section	Project Cost
1	Thanh Tri Bridge	2,928,955
2	Thanh Tri Section of SHTRR	1,067,111
3	Gia Lam Section of SHTRR	590,523
	Total	4,586,589

19.5 Results of Economic Analysis

The analysis followed the conventional discounted cash flow methodology in determining the EIRR, NPV and B/C ratio. The economic benefits quantified were the savings in vehicle operating and time costs. These results indicated that the Project is economically feasible.

Benefit cost ratio discounted at 12% 1.12

Net present value discounted at 12 % 329,449 million Dong

Economic internal rate of return 13.14 %

19.6 Results of Financial Analysis

Financial analysis is carried out for i). Project implementation by the Government and ii). Project implementation by private sector.

Two cases of toll levels are used for the estimation of revenue calculation as follows:

Case 1: To keep the same toll/users' benefit ratio of 45.2 % (present average of Thang Long bridge) until year 2020.

Case 2: To gradually increase toll/users' benefit ratio from 45.2 % (year 1998) to 70 % (year 2020).

The result of financial study revealed the following conclusions:

i) Project Implementation by the Government

Case 1: Obtained FIRR of 2.83 % is lower than the average interest rate of 4.61 % and judged to be financially not feasible.

Case 2: FIRR shows 5.64 % which is higher than the average interest rate of 4.61 % and the Project is judged to be financially feasible.

ii) Project Implementation by Private Sector

Cases 1 and 2: Calculated FIRRs are 2.80 % and 5.63 % for Case 1 and Case 2 respectively. These FIRRs are far lower than the average interest rate of 8.50 % and judged to be financially not feasible.

19.7 Recommendations

(1) Implementation of the Project

The results of the Study indicate that the Project is technically sound (no serious technical difficulty is anticipated for the construction) and economically feasible. Taking into account the direct and enormous indirect benefits towards regional development other than the quantified savings in travel costs, the Project should be implemented at the earliest opportunity.

(2) Land Acquisition and Resettlement

Delay of implementation would entail increasingly difficult land acquisition and resettlement due to the rapid development of the region, especially in Thanh Tri area. Arrangement of land acquisition and resettlement should commence immediately.

(3) Project Implementation Schedule

Proposed implementation schedule is to emphasize simultaneous commencement of services in all three construction sections, subject to due consideration on inevitable lead-time for land acquisition and resettlement, to optimize investment schedule.

(4) Construction Scheme for Thanh Tri Bridge

Such a stage construction scheme as widening from four lanes to six lanes in due time will entail diverse technical difficulties when applied to Thanh Tri Bridge. Thus it is recommendable to provide whole six lanes in the initial and single construction stage.

. . .



