

社会開発調査部報告書

116 22 4

JAPAN INTERNATIONAL CO-OPERATION ASSOCIATION

NATIONAL INSTITUTE OF INTERNATIONAL CO-OPERATION

100-8302 TOKYO, JAPAN

〒100-8302 東京都千代田区千代田

THE BUREAU OF ECONOMIC CO-OPERATION DEVELOPMENT

OF

THE GOVERNMENT OF IRELAND

OF

THE ECONOMIC DEVELOPMENT OF IRELAND

FINAL REPORT

OF THE DATA BOOK

(October 1988)

JICA LIBRARY



J1154100(0)

THE ECONOMIC CO-OPERATION DEVELOPMENT

OF THE GOVERNMENT OF IRELAND

116
22
4





JAPAN INTERNATIONAL COOPERATION AGENCY

NATIONAL INSTITUTE FOR WATER
RESOURCES AND MANAGEMENT
REPUBLIC OF CAPE VERDE

THE STUDY ON GROUNDWATER DEVELOPMENT
FOR
SANTIAGO ISLAND
IN
THE REPUBLIC OF CAPE VERDE

FINAL REPORT

Vol. 4 DATA BOOK

September 1999

KOKUSAI KOGYO CO., LTD., TOKYO
JAPAN TECHNO CO., LTD., TOKYO



1154100{0}



DATA BOOK

CONTENTS

1. RESISTIVITY PROFILES CORELATED WITH GEOLOGY
2. PROSESSED PUMPING TEST DATA
3. METEOROLOGICAL DATA
4. WATER SOURCE INVENTORY




RESISTIVITY PROFILES CORELATED WITH GEOLOGY

Cross Section of Electrical Resistivity Survey







LEGEND

- DI (sand, conglomerate)
- CA (Basement rocks)
- PA (volcanic lava flow)
- MA (volcanic lava & agglomerate)
- FI (tuff breccia, agglomerate)
- AI (sand, clay, conglomerate)
- CB (volcanic, tuff breccia)





Cross Section of Electrical Resistivity Survey















LEGEND

- Dt (sand, conglomerate)
- CA (Basement rocks)
- PA (volcanic lava flow)
- MA (volcanic lava & agglomerate)
- FI (tuff breccia, agglomerate)
- At (sand, clay, conglomerate)
- CB (volcanic, tuff breccia)



Cross Section of Electrical Resistivity Survey





PROSESSED PUMPING TEST DATA

ST-004

SST-10

FBE-116

FT-117

FBE-120

FBE-143

FBE-156

FBE-170

FBE-172

FBE-180

SST-25

FT-271

FBE-97





Fig. Result of Preliminary Test

Well No ST-004

S.W.L. (GL-m)


52.16

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	52.24	0.08	10.588	132.35	0.45
2	52.27	0.11	12.203	110.94	0.54
3	52.28	0.12	14.400	120.00	0.50
4	52.28	0.12	16.363	136.36	0.44
5	52.29	0.13	18.367	141.28	0.42
6	52.30	0.14	20.000	142.86	0.42
7	52.34	0.18	22.500	125.00	0.48
8	52.36	0.20	24.827	124.14	0.48
9	52.38	0.22	26.666	121.21	0.50
10	52.41	0.25	28.800	115.20	0.52
11	52.45	0.29	30.000	103.45	0.58
12	52.48	0.32	32.724	102.26	0.59



INGRH-JICA Groundwater Dev. Project		Pumping test analysis Time-Drawdown plot with discharge		ANNEX, Page 2	
				Project: JICA-INGRH	
				Evaluated by: KI	Date: 07.11.1998
Pumping Test No. SD			Test conducted on: 31/AUG/1998		
ST-004			ST-004		
Discharge 32.574 m ³ /h			Distance from the pumping well 0.100 m		
Static water level: 52.160 m below datum					
	Pumping test duration	Water level	Drawdown		
	[min]	[m]	[m]		
1	0.00	52.160	0.000		
2	2.00	52.220	0.060		
3	4.00	52.240	0.080		
4	6.00	52.250	0.090		
5	8.00	52.300	0.140		
6	10.00	52.340	0.180		
7	12.00	52.360	0.200		
8	14.00	52.370	0.210		
9	16.00	52.370	0.210		
10	20.00	52.370	0.210		
11	25.00	52.370	0.210		
12	30.00	52.370	0.210		
13	35.00	52.370	0.210		
14	40.00	52.370	0.210		
15	50.00	52.370	0.210		
16	60.00	52.370	0.210		
17	70.00	52.370	0.210		
18	80.00	52.370	0.210		
19	90.00	52.370	0.210		
20	120.00	52.370	0.210		
21	150.00	52.370	0.210		
22	152.00	52.400	0.240		
23	154.00	52.420	0.260		
24	156.00	52.430	0.270		
25	158.00	52.430	0.270		
26	160.00	52.430	0.270		
27	162.00	52.430	0.270		
28	164.00	52.440	0.280		
29	166.00	52.440	0.280		
30	170.00	52.440	0.280		
31	175.00	52.440	0.280		
32	180.00	52.440	0.280		
33	185.00	52.440	0.280		
34	190.00	52.440	0.280		
35	200.00	52.440	0.280		
36	210.00	52.440	0.280		
37	220.00	52.440	0.280		
38	230.00	52.440	0.280		
39	240.00	52.440	0.280		
40	270.00	52.440	0.280		
41	300.00	52.440	0.280		
42	302.00	52.440	0.280		
43	304.00	52.490	0.330		
44	306.00	52.500	0.340		
45	308.00	52.510	0.350		
46	310.00	52.510	0.350		
47	312.00	52.510	0.350		
48	314.00	52.510	0.350		
49	316.00	52.510	0.350		
50	320.00	52.510	0.350		

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 1	
		Project: JICA-INGRH	
		Evaluated by: KI	Date: 07.11.1998
Pumping Test No. SD		Test conducted on: 31/AUG/1998	
ST-004			
Discharge 32.574 m ³ /h			




INGRH-JICA Groundwater Dev. Project		Pumping test analysis Time-Drawdown plot with discharge		ANNEX, Page 2	
				Project: JICA-INGRH	
				Evaluated by: KI	Date: 07.11.1998
Pumping Test No. CR			Test conducted on: 2/SEP/1998		
ST-004			ST-004 cr		
Discharge 30.000 m ³ /h			Distance from the pumping well 0.100 m		
Static water level: 52.160 m below datum					
	Pumping test duration	Water level	Drawdown		
	[min]	[m]	[m]		
1	0.00	52.160	0.000		
2	2.00	52.370	0.210		
3	4.00	52.380	0.220		
4	6.00	52.400	0.240		
5	8.00	52.400	0.240		
6	10.00	52.400	0.240		
7	15.00	52.410	0.250		
8	20.00	52.420	0.260		
9	25.00	52.420	0.260		
10	30.00	52.430	0.270		
11	40.00	52.430	0.270		
12	50.00	52.430	0.270		
13	60.00	52.430	0.270		
14	70.00	52.430	0.270		
15	80.00	52.430	0.270		
16	90.00	52.430	0.270		
17	120.00	52.430	0.270		
18	150.00	52.430	0.270		
19	180.00	52.430	0.270		
20	210.00	52.430	0.270		
21	240.00	52.430	0.270		
22	300.00	52.430	0.270		
23	360.00	52.430	0.270		
24	420.00	52.430	0.270		
25	480.00	52.430	0.270		
26	540.00	52.430	0.270		
27	600.00	52.430	0.270		
28	660.00	52.430	0.270		
29	720.00	52.430	0.270		
30	780.00	52.430	0.270		
31	840.00	52.430	0.270		
32	900.00	52.430	0.270		
33	990.00	52.430	0.270		
34	1080.00	52.430	0.270		
35	1170.00	52.430	0.270		
36	1260.00	52.430	0.270		
37	1350.00	52.430	0.270		
38	1440.00	52.430	0.270		
39	1441.00	52.170	0.010		
40	1442.00	52.170	0.010		
41	1444.00	52.170	0.010		
42	1446.00	52.170	0.010		
43	1448.00	52.170	0.010		
44	1450.00	52.170	0.010		
45	1452.00	52.170	0.010		
46	1454.00	52.170	0.010		
47	1456.00	52.170	0.010		
48	1458.00	52.170	0.010		
49	1460.00	52.170	0.010		
50	1465.00	52.170	0.010		

Pumping Test No. CR

Test conducted on: 2/SEP/1998

ST-004

Discharge 30.000 m³/h




Pumping Test No. CR

Test conducted on: 2/SEP/1998

ST-004

Discharge 30.000 m³/h



Transmissivity (m²/min): 2.27×10^0

Storativity: 1.33×10^{-1}

INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Recovery method after
THEIS & JACOB
Confined aquifer

ANNEX, Page 1

Project: JICA-INGRH

Evaluated by: KI

Date: 07.11.1998

Pumping Test No. CR

Test conducted on: 2/SEP/1998

ST-004

Discharge 30.000 m³/h

Pumping test duration: 1440.00 min





Fig. Result of Preliminary Test

Well No SST-10

S.W.L. (GL-m)

93.60

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	93.61	0.01	5.027	502.70	0.12
2	93.61	0.01	7.031	703.10	0.09
3	93.61	0.01	9.000	900.00	0.07
4	93.61	0.01	11.250	1125.00	0.05
5	93.61	0.01	13.043	1304.30	0.05
6	93.61	0.01	15.254	1525.40	0.04
7	93.62	0.02	17.307	865.35	0.07
8	93.63	0.03	19.148	638.27	0.09
9	93.64	0.04	21.428	535.70	0.11
10	93.65	0.05	23.076	461.52	0.13
11	93.67	0.07	25.000	357.14	0.17
12	93.68	0.08	28.125	351.56	0.17




INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 2	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 30.11.1998

Pumping Test No. STEP-DRAWDOWN	Test conducted on: 24/10/98
SST-10	SST-10 SD
	Distance from the pumping well 0.100 m

Static water level: 93.610 m below datum

	Pumping test duration [min]	Water level [m]	Drawdown [m]	
1	0.00	93.610	0.000	
2	2.00	93.630	0.020	
3	4.00	93.640	0.030	
4	6.00	93.640	0.030	
5	8.00	93.640	0.030	
6	10.00	93.640	0.030	
7	12.00	93.640	0.030	
8	14.00	93.640	0.030	
9	16.00	93.640	0.030	
10	20.00	93.640	0.030	
11	25.00	93.640	0.030	
12	30.00	93.640	0.030	
13	35.00	93.640	0.030	
14	40.00	93.640	0.030	
15	50.00	93.640	0.030	
16	60.00	93.640	0.030	
17	70.00	93.640	0.030	
18	80.00	93.640	0.030	
19	90.00	93.640	0.030	
20	120.00	93.640	0.030	
21	150.00	93.640	0.030	
22	152.00	93.650	0.040	
23	154.00	93.660	0.050	
24	156.00	93.660	0.050	
25	158.00	93.660	0.050	
26	160.00	93.660	0.050	
27	162.00	93.660	0.050	
28	164.00	93.660	0.050	
29	166.00	93.660	0.050	
30	170.00	93.660	0.050	
31	175.00	93.660	0.050	
32	180.00	93.660	0.050	
33	185.00	93.660	0.050	
34	190.00	93.660	0.050	
35	200.00	93.660	0.050	
36	210.00	93.660	0.050	
37	220.00	93.660	0.050	
38	230.00	93.660	0.050	
39	240.00	93.660	0.050	
40	270.00	93.660	0.050	
41	300.00	93.660	0.050	
42	302.00	93.660	0.050	
43	304.00	93.660	0.050	
44	306.00	93.660	0.050	
45	308.00	93.660	0.050	
46	310.00	93.660	0.050	
47	312.00	93.660	0.050	
48	314.00	93.660	0.050	
49	316.00	93.660	0.050	
50	318.00	93.660	0.050	

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 1	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 30.11.1998
Pumping Test No. STEP-DRAWDOWN		Test conducted on: 24/10/98	
SST-10			



o SST-10 SD

INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Time-Drawdown plot
with discharge

ANNEX, Page 2

Project: INGRH-JICA

Evaluated by: KI

Date: 30.11.1998

Pumping Test No. CR

Test conducted on: 26/10/98

SST-10

SST-10 CR

Discharge 34.285 m³/h

Distance from the pumping well 0.100 m

Static water level: 93.600 m below datum


	Pumping test duration	Water level	Drawdown
	[min]	[m]	[m]
1	0.00	93.600	0.000
2	2.00	93.680	0.080
3	4.00	93.680	0.080
4	6.00	93.680	0.080
5	8.00	93.680	0.080
6	10.00	93.680	0.080
7	15.00	93.680	0.080
8	20.00	93.680	0.080
9	25.00	93.680	0.080
10	30.00	93.680	0.080
11	40.00	93.680	0.080
12	50.00	93.680	0.080
13	60.00	93.680	0.080
14	70.00	93.680	0.080
15	80.00	93.690	0.090
16	90.00	93.690	0.090
17	120.00	93.690	0.090
18	150.00	93.690	0.090
19	180.00	93.690	0.090
20	210.00	93.700	0.100
21	240.00	93.700	0.100
22	300.00	93.710	0.110
23	360.00	93.710	0.110
24	420.00	93.720	0.120
25	480.00	93.720	0.120
26	540.00	93.720	0.120
27	600.00	93.720	0.120
28	660.00	93.720	0.120
29	720.00	93.720	0.120
30	780.00	93.720	0.120
31	840.00	93.720	0.120
32	900.00	93.720	0.120
33	990.00	93.720	0.120
34	1080.00	93.730	0.130
35	1170.00	93.740	0.140
36	1260.00	93.740	0.140
37	1350.00	93.740	0.140
38	1440.00	93.740	0.140
39	1441.00	93.650	0.050
40	1442.00	93.650	0.050
41	1444.00	93.650	0.050
42	1446.00	93.640	0.040
43	1448.00	93.640	0.040
44	1450.00	93.640	0.040
45	1452.00	93.640	0.040
46	1454.00	93.640	0.040
47	1456.00	93.640	0.040
48	1458.00	93.640	0.040
49	1460.00	93.640	0.040
50	1465.00	93.630	0.030

Pumping Test No. CR

Test conducted on: 26/10/98

SST-10

Discharge 34.285 m³/h



INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Theis analysis method
Confined aquifer

ANNEX, Page 1

Project: INGRH-JICA

Evaluated by: KI


Date: 30.11.1998

Pumping Test No. CR

Test conducted on: 26/10/98

SST-10

Dischargo 34.285 m³/h



Transmissivity [m²/min]: 4.45×10^0

Storativity: 6.27×10^0

INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Time-Drawdown-method after
COOPER & JACOB
Confined aquifer

ANNEX, Page 1

Project: INGRH-JICA

Evaluated by: KI


Date: 30.11.1998

Pumping Test No. CR

Test conducted on: 26/10/98

SST-10

Discharge 34.285 m³/h



Transmissivity [m²/min]: 3.91×10^0

Storativity: 1.81×10^{-1}


Fig. Result of Preliminary Test

Well No FBE-116

S.W.L. (GL-m)

121.26

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	122.60	1.34	3.214	2.40	25.02
2	123.40	2.14	4.500	2.10	28.53
3	123.54	2.28	5.806	2.55	23.56
4	124.45	3.19	6.923	2.17	27.65
5	124.85	3.59	8.181	2.28	26.33
6	125.30	4.04	9.677	2.40	25.05
7	125.44	4.18	10.588	2.53	23.89
8	126.56	5.30	11.842	2.23	26.85
9	126.86	5.60	12.857	2.30	26.13
10	127.50	6.24	13.846	2.22	27.04
11	128.02	6.76	15.000	2.22	27.04
12	128.82	7.56	16.363	2.16	27.72



Pumping Test No. SD

Test conducted on: 9/OCT/1998

FBE-116

FBE-116 SD

Discharge 16.392 m³/h

Distance from the pumping well 0.100 m

Static water level: 121.300 m below datum


	Pumping test duration	Water level	Drawdown
	[min]	[m]	[m]
1	0.00	121.300	0.000
2	2.00	124.000	2.700
3	4.00	124.700	3.400
4	6.00	124.910	3.610
5	8.00	125.070	3.770
6	10.00	125.150	3.850
7	12.00	125.220	3.920
8	14.00	125.310	4.010
9	16.00	125.400	4.100
10	20.00	125.620	4.320
11	25.00	125.900	4.600
12	30.00	126.300	5.000
13	35.00	126.720	5.420
14	40.00	127.050	5.750
15	50.00	127.090	5.790
16	60.00	127.150	5.850
17	70.00	127.200	5.900
18	80.00	126.260	4.960
19	90.00	127.330	6.030
20	120.00	127.400	6.100
21	150.00	127.490	6.190
22	152.00	130.160	8.860
23	154.00	130.400	9.100
24	156.00	130.630	9.330
25	158.00	130.800	9.500
26	160.00	130.800	9.500
27	162.00	130.800	9.500
28	164.00	130.800	9.500
29	166.00	130.800	9.500
30	170.00	130.800	9.500
31	175.00	130.910	9.610
32	180.00	131.120	9.820
33	185.00	131.170	9.870
34	190.00	131.300	10.000
35	200.00	131.320	10.020
36	210.00	131.360	10.060
37	220.00	131.400	10.100
38	230.00	131.440	10.140
39	240.00	131.480	10.180
40	270.00	131.560	10.260
41	300.00	131.670	10.370
42	302.00	140.100	18.800
43	304.00	140.820	19.520
44	306.00	141.000	19.700
45	308.00	141.190	19.890
46	310.00	141.300	20.000
47	312.00	141.430	20.130
48	314.00	141.560	20.260
49	316.00	141.700	20.400
50	320.00	141.980	20.680

Pumping Test No. SD

Test conducted on: 9/OCT/1998

FBE-116

Discharge 16.392 m³/h



o FBE-116 SD

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 2	
		Project: JICA-INGRH	
		Evaluated by: KI	Date: 06.11.1998


Pumping Test No. CR	Test conducted on: 13/OCT/1998
FBE-116	FBE-116 CR
Discharge 20.000 m ³ /h	Distance from the pumping well 0.100 m

Static water level: 121.300 m below datum

	Pumping test duration	Water level	Drawdown
	[min]	[m]	[m]
1	0.00	121.300	0.000
2	2.00	126.600	5.300
3	4.00	132.880	11.580
4	6.00	133.950	12.650
5	8.00	134.250	12.950
6	10.00	134.650	13.350
7	15.00	134.900	13.600
8	20.00	135.900	14.600
9	25.00	136.910	15.610
10	30.00	137.200	15.900
11	40.00	137.790	16.490
12	50.00	137.790	16.490
13	60.00	137.790	16.490
14	70.00	137.820	16.520
15	80.00	137.820	16.520
16	90.00	137.820	16.520
17	120.00	137.830	16.530
18	150.00	137.900	16.600
19	180.00	138.000	16.700
20	210.00	138.040	16.740
21	240.00	138.090	16.790
22	300.00	138.340	17.040
23	360.00	138.400	17.100
24	420.00	138.500	17.200
25	480.00	138.500	17.200
26	540.00	138.500	17.200
27	600.00	138.520	17.220
28	660.00	138.680	17.380
29	720.00	138.680	17.380
30	780.00	138.700	17.400
31	840.00	138.720	17.420
32	900.00	138.800	17.500
33	990.00	138.860	17.560
34	1080.00	138.900	17.600
35	1170.00	138.960	17.660
36	1260.00	139.000	17.700
37	1350.00	139.030	17.730
38	1440.00	139.050	17.750
39	1441.00	123.240	1.940
40	1442.00	122.300	1.000
41	1444.00	121.740	0.440
42	1446.00	121.660	0.360
43	1448.00	121.640	0.340
44	1450.00	121.630	0.330
45	1452.00	121.620	0.320
46	1454.00	121.610	0.310
47	1456.00	121.600	0.300
48	1458.00	121.600	0.300
49	1460.00	121.600	0.300
50	1465.00	121.590	0.290


INGRII-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 1	
		Project: JICA-INGRII	
		Evaluated by: KI	Date: 06.11.1998

Pumping Test No. CR	Test conducted on: 13/OCT/1998
FBE-116	
Discharge 20.000 m ³ /h	



○ FBE-116 CR

INGRRH-JICA Groundwater Dev. Project	Pumping test analysis Theis analysis method Confined aquifer	ANNEX, Page 1	
		Project: JICA-INGRRH	
		Evaluated by: KI	Date: 06.11.1998
Pumping Test No. CR		Test conducted on: 13/OCT/1998	
FBE-116			
Discharge 20.000 m ³ /h			



Transmissivity [m²/min]: 2.17×10^{-2}

Storativity: 1.25×10^{-3}

INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Time-Drawdown-method after
COOPER & JACOB
Confined aquifer

ANNEX, Page 1

Project: JICA-INGRH

Evaluated by: KI


Date: 06.11.1998

Pumping Test No. CR

Test conducted on: 13/OCT/1998

FBE-116


Discharge 20.000 m³/h



Transmissivity [m²/min]: 2.05×10^{-2}

Storativity: 2.53×10^{-3}

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Recovery method after THEIS & JACOB Confined aquifer	ANNEX, Page 1	
		Project: JICA-INGRH	
		Evaluated by: KI	Date: 06.11.1998
Pumping Test No. CR	Test conducted on: 13/OCT/1998		
FBE-116			
Discharge 20.000 m³/h			
Pumping test duration: 1460.00 min			



Transmissivity [m^2/min]: 6.04×10^{-1}


Fig. Result of Preliminary Test

Well No FT-117

S.W.L. (GL-m)

33.50

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	42.14	8.64	3.103	0.36	167.06
2	46.68	13.18	4.090	0.31	193.35
3	52.19	18.69	5.000	0.27	224.28
4	63.00	29.50	6.000	0.20	295.00
5	63.00	29.50	4.000	0.14	442.50
6	63.10	29.60	3.501	0.12	507.28
7	54.99	21.49	2.727	0.13	472.83



INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 2	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998

Pumping Test No. PRE	Test conducted on: 5/11/98
FT-117	FT-117
Discharge 3.774 m ³ /h	Distance from the pumping well 0.100 m
Static water level: 33.500 m below datum	


	Pumping test duration	Water level	Drawdown	
	[min]	[m]	[m]	
1	0.00	33.500	0.000	
2	5.00	37.470	3.970	
3	10.00	38.800	5.300	
4	20.00	39.610	6.110	
5	30.00	40.520	7.020	
6	40.00	40.700	7.200	
7	50.00	41.770	8.270	
8	60.00	42.140	8.640	
9	65.00	44.820	11.320	
10	70.00	44.930	11.430	
11	80.00	45.500	12.000	
12	90.00	45.850	12.350	
13	100.00	46.260	12.760	
14	110.00	46.540	13.040	
15	120.00	46.680	13.180	
16	125.00	48.900	15.400	
17	130.00	49.280	15.780	
18	140.00	50.020	16.520	
19	150.00	50.640	17.140	
20	160.00	51.250	17.750	
21	170.00	51.680	18.180	
22	180.00	52.190	18.690	
23	185.00	53.870	20.370	
24	190.00	54.910	21.410	
25	200.00	55.820	22.320	
26	210.00	57.330	23.830	
27	220.00	60.330	26.830	
28	230.00	63.000	29.500	
29	240.00	55.390	21.890	
30	250.00	54.960	21.460	
31	260.00	54.520	21.020	
32	270.00	54.420	20.920	
33	290.00	54.570	21.070	
34	300.00	54.700	21.200	
35	310.00	54.920	21.420	
36	320.00	55.010	21.510	
37	330.00	55.150	21.650	
38	340.00	55.380	21.880	
39	350.00	55.550	22.050	
40	360.00	55.700	22.200	
41	370.00	55.890	22.390	
42	380.00	56.300	22.800	
43	390.00	56.440	22.940	
44	400.00	56.570	23.070	
45	410.00	56.650	23.150	
46	420.00	58.820	25.320	
47	430.00	60.580	27.080	
48	440.00	61.310	27.810	
49	450.00	63.000	29.500	
50	460.00	55.470	21.970	

Pumping Test No. PRE

Test conducted on: 5/11/98

FT-117

Discharge 3.774 m³/h




o FT-117

Pumping Test No. PRE

Test conducted on: 5/11/98

FT-117


Discharge 3.774 m³/h



Transmissivity [m²/min]: 8.97×10^{-4}

Storativity: 1.38×10^0

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown-method after COOPER & JACOB Confined aquifer	ANNEX, Page 1	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998
Pumping Test No. PRE		Test conducted on: 5/11/98	
FT-117			
Discharge 3.774 m ³ /h			



Transmissivity [m²/min]: 8.54×10^{-4}
 Storativity: 1.58×10^0


Fig. Result of Preliminary Test

Well No FBE-120

S.W.L. (GL-m)

114.60

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	114.95	0.35	3.214	9.18	6.53
2	115.14	0.54	4.285	7.94	7.56
3	115.32	0.72	5.294	7.35	8.16
4	115.70	1.10	6.338	5.76	10.41
5	115.80	1.20	7.200	6.00	10.00
6	115.90	1.30	8.333	6.41	9.36
7	116.10	1.50	9.473	6.32	9.50
8	116.40	1.80	10.588	5.88	10.20
9	116.60	2.00	11.538	5.77	10.40
10	117.00	2.40	12.857	5.36	11.20
11	117.58	2.98	13.846	4.65	12.91
12	117.99	3.39	15.000	4.42	13.56



Pumping Test No. SD	Test conducted on: 2/OCT/1998
FBE-120	FBE-120 SD
Discharge 20.313 m ³ /h	Distance from the pumping well 0.100 m

Static water level: 114.400 m below datum


	Pumping test duration	Water level	Drawdown	
	[min]	[m]	[m]	
1	0.00	114.400	0.000	
2	2.00	116.500	2.100	
3	4.00	116.520	2.120	
4	6.00	116.660	2.260	
5	8.00	116.720	2.320	
6	10.00	116.870	2.470	
7	12.00	116.950	2.550	
8	14.00	117.000	2.600	
9	16.00	117.050	2.650	
10	20.00	117.300	2.900	
11	25.00	117.440	3.040	
12	30.00	117.500	3.100	
13	35.00	117.530	3.130	
14	40.00	117.560	3.160	
15	50.00	117.620	3.220	
16	60.00	117.660	3.260	
17	70.00	117.770	3.370	
18	80.00	117.800	3.400	
19	90.00	117.850	3.450	
20	120.00	117.900	3.500	
21	150.00	117.900	3.500	
22	152.00	118.980	4.580	
23	154.00	119.060	4.660	
24	156.00	119.160	4.760	
25	158.00	119.220	4.820	
26	160.00	119.300	4.900	
27	162.00	119.350	4.950	
28	164.00	119.370	4.970	
29	166.00	119.390	4.990	
30	170.00	119.500	5.100	
31	175.00	119.550	5.150	
32	180.00	119.570	5.170	
33	185.00	119.600	5.200	
34	190.00	119.620	5.220	
35	200.00	119.650	5.250	
36	210.00	119.670	5.270	
37	220.00	119.700	5.300	
38	230.00	119.730	5.330	
39	240.00	119.730	5.330	
40	270.00	119.770	5.370	
41	300.00	119.780	5.380	
42	302.00	120.250	5.850	
43	304.00	120.340	5.940	
44	306.00	120.390	5.990	
45	308.00	120.420	6.020	
46	310.00	120.440	6.040	
47	312.00	120.480	6.080	
48	314.00	120.480	6.080	
49	316.00	120.480	6.080	
50	320.00	120.490	6.090	

Pumping Test No. SD

Test conducted on: 2/OCT/1998

FBE-120

Discharge 20.313 m³/h



Pumping Test No. CR	Test conducted on: 5/OCT/1998
FBE-120	FBE-120 CR
Discharge 25.714 m ³ /h	Distance from the pumping well 0.100 m

Static water level: 114.400 m below datum


	Pumping test duration	Water level	Drawdown
	[min]	[m]	[m]
1	0.00	114.400	0.000
2	2.00	118.350	3.950
3	4.00	118.800	4.400
4	6.00	119.020	4.620
5	8.00	119.320	4.920
6	10.00	119.450	5.050
7	15.00	119.640	5.240
8	20.00	119.750	5.350
9	25.00	119.850	5.450
10	30.00	119.900	5.500
11	35.00	120.000	5.600
12	40.00	120.070	5.670
13	50.00	120.150	5.750
14	60.00	120.220	5.820
15	70.00	120.280	5.880
16	80.00	120.320	5.920
17	90.00	120.360	5.960
18	120.00	120.440	6.040
19	150.00	120.500	6.100
20	180.00	120.540	6.140
21	210.00	120.570	6.170
22	240.00	120.600	6.200
23	300.00	120.650	6.250
24	360.00	120.750	6.350
25	420.00	120.750	6.350
26	480.00	120.750	6.350
27	540.00	120.760	6.360
28	600.00	120.780	6.380
29	660.00	120.800	6.400
30	720.00	120.820	6.420
31	721.00	117.360	2.960
32	722.00	116.930	2.530
33	724.00	116.470	2.070
34	726.00	116.240	1.840
35	728.00	116.090	1.690
36	730.00	115.980	1.580
37	732.00	115.860	1.460
38	734.00	115.780	1.380
39	736.00	115.690	1.290
40	738.00	115.640	1.240
41	740.00	115.590	1.190
42	745.00	115.460	1.060
43	750.00	115.400	1.000
44	760.00	115.260	0.860
45	770.00	115.170	0.770
46	780.00	115.080	0.680
47	790.00	115.020	0.620
48	800.00	114.980	0.580
49	810.00	114.950	0.550
50	820.00	114.910	0.510

Pumping Test No. CR

Test conducted on: 5/OCT/1998

FBE-120

Discharge 25.714 m³/h



INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Theis analysis method
Confined aquifer

ANNEX, Page 1

Project: JICA-INGRH

Evaluated by: KI


Date: 06.11.1998

Pumping Test No. CR

Test conducted on: 5/OCT/1998

FBE-120


Discharge 25.714 m³/h



Transmissivity [m²/min]: 7.74×10^{-2}

Storativity: 2.52×10^{-3}

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown-method after COOPER & JACOB Confined aquifer	ANNEX, Page 1	
		Project: JICA-INGRH	
		Evaluated by: KI	Date: 06.11.1998
Pumping Test No. CR	Test conducted on: 5/OCT/1998		
FBE-120			
Discharge 25.714 m ³ /h			



Transmissivity [m²/min]: 8.68×10^{-2}

Storativity: 6.19×10^{-4}

INGRH-JICA
Groundwater Dev. Project

Pumping test analysis
Recovery method after
THEIS & JACOB
Confined aquifer

ANNEX, Page 1

Project: JICA-INGRH

Evaluated by: KI

Date: 06.11.1998


Pumping Test No. CR

Test conducted on: 5/OCT/1998

FBE-120

Discharge 25.714 m³/h

Pumping test duration: 720.00 min




Transmissivity [m²/min]: 6.41×10^{-2}

Fig. Result of Preliminary Test

Well No FBE-143 S.W.L. (GL-m) 7.80

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	7.85	0.05	3.214	64.28	0.93
2	7.86	0.06	4.285	71.42	0.84
3	7.89	0.09	5.294	58.82	1.02
4	7.95	0.15	6.428	42.85	1.40
5	7.96	0.16	7.500	46.88	1.28
6	7.97	0.17	8.571	50.42	1.19
7	8.00	0.20	9.473	47.37	1.27
8	8.03	0.23	10.588	46.03	1.30
9	8.10	0.30	11.538	38.46	1.56
10	8.15	0.35	12.500	35.71	1.68
11	8.19	0.39	13.846	35.50	1.69
12	8.21	0.41	14.516	35.40	1.69



Pumping Test No. SD	Test conducted on: 10/SEP/1998
FBE-143	STEP
Discharge 24.327 m ³ /h	Distance from the pumping well 0.100 m

Static water level: 7.050 m below datum


	Pumping test duration [min]	Water level [m]	Drawdown [m]	
1	0.00	7.800	0.750	
2	2.00	8.050	1.000	
3	4.00	8.070	1.020	
4	6.00	8.100	1.050	
5	8.00	8.120	1.070	
6	10.00	8.120	1.070	
7	12.00	8.120	1.070	
8	14.00	8.120	1.070	
9	16.00	8.120	1.070	
10	20.00	8.120	1.070	
11	25.00	8.120	1.070	
12	30.00	8.120	1.070	
13	35.00	8.120	1.070	
14	40.00	8.120	1.070	
15	50.00	8.120	1.070	
16	60.00	8.120	1.070	
17	70.00	8.120	1.070	
18	80.00	8.120	1.070	
19	90.00	8.120	1.070	
20	120.00	8.120	1.070	
21	150.00	8.120	1.070	
22	152.00	8.220	1.170	
23	154.00	8.220	1.170	
24	156.00	8.220	1.170	
25	158.00	8.230	1.180	
26	160.00	8.230	1.180	
27	162.00	8.230	1.180	
28	164.00	8.230	1.180	
29	166.00	8.230	1.180	
30	170.00	8.230	1.180	
31	175.00	8.230	1.180	
32	180.00	8.230	1.180	
33	185.00	8.240	1.190	
34	190.00	8.240	1.190	
35	200.00	8.240	1.190	
36	210.00	8.240	1.190	
37	220.00	8.240	1.190	
38	230.00	8.240	1.190	
39	240.00	8.240	1.190	
40	270.00	8.240	1.190	
41	300.00	8.240	1.190	
42	302.00	8.440	1.390	
43	304.00	8.560	1.510	
44	306.00	8.570	1.520	
45	308.00	8.580	1.530	
46	310.00	8.580	1.530	
47	312.00	8.580	1.530	
48	314.00	8.580	1.530	
49	316.00	8.580	1.530	
50	320.00	8.590	1.540	

Pumping Test No. SD

Test conducted on: 10/SEP/1998

FBE-143

Discharge 24.327 m³/h




Pumping Test No. CR

Test conducted on: 14/SEP/1998


FBE-143

Discharge 37.894 m³/h



◦ FBE-143


INGRH-JICA Groundwater Dev. Project	Pumping test analysis Theis analysis method Confined aquifer	ANNEX, Page 1	
		Project: JICA-INGRH	
		Evaluated by: KI	Date: 07.11.1998
Pumping Test No. CR		Test conducted on: 14/SEP/1998	
FBE-143			
Discharge 37.894 m ³ /h			



Transmissivity [m²/min]: 6.08×10^{-1}

Storativity: 4.38×10^{-3}

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown-method after COOPER & JACOB Confined aquifer	ANNEX, Page 1	
		Project: JICA-INGRH	
		Evaluated by: KI	Date: 07.11.1998
Pumping Test No. CR		Test conducted on: 14/SEP/1998	
FBE-143			
Discharge 37.894 m³/h			




o FBE-143

Transmissivity [m²/min]: 2.02×10^0

Storativity: 3.46×10^{-16}

INGRII-JICA Groundwater Dev. Project	Pumping test analysis Recovery method after THEIS & JACOB Confined aquifer	ANNEX, Page 1	
		Project: JICA-INGRH	
		Evaluated by: Ki	Date: 07.11.1998
Pumping Test No. CR	Test conducted on: 14/SEP/1998		
FBE-143			
Discharge 37.894 m ³ /h			
Pumping test duration: 180.00 min			



Transmissivity [m²/min]: 1.40 x 10⁰


Fig. Result of Preliminary Test

Well No FBE-156

S.W.L. (GL-m)

111.69

Step	Water Level (GL-m)	Drawdown (m)	Discharge (m ³ /h)	SC (m ³ /h/m)	SW/Q (m/m ³ /min)
1	112.23	0.54	3.214	5.95	10.08
2	112.36	0.67	4.090	6.10	9.83
3	112.64	0.95	5.000	5.26	11.40
4	112.88	1.19	6.000	5.04	11.90
5	113.18	1.49	7.031	4.72	12.72
6	113.66	1.97	8.035	4.08	14.71
7	113.83	2.14	9.000	4.21	14.27
8	113.98	2.29	10.000	4.37	13.74
9	114.07	2.38	10.588	4.45	13.49




INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 2	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998

Pumping Test No. SD	Test conducted on: 31/10/98
FBE-156	FBE-156 SD
Discharge 6.696 m ³ /h	Distance from the pumping well 0.100 m

Static water level: 111.700 m below datum

	Pumping test duration	Water level	Drawdown
	[min]	[m]	[m]
1	0.00	111.700	0.000
2	2.00	111.910	0.210
3	4.00	111.980	0.280
4	6.00	112.070	0.370
5	8.00	112.100	0.400
6	10.00	112.130	0.430
7	12.00	112.150	0.450
8	14.00	112.150	0.450
9	16.00	112.150	0.450
10	20.00	112.150	0.450
11	25.00	112.150	0.450
12	30.00	112.150	0.450
13	35.00	112.150	0.450
14	40.00	112.150	0.450
15	50.00	112.150	0.450
16	60.00	112.150	0.450
17	70.00	112.150	0.450
18	80.00	112.150	0.450
19	90.00	112.150	0.450
20	120.00	112.150	0.450
21	150.00	112.150	0.450
22	152.00	112.420	0.720
23	154.00	112.520	0.820
24	156.00	112.600	0.900
25	158.00	112.660	0.960
26	160.00	112.660	0.960
27	162.00	112.660	0.960
28	164.00	112.660	0.960
29	166.00	112.660	0.960
30	170.00	112.660	0.960
31	175.00	112.660	0.960
32	180.00	112.660	0.960
33	185.00	112.660	0.960
34	190.00	112.660	0.960
35	200.00	112.660	0.960
36	210.00	112.660	0.960
37	220.00	112.660	0.960
38	230.00	112.660	0.960
39	240.00	112.660	0.960
40	270.00	112.670	0.970
41	300.00	112.670	0.970
42	302.00	113.290	1.590
43	304.00	113.310	1.610
44	306.00	113.320	1.620
45	308.00	113.320	1.620
46	310.00	113.320	1.620
47	312.00	113.320	1.620
48	314.00	113.320	1.620
49	316.00	113.320	1.620
50	320.00	113.320	1.620

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 1	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998
Pumping Test No. SD		Test conducted on: 31/10/98	
FBE-156			
Discharge 6.696 m ³ /h			



o FBE-156 SD


INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 2	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998

Pumping Test No. SREP-DRAWDOWN	Test conducted on: 8/11/98
FBE-156	FBE-156 CR
Discharge 9.000 m ³ /h	Distance from the pumping well 0.100 m

Static water level: 111.700 m below datum


	Pumping test duration	Water level	Drawdown	
	[min]	[m]	[m]	
1	0.00	111.700	0.000	
2	2.00	112.670	0.970	
3	4.00	113.810	2.110	
4	6.00	113.860	2.160	
5	8.00	113.870	2.170	
6	10.00	113.870	2.170	
7	15.00	113.870	2.170	
8	20.00	113.870	2.170	
9	25.00	113.870	2.170	
10	30.00	113.870	2.170	
11	40.00	113.870	2.170	
12	50.00	113.870	2.170	
13	60.00	113.870	2.170	
14	70.00	113.870	2.170	
15	80.00	113.870	2.170	
16	90.00	113.870	2.170	
17	120.00	113.870	2.170	
18	150.00	113.870	2.170	
19	180.00	113.870	2.170	
20	210.00	113.870	2.170	
21	240.00	113.870	2.170	
22	300.00	113.870	2.170	
23	360.00	113.870	2.170	
24	420.00	113.870	2.170	
25	480.00	113.870	2.170	
26	540.00	113.870	2.170	
27	600.00	113.870	2.170	
28	660.00	113.870	2.170	
29	720.00	113.870	2.170	
30	780.00	113.870	2.170	
31	840.00	113.870	2.170	
32	900.00	113.870	2.170	
33	990.00	113.870	2.170	
34	1080.00	113.870	2.170	
35	1170.00	113.870	2.170	
36	1260.00	113.870	2.170	
37	1350.00	113.870	2.170	
38	1440.00	113.870	2.170	
39	1441.00	111.770	0.070	
40	1442.00	111.730	0.030	
41	1444.00	111.730	0.030	
42	1446.00	111.720	0.020	
43	1448.00	111.720	0.020	
44	1450.00	111.720	0.020	
45	1452.00	111.710	0.010	
46	1454.00	111.710	0.010	
47	1456.00	111.710	0.010	
48	1458.00	111.710	0.010	
49	1460.00	111.710	0.010	
50	1465.00	111.710	0.010	

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Time-Drawdown plot with discharge	ANNEX, Page 1	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998
Pumping Test No. SREP-DRAWDOWN		Test conducted on: 8/11/98	
FBE-156			
Discharge 9.000 m³/h			



◦ FBE-156 CR

INGRH-JICA Groundwater Dev. Project	Pumping test analysis Theis analysis method Confined aquifer	ANNEX, Page 1	
		Project: INGRH-JICA	
		Evaluated by: KI	Date: 01.12.1998
Pumping Test No. SREP-DRAWDOWN		Test conducted on: 8/11/98	
FBE-156			
Discharge 9.000 m³/h			



Transmissivity [m²/min]: 7.40×10^{-2}

Storativity: 4.26×10^{-3}