14.5 Impact of the Project on Environment and Mitigation Measures

14.5.1 Preparation of the Land and Activities during Construction and Installation Stage

The detailed information can be obtained in "Preliminary Design of Cimsa Site Development of Annex 9 in Volume III".

Main construction activities consist of planting of green trees in buffer zone, earthworks for disposal site (phase 1, 2 and 3) and intermediate plant site, building of sorting plant and compost plant, and construction of medical waste disposal site and leachate treatment facility.

As shown in Figure 14-38 construction will start at phase 1 site and shift to phase 2 and 3 in order. The depth of cutting is approximately 15m and the height of filling is around 5m as shown by the cross section of A-A, B-B and C-C in Figure 14-39. The numbers show the height at the bottom of the site. Phase 3 site is constructed before termination of the operation at phase 2 site.





Figure 14-38: The Plan of the Proposed Disposal Site



A14-67