

1

4.4.2 Auxiliary Structures

(1) Connecting Reservoir, CR4

(a) General

1

Connecting reservoir is required for smooth conveyance of water from pressurized pipeline of diameter 700mm to the pipeline of diameter 600 by gravity.

(b) Design Conditions

1) Finished Ground Level

- F.G.L.: EL. 190.0 m

2) Water Level in the Reservoir

- H.W.L. : EL. 194.0 m - L.W.L. : EL. 189.0 m

3) Required storage capacity As same as CR2.

(c) Design of Connecting Reservoir

The dimensions of CR4 are the same as CR1 and CR2 as shown in Figure-4.5.

(d) Sequence of Construction

One basin of CR4 with the storage capacity of 1,500m³ is constructed in Phase 1 and the other basin with the same capacity is constructed in Phase 2.


(2) One Way Surge Tank


(a) Design Conditions

| No. | Location(m) | Ground Elevation(EL. m) | W.L.(EL. m) | Cross section Area (m²) | Height(m) |
|-----|-------------|-------------------------|-------------|-------------------------|-----------|
| 1 | 3,300 | 150.0 | > 160.0 | 10 | > 3.0 |
| 2 | 6,200 | 186.0 | > 195.0 | 10 | > 5.0 |


(b) Design of Surge Tank

One way surge tank is elevated reinforced concrete tank as shown in Figure-4.19 and is constructed in Phase 1.





4






Figure-4.19 Surge Tank

4.5 Agreste Water Conveyance Pipeline

4.5.1 Characteristics of Pipeline

Characteristics of Pipeline route determined based on the water conveyance plan in CHAPTER 3 are as follows:

(1) Design Conditions

Service Pressure in the Pipeline

Permissible Service Pressure : 2.10Mpa
Maximum Service Pressure : 2.88Mpa

(2) Materials

Unless otherwise specified, all pipe materials are ductile cast iron.

Class of Push-on Joint Type pipe will be K7 in accordance with the Service pressure in the pipeline.

(3) Length

1.

 ϕ 700 : 8,784 m

 ϕ 500 : 7,659 m per Phase (total length in two phases 15,318 m) ϕ 600 : 7,529 m per Phase (total length in two phases 15,058 m)

(4) Ground Elevation

Vertical profile of the pipeline is shown in Figure-4.20.

Lowest elevation: MSL+40m Highest elevation: MSL+240m

(5) Conditions of Ground Surface in Pipeline Route

Type of ground surface and its length is as follows:

Pasture : 19,055 m Bare land : 4,138 m Pavement : 160 m Over-pass : 610 m


(6) Details of Over-pass


(a) Vaza Barris Dam Crossing

- Pipe runs on the crest of dam in non-overflow portion with length of 280m
- Pipe runs on the support bridge over spillway with length of 150m. The bridge is supported by piers constructed in the spillway.
- Materials of pipe are carbon steel.

(b) Ribeira River Crossing

- 40m of river crossing
- Pipes to cross over the river with reinforced concrete pier constructed at 6m interval





| 그는 사람들은 그는 그는 그는 그는 그는 것이 되는 것이 되었다. 사람들은 사람들은 사람들은 사람들은 사람들은 사람들은 사람들은 사람들은 | |
|--|--|
| | |
| 으로 보고 있는 것이 되는 것이 되는 것이 되는 것이 되었다. 그런 | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

(c) Small River Crossings

- 20m and 40m of river crossings
- Pipes to cross over the river with reinforced concrete pier constructed at 6m interval

(d) Moca River Crossing

- 20m of river crossing
- Pipes to cross over the river with reinforced concrete pier constructed at 6m interval

(e) Pedras River Crossing

- 50m of river crossing
- Pipes to cross over the river with reinforced concrete pier constructed at the center of the river
- Materials of pipe are carbon steel.

(f) Marsh Crossing

- 110m of marsh crossing
- Pipes to cross over the marsh with reinforced concrete support constructed at 6m interval

(g) Taboca River Crossing

- 50m of river crossing
- Pipes to cross over the river with reinforced concrete pier constructed at 6m interval

(7) Road Crossings

Major road crossings are as follows:

(a) BR-235

Crossing with BR-235 coming from Aracaju at the intersection of SE-104 from Lagarto. Crossing width is 120m.

(b) Itabaiana Water Treatment Station

Crossing with branch road from BR-235 just before Itabaiana Water Treatment Station. Crossing width is 40m.

4.5.2 Auxiliary Structures

(1) Connecting Reservoir, CR3

(a) General

Connecting reservoir is required for smooth conveyance of water from pressurized pipeline of diameter 700mm to the pipeline of diameter 500 by gravity.

(b) Design Conditions

1) Finished Ground Level

- F.G.L. : EL. 255.0 m

医乳腺素 医多数医毒性 医多角管

and a community of a second of the company

- 2) Water Level in the Reservoir
 - -- H.W.L. : EL. 259.0 m
 - L.W.L. : EL. 254.0 m
- 3) Required storage capacity

As same as CR2.

(c) Design of Connecting Reservoir

The dimensions of CR3 are the same as CR1 and CR2 as shown in Figure-4.5.

(d) Sequence of Construction

One basin of CR3 with the storage capacity of 1,500m³ are constructed in Phase 1 and the other basin with the same capacity is constructed in Phase 2.

(2) One Way Surge Tank

(a) Design Conditions

No. Location(m) Ground Elevation(EL. m) W.L.(EL. m) Cross section Area (m²) Height(m) 1 6,000 180.0 > 188.0 20 > 2.0

(b) Design of Surge Tank

One way surge tank is elevated reinforced concrete tank as shown in Figure-4.19 and is constructed in Phase 1.

4.6 Electric Power Supply

4.6.1 Existing Electric Power Supply System

(1) Cajaiba Substation

The existing electric power supply facility near the Project site is Cajaiba Substation (S/S). Cajaiba S/S, operated by ENERGIPE, is located in Cajaiba Village, was constructed for the electric power supply to Cajaiba Village as well as to the Raw Water Pump Station, which supplies drinking water to Itabaiana City and irrigation water for farms near the Dam. The electric power for Cajaiba S/S is supplied from Itabaiana S/S, located at Queimadas near Itabaiana City, via 69kV transmission line.

The technical data of main transformer in Cajaiba S/S is as follows:

Type : Outdoor use

Number of phase : 3
Rated frequency : 60Hz
Rated Primary Voltage : 69kV
Rated Secondary Voltage : 13.8kV
Rated Capacity : 5MVA

(2) 69 kV Outgoing Switchgear Bay

69 kV outgoing switchgear bay is constructed in the existing Cajaiba S/S to supply electric power to the new Vaza Barris S/S. Specification of equipment and structures is in

accordance with ENERGIPE Standard.

Composition of equipment :Lightning arresters, disconnecting switches, gas circuit

breakers, current transformers, post

potential transformers and cable heads

RC Structures

:Gantry towers and pedestals

Others

:Insulators, hardwares, conductors, etc.

(3) Electric Power Failure

The duration and stoppage of electric power in Cajaiba S/S in the past four years is shown in Table-4.8.

Electric Power Failure in Cajaiba S/S Table-4.8

| | 1996 | 1997 | 1998 | 1999 |
|--------|-------|-------|-------|-------|
| EDPC | 94.91 | 76.67 | 24.29 | 10.24 |
| EFPC | 80.45 | 54.87 | 14.87 | 7.67 |
| AEDPC | 1.18 | 1.40 | 1.63 | 1.34 |
| AIESPC | 4.5 | 6.7 | 24.5 | 24.6 |

Notes: Source of information

: ENERGIPE

EDPC

: Equivalent duration per consumer, hours

EFPC

: Equivalent frequency per consumer, times

AEDPC

: Averaged equivalent duration per consumer per stoppage, hours

AIESPC (*) : Averaged interval of effective stoppage per consumer, days : Information accumulated in the first semester of 1999

Table-4.8 shows that the electrical stoppage at Cajaiba S/S is occurred in every 25 days and its duration is 1.5 hour in 1998 and 1999 on average.


4.6.2 Vaza Barris Substation


(1) General

The new substation, called Vaza Barris S/S, is constructed for electric power supply to Water Intake Pump Station for the Water Supply Projects to Itabaiana and Lagarto Cities and Vaza Barris Irrigation Area. The electric power is received from Cajaiba S/S.

(2) Electric Power Demand


| ** |
|---------------------|
| $= 660 \mathrm{kW}$ |
| = 1,200 kW |
| = 1,200 kW |
| 3,060 kW |
| = 8,800 kW |
| 1,000 kW |
| 12,860 kW |
| |





EXTERIOR FINISH SCHEDULE INTERIOR FINISH SCHEDULE FIBERCENENT ROOFING CANALETE 49 TYPE OR EQUIYALENT ROOF OFFICE , STORAGE ROOM , CONTROL AND ELECTRICAL ROOM TOILET AND SHOWER ROOM PLASTER WITH LATEX PAINT FLOOR CONCRETE STEEL TROWEL WITH SILICON PAINT CERAMIC TILE WALL PLASTER WITH LATEX PAINT CERANIC TILE COLUMN SILICÓN PAINT SILICÓN PAINT DITTO DITTO

Figure-4.21 Control and Electical Building



(3) Components to be constructed and/or installed

(a) Control and Electrical Building

Type : Concrete masonry, one-story

Total floor area : 220 m²

Air conditioning : Natural Ventilation

Accessories : Lighting, outlet, telephone and lightning arrester

Design : Refer to Figure-4.21

(b) Main Transformer

- High voltage

Quantity :1

Type / Difference of the control of

Number of phase : 3
Rated frequency : 60Hz
Rated Primary Voltage : 69kV
Rated Secondary Voltage : 2.3kV
Rated Capacity : 18MVA

- Low voltage

Quantity : 2

Type : Outdoor use

Number of phase : 3
Rated frequency : 60Hz
Rated Primary Voltage : 2.3kV
Rated Secondary Voltage : 440V
Rated Capacity : 2,500kVA

(c) 69kV Outdoor Switchgear

- Composition of equipment : Lightning arresters, disconnecting switches, gas circuit

breakers, current transformers, post insulators,

potential transformers and cable heads

- RC Structures :Gantry towers and pedestals

- Others :Insulators, hardwares, conductors, etc.

(d) Distribution Board

- High voltage distribution board

Purpose : Electric power supply for high voltage motors

Type : Indoor use, metal-enclosed and self-standing type

Rate voltage : 2.3kV

Power Distribution: Unit method composed of VCB, metering and protective relays,

etc.

Low voltage distribution board

Purpose : Electric power supply for low voltage motors and building

facilities

Type : Indoor use, metal-enclosed and self-standing type

Rate voltage : 440V

Power Distribution: Unit method composed of MCCB, magnetic conductor, thermal

relay, etc.

(e) DC Power Supply Equipment

Composition of equipment: Battery, battery charger and distribution board

Rated voltage : 110V DC

(f) Control and Protection Panel for 69kV Outdoor Switchgear

Composition of equipment: On-off switch for GCB, position indicator for GCB and

DS, alarm indicator, metering and protective relays, etc.

Type : Indoor use, metal-enclosed and self-standing type

4.6.3 Layout Plan

The substation equipment for the Project is installed on the land near the Water Intake Pump Station and the following equipment configuration is adopted.

(1) Outdoor Equipment

The 69kV switchgear and the main transformers are installed outdoor.

(2) Indoor Equipment

A control building is constructed to install the indoor equipment mentioned above.

4.6.4 Transmission Line

The route for the 69kV transmission line from Cajaiba S/S to Vaza Barris S/S has been selected based on the existing 1:5,000 map and the electrical network map supplied by ENERGIPE. The type of electric poles, bare conductor for overhead transmission lines and other required materials and equipment for transmission lines are in conformity with ENERGIPE standard.

JAPAN INTERNATIONAL COOPERATION AGENCY

STATE SECRETARIAT OF PLANNING, SCIENCE AND TECHNOLOGY THE STATE OF SERGIPE, THE FEDERATIVE REPUBLIC OF BRAZIL

THE STUDY ON WATER RESOURCES DEVELOPMENT IN THE STATE OF SERGIPE IN THE FEDERATIVE REPUBLIC OF BRAZIL

FINAL REPORT SUPPORTING (VOLUME II) FEASIBILITY STUDY

[H] OPERATION AND MAINTENANCE PLAN

MARCH 2000

YACHIYO ENGINEERING CO., LTD. (YEC)

THE STUDY ON WATER RESOURCES DEVELOPMENT IN THE STATE OF SERGIPE IN THE FEDERATIVE REPUBLIC OF BRAZIL

SUPPORTING REPORT (H) OPERATION AND MAINTENANCE PLAN

Table of Contents

Table of Contents List of Tables List of Figures

| Ū | | • |
|---------------------------------------|--|-------------|
| | | Page |
| CHAPTEI | R 1 PREPARATION OF ORGANIZATION | .H-1 |
| 1.1 | Operating Entities | |
| 1.2 | Establishing Operating Entity for Multi-purpose Facilities | |
| CHAPTE | | |
| 2.1 | Vaza Barris Dam Facilities | |
| | 2.1.1 Reporting and Communication | H-2 |
| | 2.1.2 Operation/Inspection/Observation/Monitoring | H-2 |
| * 4 | 2.1.3 Control of Intake | H-3 |
| 2.2 | Domestic Water Supply | H-5 |
| 2.3 | Irrigation Water Supply | H-5 |
| | 2.3.1 Integrated Approach with Close Coordination | H-5 |
| | 2.3.2 Increased Role of Farmer's Associations | H-5 |
| | | : ** |
| · · · · · · · · · · · · · · · · · · · | | |
| | | |
| | | |
| | List of Tables | |
| | | |
| | | Page |
| Table-2.1 | Inspection and Maintenance of Dam Facilities | H-3 |
| | | |
| | | |
| | List of Figures | |
| | | D |
| Figure-2.1 | Recommended Management of Irrigation | Page H-6 |
| Figure-2.2 | | H-6 |

CHAPTER 1 PREPARATION OF ORGANIZATION

1.1 Operating Entities

After completion of the construction works of the Project, the following entities would be in charge of operation. Completed facilities should be handed over to each entity for operation and maintenance.

- 1) Vaza Barris Multipurpose Dam: A project office under a water agency
- 2) Domestic Water Supply in Urban and Large Rural Areas: DESO
- 3) Irrigation Water Supply: COHIDRO

(or the autarchy as proposed in the Master Plan)

Since DESO and COHIDRO are currently operate similar schemes, preparation of operating organization is discussed only for the operation of the multi-purpose facilities.

1.2 Establishing Operating Entity for Multi-purpose Facilities

Possible entity in charge of operation and maintenance of the multi-purpose facility would be DESO or COHIDRO, both of which have experience in operation and maintenance of water facilities. However, the project has a characteristic of multi-purpose, and equitable operation and maintenance can not be fully expected by a single-purpose operator such as DESO or COHIDRO, although they are the public entities, in case some conflicts between domestic water supply and irrigation arise. SEPLANTEC should promote establishment of a water agency in coordination with Bahia State under permission of federal organs, allocating capable staff with similar experiences, and preparation of operation rules/manuals and training in cooperation with DESO and COHIDRO.

Since the Vaza Barris river, which runs in Sergipe and Bahia states, is of federal domain, the competent water agency is the agency for Vaza Barris basin under the National Water Agency (ANA). In case of delay of establishment of the agency, SEPLANTEC can ask ANA to delegate the operation and maintenance in the area of the State to the State Government. Current draft of the law establishing ANA (Art. 2), shows high possibility of the delegation. In case ANA approves the delegation, the functions of operation and maintenance can be placed under SEPLANTEC with the inspection by ANA. SEPLANTEC can conclude an agreement for outsourcing to DESO or COHIDRO for day-to-day operation, as far as equitable management is assured, using their capability of operation of water facility.

A site office should be established with one full-time employee responsible for daily operation and maintenance, according to the operation and maintenance activities as mentioned below. Some inspection, observation and daily operation can be carried out by persons working for intake operation hired by DESO or COHIDRO, concluding a contract with one of these companies. Water quality monitoring can be contracted out to DESO, ADEMA or ITPS. Sounding survey should be conducted by a survey company with a contract.

CHAPTER 2 RECOMMENDED PLANS

2.1 Vaza Barris Dam Facilities

Principles to be applied in operation and maintenance are a) safety, b) efficient water use and equitable water resources allocation, and c) environmental conservation. In order to realize these principles, 1) reporting and communication, 2) operation/inspection/observation/monitoring, and 3) accounting will be carried out. Operation rules should be determined before completion of the facilities. Regarding 3), a draft of the operation rule should be prepared with the consultant for design and construction supervision. Since accounting should just follow the rules of cost allocation as described in Section 5.1 of Part 1, items of 1) and 2) of the above are discussed below.

2.1.1 Reporting and Communication

Results of the operation/inspection/observation/monitoring and accounting should be recorded and periodically reported to the organs in charge of inspection of the operation and maintenance by the site office. Methods and frequency of the reporting should be determined before the operation. Forms for reporting should also be prepared.

Communication system in emergent cases, such as drought or deterioration of water quality, should be established before the commencement of the operation. Required communication facilities should also be installed. Periodical check, at least once a year in the beginning of dry season, should be conducted on the system (command-operation lines) and communication facilities.

2.1.2 Operation/Inspection/Observation/Monitoring

Detailed manner of operation and inspection should be discussed after detail specifications of facilities are determined. Operation and inspection of dams of similar type and scale to the Vaza Barris Dam facilities are generally discussed below.

(1) Low Flow Control

Assurance of maintenance discharge is inevitable for conservation of river environment of the downstream. Operation of valves for control of the discharge from the outlets of bypass pipeline and low flow discharge pipe should be carried out in a frequency of once in a day to once in a week, corresponding to the water level (discharge) of the reservoir of the check dam. A reliable system for the operation should be established.

(2) Inspection and Maintenance

Safety of the dam and dam facilities are fatally important for the residents along the downstream and users of the reservoir water. Inspection as shown in Table-2.1 below should certainly be carried out.

Since the frequency of inspection at the stage 1 is high and the results of the inspection of this stage is important for operation and the inspection of the latter stage, the inspection of this stage should be conducted by or with a specialist.

In case extraordinary values are measured in the inspection, more precise and detail inspection should be carried out. Depending on the results of detail inspection some rehabilitation and immediate counter-measures might be required.

Table-2.1 Inspection and Maintenance of Dam Facilities

| | Frequency | | | |
|-------------------|-----------------------------------|---------------------|----------------------|--|
| luousetian Itania | Stage 1: from the start to | Stage 2: up to the | | |
| Inspection Items | filling to a certain period of | stable condition of | Stage 3: later stage | |
| | time after bankfull stage the Dam | | | |
| Water Leakage | daily | weekly | monthly | |
| Displacement | weekly | monthly | one in three month | |
| Uplift Pressure | weekly | monthly | one in three month | |
| Valve Facilities | monthly | monthly | monthly | |

(3) Observation and Monitoring

(a) Rainfall and Meteorological Observation

Accumulation of rainfall and meteorological data and subsequent analysis is important for operation improvement for efficient use of water. Regarding rainfall and meteorological observation, data of the stations in the catchment area and the area near the dam should periodically be collected. Communication system should be established to obtain these data.

(b) Water Level (Discharge)

Discharge data is very important for operation and inspection as well as for understanding flow regime of the river. Measurement of the water level should be measured every day at the point of the main dam and the check dam.

(c) Reservoir Sediment

Sediment data is also important to know the available volume of water and to use the water efficiently. Sounding survey should be conducted once in several years (around five years) in the main reservoir.

(d) Water Quality

Vaza Barris Reservoir will be the source of water for the two integrated domestic water supply systems, namely Itabaiana and Piauitinga Integrated system and will serve to 539,000 persons in 2020. Water quality of the reservoir is extremely important. The water quality monitoring at the intake point and at a point of the check dam reservoir should preferably be made once in a month, more frequently than that of monitoring of ordinary Class 1 waters. In order to understand conditions of density strata of the reservoir, water quality at different depth (3 points) of the intake point should preferably be monitored twice a year.

2.1.3 Control of Intake

Intake operation should be controlled under the initiative of SEPLANTEC (SRH) since the Vaza Barris Dam should be destined to the most effective and efficient water use among the sectors. Regarding control of intake, a) restriction at the times of droughts and other critical hydrological events, and b) integrated intake management at the times of ordinary conditions and critical conditions are discussed below.

(1) Intake Restriction

In order to optimize the use of limited water in case of drought and other hydrological events, phased intake restriction should be conducted; 1) to secure water for the late stage of a drought with moderate restriction at the early stage of the drought, 2) to avoid damage

of a sudden restriction with giving some period for preparation to more severe restriction.

Rules for water allocation and the restriction of intake in the critical conditions should be decided by the River Basin Committee and the National Council of Water Resources after submission of a draft by SEPLANTEC (SRH) through ANA. Conflicts between domestic water supply and irrigation water supply should be settled in the Committee and the Council. Introduction of drought charge or seasonal charge into water right charging might give an incentive for efficient allocation at times of droughts.

Three methods for phased intake restriction are possible: a) to predict the future available volume of water in the reservoir according to the long-term weather forecast and determine the rate of intake restriction, b) to determine the rate of the restriction by available volume of water at times, c) to estimate probable discharge to reservoir as expected value according to probability of rainfall in the catchment calculated with the past rainfall records.

Results of a simulation in Japan shows; that Method c) worked most effective the reduction of 40% of drought damage compared to the case without any restriction (use water as much as available at times even in the period of drought), that Method c) also substantially reduced the drought damage as much as 15% to 20% compared to the cases without any restriction. Effectiveness of Method a) would heavily depends on the preciseness and reliability of available long-term weather forecast.

Since many data on rainfall, river discharge and drought damage are required to apply Method c), and easiness to apply Method c), Method c) is recommendable at present. With the development of information system on water resources potential and water use, including those on drought damage, Method b) is also recommendable as a future method.

(2) Integrated Intake Management

The Vaza Barris reservoir will provide water to Itabaiana Integrated Water Supply System and Piauitinga Integrated Water Supply System, as well as irrigation perimeters near the dam. Both integrated water supply system has water sources of dam/reservoir, weirs for direct intake from rivers and wells for groundwater pumping.

The integrated intake management consists of a) to precisely analyze water resource potential in terms of quantity and quality at every sources at ordinary times and drought times and to calculate load factors of the current intake, b) to analyze social and economic losses in every types of water use caused by various level of droughts, and c) to control intake operation for overall efficiency of water use in cases of ordinary situations and droughts. Cooperation with DESO and COHIDRO is inevitable to formulate an operation plan.

A criterion for the optimal intake operation at ordinary times is variable costs for intake and water conveyance to water treatment plants. In case treatment costs vary depending on the water sources, variable costs for the treatments should also be taken into consideration. The optimal operation at ordinary times is that to minimize the variable costs. In drought cases, optimal operation can be made by full use of the potential of all water sources and to minimize economic and social losses caused by intake restriction or to make the level of losses by the restriction same in all sectors of water use.

2.2 Domestic Water Supply

Since DESO has been supplying water in the target areas and has enough experiences for domestic water supply, expansion of operation and maintenance in these areas would not be difficult for DESO. As proposed in the Master Plan, however, DESO should expand the operation and maintenance not by increasing its staff but by shifting its staff from the administrative sector as far as possible. Training for the shift should be conducted.

2.3 Irrigation Water Supply

Although COHIDRO has enough experiences in operation and maintenance of irrigation schemes, its management seems to have to be improved, as recommended in the Master Plan. A management reform is discussed below, since well-organized irrigation management is essential for the sound management of the Project.

2.3.1 Integrated Approach with Close Coordination

Integrated management is necessary to achieve higher objectives without leaving uncontrollable management factors outside of the operating entities. Brazilian irrigation management, especially those developed in settlement programs, seems to be oriented to integrated management. In some cases irrigation perimeter management includes building social facilities. However, this type of management requires excessive duties on government organs as well as duplications of functions in the same level of the governments, and often causes financial burdens heavier than those levels of the government can afford.

In proposed irrigation management, the role of the government operating entity will be limited to management of water facility. In order not to lose the merits of integrated management, a mechanism of close coordination with supporting entities in charge of agricultural extension, research, and crediting should be established. Periodical meetings among the operating entity of irrigation management, supporting entities and the farmers' association should be encouraged. The merger of COHIDRO and EMDAGRO and increased farmers' participation as described below might help promoting the required close coordination.

2.3.2 Increased Role of Farmer's Associations

For equitable, efficient and flexible water management, role of farmers themselves should be enhanced, although role of government entity is very important at the construction stage and the initial stage of operation. Establishment of water users' association or irrigation association should be promoted with assistance through mobilization and education/ training activities. Increased capability will allow less government involvement in the future. Farmers' participation in water management will often cause not only better efficiency of irrigation management but also better cost recovery, resulting less financial burdens on the government.




Figure-2.1 Recommended Management of Irrigation

However, farmers of the target area do not have any experience in irrigation and water management. Mobilization activities would be examined, referring successful cases in other parts of Brazil and other countries. The establishment of "Irrigation Districts" by CODEVASF, such as that in Petrolina perimeter would be a good example. Consultation with or supports by CODEVASF help organizing sustainable perimeter management.




Figure-2.2 Organization of the District in Petrolina Perimeter

JAPAN INTERNATIONAL COOPERATION AGENCY

STATE SECRETARIAT OF PLANNING, SCIENCE AND TECHNOLOGY THE STATE OF SERGIPE, THE FEDERATIVE REPUBLIC OF BRAZIL

THE STUDY ON WATER RESOURCES DEVELOPMENT IN THE STATE OF SERGIPE IN THE FEDERATIVE REPUBLIC OF BRAZIL

FINAL REPORT
SUPPORTING
(VOLUME II)
FEASIBILITY STUDY

[I] COST ESTIMATE

MARCH 2000

YACHIYO ENGINEERING CO., LTD. (YEC)

THE STUDY ON WATER RESOURCES DEVELOPMENT IN THE STATE OF SERGIPE IN THE FEDERATIVE REPUBLIC OF BRAZIL

SUPPORTING REPORT (I) COST ESTIMATE

Table of Contents

Table of Contents List of Tables List of Figures

| CHAPTER 1 | | | Page |
|--|-----------|--|-------------------|
| CHAPTER 2 CONDITIONS OF COST ESTIMATION | СНАРТЕ | ER 1 INTRODUCTION | I-1 |
| 2.1 Price Level 1-1 2.2 Unit Price 1-1 2.2.1 General 1-1 2.2.2 CEHOP Data Base 1-1 2.3 Composition of Project Cost 1-2 2.3.1 General 1-2 2.3.2 Administration Cost, AC 1-2 2.3.3 Consulting Engineering Services Cost, ESC 1-2 2.3.4 Construction Cost, CC 1-2 2.3.5 Compensation Cost, LCC 1-2 2.3.6 Land Acquisition Cost, LAC 1-3 2.3.7 Contingency, CT 1-3 2.4 Price Escalation 1-3 2.5 Method of Estimation of the Project Cost 1-4 2.5.1 Cost Estimation based on the Result of Facility Design 1-4 2.5.2 Cost Estimation based on the Result in the Master Plan Study 1-5 CHAPTER 3 PROJECT COST 1-6 3.1 Total Project Cost 1-6 3.2 Dam Project 1-6 3.3.1 Agreeste Water Supply Project 1-6 3.3.2 Piauitinga Water Supply Project | CHAPTE | | |
| 2.2 Unit Price 1-1 2.2.1 General 1-1 2.2.2 CEHOP Data Base 1-1 2.3 Composition of Project Cost 1-2 2.3.1 General 1-2 2.3.2 Administration Cost, AC 1-2 2.3.3 Consulting Engineering Services Cost, ESC 1-2 2.3.4 Construction Cost, CC 1-2 2.3.5 Compensation Cost, LCC 1-2 2.3.6 Land Acquisition Cost, LAC 1-3 2.3.7 Contingency, CT 1-3 2.4 Price Escalation 1-3 2.5 Method of Estimation of the Project Cost 1-4 2.5.1 Cost Estimation based on the Result of Facility Design 1-4 2.5.2 Cost Estimation based on the Result in the Master Plan Study 1-5 CHAPTER 3 PROJECT COST 1-6 3.1 Total Project Cost 1-6 3.2 Dam Project 1-6 3.3.1 Agreste Water Supply Project 1-6 3.3.2 Piauitinga Water Supply Project 1-7 3.4 Reforestation 1-7 3.5 Irrigation Water Supply Facilities 1-7 APPENDICES Appendix-1 Current Supply Conditions of Construction Materials in the State of Sergipe | 2.1 | | |
| 2.2.1 General | | | |
| 2.2.2 CEHOP Data Base 1-1 2.3 Composition of Project Cost 1-2 2.3.1 General 1-2 2.3.2 Administration Cost, AC 1-2 2.3.3 Consulting Engineering Services Cost, ESC 1-2 2.3.4 Construction Cost, CC 1-2 2.3.5 Compensation Cost, LCC 1-2 2.3.6 Land Acquisition Cost, LAC 1-3 2.3.7 Contingency, CT 1-3 2.4 Price Escalation 1-3 2.5 Method of Estimation of the Project Cost 1-4 2.5.1 Cost Estimation based on the Result of Facility Design 1-4 2.5.2 Cost Estimation based on the Result in the Master Plan Study 1-5 CHAPTER 3 PROJECT COST 1-6 3.1 Total Project Cost 1-6 3.2 Dam Project 1-6 3.3 Water Supply Project 1-6 3.3.1 Agreste Water Supply Project 1-6 3.3.2 Piauitinga Water Supply Project 1-7 3.4 Reforestation 1-7 3.5 | 2.2 | Unit Price | l-1 |
| 2.3 Composition of Project Cost | | 2.2.1 General | l-l |
| 2.3.1 General 1-2 | | | the second second |
| 2.3.2 Administration Cost, AC 1-2 2.3.3 Consulting Engineering Services Cost, ESC 1-2 2.3.4 Construction Cost, CC 1-2 2.3.5 Compensation Cost, LCC 1-2 2.3.6 Land Acquisition Cost, LAC 1-3 2.3.7 Contingency, CT 1-3 2.3.7 Contingency, CT 1-3 2.4 Price Escalation 1-3 2.5 Method of Estimation of the Project Cost 1-4 2.5.1 Cost Estimation based on the Result of Facility Design 1-4 2.5.2 Cost Estimation based on the Result in the Master Plan Study 1-5 CHAPTER 3 PROJECT COST 1-6 3.1 Total Project Cost 1-6 3.2 Dam Project 1-6 3.3 Water Supply Project 1-6 3.3.1 Agreste Water Supply Project 1-6 3.3.2 Piauitinga Water Supply Project 1-7 3.4 Reforestation 1-7 3.5 Irrigation Water Supply Facilities 1-7 APPENDICES Appendix-1 Current Supply Conditions of Construction Materials in the State of Sergipe Cost Estimation Sheet 1-2 Cost Estimation She | 2.3 | | |
| 2.3.3 Consulting Engineering Services Cost, ESC | | 2.3.1 General | I-2 |
| 2.3.4 Construction Cost, CC | • | 2.3.2 Administration Cost, AC | I-2 |
| 2.3.5 Compensation Cost, LCC | | | |
| 2.3.6 Land Acquisition Cost, LAC | | | ۱-۲۲-۲ |
| 2.3.7 Contingency, CT | | 2.3.6 Land Acquisition Cost LAC | I-2 |
| 2.4 Price Escalation | • • • • | 2.3.7 Contingency, CT | I-3 |
| 2.5 Method of Estimation of the Project Cost | 2.4 | | |
| 2.5.1 Cost Estimation based on the Result of Facility Design | | Mathad of Patimatian of the Pusicat Cost | T 4 |
| 2.5.2 Cost Estimation based on the Result in the Master Plan Study | 2.3 | 2.5.1 Cost Retimation based on the Popult of Facility Decien | l-4 |
| CHAPTER 3 PROJECT COST | | 2.5.2 Cost Estimation based on the Result in the Master Plan | |
| 3.1 Total Project Cost | CHADTE | | - |
| 3.1 Total Project Cost | | | |
| 3.3 Water Supply Project | 3.1 | | I-6 |
| 3.4 Reforestation | 3.2 | Dam Project | l-6 |
| 3.4 Reforestation | 3.3 | Water Supply Project | I-6 |
| 3.4 Reforestation | | 3.3.1 Agreste Water Supply Project | I-6 |
| 3.4 Reforestation | | 3.3.2 Piauitinga Water Supply Project | I-7 |
| 3.5 Irrigation Water Supply Facilities | 3.4 | | |
| APPENDICES Appendix-1 Current Supply Conditions of Construction Materials in the State of Sergipe Appendix-2 Cost Estimation Sheet | 3.5 | | |
| Appendix-1 Current Supply Conditions of Construction Materials in the State of Sergipe Appendix-2 Cost Estimation Sheet | 3.3 | migation rater supply racinities | 1- <i>/</i> |
| Appendix-1 Current Supply Conditions of Construction Materials in the State of Sergipe Appendix-2 Cost Estimation Sheet | APPEND | DICES | |
| Appendix-2 Cost Estimation Sheet | | | State of Sergine |
| Appendix-3 Cost Estimation of Alternative for Low Flow Bypass | | -2 Cost Estimation Sheet | |
| | Appendix- | -3 Cost Estimation of Alternative for Low Flow Bypass | |

List of Tables

| | Pag | C |
|------------|---|---|
| Table-3.1 | Summary of Project CostI- | 5 |
| Table-3.2 | Summary of Dam Project CostI- | 5 |
| Table-3.3 | Summary of Agreste Water Supply Project CostI- | |
| Table-3.4 | Summary of Piauitinga Water Supply Project CostI- | |
| Table-3.5 | Summary of Reforestation CostI- | 7 |
| Table-3.6 | Summary of Irrigation Water Supply Facilities CostL | 7 |
| | | |
| | List of Figures | ٠ |
| r * . | Pàg | e |
| Figure-2.1 | Monthly Variation of Construction Cost | 4 |

CHAPTER 1 INTRODUCTION

This report covers the details of estimation of the Project cost for the construction of the facilities included in the Feasibility Study.

CHAPTER 2 CONDITIONS OF COST ESTIMATION

2.1 Price Level

Cost estimation for the Study is based on the costs and prices in Brazilian "Real", R\$, at the time of September 1999, namely 1 US\$ = 1.92R\$ and 1 US\$ = 106.95 yen.

2.2 Unit Price

2.2.1 General

In principal, unit prices used for cost estimation of the Projects in the Feasibility Study are determined based on the data base for cost estimation of public works in the Sergipe State provided by CEHOP.

Unit prices not covered by the CEHOP data base are obtained by quotations from manufacturers, suppliers or distributors of products required for the Projects or estimation from the prices of the similar projects in the past.

2.2.2 CEHOP Data Base

The data base was developed by CEHOP in order to achieve the efficient preparation of documents required in the budgeting and tendering process for the Public Works in the State of Sergipe.

The data base includes:

- List of approximately 9,000 possible materials to be used
- Grouped description and listing of approximately 8,000 service items
- Price compositions more than 6,000
- Approximately 230 specifications concerning main basic services

The data base can provide preparation of the following reports:

- Budget Table
- Physical-financial work schedule
- Material curve
- Presentation of the specific price compositions
- List of all materials with identical information
- Suppliers list of materials and prices

The software including data base is supplied by CEHOP in the form of CD ROM. The software is developed in a client-server base in a way to make possible also the access through Internet.

(4) (4) 大海南南南部 (4) (4) (4) (4) (4) (4) (4) (4) (4)

2.3 Composition of Project Cost

2.3.1 General

Project cost is composed of the following cost items:

- Administration Cost, AC
- Consulting Services Cost, CSC
- Construction Cost, CC
- Compensation Cost, LCC
- Land Acquisition Cost, LAC
- Contingency, CT

2.3.2 Administration Cost, AC

Administration cost of the Government covers the cost for supervision and management of the project implementation by the Government staff and is taken as 1% of CSC, CC, LCC, LAC and CT.

tion of the state of the feet of the state of the state of the state of the state of

2.3.3 Consulting Services Cost, CSC Advantages and the consulting Services Cost, CSC

The cost covers the cost for consulting engineering services required in the whole period of the project implementation and is taken as 10% of CC, LCC and LAC. This rate is estimated as the average of rates for all CSC required in the Project.

2.3.4 Construction Cost, CC

The cost required for the construction of facilities and other related works including the preparatory works. The cost includes material and equipment cost and labor cost including installation and erection of equipment, etc. as a direct cost and the direct and indirect benefit, BDI, as an indirect cost.

2.3.5 Compensation Cost, LCC

This cost covers the cost associated with the compensation for properties such as resettlement of residents, permanent and temporary use of land, etc.

(1) Evaluation Method of House Compensation

(a) Cost Reproduction Method

The current cost for the construction of a new house is estimated, considering details such as type of floor, doors, etc. The depreciation is calculated to reach a final value for compensation as 2% per year and durability in years of the house.

(b) Comparison Method

The house to be resettled is compared to a similar house sold recently in the region, and the price paid for this house is the parameter for the calculation of the compensation for the dispossessed house.

(2) Evaluation Method of Land Compensation

The compensation for land along the pipeline is necessary only when the pipe crosses or is in a private area. In case the pipeline is along the existing road or pathway, there is no need for compensation but an authorization from DNER to install the pipeline. Regarding the pipeline from Ribeira to Itabaiana, it can be implemented along the existing pipeline with small compensation, since the area was already compensated at the time of the execution of existing work and the compensated area is larger than the required for the existing pipeline considering the possibility of future expansion. Unit cost of land for compensation is as same as for land acquisition.

2,3.6 Land Acquisition Cost, LAC

This cost covers the cost associated with the acquisition of land for construction of the facilities and their influence area.

(1) Land to be inundated in the Reservoir

Inundated area in the reservoir is measured based on 1:5000 scale map. Unit cost of land is 520 R\$/ha established in the Master Plan Study for the region based on the information from INCRA. The same unit rate is applied for the acquisition of land required for the construction of Water Intake and Lift Pump Stations.

(2) Land for Water Supply Facility

The land acquisition in the urban areas is done considering the region and it is calculated by a lot in size of 8m x 25m called "chao de casa", informal popular measuring unit of land with an average unit cost of 3,000 R\$/lot.

2.3.7 Contingency, CT

Contingency includes the physical contingency.

5% of the sum of CSC, CC, LCC and LAC is taken as the physical contingency of the Project cost.

2.4 Price Escalation

The index for variation of construction cost is the civil construction cost per square meters of buildings published by IBGE in their annual and monthly statistical reports. The period of index to be analyzed is between July 1994 and May 1999.

The following indexes have been analyzed:

- National Consumer Price Indes NCPI in Brazil
- Average civil construction cost per m², ACCC in Brazil, Sao Paulo and Sergipe in R\$ and US\$
- Foreign exchange rate from Brazilian Reals to U.S. dollars

Figure-2.1 indicates the variation of the indexes between July 1994 and May 1999. It is noted that IBGE started to adopt a new series of ACCC from January 1999 to suit the updated technical reference of SINAPI, National Research System of costs and rates of the civil construction, promoted by the "Caixa Economica Federal", Federal Financial Organ.

In this analysis, ACCC in 1998 base is used by multiplying increase rate of new ACCC in 1999, which is also shown in IBGE Report, to ACCC in December 1998.

Figure-2.1 shows that the increase rate of ACCC Sergipe R\$ is very small and is less than those of NCPI and ACCC Brazil R\$. On the contrary, ACCC US\$ is decreasing month by month and is oscillated drastically at the beginning of 1999 due to the sharp decline of exchange rate of Brazilian "Real" to US dollar caused by the economic crisis in Brazil. The current exchange rate is still regarded as unstable. Therefore, the Project cost is evaluated in Brazilian Real basis. The annual price escalation rate of ACCC R\$ in Sergipe and Sao Paulo between July 1995 and June 1999 is calculated as 1.8% and 5.0%, respectively. Since the prices of most of the construction equipment and materials are strongly affected by the prices in Sao Paulo, the annual rate of price escalation for the Project cost is taken as 5.0%.




Figure-2.1 Monthly Variation of Construction Cost

2.5 Method of Estimation of the Project Cost

2.5.1 Cost Estimation based on the Result of Facility Design

The cost estimation for the following construction works was made based on the quantities of equipment, materials, labor and other related items calculated from the design drawings of facilities:

(1) Facilities related to Dam

- Vaza Barris Dam
- Check Dam
- Low Flow Bypass

(2) Facilities related to Water Conveyance

Facilities related to water conveyance from Vaza Barris Reservoir to Agreste and Piauitinga Regions were included in this category.

- Water Intake Pump Station
- Water Lift Pump Stations.
- Connecting Reservoirs
- Water Conveyance Pipelines
- Surge Tanks
- Control and Electrical Building
- Substation

2.5.2 Cost Estimation based on the Result in the Master Plan Study

The cost estimation of the Water treatment stations, treated water pump stations and distribution networks for the following municipalities included in Agreste and Piauitinga Integrated Water Supply Systems was made by adjusting the result of cost estimation in the Master Plan Study:

(1) Agreste Integrated Water Supply System

- Areia Branca
- Campo do Brito
- Itabaiana
- Macambira
- Sao Domingos

(2) Piauitinga Integrated Water Supply System

- Poco Verde
- Simao Dias
- Lagarto
- Richao do Dantas

(3) Method of Adjustment of Construction Cost

The price escalation from September 1998 to September 1999 is considered in the adjustment of the construction cost estimated in the Master Plan Study.

CHAPTER 3 PROJECT COST

3.1 Total Project Cost

Table-3.1 shows the Total Project Cost included in the Feasibility Study.

Table-3.1 Summary of Project Cost

Unit: R\$ thousand

| | Onn. | tra monsona |
|---------|---|---|
| Phase 1 | Phase 2 | Total |
| 2,065 | 563 | 2,628 |
| 17,877 | 4,876 | 22,753 |
| 176,253 | 48,759 | 225,012 |
| 67,280 | 0 | 67,280 |
| 34,597 | 23,993 | 58,590 |
| 36,716 | 24,766 | 61,482 |
| 719 | 0 | 719 |
| 36,941 | 0 | 36,941 |
| 2,536 | 0 | 2,536 |
| 9,833 | 2,682 | 12,515 |
| 208,564 | 56,880 | 265,444 |
| | 2,065 17,877 176,253 67,280 34,597 36,716 719 36,941 2,536 9,833 | Phase 1 Phase 2 2,065 563 17,877 4,876 176,253 48,759 67,280 0 34,597 23,993 36,716 24,766 719 0 36,941 0 2,536 0 9,833 2,682 |

3.2 Dam Project

Table-3.2 shows the Dam Project Cost included in the Feasibility Study.

Table-3.2 Summary of Dam Project Cost

Unit: R\$ thousand

| Cost Item | Phase I | Phase 2 | Total |
|----------------------------|---------|---------|--------|
| 1. Administration Cost | 806 | 0 | 806 |
| 2. Consulting Service Cost | 6,980 | 0 | 6,980 |
| 3. Construction Cost | 67,280 | 0 | 67,280 |
| (1) Dam | 30,189 | 0 | 30,189 |
| (2) Check Dam | 4,260 | . 0 | 4,260 |
| (3) Low Flow Bypass | 32,830 | 0 | 32,830 |
| 4. Land Acquisition Cost | 2,523 | 0 | 2,523 |
| 5. Contingency | 3,839 | 0 | 3,839 |
| Total | 81,428 | 0 | 81,428 |

3.3 Water Supply Project

3.3.1 Agreste Water Supply Project

Table-3.3 shows the summary of Agreste Water Supply Project Cost included in the Feasibility Study.

Table-3.3 Summary of Agreste Water Supply Project Cost

Unit: R\$ t

| | | Om. | va monzama |
|----------------------------|---------|---------|------------|
| Cost Item | Phase 1 | Phase 2 | Total |
| 1. Administration Cost | 400 | 277 | 677 |
| 2. Consulting Service Cost | 3,459 | 2,399 | 5,858 |
| 3. Construction Cost | 34,597 | 23,993 | 58,590 |
| (1) Conveyance | 17,500 | 12,137 | 29,637 |
| (2) Distribution | 17,097 | 11,856 | 28,953 |
| 4. Land Acquisition Cost | 5 | 0 | 5 |
| 5. Contingency | 1,903 | 1,320 | 3,223 |
| Total | 40,364 | 27,989 | 68,353 |

3.3.2 Piauitinga Water Supply Project

Table-3.4 shows the Piauitinga Water Conveyance Project Cost included in the Feasibility Study.

Table-3.4 Summary of Piauitinga Water Supply Project Cost

Unit: R\$ thousand Cost Item Phase 1 Phase 2 Total 1. Administration Cost 424 286 710 2. Consulting Service Cost 3,671 2,477 6,148 3. Construction Cost 36,716 24,766 61,482 (1) Conveyance 17,723 11,955 29,678 (2) Distribution 18,993 12,811 31,804 4. Land Acquisition Cost 5. Contingency 2,020 1,362 3,382 Total 42.839 28,891 71,730

3.4 Reforestation

Table-3.5 shows the Reforestation Cost included in the Feasibility Study.

Table-3.5 Summary of Reforestation Cost

Unit: R\$ thousand Phase 2 Cost Item Phase 1 Total 1. Administration Cost 0 2. Consulting Service Cost 72 0 72 3. Reforestation Ó 719 719 4. Land Acquisition Cost 0 5. Contingency 40 40 Total 839 839

3.5 Irrigation Water Supply Facilities

Table-3.6 shows the Irrigation Water Supply Facilities Cost included in the Feasibility Study. The cost for Irrigation Water Supply Facilities is referred from the Technical Report of Pre-Feasibility Study of Vaza Barris Irrigation Project, proposed by SRH with same modification on CSC.

Table-3.6 Summary of Irrigation Water Supply Facilities Cost

Unit: R\$ thousand Cost Item Phase I Phase 2 Total 1. Administration Cost 427 0 427 2. Engineering 3,694 3,694 3. Supply Facilities Õ 36,941 36,941 4. Contingency 2,032 2,032 Total 43,094 43,094

APPENDIX-1

Current Supply Conditions of Construction Materials in the State of Sergipe

APPENDICES

Appendix-1 Current Supply Conditions of Construction Materials in the State of Sergipe

(1) General

Common construction materials required for the Priority Projects can be procured in the State of Sergipe. Current supply condition of construction materials in the State of Sergipe is as follows:

(2) Ready-mixed Concrete

There are only three commercial concrete producers that are equipped with concrete mixing plant and agitator trucks in their own plants in the State of Sergipe. All of their plants are located at boundary area of Aracaju city. These producers are nation wide company which own their branches in major capitals of the States in Brazil. They can provide concrete mixing plant in the dam construction site as well. The production capacity of concrete producers is shown in Table-1.1.

Table- 1.1 Production Capacity of Concrete Producers

| Company Name | Address | Production Capacity (m³/month) | Strength of Concrete (MPA) 9, 11,13, 15, 18, 20, 22, 25 and 30 | |
|--------------------------------|--|--------------------------------|---|--|
| Concrete Redimix do Brasil S/A | Rodovia BR235 KM 4.2 | Max. 10,000 Average 5,000 | | |
| Supermix Concreto S/A | S/N Faz. Itacanema | - | | |
| Polimix Concreto Ltda. | Rod. BR235 Km 04 – S/N Nossa Senhora Do Socorro | Average 5,000 | 9 ~35, max 60 | |

(3) Crushed Stone

There are four crushed stone producers in the State of Sergipe. Quarries of three producers are located in the so-called Itabaiana dome region near to the Vaza Barris Dam construction site. The production capacity of the producers is shown in Table-1.2.

Table- 1.2 Production Capacity of Crushed Stone Producers

| Company Name | Place of Production | Production Capacity (m³/month) | Size (mm) |
|-------------------------|--------------------------------|--------------------------------|----------------|
| Pedreira Dinanica Ltda. | Povoado Sao Jose, Itabaiana | Average 14,000 | 16, 25, 32, 50 |
| Pedreira Cajaiba Ltda. | Povoado Cajaiba, | Average 12,000 | |
| | Itabaiana | 23,000 (From Sep. 99) | |
| Pedreira Anhanguera S/A | Itabaiana | Average 6,000 | 16, 19, 25, 38 |

All of these producers can also supply rock-fill materials for dam construction. Their production capacities of rock-fill materials are around 5,000 m³ per month on average.

(4) Sand

Sand for fine aggregate is excavated in the margin of Poxim River near to the cities of Itaporanga and Riachuelo by a large number of persons, like self-employed excavators. Some crushed stone producers also supply crushed stone powder as fine aggregate in stead. The production capacity of the producers is shown in Table-1.3.

Table- 1.3 Production Capacity of Fine Aggregate Producers

| Company Name | Place of Production | Production Capacity (m³/month) | Remarks |
|-------------------------|--------------------------------|--------------------------------|-------------------------|
| Pedreira Dinanica Ltda. | Povoado Sao Jose, Itabaiana | Average 3,000 | Powder of crushed stone |
| Morais | Laranjeiras | Average 4,000 | Sand |
| Jazida do Poxim | Pacatuba | Average 6,000 | Sand |

APPENDIX-2

Cost Estimation Sheet

REMARKS 30.189,340 3,148,415 2,025,364 25,015,561 Prices (RS) Sub-total Unit Price YT'O TIND <u>ö</u> ট্ ö DESCRIPTION APAN INTERNATIONAL COOPERATION AGENCY : JICA Appendix-2 Cost Estimation Sheet PROJECT: Vaza Barris Water Supply Project Preliminary works Temporary works Grand Total Civil works ITEM

| | AFALL LANGE COOK LANGE TO THE PORT OF THE | 1.7 | | | | | | |
|--------------------------------------|---|---------------------------------------|-------------|-------------------------------------|---|---------------------------------------|-----------|-----------|
| PROJECT | Vaza Barris Dam Proiect | 7 | OCATIO | . N. | | | | |
| WORK | Dam | רו | NIT: FI | UNIT: FIRST PHASE | 1 1 | | | PAGE 2/8 |
| | | | | | ; | Prices (RS) | E | 001010100 |
| ITEM | DESCRIPTION | | | λΙΔ | Onit Price | Sub-total | Logal | KEMAKKS |
| <u> </u> | Preliminary works | | | | | | 2,025,364 | |
| F | Mobilization and demobilization | | lot | - | | 300,000 | 300,000 | |
| 1.2 | Site office, work spaces and camps | • | jo | , - | | 800,000 | 800,000 | |
| 1.3 | Access Road | | | | | | 917,216 | |
| 1.3.1 | | · · · · · · · · · · · · · · · · · · · | | - | | | 518,069 | |
| 13.1.1 13.1.2 13.1.3 13.1.4 | Total distance = 9500 m, Road Width = 5 m and Waiting Area per 500m Regularization of sub-base Reinforcement (Distance = 3000 m, Thk = 0.5 m) Base With Graded Crushed Stone (Thk = 0.3 m) Excavation | | "៩ មិ មិ មិ | 48,450 7,500 14,535 20,000 | 0. 2. 9. 42 4. 85 4. 85 4. 90 5. 90 | 20,349 29,550 143,170 41,800 | | |
| 1.3.1.5 | Embankment | | È | 30,000 | y. | 007.687 | | |
| 1.3.2 | Access road from Jenipapo to Dam Site Total distance = 1500 m, Road Width = 5 m and Waiting Area per 500m Total distance = 3500 m, Exp. Width = 2 m and Waiting Area per 500m | | | | (| | 399,147 | |
| 1.3.2.1 1.3.2.2 | Regularization of sub-base Reinforcement (Thk $= 0.5 \text{ m}$) | | E E | 5,970 | 3.94 | 23,522 | | |
| 1323 1324 1325 | Base With Graded Crushed Stone (Thk = 0.3 m) Excavation Embankment | | a a a | 20,000 30,000 | 2.89 2.09 44.69 | `` | | |
| 7.7 | Deforestation and stripping of construction site | | m, | 67,900 | 0.12 | 8,148 | 8,148 | |
| | | | - | | | | | |
| | | | | | | | | 1 |
| | | | | | | | | |

| JAPAN INT | APAN INTERNATIONAL COOPERATION AGENCY: JICA | YACHIYO | ENGINEER | YACHIYO ENGINEERING CO., LTD.: YEC | D.: YEC | | DATE: 30/9/99 |
|-----------------------------|--|-----------------|-------------------|------------------------------------|-----------------------|-------------------------------|--------------------------------|
| PROJECT | PROJECT : Vaza Barris Dam Project | LOCATION | . Z | | | | |
| WORK: | Dam | UNIT: FI | UNIT: FIRST PHASE | | | | PAGE 3/8 |
| ITEM | DESCRIPTION | TIND | OTY . | Unit Price | Prices (RS) Sub-total | Totai | REMARKS |
| 2. | Temporary works | | | | | 3,148,415 | |
| 2.1 | Construction and Installation of Concrete Casting Facility | | | | | 1.721,783 | <u>Karangiy</u> |
| 21.1 21.1.1 21.1.2 | Crane Rental fee, operation and maintenance cost of crane Tecnotra BR-200 or equivalent including operator, etc., 2 units Transportation | unit-mth lot | 09 | 16,000.00 | 960,000 | 969,600 | |
| 2.1.2 2.1.2.1 2.1.2.1 | Platform Pre-fabricated Concrete Slab and Beam Pre-fabrication | | | | | 752,183 308,914 200,677 | to bi managa maga <u>salad</u> |
| | Concrete | Ë | 658 | 137.33 | 90,363 | 110,467 | 56.A036 |
| | Reinforcing bars Form | %"E | 5,048 | 1.69 | 122,337 | | |
| 2.1.2.1.2 | Transportation and installation Loading and Transportation (0.5km) | | 1,612 | 2,35 | 3.788 | 9,237 | |
| 2122 | Unloading and installation Prefabricated congrete pile | | 1,612 | 3.38 | 5,449 | 070 277 | |
| 2.1.2.2.1 | Pre-fabrication Concrete | Ê | 191 | 13733 | 22 110 | 85,427 | |
| | Reinforcing bars Form | 50.5 | 17,738 | 1.69 | 33,340 | | 16 |
| 2.1.2.2.2 | Transportation and installation Loading and Transportation (0.5km) | | 395 | 2.35 | 928 | 5,187 | |
| | Manual Ground perforation, Dia 0.25m | · E · | 888 | 4.25 | 2,924 | r der v tand te sa van | |
| 2.1.2.3 | Support Foundations | . ' | 7 6 7 | 0::0 | CCC.1 | 352,655 | Sef and characters a |
| | Concrete Name Name | e . | 1,376 | 137.33 | 188,966 | | |
| | Form | 29°E | 2,752 | 17.23 | 47.417 | | |
| | | | | | | | |
| | $(\mathbf{BDI} = 0.3)$ | | | | | | |
| | | | | | | | |

| | APAN INTERNATIONAL COOFERATION ACENCY SICA | LOCATI | . No | LOCATION: | | | |
|--------------------------------|---|--------|----------------------------|----------------------|-------------------------------|-----------|----------|
| WORK . | Dam | TINU. | UNIT: FIRST PHASE | | | | PAGE 4/8 |
| ITEM | DESCRIPTION | UNIT | ΥΤΌ | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| 2.2 2.2.1 2.2.2 2.2.3 | Diversion of niver Excavation of 1st category of soil Loading and transportation of 1at category of soil(.0.5km) Embankment | ฮิฮิฮิ | 61,863 61,863 84,676 | 2:09 2:37 1:78 | 129,294 146,615 150,723 | 426,632 | |
| 2.3. | Waste Water Treatment Facility Waste Water Treatment Facility | Į. | 944 | | 1,000,000 | 1,000,000 | |
| | | | | | | | |

| JAPAN INTE | JAPAN INTERNATIONAL COOPERATION AGENCY: JICA | YACHIYO ENGINEERING CO., LTD.: YEC | VGINEER | ING CO. LT | D.: YEC | | DATE: 30/9/99 |
|--|--|------------------------------------|---------------------------------------|------------------------------|---|------------|---|
| PROJECT | PROJECT: Vaza Barris Dam Project | LOCATION | | | | | |
| WORK: | Dam | UNIT: FIRST PHASE | T PHASE | | | | PAGE 5/8 |
| ITEM | DESCRIPTION | UNIT | OTY | Unit Price | Prices (R\$) Sub-total | Total | REMARKS |
| 3. | Civil works | | | | | 25,015,561 | |
| 8 8 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | Earth work Excavation of 1st category of soil Excavation of 2nd category of soil Loading and transportation of 1at category of soil(0.8km) Loading and transportation of 2nd category of soil(0.8km) Compaction of soil to NP 95% | ัยโยโยโย | 342.000 34.200 34.200 34.200 | 2.09 1.89 2.69 1.11 | 714,780 71,820 91,998 10,222 37,962 | 218.842 | orationa mentre qualiformation mentre il servicioni ma absenzação |
| 3.2. 3.2.2 3.3.2 3.3.3 | Concrete Production Dam Concrete Type-1 Production, transportation and easting Dam Concrete Type-2 Production, transportation and casting Form Construction Joint and Water-stop (3% of concrete work) | ខ្មែន | 216,100 42,600 36,000 | 80.11 71.85 18.46 | 3.060.810 664.560 630.000 | 21,037,141 | |
| 3,3 | Grouting Curtain Grouting and Consolidation Grouting (6.5% of concrete work) | lo: | ← | | 1,370.000 | 1,370.000 | |
| 3.4 | Monitoring Instrument Monitoring Instrument (2% of concrete work) | lot | - | | 420,000 | 420,000 | |
| | | | | | | | |
| | | | | | | | |
| ź | | : | | | | | |
| | (BDI = 0.3) | | | | | | |

| TATNAGAT | APAN INTERNATIONAL COOPERATION AGENCY IICA | YACHIYO | ENGINEE | YACHIYO ENGINEERING CO., LTD.: YEC | D.: YEC | | DATE: 30/9/99 |
|----------|---|--------------|-------------------|------------------------------------|--------------------------|-------|------------------------|
| PROTECT | Vaza Barris Dam Project | LOCATION: | . No | | | | |
| 1 | Concrete Production for Dam Body | GNIT: F | UNIT: FIRST PHASE | 3 | | | PAGE 6/8 |
| , and | NOTE A SPECIAL STATES OF THE SPECIAL STATES | I |) ALC | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| S-1 | Dam Concrete Type-1 Production for Dam Body per m3 | | | | | 80.11 | |
| <u></u> | Plant and Equipment | | | | | 20.21 | |
| | Mixing Plant Supply and Operation of mixing plant Diesel oil | m, liters | ∺ 4 | 18.00 | 18.00 | 20.12 | |
| 21 | Water Pumping Facility Facility for water pumping Diesel oil | liters | 0.036 | 0.07 | 0.07 | 0.09 | |
| <u>~</u> | Material | | | | | 59.90 | |
| 2.1 | Cement Supply of cement | ķ. | 200 | 0.16 | 32.00 | 32.00 | |
| | Crushed stone Supply of crushed stone 15cm - 50cm Supply of crushed stone < 2cm | មិនិ | 0.00 | 15.00 | 13.50 | 27.90 | Quotation Quotation |
| | Transportation of crushed stone | Ē | OC: T | | | | uougon |
| | | | · · · · · · | | | | |
| | | | | | | | |
| | (BDI=0.3.) | | | | | | |
| | | | | | | | |

| Description of mixing plant Description of crushed some Description of crushed some Description | | | | | | 1 | | |
|--|-------------|--|----------------|----------------------|-------------|-----------------------|-------|-------------------------------------|
| Prices (RS) Prices (RS) Prices (RS) | JAPAN INT | SKNATIONAL COOPERATION AGENCY: JICA | YACHIYO | ENGINEE | KING CO. L. | ::1 | | JA1E: 50/9/99 |
| TIEM | PROJECT | Vaza Barris Darn Project | LOCALL TATE | ON: | | | | 0,000 |
| Designation | WCK. | Concrete rioduction for Dan Body | T TNO | INDI FRIMD, | .1 | Discos (DC) | | מיי שמע ייס |
| Dam Concrete Type-2 Production for Dam Body per m² 71.85 | ITEM | DESCRIPTION | LINS | OTY | Unit Price | Sub-total | Total | REMARKS |
| Plant and Equipment Mixing Plant Mixing Plant | S-2 | Dam Concrete Type-2 Production for Dam Body per m3 | | | | | 71.85 | J |
| Mixing Plant m² 1 18.00 20.12 Diesel 0i. Diesel 0i. 1 0.65 2.12 Water Pumping Facility 6.09 0.09 0.09 Facility for water pumping m² 1 0.07 0.07 Diesel oil m² 0.036 0.53 0.02 Material liters 0.036 0.53 0.02 Comment comment kg 160 0.16 25.60 Supply of constent Supply of constent m² 0.80 15.00 25.60 Supply of constent m² 0.80 15.00 9.00 Transportation of crushed stone m² 1.40 3.60 3.00 | ₽ -4 | Plant and Equipment | | : | | | 20.21 | |
| Water Pumping Facility m² 1 0.07 0.07 Pacility for water pumping Diseased oil 0.036 0.53 0.02 Diseased oil Material 51.64 Comment Comment kg 160 0.16 25.60 Supply of coment Supply of cursted stone 15cm - 50cm m² 0.80 15.00 12.00 Supply of cursted stone < 2cm | p=4 p=1 | Mixing Plant Supply and Operation of mixing plant Driesel oil | ii m³ | ₹ | 18.00 | 18.00 | 20.12 | |
| Cement Cement Cement Cement Cement Cement Cement Cement Case Case | 12 | Water Pumping Facility Facility for water pumping Diesel oil | m³ | 0.036 | 0.07 | 0.07 | 0.09 | · · · |
| Cement Supply of cement Crushed stone Supply of cushed stone 15cm - 50cm Supply of crushed stone − 2cm Transportation of crushed stone Transportation of crushed stone Transportation of crushed stone Transportation of crushed stone | _ 7 | Material | | | | | 51.64 | |
| Crushed stone Supply of crushed stone 15cm - 50cm Supply of crushed stone < 2cm Transportation of crushed stone | | Cement Supply of cement | 89 | 160 | 0.16 | 25.60 | 25.60 | |
| | 2.2 | Crushed stone Supply of crushed stone 15cm - 50cm Supply of crushed stone < 2cm Transportation of crushed stone | មិខិទ | 0.80 0.60 1.40 | | 12.00 9.00 8.04 | 26.04 | Quotation Quotation Quotation |
| | | | | | | | | |
| | | | | | | | | |

| JAPAN INTERNATIONAL COOPERATION AGENCY: JICA | YACHIYOE | TOCATION : | 2000 | | | |
|--|--------------|----------------------|----------------------|-------------------------|--------|--------------|
| PKOJECI : vaza Barris Dam mojeci Wood : West Brazile Easilia | LIND | FIRST PHASE | Ξ | | | PAGE 8/8 |
| water rumping raciney | | | | Prices (RS) | 8 | 3/10/13/12/0 |
| ITEM DESCRIPTION | LING | OTY | Unit Price | Sub-total | Total | KEINIAKKS |
| Facility for water pumping from nearest perennial brook | | | . * | | 17,508 | |
| Earth work Deforestation and stripping Excavation Embankment | ê ê ê | 14,000 742 742 | 0.12 2.09 1.78 | 1,680 1,551 1,321 | 4,552 | |
| Steel Pipes Supply and Installation of pipe dia 75mm Supply and Installation of check valve dia 75mm | a iii | 510 | 20.22 | 10,312 | 10,840 | |
| Submersible Pump Supply of pump unit 20HP 125mca Installation of pump | unit unit | | 1560.00 | 1.560 | 2,116 | |
| Facility for water pumping per m? | | | | | 0.02 | |
| | | | | | | |
| | | | | | | |
| | | 1 | | | | |
| (BD) = 0.3 | | | | _ | | |

| PROJECT: Vaza B | PROJECT: Vaza Barris Water Supply Project | LOCATI | ON: | LOCATION: | 277 | | 77.00 |
|-----------------|---|---------|-------------------|------------|-----------------------|-----------|----------|
| 1 1 | Jam | UNIT: F | UNIT: FIRST PHASE | SE | | | PAGE 1/6 |
| ITEM | DESCRIPTION | TINS | ALO. | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| | Preliminary works | lot | | | 382,544 | | |
| Tempo | Temporary works | lot | | | 172,950 | ٠ | |
| Civil works | orks | lot | | · . | 3,704,700 | | |
| Grand Total | kio. | | | · | | 4.260.194 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | · |
| | | | | | | | |
| | | | . • | | | | ····· |
| | | | | | | | |
| | | | | - : : : | | | |
| (BDI = 0.3) | | | : | - | | | |

| TAPAN INTE | APAN INTERNATIONAL COOPERATION AGENCY : JICA | YACHI | YACHIYO ENGINEERING CO., LTD.: YEC | RING CO., L | TD.: YEC | | DATE: 30/9/99 |
|--|--|---------------|---------------------------------------|----------------------|-------------------------------------|---------|---------------|
| PROTECT | Vaza Barris Dam Project | LOCATION | TION: | | | | |
| WORK | Check Dam | TIND | UNIT: FIRST PHASE | 3) | | | PAGE 2/6 |
| MHT | DESCRIPTION | TIND | VT/V | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| 1. | Preliminary works | | | | | 382,544 | |
| 1.1 | Mobilization and demobilization | lot | *** | | 50,000 | 50.000 | |
| 1.2 | Site office, work spaces and camps | lot | | | 20,000 | 20.000 | |
| 1.3 | | | · · · · · · · · · · · · · · · · · · · | | | 281,644 | |
| 2.00 2.00 4.00 4.00 4.00 4.00 4.00 4.00 | 1 otal distance = 1500 m, koad widm = 5 m and walling ruca per 500m Regularization of sub-base Reinforcement (Thk = 0.5 m) Base With Graded Crushed Stone (Thk = 0.3 m) | ัย โย โย - | 7.650 3.750 2.295 25,000 | 3.94 2.85 2.09 | 3,213 14,775 22,606 52,250 | | |
| 13.5 | Embankment Deforestation and errinning of construction site | B B | 20,000 | | | 006 | |
| | | | | | | | |
| | | | | | | | |
| | | | | , | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | 《日本》,《《中文》,《本本》,日本《日本》,《古本》,中本《宋文》,《古书》,《古书》,《古书》,《《古书》,《《古书》,《《古书》,《《古书》,《《古书》,《《古书》,《《古书》,《《古书》,《 | ·. | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | | | · |
| | | | | ; | | | |
| | | | | | | | |
| | | | | | | | |

| PROTECT | AFAN INTERNATIONAL COOPERATION AGENCY : JICA PROJECT - Vara Barris Dan Project | | 1 OCATION | YACHIYO ENGINEERING CO., LID. : YEC | KING CO. | LID. YEC | | DAIE: 30/9/99 |
|-----------------------|---|---|-----------|-------------------------------------|------------|-------------|---------|---------------|
| WORK: | | | LING | UNIT : FIRST PHASE | Ö | | | PAGE 3/6 |
| ITEM | DESCRIPTION | | LINS | OTY | Unit Price | Prices (RS) | Total | REMARKS |
| | Temporary works | | | | | | 172,950 | 1 |
| 2.1 2.1.1 2.1.3 | Diversion of river Excavation of 1st category of soil Embankment | | 'a 'a | 15,000 | 2.09 | 31,350 | 172,950 | |
| | | | | | | | | |
| | | : | | | | | | |
| | | | | | | . : | | |

| APANINT | ATTON AGENCY : JICA | NOTATION. | ON . NO | TACALIO ENGINEERING CO.: ELC. TEC | 22 | | |
|----------------------------------|---|------------------|----------------------------|-----------------------------------|---------------------------------|-----------|----------|
| PROJECT: | Vaza Barris Dam Project | H LINS | UNIT: FIRST PHASE | Ü | | | PAGE 4/6 |
| WORK. | NOTE OF THE STATE | LING | O.T. | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| 11 EM | Civil works | | | | | 3.704.700 | · |
| 3.1.3 3.1.3 3.1.3 3.1.3 | Earth work Excavation of 1st category of soil Loading and transportation of 1at category of soil(0.4km) Embankment | មិនិមិ | 20.800 20.800 20.800 | 2.09 6.11 9.44 | 43,472 127,088 196,352 | 366,912 | |
| 3.2.1 3.2.1 3.3.2 | Concrete Production Concrete - Production, transportation and casting Reinforcing bars Form | e X e | 28,400 262,200 7,100 | 97.31 1.69 18.46 | 2,763,604 443,118 131,066 | 3.337,788 | |
| | | | | . • | | | |
| | | | | | | · | |
| | | | · | | | | |
| | | | | | | | |
| | | T ₂ . | | | | | |
| | | , | | | | | |
| | | | | | | | |
| | | | | | | | |
| | $\langle n_0 \rangle = 0.3$ (where $n_0 > 0.0$) is the second of the | | | 1 | | | |
| | (<i>BLX</i> = 0.3.) | | | | | | |

| ORK: ITEM | | | | | | | | |
|--------------|---|---------------------------------------|--------|----------------------|----------|-----------------------|-------|-------------------------------------|
| пем S-1 | Check Dam | | CNIT | UNIT: FIRST PHASE | SE | | | PAGE 5/6 |
| I EM | | | 1 | , ALLIC | 11.00 | Prices (RS) | Total | 3/10///20 |
| | Concrete Production for Dam Rody per m ³ | | T I | | Ont ruce | Suocore | 97.31 | NEWYNN |
| | | | | | | | | |
| | Plant and Equipment | | | | | | 36.12 | |
| | Mixing Plant Supply and Operation of mixing plant | | Ë | | | | 36.12 | |
| | Diesel oil | | liters | | 4 0.53 | 2.12 | | |
| | Material | | | | | | 61.19 | |
| | Cement Supply of cement | | gy | 200 | 0.16 | 32.00 | 32.00 | |
| 2.2 | Water Water produced by desalination plant | | Ē | 0.25 | 2.75 | 69:0 | 69:0 | |
| 2.3 | Crushed stone | | | | | | 28.50 | |
| | Supply of crushed stone 15cm - 50cm Supply of crushed stone < 2cm Transportation of crushed stone | | EEE | 0.90 0.60 1.50 | 15.00 | 13.50 9.00 6.00 | | Quotation Quotation Quotation |
| | | | | | | | | |
| | | · | - | | | | | |
| • | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | * * * * * * * * * * * * * * * * * * * | | | | | | |
| | | | | | | | : | : |
| | (BDI = 0.3) | | | | | | | |

| LOCATION: LOCATION: UNIT: FIRST PHASE Prices (RS) | TAPAN INT | APAN INTERNATIONAL COOPERATION AGENCY: JICA | YACHIYO I | SNGINEE | YACHIYO ENGINEERING CO., LTD.: YEC | D. : YEC | | DATE: 30/9/99 |
|--|-----------|--|-----------|------------------|------------------------------------|------------------------------------|-----------|---------------|
| TIEN | PROJECT | | LOCATIO | | | | | |
| Perices (KS) Perices (KS) | WORK | Check Dam | UNIT: FIR | ST PHAS | 3 | | | PAGE 6/6 |
| Water Production by Desaination Plant per m² Plant and Equipment Desaination Plant with production capacity of 50m²/day Supply of desalination plant sm x 5m Generator Operating Period Cost of desalination plant per m³ of water Water Production Cost by desalination plant per m³ of water (BDI = 0.3) | ITEM | | TIND | OTY | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| production capacity of 50m²/day unit 1 32500.00 13,000.00 unit 1 13000.00 5,000.00 unit 1 1 3000.00 5,000.00 s 5m²/day unit 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | S-2 | Production by Desalination Pl | | | | | | |
| production capacity of 50m²/day unit 1 32500.00 32,500.00 x 5m 1 15000.00 13,000.00 unit 1 15000.00 5,000.00 5,000.00 sign plant per m³ of water | | Plant and Equipment | | | | | 50.500.00 | |
| s nation plant per m³ of | 1.1 | Desalination Plant Supply of Gom ² /day Supply of desalination plant with production capacity of 50m ² /day House for desalination plant 3m x 5m Generator | unit ti | first first dwar | 32500.00 13000.00 5000.00 | 32,500.00 13,000.00 5,000.00 | 50,500.00 | |
| nation plant per m³ of | | | | | | | | |
| | | Cost of desalination plant per m ³ Operation cost per m ³ | | | | | 2.35 | |
| | | | | | | | | |
| $(\mathbf{EDI} = 0.3)$ | | | | | | | 2.75 | |
| (BDI = 0.3) | | | | | | | | |
| (BDI = 0.3.) | | | | | | - | | - |
| (BDI = 0.3.) | | | | ÷ | | | | |
| (BDI = 0.3.) | | | | | | | | |
| (BDI = 0.3) | | | | | | | | |
| | | | | ; · | | | | |
| (BDI = 0.3) | | | | | | | | |
| | | (BDI = 0.3) | | | | | | |

| OJECT: | PROJECT: Vaza Barris water Supply Project | LOCATION | | LOCATION: | | | |
|--------|---|----------|-------------------|------------|-----------------------|-------|----------|
| WORK: | Low Flow Bypass - Box Culvert 1,050 x 1,050 | HIS | UNIT: FIRST PHASE | SE | | | PAGE 1/7 |
| ITEM | DESCRIPTION | UNIT | OTY | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| | Preliminary works | lot | | | 2,916,208 | (U) | |
| | Civil works | ğ | | | 29,913,782 | | |
| | | | | | | | |
| | | | | | | | |

| T. 1 . 7 . 7 . 7 | A COLOR OF | VACHIVO | FACINE | VACHIYO ENGINEERING CO. L.TD.: YEC | TD: YEC | | DATE: 30/9/99 |
|--------------------------------------|--|------------|---|---|---|-----------|--|
| DOOTE OF | AGENCI : JOSE | LOCATION | Z | | | | |
| | I ow Flow Bynass - Box Culvert 1.050 x 1.050 | SNT: FI | UNIT: FIRST PHASE | Ξ | | | PAGE 2/7 |
| TTEM | DESCRIPTION | EN S | O.T.V | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| 1. | Preliminary works | | | | | 2,916,208 | |
| 7.7 | Mobilization and demobilization | lot | | | 300,000 | 300,000 | |
| 1:2 | Site office, work spaces and camps | lot | 1-4 | | 900,000 | 900,000 | |
| 1.3 | Access road | | | | | 1,683,870 | |
| 1.3.1 | Access Road (New construction) Total Distance = 1500 m x 3 routes | | | | | 844,931 | |
| 13.1.1 13.1.2 13.1.3 13.1.4 | 1 Per 500 of Sub-Ba of Sub-Ba of Crushe | មិនិមិនិ | 22.950 11.250 6.885 75.000 60,000 | 0.8.9.9. 24.8.8.4 24.09.4 | 9.639 44.325 67.817 156.750 566.400 | | 20301001 20302001 20307003 20307003 |
| 1.3.2 | Access Road (Expansion of existing pathway) Total Distance = 3500 m x 3 routes Expansion of Road Width = 2 m | | | | | 838,939 | |
| 1321 1322 1323 1324 1325 | Dista one (| ริธิธิธิธิ | 22,050 10,500 6,615 75,000 | 0 8 9 9 9 9 4 5 4 5 6 5 4 5 6 5 6 5 6 5 6 5 6 5 6 5 | 9.261 41,370 65,158 156,750 566,400 | | 20301001 20302001 20307003 20307003 20307003 |
| 7. 1 | Deforestation | 2 | 269,485.00 | 0.12 | 32.338 | 32,338 | |
| | (BDI=0.3): Let us the second of the second o | | | | | | |

| TABAN BITE | ADAN BITTERNATIONAL COOREDATION ACENICY - 11CA | VACCITY | OO OM dasidons Oxino v x | T OD SINIA | 737. 77.1 | | DATE: 30/0/00 |
|------------|---|---------|--------------------------|------------|----------------------|------------------------------------|---|
| PROJECT | Vaza Barris water Supply Project | LOCAT | LOCATION: | ≺ I : | } | ar on the windows throught and the | 200000000000000000000000000000000000000 |
| | Low Flow Bypass - Box Culvert 1,050 x 1,050 | HIS | UNIT: FIRST PHASE | SE | | | PAGE 3/7 |
| H | | | | | Prices (RS) | | |
| ITEM | DESCRIPTION | LINS. | Q'T'Y | Unit Price | Sub-total | Total | REMARKS |
| .5 | Civil works | | | | | 29,913,782 | idania eta 10 Peta 51 |
| 2.1.1 | Box Culvert Box Culvert 1,050 x 1,050 | E | 27,720.00 | 982.60 | 27,237,672 | 27.237.672 | |
| 222 | Earth work Mechanical Soil Excavation Embankment w/ excavated soil, 95% Proctor | ÊÊ | 239,509.00 | 3.38 | 809.540 1,866,570 | 2,676,110 | edau sercentarena anti- |
| | | | | | | | |
| | | | | | | | |
| | | i. | | | ·. | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | and the second second |
| | | | | | : | | nacenies |
| | | | | | , , | | |
| | | | | | 4 | | |
| | (BDI = 0.5) | | | | | | |

| JAPAN INT | ERNATIONAL COOPERATION AGENCY: JICA | YACHIY | O ENGINE | YACHIYO ENGINEERING CO., LTD. : YEC | JTD.: YEC | | DATE: 30/9/99 |
|------------|---|----------------|-------------------|-------------------------------------|-----------------------|--------|---------------|
| PROJECT | : Vaza Barris water Supply Project | LOCATION | : NOI | | | | |
| WORK | Low Flow Bypass - Box Culvert 1.050 x 1.050 | LENS | UNIT: FIRST PHASE | SE | | | PAGE 4/7 |
| Mari | DESCRIPTION | TIND | YTO | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| S-1 | Box Culvert per meter | | | | | 982.60 | |
| | Leveling Concrete | Ê | 0.205 | 111.6 | 22.88 | | 10303006 |
| | Concrete Fck=21Mpa | Ê | 2.320 | 150.28 | 348.65 | | 10303006 |
| - | Form | m ₂ | 5.800 | 19.59 | 113.62 | | 10301003 |
| · . | Reinforcement 120kg/m ³ | ** \$0 | 278.40 | 1.69 | 470.50 | | 10305004 |
| ين و دار د | Water-Stop | E | 0.390 | 46.67 | 18.20 | | 10301003 |
| | Scaffolding | E | 1.103 | 7.94 | 8.75 | | 10304005 |
| | | | | - | | | |
| | | | | | | | |
| | | | | : | | | |
| | | | | | | | |
| | | | | | | • | - |
| | (108) = 103) | | | | : | : | |
| | | | | | | | |

| PROJECT: Vaza Barris water Supply Project | LOCATION: | EERLING CO., E. | 17 15. | | DA1E. 30(3)37 |
|--|---------------------------------------|-----------------|-------------|--------|---------------|
| WORK: Low Flow Bypass - Box Culvert 1.050 x 1.050 | UNIT: FIRST PHASE | ASE | | | PAGE 5/7 |
| 1 Committee of the state of the | | 4 | Prices (RS) | £ | |
| Over the Droding Box | ONII OLIX | Onit Price | Suo-total | 100al | KEMAKKS |
| Convicte 211799 Frounchion for Day Curvett per III | | : | | 120.28 | |
| Plant and Equipment | | | | 26.12 | |
| Mixing Plant | e e | | | 26.12 | |
| Supply and Operation of mixing plant Diesel oil | m' liters | 4 0.53 | 24.00 | | |
| Material | | | | 85.19 | |
| Cement | • | | | 26.00 | |
| Supply of cement | kg 350 | 0.16 | 26.00 | | |
| Water | · · · · · · · · · · · · · · · · · · · | | | 0.69 | |
| Water produced by desalination plant | m³ 0.25 | 5 2.75 | 0.69 | | |
| Crushed stone | | | | 28.50 | |
| Supply of crushed stone < 2cm Supply of sand | m ³ 0.90 | 15.00 | 13.50 | | |
| Transportation of crushed stone | | | 8.9 | | |
| Transportation | | - | | 4.58 | |
| Concrete | т, | 0 4.58 | 4.58 | | |
| Casting of concrete | | | | 34.39 | |
| Casting of concrete for structure | 1.00 | 34.39 | 34.39 | | |
| | | | | | |
| | | | | : | • |
| | | | | | |
| | | | | | |
| | | | | | |

| PROTECT | PROJECT : Vaza Barris water Supply Project | 1001 | LOCATION: | | | | |
|---------|--|------------|---------------------------------------|------------|-----------------------|--------|----------|
| WORK: | Low Flow Bypass - Box Culvert 1.050 x 1.050 | 5 | UNIT: FIRST PHASE | SE | | | PAGE 6/7 |
| | | _ | | | Prices (RS) | | |
| TEM | DESCRIPTION | TIND | OTY | Unit Price | Sub-total | Total | REMARKS |
| | Concrete Production for leveling concrete per m ³ | | | | | 111.60 | |
| | Plant and Equipment | | · · · · · · · · · · · · · · · · · · · | | | 26.12 | |
| | Mixing Plant Supply and Operation of mixing plant | m. | - V | 24.00 | 24.00 | 26.12 | |
| | Dieser ou Material | | | | | 61.19 | |
| | Cement Supply of coment | × × | 500 | 0.16 | 32.00 | 32.00 | |
| | Water Water produced by desalination plant | . É | 0.25 | 2.75 | 0.69 | 69:0 | |
| | Crushed stone Supply of crushed stone < 2cm Supply of sand Transportation of crushed stone | EEE | 0.90 0.60 0.60 0.50 | 15.00 | 13.50 9.00 6.00 | 28.50 | |
| | Transportation Concrete | Ê | 1.8 | 4.58 | 4.58 | 4.58 | |
| | Casting of concrete Casting of leveling concrete | Ē | 1.00 | 19.71 | 19.71 | 19.71 | |
| | | | | | | | |
| | | | | | | | |

| APAN INT | APAN INTERNATIONAL COOPERATION AGENCY : JICA | YACHIYO | ENGINE | YACHIYO ENGINEERING CO., LTD | TD. : YEC | | DATE: 30/9/99 |
|-----------|---|--------------|-------------------|---------------------------------|------------------------------------|-----------|---------------------------------------|
| PROJECT | PROJECT : Vaza Bartis water Supply Project | LOCATION | . NO | | | | |
| WORK: | Low Flow Bypass - Box Culvert 1.050 x 1.050 | UNIT: F | UNIT: FIRST PHASE | SE. | | • | PAGE 7/7 |
| ITEM | DESCRIPTION | LINS | O.T. | Unit Price | Prices (RS) | Total | REMARKS |
| %4 8.4 | Water Production by Desalination Plant per m³ | | | | | | |
| | Plant and Equipment | | | | | 50,500.00 | · . |
| = | Desalination Plant Supply of desalination plant with production capacity of 50m³/day House for desalination plant 3m x 5m Generator | unit unit | | 32500.00 13000.00 5000.00 | 32.500.00 13,000.00 5.000.00 | 50.500.00 | |
| | Operating Period 20 months | | | | | | |
| | Cost of desalination plant per m ³ Operation cost per m ³ | | | | | 2.35 | · · · · · · · · · · · · · · · · · · · |
| | | | | | | | |
| | Water Production Cost by desalination plant per m² of water | | | | | 2.75 | |
| • | | | | | | : | |
| | | | | | | | · |
| | | | | | | : . | |
| | | | | | | | |
| | | | | . • | | | |
| | | | | | | | |
| | | | | | | | - |
| | 100 - | | | : | : | | |
| | (5.7 - 1.3) | | | | | | |

Sec. 1

| | Items | Phasel | Phase2 | Total |
|--|--|------------|------------|---------------------------------------|
| ি | Site Preparation | 1,601,874 | 0 | |
| 3.7% | S/S | 1,618,902 | 0 | |
| 4 | Control Building | 24,579 | 0 | |
| ting | Water Intake Pump Station | 2,600,522 | 0 | |
| Common 3%, Piaui | Water Intake Pump Station | 0 | 688,857 | : * |
| o v | Pipeline from WIPS to CR1 | 182,744 | 0 | |
| ဝရွိ | Pipeline from WIPS to CR2 | 0 | 127,192 | |
| 5 | Connecting Reservoir No.1 Capacity 3,000m ³ | 653,230 | 0 | |
| Common Agreste 51.3%, Piauitinga 48.7%) | Connecting Reservoir No.2 Capacity 3,000m³ | 0 | 554,285 | • |
| \$ | Pipeline from CR1 to WLPS1and CR2 to WLPS2 | 52,788 | 0 | 11. |
| , . | Common Total | 6,734,639 | 1,370,334 | 8,104,97 |
| | Water Lift Pump Station No.1 to Itabaiana | 690,860 | 0 | |
| | Water Lift Pump Station No.1 to Itabaiana | . 0 | 451,667 | * * * * * * * * * * * * * * * * * * * |
| . Ste | Pipeline from WLPS1 to CR3 | 15,481,862 | 0 | |
| Agreste | Pipeline from WLPS1 to CR3 | 0 | 8,176,107 | |
| ~ | One Direction Surge Tank | 77,311 | 0 | |
| | Connecting Reservoir No.3 Capacity 3,000m ³ | 0 | 603,758 | |
| | Agreste Total | 16,250,033 | 9,231,532 | 25,481,50 |
| | Water Lift Pump Station No.2 to Lagarto | 690,860 | 0 | |
| | Water Lift Pump Station No.2 to Lagarto | 0 | 451,667 | |
| ga | Pipeline from WLPS2 to CR4 | 15,587,606 | 0 | |
| Piauitinga | Pipeline from WLPS2 to CR4 | 0 | 8,222,062 | |
| Pia | One Direction Surge Tank No.1 | 82,126 | 0 | |
| | One Direction Surge Tank No.2 | 90,150 | 0 | |
| | Connecting Reservoir No.4 Capacity 3,000m ³ | 0 | 603,757 | |
| 1. | Piauitinga Total | 16,450,742 | 9,277,486 | 25,728,2 |
| | Total | 39,435,414 | 19,879,352 | 59,314,7 |

| | JAPAN IN IERNATIONAL COOPERATION AGENCY : JICA | YACHIY | O ENGINE | YACHIYO ENGINEERING CO., LTD. : YEC | JD. : YEC | | DATE: 30/9/99 |
|---------|--|-----------|-------------------|-------------------------------------|-------------|-----------|---------------|
| PROJECT | : Vaza Barris Water Supply Project | LOCATION: | : NO | | | | |
| WORK: | WORK: Preparation work (Common) | TIND | UNIT: FIRST PHASE | SE | | | PAGE 1/3 |
| ITEM | DESCRIPTION | UNIT | OTY | Unit Price | Prices (RS) | Total | REMARKS |
| | Preliminary works | lot | - | | 1,401,848 | | |
| | Civil works | ŏ | end | | 200,026 | | |
| | Grand Total | | | | | 1,601,874 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | - | |
| | | | | | · . | | |
| | (BDI ± 0.3) | | | | | | |

| A PAN IN LA | APAN INTERNATIONAL COOPERATION AGENCY SUCA BEATECT: Very Bornis Water Suraly Project | CT: JICA | LOCATION | TON: | LOCATION: | | | |
|-------------|---|-------------|-----------|--------------------|------------|--------------------------|-----------|----------|
| WORK . | Varia Battle Water Supply Figure Preparation work (Common) | | : LIND | UNIT : FIRST PHASE | SE | | | PAGE 2/3 |
| ITEM | | DESCRIPTION | דואט | OTY | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| | Preliminary Works | | | | | | 1,401,848 | |
| 1.1 | Mobilization and demobilization | | <u>10</u> | | | 400,000 | | |
| 1.2 | Site office, work space and camp | | Jot | | | 1,000,000 | | |
| 1.3 | Deforestation and stripping | | Ë | 15,397 | 0.12 | 1,848 | | |
| | | | | | | | | |
| | | | <u> </u> | | | : | | |
| | | | | | | | | |
| | | | | | , | | | |
| | (BD) = 0.3) | | | | | | | |

| TAPANTANT | APAN NITERNATIONAL COOPERATION A CENCY - IICA | IVACHIV | ココンロンコンド | VACHIVO ENGINEERING CO. T.T.D | | a service and a service and a | DATE: 30/9/99 |
|-------------------------------------|--|----------|----------------------|-------------------------------|-----------------------|-------------------------------|---|
| PROJECT | PROJECT: Vaza Barris Water Supply Project | LOCATION | . NO | | | | |
| WORK: | Preparation work (Common) | LINS | UNIT: FIRST PHASE | E E | | | PAGE 3/3 |
| ITEM | DESCRIPTION | LIND | OTY | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| 2 | Civil Works | | | | | 200,026 | |
| 2.1. | Earthworks Mechanical excavation, loading and transportation (0.4km) of soil | Ë | 76,778 | 2.03 | 155,860 | 155,860 | |
| 2221 2221 2221 2221 232 | Others Fence and Gates Fence H=2.1 with concrete post Double Swing Gate, W = 4.0m x 2 Concrete pavement t=10cm | 2 a a a | 420 16.8 1,717 | 24.84 137.4 15.39 | 10,433 | 44,166 | |
| | | \$ | • | |))) ; | | от простуду в постой выборий в постой |
| | | | | | | | |
| | | | | | | | |
| · | | · . | , , | | | | |
| | | | | | | | |
| | | | | | | : | |
| | (BDI=0.3) | | | | | | |

| TOTAL CAR | DECIECT : Very Bearing Water Strank Project | 1000 | | | | LOCATION | . NC | LOCATION: | | | |
|-----------|---|-------------|---|----|---|--------------|--------------------|------------|--------------------------|-----------|----------|
| | 69kV Substation Yard (Common) | | | | | TINS TINS | UNIT : FIRST PHASE | SE | | | PAGE 1/3 |
| ITEM | | DESCRIPTION | | | | TIND | QTY | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| | Civil works | | · | | | lot | 1 | | 19,773 | | |
| | Electrical works Grand Total | | | | | ţo | H | | 6,020,906 | 6,040,679 | |
| | | | 4 | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | · · · · · · · · · · · · · · · · · · · | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | .* | | | | | | | |
| | | | | | · | - | | | | | |
| | | | | | | | , | | | . : | |
| | | | | | | | | | | | |
| * ; | | | | | | | | | | | |

| JAPAN INT | APAN INTERNATIONAL COOPERATION AGENCY : JICA | YACHIYC | SENGINEE | YACHIYO ENGINEERING CO., L.TD. : YEC | TD.: YEC | | DATE: 30/9/99 |
|-------------------------------------|---|----------|------------------------|---------------------------------------|--------------------------------|--------|--|
| PROJECT | PROJECT: Vaza Barris Multi-purpose Dam Project | LOCATION | ON: | | | | |
| WORK: | 69kV Substation Yard (Common) | UNIT: F | UNIT : FIRST PHASE | B | | | PAGE 2/3 |
| ITEM | DESCRIPTION | UNIT | OTY | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| 1 | Civil works | | | | | 19,773 | |
| 111 1112 1113 1114 1115 | Earthworks Mechanical excavation of soil Disposal of excavated material Compacted backfill Compacted Gravel for fdn Gravel for yard | สิธิสิสิ | 2,821 4 8 2,821 4 8 | 2.09 2.37 1.78 18.88 17.1 | 107 71 37 76 855 | 1,146 | and an angle of the second |
| 121 122 123 123 121 | Concrete works Structural concrete, fck=25Mpa Reinforcing steel Form - structure Leveling concrete, fck=15Mpa | .e %.e.e | 45 3,210 108 | 142.38 1.69 19.59 129.1 | 6,407 5,425 2,116 258 | 14,206 | Pakirianthalish Dakirayay vecinyay seri |
| 1.3 1.3.1 1.3.2 | Fence and Gates Barbed wire fence H=2.5 Double swing gate | S B | 25 | 27.92 | 1,536 | 4,421 | |
| | | | | | | | |
| | App = 0.3.) | | | | | | nacional de la constitución de l |
| | | | | | - | | 8 |

| PROJECT Van Barris Water Supply Protect | JAPAN INT | APAN INTERNATIONAL COOPERATION AGENCY : JICA | YACHIY | O ENGINE | YACHIYO ENGINEERING CO., LTD. : YEC | TD: YEC | | DATE: 50/9/99 |
|--|----------------------------|---|----------|--------------|-------------------------------------|-----------------------------------|-----------|-------------------------------------|
| Electrical Works DESCRIPTION UNIT FIRST PHASE Prices (ES) Electrical Works | PROJECT | Vaza Barris Water Supply Project | LOCAT | ION: | | | | |
| Exercical Works Supply and erection of electrical cut-going and out-door switchgaar facilities Supply and erection of electrical out-going and out-door switchgaar facilities at the Existing Capinos 856 (facilidating the cost for related civil works) Supply and centro of electrical in-coming and out-door switchgaar facilities (Including the cost for related civil works) Supply and centro of electrical in-coming and out-door switchgaar facilities Admin transformers, distribution beards, DC power swipply equipment, control and protection panels and eables Equipment and material supply Insurance and Freight Exerciton and commissioning Grounding (IND) = 0.3 (IND) = | WORK | 69kV Substation Yard (Common) | EES | FIRST PHAS | SE | | | PAGE 3/3 |
| Electrical Works Electrical Works Supply and erection of electrical investigate facilities at the Evisting Cajaiba S/S (Including the cost for related civil works) Supply and erection of electrical in-coming and out-cloor switchgaar facilities into the Evisting Cajaiba S/S (Including the cost for related civil works) Supply and erection of transmission line from Cajaiba S/S to the New S/S km in including the cost for related civil works) Supply and erection of transmission line from Cajaiba S/S to the New S/S (Including the cost for related civil works) Main mansformers, distribution beautist D/C power supply equipment, control and protection panels and cabies Equipment and material supply in including the cost for related civil works) Main mansformers, distribution beautists D/C power supply equipment, control and protection panels and cabies Equipment and material supply Exection and commissioning Grounding INDI-0.3.3 INDI-0.3.3 INDI-0.3.3 | 1 | | | | | Prices (RS) | | 1 |
| Electrical Works Supply and erection of electrical out-going and out-door switchgear facilities at the Existing Cajaba S/S (Including the cost for related civil works) Supply and construction of frantamission line from Cajaba S/S to the New S/S (Including the cost for related civil works) Supply and crection of electrical in-coming and outdoor switchgear facilities at New S/S (Including the cost for related civil works) Main transformers, distribution boards, DC power supply equipment, control and protection panels and cabics Equipment and material supply Insurance and Freight Erection and commissioning Grounding Grounding In 1,000,00 In 1,000,00 In 1,000,00 | ITEM | DESCRIPTION | TINS | O'TY | Unit Price | Sub-total | Total | REMARKS |
| Supply and erection of electrical out-going and out-door switchgear facilities at the Existing Cajaiba S/S (Including the cost for related civil works) Supply and construction of transmission line from Cajaiba S/S to the New S/S (Including the cost for related civil works) Supply and ceretion of electrical in-coming and outdoor switchgear facilities at New S/S (Including the cost for related civil works) Main transformers, distribution boards, DC power supply equipment, control and protection panels and cables Equipment and material supply Insurance and Freight Eventon and commissioning Grounding Grounding (FIDT = 0.3) | 2 | Electrical Works | | | | | 6,020,906 | |
| Supply and construction of transmission line from Cajaiba S/S to the New S/S (Including the cost for related civil works) Supply and erection of electrical in-coming and outdoor switetgear facilities at New S/S (Including the cost for related civil works) Main transformers, distribution boards, DC power supply equipment, control and proceeding panels and eables Equipment and material supply Exercise and Freight Exercise and commissioning Grounding (Grounding - 100000 1.0000000000000000000000000000 | 2.1 | Supply and erection of electrical out-going and out-door switchgear facilities at the Existing Cajaiba S/S (Including the cost for related civil works) | io | | | 272,470 | 272,470 | Quotation |
| Supply and erection of electrical in-coming and outdoor switchgear facilities at New S/S (Including the cost for related civil works) Main transformers, distribution boards, DC power supply equipment, control and protection panels and cables Equipment and material supply Insurance and Freight Erection and commissioning Grounding Grounding Supply and outcoles 100 11 1272,470 4,917,216 13,335,002 238,214 100 11,000,00 1,000 1,000 1,000,00 1,000 1,000,00 1,000,00 1,000,00 1,000,00 1,000 | 2.2 | Supply and construction of transmission line from Cajaiba S/S to the New S/S (Including the cost for related civil works) | Ę | 11.5 | | 557,750 | 557.750 | Quotation |
| Main transformers, distribution boards, DC power supply equipment, control and protection panels and cables 3,335,002 100 10 | 2.3 | Supply and erection of electrical in-coming and outdoor switchgear facilities at New S/S (Including the cost for related civil works) | ĵo Ot | | | 272,470 | 272,470 | Quotation |
| Equipment and material supply Insurance and Freight Erection and commissioning Grounding (GR)1=0.3.) | 2.4 | Main transformers, distribution boards, DC power supply equipment, control and | | | | | 4,917,216 | |
| Grounding 1 1,000.00 1 1,000 | 2.2.2. 2.4.1. 2.4.2. | protection panels and cables Equipment and material supply Insurance and Freight Erection and commissioning | <u> </u> | H H H | | 3,335,002 238,214 1,344,000 | | Quotation Quotation Quotation |
| | 2.5 | Grounding | lot | | : | 1,000.00 | 1,000 | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | · | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

| PROJECT | PROJECT: Vaza Barris Water Supply Project | | LOCATION | . ZO | LOCATION: | | | |
|---------|---|----------------|----------|---------------|------------|-----------------------|--------|----------|
| WORK: | Control and Electrical Building (Common) | | UNIT: FI | : FIRST PHASE | SE | | | PAGE 1/4 |
| ITEM | SCRIPTIC | X _C | TIND | O'T'Y | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| | Execution of civil works Electrical erections | | lot | | | 86,714 | | |
| | Grand Total | | | | | | 91.714 | |
| | | | | | | | | - - |
| | (BDI = 0.3) | | | | | | | - |

| TAPANINT | APAN INTERNATIONAL COOPERATION AGENCY : IICA | YACHIY | ENGINE | YACHIYO ENGINEERING CO., LTD. : YEC | LTD.: YEC | | DATE: 30/9/99 |
|--|---|----------------------|--------------------------|-------------------------------------|------------------------------------|--------|---------------|
| PROTECT | | LOCATION | . No | | | | |
| WORK | Control and Electrical Building (Common) | LLIS | UNIT: FIRST PHASE | SE | | | PAGE 2/4 |
| TTEM | DESCRIPTION | TING | \$T\$ | Unit Price | Prices (RS) Sub-total | Total | REMARKS |
| | Execution of civil works | | | | | 86,714 | · |
| | Preliminary works Location of the building | ²E | 231 | 1.61 | 372 | 372 | |
| 1.2 1.2.1 1.2.2 1.2.3 | Earthworks Mechanical excavation of soil H<=2 Disposal of excavated material Compacted backfill | ខិតិ | 151 34 117 | 2.09 2.37 9.44 | 316 81 1,104 | 1,501 | |
| 1.3.2 1.3.3 1.3.4 | Concrete works Plain concrete, fck=15Mpa Scructural concrete, fck=21Mpa Reinforcing steel Form | a"% B B | 32 85 9,350 508 | 129.1 148.59 1.69 19.59 | 4,131 12,630 15,802 9,952 | 42,515 | |
| 4. | Scaffolding and Stage Scaffolding Stage | 12,5 | 108 130 | 7.94 | 858 11,259 | 12,117 | |
| 115.1 15.1 15.2 15.2 | Closure Brick masonry, Ceramic brick 8 holes Rocking, including wood works, hardware, fibercement roof Canalete 49 type or equivalent | ë ë | 143 | 29.41 | 4,206 9,418 | 24,023 | |
| 11.55.11 15.53.12 11.52.22 11.52.22 | Aluminum tilting window Aluminum door Wooden door Plain transparent glass with 4mm thk | m ² fruit | 58 10 8 3 8 | 122.03 109.03 39.94 36.4 | 7,078 1,090 120 2,111 | | |
| | | | | | | | |
| | | | | | | | |