

JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)

No. 64


DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA  
MINISTRY OF TRANSPORT AND HIGHWAYS  
ROAD DEVELOPMENT AUTHORITY (RDA)

# THE STUDY ON THE OUTER CIRCULAR HIGHWAY TO THE CITY OF COLOMBO

## FINAL REPORT



VOLUME 3 OF 5



**MAIN TEXT II**  
**ANNEX I**  
**TRAFFIC SURVEY DATA & TRAFFIC MODEL RESULTS**  
**ANNEX II**  
**GROUND SURVEY DATA**

FEBRUARY 2000

ORIENTAL CONSULTANTS COMPANY LIMITED

SSF

CR(3)

00-054







JAPAN INTERNATIONAL COOPERATION AGENCY (JICA)

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA  
MINISTRY OF TRANSPORT AND HIGHWAYS  
ROAD DEVELOPMENT AUTHORITY (RDA)

**THE STUDY ON  
THE OUTER CIRCULAR HIGHWAY  
TO THE CITY OF COLOMBO**

**FINAL REPORT**

**VOLUME 3 OF 5**

**MAIN TEXT II**

**ANNEX I**

**TRAFFIC SURVEY DATA & TRAFFIC MODEL RESULTS**

**ANNEX II**

**GROUND SURVEY DATA**

FEBRUARY 2000

**ORIENTAL CONSULTANTS COMPANY LIMITED**



1157443 [1]

The following foreign exchange rate is applied in the study :

Sri Lankan Rs.= 1.6 YEN (as of December 1999)

## TABLE OF CONTENTS

### FINAL REPORT

#### VOLUME 1 of 5 : EXECUTIVE SUMMARY

#### VOLUME 2 of 5 : MAIN TEXT I

#### LOCATION MAP SUMMARY

	PAGE
CHAPTER 1 GENERAL.....	1-1
1.1 Introduction .....	1-1
1.2 Background.....	1-1
1.3 Objective.....	1-2
1.4 Study Area .....	1-3
1.5 Scope of the Study.....	1-3
1.6 Study Approach .....	1-6
1.7 Study Implementation Plan .....	1-6
1.7.1 Preparatory Work in Japan.....	1-6
1.7.2 First Mission to Sri Lanka .....	1-6
1.7.3 First Project Work in Japan.....	1-9
1.7.4 Second Mission to Sri Lanka.....	1-9
1.7.5 Second Project Work in Japan .....	1-11
1.7.6 DF/R Explanation Mission to Sri Lanka .....	1-11
1.7.7 Final Report Preparation Work in Japan.....	1-11
1.7.8 Study Organization .....	1-12
1.7.9 Report Submission.....	1-12
CHAPTER 2 PRESENT SITUATION.....	2-1
2.1 Natural Conditions.....	2-1
2.1.1 Topography .....	2-1
2.1.2 Climate and Hydrology.....	2-1
2.1.3 Geology.....	2-3
2.2 Socio-Economic Characteristics.....	2-6

	PAGE
2.2.1 Administrative Structure of Colombo Metropolitan Region ( CMR ) .....	2-6
2.2.2 International and National Socio-Economic Context of the CMR.....	2-6
2.2.3 Socio-Economic Characteristics in the Study Area.....	2-11
2.3 Transportation.....	2-20
2.3.1 Road Transport .....	2-20
2.3.2 Rail Transport .....	2-24
2.3.3 Problems with Transportation System.....	2-26
2.3.4 The Direction Forward .....	2-27
<b>CHAPTER 3 RELEVANT DEVELOPMENT PLANS AND STUDIES.....</b>	<b>3-1</b>
3.1 General.....	3-1
3.2 Colombo Metropolitan Regional Structure Plan (CMRSP) .....	3-1
3.3 Colombo Urban Transportation Study (CUTS).....	3-2
3.4 Pre-Feasibility Study for an Outer Circular Road to City of Colombo.....	3-2
3.5 Southern Area Development.....	3-2
3.6 Southern Transport Corridor.....	3-3
3.7 Colombo-Katunayake Expressway (CKE).....	3-5
3.8 Land Reclamation and Urban Development in Kerawalapitiya....	3-5
3.9 Other New Highway Projects .....	3-6
3.9.1 Colombo-Kandy Expressway .....	3-6
3.9.2 Alternate Highway from Katunayake to Padeniya .....	3-7
3.9.3 Alternate Highway from Colombo to Ratnapura Via Ingiriya .....	3-7
3.10 Major Road Rehabilitation Projects .....	3-7
3.10.1 Colombo-Ratnapura Road (A4).....	3-7
3.10.2 Panadura-Ratnapura Road (A8).....	3-8
<b>CHAPTER 4 SOCIO – ECONOMIC FRAMEWORK .....</b>	<b>4-1</b>
4.1 General.....	4-1
4.1.1 Objectives of the Socio-Economic Framework Formulation.....	4-1
4.1.2 Basic Policy for Formulating the Socio-Economic Framework .....	4-1



	PAGE
4.1.3 Existing Studies.....	4-2
4.2 Forecast of Economic Growth by District.....	4-2
4.2.1 General.....	4-2
4.2.2 Outline of Forecasting Steps and Procedures.....	4-3
4.2.3 Results of Forecast.....	4-11
4.3 Forecast of CMR Population by DS Division.....	4-24
4.3.1 Forecasting Methods.....	4-24
4.3.2 Forecasting Procedures of DS Division Population.....	4-29
4.3.3 Results of Forecast.....	4-30
4.4 Forecast of Employment by DS Division in the CMR.....	4-33
4.4.1 Outline of Forecasting Method.....	4-33
4.4.2 Forecasting Procedures of Employment by DS Division...	4-34
4.4.3 Results of Forecast.....	4-41
4.5 Forecast of Number of Vehicles by Vehicle Type and Division in the CMR.....	4-47
4.5.1 Comments and Summary.....	4-47
4.5.2 Forecast of Car Ownership by DS Division.....	4-50
4.5.3 Forecast of Motorcycle Ownership by DS Division.....	4-62
4.5.4 Forecast of Bus Ownership by DS Division.....	4-68
4.5.5 Forecast of Van Ownership by Division.....	4-74
4.5.6 Forecast of 3-Wheeler Ownership by District.....	4-79
4.5.7 Forecast of Number of Lorries (Freight vehicle).....	4-84
 CHAPTER 5 TRAFFIC DEMAND.....	 5-1
5.1 Objective.....	5-1
5.2 Overall Workflow.....	5-1
5.3 Traffic Survey.....	5-2
5.3.1 Execution Plan for Traffic Survey.....	5-3
5.3.2 Roadside OD Survey, Traffic Volume Survey, Bus Passenger Volume Survey.....	5-6
5.3.3 Turning Movement Survey.....	5-12
5.3.4 Travel Speed Survey.....	5-12
5.3.5 Bus Passenger Interview Survey.....	5-12
5.3.6 Traffic Survey Results & Analyses.....	5-19
5.4 Building of Traffic Demand Model.....	5-29
5.4.1 Forecasting Methodology.....	5-29

	PAGE
5.4.2 Outline of Traffic Model Data and Development .....	5-29
5.4.3 Trip Generation/ Attraction Model .....	5-36
5.4.4 Trip Distribution Model.....	5-37
5.4.5 Modal Split Model.....	5-42
5.4.6 Traffic Assignment Model.....	5-42
5.5 Future Traffic Demand .....	5-44
5.5.1 Future Road Network Improvements .....	5-44
5.5.2 Traffic Demand Forecasts for 2010 &2020.....	5-46
<b>CHAPTER 6 ENGINEERING SURVEY .....</b>	<b>6-1</b>
6.1 Aerial Photograph Survey.....	6-1
6.1.1 Air Survey.....	6-1
6.1.2 Creation of Digital Photo -- Mosaics for Route Selection ....	6-3
6.1.3 Ground Survey.....	6-4
6.1.4 Photogrammetry.....	6-5
6.2 Natural Conditions Survey .....	6-7
6.2.1 Work in Sri Lanka.....	6-7
6.2.2 Topography .....	6-8
6.2.3 Geology.....	6-16
6.2.4 Study in Terms of Geotechnical Engineering.....	6-21
6.2.5 Study on the Maximum Flood Run-Off of Kelani and Bolgoda Rivers.....	6-52
<b>CHAPTER 7 THE OCH CONCEPT .....</b>	<b>7-1</b>
7.1 Objective.....	7-1
7.2 Concept for the OCH .....	7-1
7.3 Functions of the OCH.....	7-3
7.4 Physical Structure for Outer Circular Highway.....	7-4
<b>CHAPTER 8 SELECTION OF HIGHWAY ALIGNMENT .....</b>	<b>8-1</b>
8.1 Highway Sections .....	8-1
8.2 Alternative Highway Alignments Method for Selecting.....	8-1
8.3 Selection of Alternative Highway Alignments.....	8-5
8.3.1 Possible Highway Alignments.....	8-5
8.3.2 Preferred Possible Highway Alignments.....	8-9

	PAGE
8.3.3 Prevalent Characteristics of Preferred Possible	
Alignments .....	8-11
8.3.4 Aerial Photographs of Preferred Possible OCH Alignments	
.....	8-30
8.4 Evaluation of Preferred Possible Alignments.....	8-43
<b>CHAPTER 9 ENGINEERING STUDY .....</b>	<b>9-1</b>
9.1 Geometric Feature for Outer Circular Highway (OCH).....	9-1
9.1.1 General.....	9-1
9.1.2 Geometric Design Standards .....	9-4
9.1.3 Related Geometric Design Condition.....	9-5
9.1.4 Design Vehicle Dimensions.....	9-7
9.1.5 Design Speed .....	9-7
9.1.6 Cross Road Elements.....	9-8
9.2 Earthworks.....	9-22
9.2.1 Slope Ratio of Embankment.....	9-22
9.2.2 Slope Ratio of Cutting .....	9-23
9.3 Pavement .....	9-23
9.3.1 Design Conditions .....	9-23
9.3.2 Pavement Design .....	9-24
9.4 Horizontal Alignment .....	9-25
9.4.1 Basic Concept .....	9-25
9.4.2 Control Points.....	9-26
9.4.3 Alignment Setting.....	9-42
9.5 Vertical Alignment.....	9-43
9.5.1 Basic Concept .....	9-43
9.5.2 Control Points.....	9-44
9.5.3 Vertical Alignment Setting .....	9-46
9.6 Structure Design .....	9-47
9.6.1 Basic Policy of Structure Design.....	9-47
9.6.1.1 Bridge Design Standard.....	9-47
9.6.1.2 Design Basic Conditions .....	9-48
9.6.1.3 Structural Type of Bridge .....	9-53
9.6.2 Bridge Planning .....	9-65
9.6.2.1 Outline of Bridges for the Outer Circular Highway .....	9-65
9.6.2.2 Bridges Crossing Over Rivers .....	9-70

	PAGE
9.6.2.3 Bridge Crossing Over Existing Railways and Major Roads.....	9-72
9.6.2.4 Overpass .....	9-73
9.6.2.5 Box Culverts .....	9-75
9.6.2.6 Drawings.....	9-75
9.7 Junction and Interchange Planning.....	9-76
9.7.1 Design Daily Traffic Volume.....	9-76
9.7.2 Determination of the Interchange Configuration.....	9-76
9.7.2.1 Interchange Configuration.....	9-76
9.7.2.2 Length of Speed Change Lane.....	9-81
9.7.2.3 Configuration of IC and JCT.....	9-82
9.8 Design of Road Accessory Works .....	9-89
9.8.1 Frontage Road Construction Plan.....	9-89
9.8.2 Intersection Structures .....	9-89
CHAPTER 10 ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT.....	10-1
10.1 Summary.....	10-1
10.1.1 Introduction .....	10-1
10.1.2 Methodology.....	10-1
10.1.3 Environmental Policy, Regulations and Guidelines .....	10-2
10.1.4 Existing Environment.....	10-2
10.1.5 Environmental and Social Impacts.....	10-3
10.1.6 Mitigation Measures.....	10-7
10.1.7 Extended Environmental Cost Benefit Analysis .....	10-7
10.1.8 Institutional Requirements and Environmental Monitoring Program.....	10-8
10.1.9 Conclusion and Recommendations .....	10-8
10.2 Environmental Impact Assessment Report.....	10-8
VOLUME 3 of 5 : MAIN TEXT II	
ANNEX I   TRAFFIC SURVEY DATA & TRAFFIC MODEL RESULTS	
ANNEX II   GROUND SURVEY DATA	
CHAPTER 11 CONSTRUCTION PLAN.....	11-1
11.1 General.....	11-1

	PAGE
11.2 Basic Conditions of Construction Plan.....	11-1
11.3 Construction Method .....	11-4
11.3.1 Equipment Intensive Construction.....	11-4
11.3.2 Earthwork.....	11-4
11.3.3 Paving Work.....	11-7
11.3.4 Bridge and Viaduct Construction.....	11-8
11.3.5 Cross Drainage/ Side Ditch/ Kerb .....	11-14
11.3.6 Cross and Side Road Treatment.....	11-14
11.3.7 Other Accessories .....	11-14
11.4 Land Acquisition and Resettlement.....	11-14
11.4.1 Establishment of Right-of-Way .....	11-14
11.4.2 Utility Relocation.....	11-15
11.5 Construction Time Schedule.....	11-16
11.5.1 Conditions for Scheduling .....	11-16
11.5.2 Time Schedule .....	11-16
11.6 Construction Schedule.....	11-19
CHAPTER 12 PROJECT COST ESTIMATION.....	12-1
12.1 General.....	12-1
12.2 Procurements .....	12-4
12.3 Construction Quantities .....	12-11
12.4 Construction Cost .....	12-11
12.4.1 Unit Cost Analysis.....	12-11
12.4.2 Unit Costs of Construction Works.....	12-11
12.4.3 Estimated Construction Cost .....	12-14
12.4.4 Estimated Engineering Service (E/S) Cost.....	12-15
12.5 Land Acquisition and Resettlement Cost .....	12-15
12.5.1 Demolition Cost.....	12-15
12.5.2 Land Acquisition Cost.....	12-16
12.5.3 Resettlement Cost.....	12-17
12.5.4 Relocation Cost for High Tension Tower .....	12-18
12.5.5 Total Cost for Land Acquisition and Resettlement Cost ....	12-19
12.6 Estimated Project Cost.....	12-19
12.6.1 Estimated Project Cost in the Initial and Final Improvement Stages.....	12-19
12.6.2 Operation and Maintenance Cost .....	12-21



**ANNEX I TRAFFIC SURVEY DATA & TRAFFIC MODEL RESULTS**

**ANNEX II GROUND SURVEY DATA**

**VOLUME 4 of 5 : PRELIMINARY DRAWINGS**

**VOLUME 5 of 5 : ENVIRONMENTAL & SOCIAL IMPACT ASSESSMENT I & II**





## LIST OF FIGURES & TABLES

Figures	Page
1.1 – Study Flow.....	1-5
1.2 – Study Organization.....	1-12
2.1 – Simplified geological map of Sri Lanka.....	2-4
2.2 – Geological map around Colombo, Sri Lanka.....	2-4
2.3 – Administrative Structure of CMR.....	2-7
2.4 – DS Divisions, Population and No. of GN Divisions in parts of Gampaha, Colombo and Kalutara Districts.....	2-8
2.5 – Population by Province in 1993.....	2-9
2.6 – Regional Breakdown of the GDP in Sri Lanka in 1995.....	2-10
2.7 – Outline of Road Network Structure.....	2-22
2.8 – Annual Auto Accident Injuries in Colombo.....	2-23
2.9 – Annual Auto Fatalities in Sri Lanka.....	2-24
2.10 – Existing Railway Network in CMR.....	2-25
2.11 – Urban Density & Fuel Consumption.....	2-28
3.1 – Proposed Highway.....	3-4
4.1 – Conceptual Model for Forecasting of National Economy.....	4-4
4.2 – Forecasting Procedures of National GDP by Industrial Sector.....	4-6
4.3 – Estimating and Forecasting Procedures of CMR and District GDP by Industrial Sector.....	4-7
4.4 – Procedure for Case Setting (High and Low Cases).....	4-10
4.3 – Estimating and Forecasting Procedures of Employment by DS Division in the CMR.....	4-40
5.1 – Overall Workflow for Estimating Future Traffic Demand.....	5-1
5.2 – Traffic Survey Execution & Traffic Data Handling.....	5-2
5.3 – Location for OD Survey, Traffic Volume Survey & Bus Passenger Volume Survey....	5-8
5.4 – Turning Movement Survey Points.....	5-13
5.5 – Travel Speed Survey Routes.....	5-14
5.6 – Bus Passenger Interview Survey Locations.....	5-15

	Page
5.7 – Vehicle Trip Composition by Purpose .....	5-20
5.8 – Commodities Carried by Freight Vehicles.....	5-20
5.9 – Outline of Vehicle Trip Movements .....	5-21
5.10 – Process for Building Daily OD Matrix .....	5-21
5.11 – Traffic Composition.....	5-23
5.12 – Average Vehicle Occupancy (incl. driver).....	5-23
5.13 – Average Daily Traffic Volume on Major Arterials in Colombo .....	5-24
5.14 – Type of Bus Operation.....	5-25
5.15 – Bus Seating Capacity .....	5-25
5.16 – Passenger Loads on Bus .....	5-26
5.17 – Average Travel Speed on Major Traffic Corridors to Colombo .....	5-27
5.18 – Average Travel Speed on Major Traffic Corridors from Colombo .....	5-27
5.19 – Access Mode to Bus Stops.....	5-28
5.20 – Egress Mode from Bus Stops.....	5-28
5.21 – Car Ownership for Bus Users .....	5-28
5.22 – Reasons for Car Owners Using Bus .....	5-29
5.23 – Process for Forecasting Future Traffic Demand .....	5-30
5.24 – Zoning Map for Study Area.....	5-31
5.25 – QV for Existing Roads.....	5-35
5.26 – QV for OCH and Southern Highway.....	5-35
5.27 – QV for CKE and New Kandy Expressway.....	5-35
5.28 – Desired Line Chart for the CMR .....	5-39
5.29 – Average Daily Traffic Volume at Screen Line (1999) .....	5-42
5.30 – Future Road Improvement & Construction .....	5-45
5.31 – Traffic Volume (both directions) for Road Links of Outer Circular Highway for 2010 for Most Appropriate Alignment .....	5-49
5.32 – Traffic Volume (both directions) for Road Links of Outer Circular Highway for 2020 for Most Appropriate Alignment .....	5-50
6.1 – Orientation Map of Aerial Photograph .....	6-2
6.2.1 – Elevation Distribution of Longitudinal Profile.....	6-9
6.2.2 – Geological Cross Section (Provisional).....	6-17
6.2.3 – Geological Cross Section (Provisional).....	6-18
6.2.4 – Geological Cross Section (Provisional).....	6-19
6.2.5 – Geological Cross Section (Provisional).....	6-20

	Page
6.2.6 – Estimation for the thickness of Peat and Organic Clay from existing data at Nawanmehara Marsh (in meters, arbitrary X-Y coordinate, existing data form "WELISARA Landfill – Geotechnical Investigation 1994").....	6-23
6.2.7 – e-logP Curve of Alluvial Peat (Ap) at BH – 02 and existing data of Katunayake (1992) at Horape – Ragama Area .....	6-24
6.2.8 – No Existence .....	-----
6.2.9 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-28
6.2.10 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-29
6.2.11 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-30
6.2.12 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-31
6.2.13 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-32
6.2.14 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-33
6.2.15 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-34
6.2.16 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-35
6.2.17 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-36
6.2.18 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-37
6.2.19 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-38
6.2.20 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-39
6.2.21 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-40
6.2.22 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-41
6.2.23 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-42
6.2.24 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-43
6.2.25 – Minimum safety factor circular arc and equi-safety factor diagram .....	6-44
6.2.26 – Critical Height and Slope Angle for Latritic Soils .....	6-45
6.2.27 – Consolidation settlement at center of road fill with time in relation to the step filling for original ground at BH-02 3 meters of height of filling.....	6-46
6.2.28 – Consolidation settlement at center of road fill with time in relation to the step filling for original ground at BH-02 7 meters of height of filling.....	6-46
6.2.29 – Geological Cross Section (Provisional).....	6-50
6.2.30 – Geological Cross Section (Provisional).....	6-51
6.2.31 – Climatic zones and annual isohyets .....	6-56
6.2.32 – Geographical location of Kelani river .....	6-57
6.2.33 – Meteorological stations and hydrometric stations of Kelani river basin .....	6-58
6.2.34 – Flood profiles of Kelani river Surveyed in 1990 .....	6-59

	Page
6.2.35 – Mean monthly stream flow pattern at Hanwella gauging station during 1972 to 1997 .....	6-59
6.2.36 – Mean monthly discharge at Hanwella.....	6-60
6.2.37 – Annual maximum discharge at Hanwella.....	6-60
6.2.38 – Details of hydrometric stations of Bolgoda basin.....	6-61
6.2.39 – Catchments area of Bolgoda basin.....	6-62
7.1 – Future Urban & Industrial Development and the OCH Alignments .....	7-2
8.1 – Highway Sections .....	8-3
8.2 – Flow Chart for Alignment Selection Method .....	8-4
8.3 – Radial and Circular Highway Network in Tokyo Area .....	8-6
8.4 – Possible Highway Alignments.....	8-7
8.5 – Urbanization Trend in Colombo Area and Green Belt Concept.....	8-10
8.6 – Alignment A1 .....	8-13
8.7 – Alignment A2 .....	8-15
8.8 – Alignment A3 .....	8-17
8.9 – Alignment A4 .....	8-19
8.10 – Alignment A5 .....	8-21
8.11 – Alignment A6.....	8-23
8.12 – Alignment A7 .....	8-25
8.13 – Alignment A8 .....	8-27
8.14 – Alignment A9 .....	8-29
8.15 – Location Map: Highway Alignment on the Mosaic Photograph.....	8-31
8.16 – Average Daily Travel Speeds in Selected Cities in Asia .....	8-45
9.1 – Standard Cross Section (1) .....	9-9
9.2 – Standard Cross Section (2) .....	9-10
9.3 – Cross Section of an Expressway.....	9-13
9.4 – Standard Shoulder.....	9-13
9.5 – Cross Section of Frontage Road .....	9-17
9.6 – Fencing .....	9-19
9.7– Drainage Connection at Temporarily 4 Traffic Lanes (Embankment) .....	9-20
9.8– Drainage Connection at Temporarily 4 Traffic Lanes (Cut).....	9-21
9.9– Structure Design Method of Asphalt Pavement for Expressways.....	9-23
9.10– Pavement Structure.....	9-25

	Page
9.11- Control Point 1 .....	9-27
9.12- Control Point 2 .....	9-28
9.13- Control Point 3 .....	9-29
9.14- Control Point 4 .....	9-30
9.15- Control Point 5 .....	9-31
9.16- Control Point 6 .....	9-32
9.17- Control Point 7 .....	9-33
9.18- Control Point 8 .....	9-34
9.19- Control Point 9 .....	9-35
9.20- Control Point 10 .....	9-36
9.21- Control Point 11 .....	9-37
9.22- Control Point 12 .....	9-38
9.23- Control Point 13 .....	9-39
9.24- Control Point 14 .....	9-40
9.25- Control Point 15 .....	9-41
9.26- Comparison of Bending Moment by the BS5400 and JRA-SHB "B" .....	9-48
9.27- Clearance between Bearing Level and H.W. L. (SLS) .....	9-50
9.28- Flow Chart to Determine Minimum Span Length .....	9-51
9.29.1- Vertical Road Clearance .....	9-52
9.29.2- Crossing over Railway .....	9-53
9.30- Connection .....	9-58
9.31- Location Map of Bridges .....	9-66
9.32- Selection of Interchange Types .....	9-77
9.33- IC & JCT Types for the Outer Circular Highway .....	9-80
11.1- Staged Construction .....	11-1
11.2- OCH Construction Strategy .....	11-3
11.3- Location for Kelani River Bridge .....	11-9
11.4- Construction of Kelani River Bridge .....	11-10
11.5- Location for Bolgoda River Bridge .....	11-12
11.6- Construction of Bolgoda River Bridge .....	11-12
11.7- Right of Way, Building Line, Control Line .....	11-15
11.8 - Construction Time Schedule for Initial Stage .....	11-17
11.9 - Construction Time Schedule for Final Stage .....	11-18
12.1- Procedure for Cost Estimation .....	12-3

	Page
13.1– Procedures for the Economic Evaluation of a Project .....	13-5
13.2 – Estimation Procedure for Calculating Air Pollution Reduction Benefits of OCH Project.....	13-37
13.3 – Estimation Procedure for Calculating Traffic Accident Reduction Benefits of the OCH.....	13-42
13.4– Domains Relating to Setting the User Charge .....	13-64
13.5– Demand and Supply Curves for of Service Provided by Facility.....	13-68
13.6– Relationship between the Supply Curve and User Charge .....	13-69
13.7– Process for Approach 1.....	13-72~13-73
13.8– Process for Approach 2.....	13-74~13-75
13.9– Demand Curve of Potential Car User for OCH.....	13-83
13.10– Forecasting Procedures for RDA’s Budget by Component Cost Item.....	13-90
14.1 – Staging of Implementation.....	14-6
14.2 – Project Implementation Schedule .....	14-11

Tables	Page
2.1 – Maximum Recorded Flood Peaks in Some Rivers .....	2-2
2.2 – Principal Geological Formations Present Sri Lanka.....	2-3
2.3 – Population in the Study Area.....	2-11
2.4 – Family Size in the Study Area .....	2-12
2.5 – Composition of Economic Activities.....	2-16
2.6 – Education Levels of Population in the Study Area.....	2-17
2.7 – Sensitive Features of the Socio-Economic Environment in the Study Area .....	2-19
2.8 – Length and Density of Public Roads by Province (1993) .....	2-20
2.9 – Road System Length & Density by District in the CMR .....	2-21
2.10 – Comparison of Auto Fatality Rate.....	2-24
2.11 – Maximum Train Load Factors .....	2-26
4.1 – Forecast of National Economic Growth by Industrial Sector till the Year 2020 .....	4-12
4.2 – (Summary) Forecasts of GDP by District in the Colombo Metropolitan Region (CMR) till the Year 2020.....	4-15
4.3 – Forecasts of GDP by Districts in the CMR and Industrial Sectors till the Year 2020...4-16	
4.4 – Forecasts of GDP by Districts in the CMR and Industrial Sectors till the Year 2020...4-20	
4.5 – Forecasts of CMR GDP by Districts and Industrial Sectors till the Year 2020 .....	4-22

	Page
4.6 – Growth Rates and Shares of Population at CMR Level .....	4-24
4.7 – Forecast of District/ DS Division Population (UDA).....	4-26
4.8 – Characteristics of Study Team’s Population Forecast .....	4-30
4.9 – Forecast of CMR District Population till the Year 2020.....	4-32
4.10 – Estimate of Employment by Division in the CMR in 1998.....	4-35
4.11 – Improvement of Labor Productivity by Industrial Sector .....	4-36
4.12 – Estimate of Employment Shares by DS Division in the CMR and Industrial Sector in 1996.....	4-38
4.13 – Forecast of Employment by District in the CMR and Economic Scenario .....	4-42
4.14 – Estimate of Employment by DS Division in the CMR.....	4-44
4.15 – (Summary) Forecast of CMR Vehicle Ownerships by Vehicle Type – Base case - ....	4-49
4.16 – Forecast of Per Capita GDP by District in the CMR .....	4-52
4.17 – Cars per Capita from 1996 to 2020.....	4-54
4.18 – Elasticity of Car Ownership in Relation to Economic Growth in the CMR.....	4-56
4.19 – Forecast of Car Ownership by District .....	4-57
4.20 – Forecast of Car Ownership by DS Division .....	4-59
4.21 – Elasticity of CMR and District Motorcycle Ownership in relation to Economic Growth.....	4-63
4.22 – Forecast of CMR Motorcycle Ownership by District.....	4-64
4.23 – Forecast of Motorcycles by Division in the CMR.....	4-65
4.24 – Elasticity of Bus Trips in Relation to Economic Growth .....	4-68
4.25 – Forecast of Number of Bus by District in the CMR.....	4-70
4.26 – Forecast of Number of Bus Ownership by DS Division .....	4-71
4.27 – Elasticity of Van Trips in Relation to Economic Growth .....	4-74
4.28 – Forecast of Van Ownership by District in the CMR.....	4-75
4.29 – Forecast of Van Ownership by DS Division.....	4-76
4.30 – Forecast of Number of 3-Wheelers by District in the CMR.....	4-79
4.31 – Forecast of 3-Wheeler Ownership by DS Division .....	4-81
4.32 – Forecast of Lorry Ownership by District in the CMR.....	4-85
4.33 – Forecast of Lorry Ownership by DS Division .....	4-86
5.1 – Execution Plan .....	5-3
5.2(1) – Roadside OD Passenger Survey Sheet.....	5-9
5.2(2) – Roadside OD Survey Sheet for Goods Vehicles .....	5-9
5.3 – Traffic Volume Survey Sheet (Manual Classified Counts).....	5-10
5.4 – Bus Passenger Volume Survey Sheet.....	5-11

	Page
5.5 – Turning Movement Survey Sheet .....	5-16
5.6 – Travel Time Survey Sheet.....	5-17
5.7 – Bus Passenger Interview Sheet .....	5-18
5.8 – OD Survey Sampling Rates (12 hours).....	5-19
5.9 – Vehicle OD Matrix for 1999 .....	5-22
5.10 – Total Future Daily Trips for the CMR .....	5-32
5.11 – Daily Design Capacity and Free Flow Speeds for Road Network Links .....	5-34
5.12 – PCU Values by Vehicle Type (excluding hilly terrain).....	5-36
5.13 – Vehicle Trip Generation Models .....	5-36
5.14 – Vehicle Trip Attraction Models .....	5-37
5.15 – Vehicle Trip Distribution Model Results .....	5-38
5.16 – Vehicle OD Matrix for 2010 .....	5-40
5.17 – Vehicle OD Matrix for 2020 .....	5-41
5.18 – Comparison of Model Estimates with Observed Traffic Volumes .....	5-43
5.19 – Comparison of Observed and Modeled Travel Speeds.....	5-43
5.20 – High Mobility Corridors .....	5-46
5.21 – Comparison Traffic Impact with and without the OCH for 1999.....	5-47
5.22 – Comparison Traffic Impact with and without the OCH for 2010.....	5-47
5.23 – Comparison Traffic Impact with and without the OCH for 2020.....	5-47
6.1 – Results of Labo-CBR tests for Proctor 95% compaction of disturbed soil from borrow pits and Field CBR tests for Subgrade at the shoulder of existing National Roads .....	6-21
6.2.1 – Summary of stability calculations for road fill on very soft ground.....	6-27
6.2.2 – Ultimate end bearing capacity of pile.....	6-48
6.2.3 – Ultimate frictional resistance of pile peripheral surface.....	6-48
6.2.4 – Upper limit of maximum subgrade reaction in ordinary condition .....	6-49
6.2.5 – Upper limit of maximum subgrade reaction of bedrock.....	6-49
6.2.6 – Result of interview with residents on the flood level along the route .....	6-54
6.2.7 – Average annual rainfall of meteorological stations in Kelani river catchments area.....	6-55
6.2.8 – Mean monthly rainfall of meteorological stations in Kelani river catchments during period specified in Tab. 6.2.7 .....	6-55
6.2.9 – Calculated floods for different return periods using Gumbel distribution at Hanwella.....	6-55



	Page
7.1 – The OCH Types of Urban Roads and Their Functions.....	7-3
8.1 – Geological and Geomorphological Analysis.....	8-8
8.2 – Evaluation of the Traffic Impacts for the 9 OCH Alternative Alignments.....	8-44
9.1 – Driver Vehicle and Road Characteristics in Geometric Design.....	9-2
9.2 – Comparison of Standards.....	9-3
9.3 – Comparative Study on Center Median for Outer Circular Highway.....	9-15
9.4 – Comparative Study on Width of Center Median for Outer Circular Highway.....	9-16
9.5 – Estimated Traffics Volume of the Heavy Truck and Bus.....	9-24
9.6 – List of Control Points on Bridges and Viaduct for the Outer Circular Highway.....	9-45
9.7 – Cross Section of Bridges and Viaducts.....	9-49
9.8 – Minimum Clearance under the Deck Girder (Japan).....	9-50
9.9 – Standard Precast Pretensioned Beam in Sri Lanka.....	9-54
9.10 – Standard Applicable Span.....	9-55
9.11(a) – Standard Applicable Span for PC Bridge.....	9-56
9.11(b) – Standard Applicable Span for PC Bridge.....	9-57
9.12 – Basic PSC Beam types for the Project.....	9-58
9.13(a) – Recommended PSC Girder .....	9-60
9.13(b) – Recommended PSC Girder .....	9-61
9.14 – Abutment Types for the Height .....	9-62
9.15 – Pier Types .....	9-63
9.16 – The Applicable Depth for Foundation Type.....	9-64
9.17 – List of Bridges (Main Line).....	9-67
9.18 – Bridge Comparison Between 4 Lanes and 6 Lanes .....	9-68
9.19 – List of Bridges (IC and JCT) .....	9-69
9.20 – List of Interchange Bridges Area.....	9-69
9.21 – List of Overpasses.....	9-74
9.22 – Box Culvert.....	9-75
9.23 – Selection of Interchange Type .....	9-79
10.1 – Summary of Environmental and Social Impacts .....	10-6
11.1 – Earthwork Equipment .....	11-5
11.2 – Outline for OCH Earthwork.....	11-6
11.3 – Paving Work Equipment .....	11-7

	Page
11.4 – Sources of Paving Materials .....	11-7
11.5 – Bridge Construction Equipment .....	11-8
11.6 – Construction Working Cycle-time .....	11-16
12.1 – Concrete Suppliers.....	12-4
12.2 – Asphalt Suppliers.....	12-5
12.3 – Proportion of Local and Foreign Currency for Procurements .....	12-6
12.4 – Construction Machinery Possessed by the Government Agency (1998) .....	12-7
12.5 – List of Construction Machinery Procurable in Sri Lanka (1998).....	12-8
12.6 – Construction Machinery Possessed by Foreign Companies (1998).....	12- 9
12.7 – Machinery to be Imported .....	12-10
12.8 – Lump Sum Items .....	12-11
12.9 – Unit Rate of Labor.....	12-12
12.10 –Unit Rate of Major Materials.....	12-12
12.11 –Unit Rate of Major Equipment .....	12-12
12.12 –Unit Cost for Major Construction Work Items.....	12-13
12.13 –Summary of Estimated Construction Cost (including Contingency) in 1999 Prices .	12-14
12.14 –Summary of Estimated E/S Cost (including Contingency) in 1999 Prices .....	12-15
12.15 –Demolition Cost of Residential Buildings.....	12-15
12.16 –Floor Area of Non-Residential Structures to be Demolished .....	12-16
12.17 –Demolition Cost.....	12-16
12.18 –Agricultural Land Area to be Acquired by the Project.....	12-16
12.19 –Summary of Land Acquisition Costs.....	12-17
12.20 –Land Acquisition Cost .....	12-17
12.21 –Compensation Package .....	12-17
12.22 –Shifting Cost for Relocation .....	12-17
12.23 –Cash Assistance for Income Restoration .....	12-17
12.24 –Loss of Employment due to the Project ROW .....	12-18
12.25 –Resettlement Cost .....	12-18
12.26 –Number of High Tension Tower to be Relocated .....	12-18
12.27 –Summary of Estimated Land Acquisition and Resettlement Cost.....	12-19
12.28 –Summary of Project Cost in 1999 Prices.....	12-19
12.29 –Summary of Project Cost of Foreign and Local Currency in 1999 Prices .....	12-20
12.30 –Unit Cost for Maintenance.....	12-21
12.31 –Summary of Operation and Maintenance Cost (2005 – 2039).....	12-21

	Page
13.1 – Cost and Benefit Items of the OCH Project which are taken into Consideration in the Economic Analysis .....	13-7
13.2 – Attributes of Prices adopted for Economic Evaluation of Projects .....	13-10
13.3 – Conversion of Values by Type of Numeraire.....	13-12
13.4 – Evaluation Method of Calculated Values of Evaluation Indices for Investment Efficiency of the Project .....	13-13
13.5 – OCH Project Cost .....	13-17
13.6 – Basic Data for Estimation of the SCF in Sri Lanka.....	13-19
13.7 – Basic Data for Estimation of Unskilled Labour Cost at the Opportunity Cost Base... ..	13-20
13.8 – OCH Operation and Maintenance Costs.....	13-22
13.9 – Total Annual Running Distance by Vehicle Type and Without/ With Project Cases ..	13-25
13.10 – Vehicle Operating Cost (VOC).....	13-26
13.11 – Basic Data for Estimating Vehicle Operating Costs (VOC) by Vehicle Type .....	13-30
13.12 – No Existence.....	-----
13.13 – Vehicle Running Cost Reduction Benefit.....	13-32
13.14 – Total Annual Running Time by Vehicle Type for Without and With Project Cases..	13-34
13.15 – Running Time Reduction Benefits.....	13-36
13.16 – Emission Factor .....	13-39
13.17 – Installation Ratio of Emission Control Equipment (1998).....	13-39
13.18 – Number of Operating Vehicles in the Western Province .....	13-39
13.19 – Installation Cost of Emission Control Equipment during a Vehicle's Lifetime .....	13-40
13.20 – Air Pollution Reduction Benefits.....	13-40
13.21 – Annual Number of Persons Involved in Traffic Accident per Km of Vehicle Running Distance by Accident Level .....	13-45
13.22 – Number of Traffic Accidents and Persons Involved by Accident Level on all Classes of Roads in Sri Lanka .....	13-45
13.23 – Total Running Distance on A and B Class Roads in Sri Lanka.....	13-45
13.24 – Vehicle Ownership by Vehicle Type in the Western Province in 1996.....	13-46
13.25 – Fatal Accidents by Vehicle Type.....	13-46
13.26 – Traffic Accident Cost per Passenger by Accident Level .....	13-46
13.27 – Traffic Accident Reduction Benefits .....	13-47
13.28 – Depreciation Methods Applied to OCH Facilities.....	13-49
13.29 – B/C and Net Present Worth for the 4 Options of the OCH.....	13-50
13.30 – Annual Costs and Benefits Flows of the OCH Project.....	13-51
13.31 – EIRR for the OCH Project .....	13-52
13.32 – Four (4) Levels of Tolls and their Attributes .....	13-62

	Page
13.33 – Ratios of User Charge by Vehicle Type to the User Charge for “Car”(W <sub>p</sub> ).....	13-76
13.34 – Frequency of OCH Usage by Vehicle Type for 2010 .....	13-76
13.35 – User Charge by Vehicle Type that Corresponds to Maintenance Cost of the OCH Facility.....	13-77
13.36 –Operation Cost of Car and Additional Expenditure Car Owners Can Bear by Income Level .....	13-77
13.37 –Annual Income and Expenditure Data for Car Owners in 1999.....	13-78
13.38 – Annual Income and Expenditure Data for Motorcycle Owners in 1999 .....	13-79
13.39 –Toll and OCH Demand Elasticity by Income Level for Car Owners .....	13-81
13.40 –Number of Cars that would Use the OCH.....	13-82
13.41 –Frequency of OCH Usage per Car.....	13-82
13.42 –User Charge for OCH Desired by Low-Income Users .....	13-82
13.43 – Forecast of Price Inflation Rates by Categories.....	13-88
13.44 – Average Annual Operation and Maintenance Costs.....	13-88
13.45 – RDA’s Budget (at National Treasury’s Approval Base) .....	13-92
13.46 – Forecast for RDA Budget (at the National Treasury Approval Base).....	13-94
14.1 – Comparison of Construction Costs for Different Lane Number Scenarios .....	14-1
14.2 – Comparison of Construction Costs With and Without a Frontage Road.....	14-2
14.3 – The OCH Types of Urban Roads and Their Functions.....	14-3
14.4 – Comparison of Construction Costs by Type of Crossing .....	14-3
14.5 – Comparison of Construction Costs Bridge Widening .....	14-4
14.6 – Comparison of Construction Costs for Different Right-of-Way.....	14-4
14.7 – Number of Lanes .....	14-8
14.8 – Disbursement Schedule of Project Cost in 1999 Prices (Part 2 – Part 4).....	14-13
14.9 – Disbursement Schedule of Project Cost in 1999 Prices (Part 1 – Part 4).....	14-14
A.1.1 –Summary of Quantity (Initial Stage).....	A-1-2
A.1.2 –Summary of Quantity (Final Stage).....	A-1-3
A.1.3 –Summary of Quantity (Interchange & Junction).....	A-1-4
A.1.4 1 – Quantities of Pavement & Kerb (Initial Stage).....	A-1-5
A.1.4 2 – Quantities of Pavement & Kerb (Initial Stage).....	A-1-6
A.1.4 3 – Quantities of Pavement & Kerb (Initial Stage).....	A-1-7
A.1.4 4 – Quantities of Pavement & Kerb (Initial Stage).....	A-1-8
A.1.5 1 – Quantities of Pavement & Kerb (Final Stage).....	A-1-9
A.1.5 2 – Quantities of Pavement & Kerb (Final Stage).....	A-1-10

	Page
A.1.5 3 – Quantities of Pavement & Kerb (Final Stage).....	A-1-11
A.1.6 1 – Quantities for Frontage Road.....	A-1-12
A.1.6 2 – Quantities for Frontage Road.....	A-1-13
A.1.6 3 – Quantities for Frontage Road.....	A-1-14
A.1.6 4 – Quantities for Frontage Road.....	A-1-15
A.1.6 5 – Quantities for Frontage Road.....	A-1-16
A.1.6 6 – Quantities for Frontage Road.....	A-1-17
A.1.6 7 – Quantities for Frontage Road.....	A-1-18
A.1.7.1 – Quantities of Bridge & Viaduct (Main Part) (Initial Stage).....	A-1-19
A.1.7.2 – Quantities of Bridge & Viaduct (Main Part) (Final Stage).....	A-1-20
A.1.8.1 – Quantities of Overpass.....	A-1-21
A.1.8.2 – Quantities of Overpass.....	A-1-22
A.1.8.3 – Quantities of Overpass.....	A-1-23
A.1.9.1 – Quantities for Box Culvert.....	A-1-24
A.1.9.2 – Quantities for Box Culvert.....	A-1-25
A.1.9.3 – Quantities for Box Culvert.....	A-1-26
A.1.9.4 – Quantities for Box Culvert.....	A-1-27
A.1.10.1 – Quantities of Pipe Culvert.....	A-1-28
A.1.10.2 – Quantities of Pipe Culvert.....	A-1-29
A.1.10.3 – Quantities of Pipe Culvert.....	A-1-30
A.1.10.4 – Quantities of Pipe Culvert.....	A-1-31
A.1.11 – Quantities for Shifted Channel.....	A-1-32
A.1.12.1 – Total Length(IC & JCT).....	A-1-33
A.1.12.2 – Total Length(IC & JCT).....	A-1-34
A.1.13.1 – Quantities of Earth Works(IC & JCT).....	A-1-35
A.1.13.2 – Quantities of Earth Works(IC & JCT).....	A-1-36
A.1.13.3 – Quantities of Earth Works(IC & JCT).....	A-1-37
A.1.13.4 – Quantities of Earth Works(IC & JCT).....	A-1-38
A.1.13.5 – Quantities of Earth Works(IC & JCT).....	A-1-39
A.1.13.6 – Quantities of Earth Works(IC & JCT).....	A-1-40
A.1.13.7 – Quantities of Earth Works(IC & JCT).....	A-1-41
A.1.13.8 – Quantities of Earth Works(IC & JCT).....	A-1-42
A.1.13.9 – Quantities of Earth Works(IC & JCT).....	A-1-43
A.1.13.10 – Quantities of Earth Works(IC & JCT).....	A-1-44
A.1.14.1 – Quantities of Slope Protection(IC & JCT).....	A-1-45
A.1.14.2 – Quantities of Slope Protection(IC & JCT).....	A-1-46

	Page
A.1.14.3 – Quantities of Slope Protection(IC & JCT).....	A-1-47
A.1.15 – Quantities of Retaining Wall(IC & JCT) .....	A-1-48
A.1.16.1 – Quantities of Pavement(IC & JCT).....	A-1-49
A.1.16.2 – Quantities of Pavement(IC & JCT).....	A-1-50
A.1.16.3 – Quantities of Pavement(IC & JCT).....	A-1-51
A.1.16.4 – Quantities of Pavement(IC & JCT).....	A-1-52
A.1.16.5 – Quantities of Pavement(IC & JCT).....	A-1-53
A.1.16.6 – Quantities of Pavement(IC & JCT).....	A-1-54
A.1.17 – Quantities of Bridge & Viaduct(IC & JCT).....	A-1-55
A.1.18 – Quantities of Box Culvert(IC & JCT).....	A-1-56
A.1.19 –Interchange at Road A2 .....	A-1-57
A.2.1 –Summary of Project Cost (Initial Stage).....	App.1
A.2.2 –Summary of Project Cost (Final Stage) .....	App.2
A.2.3 –Cost Break Down for Interchange & Junction (Part 1).....	App.3
A.2.4 –Cost Break Down for Interchange & Junction (Part 2).....	App.4
A.2.5 –Cost Break Down for Interchange & Junction (Part 3).....	App.5
A.2.6 –Cost Break Down for Interchange & Junction (Part 4).....	App.6

Photographs	Page
6.2.1 – Boggy area at Nawanmehara Marsh: near STA24 .....	6-10
6.2.2 – Old Rock Quarry at Ihara Karagahamura: near STA70.....	6-10
6.2.3 – Topographic view of paddy and low hills around STA90 .....	6-12
6.2.4 – Kelani river at STA161.....	6-12
6.2.5 – A view on A4 road at STA277 toward Colombo .....	6-12
6.2.6 – Topographic view of Paddy and round hill at STA295 .....	6-13
6.2.7 – Representative cut of Laterite near STA330.....	6-14
6.2.8 – Bolgoda river near STA443 .....	6-15
6.2.9 – Topographic view of low hill and low land near STA460 .....	6-15
6.2.10 – Varying thickness of Laterite covering the base rock, near STA70.....	6-16

## ABBREVIATIONS

(In alphabetical order)

1. AASHTO: American Association of State Highway and Transportation Officials
2. ADB: Asian Development Bank
3. B/C: Benefit / Cost Ratio
4. BOI: Board of Investment (of Sri Lanka)
5. BS: British Standards
6. CBR: California Boring Ratio
7. CEA: Central Environment Agency (of Sri Lanka)
8. CKE: Colombo-Katunayake Expressway
9. CMR: Colombo Metropolitan Region
10. CMRSP: Colombo Metropolitan Regional Structure Plan
11. CPU: Computer Processing Unit
12. CUTS: Colombo Urban Transport Study
13. dpi: dots per inch
14. DS: Divisional Secretaries
15. EIA: Environmental Impact Assessment
16. EIRR: Economic Internal Rate of Return
17. ERD: Department of External Resources, Ministry of Finance and Planning (of Sri Lanka)
18. FIRR: Financial Internal Rate of Return
19. GB: Gigabyte
20. IEE: Initial Environmental Evaluation
21. ISE: Initial Social Examination
22. JBIC: Japan Bank for International Cooperation
23. JICA: Japan International Cooperation Agency
24. JRSO: Japan Road Structure Ordinance
25. MOTH: Ministry of Transport and Highways (of Sri Lanka)
26. MFE: Ministry of Forest and Environment (of Sri Lanka)
27. NAASRA: National Association of Australian State Road Authorities
28. NEA: National Environmental Act
29. NPV: Net Present Value
30. OCH: Outer Circular Highway
31. OD: Origin-Destination (matrix)
32. OECF: Overseas Economic Cooperation Fund, Japan
33. PCU: Passenger-Car Unit
34. PCU-km: Passenger-Car-Unit Kilometers (car-usage output from traffic assignment)

- model)
35. QV func.: Quantity-Velocity function (input used in traffic assignment model)
36. RAM: Random Access Memory
37. RDA: Road Development Authority (of Sri Lanka)
38.  $R^2$ : Coefficient of Determination
39. SIDA: Swedish International Development Cooperation
40. STRADA: System for Traffic Demand Analysis (transportation demand model from JICA)
41. UDA: Urban Development Authority
42. VCR: Volume-Capacity Ratio (road link congestion index in traffic assignment model)
43. Vmax: Velocity Maximum (max. velocity for road links in traffic assignment model)



# **CHAPTER 11**

## **CONSTRUCTION PLAN**

THE  
UNIVERSITY OF CHICAGO  
LIBRARY

## CHAPTER 11 CONSTRUCTION PLAN

### 11.1 General

Construction planning is mainly comprised of i) establishing a construction method and ii) preparing a construction time schedule. The results of this work are utilized in estimating construction costs and establishing a project implementation schedule.

### 11.2 Basic Conditions of Construction Plan

#### (1) Staged Construction

Since the OCH project requires large-scale construction work, it is desirable both economically and technically to phase this work over a period of time. After careful study, it is planned to construct the OCH in two stages in order to obtain optimal results in regards to meeting traffic demand and investment scheduling:

- Initial Stage : Initial construction of a four-lane dual carriageway highway for the entire length of the OCH.
- Final Stage : Widening from four to six lanes sections requiring greater capacity due to increases in traffic demand.

Based on the initial structure of a four-lane carriageway, there are three alternative methods shown below for widening a carriageway from four to six lanes.



Fig. 11.1 Staged Construction

- Method - 1 : The initial carriageway is paved for four lanes, but can be widened to six lanes by simply paving the median area.
- Method - 2 : The initial carriageway can only accommodate four paved lanes. Widening to a paved six-lane structure requires future widening of the earthworks and paving of the outer lanes.

Method - 3 : The initial structure has the capacity to accommodate six lanes, but requires that the central median area be filled and paved.

Of the above-mentioned three methods, the initial investment for Method-1 would be too large and it would be difficult to attain a reasonable economic return and is therefore not considered. In terms of cost and socioeconomic impacts, Method-3 is preferable to Method-2 for the following reasons:

- Removal of residences or businesses abutting the OCH is not required.
- Renovation of interchanges is not required.
- Less equipment and manpower is required.
- Improvement of traffic safety during the final construction stage is possible.
- There is less demolition and reconstruction of slope protection facilities.

**(2) Framework of Construction**

A construction plan is developed within the framework of the following construction parts, taking into account the OCH construction strategy shown in Fig.11.2. The construction of the OCH is executed in the order of the part numbers. Note also that part 4 is to remain as a four-lane structure, while all the other parts will be upgraded to a six-lane structure.

Part No.	Part	Construction Phase	
		Initial Stage	Final Stage
1	Bandaragama – Kottawa	4	6
2	Kottawa – Kadawata	ditto	ditto
3	Kadawata – CKE (Kerawalapitiya)	ditto	ditto
4	Bandaragama - Panadura	ditto	4

**(3) Quantities of Major Works Items**

Selection of the construction method is based on actual work quantities and site conditions.

**(4) Road Network for Hauling Materials**

The construction of the OCH involves the hauling of large quantities of embankment/pavement materials.




Fig.11.2 OCH Construction Strategy

The project area has a sufficient existing road network for the hauling of said materials. However, the pavement strength of existing local roads is sometimes insufficient. Therefore, pavement strengthening/repair will be necessary. However, the construction of new roads is unlikely.

On the other hand, the construction of some temporary roads will be required in order to transport the construction materials, together with the use of parallel roads.

### **11.3 Construction Method**

#### **11.3.1 Equipment Intensive Construction**

To realize cost efficiency gains via a shorter construction period, the intensive use of mechanical equipment for construction will be adopted.

#### **11.3.2 Earthwork**

##### **(1) Cutting (Hilly and/or Rolling Terrain)**

In hilly and/or rolling areas where the topography and profile indicates the need for cutting, excavation work (including the removal of soil to a stockpile) will be carried out.

##### **(2) Balance of Cut and Fill**

On hilly sections, where the natural ground line crosses the planning section, a balance between cutting and embanking will be carried out taking into account the effective use of resources.

##### **(3) Embankment with Borrow Materials**

Fill materials for embankments shall be supplied from borrow pits, which will be located in the vicinity of each site. For slope protection, turfing and/or planting are suitable considering the Sri Lankan climate.

**(4) Embankments Susceptible to Displacement (Marshy and/ or Soft Soil Areas)**

A few sections of the proposed alignment are located on a peat layer, which is approximately 5 to 10 meters thick. Soft soil such as peat is highly susceptible to long-term settlement caused by traffic loads or other factors. Therefore, methods to strengthen the ground in these areas in order to stabilize embankments should be applied. If a peat layer is less than 7 meters thick, the removal of soil is an efficient method for embankment stabilization.

**(5) Major Equipment**

The use of the following major earthwork equipment is planned for the OCH construction (Tab. 11.1).

**Tab. 11.1 Earthwork Equipment**

Main Work	Equipment	
	Hauling distance less than 100m	Hauling distance more than 100m
Clearing	Bulldozer	
Excavation	Bulldozer	Tractor Shovel
Loading	-	Tractor Shovel/Payloader
Hauling	Bulldozer	Dump Truck
Spreading	Bulldozer/Motor grader	
Compaction	Tamping Roller/Tire Roller	

**(6) Outline of Earthwork Planning**

Tab. 11.2 shows the outline for OCH earthwork, as well as the sources for embankment materials for construction. On average, hauling distance is not more than 2 km.

Tab. 11.2 Outline for OCH Earthwork

Part No.	Location	Outline of Earthworks
1	Bandaragama - A4(Kottawa)	The proposed highway runs through paddy and lowland area. Low embankments less than 2 meters in height are mostly anticipated. Borrow pits shall be situated in the neighboring hills around Kottawa for supplying the embankment materials. Countermeasures due to scouring by the Bolgoda River shall be considered during/after embankment construction.
2	A4 (Kottawa) - A110(Kadawata)	The topography is a combination of rolling and flat land in this section. Where the flat terrain consists of paddy fields, a low embankment less than 2 meters in height will be constructed. Materials for embankment will be obtained from a borrow pit situated in the neighboring hills of Biyagama and from the Kelani River (river sand).
3	A110(Kadawata) - CKE(Kerawalapitiya)	The proposed highway runs through rolling and flat terrain in this section. Approximately 2 kms of the proposed highway will be located in a marshy area lying south of the Matara navy camp. A detailed soil investigation shall be carried out to research the peat layer embankment settlement, which has a direct impact on construction costs. Also, since the IC for CKE is constructed near a swampy area, a soil investigation shall be carried out there to clarify soft soil areas as well. Embankment materials will be obtained from a borrow pit in the neighboring hills of either Nugegoda or Biyagama.
4	Bandaragama - A2(Panadura)	The proposed highway runs above the northern side of the Bolgoda River. Materials are to be obtained from the neighboring hills of Bandaragama, Bolgoda and existing rivers (sandy gravel) for roadway improvement.



### 11.3.3 Paving Work

The Study Team calculated the pavement structure applying AASHTO standards. Flexible pavement, such as asphalt/concrete, was selected for the OCH itself and for structural add-ons such as bridges, fly-over crossings and culverts.

#### (1) Main Equipment

The following equipment will be used for the execution of paving work (Tab. 11.3).

**Tab. 11.3 Paving Work Equipment**

Main Work	Equipment
Sub-grade Preparation	Motor Grader, Tire Roller, Macadam Roller
Sub-base	Motor Grader, Tire Roller, Macadam Roller
Prime/Tack Coat	Asphalt Distributor
Surface Course	Asphalt Mixing Plant, Asphalt Finisher, Macadam Roller, Tire Roller

#### (2) Material Sources

The sources for paving materials are shown in Tab.11.4.

**Tab. 11.4 Sources of Paving Materials**

Materials	Location of Quarry	Remarks
Gravel and Sand	Colombo Seashore*	Deposit: 500,000m <sup>3</sup>
Sand		Deposit: 250,000m <sup>3</sup>
Coarse Aggregate	Kaduwela	Granite
Coarse Aggregate	Northern Mahara	Granite
Coarse Aggregate	Northern Biyagama	Granite

\*: Only to be permitted if environmental impacts negligible.

#### (3) General Descriptions of Materials

##### 1) Sub-base Course Materials

Sub-base course materials will be obtained from existing rivers and/or rock deposits and will be processed as necessary for gradation control.

## 2) Base Course Materials, Coarse and Fine Aggregate

There are a number of aggregate producers that mainly operate north of the Kelani River and between the Kelani River and Route A4 to the east of the OCH alignment. If demand warrants it, contractors can establish their own quarries and gravel pits, as well as operate their own crushing/ screening plant.

## 3) Asphalt Concrete

The procurement of hot-mix asphaltic concrete is possible for the construction of asphalt treated base course and surface course.

### 11.3.4 Bridge and Viaduct Construction

Continuous PC girder bridges are to be built for the two major rivers, i.e., the Kelani and Bolgoda Rivers. Abutments and piers are assumed to be pile foundations in order to ensure bearing capacity. As for minor bridges, slab/ PC girder bridges are assumed.

Viaducts are assumed to be of the same scale as the flyover built in Ragama by the RDA for crossing on existing railway (length: 450 meters).

#### (1) Main Equipment

The equipment used for bridge construction is shown in Tab.11.5.

**Tab. 11.5 Bridge Construction Equipment**

Main Work	Equipment
Foundation	Diesel Pile Hammer, Pile Driver, Truck Crane, Floating Crane, Reverse Circulation Drilling Machine.
Structure Excavation	Clamshell, Dump Truck, Barge
Substructure	Transit Mixer, Concrete Pump Truck
Superstructure	Crawler Crane, Erection Truss, Launching Girder
Superstructure	Floating Crane

## (2) Construction of the Kelani River Bridge

Construction of the Kelani River Bridge will require the following construction methods:

- An open caisson will be required for substructure construction.
- Cast-in-place concrete piling will be executed by a reverse-circulation-drill method.
- PSC-girders will be erected by means of conventional crane erection method or erection girder method.

### 1) Construction Yards

A river terrace on the left bank, located in an area with relatively few houses between the Kelani River and Kaduwela Road A110, will be used as work yards for the construction of the Kelani River Bridge. The yards will include a simple ready-mixed concrete plant, pretension girder fabrication yard, material storage yard and workshop, heavy construction equipment parking area, field office, accommodations for workers, and a temporary storage yard for excavated soil.

Since the elevation of the terrace is around 5.5 m here, as compared to a HWL for the river of more than 5.4 m, embanking and leveling of this area to an elevation of + 1.0 m of the HWL will be executed prior to use as yards.

If a simple ready-mixed concrete plant and girder fabrication yards can be secured and shared by all sites for the supply of ready-mixed concrete and precast girders to the multiple bridge-building sites (including this site), then quality control can be improved and construction costs reduced.

### 2) Protection Work for Existing Roads

Before abutment construction, work to protect pedestrians, animals, and vehicles using Biyagama Road B214 and Kaduwela Road A110 will be carried out.




Fig.11.3 Location for Kelani River Bridge

### 3) Construction of Open Caisson

#### (a) Man-made Islands

If the elevation of a man made island is  $LWL + 1.0$  m, its embankment height should be about 4.5 m. As water depth is 3 m or more even in the dry season, the periphery of a man-made island is first surrounded with steel sheet piles, then soil to build the island is added. This method is employed in order to prevent the loosening of embankment material during the excavation of the open caisson and the washout of embankment material by the river. Steel sheet piles are driven by a high-powered hammer from a floating crane. Man-made islands for each pier are connected via a temporary jetty.




Fig.11.4 Construction of Kelani River Bridge

#### (b) Excavation for Caissons

Excavation work for open caissons is carried out using a crane, clamshell buckets, etc.. Excavated soil is stored in a temporary storage yard on the left bank of the river for subsequent use as embankment material for the main line on the left bank.

In the case of an open caisson, once settlement has proceeded to a certain degree, it is

difficult to correct the inclination. It is therefore essential to thoroughly control settlement during the initial settlement period after excavation, and to proceed with work with the utmost care so as not to cause any inclination.

Generally, a method to reduce friction between the ground and wall surface is employed to promote caisson settlement. If settlement is hard to achieve, it may be possible to press the caisson into the ground in a forced manner by using an earth anchor.

#### 4) Erection of Superstructure

Three spans near the A1 abutment on the right bank of the river and the end span near the A2 abutment on the left bank are erected on existing ground, using either a single 100-ton truck crane or two 50-ton truck cranes. The four spans for the river section may be built applying one of following methods:

- (a) Erection with a crane-equipped barge
- (b) Erection with a truck crane
- (c) Erection via temporary girders

The appropriate method will be selected depending on the conditions of the bridge site.

- Method (a) is extremely economical and advantageous if a barge is available and can be towed to the bridge site.
- Method (b) consists of erecting a bridge superstructure by first completing a single section of bridge to allow a truck crane to use that section of bridge to continue with the building of superstructure for subsequent spans. This method is most commonly used when the space under a bridge cannot be used for scaffolding. However, this method cannot be used for continuous PC girder bridges.
- Method (c) consists of installing superstructure via the use of a gantry crane, for example moving between temporary girders set on the pier substructure. This method enables the continuous installation of girders, reducing the installation period, but its cost is higher than the other methods.

**(3) Construction of the Bolgoda River Bridge**

**1) Construction Yards**

The left bank of the Bolgoda River is used for the construction yards. This site has a ground elevation of about 1.5 m and entry is possible from a national highway. The yard is embanked and leveled to an elevation of about 1.0 m greater than the HWL..




Fig.11.5 Location for Bolgoda River Bridge

**2) Construction of Pile Bent Pier**




Fig.11.6 Construction of Bolgoda River Bridge

**(a) Installation of Temporary Work Jetty**

To install cast-in-place piles, a temporary jetty for work is constructed. The elevation of installation is to be LWL + 1.0 m. Temporary work jetties are to be connected with temporary passage jetties. For pier P5 of the A2 abutment where the river is relatively shallow, a man-made island may be used for construction.

**(b) Construction of Pile Bend ( $\phi$ 1.0 m RC cast-in-place piles)**

Except for the bottom end of piles where soil collapse is highly unlikely, piles will be installed using casings. Casing portions not exposed to water will be left embedded. For casing portions that will be exposed to water, they will be removed since they are susceptible to corrosion.

**3) Erection of Superstructure**

Both end spans, which are located on land, will be installed using a single 35-ton truck crane. The four spans of the river section may be installed applying one of the following methods:

- (a) Erection with a truck crane using installed girders
- (b) Draw erection using installed girders

The appropriate method will be selected depending on the conditions of the site. The merits and demerits of these methods are the same as for the Kelani River, except that the installed girder of Method (b) must be set at the central portion of the abutment and pier (median strip of the superstructure).

**(4) Overpass and Interchange Structures**

As for the construction of overpasses and interchanges at intersections with existing roads, the superstructure will normally be erected by means of a conventional crane.

**(5) Railway Crossing**

The construction of railway crossings shall be carefully executed to avoid interfering with railway operation. Surveying shall be carried out to determine existing obstacles such as power lines, traffic lights and telecommunications. Then, methods to protect these facilities during construction will be examined. Sufficient discussions shall be held with the client on the construction procedures as well.

## **(6) Box-Culverts**

Confirming the bearing capacity of the foundation is extremely important, since a box-culvert normally applies a spread foundation. Therefore, a foundation test shall be carried out before excavation.

### **11.3.5 Cross Drainage/ Side Ditch/ Kerb**

The size and number of pipe culverts have been estimated based on hydrology calculations. The side ditches, pipe under the center median and kerb are considered in the carriageway design shown in a typical cross section. These quantities are included in the earthworks.

### **11.3.6 Cross and Side Road Treatment**

It is necessary to consider how local roads, which shall either be terminated or connected to the OCH frontage road, will be dealt with in relation to the new highway profile.

### **11.3.7 Other Accessories**

Streetlights, traffic signs, road markings, traffic control units, traffic signals and other traffic control facilities will be employed.

## **11.4 Land Acquisition and Resettlement**

### **11.4.1 Establishment of Right-of-Way**

The right-of-way is defined as an area necessary to accommodate all necessary road structures and facilities for the OCH, which has been set out in accordance with the following terms:


- a) The RDA shall reserve the right-of-way for the operation of the OCH.
- b) Land, such as temporary construction yards, required outside of the designated right-of-way shall be provided under the contractor's obligation.

The right-of-way for the OCH is given in Fig.11.7 and will include the installation of utilities for electricity and water for highway use on the road shoulders. Utilities for other purposes will not be installed within the right-of-way. The dotted lines shown in the figure, distinguish the following:



- Road boundary: A boundary for defining OCH operation and which is normally categorized as the right-of-way. The border of the road boundary for the OCH is at the edge of the slope drainage.
- Building line: This is the architectural gauge for buildings. Any building will not be allowed to be constructed beyond this line.
- Control line: This line defines an area for use by temporary construction yards. The yards should be 10 to 15 meters from the road boundary in order to accommodate temporary road and drainage facilities.

Fig.11.7 Right-of-Way, Building Line, Control Line



#### 11.4.2 Utility Relocation

Utilities requiring relocation have been identified by the Study Team via on-site inspection and a 1/5000 topographical map. There are high-tension towers and local electricity distribution facilities, water supply and telecommunications facilities, etc. The number of high-tension towers requiring relocation has been worked out during the preliminary design and the relocation cost estimated by the Ceylon Electricity Board in the preceding chapter.

## 11.5 Construction Time Schedule

### 11.5.1 Conditions for Scheduling

#### (1) Critical Construction Period

Taking into account the scale and urgency of the construction of the OCH, the maximum possible construction period was set at 2.5 years for each part.

#### (2) Weather Conditions

According to rainfall data, the number of workdays for earthworks and the construction of pavement were estimated as shown in Tab. 11.6.

**Tab. 11.6 Construction Working Cycle-time(Dry Season/Rainy Season)**

Item	Dry Season Jul.- Sep. Dec.- Mar (8 months)	Rainy Season Apr.- Jun. Oct.-Nov. (4 months)	Annual
Number of rainy days	10.1 days/ month	14.0 days/ month	145 days
Working efficiency on a rainy day	65 %	35 %	52.5 %
Number of holidays	5.0 days/ month	4.3 days/ month	60 days
Number of working days	21.5days/ month	16.6 days/ month	229 days
Working efficiency	72 %	55 %	63 %

### 11.5.2 Time Schedule

The construction time schedule for each construction section was prepared based on the conditions described in Subsection 11.4.1 above, and is shown in Fig 11.8 and 11.9.

Fig.11.8 Construction Time Schedule for Initial Stage




Fig.11.9 Construction Time Schedule for Final Stage

Item	Month						
	0	5	10	15	20	25	30
<b>Part 1(Bandaragama-Kottawa:16.32km)</b>		<b>Upgrading (Six Lane) Stage</b>					
Preparatory Work	■						
Earthwork		■	■	■			
Pavement Construction			■	■	■		
Miscellaneous			■	■	■		
Bridge Widening		■	■	■	■		
<b>Part 2(Kottawa-Kadawata:19.9km)</b>		<b>Upgrading (Six Lane) Stage</b>					
Preparatory Work	■						
Earthwork		■	■	■			
Pavement Construction			■	■	■	■	
Miscellaneous				■	■	■	
Bridge Widening		■	■	■	■	■	
<b>Part 3(Kadawata-CKE(Kelawarapitiya):8.13km)</b>		<b>Upgrading (Six Lane) Stage</b>					
Preparatory Work	■						
Earthwork		■	■				
Pavement Construction			■	■			
Miscellaneous			■	■			
Bridge Widening		■	■	■	■		
<b>Part 4(Bandaragama-Panadura:6.82km)</b>		<b>No widening</b>					
<b>No Upgrading</b>							

## **11.6 Construction Schedule**

A construction schedule has been prepared for each construction stage (i.e., the initial and final stages) of the OCH. The detailed design for the initial four-lane stage will commence by the beginning of 2002 for a 1.5 year period, and construction will be executed in 2.0 - 2.5 years from the beginning or middle of 2003. The implementation of construction for a six-lane upgrade is dependent on traffic demand and the government policy regarding investment.