





























1US\$=108JP Yen=14,100VND

No.	Description	Specification	Unit	Quantity	Unit Price			Local Currency (VND)	Local Currency (US\$)	COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (US\$)				
1	Tensioning Jack	400t	day in demand	321.00	4,050	0.00	0	0.00	169,728,750	EL 178030	
2	Gantry Crane	3t lifting force	day in demand	153.50	3,038	0.00	0	0.00	60,882,364	EL 145000	
3	Electric Hoist	3t lifting force	day in demand	153.50	549	0.00	0	0.00	11,002,178	EL 146000	
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	153.50	1,070	0.00	0	0.00	21,443,097	EL 147000	
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	EL 123100	
6	Hydraulic Jack	196.1kN (20t)	day in demand	602.00	367	0.00	0	0.00	28,844,161	EL 148000	
7	Hydraulic Pump	Electric 1.5kW	day in demand	301.00	2,044	0.00	0	0.00	80,323,522	EL 149000	
8	Hydraulic Jack Extrude Table	75t	day in demand	602.00	437	0.00	0	0.00	34,345,772	EL 150000	
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	301.00	85	0.00	0	0.00	3,340,264	EL 151000	
10	Tiehole	29.4kN (3.0t)	day in demand	301.00	169	0.00	0	0.00	6,641,231	EL 152000	
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30.1t) * 2.0m	day in demand	301.00	871	0.00	0	0.00	34,227,881	EL 153000	
12	Steel Form Work for Post Tension J-Beam	L31m.H1.65m(122.378m <sup>2</sup> )	day in demand	150.50	0	0.00	0	22.86	48,510,063	EL 154012	
13	Mill Table for Post Tension J-Beam	L31m(L32m), w=0.65m	day in demand	602.00	0	0.00	0	6.70	56,870,940	EL 155012	
	Summary								559,605,320		

A=(n\*s\*(s-1)/s)\*14 (days) ; n= 40 (The number of girder), s=4 (The number of Mill Table )  
 B=3 (days) ; Setting and Removal of Gantry Crane  
 C=10 (days) ; Transportation of Tension Jack

per lot  
 REMARKS

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT												
Process Cost												
Depression of Equipment (Small Tra Va)												
(Girder Production)												
Unit: 1 lot												
Sheet #: PC 410610												
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Tensioning Jack	400t	day in demand	251.00	4,050	0.00	0	0.00	132,716,250	EL	178030	
2	Gantry Crane	3t lifting force	day in demand	118.50	3,038	0.00	0	0.00	47,000,392	EL	145000	
3	Electric Hoist	3t lifting force	day in demand	118.50	549	0.00	0	0.00	8,493,553	EL	146000	
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	118.50	1,070	0.00	0	0.00	16,553,792	EL	147000	
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	EL	123100	
6	Hydraulic Jack	196.1kN (20t)	day in demand	462.00	367	0.00	0	0.00	22,136,217	EL	148000	
7	Hydraulic Pump	Electric 1.5kW	day in demand	231.00	2,044	0.00	0	0.00	61,643,633	EL	149000	
8	Hydraulic Jack Extrude Table	75t	day in demand	462.00	437	0.00	0	0.00	26,338,383	EL	150000	
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	231.00	85	0.00	0	0.00	2,563,458	EL	151000	
10	Tiehole	29.4kN (3.0t)	day in demand	231.00	169	0.00	0	0.00	5,096,758	EL	152000	
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1.2*A	day in demand	231.00	871	0.00	0	0.00	26,267,908	EL	153000	
12	Steel Form Work for Post Tension I-Beam	L37m.H1.85m(160.775m2)	day in demand	115.50	0	0.00	0	30.03	48,905,427	EL	154011	
13	Mill Table for Post Tension I-Beam	L37m(L38m), w=0.65m	day in demand	462.00	0	0.00	0	7.96	51,853,032	EL	155011	
Summary												
per lot											453,033,901	
REMARKS											453,033,901	

A=(n/s+(s-1)/s)\*14 (days) ; n= 30 (The number of girder), s=4 (The number of Mill Table )  
 B=2 (days) : Setting and Removal of Gantry Crane  
 C=10 (days) : Transportation of Tension Jack

1US\$=108JP Yen=14,100VND

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)		Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Tensioning Jack	400t	day in demand	225.33	4,050	0.00	0	0.00	119,143,303	EL 178030
2	Gantry Crane	3t lifting force	day in demand	105.67	2,038	0.00	0	0.00	41,911,597	EL 145000
3	Electric Hoist	3t lifting force	day in demand	105.67	549	0.00	0	0.00	7,573,919	EL 146000
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	105.67	1,070	0.00	0	0.00	14,761,525	EL 147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	EL 123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	410.67	367	0.00	0	0.00	19,676,811	EL 148000
7	Hydraulic Pump	Electric 1.3kW	day in demand	205.33	2,044	0.00	0	0.00	54,793,514	EL 149000
8	Hydraulic Jack Extrude Table	75t	day in demand	410.67	437	0.00	0	0.00	23,429,892	EL 150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	205.33	85	0.00	0	0.00	2,278,586	EL 151000
10	Tilehole	29.4kN (3.0t)	day in demand	205.33	169	0.00	0	0.00	4,530,408	EL 152000
11	Side Leader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1*2*A	day in demand	205.33	871	0.00	0	0.00	23,348,817	EL 153000
12	Steel Form Work for Post Tension I-Beam	L37m, H1.85m(160.775m <sup>2</sup> ) 1*1*A	day in demand	102.67	0	0.00	0	30.03	43,472,838	EL 154011
13	Mill Table for Post Tension I-Beam	L37m(L38m), w=0.65m 1*3*A	day in demand	308.00	0	0.00	0	7.96	34,568,688	EL 155011
Summary										
								392,934,996		
per lot										
392,934,996										

REMARKS

A=(n/s+(s-1)/s)\*14 (days) : n= 20 (The number of girder), s=3 (The number of Mill Table )  
 B=3 (days) : Setting and Removal of Gantry Crane  
 C=10 (days) : Transportation of Tension Jack



1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Deposition of Equipment (Cal. Tac 1) (Girder Production) Unit: 1 lot Sheet #: FC 410640

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	
1	Tensioning Jack	400t	day in demand	391.00	4,050	0.00	0	0.00	206,741,250	EL	178030
2	Gantry Crane	3t lifting force	day in demand	188.50	3,038	0.00	0	0.00	74,764,336	EL	145000
3	Electric Hoist	3t lifting force	day in demand	188.50	549	0.00	0	0.00	13,510,803	EL	146000
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	188.50	1,070	0.00	0	0.00	26,332,403	EL	147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	EL	123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	742.00	367	0.00	0	0.00	35,552,106	EL	148000
7	Hydraulic Pump	Electric 1.5kW	day in demand	371.00	2,044	0.00	0	0.00	99,003,411	EL	149000
8	Hydraulic Jack Extend Table	75t	day in demand	742.00	437	0.00	0	0.00	42,333,161	EL	150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	371.00	85	0.00	0	0.00	4,117,069	EL	151000
10	Titchole	29.4kN (3.0t)	day in demand	371.00	169	0.00	0	0.00	8,185,703	EL	152000
11	Side Loader (for FC Girder)	Steel Bowl Type 294.2kN (30.1*2*A)	day in demand	371.00	871	0.00	0	0.00	42,187,853	EL	153000
12	Steel Form Work for Post Tension I-Beam	L37m.H1.85m(L60.775m2)	day in demand	185.50	0	0.00	0	30.03	78,545,037	EL	154011
13	Mill Table for Post Tension I-Beam	L37m(L38m), w=0.65m	day in demand	742.00	0	0.00	0	7.96	83,279,112	EL	155011
Summary											
per lot									717,997,341		

A=(n+s\*(s-1)/s)\*14 (days) : n= 50 (The number of girder), s=4 (The number of Mill Table)

B=3 (days) : Setting and Removal of Gantry Crane

C=10 (days) : Transportation of Tension Jack

REMARKS

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT											
Process Cost											
Depression of Equipment (Cal Tac 2)											
(Girder Production)											
Unit: 1											
Sheet #: PC											
lot											
410660											
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)			
1	Tensioning Jack	400t	day in demand	132.00	4,050	0.00	0	0.00	69,795,000	EL	178030
2	Gantry Crane	3t lifting force	day in demand	59.00	3,038	0.00	0	0.00	23,401,038	EL	145000
3	Electric Hoist	3t lifting force	day in demand	59.00	549	0.00	0	0.00	4,228,825	EL	146000
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	59.00	1,070	0.00	0	0.00	8,241,972	EL	147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	EL	123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	224.00	367	0.00	0	0.00	10,732,711	EL	148000
7	Hydraulic Pump	Electric 1.5kW	day in demand	112.00	2,044	0.00	0	0.00	29,887,822	EL	149000
8	Hydraulic Jack Extrude Table	75t	day in demand	224.00	437	0.00	0	0.00	12,779,822	EL	150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	112.00	85	0.00	0	0.00	1,242,889	EL	151000
10	Tilehole	29.4kN (3.0t) * 1.5m	day in demand	112.00	169	0.00	0	0.00	2,471,156	EL	152000
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1*2*A	day in demand	112.00	871	0.00	0	0.00	12,735,956	EL	153000
12	Steel Form Work for Post Tension I-Beam	137m.H1.85m(160.775m2)	day in demand	56.00	0	0.00	0	30.03	23,711,688	EL	154011
13	Mill Table for Post Tension I-Beam	137m(L38m), w=0.65m	day in demand	168.00	0	0.00	0	7.96	18,855,648	EL	155011
Summary											
per lot											221,529,626
Summary											221,529,626

A=(n/s\*(s-1)/s)\*14 (days) ; n= 10 (The number of girder), s=3 (The number of Mill Table)

B=3 (days) ; Setting and Removal of Gantry Crane

C=10 (days) ; Transportation of Tension Jack

REMARKS

1US\$=108JP Yen=14,100VND

No.	Description	Specification	Unit	Quantity	Unit Price				Local Currency (VND)	Local Currency (US\$)	COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)				
1	Tensioning Jack	400k	day in demand	251.00	4,050	0.00	0	0.00	0	132,716,250	EL 178030	
2	Gantry Crane	3t lifting force	day in demand	118.50	3,038	0.00	0	0.00	0	47,000,392	EL 145000	
3	Electric Hoist	3t lifting force	day in demand	118.50	549	0.00	0	0.00	0	8,493,553	EL 146000	
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	118.50	1,070	0.00	0	0.00	0	16,553,792	EL 147000	
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	0	3,445,098	EL 123100	
6	Hydraulic Jack	196.1KN (20t)	day in demand	462.00	367	0.00	0	0.00	0	22,136,217	EL 148000	
7	Hydraulic Pump	Electric 1.5kW	day in demand	231.00	2,044	0.00	0	0.00	0	61,643,633	EL 149000	
8	Hydraulic Jack Extrude Table	75t	day in demand	462.00	437	0.00	0	0.00	0	26,358,383	EL 150000	
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	231.00	85	0.00	0	0.00	0	2,563,458	EL 151000	
10	Tilehole	29.4kN (3.0t)	day in demand	231.00	169	0.00	0	0.00	0	5,096,758	EL 152000	
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1*2*A	day in demand	231.00	871	0.00	0	0.00	0	26,267,908	EL 153000	
12	Steel Form Work for Post Tension I-Beam	L37m.H1.85m(160.775m <sup>2</sup> ) 1*1*A	day in demand	115.50	0	0.00	0	30.03	0	48,903,427	EL 154011	
13	Mill Table for Post Tension I-Beam	L37m(L38m) w=0.65m 1*4*A	day in demand	462.00	0	0.00	0	7.96	0	51,853,032	EL 155011	
Summary												
per lot												
REMARKS												

A=(n/s+(s-1)/s)\*14 (days) ; n= 30 (The number of girder), s=4 (The number of Mill Table )  
 B=3 (days) ; Setting and Removal of Gantry Crane  
 C=10 (days) ; Transportation of Tension Jack

453,033,901  
 453,033,901

1US\$=108JP Yen=14,100VND

No.	Description	Specification	Unit	Quantity	Unit Price			Local Currency (VND)	Local Currency (US\$)	COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (US\$)				
1	Tensioning Jack	400t	day in demand	132.00		4,050	0	0.00	69,795,000	EL 178030	
2	Gantry Crane	3t lifting force	day in demand	59.00		3,038	0	0.00	23,401,039	EL 145000	
3	Electric Hoist	3t lifting force	day in demand	59.00		549	0	0.00	4,228,825	EL 146000	
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	59.00		1,070	0	0.00	8,241,972	EL 147000	
5	Wheel Crane	Hydraulic 25t	day in demand	3.00		0	1,148,366	0.00	3,445,098	EL 123100	
6	Hydraulic Jack	196.1kN (20t)	day in demand	224.00		367	0	0.00	10,732,711	EL 148000	
7	Hydraulic Pump	Electric 1.5kW	day in demand	112.00		2,044	0	0.00	29,887,822	EL 149000	
8	Hydraulic Jack Extrude Table	75t	day in demand	224.00		437	0	0.00	12,779,822	EL 150000	
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	112.00		85	0	0.00	1,242,889	EL 151000	
10	Tilehole	29.4kN (3.0t)	day in demand	112.00		169	0	0.00	2,471,156	EL 152000	
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1.2*A	day in demand	112.00		871	0	0.00	12,735,956	EL 153000	
12	Steel Form Work for Post Tension I-Beam	L25m.H1.45m(86.984m2)	day in demand	56.00		0	0	16.25	12,831,000	EL 154013	
13	Milli Table for Post Tension I-Beam	L25m(L26m), w=0.60m	day in demand	168.00		0	0	5.03	11,915,064	EL 155013	
Summary											
Total											
203,708,354											
203,708,354											

REMARKS  
 A=(n/s+(s-1)/s)\*14 (days) : n= 10 (The number of girder), s=3 (The number of Mill Table )  
 B=3 (days) : Setting and Removal of Gantry Crane  
 C=10 (days) : Transportation of Tension Jack

1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Deposition of Equipment (Cai Nai)

(Girder Production?)

Unit: I

lot

410680

No.	Description	Specification	Unit	Quantity	Unit Price				COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Tensioning Jack	400t	day in demand	251.00	4,950	0.00	0	0.00	132,716,250	EL 178030
2	Gantry Crane	3t lifting force	day in demand	118.50	3,038	0.00	0	0.00	47,000,392	EL 145000
3	Electric Hoist	3t lifting force	day in demand	118.50	549	0.00	0	0.00	8,493,553	EL 146000
4	Track (per100m) for Gantry Crane	30kg/m including Steeper	day in demand	118.50	1,070	0.00	0	0.00	16,553,792	EL 147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,443,098	EL 123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	462.00	367	0.00	0	0.00	23,136,217	EL 148000
7	Hydraulic Pump	Electric 1.5kW	day in demand	231.00	2,044	0.00	0	0.00	61,643,633	EL 149000
8	Hydraulic Jack Extrude Table	75t	day in demand	462.00	437	0.00	0	0.00	26,358,383	EL 150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	231.00	85	0.00	0	0.00	2,563,458	EL 151000
10	Tilehole	29.4kN (3.0t)	day in demand	231.00	169	0.00	0	0.00	5,096,758	EL 152000
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1.2*A	day in demand	231.00	871	0.00	0	0.00	26,267,908	EL 153000
12	Steel Form Work for Post Tension I-Beam	L37m.H1.85m(160.775m <sup>2</sup> ) 1*1*A	day in demand	115.50	0	0.00	0	30.03	48,903,427	EL 154011
13	Mill Table for Post Tension I-Beam	L37m(L38m), w=0.65m 1*4*A	day in demand	462.00	0	0.00	0	7.96	51,853,032	EL 155011
Summary										
									453,033,901	
									453,033,901	

A=(n/s\*(s-1)/s)\*14 (days) ; n= 30 (The number of girder), s=4 (The number of Mill Table )

B=3 (days) ; Setting and Removal of Gantry Crane

C=10 (days) ; Transportation of Tension Jack

REMARKS

per lot

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost

(Girder Production)

Unit: 1

lot

Sheet #: PC 410690

No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	
1	Tensioning Jack	400t	day in demand	391.00	4,050	0.00	0	0.00	0	0.00	178030
2	Gantry Crane	3t lifting force	day in demand	188.50	3,038	0.00	0	0.00	0	0.00	145000
3	Electric Hoist	3t lifting force	day in demand	188.50	549	0.00	0	0.00	0	0.00	146000
4	Track (per 100m) for Gantry Crane	30kg/m including Sleeper	day in demand	188.50	1,070	0.00	0	0.00	0	0.00	147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	0	0.00	123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	742.00	367	0.00	0	0.00	0	0.00	148000
7	Hydraulic Pump	Electric 1.5kW	day in demand	371.00	2,044	0.00	0	0.00	0	0.00	149000
8	Hydraulic Jack Extrude Table	75t	day in demand	742.00	437	0.00	0	0.00	0	0.00	150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	371.00	85	0.00	0	0.00	0	0.00	151000
10	Tilehole	29.4kN (3.0t)	day in demand	371.00	169	0.00	0	0.00	0	0.00	152000
11	Side Loader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1*2*A	day in demand	371.00	871	0.00	0	0.00	0	0.00	153000
12	Steel Form Work for Post Tension I-Beam	L37m, H1.85m (160,775m <sup>2</sup> ) 1*1*A	day in demand	185.50	0	0.00	0	0.00	0	30.03	154011
13	Mill Table for Post Tension I-Beam	L37m (L38m), w=0.65m 1*4*A	day in demand	742.00	0	0.00	0	0.00	0	7.96	155011
Summary											
per lot											
REMARKS											

A=(n/s\*(s-1)/s)\*14 (days) ; n= 50 (The number of girder), s=4 (The number of Mill Table)

B=3 (days) ; Setting and Removal of Gantry Crane

C=10 (days) ; Transportation of Tension Jack

717,997,341

717,997,341



1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost: Deposition of Equipment(NH91B)(RD) (Girder Production)

Unit: 1 lot  
Sheet #: PC 410710

No.	Description	Specification	Unit	Quantity	Unit Price				COMBINED TOTAL COST (VND)			Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)	
1	Tensioning Jack	400t	day in demand	122.67	4,050	0.00	0	0.00	64,861,828	0	0.00	EL 178050
2	Gantry Crane	3t lifting force	day in demand	54.33	3,038	0.00	0	0.00	21,548,847	0	0.00	EL 145000
3	Electric Hoist	3t lifting force	day in demand	54.33	549	0.00	0	0.00	3,894,081	0	0.00	EL 146000
4	Track (per100m) for Gantry Crane	30kg/m including Sleeper	day in demand	54.33	1,070	0.00	0	0.00	7,589,586	0	0.00	EL 147000
5	Wheel Crane	Hydraulic 25t	day in demand	3.00	0	0.00	1,148,366	0.00	3,445,098	0	0.00	EL 123100
6	Hydraulic Jack	196.1kN (20t)	day in demand	205.33	367	0.00	0	0.00	9,838,144	0	0.00	EL 148000
7	Hydraulic Pump	Electric 1.5kW	day in demand	102.67	2,044	0.00	0	0.00	27,397,997	0	0.00	EL 149000
8	Hydraulic Jack Extrude Table	75t	day in demand	205.33	437	0.00	0	0.00	11,714,619	0	0.00	EL 150000
9	Lever Block	29.4kN (3.0t) * 1.5m	day in demand	102.67	85	0.00	0	0.00	1,139,358	0	0.00	EL 151000
10	Thiethole	29.4kN (3.0t)	day in demand	102.67	169	0.00	0	0.00	2,265,269	0	0.00	EL 152000
11	Side Leader (for PC Girder)	Steel Bowl Type 294.2kN (30t) 1*2*A	day in demand	102.67	871	0.00	0	0.00	11,675,061	0	0.00	EL 153000
12	Steel Form Work for Post Tension I-Beam	L37m.H1.85m(160.775m <sup>2</sup> ) 1*1*A	day in demand	51.33	0	0.00	0	30.03	21,734,304	0	30.03	EL 154011
13	Mill Table for Post Tension I-Beam	L37m(L38m), w=0.65m	day in demand	154.00	0	0.00	0	7.96	17,284,344	0	7.96	EL 155011
Summary												
lot												204,388,538

A=(n/s+(-1)/s)\*14 (days) ; n= 9 (The number of girder), s=3 (The number of Mill Table)

B=3 (days) ; Setting and Removal of Gantry Crane

C=10 (days) ; Transportation of Tension Jack

REMARKS



























































1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT										Unit: 10	Remarks
Process Cost										Sheet #: PC	413530
Transverse Prestressing Work										(570KN, 1521.8)	cable
No.	Description	Specification	Unit	Quantity	Unit Price			COMBINED TOTAL COST (VND)		Remarks	
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)			
1	Foreman	Local 1*0.4	M/day	0.40	0	0.00	146,392	0.00	58,557	L	101000
2	Skilled Labor	Local 1*1.3	M/day	1.30	0	0.00	118,898	0.00	154,567	L	104000
3	Common Labor	Local 1*0.8	M/day	0.80	0	0.00	58,671	0.00	46,937	L	103000
4	Anchorage of PC Cable (Fixed Side)	IT21.8	nos	10.00	3,384	0.00	0	0.00	4,418,000	M	140036
5	Anchorage of PC Cable (Tensioning Side)	IT21.8	nos	10.00	3,032	0.00	0	0.00	3,958,444	M	140056
Summary										8,636,505	
per cable										863,651	
REMARKS											















1US\$=108JP Yen=14,100VND

CAN THO BRIDGE CONSTRUCTION PROJECT

Process Cost Bearing(Move Side) Installation 600\*300\*57 (15\*3) Unit: 10 nos 414140 Sheet #: PC

No.	Description	Specification	Unit	Quantity	Unit Price				COMBINED TOTAL COST (VND)	Remarks
					Foreign Currency (JP Yen)	Foreign Currency (US\$)	Local Currency (VND)	Local Currency (US\$)		
1	Foreman	Local 1*10/N*1	M/day	1.25	0	0.00	146,392	0.00	182,990	L 101000
2	Skilled Labor	Local 1*10/N*2	M/day	2.50	0	0.00	118,898	0.00	297,245	L 104000
3	Common Labor	Local 1*10/N*2	M/day	2.50	0	0.00	58,671	0.00	146,678	L 103000
	Miscellaneous Fee	1 % of above							6,269	
4	Rubber Shoe (Move Side)	600*300*57(15*3)	nos	10.00	0	246.40	0	0.00	34,742,400	M 140224
5	Anchor Bolt	SD295	kg		192	0.00	0	0.00	0	M 140310
6	Anchor Cap (Move Side)	D***	m		0	0.00	0	0.00	0	M 140450
7	Grid Rebar around Shoe		t		0	0.00	3,492,000	0.00	0	M 140511
8	Spiral Hoop	D10*Ø300-Ø500	t		0	0.00	3,492,000	0.00	0	M 140521
Summary										
									35,375,582	
PER NOS									3,537,558	
REMARKS										
N=8 (days)										

